

P 220000	PLUMBING FIXTURE SCHEDULE					
ID	NAME	DESCRIPTION	CW	HW	SAN	
WC-1 & WC-2	WATER CLOSET NON-HANDICAPPED / HANDICAPPED	WATER CLOSET: EXISTING TO REMAIN FLUSH VALVE: EXPOSED, QUIET DIAPHRAGM-TYPE, CHROME PLATED FLUSHOMETER VALVE WITH A POLISHED EXTERIOR, ADA COMPLIANT WITH A NON-HOLD OPEN AND NO LEAK HANDLE FEATURE. DUAL FLUSH ACTION. POSITION HANDLE TO WIDE SIDE OF ROOM. EQUAL TO ZURN MODEL Z6000AV. SEAT: ELONGATED, STANDARD WHITE, OPEN FRONT TOILET SEAT, LESS COVER, WITH CHECK HINGE. EQUAL TO BENIS MODEL 1955CT 000.	1"	N/A	4"	
UR-1	URINAL NON-HANDICAPPED	URINAL: EXISTING TO REMAIN FLUSH VALVE: EXPOSED, QUIET DIAPHRAGM-TYPE, CHROME PLATED FLUSHOMETER VALVE WITH A POLISHED EXTERIOR, ADA COMPLIANT WITH A NON-HOLD OPEN AND NO LEAK HANDLE FEATURE. POSITION HANDLE TO RIGHT SIDE. EQUAL TO ZURN MODEL Z6000AV.	3/4"	N/A	2"	
L-1	LAVATORY HANDICAPPED OR NON-HANDICAPPED	BOWL: EXISTING TO BE REMOVED AND RE-INSTALLED FAUCET: TWO-HANDLE ADA COMPLIANT, 4" CENTERSET MOUNTING, CHROME PLATED SOLID BRASS CONSTRUCTION, VANDAL RESISTANT, 1/2" IPS SUPPLY SHANKS. EQUAL TO MOEN MODEL 82153MF12 OR EQUAL. DRAIN: GRID TYPE STRAINER WITH 4" TAIL PIECE. P-TRAP: 1-1/4" INLET AND 1-1/2" OUTLET POLISHED CHROME PLATED CAST BRASS BODY ADJUSTABLE P-TRAP WITHOUT CLEANOUT, WITH 17-GAUGE SEAMLESS TUBULAR WALL BEND, CAST BRASS SLIP NUTS AND CHROME PLATED SET SCREW ESCUTCHEON. EQUAL TO CATY PART NO. 700-1. TAILPIECE: 1-1/4" INLET WITH 1/2" TRAP PRIMER OUTLET WHERE INDICATED TO PROVIDE PRIMER WATER FOR FLOOR DRAIN SEE PLANS. STANDARD TAILPIECE TO BE UTILIZED IN LOCATIONS NOT SERVING FLOOR DRAINS. EQUAL TO CATY PART NO. 831-1. SUPPLY STOPS: TWO REQUIRED, 1/2" x 3/8" O.D. HEAVY CAST BRASS ANGLE STOP, ANNEALED VERTICAL TUBES, CHROME PLATED CAST BRASS SET SCREW ESCUTCHEON, CHROME PLATED BRASS NIPPLE TO WALL. EQUAL TO MCGUIRE MODEL LFH508LK OR EQUAL. PROVIDE LAV SHIELD RIGID ENCLOSURE TO COMPLY WITH ADA REQUIREMENTS. COORDINATE TRUEBRO LAV SHIELD MODEL WITH LAVATORY BOWL MANUFACTURER.	1/2"	1/2"	1-1/4"	
EW-1	ELECTRIC WATER COOLER	EXISTING TO REMAIN	1/2"	N/A	1-1/4"	
SH-1 & SH-2	SHOWER	ENCLOSURE: SEE ARCHITECTURAL DRAIN: EXISTING TO REMAIN VALVE: PROVIDE BRASS VALVE WITH 1/4 TURN INTEGRAL STOPS ON EACH INLET. METAL HANDLE CONSTRUCTION WITH CHROME FINISH. EQUAL TO MOEN MODEL NO. U8550 SHOWER HEAD: METAL CONSTRUCTION WITH CHROME PLATED FINISH, VANDAL RESISTANT SHOWER HEAD WITH EASY CLEANING RUBBER NOZZLES. EQUAL TO MOEN WATERSENSE CERTIFIED NO. 5035EP15. SHOWER ARM: 1/2" IPS MALE THREADS WITH CHROME FINISH AND CHROME FLANGE. EQUAL TO MOEN MODEL NO. S122.	1/2"	1/2"	2"	
SS-1	SERVICE SINK	BOWL: EXISTING TO REMAIN	1/2"	1/2"	3"	
EW-1 & EW-2	ELECTRIC WATER HEATER	THE HEATER(S) SHALL BE GOLD X1 COMMERCIAL ELECTRIC MODEL NUMBER DVE-120-27 AS MANUFACTURED BY A. O. SMITH WATER PRODUCTS COMPANY OR EQUIVALENT. HEATER(S) SHALL BE RATED AT 27 KW 208V 3-PHASE, 60 CYCLE AC AS LISTED BY UNDERWRITERS' LABORATORIES. ALL MODELS MEET NATIONAL SANITATION FOUNDATION NSF-5 REQUIREMENTS. WATER HEATER SHALL HAVE LCD DISPLAY WITH BUILT-IN DIAGNOSTIC AND TROUBLESHOOTING INFORMATION. TANK(S) SHALL BE 119 GALLON CAPACITY WITH 160 (ASME) PSI WORKING PRESSURE AND EQUIPPED WITH DUAL EXTRUDED HIGH-DENSITY ANODES. ALL INTERNAL SURFACES OF THE HEATER(S) EXPOSED TO WATER SHALL BE GLASS-LINED WITH AN ALKALINE BOROSILICATE COMPOSITION THAT HAS BEEN FUSED TO STEEL BY FIRING AT A TEMPERATURE RANGE OF 1400°F TO 1800°F. INTERNAL POWER CIRCUIT FUSING SHALL BE PROVIDED. ELEMENT OPERATION SHALL BE LINEAR SEQUENCING THROUGH INDIVIDUAL MAGNETIC CONTACTORS. CONTROL CIRCUIT SHALL BE FACTORY FUSED AND INCLUDE AN IMMERSION THERMISTOR TEMPERATURE PROBE WITH BUILT-IN ECO CONTROL. CONTROL CABINET AND JACKET SHALL BE OF BAKED ENAMEL FINISH AND SHALL PROVIDE FULL SIZE CONTROL AND ELEMENT COMPARTMENT FOR COMPLETE SERVICE AND MAINTENANCE PERFORMANCE THROUGH FRONT HINGED COMPARTMENT DOOR, AND ENCLOSE TANK WITH FOAM INSULATION. 1 1/4" INLET AND OUTLET CONNECTION SHALL BE PROVIDED. THE HEATER TANK SHALL HAVE A THREE YEAR LIMITED WARRANTY AND CONTROLS AND ACCESSORIES SHALL HAVE A ONE YEAR LIMITED WARRANTY AS OUTLINED IN THE WRITTEN WARRANTY. FULLY ILLUSTRATED INSTRUCTION MANUAL TO BE INCLUDED. FOR MULTIPLE INSTALLATION FACTORY BUILT MANIFOLD KITS FOR 2 HEATER INSTALLATION SHALL BE PROVIDED. MEETS OR EXCEEDS THE THERMAL EFFICIENCY AND STANDBY LOSS REQUIREMENTS OF THE U.S. DEPARTMENT OF ENERGY AND CURRENT EDITION OF ASHRAE/IES 90.1.	1-1/4"	1-1/4"	N/A	
EW-3	ELECTRIC WATER HEATER	TANKLESS WATER HEATER SHALL BE AN EEMAX MODEL NUMBER SPEX3208 WITH A 3KW ELEMENT AT 208V. UNIT SHALL HAVE ABS-UL 94 EVA RATED COVER. UNIT SHALL ALLOW MOUNTING IN ANY ORIENTATION. ELEMENT SHALL BE REPLACEABLE CARTRIDGE INSERT. ELEMENT SHALL BE IRON-FREE. NICKEL-CHROME MATERIAL. UNIT SHALL HAVE REPLACEABLE FILTER IN THE INLET CONNECTOR. UNIT SHALL INCLUDE AN INTEGRATED FLOW METER TO ENSURE ACCURATE TURN-ON / TURN-OFF FLOW RATE. HEATER SHALL BE FITTED WITH 3/8" COMPRESSION FITTINGS TO ELIMINATE THE NEED FOR SOLDERING. MAXIMUM OPERATING PRESSURE OF 150 PSI. DIAGNOSTIC FEATURES TO INCLUDE LED ERROR/FAULT INDICATOR. HEATER SHALL EMPLOY TECHNOLOGY THAT ENGAGES UPON START-UP TO AVOID DRY-FIRE OCCURRENCE. HOT WATER STORAGE TANKS PROHIBITED. UNIT SHALL BE EEMAX OR APPROVED EQUAL.	3/8"	3/8"	N/A	
TD-1	TRENCH DRAIN	6" WIDE MODULAR TRENCH DRAIN WITH POLISHED NICKLE BRONZE TOP. PROVIDE WITH DEEP SEAL TRAP. FIELD MEASURE EXISTING FOR EXACT REQUIREMENTS. COORDINATE WITH ARCHITECTURAL DRAWINGS. PROVIDE SECTIONS AS REQUIRED.	N/A	N/A	3" U.N.O	
EW-1	ELECTRIC WATER COOLER ADA COMPLIANT WITH BOTTLE FILLING STATION (DOUBLE UNIT)	B4-LEVEL DRINKING FOUNTAIN WATER COOLER: B4-LEVEL STAINLESS-STEEL BASIN WITH GREY STONE POWDER COATED GALVANIZED STEEL CABINET WITH BOTTLE FILLING STATION, VANDAL RESISTANT PUSH-BUTTON ACTIVATION, 8.0 GPH COOLED TO 50°F AT 370 WATTS, 5.0 FLA. UNIT SHALL INCORPORATE A MECHANICALLY OPERATED VALVE TO MAINTAIN WATER STREAM WITHOUT POWER TO UNIT, AUTOMATIC 20 SECOND SHUTOFF. INSTALL LOWER UNIT IN COMPLIANCE WITH CHILDREN'S ADA... ACCEPTABLE MANUFACTURERS: ELKAY MODEL NO. VRCL26WK HALSEY CARRIER (BLOCK WALL): WATER COOLER SUPPORT WITH ADJUSTABLE DURA-COATED TOP AND BOTTOM SUPPORT PLATES, COMPLETE WITH MOUNTING FASTENERS. ACCEPTABLE MANUFACTURERS: ZURN Z1259 CARRIER (STUD WALL): WATER COOLER SUPPORT SYSTEM WITH TOP AND BOTTOM PLATES, COMPLETE WITH DURA-COATED RECTANGULAR STEEL UPRIGHTS WITH WELDED FEET, CAST IRON ADJUSTABLE HEADERS, STEEL SLEEVES, ALIGNMENT TRUSS AND MOUNTING FASTENERS. ACCEPTABLE MANUFACTURERS: ZURN Z1225 NOTE: PVC TRAPS MUST BE PROVIDED. ELKAY 36281C VOLTAGE SPIKE LIMITER (SNUBBER) SHALL BE SPECIFIED TO AVOID ISSUES WITH GFI OUTLETS TRIPPING.	1/2"	N/A	2"	
HB-1	HOSE BIBB	CAST BRASS CHROME FINISH WHEEL HANDLE HOSE BIBB WITH 3/4" MALE HOSE THREAD AND ANTI-SIPHON VACUUM BREAKER. ACCEPTABLE MANUFACTURERS: WOODFORD MODEL 24	1/2"	N/A	N/A	

P 220000	GENERAL PLUMBING NOTES
1.	IN GENERAL, PLANS AND DIAGRAMS ARE SCHEMATIC AND SHOULD NOT BE SCALED.
2.	INTENT OF THESE NOTES AND PLUMBING NOTES ON DRAWINGS IS TO CLARIFY THE SCOPE OF WORK.
3.	THE CONTRACTOR IS RESPONSIBLE FOR ANY AND ALL DAMAGE TO OWNER'S PROPERTY OR OTHER UNCOORDINATED TRADES DURING THE COURSE OF CONSTRUCTION.
4.	THE CONTRACTOR IS RESPONSIBLE FOR ALL TRADES INSTALLATION SCHEDULES, FIXED WORK SUCH AS DUCTWORK AND PLUMBING SHALL BE INSTALLED PRIOR TO ANY TRADE WORK THAT CAN BE EASILY RELOCATED OR OFFSET SUCH AS ELECTRIC CONDUITS, SMALL WATER LINES, ETC.
5.	CONTRACTOR SHALL NOTIFY ARCHITECT/ENGINEER IN WRITING OF ANY CONFLICTS BETWEEN THE TRADES.
6.	IN THE EVENT OF A CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND THE CODES, THE CODES SHALL TAKE PRECEDENCE.
7.	CONTRACTOR SHALL PROVIDE ANY NECESSARY ITEMS NOT EXPRESSLY MENTIONED IN THE CONTRACT DOCUMENTS NEEDED TO PROVIDE A COMPLETE PLUMBING SYSTEM.
8.	UNLESS OTHERWISE NOTED, ALL PIPING SHALL BE LOCATED IN CONCEALED SPACES. PROVIDE MIN. 12"x12" LOCKING ACCESS PANELS IN WALLS AND HARD CEILINGS FOR ACCESS TO VALVES.
9.	PENETRATIONS FOR PIPES THROUGH ASSEMBLIES (FLOORS, ROOF, WALLS, PARTITIONS, ETC) WITH A REQUIRED FIRE RESISTANCE RATING SHALL BE SEALED TO THE PENETRATING MEMBER IN AN APPROVED MANNER WHICH MAINTAINS THE REQUIRED FIRE RESISTANCE RATING OF THE ASSEMBLY.
10.	ALL PLUMBING FIXTURES, PIPES AND FITTINGS SHALL BE WARRANTED FOR 1 YEAR AFTER DATE OF SUBSTANTIAL COMPLETION.
11.	PROVIDE WATER HAMMER ARRESTORS SIZE PDI "A" AT EACH PLUMBING FIXTURE CONNECTION INCORPORATING QUICK CLOSING FAUCETS OR VALVES. PROVIDE AIR CHAMBERS AT ALL REMAINING FIXTURES WITHOUT SELF CLOSING VALVES.
12.	WALL CLEANOUTS SHALL MAINTAIN A MINIMUM 18" CLEARANCE FOR SERVICE ACCESS.
13.	ALL DRAINAGE AND VENT PIPING SHALL BE: A. ALL MATERIALS SHALL BE NEW, FREE OF DAMAGE AND MEET THE FOLLOWING REQUIREMENTS: a. PVC PIPE: SHALL BE MARKED AS MEETING ASTM D 2685 SPECIFICATION FOR PVC PLASTIC DRAIN, WASTE, AND VENT PIPE AND FITTINGS AND/OR ASTM D 1785 SPECIFICATION FOR PVC PLASTIC PIPE, SCHEDULES 40, 80 AND 120. b. CAST IRON: SHALL BE MARKED AS MEETING ASTM A888 OR CISPI 301 FOR CAST IRON PIPING
14.	ALL DOMESTIC HOT AND COLD WATER PIPING SHALL BE: A. ALL MATERIALS SHALL BE NEW, FREE OF DAMAGE AND MEETING THE FOLLOWING REQUIREMENTS: a. COPPER PIPE: SHALL BE TYPE L HARD TEMPER COPPER TUBING, ASTM B-88, WROUGHT COPPER FITTINGS, 95/5 TIN/ANTIMONY, NO-LEAD SOLDER. b. CPVC PIPE: SHALL BE COPPER TUBE SIZE CPVC PIPE, ASTM 2846 WITH ASTM F 493 SOLVENT CEMENTS FOR JOINING CPVC PIPE AND SOCKET FITTINGS.
15.	ALL PLUMBING ISOLATION VALVES SHALL BE: A. 1/2" - 3" SHALL BE QUARTER TURN, FULL PORT, ONE-PIECE BALL VALVES, BLOW OUT PROOF STEM, BRONZE BODY, STAINLESS STEEL BALL, TFE SEATS, EXTENDED NECK SUITABLE FOR INSULATION, SOLDERED, SCREWED OR COMPRESSION FITTINGS. PUSH-ON FITTINGS WILL NOT BE ACCEPTED. B. 4" - 12" SHALL BE RESILIENT WEDGE GATE VALVES, FLANGED CONNECTIONS, DUCTILE IRON AWWA/ANSI C515 BODY, DUCTILE IRON WEDGE WITH EPDM RUBBER SEALS, MUST BE NSF 61 AND NSF 372 LISTED.
16.	INSULATION FOR HOT WATER PIPING: A. MIN. 1" THICK FIBERGLASS INSULATION WITH WHITE ASJ. PREFORMED FITTINGS SHALL BE UTILIZED AT ALL STANDARD ELBOWS AND FITTINGS. B. MIN. 3/4" THICK CLOSED CELL FOAM SPLIT INSULATION.

P 220000	CODE COMPLIANCE
1.	ALL WORK SHALL BE INSTALLED IN ACCORDANCE WITH THE 8TH EDITION (2023) FLORIDA BUILDING CODE A. BUILDING EDITION B. EXISTING BUILDING EDITION C. MECHANICAL EDITION D. PLUMBING EDITION E. FUEL GAS EDITION F. ENERGY EFFICIENCY EDITION G. 8TH EDITION (2023) FLORIDA FIRE PREVENTION CODE.
2.	NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) A. NFPA-1 NATIONAL FIRE CODE WITH FLORIDA MODIFICATIONS B. NFPA-70 NATIONAL ELECTRIC CODE C. NFPA-72 NATIONAL FIRE ALARM CODE D. NFPA-101 NATIONAL LIFE SAFETY CODE
3.	AMERICAN SOCIETY OF HEATING, REFRIGERATION, AND AIR CONDITIONING ENGINEERS, INC. (ASHRAE)
4.	SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

P 220000	SCOPE OF WORK
1.	REPLACE EXISTING FIXTURE TRIM PACKAGES WITH NEW FOR EXISTING LAVATORIES, WATER CLOSETS, URINALS AND SINKS.
2.	REFRESH EXISTING SHOWERS WITH NEW VALVES, ARMS AND SHOWER HEADS.
3.	REPLACE EXISTING SHOWER TRENCH DRAIN.
4.	REPLACE EXISTING ELECTRIC TANK TYPE WATER HEATERS.

P 220000	LEGEND				
DRAWING SYMBOL		DESCRIPTION	DRAWING SYMBOL		DESCRIPTION
		NEW EQUIPMENT			SANITARY PIPING
		DOMESTIC COLD WATER			SANITARY PIPING BELOW
		DOMESTIC HOT WATER			STORM PIPING
		HOT WATER RETURN LOOP			VENT PIPING
		TEE FITTING PIPE UP			PIPE UP
		TEE FITTING PIPE DOWN			PIPE DOWN
		ANGLE VALVE			UNION
		VALVE			PRESSURE GAUGE WITH GAUGE COCK
		GATE VALVE			THERMOMETER
		BALL VALVE			WALL CLEAN OUT
		CHECK VALVE			END OF PIPE CLEAN OUT
		Y-STRAINER			FLOOR CLEAN OUT
		Y-STRAINER WITH DRAIN VALVE			TWO-WAY CLEAN OUT TO GRADE
		GLOBE VALVE			HOSE BIBB OR WALL HYDRANT
		PLUG VALVE			ROOF DRAIN
		FLEXIBLE CONNECTION			FLOOR DRAIN
		VENT THRU ROOF			FLOOR SINK
		KEYED NOTE			REVISION NOTE
		DEMOLITION NOTE			SYSTEM NOTE
ABBREVIATIONS					
ABBREVIATION		DESCRIPTION	ABBREVIATION		DESCRIPTION
CW		COLD WATER	SS		SANITARY SEWER
HW		HOT WATER (110°F)	ST		STORM WATER
HWR		HOT WATER RECIRC. LOOP	CD		CONDENSATE DRAIN
UP		UP TO LEVEL ABOVE	DN		DOWN TO LEVEL BELOW
NIC		NOT IN CONTRACT	UNO		UNLESS NOTED OTHERWISE
WC		WATER CLOSET	L		LAVATORY
UR		URINAL	S		SINK
SS		SERVICE SINK	FD		FLOOR DRAIN
FS		FLOOR SINK	RD		ROOF DRAIN
HB		HOSE BIBB	WH		WALL HYDRANT
RH		ROOF HYDRANT	TP		1/2" TRAP PRIMER
EWH		ELECTRIC WATER HEATER	EWC		ELECTRIC WATER COOLER
GWH		GAS WATER HEATER	DF		DRINKING FOUNTAIN
COTG		2-WAY CLEAN-OUT TO GRADE	HD		HUB DRAIN
S		SUPPLY	R		RETURN
[R]		REPLACE	[E]		EXISTING
[D]		DEMOLISH	[N]		NEW
THE STANDARD SYMBOLS AND ABBREVIATION ABOVE MAY NOT BE USED. CONTRACTOR IS ONLY RESPONSIBLE FOR SYMBOLS CONTAINED WITHIN THE DOCUMENTS USED TO IDENTIFY REQUIRED SCOPE OF WORK.					


ALTERNATE BID ITEMS	
A.	ALTERNATE BID ITEM NO. 1: PARKING AREA - STORMWATER MITIGATION, ASPHALT MILLING, AND RESURFACE. CONNECT MAIN ARMORY ROOF DRAINS TO UNDERGROUND STORM DRAIN SYSTEM.
B.	ALTERNATE BID ITEM NO. 2: IMPROVE MAIN PARKING SHADING INTERIOR AND EXTERIOR. INSTALL COOLED TANKS WITH BOTTLE FILLING STATION.
C.	ALTERNATE BID ITEM NO. 3: REFRESH AND REPAINT COMPLETE EXTERIOR STUCCO / BRICK FACADE WITH UP TO 4 COLOR SCHEME. INCLUDE THE PAINTING OF ALL EXTERIOR HW DOORS AND FRAMES INCLUDING ALL INSIDE AND OUTSIDE FACES.
D.	ALTERNATE BID ITEM NO. 4: COMPLETE GLAZING REPLACEMENT OF ALL EXISTING LAMINATED IMPACT GLAZING IN EXISTING ALUMINUM WINDOW FRAME SYSTEMS AT THE EXTERIOR CELESTORY LEVEL.
E.	ALTERNATE BID ITEM NO. 5: COMPLETE GLAZING REPLACEMENT OF ALL EXISTING LAMINATED IMPACT GLAZING IN ALL EXISTING ALUMINUM WINDOW FRAME SYSTEMS AT ALL THE EXTERIOR 1ST FLOOR LEVEL GLAZED OPENINGS. EXCEPT NEW EXTERIOR FIXED WINDOWS & IMPACT GLAZING FOR KITCHEN ONLY.
F.	ALTERNATE BID ITEM NO. 6: PROVIDE NEW 20'-0" WIDE (K-8 FORCE PROTECTION) FENCE SYSTEM) DOUBLE SWING GATE WITH MANUAL FUNCTION TO SOUTH SIDE OF POV PARKING. EXISTING DEAD MAN ANCHOR LAYOUT TO BE RE-CONFIGURED FOR NEW GATE. COMPLETE FUNCTIONAL INSTALLATION REQUIRED.
G.	ALTERNATE BID ITEM NO. 7: PROVIDE MILL AND OVERLAY OF THE NORTH & EAST POV PARKING LOT AS INDICATED IN THE ATTACHED CIVIL DRAWINGS.
H.	ALTERNATE BID ITEM NO. 8: PROVIDE NEW DEHUMIDIFIER AND MECHANICAL AIR INSTALLED INTO THE TO THE EXISTING VAULT ROOM # 110 & #111.



154A Whisker Rd.
Lutz, Florida 33549
813.333.2103
www.balengineering.com
Registry No. 31211

TO THE BEST OF THE KNOWLEDGE OF THE ENGINEERS AND ARCHITECTS, SAID PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE MINIMUM BUILDING CODES AND THE APPLICABLE MINIMUM FIRE SAFETY STANDARDS.

THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED BY BRYANT A. LYLE ON JUNE 16, 2026 USING A DIGITAL SIGNATURE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.



100% CONSTRUCTION DOCUMENTS

DMA CFMO # 224004

PALMETTO ESP RENOVATION

NATIONAL GUARD ARMORY


1107 14TH AVE WEST, PALMETTO, FL 34221

PROJECT NO.:1910.08
DATE: MARCH 30, 2026
DRAWN BY: AG
REVISIONS:
1 06-17-26 ADDENDUM 02

SHEET TITLE:
NOTES, LEGENDS
AND SCHEDULES

SHEET NO.:

P0.1



RENKER • EICH • PARKS ARCHITECTS

1609 Dr. Martin Luther King Jr. Street North • St. Petersburg, Florida • 33704-4203 • (727)-821-2986

LIC. AA 000147