

FRANKLIN GATEWAY BRIDGE REPLACEMENT OVER ROTTENWOOD CREEK

BID SCHEDULE

Item Number	Quantity	Units	Item Description	Unit Price	Total Cost
Roadway items					
150-1000	1	LS	TRAFFIC CONTROL		
210-0100	1	LS	GRADING COMPLETE		
310-5060	670	SY	GR AGGREGATE BASE CRS, 6 INCH, INCL MATL		
310-5060	300	SY	GR AGGREGATE BASE CRS, 10 INCH, INCL MATL		
632-0003	2	EA	CHANGEABLE MESSAGE SIGN (TO BE PURCHASED BY CONTRACTOR PER CITY SPECS AND RETAIN BY THE CITY UPON COMPLETION OF THE WORK)	\$30,000.00	\$60,000.00
402-3130	300	TN	RECYCLED ASPH CONC 12.5 MM SUPERPAVE, GP 2 ONLY, INCL BITUM		
402-3190	100	TN	RECYCLED ASPH CONC 19 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATLS & H LIME		
413-0750	355	GL	TACK COAT		
402-1812	200	TN	RECYCLED ASPH LEVELING, INCL BITUM MATL & H LIME		
432-5010	460	SY	MILL ASPH CONC PVMT, VARIABLE DEPTH		
433-1200	320	SY	REINF CONC APPROACH SLAB, INCL SLOPED EDGE		
441-0104	1150	SY	CONC SIDEWALK, 4 IN		
441-5002	295	LF	CONCRETE HEADER CURB, 6 IN, TP 2		
441-6012	1080	LF	CONC CURB & GUTTER, 6 IN X 24 IN, TP 2		
634-1200	1	EA	RIGHT OF WAY MARKERS		
641-1100	288	LF	GUARDRAIL, TP T		
641-1200	38	LF	GUARDRAIL, TP W		
641-5001	4	EA	GUARDRAIL ANCHORAGE, TP 1		
641-1001	36	EA	RAISED PVMET MARKERS TP 1		
Signing and Marking Items					
611-5551	5	EA	RESET SIGN		
636-1033	5	SF	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 9		
636-1036	27	SF	HIGHWAY SIGNS, TP 1 MATL, REFL SHEETING, TP 11		
N/A	52	LF	COM DECORATIVE SIGN POST		
653-1504	200	LF	THERMOPLASTIC SOLID TRAF STRIPE, 12 IN, WHITE		
653-1704	35	LF	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE		
653-1906	1070	LF	THERMOPLASTIC SOLID TRAF STRIPE, 6 IN, WHITE		

ALLOWANCE

653-2602	1540	LF	THERMOPLASTIC SOLID TRAF STRIPE, 6 IN, YELLOW		
653-4503	1540	GLF	THERMOPLASTIC SOLID TRAF STRIPE, 6 IN, WHITE		
Erosion Control Items					
163-0232	0.15	AC	TEMPORARY GRASSING		
163-0240	9.5	TN	MULCH		
163-0301	1	EA	CONSTRUCT AND REMOVE CONSTRUCTION EXISTS		
163-0503	1	EA	CONSTRUCT AND REMOVE SILT CONTROL GATE, TP 3		
163-0527	1	EA	CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS		
163-0550	10	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP		
165-0030	1030	LF	MAINTENANCE OF TEMPORARY SILT FENCE, TP C		
165-0087	1	EA	MAINTENANCE OF SILT CONTROL GATE, TP 3		
165-0101	1	EA	MAINTENANCE OF CONSTRUCTION EXIT		
165-0105	10	EA	MAINTENANCE OF INLET SEDIMENT TRAP		
171-0030	1030	LF	TEMPORARY SILT FENCE, TYPE C		
700-7000	0.75	TN	AGRICULTURAL LIME		
700-8000	0.2	TN	FERTILIZER MIXED GRADE		
700-8100	16	LB	FERTILIZER NITROGEN CONTENT		
700-9300	1350	SY	SOD		
716-2000	1695	SY	EROSION CONTROL MATS, SLOPES		
Drainage Items					
441-0050	10	SY	CONC SLOPE DRAIN		
500-3800	5	CY	CLASS A CONCRETE, INCL REINF STEEL		
550-5180	230	LF	STORM DRAIN PIPE, 18 IN, CLASS III		
550-5240	55	LF	STORM DRAIN PIPE, 24 IN, CLASS III		
600-0001	5	CY	FLOWABLE FILL		
668-1100	5	EA	CATCH BASIN, GP 1		
668-1110	3	LF	CATCH BASIN, GP 1, ADDL DEPTH		
668-4300	2	EA	STORM SEWER MANHOLE, TP 1		
668-4312	5	LF	STORM SEWER MANHOLE, TP 1, ADDL DEPTH, CL 2		

FRANKLIN GATEWAY BRIDGE REPLACEMENT OVER ROTTENWOOD CREEK: BID SCHEDULE (CONTINUED)

Bridge Items					
500-0100	453	SY	GROOVED CONCRETE		
500-1011	221	CY	SUPERSTR CONCRETE, CL D, BR NO - 1		
500-2100	158	LF	CONCRETE BARRIER		
500-2110	158	LF	CONCRETE PARAPET, CPCL DESING		
500-3101	52	CY	CLASS A CONCRETE		
507-9003	833	LF	PSC BEAMS, AASHTO TYPE III, BE NO - 1		
511-1000	6835	LB	BAR REINF STEEL		
511-3000	61242	LB	SUPERSTR REINF STEEL, BR NO - 1		
520-1104	955	LF	PILING IN PLACE, STEEL H, HP 10 X 42		
520-5000	20	LF	PILOT HOLES		
540-1101	1	LS	REMOVAL OF EXISTING BR, STA NO - 106+32		
603-2018	213	SY	STN DUMPED RIP RAP, TP 1, 18 IN		
603-7000	213	SY	PLASTIC FILTER FABRIC		
Water and Sanitary Sewer Items					
156-0100	1	LS	GPS DATA COLLECTION AND SUBMITTAL		
209-0201	100	TN	STABILIZER MATERIAL, TP I (#57 Stone)		
310-1101	450	TN	GRADED AGGREGATE BASE CRS, Incl Mtl (FOR BACKFILL OF TRENCH IN PAVED AREA)		
326-1180	100	SY	PORTLAND CEMENT CONCRETE SUBBASE, 8 IN THICK (CONCRETE TRENCHCAP)		
500-3191	35	CY	CLASS A CONCRETE, HES (FOR CONCRETE BLOCKING AND THRUST COLLARS)		
600-0001	14	CY	FLOWABLE FILL (FOR ABANDONING SEWER MAIN)		
610-2385	315	LF	REMOVE WATER MAIN, 16 IN		
611-8050	4	EA	ADJUST MANHOLE TO GRADE		
611-8140	6	EA	ADJUST WATER VALVE BOX TO GRADE		
615-2550	280	LF	JACK AND BORE PIPE, STEEL CASING, 24 IN. (W.T. 0.375")		
660-0012	58	LF	SANITARY SEWER PIPE, 12 IN. PVC, (8'-12' CUT)		
660-0016A	36	LF	SANITARY SEWER PIPE, 16 IN. PVC, (0'-8' CUT)		
660-0016B	161	LF	SANITARY SEWER PIPE, 16 IN. PVC, (8'-12' CUT)		
660-0016C	28	LF	SANITARY SEWER PIPE, 16 IN. PVC, (12'-16' CUT)		
660-0016D	81	LF	SANITARY SEWER PIPE, 16 IN. PVC, (16'-20' CUT)		
660-0016E	140	LF	SANITARY SEWER PIPE, 16 IN. PVC, (IN CASING)		

660-1112	1	LS	TEMPORARY BYPASS PUMPING SYSTEM		
660-1150	6	EA	CUT AND PLUG EXISTING SAN. SEWER MAIN (ON OUTSIDE OF MANHOLE)		
660-3275	3	EA	ABANDON MANHOLE		
668-3300A	1	EA	SAN. SEWER MANHOLE, TP 1, 72" DIAMETER, DOGHOUSE MANHOLE		
668-3300B	2	EA	SAN. SEWER MANHOLE, TP 1, 60" DIAMETER, OUTSIDE DROP MANHOLE		
668-3300C	2	EA	SAN. SEWER MANHOLE, TP 1, 48" DIAMETER, DOGHOUSE MANHOLE		
668-3300D	2	EA	SAN. SEWER MANHOLE, TP 1, 48" DIAMETER, CUT-IN MANHOLE		
668-3300E	3	EA	SAN. SEWER MANHOLE, TP 1, 48" DIAMETER		
668-3311A	4	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 1, 72" DIAMETER		
668-3311B	8	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 1, 60" DIAMETER		
668-3311C	27	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 1, 48" DIAMETER		
668-3312A	10	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 2, 72" DIAMETER		
668-3312B	16	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 2, 60" DIAMETER		
668-3312C	15	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 2, 48" DIAMETER		
668-3313A	4	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 3, 72" DIAMETER		
668-3313B	1	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 3, 60" DIAMETER		
668-3313C	1	LF	SAN. SEWER MANHOLE, TP 1, ADDL DEPTH, CL 3, 48" DIAMETER		
670-1060	50	LF	WATER MAIN, 6 IN		
670-1120	10	LF	WATER MAIN, 12 IN		
670-1160	420	LF	WATER MAIN, 16 IN		
670-2002	3	EA	VALVE MARKER		
670-2005	1	EA	BLOW-OFF ASSEMBLY, COMPLETE (VALVE PAID FOR SEPARATELY)		
670-2060	3	EA	GATE VALVE. 6 IN		
670-2120	1	EA	GATE VALVE, 12 IN		
670-2160	2	EA	GATE VALVE, 16 IN		
670-2700	3	EA	ABANDONMENT OF WATER VALVE (REMOVE VALVE BOX)		
670-4000	1	EA	FIRE HYDRANT		
670-9450	700	CY	SOLID ROCK EXCAVATION (FOR WATER MAIN AND/OR SANITARY SEWER MAIN)		
670-9920	1	EA	REMOVE EXISTING FIRE HYDRANT, INCL. SALVAGE		
700-6910	0.6	AC	GRASSING - COMPLETE, SEEDS		
716-1000	40	SY	EROSION CONTROL MATS, WATERWAYS (TEMPORARY)		

TOTAL