

PROJECT

JACKSON COUNTY, GEORGIA

JACKSON COUNTY JAIL

PRECISION PLANNING, Inc.

Planners, engineers, architects & surveyors

P.O. Box 2210
Lawrenceville, GA 30046-2210
(770) 338-8000 or (770) 962-8000
(Fax) (770) 822-5990

STAMP

SHEET TITLE

SECURE CEILING
PLAN
AREAS "A" AND "B"

DESIGN
GMM

BCS/JP
GMM

CHECKED
GMM

RELEASE

DATE
02-13-08

NO. DESCRIPTION
100% STRUCTURAL BID PACKAGE CD's

DATE
09/12/07

NO. DESCRIPTION
APPENDUM 1 STRUCTURAL BID PACKAGE

DATE
09/27/07

NO. DESCRIPTION
RFI # 024R STRUCTURAL DIMENSION CLARIFICATIONS

DATE
01/18/08

NO. DESCRIPTION
RFI # 024R STRUCTURAL DIMENSION CLARIFICATIONS

FILE NUMBER
S3.1

CAD FILE NAME
A06196

PROJ. NUMBER
A06196

DATE
02-13-08

PLAN NOTES:

1. SEE ARCHITECTURAL DRAWINGS FOR DIMENSIONS NOT SHOWN.
2. SLAB BEARING EL. +10'-8" U.N.O.
3. FRAMING IS DEPICTED AS VIEWED FROM ABOVE.
4. SEE TYPICAL LINTEL SCHEDULE 2A/SS.3 FOR LINTEL SIZES NOT CALLED OUT ON PLAN.
5. ⓧ INDICATES PLAN - SPECIFIC LINTEL PER SCHEDULE 2C/SS.3.

REMARKS:

1. SEE PRECAST SLAB DESIGN BY PRECAST SPECIALTY ENGINEER.
2. HSS20x8x3/4
3. SKYLIGHT SHAFT WALL, SEE ARCHITECTURAL

WALL KEY

- NON-SECURE WALL - 8" CMU TO THE UNDERSIDE OF THE ROOF DECK OR TOP OF PARAPET
- NON-SECURE WALL - 8" CMU TO THE UNDERSIDE OF SECURE CONCRETE CEILING
- SECURITY WALL - 8" CMU TO UNDERSIDE OF ROOF DECK OR TOP OF PARAPET, REINFORCE WITH #4 BARS AT 8" o.c. FINISHING LIMITED AT LINTELS FOR CLARITY.
- SECURITY WALL - 8" CMU TO A MINIMUM OF 8" ABOVE FINISH CEILING HEIGHT, REINFORCE WITH #4 BARS AT 8" o.c.
- SECURITY WALL - 8" CMU TO UNDERSIDE OF SECURE CONCRETE CEILING, REINFORCE WITH #4 BARS AT 8" o.c. FINISHING LIMITED TO FINISHING OR SUB AT 4'-0" o.c.

SEPA JOB #070233-01
JACKSON COUNTY, GEORGIA
JACKSON COUNTY JAIL
PRECISION PLANNING, Inc.
PLANNERS, ENGINEERS, ARCHITECTS & SURVEYORS
1000 W. BROADWAY, SUITE 200
ATLANTA, GEORGIA 30334
PHONE: (404) 525-1100
FAX: (404) 525-1101
WWW.PRECISIONPLANNING.COM