

232

FILE NUMBER

AD696

PROJ. NUMBER

02-19-08

DATE

02/13/08

MASONRY/F.P./KITCHEN BID PACKAGE RELEASE

01/18/08

RFI # 024R STRUCTURAL DIMENSION CLARIFICATIONS

09/27/07

ADDITIONAL 1 STRUCTURAL BID PACKAGE

09/12/07

100% STRUCTURAL BID PACKAGE CD's

NO DESCRIPTION

RELEASE

SHEET TITLE

SECURE CEILING
PLAN
AREA "C"

DESIGN

GMM

DBS/AP

GMM

CHECKED

GMM

PROJECT

JACKSON COUNTY, GEORGIA
JACKSON COUNTY JAIL

PRECISION PLANNING, INC.

Partners, engineers, architects & surveyors

P.O. Box 2210
Lawrenceville, GA 30046-2210
(770) 962-8000 or (770) 962-8000
(fax) (770) 822-5990

STAMP

PRECISION PLANNING, INC.

REGISTERED PROFESSIONAL ENGINEER

STATE OF GEORGIA

NO. 10000

EXPIRATION DATE 12/31/2010

PLAN NOTES:

- SEE ARCHITECTURAL DRAWINGS FOR DIMENSIONS NOT SHOWN.
- SLAB BEARING EL.=10'-8" TYP.
- FRAMING IS DEPICTED AS VIEWED FROM ABOVE. THIS IS NOT A REFLECTED PLAN.
- SEE TYPICAL UNITS SCHEDULE 2A/SS.3 FOR UNITS.
- SEE TYPICAL UNITS SCHEDULE 2C/SS.3 FOR UNITS.

KEYNOTES:

- 8" THICK SOLID PRECAST SLAB, DESIGN BY PRECAST SPECIALTY ENGINEER.
- HS20X8x6
- SKYLIGHT SHAFT WALL, SEE ARCHITECTURAL
- CONTINUE COLUMN TO ROOF LEVEL.
- STOP COLUMN AT BOTTOM OF SECURE CEILING SLAB, PROVIDE 3/4" CAP-PP WITH (2) 3/4" DIA. x 44" EMBED. WEDGE ANCHORS TO BOTTOM OF SLAB.

1
SECURE CEILING PLAN AREA "C"
SCALE: 1/8" = 1'-0"

WALL KEY

- NON-SECURE WALL - 8" CMU TO THE UNDERSIDE OF SECURE CONCRETE CEILING.
- SECURITY WALL - 8" CMU TO UNDERSIDE OF ROOF DECK OR TOP OF PARAPET, REINFORCE WITH #4 BARS AT 8" o.c. HATCHING OMITTED AT UNITS FOR CLARITY.
- SECURITY WALL - 8" CMU TO A MINIMUM OF 8" ABOVE FINISH CEILING HEIGHT, REINFORCE WITH #4 BARS AT 8" o.c.
- SECURITY WALL - 8" CMU TO UNDERSIDE OF SECURE CONCRETE CEILING, REINFORCE WITH #4 BARS AT 8" o.c. PROVIDE #4 DOWELS TO FOOTING OR SLAB AT 4'-0" o.c.