Specifications for

Concho Billie Trail Stone

Contractor shall provide all labor, supervision, licenses, tools, transportation, and equipment necessary to deliver approximately 1,000 tons of 2 – 5” limestone ballast rock with max 2% fines. The Government will maintain the stockpiles and will be available at stockpile site to sign delivery tickets. There is adequate room for trucks to turn around. Stockpile site is approximately 3.5 miles North of US41 off Turner River Rd:

BICY - Pad 94

Ochopee, FL 34141

(25°56'17.22"N, 81°15'48.57"W)

See maps for delivery location, and GPS attachments.

Damien Hardgrove

DAMIEN HARDGROVE

Digitally signed by DAMIEN HARDGROVE
Date: 2026.04.29 14:27:52 -04'00'