US Department of Agriculture (USDA)

Statement of Work

Contents

Project 3
General Information 3
1.0 Scope of Work 3
2.0 Background 3
Contractor Requirements 3
3.0 Technical Requirements / Tasks 3
707.02 Metallic-Coated Corrugated Steel Pipe 3
4.0 Government Furnished 3
5.0 Deliverables / Schedule 3

Project
Superior National Forest Culvert Supply

General Information

1.0 Scope of Work
Supply, deliver and unload culverts/culvert bands at designated storage areas. Culvert sizes will be listed on culvert schedule.

2.0 Background
NA

Contractor Requirements

3.0 Technical Requirements / Tasks
Culverts will be 14ga aluminized/galvanized spiral ribbed corrugated steel pipe (no riveted culverts). Culverts should meet the following FP14 specification. Culvert bands will be the 24" wide style.

707.02 Metallic-Coated Corrugated Steel Pipe ***Furnish pipe, special sections (such as elbows, branch connections, and prefabricated flared end sections) and coupling bands conforming to AASHTO M 36 and either AASHTO M 218, AASHTO M 274, or AASHTO M 289 for the dimensions and thicknesses specified.***

4.0 Government Furnished
No Government furnished materials

5.0 Deliverables / Schedule
The designated point of contact for the delivery point must be notified at least 48 hours prior to delivery to ensure facility will be unlocked. All culverts will be unloaded at their designated site. Culverts should be unloaded in a safe manner and to avoid damage to culverts. Rolling culverts off the transport is not allowed. Culverts should be stacked so that they do not block driveways or other material that may be present.
See quantity lists and delivery locations on following pages

Deliver to:

Kawishiwi Ranger District Storage Yard, 1393 Hwy 169
Ely, MN 55731

Quantity	Diameter (Inches)	Span (Inches)	Rise (Inches	Length (Feet)
2	12			14
2	12			16
2	12			18
2	12			20
3	18			14
3	18			16
3	18			18
3	18			20
3		17	13	14
3		17	13	16
3		17	13	18
3		17	13	20
3		21	15	14
3		21	15	16
3		21	15	18
3		21	15	20
3		28	20	14
3		28	20	16
3		28	20	18
3		28	20	20
Bands				
4	12			
6	18			
6		17	13	
6		21	15	
6		28	20	