Question & Answers for 70Z03326Q201900005

Updated: 26 June 2026

1. Does the required heat pump/mini-split system need to allow each crew duty room to heat and cool at the same time, or is it acceptable for all rooms to be in the same mode (all heating or all cooling) with separate temperature controls for each room?
   - The requirement is to provide independent and adequate temperature control for each of the four crew duty rooms using one multizone heat pump. Each mini-split should be capable of providing either heating or cooling to its respective room, regardless of the mode selected in the other rooms, ensuring that each room can be set to heating or cooling independently of the others.