Questions & Answers for 70Z03326Q2019000003

Updated: 25 June 2026

What are the working hours for the contract?

- Work is to be completed during normal working hours (M-F 0600-1700). After-hours work may be completed upon approval from Contracting Officer.

Should offerors include pricing for drywall repair in association with the removal of the existing cove base?

- When removing the old rubber cove base, every effort shall be made to prevent any drywall damage. Where damage is unavoidable, please include a unit price add/alternate to patch the drywall to facilitate new cove base installation.

A few undulations in the floor plate were noted during the site visit. Should floor prep be included in offers?

- Based on Section 1.1 and 1.2 of the SOW, offers should include all necessary labor, materials, and incidentals to ensure proper installation of the new carpet tile. This includes removal of existing adhesive and thorough cleaning of the subfloor. If undulations in the floor plate require additional floor preparation (such as leveling or patching) to meet the carpet manufacturer's installation guidelines and ensure a quality finished product, floor prep should be included in your offer. Please clearly identify any proposed floor prep activities and associated costs in your submission.