AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE

PAGE 1 OF 3

2. AMENDMENT/MODIFICATION NO. A001

3. EFFECTIVE DATE 04/02/2026

4. REQUISITION/PURCHASE REQ. NO. 26PR-SSP-0111

5. PROJECT NO. *(If applicable)*

6. ISSUED BY CODE TDP

DEPARTMENT OF THE TREASURY
PROCUREMENT SERVICES DIVISIONS
1500 PENNSYLVANIA AVENUE, NW
MAIL STOP: 1425 NEW YORK AVE, NW
SUITE 2100
WASHINGTON DC 20220

7. ADMINISTERED BY *(If other than Item 6)* CODE

8. NAME AND ADDRESS OF CONTRACTOR *(No., street, county, State and ZIP Code)*

CODE

FACILITY CODE

(x) 9A. AMENDMENT OF SOLICITATION NO. 2032H326R00009

x 9B. DATED *(SEE ITEM 11)* 04/02/2026

10A. MODIFICATION OF CONTRACT/ORDER NO.

10B. DATED *(SEE ITEM 13)*

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☒ is extended, ☐ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended , by one of the following methods: (a) By completing Items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted ; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted , such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE

A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation date, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).

C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not. ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

The purpose of AMENDMENT A001:

1) Change the site visit date from 4/15/2026 to 5/27/2026 @ 10:00 AM EST.

2) Change proposal due date from 4/22/2026 to 6/10/2026 @ 1:00 PM EST.

SUBMIT PROPOSAT TO (ARLENE.Y.DAVIS@IRS.GOV & ARLENE.DAVIS@TREASURY.GOV)
Delivery: 365 Days After Award
Delivery Location Code: SSP
SSP
US DEPARTMENT OF THE TREASURY-DEPAR
Continued ...

Except as provided herein, all terms and conditions of the document referenced in Item 9 A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*

16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*
ARLENE Y. DAVIS
TEL: (202)286-9646 EMAIL: ARLENE.DAVIS@TREASURY.GOV

15B. CONTRACTOR/OFFEROR

(Signature of person authorized to sign)

15C. DATE SIGNED

16B. UNITED STATES OF AMERICA

Arlene Y. Davis

(Signature of Contracting Officer)

Digitally signed by Arlene Y. Davis
Date: 2026.04.06 13:04:27 -04'00'

16C. DATE SIGNED

NSN 7540-01-152-8070
Previous edition unusable

STANDARD FORM 30 (REV. 10-83)
Prescribed by GSA
FAR (48 CFR) 53.243

NAME OF OFFEROR OR CONTRACTOR

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	FINANCIAL MANAGEMENT, ATTN:MET SQUA 1500 PENNSYLVANIA AVE., NW WASHINGTON DC 20220 US				
0001	Main Treasury Secretary's Fireplace				
	1. BACKGROUND The is a new competitive bid contract				
	2. SCOPE OF WORK The contractor shall provide all labor, tools, equipment, management, supplies and any other items deemed necessary to complete the following:				
	Set Up & Final Clean: a. A designated staging area for the storage and staging of all materials will be a 10 x 10 area in front of the fireplace and Treasury shall cleared if of all furniture. b. The contractor to provide temporary protection of the surrounding areas as necessary. c. When the job is complete, Treasury will work with the contractor through all working areas to confirm everything is finished and clean.				
	Crossover & Heavy Wall 7 x 11 X 40 Liner 304 a. Reline firebox flue with a heavy wall UL 7" x 11" x 40' Liner 304 stainless steel liner with lifetime warranty. b. Remove all existing flue tiles and throat damper. Insulate flue with UL listed insulation. c. Install new top tile, parge entire smoke chamber and install new top closing damper system. d. Remove the existing flue system as well as all debris. e. During this process containment will be built around the fireplace and plastic will cover the television and furniture in the surrounding area. i. The new flue system will be insulated to comply with manufacture installation instructions and warranty requirements. f. Resurface the smoke chamber entirely by prepping the masonry while using a spray bottle to promote adhesion and applying a 1¿ thick layer throughout. i. Upon Installation of the top closing damper system, the technician will go over the operation of the new system with a hands-on demonstration. Continued ...				

NAME OF OFFEROR OR CONTRACTOR

ITEM NO. (A)	SUPPLIES/SERVICES (B)	QUANTITY (C)	UNIT (D)	UNIT PRICE (E)	AMOUNT (F)
	ii. Photos will be taken throughout the process and provided to the Treasury upon completion.				
	Shroud Removal & Reinstallation				
	a. To gain access to the flue system, the existing shroud cover will temporarily be removed and set aside. Once repairs have been completed the shroud will be inspected to ensure its structural stability before being reattached.				
	b. Near the shroud's termination, an animal guard spark arrestor will be installed				
	Work to be performed during normal working hours 7am to 3pm (Monday through Friday).				