FINISH SCHEDULE

	ROOM NAME	FLOOR MATERIAL	FLOOR C	BASE MATERIAL	BASE C	WALL MATERIAL	WALL C	WAINSCOT MATERIAL	WAINSCOT HT	WAINSCOT C	CEILING MATERIAL	CEILING HT	CEILING C	REMARKS
	ADMINISTRATION & SUPPLY BLDG.													
1,142	VESTIBULE	VCT	F-4	—	B-4	BRICK	—	—	—	—	SATC	8'-0"	C-1	
2,143	CORRIDOR	↓		RESILIENT		CMU	P-4	—	—	—		8'-0"		
3,161	DUTY							—	—	—		8'-0"		
4,160	OPNG TRNG SGT							—	—	—		8'-0"		
5,159	FIRST SGT							—	—	—		8'-0"		
6,158	SECRETARY							—	—	—		8'-0"		
7,157	C.O. CDR.							—	—	—		8'-0"		
8,156	CONFERENCE							—	—	—		8'-0"		
9,155	CLASS ROOM					*		—	—	—	*	9'-0"		*1HR FIRE RATED
2,154	JANITOR'S	CONC.	—	—	—	*CMU/CONC		—	—	—	*PLASTER	8'-0"	P-7	* " " " "
0,153	STORAGE		—	—	—	*CMU		—	—	—	*PLASTER	8'-0"	P-7	* " " " "
1	MECH. ROOM		—	—	—	*CMU/CONC		—	—	—	EXPOSED STRUCTURE	—	—	△
3,152	TELEPHONE		—	—	—	*CMU		—	—	—	*PLASTER	8'-0"	P-7	△
4,151	ARMS ROOM		—	—	—	CONC		—	—	—	CONC.	8'-0"	—	
5,150	WOMENS*	CT	F-1	CT	B-1	CMU	P-5	CT	4'-0"	W-1	KC PLASTER	8'-0"	P-7	*USE TOILET METAL PARTITION -TMP-1
6,149	MENS *		F-2		B-2		P-6			W-2		8'-0"	P-7	*USE TOILET METAL PARTITION -TMP-2
7,148	CLERK	VCT	F-4	RESILIENT	B-4	CMU	P-4	—	—	—	SATC	8'-0"	C-1	
8,147	CLERK							—	—	—		8'-0"		
8,146	RE-UP							—	—	—		8'-0"		
0,145	CLERK							—	—	—		8'-0"		
1,144	CQ							—	—	—		8'-0"		
	BATTALION HQ.													
0	VESTIBULE	VCT	F-4	RESILIENT	B-4	CMU	P-4	—	—	—	SATC	8'-0"	C-1	
1	LOBBY							—	—	—				
2	CORRIDOR							—	—	—				
3	CORRIDOR							—	—	—				
4	CORRIDOR							—	—	—				
5	MAIL ROOM							—	—	—	PLASTER		P-7	
6	COMPUTER							—	—	—	SATC		C-1	
7	WOMENS **	CT	F-1	CT	B-1	CMU	P-5	* CT	4'-0"	W-1	KC PLASTER		P-7	* FULL HEIGHT AROUND SHOWER ** USE TOILET METAL PARTITION - TMP-1
8	MENS **		F-2		B-2		P-6	*		W-2			P-7	* FULL HEIGHT AROUND SHOWER ** USE TOILET METAL PARTITION-TMP-2
9	JANITOR'S	CONC.	—	—	—	*CMU	P-4	—	—	—	*GYP BD		P-7	*1 HR FIRE RATED
0	MECH. RM.		—	—	—	*		—	—	—	EXPOSED STRUCTURE	—	—	△
1	OFFICE	VCT	F-4	RESILIENT	B-4	CMU / GYP BD	P-4	—	—	—	SATC	8'-8"	C-1	
2	SR-4 CLERK							—	—	—				
3	SUPPLY SGT							—	—	—				
4	BN. CDR.							—	—	—				
5	SECRETARY							—	—	—				
6	COM. SGT. MAJOR							—	—	—				
7	CLERK TRAINING (NCO)							—	—	—				
8	XO							—	—	—				
1	OPNS							—	—	—				
0	S-1							—	—	—				
1	BATT. OPER. SGT.							—	—	—				
2	S-4							—	—	—				
3	CONFERENCE							—	—	—				
4	S-2							—	—	—				
5	S-2							—	—	—				
6	PAC SUPER							—	—	—				
7	PAC OC							—	—	—				
8	PAC							—	—	—				

ROOM NO.	ROOM NAME	FLOOR MATERIAL	FLOOR C	BASE MATERIAL	BASE C	WALL MATERIAL	WALL C	WAINSCOT MATERIAL	WAINSCOT HT	WAINSCOT C	CEILING MATERIAL	CEILING HT	CEILING C	REMARKS
G129	STORAGE	VCT	F-4	RESILIENT	B-4	*CMU / *GYP BD	P-4	—	—	—	*GYP. BD.	8'-0"	P-7	*1 HOUR FIRE RATED
G130	SUPPLY	↓	F-4			CMU/GYP BD	P-4	—	—	—	EXPOSED STRUCTURE	—	P-4	
G131	STORAGE	CONC.	—			*CMU / *GYP. BD.		—	—	—	*GYP. BD.	8'-0"	P-7	*1 HOUR FIRE RATED
G132	STORAGE		—			*		—	—	—	*			*
G133	STORAGE		—			*		—	—	—	*			*
	RED CROSS BLDG.													
H100	CORRIDOR	VCT	F-4	RESILIENT	B-4	GYP. BD.	P-4	—	—	—	*SATC / *GYP. BD	8'-0" / —	C-1 / P-7	*SEE REFLECTED CEILING PLAN SHEET A-27.
H101	WAITING							—	—	—	SATC	8'-0"	C-1	
H102	CLOSET							—	—	—	GYP. BD.		P-7	
H103	BOOKKEEPING							—	—	—	SATC		C-1	
H104	STORAGE					*		—	—	—	*GYP. BD.		P-7	*1 HR. FIRE RATED
H105	CLOSET							—	—	—	GYP. BD.		P-7	
H106	STATION DIRECTOR							—	—	—	SATC		C-1	
H107	KITCHEN					*△		—	—	—	GYP. BD.		P-7	*1 HR. FIRE RATED △
H108	PASSAGE							—	—	—				
H109	MEN *						P-6	—	—	—				*
H110	WOMEN *						P-6	—	—	—				*
H111	STORAGE	↓	↓			*GYP. BD.	P-4	—	—	—	*GYP. BD.	↓		*1 HR FIRE RATED
H112	MECH. RM.	CONC.	—			*		—	—	—	*	**	↓	* 1 HR FIRE RATED. ** GYP. BD. CLG. SHALL BE MOUNTED TO BOTTOM OF HR RAFTER.
H113	CONFERENCE	VCT	F-4			GYP. BD.		—	—	—	SATC	8'-0"	C-1	
H114	CLOSET							—	—					
H115	CLOSET							—	—					
H116	OFFICE # 3							—	—					
H117	OFFICE # 2							—	—					
H118	OFFICE # 1	↓	↓	↓	↓	↓	↓	—	—	—	↓	↓	↓	

Plate 87. FINISH SCHEDULE: Make the following changes:

(a) ADMINISTRATION & SUPPLY BLDG.: In the REMARKS column delete the fire rating for rooms F111, F131, F112, F133 and F152.

(b) Battalion HQ: In the REMARKS column delete the fire rating for room G110.

(c) Red Cross Bldg., Room H107: Add "* 1 HR FIRE RATED" in the "REMARKS" column and "*" in the "WALL" column.

REV	DATE	DESCRIPTION	BY
△	MAY 90	REVISED AS BUILT	
△	5 JUN 87	PDM 1 (SUPPLY, BATT. HQ, & RED CROSS BLDGS.)	JDD

DEPARTMENT OF THE ARMY
BALTIMORE DISTRICT, CORPS OF ENGINEERS
BALTIMORE, MARYLAND

ABERDEEN PROVING GROUND MARYLAND

ENLISTED BARRACKS PHASE IV

ROOM FINISH SCHEDULE

DRAWING NUMBER F-721-90-12 PLATE 87

SCALE: AS SHOWN DATE: 5 FEB. 1987 SHEET A-40

41792