AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF	PAGES
J	1		19

2. AMENDMENT/MODIFICATION NUMBER	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQUISITION NUMBER	5. PROJECT NUMBER *(If applicable)*
0001	25 Jun 2026	See Continuation Sheet	

6. ISSUED BY	CODE	7. ADMINISTERED BY *(If other than Item 6)*	CODE
COMMANDING GENERAL MCB CAMP LEJEUNE, BLDG 1212 PSC BOX 20004 CAMP LEJEUNE, NC 28542-0004 UNITED STATES Emily Tsan, Email: emily.n.tsan.civ@usmc.mil Telephone: 910-451-9199	M67001	SCD: PAS:	

8. NAME AND ADDRESS OF CONTRACTOR *(Number, street, county, State and ZIP Code)*

CODE | FACILITY CODE

(X)

☒ 9A. AMENDMENT OF SOLICITATION NUMBER: M6700126Q0064

9B. DATED *(SEE ITEM 11)*: 11 Jun 2026

☐ 10A. MODIFICATION OF CONTRACT/ORDER NUMBER

10B. DATED *(SEE ITEM 13)*

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☒ is extended. ☐ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

See Continuation

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

CHECK ONE	
☐	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

The purpose of this amendment is to answer vendors questions, revise the Performance Work Statement, and to extend the due date of the solicitation. No further questions will be answered after this amendment.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
		Coleman Scott	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
_____ *(Signature of person authorized to sign)*		Coleman Scott *(Signature of Contracting Officer)*	25 Jun 2026

Previous edition unusable

STANDARD FORM 30 (REV. 11/2016)
Prescribed by GSA FAR (48 CFR) 53.243

SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

Solicitation/Contract Form Continuation

The following changes have been made:

INFORMATION	FROM	TO
Response Due Date	25 Jun 2026	06 Jul 2026

Continuation of Description

Miscellaneous text in this section has been modified to:

NOTICE TO OFFERORS

QUESTIONS: Questions related to this Request for Quote (RFQ) shall be received by the Contracting Department at emily.n.tsan.civ@usmc.mil, by 17 June 2026 at 2:00 PM EST. Responses to questions will be provided after that date via Amendment to the RFQ and posted in SAM.gov.

Questions and Answers:

Question 1: PWS Section 4.2.1 states that the contractor shall repair or replace defective equipment within 48 hours and that all repair or replacement costs, including travel, must be included in the total contract price. Because the actual quantity, type, condition, age, and failure rate of equipment cannot be known until a failure occurs, can the Government clarify how offerors should price unknown future repair and replacement costs in a firm-fixed-price quote?

Answer 1: The Government does dictate the specific pricing methodologies or risk-estimation models that offerors use for firm-fixed-price contracts. In alignment with past practices for this requirement, offerors are expected to perform independent market research, review the provided equipment lists, and make a standard business decision regarding projected repair and replacement costs.

To assist offerors in assessing risk and formulating competitive, realistic FFP quotes, the Government has updated the equipment inventory table in the Performance Work Statement (PWS) to include historical data, specifically the purchase date and/or the date of the last major repair /maintenance action for each piece of equipment. Offerors should utilize this historical baseline to project their anticipated maintenance and failure rates.

Question 2: Would the Government consider adding a separate Other Direct Cost (ODC), materials, or not-to-exceed CLIN with a stated ceiling for replacement parts and major component replacements? This would allow offerors to price recurring preventive maintenance and normal support on a firm-fixed-price basis while keeping unknown future equipment failures from being priced as excessive contingency within the base maintenance CLIN.

Answer 2: The Government will not add a separate ODC or NTE CLIN. The requirement remains a single Firm-Fixed-Price (FFP) CLIN divided into 4 quarters. To mitigate pricing risk without changing the contract structure, please refer to the updated PWS equipment inventory table containing historical maintenance and procurement dates. Offerors are instructed to price all maintenance, repairs, and replacements within the existing Firm-Fixed-Price (FFP) structure based on this historical data.

Question 3: Will the Government allow a site visit or pre-quote inspection of the listed AV/VTC equipment at MCLB Albany?

Answer 3: At this time, the Government is not conducting a site visit for this requirement.

Question 4: When was the equipment installed?

Answer 4: Please see the updated PWS for the equipment listing which lists when the equipment was installed.

Question 5: Will drawings and source codes/configurations be available upon award?

Answer 5: The equipment list has the configurations/part numbers. There are no drawings. Source codes will be provided upon award.

Question 6: How many service calls/appointments have been placed in the last year?

Answer 6: Here are the number of service calls/appointments made in the past year from the previous contract.

- Quarter 1 (Aug - Oct): 11 Calls/12 On-Site Required (To include quarterly PMs and necessary firmware updates)
- Quarter 2 (Nov - Jan): 5 Calls/16 On-Site Required (To include quarterly PMs and necessary firmware updates)
- Quarter 3 (Feb - Apr): 9 Calls/14 On-Site Required (To include quarterly PMs, additional troubleshooting, and necessary firmware updates)
- Quarter 4 (May - Present 6/23): 19 Calls/10 On-Site Required (To include quarterly PMs and additional troubleshooting)
- There were also 5-6 Training Sessions for CISD/End-User personnel throughout the year - requiring on-site presence

Question 7: Will service visits outside of the quarterly PM visits be required? Do they need to be included in the total price of the contract? If so, how many service calls would you like included?

Answer 7: Yes, service visits outside of the quarterly preventative maintenance will be required. Please see Paragraph 4.1.1 and Paragraph 4.2 in the PWS for more details concerning unlimited telephone technical support and repair and replacement maintenance. It is expected that all costs will be included in the total price of the contract.

Question 8: How many equipment repairs/replacements have been needed in the last year?

Answer 8: Please see the updated PWS for the equipment listing which lists the number of equipment that had repairs/replacements in the last year.

16 equipment/components were repaired from August 2025 to Present, 23 June 2025
11 equipment/components were replaced from August 2025 to Present, 23 June 2025

Question 9: Are there any active manufacturer warranties? If so, can you please provide the dates of coverage?

Answer 9: There are no active manufacturer warranties for any of the equipment.

List of Contract Documents, Exhibits, or Attachments

Miscellaneous text in this section has been modified to:

WAGE DETERMINATION

(a) Offerors are advised that this procurement is subject to the requirements of the Service Contract Act of 1965, as amended.
(b) The contractor agrees to furnish the Contracting Officer with a copy of any collective bargaining agreements applicable to employees performing under this contract.
(c) Salaries paid to employees must be in compliance with the labor category and wage determination.

23181 Electronics Technician Maintenance I $26.91 per hour

(d) Wage Determination No 2015-4467 (Rev-34) dated May 13, 2026, can be found at: www.sam.gov

Performance Work Statement (PWS) for Marine Corps Logistics Base Albany, GA AV/VTC Maintenance Service

1.0 Scope. The contractor shall provide regular quarterly maintenance for hardware and software, software upgrades, and repair or replacement of existing equipment. Any contractor furnished software must be compatible with the existing "CRESTRON/BIAMP" operating system. These services are to support the audio, video wall systems and VTC environments for Marine Corps Logistics Base (MCLB) Albany, GA.

2.0 Period of Performance (PoP). The PoP shall be a base period of 12 months.

Base Year: 08 August 2026 - 07 August 2027

2.1 The contractor shall not provide services on recognized Federal Holidays.

2.2 Military organizational exercises and operations requirements may delay or interrupt standard operations. Contractors shall comply with force protection conditions.

3.0 Objective. The contractor shall provide analytical and technical personnel necessary for the quarterly maintenance of audio, video wall system and VTC equipment. The contractor shall provide services on the equipment and software including all components currently at the following listed facilities:

- Base Conference Room, Room 504, Bldg. 3500, AV/VTC and Teams Systems
- Carson Conference Room, Room 60, Bldg. 3500, AV and Teams Systems
- Covella Pond Amphitheater, Intersection of McCawley Ave & Radford Blvd, PA System
- Officer of the Day (OOD) Duty Hut, Room 1, Bldg. 3500, Audio System
- Garrison Mobile Equipment (GME), Bldg 5400, AV, Teams, and Security Camera Systems
- SJA Office, Room 507, Bldg 3500, AV and Teams System
- Seven Monitors Maintenance Support Services - Various Locations
- Barracks, Bldg 7130, Theater System
- Services for Four Time Zone Clocks

3.1 The contractor shall provide trained employees, in sufficient numbers, to properly perform all required maintenance and within the specified time frames.

3.2 The contractors shall be certified to service CRESTRON/BIAMP hardware and software.

3.3 Present a neat appearance and be easily recognized as contract employees. All employees shall wear contractor provided identification, which includes the contractor's name, employee's full name and duty title.

3.4 Have the ability to read, write, speak, and understand English.

3.5 All maintenance will be conducted at MCLB Albany. The contractor shall notify the Government representative immediately if maintenance cannot be completed for any reason. Upon completion of the maintenance, the contractor will furnish written records containing information of the service performed to the Government representative.

3.6 The contractor shall be escorted through locations that require additional authorization by the Government representative.

4.0 Tasks. The contractor shall provide:

4.1 Quarterly Maintenance Support Services: The contractor shall provide regular quarterly maintenance in accordance with the manufacturer's operation manual. This includes, but is not limited to:

- Cleaning the equipment with a clean, soft, and dry cloth.
- Disconnecting power supplies when cleaning equipment, if needed.
- Unplugging equipment during lightning storms or when unused for long periods of time.
- Checking to make sure equipment is not near water.
- Calibration and alignment of equipment for consistent audio and image output.

4.1.1 Unlimited telephone technical support. The contractor's Technical Help Desk will perform (with the customer's assistance) preliminary troubleshooting, remote diagnostics and if possible, a video test call to identify the problem before ordering parts for shipment. For issues that cannot be resolved remotely, the contractor will provide on-site technical support to return covered hardware products to operational condition, repairing or replacing components or entire units as necessary. Coverage includes all required parts, materials, labor, and travel. Remote services are available 24 hours per day, every day, including all holidays.

4.1.2 Preventive Maintenance. Contractor will perform all preventive maintenance on a quarterly basis (every 3 months/90 days). Date and time of the inspection will be coordinated with the MCLB/CISD AV/VTC Coordinator at least 14 days in advance. This preventive maintenance is intended to prevent or significantly minimize the need for routine service calls or equipment failure.

4.2 Equipment Repair or Replacement. The contractor shall provide standard support coverage from 0730 to 1530 EST Monday through Friday with a 4-hour response time. This is turn-key, rapid-response coverage for hardware and software for the current technical configurations in the current environment. This service includes the following support services for all equipment listed in Section 4.4 of this PWS.

4.2.1 Contractor shall repair or replace defective equipment within a 48-hour timeframe. All equipment repair or replacement costs must be included in the total price of the awarded contract to include travel. The contractor shall notify the Government representative which equipment was replaced and what the new part number will be.

4.3 Software Updates and Licensing. Complete updates for all software products and documentation updates will be made available to the system manager. The contractor shall receive licenses for updates and copy each update to all systems covered by original software license. The contractor will be responsible for providing all required licenses and software upgrades at no additional cost to the Government. In addition, the contractor must provide for re-certification of the operating system at the conclusion of the final contract period so that the system is in working condition.

4.4 Equipment Listing. The table below lists the equipment that will be associated with the maintenance service.

Building 3500 Room 504: Located at 141 Richards Dr.						
Quantity	**Description**	**Part Number**	**Manufacturer**	**Install Date**	**Repair Dates and Details**	**Room**
1	58" Samsung Monitor	TB-52MON	Tandberg	2020		504
1	Aurora Multimedia VTUNEPRO Cable Tuner	VTUNEPRO	Aurora	2020		504
				2		

1	Biamp MA75 Mixer Amplifier	MA75	Biamp	0 2 0	5/12 - on-site to troubleshoot - re-initialized Biamp DSP and re-configured audio output - issue fixed	5 0 4
1	Crestron C2NVEQ4 Control /EQ	C2N-VEQ4	Crestron	2 0 2 0		5 0 4
1	Crestron PRO3 Control System	2994603	Crestron	2 0 2 0		5 0 4
1	Crestron PW2420ru Power Supply	PW-2420U	Crestron	2 0 2 0		5 0 4
1	Crestron TPS-12 Color Touch Panel	TPS-12	Crestron	2 0 2 0		5 0 4
1	Crown CL1 Program Amplifier	CL-1	Crown	2 0 2 0		5 0 4
1	DRAPER 10789 120" Diagonal Screen	10709	Draper	2 0 2 0		5 0 4
1	Extron 60-219-06 Crosspoint 84 HVA	60-219-06	Extron	2 0 2 0		5 0 4
3	Extron 60-375-01 RGB468xi, 4 gang interface	60-375-01	Extron	2 0 2 0		5 0 4
1	Furman PS-8R Power Sequencer	PS-8R	Furman	2 0 2 0		5 0 4
1	IN5106 Projector	IN-5106	InFocus	2 0 2 0		5 0 4
2	JBL Control 28-WH Front Wall Speakers	28-WH	JBL	2 0 2 0		5 0 4
			Juice	2		5

1	Juice Goose RX10SCS Surge Suppressor for Projector	RX-10-SCS	Goose	0204		04
1	Panasonic PVD-474k DVD /VCR combo	PVD-474K	Panasonic	20204		504
1	Polycom 2200-16155-001 Soundstation Extended Mics/2 expansion 2200-16155-001	2200-16155-001	Polycom	20204		504
1	Shure MX418D/C 18" Gooseneck Microphone	MX-418D	Shure	20204		504
6	Tannoy CMS501CT60 Ceiling Speakers/Tile Bridge Kit	CMS-501-CT60	Tannoy	20204		504
1	PTZ Conferencing Camera	20X HDMI AI Auto Tracking PTZ	Fomako	20204		504
1	Webex Quad Camera	CS-QUAD CAM=	Cisco	20244		504
1	Webex Room Navigator Touch Screen	CS-T10-TS+	Cisco	20244		504
1	Webex Plus Codec - No Radio	CS-CODEC-PLUS-NR=	Cisco	20244		504
1	Wireless Computing RF350 Wireless Keyboard with glidepad & handheld presenter	RF-350	Wireless Computing	20244		504

Building 3500 Room 60 Carson Conference Room: Located at 141 Richards Dr.						

Quantity	Description	Part Number	Manufacturer	Install Date	Repair Dates and Details	Room
4	In-Ceiling Microphones	PZM-6RB	Crown	2014		CCR
1	Crestron Pro2 Control System	Pro2	Crestron	2025		CCR
2	Extron Computer Interfaces	CP-INT	Extron	2025		CCR
1	Crestron 75 Watt Power Supply	75W-PS	Crestron	2025		CCR
1	Crestron 8X8 Digital Media Switch	8X8 DM-SW	Crestron	2025		CCR
2	Crestron 8.7" Wireless Touch Screen	TST-902	Crestron	2025	12/17 - On-Site to replace TST-902 in control room and re-loaded programming to TST-902 to fix issue - 3/6 - On-Site to replace battery for TST-902 to fix issue 5/6 - Onsite-slider bar not working properly on TST-902 -Troubleshoot and re-loaded programming to fix issue	CCR
1	Crown 280A Program Amplifier	280A	Crown	2025		CCR
1	Samsung Blu-Ray/DVD Player	BLR-DVD	Crown	2014		CCR
1	VGA Wall Plate	VGA-PLATE	Extron	2014		CCR
				2		

1	Microphone Wall Plate	MIC-PLATE	Extron	2014		CCR
4	In-Ceiling Speakers	CT-72D	BES	2014		CCR
1	InFocus 4000 Lumens LCD 1080p Projector for Rear Projection Screen	IN3128	InFocus	2014		CCR
2	Sharp LC-60LE650U Full HD 1080p 60" LED Monitors	LC-60LE650U	Sharp	2014		CCR
1	Fomako 20x Camera (Teams)	20X HDMI AI Auto Tracking PTZ	Fomako	2021		CCR

Covella Pond: Located near Amphitheater closest to McCawley Ave.						
Quantity	**Description**	**Part Number**	**Manufacturer**	**Install Date**	**Repair Dates and Details**	**Room**
18	JBL All Weather (AWC) 129 Outdoor Speakers	AWC129	JBL	2022	9/10 - Onsite-Replace outdoor speaker connectors in Junction Box 5/20 - On-Site to fix one of the outdoor speakers that had no audio output - required 30' lift rental - re-wired connections to fix issue. Also, raise six of the outdoor speakers on light poles that were tilted slightly due to inclement weather - required 30' lift rental	CP
		WMS	A	20		C

8	AKG WMS470 D5 Wireless Hand Held Vocal Set	4 7 0	K G	2 2	9/11 - Onsite-Replace microphone wind socks 3/10 - Onsite-Couple of mics not working-Reset controllers	P
2	AKG WMS470 BD8 Wireless Presenter Set - Includes Headworn Mic and CK99l Lavalier	1 8 0 A	A K G	2 0 2 2		C P
3	AKG PS4000W Power Splitter	P S 4 K	A K G	2 0 2 2		C P
1	AKG PSU4000 Central Power Supply Unit	P S U 4 K	A K G	2 0 2 2		C P
2	AKG SRA2 W Active Directional Antenna	S R A 2	A K G	2 0 2 2		C P
24	AKG MKPS BNC Antenna Cables	M K P S	A K G	2 0 2 2		C P
8	35' Light Poles	3 5 L P	A E	2 0 2 2		C P
4	DCI4X600N Amplifier	D C 1 4 X 6 0 0 N	C ro w n	2 0 2 2	9/10 - Onsite-Replace speaker connectors in Equipment Rack	C P
		D C				

1	DCI2X600N Amplifier	12X600N	Crown	2022		CP
1	TesiraForte CI	911.0395.9000	Biamp	2022		CP
1	TesiraForte VT	911.0450.9000	Biamp	2022		CP
4	AC1900 Wireless Router	AC1900	TP-Link	2022		CP
1	MC4	MC4	Crestron	2022	10/7 - Onsite-Replace soundboard with Crestron touch screen, Crestron Control System, Biamp Tesiraforte VT, and network switch. 10/8 - Onsite- Reprogramming required for newly installed equipment. 10/9 - Onsite-Test/certify new system with CISD personnel	CP
1	TST-1080	TST-1080	Crestron	2022		CP

Building 5400 (GME): Located at 1725 Broom Blvd.						
Quantity	**Description**	**Part Number**	**Manufacturer**	**Install Date**	**Repair Dates and Details**	**Room**
1	Crestron Pro 3 Dual Bus Processor	CR-PRO3	Crestron	2023		54000
154	Crestron 3 Series Digital Media Presentation System 300	DMPS3-300-C-AEC	Crestron	2023	3/28 - Onsite	54000
1	Biamp Digital Signal Processor (DSP)	Nexia VC	Biamp	2023		54000
2	8 Channel VHF Wireless Microphone System	PDWM 8300	Pyle	2018	11/6 - Onsite-Microphone Server Malfunction-Replace 8 channel microphone system-tested & certified	54000
2	Da-Lite 84300LS Advantage Electrol Motorized Front Projection Screen (69" X 96" - 120" Diagonal)	DL-84300LS	Da-Lite	2018		54000
2	Epson Powerlite D6155W WXGA Projector - 1080p (1920 X 1080), 3LCD, 3500 Lumens	EPS-PL-D6155W	Epson	2018/Teams Upgrade in 2023		54000
1	Smart Podium 524 Interactive Pen Display - 24", 1080p Resolution	SM-IPD	SmartTechnologies	2018		54000

1	Recordex iMMPad SE Wireless Tablet, 50' Range, 40 Hours Continuous Use, Quick Buttons, OnScreen Annotation, Integration with Windows Tablet PC Features	RCDEX-	Recordex	2018		54000
2	Chief Projector Mount System for Epson Projector	CH-PM	Chief	2018		54000
1	Crown 180A Amplifier	CR-180A	Crown	2018		54000
8	JBL-24CTM In-Ceiling Recessed Mounted Speakers	JBL-24CT	JBL	2018		54000
1	VFI PDX20 Multimedia Podium - Locking Front/Rear Doors, 12U Equipment Rack, PC Tower Space, and Retractable Keyboard Slide	VFI-PDX20	VFI	2018		54000
1	Samsung BD-F7500 3D Blu-Ray Player with 4K Upscaling	SS-BRP	Samsung	2018		54000
1	Fomako 20x Camera (Teams)	20X HDMI AI Auto Tracking PTZ	Fomako	2023		54000
6	Wall/Side Rafter Mounted PTZ Camera	33X Zoom PTZ InfraRed IP66 Camera	Sure Vision	2023 (Replaced one camera 2026)	10/23 - Onsite-Camera Not Working 12/8 - Onsite-Camera's not operating properly-No video 12/9 - Onsite-Replace two power supplies on cameras to repair issue 2/2 - Onsite-Replaced power supplies on two camera as PM 4/10 - Onsite-Troubleshoot camera not displaying /working 4/11 - Onsite-Continue troubleshooting 4/15 - Onsite-Replace malfunctioning PTZ camera. 6/23 - On-Site to troubleshoot non-working Surveillance System	EOC

					camera - camera is now working		
1	8 Channel NVR	8 Channel NVR w /16TB HDD	Sure Vision	2023	6/23 - On-Site to troubleshoot non-working Surveillance System camera - camera is now working	EOC	

Building 3500 Miscellaneous Seven Monitors: Located at 141 Richards Dr.						
Quantity	**Description**	**Part Number**	**Manufacturer**	**Install Date**	**Repair Dates and Details**	**Room**
7	75" 4K LED Monitor	UN75U8000FFXZA	Samsung	2024		Misc

Building 3500 OOD Hut: Located at 141 Richards Dr.						
Quantity	**Description**	**Part Number**	**Manufacturer**	**Install Date**	**Repair Dates and Details**	**Room**
1	Crestron MC3 Processor	MC3	Crestron	2024		OOD
1	TIME MACHINE GPS NTP NETWORK TIME SERVER	TM1000A	Time Machine	2024		OOD
1	Crown 4 Channel Power Amplifier	DCI4X600N	Crown	2024		OOD
6	JBL 200W Outdoor Speakers	AWC129 All Weather Speakers	JBL	2024		OOD
4	Peerless Tilt Wall Mounts	PRLS-ST670	Peerless	2024		OO

			s			D
1	Biamp Digital Signal Processor (DSP)	TesiraForte CI	Biamp	2024		O O D
1	SHURE MX412D/C GOOSENECK MICROPHONE	SH- MX412D/C	Shure	2024		O O D
1	Elegiant Bar Speaker	Elegiant Bar Speaker	Eleigant	2024		O O D

Building 7130 Barracks: Located at 434 McCawley Ave.						
Quantity	**Description**	**Part Number**	**Manufacturer**	**Install Date**	**Repair Dates and Details**	**Room**
1	Shockwave Ultra 9.2 SSE soundbar	Ultra 9.2	Nakamichi	2024		7130
1	LG BU53PST Projector	BU53PST	LG	2024		7130
1	In-Ceiling Projector Mount	Proj-Mnt	Chief	2024		7130
1	Projector Screen	120" Projector Screen	Da-Lite	2024	On-Site to replace damaged HDMI cable for game console connectivity	7130

Building 3500 Room 509 (SJA): Located at 141 Richards Dr.						
Quantity	**Description**	**Part Number**	**Manufacturer**	**Install Dates**	**Repair Dates and Details**	**Room**
						350

1	Crestron TST-1080 Touch Screen	CR-TST-1080	Crestron	2022	1/13/2026 - Onsite - Firmware Upgrade	0/SJA
1	Crestron HD-MD6X2-4K-E	MD6X2	Crestron	2022	1/13/2026 - Onsite - Firmware Upgrade	350 0/SJA
1	Crestron Control Processor	CP4	Crestron	2022	1/13/2026 - Onsite - Firmware Upgrade	350 0/SJA
1	AC1900 Wireless Router	AC1900	TP-Link	2022		350 0/SJA
1	8 Channel Wireless Mic System	PDWM8900	Pyle	2022		350 0/SJA
1	CSA 1120Z Amplifier	NCSA1120Z-U-US	JBL	2022		350 0/SJA
6	Control26CT Ceiling Speakers	26CT	JBL	2022		350 0/SJA
1	75" 4K LED Monitor	QB75-N	Samsung	2022		350 0/SJA
1	Biamp Digital Signal Processor (DSP)	TesiraForte AVB VT	Biamp	2022	2/2/2026 - Onsite - No audio	350 0/SJA
1	Fomako 20x Camera (Teams)	AI Auto Tracking PTZ 20X Camera	Fomako	2022		350 0/SJA

Multi-Time Zone Clock: Located at 141 Richards Dr.						
Quantity	**Description**	**Part Number**	**Manufacturer**	**Install Date**	**Repair Dates and Details**	**Room**
1	Multi-Time Zone Clock	Programmable LED Digital Clock	BRG	2015	2024 - Repair	Carson
1	Multi-Time Zone Clock	Programmable LED Digital Clock	BRG	2015		CMD Deck
1	Multi-Time Zone Clock	Programmable LED Digital Clock	BRG	2015		504
1	Multi-Time Zone Clock	Programmable LED Digital Clock	BRG	2015	2022	EOC

5.0 Government Points of Contact. A Government Representative will be identified in the contract to evaluate the contractor's performance any time during the duration of this contract. The Government Representative will record all assessment observations. Disputes between the Government Representative and contractor personnel over performance standards shall be referred to the contracting officer for final determination. The government reserves the right to inspect tasks not shown on the Service Summary.

5.1 Government Representative:
Name: To be provided at award.
Email:
Phone:

5.2 Contract Administrator:
Name: Emily Tsan
Email: emily.n.tsan.civ@usmc.mil
Phone: 910-451-9199

5.3 Government System Manager:
Name: To be provided at award.
Email:
Phone:

6.0 Contractor Unauthorized Work Performance. The Contractor shall not perform work that deviates from contract requirements and specifications. If the Contractor deviates from contract requirements and specifications without written approval of the CONTRACTING OFFICER, such deviation shall be at the risk of the Contractor and any cost related thereto shall be borne by the Contractor.

7.0 Safety Requirements. The contractor shall comply with commercial safety standards as identified by the Occupational Safety and Health Administration (OSHA).

8.0 Performance Requirements Summary (PRS). The performance standards are stated in the summary below.

	PWS	Performance	Assess	Assessment

Performance Objective	Paragraph	Standard	ment Method	Schedule
Hardware, software, software upgrades, parts, labor, and material maintenance of audio, video wall system and VTC and response time	4.0-4.4	Contractor must meet 97% of the completion times.	100%	Assessment of all maintenance requirements

9.0 Base Access. Base Instructions for Marine Corps Logistics Base Albany.

- To gain initial access to the base, Contractors and/or Delivery Drivers must have in their possession: their contract number, delivery address, and sponsor's contact information.

For **SERVICES** the Contracting Officer's Representative (COR) is the sponsor.
For delivery of **SUPPLIES** the customer/delivery point of contact is the sponsor.

Contract Number: To be provided at award.
Sponsor/COR:
Delivery Address:

- Contractors must be registered in the Defense Biometrics Identification System (DBIDS). It is the Contractor's responsibility to ensure all their employees and or subcontractors are properly registered within DBIDS.

- Contractors requiring access for less than 60 days will receive a temporary paper pass.

- Contractor Common Access Card (CAC) Eligibility: Contractor personnel authorized CACs are exempt from DBIDS enrollment.

If you have questions regarding base access, Contractor CAC or DBIDS requirements contact the Contractor Vetting Office at 229-639-5118. The Contractor Vetting Office is co-located at Building 3010 off of Fleming Road, in Albany GA. the Hours of operation are from 7AM until 3 PM, Monday through Friday (excluding holidays).

**The Government will not be responsible for any contractor access delays. Delays that may result from inadequate planning are strictly the responsibility of the contractor.

- Separate access requests are required for MCLB Albany. Please note, due to the Real ID Act, some state driver's licenses will not be accepted without a second form of identification, like a passport.

- Additional information regarding access to the Air Station is available by phone at 229-639-5118. Failure to submit the proper visit request information may result in denial of access to the facility.

- The MCLB Albany main gate is located off Fleming Road in Albany Georgia. Visitors without proper vehicle identification are required to check-in at the visitor's center adjacent to the main gate.
-DBIDS credentials will be valid for the duration of your contract, not to exceed three years; however, re- vetting of individuals' information will occur each year.

-Contractors requiring access for over 60 days will receive a credential valid for up to one year.

-Contractors requiring access for less than 60 days will receive a temporary paper pass.

-Contractor Common Access Card (CAC) Eligibility: Contractor personnel authorized CACs are exempt from DBIDS enrollment.

-If you have questions regarding base access, Contractor CAC or DBIDS requirements contact the Visitor Control Office at (229) 639-5118.

**The Government will not be responsible for any contractor access delays. Delays that may result from inadequate planning are strictly the responsibility of the contractor.