GATEWAY ARCH NATIONAL PARK
11 NORTH 4TH STREET
ST LOUIS, MO 63102

REPLACE COOLING TOWER AND BOILER UNITS
PMIS 320855

PROJECT SPECIFICATIONS

NATIONAL PARK SERVICE
February 3rd, 2026

TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

Section 01 10 00 - Division 01 Short Form General Requirements

DIVISION 23 -- HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)

23-0519 – METERS AND GAUGES FOR HVAC PIPING

23-0523 - GENERAL-DUTY VALVES FOR HVAC PIPING

23-0529 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

23-0553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

23-0593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

23-0719 - HVAC PIPING INSULATION

23-0913 - INSTRUMENTATION AND CONTROL DEVICES FOR HVAC

23-1123 - FACILITY NATURAL-GAS PIPING

23-2113 - HYDRONIC PIPING

23-2114 - HYDRONIC SPECIALTIES

23-2123 - HYDRONIC PUMPS

23-3600 – AIR TERMINAL UNITS

23-5216 - CONDENSING BOILERS

23-5700 - HEAT EXCHANGERS FOR HVAC

23-6513 - FORCED-DRAFT COOLING TOWERS

DIVISION 26 -- ELECTRICAL

26-0519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

26-0529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

26-0533.13 - CONDUIT FOR ELECTRICAL SYSTEMS

26-0533.16 - BOXES FOR ELECTRICAL SYSTEMS

26-0553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

26-2813 – FUSES

26-2913 – ENCLOSED CONTROLLERS

DRAWINGS

0 – COVER SHEET
0 – PH – PHASING PLAN
M00 – MECHANICAL INFO SHEET
M001 – DEMOLITION FLOOR PLAN – MECHANICAL
M002 – DEMOLITION FLOOR PLAN – MECHANICAL
M101 – FLOOR PLAN – MECHANICAL
M102 – FLOOR PLAN – MECHANICAL
M401 – DETAILS – MECHANICAL
M501 – SCHEDULE – MECHANICAL
E00 – ELECTRICAL INFO SHEET
E01 – ELECTRICAL INFO SHEET
E001 – FLOOR PLAN - DEMOLITION
E002 – FLOOR PLAN – DEMOLITION
E201 – FLOOR PLAN - POWER
E601 – EQUIPMENT SCHEDULE
E701 – ELECTRICAL PANEL SCHEDULES
E702 – ELECTRICAL PANEL SCHEDULES

SECTION 01 10 00

DIVISION 1 SHORT FORM GENERAL REQUIREMENTS

PART 1 – GENERAL

ITEM 1 - DESCRIPTION OF WORK

1.1 Gateway Arch Visitor Center was built in 1976. The building is served by a variable air volume with terminal reheat system. The Grounds Maintenance Complex was built in 2002. There are currently two boilers installed one boiler provides hydronic hot water to the reheat system in the building and the second boiler is used for a radiant floor system.

Several renovations have been completed through the years. The Arch Visitor Center is cooled by two (2) water cooled chillers and one heat recovery chiller. The chillers are connected to a counterflow cooling tower.

1.2 Work Covered by the Contract Documents:

A. Project Location: 11 North 4 Street, St Louis, MO 63102, City of St. Louis.

1.2 Work consists of: At the grounds building the work will consist of the following. One new boiler will be installed to provide heat to both reheat and radiant floor system with a heat exchanger installed to lower the water temperature for the radiant in floor system.

At the Arch complex, work will consist of the following:

A. The cooling tower will be replaced by a new 800 T counterflow cooling tower, as part of the project, new condenser water pumps will be installed.

B. All work will be performed under a single contract.

C. Period of performance: Work shall be completed within 365 calendar days of the start date provided on the Notice to Proceed.

a. Clarification: The Notice to Proceed will be issued with a period of performance that is all inclusive of supply lead times, material deliveries, decommissioning, installation, anticipated average weather days for location, final commissioning, and acceptance of completed work. The contractor will be expected to provide a project schedule with adequate critical path details to ensure all work is completed within the stated calendar days from issuance of the Notice to Proceed. If weather impacts project beyond typical average weather patterns, contractor shall provide documentation in request for additional days.

1.3 Existing Condition Protections:

A. Preservation of Historical and Archeological Fabric:

i. The Historic and Archeological Data Preservation Act of 1974 provides for the preservation of historical and archeological data that might otherwise be lost as the result of alterations to the terrain caused by a federal or federally licensed activity or program.

ii. IF, in connection with operations under this contract, the Contractor, subcontractors, or employees of any of them, discovers, encounters or becomes aware of any possible historical or archeological data, objects or sites of cultural value on the project area, such as historical ruins, graves or grave markers, fossils, or artifacts, the Contractor shall immediately suspend all operations in the vicinity of the discovery and notify the Contracting Officer immediately, when safe to do so, and follow up in writing within 2 days, giving the location and nature of the findings. No objects of cultural resource value may be removed. Contracting Officer will contact other entities as required. iii. Where appropriate by reason of discovery, the Contracting Officer may order delays in the time of performance and/or changes in the work. If such delays and/or changes are ordered, the time of performance and contract price shall be adjusted in accordance with Changes clause.

iv. The Contractor will be responsible for protecting the cultural resources within and adjacent to the project area from damage. In addition, the Contractor will be liable for all damage to the cultural resources caused by their actions or the actions of their agents or representatives. The Contractor shall immediately notify the Contracting Officer or their representative if any damage occurs to any cultural resource and immediately suspend work in the area in which damage has occurred until authorized to proceed.

v. The Contractor agrees to include this language within all subcontracts.

ITEM 2 – PROTECTING EXISTING UTILITIES

2.1 Protecting Existing Utilities: Notify Contracting Officer (CO), Contracting Officer's Representative (COR) and utility companies as required to request location services prior to and to coordinate any excavation/digging operations, and/or for demolition if within Scope of Work.

2.2 Contractor shall be responsible for locating and preventing damage to known utilities on site or indoors. If contractor damage occurs, alert CO and COR as soon as safely possible, and repair utility at no additional expense to the Government. If damage occurs to an unknown utility, contact CO and COR as soon as safely possible.

2.3 Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Government or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated below:

Notify CO and COR not less than two business days in advance of proposed utility interruptions.

A. Hours for Utility Shutdowns: Shutdowns shall not exceed 2 to 3 hours. Temporary provisions will be needed by the Contractor for periods longer than stated allowance or if required for critical systems as determined by COR.

ITEM 3 - CONTRACTOR'S USE OF PREMISES

3.1 Conduct of Operations: At all times the contractor shall conduct his operations in conformance with the rules and regulations promulgated by the Secretary of the Interior for the National Park Service, and applicable park rules and regulations prescribed by the Park Superintendent.

A. Communications: Contractor shall provide the Contracting Officer and COR with methods of communication including land and/or cell phone numbers (note some areas of work have limited service coverage), email and in case of emergency 24-hour contact options for duration of time operations.

B. No signs or advertisements (except those specified herein and as required for safety) shall be displayed on the construction site or within the park unless approved by the Contracting Officer.

C. Smoking is not permitted within any Federal building or within 25 feet of entrances, operable windows, or outdoor air intakes. Contractor must coordinate with the COR to establish and manage designated smoking areas.

D. Public Use of Site: Contractor shall at all times conduct operations to ensure the least inconvenience to the public. The site is located in downtown St Louis with limited availability for lay down space and will be difficult to get deliveries of equipment. All deliveries will need to be coordinated if road closures are necessary. Cranes for moving the cooling tower will need to be carefully placed to avoid heavy loads on the underground visitor's center. Contractor will have very limited lay down and storage space.

E. The Gateway Arch National Park Superintendent's Compendium for 2026 lays out operational activities that are allowed in the park to preserve the physical site and experiences for all visitors. It can be found at Superintendent's Compendium for 2026 - Gateway Arch National Park (U.S. National Park Service)

3.2 On-site work hours: Work shall be generally performed during Facility Office normal business working hours of 7 a.m. to 4 p.m., Monday through Friday, except when otherwise indicated.

A. Work on Saturdays, Sundays, Federal holidays, early morning, or at night may not be performed without prior consent from the CO and COR. Submit requests for work outside of the stated normal business hours to the CO and COR for approval at least 48 hours in advance of the work.

The following Federal holidays are observed by the National Park Service:
New Year Day
Martin Luther King, Jr's Birthday
Washington's Birthday
Memorial Day
Juneteenth National Independence Day
Independence Day
Labor Day
Columbus Day
Veterans Day
Thanksgiving Day
Christmas Day

B. Note: Any of the above holidays falling on a Saturday will be observed on the preceding Friday: holidays falling on Sunday will be observed on the following Monday. The specific day that each holiday is recognized for each year can be found at the following site: Federal Holidays (opm.gov).

3.3 Contractor Use of Site:

A. General: Contractor shall have limited use of the site for construction operations. Limit use of premises to construction area as shown on site plan on the coversheet. Contractor is to take special note of crane location for cooling tower install to avoid heavy loads on the museum space below. Stay on the exposed aggregate sidewalk until as much as possible. Do not disturb portions of Project site beyond areas in which the Work is indicated.

B. Driveways and Entrances: Keep driveways, access roads, and entrances serving premises clear and available to Government, Government's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials. Schedule deliveries to minimize use of driveways and entrances.
   a Only working vehicles will be permitted on site.
   b Limited Parking is available at the Old Cathedral and nearby parking garages.

C. Do Not disturb site outside of noted disturbance area, including earthwork and clearing of vegetation, to: NA

D. Utilities

1. General: Power and water can be obtained from the building.

2. Waste Operation:

   a. Toilets: Park Restrooms will be provided at each building.
   b. Solid Waste Removal / Recycling: Contractor is responsible for removing all waste created by the project. Contractor shall recycle to the highest degree possible and empty dumpsters as necessary to avoid debris on site. Locate as shown on site plan or coordinated with COR.

DI. Security and Protection facilities:

1. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction in ways and by methods that comply with state and federal environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
2. Cleaning of Equipment: The Contractor shall ensure that prior to moving on to the Project Area, all equipment is free of soil, seeds, vegetative matter, or other debris that could contain or hold seeds. Ensure that all equipment has been pressure-washed and is free of exotic species prior to start-up of operations and moving of equipment to Project Area. Equipment shall be considered free of soil, seeds, and other debris when a visual inspection does not disclose such material. Disassembly of equipment components or specialized inspection tools are not required.

3. Tree, sod and Plant Protection: The Contractor shall furnish and install appropriate ground protection mats (e.g., composite, timber, or equivalent) whenever vehicles or equipment are driven or operated off paved or improved surfaces. Mats shall be installed in a manner sufficient to prevent rutting, soil compaction, damage to landscaping, underground utilities, or existing site features. The Contractor shall be responsible for the installation, maintenance, and removal of all ground protection mats and for restoring disturbed areas to their original condition upon completion of the work.

4. Pest Control: Follow best practices to minimize attraction and harboring of rodents, roaches, and other pests and to perform extermination and control procedures at regular intervals so Project will be free of pests and their residues at project completion. Perform control operations lawfully, using environmentally safe materials.

5. Temporary Enclosures: Provide temporary enclosures such as snow fence as required for protection of construction in progress and completed, from access by visitors or staff, other construction operations, and similar activities.

6. Site Enclosure Fence: N/A

7. Hot Work Permit: Submit HW-1 Hot work permit form and receive approval from COR prior to Hot work activities commencing on site.

3.4 Storage - Staging Areas:

A. Confine Storage of materials and equipment to the project staging area noted on the cover sheet. Specific storage units shall be provided by the contractor and exact location within staging area will be discussed at the preconstruction briefing. All storage units provided by the contractor shall be in a clean and acceptable condition to the COR. Security of the materials and equipment on site is the Contractor's responsibility. See coversheet for more details.

3.5 Preservation of Natural Features: N/A.

3.6 Hauling Restrictions: Contractor shall verify and be responsible for the path accessing the site and obtaining / maintaining all local, state and federal permits/licenses associated with hauling/road requirements and dumping of materials associated with the project.

3.7 Housekeeping:

A. Keep project neat, orderly, and in a safe condition at all times.

1. Dispose of waste materials and recycling legally outside the park. The contractor shall not use park dumpsters

2. Address Recycling: Government goal is to salvage and recycle as much nonhazardous construction waste as possible. Use sustainable methods to extent possible during this project, recycling material as is probable with local means. Maintain accurate documentary records for submittal of all recycled materials used including fly ash and slag cement. Records will be submitted to COR detailing construction debris in CY or Tons.

3.8 Occupancy Requirements for Buildings:

A. Existing Buildings:

1. Full Government Occupancy: Government will occupy buildings that will be under construction during the entire contract period. Cooperate with Government during construction operations to minimize conflicts and facilitate Government usage. Perform the Work so as not to interfere with Government's day-to-day operations. Maintain existing exits, unless otherwise indicated.

   a. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from the CO or COR.
   b. Maintain existing building in a weather tight condition throughout construction period. Repair damage caused by construction operations. Protect building and its occupants during construction period.

B. New /Existing Buildings Unoccupied: N/A

3.9 Photo Documentation:

A. Contractor must provide existing condition, progress, and completion photos. All photos shall be in focus, show maximum range of depth of field general photo and then close up detail photo as needed. Shall be in JPEG digital form and **submitted preferably electronically by** **utilizing an encrypted thumb drive** within 7 days from time of taken or as approved by COR.

B. Existing Condition Images:

1. Before starting construction, take color, dated, digital images of project site and adjacent property/roads/etc. that may be impacted by construction activity/traffic. Include existing items to remain or be salvaged from different vantage points and with context for location identification.

C. Construction Progress Images:

1. Document all sub-surface work/ trenches etc. prior to backfill with photos covering enough overall field view to show location and then zoom in for details. (Locations and dimensions shall also be noted on as built drawing set.)
2. Maintain organized index for photos with date, description, etc.
3. Additional images as needed when questions or emergency situations occur. Submit within 24 hours.

D. Completion Images:

1. Document all completed work within scope of work.
2. Maintain organized index for photos with date, description, etc..
3. Additional images as needed when questions or emergency situations occur. Submit within 24 hours.

3.10 Fire and Life Safety:

B. As a minimum, conduct one weekly 15 minute "toolbox" safety meetings. These meetings shall be conducted by a foreman or supervisor and attended by all construction personnel at the worksite. Topics need to coincide with work scheduled for the following week. Document and submit meeting minutes to the CO and COR within one day after the meeting and document the meetings on the daily reports.

C. Comply with the requirements of NFPA 241 (Standard for Safeguarding Construction, Alteration, and Demolition Operations). Take all necessary precautions to prevent fire during construction. Provide adequate ventilation during use of volatile or noxious substances.

D. Store and handle hazardous materials in accordance with manufacturers and OSHA 29CFR1926 Subpart D requirements 1926 | Occupational Safety and Health Administration (osha.gov). Maintain readily available, on site, MSDS/Safety Data Sheets (SDS) for each chemical.

1. Immediately report all spills of hazardous materials to the CO, COR, and park.
2. Maintain a spill emergency response kit.
3. Train employees how to respond to a spill and use the emergency response kit.

3.11 Noise and Acoustics Management

A. Contractor shall not have personal radios or other media sources, and they shall not be broadcast within NPS property.

B. Noise Control: Perform sheet metal cutting and installation operations to minimize noise. Perform noise-producing work in less sensitive hours of the day or week as directed by the Contracting Officer or COR.

C. Repetitive and/or intermittent, high-level noise: N/A

ITEM 4 - COMMENCEMENT, PROSECUTION, AND COMPLETION

4.1 The Contractor shall commence work in accordance with the terms and conditions of the contract. Contractor shall coordinate and incorporate long lead and delivery time items within the schedule.

ITEM 5 - EXAMINATION OF THE SITE

5.1 All bidders are urged to visit the job site and examine existing conditions before submitting bids. Contractors will be accountable for understanding existing conditions. No cost changes for items visible during site visit will be allowed.

ITEM 6 - ABBREVIATIONS

6.1 The list of abbreviations, standards and organizations which may be used in/referred within the Construction Specifications or Special Provisions, may be found linked from the listed page below. On the home page, follow the link under "Contracting and Procurement" labeled "NPS Reference Standards." https://www.nps.gov/orgs/1671/do-business-with-us.htm

ITEM 7 - ACCIDENT PREVENTION

7.1 Description: The work of this section consists of establishing and implementing an effective accident prevention program (APP) and providing a safe environment for all personnel and visitors.

7.2 Submittals:

A. Accident Prevention (Safety) Plan (APP): Submit a site-specific accident prevention (safety) plan. The Plan shall be written to comply with OSHA and project requirements (a generic plan is not acceptable) including but not limited to the following:
   1. Name and qualifications of responsible supervisor to carry out the program.
   2. First aid and rescue procedures.
   3. Training, both initial and continuing.
   4. Outline of each phase of the work, the hazards associated with each major phase, and the methods proposed to provide for property protection and safety of the public, National Park Service personnel, and Contractor's employees. Identify the work included under each phase, with a Job Hazard Analysis (JHA)/Job Safety Analysis (JSA), etc. A sample JHA template may be provided upon request.
   5. Planning for possible emergency situations, such as earthquake, explosions, fires, floods, power outages, and windstorms. Such planning shall take into consideration the nature of construction, site conditions, and degree of exposure of persons and property.
   6. Contractor to identify nearest location of medical facility for emergencies
   7. Recognition that works will be performed in remote areas with limited communication or cell phone coverage if applicable.
   8. Supplemental hazard specific plans may be required IAW 29 CFR 1926 or 1910.

B. Meeting and Inspection Reports: Safety Meetings: As a minimum, conduct 15 minute "toolbox" safety meetings. These meetings shall be conducted by a foreman and attended by all construction personnel at the worksite. Submit a report of safety meetings and inspections to CO and COR within one day after the meeting and document the meetings on the daily reports.

7.3 Qualification of Employees:

A. Ensure that employees are physically qualified to perform their assigned duties in a safe manner to include operators of vehicles and equipment. Provide operating instructions for all equipment.

B. Do not allow employees to work whose ability or alertness is impaired because of drugs, fatigue, illness, intoxication, or other conditions that may expose themselves or others to injury.

7.4 Accident Reporting: The Contractor shall report all accidents to the CO and COR as soon as safely possible and assist the CO and COR and other officials as required in the investigation of the accident.

7.5 First Aid Facilities: Provide access to facilities for the number of employees and appropriate to the hazards associated with the types of ongoing construction work at the site.

7.6 Park will provide emergency fire, life safety, and site access protocol at preconstruction meeting.

7.7 Personal Protective Equipment (PPE): It is the Contractor's responsibility to require all those working on or visiting the site to wear necessary protective equipment at all times.

A. PPE must meet requirements of applicable ANSI standards. Selection shall conform to OSHA 29CFR 1926 Subpart E.

B. A hard hat use area shall be designated by the Contractor. The hard hat area shall be posted by the Contractor in a manner satisfactory to the Contracting Officer.

C. All PPE will be serviceable at all times. At a minimum, maintain four sets of PPE including hard hats and all other Accident Prevention Plan required equipment.

7.8 Hazardous Materials: It shall be the responsibility of all operators and contractors, functioning within the park to properly cleanup, mitigate and remediate if necessary, all unauthorized discharges of hazardous materials or non-hazardous chemical and biological products released from fleet and/or other support vehicles or stationary sources. Response shall be consistent with guidelines established by federal, state, and local regulations, and as outlined within the operator's Safety or Hazardous Materials Business Plan.

A. If a spill, leak, or other release occurs, the operator shall as soon as possible, without impeding cleanup, notify the local 911 Emergency Response, COR and or the National Park Service Emergency Dispatch. Park requests SDS sheets be submitted to COR at first notification of hazardous material discharge in the park.

ITEM 8 - PRECONSTRUCTION CONFERENCE

8.1 The Contracting Officer will conduct a preconstruction conference, the successful offeror will be notified and will be required to attend. The Contracting Officer's notification will include specific details regarding the date, time, and location of the conference, any need for attendance by subcontractors, and information regarding the items to be discussed. See Item 9.1C below.

ITEM 9 - SUBMITTALS

9.1 General Contracting Submittal Procedures:

A. General: Prepare and submit submittals required by individual Technical Specification Sections. Types of submittals are indicated in individual specific sections.

1. CM-16 Transmittal Form: All submittals shall be transmitted via electronic email using National Park Service form CM-16 form. The form will be provided by the Contracting Officer. No action will be taken on a submittal item unless accompanied by the CM-16 transmittal form. Submit completed CM-16 forms to the CO and the COR

B. Submittal List: administrative required submittals are listed below in 9.1.C and does not include technical section submittal requirements included in each technical section.

C. Preconstruction Conference Submittal: Satisfactory evidence of liability insurance coverage and workman's compensation, and any applicable bonds, must be submitted within 10 calendar days of Notice of Award. The following items are to be submitted prior to the Preconstruction Conference or as specified at the CO's discretion. The timeline for the documents to be submitted will be addressed at the pre-construction conference for those items that were not received and approved prior. Notice to Proceed may not be issued, and the Contracting Officer will consider other contractual remedies if not resolved as directed. Work shall not commence until written Notice to Proceed has been issued. Contracting Officer will notify Contractor of tentative date for the Pre-Construction Conference:

1. Letter designating Project Superintendent.
2. Construction Schedule. (Must include shop drawings, procurement time including long lead time items, mobilization, trade work progression and completion at minimum.)
3. A comprehensive breakdown of the Schedule of Values.
4. Accident Prevention (Safety) Plan (see section 7 of this document).
5. A list of Subcontractors for this project.

6. Written statements from subcontractors certifying compliance with applicable labor standard clauses (SF1413).
7. Quality Control Plan.

9.2 Project Submittal Process (Shop Drawings, Product Data, and Samples): Contracting Officer will provide sample cover sheet, and a list of required submittals is included in each technical specification or attached at the end of this document.

A. Shop Drawings: Indicate all coordinating materials and work impacting the installation coordination, connection details, anchorage requirements, hardware locations, and installation details and locations.

1. Submit Shop Drawings according to Part 9.1 of this section to include one digital file (PDF/jpg) and two full size hardcopy documents to COR.

B. Product Data: Provide component construction and specification data sheets, anchorage requirements and any other product specific data.

1. Submit Product Data according to Part 9.1 of this section to include one digital file (PDF) to COR.

C. For submittals specified above, forward submittals to Contracting Officer and COR at least 15 days before need for approval (depends on length of project).

D. After approving submittals, Contracting Officer and/or COR will return one copy to the Contractor. If submittals are not approved, Contracting Officer will return all copies to Contractor with reasons for rejection. Resubmit, identifying changes. Any work done before approval shall be at Contractor's own risk.

9.3 Approved Equals: All brand names noted are subject to 'or equal' products. If an item in this solicitation is identified as "brand name or equal" or lists more than 1 manufacturer, the description of the proposed item must reflect the characteristics and level of quality that will satisfy the Government's needs as demonstrated by the salient physical, functional, or performance characteristics that "equal" products must meet and/or exceed that as specified in the solicitation or relevant specification. Contractor shall incorporate and be responsible for all collateral costs due to the or equal proposed as required to provide a complete project.

A. For each item proposed as an "approved equal," submit supporting data, including:

1. Drawings and samples as appropriate.
2. Comparison of the characteristics of the proposed item with that specified and with the salient characteristics provided.
3. Changes required in other elements of the work because of the substitution.
4. Name, address, and telephone number of vendor.
5. Manufacturer's literature regarding installation, operation, and maintenance, including schematics for electrical and hydraulic systems, lubrication requirements, and parts lists. Describe availability of maintenance service and state source of replacement materials.

A. A request for approval constitutes a representation that General Contractor:

1. Has investigated and shall provide documentation in request showing that the proposed item is equal or superior in all respects to the salient characteristics specified.
2. Will meet or exceed warranties for the proposed item specified.
3. Has determined that the proposed item is compatible with interfacing items.

4. Will coordinate the installation of an approved item and make all changes required in other elements of the work because of the substitution.
5. Waives all claims for additional expenses that may be incurred as a result of the substitution.

B. Approved Equals will be evaluated and approved/disapproved during the submittal process.

9.4 Schedule of Values: Submit the Schedule of Values a minimum of one week prior to the Preconstruction Conference for COR review. Schedule of Values shall include defined work line items with cost breakdowns including labor, material, and equipment for COR approval.

9.5 Progress Reporting: The initial Construction Schedule and Schedule of Values are required a minimum of one week prior to the Preconstruction Conference. After the Notice to Proceed is issued and after on-site work begins, progress will be documented via daily logs and by providing an updated Construction Schedule and Schedule of Values when requested, but minimally with each pay application. Submit digital copy electronically (PDF preferred) of all required documents. Construction Schedules are normally in bar chart form and indicate estimated starting and completion dates for each part of the work. For a pay application to be reviewed and processed in a timely manner, the following information must either be submitted prior to or accompany submission of the pay application:

A. Daily/weekly progress reports during construction as part of the administration process.

B. Updated Schedule of Values: Breakdown each lump-sum item into component work activities used in the schedule, for which progress payments may be requested. The Schedule of Values will form the basis for payment. The work activities broken out within the schedule of values shall be integrated into and made a logical part of the construction baseline schedule submitted under this specification. The total costs for the component work activities shall equal the contract price for that lump-sum item. The Contracting Officer may request data to verify accuracy of dollar values. A sample Schedule of Values format may be provided upon request.

ITEM 10 – TEMPORARY SERVICES

10.1 It is the Contractor's responsibility to provide temporary services, equipment, tools, and skilled labor as required for the chosen means and methods to perform the work in accomplishing this Contract.

ITEM 11 - PROJECT CLOSEOUT

11.1 Description: The work of this section consists of final cleanup, closeout submittals, final inspection procedures working toward Final Acceptance.

11.2 Cleaning: Remove all tools, equipment, surplus materials, and rubbish. Move attic stock to location coordinated with COR. At time of final inspection, project shall be thoroughly clean and ready for intended use. Inspector holds the right to reschedule if project is not ready for inspection.

11.3 Completion and Final Inspection: Contractor shall submit written certification of project completion and request a final inspection to the Contracting Officer and COR. The Contracting Officer or designee will make an inspection within 10 days of receipt of request or at a mutually agreeable time.

A. If the work is determined to be complete following the final inspection with minor comments, the COR will prepare and provide the Contractor a Punch List noting outstanding items to be addressed.
B. If the work is not determined to be complete following the final inspection, the Contracting Officer will notify Contractor in writing, stating reasons. Contractor, after completing the work according to the Contract Documents, shall

resubmit completion and request a new final inspection. Re-inspection costs may be charged against the Contractor in accordance with the Inspection of Construction contract clause.

C. Contractor shall complete the Punch List within 30 calendar days, or a time directed by the CO.

D. Once Contractor completes all items of work on the Punch List and all contractually required items are accepted, Contracting Officer will issue Letter of Final Acceptance of Work and request the final pay application.

E. If the Contractor fails to complete the work within the time frame, the Contracting Officer may correct the work with an appropriate reduction in contract price or charge for re-inspection costs in accordance with the Inspection of Construction contract clause.

F. Disposition of any permits and warranties required by the specifications in this section.

11.4 Final Acceptance of the Work: After all punch list deficiencies have been corrected, a Letter of Final Acceptance will be issued. A Release of Claims document must be executed and submitted to the Contracting Officer before final payment can occur.

11.5 Warranties

A. Construction Warranty shall be based on date of final acceptance of the work and remain in effect for one year.

B. Provide all manufacturer warranty information of products installed organized by Division. All contact information, extent of coverage and conditions shall be clearly noted as well as date of overall final acceptance.

C. Information shall include operation and maintenance manuals for each warranted product.

ITEM 12 DEFINITION OF CONTRACT LINE ITEMS

12.1 Summary

A. The intent of this section is to explain, in general, what is and what is not included in a contract line item, and the limits or cut off points where one item ends and another begins.

B. If no contract line item exists for a portion of the work, include the costs in a related item.

12.2 List of Contract Line Items

A. Contract Line Item No.1 Cooling Tower Replacement
Payment will be made per the contract and percentage of completion level.

B. Contract Line Item No.2 Boiler Replacement.
Payment will be made per the contract and percentage of completion level.

PART 2 – PRODUCTS (NOT USED)
PART 3 – EXCUTION (NOT USED)

END OF SECTION