GENERAL GRANT NATIONAL MEMORIAL
NEW YORK, NEW YORK

REPLACE EPDM ROOF AT GEGR
GEGR
247283

PROJECT SPECIFICATIONS

NATIONAL PARK SERVICE (NPS)
DENVER SERVICE CENTER (DSC)

April 15, 2026

TABLE OF CONTENTS

DIVISION 01 – GENERAL REQUIREMENTS

01 11 00 Summary of Work
01 26 01 Contract Modification Procedures
01 27 00 Definition of Contract Line Items
01 31 00 Project Management and Coordination
01 32 16 Construction Schedule
01 32 33 Photographic Documentation
01 33 23 Submittal Procedures
01 35 23 Safety Requirements
01 35 91 Historic Preservation Treatment Procedures
01 40 00 Quality Requirements
01 42 00 Reference Standards
01 50 00 Temporary Facilities and Controls
01 57 19.11 Indoor Air Quality (IAQ) Management
01 57 19.12 Noise and Acoustics Management
01 57 23 Under-an-Acre Pollution Prevention (UPP)
01 67 00 Product Requirements
01 73 40 Execution
01 74 19 Construction Waste Management and Disposal
01 77 00 Closeout Procedures
01 78 23 Operation and Maintenance (O&M) Data

DIVISION 02 – EXISTING CONDITIONS

02 42 97 Selective Removals and Salvaging

DIVISION 04 – MASONRY

04 03 43 Historic Stone Masonry Repointing

DIVISION 06 – WOOD, PLASTICS, AND COMPOSITES

06 10 53 Miscellaneous Rough Carpentry

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

07 01 50.19 Preparation for Reroofing

07 14 16	Cold Fluid-Applied Waterproofing
07 53 23	Ethylene-Propylene-Diene-Monomer (EPDM) Roofing
07 62 00	Sheet Metal Flashing and Trim
07 79 00	Preformed Joint Seals
07 92 00	Joint Sealants

DIVISION 09 – FINISHES

09 96 00	High-Performance Coatings

DIVISION 22 – PLUMBING

22 14 23	Storm Drainage Piping Specialties

SECTION 01 11 00 - SUMMARY OF WORK

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes the following:

1. Work Covered by Contract Documents.
2. Work Phases.
3. Work under Other Contracts.
4. Contractor Use of Site.
5. Public Use of Site.
6. Occupancy Requirements for Buildings.
7. Conduct of Operations.
8. Work Restrictions.

1.2 WORK COVERED BY CONTRACT DOCUMENTS

A. Project Location: General Grant National Memorial, Riverside Drive and 122nd Street, New York, NY.

B. The Work consists of:

1. Removal and replacement of failed roofing systems at the Memorial structure; repointing stone joints at the dome; resealing stone surfaces at the drum; repainting exterior doors and hatches.

2. Options include painting steel structural elements supporting the stone dome; and cleaning and pointing at the stone roof over the porch.

C. Project will be constructed under a single prime contract.

1.3 WORK PHASES

A. The Work shall be conducted in a single phase.

1.4 WORK UNDER OTHER CONTRACTS

A. General: Cooperate with separate contractors so work on those contracts may be carried out smoothly, without interfering with or delaying work under this Contract. Coordinate Work of this Contract with work performed under separate contracts.

B. Concurrent Work: Government does not anticipate award of separate contract(s) at Project site.

1.5 CONTRACTOR USE OF SITE

A. General: Contractor shall have limited use of site for construction operations. Limit use of premises to work in areas indicated on drawings. Do not disturb portions of Project site beyond areas in which the Work is indicated.

1. Limits: Confine constructions operations to Memorial roof areas and designated staging areas and access routes.

B. Storage of Materials: Confine storage of materials to staging area and roof areas as approved by the Contracting Officer.

C. Parking: Confine parking to staging area and other locations as indicated. General parking for construction workers is not provided.

D. Preservation of Natural Features:

1. Prevent damage to natural surroundings. Restore damaged areas, repairing or replacing damaged trees and plants, at no additional expense to the Government.
2. Provide temporary barriers to protect existing trees and plants and root zones.
3. Do not remove, injure, or destroy trees or other plants without prior approval. Consult with Contracting Officer (CO) and remove agreed-on roots and branches that interfere with construction.
4. Do not fasten ropes, cables, or guys to existing trees.
5. Carefully supervise excavating, grading, filling, and other construction operations near trees to prevent damage.

E. Driveways and Entrances: Keep driveways entrances serving premises clear and available to Government employees, and emergency vehicles at all times. Do not use for parking or storage of materials.

1. Schedule deliveries to minimize use of driveways and entrances.
2. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.

F. Construction Camp: Establishment of a camp within park will not be permitted.

G. Hauling Restrictions: Comply with legal load restrictions in hauling of materials. Load restrictions on park roads are identical to state load restrictions with such additional regulations as may be imposed by the Park Superintendent. Information regarding rules and regulations for vehicular traffic on park roads may be obtained from the Office of the Park Superintendent. A special permit will not relieve Contractor of liability for damage which may result from moving of equipment.

1.6 PUBLIC USE OF SITE

A. Contractor shall conduct his operations to ensure the least inconvenience to public. Monument and partial site closures may be permitted, when required, upon specific approval of Contracting Officer for a maximum of 24 hours. Submit requests 3 business days in advance of the closure to

the Contracting Officer for approval. Do not obstruct access to the Security Booth, or entrance to the Monument without prior approval of the Contracting Officer.

1.7 OCCUPANCY REQUIREMENTS FOR BUILIDINGS

A. Existing Buildings:

1. Full Government Occupancy: Government will occupy buildings under construction during the entire contract period. Cooperate with Government during construction operations to minimize conflicts and facilitate Government usage. Perform Work so as not to interfere with Government's day-to-day operations. Maintain existing exits, unless otherwise indicated.

   a. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Contracting Officer.
   b. Maintain existing building in weather tight condition throughout construction period. Repair damage caused by construction operations. Protect building and occupants during construction period.

1.8 CONDUCT OF OPERATIONS

A. Contractor shall conduct his operations in conformance with rules and regulations promulgated by the Secretary of the Interior for the National Park Service, and applicable park rules and regulations prescribed by Park Superintendent.

B. Work on Saturdays, Sundays, Federal holidays or at night may not be performed unless stated in the Work Restrictions below or without prior consent from the Contracting Officer. Submit requests 3 business days in advance of the work to the Contracting Officer for approval.

C. No signs or advertisements (except those specified herein) shall be displayed on the construction site or within the park unless approved by the Contracting Officer.

1.9 WORK RESTRICTIONS

A. On-Site Work Hours: Work shall be generally performed during normal business working hours of 7:00 a.m. to 3:00 p.m., Monday through Friday, except when otherwise indicated.

1. Weekend Hours: Only as approved in writing 72 hours in advance by the Contracting Officer.
2. Early Morning Hours: Only as approved in writing 72 hours in advance by the Contracting Officer.

B. Existing Utilities:

1. Contractor shall be responsible for locating and preventing damage to known utilities in work area, staging areas, and access routes. If damage occurs, repair utility at no additional expense to the Government.

2. If damage occurs to an unknown utility, repair utility. An equitable adjustment will be made in accordance with the Changes clause of the contract.

C. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Government or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:

1. Notify Contracting Officer in writing not less than three business days in advance of proposed utility interruptions.
2. Do not proceed with utility interruptions without Contracting Officer's written permission.
3. Hours and Length of Utility Shutdowns: As determined by the Contracting Officer.

D. Nonsmoking Building/Tobacco Use/Vaping: Smoking and vaping are not permitted within building, on roofs, or within 25 feet of entrances, operable windows, outdoor air intakes, or visitor-occupied site areas.

1.10 SPECIFICATION AND DRAWING CONVENTIONS

A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:

1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.

B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.

C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:

1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specification Sections.
2. Abbreviations: Materials and products are identified by abbreviations published as part of the U.S. National CAD Standard and scheduled on Drawings.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 11 00

SECTION 01 26 01 – CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section consists of administrative and procedural requirements for contract modifications.

1.2 DEFINITIONS AND ALLOWANCES

A. Home Office Overhead: Costs incurred in support of all of a contractor's projects and not attributable to a specific job. The cost for home office overhead is only allowed as a percentage of all direct work excluding profit. The following items represent allowable home office overhead costs identified in Part 31 of the Federal Acquisition Regulation (FAR):

1. Rent.
2. Utilities.
3. Furnishings.
4. Office equipment.
5. Executive and management staff not exclusively assigned to the project.
6. Support, accounting, and administrative staff.
7. Preparation of cost proposals, estimating, and schedule analyses connected with Modifications.
8. Estimating and preconstruction services.
9. Mortgage costs.
10. Real estate and corporate taxes.
11. Automobile maintenance and travel costs for home office personnel.
12. Home office insurances i.e. structure, automotive, umbrella, flood, etc.
13. Depreciation of equipment and other assets.
14. Home office supplies (paper, staples, etc.)
15. Legal services.
16. Accounting and data processing.
17. Professional fees/registration.

B. General Conditions (Field Office Overhead): Management and administrative costs incurred on site for the designated project. Costs associated with preparation of modifications will not be allowed. Costs for these items are to be included only in the general conditions of the modification estimate. Only in the case of a contract time extension are additional general conditions included in modifications. The following items, if applicable, are considered allowable costs for calculating General Conditions:

1. Project Manager (PM), Assistant Project Manager.
2. Superintendent, Assistant Superintendent.
3. Quality Control, Safety Officer, Environmental Manager, etc.
4. Engineers.
5. Travel, lodging, and per diem (as established by Federal Travel Regulations).
6. Scheduling.

7. Field Office Trailers and associated temporary utilities.
8. Field office supplies.

    a. Mailing and couriers.
    b. Reproduction costs.
    c. Storage.
    d. Phones.
    e. Computers.
    f. Copiers.

9. Personal vehicles i.e. Superintendent Pickup trucks.

C. General Requirements: Costs directly associated with the project and are necessary to perform the actual work of the modification. These costs shall be shown as direct costs in the estimate. The following items, if applicable, are considered allowable costs for calculating General Requirements:

1. Hoisting.
2. Material handling.
3. Temporary fencing.
4. Port-a-lets.
5. Trash removal, dumpsters.
6. Barricades.
7. Small tools.
8. Safety supplies.
9. Scaffolding.
10. Daily cleaning.
11. Traffic control.
12. Temporary signage.
13. Temporary heating and power.

D. Personnel Costs: Costs included in the modification must only be for General Conditions staff and workers actually present and working on project site. Modification costs for salaried workers are only allowed within the structure of a 40-hour week and no overtime or holiday pay will be allowed.

1. Worker Hourly Rates are costs directly associated with the individual worker and consist of the following:

    a. Base Rate: The hourly rate paid directly to the worker.
    b. Labor Burden: Employer payments of all applicable burdens; includes insurance and taxes the business must pay on behalf of the worker to government entities and educational forums, such as:

        1) Social Security.
        2) Medicare.
        3) Workers Compensation – Policy and company calculation to be made available.
        4) Federal Unemployment Tax Act (FUTA) - Cap Rate and percentage to be proportionally allocated over one year.
        5) State Unemployment Tax Act (SUTA) - Cap Rate and percentage to be proportionally allocated over one year.

6) Union agreement costs - Other costs required under an enforceable collective bargaining agreement.

c. Fringe Benefits: Various non-wage compensations provided to employees such as:

1) Health Care Insurance Premiums.
2) Cell Phone.
3) Clothing.
4) 401K and Pensions.
5) Vehicle allowances.
6) Gas allowance.
7) Life insurance premiums.
8) Disability insurance.
9) Other Fringe Benefits required under an enforceable collective bargaining agreement.

E. Bonuses or Deferred Compensation: No Bonus or Deferred Compensation will be allowed within any components of pricing including Home Office Overhead, General Conditions, General Requirements, Hourly Worker Rates, or the direct costs of work.

F. General Liability Insurance: An insurance policy that protects Contractor from claims resulting from bodily injury or property damage to a third party. Include as a separate line item within all modification proposals and provide a current insurance quote upon request.

G. Performance and Payment Bonds: A performance bond is a surety bond issued by an insurance company or bank to guarantee satisfactory completion of a project. The Payment Bond guarantees the Contractor will pay the labor and material costs incurred. Banks and Insurance companies charge a premium for individual project based on a sliding scale related to the size of the project. Include as a separate line item in modification proposals and provide current company bonding rates upon request.

H. Builder's Risk Insurance: Covers the contractor's loss due to fire, high winds, or other natural forces. Not reimbursed by the National Park Service (NPS) and shall not be included in modification proposals.

1.3 MODIFICATION PROPOSAL PRICING REQUIREMENTS

A. General:

1. Proposal be received in the format and within the time frame specified in the Request for Proposal (RFP) letter. Costs or delays resulting from failure of contractor to submit within the time frame specified will not be compensable.
2. Proposal shall be detailed with itemized lists of equipment, materials, labor, production rates, overhead, profit, and bond markup for each item. Labor costs must be itemized by craft and hourly rate, including Fringe Benefits and Labor Burden. If the costs of Fringe Benefits and Labor Burden are not itemized, it is assumed they are included in the hourly rate shown, or contractor is not requesting reimbursement. Contractor may utilize the government provided Contractor Estimate Form, or their own form, provided that it contains the same information and level of detail as the Government's form.

Contractor Estimate Form is also available here: http://www.nps.gov/dscw/publicforms.htm#CP___PAGEID=396735|

3. Requests for extensions of contract time as a result of change must be justified with a Time Impact Analysis (TIA). Refer to Section 01 32 16 "Construction Schedule", for time impact analysis requirements. TIA and associated costs shall be received with the proposal by the date shown within the Request for Proposal letter. Contractor's failure to submit within the specified time frame will be construed as the Contractor waiving right for additional time and no time extension will be allowed.
4. All supporting documentation used to justify the proposed modification will be made available to the Contracting Officer (CO) upon request.
5. Contractor shall review and approve all subcontractor/supplier pricing in detail for proper format, scope, production rates, and pricing prior to submission to NPS. All delay costs associated with not reviewing and approving subcontractor/supplier pricing will be borne by the Contractor.
6. All pricing and production rates within the estimate must be based on fair and reasonable pricing and cannot include built-in contingency.

B. Labor:

1. Contractor shall estimate cost of labor by itemizing each craft involved, indicating worker hourly rate (base rate + labor burden + fringe benefits) for each and itemizing hours required for each craft directly engaged in modification work. Any work proposed requiring overtime work or premium pay shall be itemized separately. Rates shall be in accordance with the Davis-Bacon Act as incorporated herein. Labor Burden may include payroll taxes, Social Security, unemployment insurances, workers compensation insurance, Federal Insurance Contributions Act (FICA), FUTA, and other direct costs resulting from Federal, State or local laws.
2. Itemize labor costs for equipment operators separate from equipment costs.
3. Labor cost for foremen shall only be costs for related work required for the modification.

C. Materials:

1. Estimated cost for materials shall include quotes from multiple sources. Material prices shall include applicable fees and credits, including but not limited to, sales tax, freight and delivery charges, and tax rebates.
2. No markup shall be applied to any material provided by NPS.

D. Equipment:

1. Equipment used for the project must be appropriately sized for work being performed.
2. Do not include costs for "miscellaneous tools and equipment", in your proposal for a replacement value of $500 or less. Costs shown in excess of $500 shall be broken out separately.
3. Regardless of ownership, rates to be used in determining equipment rental costs shall be the lowest cost from one of the following sources:

   a. United States (U.S.) Army Corps of Engineers, Ownership and Operating Expense Schedule (use latest edition and applicable region)
   b. Construction Blue Book

c. Local equipment rental rates, documented by actual invoice charges, or itemized vendor quotes.

4. Estimated equipment rates shall include operating costs of all fuel, oil, lubrication, supplies, small tools, necessary attachments, ground engaging components, tires and tracks, routine repairs and maintenance (cost of major repair and overhaul is not allowed per Federal Acquisition Regulation (FAR) 31.105(d)(2)), depreciation, storage, insurance, and all incidentals. Mobilization, if applicable, may be included for equipment solely used on the modification work but must be listed separately.
5. Estimate full rate for equipment only for duration that equipment will be utilized to accomplish work of the modification.
6. Standby unit rates used in accordance with paragraph 1.3, D, 2, above. If the U.S. Army Corp of Engineers is utilized then their standby rates prevail. If Bluebook or local equipment pricing is accepted, then 1/2 of equipment costs minus any operating costs, major repair and overhaul will be accepted.
7. If equipment is in standby mode due solely to a documented NPS delay, established standby rate shall apply from the first day of the delay.
8. Equipment not used and on job site for up to five consecutive days may be classified at standby rates, provided the equipment is or has been used solely to perform work on the modification and will be necessary to complete additional modification work. Equipment still on the jobsite but not in use after five consecutive days will not be considered in the modification pricing.
9. Requests for compensation for equipment stand by time must be justified, documented and itemized separately.
10. The estimated timeframe (daily, weekly, monthly) for use of the equipment must reflect the lowest cost to the Government.

E. Establishment and Application of Overhead and Profit Percentages:

1. Home Office Overhead and Profit (OH&P) shall be applied to direct costs only. Profit shall not be applied to overhead amounts; and overhead shall not be applied to profit. Home office overhead shall contain only allowable, allocable, and reasonable costs per the contract documents and FAR Part 31. Profit percentages are based on risk factors found in FAR Part 31which have been applied to the specific type of work included in this project. Negotiated rates shall not exceed the following percentages for OH&P for contractor self-performed work:

Overhead……10%
Profit……7.75%

2. Total aggregate limit of markup (OH&P) for Contractor and Subcontractors on modification work shall not exceed 25%. The NPS will not be responsible for allocation of percentages between contractor and subcontractors at any tier.
3. If Contractors form a partnership, partnership may only receive home office overhead and profit in same amount as an individual Contractor (refer to paragraph 1.3,E,1 above). It is the responsibility of the partners to decide on division of revenue.
4. Combined Increases and Decreases: On proposals involving both increases and decreases in the Contract Price, overhead and profit mark-ups are required on net increases and deducted on net decreases.
5. At no time can profit be calculated on Overhead or itself, it must be calculated on direct costs of work only.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 26 01

SECTION 01 27 00 – DEFINITION OF CONTRACT LINE ITEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section explains in general, what is and is not included in a contract line item, and limits or cut-off points where one item ends and another begins.

B. If no contract line item exists for a portion of work, include costs in a related item.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 LIST OF CONTRACT LINE ITEMS

A. Contract Line Item Number 1: Replace EPDM Roof.

1. This item consists of removal and replacement of existing roof systems at the upper and lower roofs; sealing stone joints at the colonnade and upper roof gutter; repointing stone joints at the conical dome; repainting metal access doors at the drum and dome; repainting the metal roof system at the tin roof below the Dome Chamber; and other construction as indicated.
2. Measurement for payment will be Percent complete.
3. Payment will be made at the contract lump sum price.

B. Contract Line Item Number 2, Option A: Repair and repaint structural steel supports for stone dome.

1. This item consists of preparation and painting of the steel structure supporting the dome stones with a high-performance coating. Allow for plating repairs at severely corroded areas.
2. Measurement for payment will be percent complete.
3. Payment will be made at the contract lump sum price.

C. Contract Line Item Number 3, Option B: Porch Stone Roof – Clean and Repoint.

1. This item consists of cleaning and repointing the roof and gutter of the south colonnade. Remove all debris and organic growth. Clean out all scuppers and replace strainers.
2. Measurement for payment will be percent complete.
3. Payment will be made at the contract lump sum price.

END OF SECTION 01 27 00

SECTION 01 31 00 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:

1. Definitions
2. Construction Coordination.
3. Requests for Information (RFIs).
4. Project Meetings.
5. Environmental Coordination.

1.2 DEFINITIONS

A. Agency with Jurisdiction: An Agency that has been granted legal authority over a location, action, or resource. This authority includes the ability to issue a permit or other legal permission document.

1.3 CONSTRUCTION COORDINATION

A. Coordination: Coordinate construction operations included in different Sections of Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, which depend on each other for proper installation, connection, and operation.

1. Schedule construction operations in sequence required to obtain best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
2. Coordinate installation of different components with other contractors to ensure maximum accessibility for required maintenance, service, and repair.
3. Make provisions to accommodate items scheduled for later installation.
4. Where availability of space is limited, coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair of components, including mechanical and electrical.
5. Properly plan construction operations to include permit requirements. Allow enough time to execute permit provisions to maintain work schedule, site visits, inspections, and reporting deadlines.

B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.

C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities and activities of other contractors to avoid conflicts

and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to:

1. Preparation of Contractor's Construction Schedule.
2. Preparation of the Schedule of Values.
3. Installation and removal of temporary facilities and controls.
4. Delivery and processing of submittals.
5. Progress meetings.
6. Permit requirements.
7. Pre-installation conferences.
8. Project closeout activities.

1.4 SUBMITTALS

A. Division 01 Documents: The following items shall be submitted a minimum of one week prior to Preconstruction Conference. Contracting Officer will notify Contractor of tentative date for Preconstruction Conference.

1. Letter designating Project Superintendent.
2. Construction Schedule.
3. Comprehensive Schedule of Values.
4. Accident Prevention Plan.
5. List of Subcontractors for Project.
6. Written statements from Subcontractors certifying compliance with applicable labor standard clauses.
7. Certificates of Insurance or SF1413 for Contactor and all Subcontractors.
8. Waste Management Plan.
9. Quality Control Plan.
10. Under-an-Acre Pollution Prevention Plan (UPPP).
11. Indoor Air Quality (IAQ) Management Plan.
12. Historic Preservation Treatment Plan (HPTP).

B. Provide items listed to Contracting Officer before Preconstruction Conference. If all documents have not been received one week prior to scheduled Preconstruction Conference date, conference may be cancelled, Notice to Proceed may not be issued, and Contracting Officer will consider other contractual remedies. Work shall not commence until written Notice to Proceed has been issued.

1.5 REQUESTS FOR INFORMATION (RFIs)

A. General: Immediately on discovery of the need for additional information or interpretation of Contract Documents, Contractor shall prepare and submit an RFI.

1. Contracting Officer will not respond to RFIs submitted by other entities controlled by Contractor.
2. Coordinate and submit RFIs in a prompt manner to avoid delays in the work.

B. Content of RFI: Include detailed, legible description of item needing information or interpretation and the following:

1. RFI number, numbered sequentially.
2. Date.
3. RFI subject.
4. Specification Section number and title and related paragraphs, as appropriate.
5. Drawing number and detail references, as appropriate.
6. Field dimensions and conditions, as appropriate.
7. Contractor's suggested resolution: If Contractor's suggested resolution impacts Contract Time or Contract Sum, Contractor shall state impact in RFI.
8. Contractor's signature.
9. Requested date for response.
10. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.

    a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.

C. Contracting Officer’s Action: Contracting Officer will review each RFI, determine action required, and respond. Contracting Officer will determine critical nature of each RFI and issue response accordingly.

1. The following are not considered to be RFIs and will receive no action:

    a. Requests for approval of submittals.
    b. Requests for approval of substitutions.
    c. Requests for approval of Contractor's means and methods.
    d. Requests for coordination information already indicated in Contract Documents.
    e. Requests for adjustments in Contract Time or Contract Sum.
    f. Requests for interpretation of Contracting Officer’s actions on submittals.
    g. Incomplete RFIs or inaccurately prepared RFIs.

2. Contracting Officer's action may include a request for additional information; time for response will date from time of receipt of additional information.
3. Contracting Officer's action on RFIs may result in need for a change to Contract Time or Contract Sum. All contract changes will be processed following terms and conditions of contract.

1.6 PROJECT MEETINGS

A. Preconstruction Conference: Before start of construction, Contracting Officer will arrange an on-site meeting with Contractor. Meeting agenda will include the following as a minimum:

1. Roles & Responsibilities / Lines of Authority.
2. Park rules and regulations.
3. Jobsite Safety.
4. Resolution of comments on required Division 01 documents.
5. Coordination of Subcontractors.
6. Labor law application.
7. Modifications.
8. Payments to Contractor.

9. Payroll reports.
10. Contract time.
11. Liquidated damages.
12. Contractor Performance Evaluation.
13. Display of Hotline posters.
14. Notice to proceed.
15. Correspondence procedures.
16. Acceptance/rejection of work.
17. Progress meetings.
18. Submittal procedures.
19. NPS Final Accessibility Inspection.
20. Environmental requirements.
21. Permit requirements.
22. As-constructed drawings/operation and maintenance (O&M) manuals.
23. Saturday, Sunday, holiday and night work.
24. Reference materials.
25. Value engineering.
26. Schedule of Values.

B. Progress Meetings: Contracting Officer will schedule weekly meetings with Contractor.

1. Attendees: In addition to Government Representatives, each Contractor, Subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented. Participants at meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Meeting agenda will include:

    a. Approval of minutes of previous meetings.
    b. Submittal status.
    c. Review of off-site fabrication and delivery schedules.
    d. Requests for information (RFI) and other issues.
    e. Modifications.
    f. Work in progress and projected.

        1) Status of required inspections (Special Inspections, Accessibility, etc.)

    g. Inspections of work in progress and projected (Special inspections, Accessibility, etc.)
    h. Construction Schedule update.

        1) Provide updated Critical Path Method (CPM).

    i. Status of Project Record Drawings and O&M manuals.
    j. Other business relating to work.
    k. Permit requirements.

C. Preinstallation Conferences: Conduct at Project site before each construction activity that requires coordination with other construction.

1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend meeting. Advise Contracting Officer of scheduled meeting dates.
2. Agenda: Review progress of other construction activities and preparations for particular activity under consideration, including requirements for:

    a. Contract Documents.
    b. Options.
    c. Related RFIs.
    d. Related Change Orders.
    e. Purchases.
    f. Deliveries.
    g. Submittals.
    h. Review of mockups.
    i. Possible conflicts.
    j. Compatibility requirements.
    k. Time schedules.
    l. Weather limitations.
    m. Manufacturer's written instructions.
    n. Warranty requirements.
    o. Compatibility of materials.
    p. Acceptability of substrates.
    q. Temporary facilities and controls.
    r. Space and access limitations.
    s. Regulations of agency(ies) with jurisdiction.
    t. Testing and inspecting requirements.
    u. Installation procedures.
    v. Coordination with other work.
    w. Required performance results.
    x. Protection of adjacent work.
    y. Protection of construction and personnel.

3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
4. Reporting: Distribute minutes of meeting to each party present and to other parties requiring information.
5. Do not proceed with installation if conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of Work and reconvene conference at earliest feasible date.

1.7 ENVIRONMENTAL COORDINATION

A. Contractor’s Environmental Manager: Designate on-site party responsible for overseeing Contractor’s conformance to environmental goals for project and implementing procedures for environmental protection.

1. Qualifications: Minimum 3 years Construction experience on projects of similar size and scope; with environmental procedures similar to this Project; familiar with environmental regulations applicable to construction operations.

2. Responsibilities: Responsibilities shall include:

    a. Compliance with applicable Federal, State, and local environmental regulations, including maintaining required documentation.
    b. Implementation of Waste Management Plan (WMP).
    c. Implementation of Indoor Air Quality (IAQ) Management Plan.
    d. Implementation of Under-an-Acre Pollution Prevention Plan (UPPP).
    e. Present overview of environmental issues and summarize site specific procedures relating to management plans at Preconstruction conference.
    f. Training for Contractor personnel in accordance with position requirements.
    g. Monitoring and documentation of environmental procedures.

B. Perform project quality control in accordance with requirements specified in Related Sections, including:

1. Quality Requirements.
2. Regulatory Requirements.
3. Indoor Air Quality (IAQ) Management.
4. Noise and Acoustics Management.
5. Under and Acre Pollution Prevention Environmental Management.
6. Construction Waste Management.

C. Contractor's Environmental Training Program: Contractor shall provide environmental training for workers performing work on project site. Training shall include:

1. Overview of environmental issues related to building industry.
2. Overview of environmental issues related to Project.
3. Review of site-specific procedures and management plans:

    a. Construction Waste Management.
    b. Indoor Air Quality (IAQ) Management.
    c. Noise and Acoustics Management.
    d. Under-an-Acre Pollution Prevention.

4. Pollution Prevention (P2) Practices: Submit evidence of familiarity with P2 practices.
5. Compliance with Environmental Regulations: As specified in Regulatory Requirements. Submit Contractor 40 CFR (Code of Federal Regulations) employee training records upon request of Contracting Officer.

D. Provide documentation for environmental procedures as specified and in accordance with approved Waste Management Plan, IAQ Management Plan, and Under-an-Acre Pollution Prevention Plan.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 31 00

SECTION 01 32 16 – CONSTRUCTION SCHEDULE

PART 1 - GENERAL

1.1 SUMMARY

A. Section consists of Construction Schedule requirements including:

1. Schedule of Values.
2. Construction Schedule Requirements.
3. Construction Schedule Updates.
4. Time Impact Analysis.

B. Purpose: The Construction Schedule ensures adequate planning, coordination, scheduling, and reporting during execution of the work by the Contractor. It shall assist the Contractor and Contracting Officer (CO) in monitoring the progress of the work, evaluating proposed changes, and processing Contractor's monthly progress payments. It shall include the dates in the contract, phases, milestones, occupancies, holidays, weather consideration, a critical path, and the requirements of this section.

1.2 DEFINITIONS

A. Activity: A discrete part of a project identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.

1. Critical activities are activities on the critical path. They start and finish on the planned early start and finish times.
2. Predecessor Activity: An activity that precedes another activity in the network.
3. Successor Activity: An activity that follows another activity in the network.

B. Cost Loading: Allocation of the Schedule of Values for completion of an activity as scheduled. The sum of costs for all activities must equal the total Contract Sum, unless otherwise approved by the Contracting Officer.

C. Critical Path Method (CPM): Method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.

D. Critical Path: Longest connected chain of interdependent activities through the network schedule that establishes minimum overall Project duration and contains no float.

E. Float: Measure of leeway in starting and completing an activity.

1. Float: Not for the exclusive use or benefit of the Government or Contractor but is jointly owned.
2. Free Float: Amount of time an activity can be delayed without adversely affecting the early start of the successor activity.

3. Total Float: Measure of leeway in starting or completing an activity without adversely affecting planned Project completion date.

F. Resource Loading: Allocation of manpower and equipment necessary for completion of an activity as scheduled.

G. Fragnet: A partial or fragmentary network that breaks down activities into smaller activities for greater detail.

H. Two-Week Look-Ahead Schedule: Contractor's proposed construction schedule for two-week period following construction progress meeting.

1.3 SUBMITTALS

A. Electronic Copies: Schedules and reports submitted shall be posted on the NPS/DSC management software website in native electronic file formats. The intent of the Government is to limit the number of printed reports to those determined by the project team as essential.

B. Schedule of Values: After contract award and before Preconstruction conference, submit schedule of dollar values based on Contract Price Schedule.

C. Construction Baseline Schedule: After contract award and before Preconstruction conference, submit two paper copies of baseline schedule, large enough to show entire schedule for entire construction period. Utilize Schedule of Values in preparation of Construction Baseline Schedule.

D. Critical Path Method (CPM) Reports: Concurrent with CPM schedule, submit three paper copies of the following computer-generated reports. For each activity, include activity number, activity description, cost and resource loading, original duration, remaining duration, early start date, early finish date, late start date, late finish date, and total float in calendar days.

1. Activity Report: List of activities sorted by activity number and then early start date, or actual start date if known.
2. Logic Report: List of predecessor and successor tasks for activities sorted in ascending order by activity number and then early start date, or actual start date if known.
3. Total Float Report: List of activities sorted in ascending order of total float.

E. Construction Schedule Updates: On or before 7th day preceding progress payment request date, submit estimates of percent completion of each schedule activity and necessary supporting data. Provide two paper copies.

F. Construction Schedule Revisions and Time Impact Analysis: For each Construction Schedule revision, submit two paper copies of a Time Impact Analysis. Incorporate a Fragmentary Network (Fragnet) into currently accepted Construction Schedule that demonstrating how Contractor proposes to incorporate a modification, change, delay, or Contractor request.

1.4 QUALITY ASSURANCE

A. Contractor shall meet with Contracting Officer on day of the preconstruction conference to go over:

1. Review software limitations, content and format for reports.
2. Verify availability of qualified personnel needed to develop and update schedule.
3. Discuss constraints**.**
4. Review schedule for work of separate Government contracts.
5. Review time required for review of submittals and re-submittals.
6. Review requirements for tests and inspections by independent testing and inspecting agencies.
7. Review time required for obtaining and activating permits.
8. Review and finalize list of construction activities to be included in schedule.
9. Review baseline schedule comments, resolve issues and progress on incorporating them
10. Review procedures for updating schedule.
11. Discuss reporting requirements and establish protocol for naming and transmitting electronic schedules.

B. Contractor's Schedule Representative: Before the preconstruction conference, designate an authorized representative to be responsible for preparing and maintaining the Construction Schedule. Submit resume outlining qualifications of Scheduler to Contracting Officer for acceptance. Scheduler shall have prepared and maintained at least 5 previous schedules of similar size and complexity similar to this Contract, demonstrating proficiency of using scheduling software. Authorized representative will be responsible for preparing the Baseline Schedule, required updates, revisions, Time Impact Analyses, and reports.

1.5 COORDINATION

A. Coordinate preparation and processing of schedules and reports with performance of construction activities and with scheduling and reporting of separate contractors.

B. Coordinate Construction Baseline Schedule with Schedule of Values, list of subcontracts, Submittals Schedule, progress reports, payment requests, and other required schedules and reports.

1. In developing Construction Baseline Schedule, ensure Subcontractor’s work at all tiers, and prime Contractor’s work, is included and coordinated.
2. Secure time commitments for performing critical elements of work from parties involved.
3. Coordinate each construction activity in network with other activities and schedule in proper sequence.

PART 2 - PRODUCTS

2.1 SCHEDULE OF VALUES

A. Breakdown each lump-sum item into component work activities used in the schedule for which progress payments may be requested. Work activities broken out within schedule of values shall be integrated into and made a logical part of the construction baseline schedule. Total costs for the component work activities shall equal contract price for that lump-sum item. Contracting Officer may request data to verify accuracy of dollar values. Include mobilization, general condition costs, overhead and profit in the total dollar value of unit price items and in the

component work activities for each lump-sum item. Do not include mobilization, general condition costs, overhead or profit as a separate item.

B. Do not break down unit price items. Use only the contract price for unit price items.

C. Total cost of all items shall equal the contract price. The Schedule of Values will form the basis for progress payments and the Construction Schedule.

2.2 CONSTRUCTION SCHEDULE REQUIREMENTS

A. Construction Baseline Schedule: Prepare Construction Baseline Schedule using a computerized, cost and resource-based, time-scaled Critical Path Method network analysis diagram for the Work.

1. Develop and finalize Construction Baseline Schedule so it can be accepted for use no later than 30 days after date established for the Notice of Award.

   a. Failure to include any work item required for performance of this Contract shall not excuse Contractor from completing work within applicable completion dates, regardless of Government's acceptance of schedule.

2. Establish procedures for monitoring and updating Construction Baseline Schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.

B. Construction Baseline Schedule Preparation: Prepare a list of all activities required to complete the Work. Using preliminary Critical Path Method network diagram, prepare a skeleton network to identify probable critical paths.

1. Activities: Indicate estimated duration, sequence requirements, and relationship of each activity in relation to other activities.
2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
3. Processing: Process data to produce output data on a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the Critical Path Method schedule within the limitations of the Contract Time.
4. Show sequence and interdependence of activities required for completion of work. Ensure work sequences are logical and Construction Baseline Schedule shows a coordinated plan of the work.
5. Resource loading of each activity shall include personnel by labor category and equipment type and capacity proposed to complete the activity in duration shown.
6. Consider seasonal weather conditions in planning and scheduling work influenced by high and low ambient temperatures, wind, or precipitation to ensure completion of work within contract time.
7. Time Frame: Proposed duration assigned to each activity shall be Contractor's best estimate of time required to complete activity considering the scope and resources planned for activity.

a. An early finish date may be shown but the late finish date shall be same date as last day of contract period. An early completion schedule shall contain:

1) Insert an activity titled "Project Float" as a successor to last activity in early project completion schedule network.
2) Add a milestone titled "Contract End Date" as a successor to the activity "Project Float".
3) Add duration to the activity "Project Float" as required so the milestone "Contract End Date" equals the last day of Contract Period.

b. Contract completion date shall not be changed by submission of a schedule that shows an early completion date.
c. Contractor shall limit use of lead or lag durations between schedule activities.
d. Project Calendars: Develop and incorporate the following calendars:

1) Administrative Calendar: Include calendar based on a 7-day week to be used on activities based on calendar days. Apply this calendar to administrative tasks or other tasks not affected by non-working days (Federal Holidays, weather, etc.).
2) Project Calendar: Include calendar based on planned work week for the project. Include Federal Holidays, weekends, and non-workdays indicated in contract documents. Apply this calendar to activities not anticipated to be affected by weather. Be clear when identifying number of work days in work week.
3) Weather Calendar: Utilize Project Calendar and show anticipated normal downtime related to weather as non-working time. Weather days shall be based on data for local area from a reliable source like the National Oceanic and Atmospheric Administration (NOAA), National Park Service records, or source acceptable to Contracting Officer. Apply this calendar to activities anticipated to be affected by weather.

e. Activity Duration: Define so no activity is longer than 14 days, except for non-construction activities including mobilization, shop drawings and submittals, fabrication and delivery of materials and equipment.
f. Procurement Activities: Include procurement process activities for long lead items and major items, requiring a cycle of more than 60 calendar days, as separate activities in the schedule. Procurement cycle activities can include submittals, approvals, purchasing, fabrication, and delivery.
g. Submittal Review Time: Include review and re-submittal times indicated. Coordinate submittal review times in Construction Baseline Schedule.
h. Substantial Completion: Allow time for Government administrative procedures necessary for certification of Substantial Completion. (For more information, refer to Specification 01 77 00 "Closeout Procedures.")

8. Constraints: Include constraints and work restrictions indicated in Contract Documents and as follows in schedule and show how the sequence of Work is affected.

a. Work Restrictions: Show effect of the following on the schedule:

1) Coordination with existing construction.
2) Limitations of continued occupancies.

3) Uninterruptible services.
4) Government occupancy.
5) Use of premises restrictions.
6) Environmental control.
7) Permit provisions.

b. Work Stages: Indicate important stages of construction for each major portion of the Work.

1) Subcontract awards.
2) Submittals.
3) Purchases.
4) Mockups.
5) Fabrication.
6) Sample testing.
7) Deliveries.
8) Installation.
9) Tests and inspections.
10) Adjusting.
11) Curing.

9. Milestones: Include milestones indicated in Contract Documents in schedule, including, but not limited to, Notice to Proceed, and Substantial Completion**.**

C. Joint Review, Revision, and Acceptance:

1. Within seven calendar days of receiving Contractor's proposed Construction Baseline Schedule, Contracting Officer shall review initial Construction Baseline Schedule.
2. Within seven calendar days after review, Contractor shall revise and resubmit Construction Baseline Schedule in accordance with comments presented from review.
3. In the event the Contractor fails to define any element of work, activity, or logic, and the Contracting Officer review does not detect this omission or error, such omission or error, when discovered by Contractor or Contracting Officer, shall be corrected by Contractor within seven calendar days and shall not affect contract period.
4. Upon acceptance of the Construction Baseline Schedule, Contracting Officer saves schedule as a baseline and updates on a monthly basis. Construction schedule update will be used to evaluate Contractor's monthly applications for payment based upon information developed at monthly Construction Schedule update meeting.

D. Cost Correlation: In the heading of the schedule, provide a cost correlation line, indicating planned and actual costs. On the line, show dollar volume of Work performed as of dates used to prepare payment requests.

1. Contractor shall assign cost to construction activities on Construction Baseline Schedule. Costs shall not be assigned to submittal activities unless specified otherwise but may, with Contracting Officer’s approval, be assigned to fabrication and delivery activities. Costs shall be included for testing and commissioning activities, operation and maintenance manuals, punch list activities, Project Record Documents, and demonstration and training (if applicable).
2. Each activity cost shall reflect an accurate value based on the Contract Price Schedule.
3. Total cost assigned to activities shall equal total Contract Price.

E. Recovery Schedule: When periodic schedule update indicates Work is 14 or more calendar days behind current accepted schedule, a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule shall also be submitted. Indicate changes to working hours, working days, crew sizes, and equipment required to achieve compliance, and date by which recovery shall be accomplished.

F. Computer Software: Prepare schedules using a program developed specifically to manage construction schedules.

1. Use Microsoft Project or Primavera, for Windows 7 and newer.

PART 3 - EXECUTION

3.1 CONSTRUCTION SCHEDULE UPDATES

A. Progress Meeting Updates: Provide a two week look-ahead schedule, derived from the currently accepted schedule, before each weekly progress meeting. Utilize look-ahead schedule to facilitate and take notes on discussions held during progress meeting.

B. Monthly Schedule Updates:

1. General: Update Construction Schedule on monthly basis to reflect construction progress and activities throughout entire contract period and until project substantial completion. The status date of each schedule update shall be the 7th day preceding the progress payment request date.
2. Procedure: Contractor shall meet with Contracting Officer each month at Construction Schedule update meeting to review progress made through the status date of the Construction Schedule update, including dates activities were started or completed and percentage of work completed on each activity started or completed.
3. Reports: Concurrent schedule revisions, prepare tabulated reports showing:

    a. Identification of activities that have changed.
    b. Changes in early and late start dates.
    c. Changes in early and late finish dates.
    d. Changes in activity durations in workdays.
    e. Changes in the critical path.
    f. Changes in total float or slack time.
    g. Changes in the Contract Time.

4. Narrative: Report shall include a brief description of actual progress made during update period; actual and potential delaying activities; impediments to progress; issues related to inclement weather; progress toward established milestones and project float. Report shall include a brief description of work anticipated to be performed in the next month. Minor revisions to the schedule should be identified for evaluation and acceptance or rejection.
5. As Work progresses, indicate Actual Completion percentage for each activity.
6. If schedule update shows a late finish date after contract completion date, include:

    a. Known delays.
    b. Actions to get back on schedule.

c. Pending modifications.
d. Impediments or constraints affecting progress.

7. Progress Payments: Monthly updating of the currently accepted Construction Schedule shall be an integral part of the process upon which progress payments will be made. If Contractor fails to provide schedule updates or revisions, a portion of the monthly payment may be retained until corrections have been made.

C. Distribution: Distribute copies of accepted schedule to Contracting Officer, Contracting Officers Representative, Construction Management Representative, Subcontractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.

1. Post copies in Project meeting rooms and temporary field offices.
2. When revisions are made, distribute updated schedules to same parties and post in same locations. Delete parties from distribution when they have completed their assigned portion of the Work.

D. Construction Schedule Revisions:

1. Required Revisions: If, as a result of the monthly schedule update, it appears the currently accepted Construction Schedule no longer represents actual prosecution and progress of the work, Contracting Officer will request, and Contractor shall submit, a revision to the Construction Schedule. Contractor may also request reasonable revisions to currently accepted Construction Schedule in event the Contractor's planning for the work is revised. If Contractor desires to make changes, Contractor shall notify Contracting Officer in writing, stating reason for proposed revision. Accepted revisions shall be incorporated into currently accepted Construction Schedule for next monthly schedule update.
2. Procedure: If revision to currently accepted Construction Schedule is contemplated, Contractor or Contracting Officer shall advise the other in writing at least seven calendar days prior to next monthly schedule update meeting, describing revision and reasons for the revision. Government-requested revisions will be presented in writing to the Contractor, who shall respond in writing within seven calendar days.
3. Reports: Concurrent with making revisions to schedule, prepare tabulated reports showing:

a. Identification of activities changed.
b. Changes in early and late start dates.
c. Changes in early and late finish dates.
d. Changes in activity durations in workdays.
e. Changes in critical path.
f. Changes in total float or slack time.

3.2 TIME IMPACT ANALYSIS FOR CONTRACT MODIFICATIONS CHANGES DELAYS AND CONTRACTOR REQUESTS:

1. Requirements: When contract modifications or changes are initiated, delays experienced, or Contractor desires to revise currently accepted Construction Schedule, Contractor shall submit to Contracting Officer a written time impact analysis illustrating the influence of modification, change, delay, or Contractor request on contract time.
2. Time Extensions: Activity delays, resulting in a late completion date projection, shall not automatically mean an extension of contract time is warranted or due to Contractor. It is

possible a modification, change, or delay will not affect existing critical path activities or cause non-critical activities to become critical. A modification, change, or delay may result in absorbing a part of available total float that may exist within an activity chain of the Schedule, not causing any effect on contract time. Time extensions will be granted in accordance with terms of contract.

3. Extension of contract time will be granted only to the extent the equitable time adjustments to activity or activities affected by modification, change, or delay exceeds total (positive or zero) float available on a particular activity.
4. Procedure: Each time impact analysis shall be submitted within time period stated in a request for proposal, or time period designated under the clauses entitled Changes or Default. In cases where Contractor does not submit a written request for extension of time and a time impact analysis within the designated time, it is mutually agreed that the particular modification, change, delay, or Contractor request does not require an extension of the contract time. Upon acceptance, time impact analysis shall be incorporated into currently accepted Construction Schedule at next monthly schedule update.
5. Contract Modifications: Prepare time-impact analysis using fragnets to demonstrate effect of proposed change on overall Construction Schedule for each proposed contract modification concurrent with submission.

END OF SECTION 01 32 16

SECTION 01 32 33 – PHOTO DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for:

1. Existing condition images.
2. Periodic construction images.

1.2 SUBMITTALS

A. Construction Images: Submit images electronically within seven days of taking the image. Include:

1. Date, time and number (sequentially number all images) in filename.
2. Description of vantage point, indicating location, direction (by compass point), and elevation or story of construction.
3. Submit digital images exactly as originally recorded in digital camera, without alteration, or modifications using image-editing software.

B. Closeout: Submit complete set of digital image electronic files as a Project Record Document**.** Submit on Digital Video Disc (DVD).

1. Provide index as separate file on Disc. List each image as a file name with number, date, and time. Include description and or vantage point image was taken.
2. Submit images that have the same aspect ratio as the sensor, un-cropped.

PART 2 - PRODUCTS

2.1 FORMAT REQUIREMENTS

A. Media: DVD-R Archival Gold.

B. Media Labels: Archival DVD labeling markers, archival labels, or direct print.

C. Images: Provide sRGB (standard Red Green Blue) color images in JPEG (Joint Photographic Experts Group) format. Minimum sensor size of eight megapixels, and at image resolution of not less than 3200 by 2400, and 300 dpi (dots per inch).

PART 3 - EXECUTION

3.1 CONSTRUCTION IMAGES

A. General: Take digital images using the maximum range of depth of field, in-focus, to clearly show the Work. No blurry or out-of-focus areas accepted.

1. Maintain index with each set of Construction images and identify the number, date, time, and description for each.
2. Maintain one set of images accessible in field office at Project site available for reference.

B. Existing Condition Images: Before starting construction, take color digital images of Project site and surrounding properties, including existing items to remain during construction, from different vantage points.

1. Take 12 separate images to show existing conditions adjacent to property before starting Work.
2. Take 12 separate images of existing buildings either on or adjoining property to accurately record physical conditions at start of construction.
3. Document fully the condition of the pavers along the access routes and other areas that may be affected by construction operations. Document all cracked, broken, missing, and displaced stones. Documentation may be video or photographic.

C. Periodic Construction Images: Take 12 color, digital images monthly, coinciding with cutoff date associated with each Application for Payment. Select vantage points to show status of construction and progress since last images were taken.

D. Additional Images: Contracting Officer may issue requests for additional images.

1. Three days advance, where feasible.
2. In emergency situations, take additional images within 24 hours of request.
3. Additional images include, but are not limited to:

a. Immediate follow-up when on-site events result in construction damage or losses.
b. Fabrication locations away from Project site.
c. Substantial Completion of a major phase or component of Work.
d. Extra record images at time of final acceptance.

END OF SECTION 01 32 33

SECTION 01 33 23 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.

1.2 DEFINITIONS

A. Action Submittals: Written, graphic information, and physical samples that require Government's responsive action.

B. Informational Submittals: Written information that does not require Government's responsive action. Submittals may be rejected for not complying with requirements.

C. File Transfer Protocol (FTP): Communications protocol that enables transfer of files to and from another computer over a network and that serves as the basis for standard Internet protocols. An FTP site is a portion of a network located outside of network firewalls within which internal and external users are able to access files.

D. Portable Document Format (PDF): An open standard file format licensed by Adobe Systems used for representing documents in a device-independent and display resolution-independent fixed-layout document format.

1.3 GENERAL SUBMITTAL PROCEDURES

A. General: Prepare and submit submittals required by individual Specification Sections and in some cases as requested in drawings. Types of submittals are indicated in individual Sections.

1. Contracting Officer (CO) reserves right to require submittals in addition to those called for in individual Sections.

B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities. Review for legibility, accuracy, completeness, and compliance with Contract Documents.

1. Coordinate submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
2. Coordinate transmittal of different types of submittals for related parts of Work so processing will not be delayed because of need for concurrent review coordination.

a. Contracting Officer reserves right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.

C. Submittal List: Submittal list is attached to the end of this Specification Section. The intent is to provide an overall summary of submittal requirements. The requirements of individual Specification Sections and terms and conditions of the Contract still apply regardless of what is shown on submittal list.

D. Processing Time: Allow time for submittal review, including time for re-submittals, as follows. Time for review shall commence when e-mail notification is received by Contracting Officer (or designee) indicating submittal has been posted on NPS management software website and is ready for review. When Contracting Officer has completed review, e-mail notification will be sent to Contractor indicating submittal has been processed. No extension of Contract Time will be authorized because of failure to transmit submittals in advance of Work to permit processing, including re-submittals.

1. Action Submittals:

    a. Initial Review: Allow 30 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required.
    b. Re-submittal Review: Allow 21 days for review of each re-submittal.

2. Informational Submittals:

    a. Review: Allow 10 days for review of each submittal.

E. Approved Equals:

1. For each item proposed as an "approved equal," submit supporting data, including:

    a. Drawings and samples as appropriate.
    b. Comparison of the characteristics of the proposed item with that specified.
    c. Changes required in other elements of the work because of the substitution.
    d. Name, address, and telephone number of vendor.
    e. Manufacturer’s literature regarding installation, operation, and maintenance, including schematics for electrical and hydraulic systems, lubrication requirements, and parts lists. Describe availability of maintenance service, and state source of replacement materials.

2. A request for approval constitutes a representation that Contractor:

    a. Has investigated the proposed item and determined that it is equal or superior in all respects to that specified.
    b. Will provide the same warranties for the proposed item as for the item specified.
    c. Has determined that the proposed item is compatible with interfacing items.
    d. Will coordinate installation of an approved item and make changes required in other elements of the work because of the substitution.
    e. Waives claims for additional expenses that may be incurred as a result of the substitution.

F. Electronic Submittals: Identify and incorporate information in each electronic submittal file as follows:

1. Transmittal Form (CM-16): All submittals shall be transmitted using National Park Service Transmittal Form (CM-16). The form can be downloaded from the DSC Workflows website's Submittal Review page (https://www.nps.gov/dscw/con_subreview21.htm) and completed on the NPS/DSC management software website. No action will be taken on a submittal item unless accompanied by this Transmittal Form.

    a. Complete the general information at the top of form.
    b. Provide all required information based on submittal type.
    c. Attach all related documents.
    d. Sign the Contractor section at bottom of the Transmittal Form (CM-16).

2. PDF Submittals: Prepare submittals as PDF package, incorporating complete information into each PDF file name. Name PDF file with submittal number.

    a. Ensure PDFs can be printed with Contractor's annotation visible. Flatten PDFs before submitting for Contracting Officer's review.
    b. Submittals with embedded annotations that cannot be printed will not be accepted.

3. Physical Samples: Complete Transmittal Form (CM-16) on the NPS/DSC management software website as described above. Deliver physical sample to the Contracting Officer (or designee) on site for processing. All comments and actions will be documented on the Transmittal Form (CM-16) on the NPS/DSC management software website.

G. Identification: Submittal number or other unique identifier, including revision identifier.

1. Submittal number shall use a sequential number (e.g. .001). Re-submittals shall include alphabetic suffix after another decimal point (e.g. .001.A).

H. Re-submittals: Make re-submittals using same process used with initial submittal.

1. Note date and content of previous submittal.
2. Note date and content of revision in the title block on the Transmittal Form (CM-16) and clearly indicate extent of revision.
3. Re-submit submittals until they are marked "Approved" or "Approved with notations".

I. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, and others as necessary for performance of construction activities.

J. Use for Construction: Use only final submittals with mark indicating "Approved" or "Approved with notations". Ensure notations have been incorporated and, at a minimum, keep one copy of final approved submittal on site for use during construction.

1.4 CONTRACTOR'S USE OF CAD FILES

A. General: At Contractor's written request, copies of CAD (Computer Aided Design) files will be provided to Contractor for Contractor's use in connection with Project, subject to:

1. Files provided as is; no format or other changes to files or changes to objects in the drawing will be done by the Government.
2. Government makes no representation to the accuracy or completeness of CAD files.

3. Contractor shall execute a data licensing agreement in the form of Architect's standard CAD waiver.

PART 2 - PRODUCTS

2.1 ACTION SUBMITTALS

A. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.

1. If information must be specially prepared for submittal because standard printed data are not suitable for use, submit as Shop Drawings, not as Product Data.
2. Mark each submittal to show which products and options are applicable.
3. As applicable, include:

a. Manufacturer's product specifications.
b. Manufacturer's installation instructions: When Contract Documents require compliance with manufacturer's printed instructions, provide one complete set of instructions to Contracting Officer and keep another complete set of instructions at the project site until substantial completion.
c. Manufacturer's catalog cuts: Submit only pertinent pages; mark each page of standard printed data to identify specific products proposed for use.
d. Wiring diagrams showing factory-installed wiring.
e. Printed performance curves.
f. Operational range diagrams.
g. Compliance with specified referenced standards.
h. Testing by recognized testing agency.

4. Submit product data in PDF (portable document format) file format before or concurrent with samples.

B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.

1. Preparation: Fully illustrate requirements in Contract Documents. As applicable, include:

a. Dimensions.
b. Identification of products.
c. Fabrication and installation drawings.
d. Roughing-in and setting diagrams.
e. Wiring diagrams showing field-installed wiring, including power, signal, and control wiring.
f. Shopwork manufacturing instructions.
g. Templates and patterns.
h. Schedules.
i. Notation of coordination requirements.
j. Notation of dimensions established by field measurement.
k. Relationship to adjoining construction clearly indicated.
l. Seal and signature of professional engineer if specified.

m. Wiring Diagrams: Differentiate between manufacturer-installed and field-installed wiring.

2. Submit shop drawings as PDF electronic file.

C. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.

1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
2. Complete and post the Transmittal Form (CM-16) on the NPS/DSC management software website for processing and documentation of action on submitted samples.
3. Identification: Attach label on unexposed side of Samples that includes:

a. Generic description of Sample.
b. Product name and name of manufacturer.
c. Sample source.
d. Submittal Number and title of appropriate Specification Section.

4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
5. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing full range of colors, textures, and patterns available.

a. Number of Samples: Submit three full set(s) of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Contracting Officer will return with options selected.

6. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.

a. Number of Samples: Submit five sets of Samples. Contracting Officer will retain three Sample sets; remainder will be returned. Retain Sample set as a Project Record Sample.

D. Construction Materials: Contractor is encouraged to submit products made out of recycled or environmentally responsible material. Every effort will be made by National Park Service to approve these materials.

2.2 INFORMATIONAL SUBMITTALS

A. General: Prepare and submit Informational Submittals required by individual Specification Sections.

1. Post informational submittals as PDF electronic files directly to the NPS management software website.
2. Certificates and Certifications: Provide a notarized statement with signature of entity responsible for preparing certification. Certificates and certifications shall be signed by officer or other individual authorized to sign documents on behalf of that entity.
3. Informational submittals that do not comply with requirements specified in Contract Documents will be rejected and one copy will be returned.

B. Contractors Construction Schedule: Comply with requirements specified in Section 01 32 16 "Construction Schedule."

C. Accident Prevention Plan: Comply with requirements specified in Section 01 35 23 "Safety Requirements."

D. Schedule of Values: Comply with requirements specified in Section 01 32 16 "Construction Schedule."

E. Waste Recycling Plan: Comply with requirements specified in Section 01 74 19 "Construction Waste Management and Disposal."

F. Quality Control Plan: Comply with requirements specified in Section 01 40 00 "Quality Requirements."

G. Under-an-Acre Pollution Prevention Plan: Comply with requirements specified in Section 01 57 23 "Under-an-Acre Pollution Prevention" and storm water permit requirements identified in Section 01 31 00 "Project Management and Coordination."

H. Indoor Air Quality Management Plan: Comply with requirements specified in Section 01 57 19.11 "Indoor Air Quality Management."

I. Qualification Data: Prepare written information demonstrating capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, photographs, and other information specified.

J. Welding Certificates: Prepare written certification that welding procedures and personnel comply with Contract Documents. Submit record of Welding Procedure Specification (WPS) and Procedure Qualification Record (PQR) on American Welding Society (AWS) forms. Include names of firms and personnel certified.

K. Installer Certificates: Prepare written statements on manufacturer's letterhead certifying Installer complies with Contract Documents and, where required, is authorized by manufacturer for this specific Project.

L. Manufacturer Certificates: Prepare written statements on manufacturer's letterhead certifying manufacturer complies with Contract Documents. Include evidence of manufacturing experience where required.

M. Product Certificates: Prepare written statements on manufacturer's letterhead certifying product complies with Contract Documents.

N. Material Certificates: Prepare written statements on manufacturer's letterhead certifying material complies with Contract Documents.

O. Material Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in Contract Documents.

P. Product Test Reports: Prepare written reports indicating current product produced by manufacturer complies with requirements in Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.

Q. Research/Evaluation Reports: Prepare written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project.

R. Preconstruction Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in Contract Documents.

S. Compatibility Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.

T. Field Test Reports: Prepare reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in Contract Documents.

U. Maintenance Data: Prepare written and graphic instructions and procedures for operation and normal maintenance of products and equipment. Comply with requirements specified in Section 01 78 23 "Operation and Maintenance Data."

V. Design Data: Prepare written and graphic information, including: performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.

W. Manufacturer's Instructions: Prepare written or published information documenting manufacturer's recommendations, guidelines, and procedures for installing or operating a product or equipment. Include name of product and name, address, and telephone number of manufacturer.

X. Manufacturer's Field Reports: Prepare written information documenting factory-authorized service representative's tests and inspections. As applicable, include:

1. Statement on condition of substrates and their acceptability for installation of product.
2. Summary of installation procedures being followed, compliance with requirements and, if not, what corrective action was taken.

3. Results of operational and other tests and a statement of whether observed performance complies with the requirements.

Y. Permit Compliance Products: Prepare required information for compliance with permit provisions. Products include written notification of project startup, suspension, and completion of work; photo documentation of site conditions; reports; and drawings.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

A. Review each submittal and check for coordination with other Work of Contract and for compliance with Contract Documents. Note corrections and field dimensions.

3.2 CONTRACTING OFFICER'S ACTION

A. General: Submittals will be disapproved without technical review if identification information is missing, not filled in, or if placed on back of submittal; an incorrect format of submittals is provided; transmittal form is incorrectly filled out; submittals are not coordinated; or submittals do not show evidence of Contractor's approval.

1. Any work done or orders for materials or services placed before approval shall be at Contractor's own risk.

B. Action Submittals: Contracting Officer will review each submittal, generate comments on corrections or modifications required, and indicate appropriate action on the Transmittal Form (CM-16). Submittal will be marked as defined below:

1. APPROVED: Acceptable with no corrections.
2. APPROVED WITH NOTATIONS: Minor corrections or clarifications required. Comments are clear and no further review is required. Contractor shall address review comments when proceeding with the work.
3. DISAPPROVED - RESUBMIT: Rejected as not in accordance with the contract or as requiring major corrections or clarifications. Contracting Officer will identify reasons for disapproval. Contractor shall revise and resubmit with changes clearly identified.

C. Informational Submittals: Contracting Officer will review each submittal and will either accept or reject it.

D. Partial submittals are not acceptable, will be considered non-responsive, and will be returned without review.

END OF SECTION 01 33 23

SECTION 01 35 23 - SAFETY REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes establishing an effective accident prevention program and providing a safe working environment for personnel and visitors.

1.2 CONDITIONS PRESENT FOR PROJECT

A. Potential roof-edge fall.

B. Stair tower/man lifts.

1.3 SUBMITTALS

A. Accident Prevention Plan (APP): Submit APP after contract award and before Preconstruction conference. Contracting Officer (CO) will review proposed APP. If APP requires any revisions or corrections, Contractor shall resubmit Plan within 10 days. No progress payments will be made until the APP is accepted.

1.4 QUALITY ASSURANCE

A. Comply with contract clauses "Accident Prevention" and "Permits and Responsibilities." In case of conflicts between Federal, State, and local safety and health requirements, the most stringent shall apply. Onsite equipment shall meet 29 CFR 1926 (Code of Federal Regulations) (Occupational Safety and Health Administration (OSHA)) requirements. Failure to comply with requirements of this section and related sections may result in suspension of work.

B. Site Safety Supervisor:

1. Designate authorized onsite representative for preparation and maintenance of the APP.
2. Shall be responsible for:

a. Implementation and enforcement of the APP.
b. Daily safety inspections.
c. Conducting and documenting weekly and monthly safety meetings.
d. Review of safety requirements at progress meetings.
e. Compilation and maintenance of Safety Data Sheets (SDS) and safety reference materials.
f. Tracking and resolution of safety violations.
g. Site personnel and visitor compliance with site safety and health requirements and APP.
h. Investigation and reporting of accidents and injuries.

C. Qualifications of Employees:

1. Physically and able to perform their assigned duties in a safe manner.
2. Do not allow employees whose ability or alertness is impaired because of prescription or illegal drug use, fatigue, illness, intoxication, or other conditions that may expose themselves or others to injury to perform work.
3. Provide operating instructions for equipment. Operators of vehicles, hoisting equipment, and hazardous plant equipment shall be able to understand signs, signals, operating instructions, and be fully capable of operating such equipment. Retain copies of operator licenses and certifications onsite.

1.5 ACCIDENT REPORTING

A. Reportable Accidents: Defined as: death, occupational disease, and/or traumatic injury to employees or the public; fires; and/or property damage by accident in excess of $100.

1. Notify Contracting Officer immediately in the event of a reportable accident.
2. Fill out and forward an Accident/Property Damage Report Form (CM-22) to Contracting Officer within 7 days of a reportable accident. Obtain form from Contracting Officer.

PART 2 - PRODUCTS

2.1 ACCIDENT PREVENTION PLAN (APP)

A. APP shall be written to comply with OSHA and project requirements. Generic plan is not acceptable. APP shall include, but is not limited to, the following:

1. Name and qualifications of supervisor responsible to carry out program.
2. Weekly and monthly safety meetings shall be documented with topics and attendees.
3. First aid and rescue procedures.
4. Job Hazard Analysis (JHA) for each major phase. List of hazards associated and methods proposed to provide for property protection and safety of the public, National Park Service personnel, and Contractor's employees. Include initial and continuing training.
5. Planning for possible emergency situations, as detailed in Article 1.2. Such planning shall take nature of construction, site conditions, and degree of exposure of persons and property into consideration.
6. Infectious Disease Preparedness:

   a. Contractors are responsible for their employees' safety and the safety of job site visitors during the performance of this contract. We encourage Contractors to follow guidance from the Department of Labor (DOL), Occupational Safety and Health Administration (OSHA), the Centers for Disease Control and Prevention (CDC), and all other applicable local, city, and state mandates. We encourage Contractors to develop policies for infection prevention and an Infectious Disease Preparedness and Response Plan.
   b. To the extent appropriate, Contractors should include the protective health and safety measures they intend to implement in any accident prevention or safety submittals required under this contract. These plans should contain preventive

measures the Contractor intends to follow while performing work on government property as well as responsive and corrective actions to be taken if an employee exhibits symptoms or tests positive for contagion.

c. Upon contract award, Contractors should communicate with Contracting Officer regarding Contractor decisions and actions to protect the health and safety of workers for the duration of contract performance under which pandemic conditions exist.

2.2 FIRST AID FACILITIES

A. Provide adequate facilities for number of employees and appropriate to construction hazards.

2.3 PERSONNEL PROTECTIVE EQUIPMENT (PPE)

A. Selection shall conform to OSHA Subpart E.

PART 3 - EXECUTION

3.1 DAILY SAFETY INSPECTIONS

A. Conduct daily safety inspections and maintain daily safety reports which include:

1. Area/operation inspected.
2. Date of inspection.
3. Identified hazards.
4. Corrective actions taken.

3.2 EMERGENCY INSTRUCTIONS

A. Post telephone numbers and reporting instructions for ambulance, physician, hospital, fire department, and police in conspicuous locations at work site.

3.3 FIRE AND LIFE SAFETY

A. Comply with requirements of National Fire Protection Association (NFPA) 241 (Standard for Safeguarding Construction, Alteration, and Demolition Operations).

3.4 HAZARDOUS MATERIALS

A. Hazardous materials: Explosive, flammable, poisonous, corrosive, oxidizing, irritating, or otherwise harmful substances that could cause death or injury.

B. Store hazardous materials in accordance with manufacturer's and OSHA Subpart D requirements. Maintain Safety Data Sheets (SDS) for each chemical readily available on site.

1. Immediately report spills of hazardous materials to the Park.
2. Maintain a spill emergency response kit.
3. Train employees how to respond to a spill and use emergency response kit.

3.5 PROTECTIVE EQUIPMENT

A. Inspect personal protective equipment daily and maintain in a serviceable condition. Clean, sanitize, and repair personal items as appropriate before issuing to another individual.

3.6 SAFETY MEETINGS

A. As a minimum, conduct one weekly 15-minute "toolbox" safety meeting conducted by a foreman or supervisor and attended by construction personnel at worksite. Topics shall coincide with work scheduled for following week. Document and submit meeting minutes to Contracting Officer within one day after meeting.

B. Conduct monthly safety meetings for personnel, contractors, and subcontractors performing work on the site. Notify Contracting Officer of meeting dates and times. Meetings shall be used to: review effectiveness of Contractor's safety effort; resolve current health and safety problems; provide a forum for planning safe construction activities, and for updating Accident Prevention Plan. Contracting Officers Representative will attend meetings and enter results of meetings into the daily log.

3.7 HARD HATS AND PROTECTIVE EQUIPMENT AREAS

A. A hard hat use area shall be designated by Contractor. Hard hat area shall be posted by Contractor in a manner satisfactory to Contracting Officer.

B. It is Contractor's responsibility to require persons working on or visiting site to wear hard hats and PPE in good repair at all times. As a minimum, maintain six hard hats and other APP required equipment.

3.8 TRAINING

A. First Aid: Provide training to personnel to ensure prompt and efficient first aid.

B. Hazardous Material: Train and instruct each employee exposed to hazardous material in safe and approved methods of handling and storage.

END OF SECTION 01 35 23

SECTION 01 35 91 - HISTORIC PRESERVATION TREATMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes special procedures for historic treatment on Project including, but not limited to:

1. Storage and protection of existing historic materials.
2. Project site conditions.
3. Historic Preservation Treatment Plan.
4. General protection requirements.
5. Protection during use of heat-generating equipment.
6. Historic preservation treatment procedures.

1.2 DEFINITIONS

A. "Preservation" - To apply measures necessary to sustain existing form, integrity, and materials of historic property. Work may include preliminary measures to protect and stabilize the property.

B. "Rehabilitation" - To make possible a compatible use for property through repair, alterations, and additions while preserving those portions or features that convey its historical, cultural, or architectural values.

C. "Restoration" - To accurately return form, features, and character of a property to its appearance at a particular period of time by means of removal of features from other periods in its history and repair and reconstruction of missing and deteriorated features from the restoration period.

D. "Reconstruction" - To reproduce in exact form and detail, a building, structure, or artifact as it appeared at a specific period in time. Reconstructed elements do not possess historic integrity in their own right since they are-not original fabric.

E. "Stabilize" - To apply measures designed to reestablish a weather-resistant enclosure and structural reinforcement of an item or portion of the building while maintaining essential form as it exists at present. This level of intervention is aimed at retarding or arresting adverse impacts to structures.

F. "Protect and Maintain" - To remove deteriorating corrosion, reapply protective coatings, and install protective measures such as temporary guards; to provide the least degree of intervention.

G. "Repair" - To stabilize, consolidate, or conserve; to retain existing materials and features while employing as little new material as possible. Repair includes patching, piecing-in, splicing, consolidating, or otherwise reinforcing or upgrading materials. Within restoration, repair also includes limited replacement in kind, rehabilitation, and reconstruction, with compatible substitute materials for deteriorated or missing parts of features when there are surviving prototypes.

H. "Replace" - To duplicate in its entirety, a historic element or feature by matching its historic pattern, detail and appearance. Replacement is justified when original or historic elements are damaged beyond repair or are missing. Replacement conditions and methods include:

1. Replacement with Original or Historic Fabric: Includes fabric salvaged from other locations or projects having identical architectural qualities. Duplication of appearance using identical material possessing historical significance.
2. Replacement with New Materials: Includes replacement with new material of like kind (custom fabricated of manufactured). Duplication of appearance using like material.
3. Replacement with Substitute Materials: Includes replacement with a compatible substitute that is frequently contemporary and unlike the historic fabric. Duplication of appearance using modern (non-traditional) material Use of substitute materials is not approved unless matching materials are not available.

I. "Remove" - To demolish or detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.

J. "Remove and Salvage" - To detach items from existing construction and deliver them ready for reuse to Contracting Officer (CO) or designee.

K. "Remove and Reinstall" - To detach items from existing construction, repair and prepare for reuse, and reinstall where indicated.

L. "Existing to Remain" or "Retain" - Existing items of construction not to be removed and not otherwise indicated to be removed and salvaged or removed and reinstalled.

M. "Material in Kind" - Material that closely matches existing materials through comparison of architectural qualities and salient characteristic such as species, cut, color, grain, dimension, profile, thickness, and finish.

1.3 PROJECT MEETINGS FOR HISTORIC TREATMENT

A. Preliminary Historic Treatment Conference: Before starting historic treatment work, conduct conference at Project site.

1. Attendees: In addition to Contracting Officer and Contractor, testing service representative, and installers whose work interfaces with or affects historic treatment shall be represented at the meeting.
2. Agenda: Discuss items of significance that could affect progress of historic treatment work, including review of the following:

   a. Historic Treatment Schedule: Discuss and finalize; verify availability of materials, historic treatment specialists' personnel, equipment, and facilities needed to make progress and avoid delays.
   b. Fire-prevention plan.
   c. Governing regulations.
   d. Areas where existing construction is to remain and the required protection.
   e. Hauling routes.
   f. Sequence of historic treatment work operations.
   g. Storage, protection, and accounting for salvaged and specially fabricated items.

h. Existing conditions, staging, and structural loading limitations of areas where materials are stored.
i. Qualifications of personnel assigned to historic treatment work and assigned duties.
j. Requirements for extent and quality of work, tolerances, and required clearances.
k. Methods and procedures related to historic treatments, including product manufacturers' written instructions and precautions regarding historic treatment procedures and their effects on materials, components, and vegetation.
l. Embedded work such as flashings and lintels, special details, collection of wastes, protection of the public, and condition of other construction that affect the Work or will affect the Work.

3. Reporting: Record conference results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from conference.

1.4 ACTION SUBMITTALS

A. Historic Preservation Treatment Plan:

1. After contract award and before Preconstruction Conference, submit for approval a written Historic Preservation Treatment Plan (HPTP).
2. If the plan requires revisions or corrections, resubmit plan within 10 days.
3. No change in approved plan may be made without written concurrence by Contracting Officer.

B. Alternative Methods and Materials: If alternative methods and materials to those indicated are proposed for any phase of work, provide a written description including evidence of successful use on other, comparable projects, and program of testing to demonstrate effectiveness for use on this Project.

C. Photographs or Videotape: In accordance with Section 01 32 33 "Photo Documentation," show existing conditions of adjoining construction and site improvements including finish surfaces that might be misconstrued as damage caused by historic treatment operations. Submit before work begins.

D. Fire-Prevention Plan: Prepare a written plan for preventing fires during the Work, including placement of fire extinguishers, fire blankets, rag buckets, and other fire-control devices during each phase or process. Coordinate plan with Government’s fire protection equipment and requirements. Include fire-watch personnel’s training, duties, and authority to enforce fire safety.

E. Qualifications for Historic Preservation Treatment Specialist firm and personnel.

1.5 QUALITY ASSURANCE

A. Historic Preservation Treatment Specialist Qualifications: Work must be performed by a qualified Contractor having not less than five years of regularly engaged, successful experience in historic treatments of similar nature, materials, and design to this Project on at least three buildings listed or eligible to be listed in the National Register of Historic Places under the review of a federal and/or state historic preservation agencies in the last five years, and employing personnel skilled in the restoration processes and operations required by the Contract Documents.

1. Field Supervisor Qualifications: On-site full-time supervisor experienced in historic treatment work similar in nature, material, design, and extent to that indicated for this Project.
2. Worker Qualifications: Persons who are experienced in historic treatment work of types they will be performing.
3. Experience in new work is insufficient experience for historic treatment work.
4. In acceptance or rejection of historic treatment work, no allowance will be made for lack of skill on the part of the workers.

1.6 STORAGE AND PROTECTION OF HISTORIC MATERIALS

A. Existing Historic Materials to Remain: Protect construction indicated to remain against damage and soiling during historic treatment and other construction operations. When permitted by Contracting Officer, items may be removed to suitable, protected storage location during historic treatment and reinstalled in their original locations after historic treatment operations are complete.

B. Storage and Protection: When removed from existing location, store historic materials protected from wetting by rain, snow, or ground water, and temperature variations. Secure stored materials to protect from theft.

1. Identify removed items with an inconspicuous mark indicating original location.
2. Develop key plan when many similar items are scheduled for removal and reinstallation.

1.7 PROJECT-SITE CONDITIONS

A. Exterior Cleaning, Repointing, and Repairing:

1. Proceed with work only when forecasted weather conditions are favorable.

a. Wet Weather: Do not attempt repairs during rainy or foggy weather. Do not apply primer, paint, putty, or epoxy when relative humidity is above 80 percent. Do not remove exterior elements of structures when rain is forecast or in progress.
b. Do not perform exterior wet work when air temperature is below 40 degrees Fahrenheit.
c. Do not begin cleaning, patching, repointing, or repairing given likelihood of frost or freezing.
d. Do not begin cleaning when either air or surface temperature is below 45 degrees Fahrenheit unless approved means are provided for maintaining 45 degrees Fahrenheit temperature of air and materials during, and for 48 hours subsequent to, cleaning.

2. Perform pointing at the exterior only during daylight hours.

B. National Park Service will occupy portions of building immediately adjacent to historic treatment area. Conduct historic treatment so National Park Service operations will not be disrupted. Provide 72 hours' notice to Contracting Officer of activities that will affect National Park Service operations.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 HISTORIC PRESERVATION TREATMENT PLAN

A. Prepare written plan for preservation work covering preservation components of project. Plan shall verify construction strategy and intent is compatible with Department of the Interior's (DOI) Standards for Treatment of Historic Properties, Guidelines for Treatment of Cultural Landscapes, and National Park Service management policies for cultural resources. Plan shall satisfy both project scope and resource protection requirements. Plan shall include:

1. Organized list of preservation components of project, systems, and tasks.
2. Staging and sequence of work.
3. Disassembly and reassembly techniques and steps.
4. Equipment and tools required.
5. Supplies and materials with manufacturer or supplier identified.
6. Skilled trades and crafts required.
7. Additional investigations for extents or magnitude of treatments needed.
8. Protective measures.
9. Seasonal limitations on work.
10. Alternative means if primary treatment method is unfeasible.
11. Work conducted off-site.

    a. Approval from Contracting Officer required prior to taking resources off-site.

3.2 PROTECTION, GENERAL

A. Comply with manufacturer's written instructions for precautions and effects of products and procedures on adjacent building materials, components, and vegetation.

B. Ensure supervisory personnel are present when work begins and during progress.

C. Temporary Protection of Historic Materials during Construction:

1. Protect existing materials during installation of temporary protections and construction. Do not deface or remove existing materials.
2. Attachments of temporary protection to existing construction shall be approved by Contracting Officer prior to installation.

D. Protect landscape work adjacent to or within work areas as follows:

1. Provide barriers to protect tree trunks and root zones.
2. Bind spreading shrubs.
3. Coverings shall allow plants to breathe. Remove coverings at end of day. Do not cover plant material with waterproof membrane more than 8 hours at a time.
4. Set scaffolding and ladder legs away from plants.

E. Existing Drains: Prior to start of work or cleaning operations, test drains and other water removal systems to ensure drains and systems function properly. Notify Contracting Officer immediately of stopped or blocked drains or systems. Do not begin Work of this Section until drains are in working order.

1. Provide method to prevent solids including stone or mortar residue from entering drains or drain lines. Clean out drains and drain lines blocked or filled because of work performed under this Contract.
2. Protect storm drains from pollutants. Block drains or filter out sediments, allowing only clean water to pass.

3.3 PROTECTION DURING USE OF HEAT-GENERATING EQUIPMENT

A. Comply with following procedures while performing work with heat-generating equipment, including welding, cutting, soldering, and other operations where implements utilizing heat are used:

1. Written notification shall be given for each occurrence and location of work with heat-generating equipment. Obtain appropriate permit from the park as required.

    a. Use of open-flame equipment is not permitted.

2. As far as practical, use heat-generating equipment in shop areas or outside building.
3. Do not perform work with heat-generating equipment in or near rooms or in areas where flammable liquids or explosive vapors are present or thought to be present. Use combustible gas indicator test to ensure area is safe.
4. Remove and keep area free of combustibles, including, rubbish, paper, waste, etc., within area of operations.

    a. If combustible material cannot be removed, provide fireproof blankets to cover such materials.

5. Where possible, furnish and use baffles of metal or gypsum board to prevent spraying of sparks or hot slag into surrounding combustible material.
6. Prevent extension of sparks and particles of hot metal through open windows, doors, holes, and cracks in floors, walls, ceilings, roofs, and other openings.
7. Fire Watch: Before working with heat-generating equipment or combustible materials, station personnel to serve as a fire watch at each location where such work is performed. Fire-watch personnel shall have the authority to enforce fire safety. Station fire watch according to NFPA 51B, NFPA 241, and as follows:

    a. Train each fire watch in proper operation of fire-control equipment and alarms.
    b. Prohibit fire-watch personnel from other work that would distract from fire-watch duties.
    c. Cease work with heat-generating equipment whenever fire-watch personnel are not present.
    d. Have fire-watch personnel perform final fire-safety inspection each day beginning no sooner than 30 minutes after conclusion of work in each area to detect hidden or smoldering fires and to ensure that proper fire prevention is maintained.

e. Maintain fire-watch personnel at each area of Project site until 60 minutes after conclusion of daily work.

B. Fire-Control Devices: Provide and maintain fire extinguishers, fire blankets, and rag buckets for disposal of rags with combustible liquids. Maintain each as suitable for type of fire risk in each work area. Ensure that nearby personnel and fire-watch personnel are trained in fire-extinguisher and blanket use.

C. Where sprinkler protection exists and is functional, maintain without interruption while operations are performed. If operations are performed near automatic sprinkler heads, shield individual heads temporarily with guards.

3.4 HISTORIC PRESERVATION TREATMENT PROCEDURES

A. The principal aim of preservation work is to halt the process of deterioration and stabilize the item's condition to sustain the integrity of the historic element, feature or structure being preserved. Cyclic maintenance is often required as well as repair work. Repair is required where specifically indicated. The following procedures shall be followed:

1. Retain as much existing material as possible; repair and consolidate rather than replace.
2. Use additional material or structure to reinforce, strengthen, prop, tie, and support existing material or structure.
3. Use reversible processes wherever possible.
4. Use traditional replacement materials and techniques if possible. New work shall be distinguishable from old work and original materials and techniques.
5. Record repair work during construction with periodic construction photos and daily inspection reporting.

B. Prohibit smoking and vaping by personnel performing work on or near historic structures including in staging areas.

C. Notify Contracting Officer of visible changes in integrity of material or components due to environmental causes including biological attack, UV degradation, freezing, or thawing, or due to structural defects including cracks, movement, or distortion.

1. Do not proceed with work in question until directed in writing by Contracting Officer.

D. Where Work requires existing features to be removed, cleaned, and reinstalled, perform operations without damage to material itself, to adjacent materials, or to substrate.

E. Identify new or replacement materials and features with inconspicuous, permanent marks to distinguish from original materials. Record legend of identification marks and locations of these marks on Record Drawings.

1. Refer to Section 01 77 00 “Closeout Procedures” for Project Record Drawings submission requirements.

END OF SECTION 01 35 91

SECTION 01 40 00 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for quality assurance and quality control.

B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with Contract Document requirements. Quality of work shall be responsibility of the Contractor.

1. Specified tests, inspections, and related actions do not limit Contractor's other quality assurance and control procedures that facilitate compliance with Contract Document requirements.

1.2 DEFINITIONS

A. Experienced: When used with an entity or individual, “experienced,” unless otherwise further described, means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of agencies with jurisdiction.

B. Quality Assurance Services: Activities, actions, and procedures performed before and during execution of the work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.

C. Quality Control Services: Tests, inspections, procedures, and related actions during and after execution of the work to evaluate actual products incorporated into the work and completed construction comply with requirements.

D. Mockups: Full-size physical assemblies constructed on-site. Mockups are constructed from selections made under Sample submittals; to demonstrate aesthetic effects and, where indicated, qualities of materials and execution; to review coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate compliance with specified installation tolerances. Mockups are not Samples. Approved mockups establish the standard by which the Work will be judged, unless otherwise indicated.

1. Laboratory Mockups: Full-size physical assemblies constructed at a testing facility to verify performance characteristics.

E. Preconstruction Testing: Tests and inspections performed specifically for project before products and materials are incorporated into work to verify performance or compliance with specified criteria.

F. Product Testing: Tests and inspections performed by a Nationally Recognized Testing Laboratory (NRTL), a National Voluntary Laboratory Accreditation Program (NVLAP), or a testing agency

qualified to conduct product testing, to establish product performance and compliance with industry standards.

G. Source Quality Control Testing: Tests and inspections performed at the source, i.e., plant, mill, factory, or shop.

H. Field Quality Control Testing: Tests and inspections performed on-site for installation of work and for completed work.

I. Testing Agency or Laboratory: Entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.

J. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.

1. Using a term such as "carpentry" does not imply certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name, such as "carpenter." It also does not imply that requirements specified apply exclusively to trades people of corresponding generic name.

1.3 CONFLICTING REQUIREMENTS

A. Reference Standards: If compliance with two or more standards is specified and standards establish different or conflicting requirements, inform the Contracting Officer of the conflict and obtain clarification prior to proceeding with the Work.

B. Minimum Quality Levels: Quality level shown or specified shall be minimum provided or performed. Actual installation may comply exactly with minimum quality specified, or it may exceed minimum within reasonable limits. To comply with requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Contracting Officer before proceeding.

1.4 SUBMITTALS

A. Contractor Quality Control Plan:

1. After contract award and before Preconstruction conference, submit a written Contractor Quality Control (CQC) plan.
2. If plan requires revisions or corrections, Contractor shall resubmit plan within 10 days.
3. Government reserves the right to require changes in plan during contract period as necessary to obtain the quality specified.
4. No change in the approved plan may be made without written concurrence by Contracting Officer.

B. Qualification Data: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in form of a recent report on inspection of testing agency by a recognized authority.

C. Contractor Quality Control (CQC) Daily Reports: Submit showing inspections and tests on first workday following date covered by report. Quality Control Supervisor shall utilize DSC Forms (http://www.nps.gov/dscw/publicforms.htm).

1. Review Construction Management Representative (CMR) Daily report if applicable and reconcile any differences prior to posting.

D. Test Reports:

1. Test reports shall be completed by person performing test.
2. Submit Daily Test Information Sheets with Contractor Quality Control Daily Reports.
3. Submit failing test results and proposed remedial actions within four hours of noted deficiency.
4. Submit three copies of complete test results no later than one calendar day after test was performed.

E. Accessibility Inspection Report:

1. Fill out applicable sections of the Accessibility Inspection Report and attach to Contractor Quality Control Daily Report.
2. Utilize attached Accessibility Inspection form to document compliance with Architectural Barriers Act Accessibility Standards (ABAAS).
3. Inspect at various stages of construction as needed to ensure finished product meets standards.
4. Submit report no later than one calendar day after inspection was performed.

F. Off-Site Inspection Reports: Submit prior to shipment.

G. If Contractor Quality Control plan and Contractor Quality Control Daily Reports are not submitted as specified, Contracting Officer may retain payments until such time plan(s) is/are accepted and implemented, or may retain payments for work completed on days with no Contractor Quality Control Daily Reports.

H. Permits, Licenses, and Certificates: For National Park Service (NPS) records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of work.

1.5 QUALITY ASSURANCE

A. General: Qualifications paragraphs in this Article establish minimum qualification levels required; individual Specification Sections specify additional requirements.

B. Contractor’s Quality Control Staff:

1. Contractor's Quality Control Supervisor may also perform other duties.
2. Contractor's designated Quality Control Supervisor shall be on the project site whenever contract work is in progress.
3. Contractor's job supervisory staff may be used to assist Quality Control Supervisor supplemented, as necessary, by additional certified testing technicians.

C. Installer Qualifications: Firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent indicated for Project, whose work has resulted in construction with a record of successful in-service performance.

D. Manufacturer Qualifications: Firm experienced in manufacturing products or systems similar to those indicated for Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

E. Fabricator Qualifications: Firm experienced in producing products similar to those indicated for Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

F. Professional Engineer Qualifications: Professional engineer legally qualified to practice in jurisdiction where Project is located and is experienced in providing engineering services of kind indicated (including Structural Tests and Special Inspections (STSI)). Engineering services are defined as those performed for installations of system, assembly, or products similar to those indicated for Project in material, design, and extent.

G. Specialists: Certain sections of the Specifications require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for activities indicated.

1. Requirement for specialists shall not supersede building codes and regulations governing Work.

H. Testing Agency Qualifications: A Nationally Recognized Testing Laboratory (NRTL), a National Voluntary Laboratory Accreditation Program (NVLAP), or an independent agency with experience and capability to conduct testing and inspecting indicated, according to ASTM E 329; and with additional qualifications specified in individual Sections; and where required by Contract, is acceptable to Contracting Officer.

1. Nationally Recognized Testing Laboratory (NRTL): Nationally recognized testing laboratory according to 29 CFR 1910.7 (Code of Federal Regulations).
2. National Voluntary Laboratory Accreditation Program (NVLAP): Testing agency accredited according to National Institute of Standards and Technology's (NIST) National Voluntary Laboratory Accreditation Program.
3. Measuring devices, laboratory equipment, and instruments shall be calibrated at established intervals against certified standards in accordance with NIST requirements. Measuring and testing devices shall be made available for use by Government for verification tests.

I. Factory-Authorized Service Representative Qualifications: Authorized representative of manufacturer who is trained and approved by manufacturer to inspect installation of manufacturer's products similar in material, design, and extent to those indicated for Project.

J. Mockups: Before installing portions of work requiring mockups, build mockups for each form of construction and finish required to comply with following requirements, using materials indicated for completed work:

1. Build mockups in location and of size indicated; if not indicated, as directed by Contracting Officer.
2. Submit products and methods to be used in the mockup prior to building mockup.

3. Notify Contracting Officer seven days in advance of dates and times when mockups will be constructed.
4. Demonstrate proposed range of aesthetic effects and workmanship.
5. Obtain Contracting Officer's approval of mockups before starting work, fabrication, or construction.
6. Maintain mockups in an undisturbed condition as a standard for judging the completed work.
7. Mockups in good condition may be retained in the work at Completion, with the approval of the Contracting Officer.

1.6 QUALITY CONTROL

A. Contractor is responsible for testing and inspections, including Structural Tests and Special Inspections (STSI), as identified in attached list of STSI. Inspect and test work as needed to ensure quality of materials, workmanship, construction, finish, and functional performance are in compliance with applicable specifications, drawings, and those required by the Building Code.

1. Engage qualified testing agency to perform quality-control services.
2. Submit appropriate report for each quality-control service.
3. Testing and inspecting requested by Contractor and not required by Contract Documents are Contractor's responsibility.
4. Contracting Officer may designate test locations.

B. Manufacturer's Field Services: Where indicated, engage factory-authorized service representative to inspect field-assembled components and equipment installation, including service connections. Report results in writing.

C. Re-testing/Re-inspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and re-inspecting, for construction of replaced work that failed to comply with Contract Documents.

D. Testing Agency Responsibilities: Cooperate with NPS and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.

1. Notify Contracting Officer and Contractor promptly of irregularities or deficiencies observed in work during performance of services.
2. Determine location from which test samples will be taken and in which in-situ tests are conducted.
3. Conduct and interpret tests and inspections, State in each report whether tested and inspected work complies with or deviates from requirements.
4. Submit three copies of certified written report of each test, inspection, and similar quality-control service through Contractor.
5. Do not release, revoke, alter, or increase Contract Document requirements or approve or accept any portion of Work.

E. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide:

1. Access to Work.
2. Incidental labor and facilities necessary to facilitate tests and inspections.

3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
4. Facilities for storage and field curing of test samples.
5. Delivery of samples to testing agencies.
6. Preliminary design mix proposed for material mixes that require control by testing agency.
7. Security and protection for samples and testing and inspecting equipment at Project site.

F. Coordination: Coordinate sequence of activities to accommodate required quality assurance and control services with minimum delay and to avoid removing and replacing construction to accommodate testing and inspecting.

1. Schedule times for tests, inspections, obtaining samples, and similar activities.

PART 2 - PRODUCTS

2.1 CONTRACTOR QUALITY CONTROL PLAN

A. Contractor Quality Control Plan shall include:

1. List of personnel responsible for quality control and assigned duties. Include each person's qualifications. Include alternate(s) and qualifications.
2. Copy of letter of direction to Contractor's Quality Control Supervisor(s) outlining assigned duties and authorities designated by principal or owner.
3. Names, qualifications / accreditations, and descriptions of laboratories to perform sampling and testing, and samples of proposed report forms from laboratories.
4. Methods of performing, documenting, and enforcing quality control of work including Contractor report forms and acknowledgment of NPS forms.
5. Methods of monitoring and controlling environmental pollution and contamination as required by regulations and laws.
6. Specific discussion regarding mockups, off-site visits, receiving inspections, manufacturers representation, startup requirements, and other aspects of performance specific to Project.
7. Provisions for substantial completion(s) and final inspection(s) per Contract.

PART 3 - EXECUTION

3.1 OFF-SITE CONTROL

A. Items fabricated or assembled off-site shall be inspected for quality control at place of fabrication.

3.2 ON-SITE CONTROL

A. Notification:

1. Notify Contracting Officer at least 48 hours in advance of preparatory phase meeting.
2. Notify Contracting Officer at least 24 hours in advance of initial and follow-up phases.

B. Preparatory Phase: Perform before beginning each feature of work.

1. Review control submittal requirements with personnel directly responsible for quality assurance and quantity control of the work. As a minimum, Contractor's Quality Control Supervisor and foreman responsible for feature of work shall be in attendance.
2. Review applicable specifications sections and drawings related to feature of work.
3. Ensure copies of referenced standards related to sampling, testing, and execution for feature of work are available on site.
4. Ensure provisions have been made for field control testing.
5. Examine work area to ensure preliminary work has been completed.
6. Verify field dimensions and advise Contracting Officer of discrepancies with contract documents.
7. Ensure necessary equipment and materials are at project site and they comply with approved shop drawings and submittals.
8. Document preparatory phase activities and discussions on Contractor's Quality Control Daily Report.

C. Initial Phase:

1. As soon as work begins, inspect and test representative portion of particular feature of work for quality of workmanship.
2. Review control testing procedures to ensure compliance with contract requirements.
3. Document initial phase activities and discussions on Contractor's Quality Control Daily Report. Exact location of initial phase shall be indicated for future reference and comparison with follow-up phases.

D. Follow-Up Phase: Inspect and test as work progresses to ensure compliance with contract requirements until completion of work.

E. Additional Preparatory and Initial Phases: Additional preparatory and initial phases may be required on same feature of work for following reasons:

1. Quality of on-going work is unacceptable.
2. Changes in quality control staff, on-site production supervision, or work crew.
3. Work on particular feature of work is resumed after substantial period of inactivity.

3.3 DOCUMENTATION

A. Maintain Quality Control Daily Reports, Daily Test Report Information Sheets, and Accessibility Inspection Reports of quality control activities and tests. (Download from DSC Workflows website > Forms/Templates/Samples/Guidelines page > Construction Forms section, also available here: https://www.nps.gov/dscw/publicforms.htm#cf)

B. Quality Control Daily Reports shall not be substituted for other written reports required under clauses of contract, such as Disputes, Differing Site Conditions, or Changes.

3.4 ENFORCEMENT

A. Contractor shall stop work on any item or feature pending satisfactory correction of deficiency noted by quality control staff or Contracting Officer.

3.5 REPAIR AND PROTECTION

A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.

1. Provide materials and comply with installation requirements specified in other Specification Sections. Restore patched areas and extend restoration into adjoining areas with durable seams as invisible as possible.
2. Comply with Contract Document requirements for Section 01 73 00 “Execution.”

B. Protect construction exposed by or for quality-control service activities.

C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 01 40 00

SECTION 01 42 00 – REFERENCE STANDARDS

PART 1 - GENERAL

1.1 INDUSTRY STANDARDS

A. Applicability of Standards: Unless Contract Documents include more stringent requirements, applicable construction industry standards have same force and effect as if bound or copied directly into Contract Documents to the extent referenced. Such standards are made a part of Contract Documents by reference.

B. Publication Dates: Comply with standards in effect as of date of Contract Documents unless otherwise indicated.

C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with Contract Documents.

1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.2 ABBREVIATIONS AND ACRONYMS

A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities found in Section 01 42 00 Sources for Reference Publications, Unified Facilities Guide Specifications (UFGS) (accessible via Masters website > Downloads section > click on UFGS Master (WBDG Website). Names, telephone numbers, and websites are subject to change and are believed to be accurate and up-to-date as of date of Contract Documents.

XX	EXAMPLE Association (The) www.EXAMPLE.org	

B. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in following list. Names, telephone numbers, and websites are subject to change and are believed to be accurate and up-to-date as of date of Contract Documents.

DIN	Deutsches Institut fur Normung e.V. www.din.de	49 30 2601-3003
IAPMO	International Association of Plumbing and Mechanical Officials www.iapmo.org	(909) 472-4100
ICC	International Code Council	(888) 422-7233

	www.iccsafe.org	
ICC-ES	ICC Evaluation Service, Inc. icc-es.org	(800) 423-6587 (562) 699-0543

C. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in following list. Names, and websites are subject to change and are believed to be accurate and up-to-date as of date of Contract Documents.

ABA & ABAAS United States Access Board	Architectural Barriers Act (ABA) Architectural Barriers Act Accessibility Standards (ABAAS) www.access-board.gov
CoE	Army Corps of Engineers www.usace.army.mil
CPSC	Consumer Product Safety Commission www.cpsc.gov
DOC	Department of Commerce www.commerce.gov
DOD	Department of Defense www.defense.gov
DOJ	Department of Justice www.justice.gov
DOE	Department of Energy www.energy.gov
EPA	Environmental Protection Agency www.epa.gov
FCC	Federal Communications Commission www.fcc.gov
FDA	Food and Drug Administration www.fda.gov
GSA	General Services Administration www.gsa.gov
HUD	Department of Housing and Urban Development www.hud.gov
LBL	Lawrence Berkeley National Laboratory www.lbl.gov

NCHRP	National Cooperative Highway Research Program (See TRB (Transportation Resource Board))
NIST	National Institute of Standards and Technology www.nist.gov
OSHA	Occupational Safety & Health Administration www.osha.gov
PHS	U.S. Department of Health and Human Services www.hhs.gov
SD	State Department www.state.gov
TRB	Transportation Research Board www.nationalacademies.org/trb/transportation-research-board
USDA	Department of Agriculture www.usda.gov
USP	U.S. Pharmacopeia www.usp.org

D. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in following list. Names, telephone numbers, and websites are subject to change and are believed to be accurate and up-to-date as of date of Contract Documents.

ABAAS	Architectural Barriers Act Accessibility Standards www.access-board.gov
CFR	Code of Federal Regulations Available from Government Printing Office www.govinfo.gov/app/collection/cfr
DOD	Department of Defense Military Specifications and Standards Available from Department of Defense Single Stock Point www.dsp.dla.mil/Specs-Standards/
DSCC	Defense Supply Center Columbus (See FS (Federal Specification))
FED-STD	Federal Standard (See FS (Federal Specification))
FS	Federal Specification Available from Department of Defense Single Stock Point www.dsp.dla.mil/Specs-Standards/

	Available from General Services Administration www.gsa.gov
	Available from National Institute of Building Sciences www.nibs.org
FTMS	Federal Test Method Standard (See FS (Federal Specification))
MIL	(See MILSPEC (Military Specification and Standards))
MIL-STD	(See MILSPEC (Military Specification and Standards))
MILSPEC	Military Specification and Standards Available from Department of Defense Single Stock Point www.dsp.dla.mil/Specs-Standards/
UFAS	Uniform Federal Accessibility Standards Available from Access Board www.access-board.gov/guidelines-and-standards/buildings-and-sites/about-the-aba-standards/ufas *(UFAS is **only** for housing projects per Fair Housing Act. See also the Fair Housing Act Design Manual, www.huduser.gov/portal/publications/destech/fairhousing)*

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 42 00

SECTION 01 50 00 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.

1.2 DEFINITIONS

A. Permanent Enclosure: As determined by Contracting Officer (CO), permanent or temporary roofing is complete, insulated, and weathertight; exterior walls are insulated and weathertight; and openings are closed with permanent construction or substantial temporary closures.

1.3 USE CHARGES

A. General: Cost or use charges for temporary facilities shall be included in Contract Sum as required.

B. Water Service: Nonpotable Water from existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations without any additional permit costs.

C. Electric Power Service: Electric power from existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations without any additional permit costs.

1.4 ACTION SUBMITTALS

A. Scaffolding Drawings: Submit scaffolding and/or hoist erection drawings that have been designed, reviewed, and stamped by a Professional Engineer licensed to perform work in New York State.

1. Contracting Officer shall review scaffolding drawings for potential adverse impact on historic building fabric only.
2. Compliance with life-safety and structural requirements remains the responsibility of the General Contractor.
3. Show locations of scaffolding and points of scaffolding in contact with building. Include details of each point of contact or anchorage.
4. Scaffolding may not be attached to the building without written authorization from Contracting Officer.

B. Temporary construction and protection materials.

1. Submit product data for all materials.
2. Submit shop drawings for all construction, including construction fencing.

C. Site logistics plan: Show staging area, access routes, and proposed protection throughout the site, including tree protection. In staging area show locations of temporary toilets, dumpsters, and office and storage structures.

1.5 QUALITY ASSURANCE

A. Electric Service: Comply with National Electrical Contractors Association (NECA), National Electrical Manufacturers Association (NEMA), and Underwriter Laboratories (UL) standards and regulations for temporary electric service. Install service to comply with National Fire Protection Association (NFPA) 70.

B. Environmental Protection: Provide environmental protection as required by agency(ies) with jurisdiction and as indicated in Contract Documents. Coordinate with requirements of the following:

1. Regulatory Requirements.
2. Indoor Air Quality (IAQ) Management.
3. Noise and Acoustics Management.
4. Environmental Management.
5. Construction Waste Management.

1.6 PROJECT CONDITIONS

A. Temporary Use of Permanent Facilities: Installer of each permanent service shall assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before NPS acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Temporary materials may be new or used, but must be adequate in capacity for required usage, be of acceptable appearance to the Contracting Officer, must not create unsafe conditions, and must not violate requirements of applicable codes and standards.

B. Portable Chain-Link Fencing: Minimum 2 inch, 9-gage, galvanized steel, chain-link fabric fencing; minimum 6 feet high with galvanized steel pipe posts; minimum 2-3/8 inch OD line posts and 2-7/8 inch OD corner and pull posts, with 1-5/8 inch OD top and bottom rails. Provide concrete or weighted galvanized steel bases for supporting posts.

1. Provide flexible or perforated material, with custom printed graphics as directed by Contracting Officer, and associated fasteners as required for proper attachment and wind ventilation at full perimeter of chain link fence.

C. Safety Barrier Fence: Orange plastic fence, minimum height, 4 feet.

D. Barrier Tape: Yellow tape Imprinted with "CAUTION: CONSTRUCTION AREA," manufactured by Reef Industries, Inc., Houston, Texas, or approved equal.

E. Wood Enclosure Fence: Plywood, 8 feet high, framed with four 2 by 4 inch rails, with preservative-treated wood posts spaced not more than 8 feet apart.

1. Refer to Section 06 10 53 “Miscellaneous Rough Carpentry” for preservative-treated wood requirements.

F. Lumber and Plywood: Comply with requirements in Division 06 Section "Miscellaneous Rough Carpentry."

G. Polyethylene Sheet: Reinforced, fire-resistive sheet, 10 mil minimum thickness, with flame-spread rating of 15 or less per ASTM E 84 and passing NFPA 701 Test Method 2.

H. Dust-Control Adhesive-Surface Walk-off Mats: Provide mats minimum 36 by 60 inches.

I. Protection matting: Rubber or wood, non-staining to substrate.

2.2 TEMPORARY FACILITIES

A. Field Offices, General: Prefabricated or mobile units with serviceable finishes, temperature controls, and foundations adequate for normal loading.

B. Storage and Fabrication Sheds: Temporary weather tight sheds or other covered facilities for storage of materials subject to weather damage. Number and size of structures shall be subject to Contracting Officer's approval.

C. Toilets: Sufficiently lighted and ventilated toilet facilities in weatherproof, sight proof, handicap accessible, sturdy enclosures with privacy locks.

1. Provide separate toilet facilities for men and women.

2.3 EQUIPMENT

A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work. .

1. Locate facilities to limit site disturbance and as directed by the Contracting Officer.

B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

A. General: Install temporary service or connect to existing service.

1. Arrange with utility company, NPS, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services. Acquire necessary permits.

B. Storm Sewers and Drainage: Provide temporary utilities to remove effluent lawfully.

1. Connect temporary sewers to municipal system as directed by the agency(ies) with jurisdiction.

C. Non-potable water for construction is available from Visitor Center. Install piping and connections as required.

D. Potable water is not available on site. Furnish cool, potable water for construction personnel in locations convenient to work stations.

E. Sanitary Facilities: Provide temporary toilets, and wash facilities for use by construction personnel.

1. Place in approved locations secluded from public observation and convenient to work stations. Relocate as work progress requires.
2. Maintain and clean toilet facilities at least twice weekly.
3. Completely remove sanitary facilities on completion of work.

F. Electric Power Service: Use of existing electric power service will be permitted, as long as equipment is maintained in a condition acceptable to NPS.

1. The Contractor's electrician shall meet with the Government on site to review the electrical system and determine the best places to tap the temporary service from.
2. The Contractor will be responsible for maintaining the exterior lighting of the dome and colonnade throughout the period of construction. The Government will instruct the Contractor on the operation of the lighting system. Any interruption of the lighting must be approved by the Government with a minimum of 48 hours' notice.
3. When temporary connections are removed, restore existing utility services to original condition.
4. Review exterior colonnade and dome lighting with the Government at completion, and replace any non-functioning lamps or fixtures.

G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.

1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

3.3 SUPPORT FACILITIES INSTALLATION

A. General: Comply with the following:

1. Provide incombustible construction for offices, shops, and sheds located within construction area or within 50 feet of building lines. Comply with NFPA 241.
2. Maintain support facilities until near Substantial Completion. Remove structures, equipment, and furnishings, and terminate services after punch list is 100 percent completed or when directed by Contracting Officer. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Contracting Officer.

B. Traffic Controls: Erect and maintain barricades, lights, danger signals, and warning signs in accordance with Manual on Uniform Traffic Control Devices (MUTCD), Part IV, latest edition.

1. Protect existing site improvements to remain including curbs, pavement, and utilities.
2. Maintain access for fire-fighting equipment and access to fire hydrants.
3. Illuminate barricades and obstructions at night; keep safety lights illuminated from sunset to sunrise.
4. Adequately barricade and post open cuts in or adjacent to thoroughfares.
5. Protect pedestrian traffic by guardrails or fences.
6. When pedestrian traffic is detoured onto a roadway, provide temporary walkways with protection as required at ends and overhead. For walkways, use lumber running parallel to direction of traffic movement and provide ramps at changes of elevation.
7. Cover pipes, hoses, and power lines crossing sidewalks and walkways with troughs using beveled edge boards.
8. Install Barrier Tape where directed by Contracting Officer. Keep a minimum of two rolls on site.

C. Parking: No on-site parking is available. Comply with local parking regulations.

D. Temporary Signs: Provide signage required for security and to facilitate access by visitors and workers. Fence, barricade, or otherwise block off the immediate work area to prevent unauthorized entry.

1. Provide temporary, directional signs for construction personnel and visitors.
2. Maintain and touchup signs so they are legible at all times.
3. Advertising signs are not permitted.

E. Waste Disposal Facilities: Provide waste-collection containers in sizes adequate to handle waste from construction operations. Comply with requirements of agency(ies) with jurisdiction.

F. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.

1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.

G. Existing Stair Usage: Use of existing interior stairs for access to lower roof will not be permitted. Construction access will be via exterior stair tower only.

1. Use of existing stairs in the Interstitial Space above the lower roof and within the dome only will be permitted, provided stairs are cleaned and maintained in a condition acceptable to Contracting Officer. At Substantial Completion, restore stairs to condition existing before initial use.

2. Provide protective coverings, barriers, devices, signs, or other procedures to protect stairs and to maintain means of egress. If stairs become damaged, restore damaged areas so no evidence remains of correction work.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

A. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction in ways and by methods that comply with environmental regulations and minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.

B. Cleaning of Equipment: Ensure prior to moving on to Project Area, equipment is free of soil, seeds, vegetative matter, or other debris that could contain or hold seeds. Ensure equipment has been pressure washed and is free of exotic species. Equipment shall be considered free of soil, seeds, and other debris when visual inspection does not disclose such material. Disassembly of equipment components or specialized inspection tools are not required.

C. Temporary Erosion and Sedimentation Control: Refer to Section 01 57 23 "Under-an-Acre Pollution Prevention".

D. Tree and Plant Protection: Refer to Section 01 11 00 "Summary of Work".

E. Pest Control: Follow NPS requirements to minimize attraction and harboring of rodents, roaches, and other pests and perform extermination and control procedures at regular intervals so Project will be free of pests and residues at Substantial Completion. Perform control operations lawfully, using environmentally safe materials.

F. Site Enclosure Fence: Before construction operations begin, furnish and install chain link fencing to prevent people and animals from easily entering site except by entrance gates.

1. Extent of Fence: As indicated on Drawings.
2. Locate vehicular gates to avoid interference with traffic on public thoroughfares.
3. Locate pedestrian entrance gates as required to provide controlled personnel entry.
4. Maintain security by limiting number of keys and restricting distribution to authorized personnel. Provide Contracting Officer with one set of keys or double-lock.

G. Security Enclosure and Lockup: Install substantial temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security.

H. Barricades, Warning Signs, and Lights: Comply with requirements of agency(ies) with jurisdiction for erecting structurally adequate barricades, including warning signs and lighting.

I. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.

J. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241.

1. Refer to Section 01 35 91 "Historic Preservation Treatment Procedures" for fire-prevention plan requirements and fire-protection procedures.
2. Responsible Person: Capable and qualified person shall be placed in charge of fire protection. Responsibilities shall include locating and maintaining fire protective equipment and establishing and maintaining safe torch cutting and welding procedures.
3. Tobacco Use, Smoking, and Vaping: Smoking within buildings or temporary storage sheds is prohibited.
4. Develop and supervise overall fire-prevention and -protection program for personnel at Project Site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
5. Hazard Control: Take necessary precautions to prevent fire during construction. Do not store flammable or combustible liquids in historic structures. Provide adequate ventilation during use of volatile or noxious substances.
6. Spark Arresters: Equip gasoline or diesel powered equipment used during periods of potential fire hazards or in potential forest and grass fire locations with spark arresters approved by United States Department of Agriculture (USDA) Forest Service.

    a. Written determinations of periods and areas of potential fire hazard will be issued by Contracting Officer.

7. Buildings: Furnish a minimum of one extinguisher for each 1,500 square feet of area or major fraction thereof.

    a. Travel distance from any work station to nearest extinguisher shall not exceed 75 feet.

8. Vehicles and Equipment: Provide one extinguisher on each vehicle or piece of equipment.

3.5 OPERATION, TERMINATION, AND REMOVAL

A. Supervision: Enforce strict discipline in use of temporary facilities. Minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.

B. Maintenance: Maintain facilities in good operating condition until removal.

1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on 24-hour basis where required to achieve indicated results and avoid possibility of damage.

C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.

D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been

delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.

1. Materials and facilities that constitute temporary facilities are property of Contractor. NPS reserves right to take possession of Project identification signs.
2. At Substantial Completion, clean and renovate permanent facilities used during construction period.

END OF SECTION 01 50 00

SECTION 01 57 19.11 – INDOOR AIR QUALITY MANAGEMENT

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes:

1. Special requirements for Indoor Air Quality (IAQ) management during construction operations.

a. Control of emissions during construction.
b. Moisture control during construction.

2. Procedures for testing baseline IAQ. Baseline IAQ requirements, specify maximum indoor pollutant concentrations for acceptance of the facility.

1.2 DEFINITIONS

A. Definitions pertaining to sustainable development: As defined in ASTM E2114.

B. Adequate ventilation: Ventilation, including air circulation and air changes, required to cure materials, dissipate humidity, and prevent accumulation of particulates, dust, fumes, vapors, or gases.

C. Hazardous Materials: Any material regulated as a hazardous material in accordance with 49 CFR 173 (Code of Federal Regulations), requires a Material Safety Data Sheet (MSDS) in accordance with 29 CFR 1910.1200, or which during end use, treatment, handling, storage, transportation or disposal meets or has components which meet or have the potential to meet the definition of a Hazardous Waste in accordance with 40 CFR 261. Throughout this specification, hazardous material includes hazardous chemicals.

1. Hazardous materials include pesticides, biocides, and carcinogens as listed by recognized authorities, such as the Environmental Protection Agency (EPA) and the International Agency for Research on Cancer (IARC).

D. Indoor Air Quality (IAQ): Composition and characteristics of air in an enclosed space that affect occupants of that space. Indoor air quality of a space refers to relative quality of air in a building with respect to contaminants and hazards and is determined by the level of indoor air pollution and other characteristics of the air, including impact on thermal comfort such as air temperature, relative humidity and air speed.

E. Interior final finishes: Materials and products exposed to interior occupied spaces; including flooring, wall covering, finish carpentry, and ceilings.

F. Packaged dry products: Materials and products installed in dry form delivered in manufacturer's packaging; including carpets, resilient flooring, ceiling tiles, and insulation.

G. Wet products: Materials and products installed in wet form, including paints, sealants, adhesives, special coatings, and materials which require curing.

1.3 QUALITY ASSURANCE

A. Inspection and Testing Lab Qualifications: Minimum of 5 years of experience in performing types of testing specified herein.

1.4 SUBMITTALS

A. Indoor Air Quality (IAQ) Management Plan: After award and before Pre-construction conference, prepare and submit IAQ Management Plan, including:

1. Procedures for control of emissions during construction.

    a. Identify schedule for application of interior finishes: Identify each interior finish that generates odors, moisture, or vapors or is susceptible to adsorption of odors and vapors. Indicate air handling zone, sequence of application, and curing times.
    b. Identify potential sources of odor and dust.
    c. Identify construction activities likely to produce odor or dust.
    d. Identify areas of project potentially affected, especially occupied areas.
    e. Evaluate potential problems by severity and describe methods of control.
    f. Describe construction ventilation to be provided, including type and duration of ventilation, use of permanent Heating HVAC systems, types of filters and schedule for replacement of filters.
    g. Describe cleaning and dust control procedures.

2. Procedures for moisture control during construction.

    a. Identify porous materials and absorptive materials.
    b. Identify schedule for inspection of stored and installed porous and absorptive materials.

3. Revise and resubmit Plan as required by Contracting Officer (CO).

    a. Approval of Contractor's Plan will not relieve the Contractor of responsibility for compliance with applicable environmental regulations.

B. Product Data:

1. Material Safety Data Sheets (MSDS): Submit MSDSs for inclusion in Operation and Maintenance Manual for:

    a. Adhesives.
    b. Floor and wall patching/leveling materials.
    c. Sealants.
    d. Paint.
    e. Lubricants.
    f. Cleaning products.

C. Inspection and Test Reports:

1. Moisture control inspections.
2. Moisture content testing.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 IAQ MANAGEMENT - EMISSIONS CONTROL

A. During construction operations, follow the recommendations in SMACNA IAQ Guidelines for Occupied Buildings under Construction.

B. Source Control: Provide low and zero VOC materials as specified.

C. Pathway Interruption: Isolate areas of work to prevent contamination of clean or occupied spaces. Provide pressure differentials and/or physical barriers to protect clean or occupied spaces.

D. Housekeeping: During construction, maintain project and building products and systems to prevent contamination of building spaces.

E. Temporary Ventilation: For materials/products that generally require ventilation for off gassing, provide an ACH (air changes per hour) of 1.5 or more and as follows:

1. Provide minimum 48-hour pre-ventilation of packaged dry products prior to installation. Remove from packaging and ventilate in a secure, dry, well-ventilated space free from strong contaminant sources and residues. Provide a temperature range of 60 degrees Fahrenheit minimum to 90-degree Fahrenheit maximum continuously during ventilation period. Do not ventilate within limits of Work unless otherwise approved by Contracting Officer.
2. Provide adequate ventilation during and after installation of interior wet products and interior final finishes.
3. Provide filtration media with a Minimum Efficiency Reporting Value (MERV) of 8 as determined by ASHRAE 52.2 during construction

F. Scheduling: Schedule construction operations involving wet products prior to packaged dry products to the greatest extent possible.

3.2 IAQ MANAGEMENT - MOISTURE CONTROL

A. Housekeeping:

1. Keep materials dry. Protect stored on-site and installed absorptive materials from moisture damage.
2. Verify installed materials and products are dry prior to sealing and weatherproofing building envelope.

3. Store interior absorptive materials only after building envelope is sealed and weatherproofed.

B. Inspections: Document and report results of inspections; state whether or not inspections indicate satisfactory conditions.

1. Examine materials for dampness as they arrive. If acceptable to Contracting Officer, dry damp materials completely prior to installation; otherwise, reject materials that arrive damp.
2. Examine materials for mold as they arrive and reject materials that arrive contaminated with mold.
3. Inspect stored and installed absorptive materials regularly for dampness and mold growth. Inspect weekly.

    a. If stored or installed absorptive materials become wet, notify Contracting Officer. Inspect for damage. If acceptable to the Contracting Officer, dry completely prior to closing in assemblies; otherwise, remove (in accordance with the Waste Management Plan) and replace with new materials.

C. Schedule:

1. Schedule work such that absorptive materials, such as porous insulations, paper-faced gypsum board, ceiling tile, and finish flooring, are not installed until they can be protected from rain and construction-related water.
2. Weather-proof as quickly as possible. Schedule installation of moisture-control materials, including but not limited to air barriers, flashing, exterior sealants and roofing, at earliest possible time.

D. Testing for Moisture Content: Test moisture content of porous materials and absorptive materials to ensure they are dry before sealing them into an assembly. Document and report results of testing. Where tests are not satisfactory, dry materials and retest. If satisfactory results cannot be obtained with retest, remove and replace with new materials.

1. Wood: Moisture test as per ASTM D4444 - Standard Test Methods for Use and Calibration of Hand-Held Moisture Meters; unless otherwise indicated acceptable upper limits for wood products are less than 20% at center of piece; less than 15% at surface.

END OF SECTION 01 57 19.11

SECTION 01 57 19.12 – NOISE AND ACOUSTICS MANAGEMENT

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes:

1. Special requirements for noise and acoustics management during construction operations.

1.2 DEFINITIONS

A. Ambient Noise Level: The total noise associated with a given environment, being usually a composite of normal or existing sounds from all sources near and far, excluding the noise source at issue.

B. Daytime: The hours from 7 A.M. to 9 P.M. on weekdays and 9 A.M. to 9 P.M. on weekends and holidays.

C. Nighttime: All non-daytime hours.

D. Property Line: The real or imaginary line along the ground surface and its vertical extension, which separates real property owned or controlled by one person from contiguous real property owned or controlled by another person or from any public right-of-way or from any public space.

E. Receiving Noise Area: Any real property where people live or work and where noise is heard, excluding the project or source area.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 NOISE MANGEMENT

A. Noise Control: Perform construction operations to minimize noise. Perform noise-producing work in less sensitive hours of the day or week as directed by the Contracting Officer.

B. Repetitive and/or intermittent, high-level noise: Permitted only during Daytime.

1. Do not exceed the following dB(A) limitations at 50 feet:

Sound Level in dB(A)	Time Duration of Impact Noise
70	More than 12 minutes in any hour
80	More than 3 minutes in any hour

2. Maximum permissible construction equipment noise levels at 50 feet:

EARTHMOVING	dB(A)	MATERIALS HANDLING	dB(A)
Front Loaders	75	Concrete Mixers	75
Backhoes	75	Concrete Pumps	75
Dozers	75	Cranes	75
Tractors	75	Derricks Impact	75
Scrapers	80	Pile Drivers	95
Graders	75	Jack Hammers	75
Trucks	75	Rock Drills	80
Pavers, Stationary	80	Pneumatic Tools	80
Pumps	75	Saws	75
Generators	75	Vibrators	75
Compressors	75		

C. Ambient Noise:

1. Maximum noise levels (dB (decibel)) for receiving noise area at property line shall be as follows:

a. Residential receiving area
Daytime: 65 dB
Nighttime: 45 dB

b. Commercial/Industrial receiving area
Daytime: 67 dB
Nighttime: 65 dB

c. In the event the existing local ambient noise level exceeds the maximum allowable receiving noise level (dB), the receiving noise level maximum for construction operations shall be adjusted as follows:

1) Residential Receiving Area: Maximum 3 additional dB above the local ambient as measured at property line.
2) Commercial/Industrial Receiving Area: Maximum 5 additional dB above the local ambient as measured at the property line.

3.2 FIELD QUALITY CONTROL

A. Assess potential effects of construction noise on facility occupants and visitors in accordance with ASTM E1686 and as follows:

1. Ambient Noise Measurement: Measure at property line at a height of at least four (4) feet above the immediate surrounding surface. Average the ambient noise level over a period of at least 15 minutes.
2. Ambient Noise Measurement at Urban Sites: Conduct during morning peak traffic hour between 7 A.M. and 9 A.M. and afternoon peak traffic hour between 4 P.M. and 6 P.M. In addition, conduct a 24-hour measurement at the proposed project site to document the noise pattern throughout the day. Adjust and weight for seasonal and climatic variations.

B. Monitor noise produced from construction operations in accordance with ASTM E1780.

END OF SECTION 01 57 19.12

SECTION 01 57 23 - UNDER-AN-ACRE POLLUTION PREVENTION

PART 1 - GENERAL

1.1 SUMMARY

A. Federal Regulations for controlling discharges of pollutants (including chemicals, erodible material, and trash) from municipal separate storm sewer systems, construction sites, and industrial activities, were brought under the National Pollution Discharge Elimination System (NPDES) permit process by amendments to the Clean Water Act (CWA), and promulgation of federal stormwater regulations issued by the United States Environmental Protection Agency (USEPA). The USEPA uses amount of ground disturbance as a measure of a project potential to generate pollution from erosion. NPDES Phase I regulates discharges from construction sites that disturb 5 acres or more. NPDES Phase II regulations expand existing General Permit requirements under Phase I to include/regulated discharges from construction sites that disturb land equal to or greater than one (1) acre and less than 5 acres, known as Small Construction Activity. Construction disturbances 1 acre and above typically require a formal NPDES permit and a formal Stormwater Pollution Prevention Plan (SWPPP) must be submitted to Agency(ies) with Jurisdiction for review and approval.

B. National Park Service (NPS) Standards and Guidelines require water quality be protected to ensure compliance with Organic Act. Contractor shall prepare an Under-An-Acre Pollution Prevention Plan (UPPP) for each project resulting in less than 1 acre of soil disturbance or not otherwise subject to requirements of NPDES program. (UPPP Guideline)

C. Work of this section consists of implementing measures to Temporary Storm Water Pollution during construction activities, either through compliance with NPDES permit program; or in conformance with NPS guidance for UPPPs.

1.2 DEFINITIONS

A. Refer to Section 01 81 13 “Sustainable Design Requirements for Non-LEED Projects” for sustainability-related terminology and definitions.

B. Environmental Pollution and Damage: The presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances; or degrade utility of the environment for aesthetic, cultural, or historical purposes.

C. National Pollution Discharge Elimination System (NPDES) Phase I: Regulates discharges from construction sites that disturb 5 acres or more.

D. NPDES Phase II: Regulations expand existing General Permit requirements under Phase I to include and regulate discharges from construction sites that disturb land equal to or greater than one (1) acre and less than 5 acres, known as Small Construction Activity.

E. Storm Water Pollution Prevention Plan (SWPPP): Developed and implemented stormwater management measures to protect surface water from pollutants during construction activities

disturbing an acre or more in compliance with federal, state, and local requirements for permit approval under NPDES program.

F. Under-an-Acre Pollution Prevention Plan (UPPP): Developed and implemented pollution prevention plan (including stormwater management measures, if needed) to protect environment from pollutants on construction projects with less than one acre of disturbance in conformance with NPS guidelines.

1.3 SUBMITTALS

A. After contract award and before pre-construction conference, prepare and submit UPPP in conformance with NPS guidelines and adherence to applicable construction storm water management practices.

B. Inspection Schedule: Submit schedule for inspection and monitoring of storm water pollution prevention measures.

C. Erosion Control Products: Submit manufacturer's product information and installation recommendations for silt fence, filter fabric, erosion control blanket, straw bales, and other materials proposed for use on this project.

1.4 QUALITY ASSURANCE

A. Contractor shall prepare and submit a plan to Contracting Officer (CO) for review and concurrence.

B. Orientation Meeting: Arrange and conduct an Erosion and Sediment Control meeting/briefing to inform parties, scheduled to be on-site during project, of measures to be implemented for proper erosion and sediment control.

1. Installation of silt fences, storm drain protection, and other forms of erosion and sediment control shall not begin until after this meeting has occurred.
2. Orientation meeting may be included as part of preconstruction conference.

C. Pollution Prevention and Erosion Control Manager: Contractor shall designate Pollution Prevention and Erosion Control Manager responsible for implementation, inspection, maintenance, and amendments to approved plan.

1. Pollution Prevention and Erosion Control Manager shall be familiar with temporary storm water pollution prevention procedures and Best Management Practices and ensure emergency procedures and plan are updated as needed and available for inspection.

2. When changes in approved plan are required, Pollution Prevention and Erosion Control Manager shall prepare and certify an amendment and submit to Contracting Officer for review and concurrence.

PART 2 - PRODUCTS

2.1 UNDER-AN-ACRE POLLUTION PREVENTION PLAN

A. Provide UPPP which conforms to NPS requirements and include:

1. Responsible Parties.
2. General Information: Project Scope, Details, Site Information, and Spill Prevention.
3. Standards and Constraints.
4. Project Scheduling.
5. Known Data on Soil and Fill.
6. Activities with Potential to Generate Sediment.
7. Activities and Materials with Potential to Pollute Storm Water.
8. Management and Reporting Best Management Practices (BMP).
9. Waste Management BMPs.
10. Non-Storm Water Pollution Control BMPs.
11. Soil Stabilization BMPs.
12. Sediment Control BMPs.
13. Other Pollution Control BMPs.
14. References.
15. Preparer's Certification.
16. Appendices: Contact Information, Pollution Prevention Control Map or Sheet(s), Standard Installation Specifications for each BMP, and blank forms.

PART 3 - EXECUTION

3.1 ENVIRONMENTAL PROTECTION

A. Protection of Natural Resources: Comply with applicable regulations and these specifications. Preserve natural resources within project boundaries and outside limits of work performed under this Contract in their existing condition or restore to an equivalent or improved condition as approved by Contracting Officer.

B. Construction Zone: Arrange construction activities to minimize pollution (i.e., erosion, trash, etc.) to maximum practical extent.
   1. Clearly mark and delineate limits of work activities.
   2. Equipment shall not be allowed to operate outside limits of work or to disturb existing vegetation.
   3. Material shall be stored away from locations where water is present to greatest extent practicable.

3.2 REGULATORY REQUIREMENTS

A. Contracting Officer Notification: Notify Contracting Officer in writing and by telephone of these events:

1. Erosion and sediment control meeting/briefing.

2. Following installation of required sediment control structures.
3. Prior to removal of or modification to sediment control structures.
4. Prior to removal of sediment control structures.

3.3 UNDER-AN_ACRE POLLUTION PREVENTION PLAN

A. Review and Acceptance: Contractor and Contracting Officer will jointly review draft UPPP and agree to needed revisions. Contractor shall incorporate revisions, sign, and submit final UPPP to Contracting Officer. Final UPPP will be the document enforced on the Project.

1. Accepted UPPP will describe and ensure implementation of practices to be used to reduce pollutants in storm water discharges.
2. Contractor shall maintain current copy of UPPP and associated records and forms at jobsite throughout duration of Project.
3. UPPP shall be available for public inspection and inspection and use of Contracting Officer.
4. Approval of Contractor's UPPP will not relieve Contractor of responsibility for compliance with applicable environmental regulations.

B. Implementation: Implement Plan as required throughout construction period and maintain erosion control elements in proper working order.

1. Do not perform construction until UPPP has been implemented.

C. UPPP (including inspection forms) and data used to complete the NOI shall be provided to Contracting Officer after Substantial Completion of project.

3.4 SITE INSPECTIONS AND PLAN REVISIONS

A. Inspections: Contractor and Contracting Officer will perform a weekly inspection onsite.

1. Inspection shall include disturbed areas not completely stabilized, areas used for storage of materials, locations where vehicles enter or exit site, and other erosion and sediment controls included in the UPPP.
2. Inspections shall be documented.
3. Inspection forms shall be retained onsite throughout construction period.

B. UPPP Revisions: It may be necessary to revise UPPP during construction to make necessary improvements, revisions, or to respond to unforeseen conditions noted during construction or site inspections.

1. UPPP shall specify mechanism whereby revisions may be proposed by Contractor or Contracting Officer.
2. Contractor and Contracting Officer will jointly review each revision to UPPP before changes incorporated and implemented. Contractor will then provide revised copy of UPPP to Contracting Officer.
3. Accepted modifications will be implemented within 7 calendar days following date of inspection when deficiencies or necessary corrections are first noted.

C. Negligence: Provide additional temporary erosion and pollution controls made necessary by Contractor's errors or negligence at no additional cost to Government.

3.5 HOUSEKEEPING AND SITE MANAGEMENT

A. Store materials onsite in conformance to Federal, state, local, and manufacturer's regulations and specifications. Use Best Management Practices to minimize risk of materials coming into contact with environmental conditions (i.e. water and wind) that could disperse them.

B. Manage solid waste in conformance to Federal, state, and local regulations. Best Management Practices should be used to minimize risk of materials coming into contact with environmental conditions (i.e. water and wind) that could disperse them.

C. Include a spill prevention and control plan with provisions placed in UPPP.

D. Manage hazardous waste (including contaminated soil) in conformance to Federal, state, local and NPS regulations and guidelines.

3.6 EROSION CONTROL MEASURES

A. Erosion control measures shall consist of Best Management Practices for storm water discharges, including silt fencing, barrier protectors, straw bales, temporary soil retention blankets, excelsior drainage filters, sediment traps and berms.

B. Berms and excelsior drainage filters shall be used to form sediment traps and control run-on and run-off into other areas, including creeks, streams, marshes, access roads, well areas, and staging areas.

C. Erosion control measures shall be used to contain only direct precipitation in construction zone. Contained water shall be allowed to percolate into ground or drain slowly through drainage filter sediment traps.

D. Earthen sediment traps or holding ponds shall not be used unless accepted in writing by Contracting Officer.

E. Reduce runoff velocity and direct surface runoff around and away from fuel containment, storage, and borrow areas.

F. Divert surface runoff around and away from cut and fill slopes.

G. Place drainage filters around catch basins to create sediment traps to control run-off from construction area.

H. Excess water used for dust control shall be contained within demolition areas by erosion control measures.

I. Prevent deposition of materials onto paved areas. Inspect paved areas for deposited materials weekly and remove materials immediately.

J. Furnish, install, maintain, and operate necessary control measures and other equipment necessary to prevent erosion as described in approved UPPP.

K. Before work begins, sufficient equipment shall be available on site to assure operation and adequacy of erosion control system can be maintained.

3.7 MAINTENANCE OF TEMPORARY FACILITIES

A. Ensure erosion and sediment control structures remain effective throughout excavation and grading operations. Relocate structures as necessary.

B. Inspect control structures after each significant rainfall. Promptly repair breaches which occur. Remove entrapped sediment from behind excelsior drainage filter after each storm.

3.8 REPORTING

A. If a discharge occurs or if project receives written notice or order from regulatory agency, Contractor shall immediately notify Contracting Officer and shall file written report to Agency(ies) with Jurisdiction within 7 days of discharge event, notice, or order. Corrective measures shall be implemented immediately following discharge, notice, or order. The report to the Agency(ies) with Jurisdiction shall contain:

1. Date, time, location, nature of operation, and type of discharge, including cause or nature of notice or order.
2. Best Management Practices deployed before discharge event, or prior to receiving notice or order.
3. Date of deployment and type of Best Management Practices deployed after discharge event, or after receiving notice or order, including additional Best Management Practices installed or planned to reduce or prevent re-occurrence.
4. An implementation and maintenance schedule for affected Best Management Practices.

3.9 SEDIMENT DISPOSAL

A. Dispose of sediment excavated from temporary sediment control structures on site with general fill, or with topsoil. Allow sediment to dry out as required before reuse.

B. Place sediment removed from traps and other structures where it will not enter a storm drain or watercourse and where it will not immediately reenter the basin.

3.10 REMOVAL OF TEMPORARY POLLUTION CONTROL MEASURES

A. Remove temporary control measures with written permission of Contracting Officer within 20 working days after final acceptance of project, and/or once grading is complete and slopes have stabilized.

END OF SECTION 01 57 23

SECTION 01 67 00 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and environmental requirements.

1.2 DEFINITIONS

A. Products: Items purchased for incorporating into Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes "material," "equipment," "system," and terms of similar intent.

1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, current as of date of Contract Documents.
2. New Products: Items that have not previously been incorporated into another project or facility, except that products consisting of recycled-content materials are allowed, unless explicitly stated otherwise. Products salvaged or recycled from other projects are not considered new products.
3. Comparable Product: Product demonstrated and approved through submittal process, or where indicated as a product substitution, to have indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.

1.3 SUBMITTALS

A. Record Submittals as specified in Section 01 77 00 “Closeout Procedures” and technical sections, submit:

1. Submit environmental data in accordance with Table 1 of ASTM E2129 for these products:

a. Masonry.
b. Roofing.
c. Joint Sealers.
d. Paints & Coatings.

.

2. Material Safety Data Sheets (MSDS): For each product required by OSHA to have a MSDS, submit an MSDS. MSDS shall be prepared within the previous five years. Include information for MSDS Sections 1 to 16 in accordance with ANSI Z400.1 and as follows:

a. Section 1: Chemical Product and Company Identification.
b. Section 2: Composition/Information on Ingredients.

c. Section 3: Hazards Identification.
d. Section 4: First Aid Measures.
e. Section 5: Fire Fighting Measures.
f. Section 6: Accidental Release Measures.
g. Section 7: Handling and Storage.
h. Section 8: Exposure Controls/Person Protection.
i. Section 9: Physical and Chemical Properties.
j. Section 10: Stability and Reactivity Data.
k. Section 11: Toxicological Information. Include data used to determine the hazards cited in Section 3. Identify acute data, carcinogenicity, reproductive effects, and target organ effects. Provide written description of the process used in evaluating chemical hazards relative to preparation of the MSDS.
l. Section 12: Ecological Information. Include data regarding environmental impacts during raw materials acquisition, manufacture, and use. Include data regarding environmental impacts in event of accidental release.
m. Section 13: Disposal Considerations. Include data regarding proper disposal of the chemical. Include information regarding recycling and reuse. Indicate whether or not product is considered to be "hazardous waste" according to United States EPA Hazardous Waste Regulations 40 CFR 261 (Code of Federal Regulations).
n. Section 14: Transportation Information. Identify hazard class for shipping.
o. Section 15: Regulatory Information. Identify federal, state, and local regulations applicable to the material.
p. Section 16: Other Information. Include additional information relative to recycled content, biobased content, and other information regarding environmental and health impacts. Identify the date MSDS was prepared.

1.4 QUALITY ASSURANCE

A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, product selected shall be compatible with products previously selected, even if previously selected products were also options.

1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle products using means and methods that prevent damage, deterioration, and loss, including theft. Comply with manufacturer's written instructions.

B. Delivery and Handling:

1. Schedule delivery to minimize long-term storage at Project site and prevent overcrowding of construction spaces.
2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
3. Deliver products to Project site in undamaged condition; in manufacturer's original sealed container or other packaging system; complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
4. Inspect products on delivery to ensure compliance with Contract Documents. Ensure products are undamaged and properly protected.

5. Obtain materials in biodegradable or recyclable/reusable packaging which uses minimum amount of packaging possible.

C. Storage:

1. Allow for inspection and measurement of quantity or counting of units.
2. Store materials in manner to not endanger Project structure.
3. Store products subject to damage by the elements, under cover in weather tight enclosure above ground, with ventilation adequate to prevent condensation.
4. Store cementitious products and materials on elevated platforms.
5. Store foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
6. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
7. Protect stored products from damage and liquids from freezing.
8. Store loose granular materials in well-drained area on solid surfaces to prevent mixing with foreign matter.

1.6 PACKAGING

A. Where Contractor has option to provide one of listed products or equal, preference shall be given to products with minimal packaging and easily recyclable packaging as defined in ASTM D5834-95.

1.7 PRODUCT WARRANTIES

A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of Contract Documents.

1. Manufacturer's Warranty: Preprinted written warranty published by individual manufacturer for product specifically endorsed by manufacturer to Owner.
2. Special Warranty: Written warranty required by or incorporated into Contract Documents, either to extend time limit provided by manufacturer's warranty or to provide more rights for Government.

B. Special Warranties: Prepare written document containing appropriate terms and identification, ready for execution. Submit draft for approval before final execution.

1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
2. Specified Form: When specified forms are included with Specifications, prepare written document using appropriate form properly executed.

C. Submittal Time: Comply with requirements in Section 01 77 00 "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

A. General Product Requirements: Provide products to comply with Contract Documents, undamaged and, unless otherwise indicated, new at time of installation.

1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types produced and used successfully in similar situations on other projects.
3. Government reserves right to limit selection to products with warranties not in conflict with requirements of Contract Documents.
4. Where products are accompanied by term "as selected," Contracting Officer will make selection.
5. Where products are accompanied by term "match sample," sample to be matched is Government's sample.
6. Descriptive, performance, and reference standard requirements in Specifications establish "salient characteristics" of products.

B. Product Selection Procedures:

1. Product: Where Specifications name single product and manufacturer, provide named product that complies with requirements or approved equal.
2. Manufacturer/Source: Where Specifications name single manufacturer or source, provide product by named manufacturer or source that complies with requirements or approved equal.
3. Products: Where Specifications include list of names of both products and manufacturers, provide one of the products listed that complies with requirements or approved equal.
4. Manufacturers: Where Specifications include list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements or approved equal.
5. Available Products: Where Specifications include list of names of both products and manufacturers, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with provisions in Part 2 "Comparable Products" Article for consideration of an unnamed product.
6. Available Manufacturers: Where Specifications include list of manufacturers, provide a product by one of the manufacturers listed, or an unnamed manufacturer, that complies with requirements. Comply with provisions in Part 2 "Comparable Products" Article for consideration of an unnamed product.
7. Product Options: Where Specifications indicate sizes, profiles, and dimensional requirements on Drawings are based on a specific product or system, provide specified product, system, or approved equal.
8. Basis-of-Design Product: Where Specifications name product and include a list of manufacturers, provide specified product or a comparable product by one of the other named manufacturers, or approved equal. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics based on the product named.

9. Visual Matching Specification: Where Specifications require matching an established Sample, select product that complies with requirements and matches Architect's sample. Contracting Officers decision will be final on whether a proposed product matches.

    a. If no product available within specified category matches and complies with other specified requirements, comply with provisions in Part 2 "Product Substitutions" Article for proposal of product.

10. Visual Selection Specification: Where Specifications include phrase "as selected from manufacturer's colors, patterns, textures" or a similar phrase, select a product that complies with other specified requirements.

    a. Standard Range: Where Specifications include phrase "standard range of colors, patterns, textures" or similar phrase, Contracting Officer will select color, pattern, density, or texture from manufacturer's product line that does not include premium items.
    b. Full Range: Where Specifications include phrase "full range of colors, patterns, textures" or similar phrase, Contracting Officer will select color, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

A. Conditions: Contracting Officer will consider Contractor's request for comparable product when the following conditions are satisfied. If following conditions are not satisfied, Contracting Officer will return requests without action, except to record noncompliance with these requirements:

1. Evidence proposed product does not require revisions to Contract Documents, that it is consistent with Contract Documents and will produce indicated results and is compatible with other portions of Work.
2. Detailed comparison of significant qualities of proposed product with those named in Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
3. Evidence proposed product provides specified warranty.
4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
5. Samples, if requested.

PART 3 - EXECUTION

3.1 PROTECTION AFTER INSTALLATION

A. Provide adequate coverings as necessary to protect installed materials from damage resulting from natural elements, traffic, and subsequent construction. Remove when no longer needed.

END OF SECTION 01 67 00

SECTION 01 73 40 - EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes general procedural requirements governing execution of Work including:

1. Construction layout.
2. Field engineering and surveying.
3. General installation of products.
4. Progress cleaning.
5. Protection of installed construction.
6. Correction of the Work.

1.2 SUBMITTALS

A. Landfill Receipts: Submit copy of receipts issued by landfill facility, licensed to accept hazardous materials, for hazardous waste disposal.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 EXAMINATION

A. Existing Conditions: Existence and location of site improvements and other construction indicated as existing are not guaranteed.

1. Before beginning work, investigate and verify the existence and location of mechanical and electrical systems and other construction affecting the Work.

B. Existing Utilities: Existence and location of underground and other utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify existence and location of underground utilities and other construction affecting Work.

C. Acceptance of Conditions: Examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.

1. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
2. Examine walls and roofs for suitable conditions where products and systems are to be installed.

3. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Field Measurements: Take field measurements as required to fit Work properly. Recheck measurements before installing each product. Where portions of Work are indicated fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying Work.

B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.

C. Review of Contract Documents and Field Conditions: Immediately on discovery of need for clarification of the Contract Documents caused by differing field conditions outside control of Contractor, submit request for information to Contracting Officer in accordance with Section 01 31 00 "Project Management and Coordination."

3.3 INSTALLATION

A. General: Locate Work and components of Work accurately in correct alignment and elevation, as indicated.

1. Make vertical work plumb and make horizontal work level.
2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.

B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.

C. Install products at the time and under conditions for best possible results. Maintain conditions required for product performance until Substantial Completion.

D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.

E. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.

1. Refer to Section 01 57 19.12 “Noise and Acoustic Management” for noise requirements.

F. Templates: Obtain and distribute to parties involved templates for work specified to be factory-prepared and field-installed. Check Shop Drawings of other work to confirm adequate provisions are made for locating and installing products to comply with indicated requirements.

G. Anchors and Fasteners: Provide anchors and fasteners as required to anchor each component securely in place, accurately located and aligned with other portions of Work.

1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Contracting Officer.
2. Allow for building movement, thermal expansion, and contraction.

3. Coordinate installation of anchorages.

H. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for best visual effect. Fit exposed connections together to form hairline joints.

I. Hazardous Materials: Use products, cleaners, and installation materials not considered hazardous.

3.4 PROGRESS CLEANING

A. General: Clean Project site, work areas, and common areas daily. Coordinate progress cleaning for joint-use areas where more than one Installer has worked. Enforce requirements strictly. Dispose of materials lawfully.

1. Comply with requirements in National Fire Protection Association (NFPA) 241 for removal of combustible waste materials and debris.
2. Do not hold materials more than 7 days during normal weather or 3 days if the temperature is expected to rise above 80 degrees Fahrenheit.
3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.

B. Site: Maintain Project site free of waste materials and debris.

C. Work Areas: Clean areas where work is in progress to level of cleanliness necessary for proper execution of Work.

1. Remove liquid spills promptly.
2. Where dust would impair proper execution of Work, broom-clean or vacuum entire work area, as appropriate.
3. Provide progress cleaning that minimizes sources of food, water, and harborage available to pests.

D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials not hazardous to health or property and will not damage exposed surfaces.

1. Utilize non-toxic cleaning materials and methods.

a. Comply with Green Seal Standard (GS) 37 for general purpose cleaning and bathroom cleaning.
b. Use natural cleaning materials where feasible. Natural cleaning materials include:

1) Abrasive Cleaners: Substitute 1/2 lemon dipped in borax.
2) Ammonia: Substitute vinegar, salt and water mixture, or baking soda and water.
3) Disinfectants: Substitute 1/2 cup borax in gallon water.
4) Drain Cleaners: Substitute 1/4 cup baking soda and 1/4 cup vinegar in boiling water.

E. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.

F. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect from damage and deterioration at time of Substantial Completion.

G. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways.

H. Clean and protect construction in progress and adjoining materials already in place during handling and installation. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.

I. Clean and provide maintenance on completed construction as frequently as necessary through remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.

J. Limiting Exposures: Supervise construction operations so that no part of construction completed or in progress, is subject to harmful, dangerous, damaging, or deleterious exposure during construction period.

K. Final Cleaning: At completion of Work, remove remaining waste materials, rubbish, tools, equipment, machinery and surplus materials. Clean exposed surfaces and leave Project clean and ready for occupancy.

1. Provide final cleaning in accordance with ASTM E1971.

3.5 PROTECTION OF INSTALLED CONSTRUCTION

A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.

B. Comply with manufacturer's written instructions for temperature and relative humidity.

3.6 CORRECTION OF THE WORK

A. Repair or remove and replace defective construction. Restore damaged substrates and finishes. Comply with requirements in Section 02 42 97 “Selective Removals and Salvaging.”

1. Repairing includes replacing defective parts, refinishing damaged surfaces, and touching up with matching materials.

B. Restore permanent facilities used during construction to pre-construction condition.

C. Remove and replace damaged surfaces exposed to view if surfaces cannot be repaired without visible evidence of repair. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.

D. Remove and replace chipped, scratched, and broken glass or reflective surfaces.

END OF SECTION 01 73 40

SECTION 01 74 19 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for:

1. Salvaging nonhazardous demolition and construction waste.
2. Recycling nonhazardous demolition and construction waste.
3. Disposing of nonhazardous demolition and construction waste.

1.2 DEFINITIONS

A. Construction Waste: Building and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.

B. Demolition Waste: Building and site improvement materials resulting from demolition or selective demolition operations.

C. Solid Waste: Garbage, debris, sludge, or other discharged material (except hazardous waste) including solid, liquid, semisolid, or contained gaseous materials resulting from domestic, industrial, commercial, mining, or agricultural operations.

D. Debris: Non-hazardous solid waste generated during construction, demolition, or renovation of a structure which exceeds 2.5 inch particle size that is: a manufactured object; plant or animal matter; or natural geologic material (e.g. cobbles and boulders). A mixture of debris and other material such as soil or sludge is also subject to regulation as debris if mixture is comprised primarily of debris by volume, based on visual inspection.

E. Disposal: Removal off-site of demolition and construction waste and subsequent sale, recycling, reuse, or deposit in landfill or incinerator acceptable to authorities having jurisdiction.

F. Environmental Pollution and Damage: Presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances; or degrade utility of environment for aesthetic, cultural, or historical purposes.

G. Garbage: Refuse and scraps resulting from preparation, cooking, dispensing, and consumption of food.

H. Hazardous Materials: Material regulated as a hazardous material in accordance with 49 CFR 173 (Code of Federal Regulations), requires a Material Safety Data Sheet (MSDS) in accordance with 29 CFR 1910.1200, or which during end use, treatment, handling, storage, transportation or disposal meets or has components which meet or have potential to meet the definition of Hazardous Waste in accordance with 40 CFR 261.

I. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.

J. Salvage: Recovery of demolition or construction waste and subsequent sale or reuse in another facility.

1.3 PRECONSTRUCTION MEETING

A. Waste Management Meeting: Conduct separate meeting or cover in Preconstruction Conference and comply with requirements in Section 01 31 00 "Project Management and Coordination." Review methods and procedures related to waste management including:

1. Review and discuss waste management plan including responsibilities of Waste Management Coordinator.
2. Review requirements for documenting quantities of each type of waste and its disposition.
3. Review and finalize procedures for materials separation and verify availability of containers and bins needed to avoid delays.
4. Review procedures for periodic waste collection and transportation to recycling and disposal facilities.
5. Review waste management requirements for each trade.

1.4 PERFORMANCE REQUIREMENTS

A. General: Project shall minimize creation of construction, deconstruction, and demolition waste to protect and restore natural habitat and resources. Minimize factors contributing to waste such as over packaging, improper storage, ordering error, poor planning, breakage, mishandling, and contamination. A Waste Management Plan shall be developed to ensure that existing site and building materials are reused, salvaged, or recycled. Minimize waste disposal in landfills.

B. Salvage /Recycle Requirements: Develop waste management plan resulting in end-of-Project rates for salvage/recycling of 50 percent by weight of total waste generated by the Work. The following waste categories, at a minimum, shall be diverted from a landfill:

1. Land clearing debris (chipped debris can be used on site for mulch or erosion control).
2. Clean dimensional wood, palettes.
3. Plywood, OSB (oriented strand board), and particle board.
4. Concrete (can be ground and used for fill on site).
5. Asphaltic concrete (can be ground and used for fill on site).
6. Cardboard, paper, packaging, newsprint.
7. Metals (from banding, stud trim, piping, rebar, roofing, other trim, steel, iron, galvanized sheet steel, stainless steel, aluminum, copper, zinc, lead, brass, and bronze).
8. Non-hazardous paint and paint cans.
9. Beverage containers: Aluminum, glass, and plastic containers.
10. Insulation.
11. Ceiling grid and tiles.
12. Other mixed construction and demolition waste as appropriate.

C. If waste materials encountered during deconstruction/demolition or construction phase are found to contain lead, asbestos, polychlorinated biphenyls (PCBs), (such as fluorescent lamp ballasts),

or other harmful substances, they are to be handled and removed in accordance with local, state, and federal laws and requirements concerning hazardous waste.

D. Existing items and material to be removed during deconstruction/demolition phase shall be reused in construction phase of the Project. Recycle items that cannot be reused. Items considered for reuse must be in refurbishable condition and must meet quality standards set forth in these specifications. Ensure quality of the item(s) in question will meet or exceed accepted industry or trade standards for first quality commercial grade application. During construction, deconstruction, or demolition Contracting Officer (CO) may designate other objects or materials for reuse.

E. Salvage/Recycle Requirements: Government goal is to salvage and recycle as much nonhazardous demolition and construction waste as possible.

1.5 SUBMITTALS

A. Waste Management Plan: After award of contract and prior to scheduled preconstruction conference, Contractor shall submit a draft Waste Management Plan to Contracting Officer for approval. Submit 3 copies of plan. Revise and resubmit Plan as required by Contracting Officer. Approval of Contractor's Plan will not relieve Contractor of responsibility for compliance with applicable environmental regulations.

B. Progress Documentation: Supplemental to Waste Management Plan, document solid waste disposal, diversion, and cost/revenue analysis and submit completed worksheet on a monthly basis. Use Appendix A - Project Waste Management Plan Worksheet, and report totals to date for column headings. Use Appendix B for solid waste volume to weight conversions.

1. With each Application for payment, submit updated Project Waste Management Plan worksheet for solid waste disposal and diversion.
2. With each Application for Payment, submit manifests, weight tickets, receipts, and invoices specifically identifying the Project and waste material.

C. Waste Reduction Calculations: Before request for Substantial Completion, submit three copies of calculated end-of-Project rates for salvage, recycling, and disposal as a percentage of total waste generated by the Work.

D. Recycling and Processing Facility Records: Indicate receipt and acceptance of recyclable waste by recycling and processing facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.

E. Landfill and Incinerator Disposal Records: Indicate receipt and acceptance of waste by landfills and incinerator facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.

F. Qualification Data: For Waste Management Coordinator.

1.6 CLOSEOUT SUBMITTALS

A. Summary Project Waste Management Plan: Submit a summary of the Project Waste Management Plan worksheet for solid waste disposal and diversion. Submit on form in Appendix A of this Section.

1.7 QUALITY ASSURANCE

A. Waste Management Coordinator Qualifications: Experienced individual or firm, with record of successful waste management coordination of projects with similar requirements.

B. Regulatory Requirements: Comply with hauling and disposal regulations of agencies with jurisdiction.

PART 2 - PRODUCTS

2.1 WASTE MANAGEMENT PLAN

A. General: Develop plan consisting of waste identification and waste reduction work plan. Include separate sections in plan for demolition and construction waste. Indicate quantities by weight or volume but use same units of measure throughout waste management plan.

B. Waste Identification: Indicate anticipated types and quantities of demolition, and construction waste generated by the Work. Include estimated quantities and assumptions for estimates.

C. Waste Reduction Work Plan: List each type of waste and whether it will be salvaged, recycled, or disposed of in landfill or incinerator. Include points of waste generation, total quantity of each type of waste, quantity for each means of recovery, and handling and transportation procedures.

1. Salvaged Materials for Reuse: For materials salvaged and reused in Project, describe methods for preparing salvaged materials before incorporation into the Work.
2. Recycled Materials: Include list of local receivers and processors and type of recycled materials each will accept. Include names, addresses, and telephone numbers.
3. Disposed Materials: Indicate how and where materials will be disposed of. Include name, address, and telephone number of each landfill and incinerator facility.
4. Handling and Transportation Procedures: Include method used for separating recyclable waste including sizes of containers, container labeling, and designated location on Project site where materials separation will be located.

D. Cost/Revenue Analysis: Indicate total cost of waste disposal as if there were no waste management plan and net additional cost or net savings resulting from implementing waste management plan. Include:

1. Landfill tip fees per ton.
2. If diverted, tip fee savings from landfill diversion.
3. Costs of recycling, salvage, or reuse.
4. Revenue from recycling, salvage, or reuse.

5. Total cost or savings from diversion. (Calculate by using tip fee savings and subtracting costs of recycling or adding revenue from recycling.)

PART 3 - EXECUTION

3.1 PLAN IMPLEMENTATION

A. General: Implement waste management plan as approved by Contracting Officer. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during entire duration of Contract.

B. Waste Management Coordinator: Engage waste management coordinator responsible for implementing, monitoring, and reporting status of waste management work plan. Coordinator shall be present at Project site full time for duration of Project. Waster Management Coordinator may be assigned other duties.

C. Establish contacts with local recycling and reuse companies to set up lines of responsibility. Contractor shall be responsible for coordination in terms of identifying materials, pickup schedules, and standard quality for recycled materials.

D. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work occurring at Project site.

1. Distribute waste management plan to everyone concerned within three days of submittal return.
2. Distribute waste management plan to entities when they begin work on-site. Review plan procedures and locations established for salvage, recycling, and disposal.

E. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

F. Separation Facilities:

1. Contractor shall designate and Contracting Officer shall approve in writing specific area(s) to facilitate separation of materials for potential reuse, salvage, recycling, and return.
2. Place waste and recycling bins near each other, and close to point of waste generation but out of traffic pattern.
3. Keep recycling and waste bin areas neat, clean, and clearly marked in order to avoid co-mingling of materials.
4. Protect bins during non-working hours from off-site contamination.
5. Check garbage dumpsters periodically for recyclables being thrown away and undocumented materials that could be recycled.

G. Materials Handling Procedures: Protect material to be recycled from contamination and handle, store, and transport in a manner that meets requirements set by designated facilities for acceptance. Establish defined area for operations of each trade, especially woodcutting so off-cuts are kept in one area and can be sorted by dimension for future reuse.

3.2 SALVAGING DEMOLITION WASTE

A. Salvaged Items for Reuse in the Work:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Store items in secure area until installation.
4. Protect items from damage during transport and storage.
5. Install salvaged items to comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make items functional for use indicated.

B. Salvaged Items for Sale and Donation: Not permitted on Project site.

C. Salvaged Items for Government's Use:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Allow for inspection if necessary.
4. Store items in secure area until delivery to Government.
5. Transport items to storage area off-site designated by Government.
6. Protect items from damage during transport and storage.

3.3 RECYCLING DEMOLITION AND CONSTRUCTION WASTE, GENERAL

A. General: Recycle paper and beverage containers used by on-site workers.

B. Recycling Incentives: Revenues, savings, rebates, tax credits, and other incentives received for recycling waste materials shall accrue to Contractor.

C. Procedures: Separate recyclable waste from other waste materials, trash, and debris. Separate recyclable waste by type at Project site to maximum extent practical.

1. Provide appropriately marked containers or bins for controlling recyclable waste until removed from Project site. Include list of acceptable and unacceptable materials at each container and bin.

    a. Inspect containers and bins for contamination and remove contaminated materials if found.

2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
3. Stockpile materials away from construction area. Do not store within drip line of remaining trees.
4. Store components off ground and protect from weather.
5. Remove recyclable waste off Government property and transport to recycling receiver or processor.

3.4 RECYCLING DEMOLITION WASTE

A. Concrete: Remove reinforcement and other metals from concrete and sort with other metals.

1. Pulverize concrete to maximum 1-1/2 inch size.

B. Masonry: Remove metal reinforcement, anchors, and ties from masonry and sort with other metals.

1. Clean and stack undamaged, whole masonry units on wood pallets.

C. Wood Materials: Sort and stack members according to size, type, and length. Separate lumber, engineered wood products, panel products, and treated wood materials.

D. Metals: Separate metals by type.

1. Remove and dispose of bolts, nuts, washers, and other rough hardware.

3.5 RECYCLING CONSTRUCTION WASTE

A. Packaging:

1. Cardboard and Boxes: Break down packaging into flat sheets. Bundle and store in dry location.
2. Polystyrene Packaging: Separate and bag materials.
3. Pallets: As much as possible, require deliveries using pallets to remove pallets from Project site. For pallets that remain on-site, break down pallets into component wood pieces and comply with requirements for recycling wood.
4. Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.

3.6 DISPOSAL OF WASTE

A. General: Except for items or materials to be salvaged, recycled, or otherwise reused, remove waste materials from Project site and legally dispose in landfill or incinerator acceptable to agencies with jurisdiction.

1. Except as otherwise specified, do not allow waste materials to accumulate on-site.
2. Remove and transport debris in manner preventing spillage on adjacent surfaces and areas.

B. Burning: Do not burn waste materials.

C. Disposal: Transport waste materials off Government property and legally dispose of them.

END OF SECTION 01 74 19

SECTION 01 77 00 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for contract closeout, including:

1. Project Record Drawings.
2. Closeout Submittals.
3. Substantial Completion and Final Inspection.
4. Permit Closure and Transfer.
5. Final Acceptance of the Work.
6. Warranties.

1.2 PROJECT RECORD DRAWINGS

A. Maintain one complete full-size set of contract drawings and one full-size set of vendor-supplied drawings. Clearly mark changes, deletions, and additions using National Park Service (NPS) drafting standards to show actual construction conditions. Show additions in red, deletions in green and special instructions in blue.

B. Keep record drawings current. Make record drawings available to Contracting Officer (CO) for inspection at the time of monthly progress payment requests. If project record drawings are not current, Contracting Officer may retain an appropriate amount of progress payment.

C. Submit complete record drawings on completion of total project. Include shop drawings, sketches, and additional drawings to be included in final set, with clear instructions showing the location of these drawings.

1.3 CLOSEOUT SUBMITTALS

A. A list of closeout requirements has been attached at the end of the Division 01 Specifications for your convenience. The intent is to provide an overall summary of requirements and not a comprehensive list. Terms and conditions of the contract require satisfaction of requirements of individual specification sections regardless of what is shown on the list. Submit the following before requesting final inspection:

1. Specific warranties, guarantees, workmanship bonds, final certifications, and similar documents.
2. NPS required forms for occupancy, Fire Sprinkler/Alarm acceptance, and other similar forms or certificates.
3. Project Record Documents, operation and maintenance manuals, final completion construction digital images recorded on CD-R (compact disc-recordable) or DVD-R (digital video disc-recordable) with index and descriptions, and similar final record information.
4. Environmental Record Documents: As specified in other Sections.

5. Deliver tools, spare parts, extra materials, and similar items to location designated by Contracting Officer. Label with manufacturer's name and model number where applicable.

    a. Special Tools: One set of special tools required to operate, adjust, dismantle, or repair equipment. Special tools are those not normally found in possession of mechanics or maintenance personnel.
6. Terminate and remove temporary facilities, mockups, construction tools, and similar elements from Project site, complete final cleaning requirements, including touchup painting.
7. Touch up and repair and restore marred exposed finishes to eliminate visual defects.
8. Instruct NPS personnel in operation, adjustment, and maintenance of products, equipment, and systems.

1.4 FINAL INSPECTION, SUBSTANTIAL COMPLETION AND ACCEPTANCE PROCEDURES

A. Request final inspection in writing when project or designated portion of project is substantially complete. Contracting Officer will proceed with inspection within 10 days of receipt of written request or will advise Contractor of items that prevent project from being substantially complete.

B. If work is determined substantially complete, following final inspection, Contracting Officer will prepare Punch List and issue a Letter of Substantial Completion.

C. If work is not determined substantially complete following final inspection, Contracting Officer will notify Contractor in writing. Contractor shall request new final inspection after completing work. Re-inspection costs may be charged against Contractor in accordance with Inspection of Construction contract clause.

D. Contractor shall complete Punch List within 30 calendar days, documented weather permitting.

E. If Contractor completes items of work on Punch List and contractually required items, Contracting Officer will issue Letter of final acceptance of work.

F. If Contractor fails to complete work within the time frame, Contracting Officer may correct work with an appropriate reduction in contract price or charge for re-inspection costs in accordance with Inspection of Construction contract clause.

1.5 PERMIT CLOSURE AND TRANSFER

A. When work covered by the permits is complete, create list of tasks required to close or transfer permits to Park. Submit to Contracting Officer for approval.

B. After substantial completion and Punch List completion, permits shall be closed and documented by Agency(ies) with Jurisdiction for the permit.

C. If responsibility for permits is to be transferred to Park, Park shall be informed of permit provisions completed and responsibilities transferring to Park staff.

1.6 WARRANTIES

A. Submittal Time: Submit written warranties on request of Contracting Officer for designated portions of Work where commencement of warranties other than date of Substantial Completion is indicated.

B. Organize warranty documents into an orderly sequence based on table of contents of Project Manual.

1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2 by 11 inch paper.
2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify product or installation. Provide typed description of product or installation, including name of product and name, address, and telephone number of Installer.
3. Identify each binder on front and spine with typed or printed title "WARRANTIES," Project name, and name of Contractor.
4. Warranty Electronic File: Scan warranties and bonds and assemble complete warranty and bond submittal package into a single indexed electronic PDF (portable document format) file with links enabling navigation to each item. Provide bookmarked table of contents at beginning of document.

C. Provide additional copies of each warranty in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

A. See Section 01 73 40 "Execution" for information on cleaning agents.

PART 3 - EXECUTION

3.1 FINAL CLEANING

A. General: Conduct final cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.

B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.

1. Complete following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:

a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.

b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
c. Rake grounds that are neither planted nor paved to smooth, even-textured surface.
d. Remove tools, construction equipment, machinery, and surplus material from Project site.
e. Remove snow and ice to provide safe access to building.
f. Clean exposed exterior and interior hard-surfaced finishes to dirt-free condition, free of stains, films, and foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to original condition.
g. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
h. Sweep concrete floors broom clean in unoccupied spaces.
i. Vacuum carpet and similar soft surfaces, removing debris and excess nap; shampoo, soil or stains remain.
j. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and vision-obscuring materials. Replace chipped or broken glass and transparent materials. Polish mirrors and glass.
k. Remove labels that are not permanent.
l. Touch up, repair, and restore marred, exposed finishes and surfaces. Replace finishes and surfaces that cannot be satisfactorily repaired or restored or that already show evidence of repair or restoration.

    1) Do not paint over "UL" (Underwriters Laboratories) and similar labels, including mechanical and electrical nameplates.

m. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency. Replace burned-out and noticeably dimmed bulbs, and defective or noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.
n. Leave Project clean and ready for occupancy.

C. Pest Control: Engage experienced, licensed exterminator to make a final inspection and rid project of rodents, insects, and other pests. Provide Government with report.

D. Waste Disposal: Comply with requirements of Section 01 74 19 "Construction Waste Management and Disposal."

END OF SECTION 01 77 00

SECTION 01 78 23 - OPERATION AND MAINTENANCE DATA

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including:

1. General manual requirements.
2. Maintenance manuals for care and maintenance of products, materials, and finishes.

1.2 SUBMITTALS

A. Manual: Submit one electronic copy at least 15 days before final inspection. Contracting Officer (CO) will return copy or edit version with comments within 15 days of receipt.

B. Format: Submit operations and maintenance manuals in following format:

1. PDF (portable document format) electronic file. Assemble each manual into composite electronically indexed file. Submit on digital media acceptable to Contracting Officer.

a. Name each indexed document file in composite electronic index with applicable item name. Include a complete electronically linked operation and maintenance directory.
b. Enable inserted reviewer comments on draft submittals.

2. Hard copy manual: In accordance with Part 2 of this Section.

3. Correct or modify each manual to comply with Contracting Officer's comments. Submit 4 copies of each corrected manual within 15 days of receipt of Contracting Officers comments.

PART 2 - PRODUCTS

2.1 MANUALS, GENERAL

A. Organization: Unless otherwise indicated, organize manual into separate sections for each system and subsystem, and separate sections for each piece of equipment not part of a system. Manual shall contain title page, table of contents, and manual contents.

B. Title Page: Enclose title page in transparent plastic sleeve. Include:

1. Project Title.
2. Location.
3. Park.

4. Contract Number.
5. Prime Contractor’s Name and Address.
6. Date of Substantial Completion.
7. Binder Volume Number.

C. Table of Contents: List each product included in manual, identified by product name, indexed to content of the volume, and cross-referenced to Specification Section number in Project Manual.

D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. Assemble instructions for subsystems, equipment, and components of one system into a single binder if needed.

1. Binders: White, commercial quality, hard back, 3-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold 8-1/2 by 11 inch paper; with clear plastic window sleeve on front and spine to hold label describing contents and pockets inside covers to hold folded oversize sheets.

    a. Cover Sheet: Identify binders on front and spine, with project title, location, park, contract number, prime contractor's name and address, date of substantial completion, and binder volume number. Insert cover sheet into clear plastic view pocket on front of binder. Insert sheet into clear plastic view pocket on spine with title "OPERATION AND MAINTENANCE MANUAL," Project title or name, and subject matter of contents. Indicate volume number for multiple-volume sets.

2. Data: Fill binders to no more than 75 percent of capacity. Punch holes shall not obscure any data. When contents of a single tabbed section cover more than one item, provide colored paper sheets to separate the data for each item.

    a. Manufacturers' Data: Provide originals for color or copyrighted data. Black and white data may be originals or clean, good quality reproductions. No copies produced by facsimile transmission and sheets with stamps, such as submittal approval stamps. Include only sheets that apply to items installed; cross out inapplicable data.
    b. Vendor Furnished As-Built Drawings: Maximum 24 inch by 36 inch sheets with minimum character or lettering size of 1/8 inch. Reduced-size reproductions may be provided instead of full-size drawings if reproductions are clear and legible. If reduced-size drawings are used, identify as "REDUCED SIZE" and provide graphic scales, if applicable.
    c. Custom Data: Data supplemented by drawings and schematics necessary to describe systems adequately.
    d. Equipment Data Sheet: Data, using form at end of this section.
    e. Schedules: Schedules reflecting final, as-installed conditions.
    f. Poorly reproduced or illegible data will be rejected.

3. Dividers: Divider sheets with Mylar reinforced edges and pre-printed numbered tabs aligned with numbers and title lines on index sheet. Include typed list of products and major components of equipment included in section on each divider, cross-referenced to Specification Section number and title of Project Manual.
4. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose CDs or flash drives.
5. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.

a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

2.2 OPERATION AND MAINTENANCE MANUALS

A. Maintenance Requirements for Systems and Equipment:

1. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranty and bond information, and equipment data sheets as described below.
2. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual.
3. Manufacturers' Maintenance Documentation: Manufacturers' maintenance documentation including maintenance instructions, drawings and diagrams for maintenance, nomenclature of parts and components, and recommended spare parts for each component part or piece of equipment:
4. Maintenance Procedures: Test and inspection instructions, troubleshooting guide, disassembly instructions, and adjusting instructions, detailing essential maintenance and environmental procedures.
5. Warranties and Bonds: Copies of warranties and bonds and lists of circumstances and conditions that affect validity of warranties or bonds.

2.3 PRODUCT MAINTENANCE MANUAL

A. Content: Organize manual into separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.

B. Source Information: List each product included in manual identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual.

C. Product Information: Include:

1. Product name and model number.
2. Manufacturer's name.
3. Color, pattern, and texture.
4. Material and chemical composition.
5. Reordering information for specially manufactured products.

D. Environmental Requirements:

1. Identify environmentally preferable products incorporated into Project. Include: product model; manufacturer's name, address, phone, and website; and local technical representative.

   a. Verify plastic products to be incorporated into Project are labeled in accordance with ASTM D1972. Where products are not labeled, provide product data indicating polymeric information in Operation and Maintenance Manual.

      1) Type 1: Polyethylene Terephthalate (PET, PETE).
      2) Type 2: High Density Polyethylene (HDPE).
      3) Type 3: Vinyl (Polyvinyl Chloride or PVC).
      4) Type 4: Low Density Polyethylene (LDPE).
      5) Type 5: Polypropylene (PP).
      6) Type 6: Polystyrene (PS).
      7) Type 7: Other. Use of this code indicates that package in question is made with a resin other than the six listed above or is made of more than one resin listed above and used in a multi-layer combination.

   b. Describe maintenance procedures associated with environmentally preferable materials and systems. Provide cleaning recommendations in accordance with ASTM E1971 and approved Integrated Pest Management (IPM) plan.

      1) Include potential environmental impacts of recommended maintenance procedures and materials.
      2) Include potential indoor air quality impacts of recommended maintenance procedures and materials.
      3) Where proposed maintenance procedures incorporate composting of plastics, assess potential effect of each type of plastic to be included in composting process in accordance with ASTM D5509 or ASTM D6002

   c. Material Safety Data Sheets (MSDS): Include MSDSs as specified.

E. Maintenance Procedures: Include manufacturer's written recommendations and inspection procedures, types of cleaning agents, methods of cleaning, schedule for cleaning and maintenance, and repair instructions.

F. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.

G. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that affect validity of warranties or bonds.

PART 3 - EXECUTION

3.1 GENERAL

A. At start of project, begin accumulating operation and maintenance data and initiate index. Install and index data in binders within 30 days after delivery of items. As custom written data and test results are produced, add to operation and maintenance data file.

B. Keep operation and maintenance data current. Make operation and maintenance binders available to Contracting Officer for inspection at time of monthly progress payment requests. If operation and maintenance binders are not current, Contracting Officer may retain an appropriate amount of the progress payment.

3.2 MANUAL PREPARATION

A. Manual Types:

1. Product Maintenance Manual: Assemble complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into Work.
2. Operation and Maintenance Manuals: Assemble complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.

B. Manual Contents: Including:

1. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark sheet to identify product or component incorporated into Work. If data include more than one item in a tabular format, identify each item using appropriate references from Contract Documents. Identify data applicable to Work and delete references to information not applicable.
2. Custom Written Data: For data not in manufacturer's standard literature, provide text, drawings, and schematics specifically applicable to installed systems. Include step-by-step descriptions of operating procedures; identification of individual components and their functions; descriptions of how system components relate to one another and operate together to accomplish a common process or function; and sequence of operation for system control circuits. For seasonally operated systems, provide start-up and shutdown instructions.

C. Comply with Section 01 77 00 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

END OF SECTION 01 78 23

SECTION 02 42 97 – SELECTIVE REMOVALS AND SALVAGING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes historic treatment procedures in the form of special types of selective removals and salvaging work for designated historic spaces, areas, rooms, and surfaces and the following specific work:

1. Removal of indicated portions of building or structure.
2. Salvage of existing items to be reused or recycled.

1.2 DEFINITIONS

A. Existing to Remain: Existing items that are not to be removed or salvaged, except to the degree indicated for performing required Work.

B. Remove: To take down or detach a non-historic item located within a historic space, area, or room, using methods and equipment to prevent damage to historic items and surfaces; disposing of items unless indicated to be salvaged or reinstalled.

C. Retain: To keep existing items that are not to be removed or salvaged.

D. Salvage: To disassemble or detach items from existing construction, using gentle methods and equipment to prevent damage to items and surfaces, and deliver them to Government.

E. Salvage and Reinstall: To detach items from existing construction, in a manner to prevent damage, prepare for reuse, and reinstall where indicated.

1.3 ACTION SUBMITTALS

A. Proposed Protection Measures: Submit report, including Drawings, that indicates the measures proposed for protecting individuals, for environmental protection, for dust control and, for noise control. Indicate proposed locations and construction of barriers.

1.4 INFORMATIONAL SUBMITTALS

A. List of Items Indicated to Be Salvaged: Prepare a list of items indicated on Drawings to be salvaged for Government's use or for reinstallation. Submit 15 days before preconstruction conference.

B. Schedule of Selective Removals and Salvaging Activities: Indicate the following:

1. Detailed sequence of selective removals and salvaging work, with starting and ending dates for each activity. Ensure Government's on-site operations are uninterrupted.
2. Interruption of utility services. Indicate how long utility services will be interrupted.

3. Do not remove debris or salvaged materials through existing building.

C. Pre-removals and Salvaging Photographs or Video: Show existing conditions of adjoining construction, including finish surfaces, that might be misconstrued as damage caused by selective removals and salvaging operations. Submit before Work begins.

1. Refer to Section 01 32 33 "Photo Documentation" for documentation requirements.

D. Inventory of Salvaged Items: After salvaging and removals work is complete, submit a list of items that have been salvaged.

1.5 CLOSEOUT SUBMITTALS

A. Warranties: Documentation indicating that existing warranties are still in effect after completion of selective removals.

1.6 QUALITY ASSURANCE

A. Selective Removals and Salvaging Historic Treatment Program: Prepare a written, detailed description of materials, methods, equipment, and sequence of operations to be used for each type of removal and salvaging work, including protection of surrounding and substrate materials and Project site.

1.7 FIELD CONDITIONS

A. Government will occupy portions of building immediately adjacent to selective removals area. Conduct selective removals so Government's operations will not be disrupted.

B. Conditions existing at time of inspection for bidding purpose will be maintained by Government as far as practical.

C. Notify Contracting Officer of discrepancies between existing conditions and Drawings before proceeding with selective removal and salvaging work.

D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.

1. It is expected that paint coatings contain lead paint. Contractor shall be responsible for compliance with requirements for worker safety regarding lead-based paint protections.

2. If materials suspected of containing hazardous materials are encountered, do not disturb; immediately notify Contracting Officer and. Government will remove hazardous materials under a separate contract.

a. In the case of suspected asbestos, stop work in the area of potential hazard, shut off fans and other air handlers ventilating the area, and rope off area until the questionable material is identified. Reassign workers to continue work in unaffected areas. Resume work in the area of concern after safe working conditions are verified.

E. Historic Areas: Removals and hauling equipment and other materials shall be of sizes that clear surfaces within historic spaces, areas, rooms, and openings, including temporary protection by 12 inches or more.

F. Storage or sale of removed or salvaged items on-site is not permitted unless otherwise indicated.

G. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective removals operations.

1. Maintain fire-protection facilities in service during selective removals operations.

1.8 COORDINATION

A. Arrange selective removals and salvaging schedule so as not to interfere with Government's operations.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective removals. Comply with hauling and disposal regulations of authorities having jurisdiction.

B. Standards: Comply with ASSE A10.6 and NFPA 241.

PART 3 - EXECUTION

3.1 SELECTIVE REMOVALS AND SALVAGING EQUIPMENT

A. Removal Equipment: Use only hand-held tools, except as follows or unless otherwise approved by Contracting Officer on a case-by-case basis:

1. Electric rotary hammers, hand-held pneumatic chisels, and Arbortech Allsaws are allowed subject to Contracting Officer's approval.
2. Large air hammers are not permitted.

B. Salvaging Equipment: Use manual, hand-held tools, except as follows or otherwise approved by Contracting Officer on a case-by-case basis:

1. Hand-held power tools and cutting torches are permitted only as submitted in the historic treatment program. They must be adjustable so as to penetrate or cut only the thickness of material being removed.
2. Pry bars more than 18 inches long and hammers weighing more than 2 pounds are not permitted for salvaging work.

3.2 EXAMINATION

A. Preparation for Removal and Salvaging: Examine construction to be removed or salvaged to determine best methods to safely and effectively perform removal and salvaging work. Examine adjacent work to determine what protective measures are necessary. Make explorations, probes, and inquiries as necessary to determine condition of construction to be removed or salvaged and location of utilities and services to remain that may be hidden by construction that is to be removed or salvaged.

   1. Inventory and record the condition of items to be removed or salvaged for reinstallation. Enter this information on the submittal of inventory of salvaged items.

B. Survey of Existing Conditions: Record existing conditions by use of preconstruction photographs and preconstruction video recordings.

   1. Comply with requirements specified in Section 01 32 33 “Photo Documentation.”
   2. Inventory and record the condition of items to be removed and salvaged. Provide photographs or video of conditions that might be misconstrued as damage caused by removals or salvage operations.
   3. Before selective removals and salvaging of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.

C. Perform surveys as the Work progresses to detect hazards resulting from selective removals and salvaging procedures.

3.3 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.

3.4 PROTECTION

A. Refer to Section 01 50 00 “Temporary Facilities and Controls” for temporary protection requirements.

B. Remove temporary barricades and protections where hazards no longer exist.

3.5 SELECTIVE REMOVALS AND SALVAGING, GENERAL

A. General: Have selective removal and salvaging work performed by a qualified selective removals and salvaging specialist. Ensure that selective removals and salvaging specialist's field supervisors are present when selective removals and salvaging work begins and during its progress.

B. Comply with requirements in Section 01 35 91 “Historic Preservation Treatment Procedures” for identifying and storing historic items.

C. Perform work according to the historic treatment program and approved mockup(s).

1. Perform selective removals and salvaging to the limits indicated.
2. Provide supports or reinforcement for existing construction that becomes temporarily weakened by selective removals and salvaging work, until the Project Work is completed unless otherwise indicated.
3. Proceed with selective removals systematically, from higher to lower level. Complete selective removals operations above each floor or tier before disturbing supporting members on the next lower level.
4. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
5. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
6. Maintain adequate ventilation when using cutting torches.
7. Do not drill or cut columns, beams, joists, girders, structural slabs, or other structural supporting elements, without having Contractor's professional engineer's written approval for each location before such work is begun.
8. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
9. Locate selective removals equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
10. Dispose of removed items promptly off-site unless indicated to be salvaged or reinstalled. Comply with requirements in Section 01 74 19 “Construction Waste Management and Disposal.”

D. Unacceptable Equipment: Keep equipment that is not permitted for selective removals and salvaging work away from the vicinity where such work is being performed.

E. Removing and Salvaging Items on or Near Historic Surfaces:

1. Use only salvaging equipment and procedures within 12 inches of historic surface. Do not use pry bars. Protect historic surface from contact with or damage by tools.
2. Unfasten items in the opposite order from which they were installed.
3. Support each item as it becomes loosened to prevent stress and damage to the historic surface.
4. Remove anchorages.

F. Salvaged Items:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Store items in a secure area until delivery to Government.
4. Transport items to Government’s storage area off-site.
5. Protect items from damage during transport and storage.

G. Salvaged and Reinstalled Items:

1. Clean and repair items to functional condition adequate for intended reuse.
2. Pack or crate items after cleaning and repairing. Identify contents of containers.
3. Store items in a secure area until delivery to Government.
4. Transport items to Government’s storage area off-site.

5. Protect items from damage during transport and storage.
6. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

H. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective removals. When permitted in writing by Contracting Officer, items may be salvaged and moved to a protected storage location during selective removals and cleaned and reinstalled in their original locations after selective removals operations are complete.

3.6 SELECTIVE REMOVALS FOR SPECIFIC MATERIALS

A. Anchorages:

1. Remove anchorages as indicated on Drawings.
2. In non-historic surfaces, patch holes created by anchorage removal according to the requirements for new work.
3. In historic surfaces, patch or repair holes created by anchorage removal according to Section that is specific to the historic surface being patched.

B. Roofing: Remove no more existing roofing than what can be covered in one day by new roofing and so that building interior remains watertight and weathertight.

3.7 DISPOSAL OF REMOVED MATERIALS

A. Remove demolition waste materials from Project site and recycle or dispose of them according to Section 01 74 19 "Construction Waste Management and Disposal."

1. Do not allow removed materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
3. Coordinate first subparagraph below with use of elevators, stairs, or building entries permitted by building manager.
4. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
5. Comply with requirements specified in Section 01 74 19 "Construction Waste Management and Disposal."

B. Burning: Do not burn removed materials.

3.8 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective removals and salvaging operations. Return adjacent areas to condition existing before selective removals and salvaging operations began.

END OF SECTION 02 42 97

SECTION 04 03 43 - HISTORIC STONE MASONRY REPOINTING

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes historic treatment work consisting of repointing stone masonry joints with mortar or sealant.

B. Related Requirements:

1. Section 01 35 91 "Historic Preservation Treatment Procedures" for general historic treatment requirements.

2. Section 07 92 00 “Joint Sealants” for joint sealants used in repointing applications.

1.2 DEFINITIONS

A. Low-Pressure Spray:

1. Pressure: 100 to 400 psi
2. Flow Rate: 4 to 6 gpm.

B. Rift: The most pronounced direction of splitting or cleavage of a stone. Rift may be obscure in igneous rocks such as granite. Often it is obvious, as with bedding planes in many sedimentary stones.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference on historic masonry repair and repointing at Project site.

1. Review methods and procedures related to repointing historic stone masonry including, but not limited to, the following:

a. Verify historic treatment specialist's personnel, equipment, and facilities needed to make progress and avoid delays.
b. Materials, material application, sequencing, tolerances, and required clearances.
c. Quality-control program.
d. Stone historic treatment program.
e. Coordination with building and park occupants.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes.
2. Include recommendations for product application and use.
3. Include test data substantiating that products comply with requirements.

B. Shop Drawings:

1. Include plans, elevations, sections, and locations of repointing work on the structure.
2. Show provisions for expansion joints or other sealant joints.
3. Show locations of scaffolding and points of scaffolding in contact with masonry. Include details of each point of contact or anchorage.

    a. Refer to Section 01 50 00 “Temporary Facilities and Controls”.

C. Samples: For the following:

1. Pointing Mortar: Submit three Samples of mortar for pointing in the form of 3 inches in diameter by 1/2 inch thick rounds. Submit the following:

    a. Samples of different mixes of sands and cements that produce a mortar matching existing, cleaned mortar designated as Design Reference Sample when cured and dry.
    b. Include with each Sample a list of ingredients. Identify sources, both supplier and quarry, of each type of sand and brand names of cementitious material.

        1) Submit with precise measurements on ingredients, proportions, gradations, and sources of sands from which each Sample was made.

2. Each type of sand used for pointing mortar; minimum 8 oz. of each in plastic screw-top jars.

    a. For blended sands, provide Samples of each component and blend. Identify blend ratio.
    b. Identify sources, both supplier and quarry, of each type of sand.

3. Sealant materials.

D. Qualification Data: For historic treatment specialist. Include photos and contact information for Owner and Architect.

E. Pre-construction testing reports..

F. Quality-control plan.

G. Stone historic treatment program.

1.5 QUALITY ASSURANCE

A. Historic Treatment Specialist Qualifications: A qualified historic stone masonry repointing specialist. Work must be performed by a firm having not less than five (5) years' successful experience in comparable masonry historic repair work on at least three (3) buildings listed or eligible to be listed in the National Register of Historic Places under the review of federal and/or state historic preservation agencies in the last five (5) years, and employing personnel skilled in the restoration processes and operations indicated.

1. Worker Qualification: Skilled workers who are familiar and experienced in stone masonry repair of types they will be performing.

a. All workers shall have an International Masonry Institute Historic Masonry Preservation Certificate (or equal) and provide evidence of prior certification, or a statement of the firm's commitment to enroll in and initiate a training program relevant to the scope of work prior to the start of the project.
b. Masonry foreman must have no less than 10 years' experience with historic masonry restoration procedures, and be available on site at all times for duration of work.

2. In acceptance or rejection of historic treatment work, no allowance will be made for lack of skill on the part of the workers.
3. Experience installing standard unit masonry or new stone masonry is insufficient experience for stone historic treatment work.

B. Quality-Control Plan: Prepare a written quality-control plan for this Project to systematically demonstrate the ability of personnel to properly follow methods and use materials and tools without damaging masonry. Include provisions for supervising worker performance and preventing damage.

C. Preconstruction Testing: Engage a qualified testing agency to preform preconstruction testing on mortar as follows:

1. Existing mortar: Test according to ASTM C1324, modified as agreed by testing service and Director's Representative for Project requirements, to determine proportional composition of original ingredients, sizes and colors of aggregates, and approximate strength. Use x-ray diffraction, infrared spectroscopy, and differential thermal analysis to supplement microscopical methods. Carefully remove existing mortar for testing from within joints at six locations designated by Constracting Officer.

D. Stone Historic Treatment Program: Prepare a written, detailed description of materials, methods, equipment, and sequence of operations to be used for each phase of the historic treatment work, including protection of surrounding materials and Project site.

1. Historic Treatment Program should include, but not be limited to, descriptions for methods for the following:

a. Removing plant growth.
b. Inspecting for open mortar joints and permanently or temporarily pointing them before cleaning to prevent the intrusion of water and other cleaning materials into the wall.
c. Raking out mortar from joints surrounding stone to be replaced and from joints adjacent to stone repairs along joints.
d. Raking out mortar from joints to be repointed.
e. Pointing mortar and applying sealant joints.
f. Keeping pointing mortar damp during curing period.
g. After repairs and repointing have been completed and cured, performing a final cleaning to remove residues from this work.
h. If materials and methods other than those indicated are proposed for any phase of historic treatment work, add to the quality-control plan a written description of such materials and methods, including evidence of successful use on comparable projects, and demonstrations to show their effectiveness for this Project.

E. Mockups: Prepare mockups of historic treatment on existing surfaces to demonstrate aesthetic effects and to set quality standards for materials and execution.

1. Repointing: Rake out joints in two separate areas as indicated for each type of repointing required, and repoint one of the areas.
2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Contracting Officer specifically approves such deviations in writing.

3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver packaged materials to Project site in manufacturer's original and unopened containers, labeled with manufacturer's name and type of products.

B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

C. Store hydrated lime in manufacturer's original and unopened containers. Discard lime if containers have been damaged or have been opened for more than two days.

D. Store sand where grading and other required characteristics can be maintained and contamination avoided.

1.7 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit repointing work to be performed according to product manufacturers' written instructions and specified requirements.

B. Temperature Limits: Repoint mortar joints only when air temperature is between 40 and 90 deg F and is predicted to remain so for at least seven days after completion of the Work unless otherwise indicated.

C. Cold-Weather Requirements: Comply with the following procedures for mortar-joint pointing unless otherwise indicated:

1. When air temperature is below 40 deg F, heat mortar ingredients and existing stone to produce temperatures between 40 and 90 deg F.
2. When mean daily air temperature is below 40 deg F, provide enclosure and heat to maintain temperatures above 40 deg F within the enclosure for seven days after pointing. Heat is to be evenly distributed within enclosure, with no “hot spots.”

D. Hot-Weather Requirements: Protect mortar-joint pointing when temperature and humidity conditions produce excessive evaporation of water from mortar materials. Provide artificial shade and wind breaks, and use cooled materials as required to minimize evaporation. Do not apply mortar to substrates with temperatures of 90 deg F and above unless otherwise indicated.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Source Limitations: Obtain each type of material for repointing historic masonry (cement, sand, etc.) from single source with resources to provide materials of consistent quality in appearance and physical properties.

2.2 MORTAR MATERIALS

A. Portland Cement: ASTM C150/C150M, Type I or Type II; white where required for color matching of mortar.

1. Provide cement containing not more than 0.60 percent total alkali when tested according to ASTM C114.

B. Hydrated Lime: ASTM C207, Type S.

C. Mortar Sand: ASTM C144 unless otherwise indicated.

1. Match size, texture, and gradation of existing mortar sand as closely as possible. Blend several sands if necessary to achieve suitable match.

2. Color: Natural sand or ground marble, granite, or other sound stone of color necessary to produce required mortar color.

3. Provide sand with rounded edges.

D. Mortar Pigments: Not permitted.

E. Pre-blended, Dry Mortar Mix: Dry mortar ingredients in the form of a pre-blended mix. Measure quantities by weight to ensure accurate proportions, and thoroughly blend ingredients before delivering to Project site.

F. Water: ASTM C270, potable.

2.3 ACCESSORY MATERIALS

A. Sealant Materials:

1. Sealant manufacturer's standard elastomeric sealant(s) of base polymer and characteristics indicated below and according to applicable requirements in Section 07 92 00 "Joint Sealants."

a. Type: Double-component, nonsag urethane sealant.

2. Colors: Provide colors of exposed sealants to match colors of mortar adjoining installed sealant unless otherwise indicated.

B. Joint-Sealant Backing:

1. Cylindrical Sealant Backings: ASTM C1330, Type C (closed-cell material with a surface skin) or Type B (bicellular material with a surface skin), and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
2. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended in writing by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint where such adhesion would result in sealant failure. Provide self-adhesive tape where applicable.

C. Masking Tape: Nonstaining, nonabsorbent material; compatible with mortar, joint primers, sealants, and surfaces adjacent to joints; and that easily comes off entirely, including adhesive.

D. Nonacidic Liquid Cleaner: Manufacturer's standard, dilutable, solvent-free cleaner designed to clean soiled stone, tile, or masonry.

1. Basis-of-Design Product: Subject to compliance with requirements, provide PROSOCO, Inc; EnviroKlean 2010 All-Surface Cleaner, or comparable products by the following:

a. Cathedral Stone Products, Inc.
b. Diedrich Technologies, Inc.

E. Water: Clean, potable.

F. Other Products: Select materials and methods of use based on the following, subject to approval of a mockup:

1. Previous effectiveness in performing work involved.
2. Minimal possibility of damaging exposed surfaces.
3. Consistency of each application.
4. Uniformity of the resulting overall appearance.
5. Do not use products or tools that could do the following:

a. Remove, alter, or harm the present condition or future preservation of existing surfaces, including surrounding surfaces not in contract.
b. Leave residue on surfaces.

2.4 MORTAR MIXES

A. Mortar Measurement and Mixing: Measure cementitious materials and sand in a dry condition by volume or equivalent weight. Do not measure by shovel; use known measure. Mix materials in a clean, mechanical batch mixer.

B. Mortar: Produce mortar of color required by using specified ingredients. Do not alter specified proportions without Contracting Officer's approval.

C. Do not use admixtures in mortar.

D. Mortar Mixes: Mix mortar materials in the following proportions:

1. Mortar by Property: ASTM C270, Property Specification, Type N unless otherwise indicated; with cementitious material limited to portland cement, lime, and sand.

PART 3 - EXECUTION

3.1 PROTECTION

A. Prevent mortar from staining face of surrounding stone and other surfaces.

1. Cover sills, ledges, and other projecting items to protect them from mortar droppings.
2. Keep wall area wet below rebuilding and pointing work to discourage mortar from adhering.
3. Immediately remove mortar splatters in contact with exposed stone and other surfaces.

B. Block or otherwise protect scuppers in upper gutter from entry of mortar or other debris.

1. Provide temporary rain drainage during work to direct water away from building.

3.2 STONE REPOINTING, GENERAL

A. Appearance Standard: Repointed surfaces are to have a uniform appearance as viewed from 10 feet away by Contracting Officer.

3.3 REPOINTING

A. Rake out and repoint joints to the following extent:

1. All joints in areas indicated.
2. Joints indicated as sealant-filled joints.

B. Do not rake out and repoint joints where not indicated.

C. Rake out joints as follows, according to procedures demonstrated in approved mockup:

1. Remove mortar from joints to depth of 2-1/2 times the joint width, or a minimum or 1-1/4”. Do not remove unsound mortar more than 2 inches deep; consult Contracting Officer for direction.

2. Remove mortar from stone surfaces within raked-out joints to provide reveals with square backs and to expose stone for contact with pointing mortar. Brush, vacuum, or flush joints to remove dirt and loose debris.
3. Do not spall edges of stone units or widen joints. Replace or patch damaged stone units as directed by Contracting Officer.

a. Cut out mortar by hand with chisel and resilient mallet. Do not use power-operated grinders without Contracting Officer’s written approval based on approved quality-control plan.

b. If power tool use is approved, cut out center of mortar bed joints using Arbortech Allsaw or equivalent tool with diamond-impregnated metal blades. Remove remaining mortar in bed joints and mortar in head joints by hand with chisel and resilient mallet. Strictly adhere to approved quality-control plan.

D. Notify Contracting Officer of unforeseen detrimental conditions, including voids in mortar joints, cracks, loose stone, rotted wood, rusted metal, and other deteriorated items.

E. Pointing with Mortar:

1. Rinse joint surfaces with water to remove dust and mortar particles. Time rinsing application so, at time of pointing, joint surfaces are damp but free of standing water. If rinse water dries, dampen joint surfaces before pointing.
2. Apply pointing mortar first to areas where existing mortar was removed to depths greater than surrounding areas. Apply in layers not greater than 3/8 inch until a uniform depth is formed. Fully compact each layer thoroughly and allow it to become thumbprint hard before applying next layer.
3. After deep areas have been filled to same depth as remaining joints, point joints by placing mortar in layers not greater than 3/8 inch. Fully compact each layer and allow it to become thumbprint hard before applying next layer. Where existing stone has worn or rounded edges, slightly recess finished mortar surface below face of stone to avoid widened joint faces. Take care not to spread mortar beyond joint edges onto exposed stone surfaces or to featheredge the mortar.
4. When mortar is thumbprint hard, tool joints to match original appearance of joints as demonstrated in approved mockup. Remove excess mortar from edge of joint by brushing.

5. Cure mortar by maintaining in thoroughly damp condition for at least 72 consecutive hours, including weekends and holidays.

    a. Acceptable curing methods include covering with wet burlap and plastic sheeting, periodic hand misting, and periodic mist spraying using system of pipes, mist heads, and timers.
    b. Adjust curing methods to ensure that pointing mortar is damp throughout its depth without eroding surface mortar.

6. Hairline cracking within the mortar or mortar separation at edge of a joint is unacceptable. Remove mortar and repoint.

F. Pointing with Sealant: Comply with Section 07 92 00 "Joint Sealants" and as follows:

1. After raking out, keep joints dry and free of mortar and debris.

2. Clean and prepare joint surfaces. Prime joint surfaces unless sealant manufacturer recommends against priming. Do not allow primer to spill or migrate onto adjoining surfaces.

3. Fill sealant joints with specified joint sealant.

    a. Install cylindrical sealant backing beneath the sealant. Where space is insufficient for cylindrical sealant backing, install bond-breaker tape.
    b. Install sealant using only proven installation techniques that ensure that sealant is deposited in a uniform, continuous ribbon, without gaps or air pockets, and with complete wetting of the joint bond surfaces equally on both sides. Fill joint flush with surrounding stonework and matching the contour of adjoining mortar joints.

c. Install sealant as recommended in writing by sealant manufacturer but within the following general limitations, measured at the center (thin) section of the bead:

1) Fill joints to a depth equal to joint width, but not more than 1/2 inch deep or less than 1/4 inch deep.

d. Tool sealant to form smooth, uniform beads, slightly concave. Remove excess sealant from surfaces adjacent to joint.

e. Do not allow sealant to overflow or spill onto adjoining surfaces, or to migrate into the voids of adjoining surfaces, particularly rough textures. Remove excess and spillage of sealant promptly as the work progresses. Clean adjoining surfaces by the means necessary to eliminate evidence of spillage, without damage to adjoining surfaces or finishes, as demonstrated in an approved mockup.

3.4 FINAL CLEANING

A. After mortar has fully hardened, thoroughly chemically clean exposed stone surfaces to remove excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water applied by low-pressure spray.

1. Do not use metal scrapers or brushes.
2. Do not use acidic or alkaline cleaners.

B. Rinse adjacent non-stone surfaces. Use potable water and soft brushes or cloths.

C. Rinse mortar and debris from roof; remove debris from gutters and downspouts. Rinse off roof and flush gutters and downspouts.

D. Re-establish roof drainage, confirming that there are no blockages or obstructions in scuppers or other drains. Snake or jet as required to remove any obstructions.

END OF SECTION 04 03 43

SECTION 06 10 53 - MISCELLANEOUS ROUGH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Framing with dimension lumber.
2. Wood blocking, cants, and nailers.
3. Plywood panels

1.2 DEFINITIONS

A. Boards or Strips: Lumber of less than 2 inches nominal size in least dimension.

B. Dimension Lumber: Lumber of 2 inches nominal or greater size but less than 5 inches nominal size in least dimension.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used and net amount of preservative retained.
2. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.

1.4 DELIVERY, STORAGE, AND HANDLING

A. Stack lumber flat with spacers beneath and between each bundle to provide air circulation. Protect lumber from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

A. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, provide lumber that complies with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Provide lumber graded by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.

1. Factory mark each piece of lumber with grade stamp of grading agency.

2. Dress lumber, S4S, unless otherwise indicated.

B. Maximum Moisture Content of Lumber: 19 percent for 2-inch nominal thickness or less; no limit for more than 2-inch nominal thickness unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED MATERIALS

A. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC4a.

1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium.

B. Kiln-dry lumber after treatment to a maximum moisture content of 19 percent. Do not use material that is warped or does not comply with requirements for untreated material.

C. Mark lumber with treatment quality mark of an inspection agency approved by the ALSC Board of Review.

D. Application: Treat items indicated on Drawings, and the following:

1. Wood cants, nailers, curbs, equipment support bases, blocking, stripping, and similar members in connection with roofing, flashing, vapor barriers, and waterproofing.
2. Lumber used in conjunction with construction fencing.

a. Refer to Section 01 50 00 “Temporary Facilities and Controls” for fencing requirements.

2.3 MISCELLANEOUS LUMBER

A. General: Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:

1. Blocking.
2. Nailers.
3. Rooftop equipment bases and support curbs.
4. Cants.
5. Furring.
6. Grounds.
7. Utility shelving.

B. Dimension Lumber Items: Construction or No. 2 grade lumber of any species.

C. For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to eliminate defects that will interfere with its attachment and purpose.

D. For blocking and nailers used for attachment of other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.

2.4 PLYWOOD PANELS

A. Panels: Plywood, DOC PS 1, Exterior, C-C Plugged, in thickness indicated or, if not indicated, not less than 3/4-inch nominal thickness.

2.5 FASTENERS

A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.

1. Provide fasteners of Type 304 stainless steel.

B. Nails, Brads, and Staples: ASTM F1667.

C. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.

2.6 MISCELLANEOUS MATERIALS

A. Flexible Flashing: Composite, self-adhesive, flashing product consisting of a pliable, butyl rubber or rubberized-asphalt compound, bonded to a high-density polyethylene film, aluminum foil, or spunbonded polyolefin to produce an overall thickness of not less than 0.025 inch.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

A. Set carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit carpentry accurately to other construction. Locate furring, nailers, blocking, grounds, and similar supports to comply with requirements for attaching other construction.

B. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.

C. Sort and select lumber so that natural characteristics do not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.

D. Comply with AWPA M4 for applying field treatment to cut surfaces of preservative-treated lumber.

E. Securely attach carpentry work to substrate by anchoring and fastening as indicated, complying with the following:

1. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.

F. Use stainless steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish

materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

3.2 INSTALLATION OF WOOD BLOCKING AND NAILERS

A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.

B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwise indicated.

END OF SECTION 06 10 53

SECTION 07 01 50.19 - PREPARATION FOR REROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Full tear-off of roof system at areas indicated on Drawings.
2. Removal of flashings and counterflashings.
3. Temporary roofing.

B. Related Requirements:

1. Section 01 10 00 "Summary" for use of premises and for phasing requirements.
2. Section 01 50 00 "Temporary Facilities and Controls" for temporary construction and environmental-protection measures for reroofing preparation.
3. Section 02 42 97 “Selective Removals and Salvaging” for protection of existing building fabric during tear-off.

1.2 DEFINITIONS

A. EPS: Molded (expanded) polystyrene.

B. Full Roof Tear-off: Removal of existing roofing system down to existing roof deck.

C. OSB: Oriented strand board.

D. Partial Roof Tear-off: Removal of selected components and accessories from existing roofing system.

E. Roofing Terminology: Definitions in ASTM D 1079 and glossary of NRCA's "The NRCA Roofing Manual: Membrane Roof Systems" apply to work of this Section.

F. Roof Re-Cover Preparation: Existing roofing system is to remain and be prepared for new roof installed over it.

1.3 PREINSTALLATION MEETINGS

A. Preliminary Roofing Conference: Before starting removal Work, conduct conference at Project site.

1. Meet with Contracting Officer, testing and inspecting agency representative, roofing Installer, and installers whose work interfaces with or affects roofing, including installers of roof accessories and roof-mounted equipment.
2. Review methods and procedures related to roofing tear-off, including, but not limited to, the following:

a. Reroofing preparation, including roofing system manufacturer's written instructions.
b. Temporary protection requirements for existing roofing system components that are to remain.
c. Existing roof drains and roof drainage during each stage of reroofing, and roof-drain plugging and plug removal.
d. Construction schedule and availability of materials, Installer's personnel, equipment, and facilities needed to avoid delays.
e. Existing roof deck conditions requiring Contracting Officer notification.
f. Existing roof deck removal procedures and Government notifications.
g. Condition and acceptance of existing roof deck and base flashing substrate for reuse.
h. Structural loading limitations of roof deck during reroofing.
i. Base flashings, special roofing details, drainage, penetrations, equipment curbs, and condition of other construction that affect reroofing.
j. Shutdown of fire-suppression, -protection, and -alarm and -detection systems.
k. Governing regulations and requirements for insurance and certificates if applicable.
l. Existing conditions that may require Contracting Officer notification before proceeding.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Temporary Roofing Submittal: Product data and description of temporary roofing system.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Field Test Reports:

1. Fastener pull-out test report.

C. Photographs or Videotape: Show existing conditions of adjoining construction and site improvements, including exterior and interior finish surfaces, that might be misconstrued as having been damaged by reroofing operations. Submit before Work begins.

1. Refer to Section 01 32 33 “Photo Documentation” for requirements.

D. Landfill Records: Indicate receipt and acceptance of demolished roofing materials and hazardous wastes, such as asbestos-containing materials, by a landfill facility licensed to accept them.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: Approved by manufacturer of roofing system.

B. Regulatory Requirements:

1. Comply with governing EPA notification regulations before beginning roofing removal.
2. Comply with hauling and disposal regulations of authorities having jurisdiction.

1.7 FIELD CONDITIONS

A. Existing Roofing System: EPDM roofing.

B. Government will occupy portions of building immediately below reroofing area.

1. Conduct reroofing so Government's operations are not disrupted.
2. Provide Contracting Officer with not less than 72 hours' written notice of activities that may affect park's operations.
3. Coordinate work activities daily with Contracting Officer so the Government has adequate advance notice to place protective dust and water-leakage covers over sensitive equipment and furnishings, shut down HVAC and fire-alarm or -detection equipment if needed, and evacuate occupants from below work area.

C. Protect building to be reroofed, adjacent buildings, walkways, site improvements, exterior plantings, and landscaping from damage or soiling from reroofing operations.

D. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities.

E. Conditions existing at time of inspection for bidding will be maintained by the Government as far as practical.

F. Weather Limitations: Proceed with reroofing preparation only when existing and forecasted weather conditions permit Work to proceed without water entering existing roofing system or building.

1. Remove only as much roofing in one day as can be made watertight in the same day.

G. Hazardous Materials: It is not expected that hazardous materials, such as asbestos-containing materials, will be encountered in the Work.

1. If materials suspected of containing hazardous materials are encountered, do not disturb; immediately notify Contracting Officer.

a. Hazardous materials will be removed by Government under a separate contract.

PART 2 - PRODUCTS

2.1 TEMPORARY PROTECTION MATERIALS

A. EPS Insulation: ASTM C 578.

B. Plywood: DOC PS 1, Grade CD, Exposure 1.

C. OSB: DOC PS 2, Exposure 1.

2.2 TEMPORARY ROOFING MATERIALS

A. Design and selection of materials for temporary roofing are Contractor's responsibilities.

2.3 AUXILIARY REROOFING MATERIALS

A. General: Use auxiliary reroofing preparation materials recommended by roofing system manufacturer for intended use and compatible with components of new roofing system.

PART 3 - EXECUTION

3.1 PREPARATION

A. Protection of In-Place Conditions:

1. Protect existing roofing elements indicated to remain.

B. Seal or isolate windows that may be exposed to airborne substances created in removal of existing materials.

C. Shut off rooftop utilities and service piping before beginning the Work.

D. Test existing roof drains to verify that they are not blocked or restricted.

1. Immediately notify Contracting Officer of any blockages or restrictions.

E. Coordinate with Contracting Officer to shut down air-intake equipment in the vicinity of the Work.

1. Cover air-intake louvers before proceeding with reroofing work that could affect indoor air quality or activate smoke detectors in the ductwork.

F. During removal operations, have sufficient and suitable materials on-site to facilitate rapid installation of temporary protection in the event of unexpected rain.

G. Maintain roof drains in functioning condition to ensure roof drainage at end of each workday.

1. Prevent debris from entering or blocking roof drains and conductors.

a. Use roof-drain plugs specifically designed for this purpose.
b. Remove roof-drain plugs at end of each workday, when no work is taking place, or when rain is forecast.

2. If roof drains are temporarily blocked or unserviceable due to roofing system removal or partial installation of new roofing system, provide alternative drainage method to remove water and eliminate ponding.

a. Do not permit water to enter into or under existing roofing system components that are to remain.

3.2 ROOF TEAR-OFF

A. Notify Contracting Officer each day of extent of roof tear-off proposed for that day.

B. Lower removed roofing materials to ground and onto lower roof levels, using dust-tight chutes or other acceptable means of removing materials from roof areas.

C. Remove aggregate ballast from roofing. Store aggregate ballast for reuse in manner not to exceed structural loading limitations of roof deck.

D. Full Roof Tear-off: Where indicated on Drawings, remove existing roofing and other roofing system components down to the existing roof deck.

1. Remove roof insulation.
2. Remove base flashings and counter flashings.
3. Remove perimeter edge flashing and gravel stops.
4. Remove flashings at pipes, curbs, mechanical equipment, and other penetrations.
5. Remove roof drains indicated on Drawings to be removed.
6. Remove wood blocking, curbs, and nailers.

7. Remove fasteners from deck.

3.3 DECK PREPARATION

A. Inspect deck after tear-off of roofing system.

B. If deck surface is unsuitable for receiving new roofing or if structural integrity of deck is suspect, immediately notify Contracting Officer.

1. Do not proceed with installation until directed by Contracting Officer.

3.4 TEMPORARY ROOFING

A. Install approved temporary roofing over area to be reroofed.

B. Remove temporary roofing before installing new roofing.

3.5 BASE FLASHING REMOVAL

A. Remove existing base flashings.

1. Clean substrates of contaminants, such as asphalt, sheet materials, dirt, and debris.

B. Do not damage metal counterflashings that are to remain.

1. Replace metal counterflashings damaged during removal with counterflashings of same metal, weight or thickness, and finish as existing.

C. Inspect parapet sheathing, wood blocking, curbs, and nailers for deterioration and damage.

1. If parapet sheathing, wood blocking, curbs, or nailers have deteriorated, immediately notify Contracting Officer.

3.6 FASTENER PULL-OUT TESTING

A. Perform fastener pull-out tests according to SPRI FX-1 and submit test report to Contracting Officer and roofing manufacturer before installing new roofing system.

1. Obtain roofing manufacturer's approval to proceed with specified fastening pattern.

a. Roofing manufacturer may furnish revised fastening pattern commensurate with pull-out test results.

3.7 DISPOSAL

A. Collect demolished materials and place in containers.

1. Promptly dispose of demolished materials.
2. Do not allow demolished materials to accumulate on-site.
3. Storage or sale of demolished items or materials on-site is not permitted.

B. Transport and legally dispose of demolished materials off Government property.

END OF SECTION 07 01 50.19

SECTION 07 14 16 - COLD FLUID-APPLIED WATERPROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes the following where indicated on drawings and in conjunction with EPDM roof installation materials and details:

1. PUMA waterproofing.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Include construction details, material descriptions, and tested physical and performance properties of waterproofing.
2. Include manufacturer's written instructions for evaluating, preparing, and treating substrate.

B. Shop Drawings:

1. Show locations and extent of waterproofing.
2. Include details for substrate joints and cracks, sheet flashings, penetrations, inside and outside corners, tie-ins with adjoining waterproofing, and other termination conditions.

C. Samples: For each exposed product and for each color and texture specified, including the following products:

1. Flashing sheet, 8 by 8 inches.
2. Membrane-reinforcing fabric, 8 by 8 inches.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Field quality-control reports.

C. Sample Warranties: For special warranties.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by waterproofing manufacturer.

1.5 FIELD CONDITIONS

A. Environmental Limitations: Apply waterproofing within the range of ambient and substrate temperatures recommended in writing by waterproofing manufacturer.

1. Do not apply waterproofing to a damp or wet substrate, when relative humidity exceeds 85 percent, or when temperatures are less than 5 deg F above dew point.
2. Do not apply waterproofing in snow, rain, fog or mist, or when such weather conditions are imminent during application and curing period.

B. Maintain adequate ventilation during application and curing of waterproofing materials.

1.6 WARRANTY

A. Manufacturer's Special Warranty: Manufacturer agrees to repair or replace waterproofing that fails in materials or workmanship within specified warranty period.

1. Warranty Period: 10 years from date of Substantial Completion.

B. Installer's Special Warranty: Specified form, signed by Installer, covering Work of this Section, for warranty period of two years.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Source Limitations for Waterproofing System: Obtain waterproofing materials from single source from single manufacturer.

2.2 PUMA WATERPROOFING

A. PUMA Waterproofing: Two-component, polyurethane methacrylate, reinforced with polyester fleece layer, walkable surface.

1. Manufacturers: Subject to compliance with requirements, provide products from Tremco Incorporated, or equal.

2. Tensile Strength: 900 psi minimum; ASTM D638.
3. Elongation at Break: 400 percent minimum; ASTM D638.
4. Water Vapor Permeance: 0.003 perm (0.172 ng/Pa x s x sq. m), maximum, ASTM E96/E96M.

2.3 AUXILIARY MATERIALS

A. General: Provide auxiliary materials recommended in writing by waterproofing manufacturer for intended use and compatible with one another and with waterproofing.

1. Furnish liquid-type auxiliary materials that comply with VOC limits of authorities having jurisdiction.

B. Primer: Manufacturer's standard primer, sealer, or surface conditioner; factory-formulated.

C. Sheet Flashing: 50-mil-minimum, nonstaining, uncured sheet neoprene.

1. Adhesive: Manufacturer's recommended contact adhesive.

D. Membrane-Reinforcing Fabric: Manufacturer's recommended fiberglass mesh or polyester fabric, manufacturer's standard weight.

E. Joint Reinforcing Strip: Manufacturer's recommended fiberglass mesh or polyester fabric.

F. Joint Sealant: Multicomponent polyurethane sealant, compatible with waterproofing; ASTM C920, Type M, Class 25 or greater; Grade NS for sloping and vertical applications and Grade P for deck applications; Use NT exposure; and as recommended by manufacturer for substrate and joint conditions.

1. Backer Rod: Closed-cell polyethylene foam.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.
1. Verify that substrate is visibly dry and within the moisture limits recommended in writing by manufacturer.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean, prepare, and treat substrates according to manufacturer's written instructions. Provide clean, dust-free, and dry substrates for waterproofing application.

B. Mask off adjoining surfaces not receiving waterproofing to prevent spillage and overspray affecting other construction.

C. Close off deck drains and other deck penetrations to prevent spillage and migration of waterproofing fluids.

3.3 PREPARATION AT TERMINATIONS, PENETRATIONS, AND CORNERS

A. Prepare surfaces at terminations and penetrations through waterproofing and at drains, sleeves, and corners according to waterproofing manufacturer's written instructions and to recommendations in ASTM C898/C898M and ASTM C1471/C1471M.

B. Apply waterproofing in two separate applications, and embed a joint reinforcing strip in the first preparation coat when recommended by waterproofing manufacturer.

3.4 INSTALLATION OF WATERPROOFING

A. Apply waterproofing according to manufacturer's written instructions and to recommendations in ASTM C898/C898M and ASTM C1471/C1471M.

B. Start installing waterproofing in presence of manufacturer's technical representative.

C. Apply primer over prepared substrate unless otherwise instructed in writing by waterproofing manufacturer.

D. Reinforced Waterproofing Applications: Mix materials and apply waterproofing by roller, notched squeegee, trowel, or other suitable application method.

1. Apply first coat of waterproofing, embed membrane-reinforcing fabric, and apply second coat of waterproofing to completely saturate reinforcing fabric and to obtain a seamless reinforced membrane free of entrapped gases and pinholes, with an average dry film total thickness of 80 mils.
2. Apply reinforced waterproofing to prepared wall terminations and vertical surfaces.
3. Verify manufacturer's recommended wet film thickness of waterproofing every 100 sq. ft..

E. Cure waterproofing, taking care to prevent contamination and damage during application and curing.

3.5 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections:

1. Testing agency shall verify thickness of waterproofing during application for each 600 sq. ft. of installed waterproofing or part thereof.

B. Manufacturer's Field Service: Engage asite representative qualified by waterproofing membrane manufacturer to inspect substrate conditions, surface preparation, membrane application, flashings, protection, and drainage components and to furnish daily reports to Government.

C. Waterproofing will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

3.6 PROTECTION

A. Do not permit foot or vehicular traffic on unprotected membrane.

B. Protect waterproofing from damage and wear during remainder of construction period.

C. Protect installed insulation drainage panels from damage due to UV light, harmful weather exposures, physical abuse, and other causes. Provide temporary coverings where insulation is subject to abuse and cannot be concealed and protected by permanent construction immediately after installation.

D. Correct deficiencies in or remove waterproofing that does not comply with requirements; repair substrates, reapply waterproofing, and repair sheet flashings.

END OF SECTION 07 14 16

SECTION 07 53 23 - ETHYLENE-PROPYLENE-DIENE-MONOMER (EPDM) ROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Adhered ethylene-propylene-diene-terpolymer (EPDM) roofing system.
2. Accessory roofing materials.
3. Substrate board.
4. Vapor retarder.
5. Roof insulation.
6. Insulation accessories and cover board.
7. Asphalt materials.
8. Walkways.

B. Related Requirements:

1. Section 06 10 00 "Rough Carpentry for wood nailers, curbs, and blocking.

2. Section 07 14 16 “Cold Fluid-Applied Waterproofing” for coordination with EPDM installation.
3. Section 07 62 00 "Sheet Metal Flashing and Trim" for metal roof flashings and counterflashings.
4. Section 07 92 00 "Joint Sealants" for joint sealants, joint fillers, and joint preparation.
5. Section 22 14 23 "Storm Drainage Piping Specialties" for roof drains.

1.2 DEFINITIONS

A. Roofing Terminology: Definitions in ASTM D1079 and glossary of NRCA's "The NRCA Roofing Manual: Membrane Roof Systems" apply to work of this Section.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Roofing Conference: Before starting roof removal, conduct conference at Project site.

1. Meet with Contracting Officer, roofing Installer, roofing system manufacturer's representative, and installers whose work interfaces with or affects roofing.
2. Review methods and procedures related to roofing installation, including manufacturer's written instructions.
3. Review and finalize construction schedule, and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
4. Review deck substrate requirements for conditions and finishes, including flatness and fastening.
5. Review structural loading limitations of roof deck during and after roofing.

6. Review base flashings, special roofing details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that affects roofing system.
7. Review governing regulations and requirements for insurance and certificates if applicable.
8. Review temporary protection requirements for roofing system during and after installation.
9. Review roof observation and repair procedures after roofing installation.

1.4 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. For insulation and roof system component fasteners, include copy of SPRI's Directory of Roof Assemblies listing.

B. Shop Drawings: Include roof plans, sections, details, and attachments to other work, including the following:

1. Layout and thickness of insulation.
2. Base flashings and membrane terminations.
3. Flashing details at penetrations.

4. Tapered insulation, thickness, and slopes.
5. Insulation fastening patterns for corner, perimeter, and field-of-roof locations.
6. Tie-in with air barrier.

C. Samples for Verification: For the following products:

1. Roof membrane and flashings of color required.
2. Walkway pads or rolls, of color required.

D. Wind Uplift Resistance Submittal: For roofing system, indicating compliance with wind uplift performance requirements.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer and manufacturer.

B. Manufacturer Certificates:

1. Performance Requirement Certificate: Signed by roof membrane manufacturer, certifying that roofing system complies with requirements specified in "Performance Requirements" Article.

a. Submit evidence of complying with performance requirements.

2. Special Warranty Certificate: Signed by roof membrane manufacturer, certifying that all materials supplied under this Section are acceptable for special warranty.

C. Product Test Reports: For components of roof membrane and insulation, for tests performed by a qualified testing agency, indicating compliance with specified requirements.

D. Evaluation Reports: For components of roofing system, from ICC-ES.

E. Field Test Reports:

1. Fastener-pullout test results and manufacturer's revised requirements for fastener patterns.

F. Field quality-control reports.

G. Sample Warranties: For manufacturer's special warranties.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For roofing system to include in maintenance manuals.

1.7 QUALITY ASSURANCE

A. Qualifications:

1. Manufacturers: A qualified manufacturer that is listed in SPRI's Directory of Roof Assemblies for roofing system identical to that used for this Project.
2. Installers: A qualified firm that is approved, authorized, or licensed by roofing system manufacturer to install manufacturer's product and that is eligible to receive manufacturer's special warranty.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, approval or listing agency markings, and directions for storing and mixing with other components.

B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.

1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.

C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.

D. Handle and store roofing materials, and place equipment in a manner to avoid permanent deflection of deck.

1.9 FIELD CONDITIONS

A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.

1.10 WARRANTY

A. Special Warranty: Manufacturer agrees to repair or replace components of roofing system that fail in materials or workmanship within specified warranty period.

1. Special warranty includes roof membrane, base flashings, roof insulation, fasteners, and other components of roofing system.

2. Warranty Period: 30 years from Date of Substantial Completion.

B. Special Project Warranty: Submit roofing Installer's warranty, on warranty form at end of this Section, signed by Installer, covering the Work of this Section, including all components of roofing system such as roof membrane, base flashing, roof insulation, fasteners, and walkway products, for the following warranty period:

1. Warranty Period: Two years from Date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. General Performance: Installed roofing system and base flashings to withstand specified uplift pressures, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Roofing and flashings to remain watertight.

1. Accelerated Weathering: Roof membrane to withstand 2000 hours of exposure when tested according to ASTM G152, ASTM G154, or ASTM G155.
2. Impact Resistance: Roof membrane to resist impact damage when tested according to ASTM D3746, ASTM D4272, or the "Resistance to Foot Traffic Test" in FM Approvals 4470.

B. Material Compatibility: Roofing materials to be compatible with one another and adjacent materials under conditions of service and application required, as demonstrated by roof membrane manufacturer based on testing and field experience.

C. SPRI's Directory of Roof Assemblies Listing: Roof membrane, base flashings, and component materials comply with requirements in FM Approvals 4450 or FM Approvals 4470 as part of a roofing system, and are listed in SPRI's Directory of Roof Assemblies for roof assembly identical for that specified for this Project.

1. Wind Uplift Load Capacity: 90 psf.

D. ENERGY STAR Listing: Roofing system to be listed on the DOE's ENERGY STAR "Roof Products Qualified Product List" for low-slope roof products.

E. Energy Performance: Roofing system to have an initial solar reflectance of not less than 0.70 and an emissivity of not less than 0.75 when tested in accordance with ANSI/CRRC S100.

F. Exterior Fire-Test Exposure: ASTM E108 or UL 790, Class A; for application and roof slopes indicated; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

2.2 ETHYLENE-PROPYLENE-DIENE-TERPOLYMER (EPDM) ROOFING

A. EPDM Sheet: ASTM D4637/D4637M, Type II, scrim or fabric internally reinforced, EPDM sheet.

1. Manufacturers: Subject to compliance with requirements, provide materials from Carlisle Syntec Systems or equal.

2. Thickness: 90 mils, nominal.

3. Exposed Face Color: White on black.

4. Source Limitations: Obtain components for roofing system from roof membrane manufacturer or manufacturers approved by roof membrane manufacturer.

2.3 ACCESSORY ROOFING MATERIALS

A. General: Accessory materials recommended by roofing system manufacturer for intended use and compatible with other roofing components.

1. Adhesive and Sealants: Comply with VOC limits of authorities having jurisdiction.

B. Sheet Flashing: 60-mil- thick EPDM, partially cured or cured, according to application.

C. Protection Sheet: Epichlorohydrin or neoprene nonreinforced flexible sheet, 55 to 60 mils thick, recommended by EPDM manufacturer for resistance to hydrocarbons, non-aromatic solvents, grease, and oil.

D. Slip Sheet: Manufacturer's standard, of thickness required for application.

E. Prefabricated Pipe Flashings: As recommended by roof membrane manufacturer.

F. Bonding Adhesive: Manufacturer's standard.

G. Seaming Material: Manufacturer's standard, synthetic-rubber polymer primer and 3-inch- wide minimum, butyl splice tape with release film.

H. Lap Sealant: Manufacturer's standard, single-component sealant, colored to match membrane roofing.

I. Water Cutoff Mastic: Manufacturer's standard butyl mastic sealant.

J. Metal Termination Bars: Manufacturer's standard, predrilled stainless steel or aluminum bars, approximately 1 by 1/8 inch thick; with anchors.

K. Metal Battens: Manufacturer's standard, aluminum-zinc-alloy-coated or zinc-coated steel sheet, approximately 1 inch wide by 0.05 inch thick, prepunched.

L. Ballast Retaining Bar: Perimeter securement system consisting of a slotted extruded-aluminum retention bar with an integrated compression fastening strip.

1. Fasteners: 1-1/2-inch stainless steel fasteners with neoprene washers.

M. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening components to substrate, and acceptable to roofing system manufacturer.

N. Miscellaneous Accessories: Provide pourable sealers, preformed cone and vent sheet flashings, molded pipe boot flashings, preformed inside and outside corner sheet flashings, reinforced EPDM securement strips, T-joint covers, in-seam sealants, termination reglets, cover strips, and other accessories.

1. Provide white flashing accessories for white EPDM membrane roofing.

2.4 ROOF INSULATION

A. General: Preformed roof insulation boards manufactured or approved by EPDM roof membrane manufacturer, approved for use in SPRI's Directory of Roof Assemblies listed roof assemblies.

B. Composite Molded (Expanded) Polystyrene Board Insulation: ASTM C578, Type II, 1.35-lb/cu. ft. minimum density, with factory-applied facings, as follows:

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Cellofoam North America, Inc.
b. Insulfoam; Carlisle Construction Materials Company.

2. Facer: DOC PS 2, Exposure 1, oriented strand board, 7/16 inch thick.

3. Size: 48 by 48 inches.
4. Thickness: 3”.

C. Tapered Insulation: Provide factory-tapered insulation boards.

1. Material: Match roof insulation.
2. Minimum Thickness: 1/4 inch.
3. Slope:

a. Roof Field: 1/4 inch per foot unless otherwise indicated on Drawings.
b. Saddles and Crickets: 1/2 inch per foot unless otherwise indicated on Drawings.

2.5 INSULATION ACCESSORIES AND COVER BOARD

A. General: Roof insulation accessories recommended by insulation manufacturer for intended use and compatibility with other roofing system components.

B. Fasteners: Factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Approvals 4470, designed for fastening roof insulation and cover boards to substrate, and acceptable to roofing system manufacturer.

C. Insulation Adhesive: Insulation manufacturer's recommended adhesive formulated to attach roof insulation to substrate or to another insulation layer as follows:

1. Full-spread, spray-applied, low-rise, two-component urethane adhesive.

2. Verify adhesives and sealants comply with the following limits for VOC content:

a. Plastic Foam Adhesives: 50 g/L.
b. Gypsum Board and Panel Adhesives: 50 g/L.
c. Multipurpose Construction Adhesives: 70 g/L.
d. Fiberglass Adhesives: 80 g/L.
e. Contact Adhesives: 80 g/L.
f. PVC Welding Compounds: 510 g/L.
g. Other Adhesives: 250 g/L.
h. Single-Ply Roof Membrane Sealants: 450 g/L.
i. Nonmembrane Roof Sealants: 300 g/L.
j. Sealant Primers for Nonporous Substrates: 250 g/L.
k. Sealant Primers for Porous Substrates: 775 g/L.

2.6 WALKWAYS

A. Flexible Walkways: Factory-formed, nonporous, heavy-duty, slip-resisting, surface-textured walkway pads, approximately 3/16 inch thick and acceptable to roofing system manufacturer.

1. Size: Approximately 36 by 60 inches.
2. Color: Contrasting with roof membrane.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements and other conditions affecting performance of the Work.

1. Verify that roof openings and penetrations are in place, curbs are set and braced, and roof-drain bodies are securely clamped in place.
2. Verify that wood blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.

3. Verify that concrete substrate is visibly dry and free of moisture, and that minimum concrete internal relative humidity is not more than 75 percent, or as recommended by roofing system manufacturer when tested according to ASTM F2170.

   a. Test Frequency: One test probe per each 1000 sq. ft., or portion thereof, of roof deck, with not less than three test probes.
   b. Submit test reports within 24 hours of performing tests.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing system installation according to roofing system manufacturer's written instructions. Remove sharp projections.

B. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.

C. Perform fastener-pullout tests according to roof system manufacturer's written instructions.

1. Submit test result within 24 hours of performing tests.

   a. Include manufacturer's requirements for any revision to previously submitted fastener patterns required to achieve specified wind uplift requirements.

3.3 INSTALLATION OF ROOFING, GENERAL

A. Install roofing system according to roofing system manufacturer's written instructions, SPRI's Directory of Roof Assemblies assembly requirements, and FM Global Property Loss Prevention Data Sheet 1-29.

B. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at end of workday or when rain is forecast. Remove and discard temporary seals before beginning work on adjoining roofing.

3.4 INSTALLATION OF INSULATION

A. Coordinate installing roofing system components so insulation is not exposed to precipitation or left exposed at end of workday.

B. Comply with roofing system and insulation manufacturer's written instructions for installing roof insulation.

C. Installation Over Concrete Decks:

1. Install base layer of insulation with joints staggered not less than 24 inches in adjacent rows.

a. Where installing composite and noncomposite insulation in two or more layers, install noncomposite board insulation for bottom layer and intermediate layers, if applicable, and install composite board insulation for top layer.
b. Trim insulation neatly to fit around penetrations and projections, and to fit tight to intersecting sloping roof decks.
c. Make joints between adjacent insulation boards not more than 1/4 inch in width.
d. At internal roof drains, slope insulation to create a square drain sump with each side equal to the diameter of the drain bowl plus 24 inches.

    1) Trim insulation so that water flow is unrestricted.

e. Fill gaps exceeding 1/4 inch with insulation.
f. Cut and fit insulation within 1/4 inch of nailers, projections, and penetrations.

g. Adhere base layer of insulation to concrete roof deck according to SPRI's Directory of Roof Assemblies listed roof assembly requirements for specified Wind Uplift Load Capacity and FM Global Property Loss Prevention Data Sheet 1-29, as follows:

    1) Prime surface of concrete deck with asphalt primer at rate of 3/4 gal./100 sq. ft., and allow primer to dry.
    2) Set insulation in a solid mopping of hot roofing asphalt, applied within plus or minus 25 deg F of equiviscous temperature.

    3) Set insulation in ribbons of bead-applied insulation adhesive, firmly pressing and maintaining insulation in place.
    4) Set insulation in a uniform coverage of full-spread insulation adhesive, firmly pressing and maintaining insulation in place.

2. Install upper layers of insulation and tapered insulation with joints of each layer offset not less than 12 inches from previous layer of insulation.

    a. Staggered end joints within each layer not less than 24 inches in adjacent rows.

    b. Install with long joints continuous and with end joints staggered not less than 12 inches in adjacent rows.
    c. Trim insulation neatly to fit around penetrations and projections, and to fit tight to intersecting sloping roof decks.
    d. Make joints between adjacent insulation boards not more than 1/4 inch in width.
    e. At internal roof drains, slope insulation to create a square drain sump with each side equal to the diameter of the drain bowl plus 24 inches.

        1) Trim insulation so that water is unrestricted.

    f. Fill gaps exceeding 1/4 inch with insulation.
    g. Cut and fit insulation within 1/4 inch of nailers, projections, and penetrations.

    h. Loosely lay each layer of insulation units over substrate.

    i. Adhere each layer of insulation to substrate using adhesive according to SPRI's Directory of Roof Assemblies listed roof assembly requirements for specified

Wind Uplift Load Capacity and FM Global Property Loss Prevention Data Sheet 1-29, as follows:

1) Set each layer of insulation in ribbons of bead-applied insulation adhesive, firmly pressing and maintaining insulation in place.
2) Set each layer of insulation in a uniform coverage of full-spread insulation adhesive, firmly pressing and maintaining insulation in place.

3.5 INSTALLATION OF ADHERED ROOF MEMBRANE

A. Adhere roof membrane over area to receive roofing according to roofing system manufacturer's written instructions.

B. Unroll membrane roof membrane and allow to relax before installing.

C. Start installation of roofing in presence of roofing system manufacturer's technical personnel.

D. Accurately align roof membrane, and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.

E. Bonding Adhesive: Apply to substrate and underside of roof membrane at rate required by manufacturer, and allow to partially dry before installing roof membrane. Do not apply to splice area of roof membrane.

F. In addition to adhering, mechanically fasten roof membrane securely at terminations, penetrations, and perimeters.

G. Apply roof membrane with side laps shingled with slope of roof deck where possible.

H. Adhesive Seam Installation: Clean both faces of splice areas, apply splicing cement.

1. Firmly roll side and end laps of overlapping roof membrane to ensure a watertight seam installation.
2. Apply lap sealant and seal exposed edges of roofing terminations.

3. Apply a continuous bead of in-seam sealant before closing splice if required by roofing system manufacturer.

I. Repair tears, voids, and lapped seams in roof membrane that do not comply with requirements.

J. Spread sealant or mastic bed over deck-drain flange at roof drains, and securely seal roof membrane in place with clamping ring.

K. Adhere protection sheet over roof membrane at locations indicated.

3.6 INSTALLATION OF BASE FLASHING

A. Install sheet flashings and preformed flashing accessories, and adhere to substrates according to roofing system manufacturer's written instructions.

B. Apply bonding adhesive to substrate and underside of sheet flashing at required rate, and allow to partially dry. Do not apply to seam area of flashing.

C. Flash penetrations and field-formed inside and outside corners with cured or uncured sheet flashing.

D. Clean splice areas, apply splicing cement, and firmly roll side and end laps of overlapping sheets to ensure a watertight seam installation. Apply lap sealant and seal exposed edges of sheet flashing terminations.

E. Terminate and seal top of sheet flashings and mechanically anchor to substrate through termination bars.

3.7 INSTALLATION OF WALKWAYS

A. Flexible Walkways: Install walkway products according to manufacturer's written instructions.

1. Install flexible walkways at the indicated locations:

2. Provide 6-inch clearance between adjoining pads.
3. Adhere walkway products to substrate with compatible adhesive according to roofing system manufacturer's written instructions.

3.8 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to inspect substrate conditions, surface preparation, roof membrane application, sheet flashings, protection, and drainage components, and to furnish reports to Architect.

B. Perform the following tests:

1. Flood Testing: Flood test each roofing area for leaks, according to recommendations in ASTM D5957, after completing roofing and flashing. Install temporary containment assemblies, plug or dam drains, and flood with potable water.

a. Perform tests before overlying construction is placed.
b. Flood to an average depth of 2-1/2 inches with a minimum depth of 1 inch and not exceeding a depth of 4 inches. Maintain 2 inches of clearance from top of base flashing.

c. Flood each area for 24 hours.
d. After flood testing, repair leaks, repeat flood tests, and make further repairs until roofing and flashing installations are watertight.

1) Cost of retesting is Contractor's responsibility.

e. Testing agency to prepare survey report indicating locations initial leaks, if any, and final survey report.

2. Infrared Thermography: Testing agency surveys entire roof area using infrared color thermography according to ASTM C1153.

   a. Perform tests before overlying construction is placed.
   b. After infrared scan, locate specific areas of leaks by electrical capacitance/impedance testing or nuclear hydrogen detection tests.
   c. After testing, repair leaks, repeat tests, and make further repairs until roofing and flashing installations are watertight.

      1) Cost of retesting is Contractor's responsibility.

   d. Testing agency to prepare survey report of initial scan indicating locations of entrapped moisture, if any.

3. Electrical Capacitance/Impedance Testing: Testing agency surveys entire roof area for entrapped water within roof assembly according to ASTM D7954/D7954M.

   a. Perform tests before overlying construction is placed.
   b. After testing, repair leaks, repeat tests, and make further repairs until roofing and flashing installations are watertight.

      1) Cost of retesting is Contractor's responsibility.

   c. Testing agency to prepare survey report indicating locations of entrapped moisture, if any.

C. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion, in presence of Architect, and to prepare inspection report.

D. Repair or remove and replace components of roofing system where inspections indicate that they do not comply with specified requirements.

E. Additional testing and inspecting, at Contractor's expense, will be performed to determine if replaced or additional work complies with specified requirements.

3.9 PROTECTING AND CLEANING

A. Protect roofing system from damage and wear during remainder of construction period. When remaining construction does not affect or endanger roofing system, inspect roofing system for deterioration and damage, describing its nature and extent in a written report, with copies to Architect and Owner.

B. Correct deficiencies in or remove roofing system that does not comply with requirements, repair substrates, and repair or reinstall roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.

C. Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

3.10 ROOFING INSTALLER'S WARRANTY

A. WHEREAS _____ of _____, herein called the "Roofing Installer," has performed roofing and associated work ("work") on the following project:

1. Owner:
2. Owner Address:
3. Building Name/Type:
4. Building Address:
5. Area of Work:
6. Acceptance Date: _____.
7. Warranty Period:
8. Expiration Date: _____.

B. AND WHEREAS Roofing Installer has contracted (either directly with Owner or indirectly as a subcontractor) to warrant said work against leaks and faulty or defective materials and workmanship for designated Warranty Period,

C. NOW THEREFORE Roofing Installer hereby warrants, subject to terms and conditions herein set forth, that during Warranty Period Roofing Installer will, at Roofing Installer's own cost and expense, make or cause to be made such repairs to or replacements of said work as are necessary to correct faulty and defective work and as are necessary to maintain said work in a watertight condition.

D. This Warranty is made subject to the following terms and conditions:

1. Specifically excluded from this Warranty are damages to work and other parts of the building, and to building contents, caused by:

   a. lightning;

   b. peak gust wind speed exceeding 150 mph;
   c. fire;
   d. failure of roofing system substrate, including cracking, settlement, excessive deflection, deterioration, and decomposition;
   e. faulty construction of parapet walls, copings, chimneys, skylights, vents, equipment supports, and other edge conditions and penetrations of the work;
   f. vapor condensation on bottom of roofing; and
   g. activity on roofing by others, including construction contractors, maintenance personnel, other persons, and animals, whether authorized or unauthorized by Owner.

2. When work has been damaged by any of foregoing causes, Warranty shall be null and void until such damage has been repaired by Roofing Installer and until cost and expense thereof have been paid by Owner or by another responsible party so designated.
3. Roofing Installer is responsible for damage to work covered by this Warranty but is not liable for consequential damages to building or building contents resulting from leaks or faults or defects of work.
4. During Warranty Period, if Owner allows alteration of work by anyone other than Roofing Installer, including cutting, patching, and maintenance in connection with

penetrations, attachment of other work, and positioning of anything on roof, this Warranty shall become null and void on date of said alterations, but only to the extent said alterations affect work covered by this Warranty. If Owner engages Roofing Installer to perform said alterations, Warranty shall not become null and void unless Roofing Installer, before starting said work, shall have notified Owner in writing, showing reasonable cause for claim, that said alterations would likely damage or deteriorate work, thereby reasonably justifying a limitation or termination of this Warranty.

5. During Warranty Period, if original use of roof is changed and it becomes used for, but was not originally specified for, a promenade, work deck, spray-cooled surface, flooded basin, or other use or service more severe than originally specified, this Warranty shall become null and void on date of said change, but only to the extent said change affects work covered by this Warranty.
6. Owner shall promptly notify Roofing Installer of observed, known, or suspected leaks, defects, or deterioration and shall afford reasonable opportunity for Roofing Installer to inspect work and to examine evidence of such leaks, defects, or deterioration.
7. This Warranty is recognized to be the only warranty of Roofing Installer on said work and shall not operate to restrict or cut off Owner from other remedies and resources lawfully available to Owner in cases of roofing failure. Specifically, this Warranty shall not operate to relieve Roofing Installer of responsibility for performance of original work according to requirements of the Contract Documents, regardless of whether Contract was a contract directly with Owner or a subcontract with Owner's General Contractor.

E. IN WITNESS THEREOF, this instrument has been duly executed this _____ day of _____, _____.

1. Authorized Signature: _____.
2. Name: _____.
3. Title: _____.

END OF SECTION 07 53 23

SECTION 07 62 00 - SHEET METAL FLASHING AND TRIM

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Formed roof-drainage sheet metal fabrications.
2. Formed low-slope roof sheet metal fabrications.

B. Related Requirements:

1. Section 06 10 53 "Miscellaneous Rough Carpentry" for wood nailers, curbs, and blocking.

1.2 COORDINATION

A. Coordinate sheet metal flashing and trim layout and seams with sizes and locations of penetrations to be flashed, and joints and seams in adjacent materials.

B. Coordinate sheet metal flashing and trim installation with adjoining roofing and wall materials, joints, and seams to provide leakproof, secure, and noncorrosive installation.

1.3 PREINSTALLATION MEETINGS

A. Preinstallation Conference: Conduct conference at Project site.

1. Review construction schedule. Verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
2. Review special roof details, roof drainage, roof-penetration flashing, equipment curbs, and condition of other construction that affect sheet metal flashing and trim.
3. Review requirements for insurance and certificates if applicable.
4. Review sheet metal flashing observation and repair procedures after flashing installation.

1.4 ACTION SUBMITTALS

A. Product Data: For each of the following:

1. Underlayment materials.
2. Elastomeric sealant.
3. Butyl sealant.

B. Shop Drawings: For sheet metal flashing and trim.

1. Include plans, elevations, sections, and attachment details.

2. Detail fabrication and installation layouts, expansion-joint locations, and keyed details. Distinguish between shop- and field-assembled Work.
3. Include identification of material, thickness, weight, and finish for each item and location in Project.
4. Include details for forming, including profiles, shapes, seams, and dimensions.
5. Include details for joining, supporting, and securing, including layout and spacing of fasteners, cleats, clips, and other attachments. Include pattern of seams.
6. Include details of termination points and assemblies.
7. Include details of expansion joints and expansion-joint covers, including showing direction of expansion and contraction from fixed points.
8. Include details of roof-penetration flashing.
9. Include details of edge conditions, including flashings, and counterflashings.
10. Include details of special conditions.
11. Include details of connections to adjoining work.
12. Detail formed flashing and trim at scale of not less than 1-1/2 inches per 12 inches (1:10).

C. Samples: For each exposed product and for each color and texture specified, 12 inches (300 mm) long by actual width.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For fabricator.

1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For sheet metal flashing and trim, and its accessories, to include in maintenance manuals.

1.7 QUALITY ASSURANCE

A. Fabricator Qualifications: Employs skilled workers who custom fabricate sheet metal flashing and trim similar to that required for this Project and whose products have a record of successful in-service performance.

B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for fabrication and installation.

1. Build mockup of typical roof edge, including flashing and counterflashing, approximately 10 feet long, including supporting construction cleats, seams, attachments, underlayment, and accessories. Build mock-up of upper roof transition approximately 5' long.
2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Owner specifically approves such deviations in writing.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

A. Do not store sheet metal flashing and trim materials in contact with other materials that might cause staining, denting, or other surface damage.

1. Store sheet metal flashing and trim materials away from uncured concrete and masonry.
2. Protect stored sheet metal flashing and trim from contact with water.

B. Protect strippable protective covering on sheet metal flashing and trim from exposure to sunlight and high humidity, except to extent necessary for period of sheet metal flashing and trim installation.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Sheet metal flashing and trim assemblies, including cleats, anchors, and fasteners, shall withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Completed sheet metal flashing and trim shall not rattle, leak, or loosen, and shall remain watertight.

B. Sheet Metal Standard for Flashing and Trim: Comply with NRCA's "The NRCA Roofing Manual: Architectural Metal Flashing, Condensation and Air Leakage Control, and Reroofing" and SMACNA's "Architectural Sheet Metal Manual" requirements for dimensions and profiles shown unless more stringent requirements are indicated.

C. Sheet Metal Standard for Copper: Comply with CDA's "Copper in Architecture Handbook." Conform to dimensions and profiles shown unless more stringent requirements are indicated.

D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes to prevent buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.

1. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

2.2 SHEET METALS

A. Protect mechanical and other finishes on exposed surfaces from damage by applying strippable, temporary protective film before shipping.

B. Copper Sheet: ASTM B370, cold-rolled copper sheet, H00 or H01 temper.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Hussey Copper Ltd.

b. Revere Copper Products, Inc.

2. Source Limitations: Obtain sheet from single source from single manufacturer.
3. Nonpatinated, Exposed Finish: Mill.

C. Stainless Steel Sheet: ASTM A240/A240M, Type 304, dead soft, fully annealed; with smooth, flat surface.

1. Finish: ASTM A480/A480M, No. 2D (dull, cold rolled).

a. Surface Preparation: Remove tool and die marks and stretch lines, or blend into finish.

D. Lead Sheet: ASTM B749 lead sheet.

2.3 UNDERLAYMENT MATERIALS

A. Felt: ASTM D226/D226M, Type II (No. 30), asphalt-saturated organic felt; nonperforated.

B. Synthetic Underlayment: Laminated or reinforced, woven polyethylene or polypropylene, synthetic roofing underlayment; bitumen free; slip resistant; suitable for high temperatures over 220 deg F; and complying with physical requirements of ASTM D226/D226M for Type I and Type II felts.

C. Slip Sheet: Rosin-sized building paper, 3 lb/100 sq. ft. minimum.

2.4 MISCELLANEOUS MATERIALS

A. Provide materials and types of fasteners, solder, protective coatings, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and as recommended by manufacturer of primary sheet metal or manufactured item unless otherwise indicated.

B. Fasteners: Wood screws, annular threaded nails, self-tapping screws, self-locking rivets and bolts, and other suitable fasteners designed to withstand design loads and recommended by manufacturer of primary sheet metal.

1. General: Blind fasteners or self-drilling screws, gasketed, with hex-washer head.

a. Blind Fasteners: High-strength aluminum or stainless steel rivets suitable for metal being fastened.

2. Fasteners for Copper Sheet: Copper, hardware bronze or passivated Series 300 stainless steel.
3. Fasteners for Stainless Steel Sheet: Series 300 stainless steel.

C. Solder:

1. For Copper: ASTM B32, Grade Sn50, 50 percent tin and 50 percent lead with maximum lead content of 0.2 percent.

2. For Stainless Steel: ASTM B32, Grade Sn60, with acid flux of type recommended by stainless steel sheet manufacturer.

D. Sealant Tape: Pressure-sensitive, 100 percent solids, polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch wide and 1/8 inch thick.

E. Elastomeric Sealant: ASTM C920, elastomeric polyurethane polymer sealant; of type, grade, class, and use classifications required to seal joints in sheet metal flashing and trim and remain watertight.

F. Butyl Sealant: ASTM C1311, single-component, solvent-release butyl rubber sealant; polyisobutylene plasticized; heavy bodied for hooked-type expansion joints with limited movement.

G. Bituminous Coating: Cold-applied asphalt emulsion in accordance with ASTM D1187/D1187M.

H. Asphalt Roofing Cement: ASTM D4586, asbestos free, of consistency required for application.

I. Reglets: Units of type, material, and profile required, formed to provide secure interlocking of separate reglet and counterflashing pieces, and compatible with flashing indicated with factory-mitered and -welded corners and junctions and with interlocking counterflashing on exterior face, of same metal as reglet.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:

a. Cheney Flashing Company.
b. Fry Reglet Corporation.
c. Heckmann Building Products, Inc.
d. Hohmann & Barnard, Inc.
e. Keystone Flashing Company, Inc.

2. Source Limitations: Obtain reglets from single source from single manufacturer.
3. Material: Copper, 16 oz./sq. ft.
4. Masonry Type: Provide with offset top flange for embedment in masonry mortar joint.
5. Accessories:

a. Counterflashing Wind-Restraint Clips: Provide clips to be installed before counterflashing to prevent wind uplift of counterflashing's lower edge.

6. Finish: Mill.

2.5 FABRICATION, GENERAL

A. Custom fabricate sheet metal flashing and trim to comply with details indicated and recommendations in cited sheet metal standard that apply to design, dimensions, geometry, metal thickness, and other characteristics of item required.

1. Fabricate sheet metal flashing and trim in shop to greatest extent possible.
2. Fabricate sheet metal flashing and trim in thickness or weight needed to comply with performance requirements, but not less than that specified for each application and metal.
3. Verify shapes and dimensions of surfaces to be covered and obtain field measurements for accurate fit before shop fabrication.
4. Form sheet metal flashing and trim to fit substrates without excessive oil-canning, buckling, and tool marks; true to line, levels, and slopes; and with exposed edges folded back to form hems.
5. Conceal fasteners and expansion provisions where possible. Do not use exposed fasteners on faces exposed to view.

B. Fabrication Tolerances:

1. Fabricate sheet metal flashing and trim that is capable of installation to a tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.
2. Fabricate sheet metal flashing and trim that is capable of installation to tolerances specified.

C. Expansion Provisions: Form metal for thermal expansion of exposed flashing and trim.

1. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with butyl sealant concealed within joints.
2. Use lapped expansion joints only where indicated on Drawings.

D. Sealant Joints: Where movable, nonexpansion-type joints are required, form metal in accordance with cited sheet metal standard to provide for proper installation of elastomeric sealant.

E. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.

F. Fabricate cleats and attachment devices of sizes as recommended by cited sheet metal standard and by FM Global Property Loss Prevention Data Sheet 1-49 for application, but not less than thickness of metal being secured.

G. Seams:

1. Fabricate nonmoving seams with flat-lock seams. Tin edges to be seamed, form seams, and solder. Rivet joints where necessary for strength.

H. Do not use graphite pencils to mark metal surfaces.

2.6 LOW-SLOPE ROOF SHEET METAL FABRICATIONS

A. Roof Edge Flashing (Gravel Stop): Fabricate in minimum 96-inch-long but not exceeding 12-foot-long sections. Furnish with 6-inch-wide, joint cover plates.

1. Joint Style: Butted with expansion space and 6-inch-wide, exposed cover plate.
2. Fabricate from the following materials:

a. Stainless Steel: 0.0188 inch thick.

B. Counterflashing: Shop fabricate interior and exterior corners. Fabricate from the following materials, or match existing thickness where required:

1. Copper: 16 oz./sq. ft.

C. Flashing Receivers: Fabricate from the following materials:

1. Copper: 16 oz./sq. ft.

D. Roof-Penetration Flashing: Fabricate from the following materials:

1. Copper: 16 oz./sq. ft.
2. Lead: 4 lb.

E. Roof-Drain Flashing: Fabricate from the following materials:

1. Copper: 12 oz./sq. ft.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with installer present, for compliance with requirements for installation tolerances, substrate, and other conditions affecting performance of the Work.

1. Verify compliance with requirements for installation tolerances of substrates.
2. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
3. Verify that air- or water-resistant barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF UNDERLAYMENT

A. Felt Underlayment: Install felt underlayment, wrinkle free, using adhesive to minimize use of mechanical fasteners under sheet metal flashing and trim.

1. Install in shingle fashion to shed water.
2. Lap joints not less than 2 inches.

B. Synthetic Underlayment: Install synthetic underlayment, wrinkle free, in accordance with manufacturers' written instructions, and using adhesive where possible to minimize use of mechanical fasteners under sheet metal.

1. Lap horizontal joints not less than 4 inches.

2. Lap end joints not less than 12 inches.

C. Install slip sheet, wrinkle free, before installing sheet metal flashing and trim.

1. Install in shingle fashion to shed water.
2. Lapp joints not less than 4 inches.

3.3 INSTALLATION, GENERAL

A. Install sheet metal flashing and trim to comply with details indicated and recommendations of cited sheet metal standard that apply to installation characteristics required unless otherwise indicated on Drawings.

1. Install fasteners, solder, protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.
2. Install sheet metal flashing and trim true to line, levels, and slopes. Provide uniform, neat seams with minimum exposure of solder.
3. Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement.
4. Install sheet metal flashing and trim to fit substrates and to result in watertight performance.
5. Install continuous cleats with fasteners spaced not more than 12 inches o.c.
6. Space individual cleats not more than 12 inches apart. Attach each cleat with at least two fasteners. Bend tabs over fasteners.
7. Install exposed sheet metal flashing and trim with limited oil-canning, and free of buckling and tool marks.
8. Do not field cut sheet metal flashing and trim by torch.
9. Do not use graphite pencils to mark metal surfaces.

B. Metal Protection: Where dissimilar metals contact each other, or where metal contacts pressure-treated wood or other corrosive substrates, protect against galvanic action or corrosion by painting contact surfaces with bituminous coating or by other permanent separation as recommended by sheet metal manufacturer or cited sheet metal standard.

1. Coat concealed side of stainless steel sheet metal flashing and trim with bituminous coating where flashing and trim contact wood, ferrous metal, or cementitious construction.
2. Underlayment: Where installing sheet metal flashing and trim directly on cementitious or wood substrates, install underlayment and cover with slip sheet.

C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim.

1. Space movement joints at maximum of 10 feet with no joints within 24 inches of corner or intersection.
2. Form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with sealant concealed within joints.
3. Use lapped expansion joints only where indicated on Drawings.

D. Fasteners: Use fastener sizes that penetrate substrate not less than recommended by fastener manufacturer to achieve maximum pull-out resistance.

E. Conceal fasteners and expansion provisions where possible in exposed work and locate to minimize possibility of leakage. Cover and seal fasteners and anchors as required for a tight installation.

F. Seal joints as required for watertight construction.

1. Use sealant-filled joints unless otherwise indicated.

a. Embed hooked flanges of joint members not less than 1 inch into sealant.
b. Form joints to completely conceal sealant.
c. When ambient temperature at time of installation is between 40 and 70 deg F, set joint members for 50 percent movement each way.
d. Adjust setting proportionately for installation at higher ambient temperatures.

1) Do not install sealant-type joints at temperatures below 40 deg F.

2. Prepare joints and apply sealants to comply with requirements in Section 07 92 00 "Joint Sealants."

G. Soldered Joints: Clean surfaces to be soldered, removing oils and foreign matter.

1. Pretin edges of sheets with solder to width of 1-1/2 inches; however, reduce pretinning where pretinned surface would show in completed Work.
2. Do not use torches for soldering.
3. Heat surfaces to receive solder, and flow solder into joint.

a. Fill joint completely.
b. Completely remove flux and spatter from exposed surfaces.

4. Stainless Steel Soldering:

a. Tin edges of uncoated sheets, using solder for stainless steel and acid flux.
b. Promptly remove acid-flux residue from metal after tinning and soldering.
c. Comply with solder manufacturer's recommended methods for cleaning and neutralization.

5. Copper Soldering: Tin edges of uncoated sheets, using solder for copper.

H. Rivets: Rivet joints in copper where necessary for strength.

3.4 INSTALLATION OF ROOF FLASHINGS

A. Install sheet metal flashing and trim to comply with performance requirements, sheet metal manufacturer's written installation instructions, and cited sheet metal standard.

1. Provide concealed fasteners where possible, and set units true to line, levels, and slopes.
2. Install work with laps, joints, and seams that are permanently watertight and weather resistant.

B. Roof Edge Flashing:

1. Install roof edge flashings in accordance with ANSI/SPRI/FM 4435/ES-1.
2. Anchor to resist uplift and outward forces in accordance with recommendations in FM Global Property Loss Prevention Data Sheet 1-49 for FM Approvals' listing for required windstorm classification.

C. Pipe or Post Counterflashing: Install counterflashing umbrella with close-fitting collar with top edge flared for elastomeric sealant, extending minimum of 4 inches over base flashing. Install stainless steel draw band and tighten.

D. Counterflashing: Coordinate installation of counterflashing with installation of base flashing.

1. Insert counterflashing in reglets or receivers and fit tightly to base flashing.
2. Extend counterflashing 4 inches over base flashing.
3. Lap counterflashing joints minimum of 4 inches.
4. Secure in waterproof manner by means of snap-in installation and sealant or lead wedges and sealant unless otherwise indicated.

E. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with elastomeric sealant and clamp flashing to pipes that penetrate roof.

3.5 INSTALLATION TOLERANCES

A. Installation Tolerances: Shim and align sheet metal flashing and trim within installed tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings and within 1/8-inch offset of adjoining faces and of alignment of matching profiles.

3.6 CLEANING

A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.

B. Clean and neutralize flux materials. Clean off excess solder. Clean off excess sealants.

3.7 PROTECTION

A. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions.

B. On completion of sheet metal flashing and trim installation, remove unused materials and clean finished surfaces as recommended in writing by sheet metal flashing and trim manufacturer. Maintain sheet metal flashing and trim in clean condition during construction.

C. Replace sheet metal flashing and trim that have been damaged or that have deteriorated beyond successful repair by finish touchup or similar minor repair procedures, as determined by Contracting Officer.

END OF SECTION 07 62 00

SECTION 07 91 00 - PREFORMED JOINT SEALS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes, where indicated on drawings or required to replace existing materials:

1. Precured, extruded-silicone joint seals.

B. Related Requirements:

1. Section 07 92 00 "Joint Sealants" for sealants applied over preformed seals in dual seal systems.

1.2 ACTION SUBMITTALS

A. Product Data: For each preformed joint seal product.

B. Samples for Initial Selection: Manufacturer's color charts showing the full range of colors available for each product exposed to view.

C. Preformed Joint Seal Schedule: Include the following information:

1. Joint seal location and designation.
2. Joint width and movement capability.
3. Joint seal manufacturer and product name.
4. Joint seal color.

1.3 INFORMATIONAL SUBMITTALS

A. Product Test Reports: For each preformed joint seal for tests performed by manufacturer and witnessed by a qualified testing agency or by a qualified testing agency.

B. Warranties: For special warranties.

1.4 QUALITY ASSURANCE

A. Mockups: Install mockups of assemblies specified in other Sections that are indicated to receive preformed joint seals specified in this Section. Use materials and installation methods specified in this Section.

1.5 WARRANTY

A. Special Warranty: Installer agrees to repair or replace preformed joint seals that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish preformed joint seals to repair or replace those that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 EXTRUDED-SILICONE JOINT SEALS

A. Extruded-Silicone Joint Seals: Manufacturer's standard seal consisting of precured low-modulus silicone extrusion, with a neutral-curing silicone sealant for bonding extrusions to substrates.

1. Manufacturers: Subject to compliance with requirements, provide products from Sika Corporation or equal.

2. Joint Seal Width: As required to fit existing stone joints.
3. Joint Seal Color: As selected by Contracting Officer from full range of industry colors.

2.2 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by preformed-joint-seal manufacturer for joint substrates indicated.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to preformed joint seal manufacturer, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces, and formulated to promote best adhesion to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with preformed joint seals and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive preformed joint seals, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting preformed-joint seal performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing preformed joint seals to comply with preformed joint seal manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of preformed joint seal, including dust, paints (except for permanent protective coatings tested and approved for seal adhesion and compatibility by seal manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimal bond with preformed joint seals. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

    a. Masonry.

B. Joint Priming: Prime joint substrates where recommended by preformed joint seal manufacturer or as indicated by tests or prior experience. Apply primer to comply with joint seal manufacturer's written instructions. Confine primers to areas of joint seal bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of adhesive or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION

A. General: Comply with preformed joint seal manufacturer's written installation instructions for products and applications indicated unless more stringent requirements apply.

B. Installation of Precured, Extruded-Silicone Joint Seals:

1. Apply masking tape to each side of joint, outside of area to be covered by seal system.
2. Apply silicone sealant to each side of joint to produce a bead of size complying with preformed silicone seal system manufacturer's written instructions and covering a bonding area of not less than 3/8 inch. Hold edge of sealant bead 1/4 inch inside masking tape.
3. Press silicone extrusion into sealant to wet extrusion and substrate. Use a roller to apply consistent pressure and ensure uniform contact with substrate.
4. Complete installation of seal system in horizontal joints before installing in vertical joints. Lap vertical joints over horizontal joints. At ends of joints, cut silicone extrusion with a razor knife.

3.4 PROTECTION

A. Protect preformed joint seals from damage resulting from construction operations or other causes so seals are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated seals immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION 07 91 00

SECTION 07 92 00 - JOINT SEALANTS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Urethane joint sealants.

B. Related Requirements:

1. Section 07 91 00 "Preformed Joint Seals" for preformed compressible foam and precured joint seals.

1.2 ACTION SUBMITTALS

A. Product Data: For each joint-sealant product.

B. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.

C. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch-wide joints formed between two 6-inch-long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

D. Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

1.3 INFORMATIONAL SUBMITTALS

A. Qualification Data: For qualified testing agency.

B. Product Test Reports: For each kind of joint sealant, for tests performed by manufacturer and witnessed by a qualified testing agency or by a qualified testing agency.

C. Preconstruction Laboratory Test Schedule: Include the following information for each joint sealant and substrate material to be tested:

1. Joint-sealant location and designation.
2. Manufacturer and product name.
3. Type of substrate material.
4. Proposed test.
5. Number of samples required.

D. Preconstruction Laboratory Test Reports: From sealant manufacturer, indicating the following:

1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
2. Interpretation of test results and written recommendations for primers and substrate preparation are needed for adhesion.

E. Preconstruction Field-Adhesion-Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on testing specified in "Preconstruction Testing" Article.

F. Field-Adhesion-Test Reports: For each sealant application tested.

G. Sample Warranties: For special warranties.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.

B. Product Testing: Test joint sealants using a qualified testing agency.

1. Testing Agency Qualifications: Qualified according to ASTM C 1021 to conduct the testing indicated.

C. Mockups: Install sealant in mockups of assemblies specified in other Sections that are indicated to receive joint sealants specified in this Section. Use materials and installation methods specified in this Section.

1.5 PRECONSTRUCTION TESTING

A. Preconstruction Laboratory Testing: Submit to joint-sealant manufacturers, for testing indicated below, samples of materials that will contact or affect joint sealants.

1. Adhesion Testing: Use ASTM C 794 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.
2. Compatibility Testing: Use ASTM C 1087 to determine sealant compatibility when in contact with glazing and gasket materials.

3. Stain Testing: Use ASTM C 1248 to determine stain potential of sealant when in contact with stone substrates.
4. Submit manufacturer's recommended number of pieces of each type of material, including joint substrates, joint-sealant backings, and miscellaneous materials.
5. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
6. For materials failing tests, obtain joint-sealant manufacturer's written instructions for corrective measures, including use of specially formulated primers.

7. Testing will not be required if joint-sealant manufacturers submit data that are based on previous testing, not older than 24 months, of sealant products for adhesion to, staining of, and compatibility with joint substrates and other materials matching those submitted.

B. Preconstruction Field-Adhesion Testing: Before installing sealants, field test their adhesion to Project joint substrates as follows:

1. Locate test joints where indicated on Project or, if not indicated, as directed by Contracting Officer.
2. Conduct field tests for each kind of sealant and joint substrate.
3. Notify Contracting Officer seven days in advance of dates and times when test joints will be erected.

4. Arrange for tests to take place with joint-sealant manufacturer's technical representative present.

   a. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1.1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.

      1) For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

5. Report whether sealant failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. For sealants that fail adhesively, retest until satisfactory adhesion is obtained.
6. Evaluation of Preconstruction Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing, in absence of other indications of noncompliance with requirements, will be considered satisfactory. Do not use sealants that fail to adhere to joint substrates during testing.

1.6 FIELD CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.7 WARRANTY

A. Special Installer's Warranty: Installer agrees to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:

1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
2. Disintegration of joint substrates from causes exceeding design specifications.
3. Mechanical damage caused by individuals, tools, or other outside agents.
4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 - PRODUCTS

2.1 JOINT SEALANTS, GENERAL

A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.

B. Colors of Exposed Joint Sealants: As selected by Contracting Officer from manufacturer's full range.

2.2 URETHANE JOINT SEALANTS

A. Nonstaining Joint Sealants: No staining of substrates when tested according to ASTM C 1248.

B. Urethane, S, NS, 25, NT: Single-component, nonsag, nontraffic-use, plus 25 percent and minus 25 percent movement capability, urethane joint sealant; ASTM C 920, Type S, Grade NS, Class 25, Use NT.

1. Manufacturers: Subject to compliance with requirements, provide products from Sika Corporation or equal.

2.3 JOINT-SEALANT BACKING

A. Sealant Backing Material, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.

B. Cylindrical Sealant Backings: ASTM C 1330, Type C (closed-cell material with a surface skin), Type O (open-cell material), Type B (bicellular material with a surface skin), or any of the preceding types, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.

C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

2.4 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and

approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.

2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:

    a. Masonry.

3. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:

    a. Metal.

B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.

B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.

C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

    1. Do not leave gaps between ends of sealant backings.
    2. Do not stretch, twist, puncture, or tear sealant backings.
    3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.

D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.

E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:

    1. Place sealants so they directly contact and fully wet joint substrates.

2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.

3. Provide concave joint profile per Figure 8A in ASTM C 1193 unless otherwise indicated.
4. Provide flush joint profile at horizontal surfaces according to Figure 8B in ASTM C 1193.

3.4 FIELD QUALITY CONTROL

A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:

1. Extent of Testing: Test completed and cured sealant joints as follows:

   a. Perform 10 tests for the first 1000 feet of joint length for each kind of joint substrate.
   b. Perform one test for each 1000 feet of joint length thereafter.

2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.

   a. For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

3. Inspect tested joints and report on the following:

   a. Whether sealants filled joint cavities and are free of voids.
   b. Whether sealant dimensions and configurations comply with specified requirements.
   c. Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.

4. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.

5. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.

B. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

3.5 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.6 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

3.7 JOINT-SEALANT SCHEDULE

A. Joint-Sealant Application: Exterior joints in vertical surfaces and horizontal nontraffic surfaces.

1. Joint Locations:

   a. Joints in dimension stone cladding.
   b. Perimeter joints between stone cladding and frames of doors.
   c. Joints between flashing and stone.
   d. Other joints as indicated on Drawings.

2. Joint Sealant: Urethane, S, NS, 50, NT.
3. Joint-Sealant Color: As selected by Contracting Officer from manufacturer's full range of colors.

END OF SECTION 07 92 00

SECTION 09 96 00 - HIGH-PERFORMANCE COATINGS

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes surface preparation and the application of high-performance coating systems on the following substrates:

1. Exterior Substrates:

a. Steel.

2. Interior Substrates:

a. Steel.

1.2 DEFINITIONS

A. MPI Gloss Level 5: 35 to 70 units at 60 degrees, according to ASTM D 523.

B. MPI Gloss Level 6: 70 to 85 units at 60 degrees, according to ASTM D 523.

C. MPI Gloss Level 7: More than 85 units at 60 degrees, according to ASTM D 523.

1.3 ACTION SUBMITTALS

A. Product Data: For each type of product. Include preparation requirements and application instructions.

1. Include printout of current "MPI Approved Products List" for each product category specified, with the proposed product highlighted.
2. Indicate VOC content.

B. Samples for Initial Selection: For each type of topcoat product indicated.

C. Samples for Verification: For each type of coating system and each color and gloss of topcoat indicated.

1. Submit Samples on rigid backing, 8 inches square.
2. Apply coats on Samples in steps to show each coat required for system.
3. Label each coat of each Sample.
4. Label each Sample for location and application area.
5. Provide drawdowns of each finish coat.

D. Product List: Cross-reference to coating system and locations of application areas. Use same designations indicated on Drawings and in schedules. Include color designations.

1.4 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Coatings: 5 percent, but not less than 1 gal. of each material and color applied.

1.5 QUALITY ASSURANCE

A. Mockups: Apply mockups of each coating system indicated to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Architect will select one surface or item to represent surfaces and conditions for application of each coating system.

2. Final approval of color selections will be based on mockups.

a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.

3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.

4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.

1. Maintain containers in clean condition, free of foreign materials and residue.
2. Remove rags and waste from storage areas daily.

1.7 FIELD CONDITIONS

A. Apply coatings only when temperature of surfaces to be coated and ambient air temperatures are between 50 and 95 deg F.

B. Do not apply coatings when relative humidity exceeds 85 percent; at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.

C. Do not apply exterior coatings in snow, rain, fog, or mist.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by the Sherwin-Williams Company, or equal.

B. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to products listed in the Exterior High-Performance Coating Schedule or Interior High-Performance Coating Schedule for the coating category indicated.

2.2 HIGH-PERFORMANCE COATINGS, GENERAL

A. MPI Standards: Products shall comply with MPI standards indicated and shall be listed in its "MPI Approved Products Lists."

B. Material Compatibility:

1. Materials for use within each paint system shall be compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
2. For each coat in a paint system, products shall be recommended in writing by topcoat manufacturers for use in paint system and on substrate indicated.
3. Products shall be of same manufacturer for each coat in a coating system.

C. Colors: As selected by Contracting Officer from manufacturer's full range.

2.3 SOURCE QUALITY CONTROL

A. Testing of Coating Materials: Owner reserves the right to invoke the following procedure:

1. Owner will engage the services of a qualified testing agency to sample coating materials. Contractor will be notified in advance and may be present when samples are taken. If coating materials have already been delivered to Project site, samples may be taken at Project site. Samples will be identified, sealed, and certified by testing agency.
2. Testing agency will perform tests for compliance with product requirements.
3. Owner may direct Contractor to stop applying coatings if test results show materials being used do not comply with product requirements. Contractor shall remove noncomplying coating materials from Project site, pay for testing, and recoat surfaces coated with rejected materials. Contractor will be required to remove rejected materials from previously coated surfaces if, on recoating with complying materials, the two coatings are incompatible.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.

B. Verify suitability of substrates, including surface conditions and compatibility, with existing finishes and primers.

C. Proceed with coating application only after unsatisfactory conditions have been corrected.

1. Application of coating indicates acceptance of surfaces and conditions.

3.2 PREPARATION

A. Comply with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual" applicable to substrates and coating systems indicated.

B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.

C. Clean substrates of substances that could impair bond of coatings, including dust, dirt, oil, grease, and incompatible paints and encapsulants.

1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce coating systems indicated.

D. Steel Substrates: Remove rust, loose mill scale, and shop primer if any. Clean using methods recommended in writing by paint manufacturer.

3.3 APPLICATION

A. Apply high-performance coatings according to manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual."

1. Use applicators and techniques suited for coating and substrate indicated.
2. Coat backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
3. Do not apply coatings over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.

B. Tint each undercoat a lighter shade to facilitate identification of each coat if multiple coats of the same material are to be applied. Tint undercoats to match color of finish coat, but provide sufficient difference in shade of undercoats to distinguish each separate coat.

C. If undercoats or other conditions show through final coat, apply additional coats until cured film has a uniform coating finish, color, and appearance.

D. Apply coatings to produce surface films without cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections. Produce sharp glass lines and color breaks.

3.4 FIELD QUALITY CONTROL

A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test coatings for dry film thickness.

1. Contractor shall touch up and restore coated surfaces damaged by testing.
2. If test results show that dry film thickness of applied coating does not comply with coating manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with coating manufacturer's written recommendations.

3.5 CLEANING AND PROTECTION

A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.

B. After completing coating application, clean spattered surfaces. Remove spattered coatings by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.

C. Protect work of other trades against damage from coating operation. Correct damage to work of other trades by cleaning, repairing, replacing, and recoating, as approved by Architect, and leave in an undamaged condition.

D. At completion of construction activities of other trades, touch up and restore damaged or defaced coated surfaces.

3.6 HIGH-PERFORMANCE COATING SCHEDULE

A. Steel Substrates:

1. Pigmented Polyurethane over Epoxy System MPI EXT 5.1H – G5:

a. Prime Coat: Primer, epoxy, anti-corrosive, for metal, MPI #101.

1) Sherwin Williams Dura-Plate 235 Multi-Purpose Epoxy, or equal.

b. Intermediate Coat: Epoxy, gloss, MPI #77.

1) Sherwin Williams Tile-Clad HS Epoxy, or equal.

c. First and Second Topcoat: Polyurethane, two component, pigmented, gloss (MPI Gloss Level 6), MPI #174.

1) Sherwin Williams Hi-Solids Polyurethane Semi-Gloss, or equal.

3.7 INTERIOR HIGH-PERFORMANCE COATING SCHEDULE

A. Steel Substrates:

1. Pigmented Polyurethane over Epoxy Primer System MPI INT 5.1U:

a. Prime Coat: Primer, epoxy, anti-corrosive, high-build for metal, MPI #1120.

1) Sherwin Williams Macropoxy 646 Fast Cure Epoxy, or equal.

b. Intermediate Coat: Polyurethane, two component, pigmented, matching topcoat.

c. Topcoat: Polyurethane, two component, pigmented, gloss (MPI Gloss Level 6), MPI #72.

1) Sherwin Williams Acrolon 218 HS, or equal.

END OF SECTION 09 96 00

SECTION 22 14 23 - STORM DRAINAGE PIPING SPECIALTIES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Cast metal roof drains.

B. Related Requirements:

1. Section 07 62 00 "Sheet Metal Flashing and Trim" for penetrations of roofs.

1.2 ACTION SUBMITTALS

A. Product Data: For each type of product.

1.3 QUALITY ASSURANCE

A. Drainage piping specialties shall bear label, stamp, or other markings of specified testing agency.

PART 2 - PRODUCTS

2.1 METAL ROOF DRAINS

A. Roof Drains:

1. Manufacturers: Subject to compliance with requirements, provide products by Jay R. Smith Mfg Co., a division of Morris Group International, or equal.

2. Material: bronze

3. Shape: dome

4. Outlet: 4” diameter.

PART 3 - EXECUTION

3.1 INSTALLATION

A. Install roof drains at low points of roof areas according to roof membrane manufacturer's written installation instructions.

1. Install flashing collar or flange of roof drain to prevent leakage between drain and adjoining roofing. Maintain integrity of waterproof membranes where penetrated.
2. Install expansion joints, if indicated, in roof drain outlets.
3. Position roof drains for easy access and maintenance.

B. Install cast metal downspout adapters on outlet of back-outlet parapet roof drains and connect to existing sheet metal sleeves.

3.2 FLASHING INSTALLATION

A. Fabricate flashing from single piece of metal unless large pans, sumps, or other drainage shapes are required.

B. Install sheet flashing on pipes, sleeves, and specialties passing through or embedded in floors and roofs with waterproof membrane.

C. Set flashing on floors and roofs in solid coating of bituminous cement.

D. Secure flashing into sleeve and specialty clamping ring or device.

3.3 PROTECTION

A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.

B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION 22 14 23