AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF	PAGES
J	1		2

2. AMENDMENT/MODIFICATION NUMBER	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQUISITION NUMBER	5. PROJECT NUMBER *(If applicable)*
0002	27 May 2026	See Continuation Sheet	J-875

6. ISSUED BY CODE N62742

NAVFACSYSCOM PACIFIC
258 MAKALAPA DR STE 100, JBPHH HI 96860-3134
JBPHH, HI 96860-3134
UNITED STATES
Jennifer Hue, Email: jennifer.m.hue.civ@us.navy.mil Telephone: 8086026755

7. ADMINISTERED BY *(If other than Item 6)* CODE

SCD: PAS:

8. NAME AND ADDRESS OF CONTRACTOR *(Number, street, county, State and ZIP Code)*

CODE FACILITY CODE

(X)

☒ 9A. AMENDMENT OF SOLICITATION NUMBER N6274226R1306

9B. DATED *(SEE ITEM 11)* 10 Apr 2026

☐ 10A. MODIFICATION OF CONTRACT/ORDER NUMBER

10B. DATED *(SEE ITEM 13)*

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☒ is extended. ☐ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

See Section 00 70 00 - Conditions of the Contract

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

CHECK ONE	
☐	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.*)

See Schedule

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
15B. CONTRACTOR/OFFEROR *(Signature of person authorized to sign)*	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA *(Signature of Contracting Officer)*	16C. DATE SIGNED

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

Block 14 (Description of Amendment/Modification): RFP N62742-26-R-1306, JFY 2022 PROJECT J-875, BATTLE STAFF TRAINING FACILITY, U.S. NAVSUPPACT MCB CAMP BLAZ, GUAM; AMENDMENT 0002 is for the following:

SF1442 - Solicitation, Offer and Award (SF1442)
Delete and replace pages 1 through 2 with attached pages 1 through 2.

SF1442 - Solicitation, Offer and Award (SF1442), Continued Price Proposal Schedule
Delete and replace pages 3 through 5 with attached pages 3 through 5 (Amendment No. 0002).

Section 00 21 16 - Instructions to Proposers, paragraph 1.2 NUMBER OF COPIES/TIME OF RECEIPT
Revise a. PRICE PROPOSAL (PAPER) and b. TECHNICAL PROPOSAL (FACTORS 1, 2 AND 3) (PAPER) due date to "June 23, 2026, 2:00 p.m., H.S.T." and c. SUBCONTRACTING PLAN (PAPER) due date to "June 24, 2026, 2:00 p.m., H.S.T."

Section 00 21 16 - Instructions to Proposers, paragraph 1.4 INSTRUCTIONS FOR SUBMITTING QUESTIONS REGARDING SOLICITATION
Revise the last sentence to state: "The Government may not respond to questions submitted after June 2, 2026."

SPECIFICATIONS (Due to system character limitation, see attached SPECIFICATIONS SUMMARY OF CHANGES)

SPECIFICATIONS SUMMARY OF CHANGES

DOCUMENT 00 01 15 – LIST OF DRAWINGS

- PARA. 1.2 CONTRACT DRAWINGS: The following drawings, bearing revision date of 4/27/2026, supersede previously issued drawings bearing the same number and title. The revised drawings accompany this Amendment, see Attachment (1).

SHEET NO.	NAVFAC DWG NO.	REVISION NO.	TITLE
G-002	17321760	1	LIST OF SHEETS
G-005	17321763	1	BUILDING CODE SUMMARY
G-101	17321764	1	CODE COMPLIANCE SITE PLAN
G-102	17321765	1	1ST FLOOR PLAN – LIFE SAFETY
G-103	17321766	1	2ND FLOOR PLAN – LIFE SAFETY
CS100	17321786	1	CIVIL SITE PLAN – BASE AND BID OPTIONS
CS101	17321787	1	CIVIL SITE LOCATION PLAN BASE AND BID OPTIONS
CS504	17321791	1	CIVIL DETAILS – SHEET 4
CS505	17321792	1	CIVIL DETAILS – SHEET 5
CG100	17321793	1	CIVIL GRADING PLAN – BASE BID
CG100B	17321794	1	CIVIL GRADING PLAN – BID OPTIONS
CP100	17321801	1	CIVIL PAVING PLAN – BASE AND BID OPTIONS
CP502	17321803	1	CIVIL PAVING DETAILS – SHEET 2
CU100	17321807	1	CIVIL UTILITY PLAN
LP101	17321828	1	LANDSCAPE PLAN - BASE AND OPTIONS
S-001	17321836	1	STRUCTURAL NOTES AND LEGEND -SHEET 1
SB105	17321851	1	SLAB PLAN - AREA 'A' (EL. 0'-0", UNO)
SB106	17321852	1	SLAB PLAN - AREA 'B' (EL. 0'-0", UNO)
SB401	17321853	1	MECHANICAL ENCLOSURE FOUNDATION / SLAB PLAN
SB402	17321854	1	CANOPY FOUNDATION / SLAB PLAN
SF102	17321860	1	SECOND FLOOR FRAMING PLAN - AREA 'A' (EL. 14'-0", UNO)
SF103	17321861	1	SECOND FLOOR FRAMING PLAN - AREA 'A' (EL. 16'-0", UNO)
SF104	17321862	1	SECOND FLOOR FRAMING PLAN -AREA 'B' (EL. 14'-0", UNO)
SF105	17321863	1	SECOND FLOOR FRAMING PLAN -AREA 'B' (EL. 16'-0", UNO)
SF401	17321869	1	MECHANICAL ENCLOSURE FRAMING PLAN
SF402	17321870	1	CANOPY ROOF FRAMING PLAN

AS101	17321901	1	ARCHITECTURAL SITE PLAN AND OPTION ITEMS
AS102	17321902	1	CHILLER ENCLOSURE PLAN, EXTERIOR ELEVATIONS, AND SECTION
A-101	17321912	1	OVERALL FIRST FLOOR PLAN
A-102	17321913	1	ENLARGED FLOOR PLAN - 1A
A-103	17321914	1	ENLARGED FLOOR PLAN - 1B & OPTION ITEM #2
A-104	17321915	1	OVERALL SECOND FLOOR PLAN
A-105	17321916	1	ENLARGED FLOOR PLAN - 2A
A-106	17321917	1	ENLARGED FLOOR PLAN - 2B
A-111	17321918	1	OVERALL FIRST FLOOR REFLECTED CEILING PLAN
A-113	17321920	1	ENLARGED REFLECTED CEILING PLAN - 1B & OPTION ITEM #2
A-114	17321921	1	OVERALL SECOND FLOOR REFLECTED CEILING PLAN
A-115	17321922	1	ENLARGED REFLECTED CEILING PLAN - 2A
A-116	17321923	1	ENLARGED REFLECTED CEILING PLAN - 2B
A-301	17321928	1	BUILDING SECTIONS
A-401	17321931	1	INTERIOR ELEVATIONS
A-402	17321932	1	INTERIOR ELEVATIONS
A-403	17321933	1	INTERIOR ELEVATIONS
A-404	17321934	1	INTERIOR ELEVATIONS
A-405	17321935	1	INTERIOR ELEVATIONS
A-411	17321936	1	DETAILED RESTROOM PLANS AND INTERIOR ELEVATIONS
A-412	17321937	1	DETAILED RESTROOM PLANS AND INTERIOR ELEVATIONS
A-413	17321938	1	DETAILED ELEVATOR PLANS AND SECTION
A-415	17321940	1	DETAILED STAIR B PLANS AND SECTION
A-416	17321941	1	DETAILED STAIR C PLANS AND SECTION
A-501	17321942	1	TYPICAL MOUNTING HEIGHTS
A-502	17321943	1	PARTITION TYPES
A-503	17321944	1	PARTITION TYPES
A-504	17321945	1	COLUMN DETAILS
A-505	17321983	1	COLUMN DETAILS – ADDED SHEET
A-601	17321946	1	DOOR AND OPERABLE PARTITION SCHEDULES
A-605	17321950	1	DOOR DETAILS
A-609	17321954	1	WINDOW DETAILS
A-610	17321955	1	INTERIOR COLOR MATERIAL SCHEDULE
A-614	17321959	1	ENLARGED SIGNAGE FLOOR PLAN – 1A
A-615	17321960	1	ENLARGED SIGNAGE FLOOR PLAN – 1B
A-730	17321968	1	MISCELLANEOUS INTERIOR DETAILS
A-801	17321972	1	ENLARGED RAF FLOOR PLAN – 1A

A-802	17321973	1	ENLARGED RAF FLOOR PLAN – 1B
A-901	17321976	1	AIR BARRIER DIAGRAM - FLOOR PLANS
A-902	17321977	1	AIR BARRIER DIAGRAM - SECTIONS
AI101	17321979	1	ENLARGED FLOOR FINISH PLAN – 1A
AI102	17321980	1	ENLARGED FLOOR FINISH PLAN – 1B
AI103	17321981	1	ENLARGED FLOOR FINISH PLAN - 2A
AI104	17321982	1	ENLARGED FLOOR FINISH PLAN - 2B
I-801	17321997	1	OVERALL FIRST FLOOR FF&E PLAN
I-804	17322000	1	ENLARGED FF&E FLOOR PLAN – 1A
I-805	17322001	1	ENLARGED FF&E FLOOR PLAN – 1B
PL115	17322061	1	PLUMBING PLAN - FIRST FLOOR - AREA 'E'
PL601	17322076	1	PLUMBING SCHEDULES - SHEET 2
MH101	17322094	1	HVAC DUCT PLAN - FIRST FLOOR - AREA 'A'
MH102	17322095	1	HVAC DUCT PLAN - FIRST FLOOR - AREA 'B'
MH103	17322096	1	HVAC DUCT PLAN - FIRST FLOOR - AREA 'C'
MH104	17322097	1	HVAC DUCT PLAN - FIRST FLOOR - AREA 'D'
MH105	17322098	1	HVAC DUCT PLAN - FIRST FLOOR - AREA 'E'
MH106	17322099	1	HVAC DUCT PLAN - FIRST FLOOR - AREA 'F'
MH111	17322101	1	HVAC DUCT PLAN - SECOND FLOOR - AREA 'A'
MH112	17322102	1	HVAC DUCT PLAN - SECOND FLOOR - AREA 'B'
MH113	17322103	1	HVAC DUCT PLAN - SECOND FLOOR - AREA 'C'
MH114	17322104	1	HVAC DUCT PLAN - SECOND FLOOR - AREA 'D'
MH115	17322105	1	HVAC DUCT PLAN - SECOND FLOOR - AREA 'E'
MH116	17322106	1	HVAC DUCT PLAN - SECOND FLOOR - AREA 'F'
MH502	17322112	1	HVAC DETAILS - SHEET 2
MH600	17322125	1	HVAC SCHEMATICS - SHEET 1
MH601	17322126	1	HVAC SCHEMATICS - SHEET 2
MH603	17322128	1	HVAC SCHEMATICS - SHEET 4
MH700	17322129	1	MECHANICAL SCHEDULES - SHEET 1
MH701	17322130	1	MECHANICAL SCHEDULES - SHEET 2
MH704	17322133	1	MECHANICAL SCHEDULES - SHEET 5
MP105	17322142	1	HVAC PIPING PLAN - FIRST FLOOR - AREA 'E'
MP107	17322144	1	HVAC PIPING PLAN - FIRST FLOOR - MECHANICAL ENCLOSURE
MP115	17322150	1	HVAC PIPING PLAN - SECOND FLOOR - AREA 'E'
E-001	17322168	1	ELECTRICAL SYMBOLS, LEGEND, ABBREVIATIONS, AND NOTES
ES100	17322170	1	ELECTRICAL SITE PLAN – BASE BID
EG101	17322172	1	OVERALL GROUNDING PLAN

EG103	17322174	1	ENLARGED GROUNDING PLAN AREA B
EG107	17322178	1	GENERATOR & PAVILION BUILDINGS - GROUNDING AND LIGHTNING PROTECTION PLANS
EL101	17322180	1	OVERALL LIGHTING PLAN - FIRST FLOOR
EL103	17322182	1	ENLARGED LIGHTING PLAN - FIRST FLOOR AREA 1B
EL105	17322184	1	ENLARGED LIGHTING PLAN - FIRST FLOOR AREA 1D
EL112	17322191	1	ENLARGED LIGHTING PLAN - SECOND FLOOR AREA 2D
EL113	17322192	1	ENLARGED LIGHTING PLAN - SECOND FLOOR AREA 2E
EL502	17322200	1	LIGHTING DETAILS - SHEET 2
EL602	17322205	1	SITE LIGHTING DIAGRAM
EL702	17322207	1	LIGHT FIXTURE SCHEDULE - SHEET 2
EP101	17322208	1	OVERALL POWER PLAN - FIRST FLOOR
EP102	17322209	1	ENLARGED POWER PLAN - FIRST FLOOR AREA 1A
EP103	17322210	1	ENLARGED POWER PLAN - FIRST FLOOR AREA 1B
EP104	17322211	1	ENLARGED POWER PLAN - FIRST FLOOR AREA 1C
EP105	17322212	1	ENLARGED POWER PLAN - FIRST FLOOR AREA 1D
EP106	17322213	1	ENLARGED POWER PLAN - FIRST FLOOR AREA 1E
EP107	17322214	1	ENLARGED POWER PLAN - FIRST FLOOR AREA 1F
EP113	17322220	1	ENLARGED POWER PLAN - SECOND FLOOR AREA 2E
EP114	17322221	1	ENLARGED POWER PLAN - SECOND FLOOR AREA 2F
EP122	17322222	1	GENERATOR BUILDING - POWER PLAN
EP402	17322225	1	ENLARGED POWER PLAN - BASE BID ELECTRICAL ROOMS
EP403	17322226	1	ENLARGED POWER PLAN - BID OPTION #2 ELECTRICAL ROOMS
EP601	17322235	1	ELECTRICAL ONELINE DIAGRAM - BASE BID SHEET 1
EP603	17322237	1	ELECTRICAL ONELINE DIAGRAM - BID OPTION 2 SHEET 3
EP701	17322239	1	PANELBOARD SCHEDULES - SHEET 1
EP703	17322241	1	PANELBOARD SCHEDULES - SHEET 3
EP704	17322242	1	PANELBOARD SCHEDULES - SHEET 4
EP706	17322244	1	PANELBOARD SCHEDULES - SHEET 6
EP710	17322248	1	PANELBOARD SCHEDULES - SHEET 10
EP720	17322249	1	CABLE SCHEDULE
T-001	17322265	1	TELECOMMUNICATIONS LEGEND
TS101	17322267	1	TELECOM SITE PLAN
TN102	17322272	1	PARTIAL PLAN - TELECOMMUNICATIONS - FIRST FLOOR - AREA 'A'

TN103	17322273	1	PARTIAL PLAN - TELECOMMUNICATIONS - FIRST FLOOR - AREA 'B'
TN502	17322287	1	TELECOMMUNICATIONS DETAILS - SHEET 3
TN604	17322296	1	TELECOM RISER DIAGRAMS - SHEET 3
TY101	17322297	1	SPECIAL SYSTEMS - FIRST FLOOR - AREA 'A'
TY102	17322298	1	SPECIAL SYSTEM - FIRST FLOOR - AREA 'B'
TY502	17322302	1	SPECIAL SYSTEMS DETAILS - SHEET 2
TA102	17322329	1	PARTIAL AV FIRST FLOOR PLAN -A
TA107	17322334	1	PARTIAL AV SECOND FLOOR PLAN -A
TA401	17322338	1	AV INTERIOR ELEVATIONS
TA403	17322340	1	AV INTERIOR ELEVATIONS
TA408	17322345	1	ENLARGED AV PLANS
TA410	17322347	1	AV INTERIOR ELEVATIONS & SECTIONS
TA601	17322352	1	AV SYSTEMS SCHEDULES
TA701	17322353	1	AV INFRASTRUCTURE RISER DIAGRAMS
TA702	17322354	1	AV INFRASTRUCTURE RISER DIAGRAMS
TA703	17322355	1	AV INFRASTRUCTURE RISER DIAGRAMS
TA704	17322356	1	AV INFRASTRUCTURE RISER DIAGRAMS

SPECIFICATIONS PROJECT TABLE OF CONTENTS

- Delete this Section in its entirety and replace it with PROJECT TABLE OF CONTENTS, dated 4-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 01 30 00 – ADMINISTRATIVE REQUIREMENTS

- Delete this Section in its entirety and replace it with Section 01 30 00 – ADMINISTRATIVE REQUIREMENTS, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 01 31 23.13 20 – ELECTRONIC CONSTRUCTION AND FACILITY SUPPORT CONTRACT MANAGEMENT SYSTEM (eCMS)

- PARA 1.6.1 Restricted Information, Line 6: Change “$250k” to “$350k”.

SECTION 01 32 17.00 20 – COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS)

- PARA 1.3.2 Weekly Look Ahead Schedule Requirements, (k), Lines 1-2: Add “or attach” after “Upload”, change “Weekly Look Ahead Schedules” to “Three-Week Look Ahead Schedule with QC Meeting Minutes”.
- PARA 1.10.1.5.6 Turnover and Closeout Activities, Line 5 after “and Acceptance”: Add “, eOMSI Progress Submittal, eOMSI Field Verification Meeting, Prefinal eOMSI Submittal and Field Verification, and Warranty Management Plan Review Meeting.”.

SECTION 01 33 00 – SUBMITTAL PROCEDURES

- PARA 1.4.2 Submittals Reserved for NAVFAC Pacific Approval, Line 2: Change "NAVFAC, Code CI4" to "NAVFACPAC, Code PDC4".

SECTION 01 45 00 – QUALITY CONTROLS

- Delete this Section in its entirety and replace it with Section 01 45 00 – QUALITY CONTROLS, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 01 45 35 – SPECIAL INSPECTIONS

- SCHEDULE OF SPECIAL INSPECTIONS, PARA. X. FIRE PROTECTION – SMOKE CONTROL, Line 1: Uncheck the box after "ALL PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED:".

SECTION 01 57 19 – TEMPORARY ENVIRONMENTAL CONTROLS

- PARA 3.5.3 Preconstruction Air Permits, 2nd paragraph, Lines 3: Change "52.263-7" to "52.236-7".

SECTION 01 57 19.03 20 – SUPPLEMENTAL TEMPORARY ENVIRONMENTAL CONTROLS

- Delete this Section in its entirety and replace it with Section 01 57 19.03 21 – SUPPLEMENTAL TEMPORARY ENVIRONMENTAL CONTROLS, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 01 78 00 – CLOSEOUT SUBMITTALS

- PARA 2.1 CERTIFICATION OF EPA DESIGNATED ITEMS, Lines 3-4: Delete "and FAR 52-223-17 Affirmative Procurement of EPA designated items in Service and Construction Contracts".

SECTION 03 42 13.00 10– PLANT-PRECAST CONCRETE PRODUCTS FOR BELOW GRADE CONSTRUCTION

- PARA. 1.1 REFERENCES, ASTM INTERNATIONAL (ASTM): Delete "ASTM A775/A775M (2022) Standard Specification for Epoxy-Coated Steel Reinforcing Bars" and delete "ASTM A884/A884M (2025) Standard Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement"
- Delete PARA. 2.2.3.4 "2.2.3.4 Epoxy Coated Reinforcement a. Reinforcing Bars: ASTM A775/A775M b. Wires and Welded Wire: ASTM A884/A884M".

SECTION 07 56 00 – FLUID-APPLIED ROOFING SYSTEM

- PARA 1.3 SUBMITTALS, SD-11 Closeout Submittals: Add "Construction Contractor Roofing Signature Checklist" after "Roofing System Installer Warranty".
- PARA. 3.7 INFORMATION CARD. After this paragraph, insert new paragraph as follows:
  "3.8 ROOFING SIGNATURE CHECKLIST
  Complete the Construction Contractor Roofing Signature Checklist attached to the end of this section."
- Insert the Construction Contractor Roofing Signature Checklist after Section 07 56 00, page 10. The Construction Contractor Roofing Signature Checklist accompanies this Amendment, see Attachment (2).

SECTION 08 71 00 – DOOR HARDWARE

- Delete this Section in its entirety and replace it with Section 08 71 00 – DOOR HARDWARE, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 09 29 00 – GYPSUM BOARD

- PARA 1.1 REFERENCE, under ASTM INSTERNATIONAL (ASTM): Add "ASTM C1658/C1658M (2019; E 2020) Standard Specification for Glass Mat Gypsum Panels"
- PARA 2.1.1 Gypsum Board, Lines 1-2: Change "ASTM C1396/C1396M. Paperless type, moisture and mildew resistant with ASTM D3273 score of 10" with "ASTM C1658/C1658M. Use paperless (glass mat) gypsum board.".

SECTION 10 21 13 – TOILET COMPARTMENTS

- PARA 1.1 REFERENCES, ASTM INTERNATIONAL (ASTM): Change "ASTM A167 (2011) Standard Specification for Stainless and Heat Resisting Chromium Nickel Steel Plate, Sheet, and Strip" to "ASTM A240/A240M (2025a) Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications".
- PARA 2.2.4.1 General Requirements, Conformance Standard, Line 5: Change "ASTM A167" to "ASTM A240/A240M".

SECTION 10 26 00 – WALL AND DOOR PROTECTION

- Delete this Section in its entirety and replace it with 10 26 00 – WALL AND DOOR PROTECTION, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 10 44 16 – FIRE EXTINGUISHERS

- Delete this Section in its entirety and replace it with 10 44 16 – FIRE EXTINGUISHERS, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 12 00 01.00 20 – FURNITURE, FIXTURES AND EQUIPMENT (FF&E) PACKAGE

- PARA 1.2.5 Construction Wage Rate Requirement Statute: Delete "Prior to the Interior Designer sending out the Best Value Determination (BVD) Request for Quote (RFQ) Package[s] to vendors, the NAVFAC Contracting Officer, Contract Specialist, Project Manager, Design Manager, NAVFAC Interior Designer and Collateral Equipment Manager must make made made a determination as to whether the FF&E [and Specialty CEQ]installation is covered by the Construction Wage Rate Requirements statute. The BVD RFQ Package must identify identified any items with installation that is subject to the Construction Wage Rate Requirements statute.".
- PARA 1.2.5.1 Construction Wage Rate Requirements Statute is Not Applicable, (a), Line 2: Change "Option (Item)" to "Planned Modification".
- PARA 3.2.2: Add "Submittal" after "Walk Through(s) and Punch List (s)".

SECTION 13 48 73– SEISMIC CONTROL FOR NONSTRUCTURAL COMPONENTS

- PARA. 1.1 REFERENCES, ASTM INTERNATIONAL (ASTM): Add "ASTM A153/A153M (2023) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware-23" after "ASTM A53/A53M (2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless".
- PARA. 1.1 REFERENCES, ASTM INTERNATIONAL (ASTM): Add "ASTM A194/A194M (2024) Standard Specification for Carbon Steel, Alloy Steel, and Stainless Steel Nuts for Bolts for High Pressure or High Temperature Service, or Both" after "ASTM A193/A193M (2025) Standard Specification for Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service and Other Special Purpose Applications".
- PARA 1.2.1 General Requirements, Table, Row 3: Change "1.48 G" with "2.25 G".
- PARA 1.2.1 General Requirements, Table, Row 4: Change "0.95 G" with "1.14 G".
- PARA 1.2.1 General Requirements, Table, Delete Rows 5 and 6.
- PARA 1.3 SUBMITTALS, SD-03 Product Data: Delete "Common Bolts; G".
- PARA. 2.1 EQUIPMENT REQUIREMENTS, after 3rd paragraph: Add "Submit supports and attachments shop drawings along with catalog cuts, templates, and erection and installation details, as

appropriate, for the items listed in paragraph ELECTRICAL EQUIPMENT, MECHANICAL EQUIPMENT, and MISCELLANEOUS EQUIPMENT AND COMPONENTS.”.

SECTION 23 03 00.00 20 – BASIC MECHANICAL MATERIALS AND METHODS

- Delete this Section in its entirety.

SECTION 23 08 00 – COMMISSIONING OF MECHANICAL [AND PLUMBING] SYSTEMS

- Delete this Section in its entirety and replace it with Section 23 08 00 – COMMISSIONING OF MECHANICAL AND PLUMBING SYSTEMS, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS

- PARA 2.1.4 Ethernet Switch, Line 2: Add “and Section 01 35 13.02 34 FACILITY-RELATED CONTROL SYSTEMS PROCUREMENT FOR NAVY.” after “FOR FACILITY-RELATED CONTROL SYSTEMS”.
- PARA 2.2 CONTROL NETWORK WIRING, (b), Line 2: Change “CAT-5e” to “CAT-6”.
- PARA 3.1.2 DDC Hardware: Change “Install all DDC Hardware that connects to an IP network in lockable enclosure. Install other DDC Hardware that is not in suspended ceilings in lockable enclosures. For all DDC hardware with a user interface, coordinate with site to determine proper passwords and configure passwords into device.” to “Install all DDC Hardware that connects to an IP network in lockable enclosure with an alarm input to monitor lockable enclosure door. Install other DDC Hardware that is not in suspended ceilings in lockable enclosures. For all DDC hardware with a user interface, coordinate with site to determine proper passwords and configure passwords into device.”.

SECTION 23 64 26 – CHILLED, CHILLED-HOT, AND CONDENSER WATER PIPING SYSTEMS

- Delete this Section in its entirety and replace it with Section 23 64 26 – CHILLED, CHILLED-HOT, AND CONDENSER WATER PIPING SYSTEMS, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 25 08 10 – CONTROL SYSTEMS UTILITY MONITORING AND CONTROL SYSTEM TESTING

- Delete this Section in its entirety and replace it with Section 25 08 10 – CONTROL SYSTEMS UTILITY MONITORING AND CONTROL SYSTEM TESTING, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 25 10 10 – UTILITY MONITORING AND CONTROL SYSTEM (UMCS) FRONT END AND INTEGRATION

- Delete this Section in its entirety and replace it with Section 25 10 10 – UTILITY MONITORING AND CONTROL SYSTEM (UMCS) FRONT END AND INTEGRATION, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 27 10 00 – BUILDING TELECOMMUNICATIONS CABLING SYSTEM

- PARA. 3.7.1 Labels, Line 1: Add “Guam C4IT labeling scheme,” after “Provide labeling in accordance with”.

SECTION 28 31 76 – INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE

- PARA. 1.9.2.2 Supervisor, Line 1: Delete "NICET Level IV", and replace with "NICET Level III".

SECTION 31 00 00 – EARTHWORK

- PARA. 3.4 SUBGRADE PREPARATION, 5th Paragraph, 1st Line: After "When subgrades", add "encounter unsatisfactory material or".
- PARA. 3.4 SUBGRADE PREPARATION, 5th Paragraph, 2nd Line: Replace "6 inches" with "3 feet or until limestone is reached".

SECTION 31 21 13 – RADON MITIGATION

- Delete this Section in its entirety and replace it with 31 21 13 – RADON MITIGATION, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 32 17 23 – PAVEMENT MARKINGS

- Delete this Section in its entirety.

SECTION 33 52 40 – FUEL SYSTEMS PIPING (NON-HYDRANT)

- Delete this Section in its entirety and replace it with 33 52 40 – FUEL SYSTEMS PIPING (NON-HYDRANT), dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 33 56 10 – FACTORY-FABRICATED FUEL STORAGE TANKS

- Delete this Section in its entirety and replace it with 33 56 10 – FACTORY-FABRICATED FUEL STORAGE TANKS, dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SECTION 33 71 02 – UNDERGROUND ELECTRICAL DISTRIBUTION

- PARA. 3.3 CABLE INSTALLATION PLAN AND PROCEDURE, Line 6: Add "break away swivel rated at factory cable maximum pulling tension," after "pulling tension,".
- PARA. 3.3 CABLE INSTALLATION PLAN AND PROCEDURE, after (k): add "l. Break away swivel rated at factory cable maximum pulling tension.".

SECTION 33 82 00 – TELECOMMUNICATIONS OUTSIDE PLANT (OSP)

- Delete this Section in its entirety and replace it with 33 82 00 – TELECOMMUNICATIONS OUTSIDE PLANT (OSP), dated 04-27-2026. The revised Section accompanies this Amendment, see Attachment (2).

SOLICITATION, OFFER, AND AWARD (Construction, Alteration, or Repair)	1. SOLICITATION NUMBER	2. TYPE OF SOLICITATION	3. DATE ISSUED	PAGE OF PAGES
	N6274226R1306	☐ SEALED BID (IFB) INVITATION FOR BID ☒ NEGOTIATED (RFP) REQUEST FOR PROPOSAL	10 Apr 2026	1 83

IMPORTANT - The "offer" section on the reverse must be fully completed by offeror.

4. CONTRACT NUMBER	5. REQUISITION/PURCHASE REQUEST NUMBER	6. PROJECT NUMBER
		J-875

7. ISSUED BY CODE N62742

NAVFACSYSCOM PACIFIC
258 MAKALAPA DR STE 100, JBPHH HI
96860-3134
JBPHH, HI 96860-3134
UNITED STATES
Jennifer Hue, Email: jennifer.m.hue.civ@us.navy.mil
Telephone: 8086026755

8. ADDRESS OFFER TO

See 00 21 16

9. FOR INFORMATION CALL:	a. NAME	b. TELEPHONE NUMBER *(Include area code) (NO COLLECT CALLS)*
	Jennifer Hue	8086026755

SOLICITATION

NOTE: In sealed bid solicitations "offer" and "offeror" mean "bid and "bidder".

10. THE GOVERNMENT REQUIRES PERFORMANCE OF THE WORK DESCRIBED IN THESE DOCUMENTS *(Title, identifying number, date)*

RFP NO. N62742-26-R-1306, JFY 2022 PROJECT J-875, BATTLE STAFF TRAINING FACILITY, U.S. NAVSUPPACT, MCB CAMP BLAZ, GUAM

GENERAL DESCRIPTION: SEE SPECS 01 11 00, SECTION 1.1.1, Project Description

THIS PROCUREMENT IS UNRESTRICTED. North American Industry Classification System (NAICS) Code 236220, COMMERCIAL AND INSTITUTIONAL BUILDING CONSTRUCTION - Average Annual Receipts for the Past 3 Years - $45M

ESTIMATED COST: BETWEEN $25,000,000 and $100,000,000.

DPAS RATING: DO-C2

ENFORCEABILITY OF PROPOSAL: The proposal must set forth full, accurate and complete information as required by this solicitation. The Government will rely on such information in the award of a contract. The awardee's proposal will be incorporated into the contract and all items proposed will become binding requirements of the contract. By submission of the offer, the offeror agrees that all items proposed (e.g. subcontractors with teaming agreements, etc.) will be utilized for the duration of the contract and any substitutions must be equal or better and will require prior approval by the Contracting Officer.

11. The contractor shall begin performance within 15 calendar days and complete it within 1157 calendar days after receiving

☐ award, ☒ notice to proceed. This performance period is ☒ mandatory ☐ negotiable. ***(See*** 00 73 00 Para 1.3 ***).***

12a. THE CONTRACTOR MUST FURNISH ANY REQUIRED PERFORMANCE AND PAYMENT BONDS? *(If "YES", indicate within how many calendar days after award in Item 12b.)*	12b. CALENDAR DAYS
☒ YES ☐ NO	21

13. ADDITIONAL SOLICITATION REQUIREMENTS:

a. Sealed offers in original and See 00 21 16 copies to perform the work required are due at the place specified in Item 8 by 02:00 PM ***(hour)*** local time 16 Jun 2026 (date). If this is a sealed bid solicitation, offers will be publicly opened at that time. Sealed envelopes containing offers shall be marked to show the offeror's name and address, the solicitation number, and the date and time offers are due.

b. An offer guarantee ☒ is, ☐ is not required.

c. All offers are subject to the (1) work requirements, and (2) other provisions and clauses incorporated in the solicitation in full text or by reference.

d. Offers providing less than 150 calendar days for Government acceptance after the date offers are due will not be considered and will be rejected.

OFFER *(Must be fully completed by offeror)*

14. NAME AND ADDRESS OF OFFEROR *(Include ZIP Code)*

CODE FACILITY CODE

15. TELEPHONE NUMBER *(Include area code)*

16. REMITTANCE ADDRESS *(Include only if different than Item 14.)*

17. The offeror agrees to perform the work required at the prices specified below in strict accordance with the terms of this solicitation, if this offer is accepted by the Government in writing within _____ calendar days after the date offers are due. *(Insert any number equal to or greater than the minimum requirement stated in Item 13d. Failure to insert any number means the offeror accepts the minimum in Item 13d.)*

AMOUNTS ▶

18. The offeror agrees to furnish any required performance and payment bonds.

19. ACKNOWLEDGMENT OF AMENDMENTS

(The offeror acknowledges receipt of amendments to the solicitation -- give number and date of each)

AMENDMENT NUMBER										
DATE										

20a. NAME AND TITLE OF PERSON AUTHORIZED TO SIGN OFFER *(Type or print)*

20b. SIGNATURE

20c. OFFER DATE

AWARD *(To be completed by Government)*

21. ITEMS ACCEPTED:

22. AMOUNT

23. ACCOUNTING AND APPROPRIATION DATA

24. SUBMIT INVOICES TO ADDRESS SHOWN IN *(4 copies unless otherwise specified)* ▶ ITEM

25. OTHER THAN FULL AND OPEN COMPETITION PURSUANT TO THE UNITED STATES CODE AT

☐ 10 U.S.C. 3204(a) ( ) ☐ 41 U.S.C. 3304(a) ( )

26. ADMINISTERED BY

27. PAYMENT WILL BE MADE BY

CONTRACTING OFFICER WILL COMPLETE ITEM 28 OR 29 AS APPLICABLE

☐ 28. NEGOTIATED AGREEMENT *(Contractor is required to sign this document and return _____ copies to issuing office.)* Contractor agrees to furnish and deliver all items or perform all work requirements identified on this form and any continuation sheets for the consideration stated in this contract. The rights and obligations of the parties to this contract shall be governed by (a) this contract award, (b) the solicitation, and (c) the clauses, representations, certifications, and specifications incorporated by reference in or attached to this contract.

☐ 29. AWARD *(Contractor is not required to sign this document.)* Your offer on this solicitation is hereby accepted as to the items listed. This award consummates the contract, which consists of (a) the Government solicitation and your offer, and (b) this contract award. No further contractual document is necessary.

30a. NAME AND TITLE OF CONTRACTOR OR PERSON AUTHORIZED TO SIGN *(Type or print)*

31a. NAME OF CONTRACTING OFFICER *(Type or print)*

30b. SIGNATURE

30c. DATE

31b. UNITED STATES OF AMERICA

BY

31c. DATE

SOLICITATION, OFFER AND AWARD (SF 1442), CONTINUED
PRICE PROPOSAL SCHEDULE
FOR
RFP NO. N62742-26-R-1306
JFY 2022 PROJECT J-875, BATTLE STAFF TRAINING FACILITY,
U.S. NAVSUPPACT MCB CAMP BLAZ, GUAM

ITEM NO.	DESCRIPTION	QTY	UNIT OF ISSUE	UNIT PRICE	AMOUNT
0001AA	**BASE ITEM:** The basis for SLIN 0001AA is the price for all labor, material, and equipment for the entire work for WON 1696746 complete and in accordance with the drawings and specifications but not including work defined in any other Item No.	1	Lump Sum		$_____
0001AB	**BASE ITEM:** The basis for Item No. 0001AB is the price to perform the removal (over-excavation) of soft, yielding, or unsatisfactory soil materials, and the placement of satisfactory fill per Section 31 00 00 for the site work, in place and complete.	1,100	Cubic Yard	$_____/cy	= $_____
0001AC	**BASE ITEM:** The basis for Item No. 0001AC is the price to install Cement Deep Soil Mixing (CDSM) operations for the ground improvements at the site as required per drawings and Section 31 62 00, in place and complete.	7,920	Cubic Yard	$_____/cy	= $_____
				TOTAL Item No 0001 (0001AA through 0001AC)	= $_____
0002	**OPTION ITEM 1:** The basis for Item No. 0002 (OPTION ITEM 1) is the entire work for the pavilion, including site development and utilities as required to support the pavilion, complete and in accordance with the drawings and specifications except work identified in any other Item No.	1	Lump Sum		= $_____
0003	**OPTION ITEM 2:** The basis for Item No. 0003 (OPTION ITEM 2) is the entire work for the Standby Back-up Generator, Generator Building, Fuel Storage Yard, and Sand Filter, including site development and utilities as required to support them, complete and in accordance with the drawings and specifications except work identified in any other Item No. If Option	1	Lump Sum		= $_____

	Item 2 is accepted, the Emergency Generator at Room 130 will not be required.				
0004	**OPTION ITEM 3:** The basis for Item No. 0004 (OPTION ITEM 3) is the entire work for the Security Chain Link Fence, complete and in accordance with the drawings and specifications except work identified in any other Item No.	1	Lump Sum		= $_____
0005AA	**PLANNED MODIFICATION:** Furniture, Fixtures and Equipment (FF&E) and Specialty Collateral Equipment (CEQ). See Note 8.			Gov't Estimated Budget	= $ 3,934,910.00
0005AB	Handling and Administrative Rate (HAR) NTE 5%. See Note 8.			_____ %	= $_____ (DO NOT ROUND)
				TOTAL Item No. 0004 (0004AA + 0004AB)	= $_____

NOTES:

1. The Offeror SHALL include a price for ALL Item Nos. The Government will not adjust the quantities noted in the schedule at time of award (Ref: FAR 52.215-1(f)(5)).

2. Multiple awards will not be made (Ref: FAR 52.215-1(f)(6)).

3. CLINs 0001 through 0004 will be funded with Japan Fiscal Year 2022 funding. It is the Government's objective to award CLINs 0001 and 0004 within the funds available.

4. In accordance with FAR 52.217-5, Evaluation of Options, "[e]xcept when it is determined in accordance with FAR 17.202(b) not to be in the Government's best interests, the Government will evaluate offers for award purposes by adding the total price for the option to the total price for the basic requirement. Evaluation of the option will not obligate the Government to exercise the option." The total of the proposed price for CLINs 0001 through 0005 will form the basis for the evaluation noted in Document 00 22 00.

5. The Government may exercise Option Item 1 (CLIN 0002), Option Item 2 (CLIN 0003), and/or Option Item 3 (CLIN 0004) at the time of award or by written notice to the Contractor within 365 calendar days of contract award. Exercising Option Items 1 (CLIN 0002), 2 (CLIN 0003), and/or 3 (CLIN 0004) will not extend the contract completion date.

6. In the event there is a difference between a unit price and the extended total, the unit price will be held to be the intended offer and the extended total recomputed accordingly. If the offer provides a total but fails to enter a unit price, the total divided by the specified quantity will be held to be the intended unit price.

7. Payment for SLINs 0001AB and 0001AC shall be for actual quantities only. For SLINs 0001AB, the unit prices will be used to adjust the contract price for any increase or decrease in the estimated quantities

subject to Document 00 73 00, Variation in Estimated Quantity. For SLIN 0001AC, refer to Specifications Section 31 62 00, paragraph 1.4.2.

8. The following notes apply to CLIN 0005 for Furniture, Fixtures, and Equipment (FF&E):

   a. **Government Estimated Amount for FF&E and Specialty CEQ**. The Government Estimated Amount for FF&E and Specialty CEQ, as shown above (SLIN 0005AA), includes the material cost, freight, and installation charges. The Government Estimated Amount has been identified to provide Offerors with the projected magnitude of effort for FF&E. The total CLIN 0005 amount shall include all costs to procure, install, and store the Furniture, Fixtures and Equipment, and includes the Prime Contractor's proposed Handling and Administration Rate (HAR).

   b. **Prime Contractor Handling and Administration Rate (HAR)**. Offerors may propose a HAR fee in SLIN 0005AB, up to but not to exceed 5%, for the handling and administration of the FF&E and Specialty CEQ. This fee will account for all administrative costs; overhead; bonding fees, if any; administration of subcontractors; profit; and any other costs associated with and related to the coordination and processing of the procurement and installation of the FF&E and Specialty CEQ. The prime contractor's proposed HAR mark-up will be applied to the Government Estimated Amount to derive a total proposed price for CLIN 0005. In the event of a difference between the proposed HAR and the extended total, the HAR percentage will be held to be the intended offer and the total recomputed accordingly.

   c. The prime contractor's HAR percentage rate will be incorporated into the contract as proposed and will not be adjusted regardless of fluctuations in the Government Estimated Amount. The HAR is a fixed percentage rate that will be utilized in calculating the final price for the planned modification. When the final FF&E Package and Specialty CEQ Package is priced, the contractor's proposed HAR percentage rate, as incorporated into the contract, will be applied to the selected supplier/vendor's quote to arrive at a total proposed price for final negotiation of the planned modification.

   d. It is anticipated that a planned modification will be awarded at least six months prior to the completion of the work. The planned modification will be issued after the receipt of appropriate funding. A minimum of six months is required for the contractor to purchase, deliver, and install the FF&E and Specialty CEQ without impacting the overall completion date of the project. No schedule extension will be granted if the planned modification is awarded at least six months prior to the contract completion date. If the Government decides to negotiate and award the planned modification less than six months prior to the contract completion date, the contractor may be entitled to a contract extension.

9. **DFARS 252.247-7023, TRANSPORTATION OF SUPPLIES BY SEA.** Within 30 days of each shipment, the Contractor is required to provide an electronic copy of the carrier's bill of lading to the Contracting Officer and to MARAD via email. MARAD email: Cargo.MARAD@dot.gov (attn.: MIL team). In addition, the Contractor shall notify the Contracting Officer when oceanic shipments have been initiated within 3 working days of shipment.