BID SCHEDULE

REMOVE/REPLACE ASPHALT SHINGLE ROOF AND GUTTERS ON BLUFFS SEASONAL AND PERMANENT HOUSING BUILDINGS (B034, B035)

REMOVE/REPLACE ASPHALT SHINGLE ROOF BUILDINGS (B034,B035)

1. Remove and dispose of the existing asphalt shingle roof(s) and roofing underlayment off site
2. Protect the building structures and contents from weather and other potentially damaging elements
3. Inspect the existing roof supports (rafters) and fascia boards, replace damaged facia boards
4. Repair or replace in kind as necessary damaged roof supports (rafters), decking, sheathing revealed by inspection
5. Replace in kind all existing flashing
6. Install new 30 pound asphalt saturated roofing underlayment or synthetic underlayment;
7. Install new dark gray 30 year architectural shingles with interlocking tabs
8. Install new drip edges around the entire perimeter of the roof
9. Install full length ridge cap(s) roof vent system
10. Install new waterproof vent collars
Total: $

REMOVE/REPLACE GUTTERS ON BLUFFS SEASONAL AND PERMANENT HOUSING BUILDINGS (B034, B035)

1. Remove and replace approximately 420 linear feet of gutter and associated downspouts on buildings B034, B035
2. Replace any damaged fascia boards behind the gutters on B034 and B035 before new gutters are installed, fascia must be in-kind to match with remainder of building fascia.
3. Install gutter guards on all gutters
Total: $