900 North 400 West, Suite 11
North Salt Lake, UT 84054
Toll Free: 888-586-5654

Site Readiness Verification Form – GWT Series Equipment

GWT Site Requirements:

- **Water (Domestic) Feed:**
  - ¾" Supply/feed line per system
    - ¾" dedicated line per system
    - ¾" FNPT ball valve connection from each drop
  - Minimum 50 PSI line pressure
  - Pressure gauge upstream side of ball valve connection for verification at all times
- **Drainage:**
  - Floor drain near system (6 ft or closer preferred)
  - Drain capacity of 3 g/m flow recommended (equipment draining at approximately 300-350 l/h)
  - Client will indicate if water must be pumped to drain
- **Power:**
  - Dedicated 120 VAC/20 AMP
  - Surge protection: 2000 Joules +
  - Duplex receptacle per unit

Client must confirm proof of site readiness items via photo attestation to service@genwater.com or brady@genwater.com. For future installations, equipment will not be shipped until readiness has been verified.