FINISH PLAN KEYNOTES

1. EDGE OF WALL TILE TO ALIGN WITH EDGE OF FLOOR TILE.
2. PROVIDE TILE TERMINATION STRIP (TS-5) AT TOP EDGE OF TILE BASE.
3. COORDINATE WITH RESTROOM ELEVATIONS FOR EXTENT OF FINISHES.
4. INSTALL TILE UP TO 4'-0" A.F.F. ON WALLS AS NOTED. SEE ELEVATION.

FINISH PLAN LEGEND & SHEET NOTES

FLOORING TYPES LEGEND

LVT -1	LUXURY VINYL TILE	
LVT-1	LUXURY VINYL TILE HERRINGBONE INSTALL *NOTE: PATTERN NOT TO SCALE	
SV-1	SHEET VINYL ROLL	
CPT-1	CARPET TILE	
ATHL-1	ATHLETIC FLOORING	
T-1	PORCELAIN TILE	
QT-1	QUARRY TILE	
SC-1	SEALED CONCRETE	
SC-2	STATIC DISSIPATIVE SEALED CONCRETE	
WM-1	WALK-OFF MAT	
	TRANSITION STRIP	
	FLOORING ORIENTATION	
	WINDOW SHADES	

GENERAL SHEET NOTES

1. ALL NEW INTERIOR PARTITIONS SHALL BE PAINTED PT-1 & B-1 SHALL BE INSTALLED UNLESS OTHERWISE NOTED.
2. PROVIDE FINGER GUARDS (FG-1) AT HINGES ON ALL INTERIOR DOORS AND EXTERIOR DOORS UP TO 48". AT ACTIVITY ROOMS, FINGER GUARDS SHALL BE INSTALLED ON ACTIVITY ROOM SIDE.
3. BULLNOSE CORNER GUARDS (CG-1) SHALL BE INSTALLED AT ALL OUTSIDE CORNERS OF INTERIOR WALLS THROUGHOUT THE FACILITY, U.N.O.
4. ALL FLOORING FINISH CHANGES TO OCCUR AT CENTERLINE OF CLOSED DOOR, U.N.O.
5. PROPERLY PREPARE, SPACKLE, SAND, ETC. ALL GWB WALLS AND CEILINGS TO PROVIDE A SMOOTH SURFACE RREADY FOR PRIMER AND PAINT TO ACHIEVE A LEVEL 4 DRYWALL FINISH, U.N.O.
6. PROVIDE ONE (1) COAT PRIMER AND TWO (2) COATS PAINT ON ALL SURFACES SCHEDULED TO RECEIVE PAINT.
7. ALL PAINTS, SEALANTS, MASTICS, AND ADHESIVES SHALL BE LOW-VOC.
8. WALL PAINT TO BE EGGSHELL FINISH, U.N.O. CEILING PAINT TO BE FLAT FINISH.
9. REFER TO DOOR SCHEDULE FOR DOOR AND TRIM FINISHES.
10. ALL FINISHES OF CEILING MOUNTED SPRINKLERS, SPEAKERS, ETC. SHALL MATCH THE ADJACENT CEILING COLOR.
11. ALL COVER PLATES, SWITCHES (TOGGLES, SLIDES, ETC.), RECEPTACLES, AND NETWORK CONNECTIONS TO BE WHITE, U.N.O.
12. EXAMINE ALL FINISHES AT THE COMPLETION OF WORK IN AN AREA AND PROCEED WITH TOUCH-UP AS NECESSARY.
13. REMOVE ALL PAINT OR STAIN SPILLED, SPLATTERED, OR SPLASHED ON ADJACENT SURFACES.
14. ALL WORK WHICH IS JUDGED TO BE UNSATISFACTORY BY THE ARCHITECT WILL BE REJECTED AND REPAIRED TO THE SATISFACTION OF THE OWNER, AT NO ADDITIONAL COST TO THE OWNERS.
15. WATER RESISTANT GYPSUM WALLBOARD SHALL BE INSTALLED AT ALL WALLS SCHEDULED TO RECEIVE WALL TILE.
16. USE EDGE PROTECTION PROFILE AT EXPOSED DRYWALL CORNERS.
17. ALL TILE GROUT JOINTS TO BE 1/8".
18. INSTALL PRE-FORMED INSIDE AND OUTSIDE VINYL WALL BASE.
19. SCRIBE ALL COUNTERS TO WALL. CAULK TO MATCH WALL COLOR.
20. WALL TILE IN ALL TOILET AREAS (T-2) SHALL BE 48" A.F.F.WITH (T-2B) AT TOP ROW. PROVIDE WALL TILE TERMINATION STRIP (TS-7) AT ALL EXPOSED TILE EDGES.
21. PROVIDE BULLNOSE CORNER TRIM (TS-7) AT ALL OUTSIDE CORNERS SCHEDULED TO RECEIVE WALL TILE.
22. PROVIDE DOOR THRESHOLD AT ALL EXTERIOR DOORS, COORDINATE WITH ARCHITECTURE.

MATCHLINE SEE A1/IF102

INFANT/PRE-TODDLER ACTIVITY RM 01 111 · STORAGE 111B · EXT STORAGE 121 · INFANT/PRE-TODDLER ACTIVITY RM 02 115 · STORAGE 112B · EXT STORAGE 121 · STORAGE 115B · CCTV EQUIPMENT 117 · TOILET 01 113 · BUGGY STORAGE 003A · CORRIDOR 003 · PRESCHOOL/PRE-K ACTIVITY RM 01 132 · PRESCHOOL/PRE-K ACTIVITY RM 02 130

NURSING MOTHERS RM 107 · INFANT/PRE-TODDLER ACTIVITY RM 03 109 · STORAGE 105B · EXT STORAGE 119 · INFANT/PRE-TODDLER ACTIVITY RM 04 105 · STORAGE 103B · STAFF LOUNGE 103 · TRAINING RM 101 · STROLLER/ CAR SEAT STORAGE 000D · STORAGE 101A · VESTIBULE 001 · ISOLATION AREA 000A · ISO TOILET 000B · JANITOR CLOSET 106 · COMMUNICATIONS 100 · RECEPTION 002 · OPEN OFFICE AREA 004 · ASSISTANT DIRECTORS OFFICE 104 · STORAGE 004B · WAITING AREA 002 · DIRECTORS OFFICE 102 · PUBLIC TOILET 000B

E7 IN501

MATCHLINE SEE A1/IF102

1 PARTIAL INTERIOR FINISH PLAN - AREA A

SCALE: 3/16" = 1'-0"

4 0 4 8

SCALE: 3/16" = 1'-0"

PLAN NORTH

A | B

US Army Corps of Engineers ®

MARK	DESCRIPTION	DATE
	60% SUBMISSION	03/27/2024
	35% SUBMISSION	04/03/2023
	30% SUBMISSION	02/15/2023

File Path: C:\Users\SHERDocuments\PH-CDC-DMM-FT.E_Rachel.Sierra.rvt

Plot Date: 10/29/2025 11:51:02 AM

ISSUE DATE: AUGUST 29, 2025
SOLICITATION NO.: W912DS24F0031
CONTRACT NO.: W912DS18D0060

DESIGNED BY: RS
DRAWN BY: RS
CHECKED BY: C. C.
SUBMITTED BY:
SIZE: ANSI D

US ARMY CORPS OF ENGINEERS
NEW YORK DISTRICT
26 FEDERAL PLAZA, NEW YORK, NY 10278

CHILD DEVELOPMENT CENTER
USAG FORT HAMILTON, NEW YORK
PROJECT NO. 75662

INTERIOR FINISH PLAN - AREA A

SHEET ID
IN101