Amendment 0001

07 JUNE 2026

1) In PART 3, 2.1 APPLICABLE CODES AND STANDARDS: Page 2:

Add the following:

"**SECURITY REFERENCES**

ICD/ICS 705 Ver 1.5.1
ICS 705-1
ICS 705-02
CNASSAM TEMPEST/1-13
DoDM 5200.01-V3
SECNAVINST 5510.36B
UFC 4-010-05 CH-1
DODM 5205.07-V3"

2) In PART 3, 2.1 2.4 CYBERSECURITY: Page 2:

Add the following:

CRITICALITY OF CONTROL SYSTEM TYPE

Mechanical/DDC: Mission Support: L-L-L
FLS (Fire Life and Safety): None
ESS: Mission Support: L-L-L
Electrical (Transformer/Lighting): Mission Support: L-L-L

The Contractor provides deliverables as defined in UFC 4-010-06 and UFGS 25 05 11 including hygiene checklist.

3) In PART 3, D3040 DISTRIBUTION SYSTEMS AND D3050 TERMINAL & PACKAGED UNITS, DEMOLITION: Page 16:

Delete the following:

CHART W226 - Remove and save in undamaged condition existing linear supply diffuser for reinstallation in new ceiling. Remove and save in undamaged condition existing return air grille for reinstallation in new ceiling.

Add the following:

Demolish VAV-35W low pressure supply ductwork from box complete including supports and linear supply diffuser.

Amendment 0001

07 JUNE 2026

4) In PART 3, D3040 DISTRIBUTION SYSTEMS AND D3050 TERMINAL & PACKAGED UNITS, DEMOLITION: Page 17:

Delete the following:

CHART E226 - Remove and save in undamaged condition existing linear supply diffuser for reinstallation in new ceiling. Remove and save in undamaged condition existing return air grille for reinstallation in new ceiling.

Add the following:

Demolish VAV-35W low pressure supply ductwork from box complete including supports and linear supply diffuser.

Delete the following:

AHARED CONTROLLED AREA SPACE E227 - Remove and save in undamaged condition existing linear supply diffuser for reinstallation in new ceiling. Remove and save in undamaged condition existing return air grille for reinstallation in new ceiling.

Add the following:

Demolish VAV-34E low pressure supply ductwork from box complete including supports and linear supply diffuser.

5) **Add the following:**

1. NAS Building 145 As-Built Drawings in pdf.
2. NAS Building 145 Fire Alarm As-Built in pdf
3. NAS Building 145 Fire Alam Shop Drawings
4. NAS Building 145 Fire Pump Test Full Report in pdf

6) UNIT PRICING for ESS to issued at a later date as Amendment 0002.

End of Amendment 0001