Attachment #1

Schedule of Items for Boulder Grazing Complex Fencing
Colville National Forest/Three Rivers Ranger District
02/19/2026

Item Number	Description	Estimated Quantity (ft.)	Estimated Unit Price Per Ft ($)	Estimated Total Amount ($)
#1, 2013 Boulder Grazing Complex, Creation of new Bulldog/Cabin Pasture 48.848776, -118.347851 **0.5 miles**	Clearing the fence Right of Way (ROW) of trees and brush at 6ft either side of the fence for a total of 12ft.	2,640 Feet		
	Remove and dispose of damaged or unusable existing fence material.	2,640 Feet		
	Provide all material need to construct new 4 strand fence.	2,640 Feet		
	Construct new 4 strand barb wire/steel post fence.	2,640 Feet		
Segment #1 Total Cost				

Item Number	Description	Estimated Quantity (ft.)	Estimated Unit Price Per Ft. ($)	Estimated Total Amount ($)
#2, 2013 Boulder Grazing Complex, Bulldog/Renner Drift Fence 48.821056, -118204548 **0.25 miles**	Clearing the fence Right of Way (ROW) of trees and brush at 6ft either side of the fence for a total of 12ft.	1,320 Feet		
	Remove and dispose of damaged or unusable existing fence material.	1,320 Feet		
	Provide all material need to construct new 4 strand fence.	1,320 Feet		
	Construct new 4 strand barb wire/steel post fence.	1,320 Feet		
Segment #2 Total Cost				

Item Number	Description	Estimated Quantity (ft.)	Estimated Unit Price Per Ft. ($)	Estimated Total Amount ($)
#3, 2013 Boulder Complex, West Boundary Drift Fence, Snowcap Allotment 48.862060, -118.439611 **0.5 miles**	Clearing the fence Right of Way (ROW) of trees and brush at 6ft either side of the fence for a total of 12ft.	2,640 Feet		
	Remove and dispose of damaged or unusable existing fence material.	2,640 Feet		
	Provide all material need to construct new 3 strand fence.	2,640 Feet		
	Construct new 3 strand barb wire/steel post fence.	2,640 Feet		
Segment #3 Total Cost				

Total Cost of Contract Proposal by Segment

Segment #1 Total Cost	
Segment #2 Total Cost	
Segment #3 Total Cost	

Total Cost of Contract Proposal = $42,042.00