Attachment 3

Below are the estimated quantities associated with services required. Vendors are required to verify the below during site visit.

Item	Description	Part Number	Unit	Qty
1	**Damaged exterior Granite tile removal and ...** Damaged exterior Granite tile removal and installation ST-3 MG4 Ghibli Grey Granite (Color finish /polished) Size: 27.5-inch x 18-inch 12 mm		each	10

Item	Description	Part Number	Unit	Qty
2	**Exterior Floor pavers / tough tile about 1000...** Exterior Floor pavers / tough tile about 1000 sq ft area. 9Grey color) Tile / paver size:18-inch x 12 inch		square foot	2,500

Item	Description	Part Number	Unit	Qty
3	**Exterior ceiling light fixtures replacement ...** Exterior ceiling light fixtures replacement with LEDs.		each	25

Item	Description	Part Number	Unit	Qty
4	**Exterior ceiling Dry wall/ cement board ...** Exterior ceiling Dry wall/ cement board removal and replacement. Cement Board size: 4ft x 8 ft x 3/4 inch		square foot	800

Item	Description	Part Number	Unit	Qty
5	**Exterior floor red Boston pavers red color.** **...** Exterior floor red Boston pavers red color. paver size: 5-inch x 8 inch		square foot	250

Item	Description	Part Number	Unit	Qty
6	**Damaged exterior Granite tile removal and ...** Damaged exterior Granite tile removal and installation ST-2 MG4 Ghibli Grey Granite (Color finish /polished) Size: 15-inch x 18.7 inch		each	10

Item	Description	Part Number	Unit	Qty
7	**Damaged exterior Granite tile removal and ...** Damaged exterior Granite tile removal and installation ST-3 MG4 Ghibli Grey Granite (Color finish /polished) Size: 607mm x 90 mm		each	14

Item	Description	Part Number	Unit	Qty
8	**Exterior Floor pavers / tough tile (Red color...** Exterior Floor pavers / tough tile (Red color) Square Red paver size:12-inch x 12 inch		each	200

Item	Description	Part Number	Unit	Qty
9	**Exterior celling paint finish work with ...** Exterior celling paint finish work with material. Manufactur er: ICI /Jotun Matt finish exterior weather shield. off-white color.		square foot	800