Continuation Sheet – Modification "A"

eProjects Work Order Number: 1894552

Construction Contract Number: --

Building: --

Project Title: **FY 26 Marine Corps Barracks – Repair by Replacement MCB Camp Lejeune – French Creek, Jacksonville, NC**

Date: **23 April 2026**

PART 2 – GENERAL REQUIREMENTS:

REVISE the following sections:

Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS

1.5.1.1.1.2 Surplus Soils Disposal for Camp Lejeune and MCAS New River

REPLACE the following language:

Remove: "Soil should be reused on its originating construction footprint. As there are currently no regulations regarding management and disposal of PFAS-impacted soil, all PFAS-impacted media should be managed so as to minimize the future impacts to the environment, should they become regulated. If PFAS-impacted soil needs to leave the originating site…"

Replace with: "Anticipate that all surplus soil media is contaminant impacted (including but not limited to PFAS/PFOA, petroleum, metals, VOC's, and PAH's) and must be disposed of at a licensed, permitted facility that accepts PFAS impacted soil media. It must be properly characterized…"

3.3.1 Cofferdams, Diversions, and Dewatering

REPLACE the following language:

Remove: "All construction dewatering effluent must be anticipated to be PFAS impacted and sampled, tested, and treated to no-detect levels."

Replace with: "Anticipate that all construction dewatering effluent is contaminant impacted (including but not limited to PFAS/PFOA, petroleum, metals, VOC's and PAH's) and must be treated to non-detect levels prior to discharge into an existing vegetated swale at a location approved by the Contracting Officer."

PART 3B – PROJECT PROGRAM:

REVISE the following:

REPLACE all occurrences of 'UFC 3-600-10N' with UFC 3-600-01, *Fire Protection Engineering for Facilities*.

2.6 Special Design Challenges

Replace the first sentence of 'Additional Building Commissioning Requirements' with: "The Government will provide details in a revised Section 01 91 00.15 22 Total Building Commissioning (currently in Part 2 of this RFP) as design progresses; no additional coordination effort by the contractor is anticipated."

G201090 OTHER ROADWAYS

Replace "…in accordance with the requirements of ESR Section D4090…" with "in accordance with the requirements of UFC 3-600-01…"

Remove "…must accommodate two fire truck trips every month and…"