SECTION 07 22 00

ROOF AND DECK INSULATION

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C1177/C1177M	(2013) Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing
ASTM C1289	(2016a) Standard Specification for Faced Rigid Cellular Polyisocyanurate Thermal Insulation Board
ASTM C208	(2012) Cellulosic Fiber Insulating Board
ASTM C552	(2016a) Standard Specification for Cellular Glass Thermal Insulation
ASTM C578	(2016) Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation
ASTM C726	(2017) Standard Specification for Mineral Wool Roof Insulation Board
ASTM C728	(2017) Standard Specification for Perlite Thermal Insulation Board
ASTM D2178/D2178M	(2015a) Asphalt Glass Felt Used in Roofing and Waterproofing
ASTM D226/D226M	(2009) Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing
ASTM D312	(2000; R 2006) Standard Specification for Asphalt Used in Roofing
ASTM D41/D41M	(2011; R 2016) Standard Specification for Asphalt Primer Used in Roofing, Dampproofing, and Waterproofing
ASTM D4263	(1983; R 2012) Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D4586/D4586M	(2007; E 2012; R 2012) Asphalt Roof Cement, Asbestos-Free
ASTM D4601/D4601M	(2004; R 2012) Asphalt-Coated Glass Fiber Base Sheet Used in Roofing

ASTM D4897/D4897M	(2016) Standard Specification for Asphalt-Coated Glass-Fiber Venting Base Sheet Used in Roofing
ASTM E84	(2016) Standard Test Method for Surface Burning Characteristics of Building Materials

FM GLOBAL (FM)

FM 4450	(1989) Approval Standard for Class 1 Insulated Steel Deck Roofs
FM 4470	(2010) Single-Ply, Polymer-Modified Bitumen Sheet, Built-up Roof (BUR), and Liquid Applied Roof Assemblies for Use in Class 1 and Noncombustible Roof Deck Construction
FM APP GUIDE	(updated on-line) Approval Guide http://www.approvalguide.com/

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2015) International Building Code

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 1	(2015; ERTA 2015) Fire Code

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS)Indoor Advantage

UNDERWRITERS LABORATORIES (UL)

UL 1256	(2002; Reprint Jul 2013) Fire Test of Roof Deck Constructions
UL 2818	(2013) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Insulation Board Layout and Attachment; G

Verification of Existing Conditions; G

SD-03 Product Data

Insulation; G

Cover Board; G

Fasteners; G

Sheathing Paper; G

Moisture Control; G

SD-06 Test Reports

Flame Spread Rating; G

SD-07 Certificates

Volatile Organic Compounds (VOC) Content; G

Installer Qualifications; G

Certificates Of Compliance For Felt Materials; G

SD-08 Manufacturer's Instructions

Nails and Fasteners; G

Roof Insulation; G

SD-11 Closeout Submittals

Volatile Organic Compounds (VOC) Content; S

1.3 SHOP DRAWINGS

Submit insulation board layout and attachment indicating methods of attachment and spacing, transitions, tapered components, thicknesses of materials, and closure and termination conditions. Show locations of ridges, valleys, crickets, interface with, and slope to, roof drains. Base shop drawings on verified field measurements and include verification of existing conditions..

1.4 PRODUCT DATA

Include data for material descriptions, recommendations for product shelf life, requirements for cover board or coatings, and precautions for flammability and toxicity. Include data to verify compatibility of sealants with insulation.

1.5 MANUFACTURER'S INSTRUCTIONS

Include field of roof and perimeter attachment requirements.

Provide a complete description of installation sequencing for each phase of the roofing system. Include weatherproofing procedures.

1.6 QUALITY CONTROL

Provide certification of installer qualifications from the insulation manufacturer confirming the specific installer has the required

qualifications for installing the specific roof insulation system(s) indicated.

Provide certificates of compliance for felt materials.

1.7 FM APPROVAL REQUIREMENTS

Provide fastening patterns in accordance with FM 1-90 for insulation on steel decks.

1.8 FIRE PERFORMANCE REQUIREMENTS

1.8.1 Insulation in Roof Systems

Comply with the requirements of ICC IBC or UL 1256 or FM 4470. Roof insulation to have a flame spread rating of 75 or less when tested in accordance with ASTM E84. Additional documentation of compliance with flame spread rating is not required when insulation of the type used for this project as part of the specific roof assembly is listed and labeled as FM Class 1 approved.

1.8.2 Fire Resistance Ratings for Roofs

Provide in accordance with ICC IBC Chapter 7 and Table 721.1(3) Min Fire and Smoke Protection For Floor and Roof Systems.

1.9 CERTIFICATIONS

Provide products that are third party certified for low Volatile Organic Compounds (VOC) Content in accordance with UL 2818 Greenguard , SCS Scientific Certification Systems Indoor Advantage .(http://www.scsglobalservices.com/indoor-air-quality-certification)

1.10 DELIVERY, STORAGE, AND HANDLING

1.10.1 Delivery

Deliver materials to the project site in manufacturer's unopened and undamaged standard commercial containers bearing the following legible information:

a. Name of manufacturer

b. Brand designation

c. Specification number, type, and class, as applicable, where materials are covered by a referenced specification

d. Asphalt flashpoint (FP), equiviscous temperature (EVT), and finished blowing temperature (FBT).

Deliver materials in sufficient quantity to allow continuity of the work.

1.10.2 Storage and Handling

Store and handle materials in accordance with manufacturer's printed instructions as well as the Tinker AFB Standards. Protect from damage, exposure to open flame or other ignition sources, wetting, condensation, and moisture absorption. Keep materials wrapped and separated from

off-gassing materials (such as drying paints and adhesives). Store all material under tarps with adequate weight to keep the tarps in place. Material for the project must not be used as weight. Do not use materials that have visible moisture, warping or biological growth. All material we shall be newley purchesed for Store in an enclosed building or trailer that provides a dry, adequately ventilated environment. Store felt rolls and roll goods on ends. For the 24 hours immediately before application of felts, store felts in an area maintained at a temperature no lower than 50 degrees F above grade and having ventilation on all sides. Replace damaged material with new material.

1.11 ENVIRONMENTAL CONDITIONS

Do not install roof insulation during inclement weather or when air temperature is below 40 degrees F and interior humidity is 45 percent or greater, or when there is visible ice, frost, or moisture on the roof deck.

1.12 PROTECTION

Provide protection as specified in Tinker Facility Satandards.

1.12.1 Flame Heated Equipment

1.12.1.1 Fire Protection

Locate melt kettles no closer than 25 feet from buildings or combustible materials. Provide and maintain two approved 4-A:40-B:C fire extinguishers within 25 feet of each operating kettle. Fire extinguishers, operations and locations must comply with NFPA 1 Section Tar Kettles. Equip asphalt (tar) kettles with tight fitting lids.

1.12.1.2 Operational Requirements

Equip kettles with automatic thermostatic control capable of maintaining asphalt temperature. Calibrate and maintain controls in working order for the duration of the work. Equip kettles with means of agitation and ensure they are operating as necessary to produce a controlled uniform temperature throughout kettle contents to prevent spot heating. Do not heat contents above flash point. Do not place flame heated equipment on the roof.

1.12.2 Special Protection

All insulation shall have the factory applied protective plastic and shall be covered with a tarp at all times. Tarp shall be free of holes and shall be anchored to prevent uncovering during inclement weather. All loose insulaiton shall be recovered with plastice wrap and covered with a tarp.

1.12.3 Drippage of Bitumen

Seal joints in and at edges of deck as necessary to prevent drippage of asphalt into the building or onto adjacent surfaces.

1.12.4 Completed Work

Cover completed work with cover board for the duration of construction. Avoid traffic on completed work particularly when ambient temperature is above 80 degrees F. Replace crushed or damaged insulation prior to roof

surface installation.

PART 2 PRODUCTS

2.1 PRODUCT SUSTAINABILITY CRITERIA

Where allowed by performance criteria:

2.1.1 Reduce Volatile Organic Compounds (VOC) Contents

Provide products with reduced VOC content and provide documentation in accordance with Section 01 33 29 SUSTAINABILITY REPORTING paragraph REDUCE VOLATILE ORGANIC COMPOUNDS.

2.1.2 Recycled Content

Provide products with recycled content and provide documentation in accordance with Section 01 33 29 SUSTAINABILITY REPORTING paragraph RECYCLED CONTENT.

2.2 INSULATION

2.2.1 Insulation Types

Provide one, or an assembly of a maximum of three, of the following roof insulation materials. Provide roof insulation that is compatible with attachment methods for the specified insulation and roof membrane.

a. Expanded Perlite Board: Provide in accordance with ASTM C728. Minimum 3/4 inch thick when both top and bottom surfaces must be in contact with asphalt.

b. Polyisocyanurate Board: Provide in accordance with ASTM C1289 REV A Type II, fibrous felt or glass mat membrane both sides, except minimum compressive strength of 20 pounds per square inch (psi).

c. Composite Boards: Provide in accordance with ASTM C1289 REV A, Type III, perlite insulation board faced on one side with fibrous felt or glass fiber mat membrane on opposite side.

d. Cellular Glass Boards: ASTM C552, Type IV.

2.2.2 Mineral Fiber Insulation Board

Provide in accordance with ASTM C726.

2.2.3 Recycled Materials

Provide thermal insulation materials containing recycled content in accordance with paragraph PRODUCT SUSTAINABILITY CRITERIA. Unless specified otherwise, the minimum required recycled content for listed materials are:

Perlite Composition Board:	75 percent postconsumer paper
Polyisocyanurate/polyurethane:	9 percent recovered material

Wood Fiberboard:	100 percent recovered material
Cellular Glass Insulation:	75 percent recovered content
Structural Fiberboard:	100 percent recovered content
Fiberglass Insulation:	25 percent recovered content
Fiber (felt) or Fiber composite:	75 percent recovered content
Rubber:	90 percent recovered content
Plastic or Plastic/Rubber composite:	90 percent recovered content
Wood/Plastic Composite:	90 percent total recovered content

2.2.4 Insulation Thickness

As necessary to provide the thermal resistance (R-value) indicated for average thickness of tapered system. Base calculation on the R-value for aged insulation. For insulation over steel decks, satisfy both specified R-value and minimum thickness for width of rib opening recommended in insulation manufacturer's published literature.

2.2.5 Tapered Roof Insulation

One layer of the tapered roof insulation assembly must be factory tapered to a slope of not less than one in 1/4 inch per foot. Factory fabricate mitered joints from two diagonally cut boards or one board shaped to provide required slopes.

2.2.6 Cants and Tapered Edge Strips

Provide preformed cants and tapered edge strips of the same material as the roof insulation. When unavailable, provide pressure-preservative treated wood, wood fiberboard, or rigid perlite board cants and edge strips as recommended by the roofing manufacturer for the specific application, unless otherwise indicated. Face of cant strips to incline at 45 degrees with a minimum vertical height of 4 inches. Taper edge strips at a rate of one to 1 1/2 inch per foot down to approximately 1/8 inch thick.

2.3 COVER BOARD

For use as a thermal barrier (underlayment), fire barrier (overlayment), or cover board for hot-mopped, torched-down, or adhesive-applied roofing membrane over roof insulation.

2.3.1 Glass Mat Gypsum Roof Board

ASTM C1177/C1177M, 0 Flame Spread and 0 Smoke Developed when tested in accordance with ASTM E84, 500 psi, Class A, non-combustible, 1/2 inch thick, 4 by 8 feet board size.

2.4 BITUMENS

2.4.1 Asphalt Primer

Provide in accordance with ASTM D41/D41M.

2.4.2 Asphalt

Provide in accordance with ASTM D312, Type III or IV. Asphalt flash point, finished blowing temperature, and equiviscous temperature (EVT) for mop and mechanical spreader application must be indicated on each container.

2.4.3 Asphalt Roof Cement

Provide in accordance with ASTM D4586/D4586M, Type I, for horizontal surfaces and surfaces sloped from 0 to 3 inches per foot. Type II for vertical and surfaces sloped more than 3 inches per foot.

2.5 SHEATHING PAPER FOR WOOD DECKS

Rosin-sized building paper or unsaturated felt weighing not less than 5 pounds per 100 square feet.

2.6 MOISTURE CONTROL

2.6.1 Vapor Retarder

2.6.1.1 Asphalt Saturated Felt Base Sheet for Single Layer Application

Provide in accordance with ASTM D4601/D4601M, weighing not less than 35 pounds per 100 square feet.

2.6.1.2 Asphalt-Coated Glass Felt

Provide in accordance with ASTM D2178/D2178M, Type IV .

2.6.2 Ventilating Felt for Poured Concrete Decks

Provide in accordance with ASTM D4897/D4897M, Type II, non-perforated, with spot mopping holes where specified.

2.6.3 Organic Roofing

Provide in accordance with ASTM D226/D226M, Type I.

2.7 FASTENERS

Provide flush-driven fasteners through flat round or hexagonal steel or plastic plates. Provide zinc-coated steel plates, flat round not less than 1 3/8 inch diameter, hexagonal not less than 28 gage. Provide high-density plastic plates, molded thermoplastic with smooth top surface, reinforcing ribs and not less than 3 inches in diameter. Fully recess fastener head into plastic plate after it is driven. Form plates to prevent dishing. Do not use bell or cup shaped plates. Provide fasteners in accordance with insulation manufacturer's recommendations for holding power when driven, or a minimum of 120 pounds each in steel deck, whichever is the higher minimum. Provide fasteners for steel or concrete decks in accordance with FM APP GUIDE (http://www.approvalguide.com/) for

Class I roof deck construction, and spaced to withstand uplift pressure of 90 pounds per square foot.

2.7.1 Roofing Nails for Wood Decks

Barbed 11 gage, zinc-coated nails with 7/16 to 5/8 inch diameter heads or annular ring shank, square head, one piece composite nails. Provide nails long enough to penetrate wood deck at least 5/8 inch without protruding through underside of decking.

2.7.2 Fasteners for Plywood Decks

Annular ring shank, square head, one piece composite nails long enough to penetrate into plywood decks approximately 1/2 inch without protruding through underside of decking.

2.7.3 Fasteners for Steel Decks

Approved hardened penetrating fasteners or screws in accordance with FM 4450 and listed in FM APP GUIDE for Class I roof deck construction. Quantity and placement to withstand a minimum uplift pressure of 90 psf in accordance with FM APP GUIDE.

2.7.4 Fasteners for Poured Concrete Decks

Approved hardened fasteners or screws to penetrate deck at least 1 inch but not more than 1 1/2 inches, in accordance with FM 4470, and listed in FM APP GUIDE for Class I roof deck construction. Quantity and placement to withstand an uplift pressure of 90 psf in accordance with FM APP GUIDE.

2.8 WOOD NAILERS

Pressure-preservative treated as specified in Section 06 10 00 ROUGH CARPENTRY.

PART 3 EXECUTION

3.1 EXAMINATION AND PREPARATION

3.1.1 Surface Inspection

Ensure surfaces are clean, smooth, and dry prior to application. Ensure surfaces receiving vapor retarder are free of projections that might puncture the vapor retarder. Check roof deck surfaces, including surfaces sloped to roof drains and outlets, for defects before starting work.

The Contractor must inspect and approve the surfaces immediately before starting installation. Prior to installing vapor retarder ventilating felt insulation, perform the following:

a. Examine wood decks to ascertain that deck boards have been properly nailed and that exposed nail heads have been set.

b. Examine steel decks to ensure that panels are properly secured to structural members and to each other and that surfaces of top flanges are flat or slightly convex.

c. Examine precast concrete decks to ensure that joints between precast units are properly grouted and leveled to provide suitable surfaces

for installation of ventilating felt vapor retarder and insulation.

d. In the presence of the Contracting Officer perform the following surface dryness test on concrete substrates:

(1) Foaming: When poured on the deck, one pint of asphalt when heated in the range of 350 to 400 degrees F, does not foam upon contact.

(2) Strippability: After asphalt used in the foaming test application has cooled to ambient temperatures, test coating for adherence. Should a portion of the sample be readily stripped clean from surface, do not consider surface to be dry and do not start application. Should rain occur during application, stop work and do not resume until surface has been re-tested by method above and found dry.

e. Prior to installing any roof system on a concrete deck, moisture test the deck in accordance with ASTM D4263. The deck is acceptable for roof system application when there is no visible moisture on underside of plastic sheet after 24 hours.

3.1.2 Surface Preparation

Correct defects and inaccuracies in roof deck surface to eliminate poor drainage from hollow or low spots, perform the following:

a. Provide wood nailers of the same thickness as the insulation at eaves, edges, curbs, walls, and roof openings for securing of cant strips, gravel stops, gutters, and flashing flanges. On decks with slopes of one in 12 (1 inch per foot) or more, install wood nailers perpendicular to slope for securing insulation and for backnailing of roofing felts. Space nailers in accordance with approved shop drawings.

b. Fill or cover cracks or knot holes larger than 1/2 inch in diameter in wood decks as necessary to form an unyielding surface.

d. Cover steel decks with a layer of insulation board of sufficient width to span the width of a deck rib opening, and in accordance with fire safety requirements. Secure with piercing or self-drilling, self-tapping fasteners of quantity and placement in accordance with FM APP GUIDE. Locate insulation joints parallel to ribs of deck on solid bearing surfaces only, not over open ribs.

e. Solidly apply asphalt primer to poured, precast concrete decks at the rate of 1 gallon per 100 square feet of roof surface , stopping approximately 4 inches from joints between precast concrete units. Allow primer to dry thoroughly. Place felt strips, 4 inches or more in width, over joints, 2 inches on each side, between precast concrete units in a heavy coating of cold-applied asphalt roof cement.

3.2 INSTALLATION OF VAPOR RETARDER

Install vapor retarder in direct contact with roof deck surface . Unless otherwise specified, vapor retarder to consist of either two plies of No. 15 asphalt-saturated felt, two plies of asphalt-coated glass felt , or one layer of asphalt-saturated felt base sheet. Lay vapor retarder at right angles to direction of slope. Install first ply of felt or base sheet as specified herein for the specific deck. Apply second ply of 2-ply vapor

retarder system using asphalt at rate of 20 to 35 lbs per 100 square feet, applied within plus or minus 25 degrees F of EVT. Do not heat asphalt above asphalt's FBT or 525 degrees F, whichever is less. Use thermometers to check temperatures during heating and application. Completely seal side and end laps. Asphalt must be visible beyond all edges of each ply as it is being installed. Lay plies free of wrinkles, buckles, creases or fishmouths. Do not walk on mopped surfaces while asphalt is sticky. Press out air bubbles to obtain complete adhesion between surfaces. At walls, eaves, rakes, and other vertical surfaces, extend vapor retarder organic felts or separate plies 9 inches, with not less than 9 inches on the substrate, and the extended portion turned back and mopped in over the top of the insulation. At roof penetrations other than walls, eaves and rakes, and vertical surfaces, extend vapor retarder or separate plies 9 inches to form a lap folded back over the edge of the insulation. Provide asphalt roof cement under the vapor retarder for at least 9 inches from walls, eaves, rakes and other penetrations.

3.2.1 Vapor Retarder on Poured Concrete Decks

Evenly mop primed substrate with asphalt at a rate of 20 to 35 lbs per 100 square feet before installing vapor retarder. Lay first ply of two-ply system with each sheet lapping 19 inches over the preceding sheet. Lap ends not less than 4 inches. Stagger laps a minimum of 12 inches. For a vapor retarder consisting of one layer of asphalt base sheet, provide side and end laps not less than 4 inches. Stagger laps a minimum of 12 inches. Cement base sheets together with a solid mopping of asphalt.

3.2.2 Vapor Retarder on Precast Concrete Decks

Evenly mop primed substrate with asphalt at a rate of 20 to 35 lbs per 100 square feet before installing vapor retarder. Lay first ply of two-ply system with each sheet lapping 19 inches over preceding sheet. Lap ends not less than 4 inches. Stagger laps a minimum of 12 inches. For vapor retarder consisting of one layer of asphalt base sheet, provide side and end laps not less than 4 inches and stagger laps a minimum of 12 inches. Cement base sheets together with a solid mopping of asphalt.

3.2.3 Over Gypsum Insulating Concrete or Lightweight Insulating Concrete

Lay one ply of venting inorganic base sheet, without mopping, at a right angle to the slope with 4 inch side laps and 6 inch end laps. Bond laps with hot asphalt. Stagger end laps. attach to the concrete deck in accordance with uplift requirements. Apply 2-ply vapor retarder over the base sheet as specified above.

3.2.4 Over Concrete Decks and First Layer of Insulation on Steel Decks

Apply 2-ply vapor retarder as specified above except delete the venting inorganic base sheet.

3.2.5 Over Structural Concrete on Non-Venting Support

Lay one ply of venting inorganic base sheet with mopping holes at a right angle to the slope with 4 inch side laps and 6 inch end laps then apply the vapor retarder as specified.

3.3 INSTALLATION OF VENTILATING FELT

Apply ventilating felt in accordance with manufacturer's printed

instructions. Extend over roof cants, up vertical surfaces and terminate under cap flashing. At roof edges terminate under outside edge of perimeter edge nailers or under gravel stop fascia.

3.4 INSULATION INSTALLATION

Apply insulation in two layers with staggered joints when total required thickness of insulation exceeds 1/2 inch. Lay insulation so that continuous longitudinal joints are perpendicular to direction of felts for the built-up roofing, as specified in Section 07 51 13, and end joints of each course are staggered with those of adjoining courses. When using multiple layers of insulation, provide joints of each succeeding layer that are parallel and offset in both directions with respect to the layer below. Keep insulation 1/2 inch clear of vertical surfaces penetrating and projecting from roof surface. Verify required slopes to each roof drain.

3.4.1 Installation Using Asphalt

Firmly embed each layer in solid asphalt mopping; mop only sufficient area to provide complete embedment of one board at a time. Provide 20 to 35 lbs of asphalt per 100 square feet of roof deck for each layer of insulation. Apply asphalt when temperature is within plus or minus 25 degrees F of EVT. Do not heat asphalt above asphalt's FBT or 525 degrees F, whichever is less, for longer than 4 consecutive hours. Use thermometers to check temperatures during heating and application.

3.4.2 Installation Using Asphalt on Steel Decks

Secure first layer of insulation and thermal barrier to deck with piercing or self-drilling, self-tapping fasteners. Engage fasteners by driving them through insulation into top flange of steel deck. Use driving method prescribed by fastener manufacturer. Locate insulation joints parallel to ribs of deck on solid bearing surfaces only, not over open ribs. Secure succeeding layers with solid asphalt moppings. Where insulation is applied over steel deck, locate long edge joints so that they bear continuously on the steel deck. Insulation that can be readily lifted after installation is not considered adequately secured. Apply insulation only in quantities that can be entirely waterproofed the same day. Phased construction is not permitted. Apply impermeable faced insulation without damage to the facing.

3.4.3 Installation of Protection for Asphalt Work

Before starting asphalt work, protect surrounding areas and surfaces from spillage and migration of asphalt onto other work. Provide non-combustible protective coverings at surfaces adjacent to hoists and kettles. Lap protective coverings at least 6 inches, secure against wind, and vent to prevent collection of moisture on covered surfaces. Keep protective coverings in place for the duration of asphalt work.

3.4.4 Installation Using Only Mechanical Fasteners

Secure total thickness of insulation with penetrating type fasteners.

3.4.5 Special Precautions for Installation of Foam Insulation

3.4.5.1 Polyisocyanurate Insulation

Where polyisocyanurate foam board insulation is provided, install 1/2 inch thick wood fiberboard, glass mat gypsum roof board, or 3/4 inch thick expanded perlite board insulation over top surface of foam board insulation. Stagger joints of insulation with respect to foam board insulation below.

3.4.6 Cant Strips

Where indicated, provide cant strips at intersections of roof with walls, parapets, and curbs extending above roof. Wood cant strips must bear on and be anchored to wood blocking. Fit cant strips flush to vertical surfaces. Where possible, nail cant strips to adjoining surfaces. Where cant strips are installed against non-nailable materials, install in heavy mopping of asphalt or set in a heavy coating of asphalt roof cementor an approved adhesive.

3.4.7 Tapered Edge Strips

Where indicated, provide edge strips in the right angle formed by the juncture of roof and wood nailing strips that extend above the level of the roof. Install edge strips flush to vertical surfaces of wood nailing strips. Where possible, nail edge strips to adjoining surfaces. Where installed against non-nailable materials, install in a heavy mopping of asphalt or set in a heavy coating of asphalt roof cementor an approved adhesive.

3.5 PROTECTION

3.5.1 Protection of Applied Insulation

Completely cover each day's installation of insulation with finished roofing specified in the Statement of Work on same day. Phased construction is not permitted. Protect open spaces between insulation and parapets or other walls and spaces at curbs, scuttles, and expansion joints, until permanent roofing and flashing are applied. Storing, walking, wheeling, or trucking directly on insulation or on roofed surfaces is not permitted. Provide smooth, clean board or plank walkways, runways, and platforms near supports, as necessary, to distribute weight in accordance with indicated live load limits of roof construction . Protect exposed edges of insulation with cutoffs at the end of each work day or whenever precipitation is imminent. Cutoffs must be two layers of bituminous-saturated felt set in plastic bituminous cement or single ply or EPDM membrane set in roof cement. Fill all profile voids in cutoffs to prevent trapping moisture below the membrane. Remove cutoffs when work resumes.

3.5.2 Damaged Work and Materials

Restore work and materials that become damaged during construction to original condition or replace with new materials.

3.6 INSPECTION

Establish and maintain inspection procedures to assure compliance of the installed roof insulation with contract requirements. Remove, replace,

correct in an approved manner, any work found not in compliance. Quality control must include, but is not limited to, the following:

a. Observation of environmental conditions; number and skill level of insulation workers; start and end time of work.

b. Verification of certification, listing or label compliance with FM Data Sheets. (https://www.fmglobal.com/fmglobalregistration/Downloads.aspx)

c. Verification of proper storage and handling of insulation and vapor retarder materials before, during, and after installation.

d. Inspection of vapor retarder application, including edge envelopes and mechanical fastening.

e. Inspection of mechanical fasteners; type, number, length, and spacing.

f. Coordination with other materials, cants, sleepers, and nailing strips.

g. Inspection of insulation joint orientation and laps between layers, joint width and bearing of edges of insulation on deck.

h. Installation of cutoffs and proper joining of work on subsequent days.

i. Continuation of complete roofing system installation to cover insulation installed same day.

j. Verification of required slope to each roof drain.

-- End of Section --