SECTION 13 48 00

SEISMIC PROTECTION FOR MISCELLANEOUS EQUIPMENT

04/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2010) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM A153/A153M	(2016) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2014) Standard Specification for Carbon Steel Bolts and Studs, 60 000 PSI Tensile Strength
ASTM A325	(2014) Standard Specification for Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength
ASTM A325M	(2014) Standard Specification for Structural Bolts, Steel, Heat Treated, 830 MPa Minimum Tensile Strength (Metric)
ASTM A36/A36M	(2014) Standard Specification for Carbon Structural Steel
ASTM A500/A500M	(2013) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A53/A53M	(2012) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A563	(2015) Standard Specification for Carbon and Alloy Steel Nuts
ASTM A563M	(2007; R 2013) Standard Specification for Carbon and Alloy Steel Nuts (Metric)

ASTM A572/A572M	(2015) Standard Specification for High-Strength Low-Alloy Columbium-Vanadium Structural Steel
ASTM A603	(1998; R 2014) Standard Specification for Zinc-Coated Steel Structural Wire Rope
ASTM A653/A653M	(2015; E 2016) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM E488/E488M	(2015) Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-310-04	(2013) Seismic Design for Buildings

1.2 SYSTEM DESCRIPTION

1.2.1 General Requirements

Apply the requirements for seismic protection measures, described in this section, to the mechanical equipment and systems outlined in Section 13 48 00.00 10 SEISMIC PROTECTION FOR MECHANICAL EQUIPMENT, the electrical equipment and systems outlined in Section 26 05 48.00 10 SEISMIC PROTECTION FOR ELECTRICAL EQUIPMENT, and the miscellaneous equipment and systems listed below, in accordance with UFC 3-310-04 and additional data furnished by the Contracting Officer. Provide seismic protection measures in addition to any other requirements called for in other sections of these specifications. The design for seismic protection shall be based on a Seismic Use Group building occupancy as shown in the contract drawings, and and on site response coefficients for S_{MS} = 0.408 g and S_{M1} = 0.185 g. Accomplish resistance to lateral forces induced by earthquakes without consideration of friction resulting from gravity loads. The basic force formulas, for Ground Motions A and B in UFC 3-310-04, use the design spectral response acceleration parameters for the performance objective of the building, not for equipment in the building; therefore, corresponding adjustments to the formulas are required.

1.2.2 Miscellaneous Equipment and Systems

The bracing for the following miscellaneous equipment and systems shall be developed by the Contractor in accordance with the requirements of this specification:

Storage cabinets
Ornamentations
Storage Racks
Signs and Billboards
Shelving
Furnishings
Partitions

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Bracing; G
Resilient Vibration Isolation Devices; G
Equipment Requirements; G

SD-03 Product Data

Bracing; G
Equipment Requirements; G

SD-06 Test Reports

Anchor Bolts; G

PART 2 PRODUCTS

2.1 EQUIPMENT REQUIREMENTS

Submit detail drawings along with calculations, catalog cuts, templates, and erection and installation details, as appropriate, for the items listed below. Indicate thickness, type, grade, class of metal, and dimensions; and show construction details, reinforcement, anchorage, and installation with relation to the building construction. For equipment and systems in buildings that have a performance objective higher than life-safety, the drawings shall be stamped by the registered engineer who stamps the calculations. Calculations shall be stamped, by a registered engineer, and verify the capability of structural members to which bracing is attached for carrying the load from the brace.

2.1.1 Rigidly Mounted Equipment

The items of equipment furnished under this contract and as indicated in the contract drawings shall be constructed and assembled to withstand the seismic forces specified in UFC 3-310-04. For any rigid equipment which is rigidly attached on both sides of a building expansion joint, provide flexible joints for piping, electrical conduit, etc., that are capable of accommodating displacements equal to the full width of the joint in both orthogonal directions.

2.1.2 Nonrigid or Flexibly-Mounted Equipment

The items of equipment furnished under this contract and as indicated in the contract drawings shall be constructed and assembled to resist a horizontal lateral force of six times the operating weight of the equipment at the vertical center of gravity of the equipment.

2.2 BOLTS AND NUTS

Squarehead and hexhead bolts, and heavy hexagon nuts, ASME B18.2.1, ASME B18.2.2, or ASTM A307 for bolts and ASTM A563 for nuts . Provide bolts and nuts galvanized in accordance with ASTM A153/A153M when used

underground and/or exposed to weather.

2.3 SWAY BRACING

Material used for members listed in this section and on the drawings, shall be structural steel conforming with the following:

a. Plates, rods, and rolled shapes, ASTM A36/A36M . If the Contractor does the design, both ASTM A36/A36Mand ASTM A572/A572M, grade 503 will be allowed.

b. Wire rope, ASTM A603.

c. Tubes, ASTM A500/A500M, Grade B .

d. Pipes, ASTM A53/A53M, Type E or S, Grade B.

e. Light gauge angles, less than 1/4 inch thickness, ASTM A653/A653M .

PART 3 EXECUTION

3.1 BRACING

Provide bracing conforming to the arrangements shown. Secure trapeze-type hanger with not less than two 1/2 inch bolts.

3.2 BUILDING DRIFT

Sway braces for a piping run shall not be attached to two dissimilar structural elements of a building that may respond differentially during an earthquake unless a flexible joint is provided.

3.3 ANCHOR BOLTS

Submit copies of test results to verify the adequacy of the specific anchor and application, as specified.

3.3.1 Cast-In-Place

Use cast-in-place anchor bolts, conforming to ASTM A307, for floor or pad mounted equipment, except as specified below. Provide two nuts on each bolt. Anchor bolts shall have an embedded straight length equal to at least 12 times nominal diameter of the bolt. Anchor bolts that exceed the normal depth of equipment foundation piers or pads shall either extend into concrete floor or the foundation or be increased in depth to accommodate bolt lengths.

3.3.2 Expansion or Chemically Bonded Anchors

Do not use expansion or chemically bonded anchors: 1)Unless test data in accordance with ASTM E488/E488M has been provided to verify the adequacy of the specific anchor and application. 2)To resist pull-out in overhead and wall installations if the adhesive is manufactured with temperature sensitive epoxies and the location is accessible to a building fire. Install expansion and chemically bonded anchors in accordance with the manufacturer's recommendations. Adjust the allowable forces for the spacing between anchor bolts and the distance between the anchor bolt and the nearest edge, as specified by the manufacturer.

3.3.2.1 General Testing

Test in place expansion and chemically bonded anchors not more than 24 hours after installation of the anchor, conducted by an independent testing agency; testing shall be performed on random anchor bolts as described below.

3.3.2.2 Torque Wrench Testing

Perform torque wrench testing on not less than 50 percent of the total installed expansion anchors and at least one anchor for every piece of equipment containing more than two anchors. The test torque shall equal the minimum required installation torque as required by the bolt manufacturer. Calibrate torque wrenches at the beginning of each day the torque tests are performed. Recalibrate torque wrenches for each bolt diameter whenever tests are run on bolts of various diameters. Apply torque between 20 and 100 percent of wrench capacity. Reach the test torque within one half turn of the nut, except for 3/8 inch sleeve anchors which shall reach their torque by one quarter turn of the nut. If any anchor fails the test, test similar anchors not previously tested until 20 consecutive anchors pass. Failed anchors shall be retightened and retested to the specified torque; if the anchor still fails the test it shall be replaced.

3.3.2.3 Pullout Testing

Test expansion and chemically bonded anchors by applying a pullout load using a hydraulic ram attached to the anchor bolt. At least 5 percent of the anchors, but not less than 3 per day shall be tested. Apply the load to the anchor without removing the nut; when that is not possible, the nut shall be removed and a threaded coupler shall be installed of the same tightness as the original nut. Check the test setup to verify that the anchor is not restrained from withdrawing by the baseplate, the test fixture, or any other fixtures. The support for the testing apparatus shall be at least 1.5 times the embedment length away from the bolt being tested. Load each tested anchor to 1 times the design tension value for the anchor. The anchor shall have no observable movement at the test load. If any anchor fails the test, similar anchors not previously tested shall be tested until 20 consecutive anchors pass. Failed anchors shall be retightened and retested to the specified load; if the anchor still fails the test it shall be replaced.

3.4 RESILIENT VIBRATION ISOLATION DEVICES

Where the need for these devices is determined, based on the magnitude of the design seismic forces, selection of anchor bolts for vibration isolation devices and/or snubbers for equipment base and foundations shall follow the same procedure as in paragraph ANCHOR BOLTS, except that an equipment weight equal to five times the actual equipment weight shall be used.

3.4.1 Resilient and Spring-Type Vibration Devices

Select vibration isolation devices so that the maximum movement of equipment from the static deflection point is 1/2 inch.

3.4.2 Multidirectional Seismic Snubbers

Install multidirectional seismic snubbers employing elastomeric pads on

floor- or slab-mounted equipment. These snubbers shall provide 1/4 inch free vertical and horizontal movement from the static deflection point. Snubber medium shall consist of multiple pads of cotton duct and neoprene or other suitable materials arranged around a flanged steel trunnion so both horizontal and vertical forces are resisted by the snubber medium.

3.5 SWAY BRACES FOR PIPING

Provide transverse sway bracing for steel and copper pipe at intervals not to exceed those shown on the drawings. Transverse sway bracing for pipes of materials other than steel and copper shall be provided at intervals not to exceed the hanger spacing as specified in Section 22 00 00 PLUMBING, GENERAL PURPOSE. Provide bracing consisting of at least one vertical angle 2 by 2 inch by 16 gauge and one diagonal angle of the same size.

3.5.1 Longitudinal Sway Bracing

Provide longitudinal sway bracing in accordance with Section 13 48 00.00 10 SEISMIC CONTROL FOR MECHANICAL EQUIPMENT.

3.5.2 Anchor Rods, Angles, and Bars

Anchor rods, angles, and bars shall be bolted to either pipe clamps or pipe flanges at one end and cast-in-place concrete or masonry insert or clip angles bolted to the steel structure on the other end. Rods shall be solid metal or pipe as specified below. Anchor rods, angles, and bars shall not exceed lengths given in the tabulation below.

3.5.3 Maximum Length for Anchor Braces

Type	Size (in)	Maximum Length* (ft-in)
Angles	1-1/2 x 1-1/2 x 1/4	4-10
	2 x 2 x 1/4	6-6
	2-1/2 x 1-1/2 x 1/4	8-0
	3 x 2-1/2 x 1/4	8-10
	3 x 3 x 1/4	9-10
Rods	3/4	3-1
	7/8	3-8
Flat Bars	1-1/2 x 1/4	1-2
	2 x 1/4	1-2
	2 x 3/8	1-9

Type	Size (in)	Maximum Length* (ft-in)
Pipes (40s)	1	7-0
	1-1/4	9-0
	1-1/2	10-4
	2	13-1

3.5.4 Bolts

Bolts used for attachment of anchors to pipe and structure shall be not less than 1/2 inch diameter.

3.6 EQUIPMENT SWAY BRACING

3.6.1 Suspended Equipment and Light Fixtures

Provide equipment sway bracing for items supported from overhead floor or roof structural systems, including light fixtures. Braces shall consist of angles, rods, wire rope, bars, or pipes arranged as shown and secured at both ends with not less than 1/2 inch bolts. Provide sufficient braces for equipment to resist a horizontal force as specified in UFC 3-310-04 without exceeding safe working stress of bracing components. Provide, for approval, specific force calculations in accordance with UFC 3-310-04 for the equipment in the project. Submit details of equipment bracing for acceptance. In lieu of bracing with vertical supports, these items may be supported with hangers inclined at 45 degrees directed up and radially away from equipment and oriented symmetrically in 90-degree intervals on the horizontal plane, bisecting the angles of each corner of the equipment, provided that supporting members are properly sized to support operating weight of equipment when hangers are inclined at a 45-degree angle.

3.6.2 Floor or Pad Mounted Equipment

3.6.2.1 Shear Resistance

Bolt to the floor, floor mounted equipment. Requirements for the number and installation of bolts to resist shear forces shall be in accordance with paragraph ANCHOR BOLTS.

3.6.2.2 Overturning Resistance

Use the ratio of the overturning moment from seismic forces to the resisting moment due to gravity loads to determine if overturning forces need to be considered in the sizing of anchor bolts. Provide calculations to verify the adequacy of the anchor bolts for combined shear and overturning.

3.7 SPECIAL INSPECTION AND TESTING FOR SEISMIC-RESISTING SYSTEMS

Perform special inspections and testing for seismic-resisting systems and components in accordance with Section 01 45 35 SPECIAL INSPECTIONS.

-- End of Section --