ePROJECTS WORK ORDER
NUMBER: 1701820
APPROPRIATION:

P-1550 SOF MARINE RAIDER
BATTALION / COMPANY / TEAM FACILITIES

At the

MARINE CORPS BASE CAMP LEJEUNE, NC

DESIGNED BY:

NAVFAC MID-ATLANTIC
9742 MARYLAND AVENUE
NORFOLK, VIRGINIA 23511-3095

SPECIFICATION PREPARED BY:

Architectural: MBF Architects
Civil: Stantec
Structural: Kaydos-Daniels Engineering
Interior Design: Within Interior Design
Mechanical/Plumbing/Electrical: Crenshaw Consulting Eng.
Fire Prot.: Jensen Hughes
Audio Video: Thorburn

Specification: Darden J. Eure, III, MBF Architects

Date: 8 May 2026

DARDEN J. EURE, III
REGISTERED ARCHITECT
8640
NORTH CAROLINA
NEW BERN NC
8 May 2026

SPECIFICATION APPROVED BY:

For Commander, NAVFAC MID-ATLANTIC:
Date: 13 May 2026 James E. Donahue, R.A.

This page is intentionally left blank.

PROJECT TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

00 01 15	02/24	LIST OF DRAWINGS

DIVISION 01 - GENERAL REQUIREMENTS

01 11 00	06/25	SUMMARY OF WORK
01 14 00	04/22	WORK RESTRICTIONS (MCBL)
01 20 00	11/20, CHG 5: 02/25	PRICE AND PAYMENT PROCEDURES
01 30 00	11/20, CHG 5: 02/25	ADMINISTRATIVE REQUIREMENTS
01 30 02.00 22	05/23	DESIGN, PROCUREMENT, AND INSTALLATION OF AUDIOVISUAL EQUIPMENT
01 31 23.13 20	08/23, CHG 1: 02/24	ELECTRONIC CONSTRUCTION AND FACILITY SUPPORT CONTRACT MANAGEMENT SYSTEM (eCMS)
01 32 17.00 20	05/25	COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS)
01 33 00	08/18, CHG 4: 02/21	SUBMITTAL PROCEDURES SUBMITTAL REGISTER
01 33 29	02/21, CHG 1: 08/25	SUSTAINABILITY REQUIREMENTS AND REPORTING HPSB CHECKLISTS
01 35 26	05/24, CHG 1: 05/25	GOVERNMENTAL SAFETY REQUIREMENTS
01 35 29.13	11/15, CHG 1: 08/22	HEALTH, SAFETY, AND EMERGENCY RESPONSE PROCEDURES FOR CONTAMINATED SITES
01 42 00	05/24	SOURCES FOR REFERENCE PUBLICATIONS
01 45 00	08/23, CHG 3: 08/25	QUALITY CONTROL SCHEDULE OF FIRE PROTECTION SYSTEM INSPECTIONS BY FPQC SPECIALIST
01 45 35	11/20	SPECIAL INSPECTIONS STATMENT OF SPECIAL INSPECTIONS SCHEDULE OF SPECIAL INSPECTIONS
01 50 00	12/21	TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
01 57 19	08/22	TEMPORARY ENVIRONMENTAL CONTROLS
01 58 00	08/19, CHG 5: 08/22	PROJECT IDENTIFICATION PROJECT SIGN DETAILS
01 74 19	02/19, CHG 3: 11/21	CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
01 78 00	04/24	CLOSEOUT SUBMITTALS
01 78 23	04/22	OPERATION AND MAINTENANCE DATA
01 78 24.00 20	03/23	FACILITY ELECTRONIC OPERATION AND MAINTENANCE SUPPORT INFORMATION (eOMSI)
01 78 30.00 22	5/22	GIS DATA DELIVERABLES
01 91 00.15 22	08/24	TOTAL BUILDING COMMISSIONING
01 91 19	05/23	BUILDING ENCLOSURE COMMISSIONING

DIVISION 02 - EXISTING CONDITIONS

02 41 00	08/22	DEMOLITION

DIVISION 03 - CONCRETE

03 30 00	02/19, CHG 4: 08/22	CAST-IN-PLACE CONCRETE

DIVISION 04 - MASONRY

04 20 00 11/15, CHG 2: 05/19 UNIT MASONRY
04 73 00 12/25 CAST STONE SCULPTURE

DIVISION 05 - METALS

05 12 00 08/18, CHG 2: 05/21 STRUCTURAL STEEL
05 21 00 05/15, CHG 1: 08/18 STEEL JOIST FRAMING
05 30 00 05/15, CHG 2: 08/18 STEEL DECKS
05 40 00 05/15, CHG 1: 08/18 COLD-FORMED METAL FRAMING
05 50 13 05/17, CHG 1: 08/18 MISCELLANEOUS METAL FABRICATIONS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 41 16.00 10 08/10, CHG 1: 11/18 PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS
06 61 16 08/20 SOLID SURFACING FABRICATIONS
06 82 14 DECORATIVE FIBERGLASS REINFORCED PLASTIC (FRP)

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 21 13 08/23, CHG 1: 08/25 BOARD AND BLOCK INSULATION
07 21 16 11/11, CHG 4: 08/18 MINERAL FIBER BLANKET INSULATION
07 27 10.00 10 08/19, CHG 1: 02/20 BUILDING AIR BARRIER SYSTEM
07 27 26 08/23 FLUID-APPLIED MEMBRANE AIR BARRIERS
07 42 13 05/11, CHG 2: 02/18 METAL WALL PANELS
07 60 00 05/17, CHG 2: 11/18 FLASHING AND SHEET METAL
07 84 00 05/10, CHG 1: 08/13 FIRESTOPPING
07 92 00 08/16, CHG 3: 11/18 JOINT SEALANTS

DIVISION 08 - OPENINGS

08 11 13 08/20 STEEL DOORS AND FRAMES
08 11 16 05/17, CHG 2: 11/18 ALUMINUM DOORS AND FRAMES
08 14 00 08/16, CHG 1: 08/18 WOOD DOORS
08 31 00 05/17, CHG 1: 08/18 ACCESS DOORS AND PANELS
08 33 23 08/20, CHG 1: 02/22 STEEL OVERHEAD COILING DOORS
08 34 02 08/09 BULLET-RESISTANT COMPONENTS
08 34 73 11/19, CHG 1: 02/21 SOUND CONTROL DOOR ASSEMBLIES
08 41 13 08/18, CHG 1: 08/18 ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
08 41 60 12/22 TRANSLUCENT FIBERGLASS WALLS
08 71 00 02/16, CHG 4: 02/22 DOOR HARDWARE
08 81 00 05/19 GLAZING
08 91 00 08/20 ALUMINUM METAL LOUVERS

DIVISION 09 - FINISHES

09 22 00 02/10, CHG 2: 08/18 SUPPORTS FOR PLASTER AND GYPSUM BOARD
09 29 00 08/16, CHG 4: 02/20 GYPSUM BOARD
09 30 10 08/20 CERAMIC, QUARRY, AND GLASS TILING
09 51 00 08/20 ACOUSTICAL CEILINGS
09 65 00 08/10, CHG 3: 08/18 RESILIENT FLOORING
09 66 23 08/16, CHG 1: 08/18 RESINOUS MATRIX TERRAZZO FLOORING
09 67 23.13 11/19 STANDARD RESINOUS FLOORING
09 68 00 11/17, CHG 2: 08/20 CARPET TILE
09 69 13 11/15, CHG 1: 08/18 RIGID GRID ACCESS FLOORING
09 72 00 08/17, CHG 1: 08/18 WALL PROTECTION & DIGITALLY PRINTED WALL GRAPHICS

09 90 00 02/21 PAINTS AND COATINGS

DIVISION 10 - SPECIALTIES

10 11 00 08/20 VISUAL DISPLAY UNITS
10 14 00.10 08/17, CHG 1: 11/18 EXTERIOR SIGNAGE
10 14 00.20 08/20 INTERIOR SIGNAGE
10 21 13 08/20 TOILET COMPARTMENTS
10 22 13 08/16, CHG 1: 08/18 WIRE MESH PARTITIONS
10 26 00 08/20 WALL AND DOOR PROTECTION
10 28 13 08/20 TOILET ACCESSORIES
10 44 16 11/19 FIRE EXTINGUISHERS
10 50 00 02/16 MISCELLANEOUS SPECIALTIES
10 56 00 10/16 PALLET STORAGE RACKS

DIVISION 12 - FURNISHINGS

12 00 01.00 20 02/23 FURNITURE, FIXTURES AND EQUIPMENT (FF&E) PACKAGE
12 24 13 08/20 ROLLER WINDOW SHADES

DIVISION 13 - SPECIAL CONSTRUCTION

13 34 19 08/20, CHG 1: 02/21 METAL BUILDING SYSTEMS
13 47 00 10/23 ELECTROMAGNETIC BARRIERS

DIVISION 21 - FIRE SUPPRESSION

21 13 13 08/20 WET PIPE SPRINKLER SYSTEMS, FIRE PROTECTION
21 13 16 08/20 DRY PIPE SPRINKLER SYSTEMS, FIRE PROTECTION
21 30 00 04/08, CHG 1: 08/13 FIRE PUMPS

DIVISION 22 - PLUMBING

22 00 00 05/24, CHG 1: 11/24 PLUMBING, GENERAL PURPOSE

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

23 03 00.00 20 08/24 MCBCL BASIC MECHANICAL MATERIALS AND METHODS
23 05 48.19 05/18, CHG 2: 08/20 BRACING FOR HVAC
23 05 93 05/25 TESTING, ADJUSTING, AND BALANCING FOR HVAC
23 07 00 08/24 THERMAL INSULATION FOR MECHANICAL SYSTEMS
23 08 00 05/23, CHG 1: 08/24 COMMISSIONING OF MECHANICAL AND PLUMBING SYSTEMS
23 09 00 02/25 MCBCL INSTRUMENTATION AND CONTROL FOR HVAC
23 09 13 02/25 MCBCL INSTRUMENTATION AND CONTROL DEVICES FOR HVAC
23 09 23.02 02/25 MCBCL BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS
23 11 20 05/20 FACILITY GAS PIPING
23 21 13.00 20 04/06, CHG 2: 11/19 LOW TEMPERATURE WATER (LTW) HEATING SYSTEM
23 23 00 08/21 REFRIGERANT PIPING
23 25 00 05/21 CHEMICAL TREATMENT OF WATER FOR MECHANICAL SYSTEMS

23 30 00	02/25	HVAC AIR DISTRIBUTION
23 52 43.00 20	05/15, CHG 2: 08/18	LOW PRESSURE WATER HEATING BOILERS (UNDER 800,000 BTU/HR OUTPUT)
23 64 10	05/25	WATER CHILLERS, VAPOR COMPRESSION TYPE
23 64 26	08/09, CHG 5: 11/19	CHILLED WATER PIPING SYSTEMS
23 81 00	05/24	DECENTRALIZED UNITARY HVAC EQUIPMENT
23 82 00.00 20	02/16, CHG 1: 08/18	TERMINAL HEATING UNITS

DIVISION 25 - INTEGRATED AUTOMATION

25 05 11.00	11/17	CYBERSECURITY FOR FACILITY-RELATED CONTROL SYSTEMS - ISOLATED SYSTEMS

DIVISION 26 - ELECTRICAL

26 08 00	11/21	APPARATUS INSPECTION AND TESTING
26 12 19.10	05/19, CHG 1: 11/19	THREE-PHASE, LIQUID-FILLED PAD-MOUNTED TRANSFORMERS
26 13 00	05/21, CHG 1: 05/22	SF6/HIGH-FIREPOINT FLUIDS INSULATED PAD-MOUNTED SWITCHGEAR
26 20 00	08/19, CHG 3: 11/21	INTERIOR DISTRIBUTION SYSTEM
26 24 13	08/21	SWITCHBOARDS
26 27 14.00 20	02/21, CHG 1: 05/21	ELECTRICITY METERING
26 28 01.00 10	08/21	COORDINATED POWER SYSTEM PROTECTION
26 29 23	02/20, CHG 1: 05/21	ADJUSTABLE SPEED DRIVE (ASD) SYSTEMS UNDER 600 VOLTS
26 32 15.00	05/20	ENGINE-GENERATOR SET STATIONARY 15-2500 KW, WITH AUXILIARIES
26 36 23	05/20, CHG 1: 08/21	AUTOMATIC TRANSFER SWITCHES AND BY-PASS/ISOLATION SWITCH
26 41 00	11/13	LIGHTNING PROTECTION SYSTEM
26 51 00	05/20, CHG 2: 11/21	INTERIOR LIGHTING
26 56 00	08/21	EXTERIOR LIGHTING

DIVISION 27 - COMMUNICATIONS

27 10 00	01/24	BUILDING TELECOMMUNICATIONS CABLING SYSTEM (MCBCL)

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

28 31 76	08/20	INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE

DIVISION 31 - EARTHWORK

31 00 00	08/23	EARTHWORK
31 11 00	11/18	CLEARING AND GRUBBING
31 31 16.13	08/22	CHEMICAL TERMITE CONTROL

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 01 16.71	11/22	COLD MILLING ASPHALT PAVING
32 01 19.61	11/19	SEALING OF JOINTS IN RIGID PAVEMENT
32 11 23	05/22	AGGREGATE BASE COURSE
32 12 16.16	11/20	ROAD-MIX ASPHALT PAVING
32 13 13.06	05/20	PORTLAND CEMENT CONCRETE PAVEMENT FOR ROADS AND SITE FACILITIES
32 16 19	05/18	CONCRETE CURBS, GUTTERS AND SIDEWALKS

32 17 23	08/16, CHG 5: 11/18	PAVEMENT MARKINGS
32 17 23.16	11/24	ROAD AND PARKING LOT PAVEMENT MARKINGS
32 31 13	11/21	CHAIN LINK FENCES AND GATES
32 92 23	04/06, CHG 1: 08/21	SODDING
32 93 00	08/17, CHG 1: 08/21	EXTERIOR PLANTS

DIVISION 33 - UTILITIES

33 01 30.16	11/21	TV INSPECTION OF SEWER LINES
33 05 07.13	02/24	UTILITY DIRECTIONAL DRILLING
33 11 00	02/18, CHG 1: 02/22	WATER UTILITY DISTRIBUTION PIPING
33 30 00	05/18	SANITARY SEWERAGE
33 31 23.00 10	08/18	SANITARY SEWER FORCE MAIN PIPING
33 32 16	11/19	PACKAGED UTILITY WASTEWATER PUMPING STATIONS
33 40 00	11/21	STORMWATER UTILITIES
33 61 14	02/10	EXTERIOR BURIED PREINSULATED WATER PIPING
33 71 02	08/21	UNDERGROUND ELECTRICAL DISTRIBUTION
33 82 00	08/22	TELECOMMUNICATIONS OUTSIDE PLANT (OSP)

-- End of Project Table of Contents --

THIS PAGE INTENTIONALLY LEFT BLANK

VOLUME 1 of 2
Division 0 - 13

eProjects Work Order
Number: 1701820
Appropriation:

P-1550 SOF MARINE RAIDER
BATTALION / COMPANY / TEAM FACILITIES

At the

MARINE CORPS BASE CAMP LEJEUNE, NC

DESIGNED BY:

NAVFAC MID-ATLANTIC
9742 MARYLAND AVENUE
NORFOLK, VIRGINIA 23511-3095

SPECIFICATION PREPARED BY:

Architectural: MBF Architects
Civil: Stantec
Structural: Kaydos-Daniels Engineering
Interior Design: Within Interior Design
Mechanical/Plumbing/Electrical: Crenshaw Consulting Eng.
Fire Prot.: Jensen Hughes
Audio Video: Thorburn

Specification: Darden J. Eure, III, MBF Architects

Date: 8 May 2026

SPECIFICATION APPROVED BY:

For Commander, NAVFAC MID-ATLANTIC:
Date:

This page is intentionally left blank.

VOLUME 1 - TABLE OF CONTENTS
Division 0 - 13

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

00 01 15	02/24	LIST OF DRAWINGS

DIVISION 01 - GENERAL REQUIREMENTS

01 11 00	06/25	SUMMARY OF WORK
01 14 00	04/22	WORK RESTRICTIONS (MCBL)
01 20 00	11/20, CHG 5: 02/25	PRICE AND PAYMENT PROCEDURES
01 30 00	11/20, CHG 5: 02/25	ADMINISTRATIVE REQUIREMENTS
01 30 02.00 22	05/23	DESIGN, PROCUREMENT, AND INSTALLATION OF AUDIOVISUAL EQUIPMENT
01 31 23.13 20	08/23, CHG 1: 02/24	ELECTRONIC CONSTRUCTION AND FACILITY SUPPORT CONTRACT MANAGEMENT SYSTEM (eCMS)
01 32 17.00 20	05/25	COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS)
01 33 00	08/18, CHG 4: 02/21	SUBMITTAL PROCEDURES SUBMITTAL REGISTER
01 33 29	02/21, CHG 1: 08/25	SUSTAINABILITY REQUIREMENTS AND REPORTING HPSB CHECKLISTS
01 35 26	05/24, CHG 1: 05/25	GOVERNMENTAL SAFETY REQUIREMENTS
01 35 29.13	11/15, CHG 1: 08/22	HEALTH, SAFETY, AND EMERGENCY RESPONSE PROCEDURES FOR CONTAMINATED SITES
01 42 00	05/24	SOURCES FOR REFERENCE PUBLICATIONS
01 45 00	08/23, CHG 3: 08/25	QUALITY CONTROL SCHEDULE OF FIRE PROTECTION SYSTEM INSPECTIONS BY FPQC SPECIALIST
01 45 35	11/20	SPECIAL INSPECTIONS STATMENT OF SPECIAL INSPECTIONS SCHEDULE OF SPECIAL INSPECTIONS
01 50 00	12/21	TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
01 57 19	08/22	TEMPORARY ENVIRONMENTAL CONTROLS
01 58 00	08/19, CHG 5: 08/22	PROJECT IDENTIFICATION PROJECT SIGN DETAILS
01 74 19	02/19, CHG 3: 11/21	CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
01 78 00	04/24	CLOSEOUT SUBMITTALS
01 78 23	04/22	OPERATION AND MAINTENANCE DATA
01 78 24.00 20	03/23	FACILITY ELECTRONIC OPERATION AND MAINTENANCE SUPPORT INFORMATION (eOMSI)
01 78 30.00 22	5/22	GIS DATA DELIVERABLES
01 91 00.15 22	08/24	TOTAL BUILDING COMMISSIONING
01 91 19	05/23	BUILDING ENCLOSURE COMMISSIONING

DIVISION 02 - EXISTING CONDITIONS

02 41 00	08/22	DEMOLITION

DIVISION 03 - CONCRETE

03 30 00	02/19, CHG 4: 08/22	CAST-IN-PLACE CONCRETE

DIVISION 04 - MASONRY

04 20 00	11/15, CHG 2: 05/19	UNIT MASONRY
04 73 00	12/25	CAST STONE SCULPTURE

DIVISION 05 - METALS

05 12 00	08/18, CHG 2: 05/21	STRUCTURAL STEEL
05 21 00	05/15, CHG 1: 08/18	STEEL JOIST FRAMING
05 30 00	05/15, CHG 2: 08/18	STEEL DECKS
05 40 00	05/15, CHG 1: 08/18	COLD-FORMED METAL FRAMING
05 50 13	05/17, CHG 1: 08/18	MISCELLANEOUS METAL FABRICATIONS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 41 16.00 10	08/10, CHG 1: 11/18	PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS
06 61 16	08/20	SOLID SURFACING FABRICATIONS
06 82 14		DECORATIVE FIBERGLASS REINFORCED PLASTIC (FRP)

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 21 13	08/23, CHG 1: 08/25	BOARD AND BLOCK INSULATION
07 21 16	11/11, CHG 4: 08/18	MINERAL FIBER BLANKET INSULATION
07 27 10.00 10	08/19, CHG 1: 02/20	BUILDING AIR BARRIER SYSTEM
07 27 26	08/23	FLUID-APPLIED MEMBRANE AIR BARRIERS
07 42 13	05/11, CHG 2: 02/18	METAL WALL PANELS
07 60 00	05/17, CHG 2: 11/18	FLASHING AND SHEET METAL
07 84 00	05/10, CHG 1: 08/13	FIRESTOPPING
07 92 00	08/16, CHG 3: 11/18	JOINT SEALANTS

DIVISION 08 - OPENINGS

08 11 13	08/20	STEEL DOORS AND FRAMES
08 11 16	05/17, CHG 2: 11/18	ALUMINUM DOORS AND FRAMES
08 14 00	08/16, CHG 1: 08/18	WOOD DOORS
08 31 00	05/17, CHG 1: 08/18	ACCESS DOORS AND PANELS
08 33 23	08/20, CHG 1: 02/22	STEEL OVERHEAD COILING DOORS
08 34 02	08/09	BULLET-RESISTANT COMPONENTS
08 34 73	11/19, CHG 1: 02/21	SOUND CONTROL DOOR ASSEMBLIES
08 41 13	08/18, CHG 1: 08/18	ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
08 41 60	12/22	TRANSLUCENT FIBERGLASS WALLS
08 71 00	02/16, CHG 4: 02/22	DOOR HARDWARE
08 81 00	05/19	GLAZING
08 91 00	08/20	ALUMINUM METAL LOUVERS

DIVISION 09 - FINISHES

09 22 00	02/10, CHG 2: 08/18	SUPPORTS FOR PLASTER AND GYPSUM BOARD
09 29 00	08/16, CHG 4: 02/20	GYPSUM BOARD
09 30 10	08/20	CERAMIC, QUARRY, AND GLASS TILING
09 51 00	08/20	ACOUSTICAL CEILINGS
09 65 00	08/10, CHG 3: 08/18	RESILIENT FLOORING
09 66 23	08/16, CHG 1: 08/18	RESINOUS MATRIX TERRAZZO FLOORING
09 67 23.13	11/19	STANDARD RESINOUS FLOORING
09 68 00	11/17, CHG 2: 08/20	CARPET TILE
09 69 13	11/15, CHG 1: 08/18	RIGID GRID ACCESS FLOORING
09 72 00	08/17, CHG 1: 08/18	WALL PROTECTION & DIGITALLY PRINTED WALL GRAPHICS

09 90 00 02/21 PAINTS AND COATINGS

DIVISION 10 - SPECIALTIES

10 11 00 08/20 VISUAL DISPLAY UNITS
10 14 00.10 08/17, CHG 1: 11/18 EXTERIOR SIGNAGE
10 14 00.20 08/20 INTERIOR SIGNAGE
10 21 13 08/20 TOILET COMPARTMENTS
10 22 13 08/16, CHG 1: 08/18 WIRE MESH PARTITIONS
10 26 00 08/20 WALL AND DOOR PROTECTION
10 28 13 08/20 TOILET ACCESSORIES
10 44 16 11/19 FIRE EXTINGUISHERS
10 50 00 02/16 MISCELLANEOUS SPECIALTIES
10 56 00 10/16 PALLET STORAGE RACKS

DIVISION 12 - FURNISHINGS

12 00 01.00 20 02/23 FURNITURE, FIXTURES AND EQUIPMENT (FF&E) PACKAGE
12 24 13 08/20 ROLLER WINDOW SHADES

DIVISION 13 - SPECIAL CONSTRUCTION

13 34 19 08/20, CHG 1: 02/21 METAL BUILDING SYSTEMS
13 47 00 10/23 ELECTROMAGNETIC BARRIERS

This page is intentionally left blank.

DOCUMENT 00 01 15

LIST OF DRAWINGS
02/24

PART 1 GENERAL

1.1 SUMMARY

This section lists the drawings for the project pursuant to contract clause "DFARS 252.236-7001, Contract Drawings and Specifications."

1.2 CONTRACT DRAWINGS

Contract drawings are as follows:

A1 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
	G	GENERAL
12903090	G-001	COVER SHEET
12903091	G-002	LOCATION MAPS AND INDEX OF DRAWINGS
12903092	G-003	INDEX OF DRAWINGS
12903093	G-004	INDEX OF DRAWINGS
	GI	LIFE SAFETY
12903094	GI001	LIFE SAFETY NOTES AND LEGEND - BATTALION HEADQUARTERS
12903095	GI002	OCCUPANT LOADS - BATTALION HEADQUARTERS
12903096	GI003	CODE COMPLIANCE SITE PLAN - BATTALION HEADQUARTERS
12903097	GI101	LIFE SAFETY FLOOR PLAN - BATTALION HEADQUARTERS AREA A
12903098	GI102	LIFE SAFETY FLOOR PLAN - BATTALION HEADQUARTERS AREA B
	S	STRUCTURAL
12903099	S-001	COVER SHEET
12903100	S-002	STRUCTURAL NOTES
12903101	S-003	STRUCTURAL NOTES
12903102	S-101	FOUNDATION PLAN - AREA A
12903103	S-102	FOUNDATION PLAN - AREA B
12903104	S-103	FOUNDATION PLAN - AREA C
12903105	S-104	FOUNDATION PLAN - AREA D
12903106	S-105	FOUNDATION PLAN - AREA E
12903107	S-106	FOUNDATION PLAN - AREA F
12903108	S-107	FOUNDATION PLAN - AREA G
12903109	S-108	FOUNDATION & FRAMING PLAN - AREA H
12903110	S-501	GENERAL CONSTRUCTION DETAILS
12903111	S-502	GENERAL CONSTRUCTION DETAILS
12903112	S-503	GENERAL CONSTRUCTION DETAILS
12903113	S-504	GENERAL CONSTRUCTION DETAILS
12903114	S-511	DETAILS
12903115	S-512	DETAILS
12903116	S-513	DETAILS
12903117	S-514	DETAILS
12903118	S-515	DETAILS
	A	ARCHITECTURAL
12903119	A-001	SYMBOL LEGEND AND ABBREVIATIONS

A1 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903120	A-101	OVERALL FLOOR PLAN
12903121	A-102	FLOOR PLAN - AREA A
12903122	A-103	FLOOR PLAN - AREA B
12903123	A-104	FLOOR PLAN - AREA C
12903124	A-105	FLOOR PLAN - AREA D
12903125	A-106	FLOOR PLAN - AREA E
12903126	A-107	FLOOR PLAN - AREA F
12903127	A-108	FLOOR PLAN - AREA G
12903128	A-109	FLOOR PLAN - AREA H
12903129	A-111	DIMENSION PLAN - AREA A
12903130	A-112	DIMENSION PLAN - AREA B
12903131	A-113	DIMENSION PLAN - AREA C
12903132	A-114	DIMENSION PLAN - AREA D
12903133	A-115	DIMENSION PLAN - AREA E
12903134	A-116	DIMENSION PLAN - AREA F
12903135	A-117	DIMENSION PLAN - AREA G
12903136	A-118	DIMENSION PLAN - AREA H
12903137	A-120	COMPREHENSIVE REFLECTED CEILING PLAN
12903138	A-121	REFLECTED CEILING PLAN - AREA A
12903139	A-122	REFLECTED CEILING PLAN - AREA B
12903140	A-123	REFLECTED CEILING PLAN - AREA C
12903141	A-124	REFLECTED CEILING PLAN - AREA D
12903142	A-125	REFLECTED CEILING PLAN - AREA E
12903143	A-126	REFLECTED CEILING PLAN - AREA F
12903144	A-127	REFLECTED CEILING PLAN - AREA G
12903145	A-128	REFLECTED CEILING PLAN - AREA H
12903146	A-129	COMPREHENSIVE ROOF PLAN
12903147	A-130	AIR & MOISTURE BARRIER PLAN
12903148	A-201	EXTERIOR ELEVATIONS
12903149	A-202	EXTERIOR ELEVATIONS
12903150	A-203	EXTERIOR ELEVATIONS
12903151	A-204	EXTERIOR ELEVATIONS
12903152	A-205	EXTERIOR ELEVATIONS
12903153	A-301	BUILDING SECTIONS
12903154	A-302	BUILDING SECTIONS
12903155	A-303	BUILDING SECTIONS
12903156	A-304	BUILDING SECTIONS
12903157	A-311	WALL SECTIONS
12903158	A-401	ENLARGED PLANS
12903159	A-402	ENLARGED PLANS
12903160	A-403	ENLARGED PLANS
12903161	A-404	ENLARGED PLANS
12903162	A-405	ENLARGED PLANS
12903163	A-406	INTERIOR ELEVATIONS
12903164	A-407	INTERIOR ELEVATIONS
12903165	A-408	INTERIOR ELEVATIONS
12903166	A-409	INTERIOR ELEVATIONS
12903167	A-501	WALL TYPE DETAILS
12903168	A-502	WALL TYPE DETAILS
12903169	A-503	MASONRY DETAILS
12903170	A-504	EXTERIOR DETAILS
12903171	A-505	EXTERIOR DETAILS
12903172	A-506	EXTERIOR DETAILS
12903173	A-507	INTERIOR AND EXTERIOR DETAILS
12903174	A-508	MISCELLANEOUS DETAILS

A1 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903175	A-509	MISCELLANEOUS DETAILS
12903176	A-510	ROOF DETAILS
12903177	A-511	MISCELLANEOUS DETAILS
12903178	A-512	WALL DETAILS
12903179	A-601	DOOR AND FRAME SCHEDULE
12903180	A-602	DOOR AND FRAME TYPES
12903181	A-603	DOOR AND FRAME DETAILS
12903182	A-604	DOOR AND FRAME DETAILS
12903183	A-605	WINDOW AND LOUVER SCHEDULES AND DETAILS
12903184	A-606	EXTERIOR FINISHES SCHEDULE
	AY	ARCHITECTURAL SECURITY
12903185	AY501	RF SHIELDING NOTES AND DETAILS
12903186	AY502	RF SHIELDING DETAILS
12903187	AY503	RF SHIELDING DETAILS
12903188	AY504	RF SHIELDING DETAILS
12903189	AY505	RF SHIELDING DETAILS
12903190	AY506	RF SHIELDING DETAILS
12903191	AY507	RF SHIELDING DETAILS
12903192	AY508	RF SHIELDING DETAILS
	I	INTERIOR DESIGN
12903193	I-101	FURNITURE PLAN - AREA A
12903194	I-102	FURNITURE PLAN - AREA B
12903195	I-103	FURNITURE PLAN - AREA C
12903196	I-104	FURNITURE PLAN - AREA D
12903197	I-105	FURNITURE PLAN - AREA E
12903198	I-106	FURNITURE PLAN - AREA F
12903199	I-107	FURNITURE PLAN - AREA G
12903200	I-108	FURNITURE PLAN - AREA H
12903201	I-109	COLLATERAL EQUIPMENT PLAN – AREA B
12903202	I-111	FINISH PLAN - AREA A
12903203	I-112	FINISH PLAN - AREA B
12903204	I-113	FINISH PLAN - AREA C
12903205	I-114	FINISH PLAN - AREA D
12903206	I-115	FINISH PLAN - AREA E
12903207	I-116	FINISH PLAN - AREA F
12903208	I-117	FINISH PLAN - AREA G
12903209	I-118	FINISH PLAN - AREA H
12903210	I-121	SIGNAGE PLAN - AREA A
12903211	I-122	SIGNAGE PLAN - AREA B
12903212	I-123	SIGNAGE PLAN - AREA C
12903213	I-124	SIGNAGE PLAN - AREA D
12903214	I-125	SIGNAGE PLAN - AREA E
12903215	I-126	SIGNAGE PLAN - AREA F
12903216	I-127	SIGNAGE PLAN - AREA G
12903217	I-128	SIGNAGE PLAN - AREA H
12903218	I-201	INTERIOR ELEVATIONS
12903219	I-202	INTERIOR ELEVATIONS
12903220	I-203	INTERIOR ELEVATIONS
12903221	I-301	INTERIOR SECTIONS & DETAILS
12903222	I-302	INTERIOR SECTIONS & DETAILS
12903223	I-401	LARGE SCALE VIEWS
12903224	I-402	LARGE SCALE VIEWS
12903225	I-403	LARGE SCALE VIEWS

A1 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903226	I-404	LARGE SCALE VIEWS
12903227	I-501	SIGNAGE DETAILS
12903228	I-502	INTERIOR DETAILS
12903229	I-601	SCHEDULES & LEGENDS
12903230	I-602	SCHEDULES & LEGENDS
	F	FIRE PROTECTION
12903231	FA001	FIRE ALARM NOTES AND LEGEND - BATTALION HEADQUARTERS
12903232	FA101	FIRE ALARM FLOOR PLAN - BATTALION HEADQUARTERS AREA A
12903233	FA102	FIRE ALARM FLOOR PLAN - BATTALION HEADQUARTERS AREA B
12903234	FA103	FIRE ALARM FLOOR PLAN - BATTALION HEADQUARTERS AREA C
12903235	FA104	FIRE ALARM FLOOR PLAN - BATTALION HEADQUARTERS AREA D
12903236	FA105	FIRE ALARM FLOOR PLAN - BATTALION HEADQUARTERS AREA E
12903237	FA106	FIRE ALARM FLOOR PLAN - BATTALION HEADQUARTERS AREA F
12903238	FA107	FIRE ALARM FLOOR PLAN - BATTALION HEADQUARTERS AREA G
12903239	FA108	FIRE ALARM FLOOR PLAN - BATTALION HEADQUARTERS AREA H
12903240	FA501	FIRE ALARM DETAILS
12903241	FA502	FIRE ALARM DETAILS
12903242	FA503	FIRE ALARM DETAILS
12903243	FX001	FIRE SUPPRESSION NOTES AND LEGEND - BATTALION HEADQUARTERS
12903244	FX002	FIRE SUPPRESSION SITE PLAN
12903245	FX101	FIRE SUPPRESSION FLOOR PLAN -BATTALION HEADQUARTERS AREA A
12903246	FX102	FIRE SUPPRESSION FLOOR PLAN -BATTALION HEADQUARTERS AREA B
12903247	FX103	FIRE SUPPRESSION FLOOR PLAN -BATTALION HEADQUARTERS AREA C
12903248	FX104	FIRE SUPPRESSION FLOOR PLAN -BATTALION HEADQUARTERS AREA D
12903249	FX105	FIRE SUPPRESSION FLOOR PLAN -BATTALION HEADQUARTERS AREA E
12903250	FX106	FIRE SUPPRESSION FLOOR PLAN -BATTALION HEADQUARTERS AREA F
12903251	FX107	FIRE SUPPRESSION FLOOR PLAN -BATTALION HEADQUARTERS AREA G
12903252	FX108	FIRE SUPPRESSION FLOOR PLAN -BATTALION HEADQUARTERS AREA H
12903253	FX501	FIRE SUPPRESSION DETAILS
	P	PLUMBING
12903254	P-001	PLUMBING COVER SHEET
12903255	P-101	FIRST FLOOR - AREA A - WASTE AND VENT
12903256	P-102	FIRST FLOOR - AREA B - WASTE AND VENT
12903257	P-103	FIRST FLOOR - AREA C - WASTE AND VENT
12903258	P-104	FIRST FLOOR - AREA D - WASTE AND VENT
12903259	P-105	FIRST FLOOR - AREA E - WASTE AND VENT
12903260	P-106	FIRST FLOOR - AREA F - WASTE AND VENT
12903261	P-107	FIRST FLOOR - AREA G - WASTE AND VENT
12903262	P-108	FIRST FLOOR - AREA H - WASTE AND VENT
12903263	P-109	FIRST FLOOR - AREA A - WATER
12903264	P-110	FIRST FLOOR - AREA B - WATER
12903265	P-111	FIRST FLOOR - AREA C - WATER
12903266	P-112	FIRST FLOOR - AREA D - WATER
12903267	P-113	FIRST FLOOR - AREA E - WATER
12903268	P-114	FIRST FLOOR - AREA F - WATER
12903269	P-115	FIRST FLOOR - AREA G - WATER
12903270	P-116	FIRST FLOOR - AREA H - WATER
12903271	P-401	ENLARGED PLANS - WASTE AND VENT
12903272	P-402	ENLARGED PLANS - WASTE AND VENT
12903273	P-403	ENLARGED PLANS - WATER
12903274	P-404	ENLARGED PLANS - WATER
12903275	P-501	PLUMBING DETAILS
12903276	P-601	PLUMBING SCHEDULES

A1 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903277	P-701	RISER DIAGRAMS - AREAS A & D - WASTE AND VENT
12903278	P-702	RISER DIAGRAMS - AREA E - WASTE AND VENT
12903279	P-703	RISER DIAGRAMS - AREA F - WASTE AND VENT
12903280	P-704	RISER DIAGRAMS - AREA G - WASTE AND VENT
12903281	P-705	RISER DIAGRAMS - AREA H - WASTE AND VENT
12903282	P-706	RISER DIAGRAMS - AREAS A & D - WATER
12903283	P-707	RISER DIAGRAMS - AREA E - WATER
12903284	P-708	RISER DIAGRAMS - AREA F - WATER
12903285	P-709	RISER DIAGRAMS - AREA G - WATER
12903286	P-710	RISER DIAGRAMS - AREA H - WATER
	M MECHANICAL	
12903287	M-001	MECHANICAL COVER SHEET
12903288	MH101	FIRST FLOOR PLAN - MECHANICAL - AREA A
12903289	MH102	FIRST FLOOR PLAN - MECHANICAL - AREA B
12903290	MH103	FIRST FLOOR PLAN - MECHANICAL - AREA C
12903291	MH104	FIRST FLOOR PLAN - MECHANICAL - AREA D
12903292	MH105	FIRST FLOOR PLAN - MECHANICAL - AREA E
12903293	MH106	FIRST FLOOR PLAN - MECHANICAL - AREA F
12903294	MH107	FIRST FLOOR PLAN - MECHANICAL - AREA G
12903295	MH108	FIRST FLOOR PLAN - MECHANICAL - AREA H
12903296	MH401	MECHANICAL ROOMS ENLARGED - MECHANICAL
12903297	MP101	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA A
12903298	MP102	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA B
12903299	MP103	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA C
12903300	MP104	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA D
12903301	MP105	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA E
12903302	MP106	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA F
12903303	MP107	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA G
12903304	MP108	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA H
12903305	MP401	MECHANICAL ROOMS ENLARGED - MECHANICAL PIPING
12903306	M-301	MECHANICAL SECTION VIEWS
12903307	M-302	MECHANICAL SECTION VIEWS
12903308	M-501	MECHANICAL DETAILS
12903309	M-502	MECHANICAL DETAILS
12903310	M-503	MECHANICAL DETAILS
12903311	M-504	MECHANICAL DETAILS
12903312	M-505	MECHANICAL DETAILS
12903313	M-506	MECHANICAL DETAILS
12903314	M-507	MECHANICAL DETAILS
12903315	M-508	MECHANICAL DETAILS
12903316	M-601	MECHANICAL SCHEDULES
12903317	M-602	MECHANICAL SCHEDULES
12903318	M-603	MECHANICAL SCHEDULES
12903319	M-604	MECHANICAL SCHEDULES
12903320	M-605	MECHANICAL SCHEDULES
12903321	M-606	MECHANICAL SCHEDULES
12903322	M-701	MECHANICAL CONTROLS
12903323	M-702	MECHANICAL CONTROLS
12903324	M-703	MECHANICAL CONTROLS
12903325	M-704	MECHANICAL CONTROLS
12903326	M-705	MECHANICAL CONTROLS
12903327	M-706	MECHANICAL CONTROLS
12903328	M-707	MECHANICAL CONTROLS
12903329	M-708	MECHANICAL CONTROLS

A1 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903330	M-801	CHILLED WATER SYSTEM DIAGRAM
12903331	M-802	HOT WATER SYSTEM DIAGRAM
12903332	M-901	MECHANICAL ROOM 177 - 3D ISOMETRIC VIEWS
12903333	M-902	MECHANICAL ROOM 203 & 219 - 3D ISOMETRIC VIEWS
12903334	M-903	MECHANICAL HVAC- 3D ISOMETRIC VIEW
12903335	M-904	MECHANICAL PIPING - 3D ISOMETRIC VIEW
	E ELECTRICAL	
12903336	E-001	ELECTRICAL NOTES AND LEGEND
12903337	E-100	BUILDING OVERALL KEYPLAN
12903338	E-101	FLOOR PLAN - AREA A POWER
12903339	E-102	FLOOR PLAN - AREA B POWER
12903340	E-103	FLOOR PLAN - AREA C POWER
12903341	E-104	FLOOR PLAN - AREA D POWER
12903342	E-105	FLOOR PLAN - AREA E POWER
12903343	E-106	FLOOR PLAN - AREA F POWER
12903344	E-107	FLOOR PLAN - AREA G POWER
12903345	E-108	FLOOR PLAN - AREA H POWER
12903346	E-109	FLOOR PLAN - AREA A SECURITY INFRASTRUCTURE
12903347	E-110	FLOOR PLAN - AREA B SECURITY INFRASTRUCTURE
12903348	E-111	FLOOR PLAN - AREA C SECURITY INFRASTRUCTURE
12903349	E-112	FLOOR PLAN - AREA D SECURITY INFRASTRUCTURE
12903350	E-113	FLOOR PLAN - AREA E SECURITY INFRASTRUCTURE
12903351	E-114	FLOOR PLAN - AREA F SECURITY INFRASTRUCTURE
12903352	E-115	FLOOR PLAN - AREA G SECURITY INFRASTRUCTURE
12903353	E-116	FLOOR PLAN - AREA H SECURITY INFRASTRUCTURE
12903354	E-117	FLOOR PLAN - AREA A EQUIPMENT CONNECTIONS
12903355	E-118	FLOOR PLAN - AREA B EQUIPMENT CONNECTIONS
12903356	E-119	FLOOR PLAN - AREA C EQUIPMENT CONNECTIONS
12903357	E-120	FLOOR PLAN - AREA D EQUIPMENT CONNECTIONS
12903358	E-121	FLOOR PLAN - AREA E EQUIPMENT CONNECTIONS
12903359	E-122	FLOOR PLAN - AREA F EQUIPMENT CONNECTIONS
12903360	E-123	FLOOR PLAN - AREA G EQUIPMENT CONNECTIONS
12903361	E-124	FLOOR PLAN - AREA H EQUIPMENT CONNECTIONS
12903362	E-125	FLOOR PLAN - AREA A LIGHTING
12903363	E-126	FLOOR PLAN - AREA B LIGHTING
12903364	E-127	FLOOR PLAN - AREA C LIGHTING
12903365	E-128	FLOOR PLAN - AREA D LIGHTING
12903366	E-129	FLOOR PLAN - AREA E LIGHTING
12903367	E-130	FLOOR PLAN - AREA F LIGHTING
12903368	E-131	FLOOR PLAN - AREA G LIGHTING
12903369	E-132	FLOOR PLAN - AREA H LIGHTING
12903370	E-133	ROOF PLAN - LIGHTNING PROTECTION
12903371	E-401	ENLARGED POWER PLANS
12903372	E-402	ENLARGED POWER PLANS
12903373	E-403	ENLARGED POWER PLANS
12903374	E-404	ENLARGED POWER PLANS
12903375	E-405	ENLARGED POWER PLANS
12903376	E-501	ELECTRICAL DETAILS
12903377	E-502	ELECTRICAL DETAILS
12903378	E-503	ELECTRICAL DETAILS
12903379	E-504	ELECTRICAL DETAILS
12903380	E-505	ELECTRICAL DETAILS
12903381	E-506	ELECTRICAL DETAILS
12903382	E-507	ELECTRICAL DETAILS

A1 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903383	E-601	ELECTRICAL SCHEDULES
12903384	E-602	ELECTRICAL SCHEDULES
12903385	E-603	ELECTRICAL SCHEDULES
12903386	E-604	ELECTRICAL SCHEDULES
12903387	E-605	ELECTRICAL SCHEDULES
12903388	E-606	ELECTRICAL SCHEDULES
12903389	E-607	ELECTRICAL SCHEDULES
12903390	E-608	ELECTRICAL SCHEDULES
12903391	E-609	ELECTRICAL SCHEDULES
12903392	E-610	ELECTRICAL SCHEDULES
12903393	E-611	ELECTRICAL SCHEDULES
12903394	E-701	ELECTRICAL RISER DIAGRAM
	T TELECOMMUNICATIONS	
12903395	T-001	TELECOMMUNICATIONS NOTES AND LEGEND
12903396	T-100	BUILDING OVERALL KEYPLAN
12903397	T-101	FLOOR PLAN - AREA A TELECOMMUNICATIONS
12903398	T-102	FLOOR PLAN - AREA B TELECOMMUNICATIONS
12903399	T-103	FLOOR PLAN - AREA C TELECOMMUNICATIONS
12903400	T-104	FLOOR PLAN - AREA D TELECOMMUNICATIONS
12903401	T-105	FLOOR PLAN - AREA E TELECOMMUNICATIONS
12903402	T-106	FLOOR PLAN - AREA F TELECOMMUNICATIONS
12903403	T-107	FLOOR PLAN - AREA G TELECOMMUNICATIONS
12903404	T-108	FLOOR PLAN - AREA H TELECOMMUNICATIONS
12903405	T-109	FLOOR PLAN - CABLE TRAY
12903406	T-110	FLOOR PLAN - AREA A A/V INFRASTRUCTURE
12903407	T-111	FLOOR PLAN - AREA D A/V INFRASTRUCTURE
12903408	T-112	FLOOR PLAN - AREA E A/V INFRASTRUCTURE
12903409	T-113	FLOOR PLAN - AREA F A/V INFRASTRUCTURE
12903410	T-114	FLOOR PLAN - AREA G A/V INFRASTRUCTURE
12903411	T-115	FLOOR PLAN - AREA H A/V INFRASTRUCTURE
12903412	T-401	ENLARGED TELECOMMUNICATIONS PLANS
12903413	T-402	ENLARGED TELECOMMUNICATIONS PLANS
12903414	T-501	TELECOMMUNICATIONS DETAILS
12903415	T-502	TELECOMMUNICATIONS DETAILS
12903416	T-503	TELECOMMUNICATIONS DETAILS
12903417	T-504	TELECOMMUNICATIONS DETAILS
12903418	T-505	TELECOMMUNICATIONS DETAILS
	TA AUDIO VISUAL	
12903419	TA001	SHEET INDEX AND NOTES
12903420	TA101	AV FLOOR PLAN
12903421	TA102	AV REFLECTED CEILING PLAN
12903422	TA103	AV FLOOR PLAN
12903423	TA104	AV FLOOR PLAN
12903424	TA201	AV ELEVATIONS
12903425	TA202	AV ELEVATIONS
12903426	TA203	AV ELEVATIONS
12903427	TA601	AV EQUIPMENT SCHEDULES
12903428	TA602	TIER 2 CLASSROOM VIDEO FUNCTIONAL
12903429	TA603	TIER 2 CLASSROOM AUDIO AND CONTROL FUNCTIONAL
12903430	TA604	TIER 2 CONFERENCE VIDEO FUNCTIONAL
12903431	TA605	TIER 2 CONFERENCE AUDIO AND CONTROL FUNCTIONAL
12903432	TA606	TIER 1A CONFERENCE FUNCTIONAL
12903433	TA607	MISCELLANEOUS FUNCTIONALS

A1 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903434	TA608	AV RACK ELEVATIONS
12903435	TA701	COORDINATION DETAILS
12903436	TA702	COORDINATION DETAILS

A2 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
	G GENERAL	
12903452	G-001	COVER SHEET
12903453	G-002	LOCATION MAPS AND INDEX OF DRAWINGS
12903454	G-003	INDEX OF DRAWINGS
	GI LIFE SAFETY	
12903455	GI001	LIFE SAFETY NOTES AND LEGEND - COMPANY HEADQUARTERS
12903456	GI002	OCCUPANT LOADS - COMPANY HEADQUARTERS
12903457	GI003	CODE COMPLIANCE SITE PLAN - COMPANY HEADQUARTERS
12903458	GI101	LIFE SAFETY FLOOR PLAN - COMPANY HEADQUARTERS
	S STRUCTURAL	
12903459	S-001	COVER SHEET
12903460	S-002	STRUCTURAL NOTES
12903461	S-003	STRUCTURAL NOTES
12903462	S-101	FOUNDATION PLAN - AREA A
12903463	S-102	FOUNDATION PLAN - AREA B
12903464	S-103	FOUNDATION PLAN - AREA C
12903465	S-104	FOUNDATION PLAN - AREA D
12903466	S-105	FOUNDATION PLAN - AREA E
12903467	S-106	FOUNDATION PLAN - AREA F
12903468	S-501	GENERAL CONSTRUCTION DETAILS
12903469	S-502	GENERAL CONSTRUCTION DETAILS
12903470	S-503	GENERAL CONSTRUCTION DETAILS
12903471	S-504	GENERAL CONSTRUCTION DETAILS
12903472	S-511	DETAILS
12903473	S-512	DETAILS
12903474	S-513	DETAILS
12903475	S-514	DETAILS
	A ARCHITECTURAL	
12903476	A-001	SYMBOL LEGEND AND ABBREVIATIONS
12903477	A-101	COMPREHENSIVE FLOOR PLAN
12903478	A-102	FLOOR PLAN - AREA A
12903479	A-103	FLOOR PLAN - AREA B
12903480	A-104	FLOOR PLAN - AREA C
12903481	A-105	FLOOR PLAN - AREA D
12903482	A-106	FLOOR PLAN - AREA E
12903483	A-107	FLOOR PLAN - AREA F
12903484	A-108	DIMENSION PLAN - AREA A
12903485	A-109	DIMENSION PLAN - AREA B
12903486	A-110	DIMENSION PLAN - AREA C
12903487	A-111	DIMENSION PLAN - AREA D
12903488	A-112	DIMENSION PLAN - AREA E
12903489	A-113	DIMENSION PLAN - AREA F

A2 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903490	A-120	OVERALL REFLECTED CEILING PLAN
12903491	A-121	REFLECTED CEILING PLAN - AREA A
12903492	A-122	REFLECTED CEILING PLAN - AREA B
12903493	A-123	REFLECTED CEILING PLAN - AREA C
12903494	A-124	REFLECTED CEILING PLAN - AREA D
12903495	A-125	REFLECTED CEILING PLAN - AREA E
12903496	A-126	REFLECTED CEILING PLAN - AREA F
12903497	A-131	COMPREHENSIVE ROOF PLAN
12903498	A-141	AIR AND MOISTURE BARRIER PLAN, DETAILS AND NOTES
12903499	A-201	EXTERIOR ELEVATIONS
12903500	A-202	EXTERIOR ELEVATIONS
12903501	A-203	EXTERIOR ELEVATIONS
12903502	A-204	EXTERIOR ELEVATIONS
12903503	A-205	EXTERIOR ELEVATIONS
12903504	A-301	BUILDING SECTIONS
12903505	A-302	BUILDING SECTIONS
12903506	A-303	BUILDING SECTIONS
12903507	A-311	WALL SECTIONS
12903508	A-312	WALL SECTIONS
12903509	A-313	WALL SECTIONS
12903510	A-401	ENLARGED PLANS
12903511	A-402	ENLARGED PLANS
12903512	A-403	ENLARGED PLANS
12903513	A-404	ENLARGED PLANS
12903514	A-405	ENLARGED PLANS
12903515	A-406	INTERIOR ELEVATIONS
12903516	A-407	INTERIOR ELEVATIONS
12903517	A-408	INTERIOR ELEVATIONS
12903518	A-409	INTERIOR ELEVATIONS
12903519	A-501	WALL TYPE DETAILS
12903520	A-502	WALL TYPE DETAILS
12903521	A-503	MASONRY DETAILS
12903522	A-504	EXTERIOR DETAILS
12903523	A-505	EXTERIOR DETAILS
12903524	A-506	EXTERIOR DETAILS
12903525	A-507	INTERIOR DETAILS
12903526	A-508	MISCELLANEOUS DETAILS
12903527	A-509	MISCELLANEOUS DETAILS
12903528	A-510	ROOF DETAILS
12903529	A-512	CEILING DETAILS
12903530	A-513	CEILING DETAILS
12903531	A-514	MISCELLANEOUS DETAILS
12903532	A-515	WALL DETAILS
12903533	A-601	DOOR AND FRAME SCHEDULE
12903534	A-602	DOOR AND FRAME TYPES
12903535	A-603	DOOR AND FRAME DETAILS
12903536	A-604	DOOR AND FRAME DETAILS
12903537	A-605	WINDOW SCHEDULES AND DETAILS
12903538	A-606	WINDOW AND STOREFRONT DETAILS
12903539	A-607	LOUVER AND TRANSLUCENT PANEL DETAILS
12903540	A-610	EXTERIOR FINISHES SCHEDULE
	I	INTERIOR DESIGN
12903541	I-101	FURNITURE PLAN - AREA A
12903542	I-102	FURNITURE PLAN - AREA B

A2 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903543	I-103	FURNITURE PLAN - AREA C
12903544	I-104	FURNITURE PLAN - AREA D
12903545	I-105	FURNITURE PLAN - AREA E
12903546	I-106	FURNITURE PLAN - AREA F
12903547	I-107	COLLATERAL EQUIPMENT PLAN – AREA A
12903548	I-108	COLLATERAL EQUIPMENT PLAN – AREA E
12903549	I-111	FINISH PLAN - AREA A
12903550	I-112	FINISH PLAN - AREA B
12903551	I-113	FINISH PLAN - AREA C
12903552	I-114	FINISH PLAN - AREA D
12903553	I-115	FINISH PLAN - AREA E
12903554	I-116	FINISH PLAN - AREA F
12903555	I-121	SIGNAGE PLAN - AREA A
12903556	I-122	SIGNAGE PLAN - AREA B
12903557	I-123	SIGNAGE PLAN - AREA C
12903558	I-124	SIGNAGE PLAN - AREA D
12903559	I-125	SIGNAGE PLAN - AREA E
12903560	I-126	SIGNAGE PLAN - AREA F
12903561	I-201	INTERIOR ELEVATIONS
12903562	I-301	CASEWORK SECTIONS
12903563	I-302	CASEWORK SECTIONS
12903564	I-501	SIGNAGE DETAILS
12903565	I-502	INTERIOR DETAILS
12903566	I-601	SCHEDULES & LEGENDS
12903567	I-602	SCHEDULES & LEGENDS
	F	FIRE PROTECTION
12903568	FA001	FIRE ALARM NOTES AND LEGEND - COMPANY HEADQUARTERS
12903569	FA101	FIRE ALARM FLOOR PLAN - COMPANY HEADQUARTERS AREA A
12903570	FA102	FIRE ALARM FLOOR PLAN - COMPANY HEADQUARTERS AREA B
12903571	FA103	FIRE ALARM FLOOR PLAN - COMPANY HEADQUARTERS AREA C
12903572	FA104	FIRE ALARM FLOOR PLAN - COMPANY HEADQUARTERS AREA D
12903573	FA105	FIRE ALARM FLOOR PLAN - COMPANY HEADQUARTERS AREA E
12903574	FA106	FIRE ALARM FLOOR PLAN - COMPANY HEADQUARTERS AREA F
12903575	FA501	FIRE ALARM DETAILS
12903576	FA502	FIRE ALARM DETAILS
12903577	FA503	FIRE ALARM DETAILS
12903578	FX001	FIRE SUPPRESSION NOTES AND LEGEND - COMPANY HEADQUARTERS
12903579	FX002	FIRE SUPPRESSION SITE PLAN
12903580	FX101	FIRE SUPPRESSION FLOOR PLAN - COMPANY HEADQUARTERS AREA A
12903581	FX102	FIRE SUPPRESSION FLOOR PLAN - COMPANY HEADQUARTERS AREA B
12903582	FX103	FIRE SUPPRESSION FLOOR PLAN - COMPANY HEADQUARTERS AREA C
12903583	FX104	FIRE SUPPRESSION FLOOR PLAN - COMPANY HEADQUARTERS AREA D
12903584	FX105	FIRE SUPPRESSION FLOOR PLAN - COMPANY HEADQUARTERS AREA E
12903585	FX106	FIRE SUPPRESSION FLOOR PLAN - COMPANY HEADQUARTERS AREA F
12903586	FX501	FIRE SUPPRESSION DETAILS
	P	PLUMBING
12903587	P-001	PLUMBING COVER SHEET
12903588	P-101	FLOOR PLAN - AREA A - WASTE AND VENT
12903589	P-102	FLOOR PLAN - AREA B - WASTE AND VENT
12903590	P-103	FLOOR PLAN - AREA C - WASTE AND VENT
12903591	P-104	FLOOR PLAN - AREA D - WASETE AND VENT
12903592	P-105	FLOOR PLAN - AREA E - WASTE AND VENT
12903593	P-106	FLOOR PLAN - AREA F - WASTE AND VENT

A2 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903594	P-107	FLOOR PLAN - AREA A - WATER
12903595	P-108	FLOOR PLAN - AREA B - WATER
12903596	P-109	FLOOR PLAN - AREA C - WATER
12903597	P-110	FLOOR PLAN - AREA D - WATER
12903598	P-111	FLOOR PLAN - AREA E - WATER
12903599	P-112	FLOOR PLAN - AREA F - WATER
12903600	P-401	ENLARGED PLANS - WASTE AND VENT
12903601	P-402	ENLARGED PLANS - WATER
12903602	P-403	ENLARGED PLANS - PLUMBING
12903603	P-501	PLUMBING DETAILS
12903604	P-601	PLUMBING SCHEDULES
12903605	P-701	RISER DIAGRAM - AREA A - WASTE AND VENT
12903606	P-702	RISER DIAGRAM - AREA B - WASTE AND VENT
12903607	P-703	RISER DIAGRAM - AREA C - WASTE AND VENT
12903608	P-704	RISER DIAGRAM - AREA D - WASTE AND VENT
12903609	P-705	RISER DIAGRAM - AREA E - WASTE AND VENT
12903610	P-706	RISER DIAGRAM - AREA F - WASTE AND VENT
12903611	P-707	RISER DIAGRAM - AREA A - WATER
12903612	P-708	RISER DIAGRAM - AREA B - WATER
12903613	P-709	RISER DIAGRAM - AREA C - WATER
12903614	P-710	RISER DIAGRAM - AREA D - WATER
12903615	P-711	RISER DIAGRAM - AREA E - WATER
12903616	P-712	RISER DIAGRAM - AREA F - WATER
	M MECHANICAL	
12903617	M-001	MECHANICAL COVER SHEET
12903618	MH101	FIRST FLOOR PLAN - MECHANICAL - AREA A
12903619	MH102	FIRST FLOOR PLAN - MECHANICAL - AREA B
12903620	MH103	FIRST FLOOR PLAN - MECHANICAL - AREA C
12903621	MH104	FIRST FLOOR PLAN - MECHANICAL - AREA D
12903622	MH105	FIRST FLOOR PLAN - MECHANICAL - AREA E
12903623	MH106	FIRST FLOOR PLAN - MECHANICAL - AREA F
12903624	MH401	MECHANICAL ROOM AND CHILLER YARD ENLARGED - MECHANICAL
12903625	MP101	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA A
12903626	MP102	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA B
12903627	MP103	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA C
12903628	MP104	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA D
12903629	MP105	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA E
12903630	MP106	FIRST FLOOR PLAN - MECHANICAL PIPING - AREA F
12903631	MP401	MECHANICAL ROOM AND CHILLER YARD ENLARGED - MECHANICAL PIPING
12903632	M-301	MECHANICAL ROOM 142 SECTION VIEWS
12903633	M-302	HOT MECHANICAL ROOM 181 SECTION VIEWS
12903634	M-303	MECHANICAL SECTION VIEWS
12903635	M-501	MECHANICAL DETAILS
12903636	M-502	MECHANICAL DETAILS
12903637	M-503	MECHANICAL DETAILS
12903638	M-504	MECHANICAL DETAILS
12903639	M-505	MECHANICAL DETAILS
12903640	M-506	MECHANICAL DETAILS
12903641	M-507	MECHANICAL DETAILS
12903642	M-508	MECHANICAL DETAILS
12903643	M-601	MECHANICAL SCHEDULES
12903644	M-602	MECHANICAL SCHEDULES
12903645	M-603	MECHANICAL SCHEDULES

A2 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903646	M-604	MECHANICAL SCHEDULES
12903647	M-605	MECHANICAL SCHEDULES
12903648	M-606	MECHANICAL SCHEDULES
12903649	M-701	MECHANICAL CONTROLS
12903650	M-702	MECHANICAL CONTROLS
12903651	M-703	MECHANICAL CONTROLS
12903652	M-704	MECHANICAL CONTROLS
12903653	M-705	MECHANICAL CONTROLS
12903654	M-706	MECHANICAL CONTROLS
12903655	M-801	CHILLED AND HOT WATER SYSTEM DIAGRAMS
12903656	M-901	PARTIAL 3D ISOMETRIC VIEWS - MECHANICAL ROOMS
12903656	M-902	OVERALL 3D ISOMETRIC VIEW - MECHANICAL
12903657	M-903	OVERALL 3D ISOMETRIC VIEW - MECHANICAL PIPING
	E ELECTRICAL	
12903658	E-001	ELECTRICAL NOTES AND LEGENDS
12903659	E-100	BUILDING OVERALL KEYPLAN
12903660	E-101	FLOOR PLAN - AREA A POWER
12903661	E-102	FLOOR PLAN - AREA B POWER
12903662	E-103	FLOOR PLAN - AREA C POWER
12903663	E-104	FLOOR PLAN - AREA D POWER
12903664	E-105	FLOOR PLAN - AREA E POWER
12903665	E-106	FLOOR PLAN - AREA F POWER
12903666	E-107	FLOOR PLAN - AREA A SECURITY INFRASTRUCTURE
12903667	E-108	FLOOR PLAN - AREA B SECURITY INFRASTRUCTURE
12903668	E-109	FLOOR PLAN - AREA C SECURITY INFRASTRUCTURE
12903669	E-110	FLOOR PLAN - AREA D SECURITY INFRASTRUCTURE
12903670	E-111	FLOOR PLAN - AREA E SECURITY INFRASTRUCTURE
12903671	E-112	FLOOR PLAN - AREA F SECURITY INFRASTRUCTURE
12903672	E-113	FLOOR PLAN - AREA A EQUIPMENT CONNECTIONS
12903673	E-114	FLOOR PLAN - AREA B EQUIPMENT CONNECTIONS
12903674	E-115	FLOOR PLAN - AREA C EQUIPMENT CONNECTIONS
12903675	E-116	FLOOR PLAN - AREA D EQUIPMENT CONNECTIONS
12903676	E-117	FLOOR PLAN - AREA E EQUIPMENT CONNECTIONS
12903677	E-118	FLOOR PLAN - AREA F EQUIPMENT CONNECTIONS
12903678	E-119	FLOOR PLAN - AREA A LIGHTING
12903679	E-120	FLOOR PLAN - AREA B LIGHTING
12903680	E-121	FLOOR PLAN - AREA C LIGHTING
12903681	E-122	FLOOR PLAN - AREA D LIGHTING
12903682	E-123	FLOOR PLAN - AREA E LIGHTING
12903683	E-124	FLOOR PLAN - AREA F LIGHTING
12903684	E-125	ROOF PLAN - LIGHTNING PROTECTION
12903685	E-401	ENLARGED POWER PLANS
12903686	E-402	ENLARGED POWER PLANS
12903687	E-403	ENLARGED POWER PLANS
12903688	E-501	ELECTRICAL DETAILS
12903689	E-502	ELECTRICAL DETAILS
12903690	E-503	ELECTRICAL DETAILS
12903691	E-504	ELECTRICAL DETAILS
12903692	E-505	ELECTRICAL DETAILS
12903693	E-506	ELECTRICAL DETAILS
12903694	E-601	ELECTRICAL SCHEDULES
12903695	E-602	ELECTRICAL SCHEDULES
12903696	E-604	ELECTRICAL SCHEDULES
12903697	E-605	ELECTRICAL SCHEDULES

A2 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903698	E-606	ELECTRICAL SCHEDULES
12903699	E-607	ELECTRICAL SCHEDULES
12903700	E-608	ELECTRICAL SCHEDULES
12903701	E-609	ELECTRICAL SCHEDULES
12903702	E-610	ELECTRICAL SCHEDULES
12903703	E-611	ELECTRICAL SCHEDULES
12903704	E-701	ELECTRICAL RISER DIAGRAM
	T TELECOMMUNICATIONS	
12903705	T-001	TELECOMMUNICATIONS NOTES AND LEGEND
12903706	T-100	BUILDING OVERALL KEYPLAN
12903707	T-101	FLOOR PLAN - AREA A TELECOMMUNICATIONS
12903708	T-102	FLOOR PLAN - AREA B TELECOMMUNICATIONS
12903709	T-103	FLOOR PLAN - AREA C TELECOMMUNICATIONS
12903710	T-104	FLOOR PLAN - AREA D TELECOMMUNICATIONS
12903711	T-105	FLOOR PLAN - AREA E TELECOMMUNICATIONS
12903712	T-106	FLOOR PLAN - AREA F TELECOMMUNICATIONS
12903713	T-107	FLOOR PLAN - AREA B A/V INFRASTRUCTURE
12903714	T-108	FLOOR PLAN - AREA D A/V INFRASTRUCTURE
12903715	T-109	FLOOR PLAN - AREA F A/V INFRASTRUCTURE
12903716	T-110	FLOOR PLAN - CABLE TRAY
12903717	T-401	ENLARGED TELECOMMUNICATIONS PLANS
12903718	T-501	TELECOMMUNICATIONS DETAILS
12903719	T-502	TELECOMMUNICATIONS DETAILS
12903720	T-503	TELECOMMUNICATIONS DETAILS
12903721	T-504	TELECOMMUNICATIONS DETAILS
	TA AUDIO VISUAL	
12903722	TA001	SHEET INDEX AND NOTES
12903723	TA101	AV FLOOR PLAN
12903724	TA102	AV FLOOR PLAN
12903725	TA201	AV ELEVATIONS
12903726	TA601	AV EQUIPMENT SCHEDULES
12903727	TA602	TIER 2 CONFERENCE VIDEO FUNCTIONAL
12903728	TA603	TIER 2 CONFERENCE AUDIO AND CONTROL FUNCTIONAL
12903729	TA604	TEIR 1A CONFERENCE FUNCTIONAL
12903730	TA605	MISCELLANEOUS DETAILS
12903731	TA606	AV RACK ELEVATIONS
12903732	TA701	COORDINATION DETAILS
12903733	TA702	COORDINATION DETAILS

A3 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
	G GENERAL	
12903743	G-001	COVER SHEET
12903744	G-002	LOCATION MAPS AND INDEX OF DRAWINGS
12903745	G-003	INDEX OF DRAWINGS
	GI LIFE SAFETY	
12903746	GI001	LIFE SAFETY NOTES AND LEGEND - COMPANY STORAGE BUILDING
12903747	GI002	CODE COMPLIANCE SITE PLAN - COMPANY STORAGE BUILDING

A3 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903748	GI101	LIFE SAFETY FLOOR PLAN - COMPANY STORAGE BUILDING
	S	STRUCTURAL
12903749	S-001	COVER SHEET
12903750	S-002	STRUCTURAL NOTES
12903751	S-003	STRUCTURAL NOTES
12903752	S-101	FOUNDATION PLAN - AREA A
12903753	S-102	FOUNDATION PLAN - AREA B
12903754	S-501	GENERAL CONSTRUCTION DETAILS
12903755	S-502	GENERAL CONSTRUCTION DETAILS
12903756	S-503	GENERAL CONSTRUCTION DETAILS
12903757	S-504	GENERAL CONSTRUCTION DETAILS
12903758	S-511	DETAILS
12903759	S-512	DETAILS
	A	ARCHITECTURAL
12903760	A-001	SYMBOL LEGEND AND ABBREVIATIONS
12903761	A-101	COMPREHENSIVE FLOOR PLAN
12903762	A-102	FLOOR PLAN - AREA A
12903763	A-103	FLOOR PLAN - AREA B
12903764	A-104	COMPREHENSIVE REFLECTED CEILING PLAN
12903765	A-105	REFLECTED CEILING PLAN - AREA A
12903766	A-106	REFLECTED CEILING PLAN - AREA B
12903767	A-107	COMPREHENSIVE ROOF PLAN
12903768	A-108	AIR AND MOISTURE BARRIER PLAN, DETAILS AND NOTES
12903769	A-201	EXTERIOR ELEVATIONS
12903770	A-202	EXTERIOR ELEVATIONS
12903771	A-203	EXTERIOR ELEVATIONS
12903772	A-301	BUILDING SECTIONS
12903773	A-302	WALL SECTIONS
12903774	A-401	ENLARGED TOILET PLANS AND ELEVATIONS
12903775	A-501	WALL TYPE DETAILS
12903776	A-502	MASONRY DETAILS
12903777	A-503	MISCELLANEOUS DETAILS
12903778	A-504	MISCELLANEOUS DETAILS
12903779	A-505	MISCELLANEOUS DETAILS
12903780	A-506	ROOF DETAILS
12903781	A-601	DOOR AND FRAME SCHEDULE
12903782	A-602	DOOR AND FRAME DETAILS
12903783	A-603	DOOR AND FRAME DETAILS
12903784	A-604	WINDOW SCHEDULE AND DETAILS
	I	INTERIOR DESIGN
12903785	I-101	FURNITURE PLAN - AREA A
12903786	I-102	FURNITURE PLAN - AREA B
12903787	I-111	FINISH PLAN - AREA A
12903788	I-112	FINISH PLAN - AREA B
12903789	I-121	SIGNAGE PLAN - AREA A
12903790	I-122	SIGNAGE PLAN - AREA B
12903791	I-201	ELEVATIONS & DETAILS
12903792	I-501	SIGNAGE DETAILS
12903793	I-601	SCHEDULES & LEGENDS
	F	FIRE PROTECTION
12903794	FA001	FIRE ALARM NOTES AND LEGEND - COMPANY STORAGE BUILDING

A3 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903795	FA101	FIRE ALARM FLOOR PLAN - COMPANY STORAGE BUILDING AREA A
12903796	FA102	FIRE ALARM FLOOR PLAN - COMPANY STORAGE BUILDING AREA B
12903797	FA501	FIRE ALARM DETAILS
12903798	FA502	FIRE ALARM DETAILS
12903799	FA503	FIRE ALARM DETAILS
12903800	FX001	FIRE SUPPRESSION NOTES AND LEGEND - COMPANY STORAGE BUILDING
12903801	FX002	FIRE SUPPRESSION SITE MAP
12903802	FX101	FIRE SUPPRESSION FLOOR PLAN - COMPANY STORAGE BUILDING AREA A
12903803	FX102	FIRE SUPPRESSION FLOOR PLAN - COMPANY STORAGE BUILDING AREA B
12903804	FX401	FIRE SUPPRESSION ENLARGED FIRE PUMP ROOM - COMPANY STORAGE BUILDING
12903805	FX501	FIRE SUPPRESSION DETAILS
	P PLUMBING	
12903806	P-001	PLUMBING COVER SHEET
12903807	P-101	FIRST FLOOR PLAN - AREA A - WASTE AND VENT
12903808	P-102	FIRST FLOOR PLAN - AREA B - WASTE AND VENT
12903809	P-103	FIRST FLOOR PLAN - AREA A - WATER
12903810	P-104	FIRST FLOOR PLAN - AREA B - WATER
12903811	P-401	ENLARGED PLANS - PLUMBING
12903812	P-501	PLUMBING DETAILS
12903813	P-601	PLUMBING SCHEDULES
12903814	P-701	RISER DIAGRAM - WASTE AND VENT
12903815	P-702	RISER DIAGRAM - WATER
	M MECHANICAL	
12903816	M-001	MECHANICAL COVER SHEET
12903817	MH101	FLOOR PLAN - MECHANICAL - AREA A
12903818	MH102	FLOOR PLAN - MECHANICAL - AREA B
12903819	M-301	MECHANICAL SECTION VIEWS
12903820	MH401	MECHANICAL ROOM AND CHILLER YARD ENLARGED - MECHANICAL
12903821	MP401	MECHANICAL ROOM AND CHILLER YARD ENLARGED - MECHANICAL PIPNG
12903822	M-501	MECHANICAL DETAILS
12903823	M-502	MECHANICAL DETAILS
12903824	M-503	MECHANICAL DETAILS
12903825	M-504	MECHANICAL DETAILS
12903826	M-505	MECHANICAL DETAILS
12903827	M-506	MECHANICAL DETAILS
12903828	M-507	MECHANICAL DETAILS
12903829	M-508	MECHANICAL DETAILS
12903830	M-601	MECHANICAL SCHEDULES
12903831	M-602	MECHANICAL SCHEDULES
12903832	M-603	MECHANICAL SCHEDULES
12903833	M-701	MECHANICAL CONTROLS
12903834	M-702	MECHANICAL CONTROLS
12903835	M-703	MECHANICAL CONTROLS
12903836	M-704	MECHANICAL CONTROLS
12903837	M-705	MECHANICAL CONTROLS
12903838	M-706	MECHANICAL CONTROLS
12903839	M-801	CHILLED AND HOT WATER SYSTEM DIAGRAMS
12903840	M-901	PARTIAL 3D ISOMETRIC VIEWS - MECHANICAL ROOMS

A3 INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12903841	M-902	OVERALL 3D ISOMETRIC VIEW - MECHANICAL
	E ELECTRICAL	
12903842	E-001	ELECTRICAL NOTES AND LEGENDS
12903843	E-101	FLOOR PLAN - AREA A POWER
12903844	E-102	FLOOR PLAN - AREA B POWER
12903845	E-103	FLOOR PLAN - AREA A EQUIPMENT CONNECTIONS
12903846	E-104	FLOOR PLAN - AREA B EQUIPMENT CONNECTIONS
12903847	E-105	FLOOR PLAN - AREA A LIGHTING
12903848	E-106	FLOOR PLAN - AREA B LIGHTING
12903849	E-107	ROOF PLAN - LIGHTNING PROTECTION
12903850	E-401	ENLARGED FLOOR PLANS
12903851	E-501	ELECTRICAL DETAILS
12903852	E-502	ELECTRICAL DETAILS
12903853	E-503	ELECTRICAL DETAILS
12903854	E-504	ELECTRICAL DETAILS
12903855	E-601	ELECTRICAL SCHEDULES
12903856	E-602	ELECTRICAL SCHEDULES
12903857	E-603	ELECTRICAL SCHEDULES
12903858	E-701	ELECTRICAL RISER DIAGRAM
	T TELECOMMUNICATIONS	
12903859	T-001	TELECOMMUNICATIONS NOTES AND LEGEND
12903860	T-101	FLOOR PLAN - AREA A TELECOMMUNICATIONS
12903861	T-102	FLOOR PLAN - AREA B TELECOMMUNICATIONS
12903862	T-501	TELECOMMUNICATIONS DETAIL S
12903863	T-502	TELECOMMUNICATIONS DETAILS
12903864	T-503	TELECOMMUNICATIONS DETAILS

SITE INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
	G GENERAL	
12902818	G-001	COVER SHEET
12902819	G-002	LOCATION MAPS AND NOTES
12902820	G-003	INDEX OF DRAWINGS
	B GEOTECHNICAL	
12902821	B-001	SYMBOL LEGEND, ABBREVIATIONS AND NOTES
12902822	B-101	SOIL BORING LOCATION PLAN
12902823	B-601	GEOTECHNICAL BORING LOGS
12902824	B-602	GEOTECHNICAL BORING LOGS
12902825	B-603	GEOTECHNICAL BORING LOGS
12902826	B-604	GEOTECHNICAL BORING LOGS
12902827	B-605	GEOTECHNICAL BORING LOGS
12902828	B-606	GEOTECHNICAL BORING LOGS
12902829	B-607	GEOTECHNICAL BORING LOGS
12902830	B-608	GEOTECHNICAL BORING LOGS
12902831	B-609	GEOTECHNICAL BORING LOGS
12902832	B-610	GEOTECHNICAL BORING LOGS
12902833	B-611	GEOTECHNICAL BORING LOGS
12902834	B-612	GEOTECHNICAL BORING LOGS

SITE INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12902835	B-613	GEOTECHNICAL BORING LOGS
12902836	B-614	GEOTECHNICAL BORING LOGS
12902837	B-615	GEOTECHNICAL BORING LOGS
12902838	B-616	GEOTECHNICAL BORING LOGS
12902839	B-701	GEOTECHNICAL OBSERVATION AND LABORATORY TESTING DATA
12902840	B-702	GEOTECHNICAL OBSERVATION AND LABORATORY TESTING DATA
12902841	B-703	GEOTECHNICAL OBSERVATION AND LABORATORY TESTING DATA
12902842	B-704	GEOTECHNICAL OBSERVATION AND LABORATORY TESTING DATA
	V SURVEY	
12902843	VF001	SURVEY CONTROL POINTS, NOTES AND LEGEND
12902844	VF100	OVERALL EXISTING CONDITIONS
12902845	VF101	PARTIAL EXISTING CONDITIONS - AREAS 1 & 2
12902846	VF102	PARTIAL EXISTING CONDITIONS - AREAS 3 & 4
12902847	VF103	PARTIAL EXISTING CONDITIONS - AREA 5
12902848	VF104	PARTIAL EXISTING CONDITIONS - AREA 6
12902849	VF105	PARTIAL EXISTING CONDITIONS - AREA 7
12902850	VF106	PARTIAL EXISTING CONDITIONS - AREA 8
12902851	VF107	PARTIAL EXISTING CONDITIONS - AREA 9
12902852	VF108	PARTIAL EXISTING CONDITIONS - AREA 10
12902853	VF109	PARTIAL EXISTING CONDITIONS - AREA 1 1
12902854	VF110	PARTIAL EXISTING CONDITIONS - AREA 12
12902855	VF111	PARTIAL EXISTING CONDITIONS - AREA 13
12902856	VF112	PARTIAL EXISTING CONDITIONS - AREA 14
12902857	VF113	PARTIAL EXISTING CONDITIONS - AREAS 15
12902858	VF114	PARTIAL EXISTING CONDITIONS - AREAS 16 & 17
12902859	VF115	PARTIAL EXISTING CONDITIONS - AREAS 18 & 19
12902860	VF116	PARTIAL EXISTING CONDITIONS - AREAS 20 & 21
12902861	VF117	PARTIAL EXISTING CONDITIONS - AREAS 22 & 23
12902862	VF118	PARTIAL EXISTING CONDITIONS - AREAS 24 & 25
12902863	VF119	PARTIAL EXISTING CONDITIONS - AREAS 26 & 27
12902864	VF120	PARTIAL EXISTING CONDITIONS - AREAS 34 & 35
12902865	VF121	PARTIAL EXISTING CONDITIONS - AREAS 32 & 33
12902866	VF122	PARTIAL EXISTING CONDITIONS - AREAS 30 & 31
12902867	VF123	PARTIAL EXISTING CONDITIONS - AREAS 28 & 29
	C CIVIL	
12902868	C-001	CIVIL ABBREVIATIONS AND LEGENDS
12902869	CD100	OVERALL DEMOLITION PLAN
12902870	CD101	PARTIAL DEMOLITION PLAN - AREA 4
12902871	CD102	PARTIAL DEMOLITION PLAN - AREA 5
12902872	CD103	PARTIAL DEMOLITION PLAN - AREA 6
12902873	CD104	PARTIAL DEMOLITION PLAN - AREA 7
12902874	CD105	PARTIAL DEMOLITION PLAN - AREA 8
12902875	CD106	PARTIAL DEMOLITION PLAN - AREA 9
12902876	CD107	PARTIAL DEMOLITION PLAN - AREA 10
12902877	CD108	PARTIAL DEMOLITION PLAN - AREA 11
12902878	CD109	PARTIAL DEMOLITION PLAN - AREA 12
12902879	CD110	PARTIAL DEMOLITION PLAN - AREA 13
12902880	CD111	PARTIAL DEMOLITION PLAN - AREA 14
12902881	CS100	OVERALL SITE PLAN
12902882	CS101	PARTIAL SITE PLAN - AREA 4
12902883	CS102	PARTIAL SITE PLAN - AREA 5
12902884	CS103	PARTIAL SITE PLAN - AREA 6
12902885	CS104	PARTIAL SITE PLAN - AREA 7

SITE INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12902886	CS105	PARTIAL SITE PLAN - AREA 8
12902887	CS106	PARTIAL SITE PLAN - AREA 9
12902888	CS107	PARTIAL SITE PLAN - AREA 10
12902889	CS108	PARTIAL SITE PLAN - AREA 11
12902890	CS109	PARTIAL SITE PLAN - AREA 12
12902891	CS110	PARTIAL SITE PLAN - AREA 13
12902892	CS111	PARTIAL SITE PLAN - AREA 14
12902893	CS112	CONCRETE JOINTING PLAN
12902894	CS121	ROADWAY PLAN & PROFILE
12902895	CS122	ROADWAY PLAN & PROFILE
12902896	CS123	ROADWAY PLAN & PROFILE
12902897	CS124	ROADWAY PLAN & PROFILE
12902898	CS125	ROADWAY PLAN & PROFILE
12902899	CG100	OVERALL GRADING PLAN
12902900	CG101	PARTIAL GRADING PLAN - AREA 4
12902901	CG102	PARTIAL GRADING PLAN - AREA 5
12902902	CG103	PARTIAL GRADING PLAN - AREA 6
12902903	CG104	PARTIAL GRADING PLAN - AREA 7
12902904	CG105	PARTIAL GRADING PLAN - AREA 8
12902905	CG106	PARTIAL GRADING PLAN - AREA 9
12902906	CG107	PARTIAL GRADING PLAN - AREA 10
12902907	CG108	PARTIAL GRADING PLAN - AREA 11
12902908	CG109	PARTIAL GRADING PLAN - AREA 12
12902909	CG110	PARTIAL GRADING PLAN - AREA 13
12902910	CG111	PARTIAL GRADING PLAN - AREA 14
12902911	CG112	PARTIAL DRAINAGE PLAN - AREA 5
12902912	CG113	PARTIAL DRAINAGE PLAN - AREA 6
12902913	CG114	PARTIAL DRAINAGE PLAN - AREA 7
12902914	CG115	PARTIAL DRAINAGE PLAN - AREA 8
12902915	CG116	PARTIAL DRAINAGE PLAN - AREA 9
12902916	CG117	PARTIAL DRAINAGE PLAN - AREA 10
12902917	CG118	PARTIAL DRAINAGE PLAN - AREA 11
12902918	CG119	PARTIAL DRAINAGE PLAN - AREA 12
12902919	CG120	PARTIAL DRAINAGE PLAN - AREA 13
12902920	CG121	PARTIAL DRAINAGE PLAN - AREA 14
12902921	CG131	PARTIAL EROSION CONTROL PLAN - AREAS 3 & 4 - PHASE 1
12902922	CG132	PARTIAL EROSION CONTROL PLAN - AREA 5 - PHASE 1
12902923	CG133	PARTIAL EROSION CONTROL PLAN - AREA 6 - PHASE 1
12902924	CG134	PARTIAL EROSION CONTROL PLAN - AREA 7 - PHASE 1
12902925	CG135	PARTIAL EROSION CONTROL PLAN - AREA 8 - PHASE 1
12902926	CG136	PARTIAL EROSION CONTROL PLAN - AREA 9 - PHASE 1
12902927	CG137	PARTIAL EROSION CONTROL PLAN - AREA 10 - PHASE 1
12902928	CG138	PARTIAL EROSION CONTROL PLAN - AREA 11 - PHASE 1
12902929	CG139	PARTIAL EROSION CONTROL PLAN - AREA 12 - PHASE 1
12902930	CG140	PARTIAL EROSION CONTROL PLAN - AREA 13 - PHASE 1
12902931	CG141	PARTIAL EROSION CONTROL PLAN - AREA 14 - PHASE 1
12902932	CG142	PARTIAL EROSION CONTROL PLAN - AREAS 3 & 4 - PHASE 2
12902933	CG143	PARTIAL EROSION CONTROL PLAN - AREA 5 - PHASE 2
12902934	CG144	PARTIAL EROSION CONTROL PLAN - AREA 6 - PHASE 2
12902935	CG145	PARTIAL EROSION CONTROL PLAN - AREA 7 - PHASE 2
12902936	CG146	PARTIAL EROSION CONTROL PLAN - AREA 8 - PHASE 2
12902937	CG147	PARTIAL EROSION CONTROL PLAN - AREA 9 - PHASE 2
12902938	CG148	PARTIAL EROSION CONTROL PLAN - AREA 10 - PHASE 2
12902939	CG149	PARTIAL EROSION CONTROL PLAN - AREA 11 - PHASE 2
12902940	CG150	PARTIAL EROSION CONTROL PLAN - AREA 12 - PHASE 2

SITE INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12902941	CG151	PARTIAL EROSION CONTROL PLAN - AREA 13 - PHASE 2
12902942	CG152	PARTIAL EROSION CONTROL PLAN - AREA 14 - PHASE 2
12902943	CU100	OVERALL UTILITY PLAN
12902944	CU101	PARTIAL UTILITY PLAN - AREA 3 & 4
12902945	CU102	PARTIAL UTILITY PLAN - AREA 5
12902946	CU103	PARTIAL UTILITY PLAN - AREA 6
12902947	CU104	PARTIAL UTILITY PLAN - AREA 7
12902948	CU105	PARTIAL UTILITY PLAN - AREA 8
12902949	CU106	PARTIAL UTILITY PLAN - AREA 9
12902950	CU107	PARTIAL UTILITY PLAN - AREA 10
12902951	CU108	PARTIAL UTILITY PLAN - AREA 12
12902952	CU109	PARTIAL UTILITY PLAN - AREA 13
12902953	CU110	PARTIAL UTILITY PLAN - AREAS 15
12902954	CU111	PARTIAL UTILITY PLAN - AREAS 16 & 17
12902955	CU112	PARTIAL UTILITY PLAN - AREAS 18 & 19
12902956	CU113	PARTIAL UTILITY PLAN - AREAS 20 & 21
12902957	CU114	PARTIAL UTILITY PLAN - AREAS 22 & 23
12902958	CU115	PARTIAL UTILITY PLAN - AREAS 24 & 25
12902959	CU116	PARTIAL UTILITY PLAN - AREAS 26 & 27
12902960	CU117	PARTIAL UTILITY PLAN - AREAS 1 & 2
12902961	CU118	PARTIAL UTILITY PLAN - AREAS 28 & 29
12902962	CU119	PARTIAL UTILITY PLAN - AREAS 30 & 31
12902963	CU120	PARTIAL UTILITY PLAN - AREAS 32 & 33
12902964	CU121	PARTIAL UTILITY PLAN - AREAS 34 & 35
12902965	CU200	PARTIAL UTILITY ALIGNMENT PLAN
12902966	CU201	PARTIAL UTILITY ALIGNMENT PLAN
12902967	CU202	PARTIAL UTILITY ALIGNMENT PLAN
12902968	CU203	STORM DRAIN PROFILES
12902969	CU204	STORM DRAIN PROFILES
12902970	CU205	STORM DRAIN PROFILES
12902971	CU206	STORM DRAIN PROFILES
12902972	CU207	STORM DRAIN PROFILES
12902973	CU208	STORM DRAIN PROFILES
12902974	CU209	STORM DRAIN PROFILES
12902975	CU210	STORM DRAIN PROFILES
12902976	CU211	STORM DRAIN PROFILES
12902977	CU212	GRAVITY SEWER PROFILE
12902978	CU213	GRAVITY SEWER PROFILE
12902979	CU214	GRAVITY SEWER PROFILE
12902980	CU215	WATER PROFILE
12902981	CU216	WATER MAIN PROFILE
12902982	CU217	WATER MAIN PROFILE
12902983	CU218	WATER MAIN PROFILE
12902984	CU219	WATER MAIN PROFILE
12902985	CU220	WATER MAIN PROFILE
12902986	CU221	WATER MAIN PROFILE
12902987	CU222	FORCE MAIN SEWER PROFILE
12902988	CU223	FORCE MAIN SEWER PROFILE
12902989	CU224	FORCE MAIN SEWER PROFILE
12902990	CU225	FORCE MAIN SEWER PROFILE
12902991	CU226	FORCE MAIN SEWER PROFILE
12902992	CU227	FORCE MAIN SEWER PROFILE
12902993	CU228	FORCE MAIN SEWER PROFILE
12902994	CU229	FORCE MAIN SEWER PROFILE
12902995	CU230	FORCE MAIN SEWER PROFILE

SITE INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
12902996	CU231	FORCE MAIN SEWER PROFILE
12902997	CU232	BORE PIT PROFILES
12902998	C-501	EROSION AND SEDIMENT CONTROL DETAILS
12902999	C-502	EROSION AND SEDIMENT CONTROL DETAILS
12903000	C-503	EROSION AND SEDIMENT CONTROL DETAILS
12903001	C-504	EROSION AND SEDIMENT CONTROL DETAILS
12903002	C-505	EROSION AND SEDIMENT CONTROL DETAILS
12903003	C-506	NCG01
12903004	C-507	NCG01
12903005	C-511	SITE DETAILS
12903006	C-512	SITE DETAILS
12903007	C-513	SITE DETAILS
12903008	C-514	SITE DETAILS
12903009	C-515	SITE DETAILS
12903010	C-516	CIVIL DETAILS
12903011	C-517	CIVIL DETAILS
12903012	C-518	SITE DETAILS
12903013	C-519	TYPICAL SECTIONS AND SITE DETAILS
12903014	C-521	SITE UTILITY DETAILS
12903015	C-522	SITE UTILITY DETAILS
12903016	C-523	SITE UTILITY DETAILS
12903017	C-524	SITE UTILITY DETAILS
12903018	C-525	SITE UTILITY DETAILS
12903019	C-526	SITE UTILITY DETAILS
12903020	C-527	SITE UTILITY DETAILS
12903021	C-528	SITE UTILITY DETAILS
12903022	C-529	SITE UTILITY DETAILS
12903023	C-530	SITE UTILITY DETAILS
12903024	C-531	SITE UTILITY DETAILS
12903025	C-532	SITE UTILITY DETAILS
12903026	C-533	SITE UTILITY DETAILS
	LS LANDSCAPE ARCHITECTURE	
12903027	LS100	OVERALL LANDSCAPING PLAN
12903028	LS101	PARTIAL LANDSCAPING PLAN - AREA 4
12903029	LS102	PARTIAL LANDSCAPING PLAN - AREA 5
12903030	LS103	PARTIAL LANDSCAPING PLAN - AREA 6
12903031	LS104	PARTIAL LANDSCAPING PLAN - AREA 7
12903032	LS105	PARTIAL LANDSCAPING PLAN - AREA 8
12903033	LS106	PARTIAL LANDSCAPING PLAN - AREA 9
12903034	LS107	PARTIAL LANDSCAPING PLAN - AREA 10
12903035	LS108	PARTIAL LANDSCAPING PLAN - AREA 1 1
12903036	LS109	PARTIAL LANDSCAPING PLAN - AREA 12
12903037	LS110	PARTIAL LANDSCAPING PLAN - AREA 13
12903038	LS111	PARTIAL LANDSCAPING PLAN - AREA 14
12903039	LS501	PARTIAL LANDSCAPING PLAN - DETAILS
	S STRUCTURAL	
12903040	S-001	COVER SHEET
12903041	S-002	STRUCTURAL NOTES
12903042	S-101	FOUNDATION PLAN
12903043	S-102	FOUNDATION PLAN
12903044	S-501	GENERAL CONSTRUCTION DETAILS
12903045	S-502	GENERAL CONSTRUCTION DETAILS
12903046	S-511	DETAILS

SITE INDEX OF DRAWINGS

NAVFAC NO	PLATE NO	SHEET TITLE
	A ARCHITECTURAL	
12903047	A-001	SYMBOL LEGEND AND ABBREVIATIONS
12903048	A-101	DUMPSTER ENCLOSURE DETAILS
	ES ELECTRICAL	
12903049	ES001	SITE ELECTRICAL LEGEND
12903050	ES100	OVERALL SITE PLAN - ELECTRICAL
12903051	ES101	SITE PLAN - ELECTRICAL
12903052	ES102	SITE PLAN - ELECTRICAL
12903053	ES103	SITE PLAN - ELECTRICAL
12903054	ES104	SITE PLAN - ELECTRICAL
12903055	ES105	SITE PLAN - ELECTRICAL
12903056	ES106	SITE PLAN - ELECTRICAL
12903057	ES107	SITE PLAN - ELECTRICAL
12903058	ES501	ELECTRICAL SITE DETAILS
12903059	ES502	ELECTRICAL SITE DETAILS
12903060	ES503	ELECTRICAL SITE DETAILS
12903061	ES504	ELECTRICAL SITE DETAILS
12903062	ES505	ELECTRICAL SITE DETAILS
12903063	ES506	ELECTRICAL SITE DETAILS
12903064	ES507	ELECTRICAL SITE DETAILS
	TS TELECOMM	
12903065	TS100	OVERALL SITE PLAN - TELECOMMUNICATIONS
12903066	TS101	SITE PLAN - TELECOMMUNICATIONS
12903067	TS102	SITE PLAN - TELECOMMUNICATIONS
12903068	TS103	SITE PLAN - TELECOMMUNICATIONS
12903069	TS104	SITE PLAN - TELECOMMUNICATIONS
12903070	TS105	SITE PLAN - TELECOMMUNICATIONS
12903071	TS106	SITE PLAN - TELECOMMUNICATIONS
12903072	TS107	SITE PLAN - TELECOMMUNICATIONS
12903073	TS108	SITE PLAN - TELECOMMUNICATIONS
12903074	TS109	SITE PLAN - TELECOMMUNICATIONS
12903075	TS110	SITE PLAN - TELECOMMUNICATIONS
12903076	TS111	SITE PLAN - TELECOMMUNICATIONS
12903077	TS112	SITE PLAN - TELECOMMUNICATIONS
12903078	TS113	SITE PLAN - TELECOMMUNICATIONS
12903079	TS501	TELECOMMUNICATIONS SITE DETAILS

-- End of Document --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 11 00

SUMMARY OF WORK

06/25

PART 1 GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

1.1.1 Project Description

The work includes P-1550, SOF Battalion Headquarters Facility (A1), SOF Company/Team Facilities (A2-1 & A2-2), Company Storage Building (A3), and supporting site infrastructure extensions, distribution, and improvements. Site infrastructure includes water main extensions, sanitary sewer distribution and lift station, comm duct bank extensions and home run to the communication building near the intersection of Rifle Range Road and Powder Lane. Site improvements include extension of Everett Creek Road, POV parking lots, tactical drives and aprons, and MARSOC installation fencing perimeter expansion to enclose the P-1550 compound.

1.1.2 Location

The work shall be located at the Marine Corps Base Camp Lejeune, North Carolina, at the building and/or area as described in the attached project description. The exact location will be indicated by the Contracting Officer.

1.2 EXISTING WORK

In addition to "FAR 52.236-9, Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements":

a. Remove or alter existing work in such a manner as to prevent injury or damage to any portions of the existing work which remain.

b. Repair or replace portions of existing work which have been altered during construction operations to match existing or adjoining work, as approved by the Contracting Officer. At the completion of operations, existing work shall be in a condition equal to or better than that which existed before new work started.

1.3 LOCATION OF UNDERGROUND FACILITIES

The Contractor will be responsible for obtaining the services of a professional utility locator to scan the construction site with electromagnetic or sonic equipment, and mark the surface of the ground where existing underground utilities are discovered. If the underground utility cannot be confirmed, the contractor shall pot-hole area until piping location is verified. Dowsing or any other type of divination method is not considered an acceptable practice for locating utilities on board MCB Camp Lejeune. Verify the elevations of existing piping, utilities, and any type of underground obstruction not indicated or specified to be removed but indicated or discovered during scanning in

locations to be traversed by piping, ducts, and other work to be installed. Verify elevations before installing new work closer than nearest manhole or other structure at which an adjustment in grade can be made.

1.3.1 Notification Prior to Excavation

Notify the Contracting Officer's Representative (COR) 48 hours prior to starting excavation work.

1.4 GOVERNMENT-FURNISHED MATERIAL AND EQUIPMENT

Government furnished material and equipment will be indicated on drawings and in scope of work if applicable.

1.5 MARINE CORPS ENTERPRISE NETWORK (MCEN) COORDINATION REQUIREMENTS

1.5.1 BaseTel Access

Allow BaseTel access to the facility towards the end of construction (finishes 90 percent complete, rough-in 100 percent complete, Inside Plant (ISP)/Outside Plant (OSP) infrastructure in place) to provide equipment in the telecommunications rooms and make final connections. Coordinate efforts with BaseTel to facilitate joint use of building spaces during the final phases of construction. After the Contracting Officer has facilitated coordination meetings between the two contractors, within one week, incorporate the effort of additional coordination with BaseTel into the construction schedule to demonstrate a plan for maintaining the Contract duration.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 14 00

WORK RESTRICTIONS (MCBL)
04/22

PART 1 GENERAL

1.1 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

List of Contact Personnel

1.2 SPECIAL SCHEDULING REQUIREMENTS

a. The Contractor shall comply with all special scheduling requirements as described in the attached project description, and as noted on the drawings.

d. Permission to interrrupt any Station roads, railroads, and/or utility service shall be requested in writing a minimum of 15 calendar days prior to the desired date of interruption.

1.3 CONTRACTOR ACCESS AND USE OF PREMISES

1.3.1 Activity Regulations

Ensure that Contractor personnel employed on the Activity become familiar with and obey Activity regulations including safety, fire, traffic and security regulations. Keep within the limits of the work and avenues of ingress and egress. Wear appropriate personal protective equipment (PPE) in designated areas. Do not enter any restricted areas unless required to do so and until cleared for such entry. Ensure all Contractor equipment, include delivery vehicles, are clearly identified with their company name.

1.3.1.1 Subcontractors and Personnel Contacts

Provide a list of contact personnel of the Contractor and subcontractors including addresses and telephone numbers for use in the event of an emergency. As changes occur and additional information becomes available, correct and change the information contained in previous lists.

1.3.1.2 Installation Access

Obtain access to Navy installations through participation in the Defense Biometrics Identification System (DBIDS). Requirements for Contractor employee registration, and transition for employees currently under Navy Commercial Access Control System (NCACS), are available at https://www.cnic.navy.mil/om/dbids.html. No fees are associated with obtaining a DBIDS credential.

Participation in the DBIDS is not mandatory, and Contractor personnel may apply for One-Day Passes at the Base Visitor Control Office to access an installation.

The following are specific details regarding contractor personnel requirements. For the most up-to-date information regarding Base Access please visit https://www.lejeune.marines.mil/Base-Access/.

1.3.1.2.1 Registration for DBIDS

Registration for DBIDS is available at https://www.cnic.navy.mil/om/dbids.html. Procedure includes:

a. Present a letter or official award document (i.e. DD Form 1155 or SF 1442) from the Contracting Officer, that provides the purpose for access, to the base Visitor Control Center representative.

b. Present valid identification, such as a passport or Real ID Act-compliant state driver's license.

c. Provide completed SECNAV FORM 5512/1 to the base Visitor Control Center representative to obtain a background check. This form is available for download at https://www.cnic.navy.mil/om/dbids.html.

d. Upon successful completion of the background check, the Government will complete the DBIDS enrollment process, which includes Contractor employee photo, fingerprints, base restriction and several other assessments.

e. Upon successful completion of the enrollment process, the Contractor employee will be issued a DBIDS credential, and will be allowed to proceed to worksite.

1.3.1.2.2 DBIDS Eligibility Requirements

Throughout the length of the contract, the Contractor employee must continue to meet background screen standards. Periodic background screenings are conducted to verify continued DBIDS participation and installation access privileges. DBIDS access privileges will be immediately suspended or revoked if at any time a Contractor employee becomes ineligible.

An adjudication process may be initiated when a background screen failure results in disqualification from participation in the DBIDS, and Contractor employee does not agree with the reason for disqualification. The Government is the final authority.

1.3.1.2.3 DBIDS Notification Requirements

a. Immediately report instances of lost or stolen badges to the Contracting Officer.

b. Immediately collect DBIDS credentials and notify the Contracting Officer in writing under the following circumstances:

(1) An employee has departed the company without having properly returned or surrendered their DBIDS credentials.

(2) There is a reasonable basis to conclude that an employee, or former employee, might pose a risk, compromise, or threat to the safety or security of the Installation or anyone therein.

1.3.1.2.4 One-Day Passes

Personnel applying for One-Day passes at the Base Visitor Control Office are subject to daily mandatory vehicle inspection, and will have limited access to the installation. The Government is not responsible for any cost or lost time associated with obtaining daily passes or added vehicle inspections incurred by non-participants in the DBIDS.

1.3.2 No Smoking Policy

Smoking is prohibited within and outside of all buildings on installation, except in designated smoking areas. This applies to existing buildings, buildings under construction and buildings under renovation. Discarding tobacco materials other than into designated tobacco receptacles is considered littering and is subject to fines. The Contracting Officer will identify designated smoking areas.

1.3.3 Working Hours

Regular working hours shall be 0730-1600, Monday through Friday, excluding Government holidays.

1.3.4 Work Outside Regular Hours

Work outside regular working hours requires COR approval. Provide written request at least 15 calendar days prior to such work to allow arrangements to be made by the Government for inspecting the work in progress. During periods of darkness, the different parts of the work shall be lighted in a manner approved by the COR.

1.3.5 Occupied Building and Existing Buildings

The Contractor shall be working in portions of an existing building which is occupied. The existing building and its contents shall be kept secure at all times.

1.3.6 Utility Cutovers and Interruptions

a. The Contractor shall coordinate a minimum of 14 calendar days prior to any planned utility cutover / interruption. Make utility cutovers and interruptions OUTSIDE normal working hours. Working hours are indicated on the drawings.

b. Ensure that new utility lines are complete, except for the connection, before interrupting existing service.

c. Interruption to water, sanitary sewer, storm sewer, telephone service, electric service, air conditioning, heating, fire alarm, and compressed air shall be considered utility cutovers. This time limit includes time for deactivation and reactivation.

d. Operation of Station Utilities: The Contractor shall not operate nor disturb the setting of control devices in the station utilities system, including water, sewer, electrical, and steam services. The Government will operate the control devices as required for normal conduct of the work. The Contractor shall notify the Contracting Officer at least 15 days prior to such operation.

1.4 SECURITY REQUIREMENTS

Contract Clause "FAR 52.204-2, Security Requirements and Alternate II," "FAC 5252.236-9301, Special Working Conditions and Entry to Work Area," apply.

1.5 EMERGENCY UNEXPLODED ORDNANCE (UXO) RESPONSE

In the event that UXO, as defined in 40 CFR 260 is encountered during the construction activities that is deemed to be a threat to human health or the environment, Camp Lejeune Military Police and EOD professionals shall be immediately contacted to conduct an emergency response. Additionally, immediately contact the Contracting Officer if UXO is encountered. An evaluation of this scenario and procedures, with contract numbers, shall be included in the Health and Safety Plan (HASP) for the fieldwork.

1.5.1 3R TRAINING

All Contractor personnel performing ground disturbing activities must complete contractor awareness training related to recognizing UXO. This training (3R TRAINING) is available online at: http://www.lejeune.marines.mil/OfficesStaff/EnvironmentalMgmt/TrainingVideo.aspx

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION 01 20 00

PRICE AND PAYMENT PROCEDURES
11/20, CHG 5: 02/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EP 1110-1-8	(2021) Engineering and Design -- Construction Equipment Ownership and Operating Expense Schedule

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Earned Value Report; G

1.3 EARNED VALUE REPORT

1.3.1 Data Required

This Contract requires the use of a cost-loaded Network Analysis Schedule (NAS). Schedule of Prices must not be used with cost-loaded Network Analysis Schedule (NAS). Use Earned Value Report derived from cost-loaded NAS. Within 15 calendar days of Contract Award, prepare and deliver to the Contracting Officer a Earned Value Report (construction Contract) as directed by the Contracting Officer. Provide a detailed breakdown of the Contract price, giving quantities for each of the various kinds of work, unit prices, and extended prices. Indirect activities (e.g., meetings, presentations, submittals, surveys, haul road or storage yard maintenance, dust control, security) will not be cost loaded. Evenly distribute the costs across the associated construction activities. Contractor overhead and profit including salaries for field office personnel, if applicable, must be proportionately spread over all pay items and not included as individual pay items.

1.3.2 Payment Schedule Instructions

Payments will not be made until the Earned Value Report from the cost-loaded NAS has been submitted to and accepted by the Contracting Officer.

Additionally, the Earned Value Report must be separated as follows:

a. Primary Facilities Cost Breakdown:

Defined as work on the primary facilities out to the 5 foot line. Work out to the 5 foot line includes construction encompassed within a theoretical line 5 foot from the face of exterior walls and includes attendant construction, such as pad mounted HVAC cooling equipment, cooling towers, and transformers placed beyond the 5 foot line.

b. Supporting Facilities Cost Breakdown:

Defined as site work, including incidental work, outside the 5 foot line.

1.3.3 Schedule Requirements for HVAC TAB

The field work requirements in Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC must be broken down in the Earned Value Report from the cost-loaded NAS by separate line items which reflect measurable deliverables. The value for each pay item listed below will be established on a case by case basis for each Contract. The line items are as follows:

a. Approval of Design Review Report: The TABS Agency is required to conduct a review of the project plans and specifications to identify any feature, or the lack thereof, that would preclude successful testing and balancing of the project HVAC systems. Submit the resulting findings to the Government to allow correction of the design. The progress payment will not be issued until the report is reviewed and approved.

b. Approval of the pre-field engineering report: The TABS Agency submits a report which outlines the scope of field work. The report must contain details of what systems will be tested, procedures to be used, sample report forms for reporting test results and a quality control checklist of work items that must be completed before TABS field work commences.

c. Season I field work: Incremental payments are issued as the TABS field work progresses. The TABS Agency mobilizes to the project site and executes the field work as outlined in the pre-field engineering report. The HVAC water and air systems are balanced and operational data must be collected for one seasonal condition (either summer or winter depending on project timing).

d. Approval of Season I report: On completion of the Season I field work, the data is compiled into a report and submitted to the Government. The report is reviewed, and approved, after ensuring compliance with the pre-field engineering report scope of work.

e. Completion of Season I field QA check: Contract QC and Government representatives meet the TABS Agency at the jobsite to retest portions of the systems reported in the Season I report. The purpose of these tests are to validate the accuracy and completeness of the previously submitted Season I report.

f. Approval of Season II report: The TABS Agency completes all Season II field work, which is normally comprised mainly of taking heat transfer temperature readings, in the season opposite of that under which Season I performance data was compiled. Compile this data into a report and submit to the Government. On completion of submittal

review to ensure compliance with the pre-field engineering report scope, progress payment is issued. Progress payment is less than that issued for the Season I report since most of the water and air balancing work effort is completed under Season I.

1.4 CONTRACT MODIFICATIONS

In conjunction with the Contract Clause DFARS 252.236-7000 Modification Proposals-Price Breakdown, and where actual ownership and operating costs of construction equipment cannot be determined from Contractor accounting records, base equipment use rates upon the applicable provisions of the EP 1110-1-8.

1.5 CONTRACTOR'S INVOICE AND CONTRACT PERFORMANCE STATEMENT

1.5.1 Content of Invoice

Requests for payment will be processed in accordance with the Contract Clause FAR 52.232-27 Prompt Payment for Construction Contracts and FAR 52.232-5 Payments Under Fixed-Price Construction Contracts. Invoices not completed in accordance with contract requirements will be returned to the Contractor for correction of the deficiencies. Include the documents listed below in the requests for payment.

a. The Contractor's invoice, on NAVFAC Form 7300/30 furnished by the Government, showing in summary form, the basis for arriving at the amount of the invoice. Form 7300/30 must include certification by Quality Control (QC) Manager as required by the Contract.

b. The Earned Value Report from the cost-loaded NAS.

c. Contractor's Monthly Estimate for Voucher and Contractors Certification (NAVFAC Form 4330) with Subcontractor and supplier payment certification. Other documents, including but not limited to, that need to be received prior to processing payment include the following submittals as required. These items are still required monthly even when a pay voucher is not submitted.

d. Monthly Work-hour report.

e. Updated Construction Progress Schedule and tabular reports required by the contract.

f. Contractor Safety Self Evaluation Checklist.

g. Updated submittal register.

h. Solid Waste Disposal Report.

i. Certified payrolls.

j. Updated testing logs.

k. Other supporting documents as requested.

1.5.2 Submission of Invoices

If DFARS Clause 252.232-7006 Wide Area WorkFlow Payment Instructions is included in the Contract, provide the documents listed in above paragraph

CONTENT OF INVOICE in their entirety as attachments in Wide Area Work Flow (WAWF) for each invoice submitted. The maximum size of each WAWF attachment is two megabytes, but there are no limits on the number of attachments. If a document cannot be attached in WAWF due to system or size restriction, provide it as instructed by the Contracting Officer.

Monthly invoices and supporting forms for work performed through the anniversary award date of the Contract must be submitted to the Contracting Officer within 5 calendar days of the date of invoice. For example, if Contract award date is the 7th of the month, the date of each monthly invoice must be the 7th and the invoice must be submitted by the 12th of the month.

1.5.3 Final Invoice

a. A final invoice must be accompanied by the certification required by DFARS 252.247.7023 Transportation of Supplies by Sea, and the Contractor's Final Release. If the Contractor is incorporated, the Final Release must contain the corporate seal. An officer of the corporation must sign and the corporate secretary must certify the Final Release.

b. For final invoices being submitted via WAWF, the original Contractor's Final Release Form and required certification of Transportation of Supplies by Sea must be provided directly to the respective Contracting Officer prior to submission of the final invoice. Once receipt of the original Final Release Form and required certification of Transportation of Supplies by Sea has been confirmed by the Contracting Officer, the Contractor must then submit final invoice and attach a copy of the Final Release Form and required certification of Transportation of Supplies by Sea in WAWF.

c. Final invoices not accompanied by the Contractor's Final Release and required certification of Transportation of Supplies by Sea will be considered incomplete and will be returned to the Contractor.

1.6 PAYMENTS TO THE CONTRACTOR

Payments will be made on submission of itemized requests by the Contractor which comply with the requirements of this section, and will be subject to reduction for overpayments or increase for underpayments made on previous payments to the Contractor.

1.6.1 Obligation of Government Payments

The obligation of the Government to make payments required under the provisions of this Contract will, at the discretion of the Contracting Officer, be subject to reductions and suspensions permitted under the FAR and agency regulations including the following in accordance with FAR 32.103 Progress Payments Under Construction Contracts:

a. Reasonable deductions due to defects in material or workmanship;

b. Claims which the Government may have against the Contractor under or in connection with this Contract;

c. Unless otherwise adjusted, repayment to the Government upon demand for overpayments made to the Contractor; and

d. Failure to maintain accurate "as-built" or record drawings in accordance with FAR 52.236.21 and the contract.

e. Failure to submit accurate monthly schedule updates in accordance with the contract.

1.6.2 Payment for Onsite and Offsite Materials

Progress payments may be made to the Contractor for materials delivered on the site, for materials stored off construction sites, or materials that are in transit to the construction sites under the following conditions:

a. FAR 52.232-5(b) Payments Under Fixed Price Construction Contracts.

b. Materials delivered on the site, but not installed, and off-site materials to be considered for progress payment must be major high cost, long lead, special order, or specialty items, not susceptible to deterioration or physical damage in storage or in transit to the construction site. Examples of materials acceptable for payment consideration include, but are not limited to, structural steel, non-magnetic steel, non-magnetic aggregate, equipment, machinery, large pipe and fittings, precast/prestressed concrete products, plastic lumber (e.g., fender piles/curbs), and high-voltage electrical cable. Materials not acceptable for payment include consumable materials such as nails, fasteners, conduits, gypsum board, glass, insulation, and wall coverings.

c. Provide the Contracting Officer with documentation (e.g., Purchase Orders or Material Contracts) to justify payment for materials in advance of installation. When appropriate, include the Defense Priorities and Allocations System (DFAS) ratings (e.g., DX or DO) on purchase orders or material contracts to ensure timely delivery.

d. Materials to be considered for progress payment prior to installation must be specifically and separately identified in the Contractor's estimates of work submitted for the Contracting Officer's approval in accordance with Earned Value Report requirement of this Contract. Requests for progress payment consideration for such items must be supported by documents establishing their value (e.g., paid invoices) and that the title requirements of the clause at FAR 52.232-5 Payments Under Fixed-Price Construction Contracts have been met.

e. Ensure materials are adequately insured and protected from theft and exposure. Provide insurance documentation (e.g., Builder's Risk Insurance) which covers the overall value of the materials to be paid in advance of installation.

f. Provide a written consent from the surety company with each payment request for offsite materials.

g. Materials to be considered for progress payments prior to installation must be stored either in Hawaii, Guam, Puerto Rico, or the Continental United States. Other locations are subject to written approval by the Contracting Officer.

h. Materials in transit to the job site or storage site are not acceptable for payment.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

SECTION 01 30 00

ADMINISTRATIVE REQUIREMENTS
11/20, CHG 5: 02/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

View Location Map

Progress and Completion Pictures

1.3 VIEW LOCATION MAP

Submit, prior to or with the first digital photograph submittals, a sketch or drawing indicating the required photographic locations. Update as required if the locations are moved.

1.4 PROGRESS AND COMPLETION PICTURES

Photographically document site conditions prior to start of construction operations. Provide monthly, and within one month of the completion of work, digital photographs, 1600x1200x24 bit true color minimum resolution in JPEG file format showing the sequence and progress of work. Take a minimum of 20 digital photographs each week throughout the entire project from a minimum of ten different viewpoints selected by the Contractor unless otherwise directed by the Contracting Officer. Submit with the monthly invoice two sets of digital photographs, each set on a separate compact disc (CD) or data versatile disc (DVD), cumulative of all photos to date. Indicate photographs demonstrating environmental procedures. Provide photographs for each month in a separate monthly directory and name each file to indicate its location on the view location sketch. Also provide the view location sketch on the CD or DVD as a digital file. Include a date designator in file names. Photographs provided are for unrestricted use by the Government.

1.5 MINIMUM INSURANCE REQUIREMENTS

Provide the minimum insurance coverage required by FAR 28.307-2 Liability,

during the entire period of performance under this contract. Provide other insurance coverage as required by North Carolina law.

1.6 SUPERVISION

1.6.1 Superintendent Qualifications

Provide project superintendent with a minimum of 10 years experience in construction with at least 5 of those years as a superintendent on projects similar in size and complexity. The individual must be familiar with the requirements of EM 385-1-1 and have experience in the areas of hazard identification and safety compliance. The individual must be capable of interpreting a critical path schedule and construction drawings. The qualification requirements for the alternate superintendent are the same as for the project superintendent. The Contracting Officer may request proof of the superintendent's qualifications at any point in the project if the performance of the superintendent is in question.

1.6.2 Minimum Communication Requirements

Have at least one qualified superintendent, or competent alternate, capable of reading, writing, and conversing fluently in the English language, on the job-site at all times during the performance of Contract work. In addition, if a Quality Control (QC) representative is required on the Contract, then that individual must also have fluent English communication skills.

1.6.3 Duties

The project superintendent is primarily responsible for managing subcontractors and coordinating day-to-day production and schedule adherence on the project. The superintendent is required to attend Red Zone meetings, partnering meetings, and quality control meetings. The superintendent or qualified alternative must be on-site at all times during the performance of this contract until the work is completed and accepted.

1.6.4 Non-Compliance Actions

The Project Superintendent is subject to removal by the Contracting Officer for non-compliance with requirements specified in the contract and for failure to manage the project to ensure timely completion. Furthermore, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders is acceptable as the subject of claim for extension of time or excess costs or damages by the Contractor.

1.7 PRECONSTRUCTION MEETING

Immediately after award, prior to commencing any work at the site, coordinate with the Contracting Officer a time and place to meet for the Preconstruction Meeting. The meeting must take place within 35 calendar days after award of the contract, but prior to commencement of any work at the site. The purpose of this meeting is to discuss and develop a mutual understanding of the administrative requirements of the Contract including but not limited to: daily reporting, invoicing, value engineering, safety, base-access, outage requests, hot work permits, schedule requirements, quality control, schedule of prices or earned value report, shop drawings,

submittals, cybersecurity, prosecution of the work, government acceptance, final inspections and contract close-out. Contractor must present and discuss their basic approach to scheduling the construction work and any required phasing.

1.7.1 Attendees

Contractor attendees must include the Project Manager, Superintendent, Site Safety and Health Officer (SSHO), Quality Control Manager and major subcontractors.

1.8 FACILITY TURNOVER PLANNING MEETINGS (Red Zone Meetings)

Meet with the Government to identify strategies to ensure the project is carried to expeditious closure and turnover to the Client. Start planning the turnover process at the Pre-Construction Conference meeting with a discussion of the Red Zone process and convene at regularly scheduled Red Zone Meetings beginning at approximately 75 percent of project completion. Include the following in the facility Turnover effort:

1.8.1 Red Zone Checklist

a. Contracting Officer's Technical Representative (COTR) will provide the Contractor a copy of the Red Zone Checklist template.

b. Prior to 75 percent completion, modify the Red Zone Checklist template by adding or deleting critical activities applicable to the project and assign planned completion dates for each activity. Submit the modified Red Zone Checklist to the Contracting Officer. The Contracting Officer may request additional activities be added to the Red Zone Checklist at any time as necessary.

1.8.2 Meetings

a. Conduct regular Red Zone Meetings beginning at approximately 75 percent project completion, or three to six months prior to Beneficial Occupancy Date (BOD), whichever comes first.

b. The Contracting Officer will establish the frequency of the meetings, which is expected to increase as the project completion draws nearer. At the beginning, Red Zone meetings may be every two weeks then increase to weekly towards the final month of the project.

c. Using the Red Zone Checklist as a Plan of Action and Milestones (POAM) and basis for discussion, review upcoming critical activities and strategies to ensure work is completed on time.

d. During the Red Zone Meetings discuss with the COTR any upcoming activities that require Government involvement.

e. Maintain the Red Zone Checklist by documenting the actual completion dates as work is completed and update the Red Zone Checklist with revised planned completion dates as necessary to match progress. Distribute copies of the current Red Zone Checklist to attendees at each Red Zone Meeting.

1.9 PARTNERING

Host the partnering session within 45 calendar days of contract award. To

most effectively accomplish this Contract, the Contractor and Government must form a cohesive partnership with the common goal of drawing on the strength of each organization in an effort to achieve a successful project without safety mishaps, conforming to the Contract, within budget and on schedule. The partnering team must consist of personnel from both the Government and Contractor including project level and corporate level leadership positions. Key Personnel from the supported command, end user, NAVFAC, PWD, FEAD/ROICC, Contractor, key subcontractors and the Designer of Record (DOR) (regardless of whether the contract is a design-build or a design-bid-build) are required to participate in the Partnering process.

1.9.1 Facilitated (Formal) Partnering

a. Within 35 calendar days after award and prior to the start of work, host a Formal Partnering session with key personnel from the project team including both Contractor and Government personnel. All costs associated with the Partnering session including the third-party independent Facilitator Consultant, meeting room and other incidental items are the responsibility of the Contractor.

b. Before the Facilitated (Formal) Partnering session, coordinate with the Facilitator all requirements for incidental items (such as audio-visual equipment, easels, flipchart paper, colored markers, note pads, pens/pencils, colored flash cards) and have these items available at the Partnering session. Provide copies of any documents required for distribution to all attendees. Participants will bear their own costs for meals, lodging and transportation associated with Partnering.

c. The Initial Partnering Session must be a duration of one day and be held at a location off base as agreed to by the Contracting Officer. Partnering session may take place concurrently with the Pre-Construction Meeting.

d. Facilitator must be experienced in conducting corporate Partnering sessions and must be a third-party independent facilitating consultant - not an employee of the Contractor. The Facilitator is responsible for leading all aspects of the Partnering session necessary to achieve the Partnering goal.

e. An outcome of the Partnering session must be an escalation matrix agreed upon by both the Government and Contractor, which identifies key Government and Contractor decision makers by name and anticipated decision durations.

f. Host follow-on Partnering Sessions at three- to six-month intervals or more frequently if needed and lasting generally a half day or less. Attendees need only be those required to resolve current issues. The same Facilitator used in the Initial Partnering session must lead the follow-on sessions unless an alternative is permitted by the Contractor Officer. All costs associated with follow-on Partnering sessions are the responsibility of the Contractor.

1.10 MOBILIZATION

Mobilize to the jobsite within 60 calendar days after contract award . Mobilize is defined as having equipment AND having a physical presence of at least one person from the contractor's team on the jobsite.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 30 02.00 22

DESIGN, PROCUREMENT, AND INSTALLATION OF AUDIOVISUAL EQUIPMENT
05/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AUDIOVISUAL AND INTEGRATED EXPERIENCE ASSOCIATION (AVIXA)

D401.01:201X	Standard Guide for Audiovisual Systems Design and Coordination Processes
F501.01:2015	Cable Labeling for Audiovisual Systems
202.01:2016	Display Image Size for 2D Content in Audiovisual Systems
A102.01:2017	Audio Coverage Uniformity in Listener Areas
F502.02:201X	Rack Design for AV Systems
V201.01:2022	Image System Contrast Ratio
S601.01:2021	Energy Management for Audiovisual Systems
10:2013	Audiovisual Systems Performance Verification

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Preliminary (Pre-Final) AV Package; G; G, DC44 NAVFAC MIDLANT Electrical Engineering

Final AV Package; G; G, DC44 NAVFAC MIDLANT Electrical Engineering

Best Value Determination; G G, DC44 NAVFAC MIDLANT Electrical Engineering

SD-07 Certificates

Contractor's AV Designer's Qualifications; G; G, DC44 NAVFAC MIDLANT Electrical Engineering

1.3 GENERAL REQUIREMENTS

This Specification Section outlines the minimum requirements and installation methods for the integrated audiovisual system, hardware, software, cables, accessories, and acceptance testing. System refers to the complete and functional assemblage of equipment required to achieve the specified functionality, performance, and design intent. Audiovisual (AV) system shall include, but is not limited to;

a. Audio equipment: Speakers, mixers, amplifiers, microphones, signal processing equipment, and source equipment.

b. Video equipment: Displays, signal routing and processing equipment, and source equipment.

c. Video projection screens

d. Remote control equipment including touch panels, control processors, software, and programming.

e. Equipment racks and associated hardware such as rack screws, power distribution products, cooling products, and blank panels.

f. Cables, snakes, connectors, plates, and wiring.

g. Other similar parts that may be required for normal operation such as projector bulbs and lenses.

h. Mounts, rigging, and required hardware such as all-thread, unistrut, chains, and cables.

i. System commissioning

j. Training

k. Documentation

l. Communication and coordination with all team members and trades to fulfill the requirements of this Specification.

AV System shall be fully integrated with the building systems and finishes. AV system may also include specialty equipment for which the customer activity shall be responsible for specifying.

The design and documentation of the AV system shall be funded as the AV Services Option. The purchase and installation of the AV Package shall be funded separately as the AV Option. The Government AV budget on the Bid Schedule/Price Proposal Form for the AV Mod is $2,175,534 and does NOT include the Contractor's Handling and Administration Rate (HAR). This Government AV estimate shall not be altered by Contractors during the bid process.

All AV items are subject to the Buy American Act/Trade Agreements Act.

1.4 AUDIOVISUAL DESIGN SERVICES OPTION

1.4.1 Qualifications and Affiliations

The AV Designer of Record, hereafter referred to as the Prime Contractor's AV Designer, shall be AVIXA Certified Technology Specialist - Design certified with at least five years of design experience utilizing D401.01:201X, F501.01:2015, 202.01:2016, A102.01:2017, F502.02:201X, V201.01:2022, S601.01:2021, and 10:2013 on designs similarly sized and complex as this project. Provide documentation of the Prime Contractor's AV Designer's Qualifications and past project performance for at least three projects. The Government reserves the right to approve/disapprove the Prime Contractor's AV Designer.

1.4.2 Concept AV package

A Concept AV package, prepared by the A/E's AV Designer, indicating the salient characteristics of all required AV items and CADD drawings, will be provided to the Prime Contractor. As a separately priced option, the Prime Contractor shall provide the services of a Certified Technology Specialist - Design (CTS-D), other than the A/E's AV Designer, to function as Prime Contractor's AV Designer, to prepare and provide the Final, Best Valued AV Package and procurement data based on the Concept AV package.

All fixed and movable furnishings selections shall be closely coordinated with the final construction documents and interior finishes. The Prime Contractor's AV Designer shall validate, through Needs Analysis, all AV requirements with the Activity, and make any necessary changes to the AV System Design. The AV package includes the design, selection, specification, color coordination, and procurement documentation of the required items necessary to meet the functional, operational, sustainability, and security needs of the facility. The AV package shall be fully integrated with the design, construction, and schedule of all building systems (HVAC, Plumbing, Fire Protection, Communuications, Electrical, Data, Architecture, etc. All outlets, switches, fire extinguishers, thermostats, etc. shall be fully accessible. All sprinkler heads, ADA, etc. clearances shall be accommodated.

The Prime Contractor's AV Designer shall attend walk-throughs, any and all required meetings, and coordinate system requirements to accomplish this task. The Contractor's AV Designer and equipment specialists shall be responsible for designing and providing specifications for procurement of the AV System, to include delivery and installation, for the facilities built or renovated under this contract as directed by the NAVFAC Electrical Engineering Branch (DC44). AV specifications shall be based on GSA Multiple Award Schedules, and other Federal contracts and complying with priorities found in FAR Part 8.404. The utilization of the current GSA MAS list is required for BVD Analysis Request for Pricing.

1.5 AUDIOVISUAL (AV) SUBMITTALS FOR THE AV DESIGN SERVICES OPTION

Develop design as described and in accordance with the Activity requirements. Include in the design all AV equipment required to produce an optimum functional facility, consistent with quality commercial design. This project also includes the preparation of specific detailed information for each selected item. Each submittal shall demonstrate thorough interaction with the Activity requirements and complete coordination with the facility design.

a. The Activity will supply the Contractor's AV Designer with a complete list of all existing AV Equipment, to include sizes, utility requirements, weight, etc., to be relocated to the new facility

b. For all projects, including fast track projects, the Prime Contractor shall be responsible for sufficiently scheduling all AV and any revisions to submittals early enough to obtain the required government approvals, and meet all ordering and installation lead times to complete the project by the contract completion date.

These are minimum requirements and the Prime Contractor shall be prepared to provide any/all additional meetings and submittals that may be necessary to support the AV Design effort/ and coordination.

1.5.1 Audiovisual Requirements (AV Design Orientation) Meeting

This meeting shall occur at the Pre-Construction meeting prior to the AV "Over the Shoulder" Review and the development of the AV package. The NAVFAC Electrical Engineer will provide the Contractor's AV Designer a sample format of the AV submittal, review the Best Value Determination (BVD) process. Minutes of this meeting shall be submitted to the NAVFAC Project Manager within 7 business days.

1.5.2 AV "Over the Shoulder" Review

Prior to the AV Concept Presentation and Best Value Determination (BVD) Analysis, the Contractor's AV Designer shall meet with the NAVFAC Electrical Engineer for an "over-the-shoulder" review to present preliminary AV options. These can be presented in a "loose" format for preliminary approval prior to the Activity presentation. The "over-the-shoulder" review meeting shall be held via conference call.

1.5.3 AV Concept Presentation

The Prime Contractor's AV Designer shall present the NAVFAC approved Preliminary (Pre-final) AV package to the Activity, via conference call, for approval. This presentation shall include preliminary drawings and basis of design equipment.

1.5.4 Best Value Determination(BVD) Analysis "Over the Shoulder Review"

Prior to issuing the Best Value Determination (BVD) Analysis, the Prime Contractor's AV Designer shall meet with the NAVFAC Electrical Engineer for an "over-the-shoulder" review of the solicitation package. The "over-the-shoulder" review meeting shall be held via conference call. The Contractor's AV Designer must provide a copy of the BVD Analysis Request for Pricing cover letter to the Contractor for review and comment prior to the BVD Analysis "Over the Shoulder Review" meeting.

BVD Analysis Solicitation shall include the following;

a. Copy of the BVD Analysis Request for Pricing cover letter.

b. BVD Analysis Request for Pricing Spreadsheet/Questionnaire with "basis of design" item product numbers, photos & descriptions.

c. Technical Specification to establish minimum acceptable AV requirements.

d. Project Specific Room/Furniture/Rack Typicals.

e. Floor Plans with Legends coded to the BVD Analysis RFP (PDF format).

1.5.5 BVD Submittal and "Over the Shoulder Review"

The Prime Contractor's AV Designer shall submit one (1) copy of the Preliminary BVA BVD package to the NAVFAC Electrical Engineer and one (1) copy to Base Property for Marine Corps projects. An electronic copy shall be sent to the NAVFAC Contracting Officer. The "over-the-shoulder" review meeting shall be held via conference call to review the results of the solicitation and determine a best value recommendation. The BVD Submittal shall be in a 3-ring binder and shall include the following items for review and approval:

a. Cover Title Page (project name, project #, location, submittal date, submittal title)

b. Table of Contents.

c. Point of Contact List.

d. Narrative of AV Designer Objectives.

e. BVD Analysis Request for Pricing Spreadsheet/Questionnaire completed by all bidders and completed Questionnaire.

f. Copy of all information sent to bidders and documentation that all required sources were contacted.

g. Back-up Information submitted by each bidder (cut sheets/highlighted pricing sheets/technical specifications, pricing, dealer and manufacturer qualification for each product showing that products meets all requirements).

h. BVD Analysis Pricing Evaluation Spreadsheet comparing bidder quotes/responses.

i. Contractor's AV Designer recommendation for the Best Value vendor and justifications.

1.5.6 Preliminary AV Submittal

The Preliminary AV submittal shall be presented to the Activity and NAVFAC in digital format at a meeting to occur via conference call. Three (3) submittals will be required; (1) for the NAVFAC Project Manager, (1) for the FEAD/ROICC and Base Property, and (1) for the Activity.

Submit the following in a 3-ring binder for review and approval:

a. Cover Title Page (project name and number, submittal date and title).

b. Table of Contents.

c. Point of Contact List (includes contact info for recommended Best Value vendors and subcontractors).

d. Preliminary AV list (Cost Summary) to include shipping, freight, handling, professional installation, project management, HAR and applicable sales tax.

f. AV floor plans coded to the Bill of Materials.

g. Technical Specifications used in bid request for the AV System.

j. Copy of Quote(s)/Bill of Materials (BOM) on letterhead from the vendor(s) determined to be the best value. Code BOM line items to AV Cost Summary Item Codes.

1.5.7 Final AV Submittal

The Final AV submittal shall be due 10 months prior to BOD following the receipt of review comments on the preliminary AV submittal and shall shall be in the format described below.

These are minimum requirements and the Contractor shall be prepared to provide any additional meetings and submittals that may be necessary to support the AV Design effort and coordination.

The Final AV Submittal shall be submitted digitally and in a 3-ring binder for review and approval. The number of final submittals required shall be;

Five (5) total; One each for the NAVFAC Project Manager and the Activity. Three to be shared between the FEAD/ROICC and IDD/Base Property.

The Final AV Submittal shall include the following;

a. Cover Title Page with project name, project #, submittal date, submittal title identified on binder cover and spine.

b. Table of Contents.

c. Point of Contact List which includes contact info for recommended Best Value vendors and subcontractors.

d. Final AV list (Cost Summary) to include shipping, handling, freight, professional installation, project management, HAR and any applicable sales tax.

g. Copy of Final Quote(s)/Bill of Materials (BOM) on letterhead from the vendor(s) determined to be the Best Value. Code BOM line items to AV Cost Summary Item Codes.

h. Best Value Determination Guidelines sheets; completed and signed by the Contactor's AV Designer.

i. Final AV Placement Plans coded to the AV list, Procurement Data Sheets and specifications.

j. CD copy of the final AV binder.

1.5.8 Punch List:

See section 2.1.13 Punch List.

1.5.9 AV Construction Submittals

Submit any revisions or deviations caused by discontinued items or NAVFAC required changes to the Contracting Officer for approval by the NAVFAC Electrical Engineer. All submittal due dates for the AV shall be reflected in the Contractor's construction schedule. Changes to the AV schedule shall be submitted to the Contracting Officer or their Representative for approval. The Final AV package shall be submitted no later than 9 months prior to the contract completion date.

1.6 BEST VALUE DETERMINATION

A Best Value Determination (BVD) is required by FAR 8.404 when placing orders against Federal Supply Schedules. Best Value is defined in FAR 2.101 as ensuring that the order to be placed under a Federal Supply Schedule results in the lowest overall cost alternative (considering price, special features, administrative costs and client's needs) to meet the government's needs.

a. A (BVD) shall be performed on a minimum of three manufacturers for orders exceeding a total procurement of $25,000 from an individual manufacturer. Multiple BVDs may be required in order to complete the final AV package.

b. The required quantity of BVD's to be performed will be determined by the NAVFAC Electrical Engineer during the design phase and is dependent on the specific project requirements.

c. Documentation shall be provided to the Government with the final AV package. Specific Documentation is indicated in the Preliminary BVD Submittal and "Over the Shoulder Review." The BVD Statement shall be

completed and signed by the Contractor's AV Designer.

The Prime Contractor's AV Designer is responsible for the following written BVD justifications:

1.6.1 Total procurement of $25,000 or less

For any procurement in the AV package with a value of $25,000 or less, the AV Designer may utilize any vendor. If the GSA MAS holders cannot supply the item, then any other vendor may be utilized.

1.6.2 Total procurement greater than $25,000 and less than $250,000

For any procurement in the AV package with a value greater than $25,000 and $250,000 or less, the Prime Contractor's AV Designer shall always review pricing from at least three vendors. In addition to the review of published list prices, the Contractor's AV Designer must confirm the pricing with the vendor. Manufacturer's quotes are NOT required. The BVD form must be completed and submitted for all AV procurements greater than $25,000 and $250,000 or less.

1.6.3 Total procurement greater than $250,000

For any procurement in the AV package with a value greater than $250,000, the Prime Contractor's AV Designer shall always review pricing from at least six vendors. The BVD form must be completed and submitted for all AV procurements greater than $250,000 and manufacturer's quotes and a summary of all proposals must be attached.

1.6.4 Evaluation Factors

The Best Value Determination shall address issues such as:

a. Special features of the supply or service required for effective program performance; Perceived appropriateness of offered product compared to Request for Pricing requirements.

b. Dealer/installation team must be located within 150 driving miles of location of project to provide proximity for support and maintenance to the Base after delivery of the product.

c. Price (including freight)

d. Probable life of the item offered as compared with that of a comparable item; Perceived product durability and quality

e. Past performance.

f. Warranty considerations.

g. Maintenance availability; Dealer/manufacturer proximity for support.

h. Environmental and energy efficiency considerations (sustainability).

i. Comfort/suitability of the system and/or component.

j. Compatibility with existing furniture and/or products.

k. Product performance.

l. Delivery terms.

m. Other (Describe).

n. Emphasis shall be to create a fully integrated design solution by providing quality products to meet the functional needs of the customer. Customer preferences shall be considered. The focus shall be on the best overall value. Use the NAVFAC Best Value Determination forms provided by the NAVFAC Electrical Engineer.

PART 2 AV TURNKEY EFFORT

2.1 AV OPTION

AV Option: As an option, provide procurement and installation coordination of the complete and usable Final AV package. The AV Package must include shipping, freight, handling, installation, applicable state sales tax, and the Prime Contractor's AV Handling and Administration Rate (HAR) percentage as applied to the final AV total cost (excluding taxes).

2.1.1 Authorization

The Government will provide separate funding for procurement and installation coordination of the AV package. Construction funds will not be used. Upon receipt of required funding, the Prime Contractor shall be authorized by the Contracting Officer, as an option to the construction contract, to procure and install all Final AV utilizing GSA Multiple Award Schedules, and other Federal contracts and complying with priorities found in FAR Part 8.404. The Prime Contractor will be expected to procure and coordinate the installation of the approved Final AV package exactly as specified. The amount of the modification will be the actual cost of these items from the Federal Government price schedules (GSA), including any freight and installation charges from the vendor as well as the Prime Contractor's HAR and any applicable state sales tax. The HAR includes all of the Prime Contractor's effort related to storage, coordination, handling, administration of subcontractors, and all other associated costs and profit for the procurement of AV Equipment.

The Government will indicate the AV estimate based on the Concept Design in the contract solicitation Price Proposal Form (Bid Schedule). This Government estimate shall not be altered by Prime Contractors during the bid process.

Prime Contractors shall propose a Handling and Administration Rate (HAR) only. The Prime Contractor will propose the AV HAR in the contract

solicitation. The Prime Contractor's proposed HAR may not exceed 5 percent of the total AV costs, as noted on the bid schedule. The HAR shall not include costs associated with the AV Design Services required in the AV Design Services Option.

AV items are subject to the Buy American Act/Trade Agreements Act.

2.1.2 Procurement and Installation

The Prime Contractor shall coordinate the building completion date with the installation dealer(s) specified in the AV Package. The Prime Contractor shall anticipate possible manufacturer price increases if order placement is delayed. It is recommended to order the AV product once the option is awarded and funds are received to avoid incurring additional costs. Delayed production and delivery dates can be noted at the time of order placement to coincide with the contract completion date. Any costs incurred due to manufacturer price increases will be the burden of the Prime Contractor.

2.1.3 Deposits

The Prime Contractor should anticipate providing a deposit of between 30 percent and 50 percent of the AV costs when placing the orders with the manufacturer's dealerships.

2.1.4 Davis Bacon Wages

Davis Bacon wages do not apply to the AV installer from the Government supply sources. The workforce for the AV installation and delivery shall be separate and distinct from the labor workforce performing under the construction contract.

2.1.5 Sales Tax

The Prime Contractor shall take maximum advantage of all exemptions from State and Local taxation authorities whether available to it directly or available to the Prime Contractor based on an exemption afforded the Government. The responsibility for paying applicable taxes rests with the Prime Contractor. Any state and local taxes applicable to the AV shall be included within the AV Dealer's quote.

2.1.6 Bonds

AV items are not considered construction and the prime contractor shall not be required to secure any additional bond for the award of the AV line item unless otherwise indicated in the contract. If any additional bond is required for the AV line item it is to be included in the prime contractor's AV HAR.

2.1.7 Unique Item Identification (IUID) and Valuation

Unique item identification and valuation is a system of marking and valuing items delivered to DoD that enhances logistics, contracting, and financial business transactions. The IUID policy is mandatory for all DoD contracts that require the delivery of items. An item is a single article or a single unit formed by a grouping of subassemblies, components, or constituent parts. The Prime Contractor shall provide DoD Unique item identification, valuation and delivery of data for all required AV items

for which the government's unit acquisition cost is $5,000 or more.

PART 3 EXECUTION

3.1 Installation

The AV package includes the installation of all AV Equipment as specified in the AV package. The installation dealer(s) specified in the AV package shall receive, store as required, transport to the project site, off load, inside deliver, unpack, assemble, place/install, clean, and dispose of all the trash for all AV Equipment. It is the Prime Contractor's responsibility to coordinate the building completion, occupancy, and AV System installation dates with the installation dealer(s) specified in the AV package. Any costs associated with or delaying AV Equipment shipments is the responsibility of the Prime Contractor.

The Prime Contractor shall provide and coordinate all Building Systems (HVAC, Plumbing, Fire Protection, Communications, Electrical, Data, Architectural, etc. with the AV plans and AV installation. All outlets, switches, thermostats, etc. shall be fully accessible. All sprinkler heads, fire extinguishers, ADA, etc., clearances shall be accommodated.

3.2 Installation Warranty

All AV Equipment shall be installed in accordance with the manufacturer's instructions and warranty requirements. All Racks shall be level and aligned. All doors, drawers and accessories shall be level and aligned to open, close and otherwise operate smoothly and securely.

All AV Equipment shall be installed by the furniture manufacturer's dealer of record and not the Prime Contractor. The Government reserves the right to approve/disapprove the Prime Contractor's AV installers. In addition, installation dealer(s) must be located within a 150 mile radius of the project site unless approved by the Government Electrical Engineer. The Prime Contractor shall repair, to the Government's satisfaction, any/all damage to any facility finish that is a result of the AV installation and correct all punch list items.

3.3 Ordering Documentation

After award of the AV package, three CD copies and one binder copy for Marine Corps projects of all ordering documentation, including Factory Order number (FO) and warranty information for all products, shall be provided to the Contracting Officer at the final AV walk-thru.

3.4 Post Award Changes

After award of the AV turnkey modification, any request to change the AV items must be submitted to the Contracting Officer. The AV turnkey modification will have been accepted, priced, and negotiated as detailed in the final package. Those items will have been agreed to considering color, specific type and quality of material, price, sustainability, life cycle, and dealership service. The Government will require the Prime Contractor to provide exactly those items. Should changes become necessary, careful consideration shall be essential to assure that equivalent quality, price and other aspects of the item are maintained. Otherwise, price adjustments must be negotiated. Coordination with building services and other AV items is required for all proposed and approved substitutions. The Prime Contractor shall obtain approval from

the Contracting Officer and NAVFAC Electrical Engineer for any changes to the AV Package.

Post award AV manufacturer's price increases, beyond the pricing guarantee date, are the responsibility of the Prime Contractor and shall not be transferred to the Government.

3.5 Punch List

The Contractor and their AV Designer shall attend at least two punch list site visits with the installation dealer(s), NAVFAC Electrical Engineer and the Base Representative/Activity Contact. The first site visit shall identify all punch list items (at installation dealer's 98 percent completion) and the second (at 100 percent completion) will confirm that all punch list items have been resolved.

3.6 Best Value Determination

A best value determination has been performed on the final AV package. A best value determination is required by FAR 8.404 when placing orders against Federal Supply Schedules for the selection of furniture and furnishings. Best Value is defined in FAR 2.101 as ensuring that the order to be placed under a Federal Supply Schedule results in the lowest overall cost alternative (considering price, special features, administrative costs and client's needs) to meet the government's needs.

-- End of Section --

SECTION 01 31 23.13 20

ELECTRONIC CONSTRUCTION AND FACILITY SUPPORT CONTRACT MANAGEMENT SYSTEM (eCMS)
08/23, CHG 1: 02/24

PART 1 GENERAL

1.1 CONTRACT ADMINISTRATION

Utilize the Naval Facilities Engineering Systems Command's (NAVFAC's) Electronic Construction and Facility Support Contract Management System (eCMS) for the transfer, sharing, and management of electronic technical submittals and documents. The web-based eCMS is the designated means of transferring technical documents between the Contractor and the Government. Paper media or email submission, including originals or copies, of the documents are not permitted unless identified within the contract.

All government contracting specialist/officer, legal, and command communications will remain the same.

1.2 USER PRIVILEGES

The Contractor's key staff may be provided access to eCMS. Contact the COR for eCMS account access. Project roles and system roles will be established to control each user's menu, application, and software privileges, including the ability to create, edit, or delete objects. Additional project roles may be assigned for workflow. The COR makes the final decision on roles for the project. User's ability to view, edit documents may be lowered at the discretion of the COR.

Only one eCMS user account is required regardless of the number of user's projects. Notify the COR within seven calendar days if a contractor user is no longer associated with company or project so they can remove them from any open record and inactivate them from the project.

1.2.1 eCMS Subcontractor Users

If the contractor's user is a subcontractor, the subcontractor must be registered under the name of their company and email. For example it is common for contractors to contract Quality Control Managers. The QC Manager's account should be under their company's name and email reducing the number of eCMS accounts required.

1.2.2 Users with Multiple Roles

Users may have multiple roles associated with their account within eCMS. Roles are used in workflow. When a user is added to the project, they will be assigned the default role when the user was created. Contact the COR to change or add roles to the user for the project.

1.2.3 Loss of Privilege

Users may lose privilege to access eCMS at the discretion of the Contracting Officer. The eCMS is a collaborative system that allows flexibility of use and does not restrict all inappropriate user actions. User activities are logged into eCMS in visible and background data

collection. Users found to use eCMS in an inappropriate action may have their eCMS access revoked. Examples include, but not limited to, fraudulent representations, sharing user accounts with others, and changing approved records without the consent of the COR. Depending on the severity of the infraction, the users can lose eCMS access for a period of time, permanently for the project, or lose eCMS access for any project. The contractor may appeal the suspension in writing to the contracting officer within 14 calendar days of notice. The appeal must identify the infraction, supporting information, and steps to ensure the infraction will not happen in the future.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

List of Contractor's Personnel; G

For Division 1 government approved Pre-Construction submittals, combine into a single Pre-Construction Submittal Package. Annotated with SD Type of SD-01. Pre-Construction submittal package approval date will be used as a KPI.

1.4 SYSTEM REQUIREMENTS AND CONNECTIVITY

1.4.1 General

NAVFAC eCMS requires a web-browser (platform-neutral) and Internet connection. For best results, recommend using browser in InPrivate/Incognito mode; Internet speeds greater than 40mbps when uploading files, computers with high RAM and Solid State Drives, "White List" eCMS website, Zip or Split files for better uploading. Non-NAVFAC Users are not to use VPN when using eCMS per NAVFAC IT.

The use of eCMS is required by the Contractor and all associated costs and time necessary to utilize eCMS will be borne by the Contractor with no allowance for time extensions and at no additional cost to the government.

1.4.2 Contractor Personnel List

Within 20 calendar days of contract award, provide to the Contracting Officer a list of Contractor's personnel who will have the responsibility for the transfer, sharing and management of electronic submittals, RFIs, daily reports, and other files and will require access to the eCMS. Project personnel roles which must be filled as applicable in the eCMS, include, at a minimum, the Contractor's Project Manager (KTR-PM), Superintendent (KTSUPT), Quality Control (QC) Manager (KTR-QC), Principal (KTR-PRIN), and Site Safety and Health Officer (KTR-SSHO). Notify the COR immediately of any personnel changes to the project. The Contracting Officer reserves the right to perform a security check on all potential users.

Provide the following information:

Company Name

Name (First, Last)

Email Address

Project Role (CQM, SSHO, Superintendent, CM, PM, Principal)

Existing or New eCMS User

1.5 SECURITY CLASSIFICATION

In accordance with Department of Navy guidance, all military construction contract data are unclassified, unless specified otherwise by a properly designated Original Classification Authority (OCA) and in accordance with an established Security Classification Guide (SCG). Refer to the project's OCA when questions arise about the proper classification of information.

In conformance with the Freedom of Information Act (FOIA), DoD INSTRUCTION 5200.48 CONTROLLED UNCLASSIFIED INFORMATION (CUI), and DoD requirements, any unclassified project documentation uploaded into the eCMS must be designated either "U - UNCLASSIFIED" (U) or "CUI - CONTROLLED UNCLASSIFIED INFORMATION" (CUI).NAVFAC eCMS must only be used for the transaction of unclassified information associated with construction projects. Controlled Unclassified Identification (CUI) documents may be loaded into eCMS with the appropriate markings.

1.5.1 Markings on CUI Documents

Contractor's proprietary information, or documents determined by the originator in accordance with CUI guidance, should be marked CUI. Proprietary information not marked CUI can be released under the Freedom of Information Act (FOIA). Apply the appropriate markings before any document is uploaded into eCMS. Markings are not required on Unclassified U documents.

1.6 eCMS UTILIZATION

Establish, maintain, and update data and documentation in the eCMS throughout the duration of the contract. Utilize eCMS to transfer all submittals, RFIs, daily reports, and other files required by contract to be forwarded to the government.

Full eCMS use is required. All Submittals/Information to use eCMS Modules including, but not limited to, RFIs, Daily Reports, Meeting Minutes, Communications, Issues, Punch Lists, Checklists, and Flysheets, unless otherwise directed by the COR or Contracting Officer.

1.6.1 Restricted Information

Personally Identifiable Information (PII) transmittal such as credit card, driver's license, passport, social security, and payroll number are not permitted in eCMS. Name, address, and email are permitted. Pre-negotiation information such as cost estimates that require formal negotiations are not allowed. For example, proposed changes over the SAP level of $250k require formal negotiations. Cost estimates for LEAN, ULTRA LEAN, and Design Changes under the SAP level are at the discretion of the COR's or Contract Specialist/Officer's direction. The eCMS must only be used for the transaction of unclassified information associated

with construction projects. Controlled Unclassified Identification (CUI) documents may be loaded into eCMS with the appropriate markings. Uploading of files directly into the Documents folder is not allowed. All documents must be uploaded using an eCMS module.

1.6.2 Naming Convention for Files

Titles of files uploaded are to be descriptive of the purpose and content of the file. For example RFI_ROOF_Leak.doc or for submittals, SUB_LIGHT_FIXTURE.pdf. Titles of file to be uploaded must only contain uppercase letters, lowercase letters, numbers, hyphens (-), underscores (_) and periods (.). Use of any other characters is not allowed and may create an error. When practicable, adding the record number to the title is desired. For example RFI_XYZ12345_ROOF_Leak.doc. Uploading files with the same title will create a new revision in eCMS. Original revision is Rev 0, the first revision is Rev 1. Uploaded files are to use the default file location regardless of the module used unless directed by the COR.

Table 1 also identifies which eCMS application is to be used in the transmittal of data (these are subject to change based on the latest software configuration).

Table 1 - Project Documentation Types

SUBJECT/NAME	REMARKS	eCMS APPLICATION
As-Built Drawings	Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager	Submittals
Building Information Modeling (BIM)	Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager	Submittals
Construction Permits	Refer to rules of the issuing activity, state or jurisdiction	Submittals
Construction Schedules (Activities and Milestones)		Submittals
Construction Schedules		Submittals
Construction Schedules (3-Week Look ahead)	Import the schedule file into the scheduling application, and select "Approve" to establish a new schedule baseline	Meeting Minutes

SUBJECT/NAME	REMARKS	eCMS APPLICATION
DD 1354 Transfer of Real Property	When applicable, required for final billing.	Submittals
Daily Production Reports	Provide weather conditions, crew size, man-hours, equipment, and materials information	Daily Report
Daily Quality Control (QC) Reports	Provide QC Phase, Definable Features of Work Identify visitors	Daily Report
Designs and Specifications	Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager	Submittals
Environmental Notice of Violation (NOV), Corrective Action Plan	Refer to rules of the issuing activity, state or jurisdiction	Submittals
Environmental Protection Plan (EPP)		Submittals
Invoice (Supporting Documentation)	Applies to supporting documentation only. Invoices are submitted in Wide-Area Workflow (WAWF)	Submittals
Jobsite Documentation, Bulletin Board, Labor Laws, SDS	Redact any PII information when loaded into eCMS	Submittals
Meeting Minutes		Meeting Minutes
Modification Documents	Provide final modification documents for the project. Upload into Modifications RFPs folder	Communications
Operations & Maintenance Support Information (OMSI/eOMSI), Facility Data Worksheet	1. Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager 2. Design reviews will be performed in existing "Dr Checks"	Submittals

SUBJECT/NAME	REMARKS	eCMS APPLICATION
Photographs	Subject to base/installation restrictions	Submittals
QCM Initial Phase Checklists		Meeting Minutes or Checklists
QCM Preparatory Phase Checklists		Meeting Minutes or Checklists
Quality Control Plans		Submittals
QC Certifications		Submittals
QC Punch List		Punch Lists
Red-Zone Checklist		Punch List or Checklists
Rework Items List		Punch Lists
Request for Information (RFI) Post-Award		RFIs
Safety Plan		Submittals
Safety - Activity Hazard Analyses (AHA)		Submittals
Safety - Mishap Reports		Daily Report
Shop Drawings	Locations of sensitive areas must be labeled as either "Controlled Area" or "Restricted Area" and may be shown on unclassified documents with the approval from Site Security Manager	Submittals
Storm Water Pollution Prevention (Notice of Intent - Notice of Termination)	Refer to rules of the issuing activity, state or jurisdiction	Submittals
Submittals and Submittal Register		Submittals

SUBJECT/NAME	REMARKS	eCMS APPLICATION
Testing Plans, Logs, and Reports		Submittals
Training/Reference Materials		Submittals
Training Records (Personnel)	Redact any PII information if storing in eCMS	Submittals
Utility Outage/Tie-In Request/Approval		Submittals
Warranties/BOD Letter		Submittals
Quality Assurance Reports		Checklists (Government initiated)
Non-Compliance Notices		Non-Compliance Notices (Government initiated)
Other Government-prepared documents		GOV ONLY
Letters to government contracting, claims, REAs, and other contracting officer communications	eCMS is not the primary tool to use in contracting officer communications. eCMS can only store documents or letters after the submission to the contracting officer is made.	Communications
All Othere Documents	Refer to FOIA guidelines and contact the FOIA official to determine whether exemptions exist	As applicable

1.6.3 RFIs Module

Create contractor RFIs using eCMS RFIs module. The contractor must confirm the numbering convention with the COR if different than eCMS default.

If the government (GOV) Response has "No" Cost or Schedule Impact, this reply is given with the expressed understanding that it does not constitute a basis for any change in the amount or time of subject contract. Information provided in this response does not authorize work not currently included in the contract. If GOV Response is "Yes" or "Potentially" then this response may require a change to the contract. If the contractor disagrees with either the government's No Cost determination or No Schedule impact determination, or both, the contractor has 14 calendar days to notify the COR and Contracting Officer in writing.

1.6.4 Submittals Module

Create contractor submittals using eCMS Submittals module. The contractor must confirm the numbering convention with the COR if different than eCMS default.

1.6.5 Submittal Packages Module

Create submittal packages using the eCMS Submittal Packages module in lieu of or in addition to Related Objects. Submittal Packages track completion of the packaged submittals and is used in NAVFAC HQ's KPIs.

1.6.6 Communications Module

Create communications using the eCMS Communications module. The Communications module is used to create or document communications that are not a part of other eCMS modules. Use of Communications module will memorialize information into an eCMS record file. The following are Types of Communications:

Email

Memo to File

Face to Face

Telephone

Web Collaboration

Photos

Other Documents

Other

Unless directed by the COR, upload documents or files that do not have a corresponding eCMS module. Choose "Photos" Type for Photos and "Other Documents" for all other documents.

1.6.7 Issues Module

Create or respond to issues using the eCMS Issues module. Respond to CPARS issues using the Issues module.

1.6.8 Meeting Minutes Module

Create or respond to Meeting Minutes using the eCMS Meetings module.

Document required contractual meetings. Dates of meetings are used in NAVFAC KPIs. Minimum meetings in eCMS include the following:

Post Award Kickoff (PAK)

Pre-construction (Pre Con)

Initial and Preparatory Three Phases of Control

Quality Control (QC)

1.6.9 Potential Change Items Module

Not used.

1.6.10 Daily Report Module

Create Daily Reports using the eCMS Daily Report Module. The contractor must confirm the numbering convention with the COR if different than eCMS default.

1.6.11 Punchlists Testing Logs (Legacy)

Punchlist Testing Logs is a legacy program that is being replaced by the Punch Lists Module. This module is to be used for reference of past projects. Use the Punch Lists Module for all future work.

1.6.12 Punch Lists Module

The eCMS Punch Lists module is useful more than just for Punchlists. The module includes the capability of batch editing, create items from Optical Character Recognition (OCR) plans, assign tasks and track completion of individual items.

Create the following using the Punch Lists module:

Rework Items List

DFOW List

Punch-Out Inspection

Pre-Final Punchlist Inspection

Final Punchlist Inspection

Testing Logs

1.6.13 FWD UltraLean COAR RFP Module

Not used.

1.6.14 Non-Compliance Notices (NCN) Module

Respond to Non-Compliance Notices listed in the Non-Compliance Notices module.

1.6.15 Checklists

Use Checklist listed in the contractor's eCMS menu and as directed by the COR. Checklists capture data and is used in dashboards and KPIs.

1.6.15.1 Partnering Team Health Survey Checklist

Contractor must use the eCMS checklist to document the partnering team health survey. Partnering Team Health Survey is in accordance with the Partnering Specification of this contract.

1.6.16 Flysheets

Use Flysheets listed in the contractor's eCMS menu, if available, and as directed by the COR. Flysheets allow the contractor to print out information from other systems and upload into eCMS. The eCMS will use OCR to capture the information as data. Flysheets capture data and used in dashboards and KPIs.

1.6.17 eCMS Outage

In the case where eCMS is unavailable for 8 hours or more, paper or email may be used in the interim to maintain project schedule.

Once the system is operational, all final records are required to be recreated using the appropriate module. Subject/title of the record to include the type of record i.e., RFI/Submittal/Daily Report/Communication/Other, the identification number(s), and the statement "Processed Outside of eCMS". Example, "RFI 001 Processed Outside of eCMS".

1.6.18 User Account Activity

NAVFAC eCMS captures user data and activities that are directly related to the user's account. The user agrees through the use of eCMS, their account activities will be captured and can be displayed on eCMS printed reports.

1.7 QUALITY ASSURANCE

Requested Government response dates on Submittals must be in accordance with the terms and conditions of the Contract unless previously agreed by the COR. Requesting response dates earlier than the required review and response time, without concurrence by the Government COR, may be cause for rejection.

Incomplete submittals will be rejected without further review and must be resubmitted. Required Government response dates for resubmittals must reflect the date of resubmittal, not the original submittal date.

All submittals and associated attachments must be transmitted to the Government via the COR. Transmittals are no longer required when using eCMS since approval status is tracked on the submittal. Transmittal forms can be attached to submittals if approved by the COR. Submittals requiring government approval are "Transmitted For" "Approval". Submittals requiring contractor approved submittals, including those designated for Contractor Quality Control approval or Information Only, are "*Transmitted For" "Information Only" in the Submittal Module. Provide and sign the QC certification or approving statement on the attachment per submittal specification section. When Submittal Packages are required, use eCMS Submittal Packages after creating individual submittals. Importing Submittals from the Submittal Register is optional. Contact the COR for the data conversion requirements.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 32 17.00 20

COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS)
05/25

PART 1 GENERAL

1.1 DEFINITIONS

The cost-loaded Network Analysis Schedule (NAS) is a tool to manage the project, both for Contractor and Government activities. The NAS is also used to report progress, evaluate time extensions, and provide the basis for progress payments.

For consistency, when scheduling software terminology is used in this section, the terms in Oracle Primavera's scheduling programs are used.

1.2 NAS REQUIREMENTS PRIOR TO THE START OF WORK

1.2.1 Preliminary Scheduling Meeting

Before preparation of the Baseline NAS, and prior to the start of work, meet with the Contracting Officer to discuss the proposed NAS and the requirements of this section. Propose projected data dates for monthly update NAS for the project and incorporate each monthly update submittal into the submittal register. Discuss required forms, terminology, and submittal requirements of this section and other requirements related to schedule management for this contract. Use the NAVFAC-provided Preliminary Scheduling Meeting Guideline in the completion of the intended mutual understanding.

1.2.2 Baseline NAS

Submit the Baseline NAS within 30 calendar days after contract award. Data date must be set to contract award date and no progress recorded for any activity. Only bonds and the required Preliminary Scheduling Meeting may be recorded as complete prior to acceptance of the Baseline NAS. The acceptance of a Baseline NAS is a condition precedent to:

a. The Contractor starting demolition work or construction stage(s) of the contract.

b. Processing Contractor's invoices(s) for any items other than bonds.

c. Review of any NAS updates. The contractor is still required to submit monthly NAS updates. Without an accepted baseline NAS, the Government may return Monthly NAS update as received for record.

Submittal of the Baseline NAS is the Contractor's certification that the submitted NAS meets the requirements of the Contract Documents and represents the Contractor's plan on how the work will be accomplished. Provide all items listed in paragraph REQUIRED TABULAR REPORTS AND NATIVE P6 XER FILES with baseline NAS submittal.

1.3 WEEKLY LOOK AHEAD SCHEDULE

1.3.1 Quality Control and Production Integration with NAS

Submit the first Look Ahead Schedule 30 days after contract award and continue to submit weekly until contract completion.

Transmit the Weekly Look Ahead Schedule Submittal to the Contracting Officer on the first day of the current week that the Look Ahead Schedule covers and at least one working day prior to any Quality Control meetings. Contractor is required to provide all attendees at meetings with a copy of the Look Ahead Schedule. A Look Ahead Schedule is required to be submitted weekly regardless of whether a meeting is held or not.

1.3.2 Weekly Look Ahead Schedule Requirements

Prepare and issue a Three-Week Look Ahead Schedule to provide a more detailed day-to-day plan of upcoming work identified on the current Network Analysis Schedule. Requirements include:

a. For each Look Ahead Schedule activity, identify parent NAS activity number(s). The parent NAS activity is the activity in the NAS that would incorporate the Look Ahead Schedule activity requirement andor scope of work.

b. Update schedule each week to show the planned work for the following three-week period. Also include previous week, as-built work, showing actual start and finish dates.

c. Include upcoming outages, closures, preparatory meetings, and initial meetings, testing and inspections.

d. Identify any offsite fabrication and production activities.

e. Clearly identify Longest Path activities on the Weekly Look Ahead Schedule. Include a key or legend that distinguishes longest path activities. Include all Longest Path activity NAS start/finish dates exceeded andor occurring during this period.

f. Identify responsibility for each activity.

g. The detail work plans are to be bar chart type schedules, derived from but maintained separately from the Project NAS on an electronic spreadsheet program and printed on 11 by 17 inch sheets as directed by the Contracting Officer.

h. Activities must not exceed 5 working days in duration and have sufficient level of detail to assign crews, tools and equipment required to complete the work.

i. Look Ahead activities are not limited to only onsite work. Include submittal, offsite fabrication, and procurement activities. Include design activities, meetings, and coordination when part of scope.

j. Upload the Weekly Look Ahead Schedules to eCMS as a submittal by the date and time required.

1.4 MONTHLY NETWORK ANALYSIS

Submittal of Monthly NAS is the Contractor's certification that the submitted NAS meets the requirements of the Contract Documents and represents the Contractor's plan on how the work will be accomplished. Provide all items listed in paragraph REQUIRED TABULAR REPORTS AND NATIVE P6 XER FILES with the monthly NAS submittal.

1.4.1 Monthly Update Meeting

Meet with Government representative(s) at monthly intervals to review and agree on the information presented in the Monthly NAS Update. The Monthly Update Meeting must be a separate and distinct meeting from other meetings required of the contract. As a minimum, accomplish the following with each meeting held monthly:

a. Prior to the meeting, provide an agenda of proposed topics to be discussed to include but not limited to narrative report and items listed in paragraph REQUIRED TABULAR REPORTS. Document agenda and minutes with Meeting Minutes object in eCMS for each monthly update meeting.

b. The Approved Designated Project Scheduler must present the NAS data using Oracle Primavera P6 software and have baseline NAS, monthly update NAS, and Time Impact Analysis native files available to review as necessary.

c. Review Time Impact Analysis.

d. Document action items in eCMS Meeting Minutes for necessary revisions to Monthly NAS Update and to address any delays and or problem areas in a timely manner.

1.4.2 Monthly NAS Updates

a. The submission of an accepted, updated NAS to the Government is a condition precedent to the processing of the Contractor's invoice.

b. Regardless of whether an invoice is being submitted monthly, or no project progress occurred, an updated NAS (or with new data date) must be submitted monthly to the Government. The Monthly NAS update must be submitted within 5 calendar days of the data date.

c. Regardless of whether a baseline or other NAS is submitted andor accepted, an updated NAS must be submitted monthly to the Government. Monthly updates submitted before the baseline being accepted may be returned as received for record.

d. Provide all items listed in paragraph REQUIRED TABULAR REPORTS AND NATIVE P6 XER FILES, with each monthly NAS update submittal.

e. Activity progress must incorporate as-built events as they occurred and correspond to records including but not limited to submittals and daily production and quality control reports.

f. Software Settings: Handle NAS calculations through Retained Logic, not Progress Override. Out of Sequence progress is not allowed. Relationships must be changed to reflect as-built relationships. Show all activity durations and float values in days. Show activity

progress using Remaining Duration. Set default activity type to "Task Dependent".

g. Updated NAS must reflect current Contract Completion Date and contract value in accordance with all conformed contract modifications issued prior to data date of NAS update.

1.4.3 As-Built NAS

As a condition precedent to the release of retention and making final payment, submit an "As-Built NAS," as the last NAS update showing all activities at 100 percent completion. This NAS must reflect the exact manner in which the project was actually constructed.

1.5 CORRESPONDENCE AND TEST REPORTS

Reference NAS Activity IDs that are being addressed in each correspondence (e.g., letters, Submittals, Requests for Information (RFIs), e-mails, meeting minute items, Production and QC Daily Reports, material delivery tickets, photographs) and test report (e.g., concrete, soil compaction, weld, pressure).

1.6 ADDITIONAL NETWORK ANALYSIS SCHEDULE REQUIREMENTS

Other specification sections may include additional NAS related requirements, including systems to be inspected, tested and commissioned, and submittal procedures. Those requirements must be incorporated into the NAS.

1.7 SUBMITTALS

Government approval/acceptance is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Baseline NAS; G

Designated Project Scheduler; G

SD-07 Certificates

Weekly Look Ahead Schedule

Monthly NAS Updates; G

SD-11 Closeout Submittals

As-Built NAS; G

1.8 SOFTWARE

Prepare and maintain project NAS using Oracle Primavera P6 software in a version compatible with Government's current version. Submit XER files exported as version 17 or earlier. Importing data into P6 using data conversion techniques or third party software is cause for rejection of the submitted NAS. NAS with Performing Organizational Breakdown Structure

(POBS) data in any form other than column is cause for rejection. NAS must be scheduled by using the Schedule command after last entry in Oracle Primavera P6 prior to export for submission to the Government.

1.9 DESIGNATED PROJECT SCHEDULER

Within 30 calendar days of contract award, submit to the Contracting Officer for approval an individual who will serve as the Designated Project Scheduler. Include a copy of the candidate's resume with qualifications. The Designated Project Scheduler is subject to removal by the Contracting Officer for non-compliance with the requirements specified in the Contract. Payment request will not be processed without an approved Designated Project Scheduler.

1.9.1 Qualifications

The Designated Project Scheduler must have served as a scheduler and prepared and maintained at least three previous NAS for projects, at least one within the last 5 years of similar size and complexity to this contract, using Oracle Primavera P6.

1.9.2 Duties

Duties of the Designated Project Scheduler include to be actively involved and be responsible for the following:

a. Prepare Baseline NAS.

b. Prepare monthly NAS updates.

c. Prepare tabular reports.

d. Prepare Time Impact Analysis (TIA) as necessary.

e. Provide certification of contract compliance for each NAS and TIA submittal transmitted to government for review.

f. Participate with the Prime Contractor and Government Representative in a monthly teleconference call, and scheduled with sufficient time to support the Monthly Network Analysis Updates process, to discuss project status, NAS updates, critical activities, potential delays, and contract modifications impacting any project progress. Have a computer with P6 software available during the meeting.

1.10 NETWORK SYSTEM FORMAT

Prepare the NAS in accordance with the following Primavera P6 settings and parameters. Deviation from these settings and parameters, without prior consent of the Contracting Officer, is cause for rejection of NAS submittal.

1.10.1 NAS Activity Properties and Level of Detail

1.10.1.1 Activity Identification and Organization

a. Identify construction activities planned for the project and other activities that could impact project completion if delayed in the NAS.

b. Each activity must have a unique name.

c. Identify administrative type activity/milestones, including all pre-construction submittal and permit requirements prior to demolition or construction stage.

d. Include durations for procurement, Contractor quality control, acceptance testing and training in the NAS.

e. Include the Government approval time required for the submittals that require Government Approval prior to construction, as indicated in Section 01 33 00 SUBMITTAL PROCEDURES.

f. Create separate activities for each Phase, Area, Floor Level and Location the activity is occurring.

g. Do not use activities to represent non-work type reference (e.g., Serial Letter, Request for Information) in NAS. When RFIs need to be included in NAS, identify Non-work reference with use of added Activity codes (e.g, RFI code, Serial Letter Code). Document use of added activity codes in narrative report.

Activity categories included in the NAS are specified below.

1.10.1.2 Activity Logic

a. With the exception of the Contract Award and Contract Completion Date (CCD) milestone activities, activity must not be open-ended; each activity must have at least one predecessor and at least one successor.

b. Activities must not have open start or open finish (dangling) logic.

c. Do not use lead or lag logic without Contracting Officer prior approval. Request for approval must be submitted at the required Preliminary Scheduling Meeting for use in the Baseline NAS and at the required Monthly Network Analysis Update Meeting for use in a monthly updated NAS.

d. Minimize redundant logic ties.

e. Once an activity exists on the NAS it must not be deleted or renamed to change the scope of the activity and must not be removed from the NAS logic without approval from the Contracting Officer. Request for approval must be submitted with the required Monthly NAS Update Narrative.

f. While an activity cannot be deleted, where said activity is no longer applicable to the NAS, but must remain within the logic stream for historical record, change the activity original and remaining duration to zero and clearly label "(NO LONGER REQUIRED)" after the Activity Name.

(1) Document any such change in the activities' "Notebook," including a date and explanation for the change.

(2) The ID number for a "NO LONGER REQUIRED" activity must not be re-used for another activity.

g. No activity can be added to the NAS without the prior approval from the Contracting Officer. Request for approval must be submitted at

the required Monthly Network Analysis Update Narrative for use in a monthly updated NAS.

h. Activity Type for all activities except for milestones must be set to "Task Dependent". "Level of Effort" Activity Type is not allowed.

i. Duration Type for all activities except for milestones must be set to "Fixed Duration & Units".

j. Percent Complete Type for all activities including milestones must be set to "Physical".

1.10.1.3 Longest Path Activity Baseline Limitation

For P6 settings, critical activities are defined as being on the Longest Path. Longest Path (Critical) Activities must not make up more than 30 percent of all activity within the Construction Baseline NAS.

1.10.1.4 Assigned Calendars

All NAS activity must be assigned calendars that reflect required and anticipated non-work days.

Total work hours/day for all defined calendars is set to 8.

1.10.1.5 Activity Categories

1.10.1.5.1 Pre-construction Activities

Examples of pre-construction activities include, but are not limited to, bond approval, permits, pre-construction submittals and approvals. Include pre-construction activities that are required to be completed prior to the Contractor starting the demolition or construction stage of work.

1.10.1.5.2 Procurement Activities

Include activities necessary to manage the ordering, fabrication, and delivery of material and equipment. Procurement activities must not have a duration in excess of 60 calendar days without prior approval by the Contracting Officer. Include within sequence of off-site assembly and fabrication any quality control and testing being performed.

Examples of procurement activities include, but are not limited to: Material/equipment submittal preparation, submittal and approval of material/equipment; material/equipment fabrication and delivery, and material/equipment on-site. As a minimum, separate procurement activities must be provided for critical items, long lead items, items requiring Government approval and material/equipment procurement for which payment will be requested in advance of installation. Show each delivery with relationship tie to the Construction Activity specifically for the delivery.

1.10.1.5.3 Government Activities

Government and other agency activities that could impact progress must be clearly identified. Government activities include, but are not limited to; Government approved submittal reviews, Government conducted inspections/tests, environmental permit approvals by State regulators,

utility outages, and delivery of Government Furnished Material/Equipment.

1.10.1.5.4 Construction Quality Management (CQM) Activities

The Preparatory and Initial Phase meetings for each Definable Feature of Work identified in the Contractor's Quality Control Plan must be included in the Weekly Look Ahead Schedules. Preparatory and Initial phase meetings are not required in the NAS, but can be represented by a start milestone linked to successor parent Construction Activity. The Follow-up Phase must be represented by the Construction Activities themselves in the NAS.

1.10.1.5.5 Construction Activities

On-site construction activities that are the responsibility of the Contractor or Contractor's subcontractors must not have a duration in excess of 20 working days without prior approval by the Contracting Officer. Contractor activities must be driven by calendars that reflect Saturdays, Sundays and all Federal Holidays as non-work days, unless otherwise defined in this contract. Federal Holidays are as defined in Federal Law 5 USC 6103.

1.10.1.5.6 Turnover and Closeout Activities

Include activities or milestones for items on the NAVFAC Red Zone Checklist/POAM that are applicable to this project. As a minimum, include required Contractor testing, required Government acceptance inspections on equipment, Pre-Final Inspection, Punch List Completion, Final Inspection and Acceptance. Add an unconstrained start milestone for the initial NAVFAC Red Zone - Facility Turnover Planning Meeting at approximately 75 percent construction contract completion or six months prior to Contract Completion Date (CCD), whichever is sooner. Include a separate NAVFAC Red Zone - Facility Turnover Planning Meeting Milestone for each phase if the contract requires construction to be completed in phases.

1.10.1.5.7 Testing of HVAC - DALT, TAB, and PVT Activities

Include in the baseline NAS, activities and milestones associated with Government acceptance of Duct Air Leakage Test (DALT), Testing, Adjusting, and Balancing (TAB) and Performance Verification Test (PVT) as required and in accordance with Section 23 05 93 TESTING, ADJUSTING AND BALANCING FOR HVAC and Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

a. Identify the general area or location(s) for Government Acceptance Testing of DALT, TAB and PVT.

b. Incorporate into the baseline NAS, time periods required for advance notification of work, and Government submittal review in accordance with Section 23 05 93 TESTING, ADJUSTING AND BALANCING FOR HVAC, paragraph DALT AND TAB SUBMITTAL AND WORK SCHEDULE.

c. Include the following as NAS activities or milestones:

(1) Pre-DALT/TAB/PVT Meeting

(2) TAB Design Review Report, Government review

(3) TAB Pre-Field Engineering Report, Government review

(4) DALT Field Work

(5) DALT Field Acceptance Testing

(6) Certified Final DALT Report, Government review

(7) Control Contractors PVT Plan, Government review

(8) Equipment Suppliers PVT Plan, Government review

(9) Endurance Testing, Government review

(10) PVT Field Work

(11) PVT Report, Government review

d. Include in the baseline schedule, the following cost-loaded activities. These activities will be successors to the Substantial Completion Milestone and predecessors to the Project Completion Milestone as defined in paragraph PROJECT COMPLETION MILESTONE.

(1) Season I TAB Field Work

(2) Season I Certified Final TAB Report, Government review

(3) Season I TAB Field Acceptance Testing

(4) Season II TAB Field Work

(5) Season II Certified Final TAB Report, Government review

(6) Season II TAB Field Acceptance Testing

(7) Post-Occupancy Endurance Testing Government review

(8) Post-Occupancy PVT Field Work

1.10.1.5.8 Commissioning Activities

Include in the baseline NAS activities and milestones associated with Commissioning.

a. Identify the general area or location(s) of systems for Commissioning Inspection and Testing

b. Incorporate into the baseline NAS time periods for Government submittal review

1.10.1.6 Contract Milestones and Constraints

1.10.1.6.1 Project Start Date Milestones

Include as the first activity on the NAS a start milestone titled, "Contract Award", which must have a Mandatory Start constraint equal to the Contract Award Date.

1.10.1.6.1.1 Post-Award Kickoff (PAK) meeting Milestone

Include an unconstrained finish milestone on the NAS titled, "Post-Award

Kickoff Meeting". The Post Award Kickoff Meeting may be a single day, or it may range over several days. The intent is to cover all PAK topics, including Partnering and Concept Design Workshop (if required) in one continuous session.

1.10.1.6.2 Pre-Construction Meeting Milestone

Include an unconstrained finish milestone on the NAS titled, "Pre-Construction Meeting". The Pre-Construction meeting may be a single day, or it may range over several days. The intent to cover all the Pre-Con topics, including Partnering and DD1354.

1.10.1.6.3 Preconstruction Submittals Finish Milestone

Include an unconstrained finish milestone on the NAS titled, "Preconstruction Submittals". This milestone is complete when all required preconstruction submittals have been reviewed and approved by the Government.

1.10.1.6.4 Contractor Mobilization Finish Milestone

Include an unconstrained finish milestone on the NAS titled, "Contractor Mobilization".

1.10.1.6.5 NAVFAC Red Zone - Facility Turnover Planning Meeting Milestones

See paragraph TURNOVER AND CLOSEOUT ACTIVITIES above.

1.10.1.6.6 Substantial Completion Milestone

Include an unconstrained finish milestone on the NAS titled "Substantial Completion." Substantial Completion is defined as the point in time the Government would consider the project ready for beneficial occupancy wherein by mutual agreement of the Government and Contractor, Government use of the facility is allowed while construction access continues in order to complete remaining items (e.g., punch list and other close out submittals). Include a separate Substantial Completion Milestone for each phase if the contract requires construction to be completed in phases.

1.10.1.6.7 DD-1354 Finish Milestone

Add unconstrained finish milestone, titled "DD-1354" and scheduled 30 calendar days prior to Substantial Completion, whenever a Form DD-1354 is required in accordance with Section 01 20 00 PRICE AND PAYMENT PROCEDURES. Include a separate DD-1354 Finish Milestone for each phase if the contract requires construction to be completed in phases.

1.10.1.6.8 Project Completion Milestone

Include an unconstrained finish milestone on the NAS titled "Project Completion." Project Completion is defined as the point in time all contract requirements are complete and verified by the Government with a successful Final Inspection in accordance with Section 01 45 00 QUALITY CONTROL. This milestone must have the Contract Completion Date (CCD) milestone as its only successor.

1.10.1.6.9 Contract Completion Date (CCD) Milestone

Last NAS entry must be an unconstrained finish milestone titled "Contract

Completion (CCD: DD-MM-YY)." DD-MM-YYYY is the current contract completion date at data date, day-month-year corresponding to P6 Must Finish By Date. NAS milestone updates of Project Completion finish date for longest path must reflect calculated float as positive or negative based on CCD. Calculation of NAS updates must be such that if the finish of the "Project Completion" milestone falls after the contract completion date, then negative float is calculated on the longest path. If the finish of the "Project Completion" milestone falls before the contract completion date, the float calculation must reflect positive float on the longest path.

1.10.1.6.10 Additional Milestones

Provide up to five additional milestones as required by Contracting Officer.

1.10.1.7 Work Breakdown Structure & Activity Code

At a minimum, establish a Work Breakdown Structure (WBS) and provide activity codes identified as follows:

1.10.1.7.1 Work Breakdown Structure (WBS)

Group all activities and milestones within appropriate WBS elements/levels including, at a minimum, the following:

a. Project Milestones:

(1) Management Milestones

(2) Project Administrative Meetings

(3) Permits

b. Pre-Construction Phase:

(1) Submittals and Reviews

(2) Procurement

(3) Mobilization

c. Construction Phase: Create multiple elements/levels in accordance with project specific definable features of work including in WBS descending order as follows:

(1) General Area

(a) Type of Work Item

1. Location

d. Project Closeout: Include activity items such as, but not limited to, Punchlist, Demobilization, O&M, As-built Drawings, Training, and As-built NAS.

e. Modifications: Create Conformed and Non-Conformed elements/levels under Modification WBS. Create multiple elements/levels as the project progresses identified by issue and Fragnet placed in Conformed

for modifications issued prior data date, or Non-Conformed for issues not modified to contract prior data date.

f. Removed Activity: Activity is "removed" by remaining within logic sequence, eliminating duration and adding "(NO LONGER REQUIRED)" after Activity Name in Activity Table.

g. Commissioning & Testing:

(1) Specific area/locations of commissioning

(2) Final Testing

(3) Training

1.10.1.7.2 Responsibility Code

Use "RESP" for Activity Code Name. All activities in the project NAS must be identified with the resource, including business name, for completing the task. Activities must not belong to more than one responsible party.

1.10.1.7.3 Activity Category Code

Use "CAT" for Activity Code Name for the following Project Level activity codes:

a. Assign "PROC" value to Procurement type activity

b. Assign "PRE-CON" value to Pre-construction activity

c. Assign "CONS" value to Construction type activity

d. Assign "TEST" value to dedicated testing type activities

e. Assign "CX" value to dedicated Commissioning type activities

f. Assign "CLOS" value to dedicated Close Out type activity

g. Assign "OTHR" to other activity not otherwise designated

1.10.1.7.4 Additional Activity Codes

Provide up to an additional five activity codes as required by the Contracting Officer

1.10.1.7.5 Drawing Code

Identify all activities in the project NAS with its respective Drawing Code. The Drawing Code is the Sheet Number on the primary project drawing which indicates work to be performed. If an activity does not have an applicable Drawing Code (e.g., Mobilize), the code must be "0000".

1.10.1.7.6 Construction Specification Institute (CSI) Masterformat Code

Identify all activities in the project NAS with its respective Specification Section number. Activities must not belong to more than one Section number. If an activity does not have an applicable CSI Code (e.g., Mobilize), the code must be "0000".

1.10.1.8 Adverse Weather Lost Work Days

Use the National Oceanic and Atmospheric Administration's (NOAA) Summary of Monthly Normals report to obtain the historical average number of days each month with precipitation, using a nominal 30-year, greater than 0.10 inch precipitation amount parameter, as indicated on the Station Report for the NOAA location closest to the project site as the basis for establishing a "Weather Calendar" showing the number of anticipated non-workdays for each month due to adverse weather, in addition to Saturdays, Sundays and all Federal Holidays as non-work days.

Assign the Weather Calendar to any activity that could be impacted by adverse weather. The Contracting Officer will issue a modification in accordance with the contract clauses, giving the Contractor a time only extension for the difference of days between the anticipated and actual adverse weather delay if the number of actual adverse weather delay days exceeds the number of days anticipated for the month in which the delay occurs and the adverse weather delayed activities are on the longest path to contract completion in the period when delay occurred. A lost workday due to weather conditions is defined as a day in which the Contractor cannot work at least 50 percent of the day on the impacted activity. Impacts resulting from adverse weather must be documented in Narrative Report for the month that it occurred.

Make changes to P6 project calendars to reflect as-built conditions where work occurred where originally anticipated as non-work days, and where work did not occur (lost work day).

1.10.1.9 Anticipated Restricted Delays

Use anticipated non-working days as defined in Section 01 14 00 WORK RESTRICTIONS, use Anticipated Restricted Delays as basis for establishing a "Security Calendar" showing the number of anticipated non-workdays for each month due to anticipated restrictions, in addition to anticipated adverse weather, Saturdays, Sundays and all Federal Holidays as non-work days. Assign the Security Calendar to any activity that could be impacted by restriction delays. The Contracting Officer will issue a modification in accordance with the contract clauses, giving the Contractor a time extension for the difference of days between the anticipated and actual lost work days if the number of actual restriction delay days exceeds the number of anticipated for the month in which the delay occurs and the restriction delayed activities are critical to contract completion. A lost workday due to restriction delay is defined as a day in which the Contractor cannot work at least 50 percent of the day on the impacted activity.

Impacts resulting from restriction delays must be documented in Narrative Report for the month that it occurred.

Make changes to P6 project calendars to reflect as-built conditions where work occurred where originally anticipated as non-work days, and where work did not occur (lost work day).

1.10.1.10 Cost Loading

The Project Network Analysis Schedule (NAS) must be cost-loaded and will provide the basis for progress payments. Earned Value Reports must be derived from and correspond to cost loaded NAS. Use the Critical Path Method (CPM) and the Precedence Diagram Method (PDM) to satisfy time and

cost applications.

Sum of all costs assigned to activities must equal the current contract value as of the data date of the baseline or update NAS. Activity cost loading must be without front-end loading. Provide additional documentation if requested by the Contracting Officer.

1.10.1.10.1 Cost Loading Activities

a. Cost load construction activities. Define construction activities as on-site work activities that can be traced directly to the construction, alteration, demolition, repair of a project facility, infrastructure, or sitework.

b. Assign costs for materials which payment will be requested in advance of installation, including their quantities, to their respective procurement activities that were approved by the Contracting Officer. Assign labor costs, including their quantities, for material and equipment paid for after installation to their respective construction activities.

c. Costs for mobilization will not be paid as individual pay items with the exception of batch plant set-up, mobilization of dredging equipment or other similar labor-intensive situations. If payment for mobilization costs are approved, assign costs for demobilization activities. The value of demobilization activities must not be less than 40 percent of the total costs for mobilization activities. If not approved as a separate line item, evenly disperse over construction activities the costs for mobilization and demobilization.

d. The value of commissioning, testing, and closeout WBS section may not be less than 10 percent of the total costs for procurement and construction activities.

e. ALL activities assigned Government responsibility will have Zero Cost. No contractor cost should be assigned to an activity designated as a Government responsibility.

f. Do not include field overhead positions as individual cost loaded activities. Evenly disperse non-construction costs (e.g., meetings, presentations, submittals, surveys, haul road or storage yard maintenance, dust control, security) and profit to construction activities assigned to the Construction Phase WBS level.

g. If assigning resources to activities, setting for Calculate costs from units in Resources tab must be unchecked.

1.10.1.10.2 Partial Payment

Breakdown unit of measure and cost must be defined within P6 Activity Detail Expenses for partial payment of any cost loaded activity. Lump sum cost loaded activity will not be partially paid.

1.10.2 NAS Software Settings and Restrictions

a. Activity Constraints: Date/time constraint(s), other than those required by the contract, are not allowed unless accepted by the Contracting Officer. Identify any constraints proposed and provide an explanation for the purpose of the constraint in the Narrative Report

as described in paragraph REQUIRED TABULAR REPORTS.

b. Default Progress Data Disallowed: Actual Start is date work begins on activity with intent to pursue work to substantial completion. Actual Finish is date work is substantially complete to point where successor activity can begin. Actual dates on the NAS must correspond with activity dates reported on the Contractor Quality Control and Production Reports.

c. At a minimum, include the following settings and parameters in P6 NAS preparation:

(1) General: Define or establish Calendars and Activity Codes at the "Project" level, not the "Global" level.

(2) Admin Drop-Down Menu, Admin Preferences, Time Periods Tab:

(a) Set time periods for P6 to 8.0 Hours/Day, 40.0 Hours/Week, 172.0 Hours/Month and 2000.0 Hours/Year.

(b) Use assigned calendar to specify the number of work hours for each time period: Must be checked.

(3) Admin Drop-Down Menu, Admin Preferences, Earned Value Tab:

(a) Technique for computing performance percent complete: Use "Activity percent Complete"

(b) Technique for computing Estimate to Complete: Use "PF = 1".

(c) Earned Value Calculation: Use "Budgeted values with current dates".

(4) Project Level, Dates Tab:

(a) Set "Must Finish By" date to "Contract Completion Date", and set "Must Finish By" time to 05:00pm.

(5) Project Level, Defaults Tab:

(a) Duration Type: Set to "Fixed Duration & Units".

(b) Percent Complete Type: Set to "Physical".

(c) Activity Type: Set to "Task Dependent".

(d) Calendar: Set to "Standard 5 Day Workweek". Calendar must reflect Saturday, Sunday and all Federal holidays as non-work days. Alternative calendars may be used with Contracting Officer approval.

(6) Project Level, Calculations Tab:

(a) Default Price/Unit for activities without resource or role Price/Units: Set to "$1/h".

(b) Activity percent complete based on activity steps: Must be Checked.

(c) Link Budget and At Completion for not started activities: Must be Checked.

(d) Reset Remaining Duration and Units to Original: Must be Selected.

(e) Subtract Actual from At Completion: Must be Selected.

(f) Recalculate Actual units and Cost when duration percent complete changes: Must be Checked.

(g) Update units when costs change on resource assignments: Must be Unchecked.

(h) Link Actual to Date and Actual This Period Units and Cost: Must be Checked.

(7) Project Level, Settings Tab:

(a) Define Critical Activities: Check "Longest Path".

(8) Work Breakdown Structure Level, Earned Value Tab:

(a) Technique for Computing Performance Percent Complete: "Activity percent complete" is selected.

(b) Technique for Computing Estimate to Complete (ETC): "PF = 1" is selected.

1.10.3 Required Tabular Reports and Native P6 XER Files

Include the following reports with the Baseline, Monthly Update and any other required NAS submittals:

a. Time Scaled Logic NAS

Provide formatted 11 by 17-inch Time-scaled Logic NAS in color and landscape-oriented with each NAS submittal. Clearly show activities on the longest path setting Gantt chart longest path activity bars to red. Group activities by WBS and sort by finish date in ascending order. Include the following information in column form for each activity and include accompanying Gantt chart:

(1) Activity ID

(2) Activity Name

(3) Original Duration

(4) Remaining duration

(5) Physical Percent Complete

(6) Start Date

(7) Finish Date

(8) Total Float

(9) Project-level Calendar

b. Previous Monthly Update Comparison Time Scaled Logic NAS (Submit with all Monthly NAS Update Submittals.)

Provide formatted 11 by 17-inch Time-scaled Logic NAS in color and landscape-oriented with each monthly NAS update submittal. Clearly show activities on the current month longest path setting Gantt chart longest path activities bars to red. Show previous month activities as yellow bars and previous month milestones in yellow within Gantt chart. Sort by finish date in ascending order. Filter activities for longest path. Maintain and assign the accepted previous monthly NAS update or the accepted baseline NAS for the first update submittal as the baseline and primary baseline in P6 before printing the NAS. Include the following information in column form for each activity and include accompanying Gantt chart:

(1) Activity ID

(2) Activity Name

(3) Original Duration

(4) Current Month Remaining Duration

(5) Current Month Start Date

(6) Previous Month Update Start Date (BL Project Start)

(7) Start Date Delta between Current Month and Previous Month (Variance - BL Project Start Date)

(8) Current Month Finish Date

(9) Previous Month Finish Date (BL Project Finish)

(10) Finish Date Delta between Current Month and Previous Month (Variance - BL Project Start Date)

(11) Current Month Total Float

c. P6 native XER file: Include the back-up native .xer program file compatible with the current Government version of Primavera P6. Each native NAS file must have a unique file name to include project name and data date using (yyyy-mm-dd) convention. Each native NAS must have a unique Project ID and Project Name.

d. Log Report: P6 Scheduling/Leveling Report.

e. Narrative Report: Identify and justify:

Each entry in the Narrative Report must cite the respective Activity ID and Activity Name, the date and reason for any changes, and description of the change.

(1) Provide Project Summary Data in format below:

(a) Data Date _____

(b) Award Date: _____

(c) Original Project Duration: _____ days post Award Date

(d) Current Project Duration: _____ days post Award Date

(e) Time percent elapsed: _____ percent at data date

(f) Original CCD: _____

(g) Current CCD: _____ (thru MOD _____)

(h) Anticipated CCD: _____ (___ calendar days early/late)

(i) Original Contract Value: $_____

(j) Current Contract Value: $_____

(k) Invoiced Amount: $_____ (____ percent)

(l) Cost Growth: ____ percent

(m) NAS Growth: ____ percent

(n) There are a total of _____ activities, _____ activities complete (____ percent), ____ activities in progress (____ percent), _____ activities not started (____ percent). Of the in progress and not started activities; ____ (____ percent) are on the longest path. The longest path has duration of _____ calendar days from data-date to anticipated project completion.

(2) Progress made in each area of the project;

(3) Longest Path;

(4) Date/time constraint(s), other than those required by the contract

(5) Listing of all changes made between the previous monthly NAS update and current monthly NAS update include as a minimum: added or deleted activities, original and remaining durations for activities that have not started, logic (sequence constraint lag/lead), milestones, planned sequence of operations, longest path, calendars or calendar assignments, and cost loading. Identify any other changes that relate to calculations within Oracle Primavera P6;

(6) Any decrease in previously reported activity Earned Amount;

(7) Pending items and status thereof, including permits, changes orders, and time extensions;

(8) Status of Contract Completion Date and interim milestones;

(9) Status of Projected Completion Milestone and account of difference in calendar days between previous update Projected Completion Milestone

(10) Current and anticipated delays listing Activity Names and IDs for impacted activities(describe cause of delay and corrective actions(s) and mitigation measures to minimize);

(11) Description of current and potential future NAS problem areas.

(12) Identification of any weather and restricted lost time as compared to anticipated weather for the month and anticipated restricted days for which the update is submitted. Impacts resulting from adverse weather must be documented in tabular form showing the calendar month (or billing period) with the days on which construction activity incurred Lost Work Days due to adverse weather. In narrative form, describe the adverse weather cause such as precipitation measurement, temperature, wind or other influencing factors, and why work was impacted. Identify the construction activity(s) by ID and Name that was (were) scheduled, impacted.

f. Earned Value Report: Derive from and correspond to P6 cost loaded Monthly NAS Update. List all activities having a budget amount cost loaded. Compile total earnings on the project from notice to proceed to current progress payment request. Show on the report for each activity:

(1) Current budget;

(2) Previous Physical Percent Complete;

(3) To-Date Physical Percent Complete;

(4) Previous Earned Value;

(5) To-Date Earned Value;

(6) Cost This Period;

(7) Cost to Complete.

g. Schedule Variance Control (SVC) Diagram: With each NAS submission, provide a SVC diagram representing only the current file showing 1) A Cash Flow Curve indicating planned project cost based on each of projected early and projected late activity finish dates and 2) one curve for Earned Value to-date. Revise Cash Flow Curves when the contract is modified, or as directed by the Contracting Officer Include a legend on report clearly indication 3 curves: early finish, late finish, and earned-value to date.

Use the following settings in Activity Usage Profile Options:

(1) In the Data section, under Display, the radio box for Cost must be selected.

(2) In the Data section, under Filter for Bars/Graphs, the checkbox for Total must be checked.

(3) In the Show Bars/Curves section:

(a) Under the By Date column, the checkboxes for Baseline, Actual and Remaining Late must be checked. The checkboxes

for Budgeted and Remaining Early must be unchecked.

(b) Under the Cumulative column, the checkboxes for Baseline, Actual and Remaining Late must be checked. The checkboxes for Budgeted and Remaining Early must be unchecked.

(c) Set the color for Baseline to green.

(d) Set the color for Actual to blue.

(e) Set the color for Remaining Late to red.

(4) In the Show Earned Value Curves section, the checkboxes for Planned Value Cost, Earned Value Cost and Estimate at Completion must be unchecked.

h. Logic Diagram showing timescale from data date to 60 days after data date with filter for longest path. Leave Group By selection blank and sort by finish date in ascending order.

i. Logic Diagram showing timescale from data date to contract completion date with filter for longest path. Leave Group By selection blank and sort by finish date in ascending order.

j. Baseline or Monthly Update Checklist as applicable completed and certified by Qualified Scheduler. Contractor Baseline Project Schedule Review, Contractor Monthly Update Schedule Review, and Contractor Baseline Project Schedule, and General Commissioning/HVAC Review Checklist. Checklists can be found on the Whole Building Design Guide website as Related Materials to UFGS 01 32 17.00 20.

k. Screen shot PDF of Primavera P6 Time Periods Settings referenced in paragraph NAS SOFTWARE SETTINGS AND RESTRICTIONS, list item c.(2): ADMIN DROP-DOWN MENU, ADMIN PREFERENCES, TIME PERIODS TAB

l. Screen shot PDF of Primavera P6 Earned Value Settings referenced in paragraph NAS SOFTWARE SETTINGS AND RESTRICTIONS, list item c.(3): ADMIN DROP-DOWN MENU, ADMIN PREFERENCES, EARNED VALUE TAB

m. HVAC/COMMISSIONING KTR Checklist. See Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC for checklist requirements. Complete checklist listing all items with baseline submittal. Complete checklist as required to complete project, submitting complete checklist in intermediately following monthly update submittal.

1.11 CONTRACT MODIFICATION

1.11.1 Time Impact Analysis (TIA)

Submit a Time Impact Analysis with each cost and time proposal for a proposed change. TIA must illustrate the influence of each change or delay on the Contract Completion Date or milestones. No time extensions will be granted nor delay damages paid unless a delay occurs which consumes all available Project Float, impacts the longest path, and extends the Projected Completion beyond the Contract Completion Date.

a. Each TIA must be in both narrative and NAS form. The narrative must:

(1) Define the scope and conditions of the change;

(2) Provide start and finish dates of impact to longest path;

(3) Identify and include any accepted NAS referenced in TIA and any changes made to accepted NAS to prepare additional NAS included in the TIA;

(4) Successor(s) and predecessor(s) activities to impact period;

(5) Responsible party;

(6) Describe how the impact originated;

b. The TIA submission must consist of at least three native XER files:

(1) Fragnet used to define the scope of the changed condition

(2) Most recent accepted baseline NAS or monthly NAS update as of the time of the impact start date. If the data date of this NAS is different than the start date of impact, update this NAS to show all activity progress as of the time of the impact start. The impact start date is identified as the time when an existing activity is impeded for either starting or finishing. This NAS must have a data date that is the same as the identified start date of impact in "a.(2)". Identify any changes made to most recent accepted NAS.

(3) The impacted NAS that has the Fragnet inserted in the updated NAS from "b.(2)" and the NAS scheduled using the Schedule command in Oracle Primavera P6 so that the new completion date is determined.

c. For claimed as-built project delay, the inserted Fragnet TIA method must be modified to account for as-built events known to occur after the data date of NAS update used. Updated NAS for periods following the impact start date will be used and included in submittal to evaluate how the project progressed (as-built) through the finish of impact. Impact to longest path must be determined for each following update period.

d. All TIAs must include any mitigation, and must determine the apportionment of the overall delay assignable to each individual delay. Apportionment must provide identification of delay type and classification of delay by compensable and non-compensable events. The associated narrative must clearly describe analysis methodology used, and the findings in a chronological listing beginning with the earliest delay event.

(1) Identify and classify types of delay defined as follows:

(a) Force majeure delay (e.g., weather delay): Any delay event caused by something or someone other than the Government or the Contractor, or the risk of which has not been assigned solely to the Government or the Contractor. If the force majeure delay is on the longest path, in absence of other types of concurrent delays, the Contractor is granted an extension of contract time, classified as a non-compensable event.

(b) A Contractor-delay: Any delay event caused by the Contractor, or the risk of which has been assigned solely to the Contractor. If the contractor-delay is on the longest path, in absence of other types of concurrent delays, Contractor is not granted extension of contract time, and classified as a non-compensable event. Where absent other types of delays, and having impact to project completion, Contractor must provide to Contracting Officer a Corrective Action Plan identifying plan to mitigate delay.

(c) A Government-delay: Any delay event caused by the Government, or the risk of which has been assigned solely to the Government. If the Government-delay is on the longest path, in absence of other types of concurrent delays, the Contractor is granted an extension of contract time, and classified as a compensable event.

(2) Functional concurrency must be used to analyze concurrent delays, where: separate delay issues delay project completion, do not necessarily occur at same time, rather occur within same monthly NAS update period at minimum, or within same as-built period under review. If a combination of functionally concurrent delay types occurs, it is considered Concurrent Delay, which is defined in the following combinations:

(a) Government-delay concurrent with contractor-delay: excusable time extension, classified non-compensable event.

(b) Government-delay concurrent with force majeure delay: excusable time extension, classified non-compensable event.

(c) Contractor-delay concurrent with force majeure delay: excusable time extension, classified non-compensable event.

(3) Pacing delay reacting to another delay (parent delay) equally or more critical than paced activity must be identified prior to pacing. Contracting Officer will notify Contractor prior to pacing. Contractor must notify Contracting Officer prior to pacing. Notification must include identification of parent delay issue, estimated parent delay time period, paced activity(s) identity, and pacing reason(s). Pacing Concurrency is defined as follows:

(a) Government-delay concurrent with contractor-pacing: excusable time extension, classified compensable event.

(b) Contractor-delay concurrent with Government-pacing: inexcusable time extension, classified non-compensable event

e. Submit electronic files containing the narrative and the Native XER NAS files used and or referenced in the time impact analysis.

1.12 PROJECT FLOAT

Project Float is the length of time between the Project Completion Milestone and the Contract Completion Date. Project Float available in the NAS will not be for the exclusive use of either the Government or the Contractor.

The use of Resource Leveling is prohibited. Techniques used for the purpose of artificially adjusting activity durations to consume float and influence longest path are prohibited.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 33 00

SUBMITTAL PROCEDURES
08/18, CHG 4: 02/21

PART 1 GENERAL

1.1 DEFINITIONS

1.1.1 Submittal Descriptions (SD)

Submittal requirements are specified in the technical sections. Examples and descriptions of submittals identified by the Submittal Description (SD) numbers and titles follow:

SD-01 Preconstruction Submittals

Submittals that are required prior to or commencing with the start of work on site.

Preconstruction Submittals include schedules and a tabular list of locations, features, and other pertinent information regarding products, materials, equipment, or components to be used in the work.

Certificates Of Insurance

Surety Bonds

List Of Proposed Subcontractors

List Of Proposed Products

Baseline Network Analysis Schedule (NAS)

Submittal Register

Schedule Of Prices Or Earned Value Report

Accident Prevention Plan

Work Plan

Quality Control (QC) plan

Environmental Protection Plan

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project.

Drawings prepared by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-04 Samples

Fabricated or unfabricated physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

Field samples and mock-ups constructed on the project site establish standards ensuring work can be judged. Includes assemblies or portions of assemblies that are to be incorporated into the project and those that will be removed at conclusion of the work.

SD-05 Design Data

Design calculations, mix designs, analyses or other data pertaining to a part of work.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. Unless specified in another section, testing must have been within three years of date of contract award for the project.

Report that includes findings of a test required to be performed on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report that includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports

Daily logs and checklists

Final acceptance test and operational test procedure

SD-07 Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that the product, system, or material meets specification

requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or Subcontractor through Contractor. The document purpose is to further promote the orderly progression of a portion of the work by documenting procedures, acceptability of methods, or personnel qualifications.

Confined space entry permits

Text of posted operating instructions

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and Safety Data Sheets(SDS)concerning impedances, hazards and safety precautions.

SD-09 Manufacturer's Field Reports

Documentation of the testing and verification actions taken by manufacturer's representative at the job site, in the vicinity of the job site, or on a sample taken from the job site, on a portion of the work, during or after installation, to confirm compliance with manufacturer's standards or instructions. The documentation must be signed by an authorized official of a testing laboratory or agency and state the test results; and indicate whether the material, product, or system has passed or failed the test.

Factory test reports.

SD-10 Operation and Maintenance Data

Data provided by the manufacturer, or the system provider, including manufacturer's help and product line documentation, necessary to maintain and install equipment, for operating and maintenance use by facility personnel.

Data required by operating and maintenance personnel for the safe and efficient operation, maintenance and repair of the item.

Data incorporated in an operations and maintenance manual or control system.

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Submittals required for Guiding Principle Validation (GPV) or Third Party Certification (TPC).

Special requirements necessary to properly close out a construction contract. For example, Record Drawings and as-built drawings. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

1.1.2 Approving Authority

Office or designated person authorized to approve the submittal.

1.1.3 Work

As used in this section, on-site and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction. In exception, excludes work to produce SD-01 submittals.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submittal Register; G

1.3 SUBMITTAL CLASSIFICATION

1.3.1 Government Approved (G)

Government approval is required for extensions of design, critical materials, variations, equipment whose compatibility with the entire system must be checked, and other items as designated by the Government.

Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, submittals are considered to be "shop drawings."

1.3.2 For Information Only

Submittals not requiring Government approval will be for information only. Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, they are not considered to be "shop drawings."

1.3.3 Sustainability Reporting Submittals (S)

Submittals for Guiding Principle Validation (GPV) or Third Party Certification (TPC) are indicated with an "S" designation. These submittals are for information only and for use as specified in Section 01 33 29 SUSTAINABILITY REQUIREMENTS AND REPORTING.

Schedule submittals for these items throughout the course of construction as provided; do not wait until closeout.

1.4 FORWARDING SUBMITTALS REQUIRING GOVERNMENT APPROVAL

As soon as practicable after award of contract, and before procurement or fabrication, forward to the Architect-Engineer: MBF Architects, 317-C Pollock St. New Bern, NC 28560, submittals required in the technical sections of this specification, including shop drawings, product data and samples. In addition, forward a copy of the submittals to the Contracting Officer.

1.4.1 O&M Data

Submit data specified for a given item within 30 calendar days after the item is delivered to the contract site.

In the event the Contractor fails to deliver O&M data within the time limits specified, the Contracting Officer may withhold from progress payments 50 percent of the price of the items to which such O&M data apply.

1.4.2 Submittals Reserved for NAVFAC Mid-Atlantic Approval

As an exception to the standard submittal procedure for Government Approval, submit the following to the Commander, NAVFAC Mid-Atlantic, 9742 Maryland Avenue, Building Z-140, Room 219, Norfolk, Virginia, 23511-3095:

a. Section 21 13 13 WET PIPE SPRINKLER SYSTEMS, FIRE PROTECTION and 21 13 16 DRY PIPE SPRINKLER SYSTEMS, FIRE PROTECTION: All fire protection system submittals

b. Section 28 31 76 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE: All fire alarm system submittals

c. Section 01 91 00.15 BUILDING COMMISSIONING: SD-06 Commissioning Plan, Certificate of Readiness, and Commissioning Report submittals

d. Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC: SD-06 field test report submittals

e. Section 23 09 13 INSTRUMENTATION AND CONTROL DEVICES FOR HVAC S: SD-06 field test report submittals

f. Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC: All submittals

g. Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS: All submittals

h. Section 26 12 19.10 THREE-PHASE, LIQUID-FILLED PAD-MOUNTED TRANSFORMERS: All submittals

1.4.2.1 Commissioning

The CxC is responsible for identifying construction submittals to be provided by the contractor for the commissioned systems. The CxC is responsible for evaluating construction submittals for compliance with the contract documents.

1.4.2.2 Communications Summittals

Section 27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEM (MCBCL) and 33 82 00 TELECOMMUNICATIONS OUTSIDE PLANT (OSP)N: All submittal should be routed to:

Telecommunications Support Division (TSD) via NAVFAC

Steve Daigle
Base Telephone
steven.daigle@usmc.mil

1.5 PREPARATION

1.5.1 Transmittal Form

Transmit each submittal, except sample installations and sample panels to the office of the approving authority using the transmittal form prescribed by the Contracting Officer. Include all information prescribed by the transmittal form and required in paragraph IDENTIFYING SUBMITTALS. Use the submittal transmittal forms to record actions regarding samples.

1.5.2 Identifying Submittals

The Contractor's Quality Control Manager must prepare, review and stamp submittals, including those provided by a subcontractor, before submittal to the Government.

Identify submittals, except sample installations and sample panels, with the following information permanently adhered to or noted on each separate component of each submittal and noted on transmittal form. Mark each copy of each submittal identically, with the following:

a. Project title and location

b. Construction contract number

c. Dates of the drawings and revisions

d. Name, address, and telephone number of Subcontractor, supplier, manufacturer, and any other Subcontractor associated with the submittal.

e. Section number of the specification by which submittal is required

f. Submittal description (SD) number of each component of submittal

g. For a resubmission, add alphabetic suffix on submittal description, for example, submittal 18 would become 18A, to indicate resubmission

h. Product identification and location in project.

1.5.3 Submittal Format

1.5.3.1 Format of SD-01 Preconstruction Submittals

When the submittal includes a document that is to be used in the project, or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

1.5.3.2 Format for SD-02 Shop Drawings

Provide shop drawings not less than 8 1/2 by 11 inches nor more than 30 by 42 inches, except for full-size patterns or templates. Prepare drawings to accurate size, with scale indicated, unless another form is required.

Ensure drawings are suitable for reproduction and of a quality to produce clear, distinct lines and letters, with dark lines on a white background.

a. Include the nameplate data, size, and capacity on drawings. Also include applicable federal, military, industry, and technical society publication references.

b. Dimension drawings, except diagrams and schematic drawings. Prepare drawings demonstrating interface with other trades to scale. Use the same unit of measure for shop drawings as indicated on the contract drawings. Identify materials and products for work shown.

Submit an electronic copy of drawings in PDF format and native electronic format.

1.5.3.2.1 Drawing Identification

Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph IDENTIFYING SUBMITTALS.

Number drawings in a logical sequence. Each drawing is to bear the number of the submittal in a uniform location next to the title block. Place the Government contract number in the margin, immediately below the title block, for each drawing.

Reserve a blank space, no smaller than FOUR inches on the right-hand side of each sheet for the Government disposition stamp.

1.5.3.3 Format of SD-03 Product Data

Present product data submittals for each section. Include a table of contents, listing the page and catalog item numbers for product data.

Indicate, by prominent notation, each product that is being submitted; indicate the specification section number and paragraph number to which it pertains.

1.5.3.3.1 Product Information

Supplement product data with material prepared for the project to satisfy the submittal requirements where product data does not exist. Identify this material as developed specifically for the project, with information and format as required for submission of SD-07 Certificates.

Provide product data in units used in the Contract documents. Where product data are included in preprinted catalogs with another unit, submit the dimensions in contract document units, on a separate sheet.

1.5.3.3.2 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing

organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.3.3.3 Data Submission

Collect required data submittals for each specific material, product, unit of work, or system into a single submittal that is marked for choices, options, and portions applicable to the submittal. Mark each copy of the product data identically. Partial submittals will not be accepted for expedition of the construction effort.

Submit the manufacturer's instructions before installation.

1.5.3.4 Format of SD-04 Samples

1.5.3.4.1 Sample Characteristics

Furnish samples in the following sizes, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately the same size as specified:

a. Sample of Equipment or Device: Full size.

b. Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11 inches.

c. Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.

d. Sample of Linear Devices or Materials: 10 inch length or length to be supplied, if less than 10 inches. Examples of linear devices or materials are conduit and handrails.

e. Sample Volume of Nonsolid Materials: Pint. Examples of nonsolid materials are sand and paint.

f. Color Selection Samples: 2 by 4 inches. Where samples are specified for selection of color, finish, pattern, or texture, submit the full set of available choices for the material or product specified. Sizes and quantities of samples are to represent their respective standard unit.

g. Sample Panel: 4 by 4 feet.

h. Sample Installation: 100 square feet.

1.5.3.4.2 Sample Incorporation

Reusable Samples: Incorporate returned samples into work only if so specified or indicated. Incorporated samples are to be in undamaged condition at the time of use.

Recording of Sample Installation: Note and preserve the notation of any area constituting a sample installation, but remove the notation at the final clean-up of the project.

1.5.3.4.3 Comparison Sample

Samples Showing Range of Variation: Where variations in color, finish, pattern, or texture are unavoidable due to nature of the materials, submit sets of samples of not less than three units showing extremes and middle of range. Mark each unit to describe its relation to the range of the variation.

When color, texture, or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

1.5.3.5 Format of SD-05 Design Data

Provide design data and certificates on 8 1/2 by 11 inch paper.

1.5.3.6 Format of SD-06 Test Reports

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.3.7 Format of SD-07 Certificates

Provide design data and certificates on 8 1/2 by 11 inch paper.

1.5.3.8 Format of SD-08 Manufacturer's Instructions

Present manufacturer's instructions submittals for each section. Include the manufacturer's name, trade name, place of manufacture, and catalog model or number on product data. Also include applicable federal, military, industry, and technical-society publication references. If supplemental information is needed to clarify the manufacturer's data, submit it as specified for SD-07 Certificates.

Submit the manufacturer's instructions before installation.

1.5.3.8.1 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.3.9 Format of SD-09 Manufacturer's Field Reports

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.3.10 Format of SD-10 Operation and Maintenance Data (O&M)

Comply with the requirements specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA for O&M Data format.

1.5.3.11 Format of SD-11 Closeout Submittals

When the submittal includes a document that is to be used in the project or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

1.5.4 Source Drawings for Shop Drawings

1.5.4.1 Source Drawings

The entire set of source drawing files (DWG) will not be provided to the Contractor. Request the specific Drawing Number for the preparation of shop drawings. Only those drawings requested to prepare shop drawings will be provided. These drawings are provided only after award.

1.5.4.2 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim, and waives to the fullest extent permitted by law any claim or cause of action of any nature against the Government, its agents, or its subconsultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities, or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic source drawing files are not construction documents. Differences may exist between the source drawing files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic source drawing files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. The Contractor is responsible for determining if any conflict exists. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished source drawing files, the signed and sealed construction documents govern. Use of these source drawing files does not relieve the Contractor of the duty to fully comply with the contract documents, including and without limitation the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction data related to this contract, remove all previous indication of ownership (seals, logos, signatures, initials and dates).

1.5.5 Electronic File Format

Provide submittals in electronic format, with the exception of material samples required for SD-04 Samples items. Compile the submittal file as a single, complete document, to include the Transmittal Form described within, and also separately attach the native files which were used to create PDF. The attached files should include the original digital files used to create the submittal. Name the electronic submittal file specifically according to its contents, and coordinate the file naming convention with the Contracting Officer. Electronic files must be of sufficient quality that all information is legible. Use PDF as the electronic format, unless otherwise specified or directed by the Contracting Officer. Generate PDF files from original documents with bookmarks so that the text included in the PDF file is searchable and can be copied. If documents are scanned, optical character resolution (OCR) routines are required. Index and bookmark files exceeding 30 pages to allow efficient navigation of the file. When required, the electronic file must include a valid electronic signature or a scan of a signature.

E-mail electronic submittal documents smaller than 10MB to an e-mail address as directed by the Contracting Officer. Provide electronic documents over 10 MB on an optical disc or through an electronic file sharing system such as the DOD SAFE Web Application located at the following website: https://safe.apps.mil/.

1.6 QUANTITY OF SUBMITTALS

1.6.1 Number of SD-01 Preconstruction Submittal Copies

Unless otherwise specified, submit two sets of administrative submittals.

1.6.2 Number of SD-04 Samples

a. Submit two samples, or two sets of samples showing the range of variation, of each required item. One approved sample or set of samples will be retained by the approving authority and one will be returned to the Contractor.

b. Submit one sample panel or provide one sample installation where directed. Include components listed in the technical section or as directed.

c. Submit one sample installation, where directed.

d. Submit one sample of nonsolid materials.

1.7 INFORMATION ONLY SUBMITTALS

Submittals without a "G" designation must be certified by the QC manager and submitted to the Contracting Officer for information-only. Provide information-only submittals to the Contracting Officer a minimum of 14 calendar days prior to the Preparatory Meeting for the associated Definable Feature of Work (DFOW). Approval of the Contracting Officer is not required on information only submittals. The Contracting Officer will mark "receipt acknowledged" on submittals for information and will return only the transmittal cover sheet to the Contractor. Normally, submittals for information only will not be returned. However, the Government reserves the right to return unsatisfactory submittals and require the Contractor to resubmit any item found not to comply with the contract.

This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.8 PROJECT SUBMITTAL REGISTER

A sample Project Submittal Register showing items of equipment and materials for when submittals are required by the specifications is provided as "Attachment A - Submittal Register."

1.8.1 Submittal Management

Prepare and maintain a submittal register, as the work progresses. Do not change data that is output in columns (c), (d), (e), and (f) as delivered by Government; retain data that is output in columns (a), (g), (h), and (i) as approved. As an attachment, provide a submittal register showing items of equipment and materials for which submittals are required by the specifications. This list may not be all-inclusive and additional submittals may be required.

Column (c): Lists specification section in which submittal is required.

Column (d): Lists each submittal description (SD Number. and type, e.g., SD-02 Shop Drawings) required in each specification section.

Column (e): Lists one principal paragraph in each specification section where a material or product is specified. This listing is only to facilitate locating submitted requirements. Do not consider entries in column (e) as limiting the project requirements.

Column (f): Lists the approving authority for each submittal.

Thereafter, the Contractor is to track all submittals by maintaining a complete list, including completion of all data columns and all dates on which submittals are received by and returned by the Government.

1.8.2 Preconstruction Use of Submittal Register

Submit the submittal register. Include the QC plan and the project schedule. Verify that all submittals required for the project are listed and add missing submittals. Coordinate and complete the following fields on the register submitted with the QC plan and the project schedule:

Column (a) Activity Number: Activity number from the project schedule.

Column (g) Contractor Submit Date: Scheduled date for the approving authority to receive submittals.

Column (h) Contractor Approval Date: Date that Contractor needs approval of submittal.

Column (i) Contractor Material: Date that Contractor needs

material delivered to Contractor control.

1.8.3 Contractor Use of Submittal Register

Update the following fields with each submittal throughout the contract.

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (j) Action Code (k): Date of action used to record Contractor's review when forwarding submittals to QC.

Column (l) Date submittal transmitted.

Column (q) Date approval was received.

1.8.4 Approving Authority Use of Submittal Register

Update the following fields:

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (l) Date submittal was received.

Column (m) through (p) Dates of review actions.

Column (q) Date of return to Contractor.

1.8.5 Action Codes

1.8.5.1 Government Review Action Codes

"A" - "Approved as submitted"

"AN" - "Approved as noted"

"RR" - "Disapproved as submitted"; "Completed"

"NR" - "Not Reviewed"

"RA" - "Receipt Acknowledged"

1.8.6 Delivery of Copies

Submit an updated electronic copy of the submittal register to the Contracting Officer with each invoice request. Provide an updated Submittal Register monthly regardless of whether an invoice is submitted.

1.9 VARIATIONS

Variations from contract requirements require Contracting Officer approval pursuant to contract Clause FAR 52.236-21 Specifications and Drawings for Construction, and will be considered where advantageous to the Government.

1.9.1 Considering Variations

Discussion of variations with the Contracting Officer before submission of a variation submittal will help ensure that functional and quality

requirements are met and minimize rejections and resubmittals. For variations that include design changes or some material or product substitutions, the Government may require an evaluation and analysis by a licensed professional engineer hired by the contractor.

Specifically point out variations from contract requirements in a variation submittal. Failure to point out variations may cause the Government to require rejection and removal of such work at no additional cost to the Government.

1.9.2 Warranting that Variations are Compatible

When delivering a variation for approval, the Contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.9.3 Review Schedule Extension

In addition to the normal submittal review period, a period of 14 working days will be allowed for the Government to consider submittals with variations.

1.10 SCHEDULING

Schedule and submit concurrently product data and shop drawings covering component items forming a system or items that are interrelated. Submit pertinent certifications at the same time. No delay damages or time extensions will be allowed for time lost in late submittals. Allow an additional 10 working days for review and approval of submittals for refrigeration and HVAC control systems.

a. Coordinate scheduling, sequencing, preparing, and processing of submittals with performance of work so that work will not be delayed by submittal processing. The Contractor is responsible for additional time required for Government reviews resulting from required resubmittals. The review period for each resubmittal is the same as for the initial submittal.

b. Submittals required by the contract documents are listed on the submittal register. If a submittal is listed in the submittal register but does not pertain to the contract work, the Contractor is to include the submittal in the register and annotate it "N/A" with a brief explanation. Approval by the Contracting Officer does not relieve the Contractor of supplying submittals required by the contract documents but that have been omitted from the register or marked "N/A."

c. Resubmit the submittal register and annotate it monthly with actual submission and approval dates. When all items on the register have been fully approved, no further resubmittal is required.

Contracting Officer review will be completed within 20 working days after the date of submission.

d. Except as specified otherwise, allow a review period, beginning with receipt by the approving authority, that includes at least 20 working days for submittals for QC manager approval and 20 working days for submittals where the Contracting Officer is the approving authority. The period of review for submittals with Contracting Officer approval

begins when the Government receives the submittal from the QC organization.

e. For submittals requiring review by a Government fire protection engineer, allow a review period, beginning when the Government receives the submittal from the QC organization, of 30 working days for return of the submittal to the Contractor.

1.10.1 Reviewing, Certifying, and Approving Authority

The QC Manager is responsible for reviewing all submittals and certifying that they are in compliance with contract requirements. The approving authority on submittals is the QC Manager unless otherwise specified. At each "Submittal" paragraph in individual specification sections, a notation "G" following a submittal item indicates that the Contracting Officer is the approving authority for that submittal item. Provide an additional copy of the submittal to the Government Approving authority

1.10.2 Constraints

Conform to provisions of this section, unless explicitly stated otherwise for submittals listed or specified in this contract.

Submit complete submittals for each definable feature of the work. At the same time, submit components of definable features that are interrelated as a system.

When acceptability of a submittal is dependent on conditions, items, or materials included in separate subsequent submittals, the submittal will be returned without review.

Approval of a separate material, product, or component does not imply approval of the assembly in which the item functions.

1.10.3 QC Organization Responsibilities

a. Review submittals for conformance with project design concepts and compliance with contract documents.

b. Process submittals based on the approving authority indicated in the submittal register.

(1) When the QC manager is the approving authority, take appropriate action on the submittal from the possible actions defined in paragraph APPROVED SUBMITTALS.

(2) When the Contracting Officer is the approving authority or when variation has been proposed, forward the submittal to the Government, along with a certifying statement, or return the submittal marked "not reviewed" or "revise and resubmit" as appropriate. The QC organization's review of the submittal determines the appropriate action.

c. Ensure that material is clearly legible.

d. Stamp each sheet of each submittal with a QC certifying statement or an approving statement, except that data submitted in a bound volume or on one sheet printed on two sides may be stamped on the front of the first sheet only.

(1) When the approving authority is the Contracting Officer, the QC organization will certify submittals forwarded to the Contracting Officer with the following certifying statement:

"I hereby certify that the (equipment) (material) (article) shown and marked in this submittal is that proposed to be incorporated with Contract Number ( ) is in compliance with the contract drawings and specification, can be installed in the allocated spaces, and is submitted for Government approval.

Certified by Submittal Reviewer _____, Date _____
(Signature when applicable)

Certified by QC Manager _____, Date _____"
(Signature)

(2) When approving authority is the QC manager, the QC manager will use the following approval statement when returning submittals to the Contractor as "Approved" or "Approved as Noted."

"I hereby certify that the (material) (equipment) (article) shown and marked in this submittal and proposed to be incorporated with Contract Number ( ) is in compliance with the contract drawings and specification, can be installed in the allocated spaces, and is approved for use.

Certified by Submittal Reviewer _____, Date _____
(Signature when applicable)

Approved by QC Manager _____, Date _____"
(Signature)

e. Sign the certifying statement or approval statement. The QC organization member designated in the approved QC plan is the person signing certifying statements. The use of original ink for signatures is required. Stamped signatures are not acceptable.

f. Update the submittal register as submittal actions occur, and maintain the submittal register at the project site until final acceptance of all work by the Contracting Officer.

g. Retain a copy of approved submittals and approved samples at the project site.

h. For "S" submittals, provide a copy of the approved submittal to the Government Approving authority.

1.11 GOVERNMENT APPROVING AUTHORITY

When the approving authority is the Contracting Officer, the Government will:

a. Note the date on which the submittal was received from the QC manager.

b. Review submittals for approval within the scheduling period specified and only for conformance with project design concepts and compliance with contract documents.

c. Identify returned submittals with one of the actions defined in

paragraph REVIEW NOTATIONS and with comments and markings appropriate for the action indicated.

Upon completion of review of submittals requiring Government approval, stamp and date submittals. Three copies of the submittal will be retained by the Contracting Officer and Four copies of the submittal will be returned to the Contractor.

1.11.1 Review Notations

Submittals will be returned to the Contractor with the following notations:

a. Submittals marked "approved" or "accepted" authorize proceeding with the work covered.

b. Submittals marked "approved as noted" or "approved, except as noted, resubmittal not required," authorize proceeding with the work covered provided that the Contractor takes no exception to the corrections.

c. Submittals marked "not approved," "disapproved," or "revise and resubmit" indicate incomplete submittal or noncompliance with the contract requirements or design concept. Resubmit with appropriate changes. Do not proceed with work for this item until the resubmittal is approved.

d. Submittals marked "not reviewed" indicate that the submittal has been previously reviewed and approved, is not required, does not have evidence of being reviewed and approved by Contractor, or is not complete. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed. Resubmit submittals returned for lack of review by Contractor or for being incomplete, with appropriate action, coordination, or change.

e. Submittals marked "receipt acknowledged" indicate that submittals have been received by the Government. This applies only to "information-only submittals" as previously defined.

1.12 DISAPPROVED SUBMITTALS

Make corrections required by the Contracting Officer. If the Contractor considers any correction or notation on the returned submittals to constitute a change to the contract drawings or specifications, give notice to the Contracting Officer as required under the FAR clause titled CHANGES. The Contractor is responsible for the dimensions and design of connection details and the construction of work. Failure to point out variations may cause the Government to require rejection and removal of such work at the Contractor's expense.

If changes are necessary to submittals, make such revisions and resubmit in accordance with the procedures above. No item of work requiring a submittal change is to be accomplished until the changed submittals are approved.

1.13 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals is not to be construed as a complete check, and indicates only that

Approval or acceptance by the Government for a submittal does not relieve

the Contractor of the responsibility for meeting the contract requirements or for any error that may exist, because under the Quality Control (QC) requirements of this contract, the Contractor is responsible for ensuring information contained with in each submittal accurately conforms with the requirements of the contract documents.

After submittals have been approved or accepted by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.14 APPROVED SAMPLES

Approval of a sample is only for the characteristics or use named in such approval and is not be construed to change or modify any contract requirements. Before submitting samples, provide assurance that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

Match the approved samples for materials and equipment incorporated in the work. If requested, approved samples, including those that may be damaged in testing, will be returned to the Contractor, at its expense, upon completion of the contract. Unapproved samples will also be returned to the Contractor at its expense, if so requested.

Failure of any materials to pass the specified tests will be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make as that material. The Government reserves the right to disapprove any material or equipment that has previously proved unsatisfactory in service.

Samples of various materials or equipment delivered on the site or in place may be taken by the Contracting Officer for testing. Samples failing to meet contract requirements will automatically void previous approvals. Replace such materials or equipment to meet contract requirements.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		01 14 00	SD-01 Preconstruction Submittals																
			List of Contact Personnel	1.3.1.1															
		01 20 00	SD-01 Preconstruction Submittals																
			Earned Value Report	1.3	G														
		01 30 00	SD-01 Preconstruction Submittals																
			View Location Map	1.3															
			Progress and Completion	1.4															
			Pictures																
		01 30 02.00 22	SD-02 Shop Drawings																
			Preliminary (Pre-Final) AV	1.5.3	G														
			Package																
			G, DC44																
			Final AV Package	1.5.9	G														
			Best Value Determination	1.6	G														
			SD-07 Certificates																
			Contractor's AV Designer's	1.4.1	G														
			Qualifications																
			G, DC44																
		01 31 23.13 20	SD-01 Preconstruction Submittals																
			List of Contractor's Personnel	1.4.2	G														
		01 32 17.00 20	SD-01 Preconstruction Submittals																
			Baseline NAS	1.2.2	G														
			Designated Project Scheduler	1.9	G														
			SD-07 Certificates																
			Weekly Look Ahead Schedule	1.3															
			Monthly NAS Updates	1.4.2	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY						
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 32 17.00 20	SD-11 Closeout Submittals															
			As-Built NAS	1.4.3	G													
		01 33 00	SD-01 Preconstruction Submittals															
			Submittal Register	1.8	G													
		01 33 29	SD-01 Preconstruction Submittals															
			Preliminary High Performance	1.5.3.2	G													
			and Sustainable Building Checklist															
			Sustainability Action Plan	1.4.1	G													
			Preliminary Sustainability	1.5.3.2	G													
			eNotebook															
			SD-11 Closeout Submittals															
			Final High Performance and	1.5.3.2	G													
			Sustainable Building Checklist															
			Final Sustainability eNotebook	1.5.3.2	G													
			Amended Final Sustainability	1.5.3.2	G													
			eNotebook															
			Amended Final High	1.5.3.2	G													
			Performance and Sustainable															
			Building Checklist															
		01 35 26	SD-01 Preconstruction Submittals															
			Accident Prevention Plan (APP)	1.9.1	G													
			Final IAQ Management Plan	1.17	S													
			Indoor Air Quality (IAQ)	1.17	G													
			Management Plan															
			SD-06 Test Reports															
			Accident Reports	1.13.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 35 26	LHE Inspection Reports	1.13.3														
			Monthly Exposure Reports	1.5	G													
			SD-07 Certificates															
			Activity Hazard Analysis (AHA)	1.10	G													
			Certificate of Compliance	1.13.4														
			Contractor Safety Self-Evaluation Checklist	1.6														
			Hot Work Permit	1.14														
			License Certificates	1.15														
			Portable Gauge Operations Planning Worksheet	1.15.1	G													
			Radiography Operation Planning Work Sheet	1.15.1	G													
			Standard Lift Plan	1.13.4.2	G													
			Critical Lift Plan	1.13.4.2	G													
		01 35 29.13	SD-02 Shop Drawings															
			Work Zones	3.9.1	G													
			Decontamination Facilities	3.10.1	G													
			SD-03 Product Data															
			Amendments to the APP/SSHP	1.4	G													
			Exposure Monitoring/Air Sampling Program	3.5														
			Site Control Log	3.9.2														
			SSHO's Daily Inspection Logs	1.8														
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 35 29.13	Certificate Of Worker/Visitor Acknowledgement	1.7														
			SD-11 Closeout Submittals															
			Safety And Health Phase-Out Report	1.9	G													
		01 45 00	SD-01 Preconstruction Submittals															
			Contractor Quality Control (CQC) Plan	1.5.2	G													
			SD-06 Test Reports															
			Verification Statement	1.13.3														
			SD-07 Certificates															
			Certificate Of Readiness	1.6.5.1	G													
		01 45 35	SD-01 Preconstruction Submittals															
			Written NDT Practices	3.1.2														
			SD-06 Test Reports															
			Daily Reports	3.1.2														
			Biweekly Reports	3.1.1														
			SD-07 Certificates															
			AISC Certified Steel Fabricator	2.1														
			Steel Joist Institute Membership	2.1														
			Certificate of Compliance	2.1														
			Special Inspector	1.5	G													
			Qualification Records	3.1.2														
			SD-11 Closeout Submittals															
			Interim Report	3.1.2	G													
			Comprehensive Final Report	3.1.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 50 00	SD-01 Preconstruction Submittals															
			Traffic Control Plan	3.4.1														
			SD-03 Product Data															
			Backflow Preventers	1.3														
			SD-06 Test Reports															
			Backflow Preventer Tests	3.5														
			SD-07 Certificates															
			Backflow Tester	1.3.1														
			Backflow Preventers	1.3														
		01 57 19	SD-01 Preconstruction Submittals															
			Preconstruction Survey	1.6.1														
			Regulatory Notifications	1.6.2	G													
			Environmental Manager	1.6.4	G													
			Qualifications															
			Employee Training Records	1.6.5	G													
			Environmental Protection Plan	1.7	G													
			Dirt and Dust Control Plan	1.7.9.1	G													
			Solid Waste Management Permit	1.10	G													
			Stormwater Notice of Intent	3.2.1.2	G													
			Spill Prevention Control And	3.14.2	G													
			Countermeasure (SPCC) Plan															
			SD-06 Test Reports															
			Monthly Solid Waste Disposal	1.10.1	G													
			Report															
			Inspection Reports	3.2.1.3														
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY						
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		01 57 19	ECATTS Certificate Of Completion	1.4.1.2	G													
			Employee Training Records	1.6.5	G													
			Erosion and Sediment Control Inspector	1.6.5														
			SD-11 Closeout Submittals															
			Regulatory Notifications	1.6.2	G													
			Assembled Employee Training Records	1.6.5	G													
			Solid Waste Management Permit	1.10	G													
			Stormwater Notice of Termination	3.2.1.5	G													
			Waste Determination Documentation	3.7.1	G													
			Project Solid Waste Disposal Documentation Report	3.7.2.1	G													
			Sales Documentation	3.7.2.1	G													
			Hazardous Waste/Debris Management	3.7.3.1	G													
			Disposal Documentation for Hazardous and Regulated Waste	3.7.3.3	G													
			Contractor Hazardous Material Inventory Log	3.8.1	G													
		01 58 00	SD-02 Shop Drawings															
			Preliminary Drawing Indicating Layout And Text Content	1.4.1	G													
			SD-04 Samples															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		01 58 00	Facility Recognition Plaque	1.3.1	G														
		01 74 19	SD-01 Preconstruction Submittals																
			Construction Waste Management	1.6	G														
			Plan																
			SD-11 Closeout Submittals																
			Final Construction Waste	1.8	S														
			Diversion Report																
		01 78 00	SD-03 Product Data																
			Warranty Management Plan	1.6.1															
			Warranty Tags	1.6.4															
			Final Cleaning	3.5															
			Spare Parts Data	1.5															
			SD-08 Manufacturer’s Instructions																
			Instructions	1.6.1															
			SD-10 Operation and Maintenance																
			Data																
			Operation and Maintenance	3.4	G														
			Manuals																
			SD-11 Closeout Submittals																
			As-Built Drawings	3.2	G														
			Record Drawings	3.3	G														
			As-Built Record of Equipment	1.6.1															
			and Materials																
			Final Approved Shop Drawings	3.7															
			Certification of EPA Designated	2.1	G														
			Items																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		01 78 00	Certification Of USDA Designated	2.2	G														
			Items																
			Interim DD FORM 1354	3.6.2	G														
			Equipment Inventory Update	3.1	G														
			As-Built Exterior Finish Material	1.7	G														
			Schedule And Submittals																
		01 78 23	SD-10 Operation and Maintenance																
			Data																
			Training Plan	3.1.1	G														
			Training Outline	3.1.3	G														
			Training Content	3.1.2	G														
			SD-11 Closeout Submittals																
			Training Video Recording	3.1.4	G														
			Validation of Training Completion	3.1.6	G														
		01 78 24.00 20	SD-11 Closeout Submittals																
			eOMSI, Progress Submittal	1.4.1	G														
			eOMSI, Prefinal Submittal	1.4.2	G														
			eOMSI, Final Submittal	1.4.3	G														
		01 78 30.00 22	SD-11 Closeout Submittals																
			GIS Data Deliverables	1.3.9	G														
		01 91 19	SD-01 Preconstruction Submittals																
			Building Enclosure	1.12.2.1	G														
			Commissioning Specialist																
			Qualifications																
			Building Enclosure Testing Work	1.8	G														
			Plan																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		01 91 19	SD-03 Product Data																
			Thermal Imaging Camera	2.3	G														
			Test Equipment	2.1	G														
			SD-05 Design Data																
			Envelope Surface Area	3.8.2	G														
			Calculations																
			SD-06 Test Reports																
			Pressure Test Procedures	3.8.5	G														
			Air Leakage Test Report	1.12.3	G														
			Air Leakage Test Report	3.8.5.8	G														
			Diagnostic Test Report	1.12.3	G														
			Diagnostic Test Report	3.8.6.6	G														
			SD-07 Certificates																
			Pressure Test Agency	1.12.2.2															
			Thermographer Qualifications	1.12.2.3															
			Certificate of Readiness	1.14															
			SD-10 Operation and Maintenance																
			Data																
			Training	3.9	G														
		02 41 00	SD-01 Preconstruction Submittals																
			Demolition Plan	1.2.2	G														
			Existing Conditions	1.11															
			SD-07 Certificates																
			Notification	1.7	G														
		03 30 00	SD-01 Preconstruction Submittals																
			Quality Control Plan	1.6.5	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		03 30 00	Quality Control Personnel	1.6.6	G													
			Certifications															
			Quality Control Organizational	1.6.6														
			Chart															
			Laboratory Accreditation	1.6.8	G													
			Maturity Method Data	3.3.10														
			SD-02 Shop Drawings															
			Reinforcing Steel	1.6.2.1														
			SD-03 Product Data															
			Joint Sealants	2.4.5														
			Joint Filler	2.4.4														
			Formwork Materials	2.1														
			Recycled Aggregate Materials	2.3.3.2														
			Cementitious Materials	2.3.1														
			Vapor Barrier	2.4.6														
			Concrete Curing Materials	2.4.1														
			Reinforcement	2.6														
			Liquid Chemical Floor Hardeners	2.4.3.1														
			and Sealers															
			Admixtures	2.3.4														
			Mechanical Reinforcing Bar	2.6.2														
			Connectors															
			Waterstops	2.2.2														
			Biodegradable Form Release	2.2.3														
			Agent															
			Nonshrink Grout	2.4.2														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		03 30 00	SD-05 Design Data																
			Concrete Mix Design	1.6.1.1	G														
			SD-06 Test Reports																
			Concrete Mix Design	1.6.1.1	G														
			Fly Ash	1.6.3.1															
			Pozzolan	1.6.3.1															
			Slag Cement	1.6.3.2															
			Aggregates	1.6.3.3															
			Tolerance Report	3.10.2.1															
			Compressive Strength Tests	3.14.3.3	G														
			Unit Weight of Structural	3.14.3.5															
			Concrete																
			Air Content	3.14.3.4															
			Slump Tests	3.14.3.1															
			Water	2.3.2															
			SD-07 Certificates																
			Reinforcing Bars	2.6.1															
			Welder Qualifications	1.8															
			Field Testing Technician and	1.6.6.2															
			Testing Agency																
			SD-08 Manufacturer’s Instructions																
			Joint Sealants	2.4.5															
			Curing Compound	2.4.1															
		04 20 00	SD-02 Shop Drawings																
			Detail Drawings	3.4.1.1	G														
			SD-03 Product Data																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		04 20 00	Hot Weather Procedures	1.5.1	G													
			Cold Weather Procedures	1.5.2	G													
			Clay or Shale Brick	2.2.2	G													
			Cementitious Materials	2.4.1.1	G													
			SD-04 Samples															
			Mock-Up Panel	1.3.1.1	G													
			Clay or Shale Brick	2.2.2	G													
			Concrete Masonry Units (CMU)	2.2.3.2	G													
			Admixtures for Masonry Mortar	2.4.1.3	G													
			Anchors, Ties, and Bar	2.6.2	G													
			Positioners															
			Joint Reinforcement	2.6.3	G													
			Clay Masonry Expansion-Joint	2.6.5	G													
			Materials															
			SD-05 Design Data															
			Masonry Compressive Strength	2.1.2	G													
			Fire-Rated Concrete Masonry	2.2.3.4														
			Units															
			Bracing Calculations	3.2.4	G													
			SD-06 Test Reports															
			Efflorescence Test	2.2.2.1.4														
			Fire-Rated Concrete Masonry	2.2.3.4														
			Units															
			Field Testing of Grout	3.6.1.1														
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		04 20 00	Special Masonry Inspector	1.3.2															
			Qualifications																
			Clay or Shale Brick	2.2.2															
			Concrete Masonry Units (CMU)	2.2.3.2															
			Cementitious Materials	2.4.1.1															
			Admixtures for Masonry Mortar	2.4.1.3															
			Admixtures for Grout	2.4.2.2															
			Anchors, Ties, and Bar	2.6.2															
			Positioners																
			Joint Reinforcement	2.6.3															
			Insulation	2.6.7															
			SD-08 Manufacturer's Instructions																
			Admixtures for Masonry Mortar	2.4.1.3															
			Admixtures for Grout	2.4.2.2															
			SD-10 Operation and Maintenance																
			Data																
			Take-Back Program	3.8															
			SD-11 Closeout Submittals																
			Clay Units	2.2.2.1.3	S														
			Recycled Content	2.2.3.2.1	S														
		04 73 00	SD-03 Product Data																
			CAST STONE	2.1	G														
			SD-04 Samples																
			CAST STONE	2.1	G														
			SD-05 Design Data																
			CAST STONE	2.1	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		04 73 00	SD-10 Operation and Maintenance																
			Data																
			MAINTENANCE	3.2	G														
		05 12 00	SD-01 Preconstruction Submittals																
			Erection and Erection Bracing	1.3.1.1	G														
			Drawings																
			SD-02 Shop Drawings																
			Fabrication Drawings	1.3.2	G														
			SD-03 Product Data																
			Shop Primer	2.6.2															
			Welding Electrodes and Rods	2.4.1															
			Direct Tension Indicator Washers	2.3.2.3															
			Non-Shrink Grout	2.4.2															
			Tension Control Bolts	2.3.3															
			Recycled Content for Structural	2.2.1	S														
			Steel																
			Recycled Content for Structural	2.2.2	S														
			Steel Tubing																
			Recycled Content for Steel Pipe	2.2.3	S														
			SD-05 Design Data																
			Design Calculations for Steel	1.3.3	G														
			Connections																
			SD-06 Test Reports																
			Class B Coating	2.6.2															
			Bolts, Nuts, and Washers	2.3															
			Weld Inspection Reports	3.7.1.2															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		05 12 00	Direct Tension Indicator Washer	3.7.2.1															
			Inspection Reports																
			Bolt Testing Reports	3.7.3.1															
			Embrittlement Test Reports	3.7.4															
			SD-07 Certificates																
			Steel	2.2															
			Bolts, Nuts, and Washers	2.3															
			Galvanizing	2.5															
			Welding Procedures and	1.3.4.1															
			Qualifications																
			Welding Electrodes and Rods	2.4.1															
			Certified Welding Inspector	3.7.1.1															
			NDT Technician	3.7.1.2															
			Welding Procedure Specifications	3.4															
			(WPS)																
		05 21 00	SD-01 Preconstruction Submittals																
			Welder Qualification	1.3.2															
			SD-02 Shop Drawings																
			Steel Joist Framing	1.3.1	G														
			SD-03 Product Data																
			Recycled Content Of Steel	2.3	S														
			Products																
			SD-05 Design Data																
			Design Calculations	2.2	G														
			SD-06 Test Reports																
			Erection Inspection	3.4															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		05 21 00	Welding Inspections	3.4															
			SD-07 Certificates																
			Certification of Compliance	1.3.2															
		05 30 00	SD-02 Shop Drawings																
			Fabrication Drawings	1.3.5	G														
			SD-03 Product Data																
			Accessories	2.2															
			Deck Units	2.1															
			Galvanizing Repair Paint	2.1.4															
			Mechanical Fasteners	2.2.14															
			Touch-Up Paint	2.1.4															
			Welding Equipment	1.3.3															
			Welding Rods and Accessories	1.3.3															
			Recycled Content of Steel Products	2.1	S														
			SD-04 Samples																
			Metal Roof Deck Units	2.1.1															
			Flexible Closure Strips	2.2.4															
			SD-05 Design Data																
			Deck Units	2.1	G														
			SD-07 Certificates																
			Powder-Actuated Tool Operator	1.3.2															
			Welder Qualifications	1.3.3															
			Welding Procedures	1.3.3															
			Fire Safety	1.3.4.1															
			Wind Storm Resistance	1.3.4.2															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		05 30 00	Manufacturer's Certificate	1.3.1															
		05 40 00	SD-02 Shop Drawings																
			Framing Components	1.6.1	G														
			SD-03 Product Data																
			Studs, Joists	2.1															
			Recycled Content of Steel	2.1															
			Products																
			SD-05 Design Data																
			Metal Framing Calculations	1.6.2	G														
			SD-07 Certificates																
			Load-Bearing Cold-Formed Metal	1.4															
			Framing																
			Welds	3.2.1															
		05 50 13	SD-02 Shop Drawings																
			Bollards/Pipe Guards	2.4															
			Downspout Terminations	2.5	G														
			Recycled Content	2.1	S														
		06 41 16.00 10	SD-02 Shop Drawings																
			Shop Drawings	2.7															
			Installation	3.1															
			SD-03 Product Data																
			Wood Materials	2.1															
			Finish Schedule	2.7.7.3															
			SD-04 Samples																
			Plastic Laminates	2.2															
			Cabinet Hardware	2.4															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		06 41 16.00 10	SD-07 Certificates																
			Quality Assurance	1.5															
			Laminate Clad Casework	3.1															
			Certification	1.5.2															
		06 61 16	SD-02 Shop Drawings																
			Detail Fabrication Drawings	2.1	G														
			Installation	3.1	G														
			Shower Wall Panel And Pan	2.3.7															
			System																
			Shower Wall Panel And Pan	2.3.7															
			System																
			SD-03 Product Data																
			Solid Polymer	2.1.1	G														
			Indoor air quality for solid surface	2.2.2	S														
			seam and sealant products																
			Shower Wall Panel And Pan	2.3.7															
			System																
			Shower Wall Panel And Pan	2.3.7															
			System																
			SD-04 Samples																
			Material	2.1	G														
			Counter Tops	2.3.5	G														
			SD-06 Test Reports																
			Test Report Results	2.1.1															
			SD-07 Certificates																
			Qualifications	1.4.1															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		06 61 16	Indoor Air Quality for solid	2.1.1	S														
			surface fabrication products																
			SD-10 Operation and Maintenance																
			Data																
			Solid Polymer	2.1.1	G														
		06 82 14	SD-01 Preconstruction Submittals																
			Qualifications of Manufacturer	1.3.1	G														
			SD-02 Shop Drawings																
			Installation Drawings	2.1.1	G														
			SD-03 Product Data																
			Anchorage Materials	2.1.2	G														
			Adhesives	2.1.2	G														
			Resins	2.1.2	G														
			Hardeners	2.1.2	G														
			Manufacturer's Sample Warranty	1.3.1															
			FRP Wall Paneling	2.1.2															
			SD-06 Test Reports																
			Ultraviolet Test Reports	2.1.3															
			Thermal Expansion Test Reports	2.1.3															
			Flame Spread Test Reports	2.1.3															
			SD-08 Manufacturer’s Instructions																
			Manufacturer's Instructions	3.2.2															
			SD-09 Manufacturer’s Field																
			Reports																
			Manufacturer's Certification of	3.1															
			Installation																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		06 82 14	SD-11 Closeout Submittals																
			Manufacturer's Warranty	3.2.1															
		07 21 13	SD-02 Shop Drawings																
			Manufacturer's Standard Details	1.3	G														
			SD-03 Product Data																
			Environmental Data for Materials	1.4	G														
			Block or Board Insulation	2.1	G														
			Vapor Retarder	2.2	G														
			Pressure Sensitive Tape	2.3	G														
			Accessories	2.4	G														
			Recycled Content for Block or	2.1.4	S														
			Board Insulation																
			SD-07 Certificates																
			Indoor Air Quality For Block Or	2.1.5	S														
			Board Insulation																
			SD-08 Manufacturer’s Instructions																
			Insulation Installation and	3.3.1															
			Handling																
			Adhesive	2.4.1															
			SD-11 Closeout Submittals																
			Draft Guarantee	1.7.1	G														
			Final Guarantee	1.7.1	G														
			Draft Warranty	1.7.2	G														
			Final Warranty	1.7.2	G														
		07 21 16	SD-03 Product Data																
			Blanket Insulation	2.1															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		07 21 16	Blanket Insulation	2.2															
			Recycled Content for Insulation	2.1.2	S														
			Materials																
			Accessories	2.3															
			SD-07 Certificates																
			Indoor Air Quality for Insulation	2.1.4	S														
			Materials																
			SD-08 Manufacturer’s Instructions																
			Insulation	3.1.1															
		07 27 10.00 10	SD-02 Shop Drawings																
			Air Barrier System Shop	2.1	G														
			Drawings																
			SD-03 Product Data																
			Air Barrier System Product Data	2.1	G														
			SD-04 Samples																
			Material Samples For Air Barrier	2.1	G														
			System																
			SD-05 Design Data																
			Design Data And Calculations	1.8	G														
			For The Air Barrier System																
			SD-06 Test Reports																
			Design Review Report	1.8	G														
			Testing and Inspection	3.1.2	G														
			SD-07 Certificates																
			Air Barrier Inspector	1.7	G														
		07 27 26	SD-01 Preconstruction Submittals																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 27 26	Qualifications of Manufacturer	1.9.1	G													
			Qualifications of Installer	1.9.2	G													
			SD-02 Shop Drawings															
			Fluid-Applied Membrane Air	1.4.1	G													
			Barrier Shop Drawings															
			SD-03 Product Data															
			Fluid-Applied Membrane Air	1.4	G													
			Barrier															
			Transition Membrane	2.3	G													
			Primers, Adhesives, and Mastics	2.2	G													
			Reinforcement	2.6	G													
			Safety Data Sheets	1.4.2	G													
			SD-06 Test Reports															
			Capillary Moisture Test	1.6	G													
			Field Peel Adhesion Test	1.4.3	G													
			Flame Propagation of Wall	1.4.3	G													
			Assemblies															
			Site Inspections	3.4.1	G													
			SD-08 Manufacturer’s Instructions															
			Fluid-Applied Membrane Air	1.4.2	G													
			Barrier Manufacturer's Printed															
			Instructions															
			Primers, Adhesives, and Mastics	1.4.2	G													
			Printed Manufacturer's Instructions															
		07 42 13	SD-01 Preconstruction Submittals															
			Qualification of Manufacturer	1.5.3	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		07 42 13	Qualification of Installation	1.5.4	G														
			Contractor																
			Warranty	1.8	G														
			SD-02 Shop Drawings																
			Installation Drawings	1.5.1.1	G														
			SD-03 Product Data																
			Recycled Content;	2.1															
			Wall Panels	2.2.1	G														
			Factory Color Finish	2.2.2	G														
			Closure Materials	1.5.5															
			Pressure Sensitive Tape	2.5.4.4															
			Sealants and Caulking	2.5.4.1															
			Galvanizing Repair Paint	1.5.3.1															
			Enamel Repair Paint	1.5.3.1															
			Accessories	1.5.5															
			Accessories	2.5															
			SD-04 Samples																
			Wall Panels	2.2.1	G														
			Fasteners	1.5.3.1															
			Metal Closure Strips	2.5.3															
			SD-05 Design Data																
			Wind load design analysis	1.5.1.2	G														
			SD-06 Test Reports																
			Leakage Tests	3.7.2	G														
			Wind Load Tests	1.3.2	G														
			Coating	2.2.2.6	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		07 42 13	Chalking	2.2.2.6	G														
			SD-07 Certificates																
			Coil Stock	1.5.3.1															
			Fasteners	1.5.3.1															
			Galvanizing Repair Paint	1.5.3.1															
			Enamel Repair Paint	1.5.3.1															
			SD-08 Manufacturer’s Instructions																
			Installation	3.3	G														
			SD-09 Manufacturer’s Field																
			Reports																
			Manufacturer's Field Reports	3.8.1															
			SD-11 Closeout Submittals																
			Warranty	1.8	G														
			Maintenance Instructions	1.5.6	G														
			20 year 'No Dollar Limit' warranty	1.8.1															
			for labor and material																
		07 60 00	SD-02 Shop Drawings																
			Exposed Sheet Metal	2.2.1															
			Gutters	3.1.15	G														
			Downspouts	3.1.16	G														
			Drip Edges	3.1.14	G														
			Recycled Content	2.1	S														
			SD-04 Samples																
			Finish Samples	1.4.2															
			SD-08 Manufacturer’s Instructions																
			Instructions for Installation	1.4.3															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		07 60 00	Quality Control Plan	3.5														
			SD-10 Operation and Maintenance															
			Data															
			Cleaning and Maintenance	1.4.3														
		07 84 00	SD-02 Shop Drawings															
			Firestopping System	2.1	G													
			SD-03 Product Data															
			Firestopping Materials	2.2	G													
			SD-06 Test Reports															
			Inspection	3.3	G													
			SD-07 Certificates															
			Inspector Qualifications	1.5.2	G													
			Firestopping Materials	2.2														
			Installer Qualifications	1.5.1	G													
		07 92 00	SD-03 Product Data															
			Sealants	2.1	G													
			Primers	2.2	G													
			Bond Breakers	2.3	G													
			Backstops	2.4	G													
			Field Adhesion	3.1	G													
			SD-07 Certificates															
			Indoor Air Quality For Interior	2.1.1	S													
			Sealants															
			Indoor Air Quality For Interior	2.1.3	S													
			Floor Joint Sealants															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		07 92 00	Indoor Air Quality For Interior	2.1.4	S														
			Acoustical Sealants																
		08 11 13	SD-02 Shop Drawings																
			Doors	2.1	G														
			Doors	2.1	G														
			Frames	2.4	G														
			Frames	2.4	G														
			Accessories	2.2															
			SD-03 Product Data																
			Doors	2.1	G														
			Recycled Content for Steel Door	2.1	S														
			Product																
			Frames	2.4	G														
			Recycled Content for Steel Frame	2.4	S														
			Product																
			Accessories	2.2															
		08 11 16	SD-02 Shop Drawings																
			Door and Frame Assembly	1.5.1	G														
			SD-03 Product Data																
			Door and Frame Assembly	1.5.1	G														
			Recycled Content of Aluminum	2.2.3	S														
			Material																
			SD-04 Samples																
			Finish Samples	1.5.2	G														
			SD-05 Design Data																
			Calculations	1.2.1	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		08 11 16	Air Infiltration	1.2.3	G													
			Water Penetration	1.2.4	G													
			NFRC Project Label Certificates	1.2.5	G													
			for Fenestration															
			SD-08 Manufacturer's Instructions															
			Door and Frame Assembly	1.5.1	G													
			Adjustments, Cleaning, and	1.5.3	G													
			Maintenance															
			NFRC Project Label Certificates	1.2.5	G													
			for Fenestration															
		08 14 00	SD-02 Shop Drawings															
			Doors	2.1	G													
			SD-03 Product Data															
			Doors	2.1	G													
			Recycled Content for Door Cores	2.1.1.1	S													
			Accessories	2.2														
			Water-resistant Sealer	2.3.5														
			Warranty	1.5														
			Sound Transmission Class	2.1.2	G													
			Rating															
			Fire Resistance Rating	2.1.3	G													
			SD-04 Samples															
			Door Finish Color	2.3.4.1	G													
			SD-06 Test Reports															
			Cycle-Slam	2.4														
			Hinge Loading Resistance	2.4														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY						
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		08 14 00	SD-07 Certificates															
			Certificates of Grade	1.3.1														
			Certified Sustainably Harvested	2.1.1	S													
			Flush Wood Doors															
			Indoor Air Quality for	2.1.1.1	S													
			Particleboard and Agrifiber Door															
			Cores															
			SD-11 Closeout Submittals															
			Warranty	1.5														
		08 31 00	SD-02 Shop Drawings															
			Access Doors And Panels	1.3	G													
			SD-03 Product Data															
			Access Doors And Panels	1.3	G													
			Hardware	1.3.2	G													
			Accessories	2.2.8	G													
			Recycled Content	2.1	S													
			SD-04 Samples															
			Finishes	2.5	G													
			SD-06 Test Reports															
			Fire-rating(s) of Assemblies	1.3.1	G													
			Acoustical Ratings of Assemblies	1.3.1	G													
		08 33 23	SD-02 Shop Drawings															
			Overhead Coiling Doors	2.2.1	G													
			Counterbalancing Mechanism	2.2.3	G													
			Electric Door Operators	2.2.4	G													
			Guides	2.1.1.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		08 33 23	Mounting Brackets	2.2.3.1	G													
			Hood	2.2.2.2	G													
			Installation Drawings	2.1.1.1	G													
			SD-03 Product Data															
			Overhead Coiling Doors	2.2.1	G													
			Hardware	2.2.2	G													
			Counterbalancing Mechanism	2.2.3	G													
			Electric Door Operators	2.2.4	G													
			Recycled content for steel curtain slats	2.2.1.1	S													
			SD-05 Design Data															
			Overhead Coiling Doors	2.2.1														
			Hardware	2.2.2	G													
			Counterbalancing Mechanism	2.2.3	G													
			Electric Door Operators	2.2.4	G													
			Wind Loading	2.1.2.1	G													
			SD-10 Operation and Maintenance Data															
			Operation and Maintenance Manuals	1.3.2	G													
			SD-11 Closeout Submittals															
			Warranty	1.3.1	G													
		08 34 02	SD-02 Shop Drawings															
			Installation	3.2	G													
			SD-03 Product Data															
			Bullet Resistant Components	1.4	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		08 34 02	SD-07 Certificates																
			Bullet Resistant Components	1.4															
			SD-10 Operation and Maintenance																
			Data																
			Bullet Resistant Components	1.4	G														
		08 34 73	SD-02 Shop Drawings																
			Fabrication Drawings	2.1															
			SD-03 Product Data																
			Hollow Metal Sound Retardant	2.1	G														
			Doors																
			Door Frames	2.1	G														
			Door Hardware	2.1	G														
			Door Frame Sound Infill	2.3.2	G														
			Intumescent Seals and Gasketing	2.1	G														
			Thresholds	2.1	G														
			Astragals	2.1	G														
			SD-06 Test Reports																
			Wind Loading Tests	2.4.4	G														
			Water Leakage Tests	2.4.4	G														
			Acoustical Tests	2.4.4	G														
			Air Infiltration Tests	2.4.4	G														
			Positive Pressure Tests	2.4.4	G														
			SD-07 Certificates																
			Hollow Metal Sound Retardant	2.1	G														
			Doors																
			Wood Sound Retardant Doors	2.1	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		08 34 73	Door Frames	2.1	G													
			Door Hardware	2.1	G													
			Thresholds	2.1	G													
			Astragals	2.1	G													
			Assembly Test Reports	3.3.1														
		08 41 13	SD-02 Shop Drawings															
			Installation Drawings	3.3	G													
			Fabrication Drawings	2.2	G													
			SD-03 Product Data															
			Finish	2.2.3	G													
			Recycled Content of Aluminum	2.1.1.2	S													
			Material															
			SD-06 Test Reports															
			Deflection	3.4.3														
			Air Infiltration	3.4.1														
			Condensation Resistance and	3.4.4														
			Thermal Transmittance															
			Water Infiltration	3.4.5														
			SD-08 Manufacturer’s Instructions															
			Manufacturer's Instructions	3.3														
			SD-11 Closeout Submittals															
			Manufacturer's Product Warranty	3.6														
		08 41 60	SD-02 Shop Drawings															
			Delegated Design	3.1														
			SD-03 Product Data															
			Wall Framing	2.1.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		08 41 60	Fiberglass Panels	2.1.2	G														
			Color	2.1.3	G														
			SD-04 Samples																
			Samples	2.1.3	G														
			SD-05 Design Data																
			Wall Framing	2.1.1	G														
			Fiberglass Panels	2.1.2	G														
			SD-06 Test Reports																
			Third Party Material Testing	3.1.2	G														
			Certification Reports	3.1.2	G														
			SD-07 Certificates																
			Certificates Of Compliance		G														
			SD-10 Operation and Maintenance																
			Data																
			Maintenance	1.5	G														
			SD-11 Closeout Submittals																
			Warranty	1.4	G														
		08 71 00	SD-02 Shop Drawings																
			Manufacturer's Detail Drawings	1.3	G														
			Verification of Existing Conditions	1.3	G														
			Hardware Schedule	1.5	G														
			Keying System	2.3.6	G														
			SD-03 Product Data																
			Hardware Items	2.3	G														
			SD-08 Manufacturer’s Instructions																
			Installation	3.1															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		08 71 00	SD-10 Operation and Maintenance																
			Data																
			Hardware Schedule	1.5	G														
			SD-11 Closeout Submittals																
			Key Bitting	1.6.1															
		08 81 00	SD-03 Product Data																
			Insulating Glass	2.3															
			Glazing Accessories	1.3															
			Sealants	2.4.1.1															
			Joint Backer	2.4.2															
			Rated Glazing	2.2.3															
			SD-04 Samples																
			Insulating Glass	2.3															
			Tape	2.4.4															
			Sealing Tapes	2.4.4															
			SD-08 Manufacturer’s Instructions																
			Setting and Sealing Materials	2.4															
			Glass Setting	3.2															
			SD-11 Closeout Submittals																
			Insulated Glass Units	1.7.1															
		08 91 00	SD-02 Shop Drawings																
			Wall Louvers	1.4															
			SD-03 Product Data																
			Metal Wall Louvers	2.2															
			SD-04 Samples																
			Wall Louver Samples	1.5	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		09 22 00	SD-03 Product Data															
			Metal Support Systems	2.1														
			Recycled Content for Metal	2.1	S													
			Support Systems															
		09 29 00	SD-03 Product Data															
			Cementitious Backer Units	2.1.4														
			Glass Mat Covered or Reinforced	2.1.2														
			Gypsum Sheathing															
			Glass Mat Covered or Reinforced	2.1.2.1														
			Gypsum Sheathing Sealant															
			Abuse Resistant Gypsum Board	2.1.3														
			Accessories	2.1.7														
			Gypsum Board	2.1.1														
			Recycled Content for Gypsum	2.1.1	S													
			Board															
			Recycled Content for Paper	2.1.1	S													
			Facing and Gypsum Cores															
			VOC Content of Joint Compound	2.1.5	S													
			SD-06 Test Reports															
			ASTM E90 Factory Test Report	3.7	G													
			ASTM E90 Factory Test Report	3.9	G													
			ASTM E336 Field Test Report	3.9	G													
			SD-07 Certificates															
			Asbestos Free Materials	2.1	G													
			Indoor Air Quality for Gypsum	2.1.1	S													
			Board															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		09 29 00	SD-08 Manufacturer's Instructions																
			Safety Data Sheets	2.1															
			SD-10 Operation and Maintenance																
			Data																
			Manufacturer Maintenance	2.1															
			Instructions																
		09 30 10	SD-02 Shop Drawings																
			Detail Drawings	3.2	G														
			SD-03 Product Data																
			Porcelain Tile	2.1.1	G														
			Recycled Content for Porcelain	2.1.1	S														
			Tile																
			Mosaic Tile	2.1.2	G														
			Recycled Content for Mosaic Tile	2.1.2	S														
			Glazed Ceramic Wall Tile	2.1.3	G														
			Recycled Content for Glazed	2.1.3	S														
			Ceramic Wall Tile																
			Transition Strips	2.1	G														
			Transition Strips	2.6.1	G														
			Metal Strips	2.6.2	G														
			Setting-Bed	2.2	G														
			Mortar, Grout, and Adhesive	2.4	G														
			Reinforcing Wire Fabric	2.2.6															
			Cementitious Backer Units	2.5.1	G														
			Waterproof Membrane	2.7	G														
			Crack Isolation Membrane	2.8	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		09 30 10	SD-04 Samples															
			Tile	2.1	G													
			Accessories	2.1	G													
			Transition Strips	2.1	G													
			Transition Strips	2.6.1	G													
			Metal Strips	2.6.2	G													
			Grout	2.4.4	G													
			SD-07 Certificates															
			Indoor Air Quality for Adhesives	2.4	S													
			Indoor Air Quality for Sealants	2.4.8	S													
			Water Absorption Rates	1.3.2														
			SD-08 Manufacturer’s Instructions															
			Manufacturer's Approved	3.8														
			Cleaning Instructions															
			SD-10 Operation and Maintenance															
			Data															
			Porcelain Tile	2.1.1														
			Mosaic Tile	2.1.2	G													
			Glazed Ceramic Wall Tile	2.1.3	G													
			Transition Strips	2.1	G													
			Transition Strips	2.6.1	G													
			Metal Strips	2.6.2	G													
		09 51 00	SD-02 Shop Drawings															
			Approved Detail Drawings	2.1	G													
			SD-03 Product Data															
			Acoustical Ceiling Systems	1.8	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		09 51 00	Recycled Content for Type III	2.2.1.1															
			Ceiling Tiles																
			Recycled Content for Type III	2.2.2.1															
			Ceiling Tiles																
			SD-04 Samples																
			Acoustical Units	2.2	G														
			Acoustical Ceiling Tiles	2.2.1.1	G														
			SD-06 Test Reports																
			Ceiling Attenuation Class and	2.1.1	G														
			Test																
			SD-07 Certificates																
			Indoor Air Quality for Type III	2.2.1.1															
			Ceiling Tiles																
			Indoor Air Quality for Type III	2.2.2.1															
			Ceiling Tiles																
			Indoor Air Quality for Sealants	2.8															
		09 65 00	SD-02 Shop Drawings																
			Resilient Flooring and	2.11	G														
			Accessories																
			SD-03 Product Data																
			Resilient Flooring and	2.11	G														
			Accessories																
			Adhesives	2.7															
			Luxury Vinyl Tile	2.1															
			Luxury Vinyl Tile	2.1															
			Wall Base	2.4															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		09 65 00	Homogeneous Sheet Vinyl	2.2															
			Rubber Tile	2.3															
			SD-04 Samples																
			Luxury Vinyl Tile	2.1	G														
			Homogeneous Sheet VinyL	2.2	G														
			SD-06 Test Reports																
			Moisture, Alkalinity and Bond	3.3	G														
			Tests																
			SD-07 Certificates																
			Indoor Air Quality for Wall Base	2.4															
			Indoor Air Quality for Adhesives	2.7															
			Indoor Air Quality For Luxury	2.1															
			Vinyl Tile																
			Indoor Air Quality For Rubber Tile	2.3															
			SD-08 Manufacturer’s Instructions																
			Surface Preparation	3.2	G														
			Installation	3.1	G														
			SD-10 Operation and Maintenance																
			Data																
			Resilient Flooring and	2.11	G														
			Accessories																
		09 66 23	SD-02 Shop Drawings																
			Detail Drawings	1.1	G														
			Strips	2.5	G														
			Control Joint Strips	2.5.2	G														
			SD-03 Product Data																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		09 66 23	Resin	2.2															
			Mixing, Proportioning, and	3.2															
			Installation																
			Cleaning and Sealing	3.4															
			SD-04 Samples																
			Resinous Terrazzo Flooring	1.1															
			SD-06 Test Reports																
			Certified Test Reports	3.3	G														
			SD-07 Certificates																
			Qualifications of Installer	1.4	G														
		09 67 23.13	SD-02 Shop Drawings																
			Installation Drawings	2.1	G														
			Fabrication Drawings	2.1	G														
			SD-03 Product Data																
			Manufacturer's Catalog Data	1.1.2	G														
			SD-04 Samples																
			Hardboard Mounted Epoxy	1.4.2	G														
			Flooring																
			SD-05 Design Data																
			Design Mix Data	1.1.3	G														
			SD-07 Certificates																
			Listing of Product Installations	1.4.1															
			Referenced Standards	1.4															
			Certificates																
			SD-11 Closeout Submittals																
			Warranty	1.5	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		09 68 00	SD-02 Shop Drawings															
			Installation Drawings	3.4	G													
			SD-03 Product Data															
			Carpet Tile	2.1	G													
			Recycled Content for Carpeting	2.1.1														
			Moldings	2.4	G													
			Indoor Air Quality for Aerosol	2.3														
			Adhesives															
			Indoor Air Quality for Non-Aerosol	2.3														
			Adhesives															
			Indoor Air Quality for Concrete	2.3														
			Primer															
			SD-04 Samples															
			Moldings	2.4	G													
			Carpet Tile	2.1	G													
			SD-06 Test Reports															
			Moisture and Alkalinity Tests	3.2	G													
			SD-07 Certificates															
			Indoor Air Quality for Carpet	2.1.2														
			SD-08 Manufacturer’s Instructions															
			Surface Preparation	3.1														
			SD-10 Operation and Maintenance															
			Data															
			Cleaning and Protection	3.5														
			SD-11 Closeout Submittals															
			Warranty	1.6														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		09 69 13	SD-02 Shop Drawings																
			Detailed Installation Drawings	2.2.2	G														
			Fabrication Drawings	2.2.1	G														
			SD-03 Product Data																
			Access Flooring System	2.1	G														
			Recycled Content of Access	2.1.1	S														
			Flooring System																
			Indoor Air Quality For Pedestal	2.1.5	S														
			Adhesive																
			Indoor Air Quality For Adhesives	2.2.5	S														
			SD-04 Samples																
			Floor Panels	2.2															
			Floor Covering	2.2.4	G														
			Panel Support System	2.3															
			Cut Outs	2.5	G														
			SD-05 Design Data																
			Seismic Calculations	2.1.7															
			SD-06 Test Reports																
			Factory Tests	2.4															
			Concentrated Load	2.1.1															
			Uniform Live Load	2.1.1															
			Rolling Load	2.1.1															
			Rolling Load	2.1.1															
			Impact Load	2.1.1															
			Ultimate Load	2.1.1															
			Stringer Load	2.1.3															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		09 69 13	Pedestal Axial Load	2.1.4														
			Bonding Strength of Pedestal	2.1.5														
			Adhesive															
			Electrical Resistance	3.2.3														
			Field Tests	3.2														
			SD-07 Certificates															
			Compliance with ICC-ES AC300	2.1														
			Compliance with ICC IBC	2.1														
			Certificate of Compliance	2.1														
			Qualification of Manufacturer	1.4.1														
			SD-10 Operation and Maintenance															
			Data															
			Operation and Maintenance	3.4	G													
			Manuals															
			SD-11 Closeout Submittals															
			Lifting Device	2.2.6														
			Warranty	1.6	G													
		09 72 00	SD-03 Product Data															
			Wallcoverings and Accessories	2.1	G													
			Primer and Adhesive	2.4														
			SD-04 Samples															
			Wallcoverings and Accessories	2.1	G													
			SD-07 Certificates															
			Indoor Air Quality	1.3.1	S													
			SD-08 Manufacturer’s Instructions															
			Wallcoverings and Accessories	2.1														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		09 72 00	SD-10 Operation and Maintenance																
			Data																
			Wallcoverings and Accessories	2.1	G														
		09 90 00	SD-02 Shop Drawings																
			Piping Identification	3.10															
			SD-03 Product Data																
			Coating	2.1	G														
			Product Data Sheets	2.1															
			SD-04 Samples																
			Color	2.2	G														
			SD-07 Certificates																
			Indoor Air Quality for Paints and	1.6.4															
			Primers																
			SD-08 Manufacturer’s Instructions																
			Application Instructions	3.2.1															
			Mixing	2.1															
			Manufacturer's Safety Data	1.8.1															
			Sheets																
			SD-10 Operation and Maintenance																
			Data																
			Coatings	2.1	G														
		10 11 00	SD-03 Product Data																
			Projection Screen	2.1	G														
			SD-07 Certificates																
			Indoor air quality for projection	2.1	S														
			screen																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		10 11 00	SD-08 Manufacturer’s Instructions																
			Manufacturer's Cleaning	3.2															
			Instructions																
			Manufacturer's Printed	3.1	G														
			Installation Instructions																
		10 14 00.10	SD-02 Shop Drawings																
			Approved Detail Drawings	3.1	G														
			SD-03 Product Data																
			Installation	3.1															
			Exterior Signage	1.2	G														
			Wind Load Requirements	1.2.1															
			SD-04 Samples																
			Exterior Signage	1.2	G														
			SD-10 Operation and Maintenance																
			Data																
			Protection and Cleaning	3.1.2	G														
		10 14 00.20	SD-02 Shop Drawings																
			Detail Drawings	1.4.2	G														
			SD-03 Product Data																
			Installation	3.1	G														
			Warranty	1.6	G														
			SD-04 Samples																
			Interior Signage	1.4.1	G														
			Software	1.3	G														
			SD-10 Operation and Maintenance																
			Data																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY						
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		10 14 00.20	Approved Manufacturer's	3.1	G													
			Instructions															
			Protection and Cleaning	3.1.2	G													
		10 21 13	SD-02 Shop Drawings															
			Fabrication Drawings	2.1														
			Installation Drawings	3.2	G													
			SD-03 Product Data															
			Cleaning and Maintenance	2.1														
			Instructions															
			Colors And Finishes	2.7														
			Anchoring Devices and Fasteners	2.2.2														
			Hardware and Fittings	2.2.4														
			Brackets	2.2.3														
			Door Hardware	2.2.5														
			Toilet Enclosures	2.3.1														
			Urinal Screens	2.3.2														
			Pilaster Shoes	2.5														
			Finishes	2.2.4.2	G													
			Finishes	2.7.2	G													
			SD-04 Samples															
			Colors and Finishes	2.7	G													
			Hardware and Fittings	2.2.4														
			Anchoring Devices and Fasteners	2.2.2														
			SD-07 Certificates															
			Warranty	1.6														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		10 21 13	SD-10 Operation and Maintenance																
			Data																
			Plastic Identification	2.1.1	G														
		10 22 13	SD-02 Shop Drawings																
			Wire Mesh Partitions	1.4															
			SD-03 Product Data																
			Wire Mesh Partitions	1.4															
			Recycled Content for Metal Post	2.1	S														
			and Framing Materials																
			Recycled Content for Wire	2.1	S														
			Materials																
		10 26 00	SD-02 Shop Drawings																
			Corner Guards	2.2	G														
			SD-03 Product Data																
			Corner Guards	2.2	G														
			SD-04 Samples																
			Finish	2.4	G														
			SD-06 Test Reports																
			Corner Guards	2.2															
			SD-07 Certificates																
			Corner Guards	2.2															
			Indoor air quality for adhesives	2.5															
		10 28 13	SD-02 Shop Drawings																
			Product Schedule	2.1															
			SD-03 Product Data																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		10 28 13	Recycled content for stainless	2.1	S														
			steel toilet accessories																
			Sanitary Napkin Disposal (SND)	2.1.3	G														
			Grab Bar (GB36) (GB42)	2.1.4	G														
			Grab Bar: L-Shaped (GBL)	2.1.5	G														
			Shelf, Mop and Broom Holder	2.1.6	G														
			(MHS)																
			Robe Hook (RH)	2.1.7	G														
			Shower Curtain Rod (SCR)	2.1.8	G														
			Toilet Tissue Dispenser (TTD)	2.1.9	G														
			Mirror (WM)	2.1.10	G														
			Foam Soap Dispenser (SD)	2.1.11	G														
			Towel Bar (TB)	2.1.12	G														
			Semi Recessed Waste	2.1.13	G														
			Receptacle and Paper Towel																
			Dispenser (ITDW)																
			Shower Seat (FSS)	2.1.14	G														
			Electric Hand Dryer (HD)	2.1.15	G														
			SD-10 Operation and Maintenance																
			Data																
			Grab Bar (GB36) (GB42)	2.1.4	G														
			Grab Bar: L-Shaped (GBL)	2.1.5	G														
			Shelf, Mop and Broom Holder	2.1.6	G														
			(MHS)																
			Robe Hook (RH)	2.1.7	G														
			Shower Curtain Rod (SCR)	2.1.8	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		10 28 13	Toilet Tissue Dispenser (TTD)	2.1.9	G													
			Mirror (WM)	2.1.10	G													
			Foam Soap Dispenser (SD)	2.1.11	G													
			Towel Bar (TB)	2.1.12	G													
			Semi Recessed Waste	2.1.13	G													
			Receptacle and Paper Towel															
			Dispenser (ITDW)															
			Shower Seat (FSS)	2.1.14	G													
			Electric Hand Dryer (HD)	2.1.15	G													
		10 44 16	SD-02 Shop Drawings															
			Cabinets	Part 2	G													
			Wall Brackets	2.1.2	G													
			SD-03 Product Data															
			Cabinets	Part 2	G													
			Wall Brackets	2.1.2	G													
			Replacement Parts List	3.2.1	G													
			SD-04 Samples															
			Equipment Samples	1.2.1	G													
		10 50 00	SD-02 Shop Drawings															
			Cell phone locker	2.1	G													
			Emergency Key Boxes	2.2	G													
			SD-03 Product Data															
			Cell phone locker	2.1	G													
			Emergency Key Boxes	2.2	G													
		10 56 00	SD-03 Product Data															
			Pallet Storage Racks	2.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		12 00 01.00 20	SD-01 Preconstruction Submittals															
			FF&E and CEQ Schedule and	3.1.1.3	G													
			Schedule Updates															
			Contractor's Interior Designer's	3.1.1.1	G													
			Qualifications															
			SD-04 Samples															
			Interior Finish Construction	3.1.2.10	G													
			Submittals															
			Post Option Award FF&E and	3.2.3	G													
			CEQ Finish Submittals															
			Post Option Award FF&E and	3.2.3	G													
			CEQ Finish Submittals															
			SD-05 Design Data															
			FF&E and CEQ Basis of Design	3.1.2.2.2	G													
			Packages															
			FF&E and CEQ BVD Request for	3.1.2.5	G													
			Quotation (RFQ) Packages															
			BVD Bid Packages Results	3.1.2.6	G													
			Pre-Final FF&E and CEQ	3.1.2.7	G													
			Packages 'Over the Shoulder'															
			Pre-Final FF&E and CEQ	3.1.2.7	G													
			Packages															
			Pre-Final FF&E and CEQ	3.1.2.8	G													
			Packages															
			Final FF&E and CEQ Packages	3.1.2.9	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		12 00 01.00 20	SD-10 Operation and Maintenance																
			Data																
			Warranty and Maintenance	3.5.1	G														
			Information																
			SD-11 Closeout Submittals																
			Punch List(s) Submittal	3.3.2	G														
		12 24 13	SD-02 Shop Drawings																
			Detailed Drawings	3.2	G														
			Location Schedule	2.1	G														
			SD-03 Product Data																
			Window Shades	2.1	G														
			Recycled Content for various	2.1	S														
			fiber components																
			SD-04 Samples																
			Window Shades	2.1	G														
			SD-06 Test Reports																
			Flammability Requirements	1.4.2	G														
			SD-07 Certificates																
			Indoor Air Quality for roller	2.1	S														
			window shades																
			Qualifications	1.4.1.1															
			SD-10 Operation and Maintenance																
			Data																
			Window Shades	2.1	G														
		13 34 19	SD-01 Preconstruction Submittals																
			Manufacturer's Qualifications	1.6.3	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		13 34 19	SD-02 Shop Drawings																
			Detail Drawings	1.6.1	G														
			Erection Plan	1.2.8	G														
			SD-03 Product Data																
			Manufacturer's Catalog Data	1.6.1	G														
			Recycled Content for Structural	2.1.1	S														
			Steel Shapes and Plates																
			Recycled Content for Steel Pipe	2.1.2	S														
			Recycled Content for Steel Sheet	2.4.1.1	S														
			Materials																
			Recycled Content for Insulation	2.6.2	S														
			Materials																
			SD-04 Samples																
			Coil Stock	2.1.6	G														
			Roof Panels	1.6.1	G														
			Fasteners	2.5	G														
			Metal Closure Strips	2.6.1	G														
			Insulation	2.6.2	G														
			Color	2.4.2	G														
			SD-05 Design Data																
			Manufacturer's Descriptive and	1.6.1	G														
			Technical Literature																
			Manufacturer's Building Design	1.6.1	G														
			Analysis																
			Lateral Force Calculations	1.6.1	G														
			SD-06 Test Reports																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		13 34 19	Test Reports	1.6.1	G														
			Coatings and Base Metals	1.6.1	G														
			Factory Color Finish Performance	1.6.1	G														
			Requirements																
			SD-07 Certificates																
			System Components	1.6.1	G														
			Coil Stock Certificates	1.6.1	G														
			Aluminized Steel Repair Paint	1.6.1	G														
			Galvanizing Repair Paint	1.6.1	G														
			Enamel Repair Paint	1.6.1	G														
			Qualification of Manufacturer	1.6.1	G														
			Qualification of Erector	1.6.1	G														
			SD-08 Manufacturer’s Instructions																
			Installation of Roof panels	1.6.2	G														
			Shipping, Handling, and Storage	1.7	G														
		13 47 00	SD-01 Preconstruction Submittals																
			Work Plan	1.5	G														
			SD-03 Product Data																
			Radiant Barrier Foil	2.1.1.1	G														
			Conductive Foil Tape	2.1.1.2	G														
			Backing Adhesive	2.1.1.3	G														
			Coatings	2.1.5.1	G														
		21 13 13	SD-01 Preconstruction Submittals																
			Qualified Fire Protection Engineer	1.2.3	G														
			(QFPE)																
			Sprinkler System Designer	1.4.2.1	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		21 13 13	Sprinkler System Installer	1.4.2.2	G													
			SD-02 Shop Drawings															
			Shop Drawing	1.2.1.1	G													
			SD-03 Product Data															
			Pipe	2.2.1	G													
			Fittings	2.3.1.2	G													
			Valves	2.3.4	G													
			Relief Valves	2.8.5	G													
			Sprinklers	2.7	G													
			Pipe Hangers and Supports	2.3.3	G													
			Sprinkler Alarm Switch	2.4.1	G													
			Valve Supervisory (Tamper)	2.4.2	G													
			Switch															
			Fire Department Connection	2.6	G													
			Backflow Prevention Assembly	2.5	G													
			Air Vent	2.8.6	G													
			Hose Valve	2.5.1	G													
			Nameplates	2.1.2	G													
			SD-05 Design Data															
			Hydraulic Calculations	1.2.1.2	G													
			SD-06 Test Reports															
			Test Procedures	3.7.1	G													
			SD-07 Certificates															
			Verification of Compliant	3.7.2.1	G													
			Installation															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY						
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		21 13 13	Request for Government Final	3.7.2.2	G													
			Test															
			SD-10 Operation and Maintenance															
			Data															
			Operating and Maintenance	3.9	G													
			(O&M) Instructions															
			Spare Parts	1.6	G													
			SD-11 Closeout Submittals															
			As-built drawings	3.9														
		21 13 16	SD-01 Preconstruction Submittals															
			Qualified Fire Protection Engineer	1.2.4	G													
			(QFPE)															
			Sprinkler System Designer	1.4.2.1	G													
			Sprinkler System Installer	1.4.2.2	G													
			Nitrogen Generation System	1.4.2.3	G													
			Commissioning Technician															
			SD-02 Shop Drawings															
			Shop Drawing	1.2.1.1	G													
			SD-03 Product Data															
			Pipe	2.2.1.1	G													
			Fittings	2.2.1.2	G													
			Valves	2.2.3	G													
			Relief Valves	2.7.5	G													
			Sprinklers	2.6	G													
			Pipe Hangers and Supports	2.2.2	G													
			Sprinkler Alarm Switch	2.5.1	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		21 13 16	Valve Supervisory (Tamper)	2.5.3	G													
			Switch															
			High/Low-Nitrogen Pressure	2.5.2	G													
			Supervisory Switch															
			Nitrogen Generation System	1.4.2.3	G													
			Nameplates	2.1.2	G													
			Dry Pipe Valve	2.3	G													
			SD-05 Design Data															
			Hydraulic Calculations	1.2.1.2	G													
			SD-06 Test Reports															
			Test Procedures	3.6.1	G													
			SD-07 Certificates															
			Verification of Compliant	3.6.2.1	G													
			Installation															
			Request for Government Final	3.6.2.2	G													
			Test															
			SD-10 Operation and Maintenance															
			Data															
			Operating and Maintenance	3.8	G													
			(O&M) Instructions															
			Spare Parts	1.6	G													
			SD-11 Closeout Submittals															
			As-built drawings	3.8														
		21 30 00	SD-01 Preconstruction Submittals															
			Fire Protection Specialist	1.6.1	G													
			SD-02 Shop Drawings															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		21 30 00	Installation Drawings	3.3.1	G														
			As-Built Drawings	3.10.2	G														
			Piping Layout	3.3.2	G														
			Pump Room	3.3.2	G														
			SD-03 Product Data																
			Catalog Data	2.1	G														
			Spare Parts	1.5															
			Preliminary Tests	3.8.2															
			Field Tests	3.8	G														
			Manufacturer's Representative	1.6.6	G														
			Field Training	3.10.1	G														
			Navy Formal Inspection and	3.8.3															
			Tests																
			SD-06 Test Reports																
			Preliminary Tests	3.8.2															
			Navy Formal Inspection and	3.8.3	G														
			Tests																
			SD-07 Certificates																
			Fire Protection Specialist	1.6.1															
			Qualifications of Welders	1.6.2															
			Qualifications of Installer	1.6.3															
			Preliminary Test Certification	1.6.4															
			Final Test Certification	1.6.5															
			SD-10 Operation and Maintenance																
			Data																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		21 30 00	Operating and Maintenance	3.10.1	G													
			Instructions															
		22 00 00	SD-02 Shop Drawings															
			Plumbing System	3.9.1	G													
			SD-03 Product Data															
			Backflow Prevention Assemblies	3.9.1.1	G													
			Fixtures	2.4														
			Shower Faucets	2.4.10	G													
			Flush Valve Water Closets	2.4.3														
			Flush Valve Urinals	2.4.4														
			Wall Hung Lavatories	2.4.6														
			Integral Lavatories	2.4.7														
			Kitchen Sinks	2.4.8														
			Water Heaters	2.9	G													
			Energy Star Label for Gas	2.9.1.1	S													
			Storage Water Heater															
			Pumps	2.10	G													
			Vibration-Absorbing Features	3.4	G													
			Plumbing System	3.9.1														
			Thermostatic Mixing Valves	2.3.6														
			Temperature Controlled Mixing	2.3.7														
			Valve															
			Point-Of-Use Mixing Valve	2.3.8														
			Automatic Temperature and	2.3.9														
			Pressure Compensating Valve															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY						
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		22 00 00	Single Supply Line Automatic	2.3.10														
			Temperature Control															
			SD-06 Test Reports															
			Tests, Flushing and Disinfection	3.9														
			Test of Backflow Prevention	3.9.1.1	G													
			Assemblies															
			SD-07 Certificates															
			Bolts	2.1.1														
			SD-10 Operation and Maintenance															
			Data															
			Plumbing System	3.9.1	G													
		23 05 48.19	SD-02 Shop Drawings															
			Coupling and Bracing	3.1														
			Flexible Couplings or Joints	3.3														
			Equipment Restraint	2.2														
			Contractor Designed Bracing	1.2.4	G													
			SD-03 Product Data															
			Coupling and Bracing	3.1	G													
			Flexible Couplings Or Joints	3.3	G													
			Equipment Restraint	2.2	G													
			Contractor Designed Bracing	1.2.4	G													
			Snubbers	2.6														
			Anchor Bolts	3.9														
			Vibration Isolators	2.2.2														
			SD-05 Design Data															
			Design Calculations	1.2.4														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 05 48.19	SD-06 Test Reports															
			Anchor Bolts	3.9	G													
		23 05 93	SD-01 Preconstruction Submittals															
			TAB Firm And Personnel	1.6	G													
			Qualifications															
			Design Review Report	1.9	G													
			TAB Pre-Field Engineering Plan	1.10	G													
			SD-06 Test Reports															
			Pre-Final DALT Report	3.1.6	G													
			Certified Final DALT Report	3.1.8	G													
			Certified TAB Report of	3.2.7	G													
			Proportional Balancing															
			Certified TAB Report of Season 1	3.2.7	G													
			SD-11 Closeout Submittals															
			Certified TAB Report of Season 2	3.3.1.2	G													
		23 07 00	SD-02 Shop Drawings															
			MICA Plates	3.2.2.4	G													
			Pipe Insulation Systems	2.3														
			Pipe Insulation Systems	3.2														
			Duct Insulation Systems	3.3														
			Equipment Insulation Systems	3.4														
			Recycled content for insulation	2.3.1	S													
			materials															
			SD-03 Product Data															
			Pipe Insulation Systems	2.3	G													
			Pipe Insulation Systems	3.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		23 07 00	Duct Insulation Systems	3.3	G														
			Equipment Insulation Systems	3.4	G														
			SD-04 Samples																
			Thermal Insulation	2.2.1.3	G														
			Display Samples	3.1.1	G														
			SD-07 Certificates																
			Indoor air quality for adhesives	2.2.1	S														
			SD-08 Manufacturer’s Instructions																
			Pipe Insulation Systems	2.3	G														
			Pipe Insulation Systems	3.2	G														
			Duct Insulation Systems	3.3	G														
			Equipment Insulation Systems	3.4	G														
		23 08 00	SD-03 Product Data																
			Test Equipment	2.1	G														
			SD-06 Test Reports																
			Pipe Flushing, Testing, And	1.5	G														
			Water Treatment Reports																
			Completed Pre-Functional	3.3	G														
			Checklists																
			Seasonal Test Report	3.12	G														
			Full-Load Test Report	3.13	G														
			Post-Construction Trend Log	3.16	G														
			Report																
			SD-07 Certificates																
			Certificate Of Readiness	1.6	G														
		23 09 00	SD-02 Shop Drawings																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		23 09 00	Control System Drawings Title Sheet	3.1.1	G														
			List Of I/O Points	3.1.2	G														
			Control System Components List	3.1.3	G														
			Control System Schematics	3.1.4	G														
			Hvac Equipment Control Ladder Diagrams	3.1.5	G														
			Sequence Of Operations	3.1.6	G														
			Component Wiring Diagrams	3.1.7	G														
			Terminal Strip Diagrams	3.1.8	G														
			Bacnet Communication Architecture Schematic (Network Riser)	3.1.9	G														
			Control Panel Layout	3.1.10	G														
			SD-06 Test Reports																
			Control Contractor's Performance Verification Testing Plan	3.6.5	G														
			Equipment Supplier's Performance Verification Testing Plan	3.6.5	G														
			Performance Verification Testing Report	3.6.14	G														
			Trends	3.7	G														
			Bus Waveform Report	3.8.1	G														
			SD-07 Certificates																
			Contractor's Qualifications	1.7.6	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 09 00	Contractor's Training	1.7.6	G													
			Certifications															
			SD-10 Operation and Maintenance															
			Data															
			Controls System Operators	3.5	G													
			Manuals															
			SD-11 Closeout Submittals															
			Training Documentation	3.9.1	G													
			Warranty Information	3.5	G													
		23 09 13	SD-03 Product Data															
			Sensors And Input Hardware	2.3	G													
			Output Hardware	2.4	G													
			Duct Smoke Detectors	2.6.1	G													
			Variable Frequency (Motor)	2.7	G													
			Drives															
			SD-06 Test Reports															
			Vfd Start-Up Test Documentation	2.7.2	G													
			SD-10 Operation and Maintenance															
			Data															
			Vfd Service Manuals	2.7.2	G													
		23 09 23.02	SD-03 Product Data															
			Direct Digital Controllers	2.1.3	G													
			Bacnet Gateways	2.1.3.12	G													
			Notebook Computer	2.1.5	G													
			Notebook Computer Software	2.1.6	G													
			Bacnet Operator Workstation	2.1.6.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		23 11 20	SD-02 Shop Drawings																
			Gas Piping System	1.5.1	G														
			Gas Piping System	2.2	G														
			Gas Piping System	3.2	G														
			SD-03 Product Data																
			Pipe and Fittings	2.1	G														
			Gas Equipment Connectors	1.5.1	G														
			Gas Piping System	1.5.1	G														
			Gas Piping System	2.2	G														
			Gas Piping System	3.2	G														
			Pressure Regulators	2.5	G														
			Valves	2.3	G														
			SD-06 Test Reports																
			Testing	3.17	G														
			Pressure Tests	3.17.1	G														
			Test with Gas	3.17.2	G														
			SD-10 Operation and Maintenance																
			Data																
			Gas Facility System and	1.3.1	G														
			Equipment Operation																
			Gas Facility System Maintenance	1.3.2	G														
			Gas Facility Equipment	1.3.3	G														
			Maintenance																
		23 21 13.00 20	SD-02 Shop Drawings																
			Hot water heating system	1.3.1															
			SD-03 Product Data																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 21 13.00 20	Pumps	2.4.1														
			Expansion tanks	2.4.2														
			Flow measuring equipment	2.4.4														
			External air separation tanks	2.4.3														
			Hot water heating pipe	2.2.1														
			Combination Strainer And Pump	2.2.10.2														
			Suction Diffuser															
			SD-06 Test Reports															
			Hydrostatic test of piping system	3.3.1														
			Auxiliary equipment and	3.3.2														
			accessory tests															
			SD-07 Certificates															
			Backflow preventer certification	1.5.4														
			Report of prior installations	1.5.2.1														
			Welding procedures	1.5.2.2														
			Welder's qualifications	1.5.2.3														
		23 23 00	SD-02 Shop Drawings															
			Refrigerant Piping System	2.3	G													
			SD-03 Product Data															
			Refrigerant Piping System	2.3														
			Qualifications	1.3.1														
			Refrigerant Piping Tests	3.4														
			SD-06 Test Reports															
			Refrigerant Piping Tests	3.4														
			SD-07 Certificates															
			Service Organization	2.1														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 23 00	SD-10 Operation and Maintenance															
			Data															
			Maintenance	1.5	G													
			Operation and Maintenance	3.3	G													
			Manuals															
		23 25 00	SD-03 Product Data															
			Water Analysis	2.1.3	G													
			Spare Parts	1.3														
			Field Instructions	3.4.1														
			Tests	3.3.1	G													
			Training Course	3.4.1	G													
		23 30 00	SD-02 Shop Drawings															
			Detail Drawings	1.4.4	G													
			SD-03 Product Data															
			Insulated Nonmetallic Flexible	2.10.1.1														
			Duct Runouts															
			Double Wall Ductwork	2.10.11														
			Duct Connectors	2.10.1.1														
			Duct Access Doors	2.10.2	G													
			Fire Dampers	2.10.3	G													
			Manual Balancing Dampers	2.10.4	G													
			Gravity Backdraft and Relief	2.10.6	G													
			Dampers															
			Diffusers	2.10.7.1														
			Registers and Grilles	2.10.7.3														
			Louvers	2.10.8														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 30 00	Air Vents, Penthouses, and	2.10.9														
			Goosenecks															
			In-Line Centrifugal Fans	2.11.1.1														
			Propeller Type Sidewall Fans	2.11.1.2														
			Air Handling Units	2.12	G													
			Variable Volume, Single Duct	2.13.1.1	G													
			Terminal Units															
			Reheat Units	2.13.1.2	G													
			Energy Recovery Devices	2.14	G													
			Test Procedures	1.4.5														
			Diagrams	1.2.1.2	G													
			Indoor Air Quality for Duct	2.10.1	S													
			Sealants															
			SD-06 Test Reports															
			Performance Tests	3.12	G													
			Damper Acceptance Test	3.10	G													
			SD-07 Certificates															
			Bolts	1.4.1														
			Ozone Depleting Substances	1.4.3														
			Technician Certification															
			SD-08 Manufacturer’s Instructions															
			Manufacturer's Installation	3.2														
			Instructions															
			Operation and Maintenance	3.14.2														
			Training															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		23 30 00	SD-10 Operation and Maintenance																
			Data																
			Operation and Maintenance	3.14.1	G														
			Manuals																
			Fire Dampers	2.10.3	G														
			Manual Balancing Dampers	2.10.4	G														
			In-Line Centrifugal Fans	2.11.1.1	G														
			Propeller Type Sidewall Fans	2.11.1.2	G														
			Air Handling Units	2.12	G														
			Variable Volume, Single Duct	2.13.1.1	G														
			Terminal Units																
			Reheat Units	2.13.1.2	G														
			Energy Recovery Devices	2.14	G														
			SD-11 Closeout Submittals																
			Indoor Air Quality During	3.13	S														
			Construction																
		23 52 43.00 20	SD-02 Shop Drawings																
			Fuel Train	1.3.2.2															
			Wiring Diagram	1.3.2.2															
			SD-03 Product Data																
			Boilers	2.1															
			Boiler Trim and Control	2.2															
			Equipment																
			Stack, Breeching, and Supports	2.2.17															
			SD-06 Test Reports																
			Operational Tests	3.3.1															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		23 52 43.00 20	SD-07 Certificates																
			Boilers	2.1															
			Boiler Trim and Control	2.2															
			Equipment																
			SD-08 Manufacturer’s Instructions																
			Boilers	2.1															
			Feedwater Treatment Feeder	2.2.7															
			SD-10 Operation and Maintenance																
			Data																
			Boilers	2.1															
			SD-11 Closeout Submittals																
			Boilers	2.1															
		23 64 10	SD-03 Product Data																
			Verification of Dimensions	1.6.1															
			System Performance Tests	3.6															
			Demonstrations	3.7															
			Refrigerant	2.5.1															
			Water Chiller - Field Acceptance	3.5.1															
			Test Plan																
			Scroll Type Water Chiller	2.4.1															
			SD-06 Test Reports																
			Field Acceptance Testing	3.5															
			Water Chiller - Field Acceptance	3.5.2															
			Test Report																
			Factory Tests	2.8															
			System Performance Tests	3.6															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 64 10	Factory Test Schedule	3.2	G													
			Startup Report	3.3														
			SD-07 Certificates															
			Refrigeration System	3.1.7	G													
			Refrigeration Technician	1.3.1														
			Certification															
			SD-08 Manufacturer’s Instructions															
			Water Chiller - Installation	3.1	G													
			Instructions															
			SD-10 Operation and Maintenance															
			Data															
			Operation and Maintenance	3.7	G													
			Manuals															
			Training Course Schedule	3.7	G													
			SD-11 Closeout Submittals															
			Indoor Air Quality During	3.4	S													
			Construction															
		23 64 26	SD-03 Product Data															
			Calibrated Balancing Valves	2.5.8	G													
			Water Temperature Regulating	2.5.9	G													
			Valves															
			Water Pressure Reducing Valve	2.5.10														
			Pressure Relief Valve	2.5.11														
			Combination Pressure and	2.5.12														
			Temperature Relief Valves															
			Expansion Joints	2.6.9	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		23 64 26	Pumps	2.7	G														
			Combination Strainer and Pump	2.6.3															
			Suction Diffuser																
			Expansion Tanks	2.8															
			Air Separator Tanks	2.9															
			Water Treatment Systems	2.10	G														
			SD-06 Test Reports																
			Piping Welds NDE Report	3.1.1.3															
			Pressure Tests Reports	3.4.2	G														
			SD-07 Certificates																
			Employer's Record Documents	3.1.1.1															
			(For Welding)																
			Welding Procedures and	3.1.1.2															
			Qualifications																
			SD-08 Manufacturer’s Instructions																
			Lesson plan for the Instruction	3.5															
			Course																
			SD-10 Operation and Maintenance																
			Data																
			Water Treatment Systems	2.10															
			Calibrated Balancing Valves	2.5.8															
			Water Temperature Regulating	2.5.9															
			Valves																
			Water Pressure Reducing Valve	2.5.10															
			Pressure Relief Valve	2.5.11															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 64 26	Combination Pressure and	2.5.12														
			Temperature Relief Valves															
			Expansion Joints	2.6.9														
			Pumps	2.7														
			Combination Strainer and Pump	2.6.3														
			Suction Diffuser															
			Expansion Tanks	2.8														
			Air Separator Tanks	2.9														
		23 81 00	SD-03 Product Data															
			Spare Parts	3.7.1														
			Posted Instructions	3.4														
			Coil Corrosion Protection	2.5.1														
			System Performance Tests	3.6														
			Training	3.4	G													
			Inventory	1.5														
			Supplied Products	2.1														
			Manufacturer's Standard Catalog	2.2														
			Data															
			Dehumidifiers	2.3.2														
			SD-06 Test Reports															
			Refrigerant Tests, Charging, and	3.5	G													
			Start-Up															
			System Performance Tests	3.6	G													
			SD-07 Certificates															
			Service Organizations	3.7.2														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		23 81 00	SD-10 Operation and Maintenance															
			Data															
			Operation and Maintenance	3.4	G													
			Manuals															
			SD-11 Closeout Submittals															
			Ozone Depleting Substances	2.2.2.3	S													
		23 82 00.00 20	SD-03 Product Data															
			Unit Heaters	2.1														
			SD-10 Operation and Maintenance															
			Data															
			Unit Heaters	2.1														
		25 05 11.00	SD-01 Preconstruction Submittals															
			Qualifications	1.7.1	G													
			Device Account Lock Exception	3.1.2.2	G													
			Request															
			Contractor Computer	1.10.1.4	G													
			Cybersecurity Compliance															
			Statements															
			Contractor Temporary Network	1.10.6	G													
			Cybersecurity Compliance															
			Statements															
			SD-02 Shop Drawings															
			Cybersecurity Riser Diagram	1.8.4	G													
			Control System Inventory Report	1.8.2	G													
			SD-03 Product Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		25 05 11.00	Control System Cybersecurity Documentation	1.8.5	G														
			SD-06 Test Reports																
			Wireless Communication Test Report	3.1.3.3	G														
			SD-07 Certificates																
			Software Licenses	1.9	G														
			SD-11 Closeout Submittals																
			Password Summary Report	3.4.2.2.3	G														
			Software Recovery And Reconstitution Images	1.8.3	G														
			Device Audit Record Upload Software	3.2.2.1	G														
		26 08 00	SD-06 Test Reports																
			Acceptance Tests and Inspections	3.1	G														
			SD-07 Certificates																
			Qualifications	1.4.1	G														
			Acceptance Test and Inspections Procedure	1.4.3	G														
		26 12 19.10	SD-02 Shop Drawings																
			Pad-mounted Transformer Drawings	1.5.1	G														
			SD-03 Product Data																
			Pad-mounted Transformers	2.2	G														
			SD-06 Test Reports																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		26 12 19.10	Acceptance Checks and Tests	3.6.1	G													
			SD-07 Certificates															
			Transformer Efficiencies	2.2.2.1	G													
			SD-09 Manufacturer's Field															
			Reports															
			Transformer Test Schedule	2.8.1	G													
			Design Tests	2.8.2	G													
			Routine and Other Tests	2.8.3	G													
			SD-10 Operation and Maintenance															
			Data															
			Transformer(s)	1.6.1	G													
		26 13 00	SD-02 Shop Drawings															
			Switchgear Drawings	1.5.1	G													
			SD-03 Product Data															
			Electronic Overcurrent Control	1.5.3	G													
			Curves															
			SF6/High-Firepoint Fluid	1.6.1	G													
			Insulated Pad-mounted Switchgear															
			SF6/High-Firepoint Fluid	2.1	G													
			Insulated Pad-mounted Switchgear															
			Insulated High-Voltage	2.2	G													
			Connectors															
			Surge Arresters	2.3	G													
			SD-06 Test Reports															
			Acceptance Checks and Tests	3.4.1	G													
			SD-07 Certificates															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		26 13 00	Paint Coating System	1.5.2	G														
			Cybersecurity	1.7	G														
			SD-09 Manufacturer's Field																
			Reports																
			Switchgear Design and	2.5.1	G														
			Production Tests																
			SD-10 Operation and Maintenance																
			Data																
			SF6/High-Firepoint Fluid	1.6.1	G														
			Insulated Pad-mounted Switchgear																
			SF6/High-Firepoint Fluid	2.1	G														
			Insulated Pad-mounted Switchgear																
		26 20 00	SD-02 Shop Drawings																
			Panelboards	2.12	G														
			Transformers	2.14	G														
			Cable Trays	2.3	G														
			SD-03 Product Data																
			Receptacles	2.11	G														
			Circuit Breakers	2.12.3	G														
			Switches	2.9	G														
			Transformers	2.14	G														
			Enclosed Circuit Breakers	2.13	G														
			Manual Motor Starters	2.15	G														
			Secondary Bonding Busbar	2.18.2	G														
			Surge Protective Devices	2.23	G														
			Cable Trays	2.3	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY						
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		26 20 00	SD-06 Test Reports															
			600-volt Wiring Test	3.5.2	G													
			Grounding System Test	3.5.5	G													
			Transformer Tests	3.5.3	G													
			Ground-fault Receptacle Test	3.5.4	G													
			SD-07 Certificates															
			Fuses	2.10	G													
			SD-09 Manufacturer’s Field															
			Reports															
			Transformer Factory Tests	2.25.1														
			SD-10 Operation and Maintenance															
			Data															
			Electrical Systems	1.5.1	G													
		26 24 13	SD-02 Shop Drawings															
			Switchboard Drawings	1.5.2	G													
			SD-03 Product Data															
			Switchboard	2.2	G													
			SD-06 Test Reports															
			Switchboard Design Tests	2.5.2	G													
			Switchboard Production Tests	2.5.3	G													
			Acceptance Checks and Tests	3.5.1	G													
			SD-10 Operation and Maintenance															
			Data															
			Switchboard Operation and	1.6.1	G													
			Maintenance															
			SD-11 Closeout Submittals															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		26 24 13	Assembled Operation and	1.6.2	G													
			Maintenance Manuals															
			Equipment Test Schedule	2.5.1	G													
			Required Settings	3.5	G													
			Service Entrance Available Fault	2.8	G													
			Current Label															
		26 27 14.00 20	SD-02 Shop Drawings															
			Installation Drawings	1.3.1	G													
			SD-03 Product Data															
			Electricity Meters	2.1.4	G													
			Current Transformer	2.1.3	G													
			Potential Transformer	2.1.2	G													
			Communications	2.2	G													
			SD-06 Test Reports															
			Acceptance Checks and Tests	3.2.1	G													
			System Functional Verification	3.2.2	G													
			Building Meter Installation Sheet,	3.2.1	G													
			per Building															
			Meter Configuration Template	2.1.1	G													
			Meter Configuration Report	3.2.1	G													
			SD-10 Operation and Maintenance															
			Data															
			Electricity Meters and	1.4.1	G													
			Accessories															
			SD-11 Closeout Submittals															
			System Functional Verification	3.2.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		26 28 01.00 10	SD-03 Product Data															
			Fault Current Analysis	2.1														
			Protective Device Coordination	2.1														
			Study															
			System Coordinator	1.3.1														
		26 29 23	SD-02 Shop Drawings															
			Schematic Diagrams	1.5.1	G													
			Interconnecting Diagrams	1.5.2	G													
			Installation Drawings	1.5.3	G													
			As-Built Drawings	1.5.3	G													
			SD-03 Product Data															
			Adjustable Speed Drives	2.1	G													
			Wires and Cables	2.3														
			Equipment Schedule	1.5.4														
			SD-06 Test Reports															
			ASD Test	3.3.1														
			Performance Verification Tests	3.3.2														
			Endurance Test	3.3.3														
			SD-08 Manufacturer’s Instructions															
			Installation instructions	1.5.5														
			SD-09 Manufacturer’s Field															
			Reports															
			ASD Test Plan	2.5.1	G													
			Standard Products	1.5.6														
			SD-10 Operation and Maintenance															
			Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		26 29 23	Adjustable Speed Drives	2.1															
		26 32 15.00	SD-02 Shop Drawings																
			Engine-Generator Set and	2.1.1	G														
			Auxiliary Equipment																
			Auxiliary Systems	1.4.8	G														
			Detailed Drawings	1.4.7	G														
			Acceptance	3.17	G														
			SD-03 Product Data																
			Harmonic Requirements	2.1.8	G														
			Engine-Generator Set	2.1.1	G														
			Efficiencies																
			Emissions	2.12	G														
			filters	2.7.2	G														
			special tools	2.14	G														
			Remote Alarm Annunciator	2.13.4	G														
			Engine-Generator Parameter	2.1.1															
			Schedule																
			Generator	2.15															
			Manufacturer's Catalog	2.5															
			Spare Parts	1.7.2															
			Onsite Training	3.12															
			Vibration-Isolation	2.1.7															
			Posted Data and Instructions	3.16	G														
			Instructions	3.6.7.1	G														
			Experience	1.4.5															
			Field Engineer	1.4.6															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		26 32 15.00	General Installation	3.2															
			Exciter	2.16															
			SD-05 Design Data																
			Performance Criteria	2.15															
			Sound Limitations	2.8	G														
			Integral Main Fuel Storage Tank	2.6.4															
			Power Factor	3.6.1.2															
			Time-Delay on Alarms	2.19.5															
			Vibration Isolation	2.1.7															
			Battery Charger	2.13.3.2															
			Capacity Calculations for	2.1.1	G														
			Engine-Generator Set																
			Brake Mean Effective Pressure	2.1.1	G														
			(BMEP) Calculations																
			Torsional Vibration Stress	2.1.1	G														
			Analysis Computations																
			Capacity Calculations for	2.1.1	G														
			Batteries																
			Turbocharger Load Calculations	2.1.1	G														
			SD-06 Test Reports																
			Performance Tests	3.6.9															
			Factory Inspection and Tests	2.27															
			Factory Tests	2.27.2															
			Onsite Inspection and Tests	3.6	G														
			Acceptance Checks and Tests	3.9.1	G														
			Functional Acceptance Tests	3.10.2	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		26 32 15.00	Maintenance Procedures	3.12	G													
			Operation and Maintenance	3.12	G													
			Manuals															
			Inspections	3.6.3	G													
			Functional Acceptance Test	3.9.5	G													
			Procedure															
			SD-07 Certificates															
			Vibration Isolation	2.1.7														
			Prototype Test	2.27.2														
			Reliability and Durability	2.1.5														
			Fuel System Certification	1.4.11	G													
			Start-Up Engineer	3.8	G													
			Instructor's Qualification Resume	3.11.1	G													
			Engine Emission Limits	2.1.2.1	G													
			Sound Limitations	2.8														
			Site Visit	3.1														
			Current Balance	2.15.1														
			Materials and Equipment	2.4														
			Factory Inspection and Tests	2.27														
			Engine Tests	3.6.4	G													
			Generator Tests	3.6.5	G													
			Assembled Engine-Generator Set	3.6.6	G													
			Tests															
			SD-10 Operation and Maintenance															
			Data															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		26 32 15.00	Preliminary Assembled Operation and Maintenance Manuals	3.9.4	G													
			Posted Data and Instructions	3.16	G													
			Training Plan	3.11.2	G													
		26 36 23	SD-02 Shop Drawings															
			Automatic Transfer Switch Drawings	1.5.2	G													
			SD-03 Product Data															
			Automatic Transfer Switches	2.1	G													
			Remote Annunciator and Control System Panel	2.3	G													
			SD-06 Test Reports															
			Acceptance Checks and Tests	3.3.1	G													
			Functional Acceptance Tests	3.3.2	G													
			Factory Testing	2.4	G													
			Factory Test Reports	2.4.2	G													
			SD-07 Certificates															
			Proof of Listing	1.5.1	G													
			SD-10 Operation and Maintenance Data															
			Operation and Maintenance Manual	1.4	G													
		26 41 00	SD-02 Shop Drawings															
			Overall lightning protection system	1.4.1.1	G													
			Each major component	1.4.1.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		26 41 00	SD-06 Test Reports																
			Lightning Protection and	1.4.3	G														
			Grounding System Test Plan																
			Lightning Protection and	3.5.1	G														
			Grounding System Test																
			SD-07 Certificates																
			Lightning Protection System	1.2.3	G														
			Installers Documentation																
			Component UL Listed and	1.4.2	G														
			Labeled																
			Lightning protection system	1.4.4	G														
			inspection certificate																
			Roof manufacturer's warranty	3.1.1	G														
		26 51 00	SD-02 Shop Drawings																
			Luminaire Drawings	1.5.1	G														
			Occupancy/Vacancy Sensor	1.5.8	G														
			Coverage Layout																
			Sequence of Operation for	2.5.1	G														
			Lighting Control System																
			SD-03 Product Data																
			Luminaires	2.2	G														
			Light Sources	2.3	G														
			LED Drivers	2.4	G														
			Luminaire Warranty	1.6.1	G														
			Lighting Controls Warranty	1.6.2	G														
			Local Area Controller	2.5.1.1.1	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		26 51 00	Switches	2.5.2.1	G													
			Wall Box Dimmers	2.5.2.2	G													
			Scene Wallstations	2.5.2.3	G													
			Occupancy/Vacancy Sensors	2.5.2.4	G													
			Time Clocks	2.5.2.5	G													
			Power Packs	2.5.2.4.2	G													
			Exit Signs	2.6.1	G													
			Emergency Drivers	2.6.3	G													
			SD-05 Design Data															
			Luminaire Design Data	1.5.2	G													
			SD-06 Test Reports															
			ANSI/IES LM-79 Test Report	1.5.3	G													
			ANSI/IES LM-80 Test Report	1.5.4	G													
			ANSI/IES TM-21 Test Report	1.5.5	G													
			ANSI/IES TM-30 Test Report	1.5.6	G													
			Occupancy/Vacancy Sensor	3.2.1.1	G													
			Verification Test															
			SD-07 Certificates															
			LED Driver and Dimming Switch	1.5.7	G													
			Compatibility Certificate															
			SD-10 Operation and Maintenance															
			Data															
			Lighting System	1.7.1	G													
			Lighting Control System	2.5.1	G													
			Maintenance Staff Training Plan	3.3.2.1	G													
			End-User Training Plan	3.3.2.2	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		26 56 00	SD-02 Shop Drawings																
			Luminaire Drawings	1.5.1.1	G														
			Pole Drawings	1.5.1.2	G														
			Control System One-Line	1.8.2	G														
			Diagram																
			SD-03 Product Data																
			Luminaires	2.2	G														
			Light Sources	2.3	G														
			LED Drivers	2.4	G														
			Luminaire Warranty	1.7.1	G														
			Lighting Controls Warranty	1.7.2	G														
			Pole Warranty	1.7.3	G														
			Photosensors	2.5.1.2	G														
			Time Clock	2.5.1.1	G														
			Lighting Contactor	2.5.1.3	G														
			Poles	2.6	G														
			Brackets	2.6.2															
			SD-05 Design Data																
			Luminaire Design Data	1.5.2	G														
			SD-06 Test Reports																
			ANSI/IES LM-79 Test Report	1.5.3	G														
			ANSI/IES LM-80 Test Report	1.5.4	G														
			ANSI/IES TM-21 Test Report	1.5.5	G														
			SD-08 Manufacturer's Instructions																
			Poles	2.6															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		26 56 00	SD-10 Operation and Maintenance																
			Data																
			Lighting System	1.8.1	G														
			Exterior Lighting Control System	1.8.2	G														
			Maintenance Staff Training Plan	3.3.1.1	G														
			End-User Training Plan	3.3.1.2	G														
		27 10 00	SD-02 Shop Drawings																
			Telecommunications Drawings	1.6.1.1	G														
			Telecommunications Space	1.6.1.2	G														
			Drawings																
			SD-03 Product Data																
			Telecommunications Cabling	2.3	G														
			Patch Panels	2.4.5	G														
			Telecommunications	2.5	G														
			Outlet/Connector Assemblies																
			Equipment Support Frame	2.4.2	G														
			Connector Blocks	2.4.3	G														
			SD-06 Test Reports																
			Telecommunications Cabling	3.5.1	G														
			Testing																
			SD-07 Certificates																
			Telecommunications Contractor	1.6.2.1	G														
			Key Personnel	1.6.2.2	G														
			Manufacturer Qualifications	1.6.2.3	G														
			Test Plan	1.6.3	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		27 10 00	SD-09 Manufacturer's Field																
			Reports																
			Factory Reel Tests	2.12.1	G														
			SD-10 Operation and Maintenance																
			Data																
			Telecommunications Cabling and	1.10.1	G														
			Pathway System																
			SD-11 Closeout Submittals																
			Record Documentation	1.10.2	G														
		28 31 76	SD-01 Preconstruction Submittals																
			Qualified Fire Protection Engineer	1.3.2	G														
			(QFPE)																
			Fire alarm system designer	1.9.2.1	G														
			Supervisor	1.9.2.2	G														
			Technician	1.9.2.3	G														
			Installer	1.9.2.4	G														
			Test Technician	1.9.2.5	G														
			Fire Alarm System Site-Specific	1.7	G														
			Software Acknowledgement																
			SD-02 Shop Drawings																
			Nameplates	1.9.1.3	G														
			Instructions	2.2.4	G														
			Wiring Diagrams	1.9.1.4	G														
			System Layout	1.9.1.5	G														
			Notification Appliances	1.9.1.6	G														
			Initiating devices	1.9.1.7	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		28 31 76	Amplifiers	1.9.1.8	G													
			Battery Power	1.9.1.9	G													
			Voltage Drop Calculations	1.9.1.10	G													
			SD-03 Product Data															
			Fire Alarm and Mass Notification	2.3	G													
			Control Unit (FMCU)															
			Local Operating Console (LOC)	1.4.4	G													
			Amplifiers	1.9.1.8	G													
			Tone Generators	2.5	G													
			Digitalized voice generators	2.5	G													
			LCD Annunciator	2.6.1	G													
			Manual Stations	2.7	G													
			Smoke Detectors	2.8	G													
			Duct Smoke Detectors	2.8.2	G													
			Carbon monoxide detector	2.9	G													
			Addressable Interface Devices	2.10	G													
			Addressable Control Modules	2.11	G													
			Notification Appliances	1.9.1.6	G													
			Batteries	2.14.1	G													
			Battery Chargers	2.14.2	G													
			Supplemental Notification	2.14.1.1	G													
			Appliance Circuit Panels															
			Auxiliary Power Supply Panels	2.14.1.1	G													
			Surge Protective Devices	2.15	G													
			Alarm Wiring	2.15	G													
			Back Boxes and Conduit	3.3.4	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		28 31 76	Ceiling Bridges	3.2.9	G														
			Terminal Cabinets	3.3.2	G														
			Digital Alarm Communicator	2.17.1	G														
			Transmitter (DACT)																
			Environmental Enclosures or	2.19	G														
			Guards																
			Document Storage Cabinet	3.11.3	G														
			SD-06 Test Reports																
			Test Procedures	3.7.1	G														
			SD-07 Certificates																
			Verification of Compliant	3.7.2.1	G														
			Installation																
			Request for Government Final	3.7.2.2	G														
			Test																
			SD-10 Operation and Maintenance																
			Data																
			Operation and Maintenance	3.9	G														
			(O&M) Instructions																
			Instruction of Government	3.10	G														
			Employees																
			SD-11 Closeout Submittals																
			As-Built Drawings	1.9.1.13															
			Spare Parts	1.11.1															
		31 00 00	SD-01 Preconstruction Submittals																
			Excavation and Trenching Plan	1.6.5	G														
			Excavation and Trenching Plan	3.1.3	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		31 00 00	Dewatering Work Plan	3.1.2.2	G													
			Jacking, Boring, and Tunneling	3.4.3	G													
			Plan															
			Preconstruction Meeting	1.6.4	G													
			SD-03 Product Data															
			Flowable Fill Mix Design	2.2	G													
			Geotextiles	2.6														
			SD-06 Test Reports															
			Material Test Report	3.11	G													
			Pipe Inspection Report	3.6.1.6	G													
			Geotechnical Evaluation Report	1.6.1	G													
		31 11 00	SD-01 Preconstruction Submittals															
			Herbicide Application Plan	3.1.1														
			SD-03 Product Data															
			Tree Wound Paint	2.1.1														
			Herbicides	1.3.2	G													
			SD-07 Certificates															
			Qualifications	1.3.2	G													
			SD-11 Closeout Submittals															
			Pest Management Report	3.5.1														
		31 31 16.13	SD-01 Preconstruction Submittals															
			Termiticide Application Plan	3.1.5	G													
			SD-03 Product Data															
			Termiticides	2.2.1														
			SD-05 Design Data															
			Mixing Formulation	3.2.2														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY						
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		31 31 16.13	SD-06 Test Reports															
			Soil Moisture	1.6.1														
			Calibration Test	3.2.1														
			SD-07 Certificates															
			Qualifications	1.4.2	G													
			Foundation Exterior	3.1.2														
			Utilities and Vents	3.1.3														
			Crawl and Plenum Air Spaces	3.1.4														
			List of Equipment	3.2.1														
			SD-08 Manufacturer’s Instructions															
			Termiticides	2.2.1														
			SD-11 Closeout Submittals															
			Verification of Measurement	3.3.1														
			Warranty	1.7														
			Pest Management Report	3.4														
		32 01 16.71	SD-01 Preconstruction Submittals															
			Equipment	2.1	G													
			Proposed Techniques	3.2	G													
			Quality Control Plan	3.1.1	G													
		32 01 19.61	SD-03 Product Data															
			Sealants	2.1														
			Manufacturer's	3.5.2														
			Recommendations															
			SD-04 Samples															
			Sealants	2.1														
			Blocking Media/Backup Materials	2.3.1														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		32 01 19.61	Backer Rod	3.3.3.1														
			Bond Breaking Tapes	2.3.2														
			SD-07 Certificates															
			Equipment List	3.1														
			SD-08 Manufacturer’s Instructions															
			Sealants	2.1														
		32 11 23	SD-03 Product Data															
			Plant, Equipment, and Tools	2.4	G													
			SD-06 Test Reports															
			Initial Tests	2.3.1	G													
			In-Place Tests	3.12.1	G													
		32 12 16.16	SD-02 Shop Drawings															
			Placement Plan	2.1	G													
			SD-03 Product Data															
			Diamond Grinding Plan	2.1.5	G													
			Mix Design	2.5	G													
			Contractor Quality Control	3.1	G													
			SD-04 Samples															
			Aggregates	2.2														
			Asphalt Cement Binder	2.3														
			Warm-mix Additive	2.5.1														
			SD-06 Test Reports															
			Aggregates	2.2	G													
			QC Monitoring	3.1.3.9														
			SD-07 Certificates															
			Asphalt Cement Binder	2.3	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		32 12 16.16	Laboratory Accreditation and	1.3.11															
			Validation																
			Warm-mix Additive	2.5.1															
		32 13 13.06	SD-03 Product Data																
			Curing Materials	2.1.6															
			Reinforcement	2.1.5.3															
			Reinforcement	3.7.9															
			Epoxy Resin	2.1.9															
			Epoxy Resin	2.1.9															
			Dowel Bars	2.1.5.1															
			Dowel Bars	3.7.10															
			Expansion Joint Filler	2.1.10.1															
			SD-04 Samples																
			Test Section	1.5.2	G														
			SD-05 Design Data																
			Mix Design Report	2.2.2	G														
			SD-06 Test Reports																
			Concrete Slump Tests	3.7.2															
			Concrete Uniformity	2.3.1															
			Flexural Strength	3.7.3															
			Air Content	3.7.4															
			SD-07 Certificates																
			Batch Tickets	1.3.3															
			NRMCA Certificate Of	1.3.1															
			Conformance																
			SD-08 Manufacturer’s Instructions																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		32 13 13.06	Diamond Grinding Plan	3.7.5.4															
		32 16 19	SD-03 Product Data																
			Concrete	2.1															
			SD-06 Test Reports																
			Field Quality Control	3.8															
		32 17 23	SD-03 Product Data																
			Surface Preparation Equipment List	2.1.1.2	G														
			Application Equipment List	2.1.2	G														
			Exterior Surface Preparation	3.2															
			Safety Data Sheets	1.3.1	G														
			Waterborne Paint	3.3.1.1	G														
			Waterborne Paint	3.3.1.1	G														
			Thermoplastic compound	2.2.1	G														
			Thermoplastic compound	2.2.1	G														
			Thermoplastic compound	3.3.2	G														
			Thermoplastic compound	3.3.2	G														
			SD-07 Certificates																
			Qualifications	1.3.2	G														
			Waterborne Paint	3.3.1.1															
			Volatile Organic Compound	1.3.1	G														
			Thermoplastic Compound	2.2.1															
			Thermoplastic Compound	3.3.2															
			SD-08 Manufacturer's Instructions																
			Waterborne Paint	3.3.1.1	G														
			Thermoplastic Compound	2.2.1	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		32 17 23	Thermoplastic Compound	3.3.2	G														
		32 17 23.16	SD-01 Preconstruction Submittals																
			Quality Control Plan	1.3.1	G														
			Qualifications	1.3.2	G														
			Safety Data Sheets For Each	2.2	G														
			Paint Type																
			Safety Data Sheets For	2.1.1	G														
			Chemicals Used In Surface																
			Preparation																
			Data Sheets For Paint Removal	2.1.1	G														
			Equipment																
			Surface Preparation Equipment	2.1	G														
			List																
			Marking Applications Equipment	2.1.2	G														
			List																
			Detour Plans	1.5.2	G														
			SD-03 Product Data																
			Manufacturer Data Sheets for all	2.2	G														
			Marking Materials																
			SD-04 Samples																
			Samples of Marking Materials	3.5.2	G														
			Samples of each Reflective	3.5.2	G														
			Media																
			SD-06 Test Reports																
			Marking Application Wet Film	3.5.4.1	G														
			Thickness Test																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		32 17 23.16	Marking Application Wet Film Thickness Test	3.5.4.2	G														
			Reflective Media Reflectivity Test	3.5.4.1	G														
			SD-07 Certificates																
			Manufacturer Certificate of Compliance for Marking Materials	2.2	G														
			Manufacturer Certificate of Compliance for Reflective Materials	2.2	G														
			Manufacturer Certificate of Conformance for Volatile Organic Compliance	1.5.1.3	G														
			SD-08 Manufacturer’s Instructions																
			Marking Materials Storage and Application	1.4	G														
			Reflective Media Storage and Application	1.4	G														
			Chemicals Used in Surface Preparation	1.4	G														
		32 31 13	SD-02 Shop Drawings																
			Fence Assembly	2.1	G														
			Location of Gate, Corner, End, and Pull Posts	3.2.2.1	G														
			Gate Assembly	2.1	G														
			Gate Hardware and Accessories	2.3.6	G														
			Erection/Installation Drawings	Part 3	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		32 31 13	SD-03 Product Data																
			Fence Assembly	2.1	G														
			Gate Assembly	2.1	G														
			Gate Hardware and Accessories	2.3.6	G														
			Zinc Coating	2.4.1	G														
			PVC Coating	1.3.1	G														
			Aluminum Alloy Coating	1.3.1	G														
			Fabric	2.2.1	G														
			Stretcher Bars	2.2.6	G														
			Concrete	2.4.2	G														
			SD-04 Samples																
			Fabric	2.2.1	G														
			Posts	2.2.2	G														
			Braces	2.2.3	G														
			Line Posts	2.2.2.1.1	G														
			Sleeves	2.2.5	G														
			Top Rail	2.2.3.1	G														
			Tension Wire	2.2.8	G														
			Stretcher Bars	2.2.6	G														
			Gate Posts	2.3.1	G														
			Gate Hardware and Accessories	2.3.6	G														
			Wire Ties	2.2.4	G														
			SD-07 Certificates																
			Certificates of Compliance	1.3.1															
			SD-08 Manufacturer’s Instructions																
			Fence Assembly	2.1															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		32 31 13	Gate Assembly	2.1															
			Hardware Assembly	2.1															
			Accessories	2.1															
			SD-11 Closeout Submittals																
			Recycled Material Content	3.3															
		32 92 23	SD-03 Product Data																
			Fertilizer	2.3															
			SD-06 Test Reports																
			Topsoil composition tests	2.2.3															
			SD-07 Certificates																
			sods	2.1															
		32 93 00	SD-01 Preconstruction Submittals																
			State Landscape Contractor's	1.4.3															
			License																
			Time Restrictions and Planting	1.6															
			Conditions																
			SD-03 Product Data																
			Peat	2.3.5															
			Composted Derivatives	2.3.8															
			Rotted Manure	2.3.11															
			Organic Mulch Materials	2.7.2															
			Gypsum	2.3.9															
			Mulch	2.7															
			Ground Stakes	2.8.1.2															
			Recycled Plastic Edging	2.9.2															
			Fertilizer	2.5															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		32 93 00	Weed Control Fabric	2.6														
			Root Control Barrier	3.2.4														
			Staking Material	2.8.1														
			Wood Edging	2.9.1														
			Metal Anchors	2.8.7														
			Antidesiccants	2.10														
			SD-06 Test Reports															
			Topsoil Composition Tests	2.2.4														
			Percolation Test	1.4.4														
			SD-07 Certificates															
			Nursery Certifications	2.1.1														
			SD-10 Operation and Maintenance															
			Data															
			Plastic Identification	1.8														
		33 01 30.16	SD-01 Preconstruction Submittals															
			Traffic Control Plan	3.1.1	G													
			Disposal Plan	1.3.1	G													
			Sewage Handling Permit	1.3.2	G													
			SD-03 Product Data															
			Cleaning Products	2.3.1	G													
			SD-07 Certificates															
			CCTV Technician's Qualifications	1.5.2	G													
			Pre-TV Inspection	3.2.2	G													
			Post-TV Inspection	3.2.3	G													
			Warranty-TV Inspection	3.2.4	G													
			RE-TV Inspection	3.2.5	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		33 01 30.16	SD-11 Closeout Submittals																
			Records of Disposals	3.4.1															
		33 05 07.13	SD-01 Preconstruction Submittals																
			Qualifications	1.3.1	G														
			SD-03 Product Data																
			Pipe	2.2.1	G														
			Drilling Fluids	2.2.2	G														
			Additives	2.2.3	G														
			Tracer Wire	2.2.4	G														
			SD-05 Design Data																
			Secondary Containment Plan	3.2.2	G														
			SD-06 Test Reports																
			Soil Test Data	3.1															
			SD-07 Certificates																
			Drill Rod	2.1.1															
			SD-11 Closeout Submittals																
			Record Drawings	3.4															
			Complete Work Logs of Guided	3.4															
			Directional Drill Operations																
		33 11 00	SD-01 Preconstruction Submittals																
			Connections	3.1.1	G														
			SD-03 Product Data																
			Pipe, Fittings, Joints and	2.1.1	G														
			Couplings																
			Valves	2.1.2	G														
			Valve Boxes	2.1.2.6	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY				MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		33 11 00	Fire Hydrants	2.1.4.1	G													
			Pipe Restraint	2.2.1	G													
			Corporation Stops	2.2.4.1	G													
			Disinfection Procedures	3.2.4	G													
			SD-06 Test Reports															
			Bacteriological Samples	3.3.1.4	G													
			Hydrostatic Sewer Test	3.2.1.1.6														
			Leakage Test	3.3.1.3														
			Hydrostatic Test	3.3.1.1														
			SD-07 Certificates															
			Pipe, Fittings, Joints and	2.1.1														
			Couplings															
			Lining	2.1.1.1.1														
			Valves	2.1.2														
			Fire Hydrants	2.1.4.1														
			Fusion Technician Qualifications	1.4.2.1	G													
			Displacement Type Meters	2.1.5.1														
			SD-08 Manufacturer’s Instructions															
			Ductile-Iron Piping	2.1.1.1														
			Copper Pipe For Service Lines	2.1.1.2														
		33 30 00	SD-01 Preconstruction Submittals															
			Contractor's License	1.3.1	G													
			SD-02 Shop Drawings															
			Installation Drawings	3.1.1	G													
			SD-03 Product Data															
			Precast Concrete Manholes	2.2.6														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		33 30 00	Frames, Covers, and Gratings	2.2.9															
			Gravity Pipe	2.2.1															
			Pressure Pipe	2.2.2															
			SD-06 Test Reports																
			Precast Concrete Sewer Manhole	3.3.1.1.1	G														
			Test																
			Hydrostatic Sewer Test	3.2.2.1.1	G														
			Negative Air Pressure Test	3.3.1.1.1	G														
			Low-Pressure Air Tests	3.3.1.1.2	G														
			Tests For Pressure Lines	3.3.1.2	G														
			SD-07 Certificates																
			Portland Cement	2.2.4															
			Gaskets	2.2.7															
			Post-Installation Inspection	3.3.2.1	G														
		33 31 23.00 10	SD-06 Test Reports																
			Disposal of Waste Water	3.2															
			Final Test Report	3.2															
		33 32 16	SD-02 Shop Drawings																
			Fabrication Drawings	2.1															
			Erection/Installation Drawings	2.1															
			SD-03 Product Data																
			Submersible Sewage nonclog	2.2	G														
			Pumps																
			Pump Performance Curve	2.3	G														
			Pump Motor	2.3	G														
			Pump Control System	2.4	G														

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		33 32 16	Wet Well and Valve Vault	2.5.1	G														
			Flexible Flanged Coupling	2.6.4	G														
			Station Piping	2.6	G														
			Valves	2.7	G														
			Spare Parts Data	3.3.1	G														
			Access Hatch Covers	2.5.2															
			SD-05 Design Data																
			Buoyancy Calculations	2.5.1.1	G														
			Pump Test	3.2.1	G														
			SD-07 Certificates																
			Submersible Sewage nonclog	2.2	G														
			Pumps																
			Recycled Material Content	2.5.1.1															
			Manhole Chamber	2.1															
			Access Hatch Covers	2.5.2															
			Gate Valves	2.7.1															
			Check Valves	2.7.2															
			Blowers	2.5.3.1															
			Dehumidifier	2.5.3.2															
			Pump Motor	2.3															
			SD-08 Manufacturer’s Instructions																
			Manhole Chamber	2.1															
			Access Hatch Covers	2.5.2															
			Pump Control System	2.4															
			Gate Valves	2.7.1															
			Check Valves	2.7.2															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		33 32 16	Blowers	2.5.3.1														
			Dehumidifier	2.5.3.2														
			Pump Motor	2.3														
			Special Tools	3.3.1														
			Posted Instructions	3.3.1														
			SD-10 Operation and Maintenance															
			Data															
			Operation And Maintenance	3.3.1														
			Manuals															
			SD-11 Closeout Submittals															
			Warranty	1.5														
		33 40 00	SD-06 Test Reports															
			Leakage Test	3.8.3.1	G													
			SD-07 Certificates															
			Hydrostatic Test on Watertight	2.4.1	G													
			Joints															
			Frame and Cover or Gratings	2.3.3	G													
			SD-08 Manufacturer’s Instructions															
			Placing Pipe and Box Culvert	3.3	G													
			SD-11 Closeout Submittals															
			Post-Installation Inspection	3.8.3.3	G													
			Report															
			LID Verification Report	3.8.2.1	G													
		33 61 14	SD-02 Shop Drawings															
			Factory-prefabricated	2.1														
			preinsulated water piping system															

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAGRAPH #	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		33 61 14	field joints	3.2															
			SD-03 Product Data																
			Pipe, fittings, and end	2.1															
			connections																
			Factory-prefabricated	2.1															
			preinsulated water piping system																
			SD-07 Certificates																
			Certification of welders'	1.4.1															
			qualifications																
			SD-08 Manufacturer’s Instructions																
			factory-prefabricated preinsulated	2.1															
			water piping system																
		33 71 02	SD-02 Shop Drawings																
			Precast Underground Structures	1.5.1	G														
			SD-03 Product Data																
			Medium Voltage Cable	2.4	G														
			Medium Voltage Cable Joints	2.6	G														
			Medium Voltage Cable	2.5	G														
			Terminations																
			Precast Concrete Structures	2.12.1.1	G														
			Sealing Material	2.12.1.4															
			Pulling-In Irons	3.5.2															
			Manhole Frames and Covers	2.12.2	G														
			Handhole Frames and Covers	2.12.3	G														
			Cable Supports	2.13	G														
			SD-06 Test Reports																

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION	MAILED TO CONTR/ DATE RCD FRM APPR AUTH	
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)	(q)	(r)
		33 71 02	Medium Voltage Cable	2.16.2	G													
			Qualification and Production Tests															
			Field Acceptance Checks and	3.17.1	G													
			Tests															
			Arc-proofing Test	2.16.1	G													
			Cable Installation Plan and	3.3	G													
			Procedure															
			SD-07 Certificates															
			Cable splicer/terminator	1.5.2	G													
			Cable Installer Qualifications	1.5.3	G													
			Certificate of Conformance	1.5.4	G													
		33 82 00	SD-02 Shop Drawings															
			Telecommunications Outside	1.6.1.1	G													
			Plant															
			Telecommunications Entrance	1.6.1.2	G													
			Facility Drawings															
			SD-03 Product Data															
			Wire and Cable	2.7	G													
			Cable Splices, and Connectors	2.4	G													
			Closures	2.3	G													
			Building Protector Assemblies	2.2.1	G													
			Protector Modules	2.2.2	G													
			SD-06 Test Reports															
			Pre-installation Tests	3.4.1	G													
			Acceptance Tests	3.4.2	G													
			Outside Plant Test Plan	1.6.3	G													

SUBMITTAL REGISTER

CONTRACT NO.

TITLE AND LOCATION
P1550 Mod to Combine

CONTRACTOR

ACTIVITY NO	TRANSMITTAL NO	SPEC SECT	DESCRIPTION ITEM SUBMITTED	PARAG # RAPH	CLASSIFICATION	GOVT OR A/E REVWR	CONTRACTOR: SCHEDULE DATES			CONTRACTOR ACTION			APPROVING AUTHORITY					MAILED TO CONTR/ DATE RCD FRM APPR AUTH	REMARKS
							SUBMIT	APPROVAL NEEDED BY	MATERIAL NEEDED BY	ACTION CODE	DATE OF ACTION	DATE FWD TO APPR AUTH/ DATE RCD FROM CONTR	DATE FWD TO OTHER REVIEWER	DATE RCD FROM OTH REVIEWER	ACTION CODE	DATE OF ACTION		
(a)	(b)	(c)	(d)	(e)	(f)		(g)	(h)	(i)	(j)	(k)	(l)	(m)	(n)	(o)	(p)		(q)	(r)
		33 82 00	SD-07 Certificates																
			Telecommunications Contractor	1.6.2.1	G														
			Key Personnel	1.6.2.2	G														
			Manufacturer's Qualifications	1.6.2.3	G														
			SD-08 Manufacturer’s Instructions																
			Building Protector Assembly	2.2.1	G														
			Installation																
			Cable Tensions	3.1.7.1	G														
			Fiber Optic Splices	3.1.8.2	G														
			SD-09 Manufacturer’s Field																
			Reports																
			Factory Reel Test Data	2.13.1	G														
			SD-10 Operation and Maintenance																
			Data																
			Telecommunications Outside	1.6.1.1	G														
			Plant (OSP)																
			SD-11 Closeout Submittals																
			Record Documentation	1.8.1	G														

This page is intentionally left blank.

SECTION 01 33 29

SUSTAINABILITY REQUIREMENTS AND REPORTING
02/21, CHG 1: 08/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. For references without a year, use the current published version.

COUNCIL ON ENVIRONMENTAL QUALITY (CEQ) (WHITE HOUSE)

HPSB Guiding Principles	Guiding Principles for Sustainable Federal Buildings and Determining Compliance with the Guiding Principles for Sustainable Federal Buildings

INTERNATIONAL CODE COUNCIL (ICC)

ICC IgCC	(2018) International Green Construction Code

U.S. DEPARTMENT OF AGRICULTURE (USDA)

FSRIA 9002	Farm Security and Rural Investment Act Section 9002 (USDA BioPreferred Program)

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 1-200-02	(2020; Change 3, 2025) High Performance and Sustainable Building Requirements
UFC 3-600-01	(2016; with Change 6, 2021) Fire Protection Engineering for Facilities

U.S. DEPARTMENT OF ENERGY (DOE)

Energy Star	Energy Star Energy Efficiency Labeling System (FEMP)
FEMP	Federal Energy Management Program (FEMP) Energy-Efficient Product Procurement

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 247	Comprehensive Procurement Guideline for Products Containing Recovered Materials

1.2 SUMMARY

This section includes requirements for Sustainability documentation and reporting submittals per the federally mandated High Performance and Sustainable Building (HPSB) or HPSB "Guiding Principles" (GP), in accordance with UFC 1-200-02 High Performance and Sustainable Building

Requirements, and other identified requirements.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Preliminary High Performance and Sustainable Building Checklist; G

Sustainability Action Plan; G

Preliminary Sustainability eNotebook; G

SD-06 Test Reports

SD-11 Closeout Submittals

Final High Performance and Sustainable Building Checklist; G

Final Sustainability eNotebook; G

Amended Final Sustainability eNotebook; G

Amended Final High Performance and Sustainable Building Checklist; G

1.4 GUIDING PRINCIPLES VALIDATION (GPV)

Guiding Principles Validation (GPV) is the project delivery team's self-assessment of UFC 1-200-02 compliance requirements, which includes meeting Federally-required tracking and reporting requirements, in order to report a sustainable Federal building. The use of a third-party certification is an additional and separate requirement.

Provide the following sustainability activities and documentation to verify achievement of HPSB Guiding Principles Validation (GPV):

a. Analysis of each Guiding Principle Requirement and how project complies. Include final government approved narrative(s) in the HPSB Checklist submittal. Multiple checklists indicate multiple buildings that require individual HPSB Checklist tracking.

b. No changes to the HPSB Checklist are allowed without approval from the Contracting Officer, in accordance with Section 01 33 00 SUBMITTAL REQUIREMENTS. Immediately bring to the attention of the Contracting Officer any project changes that impact meeting the approved HPSB Guiding Principles Requirements for this project. Demonstrate the change will not increase the life-cycle cost and maintains or improves the building performance.

c. Documentation of all work required to incorporate the applicable HPSB Guiding Principles requirements indicated on the HPSB Checklist and in this contract, including all "S" submittals.

d. Sustainability Action Plan.

e. Construction related documentation for the project Sustainability eNotebook and keep updated with regularly-scheduled Construction Quality Control Meetings. Include construction related documentation containing the following components:

(1) HPSB Checklist(s)

(2) Sustainability Action Plan

(3) Documentation illustrating HPSB Guiding Principles Requirements compliance, including "S" submittals

1.4.1 Sustainability Action Plan

Include the following information in the Sustainability Action Plan:

a. Analysis of each HPSB Guiding Principles Requirement and how project will comply. Final government approved narrative(s) must be included in the HPSB Checklist submittal.

b. Name and contact information for: Contractor's Point of Contact (POC) ensuring sustainability goals are accomplished and documentation is assembled. For TPC that include on-site visit by third party representative, provide list of required attendees.

c. Indoor Air Quality plan.

1.4.2 Calculations

Provide all calculations, product data, labels and product certifications required in this specification to demonstrate compliance with the HPSB Guiding Principles Requirements.

1.5 SUSTAINABILITY SUBMITTALS

Provide HPSB Checklist and other documentation in the Sustainability eNotebook to indicate compliance with the sustainability requirements of the project.

1.5.1 High Performance Sustainable Building (HPSB) Checklist

Provide construction documentation that provides proof of, and supports compliance with, the completed HPSB Checklist.

1.5.1.1 HPSB Checklist Submittals

Submit updated HPSB Checklist with each Sustainability eNotebook submittal. Include the final HPSB Checklist(s) with the interim DD1354 Real Property Record Submittal.

1.5.2 "S" Submittals for Sustainability Documentation

"S" submittals are the sustainability documentation requirements cited in the various sections of this contract. Submit the GPV sustainability documentation required in this section as "S" submittals in all affected UFGS Sections.

a. Highlight GPV compliance data in "S" submittal.

b. Add "S" submittals to the Sustainability eNotebook only after submittal approval, and bookmark them as required in paragraph SUSTAINABILITY ENOTEBOOK below.

c. Ensure all approved "S" submittals are included in each Sustainability eNotebook submittal.

1.5.3 Sustainability eNotebook

The Sustainability eNotebook is an electronic organizational file that serves as a repository for all required sustainability submittals. To support documentation of compliance with an approved HPSB checklist, provide and maintain a comprehensive and current Sustainability eNotebook. Include all required data in Sustainability eNotebook, to support full compliance with the HPSB Guiding Principles Requirements, including:

a. HPSB checklist

b. Sustainability Action Plan

c. Calculations

d. Labels

e. "S" submittals

f. Certifications, assessments, or validations and compliance report

1.5.3.1 Sustainability eNotebook Format

Provide Sustainability eNotebook in the form of an Adobe PDF file; bookmark each HPSB Guiding Principles Requirement and sub-bookmark at each document. Match format to HPSB Guiding Principles numbering system indicated herein. Maintain up-to-date information, such as spreadsheets, templates, with each current submittals.

Contracting Officer may deduct from the monthly progress payment accordingly if Sustainability eNotebook information is not current and on track per project goals.

1.5.3.2 Sustainability eNotebook Submittal Schedule

Provide Sustainability eNotebook Submittals at the following milestones of the project:

a. Preliminary Sustainability eNotebook

b. Submit preliminary Sustainability eNotebook with updated Preliminary High Performance and Sustainable Building Checklist at the first post award meeting in accordance with Section 01 30 00 ADMINISTRATIVE REQUIREMENTS.

c. Construction Quality Control Meetings.

d. Provide up-to-date GP documentation in the Sustainability eNotebook for each meeting.

e. Final Sustainability eNotebook

f. Submit updated Sustainability eNotebook with updated Final High Performance and Sustainable Building Checklist at Beneficial Occupancy Date (BOD). Final progress payment retainage may be held by Contracting Officer until Final Sustainability construction phase documentation is complete.

g. Amended Final Sustainability eNotebook

h. Amend and resubmit the Amended Final Sustainability eNotebook with Amended Final High Performance and Sustainable Building Checklist, to include post-occupancy corrections, updates, and requirements. Final progress payment retainage may be held by Contracting Officer until amended final sustainability documentation is complete. Submit electronic copy of the Amended Final Sustainability eNotebook Submittal to the Contracting Officer no later than 30 days after final GP determination.

1.6 DOCUMENTATION REQUIREMENTS

a. Incorporate each of the following HPSB Guiding Principles requirements into project and provide documentation that proves compliance with each listed requirement. Items below are organized by HPSB Guiding Principles. For life-cycle cost analysis requirements, one document with all analyses is acceptable, with Contracting Officer approval.

b. For each of the following paragraphs that require the use of products listed on Government-required websites, provide documentation of the process used to select products, or process used to determine why listed products do not meet project performance requirements.

1.6.1 Commissioning (Cx)

Develop and incorporate Commissioning requirements into the documents, and provide final commissioning report. Refer to Section 01 91 00.15 BUILDING COMMISSIONING and related documents for commissioning requirements.

1.6.2 Energy Efficient Products

Provide only energy-using products that are Energy Star Certified by the Environmental Protection Agency (EPA) or that meet or exceed the efficiency standard designated by the Federal Energy Management Program (FEMP). Where Energy Star or FEMP requirements have not been established, provide most efficient products that are life-cycle cost-effective. Provide only energy using products that meet FEMP requirements for low standby power consumption. Energy efficient products can be found at: https://www.energystar.gov/.

For construction submittal documentation, provide proof that product is labeled energy efficient and complies with the cited requirements.

1.6.3 Building-level Power Metering

Provide building-level meters for electricity, natural gas, and steam

where applicable.

1.6.3.1 Construction Submittal Documentation

Provide documentation of meter communication with the base-wide meter monitoring system, and manufacturer's data validating compatibility with base-wide system and component advanced meter requirements.

1.6.4 Indoor Water Use

Provide Construction Documentation proof that fixtures are labeled EPA WaterSense, for products available with EPA WaterSense labeling; for all other fixtures, proof they comply with EPA WaterSense efficiency requirements.

1.6.5 Indoor Water Metering

Provide building-level meters for potable water use. Provide the requirements cited in the following paragraphs:

1.6.5.1 Construction Submittal Documentation

Provide documentation of meter communication with the base-wide meter monitoring system, and manufacturer's data validating compatibility with base-wide system and component advanced meter requirements.

1.6.6 Outdoor Water Use

When there is no permanent irrigation system beyond plant establishment period, this element is met.

Where new irrigation is required beyond plant establishment period, provide only non-potable sources. Provide meters. Provide the requirements cited in the following paragraphs:

1.6.6.1 Construction Submittal Documentation

Provide documentation of meter communication with the base-wide meter monitoring system, and manufacturer's data validating compatibility with base-wide system and component advanced meter requirements.

1.6.7 Outdoor Water Meters

Provide meters for outdoor systems that use potable water. Provide the requirements cited in the following paragraphs:

1.6.7.1 Construction Submittal Documentation

Provide documentation of meter communication with the base-wide meter monitoring system, and manufacturer's data validating compatibility with base-wide system and component advanced meter requirements.

1.6.8 Moisture Control

Provide the following:

1.6.8.1 Construction Submittal Documentation

Ensure construction materials are separated and protected in accordance

with other sections in this contract document, with adequate humidity controls during construction. In accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA, includes plan for ongoing building moisture control.

1.6.9 Reduce Volatile Organic Compounds (VOC) (Low-Emitting Materials)

Meet the requirements of Table 3-1 at the end of this specification.

For Construction submittal documentation, provide certifications or labels that demonstrate compliance with cited requirements, based on the attached TABLE 3-1.

1.6.10 Indoor Air Quality During Construction

Prior to construction, create indoor air quality plan. Develop and implement an IAQ construction management plan during construction and flush building air before occupancy.

For new construction and for renovation of unoccupied existing buildings, meet the requirements of ICC IgCC 1001.3.1.5 (10.3.1.5) Indoor Air Quality (IAQ) Construction Management. Coordinate with moisture control requirements in Section 01 45 00 QUALITY CONTROL.

Provide documentation showing that after construction ends and prior to occupancy, HVAC filters were replaced and building air was flushed out in accordance with the cited standard.

1.6.11 Recycled Content

Comply with 40 CFR 247. Refer to: https://www.epa.gov/smm/comprehensive-procurement-guideline-cpg-program for assistance identifying products cited in 40 CFR 247. Selected products must comply with non-proprietary requirements of the Federal Acquisition Regulation and must meet performance requirements.

1.6.11.1 Construction Submittal Documentation

a. Provide manufacturers' documents stating the recycled content by material, or written justification for claiming one of the exceptions allowed on the cited website.

b. Substitutions: Submit for Government approval for proposed alternative products or systems that provide equivalent performance and appearance and have greater contribution to project recycled content requirements. For all such proposed substitutions, submit with the Sustainability Action Plan accompanied by product data demonstrating equivalence.

c. In order to complete compliance with FAR 52.223-9 Estimate of Percentage of Recovered Material Content for EPA Designated Items, refer to submittal requirement for recycled/recovered material content in Section 01 78 00 CLOSEOUT SUBMITTALS.

1.6.12 Bio-Based Products

Provide products and materials composed of the highest percentage of bio-based materials (including rapidly renewable resources and certified sustainably harvested products), consistent with FSRIA 9002 USDA

BioPreferred Program, to the maximum extent possible without jeopardizing the intended end use or detracting from the overall quality delivered to the end user and when available at a reasonable cost. Use only supplies and materials of a type and quality that conform to applicable specifications and standards.

Comply with FSRIA 9002 USDA BioPreferred Program. Refer to www.biopreferred.gov for the product categories and BioPreferred Catalog. Selected products must comply with non-proprietary requirements of the Federal Acquisition Regulation and must meet performance requirements. Provide the following documentation:

a. USDA BioPreferred label for each product; for bio-based products used on project but not listed with BioPreferred program, provide bio-based content and percentage.

b. In order to complete compliance with FAR 52.223-1 Biobased Product Certification, refer to submittal requirement for biobased products in Section 01 78 00 CLOSEOUT SUBMITTALS, paragraphs CERTIFICATION OF EPA DESIGNATED ITEMS and CERTIFICATION OF USDA DESIGNATED ITEMS.

1.6.13 Waste Material Management (Recycling – Construction)

Divert demolition and construction debris in accordance with Section 01 74 19 CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 SUSTAINABILITY COORDINATION

Provide sustainability focus and coordination at all meetings to achieve sustainability goals. Coordinate meeting requirements with other UFGS Sections meeting requirements in this project. Ensure the designated sustainability professional responsible for GP documentation participates in these meetings to coordinate documentation completion. Review GP sustainability requirements, HPSB Checklist documentation, Sustainability Action Plan, and completeness status of Sustainability eNotebook at the following meetings:

a. Pre-Construction Conference

b. Construction Quality Control Meetings

c. Facility Turnover Meetings

d. Conduct review no later than 60 days before final turnover and identify any outstanding issues that affect correct completion of all documentation, and actions that will achieve requirements. Conduct corrective actions prior to turnover, to ensure all requirements are achieved.

3.2 TABLE 3-1 VOLATILE ORGANIC COMPOUNDS (VOC) (LOW EMITTING MATERIALS) REQUIREMENTS

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ICC IgCC Chapter 8 (Materials) (Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	EMISSIONS REQUIREMENTS
Adhesives and Sealants	**CDPH/EHLB/Standard method V1.1 (California Section 01350)** (Use "office" or "classroom" space limits for all applications)	or	Adhesives (carpet, resilient, wood flooring; base cove; ceramic tile; drywall and panel; primers) Sealants (acoustical; firestop; HVAC Air duct; primers) Caulks	**SCAQMD Rule 1168** (Use "other" category for HVAC duct sealant) (for firestop adhesive, UFC 3-600-01 overrides conflicting requirements)
			Aerosol adhesives	**Section 3 of Green Seal Standard GS-36** (except: cleaners, solvent cements, and primers used with plastic piping and conduit in plumbing, fire suppression, and electrical systems; HVAC air duct sealants when the application space air temp is less than 40 F (4.5 C).

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ICC IgCC Chapter 8 (Materials) (Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	EMISSIONS REQUIREMENTS
Paints and Coatings	**CDPH/EHLB/Standard method V1.1 (California Section 01350)** (Use "office" or "classroom" space limits for all applications)	or	Flat and nonflat, nonflat high-gloss, specialty, basement specialty, fire-resistive, floor, low-solids, rust preventative, wood, reflective wall coatings; concrete/masonry sealers; primers; sealers; undercoaters; shellacs (clear and opaque); stains; varnishes; conjugated oil varnish; lacquer; clear brushing lacquer	**Green Seal Standard GS-11**

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ICC IgCC Chapter 8 (Materials) (Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	EMISSIONS REQUIREMENTS
Paints and Coatings	**CDPH/EHLB/Standard method V1.1 (California Section 01350)** (Use "office" or "classroom" space limits for all applications)	or	Concrete curing compounds; dry fog, faux finishing, graphic arts (sign paints), industrial maintenance, mastic texture, metallic pigmented, multicolor, recycled coatings; pretreatment wash primers, reactive penetrating sealers; specialty primers, wood preservatives, and zinc primers	**California Air Resources Board (CARB) Suggested Control Measure for Architectural Coatings** or **SCAQMD Rule 1113r**
Paints and Coatings	**CDPH/EHLB/Standard method V1.1 (California Section 01350)** (Use "office" or "classroom" space limits for all applications)	or	High-temperature coatings; stone consolidants; swimming-pool coatings; tub- and tile-refining coatings; and waterproofing membranes	**California Air Resources Board (CARB) Suggested Control Measure for Architectural Coatings**

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ICC IgCC Chapter 8 (Materials) (Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	EMISSIONS REQUIREMENTS
Floor Covering Materials	For carpet, all locations: **CDPH/EHLB/Standard Method V1.1 (California Section 01350)** or label for **Section 9** of **CDPH/EHLB/Standard Method V1.1 (California Section 01350)**		none	none
Insulation	**CDPH/EHLB/Standard method V1.1** (California Section 01350) (Use "office" or "classroom" space limits for all applications)		none	none

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ICC IgCC Chapter 8 (Materials) (Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	EMISSIONS REQUIREMENTS
Composite Wood, Wood Structural Panel, and Agrifiber Products, no added urea-formaldehyde resins including laminating adhesives for composite wood and agrifiber assemblies - particleboard, medium density fiberboard (MDF), wheatboard, strawboard, panel substrates, door cores	Third-party certification (approved by CARB) of **California Air Resource Board's (CARB) regulation**, Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products	or	none	**CDPH/EHLB/Standard method V1.1** (California Section 01350) (Use "office" or "classroom" space limits for all applications) (except: Structural panel components such as plywood, particle board, wafer board, and oriented strand board identified as "EXPOSURE 1," "EXTERIOR," or "HUD-APPROVED" are considered acceptable for interior use.)
Office Furniture Systems and Seating installed prior to occupancy	**ANSI/BIFMA X7.1 ANSI/BIFMA X7.1:** (95-percent of installed office furniture system workstations and seating units) **Section 7.6.2 of ANSI/BIFMA e3** (50-percent of office furniture system workstations and seating units)		none	none

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ICC IgCC Chapter 8 (Materials) (Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	EMISSIONS REQUIREMENTS
Ceiling and Wall assemblies and systems including: acoustical treatments; ceiling panels and tiles; tackable wall panels and coverings; wall coverings; wall and ceiling paneling and planking	**CDPH/EHLB/Standard method V1.1 (California Section 01350)** (Use "office" or "classroom" space limits for all applications)		none	none

-- End of Section --

NAVFAC HIGH PERFORMANCE AND SUSTAINABLE BUILDING CHECKLIST -- GOALS

PROJECT INFORMATION

Work Order No.: 1701820 FY 26 MILCON P No. / Customer Reference No.: P-1550

Project Title: SOF MARINE BATTALION / COMPANY / TEAM FACILITIES - A1 Battalion Headquarters Building

Location UIC/Name: MCB Camp Lejeune

NAVFAC Project Manager: Scott Littlefield Project Design Level: DBB

Facility Area: 73,356 U/M: SF Category Code: 14309 Facility #:

AE Contract # & T.O. N4008522D0002 AE Firm Sustainability Coordinator: Raymond Layton

AE Firm Name: MBF Architects, P.A.

Project Phase: ☐ Design Start / PDA ☑ Solicitation Documents Complete

Construction Contract Award Date (P): BOD (P):

SUSTAINABILITY DATA - GUIDING PRINCIPLES for SUSTAINABLE DEVELOPMENT

Use this form to collect Design Goals information to be recorded on the Sustainable and Energy Tab in eProjects

NOTE: 1. Mark "N/A" only when at least one of the listed justifications is applicable, and mark those justifications. Otherwise, mark "Yes."
2. If project is for more than one building for which tracking is required, complete a separate form for each building.

PRELIMINARY PROJECT INFORMATION

1 How many buildings are included in this project? 4

2 New building or stand-alone addition >/=10,000 GSF

-OR-

Existing building renovation (including additions) >/=10,000 GSF, and with a cost >$3M and 50% Estimated Replacement Cost (ERC)? Yes ☑ No ☐

3 Identify the building to be tracked in this tab: A1 - BN HQ

DESIGN DEVELOPMENT - DOCUMENTATION OF COMPLIANCE WITH GUIDING PRINCIPLES

I. Employ Integrated Design Principles

1 Integrated Design Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

2 Commissioning Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Systems commissioned

II. Optimize Energy Performance

3. Energy Efficiency Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Energy Savings Below Baseline % 33.10

(ii) Energy Standard

- [x] ASHRAE 90.1-2013 (06NOV16+)
- [ ] ASHRAE 90.1-2016
- [ ] IECC
- [ ] OTHER:

C. Energy Efficient Products

Goals In Compliance [x] Yes [ ] N/A

N/A due to

- [ ] Mission preclusion
- [ ] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

4. Renewable Energy

Goals In Compliance [ ] Yes [x] N/A

N/A due to

- [ ] Mission preclusion
- [x] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

A. Renewable energy technology types

- [ ] Geothermal
- [ ] Ground Source Heat Pumps
- [ ] Solar Photovoltaic
- [ ] Solar Thermal - domestic hot water
- [ ] Solar Thermal - space conditioning
- [ ] Daylighting (quantified passive)
- [ ] Mechanical (i.e., direct water pumping)
- [ ] Micro-hydro
- [ ] Concentrating (sterling)
- [ ] Wind

(i) Annual % of total load _____

(ii) System size (kwatts) _____

B. Solar Hot Water Percentage - 30% target

Goals In Compliance [ ] Yes [x] N/A

N/A due to

- [ ] Mission preclusion
- [x] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

(i) Annual % of total load _____

(ii) System size (kBTU/Year) _____

5. Meter (Energy)

Goals In Compliance [x] Yes [ ] N/A

N/A due to

- [ ] Mission preclusion
- [ ] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

6. Energy Use Intensity kBTU/Sq Ft/Year

(i) Total Design Energy Use Intensity (EUI): kBTU/Sq Ft/Year 38.4

III. Protect and Conserve Water

7. Indoor Water Use

A. Water-Efficient Products

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Total Design Indoor Water Use Intensity (WUI): Gallons/Sq Ft/Year 9

B. Indoor Water Meter

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

8. Outdoor Water Use

A. Outdoor Water Meter (for 25,000 SF of irrigation)

(i) Is there a permanent irrigation system serving more than 25,000 SF of landscaping?

☐ Yes ☑ No

(ii) Water Meter

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Water-efficient landscape

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

9. Alternative Water Use (indoor or outdoor water)

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☑ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

Methods Proposed:

☐ Air Handler Condensate Capture ☐ Reclaimed Water
☐ Grey Water ☐ Treated Wastewater
☐ Harvested Rainwater ☐ OTHER:

10. Stormwater Management - update the LID Data tab

IV. Enhance Indoor Environmental Quality

11. Ventilation and Thermal Comfort

A. Ventilation

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Thermal Comfort

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

12. Daylighting and Lighting Controls

A. Daylight

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☑ Installation/region issue

B. Automatic dimming controls

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☑ Installation/region issue

13. Indoor Air Quality

A. Moisture Control

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

B. Low-Emitting Materials

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

C. Indoor Air Quality during Construction

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

14. Occupant Health and Wellness

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

V. Reduce the Environmental Impact of Materials

15. Material Content and Performance

A. Resource Conservation and Recovery Act (RCRA) Section 6002 (recycled content)

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Farm Security and Rural Investment Act (FSRIA) section 9002 (Biobased content)

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

16. Waste Management

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

17. Waste Diversion - 60% target

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Percent diverted _____

VI. Assess and Consider Climate Change Risks

18. Address Climate Change Risk

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

THIRD PARTY CERTIFICATION INFORMATION

Is this building pursuing Third Party Certification? ☑ Yes ☐ No

N/A due to ☐ Installation/region issue ☐ Mission preclusion ☐ Renovation only: not part of scope

Sustainability Third Party Certification Rating

Third Party Certification Rating System and Level

☐ USGBC LEED Certified
☐ USGBC LEED Silver
☐ USGBC LEED Gold
☐ USGBC LEED Platinum
☐ USGBC "Guiding Principles Assessment"
☐ OTHER
☐ GBI Green Globes 1 Globe
☐ GBI Green Globes 2 Globe
☐ GBI Green Globes 3 Globe
☐ GBI Green Globes 4 Globe
☑ GBI "Guiding Principles Compliance"

i. Third Party Certification Rating system - Other

This page is intentionally left blank.

NAVFAC HIGH PERFORMANCE AND SUSTAINABLE BUILDING CHECKLIST -- GOALS

PROJECT INFORMATION

Work Order No.: 1701820 FY 26 MILCON P No. / Customer Reference No.: P-1550

Project Title: SOF MARINE BATTALION / COMPANY / TEAM FACILITIES - A2-1 Company / Team Building

Location UIC/Name: MCB Camp Lejeune

NAVFAC Project Manager: Scott Littlefield Project Design Level: DBB

Facility Area: 63,573 U/M: SF Category Code: 14309 Facility #:

AE Contract # & T.O. N4008522D0002 AE Firm Sustainability Coordinator: Raymond Layton

AE Firm Name: MBF Architects, P.A.

Project Phase: ☐ Design Start / PDA ☑ Solicitation Documents Complete

Construction Contract Award Date (P): BOD (P):

SUSTAINABILITY DATA - GUIDING PRINCIPLES for SUSTAINABLE DEVELOPMENT

Use this form to collect Design Goals information to be recorded on the Sustainable and Energy Tab in eProjects

NOTE: 1. Mark "N/A" only when at least one of the listed justifications is applicable, and mark those justifications. Otherwise, mark "Yes."
2. If project is for more than one building for which tracking is required, complete a separate form for each building.

PRELIMINARY PROJECT INFORMATION

1 How many buildings are included in this project? 4

2 New building or stand-alone addition >/=10,000 GSF

-OR-

Existing building renovation (including additions) >/=10,000 GSF, and with a cost >$3M and 50% Estimated Replacement Cost (ERC)? Yes ☑ No ☐

3 Identify the building to be tracked in this tab: A2-1 - CO Bldg

DESIGN DEVELOPMENT - DOCUMENTATION OF COMPLIANCE WITH GUIDING PRINCIPLES

I. Employ Integrated Design Principles

1 Integrated Design Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

2 Commissioning Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Systems commissioned

II. Optimize Energy Performance

3. Energy Efficiency Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Energy Savings Below Baseline % 31.20

(ii) Energy Standard

- [x] ASHRAE 90.1-2013 (06NOV16+)
- [ ] ASHRAE 90.1-2016
- [ ] IECC
- [ ] OTHER:

C. Energy Efficient Products

Goals In Compliance [x] Yes [ ] N/A

N/A due to

- [ ] Mission preclusion
- [ ] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

4. Renewable Energy

Goals In Compliance [ ] Yes [x] N/A

N/A due to

- [ ] Mission preclusion
- [x] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

A. Renewable energy technology types

- [ ] Geothermal
- [ ] Ground Source Heat Pumps
- [ ] Solar Photovoltaic
- [ ] Solar Thermal - domestic hot water
- [ ] Solar Thermal - space conditioning
- [ ] Daylighting (quantified passive)
- [ ] Mechanical (i.e., direct water pumping)
- [ ] Micro-hydro
- [ ] Concentrating (sterling)
- [ ] Wind

(i) Annual % of total load _____

(ii) System size (kwatts) _____

B. Solar Hot Water Percentage - 30% target

Goals In Compliance [ ] Yes [x] N/A

N/A due to

- [ ] Mission preclusion
- [x] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

(i) Annual % of total load _____

(ii) System size (kBTU/Year) _____

5. Meter (Energy)

Goals In Compliance [x] Yes [ ] N/A

N/A due to

- [ ] Mission preclusion
- [ ] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

6. Energy Use Intensity kBTU/Sq Ft/Year

(i) Total Design Energy Use Intensity (EUI): kBTU/Sq Ft/Year 40.1

III. Protect and Conserve Water

7. Indoor Water Use

A. Water-Efficient Products

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Total Design Indoor Water Use Intensity (WUI): Gallons/Sq Ft/Year 10

B. Indoor Water Meter

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

8. Outdoor Water Use

A. Outdoor Water Meter (for 25,000 SF of irrigation)

(i) Is there a permanent irrigation system serving more than 25,000 SF of landscaping?

☐ Yes ☑ No

(ii) Water Meter

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Water-efficient landscape

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

9. Alternative Water Use (indoor or outdoor water)

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☑ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

Methods Proposed:

☐ Air Handler Condensate Capture ☐ Reclaimed Water
☐ Grey Water ☐ Treated Wastewater
☐ Harvested Rainwater ☐ OTHER:

10. Stormwater Management - update the LID Data tab

IV. Enhance Indoor Environmental Quality

11. Ventilation and Thermal Comfort

A. Ventilation

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Thermal Comfort

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

12. Daylighting and Lighting Controls

A. Daylight

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☑ Installation/region issue

B. Automatic dimming controls

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☑ Installation/region issue

13. Indoor Air Quality

A. Moisture Control

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

B. Low-Emitting Materials

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

C. Indoor Air Quality during Construction

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

14. Occupant Health and Wellness

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

V. Reduce the Environmental Impact of Materials

15. Material Content and Performance

A. Resource Conservation and Recovery Act (RCRA) Section 6002 (recycled content)

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Farm Security and Rural Investment Act (FSRIA) section 9002 (Biobased content)

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

16. Waste Management

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

17. Waste Diversion - 60% target

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Percent diverted _____

VI. Assess and Consider Climate Change Risks

18. Address Climate Change Risk

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

THIRD PARTY CERTIFICATION INFORMATION

Is this building pursuing Third Party Certification? ☑ Yes ☐ No

N/A due to ☐ Installation/region issue ☐ Mission preclusion ☐ Renovation only: not part of scope

Sustainability Third Party Certification Rating

Third Party Certification Rating System and Level

☐ USGBC LEED Certified
☐ USGBC LEED Silver
☐ USGBC LEED Gold
☐ USGBC LEED Platinum
☐ USGBC "Guiding Principles Assessment"
☐ OTHER
☐ GBI Green Globes 1 Globe
☐ GBI Green Globes 2 Globe
☐ GBI Green Globes 3 Globe
☐ GBI Green Globes 4 Globe
☑ GBI "Guiding Principles Compliance"

i. Third Party Certification Rating system - Other

This page is intentionally left blank.

NAVFAC HIGH PERFORMANCE AND SUSTAINABLE BUILDING CHECKLIST -- GOALS

PROJECT INFORMATION

Work Order No.: 1701820 FY 26 MILCON P No. / Customer Reference No.: P-1550

Project Title: SOF MARINE BATTALION / COMPANY / TEAM FACILITIES - A2-2 Company / Team Building

Location UIC/Name: MCB Camp Lejeune

NAVFAC Project Manager: Scott Littlefield Project Design Level: DBB

Facility Area: 63,573 U/M: SF Category Code: 14309 Facility #:

AE Contract # & T.O. N4008522D0002 AE Firm Sustainability Coordinator: Raymond Layton

AE Firm Name: MBF Architects, P.A.

Project Phase: ☐ Design Start / PDA ☑ Solicitation Documents Complete

Construction Contract Award Date (P): BOD (P):

SUSTAINABILITY DATA - GUIDING PRINCIPLES for SUSTAINABLE DEVELOPMENT

Use this form to collect Design Goals information to be recorded on the Sustainable and Energy Tab in eProjects

NOTE: 1. Mark "N/A" only when at least one of the listed justifications is applicable, and mark those justifications. Otherwise, mark "Yes."
2. If project is for more than one building for which tracking is required, complete a separate form for each building.

PRELIMINARY PROJECT INFORMATION

1 How many buildings are included in this project? 4

2 New building or stand-alone addition >/=10,000 GSF

-OR-

Existing building renovation (including additions) >/=10,000 GSF, and with a cost >$3M and 50% Estimated Replacement Cost (ERC)? Yes ☑ No ☐

3 Identify the building to be tracked in this tab: A2-2 - CO Bldg

DESIGN DEVELOPMENT - DOCUMENTATION OF COMPLIANCE WITH GUIDING PRINCIPLES

I. Employ Integrated Design Principles

1 Integrated Design Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

2 Commissioning Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Systems commissioned

II. Optimize Energy Performance

3. Energy Efficiency Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Energy Savings Below Baseline % 31.20

(ii) Energy Standard

- [x] ASHRAE 90.1-2013 (06NOV16+)
- [ ] ASHRAE 90.1-2016
- [ ] IECC
- [ ] OTHER:

C. Energy Efficient Products

Goals In Compliance [x] Yes [ ] N/A

N/A due to

- [ ] Mission preclusion
- [ ] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

4. Renewable Energy

Goals In Compliance [ ] Yes [x] N/A

N/A due to

- [ ] Mission preclusion
- [x] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

A. Renewable energy technology types

- [ ] Geothermal
- [ ] Ground Source Heat Pumps
- [ ] Solar Photovoltaic
- [ ] Solar Thermal - domestic hot water
- [ ] Solar Thermal - space conditioning
- [ ] Daylighting (quantified passive)
- [ ] Mechanical (i.e., direct water pumping)
- [ ] Micro-hydro
- [ ] Concentrating (sterling)
- [ ] Wind

(i) Annual % of total load _____

(ii) System size (kwatts) _____

B. Solar Hot Water Percentage - 30% target

Goals In Compliance [ ] Yes [x] N/A

N/A due to

- [ ] Mission preclusion
- [x] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

(i) Annual % of total load _____

(ii) System size (kBTU/Year) _____

5. Meter (Energy)

Goals In Compliance [x] Yes [ ] N/A

N/A due to

- [ ] Mission preclusion
- [ ] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

6. Energy Use Intensity kBTU/Sq Ft/Year

(i) Total Design Energy Use Intensity (EUI): kBTU/Sq Ft/Year 40.1

III. Protect and Conserve Water

7. Indoor Water Use

A. Water-Efficient Products

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Total Design Indoor Water Use Intensity (WUI): Gallons/Sq Ft/Year 10

B. Indoor Water Meter

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

8. Outdoor Water Use

A. Outdoor Water Meter (for 25,000 SF of irrigation)

(i) Is there a permanent irrigation system serving more than 25,000 SF of landscaping?

☐ Yes ☑ No

(ii) Water Meter

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Water-efficient landscape

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

9. Alternative Water Use (indoor or outdoor water)

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☑ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

Methods Proposed:

☐ Air Handler Condensate Capture ☐ Reclaimed Water
☐ Grey Water ☐ Treated Wastewater
☐ Harvested Rainwater ☐ OTHER:

10. Stormwater Management - update the LID Data tab

IV. Enhance Indoor Environmental Quality

11. Ventilation and Thermal Comfort

A. Ventilation

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Thermal Comfort

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

12. Daylighting and Lighting Controls

A. Daylight

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☑ Installation/region issue

B. Automatic dimming controls

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☑ Installation/region issue

13. Indoor Air Quality

A. Moisture Control

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

B. Low-Emitting Materials

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

C. Indoor Air Quality during Construction

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

14. Occupant Health and Wellness

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

V. Reduce the Environmental Impact of Materials

15. Material Content and Performance

A. Resource Conservation and Recovery Act (RCRA) Section 6002 (recycled content)

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Farm Security and Rural Investment Act (FSRIA) section 9002 (Biobased content)

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

16. Waste Management

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

17. Waste Diversion - 60% target

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Percent diverted _____

VI. Assess and Consider Climate Change Risks

18. Address Climate Change Risk

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

THIRD PARTY CERTIFICATION INFORMATION

Is this building pursuing Third Party Certification? ☑ Yes ☐ No

N/A due to ☐ Installation/region issue ☐ Mission preclusion ☐ Renovation only: not part of scope

Sustainability Third Party Certification Rating

Third Party Certification Rating System and Level

☐ USGBC LEED Certified
☐ USGBC LEED Silver
☐ USGBC LEED Gold
☐ USGBC LEED Platinum
☐ USGBC "Guiding Principles Assessment"
☐ OTHER
☐ GBI Green Globes 1 Globe
☐ GBI Green Globes 2 Globe
☐ GBI Green Globes 3 Globe
☐ GBI Green Globes 4 Globe
☑ GBI "Guiding Principles Compliance"

i. Third Party Certification Rating system - Other

This page is intentionally left blank.

NAVFAC HIGH PERFORMANCE AND SUSTAINABLE BUILDING CHECKLIST -- GOALS

PROJECT INFORMATION

Work Order No.: 1701820 FY 26 MILCON P No. / Customer Reference No.: P-1550

Project Title: SOF MARINE BATTALION / COMPANY / TEAM FACILITIES - A3 Comapny Storage Building

Location UIC/Name: MCB Camp Lejeune

NAVFAC Project Manager: Scott Littlefield Project Design Level: DBB

Facility Area: 17,514 U/M: SF Category Code: 14309 Facility #:

AE Contract # & T.O. N4008522D0002 AE Firm Sustainability Coordinator: Raymond Layton

AE Firm Name: MBF Architects, P.A.

Project Phase: ☐ Design Start / PDA ☑ Solicitation Documents Complete

Construction Contract Award Date (P): BOD (P):

SUSTAINABILITY DATA - GUIDING PRINCIPLES for SUSTAINABLE DEVELOPMENT

Use this form to collect Design Goals information to be recorded on the Sustainable and Energy Tab in eProjects

NOTE: 1. Mark "N/A" only when at least one of the listed justifications is applicable, and mark those justifications. Otherwise, mark "Yes."
2. If project is for more than one building for which tracking is required, complete a separate form for each building.

PRELIMINARY PROJECT INFORMATION

1 How many buildings are included in this project? 4

2 New building or stand-alone addition >/=10,000 GSF

-OR-

Existing building renovation (including additions) >/=10,000 GSF, and with a cost >$3M and 50% Estimated Replacement Cost (ERC)? Yes ☑ No ☐

3 Identify the building to be tracked in this tab: A3 - CO Stg

DESIGN DEVELOPMENT - DOCUMENTATION OF COMPLIANCE WITH GUIDING PRINCIPLES

I. Employ Integrated Design Principles

1 Integrated Design Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

2 Commissioning Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Systems commissioned

II. Optimize Energy Performance

3. Energy Efficiency Goals — In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Energy Savings Below Baseline % 41.30

(ii) Energy Standard

- [x] ASHRAE 90.1-2013 (06NOV16+)
- [ ] ASHRAE 90.1-2016
- [ ] IECC
- [ ] OTHER:

C. Energy Efficient Products

Goals In Compliance [x] Yes [ ] N/A

N/A due to

- [ ] Mission preclusion
- [ ] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

4. Renewable Energy

Goals In Compliance [ ] Yes [x] N/A

N/A due to

- [ ] Mission preclusion
- [x] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

A. Renewable energy technology types

- [ ] Geothermal
- [ ] Ground Source Heat Pumps
- [ ] Solar Photovoltaic
- [ ] Solar Thermal - domestic hot water
- [ ] Solar Thermal - space conditioning
- [ ] Daylighting (quantified passive)
- [ ] Mechanical (i.e., direct water pumping)
- [ ] Micro-hydro
- [ ] Concentrating (sterling)
- [ ] Wind

(i) Annual % of total load _____

(ii) System size (kwatts) _____

B. Solar Hot Water Percentage - 30% target

Goals In Compliance [ ] Yes [x] N/A

N/A due to

- [ ] Mission preclusion
- [x] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

(i) Annual % of total load _____

(ii) System size (kBTU/Year) _____

5. Meter (Energy)

Goals In Compliance [x] Yes [ ] N/A

N/A due to

- [ ] Mission preclusion
- [ ] Not LCCE
- [ ] Installation/region issue
- [ ] Building/site issue
- [ ] Renovation only: not part of scope

6. Energy Use Intensity kBTU/Sq Ft/Year

(i) Total Design Energy Use Intensity (EUI): kBTU/Sq Ft/Year 53.7

III. Protect and Conserve Water

7. Indoor Water Use

A. Water-Efficient Products

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Total Design Indoor Water Use Intensity (WUI): Gallons/Sq Ft/Year 4

B. Indoor Water Meter

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

8. Outdoor Water Use

A. Outdoor Water Meter (for 25,000 SF of irrigation)

(i) Is there a permanent irrigation system serving more than 25,000 SF of landscaping?

☐ Yes ☑ No

(ii) Water Meter

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Water-efficient landscape

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

9. Alternative Water Use (indoor or outdoor water)

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☑ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

Methods Proposed:

☐ Air Handler Condensate Capture ☐ Reclaimed Water
☐ Grey Water ☐ Treated Wastewater
☐ Harvested Rainwater ☐ OTHER:

10. Stormwater Management - update the LID Data tab

IV. Enhance Indoor Environmental Quality

11. Ventilation and Thermal Comfort

A. Ventilation

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Thermal Comfort

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

12. Daylighting and Lighting Controls

A. Daylight

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☑ Installation/region issue

B. Automatic dimming controls

Goals In Compliance ☐ Yes ☑ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☑ Installation/region issue

13. Indoor Air Quality

A. Moisture Control

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

B. Low-Emitting Materials

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

C. Indoor Air Quality during Construction

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

14. Occupant Health and Wellness

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue

☐ Not LCCE ☐ Renovation only: not part of scope

☐ Installation/region issue

V. Reduce the Environmental Impact of Materials

15. Material Content and Performance

A. Resource Conservation and Recovery Act (RCRA) Section 6002 (recycled content)

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

B. Farm Security and Rural Investment Act (FSRIA) section 9002 (Biobased content)

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

16. Waste Management

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

17. Waste Diversion - 60% target

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

(i) Percent diverted _____

VI. Assess and Consider Climate Change Risks

18. Address Climate Change Risk

Goals In Compliance ☑ Yes ☐ N/A

N/A due to

☐ Mission preclusion ☐ Building/site issue
☐ Not LCCE ☐ Renovation only: not part of scope
☐ Installation/region issue

THIRD PARTY CERTIFICATION INFORMATION

Is this building pursuing Third Party Certification? ☑ Yes ☐ No

N/A due to ☐ Installation/region issue ☐ Mission preclusion ☐ Renovation only: not part of scope

Sustainability Third Party Certification Rating

Third Party Certification Rating System and Level

☐ USGBC LEED Certified
☐ USGBC LEED Silver
☐ USGBC LEED Gold
☐ USGBC LEED Platinum
☐ USGBC "Guiding Principles Assessment"
☐ OTHER
☐ GBI Green Globes 1 Globe
☐ GBI Green Globes 2 Globe
☐ GBI Green Globes 3 Globe
☐ GBI Green Globes 4 Globe
☑ GBI "Guiding Principles Compliance"

i. Third Party Certification Rating system - Other

This page is intentionally left blank.

SECTION 01 35 26

GOVERNMENTAL SAFETY REQUIREMENTS
05/24, CHG 1: 05/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 52.2	(2025) Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ANSI/ASSP A10.34	(2021) Protection of the Public on or Adjacent to Construction Sites
ANSI/ASSP A10.44	(2020) Control of Energy Sources (Lockout/Tagout) for Construction and Demolition Operations

ASTM INTERNATIONAL (ASTM)

ASTM D6245	(2012) Using Indoor Carbon Dioxide Concentrations to Evaluate Indoor Air Quality and Ventilation
ASTM D6345	(2010) Standard Guide for Selection of Methods for Active, Integrative Sampling of Volatile Organic Compounds in Air
ASTM F855	(2020) Standard Specifications for Temporary Protective Grounds to Be Used on De-energized Electric Power Lines and Equipment

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 1048	(2016) Guide for Protective Grounding of Power Lines
IEEE C2	(2023) National Electrical Safety Code

INTERNATIONAL SAFETY EQUIPMENT ASSOCIATION (ISEA)

ANSI/ISEA Z89.1	(2014; R 2019) American National Standard for Industrial Head Protection

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA Z535.2	(2011; R 2017) Environmental and Facility Safety Signs

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 51B	(2024) Standard for Fire Prevention During Welding, Cutting, and Other Hot Work
NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 70E	(2024) Standard for Electrical Safety in the Workplace
NFPA 241	(2022; ERTA 22-1) Standard for Safeguarding Construction, Alteration, and Demolition Operations

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

ANSI/SMACNA 008	(2007) IAQ Guidelines for Occupied Buildings Under Construction, 2nd Edition

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

10 CFR 20	Standards for Protection Against Radiation
29 CFR 1910	Occupational Safety and Health Standards
29 CFR 1915	Confined and Enclosed Spaces and Other Dangerous Atmospheres in Shipyard Employment
29 CFR 1926	Safety and Health Regulations for Construction
49 CFR 173	Shippers - General Requirements for Shipments and Packagings
CPL 2.100	(1995) Application of the Permit-Required Confined Spaces (PRCS) Standards, 29 CFR 1910.146

1.2 DEFINITIONS

The following definitions are for the convenience of the reader. If there is a referenced document in the text of this specification section, that is the document that should define terms for that paragraph. If further clarification is needed, contact the Contracting Officer.

1.2.1 Site Safety and Health Officer (SSHO)

A Contractor Employee that is responsible for overseeing and ensuring implementation of the prime Contractor's Safety and Occupational Health (SOH) program according to the Contract, EM 385-1-1, applicable federal, state, and local requirements.

1.2.1.1 Level One SSHO

A designated employee with full-time SOH responsibility that meets and follows the requirements of EM 385-1-1.

1.2.1.2 Level Two SSHO

A designated employee with Level Two SSHO responsibility that meets and follows the requirements of EM 385-1-1. Level Two SSHOs cannot be assigned to projects that have a residual Risk Assessment Code (RAC) of high or extremely high.

1.2.1.3 Level Three SSHO

A designated Qualified Person or Competent Person with SOH responsibility that meets and follows the requirements of EM 385-1-1. Level 3 SSHOs cannot be assigned to projects that have a residual RAC of high or extremely high.

1.2.1.4 Alternate SSHO

An employee that meets the definition of the contract-required level SSHO, but is not the primary SSHO.

1.2.2 Competent Person (CP)

The CP is a person designated in writing, who, through training, knowledge and experience, is capable of identifying, evaluating, and addressing existing and predictable hazards in the working environment or working conditions that are unsanitary, hazardous, or dangerous to personnel, and who has authorization to take prompt corrective measures to eliminate them.

1.2.3 Qualified Person (QP)

The QP is a person designated in writing, who, by possession of a recognized degree, certificate, or professional standing, or extensive knowledge, training, and experience, has successfully demonstrated their ability to solve or resolve problems related to the subject matter, the work, or the project.

1.3 SUBMITTALS

Government Acceptance or Approval does not remove responsibility from the Contractors for their actions or liability.

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Accident Prevention Plan (APP); G

Final IAQ Management Plan; S

Indoor Air Quality (IAQ) Management Plan; G

SD-06 Test Reports

Accident Reports; G

LHE Inspection Reports

Monthly Exposure Reports; G

SD-07 Certificates

Activity Hazard Analysis (AHA); G

Certificate of Compliance

Contractor Safety Self-Evaluation Checklist

Hot Work Permit

License Certificates

Portable Gauge Operations Planning Worksheet; G

Radiography Operation Planning Work Sheet; G

Standard Lift Plan; G

Critical Lift Plan; G

1.4 PUBLIC HEALTH EMERGENCIES

In the event of a declared public health emergency, follow safety precautions as required by the Occupational Safety and Health Administration (OSHA) www.osha.gov, the Centers for Disease Control and Prevention (CDC) www.cdc.gov, and as required by federal, state and local requirements.

1.5 MONTHLY EXPOSURE REPORTS

Provide a Monthly Exposure Report by the fifth day of each month for the previous month. This report is a compilation of employee-hours worked each month for all site workers, both Prime and subcontractor. Failure to submit the report may result in retention of up to 10 percent of the progress payment.

1.6 CONTRACTOR SAFETY SELF-EVALUATION CHECKLIST

Contracting Officer will provide a "Contractor Safety Self-Evaluation checklist" to the Contractor at the preconstruction conference. Complete the checklist monthly and submit with each request for payment voucher. This submission is required monthly even when a payment voucher is not

requested. An acceptable score of 90 or greater is required. Failure to submit the completed safety self-evaluation checklist or achieve a score of at least 90 may result in retention of up to 10 percent of the voucher. The Contractor Safety Self-Evaluation checklist can be found on the Whole Building Design Guide website at www.wbdg.org/dod/ufgs/ufgs-01-35-26

1.7 REGULATORY REQUIREMENTS

In addition to the detailed requirements included in the provisions of this Contract, comply with the most recent edition of USACE EM 385-1-1, and the following federal, state, and local laws, ordinances, criteria, rules and regulations at the date of the Solicitation for this Contract. Submit matters of interpretation of standards to the appropriate administrative agency for resolution before starting work. Where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary, the most stringent requirements govern.

1.7.1 Subcontractor Safety Requirements

For this Contract, neither Contractor nor any subcontractor may enter into Contract with any subcontractor that fails to meet the following requirements. The term subcontractor in this and the following paragraphs means any entity holding a Contract with the Contractor or with a subcontractor at any tier.

1.7.1.1 Experience Modification Rate (EMR)

Subcontractors on this Contract must have an effective EMR less than or equal to 1.10, as computed by the National Council on Compensation Insurance (NCCI) or if not available, as computed by the state agency's rating bureau in the state where the subcontractor is registered, when entering into a subcontract agreement with the Prime Contractor or a subcontractor at any tier. The Prime Contractor may submit a written request for additional consideration to the Contracting Officer where the specified acceptable EMR range cannot be achieved. Relaxation of the EMR range will only be considered for approval on a case-by-case basis for special conditions and must not be anticipated as tacit approval. Contractor's Site Safety and Health Officer (SSHO) must collect and maintain the certified EMR ratings for all subcontractors on the project and make them available to the Government at the Government's request.

1.7.1.2 OSHA Days Away from Work, Restricted Duty, or Job Transfer (DART) Rate

Subcontractors on this Contract must have a DART rate, calculated from the most recent, complete calendar year, less than or equal to 3.4 when entering into a subcontract agreement with the Prime Contractor or a subcontractor at any tier. The OSHA Dart Rate is calculated using the following formula:

(N/EH) x 200,000

Where:

N = number of injuries and illnesses with days away, restricted work, or job transfer

EH = total hours worked by all employees during most recent, complete calendar year

200,000 = base for 100 full-time equivalent workers (working 40-hours per week, 50 weeks per year)

The Prime Contractor may submit a written request for additional consideration to the Contracting Officer where the specified acceptable OSHA Dart rate range cannot be achieved for a particular subcontractor. Relaxation of the OSHA DART rate range will only be considered for approval on a case-by-case basis for special conditions and must not be anticipated as tacit approval. Contractor's Site Safety and Health Officer (SSHO) must collect and maintain self-certified OSHA DART rates for all subcontractors on the project and make them available to the Government at the Government's request.

1.8 SITE QUALIFICATIONS, DUTIES, AND MEETINGS

1.8.1 Site Safety and Health Officer (SSHO)

1.8.1.1 Qualifications of SSHO

All SSHOs will have met the training, experience requirements identified in the EM 385-1-1 and this Contract.

1.8.1.2 Duties of SSHO

All SSHOs will carry out the roles and responsibilities as identified in this Contract and the EM 385-1-1. All SSHOs will be designated on an ENG Form 6282, provided by the Contracting Officer. Superintendent, QC Manager, and SSHO are subject to dismissal if their required duties are not being effectively carried out. If either the Superintendent, QC Manager, or SSHO are dismissed, project work will be stopped and will not be allowed to resume until a suitable replacement is approved and the above duties are again being effectively carried out.

1.8.1.3 Safety Meetings

Conduct safety meetings to review past activities, plan for new or changed operations, review pertinent aspects of appropriate AHA (by trade), establish safe working procedures for anticipated hazards, and provide pertinent Safety and Occupational Health (SOH) training and motivation. Conduct meetings at least once a month for all supervisors at the project location. The SSHO, supervisors, or foremen must conduct meetings at least once a week for the trade workers. Document meeting minutes to include the date, persons in attendance, subjects discussed, and names of individual(s) who conducted the meeting. Maintain documentation on-site and furnish copies to the Contracting Officer on request. Notify the Contracting Officer of all scheduled meetings 7 calendar days in advance.

1.8.2 Roles and Responsibilities of Prime Contractor and SSHO

The Prime Contractor and SSHO must ensure that the requirements of all applicable OSHA and EM 385-1-1 are met for the project. The Prime Contractor must ensure an SSHO or an equally qualified Alternate SSHO(s) is at the worksite at all times to implement and administer the Contractor's safety program and Government accepted Accident Prevention Plan. If the required SSHO has to temporarily (that is, up to 24 hours / 1 day) leave the site of work due to unforeseen or emergency situations, a

Level One, Two, or Three SSHO may be used in the interim and must be on the site of work at all times when work is being performed.

If the SSHO must be off-site for a period longer than 24 hours / 1 day, a qualified alternate that meets the contract requirements must be onsite.

a. Prime contractor must ensure all SSHOs will:

(1) Are designated on an ENG Form 6282.

(2) Meet minimum training and experience requirements identified in EM 385-1-1.

(3) Execute roles and responsibilities identified in EM 385-1-1.

1.8.3 Additional Requirements

The Level One SSHO must not serve as the Quality Control Manager. The One SSHO must not serve as the Superintendent.

1.8.4 Contract Site Safety And Health Officer(s)(SSHOs) Minimum Requirements

Provide a minimum of one Level One SSHO that meets the requirements of EM 385-1-1 for this project.

1.8.5 Competent Person for Confined Space Entry

Provide a CP for Confined Space Entry who meets the requirements of EM 385-1-1 and herein. The CP for Confined Space Entry must supervise the entry into each confined space in accordance with EM 385-1-1.

1.8.6 Qualified Trainer Requirements

Individuals qualified to instruct the 40-hour contract safety awareness course, or portions thereof, must meet the definition of a Competent Person Trainer as defined in the EM 385-1-1, and, at a minimum, possess a working knowledge of the following subject areas: EM 385-1-1, Electrical Standards, Lockout/Tagout, Fall Protection, Confined Space Entry for Construction; Excavation, Trenching and Soil Mechanics, and Scaffolds in accordance with 29 CFR 1926.

Instructors are required to:

a. Prepare class presentations that cover construction-related safety requirements.

b. Ensure that all attendees attend all sessions by using a class roster signed daily by each attendee. Maintain copies of the roster for at least 5 years. This is a certification class and must be attended 100 percent. In cases of emergency where an attendee cannot make it to a session, the attendee can make it up in another class session for the same subject.

c. Update training course materials whenever an update of the EM 385-1-1 becomes available.

d. Provide a written exam of at least 50 questions. Students are required to answer 80 percent correctly to pass.

e. Request, review and incorporate student feedback into a continuous course improvement program.

1.8.7 Preconstruction Conference

a. Contractor representatives who have a responsibility or significant role in accident prevention on the project must attend the preconstruction conference. This includes the project superintendent, Site Safety and Occupational Health Officer, quality control manager, or any other assigned safety and health professionals who participated in the development of the APP (including the Activity Hazard Analyses (AHAs) and special plans, program and procedures associated with it).

b. Discuss the details of the submitted APP to include incorporated plans, programs, procedures and a listing of anticipated AHAs that will be developed and implemented during the performance of the Contract. This list of proposed AHAs will be reviewed and an agreement will be reached between the Contractor and the Contracting Officer as to which phases will require an analysis. In addition, establish a schedule for the preparation, submittal, and Government review of AHAs to preclude project delays. The creation of the APP and Schedule will be created after being given Notice to Proceed.

c. Deficiencies in the submitted APP, identified during the Contracting Officer's review, must be corrected, and the APP re-submitted for review prior to the start of construction. Work is not permitted to begin until an APP is established that is acceptable to the Contracting Officer.

1.9 ACCIDENT PREVENTION PLAN (APP)

1.9.1 Accident Prevention Plan (APP)

Submit the Accident Prevention Plan (APP) for review and acceptance by the Government at least 15 calendar days prior to the start, after being given Notice to Proceed. A competent person must prepare the written site-specific APP. Prepare the APP in accordance with the format and requirements of EM 385-1-1, ENG Form 6293, and herein. The APP must be job-specific and address any unusual or unique aspects of the project or activity for which it is written. The APP must interface with the Contractor's overall safety and occupational health program referenced in the APP in the applicable APP element, and made site-specific. Describe the methods to evaluate past safety performance of potential subcontractors in the selection process. Also, describe innovative methods used to ensure and monitor safe work practices of subcontractors. The Government considers the Prime Contractor to be the "controlling employer" for all worksite safety and health of the subcontractors. Contractors are responsible for informing their subcontractors of the safety provisions under the terms of the Contract and the penalties for noncompliance, coordinating the work to prevent one craft from interfering with or creating hazardous working conditions for other crafts, and inspecting subcontractor operations to ensure that accident prevention responsibilities are being carried out. The APP must be signed in accordance with the APP and ENG Form 6293 Accident Prevention Plan Worksheet. The SSHO must provide and maintain the APP and a log of signatures by each subcontractor foreman, attesting that they have read and understand the APP, and make the APP and log available on-site to the Contracting Officer. If English is not the foreman's primary language,

the Prime Contractor must provide an interpreter.

Submit the APP to the Contracting Officer within 30 calendar days of Contract award and not less than 10 calendar days prior to the date of the preconstruction conference for acceptance. Work cannot proceed without an accepted APP. Once reviewed and accepted by the Contracting Officer, the APP and attachments will be enforced as part of the Contract. Disregarding the provisions of this Contract or the accepted APP is cause for stopping of work, at the discretion of the Contracting Officer, until the matter has been rectified. Continuously review and amend the APP, as necessary, throughout the life of the Contract. Changes to the accepted APP must be made with the knowledge and concurrence of the Contracting Officer, project superintendent, SSHO and Quality Control Manager. Incorporate unusual or high-hazard activities not identified in the original APP as they are discovered. Should any severe hazard exposure (i.e., imminent danger) become evident, stop work in the area, secure the area, and develop a plan to remove the exposure and control the hazard. Notify the Contracting Officer within 24 hours of discovery. Eliminate and remove the hazard. In the interim, take all necessary action to restore and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public (as defined by ANSI/ASSP A10.34), and the environment.

1.9.2 Names and Qualifications

Provide plans in accordance with the requirements outlined in EM 385-1-1, including the following:

a. Names and qualifications (resumes including education, training, experience and certifications) of site safety and health personnel designated to perform work on this project to include the designated Site Safety and Health Officer and other competent and qualified personnel to be used. Specify the duties of each position.

b. As a minimum, designate and submit qualifications of Competent Persons (CP) for each of the following major areas: excavation; scaffolding; fall protection; hazardous energy; confined space; health hazard recognition, evaluation and control of chemical, physical and biological agents; and personal protective equipment and clothing to include selection, use and maintenance. Designate and submit qualifications for additional CPs as applicable to the work performed under this Contract.

1.9.3 Plans

Provide plans in the APP in accordance with the requirements outlined in EM 385-1-1, including the following:

1.9.3.1 Site Demolition Plan

Identify the safety and health aspects, and prepare in accordance with Section 02 41 00 DEMOLITION and referenced sources. Include engineering survey as applicable.

1.10 ACTIVITY HAZARD ANALYSIS (AHA)

Before beginning each activity, task or Definable Feature of Work (DFOW) involving a type of work presenting hazards not experienced in previous project operations, or where a new work crew or subcontractor is to

perform the work, the Contractor(s) performing that work activity must prepare an AHA. AHAs must be developed by the Prime Contractor, subcontractor, or supplier performing the work, and provided for Prime Contractor review and approval before submitting to the Contracting Officer. AHAs must be signed by the SSHO, Superintendent, QC Manager and the subcontractor Foreman performing the work. Format the AHA in accordance with EM 385-1-1 or as directed by the Contracting Officer. Submit the AHA for review at least 15 working days prior to the start of each activity task, or DFOW. The Government reserves the right to require the Contractor to revise and resubmit the AHA if it fails to effectively identify the work sequences, specific anticipated hazards, site conditions, equipment, materials, personnel and the control measures to be implemented.

AHAs must identify competent persons required for phases involving high risk activities, including confined entry, crane and rigging, excavations, trenching, electrical work, fall protection, and scaffolding.

1.10.1 AHA Management

Review the AHA list periodically (at least monthly) at the Contractor supervisory safety meeting, and update as necessary when procedures, scheduling, or hazards change. Use the AHA during daily inspections by the SSHO to ensure the implementation and effectiveness of the required safety and health controls for that work activity.

1.10.2 AHA Signature Log

Each employee performing work as part of an activity, task or DFOW must review the AHA for that work and sign a signature log specifically maintained for that AHA prior to starting work on that activity. The SSHO must maintain a signature log on site for every AHA. Provide employees whose primary language is other than English, with an interpreter to ensure a clear understanding of the AHA and its contents.

1.11 SITE SAFETY REFERENCE MATERIALS

Maintain safety-related references applicable to the project, including those listed in paragraph REFERENCES. Maintain applicable equipment manufacturer's manuals.

1.12 EMERGENCY MEDICAL TREATMENT

Contractors must arrange for their own emergency medical treatment in accordance with EM 385-1-1. The Government has no responsibility to provide emergency medical treatment.

1.13 NOTIFICATIONS AND REPORTS

1.13.1 Accident Notification

Notify the Contracting Officer in accordance with the EM 385-1-1 Accident Reporting Timeline.

Table
Accident Reporting Required Timeline

Accident Type	Notify KO or COR	Complete Final Accident Report on ENG 3394 and provide to KO or COR
Fatality, in-patient hospitalization, amputation, eye loss, or property damage over $600,000.	Immediately, no later than (NLT) 8 Hours	Within 7 Days
All other accidents and near misses	Immediately, no later than (NLT) 24 Hours	Within 7 Days

Within notification include Contractor name; Contract title; type of Contract; name of activity, installation or location where accident occurred; date and time of accident; names of personnel injured; extent of property damage, if any; extent of injury, if known, and brief description of accident (for example, type of construction equipment used and PPE used). Preserve the conditions and evidence on the accident site until the Government investigation team arrives on-site and Government investigation is conducted. Assist and cooperate fully with the Government's investigation(s) of any accident or near miss.

1.13.2 Accident Reports

a. Conduct an accident investigation for recordable injuries and illnesses, property damage, and near misses as defined in EM 385-1-1, to establish the root cause(s) of the accident. Complete the applicable NAVFAC Contractor Incident Reporting System (CIRS), and electronically submit via the NAVFAC Enterprise Safety Applications Management System (ESAMS). Complete and submit an accident investigation report in ESAMS within 7 days for accidents as defined by EM 385-1-1. Complete the investigation report within 30 days. Accidents must include a written report submitted as an attachment in ESAMS using the following outline:

(1) Summary description to include:

(a) process

(b) findings

(c) outcomes

(2) Root Cause

(3) Direct Factors

(4) Indirect and Contributing Factors

(5) Corrective Actions

(6) Recommendations

All accidents are reportable, regardless of whether or not it is recordable.

a. Near Misses: For Navy Projects, complete the applicable documentation in NAVFAC Contractor Incident Reporting System (CIRS), and electronically submit via the NAVFAC Enterprise Safety Applications Management System (ESAMS). Near miss reports are considered positive and proactive Contractor safety management actions.

b. Conduct an accident investigation for any load handling equipment accident (including rigging accidents) to establish the root cause(s) of the accident. Complete the Load Handling Equipment (LHE) Accident Report (Crane and Rigging Accident Report) form and provide the report to the Contracting Officer within 30 calendar days of the accident. Do not proceed with crane operations until cause is determined and corrective actions have been implemented to the satisfaction of the Contracting Officer. The Contracting Officer will provide a blank copy of the accident report form.

1.13.3 LHE Inspection Reports

Submit LHE inspection reports required in accordance with EM 385-1-1 and as specified herein with Daily Reports of Inspections.

1.13.4 Certificate of Compliance and Pre-lift Plan/Checklist for LHE and Rigging

1.13.4.1 Certificate of Compliance

Provide a Certificate of Compliance for LHE utilized to perform work under this Contract in accordance with Section 16-7 of the EM 385-1-1. Post completed certificate on the crane.

1.13.4.2 Pre-Lift Plans

Develop either a Standard Lift Plan (SLP) or Critical Lift Plan (CLP) as required in accordance with EM 385-1-1. Utilize the Standard Lift Plan ENG Form 6203 for routine crane lifts and use the Critical Lift Plan ENR Form 6213 for non-routine crane lifts requiring more detailed planning and additional safety precautions, as defined by Section 16-2j of the EM 385-1-1. Submit lift plans to the Contracting Officer for approval within 15 calendar days in advance of planned lift.

1.14 HOT WORK PERMIT

1.14.1 Permit and Personnel Requirements

Submit and obtain a written permit prior to performing "Hot Work" (i.e., welding or cutting) or operating other flame-producing/spark producing devices, from the Fire Department. A permit is required from the Explosives Safety Office for work in and around where explosives are processed, stored, or handled. Contractors are required to meet all criteria before a permit is issued. Provide at least two 20 pound 4A:20 BC rated extinguishers for normal "Hot Work". The extinguishers must be current inspection tagged, and contain an approved safety pin and tamper resistant seal. It is also mandatory to have a designated FIRE WATCH for any "Hot Work" done at this activity. The Fire Watch must be trained in

accordance with NFPA 51B and remain on-site for a minimum of 1 hour after completion of the task or as specified on the hot work permit.

When starting work in the facility, require personnel to familiarize themselves with the location of the nearest fire alarm boxes and place in memory the emergency Fire Department phone number. Report any fire, no matter how small, to the responsible Fire Department immediately.

1.14.2 Work Around Flammable Materials

Obtain permit approval from a NFPA Certified Marine Chemist, or Certified Industrial Hygienist for "Hot Work" within or around flammable materials (such as fuel systems or welding/cutting on fuel pipes) or confined spaces (such as sewer wet wells, manholes, or vaults) that have the potential for flammable or explosive atmospheres.

Whenever these materials, except beryllium and chromium (VI), are encountered in indoor operations, local mechanical exhaust ventilation systems that are sufficient to reduce and maintain personal exposures to within acceptable limits must be used and maintained in accordance with manufacturer's instruction and supplemented by exceptions noted in EM 385-1-1.

1.15 RADIATION SAFETY REQUIREMENTS

Submit License Certificates, employee training records, and Leak Test Reports for radiation materials and equipment to the Contracting Officer and Radiation Safety Office (RSO), and Contracting Oversight Technician (COT) for all specialized and licensed material and equipment proposed for use on the construction project (excludes portable machine sources of ionizing radiation including moisture density and X-Ray Fluorescence (XRF)). Maintain on-site records whenever licensed radiological materials or ionizing equipment are on Government property.

Protect workers from radiation exposure in accordance with 10 CFR 20, ensuring any personnel exposures are maintained As Low As Reasonably Achievable.

1.15.1 Radiography Operation Planning Work Sheet

Submit a Gamma and X-Ray Radiography Operation Planning Work Sheet to Contracting Officer 14 days prior to commencement of operations involving radioactive materials or radiation generating devices. For portable machine sources of ionizing radiation, including moisture density and XRF, use and submit the Portable Gauge Operations Planning Worksheet instead. The Contracting Officer and COT will review the submitted worksheet and provide questions and comments.

Contractors must use primary dosimeters process by a National Voluntary Laboratory Accreditation Program (NVLAP) accredited laboratory.

1.15.2 Site Access and Security

Coordinate site access and security requirements with the Contracting Officer and COT for all radiological materials and equipment containing ionizing radiation that are proposed for use on a government facility. For gamma radiography materials and equipment, a Government escort is required for any travels on the Installation. The Navy COT or Government authorized representative will meet the Contractor at a designated

location outside the Installation, ensure safety of the materials being transported, and will escort the Contractor for gamma sources onto the Installation, to the job site, and off the Installation. For portable machine sources of ionizing radiation, including moisture density and XRF, the Navy COT or Government authorized representative will meet the Contractor at the job site.

Provide a copy of all calibration records, and utilization records to the COT for radiological operations performed on the site.

1.15.3 Loss or Release and Unplanned Personnel Exposure

Loss or release of radioactive materials, and unplanned personnel exposures must be reported immediately to the Contracting Officer, RSO, and Base Security Department Emergency Number.

1.15.4 Site Demarcation and Barricade

Properly demark and barricade an area surrounding radiological operations to preclude personnel entrance, in accordance with EM 385-1-1, Nuclear Regulatory Commission, and Applicable State regulations and license requirements, and in accordance with requirements established in the accepted Radiography Operation Planning Work Sheet.

Do not close or obstruct streets, walks, and other facilities occupied and used by the Government without written permission from the Contracting Officer.

1.15.5 Security of Material and Equipment

Properly secure the radiological material and ionizing radiation equipment at all times, including keeping the devices in a properly marked and locked container, and secondarily locking the container to a secure point in the Contractor's vehicle or other approved storage location during transportation and while not in use. While in use, maintain a continuous visual observation on the radiological material and ionizing radiation equipment. In instances where radiography is scheduled near or adjacent to buildings or areas having limited access or one-way doors, make no assumptions as to building occupancy. Where necessary, the Contracting Officer will direct the Contractor to conduct an actual building entry, search, and alert. Where removal of personnel from such a building cannot be accomplished and it is otherwise safe to proceed with the radiography, position a fully instructed employee inside the building or area to prevent exiting while external radiographic operations are in process.

1.15.6 Transportation of Material

Comply with 49 CFR 173 for Transportation of Regulated Amounts of Radioactive Material. Notify Local Fire authorities and the site Radiation Safety Officer (RSO) of any Radioactive Material use.

1.15.7 Schedule for Exposure or Unshielding

Actual exposure of the radiographic film or unshielding the source must not be initiated until after 5 p.m. on weekdays.

1.15.8 Transmitter Requirements

Adhere to the base policy concerning the use of transmitters, such as

radios and cell phones. Obey Emissions control (EMCON) restrictions.

1.16 CONFINED SPACE ENTRY REQUIREMENTS

Confined space entry must comply with EM 385-1-1, 29 CFR 1926, 29 CFR 1910, and Directive CPL 2.100. Any potential for a hazard in the confined space requires a permit system to be used.

1.16.1 Rescue Procedures and Coordination with Local Emergency Responders

Develop and implement an on-site rescue and recovery plan and procedures. The rescue plan must not rely on local emergency responders for rescue from a confined space.

1.17 CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT PLAN

Submit an IAQ Management Plan within 15 calendar days after notice to proceed and not less than 10 calendar days before the preconstruction conference. Revise and resubmit Plan as required by the Contracting Officer. Make copies of the final plan available to all workers on site. Include provisions in the Plan to meet the requirements specified below and to ensure safe, healthy air for construction workers and building occupants. Submit Final IAQ Management Plan for inclusion in the Sustainability eNotebook, in accordance with Section 01 33 29 SUSTAINABILITY REQUIREMENTS AND REPORTING.

1.17.1 Requirements During Construction

Provide for evaluation of indoor Carbon Dioxide concentrations in accordance with ASTM D6245. Provide for evaluation of volatile organic compounds (VOCs) in indoor air in accordance with ASTM D6345. Use filters with a Minimum Efficiency Reporting Value (MERV) of 8 in permanently installed air handlers during construction.

1.17.1.1 Control Measures

Meet or exceed the requirements of ANSI/SMACNA 008 to help minimize contamination of the building from construction activities. The five requirements of this manual which must be adhered to are described below:

a. HVAC protection: Isolate return side of HVAC system from surrounding environment to prevent construction dust and debris from entering the duct work and spaces.

b. Source control: Use low emitting paints and other finishes, sealants, adhesives, and other materials as specified. When available, cleaning products must have a low VOC content and be non-toxic to minimize building contamination. Utilize cleaning techniques that minimize dust generation. Cycle equipment off when not needed. Prohibit idling motor vehicles where emissions could be drawn into building. Designate receiving/storage areas for incoming material that minimize IAQ impacts.

c. Pathway interruption: When pollutants are generated use strategies such as 100 percent outside air ventilation or erection of physical barriers between work and non-work areas to prevent contamination.

d. Housekeeping: Clean frequently to remove construction dust and debris. Promptly clean up spills. Remove accumulated water and keep

work areas dry to discourage the growth of mold and bacteria. Take extra measures when hazardous materials are involved.

e. Scheduling: Control the sequence of construction to minimize the absorption of VOCs by other building materials.

1.17.1.2 Moisture Contamination

a. Remove accumulated water and keep work dry.

b. Use dehumidification to remove moist, humid air from a work area.

c. Do not use combustion heaters or generators inside the building.

d. Protect porous materials from exposure to moisture.

e. Remove and replace items which remain damp for more than a few hours.

1.17.2 Requirements After Construction

After construction ends and prior to occupancy, conduct a building flush-out or test the indoor air contaminant levels. Flush-out must be a minimum 2 weeks with MERV-13 filtration media as determined by ASHRAE 52.2 at 100 percent outside air. Air contamination testing must be consistent with EPA's current Compendium of Methods for the Determination of Air Pollutants in Indoor Air. After building flush-out or testing and prior to occupancy, replace filtration media. Filtration media must have a MERV of 13 as determined by ASHRAE 52.2.

1.18 SEVERE STORM PLAN

In the event of a severe storm warning, the Contractor must comply with the applicable Storm Plan and:

a. Secure outside equipment and materials and place materials that could be damaged in protected areas.

b. Check surrounding area, including roof, for loose material, equipment, debris, and other objects that could be blown away or against existing facilities.

c. Ensure that temporary erosion controls are adequate.

PART 2 PRODUCTS

2.1 CONFINED SPACE SIGNAGE

Provide permanent signs integral to or securely attached to access covers for new permit-required confined spaces. Signs for confined spaces must comply with NEMA Z535.2. Provide signs with wording: "DANGER--PERMIT-REQUIRED CONFINED SPACE, DO NOT ENTER" in bold letters a minimum of one inch in height and constructed to be clearly legible with all paint removed. The signal word "DANGER" must be red and readable from 5 feet.

PART 3 EXECUTION

3.1 CONSTRUCTION AND OTHER WORK

Comply with EM 385-1-1, NFPA 70, NFPA 70E, NFPA 241, the APP, the AHA, Federal and State OSHA regulations, and other related submittals and activity fire and safety regulations. The most stringent standard prevails.

PPE is governed in all areas by the nature of the work the employee is performing. Use personal hearing protection at all times in designated noise hazardous areas or when performing noise hazardous tasks. Safety glasses must be worn or carried/available on each person. Mandatory PPE includes:

a. Head Protection that meets ANSI/ISEA Z89.1

b. Long Pants

c. Appropriate Safety Footwear

d. Appropriate Class Reflective Vests

3.1.1 Worksite Communication

Employees working alone in a remote location or away from other workers must be provided an effective means of emergency communications (i.e., cellular phone, two-way radios, land-line telephones or other acceptable means). The selected communication must be readily available (easily within the immediate reach) of the employee and must be tested prior to the start of work to verify that it effectively operates in the area/environment. Develop an employee check-in/check-out communication procedure to ensure employee safety.

3.1.2 Hazardous Material Use

Each hazardous material must receive approval from the Contracting Office or their designated representative prior to being brought onto the job site or prior to any other use in connection with this Contract. Allow a minimum of 10 working days for processing of the request for use of a hazardous material.

3.1.3 Hazardous Material Exclusions

Notwithstanding any other hazardous material used in this Contract, radioactive materials or instruments capable of producing ionizing/non-ionizing radiation (with the exception of radioactive material and devices used in accordance with EM 385-1-1 such as nuclear density meters for compaction testing and laboratory equipment with radioactive sources) as well as materials which contain asbestos, mercury or polychlorinated biphenyls, di-isocyanates, lead-based paint, and hexavalent chromium, are prohibited. The Contracting Officer, upon written request by the Contractor, may consider exceptions to the use of any of the above excluded materials. Low mercury lamps used within fluorescent lighting fixtures are allowed as an exception without further Contracting Officer approval. Notify the Radiation Safety Officer (RSO) prior to excepted items of radioactive material and devices being brought on base.

3.1.4 Unforeseen Hazardous Material

Contract documents identify materials such as PCB, lead paint, and friable and non-friable asbestos and other OSHA regulated chemicals (i.e., 29 CFR Part 1910.1000). If material(s) that can be hazardous to human health upon disturbance are encountered during demolition, repair, renovation, or construction operations, stop portions of work that would disturb the material and notify the Contracting Officer immediately. Within 14 calendar days the Government will determine if the material is hazardous. If material is not hazardous or poses no danger, the Government will direct the Contractor to proceed without change. If material is hazardous and handling of the material is necessary to accomplish the work, the Government will issue a modification.

3.2 UTILITY OUTAGE REQUIREMENTS

Apply for utility outages at least 15 days in advance in sufficient time as to not result in impacts or delays to the project schedule. At a minimum, the written request must include the location of the outage, utilities being affected, duration of outage, any necessary sketches, and a description of the means to fulfill energy isolation requirements in accordance with EM 385-1-1. In accordance with EM 385-1-1, where outages involve Government or Utility personnel, coordinate with the Government on all activities involving the control of hazardous energy.

These activities include, but are not limited to, a review of Hazardous Energy Control Program (HECP) and HEC procedures, as well as applicable Activity Hazard Analyses (AHAs). In accordance with EM 385-1-1 and NFPA 70E, work on energized electrical circuits must not be performed without prior Government authorization. Government permission is considered through the permit process and submission of a detailed AHA. Energized work permits are considered only when de-energizing introduces additional or increased hazard or when de-energizing is infeasible.

3.3 OUTAGE COORDINATION MEETING

After the utility outage request is approved and prior to beginning work on the utility system requiring shut-down, conduct a pre-outage coordination meeting in accordance with EM 385-1-1. This meeting must include the Prime Contractor, the Prime and subcontractors performing the work, the Contracting Officer, and the Installation representative. All parties must fully coordinate HEC activities with one another. During the coordination meeting, all parties must discuss and coordinate on the scope of work, HEC procedures (specifically, the lock-out/tag-out procedures for worker and utility protection), the AHA, assurance of trade personnel qualifications, identification of competent persons, and compliance with HECP training in accordance with EM 385-1-1. Clarify when personal protective equipment is required during switching operations, inspection, and verification.

3.4 CONTROL OF HAZARDOUS ENERGY (LOCKOUT/TAGOUT)

Provide and operate a Hazardous Energy Control Program (HECP) in accordance with EM 385-1-1, 29 CFR 1910, 29 CFR 1915, ANSI/ASSP A10.44, NFPA 70E.

3.4.1 Safety Preparatory Inspection Coordination Meeting with the Government or Utility

For electrical distribution equipment that is to be operated by Government or Utility personnel, the Prime Contractor and the subcontractor performing the work must attend the safety preparatory inspection coordination meeting, which will also be attended by the Contracting Officer's Representative, and required by EM 385-1-1. The meeting will occur immediately preceding the start of work and following the completion of the outage coordination meeting. Both the safety preparatory inspection coordination meeting and the outage coordination meeting must occur prior to conducting the outage and commencing with lockout/tagout procedures.

3.4.2 Lockout/Tagout Isolation

Where the Government or Utility performs equipment isolation and lockout/tagout, the Contractor must place their own locks and tags on each energy-isolating device and proceed in accordance with the HECP. Before any work begins, both the Contractor and the Government or Utility must perform energy isolation verification testing while wearing required PPE detailed in the Contractor's AHA and required by EM 385-1-1. Install personal protective grounds, with tags, to eliminate the potential for induced voltage in accordance with EM 385-1-1.

3.4.3 Lockout/Tagout Removal

Upon completion of work, conduct lockout/tagout removal procedure in accordance with the HECP. In accordance with EM 385-1-1, each lock and tag must be removed from each energy isolating device by the authorized individual or systems operator who applied the device. Provide formal notification to the Government (by completing the Government form if provided by Contracting Officer's Representative), confirming that steps of de-energization and lockout/tagout removal procedure have been conducted and certified through inspection and verification. Government or Utility locks and tags used to support the Contractor's work will not be removed until the authorized Government employee receives the formal notification.

3.5 FALL PROTECTION PROGRAM

Establish a fall protection program, for the protection of all employees exposed to fall hazards. Within the program include company policy, identify roles and responsibilities, education and training requirements, fall hazard identification, prevention and control measures, inspection, storage, care and maintenance of fall protection equipment and rescue and evacuation procedures in accordance with EM 385-1-1.

3.5.1 Fall Protection Equipment and Systems

Enforce use of personal fall protection equipment and systems designated (to include fall arrest, restraint, and positioning) for each specific work activity in the Site Specific Fall Protection and Prevention Plan and AHA at all times when an employee is exposed to a fall hazard. Protect employees from fall hazards as specified in EM 385-1-1.

Provide personal fall protection equipment, systems, subsystems, and components that comply with EM 385-1-1 and 29 CFR 1926.

3.5.1.1 Additional Personal Fall Protection Measures

In addition to the required fall protection systems, other protective measures such as safety skiffs, personal floatation devices, and life rings, are required when working above or next to water in accordance with EM 385-1-1. Personal fall protection systems and equipment are required when working from an articulating or extendible boom, swing stages, or suspended platform. In addition, personal fall protection systems are required when operating other equipment such as scissor lifts. The need for tying-off in such equipment is to prevent ejection of the employee from the equipment during raising, lowering, travel, or while performing work.

3.5.1.2 Personal Fall Protection Equipment

Only a full-body harness with a shock-absorbing lanyard or self-retracting lanyard is an acceptable personal fall arrest body support device. The use of body belts is not acceptable. Harnesses must have a fall arrest attachment affixed to the body support (usually a Dorsal D-ring) and specifically designated for attachment to the rest of the system. Snap hooks and carabineers must be self-closing and self-locking, capable of being opened only by at least two consecutive deliberate actions and have a minimum gate strength of 3,600 lbs in all directions. Use webbing, straps, and ropes made of synthetic fiber. The maximum free fall distance when using fall arrest equipment must not exceed 6 feet, unless the proper energy absorbing lanyard is used. Always take into consideration the total fall distance and any swinging of the worker (pendulum-like motion), that can occur during a fall, when attaching a person to a fall arrest system. Equip all full body harnesses with Suspension Trauma Preventers such as stirrups, relief steps, or similar in order to provide short-term relief from the effects of orthostatic intolerance in accordance with EM 385-1-1.

3.6 USE OF EXPLOSIVES

Explosives must not be used or brought to the project site without prior written approval from the Contracting Officer. Such approval does not relieve the Contractor of responsibility for injury to persons or for damage to property due to blasting operations.

Storage of explosives, when permitted on Government property, must be only where directed and in approved storage facilities. These facilities must be kept locked at all times except for inspection, delivery, and withdrawal of explosives.

3.7 ELECTRICAL

Perform electrical work in accordance with EM 385-1-1.

3.7.1 Electrical Work

As described in EM 385-1-1, electrical work is to be conducted in a de-energized state unless there is no alternative method for accomplishing the work. In those cases obtain an energized work permit from the Contracting Officer. The energized work permit application must be accompanied by the AHA and a summary of why the equipment/circuit needs to be worked energized. Underground electrical spaces must be certified safe for entry before entering to conduct work. Cables that will be cut must be positively identified and de-energized prior to performing each cut.

Attach temporary grounds in accordance with ASTM F855 and IEEE 1048. Perform all high voltage cable cutting remotely using hydraulic cutting tool. When racking in or live switching of circuit breakers, no additional person other than the switch operator is allowed in the space during the actual operation. Plan so that work near energized parts is minimized to the fullest extent possible. Use of electrical outages clear of any energized electrical sources is the preferred method.

When working in energized substations, only qualified electrical workers are permitted to enter. When work requires work near energized circuits as defined by NFPA 70, high voltage personnel must use personal protective equipment that includes, as a minimum, electrical hard hat, safety footwear, insulating gloves and electrical arc flash protection for personnel as required by NFPA 70E. Insulating blankets, hearing protection, and switching suits may also be required, depending on the specific job and as delineated in the Contractor's AHA. Ensure that each employee is familiar with and complies with these procedures and 29 CFR 1910.

3.7.2 Qualifications

Electrical work must be performed by QP with verifiable credentials who are familiar with applicable code requirements. Verifiable credentials consist of State, National and Local Certifications or Licenses that a Master or Journeyman Electrician may hold, depending on work being performed, and must be identified in the appropriate AHA. Journeyman/Apprentice ratio must be in accordance with State, Local requirements applicable to where work is being performed.

3.7.3 Arc Flash

Conduct a hazard analysis/arc flash hazard analysis whenever work on or near energized parts greater than 50 volts is necessary, in accordance with NFPA 70E.

All personnel entering the identified arc flash protection boundary must be QPs and properly trained in NFPA 70E requirements and procedures. Unless permitted by NFPA 70E, no Unqualified Person is permitted to approach nearer than the Limited Approach Boundary of energized conductors and circuit parts. Training must be administered by an electrically qualified source and documented.

3.7.4 Grounding

Ground electrical circuits, equipment and enclosures in accordance with NFPA 70 and IEEE C2 to provide a permanent, continuous and effective path to ground unless otherwise noted by EM 385-1-1.

3.7.5 Testing

Temporary electrical distribution systems and devices must be inspected, tested and found acceptable for Ground-Fault Circuit Interrupter (GFCI) protection, polarity, ground continuity, and ground resistance before initial use, before use after modification and at least monthly. Monthly inspections and tests must be maintained for each temporary electrical distribution system, and signed by the electrical CP or QP.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 35 29.13

HEALTH, SAFETY, AND EMERGENCY RESPONSE PROCEDURES FOR CONTAMINATED SITES
11/15, CHG 1: 08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN PETROLEUM INSTITUTE (API)

API RP 2219	(2016) Safe Operation of Vacuum Trucks Handling Flammable and Combustible Liquids in Petroleum Service

INTERNATIONAL SAFETY EQUIPMENT ASSOCIATION (ISEA)

ANSI/ISEA Z358.1	(2014) American National Standard for Emergency Eyewash and Shower Equipment

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH)

NIOSH 85-115	(1985) Occupational Safety and Health Guidance Manual for Hazardous Waste Site Activities

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1904	Recording and Reporting Occupational Injuries and Illnesses
29 CFR 1910	Occupational Safety and Health Standards
29 CFR 1910.120	Hazardous Waste Operations and Emergency Response
29 CFR 1926	Safety and Health Regulations for Construction
29 CFR 1926.65	Hazardous Waste Operations and Emergency Response
49 CFR 171	General Information, Regulations, and Definitions
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements

1.2 PRECONSTRUCTION SAFETY CONFERENCE

Conduct a preconstruction safety conference prior to the start of site activities and after submission of the Accident Prevention Plan/Site Safety And Health Plan (APP/SSHP). The objective of the meeting is to discuss health and safety concerns related to the impending work, discuss project health and safety organization and expectations, review and answer comments and concerns regarding the APP/SSHP or other health and safety concerns . Ensure that those individuals responsible for health and safety at the project level are available and attend this meeting.

1.3 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Work Zones; G

Decontamination Facilities; G

SD-03 Product Data

Amendments to the APP/SSHP; G

Exposure Monitoring/Air Sampling Program

Site Control Log

SSHO's Daily Inspection Logs

SD-07 Certificates

Certificate Of Worker/Visitor Acknowledgement

SD-11 Closeout Submittals

Safety And Health Phase-Out Report; G

1.4 ACCIDENT PREVENTION PLAN/SITE SAFETY AND HEALTH PLAN (APP/SSHP)

Develop and implement a Site Safety and Health Plan in accordance with Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS, and attach to the Accident Prevention Plan (APP) as an appendix (APP/SSHP). Address all occupational safety and health hazards (traditional construction as well as contaminant-related hazards) associated with cleanup operations within the APP/SSHP. Cover each SSHP element in sections 28.A.01 and 33.B of EM 385-1-1 and each APP element in Appendix A of EM 385-1-1. There are overlapping elements in Section 28.A.01 and Appendix A of EM 385-1-1. SSHP appendix elements that overlap with APP elements need not be duplicated in the APP/SSHP provided each safety and occupational health (SOH) issue receives adequate attention and is documented in the APP/SSHP. The APP/SSHP is a dynamic document, subject to change as project operations/execution change. Modify the APP/SSHP to address changing and previously unidentified health and safety conditions. Ensure that the APP/SSHP is updated accordingly. Submit amendments to the APP/SSHP to the Contracting Officer as the APP/SSHP is updated. For long

duration projects resubmit the APP/SSHP to the Contracting Officer annually for review. The APP/SSHP must contain all updates.

1.4.1 Acceptance and Modifications

Prior to submittal, the APP/SSHP must be signed and dated by the Safety and Health Manager and the Site Superintendent. Submit for review 14 days prior to the Preconstruction Safety Conference. Deficiencies in the APP/SSHP will be discussed at the preconstruction safety conference, and must be revised to correct the deficiencies and resubmitted for acceptance. Onsite work must not begin until the plan has been accepted. Maintain a copy of the written APP/SSHP onsite. Changes and modifications to the APP/SSHP must be made with the knowledge and concurrence of the Safety and Health Manager, the Site Superintendent, and the Contracting Officer. Bring to the attention of the Safety and Health Manager, the Site Superintendent, and the Contracting Officer any unforeseen hazard that becomes evident during the performance of the work, through the Site Safety and Health Officer (SSHO) for resolution as soon as possible. In the interim, take necessary action to re-establish and maintain safe working conditions in order to safeguard onsite personnel, visitors, the public, and the environment. Disregard for the provisions of this specification or the accepted APP/SSHP is cause for stopping work until the matter has been rectified.

1.4.2 Availability

Make available the APP/SSHP in accordance with 29 CFR 1910.120, (b)(1)(v) and 29 CFR 1926.65, (b)(1)(v).

1.5 STAFF ORGANIZATION, QUALIFICATION AND RESPONSIBILITIES

Provide hazardous waste operations and emergency response organization in accordance with EM 385-1-1, Section 33.

1.5.1 Safety and Health Manager

Safety and Health Manager must be an Industrial Hygienist certified by the American Board of Industrial Hygiene.

Apply the following in conjunction with the required qualifications and responsibilities stated in EM 385-1-1, Section 33.C.01.

1.5.1.1 Additional Qualifications

The Safety and Health Manager must have the following qualifications:

a. A minimum of 3 years experience in developing and implementing safety and occupational health programs .

b. Documented experience in supervising professional and technician level personnel.

c. Documented experience in developing worker exposure assessment programs and air monitoring programs and techniques.

d. Documented experience in managing personal protective equipment (PPE) programs and conducting PPE hazard evaluations for the types of activities and hazards likely to be encountered on the project.

e. Working knowledge of state and Federal occupational safety and health regulations.

1.5.1.2 Responsibilities and Duties

a. Development, implementation, oversight, and enforcement of the APP/SSHP.

b. Provide onsite consultation as needed to ensure the APP/SSHP is fully implemented.

c. Conduct initial site-specific training.

d. Be present onsite during the before start of remedial activities and at the startup of each new major phase of work.

e. Visit the site as needed and at least once per week for the duration of activities, to audit the effectiveness of the APP/SSHP.

f. Be available for emergencies.

g. Coordinate any modifications to the APP/SSHP with the Site Superintendent, the SSHO, and the Contracting Officer.

h. Be responsible for evaluating air monitoring data and recommending changes to engineering controls, work practices, and PPE.

i. Provide continued support for upgrading/downgrading of the level of personal protection.

j. Serve as a member of the quality control staff.

k. Review accident reports and results of daily inspections.

l. Sign and date the APP/SSHP prior to submittal.

1.5.2 Site Safety and Health Officer

Designate an individual and one alternate as the Site Safety and Health Officer (SSHO). Include the name, qualifications (education and training summary and documentation), and work experience of the Site Safety and Health Officer and alternate in the APP/SSHP.

The Apply the following in conjunction with the required qualifications and responsibilities stated in EM 385-1-1, Section 33.C.02.

1.5.2.1 Qualifications

The following requirements are in addition to those in Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS.

a. A minimum of 1 year experience in implementing SOH programs where personal protective equipment was required.

b. Meet 29 CFR 1910.120/29 CFR 1926.65 requirements for 40-hour initial and 8-hour supervisor training and, maintain 8-hour refresher training requirements.

c. Specific training in personal and respiratory protective equipment, confined space entry and in the proper use of air monitoring instruments and air sampling methods including monitoring for ionizing radiation.

d. Documented experience in construction techniques and construction safety procedures.

e. Working knowledge of Federal and state occupational SOH regulations.

1.5.2.2 Responsibilities and Duties

The following requirements are in addition to those in Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS.

a. Assist and represent the Safety and Health Manager in onsite training and the day to day onsite implementation and enforcement of the accepted APP/SSHP.

b. Be assigned to the site on a full time basis for the duration of field activities. The SSHO can have collateral duties in addition to SOH related duties. If operations are performed during more than 1 work shift per day, a site Safety and Health Officer must be present for each shift and when applicable, act as the radiation safety officer (RSO) as defined in paragraph 06.F.02 of EM 385-1-1 on radioactive waste cleanup projects.

c. Have authority to stop work if unacceptable health or safety conditions exist, and take necessary action to re-establish and maintain safe working conditions.

d. Have authority to ensure site compliance with specified SOH requirements, Federal, state and OSHA regulations and all aspects of the APP/SSHP including, but not limited to, activity hazard analyses, air monitoring, monitoring for ionizing radiation, use of PPE, decontamination, site control, standard operating procedures used to minimize hazards, safe use of engineering controls, the emergency response plan, confined space entry procedures, spill containment program, and preparation of records by performing a daily SOH inspection and documenting results on the Daily Safety Inspection Log in accordance with 29 CFR 1904.

e. In coordination with site management and the Safety and Health Manager, recommend corrective actions for identified deficiencies and oversee the corrective actions.

f. Consult with and coordinate any modifications to the APP/SSHP with the Safety and Health Manager, the Site Superintendent, and the Contracting Officer.

g. Conduct daily safety inspection and document SOH findings into the Daily Safety Inspection Log. Track noted SOH deficiencies to ensure that they are corrected.

h. Conduct accident investigations and prepare accident reports.

i. Serve as a member of the quality control staff on matters relating to SOH.

1.5.3 Additional Certified Health and Safety Support Personnel

Retain industrial hygiene support from an industrial hygienist certified by the American Board of Industrial Hygiene to develop occupational health practices for the APP/SSHP and, if necessary, visit the site to help implement APP/SSHP requirements.

1.5.4 Occupational Physician

Utilize the services of a licensed physician, who is certified in occupational medicine by the American Board of Preventative Medicine, or who, by necessary training and experience is Board eligible. The physician must be familiar with the site's hazards and the scope of this project. Include the medical consultant's name, qualifications, and knowledge of the site's conditions and proposed activities in the APP/SSHP. The physician is responsible for the determination of medical surveillance protocols and for review of examination/test results performed in compliance with 29 CFR 1910.120, (f) and 29 CFR 1926.65, (f) and paragraph MEDICAL SURVEILLANCE PROGRAM.

1.5.5 Persons Certified in First Aid and CPR

At least two persons who are currently certified in first aid and CPR by the American Red Cross or other approved agency must be onsite at all times during site operations. They must be trained in universal precautions and the use of PPE as described in the Bloodborne Pathogens Standard of 29 CFR 1910, Section .1030. These persons may perform other duties but must be immediately available to render first aid when needed.

1.5.6 Safety and Health Technicians

For each work crew in the exclusion zone, one person, designated as a Safety and Health technician, must perform activities such as air monitoring, decontamination, and safety oversight on behalf of the SSHO. They must have appropriate training equivalent to the SSHO in each specific area for which they have responsibility and report to and be under the supervision of the SSHO.

1.6 EMERGENCY RESPONSE AND CONTINGENCY PROCEDURES

Develop and implement an Emergency Response Plan, that meets the requirements of EM 385-1-1 Section 33.G, 29 CFR 1910.120 (l) and 29 CFR 1926.65 (l), as a section of the APP/SSHP. In the event of any emergency associated with remedial action, without delay, alert all onsite employees and as necessary offsite emergency responders that there is an emergency situation; take action to remove or otherwise minimize the cause of the emergency; alert the Contracting Officer; and institute measures necessary to prevent repetition of the conditions or actions leading to, or resulting in, the emergency. Train employees that are required to respond to hazardous emergency situations to their level of responsibility according to 29 CFR 1910.120 (q) and 29 CFR 1926.65 (q) requirements. Rehearse the plan regularly as part of the overall training program for site operations. Review the plan periodically and revised as necessary to reflect new or changing site conditions or information. Provide copies of the Emergency Response Portion of the accepted APP/SSHP to the affected local emergency response agencies. Address, as a minimum, the following elements in the plan:

a. Pre-emergency planning. Coordinate with local emergency response

providers during preparation of the Emergency Response Plan. At a minimum, coordinate with local fire, rescue, hazardous materials response teams, police and emergency medical providers to assure all organizations are capable and willing to respond to and provide services for on-site emergencies. Ensure the Emergency Response Plan for the site is compatible and integrated with the local fire, rescue, medical and police security services available from local emergency response planning agencies.

b. Personnel roles, lines of authority, communications for emergencies.

c. Emergency recognition and prevention.

d. Site topography, layout, and prevailing weather conditions.

e. Criteria and procedures for site evacuation (emergency alerting procedures, employee alarm system, emergency PPE and equipment, safe distances, places of refuge, evacuation routes, site security and control).

f. Route maps to nearest prenotified medical facility. Site-support vehicles must be equipped with maps. At the beginning of project operations, drivers of the support vehicles must become familiar with the emergency route and the travel time required.

g. Specific procedures for decontamination and medical treatment of injured personnel.

h. Emergency alerting and response procedures including posted instructions and a list of names and telephone numbers of emergency contacts (physician, nearby medical facility, fire and police departments, ambulance service, Federal, state, and local environmental agencies; as well as Safety and Health Manager, the Site Superintendent, the Contracting Officer and their alternates).

i. Criteria for initiating community alert program, contacts, and responsibilities.

j. Procedures for reporting incidents to appropriate government agencies. In the event that an incident such as an explosion or fire, or a spill or release of toxic materials occurs during the course of the project, the appropriate government agencies must be immediately notified. In addition, verbally notify the Contracting Officer and the local district safety office immediately and submit a written notification within 24 hours. Include within the report the following items:

(1) Name, organization, telephone number, and location of the Contractor.

(2) Name and title of the person(s) reporting.

(3) Date and time of the incident.

(4) Location of the incident, i.e., site location, facility name.

(5) Brief summary of the incident giving pertinent details including type of operation ongoing at the time of the incident.

(6) Cause of the incident, if known.

(7) Casualties (fatalities, disabling injuries).

(8) Details of any existing chemical hazard or contamination.

(9) Estimated property damage, if applicable.

(10) Nature of damage, effect on contract schedule.

(11) Action taken to ensure safety and security.

(12) Other damage or injuries sustained, public or private.

k. Procedures for critique of emergency responses and follow-up.

1.7 CERTIFICATE OF WORKER/VISITOR ACKNOWLEDGEMENT

A copy of a certificate of worker/visitor acknowledgement must be completed and submitted for each visitor allowed to enter contamination reduction or exclusion zones, and for each employee, following the Example Certificate Of Worker/Visitor Acknowledgement at the end of this section.

1.8 INSPECTIONS

Attach to and submit with the Daily Quality Control reports the SSHO's Daily Inspection Logs. Include with each entry the following: date, work area checked, employees present in work area, PPE and work equipment being used in each area, special SOH issues and notes, and signature of preparer.

1.9 SAFETY AND HEALTH PHASE-OUT REPORT

Submit a Safety and Health Phase-Out Report in conjunction with the project close out report, prior to final acceptance of the work. Include the following minimum information :

a. Summary of the overall performance of SOH (e.g., accidents or incidents including near misses, unusual events, lessons learned).

b. Final decontamination documentation including procedures and techniques used to decontaminate equipment, vehicles, and on site facilities.

c. Summary of exposure monitoring and air sampling accomplished during the project.

d. Signatures of Safety and Health Manager and SSHO.

PART 2 PRODUCTS

2.1 REGULATORY REQUIREMENTS

Comply with EM 385-1-1, 29 CFR 1926.65, 29 CFR 1910.120, OSHA requirements in 29 CFR 1910 and 29 CFR 1926 with work performed under this contract, and state specific OSHA requirements where applicable. Submit to the Contracting Officer for resolution matters of interpretation of standards before starting work. The most stringent requirements apply where the requirements of this specification, applicable laws, criteria, ordinances, regulations, and referenced documents vary.

2.2 PERSONAL PROTECTIVE EQUIPMENT

2.2.1 Site Specific PPE Program

Provide onsite personnel exposed to contaminants with appropriate personal protective equipment. Components of levels of protection (B, C, D and modifications) must be relevant to site-specific conditions, including heat and cold stress potential and safety hazards. Use only respirators approved by NIOSH.

Keep protective equipment and clothing clean and well maintained. Include site-specific procedures to determine PPE program effectiveness and for onsite fit-testing of respirators, cleaning, maintenance, inspection, cartridge change out, and storage of PPE within the PPE section of the APP/SSHP.

2.2.2 Levels of Protection

The Safety and Health Manager must establish and evaluate as the work progresses the levels of protection for each work activity. Also establish action levels for upgrade or downgrade in levels of PPE. Describe in the SSHP the protocols and the communication network for changing the level of protection. Address air monitoring results, potential for exposure, changes in site conditions, work phases, job tasks, weather, temperature extremes, and individual medical considerations within the PPE evaluation protocol.

2.2.3 PPE for Government Personnel

Three clean sets of personal protective equipment and personal dosimeters for work on radioactive waste cleanup sites and clothing (excluding air-purifying negative-pressure respirators and safety shoes, which will be provided by individual visitors), as required for entry into the Exclusion Zone and Contamination Reduction Zone, must be available for use by the Contracting Officer or official visitors. The items must be cleaned, maintained and stored and clearly marked: "FOR USE BY GOVERNMENT ONLY." Provide basic training in the use and limitations of the PPE provided.

2.3 EMERGENCY EQUIPMENT AND FIRST AID REQUIREMENTS

Maintain, as a minimum, the following items onsite and available for immediate use:

a. First aid equipment and supplies approved by the consulting physician.

b. Emergency eyewashes and showers that comply with ANSI/ISEA Z358.1.

c. Provide fire extinguishers of sufficient size and type at site facilities and in all vehicles and at any other site locations where flammable or combustible materials present a fire risk.

PART 3 EXECUTION

3.1 SITE DESCRIPTION AND CONTAMINATION CHARACTERIZATION

3.1.1 Project/Site Conditions

Refer to the following reports and information for the site description and contamination characterization. They are located at the ROICC offices.

3.1.2 Ordnance and Explosives (OE)

Stop work and contact the Contracting Officer if ordnance and explosives (OE), explosive media or chemical agent contaminated media (CACM) are discovered during HTRW site cleanup activities.

3.2 TASK SPECIFIC HAZARDS, INITIAL PPE, HAZWOPER MEDICAL SURVEILLANCE AND TRAINING APPLICABILITY

Task specific occupational hazards, task specific HAZWOPER medical surveillance and training applicability and task specific initial PPE requirements for the project are listed on the Task Hazard and Control Sheets at the end of this section. Reevaluate occupational safety and health hazards as the work progresses and to adjust the PPE and onsite operations, if necessary, so that the work is performed safely and in compliance with occupational safety and health regulations.

3.3 TRAINING

In conjunction with EM 385-1-1, Section 33D, meet the training program requirements for workers performing cleanup operations and who will be exposed to contaminants.

3.3.1 General HTRW Operations Training

All Personnel performing duties with potential for exposure to onsite contaminants must meet and maintain the following 29 CFR 1910.120/ 29 CFR 1926.65 (e) training requirements:

a. 40 hours of off site HTRW instruction.

b. 3 days actual on-the-job field experience under the direct supervision of a trained, experienced supervisor.

c. 8 hours refresher training annually.

Onsite supervisors must have an additional 8 hours management and supervisor training specified in 29 CFR 1910.120/29 CFR 1926.65 (e) (4).

3.3.2 Pre-Entry Briefing

Prior to commencement of onsite field activities, all site employees, including those assigned only to the Support Zone, must attend a site-specific SOH training session. This session will be conducted by the Safety and Health Manager and the Site Safety and Health Officer to ensure that all personnel are familiar with requirements and responsibilities for maintaining a safe and healthful work environment. Thoroughly discuss procedures and contents of the accepted APP/SSHP and Sections 01.B.02 and 28.D.03 of EM 385-1-1 . Each employee must sign a training log to acknowledge attendance and understanding of the training. Notify the

Contracting Officer at least 5 days prior to the initial site-specific training session so government personnel involved in the project may attend.

3.3.3 Periodic Sessions

Conduct periodic onsite training by the SSHO at least weekly for personnel assigned to work at the site during the following week. Address SOH procedures, work practices, any changes in the APP/SSHP, activity hazard analyses, work tasks, or schedule; results of previous week's air monitoring, review of safety discrepancies and accidents. Convene a meeting prior to implementation of the change should an operational change affecting onsite field work be made, to explain SOH procedures. Conduct a site-specific training sessions for new personnel, visitors, and suppliers by the SSHO using the training curriculum outlines developed by the Safety and Health Manager. Each employee must sign a training log to acknowledge attendance and understanding of the training.

3.3.4 Other Training

3.4 MEDICAL SURVEILLANCE PROGRAM

Meet all requirements of 29 CFR 1910.120/29 CFR 1926.65 medical surveillance program and EM 385-1-1, Section 33.G for workers performing cleanup operations and who will be exposed to contaminants. Ensure the Occupational Physician or the physician's designee performs the physical examinations and reviews examination results. Participation in the medical surveillance program is without cost to the employee, without loss of pay and at a reasonable time and place.

3.5 EXPOSURE MONITORING/AIR SAMPLING PROGRAM

Prepare and implement by the Safety and Health Manager an exposure monitoring/air sampling program to identify and quantify SOH hazards and airborne levels of hazardous substances in order to assure proper selection of engineering controls, work practices and personal protective equipment for affected site personnel. Include action levels for upgrading/downgrading PPE in the program. Submit personnel exposure monitoring/sampling results.

3.6 HEAT STRESS MONITORING AND MANAGEMENT

Document in the APP/SSHP and implement the procedures and practices in section 06.J. in EM 385-1-1 to monitor and manage heat stress.

3.7 SPILL AND DISCHARGE CONTROL

Develop and implement written spill and discharge containment/control procedures. Address radioactive wastes, shock sensitive wastes, laboratory waste packs, material handling equipment, as well as drum and container handling, opening, sampling, shipping and transport. Describe prevention measures, such as building berms or dikes; spill control measures and material to be used (e.g. booms, vermiculite); location of the spill control material; personal protective equipment required to cleanup spills; disposal of contaminated material; and who is responsible to report the spill. Storage of contaminated material or hazardous materials must be appropriately bermed, diked and contained to prevent any spillage of material on uncontaminated soil. If the spill or discharge is

reportable, or human health or the environment are threatened, notify the National Response Center, the state, and the Contracting Officer as soon as possible. Provide control as required by Section 01 57 19 TEMPORARY ENVIRONMENT CONTROLS. Reporting requirements must be in accordance with .

3.8 MATERIALS TRANSFER SAFETY

Remove liquids and residues from the tanks using explosion-proof or air-driven pumps. In accordance with EM 385-1-1, Section 9, electrically bond the tank and ground pump motors and suction hoses to prevent electrostatic ignition hazards. Use of a hand pump will be permitted to remove the last of the liquid from the bottom of the tanks. If a vacuum truck is used for removal of liquids or residues, the area of operation for the vacuum truck must be vapor free. Locate the truck upwind from the tank and outside the path of probable vapor travel. Discharge the vacuum pump exhaust gases through a hose of adequate size and length downwind of the truck and tank area. Vacuum truck operating and safety practices must conform to API RP 2219. Collect tank residues in drums, tanks, or tank trucks labeled according to 49 CFR 171 and 49 CFR 172 and disposed of as specified. Disconnect and drain fittings and lines of their contents after the materials have been transferred and the tanks have been exposed. Do not spill contents into the environment during cutting or disconnecting of tank fittings. Transfer materials drained into DOT-approved drums for storage and transportation. Use only non-sparking or non-heat producing tools to disconnect and drain or to cut through tank fittings. Electrical equipment (e.g., pumps, portable hand tools) used for tank preparation must be explosion-proof. Following cutting or disconnecting of the fittings, plug openings leading to the tanks.

3.9 SITE CONTROL MEASURES

Coordinate site control measures with Section 01 57 19 TEMPORARY ENVIRONMENT CONTROLS.

3.9.1 Work Zones

Initial anticipated work zone boundaries (exclusion zone, contamination reduction zone, support zone, all access points and decontamination areas) are to be clearly delineated on the site drawings. Base delineation of work zone boundaries on the contamination characterization data and the hazard/risk analysis to be performed as described in EM 385-1-1 06.A.02. As work progresses and field conditions are monitored, work zone boundaries may be modified (and site drawings modified) with approval of the Contracting Officer. Clearly identify work zones and mark in the field (using fences, tape, or signs). Submit and post a site map, showing work zone boundaries and locations of decontamination facilities in the onsite office. Work zones must consist of the following:

3.9.1.1 Exclusion Zone (EZ)

The exclusion zone is the area where hazardous contamination is either known or expected to occur and the greatest potential for exposure exists. Control entry into this area and exit may only be made through the Contamination Reduction Zone (CRZ).

3.9.1.2 Contamination Reduction Zone (CRZ)

The CRZ is the transition area between the Exclusion Zone and the Support Zone. The personnel and equipment decontamination areas must be separate

and unique areas located in the CRZ.

3.9.1.3 Support Zone (SZ)

The Support Zone is defined as areas of the site, other than exclusion zones and contamination reduction zones, where workers do not have the potential to be exposed to hazardous substances or dangerous conditions resulting from HTRW operations. Secure the Support Zone against active or passive contamination. Site offices, parking areas, and other support facilities must be located in the Support Zone.

3.9.2 Site Control Log

A log of personnel visiting, entering, or working on the site must be maintained. Include the following: date, name, agency or company, time entering and exiting site, time entering and exiting the exclusion zone (if applicable). Before visitors are allowed to enter the Contamination Reduction Zone or Exclusion Zone, they must show proof of current training, medical surveillance and respirator fit testing (if respirators are required for the tasks to be performed) and fill out a Certificate of Worker or Visitor Acknowledgment. Record this visitor information, including date, in the log.

3.9.3 Communication

Provide and install an employee alarm system that has adequate means of on and off site communication in accordance with 29 CFR 1910 Section .165. The means of communication must be able to be perceived above ambient noise or light levels by employees in the affected portions of the workplace. The signals must be distinctive and recognizable as messages to evacuate or to perform critical operations.

3.9.4 Site Security

Provide the following site security: Print signs in bold large letters on contrasting backgrounds. Signs must be visible from all points where entry might occur and at such distances from the restricted area that employees may read the signs and take necessary protective steps before entering.

3.10 PERSONAL HYGIENE AND DECONTAMINATION

Personnel entering the Exclusion or Contamination Reduction Zones or otherwise exposed to hazardous chemical vapors, gases, liquids, or contaminated solids must decontaminate themselves and their equipment prior to exiting the contamination reduction zone (CRZ) and entering the support zone. Consult Chapter 10.0 of NIOSH 85-115 when preparing decontamination procedures. Submit a detailed discussion of personal hygiene and decontamination facilities and procedures to be followed by site workers as part of the APP/SSHP. Train employees in the procedures and enforce the procedures throughout site operations.

3.10.1 Decontamination Facilities

Submit drawings showing the layout of the personnel and equipment decontamination areas.

3.10.2 Personnel Decontamination

Initially set up a decontamination line in the CRZ. Employees must exit the exclusion zone through the CRZ and implement the following decontamination procedures and techniques: Scrub and rinse water proof outer garments hand and face wash. Showers, if needed, must comply with 29 CFR 1910, Section.141 and EM 385-1-1, 02 F, Washing Facilities. It is the Site Safety and Health Officer's responsibility to recommend techniques to improve personnel decontamination procedures, if necessary.

3.10.3 Equipment Decontamination

Decontaminate the vehicles and equipment used in the EZ in the CRZ prior to leaving the EZ.

3.10.3.1 Facilities for Equipment and Personnel

Provide a vehicle/equipment decontamination station within the CRZ for decontaminating vehicles and equipment leaving the EZ.

3.10.3.2 Procedures

Procedures for equipment decontamination must be developed and utilized to prevent the spread of contamination into the SZ and offsite areas. These procedures must address disposal of contaminated products and spent materials used on the site, including, as a minimum, containers, fluids, and oils. Assume any item taken into the EZ to be contaminated and perform an inspection and decontaminate. Vehicles, equipment, and materials must be cleaned and decontaminated prior to leaving the site. Handle construction material in such a way as to minimize the potential for contaminants being spread or carried offsite. Prior to exiting the site, vehicles and equipment must be monitored to ensure the adequacy of decontamination.

Task Hazard and Control Requirements Sheet	
Task	
Initial Anticipated Hazards	
Initial PPE	
Initial Controls	
Initial Exposure Monitoring	
No	HAZWOPER Medical Surveillance Required
Yes	HAZWOPER Training Required

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS
05/24

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization (e.g., ASTM B564 Standard Specification for Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided.

ACOUSTICAL SOCIETY OF AMERICA (ASA)
1305 Walt Whitman Road, Suite 110
Melville, NY 11747-4300
Ph: 516-576-2360
Fax: 631-923-2875
E-mail: asa@acousticalsociety.org
Internet: https://acousticalsociety.org/

AIR BARRIER ASSOCIATION OF AMERICA (ABAA)
1600 Boston-Providence Hwy
Walpole, MA 02081
Ph: 1-866-956-5888
Fax: 1-866-956-5819
E-mail: abaa@airbarrier.org
Internet: https://www.airbarrier.org/

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL, INC. (AMCA)
30 West University Drive
Arlington Heights, IL 60004-1893
Ph: 847-394-0150
Fax: 847-253-0088
E-mail: communications@amca.org
Internet: http://www.amca.org

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)
2311 Wilson Blvd, Suite 400
Arlington, VA 22201
Ph: 703-524-8800
Internet: http://www.ahrinet.org

ALUMINUM ASSOCIATION (AA)
1400 Crystal Drive
Suite 430

Arlington, VA 22202
Ph: 703-358-2960

Internet: https://www.aluminum.org/

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)
1900 E Golf Rd, Suite 1250
Schaumburg, IL 60173
Ph: 847-303-5664
E-mail: customerservice@FGIAonline.org
Internet: https://fgiaonline.org/

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)
555 12th Street NW, Suite 1000
Washington, DC 20004
Ph: 202-624-5800
Fax: 202-624-5806
E-Mail: info@aashto.org
Internet: https://www.transportation.org/

AMERICAN ASSOCIATION OF TEXTILE CHEMISTS AND COLORISTS (AATCC)
1 Davis Drive
P.O. Box 12215
Research Triangle Park, NC 27709-2215
Ph: 919-549-8141

E-Mail: ordering@aatcc.org
Internet: https://www.aatcc.org/

AMERICAN BEARING MANUFACTURERS ASSOCIATION (ABMA)
1001 N. Fairfax Street Suite 500
Alexandria, VA 22314
Ph: 703-842-0030
E-mail: info@americanbearings.org
Internet: https://www.americanbearings.org/

AMERICAN CONCRETE INSTITUTE (ACI)
38800 Country Club Drive
Farmington Hills, MI 48331-3439
Ph: 248-848-3800
Fax: 248-848-3701
Internet: https://www.concrete.org/

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)
3640 Park 42 Drive
Cincinnati, OH 45241
Ph: 513-742-2020
Fax: 513-742-3355
Email: customerservice@acgih.org
Internet: https://www.acgih.org/

AMERICAN FOREST FOUNDATION (AFF)
American Tree Farm System
2000 M Street, NW, Suite 550
Washington, DC 20036
Ph: 202-765-3660
Fax: 202-827-7924
Email: info@forestfoundation.org

Internet: https://www.treefarmsystem.org

AMERICAN GAS ASSOCIATION (AGA)
400 North Capitol Street, NW
Suite 450
Washington, D.C. 20001
Ph: 202-824-7000
Internet: https://www.aga.org/

AMERICAN HARDBOARD ASSOCIATION (AHA)
1210 West Northwest Highway
Palatine, IL 60067
Ph: 847-934-8800
Fax: 847-934-8803
E-mail: aha@hardboard.org
Internet: http://domensino.com/AHA/

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)
130 East Randolph, Suite 2000
Chicago, IL 60601
Ph: 312-670-2400
Fax: 312-670-5403
Steel Solutions Center: 866-275-2472
E-mail: solutions@aisc.org
Internet: https://www.aisc.org/

AMERICAN IRON AND STEEL INSTITUTE (AISI)
25 Massachusetts Avenue, NW Suite 800
Washington, DC 20001
Ph: 202-452-7100
Internet: https://www.steel.org/

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)
1899 L Street, NW,11th Floor
Washington, DC 20036
Ph: 202-293-8020
Fax: 202-293-9287
E-mail: info@ansi.org
Internet: https://www.ansi.org/

AMERICAN PETROLEUM INSTITUTE (API)
200 Massachusetts Avenue NW Suite 1100
Washington, DC 20001-5571
Ph: 202-682-8000
Internet: https://www.api.org/

AMERICAN SOCIETY FOR NONDESTRUCTIVE TESTING (ASNT)
1201 Dublin Road Suite G04

Columbus, OH 43215-1045
Ph: 800-222-2768 or 614-274-6003

E-mail: customersupport@asnt.org
Internet: https://www.asnt.org/

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)
1801 Alexander Bell Drive
Reston, VA 20191
Ph: 800-548-2723; 703-295-6300

Email: customercare@asce.org
Internet: https://www.asce.org/

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)
180 Technology Parkway NW
Peachtree Corners, GA 30092
Ph: 404-636-8400 or 800-527-4723
Fax: 404-321-5478
E-mail: ashrae@ashrae.org
Internet: https://www.ashrae.org/

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)
Two Park Avenue
New York, NY 10016-5990
Ph: 800-843-2763
Fax: 973-882-1717
E-mail: customercare@asme.org
Internet: https://www.asme.org/

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)
520 N. Northwest Highway
Park Ridge, IL 60068
Ph: 847-699-2929
E-mail: customerservice@assp.org
Internet: https://www.assp.org/

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)
18927 Hickory Creek Drive, Suite 220
Mokena, IL 60448
Ph: 708-995-3019
Fax: 708-479-6139
Internet: http://www.asse-plumbing.org

AMERICAN WATER WORKS ASSOCIATION (AWWA)
6666 W. Quincy Avenue
Denver, CO 80235 USA
Ph: 303-794-7711 or 800-926-7337
Fax: 303-347-0804
Internet: https://www.awwa.org/

AMERICAN WELDING SOCIETY (AWS)
8669 NW 36 Street, #130
Miami, FL 33166-6672
Ph: 800-443-9353
Email: customercare@aws.org
Internet: https://www.aws.org/

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)
P.O. Box 361784
Birmingham, AL 35236-1784
Ph: 205-733-4077
Fax: 205-733-4075
Internet: http://www.awpa.com

AmericanHort (AH)
2130 Stella Court
Columbus, OH 43215
Ph: 614-487-1117 OH

Ph: 202-789-2900 DC
Internet: https://www.americanhort.org/

ASPHALT INSTITUTE (AI)
2696 Research Park Drive
Lexington, KY 40511-8480
Ph: 859-288-4960 or 1-866-540-9577
Fax: 859-288-4999
E-mail: info@asphaltinstitute.org
Internet: http://www.asphaltinstitute.org

ASSOCIATED AIR BALANCE COUNCIL (AABC)
1015 18th St. NW Suite 603
Washington, DC 20036
Ph: 202-737-0202
Fax: 202-315-0285
E-mail: info@aabc.com
Internet: https://www.aabc.com/

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)

P.O. Box 58130
Washington, DC 20037
Ph: 205-257-3839
Fax: 205-257-2540
Internet: https://aeic.org/

ASTM INTERNATIONAL (ASTM)
100 Barr Harbor Drive, P.O. Box C700
West Conshohocken, PA 19428-2959
Ph: 610-832-9500
Fax: 610-832-9555
E-mail: service@astm.org
Internet: https://www.astm.org/

AUDIOVISUAL AND INTEGRATED EXPERIENCE ASSOCIATION (AVIXA)
11242 Waples Mill Road
Suite 200
Fairfax, VA 22030
Ph: 703-273-7200/800-659-7469
E-mail: membership@avixa.org
Internet: https://www.avixa.org/

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)
529 14th Street NW Suite 1280
Washington, DC 20045
Ph: 212-297-2122
Fax: 212-370-9047
Internet: https://www.buildershardware.com/

CALIFORNIA AIR RESOURCES BOARD (CARB)
1001 I Street
Sacramento, CA 95814
Ph: 800-242-4450
Email: helpline@arb.ca.gov
Internet: https://ww2.arb.ca.gov/

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)
PO Box 997377, MS 0500
Sacramento, CA 95899-7377
Ph: 916-558-1784
Internet: https://www.cdph.ca.gov/

CARPET AND RUG INSTITUTE (CRI)
P.O. Box 2048
Dalton, GA 30722-2048
Ph: 706-278-3176
Fax: 706-278-8835
Internet: https://carpet-rug.org/

CEILINGS AND INTERIOR SYSTEMS CONSTRUCTION ASSOCIATION (CISCA)
P.O. Box 293
Elmhurst, IL 60126
Ph: 630-584-1919
Fax: 866-560-8537
E-mail: cisca@cisca.org
Internet: https://www.cisca.org

CENTERS FOR DISEASE CONTROL AND PREVENTION (CDC)
1600 Clifton Road
Atlanta, GA 30329-4027
Ph: 800-232-4636
TTY: 888-232-6348
Internet: https://www.cdc.gov

CONCRETE REINFORCING STEEL INSTITUTE (CRSI)
933 North Plum Grove Road
Schaumburg, IL 60173-4758
Ph: 847-517-1200
Email: crsi@crsi.org
Fax: 847-517-1206
Internet: http://www.crsi.org/

CONSUMER ELECTRONICS ASSOCIATION (CEA)
1919 South Eads St.
Arlington, VA 22202
Ph: 703-907-7600
E-mail: CTA@CTA.tech
Internet: https://www.cta.tech/

COPPER DEVELOPMENT ASSOCIATION (CDA)
Internet: https://www.copper.org/

COUNCIL ON ENVIRONMENTAL QUALITY (CEQ) (WHITE HOUSE)
722 Jackson Place
Washington DC 20506
Internet: https://www.whitehouse.gov/administration/eop/ceq

CSA GROUP (CSA)
178 Rexdale Blvd.
Toronto, ON, Canada M9W 1R3
Ph: 416-747-4044
Fax: 416-747-2510
E-mail: member@csagroup.org
Internet: https://www.csagroup.org/

DOOR AND ACCESS SYSTEM MANUFACTURERS ASSOCIATION (DASMA)
1300 Sumner Avenue
Cleveland, OH 44115-2851
Ph: 216-241-7333
Fax: 216-241-0105
Email dasma@dasma.com
Internet: https://www.dasma.com/

DUCTILE IRON PIPE RESEARCH ASSOCIATION (DIPRA)
P.O. Box 190306
Birmingham, AL 35216
Ph: 205-402-8700
Email: info@dipra.org
Internet: https://www.dipra.org/

ELECTRICAL GENERATING SYSTEMS ASSOCIATION (EGSA)
P.O. Box 73206
Washington, DC 20056
Ph: 561-750-5575
Fax: 561-395-8557
Email: e-mail@egsa.org
Internet: http://www.egsa.org

ELECTRONIC COMPONENTS INDUSTRY ASSOCIATION (ECIA)
310 Maxwell Road, Suite 200
Alpharetta, GA 30009
Ph: 678-393-9990
Fax: 678-393-9998
E-mail: emikoski@ecianow.org
Internet: https://www.ecianow.org

EUROPEAN COMMITTEE FOR STANDARDIZATION (CEN/CENELEC)
CEN-CENELEC Management Centre
Rue de la Science 23
B - 1040 Brussels, Belgium
Ph: 32-2-550-08-11
Fax: 32-2-550-08-19
Internet: https://www.cencenelec.eu/

EUROPEAN UNION (EU)
European Commission
Rue de la Loi 200
1000 Bruxelle
Belgium
Ph: +32 2 299 96 96
Internet: https://commission.europa.eu/index_en

EXPANSION JOINT MANUFACTURERS ASSOCIATION (EJMA)
25 North Broadway
Tarrytown, NY 10591
Fax: 914-332-1541
E-mail: inquiries@ejma.org
Internet: http://www.ejma.org

FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA)
615 Chestnut Street
One Independence Mall, Sixth Floor
Philadelphia, PA 19106-4404
Ph: 215-931-5597

E-mail: femar3newsdesk@fema.dhs.gov
Internet: https://www.fema.gov/

FM GLOBAL (FM)
270 Central Avenue
Johnston, RI 02919-4949
Ph: 401-275-3000
Fax: 401-275-3029
Internet: https://www.fmglobal.com/

FOREST STEWARDSHIP COUNCIL (FSC)
1441 Woodmont Ln NW #539
Atlanta, GA 30318
Ph: 612-353-4511
E-mail: info@us.fcs.org
Internet: https://us.fsc.org/

GLASS ASSOCIATION OF NORTH AMERICA (GANA)
National Glass Association
1945 Old Gallows Rd., Suite 750
Vienna, VA 22182
Ph: 866-342-5642
Ph: 703-442-4890
Fax: 703-442-0630
Internet: https://www.glass.org/

GREEN BUILDING INITIATIVE (GBI)
7805 SW 40th Ave. #80010
Portland, Oregon 97219
Ph: 503-274-0448
Email: info@thegbi.org
Internet: https://www.thegbi.org/

GREEN SEAL (GS)
601 13th St NW 12th Floor
Washington, DC 20005
Ph: 202-872-6400
Fax: 202-872-4324
E-mail: greenseal@greenseal.org
Internet: https://www.greenseal.org/

GYPSUM ASSOCIATION (GA)
962 Wayne Ave., Suite 620
Silver Spring, MD 20910
Ph: 301-277-8686
Fax: 301-277-8747
E-mail: info@gypsum.org
Internet: https://www.gypsum.org/

HYDRAULIC INSTITUTE (HI)
300 Interpace Parkway
Parsippany, NJ 07054-4405
Ph: 973-267-9700
Fax: 973-267-9055
Internet: http://www.pumps.org

ICC EVALUATION SERVICE, INC. (ICC-ES)
3060 Saturn Street, Suite 100
Brea, CA 92821

Ph: 800-423-6587
Fax: 562-695-4694
E-mail: es@icc-es.org
Internet: https://icc-es.org/

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY (IEPA)
1021 North Grand Avenue, East
PO Box 19276
Springfield, IL 62794-9276
Ph: 217-782-3397
Internet: https://epa.illinois.gov/

ILLUMINATING ENGINEERING SOCIETY (IES)
120 Wall Street, Floor 17
New York, NY 10005-4001
Ph: 212-248-5000
Fax: 212-248-5018
E-mail: membership@ies.org
Internet: https://www.ies.org/

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)
445 and 501 Hoes Lane
Piscataway, NJ 08854-4141
Ph: 732-981-0060 or 800-701-4333
Fax: 732-981-9667
E-mail: onlinesupport@ieee.org
Internet: https://www.ieee.org/

INSULATED CABLE ENGINEERS ASSOCIATION (ICEA)
P.O. Box 493
Miamitown, OH 45041-9998
E-mail: info@icea.net
Internet: https://www.icea.net/

INSULATING GLASS MANUFACTURERS ALLIANCE (IGMA)
27 N. Wacker Dr. Suite 365
Chicago, IL 60606-2800
Ph: 613-233-1510
Fax: 613-482-9436
E-mail: enquiries@igmaonline.org
Internet: https://fgiaonline.org//

INTELLIGENCE COMMUNITY STANDARD (ICS)
Homeland Security Digital Library
Ph: 831-272-2437
E-mail: hsdl@nps.edu
Internet: https://www.hsdl.org/c/

INTERNATIONAL CAST POLYMER ASSOCIATION (ICPA)
12195 Highway 92 Suite 114 #176
Woodstock, GA 30188
Ph: 470-219-8139
Internet: https://theicpa.com/

INTERNATIONAL CODE COUNCIL (ICC)
200 Massachusetts Ave, NW Suite 250
Washington, DC 20001
Ph: 800-786-4452 or 888-422-7233
Fax: 202-783-2348

E-mail: order@iccsafe.org
Internet: https://www.iccsafe.org/

INTERNATIONAL CONCRETE REPAIR INSTITUTE (ICRI)
1601 Utica Avenue South, Suite 213
Minneapolis MN 55416
Ph: 651-366-6095
Fax: 651-290-2266
E-mail: info@icri.org
Internet: https://www.icri.org/

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)
3050 Old Centre Ave. Suite 101
Portage, MI 49024
Ph: 269-488-6382 or 1-888-300-6382
Fax: 269-488-6383
Internet: https://www.netaworld.org/

INTERNATIONAL ELECTROTECHNICAL COMMISSION (IEC)
3, rue de Varembe, 1st floor
P.O. Box 131
CH-1211 Geneva 20, Switzerland
Ph: 41-22-919-02-11
Fax: 41-22-919-03-00
E-mail: info@iec.ch
Internet: https://www.iec.ch/

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)
ISO Central Secretariat
BIBC II
Chemin de Blandonnet 8
CP 401 - 1214 Vernier, Geneva
Switzerland
Ph: 41-22-749-01-11
E-mail: central@iso.ch
Internet: https://www.iso.org

INTERNATIONAL SAFETY EQUIPMENT ASSOCIATION (ISEA)
1101 Wilson Blvd, Suite 1425
Arlington, VA 22209-1762
Ph: 703-525-1695
Fax: 703-528-2148
Internet: https://safetyequipment.org/

L.H. BAILEY HORTORIUM (LHBH)
Plant Biology Units
The L.H. Bailey Hortorium and Herbarium
440 Mann Library Building
Ithaca, NY 14853
Ph: 607-255-1052
Fax: 607-254-5407
Internet:
https://cals.cornell.edu/school-integrative-plant-science/school-sections/plar

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)
127 Park Street, NE
Vienna, VA 22180-4602
Ph: 703-281-6613

E-mail: info@msshq.org
Internet: http://msshq.org

MARBLE INSTITUTE OF AMERICA (MIA)
Natural Stone Institute
380 E. Lorain Street
Oberlin, OH 44074
Ph: 440-250-9222
Fax: 440-774-9222
E-mail: info@naturalstoneinstitute.org
Internet: https://www.naturalstoneinstitute.org/

MASTER PAINTERS INSTITUTE (MPI)
2800 Ingleton Avenue
Burnaby, BC CANADA V5C 6G7
Ph: 1-888-674-8937
Fax: 1-888-211-8708
E-mail: info@paintinfo.com or techservices@mpi.net
Internet: http://www.mpi.net/

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)
1300 Sumner Avenue
Cleveland, OH 44115-2851
Ph: 216-241-7333
Fax: 216-241-0105
Internet: https://www.mbma.com/

METAL FRAMING MANUFACTURERS ASSOCIATION (MFMA)
330 N. Wabash Avenue
Chicago, IL 60611
Ph: 312-644-6610
E-mail: MFMAstats@smithbucklin.com
Internet: http://www.metalframingmfg.org/

MIDWEST INSULATION CONTRACTORS ASSOCIATION (MICA)
7250 Poe Avenue, Suite 410
Dayton, OH 45414
Ph: 888-294-0084
Fax: 937-278-0317
Email: info@micainsulation.org
Internet: https://www.micainsulation.org/

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)
800 Roosevelt Road, Bldg C, Suite 312
Glen Ellyn, IL 60137
Ph: 630-942-6591
Fax: 630-790-3095
E-mail: info@naamm.org
Internet: http://www.naamm.org

NATIONAL BOARD OF BOILER AND PRESSURE VESSEL INSPECTORS (NBBI)
1055 Crupper Avenue
Columbus, OH 43229-1183
Ph: 614-888-8320
Fax: 614-888-0750
E-mail: information@nationalboard.org
Internet: https://www.nationalboard.org

NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA)
1201 Pennsylvania Ave. NW, Suite 1200
Washington, DC 20004
Ph: 202-991-6300
Fax: 202-217-4171
Internet: https://www.necanet.org/

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)
1300 North 17th Street, Suite 900
Arlington, VA 22209
Ph: 703-841-3200
Email: communications@nema.org
Internet: https://www.nema.org

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)
8575 Grovemont Circle
Gaithersburg, MD 20877
Ph: 301-977-3698
Fax: 301-977-9589
Internet: http://www.nebb.org

NATIONAL FENESTRATION RATING COUNCIL (NFRC)
6305 Ivy Lane, Suite 140
Greenbelt, MD 20770
Ph: 301-589-1776
Fax: 301-589-3884
E-Mail: info@nfrc.org
Internet: http://www.nfrc.org

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
1 Batterymarch Park
Quincy, MA 02169-7471
Ph: 800-344-3555
Fax: 800-593-6372
Internet: https://www.nfpa.org

NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES (NICET)
1420 King Street
Alexandria, VA 22314-2794
Ph: 888-476-4238 (1-888 IS-NICET)
E-mail: tech@nicet.org
Internet: https://www.nicet.org/

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH)
Patriots Plaza 1
395 E Street, SW, Suite 9200
Washington, DC 20201
Ph: 800-232-4636
Fax: 513-533-8347
Internet: https://www.cdc.gov/niosh/

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST)
100 Bureau Drive
Gaithersburg, MD 20899
Ph: 301-975-2000
Internet: https://www.nist.gov/

NATIONAL READY MIXED CONCRETE ASSOCIATION (NRMCA)
Manager, Customer Service
66 Canal Center Plaza, Suite 250
Alexandria, VA 22314
Ph: 703-706-4800
Fax: 703-706-4809
E-mail: jjenkins@nrmca.org (Jacques Jenkins)
Internet: https://www.nrmca.org/

NATIONAL TERRAZZO AND MOSAIC ASSOCIATION (NTMA)
P.O. Box 2605
Fredericksburg, TX 78624
Ph: 800-323-9736
Fax: 888-362-2770
E-mail: tech-info@ntma.com
Internet: https://www.ntma.com/

NSF INTERNATIONAL (NSF)
789 North Dixboro Road
P.O. Box 130140
Ann Arbor, MI 48105
Ph: 734-769-8010 or 800-NSF-MARK
Fax: 734-769-0109
E-mail: info@nsf.org
Internet: http://www.nsf.org

ORGANISATION FOR ECONOMIC CO-OPERATION AND DEVELOPMENT (OECD)
2, rue Andre Pascal
75775 Paris Cedex 16, France
Ph: + 33 1 45 24 82 00
Fax: 33 1 45 24 85 00
Internet: http://www.oecd.org
U.S. Contact Center
OECD Washington Center
1776 I Street, NW, Suite 450
Washington, DC 20006
Ph: 202-785-6323
E-mail: washington.contact@oecd.org

PLASTIC PIPE AND FITTINGS ASSOCIATION (PPFA)
800 Roosevelt Road
Building C, Suite 312
Glen Ellyn, IL 60137
Ph: 630-858-6540
Fax: 630-790-3095
Internet: https://www.ppfahome.org/

PLUMBING AND DRAINAGE INSTITUTE (PDI)
800 Turnpike Street, Suite 300
North Andover, MA 01845
Ph: 978-557-0720 or 800-589-8956
E-Mail: pdi@PDIonline.org
Internet: http://www.pdionline.org

PROGRAMME FOR ENDORSEMENT OF FOREST CERTIFICATION (PEFC)
10, Route de l'Aeroport
Case Postale 638
1215 Geneva - Switzerland
Ph: +41 (22) 799-4540

Fax: +41 (22) 799-4550
Email: info@pefc.org
Internet: https://www.pefc.org/

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)
2000 Powell Street, Suite 600
Emeryville, CA 94608
Ph: 510-452-8000
Fax: 510-452-8001
E-mail: info@SCSglobalservices.com
Internet: https://www.scsglobalservices.com/

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
4201 Lafayette Center Drive
Chantilly, VA 20151-1219
Ph: 703-803-2980
Fax: 703-803-3732
Internet: https://www.smacna.org/

SOCIETY FOR PROTECTIVE COATINGS (SSPC)
800 Trumbull Drive
Pittsburgh, PA 15205
Ph: 877-281-7772 or 412-281-2331
Fax: 412-444-3591
E-mail: customerservice@sspc.org
Internet: http://www.sspc.org

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)
400 Commonwealth Drive
Warrendale, PA 15096
Ph: 877-606-7323 or 724-776-4841
Fax: 724-776-0790
E-mail: customerservice@sae.org
Internet: https://www.sae.org/

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)
21865 Copley Drive
Diamond Bar, CA 91765
Ph: 909-396-2000
E-mail: webinquiry@aqmd.gov
Internet: http://www.aqmd.gov

STEEL DECK INSTITUTE (SDI)
P.O. Box 426
Glenshaw, PA 15116
Ph: 412-487-3325
Fax: 412-487-3326
Internet: https://www.sdi.org/

STEEL DOOR INSTITUTE (SDI/DOOR)
30200 Detroit Road
Westlake, OH 44145
Ph: 440-899-0010
Fax: 440-892-1404
E-mail: info@steeldoor.org
Internet: https://www.steeldoor.org/

STEEL JOIST INSTITUTE (SJI)
234 W. Cheves Street
Florence, SC 29501
Ph: 843-407-4091
Internet: https://steeljoist.org/

SUSTAINABLE FOREST INITIATIVE (SFI)
2121 K Street NW
Suite 750
Washington, DC 20037
Ph: 202-596-3450
Fax: 202-596-3451
E-mail: info@sfiprogram.org
Internet: https://forests.org/

TECHNICAL ASSOCIATION OF THE PULP AND PAPER INDUSTRY (TAPPI)
15 Technology Parkway South, Suite 115
Peachtree Corners, GA 30092
Ph: 800-332-8686 or 770-446-1400
Fax: 770-446-6947
E-mail: memberconnection@tappi.org
Internet: http://www.tappi.org

TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA)
1320 North Courthouse Rosd, Suite 200
Arlington, VA 22201
Ph: 703-907-7700
Fax: 703-907-7727
E-mail: marketing@tiaonline.org
Internet: https://www.tiaonline.org/

THE MASONRY SOCIETY (TMS)
105 South Sunset Street, Suite Q
Longmont, CO 80501-6172
Ph: 303-939-9700
Fax: 303-541-9215
E-mail: info@masonrysociety.org
https://masonrysociety.org/

TILE COUNCIL OF NORTH AMERICA (TCNA)
100 Clemson Research Boulevard
Anderson, SC 29625
Ph: 864-646-8453
Fax: 864-646-2821
E-mail: info@tileusa.com
Internet: https://www.tcnatile.com/

TREE CARE INDUSTRY ASSOCIATION (TCIA)
136 Harvey Road, Suite 101
Londonderry, NH 03053
Ph: 603-314-5380 or 800-733-2622
Fax: 603-314-5386
Email: memberservices@tcia.org
Internet: https://tcia.org/

TURFGRASS PRODUCERS INTERNATIONAL (TPI)
444 E. Roosevelt Road
#346
Lombard, IL 60148

Ph: 800-405-8873 or 847-649-5555
Fax: 847-649-5678
E-mail: info@turfgrasssod.org
Internet: http://www.turfgrasssod.org

U.S. ARMY CORPS OF ENGINEERS (USACE)
CRD-C DOCUMENTS available on Internet: https://www.wbdg.org/army
THE CAD/BIM TECHNOLOGY CENTER FOR FACILITIES, INFRASTRUCTURE, AND ENVIRONMENT (USACE)on Internet:
https://cadbimcenter.erdc.dren.mil/
Order Other Documents from:
Official Publications of the Headquarters, USACE
E-mail: hqpublications@usace.army.mil
Internet: http://www.publications.usace.army.mil/
or
https://www.hnc.usace.army.mil/Missions/Engineering-Directorate/TECHINFO/

U.S. DEPARTMENT OF AGRICULTURE (USDA)
Order AMS Publications from:
AGRICULTURAL MARKETING SERVICE (AMS)
Seed Regulatory and Testing Branch
801 Summit Crossing Place, Suite C
Gastonia, NC 28054-2193
Ph: 704-810-8884
E-mail: PA@usda.gov
Internet: https://www.ams.usda.gov/
Order Other Publications from:
USDA Rural Development
Rural Utilities Service
STOP 1510, Rm 5135
1400 Independence Avenue SW
Washington, DC 20250-1510
Phone: (202) 720-9540
Internet:
https://www.rd.usda.gov/about-rd/agencies/rural-utilities-service

U.S. DEPARTMENT OF DEFENSE (DOD)
Order DOD Documents from:
Room 3A750-The Pentagon
1400 Defense Pentagon
Washington, DC 20301-1400
Ph: 703-571-3343
Fax: 215-697-1462
E-mail: customerservice@ntis.gov
Internet: https://www.ntis.gov/
Obtain Military Specifications, Standards and Related Publications from:
Acquisition Streamlining and Standardization Information System (ASSIST)
Department of Defense Single Stock Point (DODSSP)
Document Automation and Production Service (DAPS)
Building 4/D
700 Robbins Avenue
Philadelphia, PA 19111-5094
Ph: 215-697-6396 - for account/password issues
Internet: https://assist.dla.mil/online/start/; account registration required
Obtain Unified Facilities Criteria (UFC) from:
Whole Building Design Guide (WBDG)

National Institute of Building Sciences (NIBS)
1090 Vermont Avenue NW, Suite 700
Washington, DC 20005
Ph: 202-289-7800
Fax: 202-289-1092
Internet:
https://www.wbdg.org/ffc/dod/unified-facilities-criteria-ufc

U.S. DEPARTMENT OF ENERGY (DOE)
1000 Independence Avenue Southwest
Washington, D.C. 20585
Ph: 202-586-5000
Fax: 202-586-4403
E-mail: The.Secretary@hq.doe.gov
Internet: https://www.energy.gov/

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)
1200 Pennsylvania Avenue, N.W.
Washington, DC 20004
Ph: 202-564-4700
Internet: https://www.epa.gov
--- Some EPA documents are available only from:
National Technical Information Service (NTIS)
5301 Shawnee Road
Alexandria, VA 22312
Ph: 703-605-6060 or 1-800-363-2068
Fax: 703-605-6880
TDD: 703-487-4639
E-mail: info@ntis.gov
Internet: https://www.ntis.gov/

U.S. FEDERAL COMMUNICATIONS COMMISSION (FCC)
445 12th Street SW
Washington, DC 20554
Ph: 888-225-5322
TTY: 888-835-5322
Fax: 866-418-0232
Internet: https://www.fcc.gov/
Order Publications From:
Superintendent of Documents
U.S. Government Publishing Office (GPO)
732 N. Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800 or 866-512-1800
Bookstore: 202-512-0132
Internet: https://www.gpo.gov/

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)
1200 New Jersey Ave., SE
Washington, DC 20590
Ph: 202-366-4000
E-mail: ExecSecretariat.FHWA@dot.gov
Internet: https://highways.dot.gov/
Order from:
Superintendent of Documents
U.S. Government Publishing Office (GPO)
732 N. Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800 or 866-512-1800

Bookstore: 202-512-0132
Internet: https://www.gpo.gov/

U.S. GENERAL SERVICES ADMINISTRATION (GSA)
General Services Administration
1800 F Street, NW
Washington, DC 20405
Ph: 1-844-472-4111
Internet: https://www.gsaelibrary.gsa.gov/ElibMain/home.do
Obtain documents from:
Acquisition Streamlining and Standardization Information System (ASSIST)
Internet: https://assist.dla.mil/online/start/; account registration required

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)
8601 Adelphi Road
College Park, MD 20740-6001
Ph: 866-272-6272
Internet: https://www.archives.gov/
Order documents from:
Superintendent of Documents
U.S. Government Publishing Office (GPO)
732 N. Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800 or 866-512-1800
Bookstore: 202-512-0132
Internet: https://www.gpo.gov/

UL ENVIRONMENT (ULE)
2211 Newmarket Parkway, Suite 106
Marietta, GA 30067
Ph: 888-485-4733
E-mail: environment@ul.com
Internet:
https://www.ul.com/services/portfolios/sustainability-and-environment

UNDERWRITERS LABORATORIES (UL)
2600 N.W. Lake Road
Camas, WA 98607-8542
Ph: 877-854-3577 or 360-817-5500
E-mail: CustomerExperienceCenter@ul.com
Internet: https://www.ul.com/
UL Directories available through IHS at https://ihsmarkit.com/

UL SOLUTIONS (UL)
333 Pfingsten Road
Northbrook, IL 60062
Ph: 877-854-3577 or 360-817-5500
E-mail: CustomerExperienceCenter@ul.com
Internet: https://www.ul.com/
UL Directories available through IHS at https://accuristech.com/

UNI-BELL PVC PIPE ASSOCIATION (UBPPA)
Corporate Headquarters
2711 LBJ Freeway, Suite 1000
Dallas, TX 75234
Ph: 972-243-3902
Fax: 972-243-3907

E-mail: info@uni-bell.org
Internet: https://www.uni-bell.org/

VIBRATION ISOLATION AND SEISMIC CONTROL MANUFACTURERS ASSOCIATION (VISCMA)
994 Old Eagle School Road
Suite 1019
Wayne, PA 19087-1866
Ph: 610-971-4850
E-mail: info@viscma.com
Internet: http://www.viscma.com

WASHINGTON STATE ADMINISTRATIVE CODE (WAC)
Legislative Information Center
Cheri Randich, Manager
110 Legislative Building
Olympia, WA 98504-0600
Ph: 360-786-7573
E-mail: support@leg.wa.gov
Internet: https://app.leg.wa.gov/wac/

WINDOW AND DOOR MANUFACTURERS ASSOCIATION (WDMA)
2001 K Streeet NW
3rd Floor North
Washington, DC 20006
Ph: 202-367-1157
or
330 N Wabash Avenue, Suite 2000
Chicago, IL 60611
Ph: 312-321-6802
E-mail: membersupport@wdma.com
Internet: https://www.wdma.com/

WOODWORK INSTITUTE (WI)
1455 Response Road, Suite 110
Sacremento, CA 95815
Ph: 916-372-9943
Fax: 916-372-9950
E-mail: info@woodinst.com
Internet: https://woodworkinstitute.com

PART 2 PRODUCTS

Not used

PART 3 EXECUTION

Not used

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 45 00

QUALITY CONTROL
08/23, CHG 3: 08/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C1077	(2026) Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM D3666	(2016) Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials
ASTM D3740	(2019) Minimum Requirements for Agencies Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction
ASTM E90	(2023) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements
ASTM E329	(2025b) Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection
ASTM E543	(2021) Standard Specification for Agencies Performing Non-Destructive Testing

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

1.2 PAYMENT

Separate payment will not be made for providing and maintaining an effective Quality Control program. Include all associated costs in the applicable Bid Schedule item.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

SD-01 Preconstruction Submittals

Contractor Quality Control (CQC) Plan; G

SD-06 Test Reports

Verification Statement

SD-07 Certificates

Certificate Of Readiness; G

1.4 GENERAL REQUIREMENTS

Establish and maintain an effective quality control (QC) system that complies with FAR 52.246-12 Inspection of Construction. QC is comprised of plans, procedures, and organization necessary to produce an end product that complies with the Contract requirements. The QC system covers all construction operations, both onsite and offsite, and must be keyed to the proposed construction sequence. The Quality Control Manager, Superintendent, Site Safety and Health Officer (SSHO), and all on-site supervisors are responsible for the quality of work and are subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the Contract. The Quality Control Manager must maintain a physical presence at the work site at all times and is the primary individual responsible for all quality control.

1.5 QUALITY CONTROL (QC) PROGRAM REQUIREMENTS

Establish and maintain a QC program as described in this section. This QC program is a key element in meeting the objectives of the Commissioning Process (Cx). The QC program consists of a QC Organization, QC Plan, QC Plan Meeting(s), a Coordination and Mutual Understanding Meeting, QC meetings, three phases of control, submittal review and approval, testing, completion inspections, QC certifications, independent Special Inspections in accordance with Section 01 45 35 SPECIAL INSPECTIONS, and documentation necessary to provide materials, equipment, workmanship, fabrication, construction and operations that comply with the requirements of this Contract. The QC program must cover on-site and off-site work and be keyed to the work sequence. No construction work or testing may be performed unless the QC Manager is on the work site. The QC Manager must report to an officer of the firm and not be subordinate to the Project Superintendent or the Project Manager. The QC Manager, Project Superintendent and Project Manager must work together effectively. Although the QC Manager is the primary individual responsible for quality control, all individuals will be held responsible for the quality of work on the job.

1.5.1 Meetings

1.5.1.1 Quality Control Plan Meeting

Prior to submission of the QC Plan, the Contractor may request a meeting with the Contracting Officer to discuss the QC Plan requirements of this Contract.

The purpose of this meeting is to develop a mutual understanding of the QC Plan requirements prior to plan development and submission and to agree on the Contractor's list of Definable Feature of Work (DFOW).

1.5.1.2 Coordination and Mutual Understanding Meeting

After the Preconstruction Conference, before start of construction, and prior to acceptance by the Government of the CQC Plan, meet with the Contracting Officer and discuss the Contractor's quality control system. During the meeting, a mutual understanding of the system details must be developed, including the forms for recording the CQC operations, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. Minutes of the meeting will be prepared by the QC Manager and signed by the Contractor and the Government. Provide a copy of the signed minutes to all attendees and incorporate into the relevant QC Plan. At a minimum the Coordination and Mutual Understanding Meeting must be repeated when a new QC Manager is appointed. There can be other occasions when subsequent conferences will be called by either party to reconfirm mutual understandings or address deficiencies in the CQC system or procedures which can require corrective action by the Contractor.

1.5.1.2.1 Purpose

The purpose of this meeting is to develop a mutual understanding of the QC details, including documentation, administration for on-site and off-site work, design intent, Cx in accordance with Section 01 91 00.15 BUILDING COMMISSIONING, environmental requirements and procedures, coordination of activities to be performed, Special Inspections, and the coordination of the Contractor's management, production, and QC personnel. At the meeting, the Contractor must explain in detail how three phases of control will be implemented for each DFOW, as well as how each DFOW will be affected by each management plan or requirement as listed below:

a. Waste Management Plan.

b. Procedures for noise and acoustics management.

c. Environmental Protection Plan.

d. Environmental regulatory requirements.

e. Cx Plan requirements in accordance with Section 01 91 00.15 BUILDING COMMISSIONING.

f. Special Inspections.

g. Indoor Air Quality (IAQ) Management Plan.

1.5.1.2.2 Coordination of Activities

Coordinate activities included in various sections to assure efficient and orderly installation of each component. Coordinate operations included under different sections that are dependent on each other for proper installation and operation. Schedule construction operations with consideration for indoor air quality as specified in the IAQ Management Plan.Coordinate Special Inspections.

1.5.1.2.3 Attendees

As a minimum, the Contractor's personnel required to attend include an officer of the firm, the Project Manager, Project Superintendent, QC Manager, Alternate QC Manager, Assistant QC Manager, QC Specialists, Special Inspector, Commissioning Provider (CxC), Environmental Manager, and subcontractor representatives. Each subcontractor who will be assigned QC responsibilities must have a principal of the firm at the meeting.

1.5.1.3 Quality Control (QC) Meetings

After the start of construction, conduct weekly QC meetings led by the QC Manager at the work site with the Project Superintendent, the QC Specialists, the Special Inspector, CxC, and the other personnel as necessary. The QC Manager is to prepare the minutes of the meeting and provide a copy to the Contracting Officer within 2 working days after the meeting. The Contracting Officer may attend these meetings. As a minimum, accomplish the following at each meeting:

a. Review the minutes of the previous meeting.

b. Review the schedule and the status of work and deficiencies/rework. Review the most current approved schedule (in accordance with schedule specification) and the status of work and deficiencies/rework.

c. Review the status of submittals and Request For Information (RFIs).

d. Review the work to be accomplished in the next 3 weeks as defined by the schedule section paragraph WEEKLY LOOK AHEAD in Section 01 32 17.00 20 COST-LOADED NETWORK ANALYSIS SCHEDULES (NAS) and all quality control documentation required for that work.

e. Review Testing Plan and Log including status of tests performed since last QC Meeting.

f. Resolve QC and production problems. Discuss status of pending change orders.

g. Address items that may require revising the QC Plan.

h. Review Accident Prevention Plan (APP) and effectiveness of the safety program.

i. Review environmental requirements and procedures.

j. Review Environmental Management Plan.

k. Review Waste Management Plan.

l. Review the status of training completion.

m. Review Cx Plan and progress. Review Issues Log and resolution.

n. Review IAQ Management Plan.

1.5.2 Contractor Quality Control (CQC) Plan

Submit no later than 30 days after Contract Award, the CQC Plan proposed to implement the requirements FAR 52.246-12 Inspection of Construction. Construction will be permitted to begin only after acceptance of the CQC Plan and other Contract requirements

1.5.2.1 Content of Contractor Quality Control (CQC) Plan

Provide a CQC Plan, prior to start of construction that includes a table of contents, with major sections identified, pages numbered sequentially, and that documents the proposed methods and responsibilities for accomplishing quality control during the construction of the project. The CQC Plan must at a minimum include the following sections:

a. A description of the quality control organization and acknowledgment that the CQC staff will implement the three phase control system for all aspects of the work specified.

b. An organizational chart showing the quality control organization with individual names and job titles and lines of authority up to an executive of the company at the home office.

c. NAMES AND QUALIFICATIONS: Names and qualifications, in resume format, (including position titles and durations for qualifying experiences) for each person in the QC organization. Include the Construction Quality Management (CQM) for Contractors course certifications for the QC personnel as required by the paragraph CONSTRUCTION QUALITY MANAGEMENT TRAINING.

d. DUTIES, RESPONSIBILITY AND AUTHORITY OF QC PERSONNEL: Duties, responsibilities, and authorities of each person in the QC organization.

e. OUTSIDE ORGANIZATIONS: A listing of outside organizations, such as architectural and consulting engineering firms, that will be employed by the Contractor and a description of the services these firms will provide.

f. APPOINTMENT LETTERS: Letters signed by an officer of the firm appointing the QC Manager and Alternate QC Manager, CxC, and stating that they are responsible for implementing and managing the QC program as described in this Contract. Include in this letter the responsibility of the QC Manager and Alternate QC Manager to implement and manage the three phases of control, and their authority to stop work that is not in compliance with the Contract. Letters of direction are to be issued by the QC Manager to the Assistant QC Manager and all other QC Specialists or quality control representatives outlining their duties, authorities, and responsibilities. Include copies of the letters in the QC Plan.

g. SUBMITTAL PROCEDURES AND INITIAL SUBMITTAL REGISTER: Procedures for reviewing, approving, scheduling, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents. Provide the name(s) of the person(s) in the QC organization authorized to review and certify submittals prior to approval. Provide the initial submittal of the Submittal Register as specified in Section 01 33 00 SUBMITTAL PROCEDURES.

h. TESTING LABORATORY INFORMATION: Testing laboratory information required by the paragraph ACCREDITATION REQUIREMENTS, as applicable.

i. TESTING PLAN AND LOG: A Testing Plan and Log that includes the tests required, associated feature of work required, referenced by the specification paragraph number requiring the test, the frequency, and the person responsible for each test.

j. Procedures to complete construction deficiencies from identification through acceptable corrective action. Establish verification procedures that identified deficiencies have been corrected. This phase is performed prior to beginning work on each definable feature of work, after all required plans, documents, materials are approved, and after copies are at the work site.

k. Reporting procedures, including proposed reporting formats.

l. Procedures for submitting and reviewing design changes/variations prior to submission to the Contracting Officer.

m. LIST OF DEFINABLE FEATURES: A Definable Feature of Work (DFOW) is a task that is separate and distinct from other tasks and has control requirements and work crews unique to that task. A DFOW is identified by different trades or disciplines, or it is work by the same trade in a different environment. A DFOW is by definition any item or activity on the construction schedule, and the schedule specification provides direction regarding how the DFOWs are to be structured. Include in the list of DFOWs for all activities on the Construction Schedule. Although each section of the specifications can generally be considered as a definable feature of work, there are frequently more than one definable features under a particular section. Identify the specification section number and schedule activity ID for each DFOW listed. The DFOW list will be reviewed in coordination with the construction schedule and agreed upon during the Coordination and Mutual Understanding Meeting.

n. PROCEDURES FOR PERFORMING AND TRACKING THE THREE PHASES OF CONTROL: Identify procedures used to ensure the three phases of control to manage the quality on this project. For each Definable Feature of Work (DFOW), a Preparatory and Initial phase checklist will be filled out during the Preparatory and Initial phase meetings. Conduct the Preparatory and Initial Phases and meetings with a view towards obtaining quality construction by planning ahead and identifying potential problems for each DFOW.

o. Coordinate scheduled work with Special Inspections required by Section 01 45 35 SPECIAL INSPECTIONS, the Statement of Special Inspections and the Special Inspections Project Manual. Where the applicable code issued by the International Code Council (ICC) calls for inspections by the Building Official, the Contractor must include the inspections in the Quality Control Plan and must perform the inspections required by the applicable ICC. The Contractor must perform these inspections using independent qualified inspectors. Include the Special Inspections Project Manual requirements in the QC Plan.

p. p. PROCEDURES FOR COMPLETION INSPECTION: Procedures for identifying and documenting the completion inspection process. Include in these procedures the responsible party for punch out inspection, pre-final inspection, and final acceptance inspection.

q. q. TRAINING PROCEDURES AND TRAINING LOG: Procedures for coordinating and documenting the training of personnel required by the Contract.

r. r. ORGANIZATION AND PERSONNEL CERTIFICATIONS LOG: Procedures for coordinating, tracking and documenting all certifications required for entities such as subcontractors, testing laboratories, suppliers, and personnel. The QC Manager will ensure that certifications are current, appropriate for the work being performed, and will not lapse during any period of the Contract that the work is being performed.

1.5.3 Acceptance of the Quality Control (QC) Plan

The Contracting Officer's acceptance of the Contractor QC Planis required prior to the start of construction. The Contracting Officer reserves the right to require changes in the QC Plan and operations as necessary, including removal or addition of personnel, to ensure the specified quality of work. The Contracting Officer reserves the right to interview any member of the QC organization at any time to verify the submitted qualifications. All QC organization personnel are subject to acceptance by the Contracting Officer. The Contracting Officer may require the removal of any individual for non-compliance with quality requirements specified in the Contract.

1.5.4 Preliminary Construction Work Authorized Prior to Acceptance

The only construction work that is authorized to proceed prior to the acceptance of the QC Plan is mobilization of storage and office trailers, temporary utilities, and surveying with specific prior approval of the Contracting Officer.

1.5.5 Notification of Changes

Notify the Contracting Officer, in writing, of any proposed changes in the QC Plan or changes to the QC organization personnel. Proposed changes are subject to acceptance by the Contracting Officer.

1.5.6 Special Inspections

Perform all required Special Inspections per Section 01 45 35 SPECIAL INSPECTIONS, the statement of Special Inspections and the Schedule of Special Inspections.

1.6 QUALITY CONTROL (QC) ORGANIZATION

1.6.1 Quality Control (QC) Manager

1.6.1.1 Duties

Provide a QC Manager at the work site to implement and manage the QC program. The only duties and responsibilities of the QC Manager are to manage and implement the QC program on this Contract. The QC Manager must attend the partnering meetings, QC Plan Meetings, Coordination and Mutual Understanding Meeting, conduct the QC meetings, perform the three phases of control, perform submittal review and approval, ensure testing is performed and provide QC certifications and documentation required in this Contract. The QC Manager is responsible for managing and coordinating the three phases of control and documentation performed by the QC Specialists, testing laboratory personnel and any other inspection and testing

personnel required by this Contract. The QC Manager is the manager of all QC activities. The QC manager is responsible for notifying the Special Inspector of activities which require their review. The QC manager is responsible for coordinating the Special Inspection activities, see paragraph CONTRACTOR'S QUALITY CONTROL (QC) MANAGER, in Section 01 45 35 SPECIAL INSPECTIONS. The QC manager is responsible for the quality control for Secure Space Controlled Area Sound Rated perimeter construction.

1.6.1.2 Qualifications

The QC Manager must be an individual with a minimum of 5 years combined experience in the following positions: Project Superintendent, QC Manager, Project Manager, Project Engineer or Construction Manager on similar size and type construction Contracts which included the major trades that are part of this Contract. The individual must have at least 4 years experience as a QC Manager. The individual must be familiar with the requirements of EM 385-1-1 and have experience in the areas of hazard identification, safety compliance, and sustainability.

The QC Manager and all members of the QC organization must be capable of reading, writing, and conversing fluently in the English language.

1.6.1.3 Construction Quality Management Training

In addition to the above experience and education requirements, the QC Manager Alternate QC Manager, Superintendent, QC Specialist, and DQCM must have completed the CQM for Contractors course. If the QC Manager does not have a current certification, obtain the CQM for Contractors course certification within 90 days of award. This course is periodically offered by the Naval Facilities Engineering Systems Command and the Army Corps of Engineers. Contact the Contracting Officer for information on the next scheduled class.

The Construction Quality Management Training certificate expires after 5 years. If the QC Manager's certificate has expired, retake the course to remain current.

1.6.2 Organizational Changes

Maintain the QC staff with personnel as required by the specification section at all times. When it is necessary to make changes to the QC staff, revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

1.6.3 Alternate Quality Control (QC) Manager Duties and Qualifications

Designate an alternate for the QC Manager at the work site to serve in the event of the designated QC Manager's absence. The period of absence may not exceed 2 weeks at one time, and not more than 30 workdays during a calendar year. The qualification requirements for the Alternate QC Manager must be the same as for the QC Manager.

1.6.4 Assistant Quality Control (QC) Manager Duties and Qualifications

Provide a full-time assistant to the QC Manager at the work site to perform the three phases of control, perform submittal review, ensure testing is performed, and prepare QC certifications and documentation required by this Contract. The individual must be familiar with the

requirements of EM 385-1-1 and have experience in the areas of hazard identification and safety compliance.

The Assistant QC Manager must be capable of reading, writing, and conversing fluently in the English language.

1.6.5 Commissioning

Commissioning (Cx) is a systematic, quality-focused process for delivery of a project focusing on verifying and documenting all commissioned systems and assemblies are installed, tested, and operating as they were planned and designed to meet the project requirements. The Quality Control requirements outlined in this specification section are key in supporting the objectives of the Cx process, specifically coordinating testing, documenting, and verifying proper system operation. Properly executed the Quality Control support of Cx ensures timely execution of necessary tasks to deliver the fully commissioned and operating systems in coordination with the overall construction and project schedule.

Provide Cx in addition to the quality control requirements of this section and not as a substitute for quality control requirements. The QC Manager is responsible for carrying out the three phases of control while ensuring the functional performance and integrated systems tests are coordinated with the Cx provider as required for each system to be commissioned.

1.6.5.1 Certificate of Readiness

The QC Manager must issue a Certificate of Readiness for Government approval for each system to be commissioned. Schedule Functional Performance Tests for each system only after the Certificate of Readiness has been approved by the Government for the system. The Certificate of Readiness certifies that all required inspections have been completed and deficiencies that were identified through any prior review, inspection, or test activity have been corrected before the start of Functional Performance Tests. Refer to Cx requirements in Section 01 91 00.15 BUILDING COMMISSIONING for a list of systems to be commissioned and detailed requirements for the Cx provider.

1.6.6 Special Inspector

The Special Inspector (SI)must be an independent third party hired directly by the Prime Contractor. The SI must not be a company employee of the Contractor or any subcontractor performing the work to be inspected. The qualifications of the SI are defined in Section 01 45 35 SPECIAL INSPECTION.

1.7 QUALITY CONTROL (QC) SPECIALISTS

Provide a separate QC Specialist at the work site for each of the areas as listed in the Matrix listed below, who must assist and report to the QC Manager and who must have no duties other than their assigned quality control duties. These individuals or specialized technical companies are directly employed by the Prime Contractor and cannot be employed by a supplier or subcontractor on this project. QC Specialists must be physically present at the work site with frequency as indicated in the Experience Matrix below, to participate in the QC Meetings, perform the three phases of control, including participation in Preparatory and Initial Phase meetings, and to perform and document Follow-up inspections as an extension of the QC Manager for each definable feature of work in

their area of responsibility. QC Specialist must assist and be present for training events, and Critical System Acceptance inspections by the Government. Qualification, experience, Area of Responsibility, and frequency of QC surveillance are provided in Matrix listed herein.

Experience Matrix		
1. Area	**2-1. Qualification** **2-2. Experience**	**3-1. Area of Responsibility** **3-2. Frequency**
Civil	2-1. Graduate Civil Engineer or Construction Manager with a professional engineer registration , and 2-2. 2 years experience in the type of work being performed on this project or technician with 5 years related experience	3-2. Frequency of QC surveillance and inspection will be once per week during installation and including final inspection.
Mechanical	2-1. Graduate Mechanical Engineer with a professional engineer registration , and 2-2. 2 years experience or person with 5 years of experience supervising mechanical features of work in the field with a construction company	3-2. Frequency of QC surveillance and inspection will be once per week during installation and including final inspection.
Electrical	2-1. Graduate Electrical Engineer with a professional engineer registration , and 2-2. 2 years related experience or person 5 years of experience supervising electrical features of work in the field with a construction company	3-2. Frequency of QC surveillance and inspection will be once per week during installation and including final inspection.

Structural	2-1. Graduate Civil Engineer (with Structural Track or Focus) or Construction Manager with 2-2. 2 years experience or person 5 years of experience supervising structural features of work in the field with a construction company	3-2. Frequency of QC surveillance and inspection will be once per week during installation and including final inspection.
Submittals	2-1. Submittal Clerk 2-2. 1 year experience	
Testing, Adjusting and Balancing (TAB) Personnel	2.1. TAB Team Field Leader must be a member of AABC or an experienced technician of the firm certified by the NEBB 2-2. 3 years experience immediately preceding this Contract	3-2. Frequency of QC surveillance and inspection will be once per week during installation and including final inspection.

Telecommunications	2-1. RCDD 2-2. 2 years of experience	3-2. Frequency of QC surveillance and inspection will be once per week during installation and including final inspection.
Low-Voltage Specialties/ESS	2-1. RCDD 2-2. 2 years of experience	3-2. Frequency of QC surveillance and inspection will be once per week during installation and including final inspection.
Fire Protection QC Specialist (FPQC)	Note: See paragraph FIRE PROTECTION QC SPECIALIST (FPQC)	Note: See paragraph FIRE PROTECTION QC SPECIALIST (FPQC)
Building Envelope QC Specialist	2-1. Roofing Manufacturer's Technical Representative 2-2. 5 years minimum with roofing system used	3-1. Area of Responsibility: Installation and testing of roofing. 3-2. Frequency of QC surveillance and inspection will be once a week during installation, once a week during flashing installation and full-time during roof testing.

1.7.1 Fire Protection QC Specialist (FPQC)

Provide a Fire Protection Quality Control Specialist (FPQC) within the QC organization to perform quality control related activities as specified herein on fire protection and life safety systems installed under this Contract.

1.7.1.1 Qualifications

The FPQC must have the following qualifications:

a. Be a registered Professional Engineer (P.E.) licensed by a Licensing Board in the United States, the District of Columbia, Guam or Puerto Rico, having passed the National Council of Examiners for Engineering

and Surveying (NCEES) examination specifically in the discipline of Fire Protection Engineering.

b. Have a minimum of 5 years of Fire Protection Engineering experience on projects of similar relevance and complexity to the fire protection work specified under this Contract.

c. Other than the contractual obligations with the Prime Contractor, the FPQC must have no other business relationship (i.e., employee, owner, partner, operating officer, distributor, salesman, technical representative, family relationship, or financial investment) with the Prime Contractor or subcontractors.

d. Be employed by an independent engineering firm or company. The firm may identify multiple, to a maximum of five, licensed Fire Protection Engineers for the performance of the duties under this Contract but must submit the names and qualifications for Government approval for all individuals identified prior to them performing any work under this Contract. These individuals may not be substituted without prior approval from the Contracting Officer.

1.7.1.2 Responsibilities

FPQC duties and responsibilities:

a. Assist in the development of the QC Plan including the Testing Plan and Log and executing the three phases of control for work involving the installation and testing of fire protection and life safety systems as an extension of the QC Manager.

b. Participate in project QC Meetings. Participate in Preparatory and Initial Phase meetings and perform and Follow-up inspections for work involving the installation and testing of fire protection and life safety systems.

c. Review and certify that all submittals pertaining to fire protection and life safety systems are complete and accurate prior to submission to the Government for approval. The FPQC Specialist is responsible for ensuring submittals are complete and accurate and all corrections have been made prior to submission to the Government. The Government reserves the right to reject any submittal that has not first been reviewed and certified by the FPQC and so marked, in writing, attesting to such review and completeness of the submittal.

d. The Government reserves the right to reject any submittal or construction that is not in compliance to Contract. Government reviews do not relieve the Contractor responsibility for providing adequate quality control measures and do not constitute or imply acceptance of Contract variation.

e. Perform construction surveillance in accordance with the Schedule of Fire Protection System Inspections. Construction surveillance includes but is not limited to performing periodic on-site inspections during construction at specified milestones, performing a pre-final inspection of installed systems and witnessing functional testing; and participating and documenting in an on-site final acceptance inspection of fire protection and life safety systems with the Government FPE.

f. Document inspection results on a FPQC report prepared each day inspections are performed. The report must include a description of the visual inspection or observation performed, a written summary of findings, a conclusion on compliance with the Contract documents, and signature of the FPQC Specialist. In person inspection must be documented via photo (.jpeg). Video/photographic documentation must include before and after conditions and physical measurements. Forward the FPQC daily report to the QC Manager who must include the report with the submission of their daily QC Report to the Government each day. Every site visit by the FPQC must be documented on a FPQC daily report.

1.7.1.3 Schedule of Fire Protection System Inspections

A schedule, prepared by the Fire Protection DOR, which lists each of the required visual inspections and observations required by the FPQC. The schedule is included at the end of this UFGS section.

1.7.2 Quality Control (QC) for Secure Space Controlled Area Sound Rated Perimeter Construction

1.7.2.1 Periodic (Follow-Up Phase) Inspections

Once construction begins, perform periodic inspections of Secure Space Controlled Area Sound Rated Area identified in the Contract drawings at least once every 2 weeks. Increase frequency to weekly inspections within 30 days of planned acceptance testing. Coordinate periodic inspections with the appointed Government Site Security Manager (SSM) responsible for ensuring the assembly meets the requirements for accreditation. Inspections must verify that construction and materials comply with the Contract documents, the description of the assembly in the ASTM E90 Factory Report for acoustical testing, and the approved submittals. Focus inspections on the construction of the sound rated assemblies, perimeter penetrations, perimeter doors, electronic security system, man-bar installation, inspection ports, and TEMPEST countermeasures. Document periodic inspections in Daily QC Reports.

1.7.2.2 Preliminary Inspection

The Government and QC Manager will perform a joint preliminary inspection of the Secure Space Controlled Area Sound Rated Area after construction of the assembly is complete to verify compliance with the design requirements and other Contract documents. The Contracting Officer and the appointed Government SSM will participate in the preliminary inspection. Provide the Contracting Officer a minimum 14 calendar days notification in advance of the preliminary inspection.

As a result of the preliminary inspection, prepare a Secure Space Controlled Area Sound Rated Area punch list with deficiencies identified. Include with the punch list the estimated date by which the deficiencies will be corrected. Document the preliminary inspection in the Daily QC Report and attach the punch list. Notify the Contacting Officer when deficiencies are corrected. Deficiencies from the Preliminary Inspection must be corrected prior to scheduling the Final Acceptance Inspection.

1.7.2.3 Acceptance Testing for Sound Attenuation

Perform acceptance testing for sound transmission loss of sound rated door assemblies as required in Section 08 34 73 SOUND CONTROL DOOR ASSEMBLIES

and Section 09 29 00 GYPSUM BOARD for sound rated assemblies. Acceptance testing must be performed during the preliminary inspection. The Contracting Officer and the appointed Government SSM must witness acceptance testing. Deficiencies identified during acceptance testing must be included in the Secure Space Controlled Area Sound Rated Area punch list and corrected prior to the final acceptance inspection.

1.7.2.4 Acceptance Testing for Electronic Security Systems

Acceptance testing must be performed during the preliminary inspection. The Contracting Officer and the appointed Government SSM must witness acceptance testing. Deficiencies identified during acceptance testing must be included in the Secure Space Controlled Area Sound Rated Area punch list and corrected prior to the Final Inspection.

1.7.2.5 Final Inspection

Perform a final inspection of the Secure Space Controlled Area Sound Rated Area after required testing has been successfully completed as part of the preliminary inspection and all punch list items corrected. Testing is not permitted during the final inspection. QC Manager and Superintendent must attend the final inspection and Government attendees will include the Contracting Officer and appointed Government SSM. Request a final inspection by the Contracting Officer a minimum of 14 calendar days in advance.

1.8 SUBMITTAL AND DELIVERABLES REVIEW AND APPROVAL

Procedures for submission, review and approval of submittals are described in Section 01 33 00 SUBMITTAL PROCEDURES. Procedures must include field verification of relevant dimensions and component characteristics by the QC organization prior to submittal being sent to the Contracting Officer. The CQC organization is responsible for certifying that all submittals and deliverables are in compliance with the Contract. When Section 01 91 00.15 BUILDING COMMISSIONING are included in the Contract, the submittals required by those sections have to be coordinated with Section 01 33 00 SUBMITTAL PROCEDURES to ensure adequate time is allowed for each type of submittal required.

1.9 THREE PHASES OF CONTROL

CQC enables the Contractor to ensure that the construction, including that of subcontractors and suppliers, complies with the requirements of the Contract. At least three phases of control must be conducted by the QC Manager to adequately cover both on-site and off-site work for each definable feature of the construction work as follows:

1.9.1 Preparatory Phase

Document the results of the preparatory phase actions by separate minutes prepared by the QC Manager and attach to the daily CQC report. Instruct applicable workers as to the acceptable level of workmanship required to meet Contract specifications.

Notify the Contracting Officer at least 2 business days in advance of each preparatory phase meeting. The meeting will be conducted by the QC Manager and attended by the QC Specialists, the Project Superintendent, the CxC, the Special Inspector and the foreman responsible for the DFOW. When the DFOW will be accomplished by a subcontractor, that

subcontractor's foreman must attend the preparatory phase meeting. This phase is performed prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. Perform the following prior to beginning work on each DFOW:

a. Review each paragraph of the applicable specification sections, reference codes, and standards. Make available during the prepatory inspection a copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field. Maintain and make available in the field for use by Government personnel until final acceptance of the work.

b. Review the Contract drawings.

c. Verify that field measurements are as indicated on construction or shop drawings or both before confirming product orders, to minimize waste due to excessive materials.

d. Verify that appropriate shop drawings and submittals for materials and equipment have been submitted and approved. Verify receipt of approved factory test results, when required.

e. Review the testing plan and ensure that provisions have been made to provide the required QC testing.

f. Examine the work area to ensure that the required preliminary work has been completed and complies with the Contract and ensure any deficiencies/rework items in the preliminary work have been corrected and confirmed by the Contracting Officer.

g. Review coordination of product/material delivery to designated prepared areas to execute the work.

h. Examine the required materials, equipment and sample work to ensure that they are on hand and conform to the approved shop drawings and submitted data and are properly stored.

i. Check to assure that all materials and equipment have been tested, submitted, and approved.

j. Discuss specific controls to be used, construction methods, construction tolerances, workmanship standards, and the approach that will be used to provide quality construction by planning ahead and identifying potential problems for each DFOW. Ensure any portion of the plan requiring separate Contracting Officer acceptance has been approved.

k. Review the APP and appropriate Activity Hazard Analysis (AHA) to ensure that applicable safety requirements are met, and that required Safety Data Sheets (SDS) are submitted.

l. Review the Cx requirements in accordance with Section 01 91 00.15 BUILDING COMMISSIONING and ensure all preliminary work items have been completed and documented.

m. Review Special Inspections required by Section 01 45 35 SPECIAL

INSPECTION, the Statement of Special Inspections and the Schedule of Special Inspections.

1.9.2 Initial Phase

Notify the Contracting Officer at least 2 business days in advance of each initial phase. When construction crews are ready to start work on a DFOW, conduct the initial phase with the QC Specialists, the Project Superintendent, the Special Inspector and the foreman responsible for that DFOW. Observe the initial segment of the DFOW to ensure that the work complies with Contract requirements. Document the results of the initial phase in the daily CQC Report and in the Initial Phase Checklist. Repeat the initial phase for each new crew to work on-site when acceptable levels of specified quality are not being met. Indicate the exact location of initial phase for definable feature of work for future reference and comparison with follow-up phases. Perform the following for each DFOW:

a. Check work to ensure that it is in full compliance with Contract requirements. Review minutes of the preparatory meeting.

b. Verify adequacy of controls to ensure full Contract compliance. Verify required control inspection and testing comply with the Contract.

c. Establish level of workmanship and verify that it meets the minimum acceptable workmanship standards. Compare with required sample panels as appropriate.

d. Resolve any workmanship issues.

e. Ensure that testing is performed by the approved laboratory.

f. Check work procedures for compliance with the APP and the appropriate AHA to ensure that applicable safety requirements are met.

g. Review project specific work plans (i.e., Cx, HAZMAT Abatement, Stormwater Management) to ensure all preparatory work items have been completed and documented.

h. Coordinate scheduled work with Special Inspections required by Section 01 45 35 SPECIAL INSPECTIONS, the Statement of Special Inspections and the Schedule of Special Inspections.

1.9.3 Follow-Up Phase

Perform the following for on-going DFOW daily, or more frequently as necessary, until the completion of each DFOW. The Final Follow-Up for any DFOW will clearly note in the daily report the DFOW is completed, and all deficiencies/rework items have been completed in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST. Each DFOW that has completed the Initial Phase and has not completed the Final Follow-up must be included on each daily report. If no work was performed on that DFOW for the period of that daily report, it must be so noted. Document all Follow-Up activities for DFOWs in the daily CQC Report:

a. Ensure the work including control testing complies with Contract requirements until completion of that particular work feature. Record checks in the CQC documentation.

b. Maintain the quality of workmanship required.

c. Ensure that testing is performed by the approved laboratory.

d. Ensure that deficiencies/rework items are being corrected. Conduct final follow-up checks and correct all deficiencies prior to the start of additional features of work which may be affected by the deficient work.

e. Do not build upon nor conceal non-conforming work.

f. Assure manufacturers' representatives have performed necessary inspections if required and perform safety inspections.

g. Review the Cx requirements in accordance with Section 01 91 00.15 BUILDING COMMISSIONING.

h. Coordinate scheduled work with Special Inspections required by Section 01 45 35 SPECIAL INSPECTIONS, the Statement of Special Inspections and the Schedule of Special Inspections.

1.9.4 Additional Preparatory and Initial Phases

Conduct additional preparatory and initial phases on the same DFOW if the quality of on-going work is unacceptable, if there are changes in the applicable QC organization, if there are changes in the on-site production supervision or work crew, if work on a DFOW has not started within 45 days of the initial preparatory meeting or has resumed after 45 days of inactivity, or if other problems develop.

1.9.5 Notification of Three Phases of Control for Off-Site Work

Notify the Contracting Officer at least 2 weeks prior to the start of the preparatory and initial phases.

1.9.6 Deficiency/Rework Items List

The QC Manager must maintain a list of work that does not comply with the Contract, identifying what items need to be corrected, the activity ID number associated with the item, the date the item was originally discovered, the date the item will be corrected by, and the date the item was corrected.

The QC Manager reviews the list at each weekly QC Meeting:

a. There is no requirement to report a deficiency/rework item that is corrected the same day it is discovered.

b. No successor task may be advanced beyond the preparatory phase meeting until all deficiencies/rework items have been cleared by the QC Manager and concurred with by the Contracting Officer. This must be confirmed as part of the Preparatory Phase activities.

c. Attach a copy of the "Deficiency/Rework Items List" to the last daily CQC Report of each month.

d. The Contractor is responsible for including those items identified by the Contracting Officer.

e. All deficiencies/rework items must be confirmed as corrected by the QC Manager, and concurred by the Contracting Officer, prior to commencement of any completion inspections per paragraph COMPLETION INSPECTIONS unless specifically exempted by the Contracting Officer.

f. Non-Compliance with these requirements is grounds for removal in accordance with paragraph ACCEPTANCE OF THE QUALITY CONTROL (QC) PLAN.

g. All delays, concurrent or related to failure to manage, monitor, control, and correct deficiencies/rework items are entirely the responsibility of the Contractor and can not be made the subject, or any component of any request for additional time or compensation.

1.10 TESTING

Perform specified or required tests to verify that control measures are adequate to provide a product which conforms to Contract requirements. Upon request, furnish to the Government duplicate samples of test specimens for possible testing by the Government. Testing includes operation and acceptance tests when specified. Procure the services of an U.S. Army Corps of Engineers approved testing laboratory or establish an approved testing laboratory at the project site or within 5 miles. Perform the following activities and record and provide the following data:

a. Verify that testing procedures comply with Contract requirements.

b. Verify that facilities and testing equipment are available and comply with testing standards.

c. Check test instrument calibration data against certified standards.

d. Verify that recording forms and test identification control number system, including all test documentation requirements, have been prepared.

e. Record results of all tests taken, both passing and failing on the CQC report for the date taken. Specification paragraph reference, location where tests were taken, and the sequential control number identifying the test. If approved by the Contracting Officer, actual test reports are submitted later with a reference to the test number and date taken. Provide an information copy of tests performed by an offsite or commercial test facility directly to the Contracting Officer. Failure to submit timely test reports as stated results in nonpayment for related work performed and disapproval of the test facility for this Contract.

1.10.1 Accreditation Requirements

Construction materials testing laboratories must be accredited by a laboratory accreditation authority and must submit a copy of the Certificate of Accreditation and Scope of Accreditation. The laboratory's scope of accreditation must include the appropriate ASTM standards (ASTM E329, ASTM C1077, ASTM D3666, ASTM D3740, ASTM E543) listed in the technical sections of the specifications. Laboratories engaged in Hazardous Materials Testing must meet the requirements of OSHA and EPA. The policy applies to the specific laboratory performing the actual

testing, not just the Corporate Office.

1.10.2 Laboratory Accreditation Authorities

Laboratory Accreditation Authorities include the National Voluntary Laboratory Accreditation Program (NVLAP) administered by the National Institute of Standards and Technology at https://www.nist.gov/nvlap, the American Association of State Highway and Transportation Officials (AASHTO) Accreditation Program at http://www.aashtoresource.org/aap/overview, International Accreditation Services, Inc. (IAS) at https://www.iasonline.org/, U.S. Army Corps of Engineers Materials Testing Center (MTC) at https://www.erdc.usace.army.mil/Media/Fact-Sheets/Fact-Sheet-Article-View/Article/476661/materials-testing-center/, the American Association for Laboratory Accreditation (A2LA) program at https://a2la.org/, the Washington Association of Building Officials (WABO) at https://www.wabo.org/ (Approval authority for WABO is limited to projects within Washington State), and the Washington Area Council of Engineering Laboratories (WACEL) at https://www.wacel.org/lab-accreditation-and-inspection-agency-audit-programs/laboratory-accreditation-program/(Approval authority by WACEL is limited to projects within Facilities Engineering Command (FEC) Washington geographical area).

1.10.3 Capability Check

The Contracting Officer retains the right to check laboratory equipment in the proposed laboratory and the laboratory technician's testing procedures, techniques, and other items pertinent to testing, for compliance with the standards set forth in this Contract. Laboratories utilized for testing soils, concrete, asphalt, and steel must meet criteria detailed in ASTM D3740 and ASTM E329.

1.10.4 Test Results

Cite applicable Contract requirements, tests or analytical procedures used. Provide actual results and include a statement that the item tested or analyzed conforms or fails to conform to specified requirements. If the item fails to conform, notify the Contracting Officer immediately. Conspicuously stamp the cover sheet for each report in large red letters "CONFORMS" or "DOES NOT CONFORM" to the specification requirements, whichever is applicable. Test results must be signed by a testing laboratory representative authorized to sign certified test reports. Furnish the signed reports, certifications, and other documentation to the Contracting Officer via the QC Manager. Furnish a summary report of field tests at the end of each month, in accordance with paragraph DOCUMENTATION AND INFORMATION FOR THE CONTRACTING OFFICER.

1.10.5 Test Reports and Monthly Summary Report of Tests

Furnish the signed reports, certifications, and a summary report of field tests at the end of each month to the Contracting Officer. Attach a copy of the summary report to the last daily CQC Report of each month. Provide a copy of the signed test reports and certifications to the Operation and Maintenance Support Information (OMSI) preparer for inclusion into the OMSI documentation, in accordance with Sections 01 78 23 OPERATION AND MAINTENANCE DATA and 01 78 24.00 20 FACILITY DATA WORKBOOK (FDW).

1.11 COMPLETION INSPECTIONS

1.11.1 Punch-Out Inspection

Near the completion of all work or any increment thereof, established by a completion time stated in the Contract Clause entitled "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the QC Manager must conduct an inspection of the work and develop a "punch list" of items which do not conform to the approved drawings, specifications, and Contract. Include in the punch list any remaining items on the "Deficiency/Rework Items List", that were not corrected prior to the Punch-Out Inspection as approved by the Contracting Officer in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST. Include within the punch list the estimated date by which the deficiencies will be corrected. Provide a copy of the punch list to the Contracting Officer.

The QC Manager, or staff, must make follow-on inspections to ascertain that all deficiencies have been corrected. All punch list items must be confirmed as corrected by the QC Manager and concurred by the Contracting Officer. Once this is accomplished, notify the Government that the facility is ready for the Government "Pre-Final Inspection".

1.11.2 Pre-Final Inspection

The Government and QC Manager will perform this inspection to verify that the facility is complete and ready to be occupied. A Government "Pre-Final Punch List" will be documented by the QC Manager as a result of this inspection. The QC Manager will ensure that all items on this list are corrected and concurred by the Contracting Officer prior to notifying the Government that a "Final" inspection with the Client can be scheduled. All items noted on the "Pre-Final" inspection must be corrected and concurred by the Contracting Officer in a timely manner and be accomplished before the Contract completion date for the work, or any increment thereof, if the project is divided into increments by separate completion dates unless exceptions are directed by the Contracting Officer.

1.11.3 Final Acceptance Inspection

Notify the Contracting Officer at least 14 calendar days prior to the date a final acceptance inspection can be held. State within the notice that all items previously identified on the pre-final punch list will be corrected and acceptable, along with any other unfinished Contract work, by the date of the final acceptance inspection. The Contractor must be represented by the QC Manager, the Project Superintendent, and others deemed necessary. Attendees for the Government will include the Contracting Officer, other Government QA personnel, and personnel representing the Client. Failure of the Contractor to have all Contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the Contract Clause entitled "Inspection of Construction."

1.12 QUALITY CONTROL (QC) CERTIFICATIONS

1.12.1 Contractor Quality Control (CQC) Report Certification

Contain the following statement within the CQC Report: "On behalf of the Contractor, I certify that this report is complete and correct and

equipment and material used, and work performed during this reporting period is in compliance with the Contract drawings and specifications to the best of my knowledge, except as noted in this report."

1.12.2 Completion Certification

Upon completion of work under this Contract, the QC Manager must furnish a certificate to the Contracting Officer attesting that "the work has been completed, inspected, tested and is in compliance with the Contract." Provide a copy of this final QC Certification for completion to the preparer of the Operation & Maintenance (O&M) documentation.

1.12.3 Invoice Certification

Furnish a certificate to the Contracting Officer with each payment request, signed by the QC Manager, attesting that as-built drawings are current, coordinated and attesting that the work for which payment is requested, including stored material, complies with Contract requirements.

1.13 DOCUMENTATION AND INFORMATION FOR THE CONTRACTING OFFICER

1.13.1 Construction Documentation

Prepare a Construction Production Report and a Contractor Quality Control Report for each day that work is performed. Attach the Construction Production Report to the Contractor Quality Control Report prepared for the same day. Maintain current and complete records of on-site and off-site QC program operations and activities.
Account for each calendar day throughout the life of the Contract.

The Project Superintendent and the QC Manager must prepare and sign the Contractor Production and CQC Reports, respectively. Every space on the forms must be filled in. Use N/A if nothing can be reported in one of the spaces. The reporting of work must be identified by terminology consistent with the construction schedule. In the "Remarks" sections of the reports, enter pertinent information including directions received, problems encountered during construction, work progress and delays, conflicts or errors in the drawings or specifications, field changes, safety hazards encountered, instructions given and corrective actions taken, delays encountered, a record of visitors to the work site, quality control problem areas, deviations from the QC Plan, construction deficiencies encountered, and meetings held. For each entry in the report(s), identify the Schedule Activity No. that is associated with the entered remark.

1.13.2 Quality Control Activities

CQC and Contractor Production reports will be prepared daily to maintain current records providing factual evidence that required quality control activities and tests have been performed. Include in these records the work of subcontractors and suppliers on an acceptable form that includes, as a minimum, the following information:

a. The name and area of responsibility of the Contractors and any subcontractors.

b. Operating plant/equipment with hours worked, idle, or down for repair.

c. Work performed each day, giving location, description, and by whom. When a Network Analysis Schedule (NAS) is used, identify each item of work performed each day by NAS activity number.

d. Control phase activities performed. Preparatory, and Initial phase Checklists associated with the DFOW referenced to the construction schedule. Follow-up phase activities identified to the DFOW. If testing or specific QC Specialist activities are associated with the Follow-up phase activities for a specific DFOW note this and include those reports.

e. Test and control activities performed with results and references to specifications and drawings requirements. Identify the control phase (Preparatory, Initial, Follow-up). List of deficiencies noted, along with corrective action in accordance with the paragraph DEFICIENCY/REWORK ITEMS LIST.

f. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications and drawings requirements.

g. Submittals and deliverables reviewed, with Contract reference, by whom, and action taken.

h. Offsite surveillance activities, including actions taken.

i. Job safety evaluations stating what was checked, results, and instructions or corrective actions.

j. Instructions given/received and conflicts in plans and specifications.

1.13.3 Verification Statement

Indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. Cover both conforming and deficient features and include a statement that equipment and materials incorporated in the work and workmanship comply with the Contract.

Furnish the original and one copy of these records in report form to the Government by 10:00 AM the next working day after the date covered by the report. As a minimum, prepare and submit one report for every 7 days of no work and on the last day of a no work period. All calendar days need to be accounted for throughout the life of the Contract. The first report following a day of no work will be for that day only. Reports need to be signed and dated by the QC Manager. Include copies of test reports and copies of reports prepared by all subordinate quality control personnel within the QC Manager Report.

1.13.4 Reports from the Quality Control (QC) Specialist(s)

Document inspection results on a QC specialist report prepared each day work is performed in their area of responsibility. The report must include a description of the visual inspection or observation performed, a written summary of findings, a conclusion on compliance with the Contract documents, and signature of the QC Specialist. In person inspections must be documented with Video/photographs. Video/photographic documentation of deficiencies must include before and after conditions and physical measurements, as necessary. Forward the QC daily report to the QC Manager

who must include the report with the submission of their daily QC Report to the Government each day. Every site visit by the QC Specialist must be documented on a QC Specialist daily report.

1.13.5 Quality Control Validation

Establish and maintain the following in an electronic folder. Divide folder into a series of tabbed sections as shown below. Ensure folder is updated at each required progress meeting.

a. CQC Meeting minutes in accordance with paragraph QUALITY CONTROL (QC) MEETINGS.

b. All completed Preparatory and Initial Phase Checklists, arranged by specification section, further sorted by DFOW referenced to the construction schedule. Submit each individual Phase Checklist the day the phase event occurs as part of the CQC daily report.

c. All milestone inspections, arranged by Activity Number referenced to the construction schedule.

d. An up-to-date copy of the Testing Plan and Log with supporting field test reports, arranged by specification section referenced to the DFOW to which individual reports results are associated. Individual field test reports will be submitted within 2 working days after the test is performed in accordance with the paragraph QUALITY CONTROL ACTIVITIES. Monthly Summary Report of Tests: Submit the report as an electronic attachment to the CQC Report at the end of each month.

e. Copies of all Contract modifications, arranged in numerical order. Also include documentation that modified work was accomplished.

f. An up-to-date copy of the paragraph DEFICIENCY/REWORK ITEMS LIST.

g. Cx documentation in accordance with Section 01 91 00.15 BUILDING COMMISSIONING.

h. h. Special Inspection reports.

i. i. Upon commencement of Completion Inspections of the entire project or any defined portion, maintain up-to-date copies of all punch lists issued by the QC staff to the Contractor and subcontractors and all punch lists issued by the Government in accordance with the paragraph COMPLETION INSPECTIONS.

1.13.6 Testing Plan and Log

As tests are performed, the CxC and the QC Manager will record on the "Testing Plan and Log" the date the test was performed and the date the test results were forwarded to the Contracting Officer. Attach a copy of the updated "Testing Plan and Log" to the last daily CQC Report of each month. Provide a copy of the final "Testing Plan and Log" to the preparer of the Operation & Maintenance (O&M) documentation.

1.13.7 As-Built Drawings

The QC Manager must ensure the as-built drawings, required by Section

01 78 00 CLOSEOUT SUBMITTALS are kept current on a daily basis and marked to show deviations which have been made from the Contract drawings. The as-built drawings document commences with the QC Manager ensuring all amendments, or changes to the Contract prior to Contract award are accurately noted in the initial document set creating the accurate baseline of the Contract prior to any work starting. Ensure each deviation has been identified with the appropriate modifying documentation (e.g., PC No., Modification No., Request for Information No.). The QC Manager or QC Specialist assigned to an area of responsibility must initial each revision. Upon completion of work, the QC Manager will furnish a certificate attesting to the accuracy of the as-built drawings prior to submission to the Contracting Officer.

1.14 NOTIFICATION ON NON-COMPLIANCE

The Contracting Officer will notify the Contractor of any detected non-compliance with the Contract. Take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, is deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders will be made the subject of a claim for extension of time for excess costs or damages by the Contractor.

1.15 DELIVERY, STORAGE, AND HANDLING

Designate receiving/storage areas for incoming material to be delivered according to installation schedule and to be placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication. Store and handle materials in a manner as to prevent loss from weather and other damage. Keep materials, products, and accessories covered and off the ground, and store in a dry, secure area. Prevent contact with material that may cause corrosion, discoloration, or staining. Protect all materials and installations from damage by the activities of other trades.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SCHEDULE OF FIRE PROTECTION SYSTEM INSPECTIONS BY FPQC SPECIALIST

1. INSTRUCTIONS for FPQC Specialist:

Perform surveillance of fire protection system installation during construction and during pre-final and final acceptance inspections. Surveillance includes either visual inspections or observations performed by the FPQC as indicated in the following Schedule of Fire Protection System Inspections. Check boxes in the schedule indicate the inspections or observations that are applicable to this project, which must be performed and documented by the FPQC.

Surveillance of fire protection system inspections is divided into three phases:

Surveillance During Construction – Includes periodic on-site visits by the FPQC during construction

Pre-Final Acceptance Inspection – FPQC must be onsite during pre-final acceptance inspection

Final Acceptance inspection – FPQC must be onsite during final acceptance inspection

2. INSPECTION TYPE

VISUAL INSPECTION:

Perform on-site visual inspections as indicated in the Schedule of Fire Protection System Inspections as construction progresses to confirm work conforms with the contract requirements including but not limited to verifying proper installation of equipment and materials in accordance with applicable codes. Where work will be covered up by finished walls and ceilings, inspections must be scheduled and performed when work is still visible.

OBSERVATION:

Observe component and system testing in person on-site as indicated in the Schedule of Fire Protection System Inspections. Confirm testing is completed in accordance with applicable codes and that testing was successful.

DOCUMENTATION:

Document all inspections and observations in the FPQC Report in accordance with UFGS 01 45 00. Document any deficiencies and all work observed that has been successfully performed in accordance with the contract documents. Record deficiencies in the rework list.

DESIGNER NOTES (delete this box after reviewing): **Rev 2-14-23**

1. Fire Protection DOR must edit this schedule based on the project scope.
2. Indicate inspection and observation tasks applicable to your project that are to be performed by the FPQC by checking boxes next to each task required. Either delete unchecked sections or leave them in the schedule unchecked.
3. This schedule does NOT need to be printed in color.
4. When finished editing, delete this note box and save this schedule as a PDF and insert into the project specifications immediately following UFGS Section 01 45 00.

SCHEDULE OF FIRE PROTECTION SYSTEM INSPECTIONS BY FPQC SPECIALIST

PERFORM SURVEILLANCE DURING CONSTRUCTION

~ FIRE SUPPRESSION SYSTEM ~

PERFORM TASK IF CHECKED	TASK	INSPECTION TYPE	DESCRIPTION
☒	1. Verify proper installation of underground service main and service; laterals, thrust blocks, tie-rods and connection to above ground piping.	**VISUAL INSPECTION**	✓ Visually inspect materials ✓ Visually inspect installation
☒	2. Verify proper orientation of fire hydrants and fire department access	**VISUAL INSPECTION**	✓ Visually inspect installation and orientation
☐	3. Verify proper installation of interior and exterior attachments, coatings, and vortex plate prior to filling fire protection water tank	**VISUAL INSPECTION**	✓ Visually inspect fire protection water tank installation
☒	4. Hydrostatic/leak test for underground piping	**OBSERVE**	✓ Verify proper test method ✓ Confirm test was successful
☒	5. Hydrostatic/leak test for above ground piping prior to ceiling installation	**OBSERVE**	✓ Verify proper test method ✓ Confirm test was successful
☒	6. Underground system flush prior to connection to the riser	**OBSERVE**	✓ Verify system was properly flushed
☒	7. Forward flow test for Backflow preventer	**OBSERVE**	✓ Verify proper test method ✓ Confirm test was successful
☒	8. Suction pipe flush prior to fire pump startup	**OBSERVE**	✓ Verify system was properly flushed
☒	9. Hydrostatic test fire pump suction and discharge piping	**OBSERVE**	✓ Verify proper test method ✓ Confirm test was successful
☒	10. Fire pump startup	**OBSERVE**	✓ Confirm successful startup
☒	11. Verify proper installation of sprinkler piping prior to wall or ceiling installation	**VISUAL INSPECTION**	✓ Inspect pipe hangars, bracing, sprinkler heads ✓ Inspect for sprinkler obstructions; damaged, painted or covered heads ✓ Verify proper location of control valves, drains, vents, backflow, test header ✓ Verify proper component mounting heights
☒	12. Document inspections and observations in FPQC Report	**DOCUMENT**	✓ Submit report for each day inspections or observations occur ✓ Annotate deficiencies and satisfactory work observed ✓ Record rework items in FPQC report

SCHEDULE OF FIRE PROTECTION SYSTEM INSPECTIONS BY FPQC SPECIALIST

~ SPECIAL FIRE SUPPRESSION SYSTEM ~			
PERFORM TASK IF CHECKED	TASK	INSPECTION TYPE	DESCRIPTION
☐	1. Verify proper installation of gaseous fire suppression system	**VISUAL INSPECTION**	✓ Inspect gas cylinders, initiating controls, shutdowns, aborts, and visual warning
☐	2. Verify proper installation of IR hangar detector	**VISUAL INSPECTION**	✓ Inspect detector and nozzle layout ✓ Inspect for obstructions, abort stations ✓ Inspect riser piping
☐	3. Verify proper installation of elevator fire protection	**VISUAL INSPECTION**	✓ Inspect elevator recall functions ✓ Inspect two-way communication
☒	4. Verify proper installation of fire suppression in secure spaces	**VISUAL INSPECTION**	✓ Inspect location of sprinkler piping and sprinklers
☒	5. Document inspections and observations in FPQC Report	**DOCUMENT**	✓ Submit report for each day inspections or observations occur ✓ Document deficiencies and satisfactory work observed in FPQC Report ✓ Record deficiencies in rework list

~ PASSIVE FIRE PROTECTION SYSTEMS ~			
PERFORM TASK IF CHECKED	TASK	INSPECTION TYPE	DESCRIPTION
☒	1. Verify proper construction of fire rated assemblies	**VISUAL INSPECTION**	✓ Inspect partitions for proper fire rated construction per design ✓ Inspect doors and door hardware for proper fire rating ✓ Inspect glass for proper fire rating
☐	2. Verify proper installation of fireproofing	**VISUAL INSPECTION**	✓ Inspect for use of proper fireproofing materials ✓ Inspect for cracking, spalling or delaminating ✓ Inspect for proper application thickness
☒	3. Verify proper installation of firestopping	**VISUAL INSPECTION**	✓ Inspect to confirm firestopping system is UL tested or an engineering judgement has been obtained and submitted ✓ Inspect for use of proper firestopping materials ✓ Inspect penetrations through fire rated walls, partitions and ceilings ✓ Inspect construction joints and gaps
☒	4. Document inspections and observations in FPQC Report	**DOCUMENT**	✓ Submit report for each day inspections or observations occur

SCHEDULE OF FIRE PROTECTION SYSTEM INSPECTIONS BY FPQC SPECIALIST

			✓ Document deficiencies and satisfactory work observed in FPQC Report ✓ Record deficiencies in rework list
~ FIRE ALARM SYSTEMS ~			
PERFORM TASK IF CHECKED	TASK	INSPECTION TYPE	DESCRIPTION
☒	1. Verify proper installation of fire alarm system after conduit is installed and wiring pulled, but before devices are installed	**VISUAL INSPECTION**	✓ Inspect conduit, wiring, conduit fill, wire type ✓ Inspect installation heights of back boxes
☒	2. Document inspections and observations in FPQC Report	**DOCUMENT**	✓ Submit report for each day inspections or observations occur ✓ Document deficiencies and satisfactory work observed in FPQC Report ✓ Record deficiencies in rework list

~ END OF SURVEILLANCE DURING CONSTRUCTION SECTION

PERFORM DURING PRE-FINAL ACCEPTANCE INSPECTION

PERFORM TASK IF CHECKED	TASK	INSPECTION TYPE	DESCRIPTION
☒	1. Inspect all fire protection systems and all life safety features	**VISUAL INSPECTION**	✓ Verify proper installation of fire protection and life safety systems
☒	2. Witness functional testing of all fire protection and life safety systems	**OBSERVE**	✓ Verify proper testing is performed on fire protection and life safety systems
☒	3. Identify deficiencies that require correction	**VISUAL INSPECTION**	✓ Document deficiencies in FPQC Report and record in rework list
☒	4. Verify rework items have been corrected	**VISUAL INSPECTION**	✓ Record re-inspection results on FPQC Report
☒	5. Document results of pre-final inspection and photograph unsatisfactory conditions	**DOCUMENT**	✓ Document results of pre-final inspection in FPQC Report
☒	6. Certify installation and operation of all fire protection and life safety systems conform to the contract documents	**DOCUMENT**	✓ Provide separate letter certifying conformance with contract requirements

~ END OF PRE-FINAL INSPECTION SECTION

PERFORM DURING FINAL ACCEPTANCE INSPECTION

PERFORM TASK IF CHECKED	TASK	INSPECTION TYPE	DESCRIPTION

SCHEDULE OF FIRE PROTECTION SYSTEM INSPECTIONS BY FPQC SPECIALIST

☒	1. Verify proper installation and operation of all fire protection systems and all life safety features	**VISUAL INSPECTION**	✓
☒	2. Note any deficiencies identified by Government FPE on deficiency list	**DOCUMENT**	✓ Document deficiencies identified by Government FPE on deficiency list
☒	3. Verify all deficiencies have been corrected	**VISUAL INSPECTION**	✓ Inspect rework to confirm all deficiencies have been corrected
☒	4. Certify that all deficiencies have been corrected	**DOCUMENT**	✓ Document inspection results on FPQC Report

~ END OF FINAL ACCEPTANCE INSPECTION SECTION

This page is intentionally left blank.

SECTION 01 45 35

SPECIAL INSPECTIONS
11/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC (2024) International Building Code

1.2 GENERAL REQUIREMENTS

Perform Special Inspections in accordance with the Statement of Special Inspections, Schedule of Special Inspections and Chapter 17 of ICC IBC. The Statement of Special Inspections and Schedule of Special Inspections are included as an attachment to this specification. Special Inspections are to be performed by an independent third party and are intended to ensure that the work of the Prime Contractor is in accordance with the Contract Documents and applicable building codes. Special inspections do not take the place of the three phases of control inspections performed by the Contractor's QC Manager or any testing and inspections required by other sections of the specifications.

1.3 DEFINITIONS

1.3.1 Continuous Special Inspections

Continuous Special Inspections is the constant monitoring of specific tasks by a special inspector. These inspections must be carried out continuously over the duration of the particular tasks.

1.3.2 Perform

Perform these Special Inspections tasks for each welded joint or member.

1.3.3 Observe

Observe these Special Inspections items on a periodic daily basis. Operations need not be delayed pending these inspections.

1.3.4 Special Inspector (SI)

A qualified person retained by the Contractor and approved by the Contracting Officer as having the competence necessary to inspect a particular type of construction requiring Special Inspections. The SI must be an independent third party hired directly by the Prime Contractor.

1.3.5 Associate Special Inspector (ASI)

A qualified person who assists the SI in performing Special Inspections but must perform inspection under the direct supervision of the SI and

cannot perform inspections without the SI on site.

1.3.6 Third Party

A Special inspector must not be an employee of the Contractor or of any Sub-Contractor performing the work to be inspected.

1.3.7 Contracting Officer

The Government official having overall authority for administrative contracting actions. Certain contracting actions may be delegated to the Contracting Officer's Representative (COR).

1.3.8 Contractor's Quality Control (QC) Manager

An individual retained by the Prime Contractor and qualified in accordance with the Section 01 45 00 QUALITY CONTROL having the overall responsibility for the Contractor's QC organization.

1.3.9 Structural Engineer of Record (SER)

A registered design professional responsible for the overall design and review of submittal documents prepared by others. The SER is registered or licensed to practice their respective design profession as defined by the statutory requirements of the professional registration laws in the state in which the design professional works. The SER is also referred to as the Engineer of Record (EOR) in design code documents.

1.3.10 Statement of Special Inspections (SSI)

A document developed by the SER identifying the material, systems, components and work required to have Special Inspections. This statement is included at the end of this specification.

1.3.11 Schedule of Special Inspections (SSI)

A schedule which lists each of the required Special Inspections, the extent to which each Special Inspection is to be performed, and the required frequency for each in accordance with ICC IBC Chapter 17. This schedule is included at the end of this specification.

1.3.12 Definable Feature of Work (DFOW)

An inspection group that is separate and distinct from other inspection groups, having inspection requirements or inspectors that are unique.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Special Inspections Agency's Written NDT Practices with method and evidence of regular equipment calibration where applicable

SD-06 Test Reports

Special Inspections Daily Reports

Special Inspections Biweekly Reports

SD-07 Certificates

AISC Certified Steel Fabricator

Steel Joist Institute Membership

Certificate of Compliance

Special Inspector Qualifications; G

Qualification Records for NDT technicians

SD-11 Closeout Submittals

Interim Report of Special Inspections for Each DFOW; G

Comprehensive Final Report of Special Inspections; G

1.5 SPECIAL INSPECTOR QUALIFICATIONS

Submit qualifications for each special inspector .

1.5.1 Steel Construction and High Strength Bolting

1.5.1.1 Special Inspector

a. ICC Structural Steel and Bolting Special Inspector certificate with one year of related experience, or

b. Registered Professional Engineer with three years of related experience

1.5.1.2 Associate Special Inspector

Engineer-In-Training with one year of related experience.

1.5.2 Welding Structural Steel

1.5.2.1 Special Inspector

a. ICC Structural Welding Special Inspector certificate with one year of

related experience, or

b. AWS Certified Welding Inspector

1.5.2.2 Associate Special Inspector

AWS Certified Associate Welding Inspector

1.5.3 Nondestructive Testing of Welds

1.5.3.1 Special Inspector

NDT Level III Certificate

1.5.3.2 Associate Special Inspector

NDT Level II Certificate plus one year of related experience

1.5.4 Cold Formed Steel Framing

1.5.4.1 Special Inspector

a. ICC Structural Steel and Bolting Special Inspector certificate with one year of related experience, or

b. ICC Commercial Building Inspector with one year of experience, or

c. ICC Residential Building Inspector with one year of experience, or

d. Registered Professional Engineer with three years related experience

1.5.4.2 Associate Special Inspector

Engineer-In-Training with one year of related experience.

1.5.5 Concrete Construction

1.5.5.1 Special Inspector

a. ICC Reinforced Concrete Special Inspector Certificate with one year of related experience, or

b. ACI Concrete Construction Special Inspector, or

c. Registered Professional Engineer with three years of related experience

1.5.5.2 Associate Special Inspector

a. ACI Concrete Construction Special Inspector in Training, or

b. Engineer-In-Training with one year of related experience

1.5.6 Prestressed Concrete Construction

1.5.6.1 Special Inspector

a. ICC Pre-stressed Special Inspector Certificate with one year of related experience, or

b. PCI Quality Control Technician/ Inspector Level II Certificate with one year of related experience, or

c. Registered Professional Engineer with three years of related experience

1.5.6.2 Associate Special Inspector

a. PCI Quality Control Technician/ Inspector Level I Certificate with one year of related experience, or

b. Engineer-In-Training with one year of related experience

1.5.7 Post-tensioned Concrete Construction

1.5.7.1 Special Inspector

a. PTI Level 2 Unbonded PT Inspector Certificate, or

b. Registered Professional Engineer with three years of related experience

1.5.7.2 Associate Special Inspector

a. PTI Level 1 Unbonded PT Inspector Certificate with one year of related experience, or

b. Engineer-In-Training with one year of related experience

1.5.8 Masonry Construction

1.5.8.1 Special Inspector

a. ICC Structural Masonry Special Inspector Certificate with one year of related experience, or

b. Registered Professional Engineer with three years of related experience

1.5.8.2 Associate Special Inspector

Engineer-In-Training with one year of related experience.

1.5.9 Wood

1.5.9.1 Special Inspector

a. ICC Commercial Building Inspector Certificate with one year of related experience, or

b. ICC Residential Building Inspector with on year of experience, or

c. Registered Professional Engineer with three years of related experience

1.5.9.2 Associate Special Inspector

Engineer-In-Training with one year of related experience.

1.5.10 Verification of Site Soil Condition, Fill Placement and Load-Bearing Requirements

1.5.10.1 Special Inspector

a. ICC Soils Special Inspector Certificate with one year of related experience, or

b. NICET Soils Technician Level II Certificate in Construction Material Testing, or

c. Geologist-In-Training with three years of related experience, or

d. Registered Professional Engineer with three years of related experience

1.5.10.2 Associate Special Inspector

a. NICET Soils Technician Level I Certificate in Construction Material Testing with one year of related experience, or

b. Engineer-In-Training with one year of related experience

1.5.11 Deep Foundations

1.5.11.1 Special Inspector

a. NICET Soils Technician Level II Certificate in Construction Material Testing, or

b. Geologist-In-Training with three years of related experience, or

c. Registered Professional Engineer with three years of related experience

1.5.11.2 Associate Special Inspector

a. NICET Soils Technician Level I Certificate in Construction Material Testing with one year of related experience, or

b. NICET Geotechnical Engineering Technician Level I Construction or Generalist Certificate with one year of related experience, or

c. Engineer-In-Training with one year of related experience

1.5.12 Sprayed Fire Resistant Material

1.5.12.1 Special Inspector

a. ICC Spray-applied Fireproofing Special Inspector Certificate, or

b. ICC Fire Inspector I Certificate with one year of related experience, or

c. Registered Professional Engineer or Architect with related experience

1.5.12.2 Associate Special Inspector

Engineer-In-Training with one year of related experience

1.5.13 Mastic and Intumescent Fire Resistant Coatings

1.5.13.1 Special Inspector

a. ICC Spray-applied Fireproofing Special Inspector Certificate, or

b. ICC Fire Inspector I Certificate with one year of related experience, or

c. Registered Professional Engineer or Architect with related experience

1.5.13.2 Associate Special Inspector

Engineer-In-Training with one year of related experience.

1.5.14 Exterior Insulation and Finish System (EIFS)

1.5.14.1 Special Inspector

a. AWCI EIFS Inspector Certificate, or

b. Exterior Design Institute Certificate, or

c. Registered Professional Engineer or Architect with related experience

1.5.14.2 Associate Special Inspector

Engineer-In-Training with one year of related experience.

1.5.15 Fire-Resistant Penetrations and Joints

1.5.15.1 Special Inspector

a. Passed the UL Firestop Exam with one year of related experience, or

b. Passed the FM Firestop Exam with one year of related experience, or

c. Registered Professional Engineer with related experience

1.5.15.2 Associate Special Inspector

Engineer-In-Training with one year of related experience.

1.5.16 Smoke Control

1.5.16.1 Special Inspector

a. AABC Technician Certification with one year of related experience, or

b. Registered Professional Engineer with related experience

1.5.16.2 Associate Special Inspector

Engineer-In-Training with one year of related experience.

PART 2 PRODUCTS

2.1 FABRICATOR SPECIAL INSPECTIONS

Special Inspections of fabricator's work performed in the fabricator's shop is required to be inspected in accordance with the Statement of Special Inspections and the Schedule of Special Inspections unless the fabricator is certified by the approved agency to perform such work without Special Inspections. Submit the following certification certifications to the Contracting Officer for information to allow work performed in the fabricator's shop to not be subjected to Special Inspections.

AISC Certified Steel Fabricator.

Steel Joist Institute Membership

At the completion of fabrication, submit a certificate of compliance, to be included with the comprehensive final report of Special Inspections, stating that the materials supplied and work performed by the fabricator are in accordance with the construction documents.

PART 3 EXECUTION

3.1 RESPONSIBILITIES

3.1.1 Quality Control Manager

a. Supervise all Special Inspectors required by the Contract Documents and the IBC.

b. Verify the qualifications of all of the Special Inspectors.

c. Verify the qualifications of fabricators.

d. Maintain a 3-ring binder for the Special Inspector's daily and biweekly reports. This file must be located in a conspicuous place in the project trailer/office to allow review by the Contracting Officer and the SER.

Maintain a rework items list that includes discrepancies noted on the Special Inspectors daily report.

3.1.2 Special Inspectors

a. Inspect all elements of the project for which the special inspector is qualified to inspect and are identified in the Schedule of Special Inspections.

b. Attend preparatory phase meetings related to the Definable Feature of Work (DFOW) for which the special inspector is qualified to inspect.

c. Submit Special Inspections agency's written NDT practices for the monitoring and control of the agency's operations to include the following:

(1) The agency's procedures for the selection and administration of inspection personnel, describing the training, experience and

examination requirements for qualifications and certification of inspection personnel.

(2) The agency's inspection procedures, including general inspection, material controls, and visual welding inspection.

d. Submit qualification records for nondestructive testing (NDT) technicians designated for the project.

e. Submit NDT procedures and equipment calibration records for NDT to be performed and equipment to be used for the project.

f. Submit a copy of the daily reports to the QC Manager.

g. Report discrepancies that are observed during Special Inspections to the QC Manager for correction. If discrepancies are not corrected before the special inspector leaves the site the observed discrepancies must be documented in the daily report.

h. Submit a biweekly Special Inspection Report until all inspections are complete. A report is required for each biweekly period in which Special Inspections activity occurs, and must include the following:

(1) A brief summary of the work performed during the reporting time frame.

(2) Changes and discrepancies with the drawings, specifications and mechanical or electrical component certification, that were observed during the reporting period.

(3) Discrepancies which were resolved or corrected.

(4) A list of nonconforming items requiring resolution.

(5) All applicable test result including nondestructive testing reports.

i. At the completion of each DFOW requiring Special Inspections, submit an interim report of Special Inspections that documents the Special Inspections completed for that DFOW. Identify the inspector responsible for each item inspected and corrections of all discrepancies noted in the daily reports. The interim report of Special Inspections must be signed, dated and indicate the certification of the special inspector qualifying them to conduct the inspection.

j. At the completion of the project submit a comprehensive final report of Special Inspections that documents the Special Inspections completed for the project and corrections of all discrepancies noted in the daily reports. The comprehensive final report of Special Inspections must be signed, dated and indicate the certification of the special inspector qualifying them to conduct the inspection.

3.2 DEFECTIVE WORK

Check work as it progresses, but failure to detect any defective work or materials must in no way prevent later rejection if defective work or materials are discovered, nor obligate the Contracting Officer to accept such work.

-- End of Section --

Project: P-1550
Location: MCB Camp Lejeune, NC
Project #: 1701820
Date: 12/10/2025

STATEMENT OF SPECIAL INSPECTIONS

Project Seismic Design Category: B
Project Risk Category: II
Project Design Wind Speed (mph): 144
Number of Stories: 1
Structure Height Above Grade (ft): 20
Hazardous Occupancy or attached to such? No Group H Occupancies

Special Inspector of Record (SIOR)

A Special Inspector of Record (SIOR) **IS NOT** required (per UFGS 01 45 35, Section 1.3.8)

Lateral Force Resisting System (LFRS)

2018 IBC 1704.3.2 and 1704.3.3

Following is a listing of critical main wind/seismic force resisting systems for this structure. Carefully inspect these elements as part of the roles and responsiblities of the Special Inspector (reference the Schedule of Special Inspections for inspection checklists).

Vertical LFRS Elements	Notes
Steel Moment Frames (Pre-Engineered Metal Buildng System	

Horizontal LFRS Elements	Notes
Pre-Engineered Metal Building Diaphragm System	

Project: P-1550
Location: MCB Camp Lejeune, NC
Project #: 1701820
Date: 12/10/2025

Designated Seismic Systems (DSS)

(2018 IBC 1705.13.3) (ASCE 7-16, 13.2.2, C13.2.2) (UFC 3-301-1, 2-5.3)

DESIGNATED SEISMIC SYSTEMS DO NOT APPLY TO THIS PROJECT, due to the Seismic Design Category being less than C.

ELECTRICAL Designated Seismic Systems (DSS) Requiring a Certificate of Compliance
N/A
N/A
N/A
N/A
N/A

If additional space is required, append an additional sheet listing the remaining DSS

MECHANICAL/PLUMBING Designated Seismic Systems (DSS) Requiring a Certificate of Compliance
N/A
N/A
N/A
N/A
N/A
N/A

If additional space is required, append an additional sheet listing the remaining DSS

OTHER Designated Seismic Systems (DSS) Requiring a Certificate of Compliance
N/A
N/A
N/A
N/A
N/A
N/A

Final Walk Down Inspection and Report

(UFC 3 301 01 SECTION 2-5.4)

Final Walk Down Inspection of non-structural Designated Seismic Systems does not apply to this project (no Designated Seismic Systems)

SCHEDULE OF SPECIAL INSPECTIONS

Reference UFGS 01 45 35 for all requirements not noted as part of this schedule.

INSPECTION DEFINITIONS:

PERFORM: Perform these tasks for each weld, fastener or bolted connection, and noted verification.

OBSERVE: Observe these items randomly during the course of each work day to insure that applicable requirements are being met. Operations need not be delayed pending these inspections at contractor's risk.

DOCUMENT: Document, with a report, that the work has been performed in accordance with the contract documents. This is in addition to any other reports required in the Special Inspections guide specification.

CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

The Seismic Design Category for this project is: ☐ A, ☒ B, ☐ C, ☐ D, ☐ E, ☐ F (check appropriate box)

STRUCTURAL - STEEL – WELDING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

STEEL INSPECTION PRIOR TO WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.4-1		
TASK	INSPECTION TYPE[1]	DESCRIPTION
1. Verify that the welding procedures specification (WPS) is available	**PERFORM**	
2. Verify manufacturer certifications for welding consumables are available	**PERFORM**	
3. Verify material identification	**PERFORM**	Type and grade.
4. Welder Identification System	**PERFORM**	The fabricator or erector, as applicable, shall maintain a system by which a welder who has welded a joint or member can be identified. Stamps, if used, shall be the low-stress type.
5. Fit-up of groove welds (including joint geometry)	OBSERVE	✓ Joint preparation ✓ Dimensions (alignment, root opening, root face, bevel) ✓ Cleanliness (condition of steel surfaces) ✓ Tacking (tack weld quality and location)

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

		✓ Backing type and fit (if applicable)
6. Configuration and finish of access holes	OBSERVE	
7. Fit-up of fillet welds	OBSERVE	✓ Dimensions (alignment, gaps at root) ✓ Cleanliness (condition of steel surfaces) ✓ Tacking (tack weld quality and location)
STEEL INSPECTION <u>DURING</u> WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.4-2		
TASK	INSPECTION TYPE	DESCRIPTION
8. Use of qualified welders	**PERFORM**	Welding by welders, welding operators, and tack welders who are qualified in conformance with requirements.
9. Control and handling of welding consumables	OBSERVE	✓ Packaging ✓ Electrode atmospheric exposure control
10. No welding over cracked tack welds	OBSERVE	
11. Environmental conditions	OBSERVE	✓ Wind speed within limits ✓ Precipitation and temperature
12. Welding Procedures Specification followed	OBSERVE	✓ Settings on welding equipment ✓ Travel speed ✓ Selected welding materials ✓ Shielding gas type/flow rate ✓ Preheat applied ✓ Interpass temperature maintained (min./max.) ✓ Proper position (F, V, H, OH) ✓ Intermix of filler metals avoided
13. Welding techniques	OBSERVE	✓ Interpass and final cleaning ✓ Each pass within profile limitations ✓ Each pass meets quality requirements

STRUCTURAL - STEEL – WELDING SECTION (CONTINUED)

STEEL INSPECTION AFTER WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.4-3		
TASK	INSPECTION TYPE [1]	DESCRIPTION
14. Welds cleaned	OBSERVE	
15. Size, length, and location of all welds	**PERFORM**	Size, length, and location of all welds conform to the requirements of the detail drawings.
16. Welds meet visual acceptance criteria	**PERFORM AND DOCUMENT**	✓ Crack prohibition ✓ Weld/base-metal fusion ✓ Crater cross section ✓ Weld profiles ✓ Weld size ✓ Undercut ✓ Porosity
17. Arc strikes	**PERFORM**	
18. k-area	**PERFORM**	When welding of doubler plates, continuity plates or stiffeners has been performed in the k-area, visually inspect the web k-area for cracks.
19. Backing removed, weld tabs removed and finished, and fillet welds added where required	**PERFORM**	
20. Repair activities	**PERFORM AND DOCUMENT**	
21. Document acceptance or rejection of welded joint or member	**PERFORM**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - STEEL – BOLTING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

STEEL INSPECTION TASKS PRIOR TO BOLTING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.6-1		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Manufacture's certifications available for fastener materials	**PERFORM**	
2. Fasteners marked in accordance with ASTM requirements	OBSERVE	
3. Proper fasteners selected for joint detail (grade, type, bolt length if threads are to be excluded from shear plane)	OBSERVE	
4. Proper bolting procedure selected for joint detail	OBSERVE	
5. Connecting elements, including appropriate faying surface condition and hole preparation, if specified, meet applicable requirements	OBSERVE	
6. Proper storage provided for bolts, nuts, washers, and other fastener components	OBSERVE	
STEEL INSPECTION TASKS DURING BOLTING – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table C-N5.6-2		
TASK	INSPECTION TYPE [1]	DESCRIPTION
7. Fastener assemblies of suitable condition, placed in all holes and washers (if required) are positioned as required	OBSERVE	
8. Joint brought to the snug-tight condition prior to pretensioning operation	OBSERVE	
9. Fastener component not turned by the wrench prevented from rotating	OBSERVE	
10. Bolts are pretensioned in accordance with RCSC Specification, progressing systematically from the most rigid point toward the free edges	OBSERVE	
STEEL INSPECTION TASKS AFTER BOLTING – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.2.1, AISC 360-10: Table C-N5.6-3		
TASK	INSPECTION TYPE [1]	DESCRIPTION
11. Document acceptance or rejection of all bolted connections	**DOCUMENT**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - STEEL - NON DESTRUCTIVE TESTING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

NONDESTRUCTIVE TESTING OF WELDED JOINTS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Section N5.5		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Use of qualified nondestructive testing personnel	**PERFORM**	Visual weld inspection and nondestructive testing (NDT) shall be conducted by personnel qualified in accordance with AWS D1.8 clause 7.2
2. CJP groove welds	OBSERVE	Dye penetrant testing (DT) and ultrasonic testing (UT) shall be performed on 20% of CJP groove welds for materials greater than 5/16" (8mm) thick. Testing rate must be increased to 100% if greater than 5% of welds tested have unacceptable defects.
3. Welded joints subject to fatigue	OBSERVE	Dye penetrant testing (DT) and Ultrasonic testing (UT) shall be performed on 100% of welded joints identified on contract drawings as being subject to fatigue.
4. Weld tab removal sites	OBSERVE	At the end of welds where weld tabs have been removed, magnetic particle testing shall be performed on the same beam-to-column joints receiving UT

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

STRUCTURAL - STEEL - COMPOSITE CONSTRUCTION [1]

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

COMPOSITE CONSTRUCTION PRIOR TO PLACING CONCRETE – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 360-16: Table N6.1, AISC 341-16: Table J9.1		
TASK	INSPECTION TYPE [2]	DESCRIPTION
1. Placement and installation of steel headed stud anchors	**PERFORM**	
2. Material identification of reinforcing steel (Type/Grade)	OBSERVE	
3. Determination of carbon equivalent for reinforcing steel other than ASTM A706	OBSERVE	
4. Proper reinforcing steel size, spacing, clearances, support, and orientation	OBSERVE	
5. Reinforcing steel has not been re-bent in the field	OBSERVE	
6. Reinforcing clearances have been provided	OBSERVE	
7. Reinforcing steel has been tied and supported as required	OBSERVE	
8. Composite member has required size	OBSERVE	

END SECTION

STRUCTURAL - STEEL - OTHER INSPECTIONS

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

OTHER STEEL INSPECTIONS – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.2.1, AISC 341-16: Tables J8.1 & J10.1		
TASK	INSPECTION TYPE [2]	DESCRIPTION
1. Anchor rods and other embedments supporting structural steel	**PERFORM**	Verify the diameter, grade, type, and length of the anchor rod or embedded item, and the extent or depth of embedment prior to placement of concrete.
2. Fabricated steel or erected steel frame	OBSERVE	Verify compliance with the details shown on the construction documents, such as braces, stiffeners, member locations and proper application of joint details at each connection.
3. Reduced beam sections (RBS) where/if occurs	**DOCUMENT**	✓ Contour and finish ✓ Dimensional tolerances
4. Protected zones	**DOCUMENT**	No holes or unapproved attachments made by fabricator or erector
5. H-piles where/if occurs	**DOCUMENT**	No holes or unapproved attachments made by the responsible contractor

END SECTION

---

[1] See Concrete Construction Section for all concrete related inspection of composite steel construction.

[2] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - COLD-FORMED METAL DECK - PLACEMENT SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

METAL DECK INSPECTION PRIOR TO DECK PLACEMENT – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.1		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Verify compliance of materials (deck and all deck accessories) with construction documents, including profiles, material properties, and base metal thickness	**PERFORM**	
2. Document acceptance or rejection of deck and deck accessories	**DOCUMENT**	
METAL DECK INSPECTION DURING DECK PLACEMENT – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.2		
TASK	INSPECTION TYPE [1]	DESCRIPTION
3. Verify compliance of deck and all deck accessories installation with construction documents	**PERFORM**	
4. Verify deck materials are represented by the mill certifications that comply with the construction documents	**PERFORM**	
5. Document acceptance or rejection of installation of deck and deck accessories	**DOCUMENT**	
METAL DECK INSPECTION AFTER DECK PLACEMENT – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.3		
TASK	INSPECTION TYPE [1]	DESCRIPTION
6. Welding procedure specification (WPS) available	**PERFORM**	
7. Manufactures certifications for welding consumables available	OBSERVE	
8. Material identification (type/grade)	OBSERVE	
9. Check welding equipment	OBSERVE	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - COLD-FORMED METAL DECK – WELDING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

METAL DECK INSPECTION DURING WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.4		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Use of qualified welders	OBSERVE	
2. Control and handling of welding consumables	OBSERVE	
3. Environmental conditions (wind speed, moisture, temperature)	OBSERVE	
4. WPS followed	OBSERVE	
METAL DECK INSPECTION AFTER WELDING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.5		
TASK	INSPECTION TYPE [1]	DESCRIPTION
5. Verify size and location of welds, including support, sidelap, and perimeter welds.	**PERFORM**	
6. Welds meet visual acceptance criteria	**PERFORM**	
7. Verify repair activities	**PERFORM**	
8. Document acceptance or rejection of welds	**DOCUMENT**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - COLD-FORMED METAL DECK – FASTENING SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

METAL DECK INSPECTION BEFORE MECHANICAL FASTENING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.6		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Manufacturer installation instructions available for mechanical fasteners	OBSERVE	
2. Proper tools available for fastener installation	OBSERVE	
METAL DECK INSPECTION DURING MECHANICAL FASTENING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.7		
TASK	INSPECTION TYPE [1]	DESCRIPTION
3. Fasteners are positioned as required	OBSERVE	
4. Fasteners are installed in accordance with manufacturer's instructions	OBSERVE	
METAL DECK INSPECTION AFTER MECHANICAL FASTENING – VERIFY THE FOLLOWING ARE IN COMPLIANCE SDI QA/QC-2011, Appendix 1, Table 1.8		
TASK	INSPECTION TYPE [1]	DESCRIPTION
5. Check spacing, type, and installation of support fasteners	**PERFORM**	
6. Check spacing, type, and installation of sidelap fasteners	**PERFORM**	
7. Check spacing, type, and installation of perimeter fasteners	**PERFORM**	
8. Verify repair activities	**PERFORM**	
9. Document acceptance or rejection of mechanical fasteners	**DOCUMENT**	

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.

STRUCTURAL - LIGHT GAUGE STEEL FRAMING AND/OR LIGHT GAUGE TRUSSES SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

LIGHT GAUGE STEEL CONSTRUCTION AND CONNECTIONS – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.2.2, 1705.11.2, 1705.11.3, UFC 4 023 03		
TASK	INSPECTION TYPE[1]	DESCRIPTION
1. Trusses spanning 60-feet or greater where/if applies	**PERFORM**	Verify that temporary and permanent truss restraint/bracing is installed in accordance with approved truss submittal package.
2. Welded connections (seismic and/or wind resisting system)	OBSERVE	Visually inspect all welds composing part of the main wind or seismic force resisting system, including shearwalls, braces, collectors (drag struts), and hold-downs.
3. Connections (seismic and/or wind resisting system)	OBSERVE	Visually inspect all screw attachment, bolting, anchoring and other fastening of components within the main wind or seismic force resisting system, including roof deck, roof framing, exterior wall covering, wall to roof/floor connections, braces, collectors (drag struts) and hold-downs.

END SECTION

STRUCTURAL - OPEN-WEB STEEL JOISTS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

OPEN-WEB STEEL JOISTS AND JOIST GIRDERS – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC TABLE 1705.2.3		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Installation of open-web steel joists and joist girders	OBSERVE	✓ End connections – welded or bolted ✓ Bridging – horizontal and diagonal

END SECTION

[1] **PERFORM**: Perform these tasks for each weld, fastener or bolted connection, and required verification.
OBSERVE: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

STRUCTURAL - CONCRETE CONSTRUCTION SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

CONCRETE CONSTRUCTION, INCLUDING COMPOSITE DECK – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC TABLE 1705.3 (ACI 318 REFERENCES NOTED IN IBC TABLE)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Inspect reinforcement, including prestressing tendons, and verify placement.	OBSERVE	Verify prior to placing concrete that reinforcing is of specified type, grade and size; that it is free of oil, dirt and unacceptable rust; that it is located and spaced properly; that hooks, bends, ties, stirrups and supplemental reinforcement are placed correctly; that lap lengths, stagger and offsets are provided; and that all mechanical connections are installed per the manufacturer's instructions and/or evaluation report.
2. Reinforcing bar welding	OBSERVE	✓ Verify weldability of reinforcing bars other than ASTM A 706 ✓ Inspect single-pass fillet welds, maximum 5/16" in accordance with AWS D1.4
3. All other welding	**CONTINUOUS**	Visually inspect all welds in accordance with AWS D1.4
4. Cast in place anchors and post installed drilled anchors (downward inclined)	OBSERVE	Verify prior to placing concrete that cast in place anchors and post installed drilled anchors have proper embedment, spacing and edge distance.
5. Post-installed adhesive anchors in horizontal or upward inclined orientations	**CONTINUOUS AND DOCUMENT**	✓ Inspect as required per approved ICC-ES report ✓ Verify that installer is certified for installation of horizontal and overhead installation applications ✓ Inspect proof loading as required by the contract documents
6. Verify use of required mix design	OBSERVE	Verify that all mixes used comply with the approved construction documents
7. Prior to concrete placement, fabricate specimens for strength tests, perform slump and air content tests, and determine the temperature of the concrete	**CONTINUOUS**	At the time fresh concrete is sampled to fabricate specimens for strength test verify these tests are performed by qualified technicians.
8. Inspect concrete and/or shotcrete placement for proper application techniques	**CONTINUOUS**	Verify proper application techniques are used during concrete conveyance and depositing avoids segregation or contamination. Verify that concrete is properly consolidated.
9. Verify maintenance of specified curing temperature and technique	OBSERVE	Inspect curing, cold weather protection, and hot weather protection procedures.
10. Pre-stressed concrete	**CONTINUOUS**	Verify application of prestressing forces and grouting of bonded prestressing tendons.

CONTINUED ON FOLLOWING PAGE

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.
CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

STRUCTURAL - CONCRETE CONSTRUCTION (CONTINUED)

CONCRETE CONSTRUCTION, INCLUDING COMPOSITE DECK – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC TABLE 1705.3 (ACI 318 REFERENCES NOTED IN IBC TABLE)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
11. Inspect erection of precast concrete members	OBSERVE	
12. Verify in-situ concrete strength, prior to stressing of tendons in post-tensioned concrete and prior to removal of shores and forms from beams and structural slabs.	OBSERVE	
13. Inspect formwork for shape, location and dimensions of the concrete member being formed.	OBSERVE	

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
DOCUMENT: Document in a report that the work has been performed as required. This is in addition to all other required reports.
CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

STRUCTURAL - MASONRY CONSTRUCTION SECTION (ALL RISK CATEGORIES)

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

MASONRY CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE AT START OF CONSTRUCTION IBC 1705.4 (ACI 530-13 TABLE 3.1.2 & 3.1.3)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Compliance with approved submittals prior to start	OBSERVE	
2. Proportions of site-mixed mortar.	OBSERVE	
3. Grade and type of reinforcement, anchor bolts, and prestressing tendons and anchorages	OBSERVE	
4. Prestressing technique	OBSERVE	
5. Properties of thin bed mortar for AAC masonry	OBSERVE	
MASONRY CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE PRIOR TO GROUTING IBC 1705.4 (ACI 530-13 TABLE 3.1.2 & 3.1.3)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
6. Grout space	OBSERVE	
7. Proportions of site-prepared grout and prestressing grout for bonded tendons	OBSERVE	
8. Proportions of site-mixed grout and prestressing grout for bonded tendons	OBSERVE	
9. Placement of masonry units and mortar joints	OBSERVE	
10. Welding of reinforcement	**CONTINUOUS**	
MASONRY CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE DURING CONSTRUCTION IBC 1705.4 (ACI 530-13 TABLE 3.1.2 & 3.1.3)		
TASK	INSPECTION TYPE [1]	DESCRIPTION
11. Size and location of structural elements is in compliance	OBSERVE	
12. Preparation, construction, and protection of masonry during cold weather (temperature below 40°F (4.4°c) or hot weather (temp above 90°F (32.2°C))	OBSERVE	
13. Application and measurement of prestressing force	**CONTINUOUS**	
14. Placement of grout and prestressing grout for bonded tendons	**CONTINUOUS**	
15. Placement of AAC masonry units and construction of thin bed mortar joints	**CONTINUOUS**	Continuous for first 5000 square feet only (465 square meters).
16. Observe preparation of grout specimens, mortar specimens, and/or prisms	OBSERVE	
17. Type, size and placement of reinforcement, connectors, anchor bolts and prestressing tendons and anchorages, including details of anchorage of masonry to structural members, frames, or other construction	OBSERVE	

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

GEOTECHNICAL - SOILS INSPECTION SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☒

SOILS INSPECTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.6		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Materials below shallow foundations are adequate to achieve the design bearing capacity.	OBSERVE	
2. Excavations are extended to proper depth and have reached proper material	OBSERVE	
3. Perform classification and testing of compacted fill materials	**OBSERVE**	
4. Verify use of proper materials, densities and lift thicknesses during placement and compaction of compacted fill	**CONTINUOUS**	
5. Prior to placement of compacted fill, inspect subgrade and verify that site has been prepared properly.	OBSERVE	During fill placement, the special inspector shall verify that proper materials and procedures are used in accordance with the provisions of the approved geotechnical report

END SECTION

GEOTECHNICAL - DRIVEN DEEP FOUNDATION ELEMENTS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

DEEP DRIVEN FOUNDATION CONSTRUCTION – VERIFY THE FOLLOWING ARE IN COMPLIANCE IBC 1705.7		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Verify element materials, sizes and lengths comply with requirements	**CONTINUOUS**	
2. Inspect driving operations and maintain complete and accurate records for each element	**CONTINUOUS**	
3. Verify placement locations and plumbness, confirm type and size of hammer, record number of blows per foot of penetration, determine required penetrations to achiever design capacity, record tip and butt elevations and document any damage to foundation element	**CONTINUOUS**	
4. Determine capacities of test elements and conduct additional load tests if required.	**CONTINUOUS**	
5. For steel or concrete elements, perform additional special inspections in accordance with the Steel and Concrete sections in this schedule		

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.
CONTINUOUS: Constant monitoring of identified tasks by a special inspector over the duration of performance of said tasks.

FIRE PROTECTION - SPRAYED FIRE-RESISTANT MATERIALS SECTION

ALL OR PORTIONS OF THIS SECTION ARE APPLICABLE IF BOX IS CHECKED: ☐

SPRAYED FIRE RESISTANT MATERIALS (SFRM) – VERIFY THE FOLLOWING ARE IN COMPLIANCE 2018 IBC 1705.14		
TASK	INSPECTION TYPE [1]	DESCRIPTION
1. Substrate condition	OBSERVE	Prior to application, confirm that surfaces have been prepared according to the approved fire-resistance design and manufacturer's instructions.
2. Material thickness	OBSERVE	Verify SFRM thickness according to 2018 IBC 1705.14.4
3. Material density	OBSERVE	Verify SFRM density according to 2018 IBC 1705.14.5
4. Bond strength	OBSERVE	Verify bond strength of cured SFRM according to IBC 1705.14.6

END SECTION

[1] **OBSERVE**: Observe these items on a random sampling basis daily to insure that applicable requirements are met. Operations need not be delayed pending these inspections at contractor's risk.

This page is intentionally left blank.

SECTION 01 50 00

TEMPORARY CONSTRUCTION FACILITIES AND CONTROLS
12/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C511	(2017) Reduced-Pressure Principle Backflow Prevention Assembly

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Traffic Control Plan - if applicable

SD-03 Product Data

Backflow Preventers

SD-06 Test Reports

Backflow Preventer Tests

SD-07 Certificates

Backflow Tester Certification

Backflow Preventers Certificate of Full Approval

1.3 BACKFLOW PREVENTERS CERTIFICATE

Certificate of Full Approval from FCCCHR List, University of Southern California, attesting that the design, size and make of each backflow preventer has satisfactorily passed the complete sequence of performance testing and evaluation for the respective level of approval. Certificate of provisional Approval will not be acceptable.

1.3.1 Backflow Tester Certificate

Prior to testing, submit to the Contracting Officer certification issued

by the State or local regulatory agency attesting that the backflow tester has successfully completed a certification course sponsored by the regulatory agency. Tester must not be affiliated with a company participating in other phases of this Contract.

1.3.2 Backflow Prevention Training Certificate

Submit a certificate recognized by the State or local authority that states the Contractor has completed at least 10 hours of training in backflow preventer installations. The certificate must be current.

1.4 WEATHER PROTECTION

Take necessary precautions to ensure that roof openings and other critical openings in the building are monitored carefully. Take immediate actions required to seal off such openings when rain or other detrimental weather is imminent, and at the end of each workday. Ensure that the openings are completely sealed off to protect materials and equipment in the building from damage.

1.5 DOD CONDITION OF READINESS (COR)

DOD will set the Condition of Readiness (COR) based on the weather forecast for sustained winds 50 knots (60 mph) or greater. Contact the Contracting Officer for the current COR setting.

Monitor weather conditions a minimum of twice a day and take appropriate actions according to the approved Emergency Plan in the accepted Accident Prevention Plan, EM 385-1-1 Section 01 Emergency Planning and the instructions below.

Unless otherwise directed by the Contracting Officer, comply with:

a. Condition FOUR (Sustained winds of 58 mph or greater expected within 72 hours): Normal daily jobsite cleanup and good housekeeping practices. Collect and store in piles or containers scrap lumber, waste material, and rubbish for removal and disposal at the close of each work day. Maintain the construction site including storage areas, free of accumulation of debris. Stack form lumber in neat piles less than 3.3 feet high. Remove all debris, trash, or objects that could become missile hazards. Review requirements pertaining to "Condition THREE" and continue action as necessary to attain "Condition FOUR" readiness. Contact Contracting Officer for weather and COR updates and completion of required actions.

b. Condition THREE (Sustained winds of 58 mph or greater expected within 48 hours): Maintain "Condition FOUR" requirements and commence securing operations necessary for "Condition ONE" which cannot be completed within 18 hours. Cease all routine activities which might interfere with securing operations. Commence securing and stow all gear and portable equipment. Make preparations for securing buildings. Reinforce or remove formwork and scaffolding. Secure machinery, tools, equipment, materials, or remove from the jobsite. Expend every effort to clear all missile hazards and loose equipment from general base areas. Contact Contracting Officer for weather and COR updates and completion of required actions. Review requirements pertaining to "Condition TWO" and continue action as necessary to attain "Condition THREE" readiness.

c. Condition TWO (Sustained winds of 58 mph or greater expected within 24 hours): Secure the jobsite, and leave Government premises.

d. Condition ONE. (Sustained winds of 58 mph or greater expected within 12 hours): Contractor access to the jobsite and Government premises is prohibited.

1.6 TRAILERS OR STORAGE BUILDINGS

Trailers or storage buildings will be permitted, where space is available, subject to the approval of the Contracting Officer. The trailer or building shall be in good condition, free from visible damage, rust, and deterioration, and meet all applicable safety requirements. Trailers shall be roadworthy and comply with all appropriate State and local vehicle requirements. Failure to maintain storage trailers or buildings to these standards shall result in the removal of non-complying units at the Contractor's expense. A sign not smaller than 24 by 24 inches shall be conspicuously placed on the trailer depicting the company name, business phone number, and emergency phone number. Trailers shall be anchored to resist high winds and must meet applicable state and local standards for anchoring mobile trailers.

Trailers that are placed outside of project boundaries will require base site approval and NEPA review. Any temporary trailer utilities outside the project boundary limit also will require base site approval and NEPA review. Allow 30 days for approval processing and NEPA documentation.

1.7 STORAGE AREAS

The Contract Clause entitled "FAR 52.236-10, Operations and Storage Areas" applies.

PART 2 PRODUCTS

2.1 BACKFLOW PREVENTERS

Reduced pressure principle type conforming to the applicable requirements AWWA C511.

PART 3 EXECUTION

3.1 EMPLOYEE PARKING

Construction Contract employees must park privately owned vehicles in an area designated by the Contracting Officer. Employee parking must not interfere with existing and established parking requirements of the Government installation.

3.2 AVAILABILITY AND USE OF UTILITY SERVICES

3.2.1 Temporary Utilities

a. The Contract clause related to utilities applies. Reasonable amounts of water and electricity from the nearest outlet will be provided free of charge for pursuance of work within a facility under this contract. If the nearest available outlet cannot be utilized by the Contractor because of improper voltage, insufficient current, improper pressure, incompatible connectors, etc., it shall be the responsibility of the Contractor to provide temporary utilities as

required.

b. Reasonable amounts of utilities for contractor trailers and storage buildings will be made available to the Contractor, when available. The Contractor shall be responsible for providing transformers, electrical service poles and drops for electrical services, and backflow preventer devices on connections to domestic water lines. Final taps and tie-ins to the Government utility grid will be made by the Contractor after approval by the Contracting Officer. Tap-in cost, if any, shall be the responsibility of the Contractor. Under no circumstances will taps to base fire hydrants be allowed for obtaining domestic water.

c. Any and all utilities outside the established site boundary in support of trailers or temporary facilties will require both a Site Approval and REIR, which can either be routed separately from the trailer approvals or under the same request.

3.2.2 Energy and Utilites Conservation

The Contractor shall carefully conserve utilities furnished without charge. The Contractor, at his own expense and in a manner satisfactory to the Contracting Officer, shall install and maintain all necessary temporary connections and distribution lines and remove the same prior to final acceptance of the construction.

3.2.3 Location of Underground Utilites

Location and Protection of underground utilities shall be the responsibility of the Contractor. Where existing-to-remain piping, utilities, and underground obstructions of any type are indicted in locations to be traversed by new piping, ducts, and other excavations the elevations of the existing utilities and obstructions shall be determined before the new work is completed.

a. In addition, the Contractor will be responsible for obtaining the services of a professional utility locator prior to digging. Contractor will provide documentation that the site has been surveyed and checked for underground utilities. All utilities must be located, including but not limited to power, water, sewer, storm drains, fiber optics, T.V. cable, telephone, and intrusion detection wiring. A set of known utility drawings will be available in the ROICC office for review to assist the locator.

b. It is mandatory that the Contractor also contact the Base Telephone Office (451-2531) prior to accomplishing any digging at Camp Lejeune. A telephone office representative will assist in locating telephone lines.

c. It is mandatory that the Contractor also contact Charter Communications, cable TV service prior to accomplishing any digging at Camp Lejeune, to ensure that all buried cable lines are identified. Contact Mr. Olin Criswell at 353-8677 for assistance.

d. It is mandatory that the contractor also contact the North Carolina One-Call Center to coordinate the location of underground natural gas infrastructure. North Carolina 811, Inc. can be reached at 811 on a touch-tone phone in the state of North Carolina or toll-free at 1.800.632.4949 if calling from out of state.

3.2.4 Damage to Underground Utilities

Immediate notice shall be delivered to the Contracting Officer of any damage. The Contractor shall make temporary repairs immediately, and shall provide permanent repairs as soon as practicable. For any additional work required by reason of conflict between the new and existing work, an adjustment in contract price will be made in accordance with Contract clause entitled "Differing Site Conditions", if appropriate.

3.2.5 Sanitation

Provide adequate sanitary conveniences of a type approved for the use of persons employed on the work, properly secluded from public observation, and maintained in such a manner as required and approved by the Contracting Officer. Maintain these conveniences at all times without nuisance. Upon completion of the work, remove the conveniences from the premises, leaving the premises clean and free from nuisance. Dispose of sewage through connection to a municipal, district, or station sanitary sewage system. Where such systems are not available, use chemical toilets or comparably effective units, and periodically empty wastes into a municipal, district, or station sanitary sewage system, or remove waste to a commercial facility. Include provisions for pest control and elimination of odors.

3.3 STATION OPERATION AFFECT ON CONTRACTOR OPERATIONS

3.3.1 Restricted Access Areas

Follow guidelines identified on drawings and in scope of work.

3.4 TRAFFIC PROVISIONS

3.4.1 Traffic Control Plan

If during the performance of work, it becomes necessary to modify vehicular traffic patterns at any locations, notify the Contracting Officer at least 15 calendar days prior to the proposed modification date, and provide a Traffic Control Plan detailing the proposed controls to traffic movement for approval. The plans shall be in accordance with State and local regulations and the MUTCD, Part VI. Make all notifications and obtain any permits required for modification to traffic movements outside Station'a jurisdiction. Provide cones, signs, barricades, lights, or other traffic control devices and personnel required to control traffic.

3.4.2 Dust Control

Dust control methods and procedures must be approved by the Contracting Officer. Coordinate dust control methods with 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS.

3.5 REDUCED PRESSURE BACKFLOW PREVENTERS

Provide an approved reduced pressure backflow prevention assembly at each location where the Contractor taps into the Government potable water supply.

Perform backflow preventer tests using test equipment, procedures, and certification forms conforming to those outlined in the latest edition of the Manual of Cross-Connection Control published by the FCCCHR Manual. Test and tag each reduced pressure backflow preventer upon initial

installation (prior to continued water use). Tag must contain the following information: make, model, serial number, dates of tests, results, maintenance performed, and signature of tester. Record test results on certification forms conforming to requirements cited earlier in this paragraph.

3.6 DUMPSTERS

Equip dumpsters with a secure cover and paint the standard installation color. Keep dumpster closed, except when being loaded with trash and debris. Empty site dumpsters at least once a week, or as needed to keep the site free of debris and trash. If necessary, provide 55 gallon trash containers painted the darker installation color to collect debris in the construction site area. For large demolitions, large dumpsters without lids are acceptable, but must not have debris higher than the sides before emptying.

3.7 CLEANUP

Remove construction debris, waste materials, packaging material and the like from the work site daily. Any dirt or mud which is tracked onto paved or surfaced roadways must be cleaned away. Store all salvageable materials resulting from demolition activities within the fenced area described above or at the supplemental storage area. Neatly stack stored materials not in trailers, whether new or salvaged.

3.8 RESTORATION OF STORAGE AREA

Upon completion of the project remove the bulletin board, signs, barricades, haul roads, and all other temporary products from the site. After removal of trailers, materials, and equipment from within the fenced area, remove the fence. Restore areas used during the performance of the Contract to the original or better condition. Remove gravel used to traverse grassed areas and restore the area to its original condition, including top soil and seeding as necessary.

-- End of Section --

SECTION 01 57 19

TEMPORARY ENVIRONMENTAL CONTROLS
08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY (IEPA)

35 IAC 900-901	Title 35 of Illinois Administrative Code, Subtitle H: Noise, Chapter I: Pollution Control Board

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA SW-846	(Third Edition; Update IV) Test Methods for Evaluating Solid Waste: Physical/Chemical Methods

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1053	Respirable Crystalline Silica
29 CFR 1910.1200	Hazard Communication
29 CFR 1926.1153	Respirable Crystalline Silica
40 CFR 50	National Primary and Secondary Ambient Air Quality Standards
40 CFR 60	Standards of Performance for New Stationary Sources
40 CFR 63	National Emission Standards for Hazardous Air Pollutants for Source Categories
40 CFR 64	Compliance Assurance Monitoring
40 CFR 82	Protection of Stratospheric Ozone
40 CFR 112	Oil Pollution Prevention
40 CFR 122.26	Storm Water Discharges (Applicable to State NPDES Programs, see section 123.25)
40 CFR 241	Guidelines for Disposal of Solid Waste
40 CFR 243	Guidelines for the Storage and Collection of Residential, Commercial, and Institutional Solid Waste
40 CFR 258	Subtitle D Landfill Requirements

40 CFR 260	Hazardous Waste Management System: General
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 261.7	Residues of Hazardous Waste in Empty Containers
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 262.11	Hazardous Waste Determination and Recordkeeping
40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
40 CFR 264	Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 265	Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 266	Standards for the Management of Specific Hazardous Wastes and Specific Types of Hazardous Waste Management Facilities
40 CFR 268	Land Disposal Restrictions
40 CFR 273	Standards for Universal Waste Management
40 CFR 273.2	Standards for Universal Waste Management - Batteries
40 CFR 273.4	Standards for Universal Waste Management - Mercury Containing Equipment
40 CFR 273.5	Standards for Universal Waste Management - Lamps
40 CFR 273.6	Applicability - Aerosol Cans
40 CFR 279	Standards for the Management of Used Oil
40 CFR 300	National Oil and Hazardous Substances Pollution Contingency Plan
40 CFR 300.125	National Oil and Hazardous Substances Pollution Contingency Plan - Notification and Communications
40 CFR 355	Emergency Planning and Notification
40 CFR 403	General Pretreatment Regulations for Existing and New Sources of Pollution

40 CFR 745	Lead-Based Paint Poisoning Prevention in Certain Residential Structures
40 CFR 761	Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions
49 CFR 171	General Information, Regulations, and Definitions
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements
49 CFR 173	Shippers - General Requirements for Shipments and Packagings
49 CFR 178	Specifications for Packagings

WASHINGTON STATE ADMINISTRATIVE CODE (WAC)

WAC-173-303-573	Standards for Universal Waste Management
WAC-173-303-573(2)	Standards for Universal Waste Management - Batteries
WAC-173-303-573(3)	Standards for Universal Waste Management - Mercury-containing Equipment
WAC-173-303-573(5)	Standards for Universal Waste Management - Lamps

1.2 DEFINITIONS

1.2.1 Class I and II Ozone Depleting Substance (ODS)

Class I ODS is defined in Section 602(a) of The Clean Air Act. A list of Class I ODS can be found on the EPA website at the following weblink. https://www.epa.gov/ozone-layer-protection/ozone-depleting-substances.

Class II ODS is defined in Section 602(s) of The Clean Air Act. A list of Class II ODS can be found on the EPA website at the following weblink. https://www.epa.gov/ozone-layer-protection/ozone-depleting-substances.

1.2.2 Contractor Generated Hazardous Waste

Contractor generated hazardous waste is materials that, if abandoned or disposed of, may meet the definition of a hazardous waste. These waste streams would typically consist of material brought on site by the Contractor to execute work, but are not fully consumed during the course of construction. Examples include, but are not limited to, excess paint thinners (i.e., methyl ethyl ketone, toluene), waste thinners, excess paints, excess solvents, waste solvents, excess pesticides, and contaminated pesticide equipment rinse water.

1.2.3 Electronics Waste

Electronics waste is discarded electronic devices intended for salvage,

recycling, or disposal.

1.2.4 Environmental Pollution and Damage

Environmental pollution and damage is the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to humankind; or degrade the environment aesthetically, culturally or historically.

1.2.5 Environmental Protection

Environmental protection is the prevention/control of pollution and habitat disruption that may occur to the environment during construction. The control of environmental pollution and damage requires consideration of land, water, and air; biological and cultural resources; and includes management of visual aesthetics; noise; solid, chemical, gaseous, and liquid waste; radiant energy and radioactive material as well as other pollutants.

1.2.6 Hazardous Debris

As defined in paragraph SOLID WASTE, debris that contains listed hazardous waste (either on the debris surface, or in its interstices, such as pore structure) in accordance with 40 CFR 261. Hazardous debris also includes debris that exhibits a characteristic of hazardous waste in accordance with 40 CFR 261.

1.2.7 Hazardous Materials

Hazardous material is any material that: Is defined in 49 CFR 171, listed in 49 CFR 172, regulated as a hazardous material in accordance with 49 CFR 173; or requires a Safety Data Sheet (SDS) in accordance with 29 CFR 1910.1200; or during end use, treatment, handling, packaging, storage, transportation, or disposal meets or has components that meet or have potential to meet the definition of a hazardous waste as defined by 40 CFR 261 Subparts A, B, C, or D. Designation of a material by this definition, when separately regulated or controlled by other sections or directives, does not eliminate the need for adherence to that hazard-specific guidance which takes precedence over this section for "control" purposes. Such material includes ammunition, weapons, explosive actuated devices, propellants, pyrotechnics, chemical and biological warfare materials, medical and pharmaceutical supplies, medical waste and infectious materials, bulk fuels, radioactive materials, and other materials such as asbestos, mercury, and polychlorinated biphenyls (PCBs).

1.2.8 Hazardous Waste

Hazardous Waste is any material that meets the definition of a solid waste and exhibits a hazardous characteristic (ignitability, corrosivity, reactivity, or toxicity) as specified in 40 CFR 261, Subpart C, or contains a listed hazardous waste as identified in 40 CFR 261, Subpart D, or meets a state, local, or host nation definition of a hazardous waste.

1.2.9 Land Application

Land Application means spreading or spraying discharge water at a rate that allows the water to percolate into the soil. No sheeting action, soil erosion, discharge into storm sewers, discharge into defined drainage

areas, or discharge into the "waters of the United States" must occur. Comply with federal, state, and local laws and regulations.

1.2.10 National Pollutant Discharge Elimination System (NPDES)

The NPDES permit program controls water pollution by regulating point sources that discharge pollutants into waters of the United States.

1.2.11 Oily Waste

Oily waste are those materials that are, or were, mixed with Petroleum, Oils, and Lubricants (POLs) and have become separated from that POLs. Oily wastes also means materials, including wastewaters, centrifuge solids, filter residues or sludges, bottom sediments, tank bottoms, and sorbents which have come into contact with and have been contaminated by, POLs and may be appropriately tested and discarded in a manner which is in compliance with other state and local requirements.

This definition includes materials such as oily rags, "kitty litter" sorbent clay and organic sorbent material. These materials may be land filled provided that: It is not prohibited in other state regulations or local ordinances; the amount generated is "de minimus" (a small amount); it is the result of minor leaks or spills resulting from normal process operations; and free-flowing oil has been removed to the practicable extent possible. Large quantities of this material, generated as a result of a major spill or in lieu of proper maintenance of the processing equipment, are a solid waste. As a solid waste, perform a hazardous waste determination prior to disposal. As this can be an expensive process, it is recommended that this type of waste be minimized through good housekeeping practices and employee education.

1.2.12 Regulated Waste

Regulated waste are solid wastes that have specific additional federal, state, or local controls for handling, storage, or disposal.

1.2.13 Sediment

Sediment is soil and other debris that have eroded and have been transported by runoff water or wind.

1.2.14 Solid Waste

Solid waste is a solid, liquid, semi-solid or contained gaseous waste. A solid waste can be a hazardous waste, non-hazardous waste, or non-Resource Conservation and Recovery Act (RCRA) regulated waste. Types of solid waste typically generated at construction sites may include:

1.2.14.1 Debris

Debris is non-hazardous solid material generated during the construction, demolition, or renovation of a structure that exceeds 2.5-inch particle size that is: a manufactured object; plant or animal matter; or natural geologic material (for example, cobbles and boulders), broken or removed concrete, masonry, and rock asphalt paving; ceramics; roofing paper and shingles. Inert materials may not be reinforced with or contain ferrous wire, rods, accessories and weldments. A mixture of debris and other material such as soil or sludge is also subject to regulation as debris if the mixture is comprised primarily of debris by volume, based on visual

inspection.

1.2.14.2 Green Waste

Green waste is the vegetative matter from landscaping, land clearing and grubbing, including, but not limited to, grass, bushes, scrubs, small trees and saplings, tree stumps and plant roots. Marketable trees, grasses and plants that are indicated to remain, be re-located, or be re-used are not included.

1.2.14.3 Material Not Regulated As Solid Waste

Material not regulated as solid waste is nuclear source or byproduct materials regulated under the Federal Atomic Energy Act of 1954 as amended; suspended or dissolved materials in domestic sewage effluent or irrigation return flows, or other regulated point source discharges; regulated air emissions; and fluids or wastes associated with natural gas or crude oil exploration or production.

1.2.14.4 Non-Hazardous Waste

Non-hazardous waste is waste that is excluded from, or does not meet, hazardous waste criteria in accordance with 40 CFR 261.

1.2.14.5 Recyclables

Recyclables are materials, equipment and assemblies such as doors, windows, door and window frames, plumbing fixtures, glazing and mirrors that are recovered and sold as recyclable, wiring, insulated/non-insulated copper wire cable, wire rope, and structural components. It also includes commercial-grade refrigeration equipment with Freon removed, household appliances where the basic material content is metal, clean polyethylene terephthalate bottles, cooking oil, used fuel oil, textiles, high-grade paper products and corrugated cardboard, stackable pallets in good condition, clean crating material, and clean rubber/vehicle tires. Metal meeting the definition of lead contaminated or lead based paint contaminated may not be included as recyclable if sold to a scrap metal company. Paint cans that meet the definition of empty containers in accordance with 40 CFR 261.7 may be included as recyclable if sold to a scrap metal company.

1.2.14.6 Surplus Soil

Surplus soil is existing soil that is in excess of what is required for this work, including aggregates intended, but not used, for on-site mixing of concrete, mortars, and paving. Contaminated soil meeting the definition of hazardous material or hazardous waste is not included and must be managed in accordance with paragraph HAZARDOUS MATERIAL MANAGEMENT.

1.2.14.7 Scrap Metal

This includes scrap and excess ferrous and non-ferrous metals such as reinforcing steel, structural shapes, pipe, and wire that are recovered or collected and disposed of as scrap. Scrap metal meeting the definition of hazardous material or hazardous waste is not included.

1.2.14.8 Wood

Wood is dimension and non-dimension lumber, plywood, chipboard,

hardboard. Treated or painted wood that meets the definition of lead contaminated or lead based contaminated paint is not included. Treated wood includes, but is not limited to, lumber, utility poles, crossties, and other wood products with chemical treatment.

1.2.15 Surface Discharge

Surface discharge means discharge of water into drainage ditches, storm sewers, or creeks meeting the definition of "waters of the United States". Surface discharges from construction sites are discrete, identifiable sources and require a permit from the governing agency. Comply with federal, state, and local laws and regulations.

1.2.16 Wastewater

Wastewater is the used water and solids that flow through a sanitary sewer to a treatment plant.

1.2.16.1 Stormwater

Stormwater is any precipitation in an urban or suburban area that does not evaporate or soak into the ground, but instead collects and flows into storm drains, rivers, and streams.

1.2.17 Waters of the United States

Waters of the United States means Federally jurisdictional waters, including wetlands, that are subject to regulation under Section 404 of the Clean Water Act or navigable waters, as defined under the Rivers and Harbors Act.

1.2.18 Wetlands

Wetlands are those areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions.

1.2.19 Universal Waste

The universal waste regulations streamline collection requirements for certain hazardous wastes in the following categories: batteries, pesticides, mercury-containing equipment (for example, thermostats), and lamps (for example, fluorescent bulbs). The rule is designed to reduce hazardous waste in the municipal solid waste (MSW) stream by making it easier for universal waste handlers to collect these items and send them for recycling or proper disposal. These regulations can be found at 40 CFR 273.

1.2.20 Location Specific Universal Waste

Any of the following dangerous waste that are subject to the universal waste requirements of WAC-173-303-573: Batteries as described in WAC-173-303-573(2)); Lamps as described in WAC-173-303-573(5); Mercury-containing equipment as described in WAC-173-303-573(3).

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S"

classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-01 Preconstruction Submittals

Preconstruction Survey

Regulatory Notifications; G

Environmental Manager Qualifications; G

Employee Training Records; G

Environmental Protection Plan; G

Dirt and Dust Control Plan; G

Solid Waste Management Permit; G

Stormwater Notice of Intent (for NPDES coverage under the general permit for construction activities); G

Spill Prevention Control And Countermeasure (SPCC) Plan; G

SD-06 Test Reports

Monthly Solid Waste Disposal Report; G

Inspection Reports

SD-07 Certificates

ECATTS Certificate Of Completion; G

Employee Training Records; G

Erosion and Sediment Control Inspector Qualifications

SD-11 Closeout Submittals

Regulatory Notifications; G

Assembled Employee Training Records; G

Solid Waste Management Permit; G

Stormwater Notice of Termination (for NPDES coverage under the general permit for construction activities); G

Waste Determination Documentation; G

Project Solid Waste Disposal Documentation Report; G

Sales Documentation; G

Hazardous Waste/Debris Management; G

Disposal Documentation for Hazardous and Regulated Waste; G

Contractor Hazardous Material Inventory Log; G

1.4 ENVIRONMENTAL PROTECTION REQUIREMENTS

Provide and maintain, during the life of the contract, environmental protection as defined. Plan for and provide environmental protective measures to control pollution that develops during construction practice. Plan for and provide environmental protective measures required to correct conditions that develop during the construction of permanent or temporary environmental features associated with the project. Protect the environmental resources within the project boundaries and those affected outside the limits of permanent work during the entire duration of this Contract. Comply with federal, state, and local regulations pertaining to the environment, including water, air, solid waste, hazardous waste and substances, oily substances, and noise pollution.

Tests and procedures assessing whether construction operations comply with Applicable Environmental Laws may be required. Analytical work must be performed by qualified laboratories; and where required by law, the laboratories must be certified.

1.4.1 Training in Environmental Compliance Assessment Training and Tracking System (ECATTS)

1.4.1.1 Personnel Requirements

The Environmental Manager is responsible for environmental compliance on projects. The Environmental Manager and other staff, must complete applicable ECATTS training modules (installation specific or general) prior to starting respective portions of on-site work under this Contract. If personnel changes occur for any of these positions after starting work, replacement personnel must complete applicable ECATTS training within 14 days of assignment to the project.

1.4.1.2 Certification

Submit an ECATTS certificate of completion for personnel who have completed the required ECATTS training. This training is web-based and can be accessed from any computer with Internet access using the following instructions.

Register for NAVFAC Environmental Compliance Assessment, Training, and Tracking System, by logging on to https://environmentaltraining.ecatts.com/. Obtain the password for registration from the Contracting Officer.

1.4.1.3 Refresher Training

This training has been structured to allow contractor personnel to receive credit under this contract and to carry forward credit to future contracts. Ensure the Environmental Manager review their training plans for new modules or updated training requirements prior to beginning work. Some training modules are tailored for specific state regulatory requirements; therefore, Contractors working in multiple states will be required to retake modules tailored to the state where the contract work is being performed.

1.4.2 Conformance with the Environmental Management System

Perform work under this contract consistent with the policy and objectives

identified in the installation's Environmental Management System (EMS). Perform work in a manner that conforms to objectives and targets of the environmental programs and operational controls identified by the EMS. Support Government personnel when environmental compliance and EMS audits are conducted by escorting auditors at the Project site, answering questions, and providing proof of records being maintained. Provide monitoring and measurement information as necessary to address environmental performance relative to environmental, energy, and transportation management goals. In the event an EMS nonconformance or environmental noncompliance associated with the contracted services, tasks, or actions occurs, take corrective and preventative actions. In addition, employees must be aware of their roles and responsibilities under the installation EMS and of how these EMS roles and responsibilities affect work performed under the contract.

Coordinate with the installation's EMS coordinator to identify training needs associated with environmental aspects and the EMS, and arrange training or take other action to meet these needs. Provide training documentation to the Contracting Officer. The Installation Environmental Office will retain associated environmental compliance records. Make EMS Awareness training completion certificates available to Government auditors during EMS audits and include the certificates in the Employee Training Records. See paragraph EMPLOYEE TRAINING RECORDS.

1.5 SPECIAL ENVIRONMENTAL REQUIREMENTS

Comply with the special environmental requirements listed here NCDEQ and attached at the end of this section.

1.5.1 Mid-Atlantic

Comply with the following state, regional, and local requirements.

1.5.1.1 NCDEQ

1.5.1.1.1 Removal of Oil/Water Separator

Demolition and removal of any OWS (OWS-42) requires submission of a work plan, confirmatory sampling, and a Soil Cleanup Report. These must all be reviewed and approved by NCDEQ prior to construction activities moving forward. Sampling and reporting should be carried out by the project retained environmental firm of choice and must be coordinated through the EAD. This process may require up to 30-45 days or more for work plan approval. In an effort to avoid project delays, pre-confirmatory sampling in the area around the separator is recommended at the earliest feasible date in the project with sampling being performed around all 4 sides and bottom of the OWS vault. It is advisable that at least one step-out set of samples be gathered, held, and run only in the event that the initial sampling results are found to be positive. This sampling will enable the approximate delineation of any soil contamination if present and will allow the vault and any contaminated soils to be removed and the area backfilled without lengthy project delays that might otherwise occur if no pre-confirmation sampling is performed. Sampling (both pre-confirmatory and confirmatory) could include but not be limited to the following analytes: VOCs, SVOCs, MADEP VPH/EPH, and possibly RCRA metals, as well as other applicable Operable Unit (OU) constituents as necessary. As previously stated, all work plans and soil investigation reports must be reviewed and approved by NCDEQ. Coordinate with Annette Waters 466-4903 at EAD.

1.5.1.1.2 Air Quality

If the construction includes the placement of emergency generators, fuel storage tanks, boilers (including hot water heaters), paint booths, blasting stations, spray guns, welding stations, wood processing equipment (sawdust), or refrigerant recovery equipment; manufacture specifications meeting compliance with applicable standards must be provided prior to placement. These new assets must be approved by NCDEQ for inclusion and modification to the Air Quality Permit. (Title V). Air emissions produced by these assets will be evaluated for compliance with Air Quality parameters. SDS or/and analytical reports may be required to assist in the evaluation.

1.5.1.2 Camp Lejeune

1.5.1.2.1 Removal of waste from Camp Lejeune

Remove and dispose of rubbish and debris from Government property. Provide 24-hour advance written notice to the Contracting Office of Contractor's intention to dispose rubbish and debris off base. Disposal at sites or landfills not holding a valid state of North Carolina permit is specifically prohibited. The prohibition also applies to sites where a permit my have been applied for but not yet obtained. If construction debris has been disposed off-base outside the parameter of this paragraph at a site without state permits or not in accordance with regulatory requirements, remove, transport, and relocate the debris to a state-approved site at Contractor expense. Pay any required fines, penalties, or fees related to the illegal disposal of construction debris. Metal will not be accepted at the Base Sanitary Landfill.

1.5.1.2.2 Surplus Soils Disposal for Camp Lejeune and MCAS New River

Transport all surplus soil to one of the designated locations on government property. No surplus material will leave government property without approval of installation Environmental Program Manager and the Contracting Officer. Deliver and properly manage surplus soil that cannot be reused on its originating site to one of the following locations:

a. Area managed by G-3/5 for reuse on training areas for various maintenance activities:

   3.5 acre storage, within TLZ Condor off Verona Loop Road, approximate coordinates 34d 38'07.3"N 77d 26' 41.7"W.

   Coordinate with G-3/5 Project Development Specialist, MCIEAST-MCB CAMLEJ at (910) 451-5772 to determine capacity available at the storage location, prior to delivery.

   This site operates Monday through Thursday between 0730 and 1500.

b. Area managed by PWD for use as daily cover:

   Base landfill, located on Piney Green Road, approximate coordinates 34d 41' 26.9"N 77d 19' 27.4"W.

   Contractor must provide temporary silt fencing around designated stockpile areas as needed.

Coordinate with Landfill Manager at (910) 451-8666. Landfill use letters will be provided so that deliveries can be tracked.

This site operates Monday through Thursday between 0730 and 1500 and on Friday between 0700 and 1400.

Contact POCs listed above 7 to 10 days in advance to coordinate delivery of material at the storage locations.

Prior to transportation to one of the designated locations, screen all surplus soil to remove all objects greater than 3 inches and deleterious material. Deleterious material consists of organic debris such as roots, stumps, timber, and construction debris. Construction debris may include, but is not limited to wood, plastic, glass, concrete, brick, and metal. Dispose of deleterious material and objects larger than 3 inches as specified.

Provide all plant, material, and labor for placement and management of the surplus material at the designated locations. Grade surplus material to a flat condition and slope to provide positive drainage daily. Submit the following verification documents to the Contracting Officer for review and approval:

(1) Photographic documentation that surplus soil has been properly placed. Photograph will include time and date of image.

(2) Certification statement indicating volume, in cubic yards (CY), of material delivered and confirming material is free of contaminants.

NOTE: Soil contaminated with debris or chemicals cannot be disposed at the stockpile locations. If contaminated soils are suspected or confirmed through presence of UXO, odors, or visual staining, affected soils must be properly tested, manifested, and disposed of in accordance with RCRA regulations. Contact Base EMD, ER Program Manager, for more information.

1.6 QUALITY ASSURANCE

1.6.1 Preconstruction Survey and Protection of Features

This paragraph supplements the Contract Clause PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS. Prior to start of any onsite construction activities, perform a Preconstruction Survey of the project site with the Contracting Officer, and take photographs showing existing environmental conditions in and adjacent to the site. Submit a report for the record. Include in the report a plan describing the features requiring protection under the provisions of the Contract Clauses, which are not specifically identified on the drawings as environmental features requiring protection along with the condition of trees, shrubs and grassed areas immediately adjacent to the site of work and adjacent to the Contractor's assigned storage area and access route(s), as applicable. The Contractor and the Contracting Officer will sign this survey report upon mutual agreement regarding its accuracy and completeness. Protect those environmental features included in the survey report and any indicated on the drawings, regardless of interference that their preservation may cause to the work under the Contract.

1.6.2 Regulatory Notifications

Provide regulatory notification requirements in accordance with federal,

state and local regulations. In cases where the Government will also provide public notification (such as stormwater permitting), coordinate with the Contracting Officer. Submit copies of regulatory notifications to the Contracting Officer at least 45 days prior to commencement of work activities. Typically, regulatory notifications must be provided for the following (this listing is not all-inclusive): demolition, renovation, NPDES defined site work, construction, removal or use of a permitted air emissions source, and remediation of controlled substances (asbestos, hazardous waste, lead paint).

1.6.3 Environmental Brief

Attend an environmental brief to be included in the preconstruction meeting. Provide the following information: types, quantities, and use of hazardous materials that will be brought onto the installation; and types and quantities of wastes/wastewater that may be generated during the Contract. Discuss the results of the Preconstruction Survey at this time.

Prior to initiating any work on site, meet with the Contracting Officer and installation Environmental Office to discuss the proposed Environmental Protection Plan (EPP) or equipment local requirement. Develop a mutual understanding relative to the details of environmental protection, including measures for protecting natural and cultural resources, required reports, required permits, permit requirements (such as mitigation measures), and other measures to be taken.

1.6.4 Environmental Manager

Appoint in writing an Environmental Manager for the project site. The Environmental Manager is directly responsible for coordinating contractor compliance with federal, state, local, and installation requirements. The Environmental Manager must ensure compliance with Hazardous Waste Program requirements (including hazardous waste handling, storage, manifesting, and disposal); implement the EPP; ensure environmental permits are obtained, maintained, and closed out; ensure compliance with Stormwater Program requirements; ensure compliance with Hazardous Materials (storage, handling, and reporting) requirements; and coordinate any remediation of regulated substances (lead, asbestos, PCB transformers). This can be a collateral position; however, the person in this position must be trained to adequately accomplish the following duties: ensure waste segregation and storage compatibility requirements are met; inspect and manage Satellite Accumulation areas; ensure only authorized personnel add wastes to containers; ensure Contractor personnel are trained in 40 CFR requirements in accordance with their position requirements; coordinate removal of waste containers; and maintain the Environmental Records binder and required documentation, including environmental permits compliance and close-out. Submit Environmental Manager Qualifications to the Contracting Officer.

1.6.5 Employee Training Records

Prepare and maintain Employee Training Records throughout the term of the contract meeting applicable 40 CFR requirements. Provide Employee Training Records in the Environmental Records Binder. Submit these Assembled Employee Training Records to the Contracting Officer at the conclusion of the project, unless otherwise directed.

Train personnel to meet state requirements. Conduct environmental protection/pollution control meetings for personnel prior to commencing

construction activities. Conduct additional meetings for new personnel and when site conditions change. Include in the training and meeting agenda: methods of detecting and avoiding pollution; familiarization with statutory and contractual pollution standards; installation and care of devices, vegetative covers, and instruments required for monitoring purposes to ensure adequate and continuous environmental protection/pollution control; anticipated hazardous or toxic chemicals or wastes, and other regulated contaminants; recognition and protection of archaeological sites, artifacts, waters of the United States, and endangered species and their habitat that are known to be in the area. Provide copy of the Erosion and Sediment Control Inspector Certification as required by NCDEQ.

1.6.6 Non-Compliance Notifications

The Contracting Officer will notify the Contractor in writing of any observed noncompliance with federal, state or local environmental laws or regulations, permits, and other elements of the Contractor's EPP. After receipt of such notice, inform the Contracting Officer of the proposed corrective action and take such action when approved by the Contracting Officer. The Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. FAR 52.242-14 Suspension of Work provides that a suspension, delay, or interruption of work due to the fault or negligence of the Contractor allows for no adjustments to the contract for time extensions or equitable adjustments. In addition to a suspension of work, the Contracting Officer may use additional authorities under the contract or law.

1.7 ENVIRONMENTAL PROTECTION PLAN

The purpose of the EPP is to present an overview of known or potential environmental issues that must be considered and addressed during construction. Incorporate construction related objectives and targets from the installation's EMS into the EPP. Include in the EPP measures for protecting natural and cultural resources, required reports, and other measures to be taken. Meet with the Contracting Officer or Contracting Officer Representative to discuss the EPP and develop a mutual understanding relative to the details for environmental protection including measures for protecting natural resources, required reports, and other measures to be taken. Submit the EPP within 45 days after Contractor award and not less than 5 days before the preconstruction meeting. Revise the EPP throughout the project to include any reporting requirements, changes in site conditions, or contract modifications that change the project scope of work in a way that could have an environmental impact. No requirement in this section will relieve the Contractor of any applicable federal, state, and local environmental protection laws and regulations. During Construction, identify, implement, and submit for approval any additional requirements to be included in the EPP. Maintain the current version onsite.

The EPP includes, but is not limited to, the following elements:

1.7.1 General Overview and Purpose

1.7.1.1 Descriptions

A brief description of each specific plan required by environmental permit or elsewhere in this Contract such as stormwater pollution prevention plan, spill control plan, solid waste management plan, wastewater

management plan, borrowing material plan.

1.7.1.2 Duties

The duties and level of authority assigned to the person(s) on the job site who oversee environmental compliance, such as who is responsible for adherence to the EPP, who is responsible for spill cleanup and training personnel on spill response procedures, who is responsible for manifesting hazardous waste to be removed from the site (if applicable), and who is responsible for training the Contractor's environmental protection personnel.

1.7.1.3 Procedures

A copy of any standard or project-specific operating procedures that will be used to effectively manage and protect the environment on the project site.

1.7.1.4 Communications

Communication and training procedures that will be used to convey environmental management requirements to Contractor employees and subcontractors.

1.7.1.5 Contact Information

Emergency contact information contact information (office phone number, cell phone number, and e-mail address).

1.7.2 General Site Information

1.7.2.1 Drawings

Drawings showing locations of proposed temporary excavations or embankments for haul roads, stream crossings, jurisdictional wetlands, material storage areas, structures, sanitary facilities, storm drains and conveyances, and stockpiles of excess soil.

1.7.2.2 Work Area

Work area plan showing the proposed activity in each portion of the area and identify the areas of limited use or nonuse. Include measures for marking the limits of use areas, including methods for protection of features to be preserved within authorized work areas and methods to control runoff and to contain materials on site, and a traffic control plan.

Show where any fuels, hazardous substances, solvents, or lubricants will be stored. Provide a spill plan to address any releases of those materials.

1.7.2.3 Documentation

A letter signed by an officer of the firm appointing the Environmental Manager and stating that person is responsible for managing and implementing the Environmental Program as described in this contract. Include in this letter the Environmental Manager's authority to direct the removal and replacement of non-conforming work.

1.7.3 Management of Natural Resources

a. Land resources

b. Tree protection

c. Replacement of damaged landscape features

d. Temporary construction

e. Stream crossings

f. Fish and wildlife resources

g. Wetland areas

1.7.4 Protection of Historical and Archaeological Resources

a. Objectives

b. Methods

1.7.5 Stormwater Management and Control

a. Ground cover

b. Erodible soils

c. Temporary measures

(1) Structural Practices

(2) Temporary and permanent stabilization

d. Effective selection, implementation and maintenance of Best Management Practices (BMPs).

e. Stormwater Pollution Prevention Plan (SWPPP).

1.7.6 Protection of the Environment from Waste Derived from Contractor Operations

Control and disposal of solid and sanitary waste.

Control and disposal of hazardous waste.

This item consist of the management procedures for hazardous waste to be generated. The elements of those procedures will coincide with the Installation Hazardous Waste Management Plan when within an installation. The Contracting Officer will provide a copy of the Installation Hazardous Waste Management Plan as applicable.

As a minimum, include the following:

a. List of the types of hazardous wastes expected to be generated

b. Procedures to ensure a written waste determination is made for appropriate wastes that are to be generated

c. Sampling/analysis plan, including laboratory method(s) that will be used for waste determinations and copies of relevant laboratory certifications

d. Methods and proposed locations for hazardous waste accumulation/storage (that is, in tanks or containers)

e. Management procedures for storage, labeling, transportation, and disposal of waste (treatment of waste is not allowed unless specifically noted)

f. Management procedures and regulatory documentation ensuring disposal of hazardous waste complies with Land Disposal Restrictions (40 CFR 268)

g. Management procedures for recyclable hazardous materials such as lead-acid batteries, used oil, and similar

h. Used oil management procedures in accordance with 40 CFR 279; Hazardous waste minimization procedures

i. Plans for the disposal of hazardous waste by permitted facilities; and Procedures to be employed to ensure required employee training records are maintained.

1.7.7 Prevention of Releases to the Environment

Procedures to prevent releases to the environment

Notifications in the event of a release to the environment

1.7.8 Regulatory Notification and Permits

List what notifications and permit applications must be made. Some permits require up to 180 days to obtain. Demonstrate that those permits have been obtained or applied for by including copies of applicable environmental permits. The EPP will not be approved until the permits have been obtained.

1.7.9 Clean Air Act Compliance

1.7.9.1 Haul Route

Submit truck and material haul routes along with a Dirt and Dust Control Plan for controlling dirt, debris, and dust on Installation roadways. As a minimum, identify in the plan the subcontractor and equipment for cleaning along the haul route and measures to reduce dirt, dust, and debris from roadways.

1.7.9.2 Pollution Generating Equipment

Identify air pollution generating equipment or processes that may require federal, state, or local permits under the Clean Air Act. Determine requirements based on any current installation permits and the impacts of the project. Provide a list of all fixed or mobile equipment, machinery or operations that could generate air emissions during the project to the Installation Environmental Office (Air Program Manager). Ensure required permits are obtained prior to installing and operating applicable equipment/processes.

1.7.9.3 Stationary Internal Combustion Engines

Identify portable and stationary internal combustion engines that will be supplied, used or serviced. Comply with 40 CFR 60 Subpart IIII, 40 CFR 60 Subpart JJJJ, 40 CFR 63 Subpart ZZZZ, and local regulations as applicable. At minimum, include the make, model, serial number, manufacture date, size (engine brake horsepower), and EPA emission certification status of each engine. Maintain applicable records and log hours of operation and fuel use. Logs must include reasons for operation and delineate between maintenance/testing, emergency, and non-emergency operation.

1.7.9.4 Refrigerants

Identify management practices to ensure that heating, ventilation, and air conditioning (HVAC) work involving refrigerants complies with 40 CFR 82 requirements. Technicians must be certified, maintain copies of certification on site, use certified equipment and log work that requires the addition or removal of refrigerant. Any refrigerant reclaimed is the property of the Government, coordinate with the Installation Environmental Office to determine the appropriate turn in location.

1.7.9.5 Air Pollution-engineering Processes

Identify planned air pollution-generating processes and management control measures (including, but not limited to, spray painting, abrasive blasting, demolition, material handling, fugitive dust, and fugitive emissions). Log hours of operations and track quantities of materials used.

1.7.9.6 Compliant Materials

Provide the Government a list of SDSs for all hazardous materials proposed for use on site. Materials must be compliant with all Clean Air Act regulations for emissions including solvent and volatile organic compound contents, and applicable National Emission Standards for Hazardous Air Pollutants requirements. The Government may alter or limit use of specific materials as needed to meet installation permit requirements for emissions.

1.8 LICENSES AND PERMITS

Obtain licenses and permits required for the construction of the project and in accordance with FAR 52.236-7 Permits and Responsibilities. Notify the Government of all equipment that may require permits or special approvals that the Contractor plans to use on site. This paragraph supplements the Contractor's responsibility under FAR 52.236-7 Permits and Responsibilities. All permits should be submitted and get approval from appropriate agencies by MC Camp Lejeune prior to start advertisement for construction.

a. The following permits will be obtained by the Government:
   (1) Erosion & Sediment Control Certificate of Approval
   (2) Stormwaer Management - NCG01
   (3) Application for Sewer Allocation and Fast Track Sewer System Extension
   (4) Wastewater Pump Station - Application for Sewer Allocation and Fast Track Sewer System Extension

(5) Water Distribution System - Application for Water Allocation and Water Main Extension

1.9 ENVIRONMENTAL RECORDS BINDER

Maintain on-site a separate three-ring Environmental Records Binder and submit at the completion of the project. Make separate parts within the binder that correspond to each submittal listed under paragraph CLOSEOUT SUBMITTALS in this section.

1.10 SOLID WASTE MANAGEMENT PERMIT

Provide the Contracting Officer with written notification of the quantity of anticipated solid waste or debris that is anticipated or estimated to be generated by construction. Include in the report the locations where various types of waste will be disposed or recycled. Include letters of acceptance from the receiving location or as applicable; submit one copy of the receiving location state and local Solid Waste Management Permit or license showing such agency's approval of the disposal plan before transporting wastes off Government property.

1.10.1 Monthly Solid Waste Disposal Report

Monthly, submit a solid waste disposal report to the Contracting Officer. For each waste, the report will state the classification (using the definitions provided in this section), amount, location, and name of the business receiving the solid waste.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 PROTECTION OF NATURAL RESOURCES

Minimize interference with, disturbance to, and damage to fish, wildlife, and plants, including their habitats. Prior to the commencement of activities, consult with the Installation Environmental Office as applicable, regarding rare species or sensitive habitats that need to be protected. The protection of rare, threatened, and endangered animal and plant species identified, including their habitats, is the Contractor's responsibility.

Preserve the natural resources within the project boundaries and outside the limits of permanent work. Restore to an equivalent or improved condition upon completion of work that is consistent with the requirements of the Installation Environmental Office or as otherwise specified. Confine construction activities to within the limits of the work indicated or specified.

3.1.1 Flow Ways

Do not alter water flows or otherwise significantly disturb the native habitat adjacent to the project and critical to the survival of fish and wildlife, except as specified and permitted.

3.1.2 Vegetation

Except in areas to be cleared, do not remove, cut, deface, injure, or destroy trees or shrubs without the Contracting Officer's permission. Do not fasten or attach ropes, cables, or guys to existing nearby trees for anchorages unless authorized by the Contracting Officer. Where such use of attached ropes, cables, or guys is authorized, the Contractor is responsible for any resultant damage.

Protect existing trees that are to remain to ensure they are not injured, bruised, defaced, or otherwise damaged by construction operations. Remove displaced rocks from uncleared areas. Coordinate with the Contracting Officer and Installation Environmental Office to determine appropriate action for trees and other landscape features scarred or damaged by equipment operations.

3.1.3 Streams

Stream crossings must allow movement of materials or equipment without violating water pollution control standards of the federal, state, and local governments. Construction of stream crossing structures must be in compliance with all required permits including, but not limited to, Clean Water Act Section 404, and Section 401 Water Quality.

The Contracting Officer's approval and appropriate permits are required before any equipment will be permitted to ford live streams. In areas where frequent crossings are required, install temporary culverts or bridges. Obtain Contracting Officer's approval prior to installation. Remove temporary culverts or bridges upon completion of work, and repair the area to its original condition unless otherwise required by the Contracting Officer.

3.2 STORMWATER

Do not discharge stormwater from construction sites to the sanitary sewer. If the water is noted or suspected of being contaminated, it may only be released to the storm drain system if the discharge is specifically permitted. Obtain authorization in advance from the Installation Environmental Office for any release of contaminated water.

3.2.1 Construction General Permit

Provide a Construction General Permit as required by 40 CFR 122.26 or the State of North Carolina General Permit. Under the terms and conditions of the permit, install, inspect, maintain BMPs, prepare stormwater erosion and sediment control inspection reports, and submit SWPPP inspection reports. Maintain construction operations and management in compliance with the terms and conditions of the general permit for stormwater discharges from construction activities.

3.2.1.1 Stormwater Pollution Prevention Plan

Submit a project-specific Stormwater Pollution Prevention Plan (SWPPP) to the Contracting Officer for approval, prior to the commencement of work. The SWPPP must meet the requirements of 40 CFR 122.26 and the North Carolina State General Permit State General Permit for stormwater discharges from construction sites.

Include the following:

a. Comply with terms of the state general permit for stormwater discharges from construction activities. Prepare SWPPP in accordance with state requirements. Use state

b. Select applicable BMPs from EPA Fact Sheets located at https://www.epa.gov/npdes/national-menu-best-management-practices-bmps-stormwater#constr or in accordance with applicable state or local requirements.

c. Include a completed copy of the Notice of Intent, BMP Inspection Report Template, and Stormwater Notice of Termination, except for the effective date.

3.2.1.2 Stormwater Notice of Intent for Construction Activities

Prepare and submit the Notice of Intent for NPDES coverage under the general permit for construction activities to the Contracting Officer for review and approval.

Submit the approved NOI and appropriate permit fees onto the appropriate federal or state agency for approval. No land disturbing activities may commence without permit coverage. Maintain an approved copy of the SWPPP at the onsite construction office, and continually update as regulations require, reflecting current site conditions.

Comply with additional state and local requirements.

3.2.1.3 Inspection Reports

Submit "Inspection Reports" to the Contracting Officer in accordance with the State of North Carolina Construction General Permit.

3.2.1.4 Stormwater Pollution Prevention Plan Compliance Notebook

Create and maintain a three ring binder of documents that demonstrate compliance with the Construction General Permit. Include a copy of the permit Notice of Intent, proof of permit fee payment, SWPPP and SWPPP update amendments, inspection reports and related corrective action records, copies of correspondence with the the North Carolina State Permitting Agency, and a copy of the permit Notice of Termination in the binder. At project completion, the notebook becomes property of the Government. Provide the compliance notebook to the Contracting Officer.

3.2.1.5 Stormwater Notice of Termination for Construction Activities

Submit a Notice of Termination to the Contracting Officer for approval once construction is complete and final stabilization has been achieved on all portions of the site for which the permittee is responsible. Once approved, submit the Notice of Termination to the appropriate state or federal agency. Prepare as-built topographic survey information required by the permitting agency for certification of the stormwater management system, and provide to the Contracting Officer.

3.2.2 Erosion and Sediment Control Measures

Provide erosion and sediment control measures in accordance with state and local laws and regulations. Preserve vegetation to the maximum extent practicable.

Erosion control inspection reports may be compiled as part of a stormwater pollution prevention plan inspection reports.

3.2.2.1 Erosion Control

Prevent erosion by Compost Blankets,. Stabilize slopes by sodding, or such combination of these methods necessary for effective erosion control. Use of hay bales is prohibited.

3.2.2.2 Sediment Control Practices

Implement sediment control practices to divert flows from exposed soils, temporarily store flows, or otherwise limit runoff and the discharge of pollutants from exposed areas of the site. Implement sediment control practices prior to soil disturbance and prior to creating areas with concentrated flow, during the construction process to minimize erosion and sediment laden runoff. Include the following devices: silt fence, temporary diversion dikes, storm drain inlet protection, sediment basins, silt fence outlets, Location and details of installation and construction are indicated on the drawings.

3.2.3 Work Area Limits

Mark the areas that need not be disturbed under this Contract prior to commencing construction activities. Mark or fence isolated areas within the general work area that are not to be disturbed. Protect monuments and markers before construction operations commence. Where construction operations are to be conducted during darkness, all markers must be visible in the dark. Personnel must be knowledgeable of the purpose for marking and protecting particular objects.

3.2.4 Contractor Facilities and Work Areas

Place field offices, staging areas, stockpile storage, and temporary buildings in areas designated on the drawings or as directed by the Contracting Officer. Move or relocate the Contractor facilities only when approved by the Government. Provide erosion and sediment controls for onsite borrow and spoil areas to prevent sediment from entering nearby waters. Control temporary excavation and embankments for plant or work areas to protect adjacent areas.

3.3 SURFACE AND GROUNDWATER

3.3.1 Dewatering

Construction operations for dewatering must be constantly controlled to maintain compliance with existing state water quality standards and designated uses of the surface water body. Comply with the State of North Carolina water quality standards and anti-degradation provisions. Do not discharge excavation ground water to the sanitary sewer, storm drains, or to surface waters without prior specific authorization in writing from the Installation Environmental Office or Contracting Officer. Discharge of hazardous substances will not be permitted under any circumstances. Use sediment control BMPs to prevent construction site runoff from directly entering any storm drain or surface waters.

If the construction dewatering is noted or suspected of being contaminated, it may only be released to the storm drain system if the discharge is specifically permitted. Obtain authorization for any

contaminated groundwater release in advance from the Installation Environmental Officer and the federal or state authority, as applicable. Discharge of hazardous substances will not be permitted under any circumstances.

3.3.2 Waters of the United States

Do not enter, disturb, destroy, or allow discharge of contaminants into waters of the United States.

3.4 PROTECTION OF CULTURAL RESOURCES

3.4.1 Archaeological Resources

Existing archaeological resources within the work area are shown on the drawings. Protect these resources and be responsible for their preservation during the life of the Contract. If, during excavation or other construction activities, any previously unidentified or unanticipated historical, archaeological, and cultural resources are discovered or found, activities that may damage or alter such resources will be suspended. Resources covered by this paragraph include, but are not limited to: any human skeletal remains or burials; artifacts; shell, midden, bone, charcoal, or other deposits; rock or coral alignments, pavings, wall, or other constructed features; and any indication of agricultural or other human activities. Upon such discovery or find, immediately notify the Contracting Officer so that the appropriate authorities may be notified and a determination made as to their significance and what, if any, special disposition of the finds should be made. Cease all activities that may result in impact to or the destruction of these resources. Secure the area and prevent employees or other persons from trespassing on, removing, or otherwise disturbing such resources. The Government retains ownership and control over archaeological resources.

3.5 AIR RESOURCES

Equipment operation, activities, or processes will be in accordance with 40 CFR 64 and state air emission and performance laws and standards.

3.5.1 Preconstruction Air Permits

Notify the Air Program Manager, through the Contracting Officer, at least 6 months prior to bringing equipment, assembled or unassembled, onto the Installation, so that air permits can be secured. Necessary permitting time must be considered in regard to construction activities. Clean Air Act (CAA) permits must be obtained prior to bringing equipment, assembled or unassembled, onto the Installation.

3.5.2 Oil or Dual-fuel Boilers and Furnaces

Provide product data and details for new, replacement, or relocated fuel fired boilers, heaters, or furnaces to the Installation Environmental Office (Air Program Manager) through the Contracting Officer. Data to be reported include: equipment purpose (water heater, building heat, process), manufacturer, model number, serial number, fuel type (oil type, gas type) size (MMBTU heat input). Provide in accordance with paragraph PRECONSTRUCTION AIR PERMITS.

3.5.3 Burning

Burning is prohibited on the Government premises.

3.5.4 Class I and II ODS Prohibition

Class I and II ODS are Government property and must be returned to the Government for appropriate management. Coordinate with the Installation Environmental Office to determine the appropriate location for turn in of all reclaimed refrigerant.

3.5.5 Venting of Refrigerant

Accidental venting of a refrigerant is a release and must be reported immediately to the Contracting Officer. Intentional venting of refrigerants (including most Non-ODS substitute refrigerants) is prohibited per 40 CFR 82.

3.5.6 EPA Certification Requirements

Heating and air conditioning technicians must be certified through an EPA-approved program. Maintain copies of certifications at the employees' places of business; technicians must carry certification wallet cards, as provided by environmental law.

3.5.7 Dust Control

Keep dust down at all times, including during nonworking periods. Sprinkle or treat, with dust suppressants, the soil at the site, haul roads, and other areas disturbed by operations. Dry power brooming will not be permitted. Instead, use vacuuming, wet mopping, wet sweeping, or wet power brooming. Air blowing will be permitted only for cleaning nonparticulate debris such as steel reinforcing bars. Only wet cutting will be permitted for cutting concrete blocks, concrete, and bituminous concrete. Do not unnecessarily shake bags of cement, concrete mortar, or plaster. Since these products contain Crystalline Silica, comply with the applicable OSHA standard, 29 CFR 1910.1053 or 29 CFR 1926.1153 for controlling exposure to Crystalline Silica Dust.

3.5.7.1 Particulates

Dust particles, aerosols and gaseous by-products from construction activities, and processing and preparation of materials (such as from asphaltic batch plants) must be controlled at all times, including weekends, holidays, and hours when work is not in progress. Maintain excavations, stockpiles, haul roads, permanent and temporary access roads, plant sites, spoil areas, borrow areas, and other work areas within or outside the project boundaries free from particulates that would exceed 40 CFR 50, state, and local air pollution standards or that would cause a hazard or a nuisance. Sprinkling, chemical treatment of an approved type, baghouse, scrubbers, electrostatic precipitators, or other methods will be permitted to control particulates in the work area. Sprinkling, to be efficient, must be repeated to keep the disturbed area damp. Provide sufficient, competent equipment available to accomplish these tasks. Perform particulate control as the work proceeds and whenever a particulate nuisance or hazard occurs. Comply with state and local visibility regulations.

3.5.7.2 Abrasive Blasting

Blasting operations cannot be performed without prior approval of the Installation Air Program Manager. The use of silica sand is prohibited in sandblasting.

Provide tarpaulin drop cloths and windscreens to enclose abrasive blasting operations to confine and collect dust, abrasive agent, paint chips, and other debris. Perform work involving removal of hazardous material in accordance with 29 CFR 1910.

3.5.8 Odors

Control odors from construction activities. The odors must be in compliance with state regulations and local ordinances and may not constitute a health hazard.

3.6 WASTE MINIMIZATION

Minimize the use of hazardous materials and the generation of waste. Include procedures for pollution prevention/ hazardous waste minimization in the Hazardous Waste Management Section of the EPP. Obtain a copy of the installation's Pollution Prevention/Hazardous Waste Minimization Plan for reference material when preparing this part of the EPP. If no written plan exists, obtain information by contacting the Contracting Officer. Describe the anticipated types of the hazardous materials to be used in the construction when requesting information.

3.6.1 Salvage, Reuse and Recycle

Identify anticipated materials and waste for salvage, reuse, and recycling. Describe actions to promote material reuse, resale or recycling. To the extent practicable, all scrap metal must be sent for reuse or recycling and will not be disposed of in a landfill.

Include the name, physical address, and telephone number of the hauler, if transported by a franchised solid waste hauler. Include the destination and, unless exempted, provide a copy of the state or local permit (cover) or license for recycling.

3.6.2 Nonhazardous Solid Waste Diversion Report

Maintain an inventory of nonhazardous solid waste diversion and disposal of construction and demolition debris. Submit a report to the Contracting Officer on the first working day after each fiscal year quarter, starting the first quarter that nonhazardous solid waste has been generated. Include the following in the report:

Construction and Demolition (C&D) Debris Disposed	tons, as appropriate
C&D Debris Recycled	tons, as appropriate
C&D Debris Composted	tons, as appropriate

Construction and Demolition (C&D) Debris Disposed	tons, as appropriate
Total C&D Debris Generated	tons, as appropriate
Waste Sent to Waste-To-Energy Incineration Plant (This amount should not be included in the recycled amount)	tons, as appropriate

3.7 WASTE MANAGEMENT AND DISPOSAL

3.7.1 Waste Determination Documentation

Complete a Waste Determination form (provided at the pre-construction conference) for Contractor-derived wastes to be generated. All potentially hazardous solid waste streams that are not subject to a specific exclusion or exemption from the hazardous waste regulations (e.g., scrap metal, domestic sewage) or subject to special rules, (lead-acid batteries and precious metals) must be characterized in accordance with the requirements of 40 CFR 262.11 or corresponding applicable state or local regulations. Base waste determination on user knowledge of the processes and materials used, and analytical data when necessary. Consult with the Installation environmental staff for guidance on specific requirements. Attach support documentation to the Waste Determination form. As a minimum, provide a Waste Determination form for the following waste (this listing is not exhaustive): oil- and latex -based painting and caulking products, solvents, adhesives, aerosols, petroleum products, and containers of the original materials.

3.7.1.1 Sampling and Analysis of Waste

3.7.1.1.1 Waste Sampling

Sample waste in accordance with EPA SW-846. Clearly mark each sampled drum or container with the Contractor's identification number, and cross reference to the chemical analysis performed.

3.7.1.1.2 Laboratory Analysis

Follow the analytical procedure and methods in accordance with the 40 CFR 261. Provide analytical results and reports performed to the Contracting Officer. Coordinate all activities with Installation Hazardous Waste Manager.

3.7.1.1.3 Analysis Type

Identify hazardous waste by analyzing for the following characteristics: ignitability, corrosivity, reactivity, toxicity based on TCLP results.

3.7.2 Solid Waste Management

3.7.2.1 Project Solid Waste Disposal Documentation Report

Provide copies of the waste handling facilities' weight tickets, receipts, bills of sale, and other sales documentation. In lieu of sales documentation, a statement indicating the disposal location for the solid

waste that is signed by an employee authorized to legally obligate or bind the firm may be submitted. The sales documentation Contractor certification must include the receiver's tax identification number and business, EPA or state registration number, along with the receiver's delivery and business addresses and telephone numbers. For each solid waste retained for the Contractor's own use, submit the information previously described in this paragraph on the solid waste disposal report. Prices paid or received do not have to be reported to the Contracting Officer unless required by other provisions or specifications of this Contract or public law.

3.7.2.2 Control and Management of Solid Wastes

Pick up solid wastes, and place in covered containers that are regularly emptied. Do not prepare or cook food on the project site. Prevent contamination of the site or other areas when handling and disposing of wastes. At project completion, leave the areas clean. Employ segregation measures so that no hazardous or toxic waste will become co-mingled with non-hazardous solid waste. Transport solid waste off Government property and dispose of it in compliance with 40 CFR 260, state, and local requirements for solid waste disposal. A Subtitle D RCRA permitted landfill is the minimum acceptable offsite solid waste disposal option. Verify that the selected transporters and disposal facilities have the necessary permits and licenses to operate. Solid waste disposal offsite must comply with most stringent local, state, and federal requirements, including 40 CFR 241, 40 CFR 243, and 40 CFR 258.

Manage hazardous material used in construction, including but not limited to, aerosol cans, waste paint, cleaning solvents, contaminated brushes, and used rags, in accordance with 49 CFR 173.

3.7.3 Control and Management of Hazardous Waste

Do not dispose of hazardous waste on Government property. Do not discharge any waste to a sanitary sewer, storm drain, or to surface waters or conduct waste treatment or disposal on Government property without written approval of the Contracting Officer and Installation Hazardous Waste Manager.

3.7.3.1 Hazardous Waste/Debris Management

Identify construction activities that will generate hazardous waste or debris. Provide a documented waste determination for resultant waste streams. Identify, label, handle, store, and dispose of hazardous waste or debris in accordance with federal, state, and local regulations, including 40 CFR 261, 40 CFR 262, 40 CFR 263, 40 CFR 264, 40 CFR 265, 40 CFR 266, and 40 CFR 268.

Manage hazardous waste in accordance with the approved Hazardous Waste Management Section of the EPP. Store hazardous wastes in approved containers in accordance with 49 CFR 173 and 49 CFR 178. Hazardous waste generated within the confines of Government facilities is identified as being generated by the Government. Prior to removal of any hazardous waste from Government property, hazardous waste manifests must be signed by personnel from the Installation Environmental Office. Do not bring hazardous waste onto Government property. Provide the Contracting Officer with a copy of waste determination documentation for any solid waste streams that have any potential to be hazardous waste or contain any chemical constituents listed in 40 CFR 372-SUBPART D.

3.7.3.2 Universal Waste Management

Manage the following categories of universal waste in accordance with federal, state, and local requirements and installation instructions:

a. Batteries as described in 40 CFR 273.2

b. Lamps as described in 40 CFR 273.5

c. Mercury-containing equipment as described in 40 CFR 273.4

d. Aerosol cans as described in 40 CFR 273.6

e. Installation specific

Mercury is prohibited in the construction of this facility, unless specified otherwise, and with the exception of mercury vapor lamps and fluorescent lamps. Dumping of mercury-containing materials and devices such as mercury vapor lamps, fluorescent lamps, and mercury switches, in rubbish containers is prohibited. Remove without breaking, pack to prevent breakage, and transport out of the activity in an unbroken condition for disposal as directed.

3.7.3.3 Disposal Documentation for Hazardous and Regulated Waste

Contact the Contracting Officer or designated representative for the facility RCRA identification number that is to be used on each manifest.

Submit a copy of the applicable EPA and or state permit(s), manifest(s), or license(s) for transportation, treatment, storage, and disposal of hazardous and regulated waste by permitted facilities. Hazardous or toxic waste manifests must be reviewed, signed, and approved by the Contracting Officer before the Contractor may ship waste. To obtain specific disposal instructions, coordinate with the Installation Environmental Office. Refer to location special requirements for the Installation Point of Contact information.

3.7.4 Releases/Spills of Oil and Hazardous Substances

3.7.4.1 Response and Notifications

Exercise due diligence to prevent, contain, and respond to spills of hazardous material, hazardous substances, hazardous waste, sewage, regulated gas, petroleum, lubrication oil, and other substances regulated in accordance with 40 CFR 300. Maintain spill cleanup equipment and materials at the work site. In the event of a spill, take prompt, effective action to stop, contain, curtail, or otherwise limit the amount, duration, and severity of the spill/release. In the event of any releases of oil and hazardous substances, chemicals, or gases; immediately (within 15 minutes) notify the Installation Fire Department, the Installation Command Duty Officer, the Installation Environmental Office, the Contracting Officer and the state or local authority.

Submit verbal and written notifications as required by the federal (40 CFR 300.125 and 40 CFR 355), state, local regulations and instructions. Provide copies of the written notification and documentation that a verbal notification was made within 20 days. Spill response must be in accordance with 40 CFR 300 and applicable state and

local regulations. Contain and clean up these spills without cost to the Government.

3.7.4.2 Clean Up

Clean up hazardous and non-hazardous waste spills. Reimburse the Government for costs incurred including sample analysis materials, clothing, equipment, and labor if the Government will initiate its own spill cleanup procedures, for Contractor- responsible spills, when: Spill cleanup procedures have not begun within one hour of spill discovery/occurrence; or, in the Government's judgment, spill cleanup is inadequate and the spill remains a threat to human health or the environment.

3.7.5 Mercury Materials

Immediately report to the Environmental Office and the Contracting Officer instances of breakage or mercury spillage. Clean mercury spill area to the satisfaction of the Contracting Officer.

Do not recycle a mercury spill cleanup; manage it as a hazardous waste for disposal.

3.7.6 Wastewater

3.7.6.1 Disposal of Wastewater

Disposal of wastewater must be as specified below.

3.7.6.1.1 Treatment

Do not allow wastewater from construction activities, such as onsite material processing, concrete curing, foundation and concrete clean-up, water used in concrete trucks, and forms to enter water ways or to be discharged prior to being treated to remove pollutants. Dispose of the construction- related waste water off-Government property in accordance with 40 CFR 403, state, regional, and local laws and regulations.

3.7.6.1.2 Surface Discharge

For discharge of ground water, Surface discharge in accordance with federal, state, and local laws and regulations.

3.7.6.1.3 Land Application

Water generated from the flushing of lines after hydrostatic testing must be land- applied in accordance with federal, state, and local laws and regulations for land application.

3.8 HAZARDOUS MATERIAL MANAGEMENT

Include hazardous material control procedures in the Safety Plan, in accordance with Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS. Address procedures and proper handling of hazardous materials, including the appropriate transportation requirements. Do not bring hazardous material onto Government property that does not directly relate to requirements for the performance of this contract. Submit an SDS and estimated quantities to be used for each hazardous material to the Contracting Officer prior to bringing the material on the installation.

Typical materials requiring SDS and quantity reporting include, but are not limited to, oil and latex based painting and caulking products, solvents, adhesives, aerosol, and petroleum products. Use hazardous materials in a manner that minimizes the amount of hazardous waste generated. Containers of hazardous materials must have National Fire Protection Association labels or their equivalent. Certify that hazardous materials removed from the site are hazardous materials and do not meet the definition of hazardous waste, in accordance with 40 CFR 261 and state and installation requirements.

3.8.1 Contractor Hazardous Material Inventory Log

Submit the "Contractor Hazardous Material Inventory Log"(found at: https://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphics-tables), which provides information required by (EPCRA Sections 312 and 313) along with corresponding SDS, to the Contracting Officer at the start and at the end of construction (30 days from final acceptance), and update no later than January 31 of each calendar year during the life of the contract. Keep copies of the SDSs for hazardous materials onsite. At the end of the project, provide the Contracting Officer with copies of the SDSs, and the maximum quantity of each material that was present at the site at any one time, the dates the material was present, the amount of each material that was used during the project, and how the material was used.

The Contracting Officer may request documentation for any spills or releases, environmental reports, or off-site transfers.

3.9 PREVIOUSLY USED EQUIPMENT

Clean previously used construction equipment prior to bringing it onto the project site. Equipment must be free from soil residuals, egg deposits from plant pests, noxious weeds, and plant seeds. Consult with the U.S. Department of Agriculture jurisdictional office for additional cleaning requirements.

3.10 CONTROL AND MANAGEMENT OF ASBESTOS-CONTAINING MATERIAL (ACM)

Manage and dispose of asbestos- containing waste in accordance with all applicable federal, state, and local (or Host Nation) requirements. Manifest asbestos-containing waste and provide the manifest to the Contracting Officer. Notifications to the regulatory authorities and Installation Air Program Manager are required before starting any asbestos work.

3.11 CONTROL AND MANAGEMENT OF LEAD-BASED PAINT (LBP)

Manage and dispose of lead-contaminated waste in accordance with 40 CFR 745. Manifest any lead-contaminated waste and provide the manifest to the Contracting Officer.

3.12 CONTROL AND MANAGEMENT OF POLYCHLORINATED BIPHENYLS (PCBs)

Manage and dispose of PCB-contaminated waste in accordance with 40 CFR 761.

3.13 MILITARY MUNITIONS

In the event military munitions, as defined in 40 CFR 260, are discovered or uncovered, immediately stop work in that area and immediately inform

the Contracting Officer.

3.14 PETROLEUM, OIL, LUBRICANT (POL) STORAGE AND FUELING

POL products include flammable or combustible liquids, such as gasoline, diesel, lubricating oil, used engine oil, hydraulic oil, mineral oil, and cooking oil. Store POL products and fuel equipment and motor vehicles in a manner that affords the maximum protection against spills into the environment. Manage and store POL products in accordance with EPA 40 CFR 112, and other federal, state, regional, and local laws and regulations. Use secondary containments, dikes, curbs, and other barriers, to prevent POL products from spilling and entering the ground, storm or sewer drains, stormwater ditches or canals, or navigable waters of the United States. Describe in the EPP (see paragraph ENVIRONMENTAL PROTECTION PLAN) how POL tanks and containers must be stored, managed, and inspected and what protections must be provided. Storage of oil, including fuel, on the project site is not allowed. Fuel must be brought to the project site each day that work is performed.

3.14.1 Used Oil Management

Manage used oil generated on site in accordance with 40 CFR 279. Determine if any used oil generated while onsite exhibits a characteristic of hazardous waste. Used oil containing 1,000 parts per million of solvents is considered a hazardous waste and disposed of at the Contractor's expense. Used oil mixed with a hazardous waste is also considered a hazardous waste. Dispose in accordance with paragraph HAZARDOUS WASTE DISPOSAL.

3.14.2 Oil Storage Including Fuel Tanks

Provide secondary containment and overfill protection for oil storage tanks. A berm used to provide secondary containment must be of sufficient size and strength to contain the contents of the tanks plus 5 inches freeboard for precipitation. Construct the berm to be impervious to oil for 72 hours that no discharge will permeate, drain, infiltrate, or otherwise escape before cleanup occurs. Use drip pans during oil transfer operations; adequate absorbent material must be onsite to clean up any spills and prevent releases to the environment. Cover tanks and drip pans during inclement weather. Provide procedures and equipment to prevent overfilling of tanks. If tanks and containers with an aggregate aboveground capacity greater than 1320 gallons will be used onsite (only containers with a capacity of 55 gallons or greater are counted), provide and implement a Spill Prevention Control and Countermeasure (SPCC) plan meeting the requirements of 40 CFR 112. Do not bring underground storage tanks to the installation for Contractor use during a project. Submit the SPCC plan to the Contracting Officer for approval.

Monitor and remove any rainwater that accumulates in open containment dikes or berms. Inspect the accumulated rainwater prior to draining from a containment dike to the environment, to determine there is no oil sheen present.

3.15 INADVERTENT DISCOVERY OF PETROLEUM-CONTAMINATED SOIL OR HAZARDOUS WASTES

If petroleum-contaminated soil, or suspected hazardous waste is found during construction that was not identified in the Contract documents, immediately notify the Contracting Officer. Do not disturb this material

until authorized by the Contracting Officer.

3.16 CHLORDANE

Evaluate excess soils and concrete foundation debris generated during the demolition of housing units or other wooden structures for the presence of chlordane or other pesticides prior to reuse or final disposal.

3.17 SOUND INTRUSION

Make the maximum use of low-noise emission products, as certified by the EPA. Blasting or use of explosives are not permitted.

Keep construction activities under surveillance and control to minimize environment damage by noise. Comply with the provisions of the State of North Carolina rules.

Keep construction activities under surveillance and control to minimize environment damage by noise. Comply with the provisions of the State of Illinois rules given in 35 IAC 900-901.

3.18 POST CONSTRUCTION CLEANUP

Clean up areas used for construction in accordance with Contract Clause: "Cleaning Up". Unless otherwise instructed in writing by the Contracting Officer, remove traces of temporary construction facilities such as haul roads, work area, structures, foundations of temporary structures, stockpiles of excess or waste materials, and other vestiges of construction prior to final acceptance of the work. Grade parking area and similar temporarily used areas to conform with surrounding contours.

-- End of Section --

SECTION 01 58 00

PROJECT IDENTIFICATION
08/19, CHG 5: 08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)

AWPA C1	(2003) All Timber Products - Preservative Treatment by Pressure Processes
AWPA C2	(2003) Lumber, Timber, Bridge Ties and Mine Ties - Preservative Treatment by Pressure Processes

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Preliminary Drawing Indicating Layout And Text Content; G

SD-04 Samples

Facility Recognition Plaque; G

1.3 QUALITY CONTROL

1.3.1 Facility Recognition Plaque

Submit full size drawing of Facility Recognition Plaque for approval. Confirm the content (message), location and mounting with Contracting Officer prior to fabrication. The final names on the plaque will be determined at the end of the project duration to assure that current participants can be identified and recognized on the plaque.

1.4 PROJECT IDENTIFICATION SIGN

Prior to initiating any work on site, provide one project identification sign at the location indicated . Construct the sign in accordance with project sign detail, which can be downloaded at: http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphics-tables. Maintain sign throughout the life of the project. Upon completion of the project, remove the sign from the site. The Government will temporarily supply a copy of the rendering to use in the production of the final signboard artwork.

1.4.1 Project Identification Signboard

Provide a project identification signboard in accordance with attached Plates 2MC, 3, 4, and 5. Provide a preliminary drawing indicating layout and text content. Erect a signboard at a conspicuous location on the job site where directed by the Contracting Officer.

a. The field of the sign consists of a 4 by 8 foot sheet of grade B-B medium density overlaid exterior plywood.

b. Lumber is B or better Southern pine, pressure-preservative treated in accordance with AWPA C1 and AWPA C2. Nails are aluminum or galvanized steel.

c. Give one coat of exterior alkyd primer and two coats of exterior alkyd enamel paint to the entire signboard and supports. Perform the lettering and sign work by a skilled sign painter using paint known in the trade as bulletin colors. The colors, lettering sizes, and lettering styles are as indicated. Where preservative-treated lumber is required, utilize only cured pressure-treated wood which has had the chemicals leached from the surface of the wood prior to painting.

d. Use spray applied automotive quality high gloss acrylic white enamel paint as background for the NAVFAC logo. NAVFAC logo is an applied 2 mil film sticker/decal with either transparent or white background or paint the logo by stencil onto the sign. The weather resistant sticker/decal film is rated for a minimum of 2-year exterior vertical exposure. Mount the self-adhering sticker to the sign with pressure sensitive, permanent acrylic adhesive. Shop cut sticker/decal to rectangular shape and provide pull-off backing sheet on adhesive side of design sticker for shipping.

e. Sign paint colors (manufacturer's numbers/types listed below for color identification only)

(1) Blue = To match dark blue color in the NAVFAC logo.

(2) White = To match Brilliant White color in the NAVFAC logo.

f. NAVFAC logo must retain proportions and design integrity. NAVFAC logos in electronic format may be obtained from the WBDG at the following link:
http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphics-tables.
Use the following to choose color values for the paint to be used:

(1) Dark Blue = equivalent to CMYK values 100, 72, 0, 8.

(2) Light Blue = equivalent to CMYK values 69, 34, 0, 0.

(3) Cyan = equivalent to CMYK values 100, 9, 0, 6.

(4) Yellow = equivalent to CMYK values 0.9,94, 0.

g. Final signboard artwork (rendering) may be either mounted under plexiglass as indicated in attached Plates 2 and 5, or may be electrostatically printed on 4 mil self-adhering, weather resistant, glossy vinyl film and mounted to signboard. Provide film that is capable of full color reproduction of the building rendering and cover

it with an ultra-violet protection film. Laminate the 2 mil satin gloss clear protection film to the white 4 mil vinyl image film. Utilize pressure sensitive "controltac" adhesive to attach rendering to signboard and smooth out surface with hand pressure tools in accordance with manufacturer's recommendations. Shop cut sticker to size required and provide pull-off backing sheet on adhesive side of film for shipping. Provide the rendering on film that is rated for a minimum of 2-years exterior vertical exposure.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK



NOTES:

1. PAINT ALL OTHER WOOD SURFACES WITH ONE COAT EXT. PRIMER AND TWO COATS GLOSS WHITE ENAMEL.
2. ALL LETTERING SHALL BE EVENLY SPACED.
3. LETTER STYLE, 'ARIAL', COLOR 'DARK BLUE'. TYPICAL FOR ALL LETTERING.

*–ABBREVIATE STATE
**–CONFIRM USE WITH CONTRACTING OFFICER
***–VERIFY NAME WITH CONTRACTING OFFICER.

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND PROJECT IDENTIFICATION SIGNBOARD FOR MARINE CORPS PROJECTS

SCALE: 3/4" = 1'-0"

PLATE 2MC

This page is intentionally left blank.



A
1,2 | 3

TOP VIEW

SCALE: 1/2" = 1'-0"

NOTES:
1. POSTS AND BRACES SHALL BE PRESSURE TREATED.
2. ALL FASTENERS SHALL BE ZINC COATED.
3. BRACING IS REQUIRED IN ALL SOIL CONDITIONS AND HIGH WIND ENVIRONMENTS.



B
1,2 | 3

SIDE VIEW

SCALE: 1/2" = 1'-0"

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
PROJECT IDENTIFICATION SIGNBOARD
SUPPORT DETAILS

This page is intentionally left blank.



1 1,2 4 PLAN SECTION

SCALE: 3" = 1'-0"



2 1,2 4 SECTION AT TOP

SCALE: 3" = 1'-0"



3 2 4 ISO VIEW

SCALE: NONE

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND PROJECT IDENTIFICATION SIGNBOARD SECTIONS

This page is intentionally left blank.



3 / 2 5

SECTION AT RENDERING FRAME

SCALE: 6" = 1'-0"

NAVAL FACILITIES ENGINEERING SYSTEMS COMMAND
PROJECT IDENTIFICATION SIGNBOARD SECTION

This page is intentionally left blank.

SECTION 01 74 19

CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL
02/19, CHG 3: 11/21

PART 1 GENERAL

1.1 DEFINITIONS

1.1.1 Co-mingle

The practice of placing unrelated materials together in a single container, usually for benefits of convenience and speed.

1.1.2 Construction Waste

Waste generated by construction activities, such as scrap materials, damaged or spoiled materials, temporary and expendable construction materials, and other waste generated by the workforce during construction activities.

1.1.3 Demolition Debris/Waste

Waste generated from demolition activities, including minor incidental demolition waste materials generated as a result of Intentional dismantling of all or portions of a building, to include clearing of building contents that have been destroyed or damaged.

1.1.4 Disposal

Depositing waste in a solid waste disposal facility, usually a managed landfill or incinerator, regulated in the US under the Resource Conservation and Recovery Act (RCRA).

1.1.5 Diversion

The practice of diverting waste from disposal in a landfill or incinerator, by means of eliminating or minimizing waste, or reuse of materials.

1.1.6 Final Construction Waste Diversion Report

A written assertion by a material recovery facility operator identifying constituent materials diverted from disposal, usually including summary tabulations of materials, weight in short-ton.

1.1.7 Recycling

The series of activities, including collection, separation, and processing, by which products or other materials are diverted from the solid waste stream for use in the form of raw materials in the manufacture of new products sold or distributed in commerce, or the reuse of such materials as substitutes for goods made of virgin materials, other than fuel.

1.1.8 Reuse

The use of a product or materials again for the same purpose, in its

original form or with little enhancement or change.

1.1.9 Salvage

Usable, salable items derived from buildings undergoing demolition or deconstruction, parts from vehicles, machinery, other equipment, or other components.

1.1.10 Source Separation

The practice of administering and implementing a management strategy to identify and segregate unrelated waste at the first opportunity.

1.2 CONSTRUCTION WASTE (INCLUDES DEMOLITION DEBRIS/WASTE)

Divert a minimum of 60 percent by weight of the project construction waste and demolition debris/waste from the landfill or incinerator. Follow applicable industry standards in the management of waste. Apply sound environmental principles in the management of waste. (1) Practice efficient waste management when sizing, cutting, and installing products and materials and (2) use all reasonable means to divert construction waste and demolition debris/waste from landfills and incinerators and to facilitate the recycling or reuse of excess construction materials.

1.3 CONSTRUCTION WASTE MANAGEMENT

Implement a Construction Waste Management Program for the project. Take a pro-active, responsible role in the management of construction construction waste, recycling process, disposal of demolition debris/waste, and require all subcontractors, vendors, and suppliers to participate in the Construction Waste Management Program. Establish a process for clear tracking, and documentation of construction waste and demolition debris/waste.

1.3.1 Implementation of Construction Waste Management Program

Develop and document how the Construction Waste Management Program will be implemented in a Construction Waste Management Plan. Submit a Construction Waste Management Plan to the Contracting Officer for approval. Construction waste and demolition debris/waste materials include un-used construction materials not incorporated in the final work, as well as demolition debris/waste materials from demolition activities or deconstruction activities. In the management of waste, consider the availability of viable markets, the condition of materials, the ability to provide material in suitable condition and in a quantity acceptable to available markets, and time constraints imposed by internal project completion mandates.

1.3.2 Oversight

The Environmental Manager, as specified in Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS, is responsible for overseeing and documenting results from executing the Construction Waste Management Plan for the project.

1.3.3 Special Programs

Implement special programs involving rebates or similar incentives related to recycling of construction waste and demolition debris/waste materials.

Retain revenue or savings from salvaged or recycling, unless otherwise directed. Ensure firms and facilities used for recycling, reuse, and disposal are permitted for the intended use to the extent required by federal, state, and local regulations.

1.3.4 Special Instructions

Provide on-site instruction of appropriate separation, handling, recycling, salvage, reuse, and return methods to be used by all parties at the appropriate stages of the projects. Designation of single source separating or commingling will be clearly marked on the containers.

1.3.5 Waste Streams

Delineate waste streams and characterization, including estimated material types and quantities of waste, in the Construction Waste Management Plan. Manage all waste streams associated with the project. Typical waste streams are listed below. Include additional waste steams not listed:

a. Land Clearing Debris

b. Asphalt

c. Masonry and CMU

d. Concrete

e. Metals (Includes, but is not limited to, banding, stud trim, ductwork, piping, rebar, roofing, other trim, steel, iron, galvanized, stainless steel, aluminum, copper, zinc, bronze.)

f. Wood (nails and staples allowed)

g. Glass

h. Paper

i. Plastics (PET, HDPE,PVC,LDPE,PP,PS, Other)

j. Gypsum

k. Non-hazardous paint and paint cans

l. Carpet

m. Ceiling Tiles

n. Insulation

o. Beverage Containers

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Construction Waste Management Plan; G

SD-11 Closeout Submittals

Final Construction Waste Diversion Report; S

1.5 MEETINGS

Conduct Construction Waste Management meetings. After award of the Contract and prior to commencement of work, schedule and conduct a meeting with the Contracting Officer to discuss the proposed Construction Waste Management Plan and to develop a mutual understanding relative to the management of the Construction Waste Management Program and how waste diversion requirements will be met.

The requirements of this meeting may be fulfilled during the coordination and mutual Understanding meeting outlined in Section 01 45 00 QUALITY CONTROL. At a minimum, discuss and document waste management goals at following meetings:

a. Preconstruction meeting.

b. Regular site meetings.

c. Work safety meeting (if applicable).

1.6 CONSTRUCTION WASTE MANAGEMENT PLAN

Submit Construction Waste Management Plan within 15 days after notice to proceed. Revise and resubmit Construction Waste Management Plan as necessary, in order for construction to begin.. Execute demolition or deconstruction activities in accordance with Section 02 41 00 DEMOLITION . Manage demolition debris/waste or deconstruction materials in accordance with the approved construction waste management plan.

An approved Construction Waste Management Plan will not relieve the Contractor of responsibility for compliance with applicable environmental regulations or meeting project cumulative waste diversion requirement. Ensure all subcontractors receive a copy of the approved Construction Waste Management Plan. The plan demonstrates how to meet the project waste diversion requirement. Also, include the following in the plan:

a. Identify the names of individuals responsible for waste management and waste management tracking, along with roles and responsibilities on the project..

b. Actions that will be taken to reduce solid waste generation, including coordination with subcontractors to ensure awareness and participation.

c. Description of the regular meetings to be held to address waste management.

d. Description of the specific approaches to be used in recycling/reuse of the various materials generated, including the areas on site and equipment to be used for processing, sorting, and temporary storage of

materials.

e. Name of landfill and incinerator to be used.

f. Identification of local and regional re-use programs, including non-profit organizations such as schools, local housing agencies, and organization that accept used materials such as material exchange networks and resale stores. Include the name, location, phone number for each re-use facility identified, and provide a copy of the permit or license for each facility.

g. List of specific materials, by type and quantity, that will be salvaged for resale, salvaged and reused on the current project, salvaged and stored for reuse on a future project, or recycled. Identify the recycling facilities by name, address, and phone number.

h. Identification of materials that cannot be recycled or reused with an explanation or justification, to be approved by the Contracting Officer.

i. Description of the means by which materials identified in item (g) above will be protected from contamination.

j. Description of the means of transportation of the recyclable materials (whether materials will be site-separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site).

k. Copy of training plan for subcontractors and other services to prevent contamination by co-mingling materials identified for diversion and waste materials.

Distribute copies of the waste management plan to each subcontractor, Environmental Manager, and the Contracting Officer.

1.7 RECORDS (DOCUMENTATION)

1.7.1 General

Maintain records to document the types and quantities of waste generated and diverted though re-use, recycling and sale to third parties; through disposal to a landfill or incinerator facility. Provide explanations for materials not recycled, reused or sold. Collect and retain manifests, weight tickets, sales receipts, and invoices specifically identifying diverted project waste materials or disposed materials.

1.7.2 Accumulated

Maintain a running record of materials generated and diverted from landfill disposal, including accumulated diversion rates for the project. Make records available to the Contracting Officer during construction or incidental demolition activities. Provide a copy of the diversion records to the Contracting Officer upon completion of the construction, incidental demolitions or minor deconstruction activities.

1.8 FINAL CONSTRUCTION WASTE DIVERSION REPORT

A Final Construction Waste Diversion Report is required at the end of the

project. Provide Final Construction Waste Diversion Report 60 days prior to the Beneficial Occupancy Date (BOD).

1.9 COLLECTION

Collect, store, protect, and handle reusable and recyclable materials at the site in a manner which prevents contamination, and provides protection from the elements to preserve their usefulness and monetary value. Provide receptacles and storage areas designated specifically for recyclable and reusable materials and label them clearly and appropriately to prevent contamination from other waste materials. Keep receptacles or storage areas neat and clean.

Train subcontractors and other service providers to either separate waste streams or use the co-mingling method as described in the Construction Waste Management Plan. Handle hazardous waste and hazardous materials in accordance with applicable regulations and coordinate with Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS. Separate materials by one of the following methods described herein:

1.9.1 Source Separation Method

Separate waste products and materials that are recyclable from trash and sort as described below into appropriately marked separate containers and then transport to the respective recycling facility for further processing. Deliver materials in accordance with recycling or reuse facility requirements (e.g., free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process). Separate materials into the category types as defined in the Construction Waste Management Plan.

1.9.2 Co-Mingled Method

Place waste products and recyclable materials into a single container and then transport to an authorized recycling facility, which meets all applicable requirements to accept and dispose of recyclable materials in accordance with all applicable local, state and federal regulations. The Co-mingled materials must be sorted and processed in accordance with the approved Construction Waste Management Plan.

1.9.3 Other Methods

Other methods proposed by the Contractor may be used when approved by the Contracting Officer.

1.10 DISPOSAL

Control accumulation of waste materials and trash. Recycle or dispose of collected materials off-site at intervals approved by the Contracting Officer and in compliance with waste management procedures as described in the waste management plan. Except as otherwise specified in other sections of the specifications, dispose of in accordance with the following:

1.10.1 Reuse

Give first consideration to reusing construction and demolition materials as a disposition strategy. Recover for reuse materials, products, and components as described in the approved Construction Waste Management

Plan. Coordinate with the Contracting Officer to identify onsite reuse opportunities or material sales or donation available through Government resale or donation programs. Consider the use of surplus industrial supply broker services, who match entities with reusable or repurpose industrial materials with entities with need of such materials.

1.10.2 Recycle

Recycle non-hazardous construction and demolition/debris materials that are not suitable for reuse. Track rejection of contaminated recyclable materials by the recycling facility. Rejected recyclables materials will not be counted as a percentage of diversion calculation. Recycle all fluorescent lamps, HID lamps, mercury (Hg) -containing thermostats and ampoules, and PCBs-containing ballasts and electrical components as directed by the Contracting Officer. Do not crush lamps on site as this creates a hazardous waste stream with additional handling requirements.

1.10.2.1 Special Recycling Provision

Separate metal items derived from deconstruction activities. Items include structural steel sections, metal roofing, miscellaneous metals, suspended acoustical grid, mechanical equipment and fixtures, piping, ductwork, electrical equipment and fixtures, wiring, conduit, metal furniture, metal scrap and similar metals encountered.

Deliver items to the Treatment and Processing Facility located at the Piney Green Road lot. Contact the Qualified Recycling Program Manager FSC/Recycling, GF Public Works Division, Building 982, Piney Green Road, Camp Lejeune at (910) 451-2037 for applicable procedures and protocols.

1.10.3 Compost

Consider composting on site if a reasonable amount of compostable materials will be available and a utilization of compostable material can be determined and appropriately planned for. Compostable materials include plant materials, sawdust and certain food scraps. Composting as a strategy must be explicitly addressed in the Construction Waste Management Plan submitted for approval to ensure it is feasible.

1.10.4 Waste

Dispose by landfill or incineration only those waste materials with no practical use, economic benefit, or recycling opportunity.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

Not used. -- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 78 00

CLOSEOUT SUBMITTALS
04/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E1971	(2024) Standard Guide for Stewardship for the Cleaning of Commercial and Institutional Buildings

GREEN SEAL (GS)

GS-37	(2017) Cleaning Products for Industrial and Institutional Use

U.S. DEPARTMENT OF DEFENSE (DOD)

FC 1-300-09N	(2024) Navy and Marine Corps Design

1.2 DEFINITIONS

1.2.1 As-Built Drawings

As-built drawings are developed and maintained by the Contractor and depict actual conditions, including deviations from the Contract Documents. These deviations and additions may result from coordination required by, but not limited to: contract modifications; official responses to Contractor submitted Requests for Information; direction from the Contracting Officer; designs which are the responsibility of the Contractor, and differing site conditions. Maintain the as-builts throughout construction as red-lined hard copies on site. These files serve as the basis for the creation of the record drawings.

1.2.2 Record Drawings

The record drawings are the final compilation of actual conditions reflected in the as-built drawings.

1.2.3 Final Approved Shop Drawings

The final approved shop drawings are all approved submittals created during the execution of the project. All submittals, regardless of the approving authority, shall be submitted. Include the submittal cover sheet and all relevant attachments for all submittals. Each submittal shall be saved as a separate file or have its own unique folder if a submittal includes attachments of multiple files or file types. Include a PDF copy of the completed submittal register.

1.3 SOURCE DRAWING FILES

Request the full set of electronic drawings, in the source format, for Record Drawing preparation, after award and at least 30 days prior to required use.

1.3.1 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction data for the referenced project. Any other use or reuse shall be at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim and waives to the fullest extent permitted by law, any claim or cause of action of any nature against the Government, its agents or sub consultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic CAD drawing files are not construction documents. Differences may exist between the CAD files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic CAD files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished Source drawing files, the signed and sealed construction documents govern. The Contractor is responsible for determining if any conflict exists. Use of these Source Drawing files does not relieve the Contractor of duty to fully comply with the contract documents, including and without limitation, the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction data related to this contract, remove all previous indicia of ownership (seals, logos, signatures, initials and dates).

1.4 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Warranty Management Plan

Warranty Tags

Final Cleaning

Spare Parts Data

SD-08 Manufacturer's Instructions

Posted Instructions

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G

SD-11 Closeout Submittals

As-Built Drawings; G

Record Drawings; G

As-Built Record of Equipment and Materials

Final Approved Shop Drawings

Certification of EPA Designated Items; G

Certification Of USDA Designated Items; G

Interim DD FORM 1354; G

Equipment Inventory Update; G

As-Built Exterior Finish Material Schedule And Submittals; G

1.5 SPARE PARTS DATA

Submit two copies of the Spare Parts Data list.

a. Indicate manufacturer's name, part number, nomenclature, and stock level required for maintenance and repair. List those items that may be standard to the normal maintenance of the system.

1.6 WARRANTY MANAGEMENT

1.6.1 Warranty Management Plan

Develop a warranty management plan which contains information relevant to FAR 52.246-21 Warranty of Construction. At least 30 days before the planned pre-warranty conference, submit one set of the warranty management plan. Include within the warranty management plan all required actions and documents to assure that the Government receives all warranties to which it is entitled. The plan must be in narrative form and contain sufficient detail to render it suitable for use by future maintenance and repair personnel, whether tradesmen, or of engineering background, not necessarily familiar with this contract. The term "status" as indicated below must include due date and whether item has been submitted or was accomplished. Warranty information made available during the construction phase must be submitted to the Contracting Officer for approval prior to each monthly pay estimate.

Assemble approved information in a binder and turn over two (2) copies of the binder to the Government upon submittal of the initial Test & Balance (TAB) Report or no later than ninety (90) days prior to contract completion date (CCD), whichever is sooner. The contents of the binder will be verified onsite for accuracy and completeness of contents by a representative of MCBCL Public Works. Upon site approval of the binder, one copy will be distributed to the PWD representative and one copy will be stored in the O&M cabinet in the mechanical room.

The construction warranty period will begin on the date of project

acceptance and continue for the full product warranty period. A joint 4 month and 9 month warranty inspection will be conducted, measured from time of acceptance, by the Contractor, Contracting Officer and the Customer Representative. Include within the warranty management plan , but not limited to, the following:

a. Roles and responsibilities of all personnel associated with the warranty process, including points of contact and telephone numbers within the organizations of the Contractors, subcontractors, manufacturers or suppliers involved.

b. Furnish with each warranty the name, address, and telephone number of each of the guarantor's representatives nearest to the project location.

c. Listing and status of delivery of all Certificates of Warranty for extended warranty items, to include roofs, HVAC balancing, pumps, motors, transformers, and for all commissioned systems such as fire protection and alarm systems, sprinkler systems, lightning protection systems, etc.

d. As-Built Record of Equipment and Materials list for each warranted equipment, item, feature of construction or system indicating:

(1) Name of item.
(2) Model and serial numbers.
(3) Location where installed.
(4) Name and phone numbers of manufacturers or suppliers.
(5) Names, addresses and telephone numbers of sources of spare parts.
(6) Warranties and terms of warranty. Include one-year overall warranty of construction, including the starting date of warranty of construction. Items which have extended warranties must be indicated with separate warranty expiration dates.
(7) Cross-reference to warranty certificates as applicable.
(8) Starting point and duration of warranty period.
(9) Summary of maintenance procedures required to continue the warranty in force.
(10) Cross-reference to specific pertinent Operation and Maintenance manuals.
(11) Organization, names and phone numbers of persons to call for warranty service.
(12) Typical response time and repair time expected for various warranted equipment.

e. The plans for attendance at the 4 and 9 month post-construction warranty inspections conducted by the Government.

f. Procedure and status of tagging of all equipment covered by extended warranties.

g. Copies of instructions to be posted near selected pieces of equipment where operation is critical for warranty and/or safety reasons.

1.6.2 Performance Bond

The Performance Bond must remain effective throughout the construction period .

a. In the event the Contractor fails to commence and diligently pursue

any construction warranty work required, the Contracting Officer will have the work performed by others, and after completion of the work, will charge the remaining construction warranty funds of expenses incurred by the Government while performing the work, including, but not limited to administrative expenses.

b. In the event sufficient funds are not available to cover the construction warranty work performed by the Government at the Contractor's expense, the Contracting Officer will have the right to recoup expenses from the bonding company.

c. Following oral or written notification of required construction warranty repair work, respond in a timely manner. Written verification will follow oral instructions. Failure to respond will be cause for the Contracting Officer to proceed against the Contractor.

1.6.3 Pre-Warranty Conference

Prior to contract completion, and at a time designated by the Contracting Officer, meet with the Contracting Officer to develop a mutual understanding with respect to the requirements of this section. Communication procedures for Contractor notification of construction warranty defects, priorities with respect to the type of defect, reasonable time required for Contractor response, and other details deemed necessary by the Contracting Officer for the execution of the construction warranty will be established/reviewed at this meeting. In connection with these requirements and at the time of the Contractor's quality control completion inspection, furnish the name, telephone number and address of a licensed and bonded company which is authorized to initiate and pursue construction warranty work action on behalf of the Contractor. This point of contact will be located within the local service area of the warranted construction, be continuously available, and be responsive to Government inquiry on warranty work action and status. This requirement does not relieve the Contractor of any of its responsibilities in connection with other portions of this provision.

1.6.4 Warranty Tags

At the time of installation, tag each warranted item with a durable, oil and water resistant tag approved by the Contracting Officer. Attach each tag with a copper wire and spray with a silicone waterproof coating. Also, submit two record copies of the warranty tags showing the layout and design. The date of acceptance and the QC signature must remain blank until the project is accepted for beneficial occupancy. Show the following information on the tag.

Type of product/material	
Model number	
Serial number	
Contract number	

Warranty period from/to	
Inspector's signature	
Construction Contractor	
Address	
Telephone number	
Warranty contact	
Address	
Telephone number	
Warranty response time priority code	
WARNING - PROJECT PERSONNEL TO PERFORM ONLY OPERATIONAL MAINTENANCE DURING THE WARRANTY PERIOD.	

1.7 EXTERIOR FINISHES

Submit the As-Built Exterior Finish Material Schedule and Submittals Prepare and provide the final approved exterior finish material submittals created during the execution of the project. All submittals, regardless of the approving authority, shall be submitted. Include a finish schedule documenting all the exterior finish materials that were installed on the project, the submittals/shop drawings themselves, and all relevent attachements for the submittals. This should be in a seperate document in PDF format included on the CD or DVD with the Record Drawings 30 days after BOD. Provide the following information in the finish schedule:

(1) Contract Number
(2) Project Number
(3) Building Number
(4) Building Name
(5) District
(6) Submittal Number
(7) Specification Division
(8) Description
(9) Product
(10) Manufacturer
(11) Size
(12) Color
(13) Other
(14) Location
(15) Comments

PART 2 PRODUCTS

2.1 CERTIFICATION OF EPA DESIGNATED ITEMS

Submit the Certification of EPA Designated Items as required by FAR 52.223-9 Estimate of Percentage of Recovered Material Content for EPA Designated Items and FAR 52-223-17 Affirmative Procurement of EPA designated items in Service and Construction Contracts.. Include on the certification form the following information: project name, project number, Contractor name, license number, Contractor address, and certification. The certification will read as follows and be signed and dated by the Contractor. "I hereby certify the information provided herein is accurate and that the requisition/procurement of all materials listed on this form comply with current EPA standards for recycled/recovered materials content. The following exemptions may apply to the non-procurement of recycled/recovered content materials:

1) The product does not meet appropriate performance standards;
2) The product is not available within a reasonable time frame;
3) The product is not available competitively (from two or more sources);
4) The product is only available at an unreasonable price (compared with a comparable non-recycled content product)."

2.2 CERTIFICATION OF USDA DESIGNATED ITEMS

Submit the Certification of USDA Designated Items as required by FAR 52-223-1 Bio-based Product Certifications and FAR 52.223-2 Affirmative Procurement of Biobased Products Under Service and Construction Contracts. Include on the certification form the following information: project name, project number, Contractor name, license number, Contractor address, and certification. The certification will read as follows and be signed and dated by the Contractor. "I hereby certify the information provided herein is accurate and that the requisition/procurement of all materials listed on this form comply with current USDA standards for biobased materials content. The following exemptions may apply to the non-procurement of biobased content materials:

1) The product does not meet appropriate performance standards;
2) The product is not available within a reasonable time frame;
3) The product is not available competitively (from two or more sources);
4) The product is only available at an unreasonable price (compared with a comparable bio-based content product)."

PART 3 EXECUTION

3.1 EQUIPMENT INVENTORY UPDATE

Submit information for each piece of equipment removed and supplied for use of Camp Lejeune to update the Maximo equipment inventory. For the purposes of this paragraph, inventoried equipment is defined as equipment listed on the Maximo Equipment Inventory Update form.

3.1.1 Requirements

The contractor shall prepare and submit one Maximo Equipment Inventory

Update form for each individual item of inventoried equipment that is demolished, removed, replaced, or installed. (ex: three new condensing units would require the submission of three Equipment Inventory Update forms. The replacement of two existing air handling units with two new air handling units would require the submission of two Equipment Inventory Update forms). The contractor shall prepare and submit a VAV/TAB Room Number List for each VAV/Tab model installed in a single building. Only one Maximo Equipment Inventory Update form is required for each model of VAV or TAB in a single building.

3.1.1.1 Demolition of all equipment in a structure or facility

When all the inventoried equipment in a building or structure is demolished or removed, and not replaced, an Equipment Inventory Update form is not required.

3.1.1.2 Standards

The contractor shall provide accurate, complete, and legible information on all required forms. All required forms shall be completed and delivered to the Contracting Officer on or before the Beneficial Occupancy Date. All information on Equipment Inventory Update forms shall be obtained by visual inspection of equipment data plate(s).

3.1.1.3 Form Preparation

Each required Maximo Equipment Inventory Update form shall contain the following information:

(1) The name and telephone number of an individual who can be contacted for clarification or additional information pertaining to the data on the form.

(2) The date of data collection

(3) The building or structure identification number and the specific location of the equipment within the structure (ex: 3d deck mech room)

(4) A check adjacent to the description of the new or replacement item, and a check adjacent to the supplemental description if applicable (ex: circulating pump and HVAC or steam)

(5) The Maximo number or serial number of the demolished or removed item, if applicable

(6) All applicable data from the equipment data plate

Each Room Number List form shall contain the following information:

(1) The name and telephone number of the individual providing the information

(2) The date the form was completed

(3) The building or structure identification number

(4) A check in the box adjacent to each applicable room number

MAXIMO EQUIPMENT INVENTORY UPDATE

Employee: _____ Phone: _____ Date: ____/____/____

Bldg: _____ Specific Location: _____

__ AC, Computer Room
__ AC, Package
__ AC, Package Terminal
__ Assembly, Trap line
__ Backflow Preventer
__ Boiler
__ Chiller, Air Cooled Recip
__ Chiller, Air Cooled Screw
__ Chiller, Air Cooled Scroll
__ Chiller, Water Cooled Recip
__ Chiller, Water Cooled Screw
__ Compressor, Control Air
__ Compressor, Industrial Air
__ Dryer, Refrigerated Air
__ Exchanger, Heat
__ Evaporator, Freezer
__ Evaporator, Refrigerator
__ Fan, Exhaust
__ Generator
__ Heater, Space
__ Heater, Unit
__ Heat Pump, Geo-Thermal
__ Heat Pump, Indoor Unit
__ Heat Pump, Outdoor Unit
__ Heat Pump, Package
__ Heat Pump, Package Terminal
__ Pump, Circulating, Chilled Water
__ Pump, Circulating, Domestic Water
__ Pump, Circulating, Dual Temp Water
__ Pump, Circulating, Heating Water
__ Pump, Condensate
__ Pump, Sump
__ Regulator, Temperature
__ Tank, Hot Water Storage
__ Tower, Cooling
__ Unit, Air Handling
__ Unit, AC Condensing
__ Unit, Freezer Condensing
__ Unit, Refrigerator Condensing
__ Unit, Fan Coil
__ Unit, TAB (Attach Room No. List)
__ Unit, VAV (Attach Room No. List)
__ Valve, Pressure Reducing
__ Valve, Steam Pilot
__ Water Heater

Demolished/Removed Equipment

Maximo no: _____ or Ser no: _____

New Equipment

Manufacturer: _____

Model no: _____

Ser no: _____

Type: __Elec __Oil __LP Gas __Nat Gas __Steam __Water __Air

Motor Data: HP____ Volts____ Phase____ RLA_____ RPM____ Frame____

Tons____ No. of Motors____ no. of Belts____ Belt size(s)____ CFM____

KW____ Refrig type_____ Refrig Qty_____ Filter Size(s)_____

3.2 AS-BUILT DRAWINGS

Provide and maintain two black line print copies of the PDF contract drawings for As-Built Drawings. At a minimum of 30 days prior to Beneficial Occupancy Date (BOD), certify both sets of as-built drawings as correct, sign, and submit the As-Built Drawings for Contracting Officer approval.

3.2.1 Markup Guidelines

Make comments and markup the drawings complete without reference to letters, memos, or materials that are not part of the As-Built drawing. Show what was changed, how it was changed, where item(s) were relocated and change related details. These working as-built markup prints must be neat, legible and accurate as follows:

a. Use base colors of red, green, and blue. Color code for changes as follows:

   (1) Special (Blue) - Items requiring special information, coordination, or special detailing or detailing notes.

   (2) Deletions (Red) - Over-strike deleted graphic items (lines), lettering in notes and leaders.

   (3) Additions (Green) - Added items, lettering in notes and leaders.

b. Provide a legend if colors other than the "base" colors of red, green, and blue are used.

c. Add and denote any additional equipment or material facilities, service lines, incorporated under As-Built Revisions if not already shown in legend.

d. Use frequent written explanations on markup drawings to describe changes. Do not totally rely on graphic means to convey the revision.

e. Use legible lettering and precise and clear digital values when marking prints. Clarify ambiguities concerning the nature and application of change involved.

f. Wherever a revision is made, also make changes to related section views, details, legend, profiles, plans and elevation views, schedules, notes and call out designations, and mark accordingly to avoid conflicting data on all other sheets.

g. For deletions, cross out all features, data and captions that relate to that revision.

h. For changes on small-scale drawings and in restricted areas, provide large-scale inserts, with leaders to the applicable location.

i. Indicate one of the following when attaching a print or sketch to a markup print:

   1) Add an entire drawing to contract drawings

   2) Change the contract drawing to show

3) Provided for reference only to further detail the initial design.

j. Incorporate all shop and fabrication drawings into the markup drawings.

3.2.2 As-Built Drawings Content

Show on the as-built drawings, but not limited to, the following information:

a. The actual location, kinds and sizes of all sub-surface utility lines. In order that the location of these lines and appurtenances may be determined in the event the surface openings or indicators become covered over or obscured, show by offset dimensions to two permanently fixed surface features the end of each run including each change in direction on the record drawings. Locate valves, splice boxes and similar appurtenances by dimensioning along the utility run from a reference point. Also record the average depth below the surface of each run.

b. The location and dimensions of any changes within the building structure.

c. Layout and schematic drawings of electrical circuits and piping.

d. Correct grade, elevations, cross section, or alignment of roads, earthwork, structures or utilities if any changes were made from contract plans.

e. Changes in details of design or additional information obtained from working drawings specified to be prepared or furnished by the Contractor; including but not limited to shop drawings, fabrication, erection, installation plans and placing details, pipe sizes, insulation material, dimensions of equipment, and foundations.

f. The topography, invert elevations and grades of drainage installed or affected as part of the project construction.

g. Changes or Revisions which result from the final inspection.

h. Where contract drawings or specifications present options, show only the option selected for construction on the working as-built markup drawings.

i. If borrow material for this project is from sources on Government property, or if Government property is used as a spoil area, furnish a contour map of the final borrow pit/spoil area elevations.

j. Systems designed or enhanced by the Contractor, such as HVAC controls, fire alarm, fire sprinkler, and irrigation systems.

k. Changes in location of equipment and architectural features.

j. Modifications (include within change order price the cost to change working as-built markup drawings to reflect modifications) and compliance with FC 1-300-09N procedures.

l. Actual location of anchors, construction and control joints, etc., in concrete.

m. Unusual or uncharted obstructions that are encountered in the contract work area during construction.

n. Location, extent, thickness, and size of stone protection particularly where it will be normally submerged by water.

3.3 RECORD DRAWINGS

Prepare and provide Record Drawings in accordance with FC 1-300-09N. Provide 2 copies of Record Drawings on two separate CDs or DVDs 30 days after BOD.

3.4 OPERATION AND MAINTENANCE MANUALS

Provide project operation and maintenance manuals as specified in Section 01 78 23 OPERATION AND MAINTENANCE MANUALS DATA. Provide four electronic copies of the Operation and Maintenance Manual files. Submit to the Contracting Officer for approval within 60 calendar days of the Beneficial Occupancy Date (BOD). Update and resubmit files for final approval at BOD. Provide one hard copy and place in cabinet in main mechanical room.

3.5 CLEANUP

Provide final cleaning in accordance with ASTM E1971 and submit two copies of the listing of completed final clean-up items. Leave premises "broom clean." Comply with GS-37 for general purpose cleaning and bathroom cleaning. Use only nonhazardous cleaning materials, including natural cleaning materials, in the final cleanup. Clean interior and exterior glass surfaces exposed to view; remove temporary labels, stains and foreign substances; polish transparent and glossy surfaces; vacuum carpeted and soft surfaces. Clean equipment and fixtures to a sanitary condition. Replace filters of operating equipment and comply with the Indoor Air Quality (IAQ) Management Plan. Clean debris from roofs, gutters, downspouts and drainage systems. Sweep paved areas and rake clean landscaped areas. Remove waste and surplus materials, rubbish and construction facilities from the site. Recycle, salvage, and return construction and demolition waste from project in accordance with Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS.

3.6 TRANSFER AND ACCEPTANCE OF MILITARY REAL PROPERTY

Requirements/information found in this paragraph is for the development and submitting the Interim DD Form 1354. The requirements/information may be in addition to requirements of other paragraphs/sections (or missing paragraphs/sections) and supersedes any discrepancies or conflicts with information or requirements in other paragraphs/sections. The intent of obtaining copies of Schedule of Values and base line schedule is to support and validate the development and submission of the DD form 1354 required by this paragraph.

3.6.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

FC 2-000-05N, FACILITY PLANNING FOR NAVY AND MARINE CORPS SHORE

INSTALLATIONS (current)

UFC 1-300-08, CRITERIA FOR TRANSFER AND ACCEPTANCE OF DOD REAL PROPERTY (current)

MCICOM REAL PROPERTY BUSINESS PROCESS NARRATIVE (current Fiscal Year)

3.6.2 DEFINITIONS

DD Form 1354: Transfer and Acceptance of DoD Real Property. An instrument used by Military Services and WHS to document the acceptance and valuation of Real Property assets and the addition of the asset to the Accountable Property System of Record for acquisition by construction and capital improvement to existing facilities.

Draft DD Form 1354: Working document provided by government. Document includes facilities and related information (minus quantity and cost) within contract/project scope.

Interim DD Form 1354:

Updated/provided by contractor indicating expected construction contract estimated quantities and costs for facilities listed on the Draft DD form 1354. Updates can also include adjustments to faculties constructed. The estimated quantities and costs are based upon the current construction contract scope of work at time of DD form 1354 submittal.

For phased construction: Allows transfer of accountability for the DoD Real Property from the Contractor/Contracting Officer to the accountable Service on the placed-in-service date. An Interim DD Form 1354, based on the latest DD Form 1354 iteration, is prepared in advance of the placed-in-service date (also known as beneficial occupancy date) for facility acceptance or building occupancy. The Interim DD Form 1354 includes actual quantities constructed and contract cost, at time of submittal, for work accepted.

Final DD Form 1354: Allows transfer of accountability for the DoD Real Property from the Contractor/Contracting Officer to the accountable Service on the placed-in-service date. A Final DD Form 1354 is prepared in advance of the placed-in-service date (also known as beneficial occupancy date) for facility acceptance or building occupancy. The Final DD Form 1354 includes actual quantities constructed and contract cost, at time of submittal, for work accepted.

NAVFAC Disposal Form: used to document demolition of existing facilities within the footprint for new construction or demolition of existing facilities no longer required outside footprint for new construction.

Facility: Building or supporting facility or utility listed on the DD Form 1354

Primary Facilities: work on an individual building and includes attendant construction, such as pad mounted HVAC cooling equipment, cooling towers, and landscaping placed outside the face of exterior walls.

Building: A roofed and floored facility enclosed by exterior walls and consisting of one or more levels that is suitable for single or multiple functions.

Supporting Facilities: work on various type of buildings or structures supporting primary facilities such as canopies, dumpster pads, parking areas, utility buildings, and generators.

Structure: A facility, other than a building or linear structure, which is constructed above ground or below ground.

Supporting Utility Facilities: work on various type of utilities or linear structures and includes incidental work such as pavement removal and replacement for constructing the facility. Such as sidewalks, fencing, communication distribution, transformers, electrical distribution, sanitary, water, fire water, retaining walls, storm sewer and swales.

Beneficial Occupancy Date: the placed-in-service date after substantial completion of construction in preparation for facility acceptance or building occupancy. Government acceptance of overall contract or phased construction.

Phase construction: multiple facilities with different turnover dates, or when a portion of a single large facility, or a phase of a multi-phase construction project is placed into service.

Acquisition by Construction: A new real property facility (buildings, structures, or linear structures) in DoD inventory and accountability and valuation resulting in a new "footprint."

Capital Improvement: any improvement of an existing asset that increases the useful life, capacity, or size; or modifies functionality.

Noncapitalized or Expensed Cost: Any work designated as repairs or maintenance or non-project funded equipment; includes temporary trailers provided for government use; FF&E and A/V.

Excluded Cost: Other Interim DD form 1354s and/or NAVFAC Disposal Forms for Project.

Furnishings, Fixtures, and Equipment (FF&E) and Audio Visual (A/V): Non-project funded equipment, shall include, but is not limited to; furniture, shop equipment, specialty equipment, projection equipment, monitors, appliances, and other miscellaneous items to support facility functions.

3.6.3 REAL PROPERTY RECORD

1. Refer to UFC 1-300-08 for instruction on completing the DD Form 1354. Contact the Contracting Officer for any project specific information necessary to complete the DD Form 1354.

2. Government to provide the Draft DD Form 1354 at the pre-construction conference.

3.6.4 SUBMITTALS

The following shall be submitted in accordance with Section entitled SUBMITTAL PROCEDURES:

1) Interim DD Form 1354 with estimated quantities and costs and include supporting information.

i. Submit Interim DD Form 1354 thirty (30) calendar days after pre-construction conference. For Design Build contracts submit thirty (30) calendar days after IFC drawings submitted and accepted by government.

ii. Include copy of the detailed breakdown of the contract price, as required in Specification section discussing "PRICE AND PAYMENT PROCEDURES". Schedule of prices shall be separated by individual building, supporting facility, and supporting utilities with subtotals for each line item listed on Draft DD Form 1354.

iii. If overhead or other indirect costs (such as bonds, design, submittals) as a separate line item are included on Schedule of Prices and/or in the Cost-Loaded Network Analysis Schedule, these costs shall be prorated between each building, supporting facility, and supporting utilities listed on Draft DD Form 1354.

iv. Include copy of baseline schedule as required in Specification section discussing" COST-LOADED NETWORK ANALYSIS SCHEDULES".

2) Interim DD Form 1354, Transfer & Acceptance of Military Real Property

i. Submit Interim DD-1354 thirty (30) days prior to beneficial occupancy date (or partial BOD for individual building/facilities).

ii. Include total cost and actual quantities installed/constructed, any additional assets, improvements, and alterations from the Draft DD Form 1354. Quantities for utilities should match data provided by GIS submittal (if required).

iii. Attach the High Performance and Sustainable Building (HPSB) Checklist for each applicable building to the completed DD 1354, in accordance with Section entitled "SUSTAINABILITY REQUIREMENTS AND REPORTING".

3.6.5 DD Form 1354

A. Contractor responsible for providing quantities and cost for each facility listed on Draft DD Form 1354 provided by government. Abbreviations for Unit of Measure are listed in Appendix A attached.

B. Contractor responsible for updating cost and quantity for each facility listed based upon current contract requirements when submitting Interim DD-1354 thirty (30) days prior to beneficial occupancy date (or partial BOD for phased construction) when government accepts work for use (or work is accepted for government possession and use). Multiple Interim DD Forms 1354 may be required when a construction contract contains multiple facilities with different turnover dates.

C. For cost load schedules, add unconstrained finish milestone, titled "DD-1354 - Interim" and scheduled 30 calendar days prior to Substantial Completion whenever an Interim or Final Form DD 1354 is required for individual building/facilities.

D. Provide/verify FF&E/AV costs on back page in block 27.

E. Total of line items, plus noncapitalized items and excluded cost items (other Interim DD Form 1354 and NAVFAC Disposal Form) to add up to contact amount funded by project (minus non-project cost of FF&E/AV).

3.7 FINAL APPROVED SHOP DRAWINGS

Provide 2 copies of Final Approved Shop Drawings on two separate CDs or DVDs within 30 days after BOD.

Appendix A: Abbreviations for UNIT OF MEASURE CODES & DESCRIPTIONS

Unit of Measure Code	Description
AC	ACRES
BD	HOSPITAL BEDS, NORMAL CAPACITY
BL	BARRELS (42 GALS EACH)
BX	BOXES
CF	CUBIC FEET
CM	CUBIC FEET/MINUTE
CP	CANDLE POWER
CY	CUBIC YARDS
DS	DEPTH OF WATER OVERSILL @ HIGH TIDE
DW	DEPTH OF WATER OVERSILL @ LOW TIDE
EA	EACH
FA	FAMILY UNITS (HOUSING)
FB	LINEAR FEET OF BERTHING
FP	FIRING POINT (FIRING RANGES)
GA	GALLONS
GM	GALLONS PER MINUTE
HO	HOLES (GOLF COURSE)
IN	INCHES
KG	THOUSANDS OF GALLONS PER DAY
KV	KILOVOLT AMPERES
KW	KILOWATTS
LA	LANES (BOWLING)
LC	LIGHT CARE, HOSPITAL SPACE
LF	LINEAR FEET
LN	SET OF FIRING POINTS
MB	MILLIONS OF BTU PER HOUR
ME	METERS
MG	MILLIONS OF GALLONS
MI	STATUTE MILES
MW	MEGAWATTS
NF	NET SQUARE FEET (HOUSING)
NS	NET SQUARE FEET (STORAGE)
OL	OUTLETS, NUMBER OF
OU	OPERATING UNITS
PH	POUNDS PER HOUR
PN	PERSONS, DESIGN CAPACITY
SE	SEATS, NUMBER OF
SF	SQUARE FEET
SH	STACKING HEIGHT
SI	SITES
SP	STARTING POINT
SY	SQUARE YARDS
TC	TOTAL CUBIC FEET
TH	TONS PER HOUR
TN	TONS
TR	TONS, REFRIGERATION
VE	NUMBER OF VEHICLES

-- End of Section --

SECTION 01 78 23

OPERATION AND MAINTENANCE DATA
04/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E1971	(2024) Standard Guide for Stewardship for the Cleaning of Commercial and Institutional Buildings

1.2 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-10 Operation and Maintenance Data

Training Plan ; G

Training Outline ; G

Training Content ; G

SD-11 Closeout Submittals

Training Video Recording ; G

Validation of Training Completion ; G

1.3 OPERATION AND MAINTENANCE DATA

Submit Operation and Maintenance (O&M) Data for the provided equipment, product, or system, defining the importance of system interactions, troubleshooting, and long-term preventive operation and maintenance. Compile, prepare, and aggregate O&M data to include clarifying and updating the original sequences of operation to as-built conditions. Organize and present information in sufficient detail to clearly explain O&M requirements at the system, equipment, component, and subassembly level. Include an index preceding each submittal. Submit in accordance with this section and Section 01 33 00 SUBMITTAL PROCEDURES.

1.3.1 Package Quality

Documents must be fully legible. Operation and Maintenance data must be consistent with the manufacturer's standard brochures, schematics, printed instructions, general operating procedures, and safety precautions.

1.3.2 Package Content

Provide data package content in accordance with paragraph SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES. Comply with the data package requirements specified in the individual technical sections, including the content of the packages and addressing each product, component, and system designated for data package submission, except as follows. Use Data Package 3 for commissioned items without a specified data package requirement in the individual technical sections. Provide a Data Package 3 instead of Data Package 1 or 2, as specified in the individual technical section, for items that are commissioned.

1.3.3 Changes to Submittals

Provide manufacturer-originated changes or revisions to submitted data if a component of an item is so affected subsequent to acceptance of the O&M Data. Submit changes, additions, or revisions required by the Contracting Officer for final acceptance of submitted data within 30 calendar days of the notification of this change requirement.

1.4 OPERATION AND MAINTENANCE MANUAL FILE FORMAT

Assemble data packages into electronic Operation and Maintenance Manuals. Assemble each manual into a composite electronically indexed file using the most current version of Adobe Acrobat or similar software capable of producing PDF file format. Provide compact disks (CD) or data digital versatile disk (DVD) as appropriate, so that each one contains operation, maintenance and record files, project record documents, and training videos. Include a complete electronically linked operation and maintenance directory. Place one hard copy of each in cabinet in main mechanical room.

1.4.1 Organization

Bookmark Product and Drawing Information documents using the current version of CSI Masterformat numbering system, and arrange submittals using the specification sections as a structure. Use CSI Masterformat and UFGS numbers along with descriptive bookmarked titles that explain the content of the information that is being bookmarked.

1.4.2 CD or DVD Label and Disk Holder or Case

Provide the following information on the disk label and disk holder or case:

a. Building Number

b. Project Title

c. Activity and Location

d. Construction Contract Number

e. Prepared For: (Contracting Agency)

f. Prepared By: (Name, title, phone number and email address)

g. Include the disk content on the disk label

h. Date

i. Virus scanning program used

1.5 TYPES OF INFORMATION REQUIRED IN O&M DATA PACKAGES

The following are a detailed description of the data package items listed in paragraph SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES.

1.5.1 Operating Instructions

Provide specific instructions, procedures, and illustrations for the following phases of operation for the installed model and features of each system:

1.5.1.1 Safety Precautions and Hazards

List personnel hazards and equipment or product safety precautions for operating conditions. List all residual hazards identified in the Activity Hazard Analysis provided under Section 01 35 26 GOVERNMENT SAFETY REQUIREMENTS. Provide recommended safeguards for each identified hazard.

1.5.1.2 Operator Prestart

Provide procedures required to install, set up, and prepare each system for use.

1.5.1.3 Startup, Shutdown, and Post-Shutdown Procedures

Provide narrative description for Startup, Shutdown and Post-shutdown operating procedures including the control sequence for each procedure.

1.5.1.4 Normal Operations

Provide Control Diagrams with data to explain operation and control of systems and specific equipment. Provide narrative description of Normal Operating Procedures.

1.5.1.5 Emergency Operations

Provide Emergency Procedures for equipment malfunctions to permit a short period of continued operation or to shut down the equipment to prevent further damage to systems and equipment. Provide Emergency Shutdown Instructions for fire, explosion, spills, or other foreseeable contingencies. Provide guidance and procedures for emergency operation of utility systems including required valve positions, valve locations and zones or portions of systems controlled.

1.5.1.6 Operator Service Requirements

Provide instructions for services to be performed by the operator such as lubrication, adjustment, inspection, and recording gauge readings.

1.5.1.7 Environmental Conditions

Provide a list of Environmental Conditions (temperature, humidity, and other relevant data) that are best suited for the operation of each product, component or system. Describe conditions under which the item equipment should not be allowed to run.

1.5.1.8 Operating Log

Provide forms, sample logs, and instructions for maintaining necessary operating records.

1.5.1.9 Additional Requirements for HVAC Control Systems

Provide Data Package 5 and the following for control systems:

a. Narrative description on how to perform and apply functions, features, modes, and other operations, including unoccupied operation, seasonal changeover, manual operation, and alarms. Include detailed technical manual for programming and customizing control loops and algorithms.

b. Full as-built sequence of operations.

c. Copies of checkout tests and calibrations performed by the Contractor (not Cx tests).

d. Full points list. Provide a listing of rooms with the following information for each room:

(1) Floor

(2) Room number

(3) Room name

(4) Air handler unit ID

(5) Reference drawing number

(6) Air terminal unit tag ID

(7) Heating or cooling valve tag ID

(8) Minimum cfm

(9) Maximum cfm

e. Full print out of all schedules and set points after testing and acceptance of the system.

f. Full as-built print out of software program.

g. Marking of system sensors and thermostats on the as-built floor plan and mechanical drawings with their control system designations.

1.5.2 Preventive Maintenance

Provide the following information for preventive and scheduled maintenance to minimize repairs for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.5.2.1 Lubrication Data

Include the following preventive maintenance lubrication data, in addition

to instructions for lubrication required under paragraph OPERATOR SERVICE REQUIREMENTS:

a. A table showing recommended lubricants for specific temperature ranges and applications.

b. Charts with a schematic diagram of the equipment showing lubrication points, recommended types and grades of lubricants, and capacities.

c. A Lubrication Schedule showing service interval frequency.

1.5.2.2 Preventive Maintenance Plan, Schedule, and Procedures

Provide manufacturer's schedule for routine preventive maintenance, inspections, condition monitoring (predictive tests) and adjustments required to ensure proper and economical operation and to minimize repairs. Provide instructions stating when the systems should be retested. Provide manufacturer's projection of preventive maintenance work-hours on a daily, weekly, monthly, and annual basis including craft requirements by type of craft. For periodic calibrations, provide manufacturer's specified frequency and procedures for each separate operation.

a. Define the anticipated time required to perform each of each test (work-hours), test apparatus, number of personnel identified by responsibility, and a testing validation procedure permitting the record operation capability requirements within the schedule. Provide a remarks column for the testing validation procedure referencing operating limits of time, pressure, temperature, volume, voltage, current, acceleration, velocity, alignment, calibration, adjustments, cleaning, or special system notes. Delineate procedures for preventive maintenance, inspection, adjustment, lubrication and cleaning necessary to minimize repairs.

b. Repair requirements must inform operators how to check out, troubleshoot, repair, and replace components of the system. Include electrical and mechanical schematics and diagrams and diagnostic techniques necessary to enable operation and troubleshooting of the system after acceptance.

1.5.2.3 Cleaning Recommendations

Provide environmentally preferable cleaning recommendations in accordance with ASTM E1971.

1.5.3 Repair

Provide manufacturer's recommended procedures and instructions for correcting problems and making repairs for the installed model and features of each system. Include potential environmental and indoor air quality impacts of recommended maintenance procedures and materials.

1.5.3.1 Troubleshooting Guides and Diagnostic Techniques

Provide step-by-step procedures to promptly isolate the cause of typical malfunctions. Describe clearly why the checkout is performed and what conditions are to be sought. Identify tests or inspections and test equipment required to determine whether parts and equipment may be reused or require replacement.

1.5.3.2 Wiring Diagrams and Control Diagrams

Provide point-to-point drawings of wiring and control circuits including factory-field interfaces. Provide a complete and accurate depiction of the actual job specific wiring and control work. On diagrams, number electrical and electronic wiring and pneumatic control tubing and the terminals for each type, identically to actual installation configuration and numbering.

1.5.3.3 Repair Procedures

Provide instructions and a list of tools required to repair or restore the product or equipment to proper condition or operating standards.

1.5.3.4 Removal and Replacement Instructions

Provide step-by-step procedures and a list of required tools and supplies for removal, replacement, disassembly, and assembly of components, assemblies, subassemblies, accessories, and attachments. Provide tolerances, dimensions, settings and adjustments required. Use a combination of text and illustrations.

1.5.3.5 Spare Parts and Supply Lists

Provide lists of spare parts and supplies required for repair to ensure continued service or operation without unreasonable delays. Special consideration is required for facilities at remote locations. List spare parts and supplies that have a long lead-time to obtain.

1.5.3.6 Repair Work-Hours

Provide manufacturer's projection of repair work-hours including requirements by type of craft. Identify, and tabulate separately, repair that requires the equipment manufacturer to complete or to participate.

1.5.4 Appendices

Provide information required below and information not specified in the preceding paragraphs but pertinent to the maintenance or operation of the product or equipment. Include the following:

1.5.4.1 Product Submittal Data

Provide a copy of SD-03 Product Data submittals documented with the required approval.

1.5.4.2 Certificates

Provide a copy of SD-07 Certificates submittals documented with the required approval.

1.5.4.3 Manufacturer's Instructions

Provide a copy of SD-08 Manufacturer's Instructions submittals documented with the required approval.

1.5.4.4 O&M Submittal Data

Provide a copy of SD-10 Operation and Maintenance Data submittals documented with the required approval.

1.5.4.5 Parts Identification

Provide identification and coverage for the parts of each component, assembly, subassembly, and accessory of the end items subject to replacement. Include special hardware requirements, such as requirement to use high-strength bolts and nuts. Identify parts by make, model, serial number, and source of supply to allow reordering without further identification. Provide clear and legible illustrations, drawings, and exploded views to enable easy identification of the items. When illustrations omit the part numbers and description, both the illustrations and separate listing must show the index, reference, or key number that will cross-reference the illustrated part to the listed part. Group the parts shown in the listings by components, assemblies, and subassemblies in accordance with the manufacturer's standard practice. Parts data may cover more than one model or series of equipment, components, assemblies, subassemblies, attachments, or accessories, such as typically shown in a master parts catalog.

1.5.4.6 Warranty Information

List and explain the various warranties and clearly identify the servicing and technical precautions prescribed by the manufacturers or contract documents in order to keep warranties in force. Include warranty information for primary components of the system. Provide copies of warranties required by Section 01 78 00 CLOSEOUT SUBMITTALS.

1.5.4.7 Extended Warranty Information

List all warranties for products, equipment, components, and sub-components whose duration exceeds one year. For each warranty listed, indicate the applicable specification section, duration, start date, end date, and the point of contact for warranty fulfillment. Also, list or reference the specific operation and maintenance procedures that must be performed to keep the warranty valid. Provide copies of warranties required by Section 01 78 00 CLOSEOUT SUBMITTALS.

1.5.4.8 Personnel Training Requirements

Provide information available from the manufacturers that is needed for use in training designated personnel to properly operate and maintain the equipment and systems.

1.5.4.9 Testing Equipment and Special Tool Information

Include information on test equipment required to perform specified tests and on special tools needed for the operation, maintenance, and repair of components. Provide final set points.

1.5.4.10 Testing and Performance Data

Include completed prefunctional checklists, functional performance test forms, and monitoring reports. Include recommended schedule for retesting and blank test forms. Provide final set points.

1.5.4.11 Field Test Reports

Provide a copy of Field Test Reports (SD-06) submittals documented with the required approval.

1.5.4.12 Contractor Information

Provide a list that includes the name, address, and telephone number of the General Contractor and each Subcontractor who installed the product or equipment, or system. For each item, also provide the name address and telephone number of the manufacturer's representative and service organization that can provide replacements most convenient to the project site. Provide the name, address, and telephone number of the product, equipment, and system manufacturers.

1.6 SCHEDULE OF OPERATION AND MAINTENANCE DATA PACKAGES

Provide the O&M data packages specified in individual technical sections. The information required in each type of data package follows:

1.6.1 Data Package 1

a. Safety precautions and hazards

b. Cleaning recommendations

c. Maintenance and repair procedures

d. Warranty information

e. Extended warranty information

f. Contractor information

g. Spare parts and supply list

1.6.2 Data Package 2

a. Safety precautions and hazards

b. Normal operations

c. Environmental conditions

d. Lubrication data

e. Preventive maintenance plan, schedule, and procedures

f. Cleaning recommendations

g. Maintenance and repair procedures

h. Removal and replacement instructions

i. Spare parts and supply list

j. Parts identification

k. Warranty information

l. Extended warranty information

m. Contractor information

1.6.3 Data Package 3

a. Safety precautions and hazards

b. Operator prestart

c. Startup, shutdown, and post-shutdown procedures

d. Normal operations

e. Emergency operations

f. Environmental conditions

g. Operating log

h. Lubrication data

i. Preventive maintenance plan, schedule, and procedures

j. Cleaning recommendations

k. Troubleshooting guides and diagnostic techniques

l. Wiring diagrams and control diagrams

m. Maintenance and repair procedures

n. Removal and replacement instructions

o. Spare parts and supply list

p. Product submittal data

q. O&M submittal data

r. Parts identification

s. Warranty information

t. Extended warranty information

u. Testing equipment and special tool information

v. Testing and performance data

w. Contractor information

x. Field test reports

1.6.4 Data Package 4

a. Safety precautions and hazards

b. Operator prestart

c. Startup, shutdown, and post-shutdown procedures

d. Normal operations

e. Emergency operations

f. Operator service requirements

g. Environmental conditions

h. Operating log

i. Lubrication data

j. Preventive maintenance plan, schedule, and procedures

k. Cleaning recommendations

l. Troubleshooting guides and diagnostic techniques

m. Wiring diagrams and control diagrams

n. Repair procedures

o. Removal and replacement instructions

p. Spare parts and supply list

q. Repair work-hours

r. Product submittal data

s. O&M submittal data

t. Parts identification

u. Warranty information

v. Extended warranty information

w. Personnel training requirements

x. Testing equipment and special tool information

y. Testing and performance data

z. Contractor information

aa. Field test reports

1.6.5 Data Package 5

a. Safety precautions and hazards

b. Operator prestart

c. Start-up, shutdown, and post-shutdown procedures

d. Normal operations

e. Environmental conditions

f. Preventive maintenance plan, schedule, and procedures

g. Troubleshooting guides and diagnostic techniques

h. Wiring and control diagrams

i. Maintenance and repair procedures

j. Removal and replacement instructions

k. Spare parts and supply list

l. Product submittal data

m. Manufacturer's instructions

n. O&M submittal data

o. Parts identification

p. Testing equipment and special tool information

q. Warranty information

r. Extended warranty information

s. Testing and performance data

t. Contractor information

u. Field test reports

v. Additional requirements for HVAC control systems

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 TRAINING

Prior to acceptance of the facility by the Contracting Officer for Beneficial Occupancy, provide comprehensive training for the systems and equipment specified in the technical specifications. The training must be targeted for the Facilities Management Specialist, building maintenance personnel, and applicable building occupants. Instructors must be well-versed in the particular systems that they are presenting. Address aspects of the eOMSI Manual, as submitted in Section 01 78 24.00 20 FACILITY ELECTRONIC OPERATION AND MAINTENANCE SUPPORT INFORMATION (eOMSI). Training must include classroom or field lectures based on the system operating requirements. The location of classroom training requires approval by the Contracting Officer.

3.1.1 Training Plan

Submit a written training plan to the Contracting Officer for approval at least 60 calendar days prior to the scheduled training. Also, coordinate the training schedule with the Contracting Officer. Include within the plan the following elements:

a. Equipment included in training

b. Intended audience

c. Location of training

d. Dates of training

e. Objectives

f. Outline of the information to be presented and subjects covered including description

g. Start and finish times and duration of training on each subject

h. Methods (e.g. classroom lecture, video, site walk-through, actual operational demonstrations, written handouts)

i. Instructor names and instructor qualifications for each subject

j. List of texts and other materials to be furnished by the Contractor that are required to support training

k. Description of proposed software to be used for video recording of training sessions.

3.1.2 Training Content

The core of this training must be based on manufacturer's recommendations and the operation and maintenance information. The CxA is responsible for overseeing and approving the content and adequacy of the training. Provide a brief summary of the FACILITY INFORMATION manual, and a more detailed presentation of the PRODUCT AND DRAWING MANUAL, specified in Section 01 78 24.00 20 FACILITY ELECTRONIC OPERATION AND MAINTENANCE SUPPORT INFORMATION (eOMSI). Spend 95 percent of the instruction time during the presentation on the OPERATION AND MAINTENANCE DATA. Include the following for each system training presentation:

a. Start-up, normal operation, shutdown, unoccupied operation, seasonal changeover, manual operation, controls set-up and programming, troubleshooting, and alarms.

b. Relevant health and safety issues.

c. Discussion of how the feature or system is environmentally responsive. Advise adjustments and optimizing methods for energy conservation.

d. Design intent.

e. Use of O&M Manual Files.

f. Review of control drawings and schematics.

g. Interactions with other systems.

h. Special maintenance and replacement sources.

i. Tenant interaction issues.

3.1.3 Training Outline

Provide the eOMSI Manual files as specified in Section 01 78 24.00 20, FACILITY ELECTRONIC OPERATION AND MAINTENANCE SUPPORT INFORMATION (eOMSI), and a written course outline listing the major and minor topics to be discussed by the instructor on each day of the course to each trainee in the course. Provide the course outline 14 calendar days prior to the training.

3.1.4 Training Video Recording

Record classroom training session(s) on video. Provide to the Contracting Officer two copies of the training session(s) in DVD video recording format. Capture within the recording, in video and audio, the instructors' training presentations including question and answer periods with the attendees. The recording camera(s) must be attended by a person during the recording sessions to assure proper size of exhibits and projections during the recording are visible and readable when viewed as training.

3.1.5 Unresolved Questions from Attendees

If, at the end of the training course, there are questions from attendees that remain unresolved, the instructor must send the answers, in writing, to the Contracting Officer for transmittal to the attendees, and the training video must be modified to include the appropriate clarifications.

3.1.6 Validation of Training Completion

Ensure that each attendee at each training session signs a class roster daily to confirm Government participation in the training. At the completion of training, submit a signed validation letter that includes a sample record of training for reporting what systems were included in the training, who provided the training, when and where the training was performed, and copies of the signed class rosters. Provide two copies of the validation to the Contracting Officer, and one copy to the Operation and Maintenance Manual Preparer for inclusion into the Manual's documentation.

3.1.7 Quality Control Coordination

Coordinate this training with the CxA in accordance with Section 01 45 00.05 20 DESIGN AND CONSTRUCTION QUALITY CONTROL FOR DESIGN-BUILD.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 01 78 24.00 20

FACILITY ELECTRONIC OPERATION AND MAINTENANCE SUPPORT INFORMATION (eOMSI)
03/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

FC 1-300-09N (2024) Navy and Marine Corps Design

1.2 DEFINITIONS AND ABBREVIATIONS

1.2.1 eOMSI Manual

Manual (PDF file) provided by the Contractor that includes, but is not limited to, product information, a facility description with photos, and a list of primary facility systems.

1.2.2 Systems

The words "system", "systems", and "equipment", when used in this document refer to as-built systems and equipment.

1.2.3 Computer Assisted Design and Drafting (CADD)

Electronic Computer Assisted Design and Drafting graphic software program that is used to create facility design contract documents and Record Drawings.

1.2.4 KTR

An abbreviation for "Contractor."

1.3 EOMSI MEETINGS

1.3.1

Be prepared to discuss the following during this meeting:

a. eOMSI Manual Development Meetings

b. Processes and methods of gathering eOMSI Manual information during construction.

c. The eOMSI Submittals schedule. Include the eOMSI submittal schedule on the Baseline Construction Schedule.

1.3.2 eOMSI Manual Coordination Meeting

Facilitate a meeting after the Post-Award Kickoff Meeting prior to the submission of the eOMSI Progress Submittal. Meeting attendance must

include the Contractor's eOMSI Manual Preparer, and Quality Control Manager, and the Government's Design Manager (DM), Contracting Officer's Representative, and NAVFAC Public Works (PW) Facilities Management Division (FMD). Include any Mechanical, Electrical, and Fire Protection Sub-Contractors.

The purpose of this meeting is to reach a mutual understanding of the scope of work concerning the contract requirements for eOMSI and coordinate the efforts necessary by both the Government and Contractor to ensure an accurate collection, preparation and timely Government review of eOMSI.

1.3.3 Facility Turnover Meeting

Include eOMSI in NAVFAC Red Zone (NRZ) facility turnover meetings as specified in Section 01 30 00, ADMINISTRATIVE REQUIREMENTS.

1.4 SUBMITTAL SCHEDULING

1.4.1 eOMSI, Progress Submittal

Submit the Progress submittal when construction is approximately 50 percent complete, to the Contracting Officer for approval. Provide eOMSI Manual Files (Bookmarked PDF). Include the elements and portions of system construction completed up to this point.

The purpose of this submittal is to verify progress is in accordance with contract requirements as discussed during the eOMSI Coordination Meeting. Field verify a portion of the eOMSI information in accordance with paragraph FIELD VERIFICATION.

1.4.2 eOMSI, Prefinal Submittal

Submit the 100 percent submittal of the eOMSI Prefinal Submittal to the Contracting Officer for approval within 90 calendar days of the Beneficial Occupancy Date (BOD). This submittal must provide a complete, working document that can be used to operate and maintain the facility. Any portion of the submittal that is incomplete or inaccurate requires the entire submittal to be returned for correction. Any discrepancies discovered during the Government's review of eOMSI Progress submittal must be corrected prior to the Prefinal submission.

The eOMSI Prefinal Submittal must include eOMSI Manual Files (Bookmarked PDF).

1.4.3 eOMSI, Final Submittal

Submit completed eOMSI Manual Files (Bookmarked PDF). The Final submittal is due at BOD. Any discrepancies discovered during the Government's review of the Prefinal eOMSI submittal, including the Field Verification, must be corrected prior to the Final eOMSI submission.

1.5 UNITS OF MEASURE

Provide eOMSI utilizing the English Inch-Pound units of measure

1.6 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL

PROCEDURES:

SD-11 Closeout Submittals

eOMSI, Progress Submittal; G

eOMSI, Prefinal Submittal; G

eOMSI, Final Submittal; G

PART 2 PRODUCTS

2.1 eOMSI FILES FORMAT

Format eOMSI manuals and files in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA. Include a complete electronically linked operation and maintenance directory. Provide four electronic copies of the eOMSI Manuals to the Contracting Officer for approval.

Scan eOMSI Manuals and Files for viruses, malware, and spyware using a commercially available scanning program that is routinely updated to identify and remove current virus threats. Provide one hard copy of eOMSI Manuals and Files in the cabinet in the main mechanical room.

2.1.1 eOMSI Manual Organization

Organize the eOMSI Manuals into two parts: 1) Product and Drawing Information, and 2) Facility Information. Bookmark the PDF files for easy access to the information.

a. Bookmark Product and Drawing Information documents in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

b. Bookmark Facility Information to at least one level lower than the major system.

2.1.2 eOMSI Manual CD or DVD Disk Label and Disk Holder or Case

Provide disks in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA. At a minimum, provide four (4) disks and place one hard copy of all O&M Data in the cabinet in the main mechanical room.

2.2 eOMSI MANUAL

2.2.1 Product and Drawing Information

Provide an organized record of the facility products, materials, equipment, and minimum information necessary to operate the facility. Provide Product and Drawing Information for the systems in the final constructed facility.

2.2.1.1 O&M Data

As a minimum, provide the approved O&M Data, submitted in the technical specification sections, in accordance with paragraph TYPES OF INFORMATION REQUIRED IN O&M DATA PACKAGES in Section 01 78 23 OPERATION AND MAINTENANCE DATA.

2.2.1.2 Record Drawings

Provide an electronic, PDF copy of the Record Drawings, prepared in accordance with FC 1-300-09N and 01 78 00 CLOSEOUT SUBMITTALS. Bookmark drawings using the sheet title and sheet number.

Include Record Drawings as part of the Red-Zone specified in Section 01 30 00 ADMINISTRATIVE REQUIREMENTS.

2.2.1.3 Utility Record Drawings

Using Record Source Drawings, show and document details of the actual installation of the utility systems; annotate and highlight the eOMSI information. Provide Utility Record Drawings in PDF format. Provide the following drawings at a large enough scale to differentiate designated isolation units from surrounding valves and switches.

a. Utility Schematic Diagrams - Provide a one line schematic diagram for each utility system such as power, water, wastewater, and gas/fuel. Schematic diagram must show from the point where the utility line is connected to the mainline up to the five-foot connection point to the facility. Indicate location or area designation for route of transmission or distribution lines; locations of duct banks, manholes/ handholes or poles; isolation units such as valves and switches; and utility facilities such as pump stations, lift stations, and substations.

b. Enlarged Connection and Cutoff Plans - Provide enlarged floor plans that provide information between the five foot utility connection point and where utilities connect to facility distribution. Enlarge floor plans/ elevations of the rooms where the utility enters the building and indicate on these plans locations of the main interior and exterior connection and cutoff points for the utilities. Also enlarge floor plans / elevations of the rooms where equipment is located. Include enough information to enable someone unfamiliar with the facility to locate the connection and cutoff points. Indicate designations such as room number, panel number, circuit breaker, or valve number, of each utility and equipment connection and cutoff point, and what that connection and cutoff point controls.

2.2.2 Facility Information

Provide the following in Facility Information:

2.2.2.1 General Facility and System Description

Describe the function of the facility. Detail the overall dimensions of the facility, number of floors, foundation type, expected number of occupants, and facility Category Code. List and generally describe all the facility systems and any special building features (for example, HVAC Controls, Sprinkler Systems, Cranes, Elevators, and Generators). Include photographs marked up and labeled to show key operating components and the overall facility appearance.

2.2.2.2 Floor Plans

Provide uncluttered, legible 11 by 17 inches floor plans. Include room numbers, type or function of spaces, and overall facility dimensions on the floor plans. Do not include items such as construction instructions,

references, or frame numbers.

2.2.2.3 Floor Coverings, Wall Surfaces, and Ceiling Surfaces

Provide a table that lists by room number (including hallways and common spaces), the type, and area of finish, manufacturer's product name, identifying number, and color. Include a facility summary of the total area for each type of space and floor, wall, or ceiling finish in the table.

2.2.2.4 Windows

Provide a table that lists by room number (including hallways and common spaces), the type of window, window size, number of each size and type, special features, manufacturer's product name, identifying number, and color. The table must include a facility summary of the total number for each type and size of window.

2.2.2.5 Roofing

Provide the total area of each type of roof surface and system. Provide the name of the roofing product and system; manufacturer's, supplier's, and installer's names, addresses, and phone numbers; manufacturer's product name, identifying number, and color. For each type of roof, provide a recommended inspection, maintenance and repair schedule that details checkpoints, frequencies, and prohibited practices. List roof structural load limits.

2.2.2.6 HVAC Filters

Provide a table that lists the quantity, type, size, and location of each HVAC filter, manufacturer's product name, and identifying number.

2.2.2.7 Plumbing Fixtures

Provide a table that lists by room number, the number and type of plumbing and bathroom plumbing fixtures (for example, sinks, water closets, urinals, showers and drinking fountains).

2.2.2.8 Lighting Fixtures

Provide a table that lists by room number (including hallways and common spaces), the type of lighting fixture, ballast, number of lighting fixtures, type of lamps and number of lamps, and the manufacturer's product name and the identifying number. The table must include a facility summary of the total number of fixtures of each type and number of lamps of each type.

2.2.2.9 Equipment Listing

Provide a table that lists the major equipment shown on the design equipment schedules. Show the item descriptions, locations, model numbers; and the names, addresses, and telephone numbers of the manufacturers, suppliers, contractors, and subcontractors.

2.2.2.10 System Flow Diagrams

Provide a flow diagram indicating system liquid, air or gas flow during normal operations. Integrate the system components into the diagram. A

compilation of non-integrated, flow diagrams for the individual system components are not acceptable.

2.2.2.11 Valve List

Provide a list of all valves associated with the system. Show valve type, identification number, function, location and normal operating position.

2.2.2.12 Riser Diagrams

Provide riser diagrams and settings of equipment.

PART 3 EXECUTION

3.1 FIELD VERIFICATION

Field verify eOMSI Maximo and Warranty Binder information with Contractor and Government personnel. Include the following personnel in this meeting: Contractor's eOMSI Manual and Quality Control Manager, and the Government's Contracting Officer's Representative and NAVFAC PW FMD. Request, and provide, an eOMSI Field Verification Meeting no sooner than 14 calendar days after submission of the Progress eOMSI submittal, and another, no sooner than 14 calendar days after submission of the initial TAB report.

100 percent accuracy of eOMSI Maximo and Warranty Binder information is required for successful field verification.

3.2 eOMSI TRAINING

Provide training on eOMSI Manuals in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

-- End of Section --

SECTION 01 78 30.00 22

GIS DATA DELIVERABLES

5/22

PART 1 GENERAL

1.1 OBJECTIVE

The primary objective of this section is to provide detailed specifications for collection and delivery of geospatial data commonly referred to as Geographic Information System (GIS) data. Additionally, this section shall provide guidance to ensure that all GIS data delivered is compatible and will add value to the Marine Corps Base (MCB) Camp Lejeune Installation Geospatial Information and Services (IGI&S) GEOdatabase.

Failure to comply with the specifications outlined in this document will result in non-acceptance of data deliverables.

1.1.1 Point of Contact for MCB Camp Lejeune

The Points of Contact (POC) for assistance in preparation of GIS deliverables are as follows:

Resident Officer In Charge Of Construction
Construction Manager (CM)
1005 Michael Drive
Camp Lejeune, NC 28547-2521
(910) 451-2581 (Main Number)

Public Works Assigned
GIS Data Manager
1005 Michael Road
Camp Lejeune, NC 28547-2521
(910) 000-0000 ext 0000 TBD
Lejeune_PWD_GIS@usmc.mil

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES 01 33 00 CONSTRUCTION SUBMITTAL PROCEDURES:

SD-11 Closeout Submittals

GIS Data Deliverables; G

1.3 GOVERNMENT GEOSPATIAL DATA, SCHEMA, AND DOMAINS

Geo-spatial data is based on the Spatial Data Standards for Facilities, Infrastructure and Environment (SDSFIE) GEOFidelis Data Model. Because there are recurring business driven modifications and or adaptations within the SDSFIE schema, provide all spatial and non-spatial data in the most current version by the USMC utilized at the time of delivery.

1.3.1 Data Request Package Requirements

Request the existing GIS Data, Schema and Domain Properties by utilizing a Data Request Package (DRP), which is supplied via the government sponsor.

a. The DRP should be submitted prior to the start of data collection

efforts and again 4 weeks prior to data delivery to ensure that GIS data has been created and will be delivered utilizing the most up to date SDSFIE schema.

1.3.1.1 Instruction for submitting a Geospatial DRP to the CM or the Project Manager (PM)

a. Each CM or PM will provide DRP forms upon request from the contractor. Complete the request and include all information as instructed on the data request form.

b. Request only GIS data, schema and domains for feature classes that are relevant to the contract and within the boundary of project area and provide justifications as necessary.

c. Attach the Scope of Work, which is defined by this GIS DATA DELIVERABLES section for each DPR submittal.

d. Return the DRP to the CM or PM for sponsorship and submittal as instructed with required attachments and justifications for submittal.

e. Incomplete forms may delay receipt of the requested GIS data.

f. GIS data deliverables do not supplement or replace as-built drawings.

1.3.2 Data Collection and Utility Locates

a. Utilize the most up to date SDSFIE Schema when delivering GIS Data.

b. Prior to GPS efforts all underground utilities are to be located utilizing a utility locating service in order to obtain and verify accurate feature locations.

c. Actual conditions in the field always supersede drawings. Locate and field verify all features to ensure location is correctly recorded.

d. Data will be created to represent the real world, for example, water, sewer, and transportations systems will be connected. All segments will be created from source to sink in the direction of flow.

e. Research may be required to collect data. Verification of existing data which is located in the Technical Records in the Public Works Department at 1005 Michael Street, MCB Camp Lejeune.

f. Infrastructure data, as identified in paragraph "ATTRIBUTE DATA COLLECTION AND GPS REQUIREMENTS FOR SPECIFIC FEATURES" may be collected utilizing Sub-Foot or better GPS data collection methods.

g. Utility data, as identified in paragraph "ATTRIBUTE DATA COLLECTION AND GPS REQUIREMENTS FOR SPECIFIC FEATURES" will be collected utilizing Survey Grade GPS data collection methods.

1.3.3 Attribute Data Requirements

a. All attributes will be populated in accordance with paragraph ATTRIBUTE DATA COLLECTION AND GPS REQUIREMENTS FOR SPECIFIC FEATURES and will be obtained via contract specifications, plans and record drawings.

b. Demolished / Removed Real Property data will be captured, attributed and delivered in the Disposal feature classes which include Disposal Facility Area, Disposal Facility Line and Disposal Facility Point.

c. Demolished / Removed UTILITY data will be captured, attributed and delivered by creating a new feature class which will consists of adding DEMO to the feature's naming convention for each feature, such as, but not limited to the following examples; DEMO.WastUtilNode_SPump (point), DEMO.Feat_SwRetentionBasinArea,(polygon), and DEMO.WastUtilSegment (polyline)

    1. The Contractor will be responsible for properly delivering demolished features with the current attributes associated with the feature and additionally updating the new contract number, date of demolishment, and optional status.

d. Spatial and non-spatial data may be copied from existing data, with the exception of specific attributes. Potable water wells are an exception to this rule and shall remain in the feature class and attributed as Removed or AIP.

e. Abandoned In Place (AIP) utility lines will be located and updated in the current feature data set and be attributed as AIP as required.

1.3.4 GIS Topology Rules for Geospatial Data

All data must be created using GIS topology rules for polygons, points and lines, such as, but not limited to the following examples:

a. Utility and transportation systems will be created from source to sink.

b. All utilities shall be drawn in the direction of flow with no breaks in polyline except for fittings, manholes and other features nodes within the feature Dataset.

c. All utility or infrastructure system data, which is, but is not limited to, transportation system and electrical, water, thermal distribution, and wastewater collection, etc., will be created using GIS spatial connectivity rules which specify that vertex, edge and endpoints be snapped to features within the system.

d. All polygons will be closed without slivers and be topologically correct.

e. All polylines will be topologically correct, and should be connected to avoid undershoots, overshoots and dangles and will cross only if they share a point in common, at least one of which is not an endpoint.

f. For all Polygons, Polylines and points rules; please reference illustrating topology rules in ArcGIS at www.esri.com.

1.3.5 Global Positioning System (GPS) Data Collection

Utilize field survey GPS data collected by means of non-recreational GPS equipment

a. Only bench marks included in the North Carolina Geodetic Survey Base Station Network are to be used for GPS data collection.

b. Mission planning is essential. Utilize the best Position Dilution of Precision (PDOP) values for data accuracy.

c. Mission planning for GPS collection should be conducted when positional dilution of precision (PDOP) value is 4 or less.

d. Spatial accuracy requirements

1. Survey and Sub-Foot GPS grade data collection requirements are as follows:

i. Sub-Foot requirements:

1) All points shall be within plus or minus 12 inches

2) 95 percent accuracy rate for all points.

ii. Survey Grade requirements:

1) All points shall be within plus or minus 1 centimeter

2) 98 percent accuracy rate for all points

e. Make every effort to capture feature locations without using Offsets. All Offsets will be noted in the Final Report for each feature. Deliver report in PDF format.

1. Resubmittal of data will be required if PDOP planning was not observed per this specification.

1.3.6 Coordinate System Requirements

The data must be collected in the following Spatial Reference / Coordinate System for each feature for all MCB Camp Lejeune and surrounding bases:

1. Transverse Mercator (UTM) Zone 18N

a. GRS 1980 spheroid

b. North American Datum 1983 (NAD83) horizontal datum

c. North American Vertical Datum 1988 (NAVD88) vertical datum.

2. Domain precision of 1000 which will result in a database accuracy of 1/1000 m

1.3.7 Formats and Version Guidelines

All data deliverables shall be presented in the following formats and/or versions.

a. GIS data will be provided in an ArcGIS 10.8 or higher if a higher version is being used by the Government at the time of this project. Verify the ArcGIS version, via the CM or PM at the commencement of this contract.

b. Microsoft Windows 10 operating system, unless otherwise approved by the Government.

c. All reports and maps will be delivered as a hard copy and in a searchable Adobe Portable Document Format (PDF).

1.3.8 GIS Deliverable Submittal Requirements

All GIS Submittals will be submitted to the CM or PM and then analyzed by Government GIS personnel prior to final approval. Failure to comply with the specifications outlined in this document will result in non-acceptance of GIS data deliverables.

a. Prior to any spatial and non-spatial development, provide the Government with a technical approach document, in PDF format, for review and approval. The Technical Approach document will describe in detail the Contractor's technical approach for developing GIS data to include utility locating, collecting, and attributing all GIS data.

b. Provide a GIS deliverable at the end of each phase and at each Beneficial Occupancy Date (BOD) when contracted efforts, studies or construction are delivered in phases.

c. To ensure specifications compliance and quality a preliminary GIS deliverable shall be provided for review when 25 percent of the data has been collected and updated according to this specification.

d. Deliver digital geographic maps, GPS collection files and related data. All working text and documents and personal geodatabase will be included for review in the draft and final delivery of data in PDF format.

e. Do not deliver blank unused schema or feature class data with no attributes. Deliver only data pertinent to the contract that adds value to the Geodatabase per this section.

f. Do not include existing data in the GIS deliverable.

g. Spatial and non-spatial GIS data must be provided in a format that does not require translation or pre/post processing.

h. It is the Contractor's responsibility to perform quality assurance for all data and related materials required in this section prior to submitting product to the Government.

i. The data will be analyzed for discrepancies in subject content, correct format in accordance with this statement of work, and compatibility with the existing SDSFIE Schema as well as all other specifications included in this section.

1.3.9 GIS Deliverable Package Requirements

All reports must be provided in pdf format. Each GIS deliverable must contain the following information and be in the most up to date SDSFIE format utilized by the USMC at the time of delivery.

a. Digital and Paper Maps.

1. All maps of GIS DATA DELIVERABLES will be ANSI C size.

2. Each map will include a project title, contract number, scale, legend, standard symbology, attributes, i.e., building numbers,

road names, etc.

3. All utilities will be labeled with direction of flow and segment line size.

4. Provide paper copy and pdf copies of Maps for project.

5. Provide a copy of all red-line construction drawings in pdf format.

6. Communication data will be provided on a separate map.

b. Provide all spatial and non-spatial data for review and acceptance.

c. Provide a report of specific procedures, list GPS equipment, software and versions that were utilized for the GPS data collection and creation of geospatial data.

d. Submit all GPS data files collected in the field.

e. Provide details on any offsets to include justification as to why offsets were utilized and which features and or points offsets were used.

f. Provide the source that was utilized for required attributes, such as redlines drawings and or field notes.

g. Summit DD form 1354, Transfer and Acceptance of DOD Real Property.

h. Provide a coversheet that specifies the CM / PM, contract number, contract title, point of contract for GIS related questions.

i. All geospatial data, pdf reports, spreadsheet, database files, reports, and maps will be submitted on a Digital Versatile Disc (DVD) platform.

j. Failure to comply will result in non – compliance and rejection of data.

1.3.10 Ownership

All digital files, hardcopy products, GPS raw data, source data acquired for this project, and related materials, including that furnished by the Government, will become the property of the Government and will not be issued, posted, distributed, or published by the Contractor. All documentation will be delivered in the final delivery.

Note: No endorsement of software or hardware is implied.

1.4 ATTRIBUTE DATA COLLECTION AND GPS REQUIREMENTS FOR REAL PROPERTY AND OTHER MISCELLANEOUS FEATURES THAT ARE NOT CONSIDERED A UTILITY

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required. Items in this section that require Survey Grade GPS are property identified in the feature class description.

1.4.1 Feature Dataset CLJN.CL.AccessControl

Locate, GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.AccessControlPoint (point) -The location of a feature, manned or unmanned, intended to selectively restrict entrance to or use of a place or other resource.

a) accessControlType - The type of access control. Domain values, i.e., gate, tireShedder, barricade, etc.
b) builtDate - The calendar date on which the original construction was completed for a facility.
c) contractNumber - The contract number associated with the feature.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) gatePurposeType - Purpose that the gate exists and functions under. Domain values i.e., decorative, insternalSecurity, perimaterSecurity, recreation, residential, safely, vehicleBarrier, other, etc.
h) gateTypeMaterial - The type of material of the gate. Domain values i.e., metal, steel, wood, wroughtiron, etc.
i) isBaseEntryPoint -The Yes / No indicator of whether or not the location is an entry point for the military installation.
j) isCheckpoint - Indicator if location is where officials check vehicle contents or personnel. Yes / No
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) isManned - Yes / No
n) isRangeAccess - Yes / No
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.AccessControlLine (polyline) - The location of a feature, manned or unmanned, intended to selectively restrict entrance to or use of a place or other resource.

a) accessControlTypeThe type of access control. Domain AccessControlType
b) builtDate - The calendar date on which the original construction was completed for a facility.
c) contractNumber- The contract number associated with the feature.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review

current data for common name)
g) gatePurposeType- - Purpose that the gate exists and functions under. Domain values i.e., decorative, insternalSecurity, perimaterSecurity, recreation, residential, safely, vehicleBarrier, other, etc.
h) gateTypeMaterial - The type of material of the gate. Domain values i.e., metal, steel, wood, wroughtiron, etc.
i) gateUse - The type of a gate (or similar route barrier) based on its intended use.
j) mediald - gpsDataCollected
k) MetadataId - metaID000072
l) isBaseEntryPoint - Yes / No
m) isCheckpoint - Yes / No
n) isManned - Yes / No
o) isRangeAccess - Yes / No
p) operationalStatus- The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.BarricadePoint (point) - The coordinated series of obstacles designed or employed to channel, direct, restrict, delay, or stop the movement of personnel, equipment, or an opposing force and to impose additional losses in personnel, time, and equipment on the opposing force. Barricades can exist naturally, be man-made, or a combination of both.

a) accessControlType - The type of access control. Domain values, i.e., gate, tireShedder, barricade, etc.
b) builtDate - The calendar date on which the original construction was completed for a facility.
c) contractNumber - The contract number associated with the feature.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) barricadeType -The type of barricade. Domain values i.e., bollard, bollardPipe, pedestrianBarrier, other, etc.
h) barricadeUse - The intended use of the barricade Domain values i.e., pedestrianTraffic, security, vehicularTraffic, etc.
i) gatePurposeType - Purpose that the gate exists and functions under. Domain values i.e., internalSecurity, perimeterSecurity, recreation, residential, safety, vechicleBarrier, etc.
j) gateTypeMaterial - The type of material of the gate. Domain values i.e., metal, steel, wood, wroughtiron, etc.
k) gateUse - The type of a gate (or similar route barrier) based on its intended use.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.BarricadeLine (polyline) - The coordinated series of obstacles designed or employed to channel, direct, restrict, delay, or stop the movement of personnel, equipment, or an opposing force and to impose additional losses in personnel, time, and equipment on the opposing

force. Barricades can exist naturally, be man-made, or a combination of both.

a) accessControlType - The type of access control. Domain values, i.e., gate, tireShedder, barricade, etc.
b) barricadeUse - The intended use of the barricade Domain values i.e., pedestrianTraffic, security, vehicularTraffic, etc.
c) builtDate - The calendar date on which the original construction was completed for a facility.
d) contractNumber - The contract number associated with the feature.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) gatePurposeType - Purpose that the gate exists and functions under. Domain values i.e., internalSecurity,
i) perimeterSecurity, recreation, residential, safety, vechicleBarrier, etc.
j) mediald - gpsDataCollected
k) l) MetadataId - metaID000072
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) gateTypeMaterial - The type of material of the gate. Domain values i.e., metal, steel, wood, wroughtiron, etc.

1.4.2 Feature Dataset CLJN.CL.CivilWorks

Locate, GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.PitOrQuarry (Polygon) - The location where material has been or is being excavated or extracted for use at another location.

a) featureDescription - The narrative describing the feature. (Review current data for description)
b) featureName - The common name of the feature. (Review current data for common name)
c) contractNumber - The contract number associated with the feature.
d) mediald - gpsDataCollected
e) MetadataId -metaID000072
f) isWaterFilled - Yes / No
g) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

1.4.3 Feature Dataset CLJN.CL.HarbourArea

Locate, GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning

System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.BoatRampPoint - (Point) - The partially submerged hard surfaced or non-hardsurface structure on a shoreline for launching or retrieving vessels or vehicles.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) isLighted - Yes / No
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.DockOrWharf (Polygon) - The location of a manmade water-land interface structure often used for access to boats, ships, or barges.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) dockType - The kind or type of the dock. Domain values i.e., access ramp, pier, slipway, general, etc.
d) dockUseType - The predominant use. Domain values i.e., fishing, fueling, loading, staging, etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) materialType - The material composition of the feature. Domain values i.e., concrete, steel, wood, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.

CLJN.CL.MarineNavigationAid (Point) - The physical object that serves as an aid to navigation. *Requires Survey Grade GPS.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the

feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) heightAboveSurfaceLevel - The vertical distance measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature.
g) heightAboveSurfaceLevelUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
h) isLighted - Yes / No
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) navaidType - Type of the navaid. Domain value i.e., buoyMarkerDangerPoint, buoyMarkerDangerPoint etc.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, closed, abandoned, etc.

1.4.4 Feature Dataset CLJN.CL.RealProperty

Locate, GPS and collect attribute data as specified for each feature listed with GPS accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

Specific instruction for all Disposal polygons, polylines and points. All demolished or removed property shall be accounted for in the following 3 disposal features. A simple copy and paste with the following exceptions as explains in the disposal area, polyline and point may be permitted with the exception of the directions for attribution for each feature as noted. However, under no circumstance should potable water wells be removed from their original feature class. Potable wells are never deleted from their main feature, all that is required is the water wells are attributed in such a way that indicated if they are abandoned in Place (AIP) or Removed.

CLJN.CL.Disposal_FacilityArea (polygon)- The location of a facility asset in the DoD real property inventory for which a disposal action is being or has been taken to physically demolish, remove, or release the DoD of accountability for and control of the asset.

a) abandonedDate - The date the feature was abandoned. Leave blank if removed.
b) builtDate - The calendar date on which the original construction was completed for a facility.
c) contractNumber - The contract number associated with the feature demolishment or abandonment.
d) ClassType - Population is contingent only if data is currently available for feature.
e) disposalCompletionDate - The actual calendar date of the disposal or abandonment of the asset.
f) facilityNumber - Asset Identification such as building or structure number.
g) featureDescription -Population is contingent only if data is

currently available for feature.
h) featureName (Mandatory) - Feature Name and subtype
i) facilityIdfk - Population is contingent only if data is currently available for feature.
j) operationalStatus - The state of usability of the feature. Domain values i.e., removed, abandoned, etc.
k) owner - Population is contingent only if data is currently available for feature.
l) removedDate - The date the feature was removed. Leave blank if abandoned.
m) realPropertyJurisdictionType - Population is contingent only if data is currently available for feature.
n) registryIdentifier - Population is contingent only if data is currently available for feature.
o) sourceFeatureClass (Mandatory) - The feature class containing the polygon feature.

CLJN.CL.Disposal_FacilityLine (polyline) - The location of a personal property asset in the DoD real property inventory for which a disposal action is being or has been taken to physically demolish, remove, or release the DoD of accountability for and control of the asset.

a) abandonedDate - The date the feature was abandoned. Leave blank if removed.
b) builtDate - The calendar date on which the original construction was completed for a facility.
c) contractNumber - The contract number associated with the feature demolishment or abandoned.
d) classType - Population is contingent only if data is currently available for feature.
e) disposalCompletionDate - The actual calendar date of the disposal or abandonment of the asset.
f) facilityNumber - Asset Identification RoadName, fence, utility line, fence gate information, etc.
g) featureDescription - Population is contingent only if data is currently available for feature.
h) featureName (Mandatory) - Feature Name and subtype
i) operationalStatus - The state of usability of the feature. Domain values i.e., removed, abandoned, etc.
j) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.
k) removedDate - The date the feature was removed. Leave blank if abandoned.
l) realPropertyJurisdictionType - The type of real property jurisdiction. Domain values i.e., tbd, etc.
m) registryIdentifier - Population is contingent only if data is currently available for feature.
n) sdsId - Population is contingent only if data is currently available for feature.
o) sourceFeatureClass (Mandatory) - The feature class containing the line feature.

CLJN.CL.Disposal_FacilityPoint (point) - The location of a personal property asset in the DoD real property inventory for which a disposal action is being or has been taken to physically demolish, remove, or release the DoD of accountability for and control of the asset.

a) abandonedDate - The date the feature was abandoned. Leave blank if removed.
b) builtDate - The calendar date on which the original construction was completed for a facility.
c) contractNumber - The contract number associated with the feature demolishment or abandoned.
d) ClassType - Population is contingent only if data is currently available for feature.
e) disposalCompletionDate - The actual calendar date of the disposal or abandonment of the asset.
f) facilityNumber - Asset Identification such as generator, ows, towers, etc.
g) featureDescription - Population is contingent only if data is currently available for feature.
h) featureName (Mandatory) - Feature Name and subtype
i) facilityIdfk - Population is contingent only if data is currently available for feature.
j) operationalStatus - The state of usability of the feature. Domain values i.e., removed, abandoned, etc.
k) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.
l) removedDate - The date the feature was removed. Leave blank if abandoned.
m) realPropertyJurisdictionType - The type of real property jurisdiction. Domain values i.e., tbd, etc.
n) registryIdentifier - Population is contingent only if data is currently available for feature.
o) sdsId - Population is contingent only if data is currently available for feature.
p) sourceFeatureClass (Mandatory) - The feature class containing the point feature.

CLJN.CL.Bridge - Bridge (polygon) - The structure erected over a depression or an obstacle such as a body of water, railroad, etc., to provide a pathway for vehicles, rail services, pedestrians or to carry utility services.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the
c) facilityNumber - Asset number used for visual identification of the facility.
d) contractNumber - The contract number associated with the feature.
e) featureDescription - The narrative describing the feature. Value Base Area or Road Name Crossing
f) featureName - The common name of the feature. Pedestrian, Railroad, Road, other, etc.
g) heightAboveSurfaceLevel - The vertical distance measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature.
h) heightUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) isFixed - Indicator of whether the bridge cannot be opened for navigation or other purposes. Yes / No
l) operationalStatus - The state of usability of the feature

i.e., inService, notInService, abandoned, etc.

CLJN.CL.Building - Building (polygon) - The roofed and floored facility enclosed by exterior walls and consisting of one or more levels.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature if feature function does not accuracy address the description of building.
e) featureName - The common name of the feature. (Review current data for common name)
f) featureFunction - The purpose(s) of, or intended role(s) served by, the feature. Domain values i.e., Fishing (3), Aircraft Repair (341), Motor Vehicle Repair (343), Utilities (350), Water Treatment (362), Water Distribution (363), Residence (563), Guard (781), Government (811), Recreation (921) etc.
g) floorCount - The number of floors
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.Fence (polyline) - The freestanding structure designed to restrict or prevent movement across a boundary.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - FENCE or GATE.
f) FenceDesignType - The configuration of fabricated fence materials in a particular manner to build a fence. This may or may not include specifications of the post type(s). Domain values i.e., cross, postAndFrame, metalRail, postAndFrame, etc.
g) fenceFabricatedMaterialType - The fabricated material of the fence. Domain values i.e., barbedWire, chainLink, wroughtIron, metalOther, steel, wood, etc.
h) fencePrimaryMaterialType - The fundamental or raw substance of the fence. Domain values i.e., jute, metalOther, steel, wood, wroughtIron, etc.
i) fenceTopType - The fabricated material used as an upper barrier on the fence. Domain values i.e., spiked, electricfiedWire, etc.
j) fenceUseType - The purpose that the fence serves. Domain values, i.e., internalSecurity, perimeterSecurity,

recreation, residential, safety, vechicleBarrier, etc.
k) heightAboveSurfaceLevel - The vertical distance measurement in feet.
l) heightUom - The unit of measure for the height measurement. Domain values 0.3048 metres or feet, etc.
m) mediald - gpsDataCollected
n) MetadataId - metaID000072
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.Gate (polyline) - A movable barrier that closes an opening in a fence, wall, or other enclosure or enclosure.

a) accessControlType - The type of access control. Domain values, i.e., gate etc.
b) builtDate - The calendar date on which the original construction was completed for a facility.
c) contractNumber - The contract number associated with the feature.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) gateTypeMaterial - The type of material of the gate. Domain values i.e., metal, steel, wood, wroughtiron, etc.
h) gatePurposeType - Purpose that the gate exists and functions under. Domain values i.e., decorative, insternalSecurity, perimaterSecurity, recreation, residential, safely, vehicleBarrier, other, etc.
i) gateTopType - The fabricated material used as an upper barrier on the fence. Domain values i.e., spiked,
j) isBaseEntryPoint - Yes or No
k) isCheckpoint - Yes or No
l) isManned - Yes or No
m) isPortable - Yes or No
n) isRangeAccess - Yes or No
o) mediald - gpsDataCollected
p) metadataId - metaID000072
q) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.RecreationBoundary (polygon) - The area designated for recreational purposes.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) isFormallyDelineated Yes / No

g) isHandicappedAccessible Yes / No
h) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.OpenStorage - Open Storage (polygon) - The non-covered and/or covered storage areas, paved or otherwise established, for the storage of general supply materials or the receipt, processing, staging and issue of materials.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) mediald - gpsDataCollected
g) MetadataId - metaID000072
h) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.PavementSectionAirfieldArea - Pavement Section Airfield (polygon) - The location of a surface feature that comprises a section of a military airfield area. *Requires Survey Grade GPS.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) airfieldPavementUse - The use of the airfield. Domain values i.e., apron, fueling area, helipad, runway, taxiway, etc.
e) featureDescription - The narrative describing the feature. Values should include Area i.e., MCAS NEW RIVER, HADNOT POINT, RIFLE RANGE, MCOLF CAMP DAVIS, GSRA, HOSPITAL, etc.
f) featureName - The common name of the feature. (Review current data for common name)
g) highestElevation - The elevation from a specified vertical datum to the highest point on a feature.
h) highestElevationUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
i) isLighted - Yes / No
j) isPaved - Yes / No
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.
o) runwayClassification - Classification of the runway. Domain values i.e., classA, classB, rotary, olf, etc.

CLJN.CL.PavementSectionParkingArea (polygon) - The area used for parking vehicles not including residential streets and driveways.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) isLighted - Yes / No
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
j) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.
k) pavementSurfaceType - The type of material used to construct the surface of the pavement feature. Domain values i.e., asphalt, gravel, asphaltOverAsphaltConcrete, portlandCementConcrete, etc.
l) vehicleType - The type of vehicle permitted on the pavement section. Domain value i.e., all, gov, mil, pov, etc.

CLJN.CL.PavementSectionRoadway (polygon) - The surface area that comprise a road area, upon which vehicles drive and park.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - FULL Road Name All Capital Letters, i.e., D STREET, SIXTH STREET, FOSTER BOULEVARD, PORTLAND COURT
f) isPaved - Yes / No
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
j) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.
k) pavementSurfaceType - The type of material used to construct the surface of the pavement feature. Domain values i.e., gravel, asphalt, asphaltOverAsphaltConcrete, portlandCementConcrete, etc.
l) roadSectionType - The type of road asset represented by this section. Domain values i.e., roadway, stagingArea, etc.
m) vehicleType - The type of vehicle permitted on the pavement section. Domain value i.e., all, gov, mil, pov, etc.

CLJN.CL.PavementSection - Pavement Section (polygon) - The portion of

a pavement branch that differs in some aspect from other sections such that further segmentation is required to uniquely identify that section.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. Value i.e., GENERATOR PAD, TRANSFORER PAD, DUMPSTER PAD, BLEACHER PAD, UTILITY PANEL PAD, etc.
e) FeatureName - Slab.
f) featureName - The common name of the feature. (Review current data for common name)
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
j) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.

CLJN.CL.PavementSectionSidewalk (polygon) - The paved pedestrian walkway prepared to facilitate travel on foot. It may or may not be adjacent to a street/road.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) isLighted - Yes / No
g) isPaved - Yes / No
h) materialType - The material composition of the feature. Domain values i.e., asphalt, concrete, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.

CLJN.CL.StructureArea - Structure (polygon) - The facility, other than a building or linear structure, which is constructed on or in the land.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.

d) featureDescription - The narrative describing the feature. Values i.e., Picnic Pavilion, Gazebo, Postal Shelter, Buss Stop, Golf Shelter, Vehicle Wash Platform, Outdoor Classroom,
e) featureName - The common name of the feature. Values i.e., CANOPY, PLATFORM, PAVILLION, RAMP, WEIGH STATION, etc.
f) mediald - gpsDataCollected
g) MetadataId - metaID000072
h) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.TowerPoint (point) - The vertical projection, higher than its diameter, generally used for observation, etc.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. I.e., Range, Observation, Cell, etc.
e) featureName - Common name utilized for Range Area name.
f) heightMax - Maximum height of structure in feet.
g) heightUom - The unit of measure for the height measurement. Domain values .3048 metres or feet, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) towerUseType - The primary operational use of the tower. Domain values, i.e., fire, observation, communication, training, etc.

CLJN.CL.TrafficControlLight (point) - A feature used to represent traffic lights.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) heightAboveSurfaceLevel - Maximum height of structure in feet.
g) heightAboveSurfaceLevelUom - The unit of measure for the height measurement. Domain values .3048 metres or feet, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.WallLine - Wall - The linear feature used for separation of facilities, ornamental decoration, or structural reinforcement.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. Values i.e., BENCH, DUMSPTER ENCLOSURE, UTILITY ENCLOSURE, RETAINING WALL, BLAST PROTECTION, BAFFLE WALL, MECHANICAL YARD, etc.
e) featureName - The common name of the feature. (Review current data for common name)
f) height - The height of the feature in feet.
g) heightUom - The unit of measure for the height measurement. Domain values .3048 metres or feet, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) wallMaterialType - The material from which the majority of the wall is constructed. Domain values i.e., brick, cinderblock, grass, glassBlock, masonry, wood, etc.

1.4.5 Feature Dataset CLJN.CL.Recreation

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.RecreationTrail - Recreation Trail (Polyline) - The path or walkway providing opportunity for physical activities.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature area. Values i.e., HADNOT POINT, FRECH CREEK, WALLAS CREEK, MCAS, etc.
e) featureName - The common name of the feature such as common trail name. Values, i.e., GREENWAY, MCAS, KNOX, etc.
f) Mediald - gpsDataCollected
g) MetadataId - metaID000072
h) meterialType - The material composition of the feature. Domain values i.e., asphalt, concrete, etc.
i) officialLength - The officially reported length of the feature in feet.
j) officialLengthUom - The official length. Domain values i.e. 0.3048 metres, feet, etc.
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.Playground - Playground (Polygon) The area designed for children to play outdoors.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) featureDescription - The narrative describing the feature. (Review current data for description).
d) featureName - The common name of the feature. (Review current data for common name)
e) featureName - The common name of the feature such as common trail name.
f) isHandicappedAccessible - Yes / No
g) Mediald - gpsDataCollected
h) MetadataId - metaID000072
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
j) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.
k) isHandicappedAccessible - Yes / No
l) playgroundCategory - Playground categorization by physical location on the installation. Domain values i.e., childDevCenter, generalPurpose, housingArea, school, etc.
m) playgroundMaterial - The primary material that the play pieces are constructed from. Domain values i.e., paintedMetal, plastic, vinylCoatedMetal, wood, etc.
n) recreationFeatureType - The type of recreation feature. Domain values i.e., paintball, playground, obstacleCourse, picnicSite, tennisCourt, volleyballCourt, swimmingPool, etc.
o) heightAboveSurfaceLevel - The vertical distance measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature.
p) heightAboveSurfaceLevelUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.

CLJN.CL.RecreationFeatureArea - Recreation Feature Area (Polygon) - The location of an object or other physical asset associated with a recreation site. - Recreation area, i.e., swimming pool, basketball, tennis, baseball, football, and other recreation features.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) facilityNumber - Asset number used for visual identification of the facility.
c) contractNumber - The contract number associated with the feature.
d) featureDescription - The narrative describing the feature.
e) featureName - The common name of the feature if not addressed in RecreationFeatureType field.
f) mediald - gpsDataCollected
g) MetadataId - metaID000072
h) heightAboveSurfaceLevel - The vertical distance measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature.
i) heightAboveSurfaceLevelUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.

j) isHandicappedAccessible - Recreation Area has a formal designation. Yes / No
k) isIndoor - Yes or No
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.
n) RecreationFeatureType - The type of recreation feature. Domain values. i.e., athleticCourt, athleticField, basketballCourt, climbingStructure, dugout, exerciseStation, footballField, picnicSite, recreationalFirearmsRange, volleyballCourt, etc.

1.4.6 Feature Dataset CLJN.CL.Transportation

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.Sign - Sign (point) - The structure that conveys directional, warning, or other information.

a) builtDate - The calendar date on which the original construction was completed for a facility.
b) contractNumber - The contract number associated with the feature.
c) mediald - gpsDataCollected
d) MetadataId - metaID000072
e) heightAboveSurfaceLevel - The vertical distance measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature.
f) heightAboveSurfaceLevelUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
g) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
h) signAssemblyType - The type of sign assembly material. Domain values i.e., IBeamSteelBreakaway, PedestrialPole, SignalMastArm, signalPole, fire, safety, etc.
i) signText - The text displayed on the sign.
j) signType - The type of sign. Domain values i.e., regulatory, school, warning, etc.
k) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.

CLJN.CL.RoadCenterline - The center of a roadway, as measured from the edge of the navigable road with the paved or unpaved surface. Polylines is to be drawn in direction of flow with no breaks except where naturally occurring such as intersections and crossings.

a) dataSource - The agency that last updated the record.
b) dateUpdated - The date the record was created or last modified.
c) elevationFrom - Elevation value at start of segment.
d) elevationTo - Elevation value at end of segment.

e) featureDescription - The narrative describing the feature.
f) featureName - the common name of the feature.
g) fullStreetName - The combined full street name.
h) isPaved - The yes or no indicator of whether the feature has a paved surface. Domain values i.e., yes, no.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) numLanes - The number of traffic lanes throughout the length of the centerline.
l) oneWayDirection - The one-way road directionality. Domain values i.e. ft, tf, b, etc.
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) owner - The entity that owns the feature. Domain values, i.e., usmc, ncdot, etc.
o) roadClass - The general description of the type of road, based on the US Census MAF/TIGER Feature Classification Codes (MTFCC). Domain values i.e., primary, secondary, local, etc.
p) roadWidth - The width of the feature.
q) roadWidthUom - The width unit of measure in feet
r) Domain: GsipLengthUom (i.e. usSurveyFoot, metre, etc.)
s) speedLimit - The posted speed limit in MPH.
t) verticalDatum - The vertical reference datum for the z location value. Domain values i.e. navd88, etc.
u) verticalEpoch - The time period epoch to which the elevation measurement is referenced. Domain values i.e., opus, etc.

1.4.7 Attrribute Data Collection and GPS Requirements for Utilities

Locate, GPS and collect attribute data as specified for each feature listed with (Survey Grade GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

1.4.8 Feature Dataset CLJN.CL.Telecommunication

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.CommUtilSegment (polyline) - The location of a feature used for destruction in a communication network, particularity a cable for the transmission of a signal.

a) availableStrands - A list of fiber strands that are available.
b) cableCount - The number of copper pairs or fiber strands dedicated at a given location.
c) cableId - The cable identifier. (Review current data for description)
d) cableInstaller - The name of the group responsible for installation of the cable feature.
e) cableInstallType - The type of installation of the cables. Domain values i.e., aeria, directBuried, tunnel, underground,

etc.

f) cableInsulation - The material composition of the insulation of the cable. Domain values i.e., pvc, xlpe, etc.
g) cableMaterial - The material composition of the cable. Domain values i.e., fiberOpt, cu, etc.
h) cableRoute - The start and end points of a cable section. (Review current data for description)
i) cableSheathing - The type of sheathing or insulation of the cable. Domain values i.e., bp, cpnm, cj, etc.
j) communicationsSegmentType - The type of communications network segment that this feature represents. Domain values i.e., cCoaxial, cFiberOptic, etc.
k) contractNumber - The contract number associated with the feature.
l) dateInService - The date the utility equipment was put in service.
m) featureDescription - The narrative describing the feature. (Review current data for description)
n) featureName - The common name of the feature. (Review current data for naming convention)
o) numberOfPairs - The number of wire pairs in the cable.
p) numberOfSingleModeStrands - The number of single-mode fiber strands.
q) numberOfStrands -The total number of fiber strands in the cable.
r) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
s) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
t) wireGauge - The gauge of the wire.

CLJN.CL.Feat_CUgEnclosureAccess (point) - The location of a communication access point to the related communication underground enclosure.

a) commUtilityFeatureType - Type of communication feature, i.e., cUGEnclosureAccess
b) contractNumber- The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for naming convention)
f) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., elevated, semiBuried, underground, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., communications.
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) ownerName - The name of the item owner, i.e., MCB CL, MCCS,PPV, Company Name, etc.
l) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., communications, etc.

CLJN.CL.Feat_CPedestal (point) - The location of an above-ground enclosed structure that provides access to buried plant and a place to house utility features.

a) commUtilityFeatureType - Type of communication feature, i.e., cPedestal
b) contractNumber- The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for naming convention)
f) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., elevated, semiBuried, underground, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., communications.
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) ownerName - The name of the item owner, i.e., MCB CL, MCCS,PPV, Company Name, etc.

CLJN.CL.CommUtilNode_CAntenna (point) - A device that can transmit or receive radio frequency signals.

a) communicationsNodeType - Type of communication node, i.e., cAntenna
b) contractNumber- The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for naming convention)
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
j) ownerName - The name of the item owner, i.e., MCB CL, MCCS,PPV, Company Name, etc.

CLJN.CL.Feat_CDuctBank (polyline) - The location of one or more ducts routed in parallel between two nodes.

a) commUtilityFeatureType - Type of communication feature, i.e., cDuctBank, etc.
b) contractNumber- The contract number associated with the feature.

c) dateInService - The date the utility equipment was put in service.
d) ductDiameterUom - - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) ductMaterial - The material composition of the feature. Domain values i.e., cooper, carbonSteel, etc.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for naming convention)
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., communications.
k) NumberOfDucts
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS,PPV, Company Name, etc.
n) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., communications, etc.

1.4.9 Feature Dataset CLJN.CL.Utilities_Electrical Class

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.AlternativeEnergyArea (polygon) - The apparatus or device used for the production of energy from a renewable resource.

a) alternativeEnergyType - The type of alternative energy that the feature represents. Domain values i.e., photovoltaic, windTurbine, tbd, etc.
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) expansionDistributionNetwork - An indication of the distribution network interconnection an alternative energy feature uses to supply renewable energy. Domain values i.e., partOElectricalNetwork, etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, recreational, tbd, etc.
i) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
j) hasInverter - Yes / No

k) isMetered - Yes / No
l) mediald - gpsDataCollected
m) MetadataId - metaID000072
n) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
o) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
p) panelType - The type of panel present.
q) systemCapacityDc - The system capacity for the DC current produced by the solar photovoltaic array, preferably measured in kilowatts.

CLJN.CL.ElecUtilNode_EFuse (point) - The location of a device used to protect electric distribution devices from dangerously high currents, and reduce risk of severe injury for personnel.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) alternativeEnergyType - The type of alternative energy that the feature represents. Domain values i.e., photovoltaic, windTurbine, tbd, etc.
c) contractNumber - The contract number associated with the feature.
d) dateInService - The date the utility equipment was put in service.
e) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., efuse.
f) facilityNumber - Asset number used for visual identification of the facility.
g) featureDescription - The narrative describing the feature. (Review current data for description)
h) featureName - The common name of the feature. (Review current data for common name)
i) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, recreational, etc.
j) mediald - gpsDataCollected
k) MetadataId - metaID000071
l) numberOfPhases - Number of phases. Domain values i.e., one, two, three, etc.
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.

CLJN.CL.ElecUtilNode_EGenerator (point) - The location of an available kinetic power source providing electricity.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in

service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eGenerator.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) generatorPowerSource - The power source of the generator. Domain values, i.e., gas, natural gas, propane, solarPower, etc.
j) generatorType - The type of electrical generator. Domain values i.e., emergency, primary, standby, etc.
k) isPortable - Yes / No
l) kvaRate - The rating of the complex power that the generator creates.
m) kwRate - The rating of the real power that the generator creates.
n) Manufacturer - The name of the manufacturer of the feature.
o) mediald - gpsDataCollected
p) MetadataId - metaID000072
q) modelNumber - The model, product, catalog, or item number for the feature item.
r) numberOfPhases - Number of phases. Domain values i.e., one, two, three, etc.
s) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
t) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
u) serialNumber - The manufacturer serial or unique identification number for the feature item.
v) voltage - The system voltage applied to the subject item. Domain value i.e., 120V, 480V, 480YTo277V etc.

CLJN.CL.ElecUtilNode_EMeter (point) - The location of a device that measures the amount of electric energy consumed by the power user.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eMeter.
e) energySource - Indicates if the meter is measuring a standard power source or an alternative energy source. Domain values i.e., standardPowerSource, alternativeEnergySource, tbd, etc.
f) facilityNumber - Asset number used for visual identification of the facility.

g) featureDescription - The narrative describing the feature. (Review current data for description)
h) featureName - The common name of the feature. (Review current data for common name)
i) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
j) isAmi - An indicator of whether or not the meter is an AMI or smart meter. Yes / No
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) meterType - The type of meter. Domain valves i.e., diaphragm, orifice, rotary, other, tbd, etc.
n) meterUse - An indication of the type of service the meter is monitoring. Domain valves eleMeter, generator, loadPoint, commercial, etc.
o) mountingType - The type of mounting for the subject item. Domain valves electrical, pole, pad, transformer, wall, etc.
p) numberOfPhases - Number of phases. Domain values i.e., one, two, three, etc.
q) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
r) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
s) transformerKva - The kva rate for the transformer.
t) voltage - The system voltage applied to the subject item. Domain value i.e., 120V, 480V, 480YTo277V etc.

CLJN.CL.ElecUtilNode_ECircuitBreaker (point) - The location of a circuit breaker, an automatically operated electrical switch designed to protect an electrical circuit from damage caused by excess current from an overload or short circuit.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eCircuitBreaker.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, MCCS,

PPV, Company Name, etc.

CLJN.CL.ElecUtilNode_EExteriorLight (point) - The location of a lighting device that is supplied by local distribution systems and is generally the only service for which the electric utility installs, operates and maintains utilization equipment.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eExteriorLight.
e) facilityNumber - Asset number used for visual identification of the facility.
f) exteriorLightType - The type of exterior light. Domain i.e., landscapelight, parkingLotLight, pedestrianLight, recreationFieldLight, securityLight, streetlight, sidewalkLight, etc.
g) featureDescription - The narrative describing the feature. (Review current data for description)
h) featureName - The common name of the feature. (Review current data for common name)
i) feederId - The Feeder Manager identifier assigned to electric feeders and devices that participate in a specific distribution circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
j) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
k) hasSensor - Yes / No
l) heightAboveSurfaceLevel - The vertical distance measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature.
m) heightAboveSurfaceLevelUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
n) isSolar - Yes / No
o) lampType - The type of lamp per fixture. Domain i.e., led, hps, mh, etc.
p) mediald - gpsDataCollected
q) MetadataId - metaID000072
r) mountingType - The type of mounting for the subject item. Domain values i.e., pole, pad, transformer, wall, ground, etc.
s) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
t) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
u) voltage - The system voltage applied to the subject item. Domain value i.e., 120V, 480V, 480YTo277V etc.

CLJN.CL.ElecUtilNode_EAirfieldLight (point) - The location of an electrical device used to illuminate runways, taxiways, helipads,

aprons, and any other aircraft movement area, as well as to guide ground traffic.

a) airfieldLightType - The type of lighting present on the airfield. Domain value i.e., runwayLight, taxiwayLight, apron, helipadLight, approachLight, etc.
b) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
c) contractNumber - The contract number associated with the feature.
d) dateInService - The date the utility equipment was put in service
e) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eAirfieldLight.
f) facilityNumber - Asset number used for visual identification of the facility.
g) featureDescription - The narrative describing the feature. (Review current data for description)
h) featureName - The common name of the feature. (Review current data for common name)
i) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
j) mediald - gpsDataCollected
k) MetadataId - metaID000072
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) voltage - The system voltage applied to the subject item. Domain value i.e., 120V, 480V, 480YTo277V etc.

CLJN.CL.ElecUtilNode_EEnergyStorage - The location of energy storage device or natural system capable of capture of energy produced at one time for use at a later time, within the relative span of a human lifetime.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eEnergyStorage.
e) featureDescription The narrative describing the feature. (Review current data for description)
f) featureName - The narrative describing the feature. (Review current data for description)
g) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.

h) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
i) ownerName - The name of the item owner, i.e., MCB CL, Company Name, etc.

CLJN.CL.ElecUtilNode_ESubstation (point) - A substation is a part of an electrical generation, transmission, and distribution system. Substations transform voltage from high to low, or the reverse, or perform any of several other important functions. Between the generating station and consumer, electric power may flow through several substations at different voltage levels.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eSubstation
d) facilityNumber - Asset number used for visual identification of the facility.-
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) numberOfAvailableBays - The number of available bays at the substation.
k) numberOfCircuits - The number of circuits present at the substation.
l) numberOfSpareBreakers - The number of Spare Breakers in the substation.
m) numberOfTransformers - The number of transformers present.
n) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
o) ownerName - The name of the item owner, i.e., MCB CL, Company Name, etc.
p) voltageIn - The line-to-line voltage of the transmission line that is the source for the substation. Domain value i.e., 120V, 480V, 480YTo277V etc.
q) voltageOut - The line-to-line output voltage of the substation. Domain value i.e., 120V, 480V, 480YTo277V etc.

CLJN.CL.Feat_ESubstation (Polygon) - The location of a facility in an electrical system where the voltage is reduced from transmission levels to distribution levels.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) electricalUtilityFeatureType - The type of electrical utility feature. Domain value, i.e., eSubstation.

d) FaciltyNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
h) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) networkType - The primary type of utility network to which this feature relates. Domain values i.e., electrical, etc.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., electrical, etc.

CLJN.CL.ElecUtilNode_EVoltageRegulator (point) - Current Regulators are different that Voltage Regulators and are used on the airfield lighting systems.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., ecurrentRegulator.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) numberOfPhases - Number of phases. Domain values i.e., one, two, three, etc.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.

CLJN.CL.ElecUtilNode_ESwitchingStation (point) - A Switching Station is an electrical substation with only one voltage level, whose only function are switching actions.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eSwitchingStation.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - Number of Switches.
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) mediaId- gpsDataCollected
j) MetadataId - metaID000072
k) numberOfSwitches -The number of switches present.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.

CLJN.CL.ElecUtilNode_ESwitch (point) - The location of a device throughout distribution feeder circuits to redirect power flows to balance loads or for sectionalizing to allow repair of damaged lines or equipment.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes, i.e., eSwitch.
e) electricalSwitchInstallation - The mounting/installation style of the electrical switch. Domain values buildingMounted, padMounted, poleMounted, electricalPanel, etc.
f) electricalSwitchType - The type or style of electrical switch. Domain values circuitBrkr, disconnect, fuseCutout, gangDisc, hdSaftly, iso, reclosure, etc.
g) facilityNumber - Asset number used for visual identification of the facility.
h) featureDescription - The narrative describing the feature. (Review current data for description)

i) featureName - The common name of the feature. (Review current data for common name)
j) feederId - The Feeder Manager identifier assigned to electric feeders and devices that participate in a specific distribution circuit, utilize (tbd) if unknown.
k) feederId2 - The feeder Manager Identifier assigned if the electric device is supplied by second feeder, utilize. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
l) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
m) mediald - gpsDataCollected
n) MetadataId - metaID000072
o) numberOfPhases - Number of phases. Domain values i.e., one, two, three, etc.
p) numberOfSwitches - The number of switches present, i.e.,
q) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
r) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
s) switchPosition - Code indicating normal position of switch, per phase. Domain value closed, closedOpen, open, openClosed, unknown, tbd, etc.
t) voltage - The system voltage applied to the subject item. Domain value i.e., 120V, 480V, 480YTo277V etc.

CLJN.CL.Feat_EPedestal (point) An aboveground service entrance, allowing maintenance access to the specific utility, usually electric or communications.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) bcontractNumber - The contract number associated with the feature.
c) cdateInService - The date the utility equipment was put in service.
d) electricalUtilityFeatureType - The type of electrical utility feature, i.e., ePedestal
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) featureName - The common name of the feature. (Review current data for common name)
i) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
j) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) operationalStatus - The state of usability of the feature

i.e., inService, notInService, abandoned, etc.
n) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
o) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., electrical, etc.

ElecUtilNode_ETransformer - Electrical Utility Node - Transformer (point) - The location of an electric distribution or power transformer.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) electricalNodeType - The type of electrical network node that this feature represents. Domain values consist of electrical nodes i.e., eTransformer.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) feederId - The Feeder Manager identifier assigned to electric feeders and devices that participate in a specific distribution circuit, utilize (tbd) if unknown.
i) feederId2 - The feeder Manager Identifier assigned if the electric device is supplied by second feeder, utilize (tbd) if unknown.
j) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) Manufacture - The name of the manufacturer of the feature.
n) modelNumber - The model, product, catalog, or item number for the feature item.
o) mountingType - The type of mounting for the subject item. Domain value ground, pad, pole, transformer, wall, tbd, etc.
p) numberOfPhases - Number of phases. Domain values i.e., one, two, three, etc.
q) numberOfTransformers - The number of transformers present.
r) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
s) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
t) primaryVoltage - The voltage on the source side of the regulator with the associated units given. Domain value i.e., 120V, 480V, 480YTo277V etc.
u) secondaryVoltage - The voltage on the load side of the regulator with the associated units given. Domain value i.e., 120V, 480V, 480YTo277V etc.
v) totalKva - The total kva rate.

w) transformerType - The type of transformer. Domain values i.e., inverter, isolation, stepDown, stepUp, vault, etc.

CLJN.CL.ElecUtilSegment (polyline) - The location of a linear feature, particularly a cable that transmits, distributes or connects customers to electricity. All polylines shall be drawn in the direction of flow with no breaks except for what is naturally occurring such at nodes, etc.

a) ElectricalSegmentType - The identifier for Primary or Secondary line segments within an electrical distribution system.
b) cableInsultaion - The material composition of the insulation of the cable. Domain value, i.e., ip, epr, pe, pvc, rubber, xipe, tdb, unknow, etc.
c) cableMaterial - The material composition of the cable. Domain value, i.e., ac, al, copper, fiberOpt, steel, steelGalv, etc.
d) cableSheathing - The type of sheathing or insulation of the cable. Domain value, i.e., shielded, weatherProof, asbestos, cellulose, tapeArmor, tbd, etc.
e) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
f) conductorSize - The size of the conductor.
g) contractNumber - The contract number associated with the feature.
h) dateInService - The date the utility equipment was put in service.
i) facilityNumber - Asset number used for visual identification of the facility.
j) featureDescription - The narrative describing the feature. (Review current data for description)
k) featureName - The common name of the feature. (Review current data for common name)
l) feederId - The Feeder Manager identifier assigned to electric feeders and devices that participate in a specific distribution circuit, utilize (tbd) if unknown.
m) feederId2 - The feeder Manager identifier assigned if the electric device is supplied by second feeder, utilize. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
n) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
o) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
p) mediald - gpsDataCollected
q) MetadataId - metaID000072
r) neutralSize - The size of a single neutral conductor. Domain value i.e., .5, .75, 1, 1.25, 2, 4, etc.
s) numberOfPhases - Number of phases. Value, i.e., 1, 2, 3, 4, etc.
t) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
u) ownerName - The name of the item owner, i.e., MCB CL, MCCS,

PPV, Company Name, etc.
v) voltage - The system voltage applied to the subject item. Domain value i.e., 120V, 480V, 480YTo277V etc.

CLJN.CL.Feat_EScadaSensor (point) - The location of a device that is used to remotely measure the status of electrical network components as part of a Supervisory Control and Data Acquisition (SCADA) system.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) electricalUtilityFeatureType - The type of electrical utility feature, i.e., eScadaSensor
d) FacilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
h) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., electrical.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., electrical, etc.

CLJN.CL.Feat_EDemarcationPoint (point) - The location where the electrical service provider ownership ends, and the customer ownership begins.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) electricalUtilityFeatureType - The type of electrical utility feature, i.e., eDemarcationPoint.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.

h) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., electrical.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) outsideProvider - The name of the outside provider for the Utility Feature. Value, i.e., owner of point may be 3rd party company.
n) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
o) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., electrical, etc.

CLJN.CL.Feat_ESupportStructure (point) - The location of a structural framework that holds electric devices in an elevated position.

a) circuitId - An operator generated identifier locally used to reference a specific electrical circuit. (Data can be found in Geodatabase, i.e., RG2, FC1, CHB, IND, etc. or contact PWD GIS Office)
b) configurationType - The cable mounting configuration on the pole or tower. Domain value, i.e, armless, crossarmEqal, crossarmUnequal, shortArm, vertical, other, tbd, unknown, etc.
c) contractNumber - The contract number associated with the feature.
d) dateInService - The date the utility equipment was put in service.
e) electricalUtilityFeatureType - The type of electrical utility feature i.e., eSupportStructure.
f) facilityNumber - Asset number used for visual identification of the facility.
g) featureDescription - The narrative describing the feature. (Review current data for description)
h) featureName - The common name of the feature. (Review current data for common name)
i) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
j) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
k) heightAboveSurfaceLevel - The vertical distance measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature in feet.
l) heightAboveSurfaceLevelUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
m) materialType - The material composition of the feature. Domain value, i.e., cement, fiberglass, log, metal, steel, wood, etc.
n) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., electrical.
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

p) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
q) serialNumber - Physical ID on pole that is a unique identifier added to pole on label by contractor/shop.
r) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., electrical, etc.

CLJN.CL.Feat_ESurfaceStructure - The location of a structural framework that holds electric devices in a position at or near the ground surface.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) electricalStructureType - The type of electrical feature. Domain values i.e., electricalCabinet, handHole, junctionBox, manhole, etc.
d) electricalUtilityFeatureType - The type of electrical utility feature i.e., eSurfaceStructure.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The common name of the feature. (Review current data for common name)
i) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
j) mediaId - gpsDataCollected
k) MetadataId - metaID000072
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc. utilityNetworkSubtype

CLJN.CL.Feat_EAnchorGuy (point) - The location of a wire or set of wires running from the top of the pole to an anchor installed in the ground and consist of wires, appropriate fastenings and the anchor.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) electricalUtilityFeatureType - The type of electrical utility feature, i.e., eAnchorGuy.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.

h) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., electrical.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., electrical, etc.

CLJN.CL.Feat_EUgEnclosureAccess (point) - The location of an electrical access point to the related electrical underground enclosure.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) electricalUtilityFeatureType - The type of electrical utility feature i.e., eUgEnclosureAccess.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
h) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., electrical.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., electrical, etc.

1.4.10 Feature Dataset CLJN.CL.Utilities_Pol

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.PolUtilNode _OOwsSystem (point) - A filtering device placed in the fuel stream specifically to remove oil and water from the fuel.

a) contractNumber - The contract number associated with the feature.
b) dateInService The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
j) polNetworkSubType - The subtype of POL network in which this feature participates. Domain values i.e., contaminatedMedia, b5, automotiveDiesal, etc.
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

CLJN.CL.PolUtilNode_OValve (point) -The location of a network component used to control flow, pressure, and level within fueling systems.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) depth - The distance, measured vertically downward to the base in inches.
d) depthUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
f) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
g) facilityNumber - Asset number used for visual identification of the facility.
h) featureDescription - The narrative describing the feature. (Review current data for description)
i) featureName - The common name of the feature. (Review current data for common name)
j) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) polNetworkSubType - The subtype of POL network in which this feature participates. Domain values i.e., jetA, kerosene,

marineDiesel, jp5, automotiveDiesel, etc.
o) polNodeType - The type of POL network node that this feature represents i.e., oValve, etc.
p) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
q) valveMaterial - The material composition of the valve. Domain values, i.e., ductileIron, carbonSteel, etc.
r) valveType - The normal status or operating position of the valve. Domain values i.e., check, gate, etc.

CLJN.CL.PolUtilNode_OMeter (point) - The location of a device that measures the volumetric flow rate of fuel passing through the meter.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) isAmi - Description of meter - meter is an AMI or smart meter. Yes / No
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) meterType - The type of meter. Domain valves i.e., diaphragm, orifice, rotary, other, tbd, etc.
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, AmeriGas, etc., etc.
m) polNetworkSubType - The subtype of POL network in which this feature participates. Domain values i.e., jetA, kerosene, marineDiesel, jp5, automotiveDiesel, contaminatedMedia, etc.
n) polNodeType - The type of POL network node that this feature represents i.e,. oMeter

CLJN.CL.PolUtilNode_OTank (point) -The location of a container for storage of POL products at atmospheric pressure.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing,

recreational, training, water, etc.
g) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
h) locatedUnderground - Yes / No
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) nominalCapacity - The numeric volume of the feature when filled to its design capacity.
l) nominalCapacityUom - The unit of measure of the like named value. Domain values i.e., usgallon
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
o) polNetworkSubType - The subtype of POL network in which this feature participates. Domain values i.e., jetA, kerosene, marineDiesel, jp5, automotiveDiesel, contaminatedMedia, etc.
p) secondaryContainment - Indicates the storage tank has a secondary containment area that contains spills. Domain values i.e., concreteVault, doubleBottom, plasticPanSystem, other, etc.
q) polNodeType - The type of POL network node that this feature represents. Domain values, i.e, (oTank)
r) secondaryContainment - Indicates the storage tank has a secondary containment area that contains spills, i.e., spillPan, etc.
s) storageTankProduct - The product contained in the storage tank. Domain values i.e., automotiveDiesel, bf5, dielectricOil, diesel, ethanol, gasoline, heatingOilUnspecified, jp, marineDiesel, propane, reclaimedFuel, usedCookingOil, usedFuel, usedOil, etc.
t) tankTopHeight - The top of the tank reservoir measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature.
u) tankTopHeightUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.

CLJN.CL.PolUtilNode_ODispenser (point) - The location of a machine at a fueling station that is used to pump fuel into vehicles or Aerospace Ground Equipment (AGE).w

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. Type of dispenser i.e., Marine, Aircraft, Automobile, HeavyEquipment, POV, GOV, etc.
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) functionalArea - The principle activity within a landuse

area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) networkType - The primary type of utility network to which this feature relates. Domain values i.e., (pol)
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
m) polNetworkSubType - The subtype of POL network in which this feature participates. Domain values i.e., jetA, kerosene, marineDiesel, jp5, automotiveDiesel, contaminatedMedia, etc.
n) polNodeType - The type of POL network node that this feature represents i.e., oDispenser

CLJN.CL.PolUtilSegment (polyline) - The location of a linear feature, particularly a pipeline, used for the conveyance of petroleum, oil, and lubricants (POL) product. All polylines shall be drawn in the direction of flow with no breaks except for what is naturally occurring such at nodes, etc.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) depth - The distance, measured vertically downward to the base in inches.
d) depthUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
f) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
g) facilityNumber - Asset number used for visual identification of the facility.
h) featureDescription - The narrative describing the feature. (Review current data for description)
i) featureName - The common name of the feature. (Review current data for common name)
j) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
k) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
l) materialType - The material composition of the feature. Domain values i.e., cooper, carbonSteel, etc.
m) mediald - gpsDataCollected
n) MetadataId - metaID000072
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
p) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
q) polNetworkSubType - The subtype of POL network in which this feature participates. Domain values i.e., jetA, kerosene, marineDiesel, jp5, automotiveDiesel, contaminatedMedia, etc.

1.4.11 Feature Dataset CLJN.CL.Utilities_Sewer

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.Feat_SDemarcationPoint (point) - The location where the wastewater service provider ownership ends, and the customer ownership begins.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) networkType - The primary type of utility network to which this feature relates. Domain values i.e., wastewater, etc.
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) outsideProvider - The name of the outside provider for the Utility Feature. Value, i.e., owner of point may be 3rd party company.
m) owner - The entity that owns the feature. Domain values, i.e., ppv, usmc, usn, leased, federalOther, etc.
n) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates. Domain values i.e., domesticSewage, oilyWaste, industricalWaste, etc.
o) wastewaterNodeType - The type of water utility feature i.e., sDemarcationPoint.

CLJN.CL.WastUtilNode_SMeter (point) - The location of a device or set of devices used to measure the flow of wastewater.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)

e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) isAmi - An indicator of whether or not the meter is an AMI or smart meter. Yes / No
h) Manufacturer - The name of the manufacturer of the feature.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) meterType - The type of meter. Domain valves i.e., diaphragm, orifice, rotary, other, tbd, etc.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates. Domain values i.e., domesticSewage, oilyWaste, industricalWaste, etc.
o) wastewaterNodeType - The type of wastewater network node that this feature represents i.e., smeter.

CLJN.CL.Feat_SScadaSensor (point) - The location of a device that is used to remotely measure the status of wastewater network components as part of a Supervisory Control and Data Acquisition (SCADA) system.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., wastewater, etc.
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
l) utilityNetworkSubType - The subtype of wastewater network in which this feature participates. Domain values i.e., domesticSewage, etc.
m) wastewaterUtilityFeatureType - The type of water utility feature i.e., sScadaSensor

CLJN.CL.Feat_SUgEnclosureAccess (point) -The location of a wastewater access point to the related wastewater underground enclosure.

a) contractNumber - The contract number associated with the

feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
h) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
i) invertElevation - The elevation of the bottom of the feature in inches.
j) invertElevationUom - The invert elevation. Domain values, i.e., length equal to .0254, inch, etc.
k) numberOfPipes - The number of pipes connecting to the manhole.
l) mediald - gpsDataCollected
m) MetadataId - metaID000072
n) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., wastewater.
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
p) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
q) rimElevation - The elevation at the top of the feature in feet.
r) rimElevationUom - The unit of measure for rim elevation. Domain values i.e. measurement equal to 0.3048 metres, etc.
s) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., wastewater, etc.
t) wastewaterUtilityFeatureType - The type of water utility feature i.e., sUgEnclosureAccess.

CLJN.CL.WastUtilNode_SCleanOut (point) - The location of a wastewater device access point in a lateral used for maintenance purposes.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
g) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing,

recreational, training, water, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) materialType - The material composition of the feature. Domain values i.e., copper, ductileIron, fiber, fiberglassReinforcedPolyester, galvanizedIron, galvanizedSteel, PVC, terracotta, etc.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, etc.
o) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., scleanOut.

CLJN.CL.WastUtilNode_SFitting (point) - The location of a mechanical device on the wastewater system that caps or plugs a single pipe, or connects two or more pipes.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
d) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) fittingMaterial - The material of the pipe fitting. Domain values i.e., Domain values i.e., copper, ductileIron, fiber, fiberglassReinforcedPolyester, galvanizedIron, galvanizedSteel, PVC, steel, etc.
i) fittingType - The type of pipe fitting. Domain values, i.e., bend, reducer, tee, plug, etc.
j) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
k) mediald - digitized
l) MetadataId - metaID000071
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
o) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, etc.
p) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., sFitting.

CLJN.CL.WastUtilNode_SSystemValve (point) - The location of a device that regulates, directs, or controls the flow of wastewater.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
d) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
m) valveMaterial - The material composition of the valve. Domain values, i.e., ductileIron, carbonSteel, etc.
n) valvePosition - The normal status or operating position of the valve. Domain values i.e., normallyClosed, normallyOpen, other, tbd, unknown.
o) valveType - The normal status or operating position of the valve. Domain values i.e., flowControl, butterfly, check, gate, postIndicator, etc.
p) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, etc.
q) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., sSystemValve.

CLJN.CL.WastUtilNode_SReleaseValve (point) - The location of a wastewater device used to purge air from a force main.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
d) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072

k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
m) valveMaterial - The material composition of the valve. Domain values, i.e., ductileIron, carbonSteel, etc.
n) valveType - The normal status or operating position of the valve. Domain values i.e., airRelease.
o) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, etc.
p) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., sReleaseValve.

CLJN.CL.WastUtilNode_SGreaseTrap (point) - The location of a tank which separates grease from water, collects the grease for removal, and allows the water to exit.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
j) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
k) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, etc.
l) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., sGreaseTrap.

CLJN.CL.WastUtilNode_STank (point) - The location of a container for storage of products associated with the wastewater network.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) diameter - Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.5, 1.75, 2, etc.
d) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription- The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review

current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
j) hasSecondaryContainment - Yes / No
k) materialType - The material composition of the feature. Domain values i.e., concrete, etc.
l) nominalCapacity - The unit total numeric capacity in gallons.
m) nominalCapacityUom - The unit of measure of the like named value i.e., usGallon
n) mediald - gpsDataCollected
o) MetadataId - metaID000072
p) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
q) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc
r) storageTankProduct - The product contained in the storage tank. Domain values i.e., oilyWastewater, rawWater, wasteFuel.
s) volume - The volumetric capacity of the feature
t) volumeUom - The unit of measure of the like named value i.e., usGallon
u) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, oilyWaste, etc.
v) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e.,stank.
w) width - The dimension of a feature in feet.
x) widthUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.

CLJN.CL.WastUtilNode_SOilWateSeparator (point) - The location of a device or structure placed in the wastewater stream to separate water from oil products.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) nominalCapacity - The unit total numeric capacity in gallons.
j) nominalCapacityUom - The unit of measure of the like named value i.e., usGallon
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

l) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
m) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, oilyWaste, etc.
n) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., sOilWaterSeparator.

CLJN.CL.WastUtilNode_SPump (point) - The location of a piece of wastewater equipment that adds energy to a fluid being conveyed through a pipe or other closed conduit.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) isMainPump - Yes / No
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
l) pumpType - Type of pump. Domain values i.e., liftstation, booster, submersible, grinder, etc.
m) ratedFlow - The common rate of flow of each pump.
n) ratedFlowUom - The rate of flow for each pump. Domain value i.e., galMin
o) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, etc.
p) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., sPump.

CLJN.CL.Feat_SPumpStation (polygon) - The location of a facility that collects and discharges wastewater via pumps.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature.
e) featureDescription - The narrative describing the feature. (Review current data for description)
f) featureName - The common name of the feature. (Review current data for common name)
g) functionalArea - The principle activity within a landuse

area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
h) hasGeneratorBackup - Yes / No
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) isMainPump - Yes / No
l) nominalCapacity - The station total capacity in gallons.
m) nominalCapacityUom - The unit of measure of the like named value i.e., usGallon
n) numberOfPumps - The number of pumps in the feature.
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
p) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
q) pumpStationType - Type of pumping station. Domain value i.e., pumpingStation, ejectorStation, liftStation, etc.
r) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, etc.
s) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., sPumpStation.

CLJN.CL.Feat_SSepticTankPoint (point) - The location of a small-scale anaerobic digester and leach field designed to treat wastewater from an individual facility, and is not connected to the wastewater collection system.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) materialType - The material composition of the feature. Domain values i.e., plastic, concrete, fiberglass, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., wastewater.
k) nominalCapacity - The unit total numeric capacity in gallons.
l) nominalCapacityUom - The unit of measure of the like named value i.e., usGallon
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) secondaryContainment - Indicates the storage tank has a secondary containment area that contains spills. Domain values i.e., concreteVault, doubleBottom, plasticPanSystem, other, etc.
o) septicTankType - The type of septic tank. Domain values, i.e., mound, septicTank, etc.
p) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e.,

domesticSewage, etc.
q) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
r) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, oilyWaste, etc.
s) wastewaterNodeType - The type of wastewater network node that this feature represents. i.e., tbd

CLJN.CL.WastUtilSegment (polyline) - The location of a feature used for the conveyance of wastewater. All polylines shall be drawn in the direction of flow with no breaks except for what is naturally occurring such at nodes, etc.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
d) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) materialType - The material composition of the feature. Domain values i.e., asbestosCement, pvc, etc.
j) invertElevationDownstream - Numeric number of the elevation downstream invert in inches.
k) invertElevationDownstreamUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, etc.
l) invertElevationUpstream - Numeric number of the elevation upstream invert in inches.
m) invertElevationUpstreamUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, etc.
n) isLined - Yes / No
o) mediald - gpsDataCollected
p) MetadataId - metaID000072
q) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
r) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
s) pipeType - The type of pipe used. Domain values i.e., box, circular, pipArch, tbd, etc.
t) slope - The slope of the bottom of the subject item expressed as a percentage.
u) wastewaterNetworkSubType - The subtype of wastewater network in which this feature participates, i.e., domesticSewage, etc.
v) wastewaterSegmentType - The type of wastewater network segment that this feature represents. Domain values i.e., sForceMain, sGravityMain, sLateralLine, sPressurizedServiceLine, etc.

1.4.12 Feature Dataset CLJN.CL.Utilities_Stormwater

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.StormUtilNode_SwInlet (point) - The location where stormwater is collected and received into the utility system.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. Values i.e., CATCHBASIN, ENDWALL, HEADWALL, INLET, ETC.
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) inletCoverType - The type of inlet cover. Domain values i.e., Domain values i.e., concrete, metalGate, etc.
h) inletDiameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.5, 1, 4, etc.
i) inletDiameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
j) inletOpeningSize - The size of the inlet opening in inches.
k) inletOpeningSizeUom - The unit of measure for the inlet opening size. Domain values, i.e., 0.0254 metres, inches etc.
l) invertElevation - The elevation of the bottom of the feature in inches.
m) invertElevationUom - The invert elevation. Domain values, i.e., length equal to .0254, inch, etc.
n) materialType - The material composition of the feature. Domain values i.e., concrete, steel, pvc, etc.
o) mediald - gpsDataCollected
p) MetadataId - metaID000072
q) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
r) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
s) rimElevation - The elevation at the top of the feature in feet.
t) rimElevationUom - The unit of measure for rim elevation. Domain values i.e. measurement equal to 0.3048 metres, etc.
u) stormwaterInletType - The type of stormwater inlet feature. Domain values i.e., catch basin, curbinlet, grateInlet, weirInlet, etc.
v) stormwaterNodeType - The type of stormwater network node that this feature represents. Domain values i.e., swCatchBasin, swCleanout, swDownspout, swInlet, swInfall, etc.

CLJN.CL.Feat_SwUgEnclosureAccess (point) - The location of a Stormwater access point to the related Stormwater underground enclosure.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
d) diameterUom- The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. Values i.e., swManhole, etc.
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) invertElevation - The elevation of the bottom of the feature in inches.
j) invertElevationUom - The invert elevation. Domain values, i.e., length equal to .0254, inch, etc.
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) networkType - The type of stormwater network node that this feature represents. Domain values i.e., stormwater.
n) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
o) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
p) rimElevation - The elevation at the top of the feature in feet.
q) rimElevationUom - The unit of measure for rim elevation. Domain values i.e. measurement equal to 0.3048 metres, etc.
r) stormwaterUtilityFeatureType - The type of stormwater utility feature, i.e., swUgEnclosureAccess
s) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., stormwater, etc.

CLJN.CL.StormUtilSeg (polyline) - The location of a feature used for the conveyance of stormwater. For example, a pipeline, culvert, or ditch. All polylines shall be drawn in the direction of flow with no breaks except for what is naturally occurring such at nodes, etc.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
d) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) facilityNumber - Asset number used for visual identification

of the facility.
f) featureDescription - The narrative describing the feature. (Review current data for description)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) invertElevation - The elevation of the bottom of the feature in inches.
j) invertElevationUom - The invert elevation. Domain values, i.e., length equal to .0254, inch, etc.
k) invertElevationDownstream - Numeric number of the elevation downstream invert in inches.
l) invertElevationDownstreamUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, etc.
m) invertElevationUpstream - Numeric number of the elevation upstream invert in inches.
n) invertElevationUpstreamUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, etc.
o) mediald - gpsDataCollected
p) MetadataId - metaID000072
q) openDrainSurface - The surface material of the drain, typically at the bottom of the structure.
r) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
s) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
t) percentSlope - The slope of the bottom of the subject item expressed as a percentage.
u) pipeType - The type of pipe used. Domain values i.e., box, circular, pipArch, tbd, etc.
v) stormwaterSegmentType - The type of stormwater network segment that this feature represents. Domain values i.e., swCulvert, swForceMain, swGravityMain, swLateralLine, swOpenDrain, swSwale, swTrenchDrain, tbd.

CLJN.CL.StormUtilNode_SwOilWateSepa (point) - The location of a device or structure placed in the stormwater stream to separate water from oil products.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service degradationIndex
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
h) isCovered - Yes / No

i) nominalCapacity - The numeric volume of the feature when filled to its design capacity.
j) nominalCapacityUom - The unit of measure of the like named value. Domain values i.e., usgallon
k) operationalStatus - The state of usability of the feature i.e., inService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
m) stormwaterNodeType - The type of stormwater network node that this feature represents. Domain values i.e., swCatchBasin, swCleanout, swDownspout, swInlet, swInfall, etc.

CLJN.CL.Feat_SwRetentionBasinArea (polygon) - The location of a human-created area installed to improve water quality by permanently storing runoff.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) networkType - The type of stormwater network node that this feature represents. Domain values i.e., stormwater.
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
l) stormwaterUtilityFeatureType - The type of stormwater utility feature, i.e. swRetentionBasinArea
m) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., stormwater, etc.

1.4.13 Feature Dataset CLJN.CL.Utilities_Thermal

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.TherUtilNode_TPump (point) - The location of a facility that operates to maintain flow at adequate pressure for the thermal system.

a) contractNumber - The contract number associated with the

feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
h) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
i) pumpElevation - The elevation of the pump feature in feet.
j) pumpElevationUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
k) pumpType - The type of pump.
l) ratedFlow - The numeric flow rating of the pump.
m) ratedFlowUom - The rate of flow for each pump. Domain value i.e., galMin
n) thermalNodeType - The type of thermal network node that this feature represents, tPump.

CLJN.CL.TherUtilNode_TProdStruc (point) - The location of a facility which produce steam, high-temperature water, low-temperature water, dual-temperature water or chilled water.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) heightAboveSurfaceLevel - The vertical distance measured from the lowest point of the base of the feature at ground or water level to the tallest point of the feature in feet.
h) heightAboveSurfaceLevelUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) nominalCapacity - The numeric volume of the feature when filled to its design capacity
l) nominalCapacityUom - The unit of measure for nominal capacity. Domain value i.e., tons, btu, etc.
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.

o) thermalNetworkSubType - The subtype of thermal network in which this feature participates. Domain values i.e., steamSupply, otherSupply, geothermalSupply (well), highTemperatureHotWaterSupply, etc.
p) thermalNodeType - The type of thermal network node that this feature represents, tProductionStructure.
q) thermalProdStrucType - The type of production structure based upon various classifications including methods of transferring heat, piping arrangement, pumping arrangement, or the relative temperature of transferred media. Examples include Boilers, Chillers, Cooling Towers, Heat Pumps, Single/Double pipe systems, Low/Medium/High Temperatures systems, etc.
r) volume - The volumetric capacity of the feature
s) volumeUom - Rate of flow in tons, btu, etc.

CLJN.CL.TherUtilNode_TCondCollector (point) - The location of a thermal related well or a tank that collects condensation.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
h) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
i) thermalNetworkSubType - The subtype of thermal network in which this feature participates. Domain values i.e., chilledWaterReturn, dualTemperatureWaterSupply, geothermalReturn, highTemperatureHotWaterSupply, lowTemperatureHotWaterSupply, steamSupply, etc.
j) thermalNodeType - The type of thermal network node that this feature represents, tCondCollector.

CLJN.CL.TherUtilNode_TSystemValve (point) - The location of a device that regulates, directs, or controls the flow of steam or water.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)

f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
h) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
i) thermalNetworkSubType - The subtype of thermal network in which this feature participates. Domain values i.e., chilledWaterReturn, dualTemperatureWaterSupply, geothermalReturn, highTemperatureHotWaterSupply, lowTemperatureHotWaterSupply, steamSupply, etc.
j) thermalNodeType - The type of thermal network node that this feature represents, tSystemValve
k) valveMaterial - The material composition of the valve. Domain values i.e., steel, etc.
l) valvePosition - The normal status or operating position of the valve. Domain value i.e., normallyClose, normallyOpen, other, tbd, unknown.
m) valveType - The normal status or operating position of the valve. Domain values i.e., reliefValve, flowControl, gate, pressureRegulator, pressureReducing, etc.

CLJN.CL.Feat_TUgEnclosureAccess (point) - The location of a thermal access point to the related thermal underground enclosure.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
h) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
i) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
j) networkType - The primary type of utility network to which this feature relates. Domain values i.e., thermal.
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
m) thermalUtilityFeatureType - The type of thermal utility feature tUgEnclosureAccess.
n) thermalNetworkSubType - The subtype of thermal network in which this feature participates. Domain values i.e., steamSupply, otherSupply, geothermalSupply, highTemperatureHotWaterSupply, etc.

ThermalUtilitySegment (polyline) - The location of a feature used for the conveyance of steam, high-temperature water, low-temperature water, or chilled water. All polylines shall be drawn in the direction of flow with no breaks except for what is naturally occurring such at nodes, etc.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) depth - The distance, measured vertically downward to the base in inches.
d) depthUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
f) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
g) facilityNumber - Asset number used for visual identification of the facility.
h) featureDescription - The narrative describing the feature. (Review current data for description)
i) featureName - The common name of the feature. (Review current data for common name)
j) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
m) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
n) materialType - Type of segment material. Domain values i.e., steel, castiron, etc.
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
p) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
q) pipeType - The type of pipe used. Domain values i.e., box, circular, pipArch, tbd, etc.
r) thermalNetworkSubType - The subtype of thermal network in which this feature participates. Domain values i.e., steamSupply, otherSupply, geothermalSupply, highTemperatureHotWaterSupply, etc.
s) thermalSegmentType - The type of termal network segment that this feature represents. Domain values i.e., tMainLine, tService Line.

1.4.14 Feature Dataset CLJN.CL.Utilities_Water

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a

particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.WateUtilNode_WSystemValve (point) - The location of a device that regulates, directs, or controls the flow of water.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) depth - The distance, measured vertically downward to the base in inches.
d) depthUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
f) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
g) facilityNumber - Asset number used for visual identification of the facility.
h) featureDescription - Utilize CLJN.CL.Feat_WUtilityArea to use Service Area Values i.e., Stone Bay, Onslow Beach, Handnot Point, etc.
i) featureName - The common name of the feature. (Review current data for common name)
j) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
o) turnDirectionToClose - The turn direction to close the valve. Domain values i.e., leftToClose, rightToClose, other, na, tbd, unknown, etc.
p) valveMaterial - The material composition of the valve. Domain values i.e., ductileIron, steel, pvc, etc.
q) valvePosition - The normal status or operating position of the valve. Domain value i.e., normallyClose, normallyOpen, other, tbd, unknown.
r) valveType - The subtype of water network in which this feature participates. Domain values i.e., ball, gate, postIndicator, waterServiceValve, postIndicator, fireHydrantValve, etc.
s) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater, etc.
t) waterNodeType - The type of water network node that this feature represents. Domain values i.e., wAirGap, wControlValve, wFireHydrant, wFitting, wFlushingStation, wHydrant, wMeter, etc.

CLJN.CL.WateUtilNode_WReliefValve (point) - The location of a water related device designed to release when the set pressure is exceeded.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) depth - The distance, measured vertically downward to the base in inches.
d) depthUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 1.75, 2, etc.
f) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
g) facilityNumber - Asset number used for visual identification of the facility.
h) featureDescription - The common name of the feature. (Review current data for common name)
i) featureName - The common name of the feature. (Review current data for common name)
j) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
n) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
o) valveMaterial - The material composition of the valve. Domain values i.e., steel, pvc, etc.
p) valveType - The subtype of water network in which this feature participates. Domain values i.e., wReliefValve.
q) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
r) waterNodeType - The type of water network node that this feature represents. Domain values i.e., wReliefValve

CLJN.CL.WateUtilNode_WPressReduStation (point) - The location of a feature which reduces the pressure from line pressure to the desired operating pressure and can switch from low to high pressure for flushing.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) featureDescription - The common name of the feature. (Review current data for common name)
d) featureName - The common name of the feature. (Review current data for common name)
e) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
f) mediald - gpsDataCollected
g) MetadataId - metaID000072
h) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.

i) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
j) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
k) waterNodeType - The type of water network node that this feature represents. Domain values i.e., wPressureReducingStation.

CLJN.CL.WateUtilNode_WBackPrevDevice (point) - The location of a feature that is used to protect water supplies from contamination or pollution.

a) bfpType - Backflow prevention device type. Domain values i.e., ag, avb, dcva, pvb, rpz, spvb, etc.
b) contractNumber - The contract number associated with the feature.
c) dateInService - The date the utility equipment was put in service.
d) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.75, 2, etc.
e) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
f) featureDescription - The common name of the feature. (Review current data for common name)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
m) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
n) waterNodeType - The type of water network node that this feature represents. Domain values i.e., wBackflowPreventionDevice.

CLJN.CL.WateUtilNode_WMeter (point) - The location of a device used to measure the quantity and/or rate of water flowing through a pipe, which may be the amount of water used by the customer.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.75, 2, etc.
d) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.

e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The common name of the feature. (Review current data for common name)
g) featureName - The common name of the feature. (Review current data for common name)
h) fittingType - The type of pipe fitting. Domain values i.e., bend, tap, cap, other, tbd, etc.
i) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
j) isAmi - The yes or no indicator of whether or not the meter is an AMI or smart meter.
k) mediald - gpsDataCollected
l) MetadataId - metaID000072
m) meterType - The type of meter. Domain values i.e., turbine, rotary, etc.
n) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
o) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
p) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
q) waterNodeType - The type of water network node that this feature represents, wMeter.

CLJN.CL.WateUtilNode_WHydrant (point) - Hydrants not exclusively used for firefighting. Secondary uses are flushing main lines and laterals, filling tank trucks, and providing a temporary water source for construction jobs.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The common name of the feature. (Review current data for common name)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) HydrantPurpose - The purpose of the Hydrant. Values i.e., fireHydant, flushedFDC, YardHydrant, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
l) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.

m) waterNodeType - The type of water network node that this feature represents. Domain values i.e., whHydrant.

CLJN.CL.WateUtilNode_WFireHydrant (point) a valve connection on a water supply system having one or more outlets and that is used in firefighting to supply hose and fire department pumpers with water.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.5, 1.75, 2, etc.
d) diameter1 - The diameter of the outlet.
e) diameter2 - The diameter of the outlet.
f) diameter3 - The diameter of the outlet.
g) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
h) facilityNumber - Asset number used for visual identification of the facility.
i) featureDescription - The common name of the feature. (Review current data for common name)
j) featureName - The common name of the feature. (Review current data for common name)
k) fireConnectionType - The yes or no indicator of whether or not the fire hydrant is a fire protection connection. Yes or No
l) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
m) hydrantNumber - The equipment number as designated by the fire department that is primarily responsible for the fire hydrants operation and maintenance.
n) inletDiameter - The diameter of the inlet.
o) inletDiameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
p) mediald - gpsDataCollected
q) MetadataId - metaID000072
r) isFireConnection - The yes or no indicator of whether or not the fire hydrant is a fire protection connection. Yes or No
s) outletDiameter - The diameter of the outlet.
t) outletDiameter1 - The diameter of the outlet.
u) outletDiameter2 - The diameter of the outlet.
v) outletDiameter3 - The diameter of the outlet.
w) outletDiameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
x) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
y) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
z) waterNodeType - The type of water network node that this feature represents, wFireHydrant.

CLJN.CL.WateUtilNode_WFitting (point) - The location of a mechanical device that connects two or more pipes, or caps or plugs a single pipe, on the water system.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, 1, 1.25, 1.5, 1.75, 2, etc.
d) diameter1 - The diameter of the outlet.
e) diameter2 - The diameter of the outlet.
f) diameter3 - The diameter of the outlet.
g) diameter4 - The diameter of the outlet.
h) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
i) facilityNumber - Asset number used for visual identification of the facility.
j) featureDescription - The common name of the feature. (Review current data for common name)
k) featureName - The common name of the feature. (Review current data for common name)
l) fittingType - The type of pipe fitting. Domain values i.e., bend, cap, tee, etc.
m) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
n) mediald - digitized
o) MetadataId - metaID000071
p) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
q) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
r) waterNodeType - The type of water network node that this feature represents. Domain values i.e., wfitting.
s) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.

CLJN.CL.WateUtilNode_WPump (point) - The location of a water related piece of equipment that adds energy to a fluid, such as water, being conveyed through a pipe or other closed conduit.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The common name of the feature. (Review current data for common name)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) mediald - gpsDataCollected
h) MetadataId - metaID000072
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
j) ownerName - The name of the item owner, i.e., MCB CL, MCCS,

PPV, Company Name, etc.
k) pumpType - Type of pump. Domain values i.e., booster, submersible, etc.
l) ratedFlow - The common rate of flow of each pump.
m) ratedFlowUom - The rate of flow for each pump. Domain value i.e., galMin
n) waterNodeType - The type of water network node that this feature represents. Domain values i.e., wpump.
o) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.

CLJN.CL.WateUtilNode_WStorageStructure (point) - The location of a facility that store large volumes of water.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Elevation - The elevation from a specified vertical datum to the highest point on a feature.
d) elevationUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The common name of the feature. (Review current data for common name)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
j) groundElevation - The elevation of the ground at the location of the item in feet.
k) invertElevation - The elevation of the bottom of the feature in feet.
l) mediald - gpsDataCollected
m) MetadataId - metaID000072
n) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
o) overflowElevation - The elevation of the overflow device (i.e., pipe invert).
p) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
q) secondaryContainment - Indicates the storage tank has a secondary containment area that contains spills. Domain values i.e., concreteVault, doubleBottom, plasticPanSystem, other, etc.
r) storageTankProduct - The product contained in the storage tank.
s) storageTankType - The primary type of storage tank.
t) topElevation - The elevation at the top of the feature.
u) topElevationUom The unit of measure Domain values i.e. 0.3048 metres, feet, etc.

v) volume - The volumetric capacity of the feature in usgallons.
w) volumeUom - Unit of measure in usgallons
x) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
y) waterNodeType - The type of water network node that this feature represents. Domain values i.e., wstorageStructure.
z) width - The dimension of a feature in feet.
aa) widthUom - The unit of measure Domain values i.e. 0.3048 metres, feet, etc.

CLJN.CL.Feat_WUgEnclosureAccess (point) - The location of a water access point to the related water underground enclosure.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.5, 1.75, 2, etc.
d) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) facilityNumber - Asset number used for visual identification of the facility.
f) featureDescription - The common name of the feature. (Review current data for common name)
g) featureName - The common name of the feature. (Review current data for common name)
h) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
i) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
j) lidDiameter - Diameter of the lid or cover that allows access to the manhole.
k) lidDiameterUom - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 2, etc.
l) lidMaterial - Material type of the manhole access lid or cover.
m) mediald - gpsDataCollected
n) MetadataId - metaID000072
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
p) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
q) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
r) waterUtilityFeatureType - The type of water utility feature i.e., wUgEnclosureAccess.

WateUtilNode_WSource(point) - A source of water intake to the water system including reservoirs, natural water bodies, wells, and/or feeds from external water networks. Do not delete potable from any feature

class, please attribute as removed or AIP.

a) abandonedDate - The date the feature was abandoned - see feature name to add contract number for abandoned.
b) contractNumber - The contract number associated with the original construction of this feature.
c) dateInService - The date the utility equipment was put in service.
d) facilityNumber - Asset number used for visual identification of the facility.
e) featureDescription - The common name of the feature. (Review current data for common name)
f) featureName - The common name of the feature. Until such a time that the well is abandoned or removed. (Add contract number associated with removal or abandonment of water well)
g) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
k) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
l) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
m) removedDate - Enter Remove date; however, do not delete water well from well feature class. (Attribute contract number to remove well in featureName)
n) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
o) waterNodeType - The type of water network node that this feature represents. Domain values i.e., wSource.
p) waterSourceType - Source of water, well.

CLJN.CL.Feat_WScadaSensor (point) - The location of a device that is used to remotely measure the status of water network components as part of a Supervisory Control and Data Acquisition (SCADA) system.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The common name of the feature. (Review current data for common name)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities,
g) familyHousing, recreational, training, water, etc.
h) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground,

elevated, semiBuried, underground, etc.
i) mediald - gpsDataCollected
j) MetadataId - metaID000072
k) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., water.
l) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., water, etc.
o) waterUtilityFeatureType - The type of water utility feature is wScadaSensor.

CLJN.CL.Feat_WDemarcationPoint (point) - The location where the water service provider ownership ends, and the customer ownership begins.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The common name of the feature. (Review current data for common name)
e) featureName - The common name of the feature. (Review current data for common name)
f) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
g) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
h) mediald - gpsDataCollected
i) MetadataId - metaID000072
j) networkType - The primary type of utility network to which this feature relates. Domain values, i.e., water.
k) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
l) outsideProvider - The name of the outside provider for the Utility Feature.
m) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
n) utilityNetworkSubtype - The primary subtype of utility to which this feature relates. Domain values i.e., water, etc.
o) waterUtilityFeatureType - The type of water utility feature is wDemarcationPoint.

CLJN.CL.WaterUtilitySegment (polyline) - The location of a feature used for the conveyance of water.

a) contractNumber - The contract number associated with the feature.
b) dateInService - The date the utility equipment was put in service.
c) depth - The distance, measured vertically downward to the base in inches.

d) depthUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
e) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.5, 1.75, 2, etc.
f) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
g) elevation - The elevation at the top of the feature.
h) elevationUom - The elevation unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
i) facilityNumber - Asset number used for visual identification of the facility.
j) featureDescription - The narrative describing the feature. (Review current data for description)
k) featureName - The common name of the feature. (Review current data for common name)
l) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
m) groundConfiguration - The configuration of the asset in relationship to the ground. Domain values i.e., aboveground, elevated, semiBuried, underground, etc.
n) invertElevationDownstream - Numeric number of the elevation downstream invert in inches.
o) invertElevationDownstreamUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, etc.
p) invertElevationUpstream - Numeric number of the elevation upstream invert in inches.
q) invertElevationUpstreamUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, etc.
r) lateralSegmentType - The type of lateral water network segment that this feature represents. Domain values i.e., wDomesticLateral, wFireProtectionLateral, wHydrantLateral, wInlineStorageLateral, wIrrigationLateral, wTransportPipeLateral, etc.
s) materialType - The material composition of the feature. Domain values i.e., pvc, tbd, etc.
t) mediald - gpsDataCollected
u) MetadataId - metaID000072
v) operationalStatus - The state of usability of the feature i.e., inService, notInService, abandoned, etc.
w) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
x) waterNetworkSubType - The subtype of water network in which this feature participates. Domain values i.e., fireProtectionWater, nonPotableWater, potableWater, rawWater, saltWater.
y) waterSegmentType - The type of wastewater network segment that this feature represents. Domain values i.e., wDistributionMain, wGravityMain, wLateral, wTransmissionMain

1.4.15 Feature Dataset CLJN.CL.Wells

Locate, GPS and collect attribute data as specified for each feature listed with (GPS) accuracy as described in paragraph "Global Positioning System (GPS) Data Collection". Attribute fields may be associated with Domains, which are utilized to constrain the values allowed in a particular field, attribute table or feature class. Domains must be utilized when populating the feature where required.

CLJN.CL.WellPoint - (point) - The man-made vertical excavation penetrating the surface of the Earth used collect environmental samples or monitor fluid or gas characteristics, inject fluids, gases or thermal energy into the subsurface, or extract contamination or other impurities from the subsurface. *(Potable Water Wells used for water distribution are not to be deleted from the this feature class, if they are demolished or AIP, the contract number utilize to make any changes should be attributed in featureName and the operation status should be changed to removed)*

a) abandonedDate - The date the feature was abandoned - see feature name to add contract number for abandoned.
b) builtDate - The calendar date on which the original construction was completed for a facility.
c) contractNumber - The contract number associated with the original construction of this feature.
d) depth - The distance, measured vertically downward to the base in inches.
e) depthUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
f) Diameter - The diameter of the feature in inches. Domain value i.e., .5, .75, 1, 1.25, 1.5, 2, 3, etc.
g) diameterUom - The diameter unit of measure. Domain values, i.e., 0.0254 metres, inches etc.
h) facilityNumber - Asset number used for visual identification of the facility.
i) featureDescription - Utilize CLJN.CL.Feat_WUtilityArea to use Service Area Values i.e., Stone Bay, Onslow Beach, Handnot Point, etc.
j) featureName - The common name of the feature. Until such a time that the well is abandoned or removed. (Add contract number associated with removal or abandonment of water well)
k) functionalArea - The principle activity within a landuse area. Domain values i.e., utilities, familyHousing, recreational, training, water, etc.
l) locationAccuracy - The location accuracy for the data that was collected and verified i.e., Survey Grade GPS
m) mediald - gpsDataCollected
n) MetadataId - metaID000072
o) operationalStatus - The state of usability of the feature i.e., inService, notInService, removed, etc.
p) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company Name, etc.
q) removedDate - Enter Remove date; however, do not delete water well from well feature class. *(Attribute contract number to remove well in featureName)*
r) wellCapacity- The total capacity in gallons.
s) wellCapacityUom - The unit of measure of the like named value i.e., usGallon
t) wellPurposeType - The purpose of the well. Domain values extraction.
u) wellResourceType - The resource type which is being extracted, i.e. waterNonPotable.

1.4.16 Feature Dataset CLJN.CL.CadFloorPlan

All new and renovated buildings or structures shall be required to have a

linear representation, "clean floor plan", for each floor. A polyline for each level will include exterior and interior walls, doors and windows, exits and stairwells, etc. No nonpermanent fixtures, such as furniture, shall be included. Please note the dataset/feature name may change, however, the attribution requirements will remain the same.

CLJN.CL.CadFloorPlan (polyline) A linear representation of the floor plan representing the outer and inner walls, doors and windows of a building or structure that has been exported into a GIS Feature. (Note - Naming convention may change in the future)

This feature will present all levels, entry, exits, windows, stairwells. No none permanent fixtures, such as furniture should be included.

a) contractNumber - The contract number associated with the feature.
b) builtDate - The date the utility equipment was put in service.
c) facilityNumber - Asset number used for visual identification of the facility.
d) featureDescription - The narrative describing the feature. (Review current data for description)
e) featureName - The narrative describing the feature. (Review current data for description)
f) florid - Floor Level
g) mediald - digitized
h) MetadataId - metaID000071
i) operationalStatus - The state of usability of the feature i.e., inService, notInService, removed, etc.
j) ownerName - The name of the item owner, i.e., MCB CL, MCCS, PPV, Company

1.4.17 Non-Compliance

Failure to follow the specification outlined in this document will result in non-acceptance of data deliverable.

Note: Geospatial data delivery does not replace record drawing requirements.

PART 2 PRODUCTS

Not Used.

PART 3 EXECUTION

Not Used.

-- End of Section --

SECTION 01 91 00.15 22

TOTAL BUILDING COMMISSIONING
08/24

PART 1 GENERAL

1.1 SUMMARY

The Government has hired an independent Commissioning Firm.

This Section specifies the scope of work for the entire Commissioning Team which includes the scope of work for the Lead Commissioning Specialist, Commissioning Specialists, Designers of Record, Installing Contractors, and Equipment Suppliers. Refer to paragraph COMMISSIONING TEAM for descriptions of Commissioning Team members and assigned responsibilities.

1.2 COMMISSIONING LIMITATIONS

Commissioning Requirements specified in this Section are prohibited from fulfilling requirements specified in other Sections. Requirements specified in other Sections are prohibited from fulfilling requirements specified in this Section.

1.3 SYSTEMS TO BE COMMISSIONED

Commissioning must be performed for equipment, systems, and assemblies listed under each systems category in the following paragraphs whether or not listed equipment, system, or assembly is required to be commissioned by any reference related to Sustainability TPC.

Specified equipment, system, and assembly counts are totals that include all commissioned buildings and all construction phases in this project. Refer to items entitled "Sample Strategy" throughout this Section that must be applied to these counts.

1.3.1 Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category

a. Primary Systems.

(1) Up to five chilled water plant each featuring up to two air-cooled chillers with packaged controls, up to two variable speed distribution pumps, and variable-primary distribution.

(2) Up to four hot water plants each featuring up to three fuel-fired condensing boilers each with an integral circulating pump and packaged controls, one boiler master control panel, up to six variable speed distribution pumps, and primary-secondary distribution.

(3) Up to four Building Automation System.

b. Air Handling Systems.

(1) Up to ten air handling units each featuring a variable-air-volume supply air fan, a variable-air-volume relief air fan, a chilled water coil, a hot water coil, air-side energy recovery, and packaged controls.

(2) Up to 16 split system air-conditioning units each featuring packaged controls.

c. Terminal Devices.

(1) Up to 192 variable-air-volume air terminal units each featuring a fan and a hydronic heating coil.

(2) Up to sixteen unit heaters.

(3) Up to six exhaust air fans.

(4) Up to one supply air fans.

1.3.2 Plumbing Systems Category

a. Up to 197 fixtures featuring either a solenoid actuated valve (ex. water closets, urinals, and lavatories) or a local temperature limiting mixing valve (TMV)(ex. showers and manual valve lavatories), excluding fixtures with manually operated valves and no local TMV (ex. mop sinks, food prep sinks, and industrial wash racks).

b. Up to two domestic heating hot water systems each featuring one electric water heater with packaged controls.

c. Up to four domestic heating hot water systems each featuring up to three fuel-fired condensing water heaters each with packaged controls, up to one recirculating pump, and up to one temperature mixing valves.

d. Up to five semi-instantaneous water heaters.

1.3.3 Utility Systems Category

a. Up to one set of whole-building energy utility metering systems.

b. Up to one whole-building water utility metering system.

1.3.4 Electrical Type I Systems Category

a. Power - all grounding systems.

b. Power - all main distribution panels.

c. Power - all main transformers.

d. Power - all motor control centers.

e. Power - all panelboards.

f. Power - all step-down transformers.

g. Power - all transient voltage surge protective devices.

1.3.5 Electrical Type II Systems Category

a. Lighting - all daylighting control systems.

b. Lighting - all emergency egress systems, control devices, and control systems.

c. Lighting - all exit systems, control devices, and control systems.

d. Lighting - all exterior systems, control devices, and control systems.

e. Lighting - all interior systems, control devices, and control systems.

f. Photovoltaic - up to one system each featuring packaged controls.

g. Power systems - all automatic receptacles controls.

1.3.6 Building Envelope Systems, Components, and Assemblies Category

a. All building envelope systems including curtain walls, exterior penetrations, exterior air barrier assemblies, exterior windows, exterior doors, and skylights.

b. All roofing including low sloped roofs and steep sloped roofs.

1.4 COMPLEX SYSTEMS

Complex systems are defined as the following systems categories as listed under paragraph SYSTEMS TO BE COMMISSIONED with appropriate qualifiers and are subject to more stringent requirements as specified in this Section.

a. All equipment, systems, and assemblies listed under item entitled "Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category."

b. All equipment, systems, and assemblies listed under item entitled "Plumbing Systems Category" featuring on-board factory packaged controls such as domestic heating hot water systems, domestic solar heating hot water systems, and service water pressure-booster pump systems. Refer to the following paragraph for definition of equipment featuring on-board factory packaged controls.

c. All equipment, systems, and assemblies listed under item entitled "Utility Systems Category."

Equipment featuring on-board factory packaged controls is defined as equipment that is a complex system as defined in paragraph COMPLEX SYSTEMS which features a controller issuing sophisticated logic-based commands to its internal components to accomplish the intent of Plans and Specifications. This equipment may function as either a stand-alone piece of commissioned equipment or may function as part of a commissioned system. This controller may be equipment mounted or may be remote mounted and may or may not interface with a building control system. Examples of equipment meeting and not meeting this definition are provided in the following paragraphs.

a. Equipment meeting this definition includes chillers, boilers provided with or without master controllers, packaged pumping systems, dedicated outside air systems, packaged rooftop units, computer room air conditioners, and air terminal units.

b. Equipment not meeting this definition includes unitary air-conditioners, packaged terminal air-conditioners, and heat pumps.

c. Equipment not meeting this definition, but requiring demonstration of minimum safe motor speed either prior to or during Functional Performance Testing includes variable frequency drives.

1.5 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 90.1 - IP	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings
ASHRAE 202	(2018) Commissioning Process for Buildings and Systems

GREEN BUILDING INITIATIVE (GBI)

GBI DOD GP Compliance	(2017) GBI Department of Defense Guiding Principles Compliance Program for New Construction

INTERNATIONAL CODE COUNCIL (ICC)

ICC IgCC	(2018) International Green Construction Code

1.6 SUBMITTALS

Commissioning Submittals are not required to be submitted by the Installing Contractor. Exchange of information between the Commissioning Team specified in this Section must still occur.

1.7 COMMISSIONING TEAM

The Commissioning Team is defined as the entity that must perform all Commissioning Activities specified in this Section for systems listed under paragraph SYSTEMS TO BE COMMISSIONED. The Commissioning Team is composed of the Lead Commissioning Specialist, Commissioning Specialists, Designers of Record, Installing Contractors, Equipment Suppliers, and the Contracting Officer's Technical Representative.

1.7.1 Lead Commissioning Specialist

The Lead Commissioning Specialist (CxC) is defined as the entity that must perform all Commissioning Responsibilities assigned in this Section that includes, but is not limited to, coordinating all aspects of the Commissioning Process; managing all Commissioning Specialists; and submitting all Commissioning Plans, schedules, reports, and documentation directly to the Contracting Officer's Technical Representative as modified in this Section.

1.7.2 Commissioning Specialists

Commissioning Specialists are defined as entities that must perform all Commissioning Responsibilities assigned in this Section that includes, but

is not limited to, performing reviews, witnessing that all system components have been installed, that each control device operates, that each equipment piece operates, that complete systems operate, and that interactive systems operate in accordance with Plans and Specifications.

Commissioning Specialists must perform assigned responsibilities for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

1.7.3 Designers of Record

Designers of Record are defined as entities that must act as design professionals responsible for design of their respective system that is subject to Commissioning. Designers of Record must perform all Commissioning Responsibilities assigned in this Section.

1.7.4 Installing Contractors

Installing Contractors are defined as the General Contractor's Superintendent or Project Manager; Quality Control Representative; and Mechanical, Controls, Plumbing, Electrical, Test and Balance, Fire Protection, and Building Envelope Sub-Contractors who provide, install, or construct systems in whole or in part for this contract. The General Contractor must provide a Lead Commissioning Representative to manage all Sub-Contractor Commissioning Representatives and Equipment Suppliers to accomplish all Commissioning Responsibilities assigned in this Section. Each Sub-Contractor must provide a Commissioning Representative to coordinate and perform all Commissioning Responsibilities for commissioned equipment, systems, and assemblies provided as part of their respective contract as directed by the General Contractor. Submission of Commissioning related certifications or qualifications for the Lead Commissioning Representative and Installing Contractor Representatives is not required.

Installing Contractors must perform all Commissioning Responsibilities assigned in this Section that includes, but is not limited to, demonstrating performance of all commissioned equipment, systems, and assemblies provided as part of their respective contract and must provide all necessary materials, services, and labor required for successful demonstration as modified in this Section.

1.7.5 Equipment Suppliers

Equipment Suppliers (ES) are defined as factory authorized start-up technicians or factory representatives knowledgeable with start-up, demonstration, and testing of commissioned equipment featuring on-board factory packaged controls provided as part of their respective contract. Each Equipment Supplier must coordinate and perform all Commissioning Responsibilities assigned in this Section as directed by the General Contractor. Submission of Commissioning related certifications or qualifications for Equipment Suppliers is not required. Refer to paragraph COMPLEX SYSTEMS for definition of equipment featuring on-board factory packaged controls's.

Equipment Suppliers must perform all Commissioning Responsibilities assigned in this Section that includes, but is not limited to,

demonstrating performance of all commissioned equipment provided as part of their respective contract and must provide all necessary materials, services, and labor required for successful demonstration of all commissioned equipment provided as part of their respective contract as modified in this Section.

1.7.6 Installing Contractors and Equipment Suppliers Coordination

Installing Contractors and Equipment Suppliers must coordinate and share demonstration and testing responsibilities specified in this Section for commissioned equipment featuring on-board factory packaged controls. Installing Contractors and Equipment Suppliers must simultaneously perform all aspects of demonstration and testing for these types of systems. Refer to paragraph COMPLEX SYSTEMS for definition of equipment featuring on-board factory packaged controls.

1.7.7 Contracting Officer's Technical Representative

The Contracting Officer's Technical Representative (COTR) represents the Government for all elements of the Commissioning Process. The COTR will serve as the single point of contact with the Lead Commissioning Specialist, will receive all Commissioning Submittals, may attend meetings, and may, but is not required to, witness field inspections and testing specified in this Section.

1.8 COMMUNICATIONS

1.8.1 Communications with the Contracting Officer's Technical Representative

Communication with the Contracting Officer's Technical Representative must be through the Lead Commissioning Specialist who acts as the single direct point of contact for all aspects of the Commissioning Process.

1.8.2 Communications between the Commissioning Team

Communications between the Commissioning Team including, but not limited to, verbal communications, schedule information, and exchange of information specified in this Section, must occur directly between the Commissioning Team without requiring interaction of the Contracting Officer's Technical Representative.

1.9 NUMBER OF BUILDINGS AND CONSTRUCTION PHASING

1.9.1 Number Of Buildings

This project includes four commissioned buildings. Commissioning Services must be provided for only the BATTALION OPERATIONS FACILITY, COMPANY/TEAM FACILITIES, and COMPANY STORAGE BUILDINGS.

a. Commissioning Design Reviews specified in this section must be performed as a single review for each submission inclusive of all commissioned buildings in this project. Refer to item entitled "Commissioning Design Reviews" for additional requirements.

b. Construction Phase Site Observations specified in this Section are inclusive of all commissioned buildings in this project. Refer to item entitled "Construction Phase Site Observations" for additional requirements.

c. Construction Phase Functional Performance Testing must be performed during a single continuous occurrence inclusive of all commissioned buildings for each systems category until completion of testing of all systems listed under respective systems category. Refer to item entitled "Construction Phase Functional Performance Testing" for additional requirements.

d. Post-Construction Phase Site Observations specified are inclusive of all commissioned buildings in this project. Refer to item entitled "Post-Construction Phase Site Observations" for additional requirements.

1.9.2 Construction Phasing

This project's construction is not phased.

1.10 INTERNATIONAL GREEN CONSTRUCTION CODE COMMISSIONING COMPLIANCE

International Green Construction Code (IgCC) Commissioning compliance is required for this project.

1.10.1 General Requirements

All Commissioning Activities listed in ICC IgCC paragraphs 1001.1 through 1001.3.1.3.6, ICC IgCC Informative Appendix I, and ASHRAE 202 as modified in this Section, Commissioning Activities listed in references contained in ICC IgCC's paragraphs and ASHRAE 202 as modified in this Section, and Commissioning Activities specified in this Section must be performed. All Commissioning Activities that are referred to as "optional activities," "guidance," "should activities," "recommendations," "suggested practices," "informative information," or listed as similar designations are mandatory regardless of any qualifiers.

1.10.2 Commissioning Team Responsibilities

The Commissioning Team must, at a minimum, perform all Commissioning Activities specified in the preceding item entitled "General Requirements" and must perform all Commissioning Activities specified in this Section. This Section takes precedence should there be a conflict between requirements listed in this Section and requirements listed in the ICC IgCC, listed in ASHRAE 202, or listed in any of their references.

1.11 SUSTAINABILITY THIRD PARTY CERTIFICATION (TPC) COMMISSIONING COMPLIANCE

Sustainability Third Party Certification (TPC) is required for this project.

1.11.1 General Requirements

All Commissioning Activities listed in all references for pursuing Sustainability TPC as modified in this Section and Commissioning Activities specified in this Section must be performed. All Commissioning Activities that are referred to as "optional activities," "guidance," "should activities," "recommendations," "suggested practices," "informative information," or listed as similar designations are mandatory regardless of any qualifiers and whether or not activity is included as total points toward Sustainability TPC.

1.11.2 Commissioning Team Responsibilities

The Commissioning Team must, at a minimum, perform all Commissioning Activities specified in the preceding item entitled "General Requirements," perform Commissioning Activities listed in the reference for pursuing Sustainability TPC, GBI DOD GP Compliance, as modified in this Section, perform Commissioning Activities listed in all of its references as modified in this Section, and perform Commissioning Activities specified in this Section. This Section takes precedence should there be a conflict between requirements listed in this Section and requirements listed in the reference for pursuing Sustainability TPC or listed in any of its references.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 DESIGN PHASE

3.1.1 Design Phase International Green Construction Code Commissioning Compliance

3.1.1.1 General Requirements

Activities must include, but not be limited to, Design Phase Commissioning Activities listed in ICC IgCC paragraphs 1001.1 through 1001.3.1.3.6, ICC IgCC Informative Appendix I, and ASHRAE 202 as modified in this Section, Design Phase Commissioning Activities listed in references contained in ICC IgCC's paragraphs and ASHRAE 202 as modified in this Section, and Design Phase Commissioning Activities specified in this Section.

3.1.1.2 Lead Commissioning Specialist and Commissioning Specialists Responsibilities

The Lead Commissioning Specialist and Commissioning Specialists must, at a minimum, perform all activities specified under item entitled "Design Phase International Green Construction Code Commissioning Compliance."

3.1.2 Design Phase Sustainability Third Party Certification (TPC) Commissioning Compliance

3.1.2.1 General Requirements

Activities must include, but not be limited to, Design Phase Commissioning Activities listed in the reference for pursuing Sustainability TPC, GBI DOD GP Compliance, as modified in this Section, Design Phase Commissioning Activities listed in all of its references as modified in this Section, and Design Phase Commissioning Activities specified in this Section.

3.1.2.2 Lead Commissioning Specialist and Commissioning Specialists Responsibilities

The Lead Commissioning Specialist and Commissioning Specialists must, at a minimum, perform activities specified in the following paragraphs.

a. The Lead Commissioning Specialist must submit all Design Phase documentation of Commissioning Activities directly to the Suitability TPC organization as modified in this Section.

b. The Lead Commissioning Specialist and Commissioning Specialists must perform all activities specified under item entitled "Design Phase Sustainability Third Party Certification (TPC)."

3.1.3 Design Phase Commissioning Coordination Meeting

3.1.3.1 General Requirements

A Design Phase Commissioning Coordination meeting must be conducted no later than 30 calendar days prior to the first Plans and Specifications submission or no later than 30 calendar days after approval of Commissioning Firm certifications and all Commissioning Specialist certifications, whichever occurs last. Meeting topics must include, but not be limited to, the Commissioning Process, contract requirements, lines of communication, roles and responsibilities, schedules, documentation requirements, and logistics as specified in this Section. Meeting must be conducted by conference call.

3.1.3.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, conduct meeting and prepare meeting minutes complete with Attendance Roster.

3.1.3.3 Designers of Record and Others Responsibilities

Designers of Record attend this meeting. The Contracting Officer's Technical Representative, a User Representative, and a Public Works Department Representative may also attend this meeting.

3.1.4 Design Phase Commissioning Plan

3.1.4.1 General Requirements

The Design Phase Commissioning Plan must be prepared specific to this construction and contents must include, but not be limited to, contents specified in the following paragraphs.

a. Plan purpose.

b. Overview of Commissioning Activities.

c. Commissioning scope.

d. Commissioning Process outline.

e. Detailed description of Commissioning Activities.

f. List of all commissioned equipment, systems, and assemblies.

g. Description of performance criteria.

h. Building information.

i. Contact information for the Lead Commissioning Specialist,

Commissioning Specialists, Designers of Record, and Contracting Officer's Technical Representative.

j. Criteria listing including Unified Facilities Criteria and Building Codes and Standards.

k. Description of Commissioning Team members.

l. Roles and responsibilities.

m. Lines of communication.

n. Documentation requirements.

o. Description of Commissioning Plan distribution during the Design Phase and Construction Phase.

p. Description of Issues and Resolution Logs distribution during the Design Phase and Construction Phase.

q. Description of Commissioning testing document distribution during the Design Phase and Construction Phase.

r. Description of Commissioning report distribution during the Design Phase and Construction Phase.

s. Owner's Project Requirements.

t. Description of the Basis of Design.

u. Description of Plans and Specifications reviews performed by Commissioning Specialists.

v. Description of Plans and Specifications reviews performed by the Contracting Officer's Technical Representative.

w. Examples and descriptions of Site Observation Reports and Issues And Resolution Log.

x. Listing and description of Design Phase and Construction Phase Commissioning meetings.

y. Identification of Commissioning Activities for incorporation into the Project Construction Schedule.

z. Listing of submittals required by Commissioning Specialists.

aa. Examples and description of the development of Pre-Functional Checklists and Functional Performance Test Checklists.

ab. Description of Pre-Functional Checks and Functional Performance Testing complete with sample strategies.

ac. Description of Ductwork Air Leak Test (DALT) field acceptance testing specified in Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC.

ad. Description of Performance Verification Test (PVT) field acceptance testing specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR

HVAC.

ae. Description of Test and Balance (TAB) field acceptance testing specified in Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC.

af. Identification of intervals at which a summary of Functional Performance Testing results will be provided to the Contracting Officer's Technical Representative for concurrence or acceptance.

ag. Listing of Operation and Maintenance Manual requirements.

ah. Description of Systems Manuals.

ai. Description of training requirements.

aj. Description of Final Commissioning Report.

3.1.4.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, prepare and submit the **Design Phase Commissioning Plan** no later than 45 calendar days after approval of Commissioning Specialists certifications.

File one copy of **Approved Design Phase Commissioning Plan** in the Sustainability eNotebook no later than 14 calendar days after receiving approval of the Design Phase Commissioning Plan.

3.1.5 Design Phase Issues And Resolution Log

3.1.5.1 General Requirements

The Design Phase Issues and Resolution Log must be prepared and maintained to track all Commissioning Issues identified by any member of the Commissioning Team. The Design Phase Issues and Resolution Log must be prepared in an electronic format that can be used throughout the Design Phase such that it can be provided to the Government upon request. Design Phase Issues and Resolution Log contents must include, but not be limited to, contents specified in the following paragraphs.

a. Project title and location.

b. Lead Commissioning Specialist's contact information.

c. Issue number.

d. Date issue was discovered.

e. Name of Commissioning Team member identifying the issue.

f. Commissioning Team member responsible for resolving the issue.

g. Current status.

h. Issue description.

i. Pictures of item if available and appropriate.

j. Effects of issue on project or building operation.

k. Possible cause of issue.

l. Proposed resolution.

m. Final resolution and final resolution date.

n. Approvals of issue resolution, including approver's name.

3.1.5.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must prepare and maintain the **Design Phase Issues And Resolution Log** and must submit one electronic copy no later than seven calendar days after the addition of an issue or a change in status of an issue.

3.1.6 Commissioning Design Reviews

3.1.6.1 General Requirements

Commissioning Design Reviews must be performed using Government provided software in accordance with the ICC IgCC and reference for pursuing Sustainability TPC and must include, but not be limited to, review of each submission of the Owner's Project Requirements (OPR), Basis of Design (BOD), and Plans and Specifications specified in the following paragraphs, except for the last submission. Each review must include back-checks of deficiencies identified in preceding reviews. The last submission must include a review of the OPR, BOD, and back-check of deficiencies identified in preceding reviews, but not a complete Commissioning Design Review.

a. First submission: Pre-Final Documents.

b. Second submission: Final Documents.

Commissioning Design Reviews must assess completeness and clarity of the OPR, verify requirements stated in the OPR are addressed in the BOD, and verify Commissioning Aspects of the Plans and Specifications including preparation in accordance with the OPR and BOD. The OPR and BOD are for reference only and do not constitute part of this contract. Commissioning Design Reviews must identify deficiencies of commissioned equipment, systems, and assemblies that include, but not be limited to, deficiencies related to the following paragraphs as applicable to this project.

a. Adverse impacts on proper operation and maintenance.

b. Adequate accessibility for proper testing.

c. Proper specification of performance and testing criteria.

d. Proper specification of relevant control sensor and control device locations.

e. Completely, clearly, and correctly developed control sequences.

3.1.6.2 Commissioning Design Review Reports

A Commissioning Design Review Report must be prepared for each Commissioning Design Review. Each deficiency must be listed individually

and must be separated into categories corresponding to systems categories listed under paragraph SYSTEMS TO BE COMMISSIONED. Commissioning Design Review Report contents must include, but not be limited to, contents specified in the following paragraphs.

a. Project title, project number, and date of review.

b. Executive summary.

c. List of Plans and Specifications reviewed.

d. Deficiency location.

e. Clear description of deficiencies complete with proposed corrective actions.

f. Relevant observations from similar applications.

g. Clarifying questions related to constructability and maintainability if necessary.

Updated Commissioning Design Review Reports must be prepared to include resolution of outstanding issues reached during Commissioning Design Review meetings.

3.1.6.3 Commissioning Design Review Meetings

A Commissioning Design Review meeting must be conducted no later than 14 calendar days after preparation of each Commissioning Design Review Report to discuss proposed corrective actions and to resolve outstanding issues. The Contracting Officer's Technical Representative may attend these meetings. Meeting must be conducted by conference call.

3.1.6.4 Lead Commissioning Specialist Responsibilities

Lead Commissioning Specialist activities must include, but not be limited to, activities specified in the following paragraphs.

a. Prepare and provide Commissioning Design Review Reports to Designers of Record.

b. Conduct Commissioning Design Review meetings.

c. Update Commissioning Design Review Reports.

d. Prepare and submit **Updated Commissioning Design Review Reports** no later than 14 calendar days after each Commissioning Design Review meeting.

3.1.6.5 Commissioning Specialists Responsibilities

Commissioning Specialists activities must include, but not be limited to, performing Commissioning Design Reviews and attending Commissioning Design Review meetings for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.1.6.6 Designers of Record Responsibilities

Designers of Record activities must include, but not be limited to, providing written responses to Commissioning Design Review Reports, attending Commissioning Design Review meetings, implementing revisions to Plans and Specifications resulting from resolution of Commissioning Design Reports, and related activities assigned in other Sections.

3.2 CONSTRUCTION PHASE

3.2.1 Construction Phase International Green Construction Code Commissioning Compliance

3.2.1.1 General Requirements

Activities must include, but not be limited to, Construction Phase Commissioning Activities listed in ICC IgCC paragraphs 1001.1 through 1001.3.1.3.6, ICC IgCC Informative Appendix I, and ASHRAE 202 as modified in this Section, Construction Phase Commissioning Activities listed in references contained in ICC IgCC's paragraphs and ASHRAE 202 as modified in this Section, and Construction Phase Commissioning Activities specified in this Section.

3.2.1.2 Lead Commissioning Specialist and Commissioning Specialists Responsibilities

The Lead Commissioning Specialist and Commissioning Specialists must, at a minimum, perform all activities specified under item entitled "Construction Phase International Green Construction Code Commissioning Compliance."

3.2.2 Construction Phase Sustainability Third Party Certification (TPC) Commissioning Compliance

3.2.2.1 General Requirements

Activities must include, but not be limited to, Commissioning Activities listed in the reference for pursuing Sustainability TPC, GBI DOD GP Compliance, as modified in this Section, Commissioning Activities listed in all of its references as modified in this Section, and Commissioning Activities specified in this Section.

3.2.2.2 Lead Commissioning Specialist and Commissioning Specialists Responsibilities

The Lead Commissioning Specialist and Commissioning Specialists must, at a minimum, perform activities specified in the following paragraphs.

a. The Lead Commissioning Specialist must submit all Construction Phase documentation of Commissioning Activities directly to the Suitability TPC organization as modified in this Section.

b. The Lead Commissioning Specialist and Commissioning Specialists must perform all activities specified under item entitled "Construction Phase Sustainability Third Party Certification (TPC)."

3.2.3 Construction Phase Sequencing

3.2.3.1 Heating, Ventilation, and Air-Conditioning (HVAC) Systems

Heating, ventilation, and air-conditioning (HVAC) systems activities specified in the following paragraphs must be performed as applicable prior to performing Functional Performance Testing of systems listed under item entitled "Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED.

a. All equipment, systems, and assemblies have been completed, cleaned, flushed, disinfected, calibrated, tested, and operate in accordance with Plans and Specifications.

b. All Ductwork Air Leakage Testing (DALT) field work, Test and Balance (TAB) field work, Pre-Final TAB Reports, and related prerequisites have been completed, submitted, and approved in accordance with Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC.

c. All inspections, measurements, and testing of building envelope and roofing systems specified in Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM have been completed, submitted, and approved.

d. All pressure testing, infrared thermography testing, and fog testing of building envelope and roofing systems specified in Section 01 91 19 BUILDING ENCLOSURE COMMISSIONING have been completed, submitted, and approved.

e. All Pre-Functional Checks have been completed, submitted, and approved.

f. Certified TAB Report specified in Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC has been prepared, submitted, and approved.

g. Certified Certificate of Readiness has been completed, submitted, and approved.

All completed Final Functional Performance Test Checklists for commissioned equipment, systems, and assemblies listed under item entitled "Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED must be submitted and approved prior to the Government performing any Performance Verification Testing specified in
Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

3.2.3.2 Electrical Systems

Electrical systems activities specified in the following paragraphs must be performed as applicable prior to performing Functional Performance Testing of systems listed under item entitled "Electrical Type II Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED.

a. All electrical, power generation, and lighting equipment, systems, and assemblies have been completed, calibrated, tested, and operate in accordance with Plans and Specifications.

b. Building Envelope has been enclosed according to contract documents and final construction has been completed.

c. All ceiling tiles, floor coverings, and window coverings have been put

in place.

d. All lamps have completed a minimum 100-hour burn-in period.

e. All furniture has been put in place.

f. Certified Certificate of Readiness has been completed, submitted, and approved.

3.2.4 Construction Phase Scheduling

3.2.4.1 General Requirements

Commissioning Activities and other related activities for inclusion into the Project Construction Schedule must include, but not be limited to, activities specified in the following paragraphs.

a. Perform Construction Phase Commissioning Coordination meeting.

b. Submit and approve completed Pre-Functional Checklists.

c. Submit and approve proposed Functional Performance Test Checklists.

d. Submit and approve final Functional Performance Test Checklists.

e. Perform Construction Phase Site Observations.

f. Perform inspections, measurements, and testing of building envelope and roofing systems specified in Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM.

g. Perform pressure testing, infrared thermography testing, and fog testing of building envelope and roofing systems specified in Section 01 91 19 BUILDING ENCLOSURE COMMISSIONING.

h. Submit and approve Certified TAB Report specified in Section 23 05 93.00 22 TESTING, ADJUSTING, AND BALANCING FOR MECHANICAL SYSTEMS.

i. Submit and approve Certified Certificate of Readiness.

j. Witness Construction Phase Functional Performance Testing.

k. Correct deficiencies discovered during Construction Phase Functional Performance Testing.

l. Re-witness Construction Phase Functional Performance Testing.

m. Government Witness of Performance Verification Testing.

n. Correct deficiencies discovered during Performance Verification Testing.

o. Government Re-witness of Performance Verification Testing.

p. Provide all Systems Manuals contents.

q. Submit and approve completed Systems Manuals.

r. Perform training.

s. Submit and approve Final Commissioning Report.

t. Perform Post-Construction Phase Site Observations.

u. Witness Post-Construction Phase Functional Performance Testing if all requirements and activities for respective system could not be fully or successfully completed during the Construction Phase.

v. Correct deficiencies discovered during Post-Construction Phase Functional Performance Testing.

w. Re-witness Post-Construction Phase Functional Performance Testing.

3.2.4.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must request a current Project Construction Schedule from Installing Contractors no later than at the Construction Phase Commissioning Coordination Meeting and must prepare and provide to Installing Contractors a list of Commissioning Activities for inclusion into the Project Construction Schedule. The Lead Commissioning Specialist must associate each Commissioning Activity to a single construction activity such that if the date of the construction activity changes, the associated Commissioning Activity changes accordingly. List of Commissioning Activities for inclusion into the Project Construction Schedule is not required to be submitted to the Government.

3.2.4.3 Installing Contractors Responsibilities

Installing Contractors must provide a current Project Construction Schedule to the Lead Commissioning Specialist upon receiving request. Installing Contractors must incorporate the list of Commissioning Activities into the Project Construction Schedule and must link each Commissioning Activity to the associated construction activity identified by the Lead Commissioning Specialist such that if the date of the construction activity changes, the associated Commissioning Activity changes accordingly.

Installing Contractors must provide updated Project Construction Schedules to the Lead Commissioning Specialist at least on a monthly basis.

3.2.5 Construction Phase Commissioning Coordination Meeting

3.2.5.1 General Requirements

A Construction Phase Commissioning Coordination meeting must be conducted no later than 90 calendar days after award of construction contract to discuss topics that include, but not be limited to, the Commissioning Process, contract requirements, lines of communication, roles and responsibilities, Commissioning Activities for inclusion into the Project Construction Schedule, documentation requirements, Inspections and Testing, and logistics specified in this Section. Meeting must be conducted by conference call.

3.2.5.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, conduct meeting and prepare meeting minutes complete with Attendance Roster.

3.2.5.3 Installing Contractors and Others Responsibilities

Installing Contractors must attend this meeting. The Contracting Officer's Technical Representative, a User Representative, and a Public Works Department Representative may attend this meeting.

3.2.6 Construction Phase Commissioning Progress Meetings

3.2.6.1 General Requirements

Construction Phase Commissioning Progress meetings must be conducted to discuss topics that include, but not be limited to, unresolved Commissioning Issues, status of items specified to be provided to the Lead Commissioning Specialist, and upcoming Commissioning Activities. Number of Construction Phase Commissioning Progress meetings must be conducted for each systems category as specified in the following paragraphs. Meetings must be conducted by conference call.

a. Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category: Six meetings.

b. Plumbing Systems Category: Two meetings.

c. Utility Systems Category: No meetings.

d. Electrical Type I Systems Category: No meetings.

e. Electrical Type II Systems Category: Two meetings.

f. Building Envelope Systems, Components, and Assemblies Category: Two meetings.

Construction Phase Commissioning Progress meetings are prohibited from being combined with conducting Construction Phase Commissioning Coordination meeting, conducting Site Observations, or witnessing Functional Performance Testing.

3.2.6.2 Commissioning Specialists Responsibilities

Each Commissioning Specialist must, at a minimum, conduct meetings and prepare meeting minutes complete with Attendance Roster for systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing these responsibilities for systems categories assigned to other Commissioning Specialists.

3.2.6.3 Installing Contractors and Others Responsibilities

Installing Contractors must attend these meetings. The Contracting Officer's Technical Representative, a User Representative, and a Public Works Department Representative may attend these meetings.

3.2.7 Construction Phase Interim Commissioning Plan

3.2.7.1 General Requirements

The Construction Phase Interim Commissioning Plan must be prepared and must be an update to the Design Phase Commissioning Plan and contents must include, but not be limited to, contents specified in the following paragraphs.

a. All contents specified for the Design Phase Commissioning Plan.

b. Basis of Design.

c. Contact information for the entire Commissioning Team.

3.2.7.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, prepare and submit the **Construction Phase Interim Commissioning Plan** no later than 30 calendar days after the Construction Phase Commissioning Coordination meeting and no later than 14 calendar days prior to performing construction of the building envelope.

3.2.8 Construction Phase Final Commissioning Plan

3.2.8.1 General Requirements

The Construction Phase Final Commissioning Plan must be prepared and must be an update to the Construction Phase Interim Commissioning Plan and contents must include, but not be limited to, contents specified in the following paragraphs.

a. All contents specified for the Construction Phase Interim Commissioning Plan.

b. All Pre-Functional Checklists.

c. All approved final Functional Performance Test Checklists.

3.2.8.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, perform activities specified in the following paragraphs.

a. Prepare and submit the **Construction Phase Final Commissioning Plan** no later than 30 calendar days prior to performing any Functional Performance Testing.

b. File one copy of **Approved Construction Phase Final Commissioning Plan** in the Sustainability eNotebook no later than 14 calendar days after receiving approval of the Construction Phase Final Commissioning Plan.

3.2.9 Construction Phase Issues And Resolution Log

3.2.9.1 General Requirements

The Construction Phase Issues and Resolution Log must be prepared and maintained to track all Commissioning Issues identified by any member of the Commissioning Team. The Construction Phase Issues and Resolution Log must be prepared in an electronic format that can be used throughout the Construction Phase such that it can be provided to the Government upon request. Construction Phase Issues and Resolution Log contents must include, but not be limited to, contents specified in the following paragraphs.

a. Project title and location.

b. Lead Commissioning Specialist's contact information.

c. Issue number.

d. Date issue was discovered.

e. Name of Commissioning Team member identifying the issue.

f. Commissioning Team member responsible for resolving the issue.

g. Current status.

h. Issue description.

i. Pictures of item if available and appropriate.

j. Effects of issue on project or building operation.

k. Possible cause of issue.

l. Proposed resolution.

m. Final resolution and final resolution date.

n. Approvals of issue resolution, including approver's name.

3.2.9.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must prepare and maintain the **Construction Phase Issues And Resolution Log** and must submit one electronic copy no later than seven calendar days after the addition of an issue or a change in status of an issue.

3.2.10 Pre-Functional Checklists

3.2.10.1 General Requirements

Pre-Functional Checklists must be prepared for all commissioned equipment, systems, and assemblies that are subject to functional performance testing. Pre-Functional Checklist contents must include, but not be limited to, contents for physical inspections that demonstrate construction, installation and start-up of equipment, systems, and assemblies is complete. Refer to item entitled "Pre-Functional Checklists" in item entitled "Inspections and Testing" for more information.

Download example Pre-Functional Checklists for Section 01 91 00.15 TOTAL BUILDING COMMISSIONING at the following location: http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphics-tables. Checklists must contain the same level of detail shown in examples, but are not required to match the format of examples.

3.2.10.2 Lead Commissioning Specialist Responsibilities

Lead Commissioning Specialist must provide blank Pre-Functional Checklists to Installing Contractors. Blank Pre-Functional Checklists are not required to be submitted to the Government.

3.2.10.3 Commissioning Specialists Responsibilities

Commissioning Specialists must prepare Pre-Functional Checklists for all equipment, systems, and assemblies listed under systems categories assigned to them in this Section that are subject to functional performance testing. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.2.11 Functional Performance Test (FPT) Checklists

Functional Performance Test (FPT) Checklists must be prepared for all commissioned equipment, systems, and assemblies demonstrating performance is in accordance with Plans and Specifications as specified in the following paragraphs. A single final FPT Checklist must be prepared for each equipment piece, system, and assembly except that a single final FPT Checklist may be prepared for use with those that have identical features as modified in the following paragraphs. FPT Checklist contents must include, but not be limited to, step-by-step actions and expected results, as modified in the following paragraphs. Refer to item entitled "Construction Phase Functional Performance Testing" for more information.

3.2.11.1 Complex Systems Requirements

FPT Checklists must be prepared for all complex systems as defined in paragraph COMPLEX SYSTEMS. A single FPT Checklist must be prepared for each system except that a single FPT Checklist may be prepared for use with multiple systems that have identical control sequences such as unitary air-conditioners, packaged terminal air-conditioners, and heat pumps.

Contents must include, but not be limited to, contents specified in the following paragraphs and shown in example FPT Checklists for Section 01 91 00.15 TOTAL BUILDING COMMISSIONING available for download at the following location: http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphics-tables. FPT Checklists must contain the same level of detail specified below and as shown in examples, but are not required to match the format of examples.

a. Notable system features including information about such attributes as system sizing and controls to facilitate understanding of system operation.

b. Conclusions and recommendations based on control system feature, point-to-point, actuator, and system operation observations. Conclusions must clearly indicate if system does or does not perform in accordance with requirements of Plans and Specifications. Recommendation must clearly indicate that the system should or should not be accepted by the Government.

c. Test conditions including date, beginning and ending time, and beginning and ending outdoor air conditions.

d. Identification of the equipment involved in the test.

e. Attendees present throughout the entire system test.

f. Control system feature identification including control point

description, embedded/visible type, adjustable/monitoring type, actual value, and setpoint value/alarm range.

g. Point-to-point observations including demonstrating system flow meters and sensors have been calibrated and are correctly displayed on the Operator workstation.

h. Actuator operation observations demonstrating actuator responses to commands from the control system.

i. Variable frequency drive observations demonstrating minimum safe motor speed.

j. System operation observations for system-based testing demonstrating each control sequence, operation mode, and alarm condition resulting from control setpoint manipulation. System operation observations must include, but not be limited to, observations specified in the following paragraphs.

(1) Introduction identifying testing methodology.

(2) As-found conditions prior to system manipulation.

(3) Clear list of test items (step numbers).

(4) Design control sequences or interlocks segmented by unique functions.

(5) Intended test procedures following each segmented sequence or interlock identifying the system manipulation required to initiate system response.

(6) Expected system responses.

(7) Space for comments for each test item.

(8) Pass or fail indication for each test.

Performance Verification Tests prepared by the Controls Contractor as specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC are prohibited from fulfilling requirements of this Section.

3.2.11.2 Plumbing Systems Requirements

FPT Checklists must be prepared for all equipment, systems, and assemblies listed under item entitled "Plumbing Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED.

3.2.11.3 Electrical Type I Systems Requirements

FPT Checklists must not be prepared for equipment, systems, and assemblies listed under item entitled "Electrical Type I Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED.

3.2.11.4 Electrical Type II Systems Requirements

FPT Checklists must be prepared for all equipment, systems, and assemblies listed under item entitled "Electrical Type II Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED. FPT Checklists must be

system-based and demonstrate end-objective performance in accordance with Plans and Specifications. FPT Checklists must not repeat fundamental performance testing such as resistance measurements required in other Sections.

3.2.11.5 Building Envelope Systems, Components, and Assemblies Requirements

FPT Checklists must not be prepared for equipment, systems, and assemblies listed under item entitled "Building Envelope Systems, Components, and Assemblies Category" in paragraph SYSTEMS TO BE COMMISSIONED.

3.2.11.6 Proposed FPT Checklist Meeting and Draft FPT Checklist Meeting

For all complex systems as defined in paragraph COMPLEX SYSTEMS, a Proposed FPT Checklist Meeting and a Draft FPT Checklist Meeting must be conducted for detailed discussions of procedures intended to demonstrate performance is in accordance with Plans and Specifications. Meetings must be conducted by conference call.

3.2.11.7 Lead Commissioning Specialist and Commissioning Specialists Responsibilities

For all equipment, systems, and assemblies other than complex systems as defined in paragraph COMPLEX SYSTEMS, the Lead and Commissioning Specialist must perform respective responsibilities specified in the following paragraphs.

a. The Lead Commissioning Specialist must submit **Final Functional Performance Test Checklists** for each systems category listed under paragraph SYSTEMS TO BE COMMISSIONED for which FPT checklists are required to be prepared. FPT checklists must be submitted as a single submittal for each systems category no later than 30 calendar days prior to testing of any system in the respective systems category.

b. Commissioning Specialists must prepare Final Functional Performance Test Checklists for equipment, systems, and assemblies listed under systems categories assigned to them in this Section for which FPT checklists are required to be prepared. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

For all complex systems as defined in paragraph COMPLEX SYSTEMS, the Lead Commissioning Specialist and Commissioning Specialists must prepare and submit Final Functional Performance Test Checklists in the sequence specified in the following paragraphs. Commissioning Specialists must perform respective responsibilities for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing respective responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

a. Commissioning Specialists must prepare Proposed Functional Performance Test Checklists.

b. The Lead Commissioning Specialist must submit **Proposed Functional Performance Test Checklists** for all complex systems as a single submittal no later than 60 calendar days prior to testing of any complex system.

c. Commissioning Specialists must conduct the Proposed Functional Performance Test Checklist Meeting attended by the Contracting Officer's Technical Representative.

d. Commissioning Specialists must prepare Draft Functional Performance Test Checklists to incorporate input from the Contracting Officer's Technical Representative.

e. The Lead Commissioning Specialist must provide Draft Functional Performance Test Checklists to Installing Contractors and Equipment Suppliers no later than seven calendar days prior to the Draft Functional Performance Test Checklist Meeting.

f. Commissioning Specialists must conduct the Draft Functional Performance Test Checklist Meeting attended by Installing Contractors and Equipment Suppliers. The Contracting Officer's Technical Representative may attend this meeting.

g. Commissioning Specialists must prepare Final Functional Performance Test Checklists to incorporate input from Installing Contractors.

h. The Lead Commissioning Specialist must submit Final Functional Performance Test Checklists for all complex systems as a single submittal no later than seven calendar days after meeting to discuss Draft Functional Performance Test Checklists and no later than 30 calendar days prior to testing of any complex system.

3.2.11.8 Installing Contractors and Equipment Suppliers Responsibilities

Installing Contractors and Equipment Suppliers must attend Draft Functional Performance Test Checklist Meeting.

3.2.12 Construction Submittals

3.2.12.1 General Requirements

Construction Submittals must be reviewed for all commissioned equipment, systems, and assemblies to the extent necessary to verify that equipment, systems, and assemblies are in compliance with Commissioning Aspects of Owner's Project Requirements (OPR), Basis of Design (BOD), and Plans and Specifications as modified in this Section. One review for each commissioned equipment, system, and assembly must be performed coincident with Designers of Record and review must include, but not be limited to, review of shop drawings and equipment performance data. Review of resubmittals is prohibited.

The OPR and BOD are for reference only and do not constitute part of this contract.

3.2.12.2 Construction Submittal Review Reports

A Construction Submittal Review Report must be prepared for all commissioned equipment, systems, and assemblies and contents must include, but not be limited to, contents specified in the following paragraphs.

a. Project title, project number, and date of review.

b. Overview complete goals of the Commissioning-focused submittal review

process.

c. Summary of deficiencies.

d. Ongoing record of all Construction Submittals received and reviewed, list of unresolved deficiencies, and record of communications made to resolve deficiencies.

e. Descriptive outline of reviewed construction submittals complete with the Installing Contractor's submittal designation.

f. Clear description of deficiencies complete with supporting documentation.

3.2.12.3 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist activities must include, but not be limited to, activities specified in the following paragraphs.

a. Provide list of shop drawings and equipment performance data that must be reviewed to Installing Contractors.

b. Prepare and provide Construction Submittal review comments to Designers of Record.

c. Prepare and submit **Construction Submittal Review Reports** no later than seven calendar days after completion of each Construction Submittal review.

3.2.12.4 Commissioning Specialists Responsibilities

Commissioning Specialists must perform reviews of Construction Submittals for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.2.12.5 Designers of Record Responsibilities

Designers of Record activities must include, but not be limited to, receiving and considering for incorporation comments listed in Construction Submittal Review Reports provided by the Lead Commissioning Specialist.

3.2.12.6 Installing Contractors Responsibilities

Installing Contractors must provide all requested Construction Submittals and requested supplemental information to the Lead Commissioning Specialist.

3.2.13 Construction Phase Site Observations

3.2.13.1 General Requirements

Construction Phase Site Observations must be performed as specified in the following paragraphs to verify and document Commissioning Aspects of equipment, systems, and assemblies as specified in this Section. Two eight-hour Construction Phase Site Observations must be conducted for each

systems category that is not specified in the following paragraphs. Specified number of observations are totals that include all commissioned buildings and all construction phases in this project.

Construction Phase Site Observations are prohibited from being combined with witnessing Functional Performance Testing, but may be combined with Pre-Functional Checklist Verification unless indicated otherwise. Purposes of Site Observations specified in the following paragraphs for each systems category may be combined into a single Site Observation.

3.2.13.2 Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category

Site Observations must be performed for the purposes specified in the following paragraphs.

a. Eight eight-hour Site Observations to identify issues that may result in unsuccessful functional performance testing and to verify and document Commissioning Aspects of commissioned equipment, systems, and assemblies listed under this systems category.

b. One eight-hour Site Observation to verify and document HVAC pipe pressure testing.

c. One eight-hour Site Observation to verify and document HVAC pump installation.

3.2.13.3 Plumbing Systems Category

Site Observations must be performed for the purposes specified in the following paragraphs.

a. One eight-hour Site Observation to identify issues that may result in unsuccessful functional performance testing and to verify and document Commissioning Aspects of commissioned equipment, systems, and assemblies listed under this systems category.

b. One eight-hour Site Observation to verify and document Plumbing pipe pressure testing.

c. One eight-hour Site Observation to verify and document Plumbing pump installation.

3.2.13.4 Utility Systems Category

Site Observations must be performed for the purposes specified in the following paragraphs.

a. No Site Observation dedicated to this systems category. Verification and documentation of Commissioning Aspects of commissioned equipment, systems, and assemblies listed under this systems category may be combined with Site Observations for other systems categories.

3.2.13.5 Electrical Type I Systems Category

Site Observations must be performed for the purposes specified in the following paragraphs.

a. Eight eight-hour Site Observations to verify and document Commissioning Aspects and to witness testing performed by independent

testing organizations of commissioned equipment, systems, and assemblies listed under this systems category and listed by the Lead Commissioning Specialist to require on-site verification and documentation by Commissioning Specialists. Independent testing organizations typically use tests readily available from testing associations such as the InterNational Electrical Testing Association (NETA).

3.2.13.6 Electrical Type II Systems Category

Site Observations must be performed for the purposes specified in the following paragraphs.

a. Eight eight-hour Site Observations to identify issues that may result in unsuccessful functional performance testing and to verify and document Commissioning Aspects of commissioned equipment, systems, and assemblies listed under this systems category.

3.2.13.7 Building Envelope Systems, Components, and Assemblies Category

Site Observations must be performed for the purposes specified in the following paragraphs.

a. Eight eight-hour Site Observation to verifya and document that continuous air barrier materials and assemblies are in compliance with requirements of ASHRAE 90.1 - IP while the continuous air barrier is still accessible for inspection and repair.

b. Four eight-hour Site Observation to verify, document, and witness inspections, measurements, and testing of building envelope and roofing systems performed by independent testing agencies and specified in Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM.

c. Four eight-hour Site Observation to verify, document, and witness pressure testing, infrared thermography testing, and fog testing of building envelope and roofing systems performed by independent testing agencies and specified in Section 01 91 19 BUILDING ENCLOSURE COMMISSIONING.

3.2.13.8 Summary Meetings

A Summary Meeting must be conducted at the conclusion of each Site Observation for the purpose of discussing issues discovered during each Site Observation. Meeting must be conducted on-site with all attendees present.

3.2.13.9 Site Observation Reports

A Site Observation Report must be prepared for each Site Observation for the purpose of documenting issues discovered during each Site Observation.

Site Observation Reports for all equipment, systems, and assemblies listed under item entitled "Electrical Type I Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED must include results of testing performed by independent testing organizations that were witnessed by Commissioning Specialists and test results that were not witnessed by Commissioning Specialists.

3.2.13.10 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must provide list of equipment, systems, and assemblies listed under item entitled "Electrical Type I Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED that require on-site verification and documentation by Commissioning Specialists to Installing Contractors.

The Lead Commissioning Specialist must submit **Construction Phase Site Observation Reports** complete with Summary Meeting Attendance Roster no later than seven calendar days after Site Observation.

3.2.13.11 Commissioning Specialists Responsibilities

Commissioning Specialist must perform responsibilities specified in the following paragraphs.

a. Each Commissioning Specialist must be responsible to perform Site Observations, conduct Summary Meetings, and prepare Construction Phase Site Observation Reports for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.2.13.12 Installing Contractors Responsibilities

Installing Contractors must provide Commissioning Specialists access to construction and systems for Site Observations and must attend Summary Meetings.

Installing Contractors must schedule testing to occur in the presence of Commissioning Specialists as specified in the following paragraphs.

a. All equipment, systems, and assemblies listed under item entitled "Electrical Type I Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED and listed by the Lead Commissioning Specialist to require on-site verification and documentation by Commissioning Specialists. Results of testing of equipment, systems, and assemblies listed under item entitled "Electrical Type I Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED must be provided to the Lead Commissioning Specialist that were witnessed by Commissioning Specialists and that were not witnessed by Commissioning Specialists.

b. Pressure testing, infrared thermography testing, and fog testing specified in Section 01 91 19 BUILDING ENCLOSURE COMMISSIONING and inspections, measurements, and testing specified in Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM for equipment, systems, and assemblies listed under item entitled "Building Envelope Systems, Components, and Assemblies Category" in paragraph SYSTEMS TO BE COMMISSIONED. Results of all tests, inspections, and measurements must be provided to the Lead Commissioning Specialist that were witnessed by Commissioning Specialists and that were not witnessed by Commissioning Specialists.

3.2.14 Pre-Functional Checks

Pre-Functional Checks must be performed prior to performing Functional Performance Testing of respective system and activities must include, but not be limited to, activities specified in the following paragraphs.

a. Perform Pre-Functional Checklist Verification.

3.2.14.1 Pre-Functional Checklist Verification

3.2.14.1.1 General Requirements

Pre-Functional Checklist Verification must be performed using Pre-Functional Checklists from the approved Construction Phase Final Commissioning Plan by conducting on-site spot-checks to verify accuracy after receipt of completed Pre-Functional Checklists from Installing Contractors. Verification may be combined with Construction Phase Site Observations.

3.2.14.1.2 Number of Trips

The number of trips to the site for the purpose of Pre-Functional Checklist Verification for each systems category must be up to that specified in the following paragraphs. It is encouraged that these trips be combined with Construction Phase Site Observations.

a. Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category: One eight-hour trip.

b. Plumbing Systems Category: No trips. Perform these activities in conjuction with HVAC system Catagory trips.

c. Utility Systems Category: No trip dedicated to this systems category. Verification of commissioned equipment, systems, and assemblies listed under this systems category may be combined with trips for other systems categories.

d. Electrical Type I Systems Category: No Trips.

e. Electrical Type II Systems Category: One eight-hour trip.

f. Building Envelope Systems, Components, and Assemblies Category: No Trips.

3.2.14.1.3 Sample Strategy

20-Percent sample spot-check for all equipment, systems, and assemblies for which Pre-Functional Checklists have been completed. Sample spot-check must include at least one complete item such as one complete unitary air-conditioner.

3.2.14.1.4 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must provide blank Pre-Functional Checklists to Installing Contractors.

The Lead Commissioning Specialist must submit all **completed Pre-Functional Checklists** and all associated equipment start-up reports for each systems category listed under paragraph SYSTEMS TO BE COMMISSIONED as a single submittal no later than seven calendar days after receipt of all completed checklists for equipment, systems, and assemblies listed under the respective systems category from Installing Contractors.

3.2.14.1.5 Commissioning Specialists Responsibilities

Commissioning Specialists must perform Pre-Functional Checklist Verifications and then must indicate acceptance of all Pre-Functional Checklist items for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.2.14.1.6 Installing Contractors Responsibilities

Installing Contractors must complete one Pre-Functional Checklist for each piece of equipment and system. Initial each Pre-Functional Checklist item for their area of responsibility indicating the item's construction, installation, and start-up as applicable has been verified to be complete and is ready for testing.

Installing Contractors must provide completed and initialed Pre-Functional Checklists and all associated equipment start-up reports to the Lead Commissioning Specialist as a single package for each systems category no later than seven calendar days after completion of inspection of all checklist items for each piece of equipment and system.

3.2.15 Certified Certificates of Readiness and Certificates of Readiness

3.2.15.1 General Requirements

A single Certified Certificate of Readiness must be prepared for each equipment, system, and assembly subject to Functional Performance Testing by reviewing, signing, and dating Certificates of Readiness to indicate each equipment, system, and assembly is complete and ready for testing. Testing of any equipment, system, or assembly is prohibited until after its Certified Certificate of Readiness has been submitted and approved. Government approval of Certified Certificates of Readiness does not constitute the Government's responsibility for equipment, systems, or assemblies being complete and ready for testing.

A single Certificate of Readiness must be prepared for each equipment, system, and assembly subject to Functional Performance Testing. Certificate of Readiness contents must include, but not be limited to, contents specified in the following paragraphs to the extent applicable to the specific system being tested.

a. Cover sheet with spaces for signatures and dates by the Lead Commissioning Specialist and by Installing Contractors to indicate each system is complete and ready for testing.

b. Equipment and system start-up reports.

c. Control system start-up reports.

d. Diagnostic test reports.

e. Completed Pre-Functional Checklists.

3.2.15.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must sign, date, and submit **Certified**

Certificates of Readiness for all equipment, systems, and assemblies listed under each systems category listed under paragraph SYSTEMS TO BE COMMISSIONED as a single submittal no later than 14 calendar days prior to testing of any equipment, system, or assembly listed under respective systems category.

3.2.15.3 Commissioning Specialists Responsibilities

Commissioning Specialists must perform reviews of Certificates of Readiness for accuracy to ensure equipment, systems, and assemblies are complete and ready for testing for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.2.15.4 Installing Contractors Responsibilities

Installing Contractors must prepare, sign, and date Certificates of Readiness indicating equipment, systems, and assemblies are complete and ready for testing. Certificates of Readiness for all equipment, systems, and assemblies listed under each systems category listed under paragraph SYSTEMS TO BE COMMISSIONED must be provided to the Lead Commissioning Specialist as a single package for each systems category.

3.2.16 Construction Phase Functional Performance Testing

3.2.16.1 General Requirements

Construction Phase Functional Performance Testing must be performed for all equipment, systems, and assemblies for which a Functional Performance Test (FPT) Checklist has been prepared. Testing must be performed using approved checklists and all required Commissioning Team participants must be present prior to start of testing. Testing must be aborted and rescheduled to occur at a later date if any Commissioning Team participant is not present or if deficiencies discovered during testing prevent successful completion. Testing of any equipment, system, and assembly is prohibited until after its Certified Certificate of Readiness has been submitted and approved.

All necessary materials and system modifications to simulate actual conditions as close as is practically possible must be provided. Complete all testing by returning affected equipment, systems, and assemblies to pre-test conditions.

3.2.16.2 Complex Systems Requirements

Testing of complex systems as defined in paragraph COMPLEX SYSTEMS in paragraph SYSTEMS TO BE COMMISSIONED must be performed as specified in the following paragraphs.

3.2.16.2.1 Equipment Featuring On-Board Factory Packaged Controls

Testing of equipment featuring on-board factory packaged controls must include, but not be limited to, testing specified in the following paragraphs.

a. Equipment enabling and disabling.

b. Equipment standard and optional control points necessary to accomplish functionality whether or not control points are specified in Plans and Specifications.

c. Equipment standard and optional alarms critical to safe operation whether or not optional alarms are specified in Plans and Specifications.

d. All control points added by Controls Contractor in addition to on-board factory packaged controls whether or not control points are specified in Plans and Specifications.

3.2.16.2.2 Test Setup and Condition Simulation

Test setup must include all necessary materials and system modifications to simulate flows, pressures, temperatures, and other conditions necessary to perform testing according to specified conditions must be provided.

Condition simulation must be accomplished by temporarily changing control system setpoints. Condition simulation by over-writing control system inputs (actual) values is prohibited unless approved in advance of test by the Contracting Officer's Technical Representative.

3.2.16.2.3 Condition Simulation Methods

Condition simulation methods for equipment, systems, and assemblies listed under item entitled "Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED that are acceptable are specified in the following paragraphs.

a. When varying static pressures inside ductwork cannot be simulated within the duct, and where a sensor signals the controls system to initiate sequences at various duct static pressures, it is acceptable to simulate the various pressures with a Pneumatic Squeeze-Bulb Type Signaling Device with gauge temporarily attached to the sensing tube leading to the transmitter. It is not acceptable to reset the various setpoints, nor to simulate an electric analog signal unless approved as specified in the preceding paragraphs.

b. Dirty filter pressure drops can be simulated using sheets of cardboard at filter face.

c. Freeze-stat safeties can be simulated by packing portion of sensor with ice.

d. High outside air temperatures can be simulated with a hair blower.

e. High entering cooling coil temperatures can be used to simulate entering cooling coil conditions.

f. Do not use signal generators to simulate sensor signals unless approved by the Contracting Officer's Technical Representative, as noted above, for special cases.

g. Control setpoints can be altered. For example, to see the air conditioning compressor lockout work at an outside air temperature below lockout setpoint, when the outside air temperature is above lockout setpoint, temporarily change the lockout setpoint to be minus 0 degrees above the current outside air temperature. Caution:

Setpoints are not to be raised or lowered to a point such that damage to the components, systems, or the building structure and/or contents will occur.

h. Test duct mounted smoke detectors in accordance with the manufacturer's recommendations. Perform testing with air system at minimum airflow condition in ductwork.

i. Test current sensing relays used for fan and pump status signals to control system to indicate unit failure and run status by resetting the setpoint on the relay to simulate a lost belt or unit failure while the unit is running. Confirm that the failure alarm was generated and received at the control system. After the test is performed, return the setpoint to its original setpoint or a setpoint as indicated by the Contracting Officer's Technical Representative.

3.2.16.3 Sample Strategy

3.2.16.3.1 General Requirements

100-Percent testing of all equipment, systems, and assemblies as modified in the following paragraphs. Sample strategy for testing less than 100-percent testing must be equally applied to each commissioned building in this project.

Sample strategy testing must be applied to total equipment and system counts specified for system categories under paragraph SYSTEMS TO BE COMMISSIONED.

3.2.16.3.2 Complex Systems

Sample strategy for all complex systems as defined in paragraph COMPLEX SYSTEMS must be as specified in the following paragraphs.

a. 100-Percent testing for equipment, systems, and assemblies such as chilled water systems, HVAC heating hot water systems, renewable energy systems, building automation systems, energy management and control systems, aircraft pre-conditioned air systems, air handling unit systems including all associated fans except for remote exhaust air fans, dedicated outside air systems including all associated fans except for remote exhaust air fans, computer room air-conditioning units, whole-building energy monitoring, and whole-building water utility monitoring.

b. 20-Percent sample testing for equipment, systems, and assemblies with identical control sequences such as heat pumps, split system air-conditioning units, and packaged terminal air-conditioner units. Sample must include at least one complete item such as one complete heat pump.

3.2.16.3.3 Plumbing Systems

Sample strategy for all equipment, systems, and assemblies listed under item entitled "Plumbing Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED except plumbing systems defined as complex systems in paragraph COMPLEX SYSTEMS must be as specified in the following paragraphs.

a. 100-Percent testing for equipment, systems, and assemblies such as domestic heating hot water systems, domestic solar heating hot water

systems, service water pressure-booster pump systems, process water systems, natural gas systems, and irrigation systems.

b. 20-Percent sample testing for equipment, systems, and assemblies with identical features such as fixtures, semi-instantaneous water heaters, emergency eyewash stations, and vacuum systems. Sample must include at least one complete item such as one complete fixture.

3.2.16.3.4 Electrical Type II Systems

Sample strategy for all equipment, systems, and assemblies listed under item entitled "Electrical Type II Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED except electrical systems defined as complex systems in paragraph COMPLEX SYSTEMS must be as specified in the following paragraphs.

a. 100-Percent testing for equipment, systems, and assemblies such as frequency converters, emergency power off control systems, emergency response systems, electrical utility metering systems, and photovoltaic systems.

b. 20-Percent sample testing for equipment, systems, and assemblies with identical features such as audiovisual systems, automatic receptacles controls, communications systems, energy monitoring, lighting systems, lighting control devices, lighting control systems, and security systems. Sample must include at least one complete item such as lighting in one space.

3.2.16.4 Unsuccessful Testing and Re-Testing

3.2.16.4.1 Unsuccessful Testing of 100-Percent Sample

Testing must be failed for equipment or systems for which 100-percent sample size are tested if one or more of the test procedures results in discovery of a deficiency that cannot be resolved within five minutes during testing.

Re-testing must be witnessed to the extent necessary to confirm that deficiencies have been corrected without negatively impacting the performance of the rest of the system.

3.2.16.4.2 Unsuccessful Testing of Less than 100-Percent Sample

Testing must be failed for equipment or systems for which less than 100-percent sample size are tested if one or more of the test procedures results in discovery of a deficiency, regardless of whether the deficiency is corrected during the sample test.

a. Re-testing must be witnessed of only items which experienced initial failures if the failure rate is 5-percent or less, meaning that 5-percent or less of the equipment or systems had at least one deficiency.

b. Re-testing must be witnessed of items which experienced initial failures to the extent necessary to confirm that the deficiencies have been corrected if the failure rate is higher than 5-percent, meaning that more than 5-percent of equipment or systems tested had at least one deficiency. In addition, testing of another random sample must be witnessed for the same size as the initial sample for the first time. If the second random sample set has any failures, those failed items

must be retested and all remaining equipment, systems, and assemblies must be tested to complete 100-percent testing of that system type.

3.2.16.5 Re-Testing Costs

Re-testing costs may be withheld by the Contracting Officer from payments to Installing Contractors. These costs may include salary, travel costs, and per diem associated with re-testing for the Lead Commissioning Specialist, Commissioning Specialists, and Government personnel.

3.2.16.6 Commissioning Team Participants

Participants of Functional Performance Testing must include, but not be limited to, participants specified in the following paragraphs. The Contracting Officer's Technical Representative, Public Works Department Division (PWD) Representatives, and Using Agent's Representatives (Users) may, but are not required to, participate in any testing.

3.2.16.6.1 Heating, Ventilation, and Air-Conditioning (HVAC) Systems

Commissioning Team members participating in Functional Performance Testing of equipment, systems, and assemblies listed under item entitled "Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED must include, but not be limited to, participants specified in the following paragraphs.

a. Mechanical Commissioning Specialist (CxM).

b. Installing Contractors’ Quality Control Personnel (CQC).

c. Installing Contractors’ Controls Commissioning Representative (CC).

d. Installing Contractors’ TAB Commissioning Representative (TAB).

e. Installing Contractors’ Mechanical Commissioning Representative (MC).

f. Equipment Supplier (ES).

3.2.16.6.2 Plumbing Systems

Commissioning Team members participating in Functional Performance Testing of equipment, systems, and assemblies listed under item entitled "Plumbing Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED must include, but not be limited to, participants specified in the following paragraphs.

a. Mechanical Commissioning Specialist (CxM).

b. Installing Contractors’ Quality Control Personnel (CQC).

c. Installing Contractors’ Controls Commissioning Representative (CC).

d. Installing Contractors’ Plumbing Commissioning Representative (PC).

e. Equipment Supplier (ES).

3.2.16.6.3 Utility Systems

Commissioning Team members participating in Functional Performance Testing of equipment, systems, and assemblies listed under item entitled "Utility

Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED must include, but not be limited to, participants specified in the following paragraphs.

a. Mechanical Commissioning Specialist (CxM).

b. Installing Contractors' Quality Control Personnel (CQC).

c. Installing Contractors' Controls Commissioning Representative (CC).

d. Installing Contractors' TAB Commissioning Representative (TAB).

e. Installing Contractors' Mechanical Commissioning Representative (MC).

f. Installing Contractors' Plumbing Commissioning Representative (PC).

g. Installing Contractors' Electrical Commissioning Representative (EC).

h. Equipment Supplier (ES).

3.2.16.6.4 Electrical Type II Systems

Commissioning Team members participating in Functional Performance Testing of equipment, systems, and assemblies listed under item entitled "Electrical Type II Systems Category" in paragraph SYSTEMS TO BE COMMISSIONED must include, but not be limited to, participants specified in the following paragraphs.

a. Electrical Commissioning Specialist (CxE).

b. Installing Contractors' Quality Control Personnel (CQC).

c. Installing Contractors' Electrical Commissioning Representative (EC).

d. Equipment Supplier (ES).

3.2.16.7 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, perform activities specified in the following paragraphs.

a. Contact Contracting Officer's Technical Representative no later than 30 calendar days prior to performing Testing to select which systems must be tested for samples of less than 100-percent.

b. Coordinate logistics with Installing Contractors.

c. Provide summary of Functional Performance Testing results to the Contracting Officer's Technical Representative for concurrence or acceptance at intervals no later than seven calendar days after the start of each occurrence of testing.

d. Submit **completed Final Functional Performance Test Checklists** for each systems category listed under paragraph SYSTEMS TO BE COMMISSIONED as a single submittal no later than 14 calendar days after successful testing of all systems listed under the respective systems category.

3.2.16.8 Commissioning Specialists Responsibilities

Commissioning Specialists must witness, re-witness, and document all

testing for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.2.16.9 Installing Contractors Responsibilities

Installing Contractors must provide all necessary materials and perform all aspects of testing including modifications to simulate actual conditions for all equipment, systems, and assemblies related to their contract.

3.2.16.10 Equipment Suppliers Responsibilities

Equipment Suppliers must perform all aspects of testing of equipment featuring on-board factory packaged controls provided as part of their contract. Refer to paragraph COMPLEX SYSTEMS for definition of equipment featuring on-board factory packaged controls.

3.2.16.11 Installing Contractors and Equipment Supplier Coordination

Installing Contractors and Equipment Suppliers must simultaneously perform all aspects of testing of equipment featuring on-board factory packaged controls provided as part of their contract.

3.2.17 Systems Manuals

3.2.17.1 General Requirements

Systems Manuals must be prepared for all commissioned equipment, systems, and assemblies and contents must include, but not be limited to, contents specified in the following paragraphs.

a. Executive summary containing overview of design, construction, and operation requirements.

b. Certificate of Occupancy.

c. Approved Construction Phase Commissioning Plan.

d. Approved Construction Phase Issues and Resolution Log.

e. Identification of unresolved deficiencies complete with resolution plan if not included in approved Final Commissioning Report.

f. Final Owner's Project Requirements.

g. Final Basis of Design.

h. Record documents including as-built Plans and Specifications and approved Construction Submittals.

i. Operation and Maintenance Manuals.

j. Maintenance procedures, checklists, and records.

k. Recommended maintenance schedules when schedules are not provided in Operation and Maintenance manuals.

l. Ongoing Commissioning operational and maintenance record keeping procedures to monitor equipment, systems, and assemblies performance.

m. Building and equipment operation schedules.

n. Equipment and system limitations.

o. Emergency procedures.

p. Recommended schedule for sensor and actuator calibration.

q. Recommended re-testing schedule.

r. Blank copy of all approved final Functional Performance Test Checklists.

s. Completed Functional Performance Test Checklists if not included in approved Final Commissioning Report.

t. Equipment warranty information.

u. Installing Contractors and Equipment Suppliers contact information.

v. Training Plans if not included in approved Final Commissioning Report, training materials, and completed Training Attendance Rosters if not included in approved Final Commissioning Report.

w. Commissioning Design Review Reports if not included in approved Final Commissioning Report.

x. Construction Submittal Review Reports.

y. Approved Final Commissioning Report.

z. All Commissioning reports that are not specified in the preceding paragraphs and are not specified to be included in the approved Final Commissioning Report.

Systems Manual contents for all complex systems as defined in paragraph COMPLEX SYSTEMS, in addition to contents specified in the preceding paragraphs, must include, but not be limited to, contents specified in the following paragraphs.

a. As-built system single line diagrams.

b. As-built sequences of operation and controls drawings.

c. As-built control system setpoints and operating ranges.

3.2.17.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, provide all review comments to the Installing Contractors for all equipment, systems, and assemblies listed under each systems category as a single package no later than 45 calendar days prior to first training event for any equipment, system, or assembly in respective systems category. Review comments are not required to be submitted to the Government.

3.2.17.3 Commissioning Specialist Responsibilities

Commissioning Specialists must, at a minimum, review and prepare review comments for all Systems Manuals. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.2.17.4 Installing Contractors Responsibilities

Installing Contractors must, at a minimum, perform activities specified in the following paragraphs.

a. Prepare and provide all Systems Manuals to the Lead Commissioning Specialist for all equipment, systems, and assemblies listed under each systems category as a single package no later than 60 calendar days prior to first training event for any equipment, system, or assembly in respective systems category.

b. Incorporate all review comments.

3.2.18 Training

3.2.18.1 Training Plans

Training Plans must be prepared for all commissioned equipment, systems, and assemblies and contents must include, but not be limited to, contents specified in the following paragraphs.

a. List of those who should receive training by position or name.

b. List of systems that require training organized by Specification Section.

c. Outline of training topics that addresses design, construction, operation, and maintenance.

d. Learning objectives and training delivery methods.

e. Planned location of the training sessions (classroom, on-site, and off-site).

f. Minimum duration of each training session.

g. Training materials requirements to be used during the instructional process.

h. Training report, records, and recording requirements.

i. Instructor qualifications.

j. Instructor name and contact information.

k. Criteria for determining whether provided training is acceptable.

l. Blank Training Attendance Rosters.

3.2.18.2 Training

Training must be performed in accordance with Training Plans and in accordance with requirements specified in other Sections.

3.2.18.3 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, provide all review comments to the Installing Contractors for all equipment, systems, and assemblies listed under each systems category as a single package no later than 45 calendar days prior to first training event for any equipment, system, or assembly in respective systems category. Review comments are not required to be submitted to the Government.

3.2.18.4 Commissioning Specialist Responsibilities

Commissioning Specialists must, at a minimum, review and prepare review comments for all Training Plans. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.2.18.5 Installing Contractors Responsibilities

Installing Contractors must, at a minimum, perform activities specified in the following paragraphs.

a. Prepare and provide all Training Plans to the Lead Commissioning Specialist for all equipment, systems, and assemblies listed under each systems category as a single package no later than 60 calendar days prior to first training event for any equipment, system, or assembly in respective systems category.

b. Incorporate all review comments.

c. Perform training as specified in the preceding paragraphs.

d. Require all training attendees to sign Training Attendance Rosters.

e. Provide all Approved Training Plans and Completed Training Attendance Rosters to the Lead Commissioning Specialist for all equipment, systems, and assemblies listed under each systems category as a single package no later than 30 calendar days after the last training event for all equipment, systems, and assemblies in respective systems category.

3.2.19 Final Commissioning Report

3.2.19.1 General Requirements

The Final Commissioning Report must be prepared and contents must include, but not be limited to, contents specified in the following paragraphs.

a. Executive summary describing the overall Commissioning Process.

b. Results of the Commissioning Process.

c. Issues And Resolution Log.

d. Commissioning Design Review Reports.

e. Approved Construction Phase Final Commissioning Plan.

f. Approved Pre-Final Test and Balance Reports.

g. Completed Pre-Functional Checklists.

h. Completed Functional Performance Test Checklists.

i. Approved Training Plans.

j. Completed Training Attendance Rosters.

k. Indication that equipment, systems, and assemblies meet requirements of the Owner's Project Requirements, Basis of Design, and Plans and Specifications.

l. Identification of all deficiencies complete with corrective actions taken.

m. Identification of all repairs, replacements, and calibrations.

n. Identification of unresolved deficiencies complete with resolution plan and responsible Commissioning Team member.

o. List and plan for completion of any testing that must be performed during the Post-Construction (Warranty) Phase.

3.2.19.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, perform activities specified in the following paragraphs.

a. Prepare and submit the **Final Commissioning Report** no later than 30 calendar days after Beneficial Occupancy.

b. File one copy of **Approved Final Commissioning Report** in the Sustainability eNotebook no later than 14 calendar days after receiving approval of the Final Commissioning Report.

3.3 POST-CONSTRUCTION (WARRANTY) PHASE

3.3.1 Post-Construction Phase International Green Construction Code Commissioning Compliance

3.3.1.1 General Requirements

Activities must include, but not be limited to, Post-Construction Phase Commissioning Activities listed in ICC IgCC paragraphs 1001.1 through 1001.3.1.3.6, ICC IgCC Informative Appendix I, and ASHRAE 202 as modified in this Section, Post-Construction Phase Commissioning Activities listed in references contained in ICC IgCC's paragraphs and ASHRAE 202 as modified in this Section, and Post-Construction Phase Commissioning Activities specified in this Section.

3.3.1.2 Lead Commissioning Specialist and Commissioning Specialists Responsibilities

The Lead Commissioning Specialist and Commissioning Specialists must, at a minimum, perform all activities specified under item entitled "Post-Construction Phase International Green Construction Code Commissioning Compliance."

3.3.2 Post-Construction Phase Sustainability Third Party Certification (TPC) Commissioning Compliance

3.3.2.1 General Requirements

Activities must include, but not be limited to, Post-Construction Phase Commissioning Activities listed in the reference for pursuing Sustainability TPC, GBI DOD GP Compliance, as modified in this Section, Post-Construction Phase Commissioning Activities listed in all of its references as modified in this Section, and Post-Construction Phase Commissioning Activities specified in this Section.

3.3.2.2 Lead Commissioning Specialist and Commissioning Specialists Responsibilities

The Lead Commissioning Specialist and Commissioning Specialists must, at a minimum, perform activities specified in the following paragraphs.

a. The Lead Commissioning Specialist must submit all Post-Construction Phase documentation of Commissioning Activities directly to the Suitability TPC organization as modified in this Section.

b. The Lead Commissioning Specialist and Commissioning Specialists must perform all activities specified under item entitled "Post-Construction Phase Sustainability Third Party Certification (TPC)."

3.3.3 Post-Construction Phase Issues And Resolution Log

3.3.3.1 General Requirements

The Post-Construction Phase Issues and Resolution Log must be prepared and maintained to track all Commissioning Issues identified by any member of the Commissioning Team. The Post-Construction Phase Issues and Resolution Log must be prepared in an electronic format that can be used throughout the Post-Construction Phase such that it can be provided to the Government upon request. Post-Construction Phase Issues and Resolution Log contents must include, but not be limited to, contents specified in the following paragraphs.

a. Project title and location.

b. Lead Commissioning Specialist's contact information.

c. Issue number.

d. Date issue was discovered.

e. Name of Commissioning Team member identifying the issue.

f. Commissioning Team member responsible for resolving the issue.

g. Current status.

h. Issue description.

i. Pictures of item if available and appropriate.

j. Effects of issue on project or building operation.

k. Possible cause of issue.

l. Proposed resolution.

m. Final resolution and final resolution date.

n. Approvals of issue resolution, including approver's name.

3.3.3.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must prepare and maintain the **Post Construction Phase Issues And Resolution Log** and must submit one electronic copy no later than 14 calendar days after completion of any Post-Construction Phase Commissioning Activity.

3.3.4 Post-Construction Phase Site Observations

3.3.4.1 General Requirements

Post-Construction Phase Site Observations must be performed for each systems category specified in the following item entitled "Number of Trips" between eight and 10 months after Beneficial Occupancy to verify and document that all commissioned equipment, systems, and assemblies are operating in accordance with the Owner's Project Requirements.

Post-Construction Phase Site Observations are prohibited from being combined with witnessing Post-Construction Phase Functional Performance Testing.

3.3.4.2 Number of Trips

The Number of Post-Construction Phase Site Observations inclusive of all commissioned buildings in this project must be as follows

a. Heating, Ventilation, and Air-Conditioning (HVAC) Systems Category: One eight-hour trip.

b. Plumbing Systems Category: No trips. Perform these activities in conjuction with HVAC system Catagory trips.

c. Utility Systems Category: No trips.

d. Electrical Type I Systems Category: No trips.

e. Electrical Type II Systems Category: One eight-hour trip.

f. Building Envelope Systems, Components, and Assemblies Category: One eight-hour trip.

3.3.4.3 Site Observation Reports

Site Observation Reports must be prepared for each Site Observation for the purpose of documenting issues discovered during Site Observation.

3.3.4.4 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, perform activities specified in the following paragraphs.

a. Contact Contracting Officer's Technical Representative no later than 30 calendar days prior to performing Site Observation to schedule attendance of Operations and Maintenance staff and occupants and to make provisions for access to all commissioned equipment, systems, and assemblies.

b. Submit **Post-Construction Phase Site Observation Reports** no later than 14 calendar days after Site Observation.

3.3.4.5 Commissioning Specialists Responsibilities

Commissioning Specialists must, at a minimum, perform activities specified in the following paragraphs for equipment, systems, and assemblies listed under systems categories assigned to them in this Section. Commissioning Specialists are prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

a. Interview Operations and Maintenance staff.

b. Interview occupants.

c. Determine status of unresolved Commissioning Issues.

d. Compare current operations to operations identified throughout the Commissioning Process.

e. Prepare Post-Construction Phase Site Observation Reports.

3.3.5 Certified Certificates of Readiness and Certificates of Readiness

Certified Certificates of Readiness and Certificates of Readiness are not required for any Post-Construction Phase activity.

3.3.6 Post-Construction Phase Functional Performance Testing

3.3.6.1 General Requirements

Post-Construction Phase Functional Performance Testing must be performed for all commissioned equipment, systems, and assemblies that could not be fully or successfully tested during the Construction Phase. Testing must be performed using approved checklists and all required Commissioning Team participants must be present prior to start of testing. Testing must be aborted and rescheduled to occur at a later date if any Commissioning Team participant is not present or if deficiencies discovered during testing prevent successful completion.

Post-Construction Phase Functional Performance Testing requirements and activities must include, but not be limited to, requirements and

activities specified for Construction Phase Functional Performance Testing as modified in paragraphs under paragraph POST-CONSTRUCTION (WARRANTY) PHASE.

3.3.6.2 Commissioning Team Participants

Participants of Functional Performance Testing must include, but not be limited to, participants specified in the following paragraphs. The Contracting Officer's Technical Representative, Public Works Department Division (PWD) Representatives, and Using Agent's Representatives (Users) may, but are not required to, participate in any testing.

a. Lead Commissioning Specialist.

b. Commissioning Specialists.

c. Installing Contractors.

d. Equipment Suppliers.

3.3.6.3 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, perform activities specified in the following paragraphs.

a. Contact Contracting Officer's Technical Representative no later than 30 calendar days prior to witnessing Post-Construction Phase Functional Performance Testing to make provisions for access to all commissioned equipment, systems, and assemblies.

b. Coordinate logistics with Installing Contractors.

c. Submit completed Final Functional Performance Test Checklists for each systems category listed under paragraph SYSTEMS TO BE COMMISSIONED as a single submittal no later than 14 calendar days after successful testing of all systems listed under the respective systems category.

3.3.7 Updated Systems Manuals

3.3.7.1 General Requirements

Updated Systems Manuals must be prepared and must be an update to Systems Manuals prepared during the Construction Phase and contents must include, but not be limited to, changes resulting from Post-Construction Phase Commissioning Activities.

3.3.7.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, provide all review comments to the Installing Contractors as a single package 45 calendar days after Post-Construction Phase Site Observations or no later than 45 calendar days after Post-Construction Phase Functional Performance Testing, whichever occurs last. Review comments are not required to be submitted to the Government.

3.3.7.3 Commissioning Specialist Responsibilities

Commissioning Specialists must, at a minimum, review and prepare review comments for all Updated Systems Manuals. Commissioning Specialists are

prohibited from performing these responsibilities for equipment, systems, and assemblies listed under systems categories assigned to other Commissioning Specialists.

3.3.7.4 Installing Contractors Responsibilities

Installing Contractors must, at a minimum, perform activities specified in the following paragraphs.

a. Prepare and provide all Updated Systems Manuals to the Lead Commissioning Specialist as a single package no later than 30 calendar days after Post-Construction Phase Site Observations or no later than 30 calendar days after Post-Construction Phase Functional Performance Testing, whichever occurs last.

b. Incorporate all review comments.

3.3.8 Updated Final Commissioning Report

3.3.8.1 General Requirements

The Updated Final Commissioning Report must be prepared and must be an update to the Final Commissioning Report prepared during the Construction Phase and contents must include, but not be limited to, changes resulting from Post-Construction Phase Commissioning Activities.

3.3.8.2 Lead Commissioning Specialist Responsibilities

The Lead Commissioning Specialist must, at a minimum, prepare and submit the **Updated Final Commissioning Report** no later than 30 calendar days after completion of all Functional Performance Testing.

File one copy of **Approved Updated Final Commissioning Report** in the Sustainability eNotebook no later than 14 calendar days after receiving approval of the Updated Final Commissioning Report.

-- End of Section --

SECTION 01 91 19

BUILDING ENCLOSURE COMMISSIONING
05/23

PART 1 GENERAL

1.1 SUMMARY

Use this Section in conjunction with UFGS 01 91 00.15 BUILDING COMMISSIONING. Building Enclosure Commissioning (BECx) is an essential part of overall Building Commissioning. The final BECx report is part of the Final Commissioning Report as defined in 01 91 00.15 BUILDING COMMISSIONING. This Section covers Building Enclosure Commissioning for all six surfaces (walls, roof, and floor, for a rectangular shaped zone) of a building. Additional Quality Control and testing requirements for specific components of the building enclosure are described in the Division 03 thru 08 UFGS Sections of the project specifications.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referenced within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 501.2	(2015) Quality Assurance and Diagnostic Water Leakage Field Check of Installed Storefronts, Curtain Walls and Sloped Glazing Systems

AMERICAN SOCIETY FOR NONDESTRUCTIVE TESTING (ASNT)

ANSI/ASNT CP-105	(2020) ASNT Standard Topical Outlines for Qualification of Nondestructive Testing Personnel
ANSI/ASNT CP-189	(2020) ASNT Standard for Qualification and Certification of Nondestructive Testing Personnel
ASNT SNT-TC-1A	(2020) Recommended Practice for Personnel Qualification and Certification in Nondestructive Testing

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 90.1 - IP	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings
ASHRAE 202	(2018) Commissioning Process for Buildings and Systems
ASHRAE RP-935	(1998) Protocol for Field Testing of Tall Buildings to Determine Envelope Air Leakage Rate

ASTM INTERNATIONAL (ASTM)

ASTM C1193	(2013) Standard Guide for Use of Joint Sealants
ASTM D3464	(1996; R 2014) Standard Test Method for Average Velocity in a Duct Using a Thermal Anemometer
ASTM D4541	(2022) Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers
ASTM E779	(2019) Standard Test Method for Determining Air Leakage Rate by Fan Pressurization
ASTM E783	(2002; R 2018) Standard Test Method for Field Measurement of Air Leakage Through Installed Exterior Windows and Doors
ASTM E1105	(2015; R 2023) Standard Test Method for Field Determination of Water Penetration of Installed Exterior Windows, Skylights, Doors, and Curtain Walls, by Uniform or Cyclic Static Air Pressure Difference
ASTM E1186	(2022) Standard Practices for Air Leakage Site Detection in Building Envelopes and Air Barrier Systems
ASTM E1258	(1988; R 2018) Standard Test Method for Airflow Calibration of Fan Pressurization Devices
ASTM E1827	(2022) Standard Test Methods for Determining Airtightness of Buildings Using an Orifice Blower Door
ASTM E2029	(2011) Standard Test Method for Volumetric and Mass Flow Rate Measurement in a Duct Using Tracer Gas Dilution
ASTM E2813	(2018) Standard Practice for Building Enclosure Commissioning
ASTM E2947	(2021) Standard Guide for Building Enclosure Commissioning

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

ISO 6781	(1983) Thermal Insulation - Qualitative Detection of Thermal Irregularities in Building Envelopes - Infrared Method
ISO 6781-2	(2010) Performance of Buildings - Detection of Heat, Air, and Moisture Irregularities in Buildings by Infrared

	Methods - Part2: Equipment Requirements
ISO 6781-3	(2015) Performance of Buildings - Detection of Heat, Air, and Moisture Irregularities in Buildings by Infrared Methods - Part 3: Qualifications of Equipment Operators, Data Analysts, and Report Writers

1.3 DEFINITIONS

The definitions included here are specific to this Section. Refer to UFGS 01 91 00.15 BUILDING COMMISSIONING for definitions that apply to both Sections. The following terms as they apply to this section:

1.3.1 Air Barrier Envelope

The surface that separates the inside air from the outside air. The combination of air barrier assemblies and air barrier components, connected by air barrier accessories are designed to provide a continuous barrier to the movement of air through an environmental separator. A single building may have more than one air barrier envelope. The air barrier surface includes the top, bottom, and sides of the envelope. The term "air barrier envelope" is also known as "air barrier system" or simply "air barrier".

1.3.2 Air Leakage Rate

A measurement of air infiltration or exfiltration through the building envelope over time. The air leakage rate is the rate of air flow across the air barrier per unit surface area of the envelope at a defined differential pressure.

1.3.3 Basis of Design (BoD)

A document developed by the design team which includes technical concepts, assumptions, calculations, decisions, and product selections to support the Owner's Project Requirements (OPR).

1.3.4 Bias Pressure

Also known as zero flow pressure, baseline pressure, offset pressure or background pressure. With the envelope not artificially pressurized, bias is the differential pressure that always exists between the envelope that has been prepared (sealed) for the pressure test and the outdoors. Bias pressure is made up of two components, fixed static offset (usually due to stack effect or the HVAC system) and fluctuating pressure (usually due to wind or a moving elevator). Because of pressure fluctuations many bias pressure readings are recorded and averaged for use in the calculations.

1.3.5 Blower Door

Commonly used term for an apparatus used to pressurize and depressurize the space within the building envelope and quantify air leakage through the envelope. The blower door typically includes a door fan and an air resistant fabric or a series of hard panels that extends to cover and seal the door opening between the fan shroud and door frame. The door fan is a calibrated fan capable of measuring air flow and is usually placed in the opening of an exterior door. With the air barrier otherwise sealed, air

produced by the door fan pressurizes or de-pressurizes the envelope, depending on the fan's orientation.

1.3.6 Building Enclosure (or envelope)

The materials, components, systems, and assemblies intended to provide an environmental separator between the interior and exterior or between interior spaces with different environment requirements. "Enclosure" is used interchangeably with "envelope".

1.3.7 Building Enclosure Commissioning (BECx)

Technical service provided on behalf of the Government to provide a quality-focused process for enhancing the performance of the building enclosure by validating the design phase and verifying during the construction phase that the performance of the building enclosure materials components, assemblies, and systems are designed and installed to meet the Owner's Project Requirements (OPR).

1.3.8 Building Enclosure Commissioning Provider (BECxP)

An entity that functions as part of the overall Commissioning Team and is responsible for validating the design phase and verifying during the construction phase that the performance of the building enclosure materials, components, assemblies, and systems are designed and installed to meet the Owner's Project Requirements (OPR).

1.3.9 Construction Phase

The period of a project following the award of construction Contract to project completion.

1.3.10 Design Phase

The period of the project delivery process when a design supporting the Owner's Project Requirements is developed and translated into Contract Documents.

1.3.11 Environmental Separator

The parts of a building that separate the controlled interior environment from the uncontrolled exterior environment, or that separate spaces within a building that have dissimilar environments. The term "environmental separator" is also known as the "control layer".

1.3.12 Functional Performance Test (FPT)

A systematic process to verify that controls and other elements of the building project are capable of and configured to operate or perform as required.

1.3.13 Pressure Test

A generic term for a test in which the envelope is either pressurized or de-pressurized with respect to the outdoors.

1.3.14 Negative Pressure Test (Depressurization Test)

A test wherein air inside the envelope is drawn to the outdoors. This

places the envelope at a lower (negative) pressure with respect to the outdoors.

1.3.15 Positive Pressure Test (Pressurization Test)

A test wherein outdoor air is pushed into the envelope. This air movement places the envelope at a higher (positive) pressure with respect to the outdoors.

1.3.16 Verification & Testing (V&T) Provider

An entity who completes the activities needed to implement the building functional performance testing (FPT) activities or verify that elements of the building project meet stated requirements.

1.4 COMMUNICATION WITH THE GOVERNMENT COMMISSIONING PROVIDER

For communication responsibilities, see Section 01 91 00.15 BUILDING COMMISSIONING.

1.5 COMMUNICATION WITH GOVERNMENT ACCCEPTANCE TESTING REPRESENTATIVES

The QC Manager must communicate directly with the Government Acceptance Testing Representatives and Contracting Officer's Representative regarding Government acceptance testing activities. Inform the Contracting Officer's Representative when systems are ready for testing to be witnessed by Government Acceptance Testing Representatives, and allow access to the construction site and system(s) to be tested

1.6 ENCLOSURE COMPONENTS TO BE COMMISSIONED

1.6.1 Verification of the Design and Installation of the Continuous Air Barrier

a. Conduct periodic field inspection of the continuous air barrier materials and assemblies, including all penetrations through the six sides of the air barrier, during construction while the continuous air barrier is still accessible for inspection and repair (after installation of all penetrations and wall cladding anchoring devices and before the installation of interior finishes) to verify and document compliance with the requirements. Conduct inspections at initial installation of each building envelope component and at in-progress construction intervals as stated in Part 3 section titled BUILDING ENVELOPE INSPECTION AND TESTING.

b. Conduct Performance Verification Testing of the entire building envelope (systems, components, and assemblies) for air tightness in accordance with Part 3 section titled BUILDING ENVELOPE AIR TIGHTNESS REQUIREMENT.

1.6.2 Inspection of Fenestration and Doors

a. Fenestration and Doors must be labeled and inspected to verify compliance with Building Envelope energy requirements, including applicable U-factors, Solar Heat Gain Coefficient (SHGC), Visible Transmittance (VT), and air leakage rates.

b. Inspect doors and windows for coordination with the insulating plane of the wall, continuity with the air/weather barrier, and flashing.

c. Inspect operation of doors, closers, and operating mechanisms for conformance with manufacturer's instructions.

d. Inspect seals and gaskets for fenestration and doors (including loading dock, sectional, and coiling doors) for proper installation and to verify that seals are in good condition.

1.6.3 Inspection of Opaque Roof, Walls, and Floors

Opaque roof, above-grade and below-grade walls, and floors, must be subject to the following inspections during construction:

a. Use of ASHRAE 90.1 - IP-compliant materials and assemblies.

b. Insulation material meets design specifications and is continuous.

1.6.4 Fenestration Inspections

Conduct inspections of the following fenestration-related items during construction:

a. Skylights size and location in relation to the designed primary sidelighted area and secondary sidelighted area below.

b. Roof monitor size and location in relation to the designed primary sidelighted area and secondary sidelighted area below.

c. Dynamic glazing compliance with SHGC and U-factors, and testing of the operation for conformance with the manufacturer's instructions.

d. Permanent fenestration projections installation and performance in accordance with ASHRAE 90.1 - IP requirements and the Contract documents.

1.7 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Building Enclosure Commissioning Specialist Qualifications; G

Building Enclosure Testing Work Plan; G

SD-03 Product Data

Thermal Imaging Camera; G

Test Equipment; G

SD-05 Design Data

Envelope Surface Area Calculations; G

SD-06 Test Reports

Pressure Test Procedures; G

Air Leakage Test Report; G

Diagnostic Test Report; G

SD-07 Certificates

Pressure Test Agency

Thermographer Qualifications

Certificate of Readiness

SD-10 Operation and Maintenance Data

Training; G

1.8 BUILDING ENCLOSURE TESTING WORK PLAN

For each building enclosure test to be performed, submit the following not later than 120 calendar days before start of testing work, steps to be taken by the lead test technician to accomplish the required testing.

a. Memorandum of test procedure.

(1) Proposed dates for conducting the tests.

(2) Submit detailed test procedures prior to the test. Provide a plan view showing proposed locations (personnel doors or other similar openings) to install equipment (such as blower doors or flexible ducts for trailer-mounted fans, if used).

b. Test equipment to be used.

c. Scaffolding, scissor lifts, power, electrical extension cords, duct tape, plastic sheeting and other Contractor's support equipment required to perform all tests.

d. Other Contractor's support personnel who will be on site for testing.

1.9 ACCESSIBILITY REQUIREMENTS

Air barrier components, insulation, fenestration, and doors for commissioned systems must be made accessible for inspections. Contractor must make necessary modifications at Contractor's own expense if systems and enclosures are not accessible for inspections and testing. Assist commissioning team in testing and inspections by removing equipment covers, opening access panels, and other required activities that assist with visual oversight. Furnish ladders, flashlights, meters, gauges, or other inspection equipment as necessary.

1.10 SCHEDULING

Notify the Contracting Officer a minimum 14 calendar days in advance of

site visits and inspections by the roof system manufacturer technical representative for coordination with the Government Acceptance Testing Representative.

1.11 COORDINATION

Refer to Section 01 91 00.15 BUILDING COMMISSIONING for requirements pertaining to coordination during the commissioning process. Coordinate with the Commissioning Provider in accordance with Section 01 91 00.15 BUILDING COMMISSIONING and in accordance with the Commissioning Plan to schedule inspections as required to support the commissioning process. Furnish additional information requested by the Commissioning Provider.

Coordinate scheduling of air barrier inspections and air barrier pressure testing with the commissioning team. Upload plans, reports, notes, and other documentation to the Commissioning Provider's web-based commissioning software, or as specified in the commissioning plan, as it is completed.

1.12 QUALITY CONTROL

1.12.1 Modification of References

Perform all pressure and diagnostic tests according to the referenced publications listed in paragraph REFERENCES and as modified by this section. Consider the advisory or recommended provisions, of the referred references, as mandatory.

1.12.2 Qualifications

1.12.2.1 Building Enclosure Commissioning Specialist Qualifications

See UFGS 01 91 00.15 BUILDING COMMISSIONING for the qualification requirements of the Building Enclosure Commissioning Specialist.

1.12.2.2 Pressure Test Agency

Submit, no later than 15 calendar days after Contract award, information certifying that the pressure test agency is not affiliated with any other company participating in work on this Contract. The work of the test agency is limited to pressure testing the building envelope, performing a thermography test and fog test, and investigating, through various methods, the location of air leaks through the air barrier. See Part 3 paragraph PRESSURE TEST AGENCY for additional requirements. For thermographer qualifications, see paragraph THERMOGRAPHER QUALIFICATIONS.

Use the sample TEST AGENCY QUALIFICATIONS SHEET form (Appendix C), to submit the following information.

a. Verification of 2 years of experience as an agency in pressure testing commercial or industrial buildings.

b. List of at least ten commercial/industrial facilities with building envelopes that the agency has tested within the past 2 years. Include building name, address, and name of prime construction Contractor and Contractor's point-of-contact information.

c. Confirmation of 2 years of commercial and or industrial building pressure test experience for the lead pressure test technician and the

thermographer in using the specified ASTM E779 or ASTM E1827 testing standard. References from five Contracting Officers for facilities where the lead test technician has supervised commercial and or industrial building pressure tests in the last 2 years.

d. Verification that the lead pressure test technician has been employed by a building pressure testing agency in the capacity of a lead pressure test technician for not less than 1 year.

1.12.2.3 Thermographer Qualifications

To perform an infrared diagnostic evaluation, use a lead thermographer who has at least an active Level II Certification that is based on the requirements in ANSI/ASNT CP-105 or ANSI/ASNT CP-189 and is in accordance with ASNT SNT-TC-1A. The course of study is to be specifically focused on infrared thermography for building science. The thermographer must have at least two years of building science thermography experience in IR testing commercial or industrial buildings. The thermographer must also have experience in building envelopes and building science in order to make effective recommendations to the Contractor should the envelope require additional sealing. Thermographic equipment operators, data analysts and report writers must comply with the requirements of ISO 6781-3. Submit the thermographer's certificate for approval. Submit a list of at least ten commercial/industrial buildings on which the thermographer has performed IR thermography in the past two years. The thermographer is to have a current active certification. Submit certification at least 60 days prior to thermography testing.

1.12.3 Test Reports

No later than 14 days after completion of the pressure test, submit electronic copies of an organized report. The report is to contain a table of contents, an executive summary, an introduction, a results section and a discussion of the results. Submit the air leakage test report as described in paragraph AIR LEAKAGE TEST REPORT. Submit a diagnostic test report as described in paragraph LOCATING LEAKS BY DIAGNOSTIC TESTING. The diagnostic test report is to include the Thermographic Investigation Report and the Fog Test Report (if performed).

Submit field data and completed report forms found in the appendices. Use the sample forms, Test Agency Qualification Sheet, Air Leakage Test Form and Air Leakage Test Results Form to summarize the tests for the appropriate building envelope. Submit both electronically populated and field hand filled-in forms.

Report Data. Include in the report the following information for all tests:

a. Date of issue

b. Project title and number

c. Name, address, and telephone number of testing agency

d. Dates and locations of samples and tests or inspections

e. Names of individuals making the inspection or test

f. Designation of the work and test method

g. Identification of product and specification section

h. Complete inspection or test data

i. Test results and an interpretation of test results

j. Comments or professional opinion on whether inspected or tested work complies with Contract document requirements

k. Recommendations on retesting

1.13 CLIMATE CONDITIONS SUITABLE FOR A PRESSURE TEST

As the test date approaches, monitor the weather forecast for the test site. Avoid testing on days forecast to experience high winds, rain, or snow. Monitor weather forecasts prior to shipping pressure test equipment to the site. Based on current and forecast weather conditions, the Contracting Officer's representative is to grant final approval for testing to occur.

1.13.1 Rain

For safety reasons, avoid testing during rain or if rain is anticipated during testing. If pneumatic hoses are installed and exposed to rain inspect the hose to ensure rainwater has not migrated into the hose ends. Orient all exposed hose ends to keep them out of water puddles. Success in temporarily sealing outdoor ventilation components such as louvers and exhaust fans may also be compromised by rain. Don't seal roof-mounted ventilation components during times of potential lightning.

1.13.2 Wind

Because wind can skew pressure test results, test only on days and at times when winds are anticipated to be the calmest. Avoid pressure testing during gusty or high wind conditions. Avoid installing test fans on the windward side of the building if wind gusts during the test are anticipated to be greater than 10 miles per hour.

1.14 CERTIFICATE OF READINESS

Prior to scheduling the Commissioning Tests as required by this Section, submit Certificate of Readiness documentation in accordance with Section 01 91 00.15 BUILDING COMMISSIONING for each enclosure-related system, certifying that inspections have been completed, open issues have been resolved, and the system is ready for the Commissioning Tests. Documentation would include Building Envelope Inspection Checklists as required within this Section, as well as any inspections or test reports required within each enclosure-related technical specification section. Additional Quality Control and testing requirements for specific components of the building enclosure are described in the Division 03 thru 08 UFGS Sections of the project specifications.

Submit the Certificate of Readiness for each system 20 working days prior to Commissioning Tests of that system. Do not schedule Commissioning Tests for a system until the Certificate of Readiness is approved by the Government. Do not schedule air tightness testing of the building envelope system until Certificates of Readiness and supporting documentation for enclosure-related systems have been submitted, reviewed

and approved by the Government.

PART 2 PRODUCTS

2.1 TEST EQUIPMENT

Provide all equipment required to perform testing for the systems and components to be commissioned. Provide all testing equipment of sufficient quality and accuracy to test and measure system performance with the tolerances specified. Provide a sufficient quantity of two-way radios for each subcontractor.

Submit a signed and dated list of instruments to be used for testing, their application, manufacture, model, serial number, range of operation accuracy, and date of most recent calibration. Calibration data applicable to fan systems must be in accordance with ASTM E1258. Also list special equipment and proprietary tools specific to a piece of equipment required for testing.

2.2 PRESSURE TEST EQUIPMENT

Depending on site conditions and size of the envelope, the test may be conducted using blower door equipment and trailer-mounted fans . The testing agency is to supply sufficient quantity of blower equipment that will produce a minimum of 75 Pa differential pressure between the envelope and outdoors using the test methods described herein. Supplying additional blower test equipment to provide additional airflow capacity or to act as a backup is highly recommended.

2.2.1 Blower Door Fans and Trailer Mounted Fans

Each air flow measuring system including blower door fans and trailer mounted fans are to be calibrated within the last 5 years. Calibrated blower door fans and trailer mounted fans must measure accurately to within plus or minus 5 percent of the flow reading. Blower door equipment and trailer mounted fans are to be specifically designed to pressurize building envelopes. Each set of blower door equipment is to include fan(s), digital gage(s), door frame, door fabric or hard panels.

2.2.2 Digital Gages as Test Instruments

Use only digital gages as measuring instruments in the pressure test; analog gages are not acceptable. The gauges must be accurate to within 1.0 percent of the pressure reading or 0.15 Pa, whichever is greater. Each gage is to have been calibrated within two years of the test. The calibration is to be checked against a National Institute of Standards and Technology (NIST, formerly National Bureau of Standards) traceable standard.

2.3 THERMAL IMAGING CAMERA REQUIREMENTS

The thermal imaging camera used in the thermography test must have a thermal sensitivity (Noise Equivalent Temperature Difference.) of +/- 0.18 degrees F at 86 degrees F or less. Ensure the camera's operating spectral range falls between 2 and 15 micrometers. Ensure the camera's IR image viewing screen resolution measures at least 320x240 pixels. Ensure the camera has a means of recording thermal images seen on the camera viewing screen. The camera is to display output as individual still frame images that also can be downloaded and inserted into an electronic Thermographic

Investigation Report. All thermographic equipment must comply with the requirements of ISO 6781-2. Submit camera make and model, and catalog information that defines the camera thermal sensitivity for approval.

PART 3 EXECUTION

Conduct building enclosure commissioning in accordance with ASHRAE 202 and ASTM E2947 in addition to the requirements herein. Follow ASTM E2947 except where it references ASTM E2813. Commissioning must document in sufficient detail compliance of the building envelope with the design intent as defined in the Contract documents.

3.1 MEETINGS

Attend all meetings in accordance with Section 01 91 00.15 BUILDING COMMISSIONING.

Provide timely updates on construction schedule changes so Commissioning Provider has scheduling information needed to execute commissioning process efficiently. Notify Contracting Officer of anticipated construction delays to commissioning activities not yet performed or not yet scheduled.

3.2 PRELIMINARY BECx PLAN

Submit the Preliminary BECx Plan no later than 14 calendar days after the Commissioning Kickoff Meeting. Submit the Preliminary BECx Plan for inclusion in the Interim Construction Phase Commissioning Plan as identified in Section 01 91 00.15 BUILDING COMMISSIONING. Coordinate the development of this plan with the commissioning plans required in Section 01 91 00.15 BUILDING COMMISSIONING. Outline the commissioning process, commissioning team members and responsibilities, lines of communication, inspections, and documentation requirements for BECx. Identify the Commissioning Standards chosen for the project. Establish appropriate and quantifiable enclosure related performance metrics, test standards, and test methodology in accordance with referenced standards for inclusion in the Contract documents. Provide a list of team members for systems to be commissioned with contact information, a list of tests as required to complete the scope of all commissioning and a copy of the project schedule as required by Section 01 32 17.00 20 COST-LOADED NETWORK ANALYSIS SCHEDULE for inclusion in the Preliminary BECx Plan.

The Preliminary BECx Plan must include, at a minimum, the following:

1. Required performance of commissioned equipment, systems, and assemblies, and results of FPT and verification.

2. Summary of compliance of the building and its components, assemblies, controls, and systems with requirements.

3. Issues and resolution logs, including itemization of deficiencies found during verification, testing, and commissioning that have not been corrected at the time of report preparation.

4. Deferred tests that cannot be performed at the time of report preparation.

5. Documentation of the training of operation personnel and building

occupants on commissioned systems, and a plan for the completion of any deferred trainings not completed at the time of report preparation.

6. A plan for the completion of commissioning and training, including climatic and other conditions required for performance of the deferred tests.

3.3 DESIGN REVIEW

Provide a Design Review Report identifying discrepancies or deficiencies that would prevent the systems to be commissioned from operating or performing in accordance with the design requirements or being safely maintained. Submit the building enclosure-related Design Review Report for inclusion in the overall project Design Review Report as identified in Section 01 91 00.15 BUILDING COMMISSIONING. Report must include individual list of each deficiency and corresponding corrective action necessary for proper system performance. Submit the Design Review Report no later than 14 calendar days after approval of the Commissioning Firm and Commissioning Specialists. The Contracting Officer, Construction Manager, the BECxP, and the Designers of Record for the associated systems must meet, discuss, and resolve any outstanding items contained in the report no later than 14 calendar days after submission of the report.

The BECxP is responsible for reviewing the design and preparing a Design Review Report identifying discrepancies or deficiencies that would prevent the systems to be commissioned from operating or performing in accordance with the design requirements or being safely maintained. The Contracting Officer, the CxC, the BECxP, and the Designers of Record for the associated systems must meet, discuss, and resolve any outstanding items contained in the report no later than 14 calendar days after submission of the report. The BECxP must verify that the review comments have been adequately addressed in subsequent design submittals.

Give particular attention to the continuity of the air barrier, vapor and moisture control within enclosure assembly, acoustic control of the enclosure assemblies to meet required Outdoor Indoor Transmission Class (OITC) values, flashing, thermal bridges, and resistance to water penetration or ponding.

3.4 FINAL BECx PLAN

Submit the Final BECx Plan for inclusion in the Interim Construction Phase Commissioning Plan as identified in Section 01 91 00.15 BUILDING COMMISSIONING. Outline the commissioning process, commissioning team members and responsibilities, lines of communication, and documentation requirements for BECx. Identify the Commissioning Standards chosen for the project. Identify enclosure related inspections, performance metrics, test standards, and test methodologies in accordance with referenced standards for inclusion in the commissioning process.

Provide a list of team members for systems to be commissioned with contact information, a list of tests as required by this Section as well as 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM, and a copy of the project schedule as required by Section 01 32 17.00 20 COST-LOADED NETWORK ANALYSIS SCHEDULE for inclusion in the Final BECx Plan. Final BECx plan must be submitted with the Interim Construction Phase Commissioning Plan, and must be updated and included with the Final Construction Phase

Commissioning Plan as identified in Section 01 91 00.15 BUILDING COMMISSIONING.

3.5 CONSTRUCTION SUBMITTAL REVIEWS

Coordinate construction submittal document reviews for commissioned systems and assemblies with the CxC and BECxP. The commissioning submittal review does not replace the designer of record (DoR) or Government submittal review, in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.

The BECxP is responsible for identifying construction submittals to be provided by the Contractor for the commissioned systems and coordinating with the CxC. The BECxP is responsible for evaluating construction submittals related to BECx for compliance with the Contract documents.

3.6 TEMPLATE BUILDING ENVELOPE INSPECTION CHECKLISTS

Use the Template Building Envelope Inspection Checklists prepared by the CxC to verify the building materials and construction maintain the required air tightness of the building envelope system.

The Building Envelope Compliance Documentation Form from ASHRAE 90.1 - IP User's Manual may be used as an example. The submitted checklist is not required to match the format of the form; however, the checklist must contain the same level of detail as shown on the mandatory provisions of the sample form.

3.7 BUILDING ENVELOPE INSPECTION AND TESTING

Demonstrate that all system components have been installed, that each building enclosure component operates, and that the systems operate and perform in accordance with Contract documents and the Owner's Project Requirements. Provide all materials, services, and labor required to perform the Building Envelope Inspections.

Participate in periodic building envelope inspections with the commissioning specialists using the approved Template Building Envelope Inspection Checklists to observe and document construction of the building envelope in-progress. Coordinate inspection requirements with Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM and other Division 7 Specifications. Complete the checklists and indicate inspection and validation of each Building Envelope Inspection Checklist item by initials at the time they are inspected. Notify the Commissioning Specialist and Contracting Officer at least 21 calendar days before checklist items are concealed to ensure inspection items can be observed before construction progresses. Submit the initialed and Completed Building Envelope Inspection Checklists no later than 14 calendar days after completion of inspection of all checklist items. Notify the BECx at least 21 calendar days prior to the building envelope pressure tests and diagnostic tests specified in this Section.

3.7.1 Additional Building Enclosure Testing

a. Conduct adhesion tests on liquid-applied and adhered waterproofing and air/weather barrier in accordance with ASTM D4541.

b. Conduct air leakage testing of fenestration in accordance with

ASTM E783.

c. Conduct small scale bubble tests of waterproofing and air/weather barriers in accordance with ASTM E1186.

d. Conduct water penetration tests of fenestration in accordance with ASTM E1105.

e. Conduct water penetration tests of installed storefronts, curtainwall, and sloped glazing systems in accordance with AAMA 501.2.

f. Conduct adhesion and cohesion tests of sealants in accordance with ASTM C1193.

3.8 BUILDING ENCLOSURE AIR BARRIER PRESSURE TESTING

3.8.1 Pressure Test Agency

Employ an independent agency to conduct the pressure test on the building envelope in accordance with ASTM E779 and this specification section. The test agency is to be an independent third-party subcontractor, not an affiliated or subsidiary of the prime Contractor, subcontractors, or A/E firm. The agency is to be regularly engaged in pressure testing of commercial/industrial building envelopes. If using blower door or trailer-mounted fans, the lead test technician must have at least two years of experience in using such equipment in building envelope pressurization tests. Formal training using pressure test equipment is highly recommended. Technicians using the building's air handling system for pressure testing are to have tested at least five commercial/industrial buildings within the past two years with each building having over 50,000 square feet of floor area. Submit the name, address, and floor areas of each of these five buildings for approval.

3.8.1.1 Field Work

The lead pressure test technician and thermographer are to be present at the project site while testing is performed and is to be responsible for conducting, supervising, and managing of their respective test work. Management includes health and safety of test agency employees.

3.8.1.2 Reporting Work

The lead pressure test technician is to prepare, sign, and date the test agenda, equipment list, and submit a certified Air Leakage Test Report. The thermographer is to prepare, sign, and date the test agenda, equipment list, and submit a certified Thermographic Investigation Report. The Contractor is to prepare a final report that identifies improvements that were made to the envelope to reduce air leaks , mitigate thermal bridging, eliminate moisture migration,, repair insulation voids discovered during diagnostic tests. The Verification & Testing (V&T) providers must certify completion of required verification and FPT and include a plan for the completion of any deferred FPT, including climatic and other conditions required for performance of the deferred tests; include the results of the FPT and verification activities in the completed verification and FPT (functional performance testing) documentation. Jointly submit all reports.

3.8.2 Envelope Surface Area Calculation

The architectural air barrier boundary includes the floor, walls, and ceiling. After construction of the air barrier envelope is complete, field measure the envelope to ensure the physical measurements match the design drawings and the air barrier envelope surface area calculations are generated. If the calculation result is not within 10 percent of the defined air barrier boundary calculation result as indicated, submit the envelope surface area calculation and results for review. If the air barrier was defined during design but the air barrier envelope surface area was not calculated, calculate it during construction and submit the envelope surface area calculations and result for review.

3.8.3 Preparing The Building Envelope For The Pressure Test

3.8.3.1 Testing During Construction

The pressure test cannot be conducted until all components of the air barrier system have been installed. After all sealing as described herein has been completed, inspect the envelope to ensure it has been adequately prepared. During the pressure test, stop all ongoing construction within and neighboring the envelope which may impact the test or the air barrier integrity. The pressure test may be conducted before finishes that are not part of the air barrier envelope have been installed. For example, if suspended ceiling tile, interior gypsum board or cladding systems are not part of the air barrier the test can be conducted before they are installed. Recommend testing prior to installing the finished ceilings and interior wall finishes within the envelope and immediately surrounding it. The absence of finishes allows for inspection and diagnostic testing of the roof/wall interface and for implementation of repairs to the air barrier, if necessary to comply with the maximum allowed leakage.

3.8.3.2 Sealing the Air Barrier Envelope

The Contractor is to seal all penetrations through the air barrier. Unavoidable penetrations due to electrical boxes or conduit, plumbing, and other assemblies that are not air-tight are to be made so by sealing the assembly and the interface between the assembly and the air barrier or by extending the air barrier over the assembly. Support the air barrier to withstand the maximum positive and negative air pressure to be placed on the building without displacement or damage, and transfer the load to the structure. Durably construct the air barrier to last the anticipated service life of the assembly and to withstand the maximum positive and negative pressures placed on it during pressure testing. Do not install lighting fixtures that are equipped with ventilation holes through the air barrier.

3.8.3.3 Sealing Plumbing

Prime all plumbing traps located within the envelope full of water.

3.8.3.4 Close and Lock Doors

Close and lock all doors and windows in the envelope perimeter. For doors not equipped with latching hardware, temporarily secure them in the closed position. Secure the doors in such a way that they remain fully closed even when the maximum anticipated differential air pressure produced during the test acts on them. Provide signage stating not to open the door and the time and duration of the test.

3.8.3.5 Hold Excluded Building Areas at the Outdoor Pressure Level

Keep building areas immediately surrounding but excluded from the test envelope at the outdoor pressure level during the pressure test. Maintain these areas at the outdoor pressure level by propping exterior doors open, opening windows and de-energizing all air moving devices in or serving these areas.

3.8.3.6 Maintain an Even Pressure within the Envelope

Ensure the pressure differences within the envelope are minimized by opening all internal air pathways including propping open all interior doors. Distribute test fans throughout the envelope as necessary to ensure the internal pressures are uniform (within 10 percent of the average differential pressure). Ideally, do not install suspended ceilings until after all pressure tests have been completed. If, however the envelope includes finished suspended ceiling spaces, temporarily remove approximately 5 percent of all ceiling tiles or a minimum of 1 tile from each isolated suspended ceiling space, whichever comprises the greatest surface area. Temporarily remove additional ceiling tiles during testing to allow for inspection and diagnostic testing of the ceiling/wall interface. An alternative to removing ceiling tiles is to measure the differential pressure between each isolated suspended ceiling space and the outdoors when the area below the suspended ceiling is maintained at a differential pressure of 75 Pa with respect to the outdoors. If the suspended ceiling differential pressure measurement is within ten percent of the 75 Pa pressure below the suspended ceiling no ceiling tiles need to be removed.

3.8.3.7 Maintain Access to Mechanical and Electrical Rooms

Maintain access to mechanical rooms and electrical rooms associated with the envelope to allow for de-energizing ventilation equipment and resetting circuit breakers tripped by blower door equipment, if used.

3.8.3.8 Minimize Potential for Blowing Dust and Debris

Because high velocity air will be blown into and out of the envelope during the test, debris, including dust and litter, may become airborne. Airborne debris may become trapped or entangled in test equipment, thereby skewing test results. Ensure areas within and surrounding the envelope are free of dust, litter and construction materials that are easily airborne. If pressurizing existing, occupied areas, provide adequate notice to building occupants of blowing dust and debris, and general disruption of normal activities during the test.

3.8.3.9 De-energize Air Moving Devices

De-energize all air moving devices serving the envelope to keep air within the envelope as still as reasonably achievable. De-energize all fans that deliver air to, exhaust air from, or recirculate air within the envelope. Also, de-energize all fans serving areas adjacent to but excluded from the envelope.

3.8.3.10 Installing Blower Door Equipment in a Door Opening

Where blower door fans are used, before installing blower door equipment, select a door opening that does not restrict air flow into and out of the

envelope and has at least 5 feet clear distance in front of and behind the door opening. Disconnect the door actuator and secure the door open to prevent it from being drawn into the fan-by-fan pressure. Avoid installing blower door equipment on the windward side of the building.

3.8.4 Building Envelope Air Tightness Requirement

For each building envelope, perform the Architectural Only test and if noted below, the Architectural Plus HVAC System test. The purpose of the pressure (air leakage) test is to determine final compliance with the airtightness requirement by demonstrating the performance of the continuous air barrier. An effective air barrier envelope minimizes infiltration and exfiltration through unintended air paths (leaks). The tests may be performed in any desired order.

3.8.4.1 Architectural Only Test

The test envelope is the architectural air barrier boundary as defined on the Contract drawings. This boundary includes connecting walls, roof and floor which comprise a complete, whole, and continuous three-dimensional envelope. Perform both a positive pressure test and a negative pressure test on this envelope, unless otherwise directed.

3.8.4.1.1 Test Goal

Input data from the test into the Air Leakage Rate by Fan Pressurization spreadsheet as described in paragraph CALCULATION PROGRAM via the Air Leakage Test Form. Compare output from the spreadsheet against the maximum allowable leakage defined in Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM. The envelope passes the test if the leakage rate, as calculated using the spreadsheet, is equal to or lower than the Architectural Only leakage rate goal.

3.8.4.1.2 Preparing the Envelope for the Pressure Test - Seal All Openings through the Air Barrier

Temporarily close all perimeter windows, roof hatches and doors in the envelope perimeter except for those doors that are to remain open to accommodate blower door or trailer mounted fan test equipment installation. Seal, or isolate all other intentional openings, pathways, and fenestrations through the architectural envelope prior to pressure testing. Follow the Recommended Test Envelope Conditions identified in ASTM E1827, Table 1, for the Closed Envelope condition. These openings may include boiler flues, fuel-burning water heater flues, fuel-burning kitchen equipment, clothes dryer vents, fireplaces, wall or ceiling grilles, diffusers, and other similar openings. Before sealing flues, close their associated fuel valves and verify the associated pilot lights are extinguished. Prime all plumbing traps located within the envelope full of water. In lieu of applying tape or plastic, typical temporary sealing materials include tape and sheet plastic or a self-adhesive grille wrap. Use and apply tape and plastic in a manner that does not deface or remove paint or mar the finish of permanent surfaces. Be especially aware of residue that remains from tape applied to stainless steel surfaces such as kitchen hoods or rollup doors. For painted surfaces, use tape types that do not remove finish paint when the tape is removed. If paint is removed from the finished surface, repaint to match existing surfaces. Secure dampers closed either manually or by using the building's HVAC system controls. Use the table below for further guidance in building preparation.

Building Component	Envelope Condition
Air handling units, duct fans	As found (open) or temporarily sealed as necessary
Clothes dryer	Off
Clothes dryer vents	Temporarily sealed
Dampers - intake, exhaust	Physically closed or closed using control power or temporarily sealed
Diffusers, registers, grilles within the envelope	Temporarily sealed
Doors, personnel type, at the envelope perimeter	Secured closed
Doors, personnel type, within the envelope	Secured (propped) open
Doors, roll-up type, at the envelope perimeter	Closed (no additional sealing)
Exhaust hoods	Closed* and temporarily sealed
Fireplace hearth	Temporarily sealed *
Kitchen hoods	Temporarily sealed *
Pilot light and associated fuel valve	Extinguished and closed, respectively
Vented combustion appliance	Temporarily sealed *
Vented combustion appliance exhaust flue	Off
Windows	Secured closed
* If the building component has an associated manual or automatic damper, consider securing the damper closed in lieu of temporarily sealing.	

3.8.4.2 Architectural Plus HVAC System Test

This test envelope includes the architectural air barrier boundary as defined on the Contract drawings plus all HVAC supply, return and exhaust systems that penetrate and terminate within said architectural air barrier boundary and that extends outward from said boundary. All associated ductwork, intake and exhaust dampers, and air moving devices, including air handling units and fans, are included in this test envelope even if they are physically located outside of the architectural air barrier boundary. The boundary extends to and includes the low leakage intake and exhaust dampers. Perform both a positive pressure test and a negative pressure test on this envelope, unless otherwise indicated.

3.8.4.2.1 Test Goal

Data from the test is to be input into the Air Leakage Rate by Fan Pressurization spreadsheet as described in paragraph CALCULATION PROGRAM via the Air Leakage Test Form. If both positive and negative pressure tests were performed, both data sets are to be input in the spreadsheet.

Compare output from the spreadsheet against the leakage rate goal. The envelope passes the test if the leakage rate, as calculated using the spreadsheet, is equal to or lower than the Architectural Plus HVAC System leakage rate goal.

3.8.4.2.2 Preparing the Building for the Pressure Test

In preparation for this test, de-energize all air moving devices within this envelope by putting their controls in the Unoccupied mode. This allows the building's HVAC controls to close all associated motorized intake, exhaust, and relief dampers. Make no other changes to the HVAC systems. Temporarily sealing diffusers, grilles, registers, kitchen hoods, exhaust hoods, fans, air handling units and all other HVAC system elements with tape or plastic sheeting or any other means is not allowed. If the envelope includes a fireplace hearth do not seal it with tape and plastic. Use the table below for further guidance in building preparation.

Building Component	Envelope Condition
Air handling units, duct fans	As found (open)
Clothes dryer	Off
Clothes dryer vents	As found (no preparation)
Dampers - intake, exhaust	As found (no preparation)
Diffusers, registers, grilles within the envelope	As found (open)
Doors, personnel type, at the envelope perimeter	Secured closed
Doors, personnel type, within the envelope	Secured (propped) open
Doors, roll-up type, at the envelope perimeter	Closed (no preparation)
Exhaust hoods	Closed
Fireplace hearth	As found (open)
Kitchen hoods	As found (open)
Pilot light and associated fuel valve	Extinguished and closed, respectively
Vented combustion appliance	Off
Vented combustion appliance exhaust flue	As found (open)
Windows	Secured closed

3.8.5 Conducting The Pressure Test

Notify the Contracting Officer at least ten(10) working days before conducting the pressure tests to provide the Government the opportunity to witness the tests and to monitor weather forecasts for conditions

favorable for testing. Do not pressure test until verifying that the continuous air barrier is in place and installed without failures in accordance with installation instructions. During the pressure test periodically inspect temporarily sealed items to ensure they are still sealed. Seals on temporarily sealed items tend to release more readily at higher pressures. Test data obtained after temporarily sealed items become unsealed cannot be used as input into the calculation program. Follow the Envelope Pressure Test Procedures in the paragraphs below. Submit detailed pressure test procedures indicating the test apparatus, the test methods and procedures, and the analysis methods to be employed for the building envelope pressure (air tightness) test. Submit these procedures not later than 60 days after Notice to Proceed.

3.8.5.1 Extend Pneumatic Tubes and Establish a Reference Differential Pressure

Confirm the various zones within the envelope have a relatively uniform interior pressure distribution by establishing a representative differential pressure between the envelope and the outdoors with blower door or trailer-mounted fans operating. The number of indoor pressure difference measurements (pneumatic hoses) required depends on the number of interior zones separated by bottle necks that could create significant pressure drops (e.g., doorways and stairwells). Extend at least four pneumatic hoses (differential pressure monitoring ports) to locations within the envelope that are physically opposite of each other. In multiple story buildings, especially those over three stories, extend hoses to multiple floors. Locate the hose ends away from the effects of air discharge from blower test equipment. Select one of the four (or more) interior hoses, one judged by the test agency to be the most unaffected by air velocity produced by blower test equipment, to serve as the interior reference pressure port. Extend at least one additional pneumatic hose to the outdoors (outdoor pressure port). To the end of this hose manifold at least four hoses together and terminate each hose on a different side of the building. With the envelope sealed and the blowers energized, measure the differential pressure using the interior reference pressure port and the four outdoor pressure ports. Then measure and record the differential pressure by individually using each of the remaining three interior hoses. Ensure each reading is within plus or minus 10 percent of the reference reading. Thus, at an average 75 Pa maximum pressure difference across the envelope, the difference between the highest and lowest interior pressure difference measurements should be 15 Pa or less. If this condition cannot be met, attempt to create additional air pathways within the envelope to minimize pressure differences within the envelope. If necessary, move the interior hose ends. See step 2.13 of the Air Leakage Test Form in Appendix A.

3.8.5.2 Bias Pressure Readings

With the fan pressurization equipment de-energized and the envelope sealed, obtain the differential pressure between the outdoors and the envelope. Record 12 bias pressure readings before the pressure test and 12 bias pressure readings after the pressure test. Each reading is the average of ten or more 1-second measurements. Include positive and negative signs for each reading. To help dampen bias pressures that significantly contribute to test pressure, reduce temperature differences between indoor and outdoor air. Temperature differences can be reduced by operating test fan equipment for a few minutes to replace most of the indoor air with outdoor air.

3.8.5.3 Testing in Both Positive and Negative Directions

The preferred method for testing a building envelope is to test in both the pressurized and depressurized directions. Testing in one direction is only allowed if opposite direction testing cannot logistically be performed due to test equipment limitations or restrictions. After obtaining the pre-test bias differential pressure readings, conduct the pressure test. Record the envelope pressures (in units of Pascals) from one interior pneumatic hose (monitoring port) and the outdoor pneumatic hose(s), averaged or manifolded, with corresponding flows (in units of cfm) for each fan. Record the flow rates at least 10 to 12 positive and 10 to 12 negative building pressure readings. If conducting both positive and negative pressure tests the lowest allowable test pressure is 40 Pa and the highest test pressure is 85 Pa. Keep at least 25 Pa difference between the lowest and highest test pressure readings. Include the 75 Pa pressure value between the lowest and highest readings. The 10 to 12 readings in each direction are to be roughly evenly spaced along the range of pressures and flows. After testing is complete de-energize the equipment used to provide pressurization and obtain an additional 10 to 12 post-test bias pressure readings. None of the bias pressure readings are allowed to exceed 30 percent of the minimum test pressure. If these limits are exceeded the test fails and must be repeated.

3.8.5.4 Single Direction Testing

After obtaining the 12 aforementioned bias pressure readings, conduct the positive pressure test. Obtain flow rates at 10 to 12 roughly evenly spaced pressure readings over a pressure range of 50 to 85 Pa. After the data is recorded, de-energize the blower equipment and obtain an additional 10 to 12 bias pressure readings. None of the bias pressure readings may exceed 10 percent of the minimum test pressure. If these limits are exceeded the test fails.

3.8.5.5 Using a Building's Own Air Handling System to Pressure Test an Envelope

3.8.5.5.1 Test Setup

Temporarily seal the envelope in a manner similar to that for testing with blower door or trailer-mounted fans. To positively pressurize the envelope, de-energize all ventilation equipment and close all associated dampers, except those outside air intake dampers associated with supply fans that will be used to pressurize the building envelope. Fully open these dampers. For the negative pressure test, de-energize all ventilation equipment except for those fans that will be used to de-pressurize the envelope. All dampers associated with de-energized fans are to be closed and all exhaust dampers associated with fans used to de-pressurize the envelope will be fully opened.

3.8.5.5.2 Measuring Airflows

When using the building's own air handling system to pressure test the envelope, air flows can generally be measured using one of the following methods:

a. When testing using the building's own air handling system, ensure flow readings obtained by anemometer comply with ASTM D3464. Pitot tube or hot wire anemometer traverse in accordance with ASTM D3464.

b. Pressure compensated shrouds (especially recommended for rooftop exhaust fans)

c. Tracer gas methods for measuring airflows in ducts in accordance with ASTM E2029. Do not use tracer gas decay, constant injection, and constant concentration methods for estimating the total ventilation rate of the envelope.

3.8.5.5.3 Outdoor Air Flow Measuring Stations

Air flow stations may be used to measure outdoor airflows if one of the above methods is used to check accuracy of at least one air flow reading for each station or if the design of the HVAC system specifically placed outdoor air flow stations in locations that will yield accurate results. Field verify the accuracy of readings at the air flow measuring stations before obtaining pressure test readings.

3.8.5.6 Pressure Testing - Special Cases

3.8.5.6.1 Pressure Testing a Tall or Large Building Envelope

Pressure testing the envelope of a tall or large building may be unworkable and unrealistic using blower door or trailer-mounted equipment. In this case, the test agency may define and pressure test separate zones or floors within the envelope and sum the leakage all of the zones to create an overall envelope leakage rate. Using this method, the test agency is to comply with the requirements of ASHRAE RP-935.

3.8.5.6.2 Pressure Testing a Multiple Isolated Zoned Building

Pressure test each exterior corner zone plus at least an additional 20 percent (as measured by floor area) of remaining zones. The Contracting Officer is responsible for selecting which of these additional zones to test. If all zones pass the pressure test it is assumed that all untested zones also pass and no further testing is required. If, however, any zone fails to pass the test's leakage requirements, re-seal, and re-test until it passes in accordance with paragraph FAILED PRESSURE TEST. Test an additional 20 percent of previously untested zones. If all tested zones pass, no further testing is needed. If any zone in this group fails the test re-seal and re-test the zone until it passes. Continue this process until all the tested zones pass. When testing a zone, the doors to all adjacent zones that share a common surface with the tested zone are to have their doors opened to the outdoors. The resulting leakage from the test zoned is that through all six surfaces (4 walls, roof, and floor, for a rectangular shaped zone).

3.8.5.6.3 Pressure Testing a Building Addition

If the existing building is occupied, coordinate the pressure test with building representatives. In preparation of the test, de-energize the air handling system serving that portion of the existing building that shares surfaces with the new building addition. Pressure testing a new building addition may also require pressurizing that part of the existing building that shares surfaces in common with the new building addition. If an air barrier is applied to the common surfaces separating the existing building from the new addition, prior to the test prop open a sufficient quantity of doors and windows to keep the existing building at the same pressure as the outdoors. If an air barrier is not applied to the common surfaces separating the existing building from the new addition, pressurize that

part of the existing building that shares surfaces in common with the building addition to the same level as the as the addition using separate test pressurization equipment.

3.8.5.7 Failed Pressure Test

If the pressure test fails to meet the established criteria, use diagnostic test methods described in paragraph LOCATING LEAKS BY DIAGNOSTIC TESTING to discover the leak locations. Provide additional permanent sealing measures to reduce or eliminate leak sources discovered during diagnostic testing. Retest (perform another pressure test) after sealing has been completed. Repeat this sequence of documenting test results in the test report, performing diagnostic tests, documenting recommendations for additional sealing measures in the test report, sealing leak locations per recommendations, and re-testing as necessary until the building envelope passes the pressure test and is in compliance with the performance requirements.

3.8.5.8 Air Leakage Test Report

Report volumetric flow rates and corresponding differential pressures in cubic feet per minute (cfm) and Pascals (Pa), respectively, on the Air Leakage Test Form sample form found in Appendix A. Populate the accompanying spreadsheet file titled Pressure Test Data Analysis with information obtained during the test. The spreadsheet uses equations found in ASTM E779 as a basis for calculating the envelope leakage rate. Other similar leakage rate calculation programs cannot be used or submitted for review. Submit a printout of the data input and output in the report. Should any air tightness (pressure) test fail, the pressure test report is to include data and results from all previous failed tests along with the final successful test data and results. Indicate if the resulting leakage rate did or did not meet the goal leakage requirement. Identify and document deficiencies in the building construction upon failure of a test to meet the specified maximum leakage rate.

Test reports on leakage tests performed using fan pressurization must meet ASTM E779 requirements; reports on tests performed utilizing blower door testing must meet ASTM E1827 requirements. Include the Test Agency Qualification Sheet, Air Leakage Test Form and Air Leakage Test Results Form in the written report. Document every test set-up condition with diagrams and photos to ensure the tests can be made repeatable. Document all pneumatic hose termination locations. Record in detail how the building envelope was prepared for the tests. Also describe in detail which building items were temporarily sealed. Include photos of test equipment and sealing measures in the report. Include an electronic (pdf) version of all test reports on a CD. If the building envelope fails to meet the leakage rate goal, provide recommendations to further seal the envelope and document these recommendations in the test report.

3.8.6 Locating Leaks By Diagnostic Testing

Use diagnostic test methods described herein to discover obvious leaks through the envelope. Perform diagnostic tests on the building envelope regardless of the envelope meeting or failing to meet the designated leakage rate goal. Use diagnostic test methods in accordance with ASTM E1186 and in conjunction with pressurization equipment, as necessary. Use the thermography diagnostic test to establish a baseline for envelope leakage. Apply additional diagnostic tests (find, feel, fog or other tests) as necessary to further define leak locations and pathways

discovered using thermography or to find additional leaks not readily detected by thermography. Using a variety of diagnostic tests may help locate leaks that would otherwise go undetected if only a single diagnostic test were used. Pay special attention to locating leaks at interfaces where there is a change in materials or a change in direction of like materials. These interfaces, at a minimum, include roof/wall, wall/wall, floor/wall, wall/window, wall/door, wall/louver, roof mounted equipment/roof curb interfaces and all utility penetrations (such as ducts, pipes, and conduit) through the envelope's architecture. Also use diagnostic tests to check for leakage between the air duct and duct damper, when the damper, under normal control power, is placed in the closed position.

3.8.6.1 Sealing and Re-Testing

Should leaks be discovered during diagnostic tests, thoroughly document the exact leak locations on a floor plan so that sealing can be later applied, if required or as directed. If the envelope passes the leakage test, use the diagnostic test procedure described above to identify obvious leakage locations. Seal the leaks at the discretion of the COR based on the magnitude, location, potential for liquid moisture penetration or retention, potential for condensation, presence of daylight through an architectural surface or if the leakage location could potentially cause rapid deterioration or mold growth of, or in the building envelope materials and assemblies. Apply sealing measures after diagnostic testing is complete and all pressurization blowers are off. To verify that the applied sealing measures are effective, re-test for leaks using the same diagnostic methods that discovered the leak. Reseal and retest until the envelope meets the leakage rate goal and all obvious leaks through the envelope are sealed.

3.8.6.2 Find Test

Use visual observation to locate daylight or artificial light streaming from the opposite side of the envelope. Observe all interfaces identified above.

3.8.6.3 Feel Test

Use the building's air handling system or blower door equipment to negatively pressurize the building envelope, to at least 25 Pa but no greater than 85 Pa, with respect to the outdoors. The larger the pressure difference, the easier discovering leaks by feeling them becomes. While inside the envelope, hand feel roof/wall, wall/wall, and floor/wall interfaces and utility penetrations (such as ducts, pipes and conduit) for leaks and note the leak locations on a floor plan. The "Feel" test may also be used to check for leaks between the ductwork and ductwork damper. To do this, positively pressurize the envelope and check for air movement from the envelope exterior.

3.8.6.4 Infrared Thermography Test

Coordinate thermography examination with the pressure test agency and the test agency's pressurization equipment. The pressure test agency is to allow adequate time for the thermographer to perform a complete thermographic examination, as described hereinafter, of the envelope interior and exterior, including readings of the roof.

3.8.6.4.1 Thermography Test Methods

Before thermographic testing, remove furniture, construction equipment, and all other obstructions both inside and outside the building as necessary to gain a clear field of view. In the Thermographic Investigation Report, document all areas where obstructions remain. For exterior thermal examination of the envelope, including readings of the roof, verify that no direct solar radiation has heated the envelope surfaces to be examined for a period of approximately 3 hours for frame construction and for approximately 8 hours for masonry veneer construction. Conduct exterior investigations after sunset, before sunrise, or on an overcast day when the influence of solar radiation can be determined to be minimal. Limit exterior examinations to times when the influence of solar radiation is minimal, such as after sunset or before sunrise or during an overcast day. Conduct thermal imaging tests only when wind speeds are less than 8 mph at the time of analysis and at the end of analysis. Document any variations in wind during the test. Document all variations of test conditions in the Thermographic Investigation Report. Test only when exterior surfaces are dry. Monitor and document ongoing test parameters, such as the temperatures inside and outside the air barrier envelope, wind speed, and differential pressure.

3.8.6.4.1.1 Thermography Testing of the Air Barrier

Test the building envelope in accordance with ISO 6781, and ASTM E1186. Perform a complete thermographic inspection consisting of the full inspection of the interior and exterior of the complete air barrier envelope, to include readings of the roof. Document envelope areas that are inaccessible for testing. Use infrared thermography technology in concert with standard pressurization methods (blower doors, trailer mounted fans or the building's own air handling systems) to locate leaks through the air barrier. Adjust the HVAC system, if possible, to create or enhance the temperature difference between the envelope interior and exterior. The minimum allowable temperature difference is 9 degrees F. Maintain this temperature difference for at least 3 hours prior to the test. Use pressurization methods to establish a minimum of +20 Pa pressure difference with respect to the outdoors while using an infrared camera to view the envelope from outdoors. When viewing with the camera from inside the envelope, keep the envelope at a pressure differential of -20 Pa with respect to the outdoors using pressure testing equipment or the building's own air handling system.

3.8.6.4.2 Thermography Test Results

Document the location of all leaks, anomalies, and unusual thermal features on a floor plan or elevation view and catalog them with a visible light picture for locating the defect for correction. The thermographer is to recommend corrective actions to eliminate the leaks, anomalies, and unusual thermal features. Where leaks are found perform corrective sealing as necessary to achieve the whole envelope air leakage rate specified. After sealing, again use thermography in concert with standard pressurization methods to verify that the air leakage has been reduced. After these leaks have been permanently sealed, note all actions taken on the drawings or in the Thermographic Investigation Report. Submit the drawings for approval as part of the Thermographic Investigation Report. Also include thermographic photos that show where leaks were discovered. Include thermograms using an imaging palette that clearly shows the observed thermal patterns indicating air leakage. The Contracting Officer's Representative is to witness all testing.

3.8.6.5 Fog Test

Before using a theatrical fog generator, disable all building smoke detectors as they may alarm when fog is issued. Coordinate fog tests and the disabling of all smoke detectors with the Contracting Officer's representative and the local fire department as necessary. Use pressure test equipment or the buildings own air handling system to positively pressurize the building envelope to at least 25 Pa but not greater than 85 Pa over the outdoors. Using a theatrical fog generator within the envelope, direct fog at suspected leakage points such as at building interfaces. Test the following interfaces: roof/wall, wall/wall, floor/wall, wall/window, roof/mounted mechanical equipment. From the vantage point immediately outside the envelope and opposite that of the interface being tested, observe the effect as the fog is issued. Detection may also be further enhanced by using a scented fog liquid or a fog liquid that produces a colored fog. Look for fog and smell for associated odor percolating through the interface. Also use smoke puffers and smoke sticks as necessary to locate leaks at these and other interface locations. If the Architectural Plus HVAC System pressure test will be/was performed introduce fog into ductwork to check for leakage between ductwork and associated dampers. After fog testing has ended, reactivate the building smoke detectors, and notify the Contracting Officer and local fire department that the test has ended. After sealing has been completed retest these areas using fog. Seal additional leaks that are found. (Note that theatrical fog may release quantities of the water vapor, glycol, mineral oil, or other media that could damage electronics and interior finishes or cause allergic reactions. Small scale smoke trace could be used as an alternative. See "Effects of Theatrical Smokes and Fogs on Respiratory Health in the Entertainment Industry" at www.nih.gov.)

3.8.6.6 Diagnostic Test Report

Once the diagnostic tests have been completed and the leakage locations identified and sealed, document these procedures, locations, and recommendations in the diagnostic test report. Submit plan and profile drawings that thoroughly identify leak locations. Describe in detail all leak locations so that the seal-up crew knows where to apply sealing measures. After sealing measures have been applied, describe the methods used along with applicable photos of the final sealed condition.

3.8.6.6.1 Thermographic Investigation Report

Submit a report of each thermographic investigation identifying the thermal discontinuities in the thermal control layer. Indicate in the final report locations to which improvements for both the air control layer and the thermal control layer were made to reduce air leaks and correct discontinuities in the thermal control layer. Include in the report some selected radiometric images of suspected failure points in the air barrier envelope that indicate before and after conditions. Devote a chapter(s) of the Thermographic Investigation Report to identifying suspected points of thermal bridging, moisture migration through roofs and walls, and insulation voids. Indicate in the final report improvements that were made to the envelope to reduce air leaks. Include the following items in the report:

a. Brief description of the building construction

b. Types of interior and exterior surface materials used in the building.

c. Geographical orientation of the building with a description of the exterior surroundings including other buildings, vegetation, landscaping, and surface water drainage.

d. Camera brand, model and serial number, and most recent calibration date; optional lenses with serial numbers (if applicable)

e. Thermographer's and Government Inspector's names

f. Date and time of tests

g. Air temperature and humidity inside the air barrier envelope

h. Outdoor air temperature and humidity

i. General information for the last 12 hours on the solar radiation conditions in the geographic area where the test is being performed.

j. Ambient conditions such as precipitation and wind direction and speed occurring with the last 24 hours, as applicable. Refer to specific requirements in each section of each thermographic inspection type for requirements in each specific area.

k. Documentation of those portions of the building envelope which were not within test conditions when the scan was performed, and which portions were obstructed by adjacent structures, interior furnishings, intervening cavities, or reflective surfaces.

l. Other relevant information, which may have influenced test results.

m. Drawings, sketches, floor plans and photographs detailing the locations in the buildings where thermograms were taken detailing possible irregularities in the components being tested.

n. Thermal images taken during the inspection with their relative locations and written or voiced recorded explanations of the anomaly listed along with visual and reference images.

o. An identification of the aspects or components of the building being examined.

p. Explanations for the type and the extent of each construction defect observed during the inspection.

q. Any results from additional measurements and investigations. Identify additional equipment used and support with type, model number, serial number, and date of most recent calibrated.

3.8.6.6.2 Fog Test Report

Document all turbulent air flow and dead air spaces within the envelope. Report fog behavior as it exits from or is entrained within the building. Include a floor plan in the report that documents the locations where fog passed through the envelope.

3.8.7 Calculation Program

To calculate the envelope leakage rate and other required outputs, input

the data obtained during the pressure tests as documented in the Air Leakage Test Form (Appendix A) into the Air Leakage Rate by Fan Pressurization Excel spreadsheet. This spreadsheet can be found at the following web site:
http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphic

3.8.8 After Completion Of The Pressure And Diagnostic Test

After all pressure and diagnostic testing has been completed unseal all temporarily sealed items. Unless otherwise directed by the Contracting Officer, return all dampers, doors, and windows to their pre-test condition. Remove tape and plastic from all temporarily sealed openings, being careful not to deface painted surfaces. If paint is removed from finished surfaces, repaint to match existing surfaces. Unless otherwise directed by the Contracting Officer's representative, return fuel (gas) valves to their pre-test position and relight pilot lights. Return all fans and air handling units to pre-test conditions. Restore smoke/fire detectors to operating condition.

3.8.9 Repair And Protection

Repair and protection are the Contractor's responsibility, regardless of the assignment of responsibility for testing, inspection, and similar services. Upon completion of inspection, testing, or sample taking and similar services, repair damaged construction and restore substrates and finishes, protect construction exposed by or for quality control service activities, and protect repaired construction.

3.9 TRAINING

The Commissioning Provider is responsible for overseeing and approving the training plan required by Section 01 78 00 OPERATION AND MAINTENANCE DATA and identifying any deficiencies to the Contracting Officer's Representative and the Contractor's Quality Control Personnel.

Coordinate, schedule, and document training of all commissioned systems as required by Section 01 91 00.15 BUILDING COMMISSIONING paragraph titled "Training Plan".

3.10 FINAL BECx REPORT

The BECx must provide a final BECx report that includes information generated by the BECx process including: BECx meeting minutes, design reports, test reports, the final OPR, BoD, final BECx Plan, issue and resolution log, site observations, as-built drawings (provided by the Contractor), submittals, record of training, and recommended preventive maintenance actions and intervals.

The BECxP must ensure the Final BECx Report is submitted as a portion of the Final Commissioning Report for the project, as defined in Section 01 91 00.15 BUILDING COMMISSIONING. Submit report within 14 calendar days of completion of all commissioning efforts.

3.11 APPENDICES

The following forms are available for download as a MS Word file at
http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphic

Appendix A - Air Leakage Test Form

Appendix B - Air Leakage Test Results Form
Appendix C - Test Agency Qualifications Sheet

-- End of Section --

SECTION 02 41 00

DEMOLITION
08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 145	(1991; R 2012) Standard Specification for Classification of Soils and Soil-Aggregate Mixtures for Highway Construction Purposes
AASHTO T 180	(2017) Standard Method of Test for Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and a 457-mm (18-in.) Drop

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.6	(2006) Safety & Health Program Requirements for Demolition Operations - American National Standard for Construction and Demolition Operations

ASTM INTERNATIONAL (ASTM)

ASTM D2487	(2017; E 2020) Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61	National Emission Standards for Hazardous Air Pollutants

1.2 PROJECT DESCRIPTION

1.2.1 Definitions

1.2.1.1 Demolition

Demolition is the process of tearing apart and removing any feature of a facility together with any related handling and disposal operations.

1.2.1.2 Demolition Plan

Demolition Plan is the planned steps and processes for managing demolition activities and identifying the required sequencing activities and disposal mechanisms.

1.2.2 Demolition

Prepare a Demolition Plan and submit proposed demolition, and removal procedures for approval before work is started. Include in the plan procedures for careful removal and disposition of materials specified to be salvaged, coordination with other work in progress, a disconnection schedule of utility services, a detailed description of methods and equipment to be used for each operation and of the sequence of operations. Identify components and materials to be salvaged for reuse or recycling with reference to paragraph Existing Facilities to be Removed. Append tracking forms for all removed materials indicating type, quantities, condition, destination, and end use. Provide procedures for safe conduct of the work in accordance with EM 385-1-1. Plan must be approved by Contracting Officer prior to work beginning.

1.2.3 General Requirements

Do not begin demolition or deconstruction until authorization is received from the Contracting Officer. The work of this section is to be performed in a manner that maximizes the value derived from the salvage and recycling of materials. The work includes demolition of identified items and materials, and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Store materials that cannot be removed daily in areas specified by the Contracting Officer. In the interest of occupational safety and health, perform the work in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections.

1.3 ITEMS TO REMAIN IN PLACE

Comply with FAR 52.236-9 to protect existing vegetation, structures, equipment, utilities, and improvements. Coordinate the work of this section with all other work indicated. Construct and maintain shoring, bracing, and supports as required. Ensure that structural elements are not overloaded. Increase structural supports or add new supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract. Do not overload pavements to remain. Provide new supports and reinforcement for existing construction weakened by demolition, deconstruction, or removal work. Repairs, reinforcement, or structural replacement require approval by the Contracting Officer prior to performing such work.

1.3.1 Existing Construction Limits and Protection

Do not disturb existing construction beyond the extent indicated or necessary for installation of new construction. Provide temporary shoring and bracing for support of building components to prevent settlement or other movement. Provide protective measures to control accumulation and migration of dust and dirt in all work areas. Remove dust, dirt, and debris from work areas daily.

1.3.2 Weather Protection

For portions of the building to remain, protect building interior and materials and equipment from the weather at all times. Where removal of existing roofing is necessary to accomplish work, have materials and workmen ready to provide adequate and temporary covering of exposed areas.

1.3.3 Trees

Protect trees within the project site which might be damaged during demolition or deconstruction, and which are indicated to be left in place, by a 6 foot high fence. Erect and secure fence a minimum of 5 feet from the trunk of individual trees or follow the outer perimeter of branches or clumps of trees. Replace any tree designated to remain that is damaged during the work under this contract with like-kind or as approved by the Contracting Officer.

1.3.4 Utility Service

Maintain existing utilities indicated to stay in service and protect against damage during demolition and deconstruction operations. Prior to start of work, utilities serving each area of alteration or removal will be shut off by the Government and disconnected and sealed by the Contractor.

1.3.5 Facilities

Protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities. Floors, roofs, walls, columns, pilasters, and other structural components that are designed and constructed to stand without lateral support or shoring, and are determined to be in stable condition, must remain standing without additional bracing, shoring, or lateral support until demolished or deconstructed, unless directed otherwise by the Contracting Officer. Ensure that no elements determined to be unstable are left unsupported and place and secure bracing, shoring, or lateral supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract.

1.4 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted. Where burning is permitted, adhere to federal, state, and local regulations.

1.5 AVAILABILITY OF WORK AREAS

Areas in which the work is to be accomplished will be available at contract award.

1.6 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-01 Preconstruction Submittals

Demolition Plan; G

Existing Conditions

SD-07 Certificates

Notification; G

1.7 QUALITY ASSURANCE

Submit timely notification of demolition projects to Federal, State, regional, and local authorities in accordance with 40 CFR 61, Subpart M. Notify the State's environmental protection agency and the Contracting Officer in writing 10 working days prior to the commencement of work in accordance with 40 CFR 61, Subpart M. Comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," conform to the safety requirements contained in ASSP A10.6. Comply with the Environmental Protection Agency requirements specified. Use of explosives will not be permitted.

1.7.1 Dust Control

Prevent the spread of dust and debris and avoid the creation of a nuisance in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution. Sweep pavements as often as necessary to control the spread of debris that may result in foreign object damage potential to aircraft.

1.8 PROTECTION

1.8.1 Traffic Control Signs

a. Where pedestrian and driver safety is endangered in the area of removal work, use traffic barricades with flashing lights. Anchor barricades in a manner to prevent displacement by wind. Notify the Contracting Officer prior to beginning such work.

1.8.2 Protection of Personnel

Before, during and after the demolition work continuously evaluate the condition of the site specific features being demolished and take immediate action to protect all personnel working in and around the project site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.9 FOREIGN OBJECT DAMAGE (FOD)

Aircraft and aircraft engines are subject to FOD from debris and waste material lying on airfield pavements. Remove all such materials that may appear on operational aircraft pavements due to the Contractor's operations. If necessary, the Contracting Officer may require the Contractor to install a temporary barricade at the Contractor's expense to control the spread of FOD potential debris. Provide a barricade consisting of a fence covered with a fabric designed to stop the spread of debris. Anchor the fence and fabric to prevent displacement by winds or jet/prop blasts. Remove barricade when no longer required.

1.10 RELOCATIONS

Perform the removal and reinstallation of relocated items as indicated with workmen skilled in the trades involved. Repair or replace items to be relocated which are damaged by the Contractor with new undamaged items as approved by the Contracting Officer.

1.11 EXISTING CONDITIONS

Before beginning any demolition or deconstruction work, survey the site and examine the drawings and specifications to determine the extent of the work. Record existing conditions in the presence of the Contracting Officer or the Contracting Officer's Representative showing the condition of structures and other facilities adjacent to areas of alteration or removal. Photographs or electronic images with a minimum resolution of 3072 x 2304 pixels, capable of a print resolution of 300 dpi, will be acceptable as a record of existing conditions. Include in the record the elevation of the top of foundation walls, finish floor elevations, possible conflicting electrical conduits, plumbing lines, alarms systems, the location and extent of existing cracks and other damage and description of surface conditions that exist prior to starting work. It is the Contractor's responsibility to verify and document all required outages which will be required during the course of work, and to note these outages on the record document. Submit survey results to the Contracting Officer.

PART 2 PRODUCTS

2.1 FILL MATERIAL

a. Comply with excavating, backfilling, and compacting procedures for soils used as backfill material to fill basements, voids, depressions or excavations resulting from demolition or deconstruction of structures. Provide fill material consisting of waste products from demolition or deconstruction until all waste appropriate for this purpose is consumed.

b. Provide fill material conforming to the definition of satisfactory soil material as defined in ASTM D2487. In addition, fill material must be free from roots and other organic matter, trash, debris, frozen materials, and stones larger than 2 inches in any dimension.

c. Proposed fill material must be sampled and tested by an approved soil testing laboratory, as follows:

Soil classification	AASHTO M 145
Moisture-density relations	AASHTO T 180, Method B or D

PART 3 EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED

Inspect and evaluate existing structures onsite for reuse. Disassemble existing construction scheduled to be removed for reuse. Dismantled and removed materials are to be separated, set aside, and prepared as specified, and stored or delivered to a collection point for reuse, remanufacture, recycling, or other disposal, as specified. Designate

materials for reuse onsite whenever possible.

3.1.1 Utilities and Related Equipment

3.1.1.1 General Requirements

Do not interrupt existing utilities serving occupied or used facilities, except when authorized in writing by the Contracting Officer. Do not interrupt existing utilities serving facilities occupied and used by the Government except when approved in writing and then only after temporary utility services have been approved and provided. Do not begin demolition or deconstruction work until all utility disconnections have been made. Shut off and cap utilities for future use, as indicated.

3.1.1.2 Disconnecting Existing Utilities

Remove existing utilities , as indicated and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Contracting Officer. When utility lines are encountered but are not indicated on the drawings, notify the Contracting Officer prior to further work in that area. Remove meters and related equipment and deliver to a location in accordance with instructions of the Contracting Officer.

3.1.2 Chain Link Fencing

Remove chain link fencing, gates and other related salvaged items scheduled for removal and transport to designated areas. Remove gates as whole units. Cut chain link fabric to 25 foot lengths and store in rolls off the ground.

3.1.3 Concrete

Saw concrete along straight lines to a depth of a minimum 2 inch. Make each cut in walls perpendicular to the face and in alignment with the cut in the opposite face. Break out the remainder of the concrete provided that the broken area is concealed in the finished work, and the remaining concrete is sound. At locations where the broken face cannot be concealed, grind smooth or saw cut entirely through the concrete. Sawcuts in existing concrete sidewalk concrete pads must be at the nearest existing expansion joint or weakened plane joint and at full depth.

3.2 CONCURRENT EARTH-MOVING OPERATIONS

Do not begin excavation, filling, and other earth-moving operations that are sequential to demolition or deconstruction work in areas occupied by structures to be demolished or deconstructed until all demolition and deconstruction in the area has been completed and debris removed. Fill holes, open basements and other hazardous openings.

3.3 CLEANUP

Remove debris and rubbish from project site and similar excavations. Remove and transport the debris in a manner that prevents spillage on streets or adjacent areas. Apply local regulations regarding hauling and disposal.

3.4 DISPOSAL OF REMOVED MATERIALS

3.4.1 Regulation of Removed Materials

Dispose of debris, rubbish, scrap, and other nonsalvageable materials resulting from removal operations with all applicable federal, state and local regulations as contractually specified in the Waste Management Plan. Storage of removed materials on the project site is prohibited.

3.4.2 Burning on Government Property

Burning of materials removed from demolished and deconstructed structures will not be permitted on Government property.

3.4.3 Removal to Spoil Areas on Government Property

Transport noncombustible materials removed from demolition and deconstruction structures to designated spoil areas on Government property.

3.4.4 Removal from Government Property

Transport waste materials removed from demolished and deconstructed structures, except waste soil, from Government property for legal disposal. Dispose of waste soil as directed.

3.5 REUSE OF SALVAGED ITEMS

Recondition salvaged materials and equipment designated for reuse before installation. Replace items damaged during removal and salvage operations or restore them as necessary to usable condition.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 03 30 00

CAST-IN-PLACE CONCRETE
02/19, CHG 4: 08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 117	(2010; Errata 2011) Specifications for Tolerances for Concrete Construction and Materials and Commentary
ACI 121R	(2008) Guide for Concrete Construction Quality Systems in Conformance with ISO 9001
ACI 301	(2016) Specifications for Structural Concrete
ACI 302.1R	(2015) Guide for Concrete Floor and Slab Construction
ACI 304.2R	(2017) Guide to Placing Concrete by Pumping Methods
ACI 304R	(2000; R 2009) Guide for Measuring, Mixing, Transporting, and Placing Concrete
ACI 305R	(2020) Guide to Hot Weather Concreting
ACI 306R	(2016) Guide to Cold Weather Concreting
ACI 308.1	(2011) Specification for Curing Concrete
ACI SP-2	(2007; Abstract: 10th Edition) ACI Manual of Concrete Inspection
ACI SP-15	(2011) Field Reference Manual: Standard Specifications for Structural Concrete ACI 301-05 with Selected ACI References

AMERICAN HARDBOARD ASSOCIATION (AHA)

AHA A135.4	(1995; R 2004) Basic Hardboard

AMERICAN WELDING SOCIETY (AWS)

AWS D1.4/D1.4M	(2011) Structural Welding Code - Reinforcing Steel

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A184/A184M	(2019) Standard Specification for Welded Deformed Steel Bar Mats for Concrete Reinforcement
ASTM A615/A615M	(2022) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A706/A706M	(2022) Standard Specification for Low-Alloy Steel Deformed and Plain Bars for Concrete Reinforcement
ASTM A780/A780M	(2020) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A884/A884M	(2019) Standard Specification for Epoxy-Coated Steel Wire and Welded Wire Reinforcement
ASTM A934/A934M	(2016) Standard Specification for Epoxy-Coated Prefabricated Steel Reinforcing Bars
ASTM A996/A996M	(2016) Standard Specification for Rail-Steel and Axle-Steel Deformed Bars for Concrete Reinforcement
ASTM A1022/A1022M	(2016b) Standard Specification for Deformed and Plain Stainless Steel Wire and Welded Wire for Concrete Reinforcement
ASTM A1060/A1060M	(2016b) Standard Specification for Zinc-Coated (Galvanized) Steel Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM A1064/A1064M	(2024) Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM C31/C31M	(2022) Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C33/C33M	(2024a) Standard Specification for Concrete Aggregates
ASTM C39/C39M	(2021) Standard Test Method for Compressive Strength of Cylindrical

	Concrete Specimens
ASTM C42/C42M	(2020) Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete
ASTM C78/C78M	(2022) Standard Test Method for Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading)
ASTM C94/C94M	(2022a) Standard Specification for Ready-Mixed Concrete
ASTM C136/C136M	(2019) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM C138/C138M	(2017a) Standard Test Method for Density (Unit Weight), Yield, and Air Content (Gravimetric) of Concrete
ASTM C143/C143M	(2020) Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C150/C150M	(2024) Standard Specification for Portland Cement
ASTM C172/C172M	(2017) Standard Practice for Sampling Freshly Mixed Concrete
ASTM C173/C173M	(2016) Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method
ASTM C231/C231M	(2022) Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C260/C260M	(2010a; R 2016) Standard Specification for Air-Entraining Admixtures for Concrete
ASTM C311/C311M	(2022) Standard Test Methods for Sampling and Testing Fly Ash or Natural Pozzolans for Use in Portland-Cement Concrete
ASTM C330/C330M	(2017a) Standard Specification for Lightweight Aggregates for Structural Concrete
ASTM C494/C494M	(2019; E 2022) Standard Specification for Chemical Admixtures for Concrete
ASTM C567/C567M	(2019) Determining Density of Structural Lightweight Concrete
ASTM C595/C595M	(2025) Standard Specification for Blended Hydraulic Cements
ASTM C618	(2025a) Standard Specification for Coal Fly Ash and Raw or Calcined Natural

	Pozzolan for Use in Concrete
ASTM C803/C803M	(2018) Standard Test Method for Penetration Resistance of Hardened Concrete
ASTM C845/C845M	(2018) Standard Specification for Expansive Hydraulic Cement
ASTM C873/C873M	(2015) Standard Test Method for Compressive Strength of Concrete Cylinders Cast in Place in Cylindrical Molds
ASTM C900	(2015) Standard Test Method for Pullout Strength of Hardened Concrete
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM C989/C989M	(2022) Standard Specification for Slag Cement for Use in Concrete and Mortars
ASTM C1012/C1012M	(2018b) Standard Test Method for Length Change of Hydraulic-Cement Mortars Exposed to a Sulfate Solution
ASTM C1017/C1017M	(2013; E 2015) Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete
ASTM C1074	(2019) Standard Practice for Estimating Concrete Strength by the Maturity Method
ASTM C1077	(2026) Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM C1107/C1107M	(2020) Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)
ASTM C1157/C1157M	(2020a) Standard Performance Specification for Hydraulic Cement
ASTM C1218/C1218M	(2020c) Standard Test Method for Water-Soluble Chloride in Mortar and Concrete
ASTM C1240	(2020) Standard Specification for Silica Fume Used in Cementitious Mixtures
ASTM C1260	(2021) Standard Test Method for Potential Alkali Reactivity of Aggregates (Mortar-Bar Method)
ASTM C1293	(2008; R 2015) Standard Test Method for Determination of Length Change of Concrete Due to Alkali-Silica Reaction
ASTM C1567	(2025) Standard Test Method for

	Determining the Potential Alkali-Silica Reactivity of Combinations of Cementitious Materials and Aggregate (Accelerated Mortar-Bar Method)
ASTM C1602/C1602M	(2022) Standard Specification for Mixing Water Used in Production of Hydraulic Cement Concrete
ASTM C1778	(2016) Standard Guide for Reducing the Risk of Deleterious Alkali-Aggregate Reaction in Concrete
ASTM D412	(2016; R 2021) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D471	(2016a) Standard Test Method for Rubber Property - Effect of Liquids
ASTM D1751	(2018) Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D2628	(1991; R 2016) Standard Specification for Preformed Polychloroprene Elastomeric Joint Seals for Concrete Pavements
ASTM D2835	(1989; R 2017) Standard Specification for Lubricant for Installation of Preformed Compression Seals in Concrete Pavements
ASTM D5759	(2012; R 2020) Characterization of Coal Fly Ash and Clean Coal Combustion Fly Ash for Potential Uses
ASTM D6690	(2015) Standard Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements
ASTM E96/E96M	(2024a) Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials
ASTM E329	(2025b) Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection
ASTM E1155	(2020) Standard Test Method for Determining Floor Flatness and Floor Levelness Numbers
ASTM E1643	(2018a) Standard Practice for Selection, Design, Installation, and Inspection of Water Vapor Retarders Used in Contact with Earth or Granular Fill Under Concrete Slabs

ASTM E1745	(2017; R 2023) Standard Specification for Water Vapor Retarders Used in Contact with Soil or Granular Fill under Concrete Slabs

CONCRETE REINFORCING STEEL INSTITUTE (CRSI)

CRSI 10MSP	(2018) Manual of Standard Practice
CRSI RB4.1	(2016) Supports for Reinforcement Used in Concrete

NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY (NIST)

NIST PS 1	(2009) DOC Voluntary Product Standard PS 1-07, Structural Plywood

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE CRD-C 104	(1980) Method of Calculation of the Fineness Modulus of Aggregate
COE CRD-C 513	(1974) Corps of Engineers Specifications for Rubber Waterstops
COE CRD-C 572	(1974) Corps of Engineers Specifications for Polyvinylchloride Waterstops

1.2 DEFINITIONS

a. "Cementitious material" as used herein must include all portland cement, pozzolan, fly ash, slag cement, and silica fume.

b. "Exposed to public view" means situated so that it can be seen from eye level from a public location after completion of the building. A public location is accessible to persons not responsible for operation or maintenance of the building.

c. "Chemical admixtures" are materials in the form of powder or fluids that are added to the concrete to give it certain characteristics not obtainable with plain concrete mixes.

d. "Supplementary cementing materials" (SCM) include coal fly ash, silica fume, slag cement, natural or calcined pozzolans, and ultra-fine coal ash when used in such proportions to replace the portland cement that result in improvement to sustainability and durability and reduced cost.

e. "Design strength" (f'c) is the specified compressive strength of concrete at time(s) specified in this section to meet structural design criteria.

f. "Mass Concrete" is any concrete system that approaches a maximum temperature of 158 degrees F within the first 72 hours of placement. In addition, it includes all concrete elements with a section thickness of 3 feet or more regardless of temperature.

g. "Mixture proportioning" is the process of designing concrete mixture proportions to enable it to meet the strength, service life and constructability requirements of the project while minimizing the

initial and life-cycle cost.

h. "Mixture proportions" are the masses or volumes of individual ingredients used to make a unit measure (cubic meter or cubic yard) of concrete.

i. "Pozzolan" is a siliceous or siliceous and aluminous material, which in itself possesses little or no cementitious value but will, in finely divided form and in the presence of moisture, chemically react with calcium hydroxide at ordinary temperatures to form compounds possessing cementitious properties.

j. "Workability (or consistence)" is the ability of a fresh (plastic) concrete mix to fill the form/mould properly with the desired work (vibration) and without reducing the concrete's quality. Workability depends on water content, chemical admixtures, aggregate (shape and size distribution), cementitious content and age (level of hydration).

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Quality Control Plan; G

Quality Control Personnel Certifications; G

Quality Control Organizational Chart

Laboratory Accreditation; G

Maturity Method Data

SD-02 Shop Drawings

Reinforcing Steel

SD-03 Product Data

Joint Sealants

Joint Filler

Formwork Materials

Recycled Aggregate Materials

Cementitious Materials

Vapor Barrier

Concrete Curing Materials

Reinforcement

Liquid Chemical Floor Hardeners and Sealers

Admixtures

Mechanical Reinforcing Bar Connectors

Waterstops

Biodegradable Form Release Agent

Nonshrink Grout

SD-04 Samples

SD-05 Design Data

Concrete Mix Design; G

SD-06 Test Reports

Concrete Mix Design; G

Fly Ash

Pozzolan

Slag Cement

Aggregates

Tolerance ReportCompressive Strength Tests; G

Unit Weight of Structural Concrete

Air Content

Slump Tests

Water

SD-07 Certificates

Reinforcing Bars

Welder Qualifications

Field Testing Technician and Testing Agency

SD-08 Manufacturer's Instructions

Joint Sealants

Curing Compound

1.4 MODIFICATION OF REFERENCES

Accomplish work in accordance with ACI publications except as modified herein. Consider the advisory or recommended provisions to be mandatory. Interpret reference to the "Building Official," the "Structural Engineer,"

and the "Architect/Engineer" to mean the Contracting Officer.

1.5 DELIVERY, STORAGE, AND HANDLING

Follow ACI 301, ACI 304R and ASTM A934/A934M requirements and recommendations. Do not deliver concrete until vapor retarder, vapor barrier, forms, reinforcement, embedded items, and chamfer strips are in place and ready for concrete placement. Do not store concrete curing compounds or sealers with materials that have a high capacity to adsorb volatile organic compound (VOC) emissions. Do not store concrete curing compounds or sealers in occupied spaces.

1.5.1 Reinforcement

Store reinforcement of different sizes and shapes in separate piles or racks raised above the ground to avoid excessive rusting. Protect from contaminants such as grease, oil, and dirt. Ensure bar sizes can be accurately identified after bundles are broken and tags removed.

1.6 QUALITY ASSURANCE

1.6.1 Design Data

1.6.1.1 Concrete Mix Design

Sixty days minimum prior to concrete placement, submit a mix design for each strength and type of concrete. Submit a complete list of materials including type; brand; source and amount of cement, supplementary cementitious materials, and admixtures; and applicable reference specifications. Submit mill test and all other test for cement, supplementary cementitious materials, aggregates, and admixtures. Provide documentation of maximum nominal aggregate size, gradation analysis, percentage retained and passing sieve, and a graph of percentage retained verses sieve size. Provide mix proportion data using at least three different water-cementitious material ratios for each type of mixture, which produce a range of strength encompassing those required for each type of concrete required. If source material changes, resubmit mix proportion data using revised source material. Provide only materials that have been proven by trial mix studies to meet the requirements of this specification, unless otherwise approved in writing by the Contracting Officer. Indicate clearly in the submittal where each mix design is used when more than one mix design is submitted. Resubmit data on concrete components if the qualities or source of components changes. Required average strength can be documented by field experience if field strength test data are available and represent a single group of at least 10 consecutive strength tests for one mixture, using materials and conditions similar to those expected for work, and encompassing a period of not less than 45 days. The average of field strength tests shall equal or exceed fcr'. Changes in materials, conditions, and proportions within the test record shall not have been more closely restricted than those for the proposed work. Test records shall not be more than 24 months old. Obtain mix design approval from the contracting officer prior to concrete placement.

1.6.2 Shop Drawings

1.6.2.1 Reinforcing Steel

Indicate bending diagrams, assembly diagrams, splicing and laps of bars,

shapes, dimensions, and details of bar reinforcing, accessories, and concrete cover. Do not scale dimensions from structural drawings to determine lengths of reinforcing bars. Reproductions of contract drawings are unacceptable.

1.6.3 Test Reports

1.6.3.1 Fly Ash and Pozzolan

Submit test results in accordance with ASTM C618 for fly ash and pozzolan. Submit test results performed within 6 months of submittal date.

1.6.3.2 Slag Cement

Submit test results in accordance with ASTM C989/C989M for slag cement. Submit test results performed within 6 months of submittal date.

1.6.3.3 Aggregates

Submit test results in accordance with ASTM C33/C33M, or ASTM C330/C330M for lightweight aggregate, and ASTM C1293 or ASTM C1567 as required in the paragraph titled ALKALI-AGGREGATE REACTION.

1.6.4 Field Samples

1.6.5 Quality Control Plan

Develop and submit for approval a concrete quality control program in accordance with the guidelines of ACI 121R and as specified herein. The plan must include approved laboratories. Provide direct oversight for the concrete qualification program inclusive of associated sampling and testing. All quality control reports must be provided to the Contracting Officer, Quality Manager and Concrete Supplier. Maintain a copy of ACI SP-15 and CRSI 10MSP at project site.

1.6.6 Quality Control Personnel Certifications

The Contractor must submit for approval the responsibilities of the various quality control personnel, including the names and qualifications of the individuals in those positions and a quality control organizational chart defining the quality control hierarchy and the responsibility of the various positions. Quality control personnel must be employed by the Contractor.

Submit American Concrete Institute certification for the following:

a. CQC personnel responsible for inspection of concrete operations.

b. Lead Foreman or Journeyman of the Concrete Placing, Finishing, and Curing Crews.

c. Field Testing Technicians: ACI Concrete Field Testing Technician, Grade I.

1.6.6.1 Quality Manager Qualifications

The quality manager must hold a current license as a professional engineer in a U.S. state or territory with experience on at least five similar projects. Evidence of extraordinary proven experience may be considered

by the Contracting Officer as sufficient to act as the Quality Manager.

1.6.6.2 Field Testing Technician and Testing Agency

Submit data on qualifications of proposed testing agency and technicians for approval by the Contracting Officer prior to performing testing on concrete.

a. Work on concrete under this contract must be performed by an ACI Concrete Field Testing Technician Grade 1 qualified in accordance with ACI SP-2 or equivalent. Equivalent certification programs must include requirements for written and performance examinations as stipulated in ACI SP-2.

b. Testing agencies that perform testing services on reinforcing steel must meet the requirements of ASTM E329.

c. Testing agencies that perform testing services on concrete materials must meet the requirements of ASTM C1077.

1.6.7 Laboratory Qualifications for Concrete Qualification Testing

The concrete testing laboratory must have the necessary equipment and experience to accomplish required testing. The laboratory must meet the requirements of ASTM C1077 and be Cement and Concrete Reference Laboratory (CCRL) inspected.

1.6.8 Laboratory Accreditation

Laboratory and testing facilities must be provided by and at the expense of the Contractor. The laboratories performing the tests must be accredited in accordance with ASTM C1077, including ASTM C78/C78M and ASTM C1260. The accreditation must be current and must include the required test methods, as specified. Furthermore, the testing must comply with the following requirements:

a. Aggregate Testing and Mix Proportioning: Aggregate testing and mixture proportioning studies must be performed by an accredited laboratory and under the direction of a registered professional engineer in a U.S. state or territory competent in concrete materials who is competent in concrete materials and must sign all reports and designs.

b. Acceptance Testing: Furnish all materials, labor, and facilities required for molding, curing, testing, and protecting test specimens at the site and in the laboratory. Furnish and maintain boxes or other facilities suitable for storing and curing the specimens at the site while in the mold within the temperature range stipulated by ASTM C31/C31M.

c. Contractor Quality Control: All sampling and testing must be performed by an approved, onsite, independent, accredited laboratory.

1.7 ENVIRONMENTAL REQUIREMENTS

Provide space ventilation according to material manufacturer recommendations, at a minimum, during and following installation of concrete curing compound and sealer. Maintain one of the following ventilation conditions during the curing period or for 72 hours after installation:

a. Supply 100 percent outside air 24 hours a day.

b. Supply airflow at a rate of 6 air changes per hour, when outside temperatures are between 55 degrees F and 84 degrees F and humidity is between 30 percent and 60 percent.

c. Supply airflow at a rate of 1.5 air changes per hour, when outside air conditions are not within the range stipulated above.

1.7.1 Submittals for Environmental Performance

a. Provide data indication the percentage of post-industrial pozzolan (fly ash, slag cement) cement substitution as a percentage of the full product composite by weight.

b. Provide data indicating the percentage of post-industrial and post-consumer recycled content aggregate.

c. Provide product data indicating the percentage of post-consumer recycled steel content in each type of steel reinforcement as a percentage of the full product composite by weight.

d. Provide product data stating the location where all products were manufactured

e. For projects using FSC certified formwork, provide chain-of-custody documentation for all certified wood products.

f. For projects using reusable formwork, provide data showing how formwork is reused.

g. Provide SDS product information data showing that form release agents meet any environmental performance goals such as using vegetable and soy based products.

h. Provide SDS product information data showing that concrete adhesives meet any environmental performance goals including low emitting, low volatile organic compound products.

1.8 QUALIFICATIONS FOR WELDING WORK

Welding procedures must be in accordance with AWS D1.4/D1.4M.

Verify that Welder qualifications are in accordance with AWS D1.4/D1.4M for welding of reinforcement or under an equivalent qualification test approved in advance. Welders are permitted to do only the type of welding for which each is specifically qualified.

PART 2 PRODUCTS

2.1 FORMWORK MATERIALS

a. Form-facing material in contact with concrete must be lumber, plywood, tempered concrete-form-grade hardboard, or treated paper that creates specified appearance and texture of concrete surface. Submit product information on proposed form-facing materials if different from that specified herein.

b. Design formwork, shores, reshores, and backshores to support loads transmitted to them and to comply with applicable building code requirements.

c. Design formwork and shoring for load redistribution resulting from stressing of post-tensioned reinforcement. Ensure that formwork allows movement resulting from application of prestressing force.

d. Design formwork to withstand pressure resulting from placement and vibration of concrete and to maintain specified tolerances.

e. Design formwork to accommodate waterstop materials in joints at locations indicated in Contract Documents.

f. Provide temporary openings in formwork if needed to facilitate cleaning and inspection.

g. Design formwork joints to inhibit leakage of mortar.

h. Limit deflection of facing materials for concrete surfaces exposed to view to 1/400 of center-to-center spacing of facing supports.

i. Do not use earth cuts as forms for vertical or sloping surfaces.

j. Submit product information on proposed form-facing materials if different from that specified herein.

m. Submit procedure for reshoring and backshoring, including drawings signed and sealed by a licensed design engineer. Include on shop drawings the formwork removal procedure and magnitude of construction loads used for design of reshoring or backshoring system. Indicate in procedure the magnitude of live and dead loads assumed for required capacity of the structure at time of reshoring or backshoring.

n. Submit manufacturer's product data on form liner proposed for use with each formed surface.

2.1.1 Wood Forms

Provide lumber that is square edged or tongue-and-groove boards, free of raised grain, knotholes, or other surface defects. Provide plywood that complies with NIST PS 1, B-B concrete form panels or better or AHA A135.4, hardboard for smooth form lining.

2.1.1.1 Concrete Form Plywood (Standard Rough)

Provide plywood that conforms to NIST PS 1, B-B, concrete form, not less than 5/8-inch thick.

2.1.1.2 Overlaid Concrete Form Plywood (Standard Smooth)

Provide plywood that conforms to NIST PS 1, B-B, high density form overlay, not less than 5/8-inch thick.

2.1.2 Plastic Forms

Provide plastic forms that contain a minimum of 50 percent post-consumer recycled content, or a minimum of 50 percent post-industrial recycled content.

2.1.3 Carton Forms

Moisture resistant treated paper faces, biodegradable, structurally sufficient to support weight of wet concrete until initial set. Provide carton forms that contain a minimum of 10 percent post-consumer recycled content, or a minimum of 20 percent post-industrial recycled content.

2.1.4 Steel Forms

Provide steel form surfaces that do not contain irregularities, dents, or sags.

2.2 FORMWORK ACCESSORIES

a. Use commercially manufactured formwork accessories, including ties and hangers.

b. Form ties and accessories must not reduce the effective cover of the reinforcement.

2.2.1 Form Ties

a. Use form ties with ends or end fasteners that can be removed without damage to concrete.

b. Where indicated in Contract Documents, use form ties with integral water barrier plates or other acceptable positive water barriers in walls.

c. The breakback distance for ferrous ties must be at least 3/4 in. for Surface Finish-2.0 or Surface Finish-3.0, as defined in ACI 301.

d. If the breakback distance is less than 3/4 in., use coated or corrosion-resistant ties.

e. Submit manufacturer's data sheet on form ties.

2.2.2 Waterstops

Submit manufacturer's data sheet on waterstop materials and splices.

2.2.2.1 PVC Waterstop

Polyvinylchloride waterstops must conform to COE CRD-C 572.

2.2.2.2 Rubber Waterstop

Rubber waterstops must conform to COE CRD-C 513.

2.2.2.3 Thermoplastic Elastomeric Rubber Waterstop

Thermoplastic elastomeric rubber waterstops must conform to ASTM D471.

2.2.2.4 Hydrophilic Waterstop

Swellable strip type compound of polymer modified chloroprene rubber that swells upon contact with water must conform to the following requirements when tested in accordance to ASTM D412: Tensile strength 420 psi minimum;

ultimate elongation 600 percent minimum. Hardness must be 50 minimum on the type A durometer and the volumetric expansion ratio in distilled water at 70 degrees F must be 3 to 1 minimum.

2.2.3 Biodegradable Form Release Agent

a. Provide form release agent that is colorless, biodegradable, and water-based, with a zero VOC content.

b. Provide product that does not bond with, stain, or adversely affect concrete surfaces and does not impair subsequent treatments of concrete surfaces.

c. Provide form release agent that reduces formwork moisture absorption, and does not contain diesel fuel, petroleum-based lubricating oils, waxes, or kerosene. Submit documentation indicating type of biobased material in product and biobased content. Indicate relative dollar value of biobased content products to total dollar value of products included in project.

d. Submit manufacturer's product data on formwork release agent for use on each form-facing material.

2.2.4 Chamfer Materials

Use lumber materials with dimensions of 3/4 x 3/4 in.

2.2.5 Construction and movement joints

a. Submit details and locations of construction joints in accordance with the requirements herein.

b. Locate construction joints within middle one-third of spans of slabs, beams, and girders. If a beam intersects a girder within the middle one-third of girder span, the distance between the construction joint in the girder and the edge of the beam must be at least twice the width of the larger member.

c. For members with post-tensioning tendons, locate construction joints where tendons pass through centroid of concrete section.

d. Locate construction joints in walls and columns at underside of slabs, beams, or girders and at tops of footings or slabs.

e. Make construction joints perpendicular to main reinforcement.

f. Provide movement joints where indicated in Contract Documents or in accepted alternate locations.

g. Submit location and detail of movement joints if different from those indicated in Contract Documents.

h. Submit manufacturer's data sheet on expansion joint materials.

i. Provide keyways where indicated in Contract Documents.

2.2.6 Other Embedded items

Use sleeves, inserts, anchors, and other embedded items of material and

design indicated in Contract Documents.

2.3 CONCRETE MATERIALS

2.3.1 Cementitious Materials

2.3.1.1 Portland Cement

a. Unless otherwise specified, provide cement that conforms to ASTM C150/C150M Type II, V.

b. Use one brand and type of cement for formed concrete having exposed-to-view finished surfaces.

c. For portland cement manufactured in a kiln fueled by hazardous waste, maintain a record of source for each batch.

d. Submit information along with evidence demonstrating compliance with referenced standards. Submittals must include types of cementitious materials, manufacturing locations, shipping locations, and certificates showing compliance.

e. Cementitious materials must be stored and kept dry and free from contaminants.

2.3.1.2 Fly Ash

a. ASTM C618, Class F , except that the maximum allowable loss on ignition must not exceed 3 percent.

b. If fly ash is used it shall range from 15 to 20 percent by weight of cementitious material, provided the fly ash does not reduce the amount of cement in the concrete mix below the minimum requirements of local building codes. Where the use of fly ash cannot meet the minimum level,it shall not be used. Report the chemical analysis of the fly ash in accordance with ASTM C311/C311M. Evaluate and classify fly ash in accordance with ASTM D5759.

2.3.1.3 Slag Cement

ASTM C989/C989M, Grade 120.

2.3.1.4 Silica Fume

Silica fume must conform to ASTM C1240, including the optional limits on reactivity with cement alkalis. Silica fume may be furnished as a dry, densified material or as slurry. Proper mixing is essential to accomplish proper distribution of the silica fume and avoid agglomerated silica fume which can react with the alkali in the cement resulting in premature and extensive concrete damage. Supervision at the batch plant, finishing, and curing is essential. Provide at the Contractor's expense the services of a manufacturer's technical representative, experienced in mixing, proportioning, placement procedures, and curing of concrete containing silica fume. This representative must be present on the project prior to and during at least the first 4 days of concrete production and placement using silica fume. A High Range Water Reducing admixture (HRWRA) must be used with silica fume.

2.3.1.5 Other Supplementary Cementitious Materials

Natural pozzolan must be raw or calcined and conform to ASTM C618, Class N, including the optional requirement for uniformity.

Ultra Fine Fly Ash (UFFA) and Ultra Fine Pozzolan (UFP) must conform to ASTM C618, Class F or N, and the following additional requirements:

a. The strength activity index at 28 days of age must be at least 95 percent of the control specimens.

b. The average particle size must not exceed 6 microns.

c. The sum of SiO_2 + Al_2O_3 + Fe_2O_3 must be greater than 77 percent.

2.3.2 Water

a. Water or ice must comply with the requirements of ASTM C1602/C1602M.

b. Minimize the amount of water in the mix. Improve workability by adjusting the grading of the aggregate and using admixture rather than by adding water.

c. Water must be potable ; free from injurious amounts of oils, acids, alkalis, salts, organic materials, or other substances deleterious to concrete.

d. Protect mixing water and ice from contamination during storage and delivery.

e. Submit test report showing water complies with ASTM C1602/C1602M.

f. When nonpotable source is proposed for use, submit documentation on effects of water on strength and setting time in compliance with ASTM C1602/C1602M.

2.3.3 Aggregate

2.3.3.1 Normal-Weight Aggregate

a. Aggregates must conform to ASTM C33/C33M unless otherwise specified in the Contract Documents or approved by the contracting officer.

b. Aggregates used in concrete must be obtained from the same sources and have the same size range as aggregates used in concrete represented by submitted field test records or used in trial mixtures.

c. Provide sand that is at least 50 percent natural sand.

d. Store and handle aggregate in a manner that will avoid segregation and prevents contamination by other materials or other sizes of aggregates. Store aggregates in locations that will permit them to drain freely. Do not use aggregates that contain frozen lumps.

e. Submit types, pit or quarry locations, producers' names, aggregate supplier statement of compliance with ASTM C33/C33M, and ASTM C1293 expansion data not more than 18 months old.

2.3.3.2 Recycled Aggregate Materials

Use a minimum of 25 percent recycled aggregate, depending on local availability and conforming to requirements of the mix design. Recycled aggregate to include: recovered concrete recovered stone that meets the aggregate requirements specified. Submit recycled material request with the aggregate certification submittals and do not use until approved by the Contracting Officer.

2.3.4 Admixtures

a. Chemical admixtures must conform to ASTM C494/C494M.

b. Air-entraining admixtures must conform to ASTM C260/C260M.

c. Chemical admixtures for use in producing flowing concrete must conform to ASTM C1017/C1017M.

d. Do not use calcium chloride admixtures unless approved by the contracting officer.

e.

f. Admixtures used in concrete must be the same as those used in the concrete represented by submitted field test records or used in trial mixtures.

g. Protect stored admixtures against contamination, evaporation, or damage.

h. To ensure uniform distribution of constituents, provide agitating equipment for admixtures used in the form of suspensions or unstable solutions. Protect liquid admixtures from freezing and from temperature changes that would adversely affect their characteristics.

i. Submit types, brand names, producers' names, manufacturer's technical data sheets, and certificates showing compliance with standards required herein.

2.4 MISCELLANEOUS MATERIALS

2.4.1 Concrete Curing Materials

Provide concrete curing material in accordance with ACI 301 Section 5 and ACI 308.1 Section 2. Submit product data for concrete curing compounds. Submit manufactures instructions for placement of curing compound.

2.4.2 Nonshrink Grout

Nonshrink grout in accordance with ASTM C1107/C1107M.

2.4.3 Floor Finish Materials

2.4.3.1 Liquid Chemical Floor Hardeners and Sealers

a. Hardener must be a colorless aqueous solution containing a blend of inorganic silicate or siliconate material and proprietary components combined with a wetting agent; that penetrates, hardens, and densifies concrete surfaces. Submit manufactures instructions for placement of

liquid chemical floor hardener.

b. Use concrete penetrating sealers with a low (maximum 100 grams/liter, less water and less exempt compounds) VOC content. Submit manufactures instructions for placement of sealers.

2.4.4 Expansion/Contraction Joint Filler

ASTM D1751 . Material must be 1/2 inch thick, unless otherwise indicated.

2.4.5 Joint Sealants

Submit manufacturer's product data, indicating VOC content.

2.4.5.1 Horizontal Surfaces, 3 Percent Slope, Maximum

ASTM D6690 or ASTM C920, Type M, Class 25, Use T.

2.4.5.2 Vertical Surfaces Greater Than 3 Percent Slope

ASTM C920, Type M, Grade NS, Class 25, Use T ..

2.4.5.3 Preformed Polychloroprene Elastomeric Type

ASTM D2628.

2.4.5.4 Lubricant for Preformed Compression Seals

ASTM D2835.

2.4.6 Vapor Barrier

ASTM E1745 Class C polyethylene sheeting, minimum 10 mil thickness or other equivalent material with a maximum permeance rating of 0.04 perms per ASTM E96/E96M.

Consider plastic vapor barriers and adhesives with a high recycled content, low toxicity low VOC (Volatile Organic Compounds) levels.

2.4.7 Dovetail Anchor Slot

Preformed metal slot approximately 1 inch by 1 inch of not less than 22 gage galvanized steel cast in concrete. Coordinate actual size and throat opening with dovetail anchors and provide with removable filler material.

2.5 CONCRETE MIX DESIGN

2.5.1 Properties and Requirements

a. Use materials and material combinations listed in this section and the contract documents.

b. Cementitious material content must be adequate for concrete to satisfy the specified requirements for strength, w/cm, durability, and finishability described in this section and the contract documents.

The minimum cementitious material content for concrete used in floors must meet the following requirements:

Nominal maximum size of aggregate, in.	Minimum cementitious material content, pounds per cubic yard
1-1/2	470
1	520
3/4	540
3/8	610

c. Selected target slump must meet the requirements this section, the contract documents, and must not exceed 9 in. Concrete must not show visible signs of segregation.

d. The target slump must be enforced for the duration of the project. Determine the slump by ASTM C143/C143M. Slump tolerances must meet the requirements of ACI 117.

e. The nominal maximum size of coarse aggregate for a mixture must not exceed three-fourths of the minimum clear spacing between reinforcement, one-fifth of the narrowest dimension between sides of forms, or one-third of the thickness of slabs or toppings.

f. Concrete must be air entrained for members assigned to Exposure Class F1, F2, or F3. The total air content must be in accordance with the requirements of the paragraph titled DURABILITY.

g. Measure air content at the point of delivery in accordance with ASTM C173/C173M or ASTM C231/C231M.

h. Concrete for slabs to receive a hard-troweled finish must not contain an air-entraining admixture or have a total air content greater than 3 percent.

i. Concrete properties and requirements for each portion of the structure are specified in the table below. Refer to the paragraph titled DURABILITY for more details on exposure categories and their requirements.

	Minimum *f'c* psi	Exposure Categories^	Miscellaneous Requirements
Footings	3000 at 28 days	S0 ; C1 ; W1; F0	Max. slump: 6 in. Nominal maximum aggregate size must be 1 in.

	Minimum *f'c* psi	Exposure Categories^	Miscellaneous Requirements
Beams and elevated slabs	3000 at 28 days	S0 ; C1 ; W1; F0	Nominal maximum aggregate size must be 1 in.
Slabs-on-ground	4000 at 28 days	S0 ; C1 ; W1; F0	

2.5.2 Durability

2.5.2.1 Alkali-Aggregate Reaction

Do not use any aggregate susceptible to alkali-carbonate reaction (ACR). Use one of the three options below for qualifying concrete mixtures to reduce the potential of alkali-silica reaction (ASR):

a. For each aggregate used in concrete, the expansion result determined in accordance with ASTM C1293 must not exceed 0.04 percent at one year.

b. For each aggregate used in concrete, the expansion result of the aggregate and cementitious materials combination determined in accordance with ASTM C1567 must not exceed 0.10 percent at an age of 16 days.

c. Alkali content in concrete (LBA) must not exceed 4 pounds per cubic yard for moderately reactive aggregate or 3 pounds per cubic yard for highly reactive aggregate. Reactivity must be determined by testing in accordance with ASTM C1293 and categorized in accordance with ASTM C1778. Alkali content is calculated as follows:
LBA = (cement content, pounds per cubic yard) × (equivalent alkali content of portland cement in percent/100 percent)

2.5.2.2 Freezing and Thawing Resistance

a. Provide concrete meeting the following requirements based on exposure class assigned to members for freezing-and-thawing exposure in Contract Documents:

Exposure class	Maximum *w/cm**	Minimum *f'c*, psi	Air content	Additional Requirements
F0	N/A	2500	N/A	

Exposure class	Maximum *w/cm**	Minimum *f'c*, psi	Air content	Additional Requirements
F1	0.55	3500	Depends on aggregate size	N/A
F2	0.45	4500	Depends on aggregate size	See limits on maximum cementitious material by mass
F3	0.40	5000	Depends on aggregate size	See limits on maximum cementitious material by mass
F3 plain concrete	0.45	4500	Depends on aggregate size	See limits on maximum cementitious material by mass

*The maximum *w/cm* limits do not apply to lightweight concrete.

b. Concrete must be air entrained for members assigned to Exposure Class F1, F2, or F3. The total air content must meet the requirements of the following table:

Nominal maximum aggregate size, in.	Total air content, percent*^	
	Exposure Class F2 and F3	Exposure Class F1
3/8	7.5	6.0
1/2	7.0	5.5
3/4	6.0	5.0
1	6.0	4.5
1-1/2	5.5	4.5
2	5.0	4.0
3	5.5	3.5

*Tolerance on air content as delivered must be plus/minus 1.5 percent.

^For f'c greater than 5000 psi, reducing air content by 1.0 percentage point is acceptable.

c. Submit documentation verifying compliance with specified requirements.

d. For sections of the structure that are assigned Exposure Class F3, submit certification on cement composition verifying that concrete mixture meets the requirements of the following table:

Cementitious material	**Maximum percent of total cementitious material by mass***
Fly ash or other pozzolans conforming to ASTM C618	25
Slag cement conforming to ASTM C989/C989M	50
Silica fume conforming to ASTM C1240	10
Total of fly ash or other pozzolans, slag cement, and silica fume	50^
Total of fly ash or other pozzolans and silica fume	35^

*Total cementitious material also includes ASTM C150/C150M, ASTM C595/C595M, ASTM C845/C845M, and ASTM C1157/C1157M cement. The maximum percentages above must include:

i. Fly ash or other pozzolans present in ASTM C1157/C1157M or ASTM C595/C595M Type IP blended cement.

ii. Slag cement present in ASTM C1157/C1157M or ASTM C595/C595M Type IS blended cement.

iii. Silica fume conforming to ASTM C1240 present in ASTM C1157/C1157M or ASTM C595/C595M Type IP blended cement.

^Fly ash or other pozzolans and silica fume must constitute no more than 25 percent and 10 percent, respectively, of the total mass of the cementitious materials.

2.5.2.3 Corrosion and Chloride Content

a. Provide concrete meeting the requirements of the following table based on the exposure class assigned to members requiring protection against reinforcement corrosion in Contract Documents.

b. Submit documentation verifying compliance with specified requirements.

c. Water-soluble chloride ion content contributed from constituents including water, aggregates, cementitious materials, and admixtures must be determined for the concrete mixture by ASTM C1218/C1218M at age between 28 and 42 days.

d. The maximum water-soluble chloride ion (Cl-) content in concrete, percent by mass of cement is as follows:

Exposure class	Maximum *w/cm**	Minimum f'c, psi	Maximum water-soluble chloride ion (CL-) content in concrete, percent by mass of cement
Reinforced concrete			
C0	N/A	2500	1.00
C1	N/A	2500	0.30
C2	0.4	5000	0.15
Prestressed concrete			
C0	N/A	2500	0.06
C1	N/A	2500	0.06
C2	0.4	5000	0.06

*The maximum w/cm limits do not apply to lightweight concrete.

2.5.2.4 Sulfate Resistance

a. Provide concrete meeting the requirements of the following table based on the exposure class assigned to members for sulfate exposure.

Exposure class	Maximum w/cm	Minimum f'c, psi	Required cementitious materials-types			Calcium chloride admixture
			ASTM C150/C150M	ASTM C595/C595M	ASTM C1157/C1157M	
S0	N/A	2500	N/A	N/A	N/A	No restrictions
S1	0.50	4000	II*^	Types with (MS) designation	MS	No restrictions
S2	0.45	4500	V^	Types with (HS) designation	HS	Not permitted
S3	0.45	4500	V + pozzolan or slag cement**	Types with (HS) designation plus pozzolan or slag cement**	HS + pozzolan or slag cement**	Not permitted
S3	0.40	5000	V***	Types with (HS) designation	HS	Not permitted

* For seawater exposure, other types of portland cements with tricalcium aluminate (C3A) contents up to 10 percent are acceptable if the w/cm does not exceed 0.40.

** The amount of the specific source of the pozzolan or slag cement to be used shall be at least the amount determined by test or service record to improve sulfate resistance when used in concrete containing Type V cement. Alternatively, the amount of the specific source of the pozzolan or slag used shall not be less than the amount tested in

accordance with ASTM C1012/C1012M and meeting the requirements maximum expansion requirements listed herein.

*** If Type V cement is used as the sole cementitious material, the optional sulfate requirement of 0.040 percent maximum expansion in ASTM C150/C150M shall be required.

^ Other available types of cement, such as Type III or Type I, are acceptable in exposure classes S1 or S2 if the C3A contents are less than 8 or 5 percent, respectively.

b. The maximum w/cm limits for sulfate exposure do not apply to lightweight concrete.

c. Alternative combinations of cementitious materials of those listed in this paragraph are acceptable if they meet the maximum expansion requirements listed in the following table:

Exposure class	**Maximum expansion when tested using ASTM C1012/C1012M**		
	At 6 months	**At 12 months**	**At 18 months**
S1	0.10 percent	N/A	N/A
S2	0.05 percent	0.10 percent^	N/A
S3	N/A	N/A	0.10 percent

^The 12-month expansion limit applies only when the measured expansion exceeds the 6-month maximum expansion limit.

2.5.2.5 Concrete Temperature

The temperature of concrete as delivered must not exceed 95°F.

2.5.2.6 Concrete permeability

a. Provide concrete meeting the requirements of the following table based on exposure class assigned to members requiring low permeability in the Contract Documents.

Exposure class	**Maximum *w/cm****	**Minimum f'c, psi**	**Additional minimum requirements**
W0	N/A	2500	None
W1	0.5	4000	None

*The maximum w/cm limits do not apply to lightweight concrete.

b. Submit documentation verifying compliance with specified requirements.

2.5.3 Trial Mixtures

Trial mixtures must be in accordance to ACI 301.

2.5.4 Ready-Mix Concrete

Provide concrete that meets the requirements of ASTM C94/C94M.

Ready-mixed concrete manufacturer must provide duplicate delivery tickets with each load of concrete delivered. Provide delivery tickets with the following information in addition to that required by ASTM C94/C94M:

a. Type and brand cement

b. Cement and supplementary cementitious materials content in 94-pound bags per cubic yard of concrete

c. Maximum size of aggregate

d. Amount and brand name of admixtures

e. Total water content expressed by water cementitious material ratio

2.6 REINFORCEMENT

a. Bend reinforcement cold. Fabricate reinforcement in accordance with fabricating tolerances of ACI 117.

b. Submit manufacturer's certified test report for reinforcement.

c. Submit placing drawings showing fabrication dimensions and placement locations of reinforcement and reinforcement supports. Placing drawings must indicate locations of splices, lengths of lap splices, and details of mechanical and welded splices.

d. Submit request with locations and details of splices not indicated in Contract Documents.

e. Submit request to place column dowels without using templates.

f. Submit request and procedure to field-bend or straighten reinforcing bars partially embedded in concrete at locations not indicated in Contract Documents. Field bending or straightening of reinforcing bars is permitted where indicated in the Contract Documents

g. Submit request for field cutting, including location and type of bar to be cut and reason field cutting is required.

2.6.1 Reinforcing Bars

a. Reinforcing bars must be deformed, except spirals, load-transfer dowels, and welded wire reinforcement, which may be plain.

b. ASTM A615/A615M with the bars marked S, Grade 60 ; or ASTM A996/A996M with the bars marked R, Grade 60, or marked A, Grade 60.

c. Reinforcing bars may contain post-consumer or post-industrial recycled content. Submit documentation indicating percentage of post-industrial and post-consumer recycled content per unit of product. Indicate

relative dollar value of recycled content products to total dollar value of products included in project.

d. Submit mill certificates for reinforcing bars.

2.6.1.1 Bar Mats

a. Bar mats must conform to ASTM A184/A184M.

2.6.2 Mechanical Reinforcing Bar Connectors

a. Provide 125 percent minimum yield strength of the reinforcement bar.

b. Mechanical splices for galvanized reinforcing bars must be galvanized or coated with dielectric material.

c. Mechanical splices used with epoxy-coated or dual-coated reinforcing bars must be coated with dielectric material.

d. Submit data on mechanical splices demonstrating compliance with this paragraph.

2.6.3 Wire

a. Provide wire reinforcement that contains a minimum of 100 percent recycled content.Provide flat sheets of welded wire reinforcement for slabs and toppings.

b. Plain or deformed steel wire must conform to ASTM A1064/A1064M.

c. Stainless steel wire must conform to ASTM A1022/A1022M.

d. Epoxy-coated wire must conform to ASTM A884/A884M. Coating damage incurred during shipment, storage, handling, and placing of epoxy-coated wires must be repaired. Repair damaged coating areas with patching material in accordance with material manufacturer's written recommendations. If damaged area exceeds 2 percent of surface area in each linear foot of each wire, wire must not be used. The 2 percent limit on damaged coating area must include repaired areas damaged before shipment as required by ASTM A884/A884M. Fading of coating color shall not be cause for rejection of epoxy-coated wire reinforcement.

2.6.4 Welded wire reinforcement

a. Use welded wire reinforcement specified in Contract Documents and conforming to one or more of the specifications given herein.

b. Plain welded wire reinforcement must conform to ASTM A1064/A1064M, with welded intersections spaced no greater than 12 in. apart in direction of principal reinforcement.

c. Deformed welded wire reinforcement must conform to ASTM A1064/A1064M, with welded intersections spaced no greater than 16 in. apart in direction of principal reinforcement.

d. Epoxy-coated welded wire reinforcement must conform to ASTM A884/A884M. Coating damage incurred during shipment, storage, handling, and

placing of epoxy-coated welded wire reinforcement must be repaired in accordance with ASTM A884/A884M. Repair damaged coating areas with patching material in accordance with material manufacturer's written recommendations. If damaged area exceeds 2 percent of surface area in each linear foot of each wire or welded wire reinforcement, the sheet containing the damaged area must not be used. The 2 percent limit on damaged coating area must include repaired areas damaged before shipment as required by ASTM A884/A884M. Fading of coating color shall not be cause for rejection of epoxy-coated welded wire reinforcement.

e. Stainless steel welded wire reinforcement must conform to ASTM A1022/A1022M.

f. Zinc-coated (galvanized) welded wire reinforcement must conform to ASTM A1060/A1060M. Coating damage incurred during shipment, storage, handling, and placing of zinc-coated (galvanized) welded wire reinforcement must be repaired in accordance with ASTM A780/A780M. If damaged area exceeds 2 percent of surface area in each linear foot of each wire or welded wire reinforcement, the sheet containing the damaged area must not be used. The 2 percent limit on damaged coating area shall include repaired areas damaged before shipment as required by ASTM A1060/A1060M.

2.6.5 Reinforcing Bar Supports

a. Provide reinforcement support types within structure as required by Contract Documents. Reinforcement supports must conform to CRSI RB4.1. Submit description of reinforcement supports and materials for fastening coated reinforcement if not in conformance with CRSI RB4.1.

b. Legs of supports in contact with formwork must be hot-dip galvanized, or plastic coated after fabrication, or stainless-steel bar supports.

c. Minimum 5 percent post-consumer recycled content, or minimum 20 percent post-industrial recycled content.

2.6.6 Dowels for Load Transfer in Floors

Provide greased dowels for load transfer in floors of the type, design, weight, and dimensions indicated. Provide dowel bars that are plain-billet steel conforming to ASTM A615/A615M, Grade 40. Provide dowel pipe that is steel conforming to ASTM A53/A53M.

Plate dowels must conform to ASTM A36/A36M, and must be of size and spacing indicated. Plate dowel system must minimize shrinkage restraint by using a tapered shape

2.6.7 Welding

a. Provide weldable reinforcing bars that conform to ASTM A706/A706M and ASTM A615/A615M and Supplement S1, Grade 60, except that the maximum carbon content must be 0.55 percent.

b. Comply with AWS D1.4/D1.4M unless otherwise specified. Do not tack weld reinforcing bars.

c. Welded assemblies of steel reinforcement produced under factory conditions, such as welded wire reinforcement, bar mats, and deformed

bar anchors, are allowed.

d. After completing welds on zinc-coated (galvanized), epoxy-coated, or zinc and epoxy dual-coated reinforcement, coat welds and repair coating damage as previously specified.

PART 3 EXECUTION

3.1 EXAMINATION

a. Do not begin installation until substrates have been properly constructed; verify that substrates are level.

b. If substrate preparation is the responsibility of another installer, notify Contracting Officer of unsatisfactory preparation before processing.

c. Check field dimensions before beginning installation. If dimensions vary too much from design dimensions for proper installation, notify Contracting Officer and wait for instructions before beginning installation.

3.2 PREPARATION

Determine quantity of concrete needed and minimize the production of excess concrete. Designate locations or uses for potential excess concrete before the concrete is poured.

3.2.1 General

a. Surfaces against which concrete is to be placed must be free of debris, loose material, standing water, snow, ice, and other deleterious substances before start of concrete placing.

b. Remove standing water without washing over freshly deposited concrete. Divert flow of water through side drains provided for such purpose.

3.2.2 Subgrade Under Foundations and Footings

a. When subgrade material is semi-porous and dry, sprinkle subgrade surface with water as required to eliminate suction at the time concrete is deposited, or seal subgrade surface by covering surface with specified vapor barrier.

b. When subgrade material is porous, seal subgrade surface by covering surface with specified vapor barrier.

3.2.3 Subgrade Under Slabs on Ground

a. Before construction of slabs on ground, have underground work on pipes and conduits completed and approved.

b. Previously constructed subgrade or fill must be cleaned of foreign materials

c. Finish surface of capillary water barrier under interior slabs on ground must not show deviation in excess of 1/4 inch when tested with a 10-foot straightedge parallel with and at right angles to building lines.

d. Finished surface of subgrade or fill under exterior slabs on ground must not be more than 0.02-foot above or 0.10-foot below elevation indicated.

3.2.4 Edge Forms and Screed Strips for Slabs

a. Set edge forms or bulkheads and intermediate screed strips for slabs to obtain indicated elevations and contours in finished slab surface and must be strong enough to support vibrating bridge screeds or roller pipe screeds if nature of specified slab finish requires use of such equipment.

b. Align concrete surface to elevation of screed strips by use of strike-off templates or approved compacting-type screeds.

3.2.5 Reinforcement and Other Embedded Items

a. Secure reinforcement, joint materials, and other embedded materials in position, inspected, and approved before start of concrete placing.

b. When concrete is placed, reinforcement must be free of materials deleterious to bond. Reinforcement with rust, mill scale, or a combination of both will be considered satisfactory, provided minimum nominal dimensions, nominal weight, and minimum average height of deformations of a hand-wire-brushed test specimen are not less than applicable ASTM specification requirements.

3.3 FORMS

a. Provide forms, shoring, and scaffolding for concrete placement. Set forms mortar-tight and true to line and grade.

b. Chamfer above grade exposed joints, edges, and external corners of concrete 0.75 inch. Place chamfer strips in corners of formwork to produce beveled edges on permanently exposed surfaces.

c. Provide formwork with clean-out openings to permit inspection and removal of debris.

d. Inspect formwork and remove foreign material before concrete is placed.

e. At construction joints, lap form-facing materials over the concrete of previous placement. Ensure formwork is placed against hardened concrete so offsets at construction joints conform to specified tolerances.

f. Provide positive means of adjustment (such as wedges or jacks) of shores and struts. Do not make adjustments in formwork after concrete has reached initial setting. Brace formwork to resist lateral deflection and lateral instability.

g. Fasten form wedges in place after final adjustment of forms and before concrete placement.

h. Provide anchoring and bracing to control upward and lateral movement of formwork system.

i. Construct formwork for openings to facilitate removal and to produce

opening dimensions as specified and within tolerances.

j. Provide runways for moving equipment. Support runways directly on formwork or structural members. Do not support runways on reinforcement. Loading applied by runways must not exceed capacity of formwork or structural members.

k. Position and support expansion joint materials, waterstops, and other embedded items to prevent displacement. Fill voids in sleeves, inserts, and anchor slots temporarily with removable material to prevent concrete entry into voids.

l. Clean surfaces of formwork and embedded materials of mortar, grout, and foreign materials before concrete placement.

3.3.1 Coating

a. Cover formwork surfaces with an acceptable material that inhibits bond with concrete.

b. If formwork release agent is used, apply to formwork surfaces in accordance with manufacturer's recommendations before placing reinforcement. Remove excess release agent on formwork prior to concrete placement.

c. Do not allow formwork release agent to contact reinforcement or hardened concrete against which fresh concrete is to be placed.

3.3.2 Reshoring

a. Do not allow structural members to be loaded with combined dead and construction loads in excess of loads indicated in the accepted procedure.

b. Install and remove reshores or backshores in accordance with accepted procedure.

c. For floors supporting shores under newly placed concrete, either leave original supporting shores in place, or install reshores or backshores. Shoring system and supporting slabs must resist anticipated loads. Locate reshores and backshores directly under a shore position or as indicated on formwork shop drawings.

d. In multistory buildings, place reshoring or backshoring over a sufficient number of stories to distribute weight of newly placed concrete, forms, and construction live loads.

3.3.3 Reuse

a. Reuse forms providing the structural integrity of concrete and the aesthetics of exposed concrete are not compromised.

b. Wood forms must not be clogged with paste and must be capable of absorbing high water-cementitious material ratio paste.

c. Remove leaked mortar from formwork joints before reuse.

3.3.4 Forms for Standard Rough Form Finish

Provide formwork in accordance with ACI 301 Section 5 with a surface finish, SF-1.0, for formed surfaces that are to be concealed by other construction.

3.3.5 Forms for Standard Smooth Form Finish

Provide formwork in accordance with ACI 301 Section 5 with a surface finish, SF-3.0, for formed surfaces that are exposed to view.

3.3.6 Form Ties

a. For post-tensioned structures, do not remove formwork supports until stressing records have been accepted by the Contracting Officer.

b. After ends or end fasteners of form ties have been removed, repair tie holes in accordance with ACI 301 Section 5 requirements.

3.3.7 Forms for Concrete Pan Joist Construction

Pan-form units for one-way or two-way concrete joist and slab construction must be factory-fabricated units of the approximate section indicated. Units must consist of steel or molded fiberglass concrete form pans. Closure units must be furnished as required.

3.3.8 Tolerances for Form Construction

a. Construct formwork so concrete surfaces conform to tolerances in ACI 117.

b. Position and secure sleeves, inserts, anchors, and other embedded items such that embedded items are positioned within ACI 117 tolerances.

c. To maintain specified elevation and thickness within tolerances, install formwork to compensate for deflection and anticipated settlement in formwork during concrete placement. Set formwork and intermediate screed strips for slabs to produce designated elevation, camber, and contour of finished surface before formwork removal. If specified finish requires use of vibrating screeds or roller pipe screeds, ensure that edge forms and screed strips are strong enough to support such equipment.

3.3.9 Removal of Forms and Supports

a. If vertical formed surfaces require finishing, remove forms as soon as removal operations will not damage concrete.

b. Remove top forms on sloping surfaces of concrete as soon as removal will not allow concrete to sag. Perform repairs and finishing operations required. If forms are removed before end of specified curing period, provide curing and protection.

c. Do not damage concrete during removal of vertical formwork for columns, walls, and sides of beams. Perform needed repair and finishing operations required on vertical surfaces. If forms are removed before end of specified curing period, provide curing and protection.

d. Leave formwork and shoring in place to support construction loads and weight of concrete in beams, slabs, and other structural members until in-place required strength of concrete is reached.

e. Form-facing material and horizontal facing support members may be removed before in-place concrete reaches specified compressive strength if shores and other supports are designed to allow facing removal without deflection of supported slab or member.

3.3.10 Strength of Concrete Required for Removal of Formwork

If removal of formwork, reshoring, or backshoring is based on concrete reaching a specified in-place strength, mold and field-cure cylinders in accordance with ASTM C31/C31M. Test cylinders in accordance with ASTM C39/C39M. Alternatively, use one or more of the methods listed herein to evaluate in-place concrete strength for formwork removal.

a. Tests of cast-in-place cylinders in accordance with ASTM C873/C873M. This option is limited to slabs with concrete depths from 5 to 12 in.

b. Penetration resistance in accordance with ASTM C803/C803M.

c. Pullout strength in accordance with ASTM C900.

d. Maturity method in accordance with ASTM C1074. Submit maturity method data using project materials and concrete mix proportions used on the project to demonstrate the correlation between maturity and compressive strength of laboratory cured test specimens to the Contracting Officer.

3.4 WATERSTOP INSTALLATION AND SPLICES

a. Provide waterstops in construction joints as indicated.

b. Install formwork to accommodate waterstop materials. Locate waterstops in joints where indicated in Contract Documents. Minimize number of splices in waterstop. Splice waterstops in accordance with manufacturer's written instructions. Install factory-manufactured premolded mitered corners.

c. Install waterstops to form a continuous diaphragm in each joint. Make adequate provisions to support and protect waterstops during progress of work. Protect waterstops protruding from joints from damage.

3.4.1 PVC Waterstop

Make splices by heat sealing the adjacent waterstop edges together using a thermoplastic splicing iron utilizing a non-stick surface specifically designed for waterstop welding. Reform waterstops at splices with a remolding iron with ribs or corrugations to match the pattern of the waterstop. The spliced area, when cooled, must show no signs of separation, holes, or other imperfections when bent by hand in as sharp an angle as possible.

3.4.2 Rubber Waterstop

Rubber waterstops must be spliced using cold bond adhesive as recommended by the manufacturer.

3.4.3 Thermoplastic Elastomeric Rubber Waterstop

Fittings must be shop made using a machine specifically designed to mechanically weld the waterstop. A portable power saw must be used to miter or straight cut the ends to be joined to ensure good alignment and contact between joined surfaces. Maintain continuity of the characteristic features of the cross section of the waterstop (for example ribs, tabular center axis, and protrusions) across the splice.

3.4.4 Hydrophilic Waterstop

Miter cut ends to be joined with sharp knife or shears. The ends must be adhered with adhesive.

3.5 PLACING REINFORCEMENT AND MISCELLANEOUS MATERIALS

a. Unless otherwise specified, placing reinforcement and miscellaneous materials must be in accordance to ACI 301. Provide bars, welded wire reinforcement, wire ties, supports, and other devices necessary to install and secure reinforcement.

b. Reinforcement must not have rust, scale, oil, grease, clay, or foreign substances that would reduce the bond. Rusting of reinforcement is a basis of rejection if the effective cross-sectional area or the nominal weight per unit length has been reduced. Remove loose rust prior to placing steel. Tack welding is prohibited.

c. Nonprestressed cast-in-place concrete members must have concrete cover for reinforcement given in the following table:

Concrete Exposure	**Member**	**Reinforcement**	**Specified cover, in.**
Cast against and permanently in contact with ground	All	All	3
Exposed to weather or in contact with ground	All	No. 6 through No. 18 bars	2
		No. 5 bar, W31 or D31 wire, and smaller	1-1/2

Concrete Exposure	Member	Reinforcement	Specified cover, in.
Not exposed to weather or in contact with ground	Slabs, joists, and walls	No. 14 and No. 18 bars	1-1/2
		No. 11 bar and smaller	3/4
	Beams, columns, pedestals, and tension ties	Primary reinforcement, stirrups, ties, spirals, and hoops	1-1/2

d. Cast-in-place prestressed concrete members must have concrete cover for reinforcement, ducts, and end fittings given in the following table:

Concrete	Member	Reinforcement	Specified
Cast against and permanently in contact with ground	All	All	3
Exposed to weather or in contact with ground	Slabs, joists, and walls	All	1
	All other	All	1-1/2
Not exposed to weather or in contact with ground	Slabs, joists, and walls	All	3/4
	Beams, columns, and tension ties	Primary reinforcement	1-1/2
		Stirrups, ties, spirals, and hoops	1

e. Precast nonprestressed or prestressed concrete members manufactured under plant conditions must have concrete cover for reinforcement, ducts, and end fittings given in the following table:

Concrete Exposure	Member	Reinforcement	Specified cover, in.
Exposed to weather or in contact with ground	Walls	No. 14 and No. 18 bars; tendons larger than 1-1/2 in. diameter	1-1/2
		No. 11 bars and smaller; W31 and D31 wire, and smaller; tendons and strands 1-1/2 in.	3/4
	All other	No. 14 and No. 18 bars; tendons larger than 1-1/2 in.	2
		No. 6 through No. 11 bars; tendons and strands larger than 5/8 in. diameter through 1-1/2 in.	1-1/2
		No. 5 bar, W31 or D31 wire, and smaller; tendons and strands 5/8 in. diameter and smaller	1-1/4

Concrete Exposure	Member	Reinforcement	Specified cover, in.
Not exposed to weather or in contact with ground	Slabs, joists, and walls	No. 14 and No. 18 bars; tendons larger than 1-1/2 in. diameter	1-1/4
		Tendons and strands 1-1/2 in. diameter and smaller	3/4
		No. 11 bar, W31 or D31	5/8
	Beams, columns, pedestals, and tension ties	Primary reinforcement	Greater of bar diameter and 5/8 and need not exceed 1-1/2
		Stirrups, ties, spirals, and hoops	3/8

3.5.1 General

Provide details of reinforcement that are in accordance with the Contract Documents.

3.5.2 Vapor Barrier

a. Install in accordance with ASTM E1643. Provide beneath the on-grade concrete floor slab. Use the greatest widths and lengths practicable to eliminate joints wherever possible. Lap joints a minimum of 12 inches and tape.

b. Remove torn, punctured, or damaged vapor barrier material and provide with new vapor barrier prior to placing concrete. Concrete placement must not damage vapor vapor barrier material Place vapor barrier directly on underlying subgrade, base course, or capillary water barrier, unless it consists of crushed material or large granular material which could puncture the vapor barrier. In this case, a thin layer of approximately 1/2 inch of fine graded material should be rolled or compacted over the fill before installation of the vapor barrier to reduce the possibility of puncture. Control concrete placement so as to prevent damage to the vapor barrier.

3.5.3 Perimeter Insulation

Install perimeter insulation at locations indicated. Adhesive must be used where insulation is applied to the interior surface of foundation

walls and may be used for exterior application.

3.5.4 Reinforcement Supports

Provide reinforcement support in accordance with CRSI RB4.1 and ACI 301 Section 3 requirements. Supports for coated or galvanized bars must also be coated with electrically compatible material for a distance of at least 2 inches beyond the point of contact with the bars.

3.5.5 Splicing

As indicated in the Contract Documents. For splices not indicated follow ACI 301. Do not splice at points of maximum stress. Overlap welded wire reinforcement the spacing of the cross wires, plus 2 inches. AWS D1.4/D1.4M. Approve welded splices prior to use.

3.5.6 Future Bonding

Plug exposed, threaded, mechanical reinforcement bar connectors with a greased bolt. Provide bolt threads that match the connector. Countersink the connector in the concrete. Caulk the depression after the bolt is installed.

3.5.7 Setting Miscellaneous Material

Place and secure anchors and bolts, pipe sleeves, conduits, and other such items in position before concrete placement and support against displacement. Plumb anchor bolts and check location and elevation. Temporarily fill voids in sleeves with readily removable material to prevent the entry of concrete.

3.5.8 Fabrication

Shop fabricate reinforcing bars to conform to shapes and dimensions indicated for reinforcement, and as follows:

a. Provide fabrication tolerances that are in accordance with ACI 117.

b. Provide hooks and bends that are in accordance with the Contract Documents.

Reinforcement must be bent cold to shapes as indicated. Bending must be done in the shop. Rebending of a reinforcing bar that has been bent incorrectly is not be permitted. Bending must be in accordance with standard approved practice and by approved machine methods.

Deliver reinforcing bars bundled, tagged, and marked. Tags must be metal with bar size, length, mark, and other information pressed in by machine. Marks must correspond with those used on the placing drawings.

Do not use reinforcement that has any of the following defects:

a. Bar lengths, depths, and bends beyond specified fabrication tolerances

b. Bends or kinks not indicated on drawings or approved shop drawings

c. Bars with reduced cross-section due to rusting or other cause

Replace defective reinforcement with new reinforcement having required

shape, form, and cross-section area.

3.5.9 Placing Reinforcement

Place reinforcement in accordance with ACI 301.

For slabs on grade (over earth or over capillary water barrier) and for footing reinforcement, support bars or welded wire reinforcement on precast concrete blocks, spaced at intervals required by size of reinforcement, to keep reinforcement the minimum height specified above the underside of slab or footing.

For slabs other than on grade, supports for which any portion is less than 1 inch from concrete surfaces that are exposed to view or to be painted must be of precast concrete units, plastic-coated steel, or stainless steel protected bar supports. Precast concrete units must be wedge shaped, not larger than 3-1/2 by 3-1/2 inches, and of thickness equal to that indicated for concrete protection of reinforcement. Provide precast units that have cast-in galvanized tie wire hooked for anchorage and blend with concrete surfaces after finishing is completed.

Provide reinforcement that is supported and secured together to prevent displacement by construction loads or by placing of wet concrete, and as follows:

a. Provide supports for reinforcing bars that are sufficient in number and have sufficient strength to carry the reinforcement they support, and in accordance with ACI 301 and CRSI 10MSP. Do not use supports to support runways for concrete conveying equipment and similar construction loads.

b. Equip supports on ground and similar surfaces with sand-plates.

c. Support welded wire reinforcement as required for reinforcing bars.

d. Secure reinforcements to supports by means of tie wire. Wire must be black, soft iron wire, not less than 16 gage.

e. Reinforcement must be accurately placed, securely tied at intersections, and held in position during placing of concrete by spacers, chairs, or other approved supports. Point wire-tie ends away from the form. Unless otherwise indicated, numbers, type, and spacing of supports must conform to the Contract Documents.

f. Bending of reinforcing bars partially embedded in concrete is permitted only as specified in the Contract Documents.

3.5.10 Spacing of Reinforcing Bars

a. Spacing must be as indicated in the Contract Documents.

b. Reinforcing bars may be relocated to avoid interference with other reinforcement, or with conduit, pipe, or other embedded items. If any reinforcing bar is moved a distance exceeding one bar diameter or specified placing tolerance, resulting rearrangement of reinforcement is subject to preapproval by the Contracting Officer.

3.5.11 Concrete Protection for Reinforcement

Additional concrete protection must be in accordance with the Contract Documents.

3.5.12 Welding

Welding must be in accordance with AWS D1.4/D1.4M.

3.6 BATCHING, MEASURING, MIXING, AND TRANSPORTING CONCRETE

In accordance with ASTM C94/C94M, ACI 301, ACI 302.1R and ACI 304R, except as modified herein. Batching equipment must be such that the concrete ingredients are consistently measured within the following tolerances: 1 percent for cement and water, 2 percent for aggregate, and 3 percent for admixtures. Furnish mandatory batch ticket information for each load of ready mix concrete.

3.6.1 Measuring

Make measurements at intervals as specified in paragraphs SAMPLING and TESTING.

3.6.2 Mixing

a. Mix concrete in accordance with ASTM C94/C94M, ACI 301 and ACI 304R.

b. Machine mix concrete. Begin mixing within 30 minutes after the cement has been added to the aggregates. Place concrete within 90 minutes of either addition of mixing water to cement and aggregates or addition of cement to aggregates if the concrete temperature is less than 84 degrees F.

c. Place concrete within 60 minutes if the concrete temperature is greater than 84 degrees F except as follows: if set retarding admixture is used and slump requirements can be met, limit for placing concrete may remain at 90 minutes. Additional water may be added, provided that both the specified maximum slump and submitted water-cementitious material ratio are not exceeded and the required concrete strength is still met. When additional water is added, an additional 30 revolutions of the mixer at mixing speed is required.

d. If the entrained air content falls below the specified limit, add a sufficient quantity of admixture, within the manufacturer's recommended dosage, to bring the entrained air content within the specified limits. Dissolve admixtures in the mixing water and mix in the drum to uniformly distribute the admixture throughout the batch. Do not reconstitute concrete that has begun to solidify.

e. When fibers are used, add fibers together with the aggregates and never as the first component in the mixer. Fibers must be dispensed into the mixing system using appropriate dispensing equipment and procedure as recommended by the manufacturer.

3.6.3 Transporting

Transport concrete from the mixer to the forms as rapidly as practicable. Prevent segregation or loss of ingredients. Clean transporting equipment thoroughly before each batch. Do not use aluminum pipe or chutes. Remove

concrete which has segregated in transporting and dispose of as directed.

3.7 PLACING CONCRETE

Place concrete in accordance with ACI 301 Section 5. Concrete shall be placed within 15 minutes of discharge into non-agitating equipment.

3.7.1 Footing Placement

Concrete for footings may be placed in excavations without forms upon inspection and approval by the Contracting Officer. Excavation width must be a minimum of 4 inches greater than indicated.

3.7.2 Pumping

ACI 304R and ACI 304.2R. Pumping must not result in separation or loss of materials nor cause interruptions sufficient to permit loss of plasticity between successive increments. Loss of slump in pumping equipment must not exceed 2 inches at discharge/placement. Do not convey concrete through pipe made of aluminum or aluminum alloy. Avoid rapid changes in pipe sizes. Limit maximum size of course aggregate to 33 percent of the diameter of the pipe. Limit maximum size of well-rounded aggregate to 40 percent of the pipe diameter. Take samples for testing at both the point of delivery to the pump and at the discharge end.

3.7.3 Cold Weather

Cold weather concrete must meet the requirements of ACI 301 unless otherwise specified. Do not allow concrete temperature to decrease below 50 degrees F. Obtain approval prior to placing concrete when the ambient temperature is below 40 degrees F or when concrete is likely to be subjected to freezing temperatures within 24 hours. Cover concrete and provide sufficient heat to maintain 50 degrees F minimum adjacent to both the formwork and the structure while curing. Limit the rate of cooling to 37 degrees F in any one hour and 50 degrees F per 24 hours after heat application.

3.7.4 Hot Weather

Hot weather concrete must meet the requirements of ACI 301 unless otherwise specified. Maintain required concrete temperature using Figure 4.2 in ACI 305R to prevent the evaporation rate from exceeding 0.2 pound of water per square foot of exposed concrete per hour. Cool ingredients before mixing or use other suitable means to control concrete temperature and prevent rapid drying of newly placed concrete. Shade the fresh concrete as soon as possible after placing. Start curing when the surface of the fresh concrete is sufficiently hard to permit curing without damage. Provide water hoses, pipes, spraying equipment, and water hauling equipment, where job site is remote to water source, to maintain a moist concrete surface throughout the curing period. Provide burlap cover or other suitable, permeable material with fog spray or continuous wetting of the concrete when weather conditions prevent the use of either liquid membrane curing compound or impervious sheets. For vertical surfaces, protect forms from direct sunlight and add water to top of structure once concrete is set.

3.7.5 Bonding

Surfaces of set concrete at joints, must be roughened and cleaned of

laitance, coatings, loose particles, and foreign matter. Roughen surfaces in a manner that exposes the aggregate uniformly and does not leave laitance, loosened particles of aggregate, nor damaged concrete at the surface.

Obtain bonding of fresh concrete that has set as follows:

a. At joints between footings and walls or columns, between walls or columns and the beams or slabs they support, and elsewhere unless otherwise specified; roughened and cleaned surface of set concrete must be dampened, but not saturated, immediately prior to placing of fresh concrete.

b. At joints in exposed-to-view work; at vertical joints in walls; at joints near midpoint of span in girders, beams, supported slabs, other structural members; in work designed to contain liquids; the roughened and cleaned surface of set concrete must be dampened but not saturated and covered with a cement grout coating.

c. Provide cement grout that consists of equal parts of portland cement and fine aggregate by weight with not more than 6 gallons of water per sack of cement. Apply cement grout with a stiff broom or brush to a minimum thickness of 1/16 inch. Deposit fresh concrete before cement grout has attained its initial set.

3.8 WASTE MANAGEMENT

Provide as specified in the Waste Management Plan and as follows.

3.8.1 Mixing Equipment

Before concrete pours, designate Contractor-owned site meeting environmental standards for cleaning out concrete mixing trucks. Minimize water used to wash equipment.

3.8.2 Hardened, Cured Waste Concrete

Crush and reuse hardened, cured waste concrete as fill or as a base course for pavement.

3.8.3 Reinforcing Steel

Collect reinforcing steel and place in designated area for recycling.

3.8.4 Other Waste

Identify concrete manufacturer's or supplier's policy for collection or return of construction waste, unused material, deconstruction waste, and/or packaging material. Return excess cement to supplier.

3.9 SURFACE FINISHES EXCEPT FLOOR, SLAB, AND PAVEMENT FINISHES

3.9.1 Defects

Repair surface defects in accordance with ACI 301 Section 5.

3.9.2 Not Against Forms (Top of Walls)

Surfaces not otherwise specified must be finished with wood floats to even

surfaces. Finish must match adjacent finishes.

3.9.3 Formed Surfaces

3.9.3.1 Tolerances

Tolerances in accordance with ACI 117 and as indicated.

3.9.3.2 As-Cast Rough Form

Provide for surfaces not exposed to public view a surface finish SF-1.0. Patch holes and defects in accordance with ACI 301.

3.9.3.3 Standard Smooth Finish

Provide for surfaces exposed to public view a surface finish SF-3.0. Patch holes and defects in accordance with ACI 301.

3.10 FLOOR, SLAB, AND PAVEMENT FINISHES AND MISCELLANEOUS CONSTRUCTION

In accordance with ACI 301 and ACI 302.1R, unless otherwise specified. Slope floors uniformly to drains where drains are provided. Where straightedge measurements are specified, Contractor must provide straightedge.

3.10.1 Finish

Place, consolidate, and immediately strike off concrete to obtain proper contour, grade, and elevation before bleedwater appears. Permit concrete to attain a set sufficient for floating and supporting the weight of the finisher and equipment. If bleedwater is present prior to floating the surface, drag the excess water off or remove by absorption with porous materials. Do not use dry cement to absorb bleedwater. Grate tampers ("jitterbugs") shall not be used.

3.10.1.1 Scratched

Use for surfaces intended to receive bonded applied cementitious applications. Finish concrete in accordance with ACI 301 Section 5 for a scratched finish.

3.10.1.2 Floated

Use for exterior slabs where not otherwise specified. Finish concrete in accordance with ACI 301 Section 5 for a floated finish.

3.10.1.3 Steel Troweled

Use for floors intended as walking surfaces and for reception of floor coverings . Finish concrete in accordance with ACI 301 Section 5 for a steel troweled finish.

3.10.1.4 Nonslip Finish

Use on surfaces of exterior platforms, steps, and landings; and on exterior and interior pedestrian ramps. Finish concrete in accordance with ACI 301 Section 5 for a dry-shake finish. After the selected material has been embedded by the two floatings, complete the operation with a broomed finish.

3.10.1.5 Broomed

Use on surfaces of exterior walks, platforms, patios, and ramps, unless otherwise indicated. Finish concrete in accordance with ACI 301 Section 5 for a broomed finish.

3.10.1.6 Pavement

Screed the concrete with a template advanced with a combined longitudinal and crosswise motion. Maintain a slight surplus of concrete ahead of the template. After screeding, float the concrete longitudinally. Use a straightedge to check slope and flatness; correct and refloat as necessary. Obtain final finish by a burlap drag. Drag a strip of clean, wet burlap from 3 to 10 feet wide and 2 feet longer than the pavement width across the slab. Produce a fine, granular, sandy textured surface without disfiguring marks. Round edges and joints with an edger having a radius of 1/8 inch.

3.10.1.7 Concrete Toppings Placement

The following requirements apply to the placement of toppings of concrete on base slabs that are either freshly placed and still plastic, or on hardened base slabs.

a. Placing on a Fresh Base: Screed and bull float the base slab. As soon as the water sheen has disappeared, lightly rake the surface of the base slab with a stiff bristle broom to produce a bonding surface for the topping. Immediately spread the topping mixture evenly over the roughened base before final set takes place. Give the topping the finish indicated on the drawings .

b. Bonding to a Hardened Base: When the topping is to be bonded to a floated or troweled hardened base, roughen the base by scarifying, grit-blasting, scabbling, planing, flame cleaning, or acid-etching to lightly expose aggregate and provide a bonding surface. Remove dirt, laitance, and loose aggregate by means of a stiff wire broom. Keep the clean base wet for a period of 12 hours preceding the application of the topping. Remove excess water and apply a 1:1:1/2 cement-sand-water grout, and brush into the surface of the base slab. Do not allow the cement grout to dry, and spread it only short distances ahead of the topping placement. Do not allow the temperature differential between the completed base and the topping mixture to exceed 41 degrees F at the time of placing. Place the topping and finish as indicated.

3.10.2 Flat Floor Finishes

ACI 302.1R. Construct in accordance with one of the methods recommended in Table 10.15.3a, "Slab-on-ground flatness/levelness construction guide" or Table 10.15.3b, "Suspended slab flatness/levelness construction guide" appropriate for the type of construction. ACI 117 for tolerance tested by ASTM E1155.

a. Specified Minimum Value:

Floor Flatness (Ff) 25 minimum
Floor Levelness (FL) 20 minimum

3.10.2.1 Measurement of Floor Tolerances

Test slab within 24 hours of the final troweling. Provide tests to Contracting Officer within 12 hours after collecting the data. Floor flatness inspector is required to provide a tolerance report which must include:

a. Key plan showing location of data collected.

b. Results required by ASTM E1155.

3.10.2.2 Remedies for Out of Tolerance Work

Contractor is required to repair and retest any floors not meeting specified tolerances. Prior to repair, Contractor must submit and receive approval for the proposed repair, including product data from any materials proposed. Repairs must not result in damage to structural integrity of the floor. For floors exposed to public view, repairs must prevent any uneven or unusual coloring of the surface.

3.10.3 Concrete Walks

Provide 4 inches thick minimum. Provide contraction joints spaced every 5 linear feet unless otherwise indicated. Cut contraction joints 1 inch deep, or one fourth the slab thickness whichever is deeper, with a jointing tool after the surface has been finished. Provide 0.5 inch thick transverse expansion joints at changes in direction where sidewalk abuts curb, steps, rigid pavement, or other similar structures; space expansion joints every 50 feet maximum. Give walks a broomed finish. Unless indicated otherwise, provide a transverse slope of 1/48. Limit variation in cross section to 1/4 inch in 5 feet.

3.10.4 Pits and Trenches

Place bottoms and walls monolithically or provide waterstops and keys.

3.10.5 Curbs and Gutters

Provide contraction joints spaced every 10 feet maximum unless otherwise indicated. Cut contraction joints 3/4 inch deep with a jointing tool after the surface has been finished. Provide expansion joints 1/2 inch thick and spaced every 100 feet maximum unless otherwise indicated. Perform pavement finish.

3.10.6 Splash Blocks

Provide at outlets of downspouts emptying at grade. Splash blocks may be precast concrete, and must be 24 inches long, 12 inches wide and 4 inches thick, unless otherwise indicated, with smooth-finished countersunk dishes sloped to drain away from the building.

3.11 JOINTS

3.11.1 Construction Joints

Make and locate joints not indicated so as not to impair strength and appearance of the structure, as approved. Joints must be perpendicular to main reinforcement. Reinforcement must be continued and developed across construction joints. Locate construction joints as follows:

3.11.1.1 Construction Joints for Constructability Purposes

a. In walls, at top of footing; at top of slabs on ground; at top and bottom of door and window openings or where required to conform to architectural details; and at underside of deepest beam or girder framing into wall.

b. In columns or piers, at top of footing; at top of slabs on ground; and at underside of deepest beam or girder framing into column or pier.

c. Near midpoint of spans for supported slabs, beams, and girders unless a beam intersects a girder at the center, in which case construction joints in girder must offset a distance equal to twice the width of the beam. Make transfer of shear through construction joint by use of inclined reinforcement.

Provide keyways at least 1-1/2-inches deep in construction joints in walls and slabs and between walls and footings; approved bulkheads may be used for slabs.

3.11.2 Isolation Joints in Slabs on Ground

a. Provide joints at points of contact between slabs on ground and vertical surfaces, such as column pedestals, foundation walls, grade beams, and elsewhere as indicated.

b. Fill joints with premolded joint filler strips 1/2 inch thick, extending full slab depth. Install filler strips at proper level below finish floor elevation with a slightly tapered, dress-and-oiled wood strip temporarily secured to top of filler strip to form a groove not less than 3/4 inch in depth where joint is sealed with sealing compound and not less than 1/4 inch in depth where joint sealing is not required. Remove wood strip after concrete has set. Contractor must clean groove of foreign matter and loose particles after surface has dried.

3.11.3 Contraction Joints in Slabs on Ground

a. Provide joints to form panels as indicated.

b. Under and on exact line of each control joint, cut 50 percent of welded wire reinforcement before placing concrete.

c. Sawcut contraction joints into slab on ground in accordance with ACI 301 Section 5.

e. Sawcutting will be limited to within 12 hours after set and at 1/4 slab depth.

3.11.4 Sealing Joints in Slabs on Ground

a. Contraction and control joints which are to receive finish flooring material must be sealed with joint sealing compound after concrete curing period. Slightly underfill groove with joint sealing compound to prevent extrusion of compound. Remove excess material as soon after sealing as possible.

b. Sealed groove must be left ready to receive filling material that is provided as part of finish floor covering work.

3.12 CONCRETE FLOOR TOPPING

3.12.1 Standard Floor Topping

Provide topping for treads and platforms of metal steel stairs and elsewhere as indicated.

3.12.1.1 Preparations Prior to Placing

a. When topping is placed on a green concrete base slab, screed surface of base slab to a level not more than 1-1/2 inches nor less than 1 inch below required finish surface. Remove water and laitance from surface of base slab before placing topping mixture. As soon as water ceases to rise to surface of base slab, place topping.

b. When topping is placed on a hardened concrete base slab, remove dirt, loose material, oil, grease, asphalt, paint, and other contaminants from base slab surface, leaving a clean surface. Prior to placing topping mixture, 2-1/2-inches minimum, slab surface must be dampened and left free of standing water. Immediately before topping mixture is placed, broom a coat of neat cement grout onto surface of slab. Do not allow cement grout to set or dry before topping is placed.

c. When topping is placed on a metal surface, such as metal pans for steel stairs, remove dirt, loose material, oil, grease, asphalt, paint, and other contaminants from metal surface.

3.12.1.2 Placing

Spread standard topping mixture evenly on previously prepared base slab or metal surface, brought to correct level with a straightedge, and struck off. Topping must be consolidated, floated, checked for trueness of surface, and refloated as specified for float finish.

3.12.1.3 Finishing

Give trowel finish standard floor topping surfaces.

Give other finishes standard floor topping surfaces as indicated.

3.12.2 Heavy-Duty Floor Topping

Provide topping where indicated.

3.12.2.1 Heavy-duty Topping Mixture

Provide mixture that consists of 1 part portland cement and 2-1/2 parts emery aggregate or 1 part fine aggregate and 1-1/2 parts traprock coarse aggregate, by volume. Exact proportions of mixture must conform to recommendations of aggregate manufacturer. Mixing water must not exceed 3-1/4 gallons per 94-pound sack of cement including unabsorbed moisture in aggregate. Maximum slump must be 1 inch.

3.12.2.2 Base Slab

a. Screed surface of slab to a level no more than 1-1/2 inches nor less than 1 inch below grade of finished floor.

b. Give slab a scratch finish as specified.

c. Preparations prior to placing.

Remove dirt, loose material, oil, grease, asphalt, paint and other contaminants from base slab surface. Prior to placing topping mixture, dampen slab surface and leave free of standing water. Immediately before topping mixture is placed, broom a coat of neat cement grout onto surface of slab. Allow cement grout to set or dry before topping mixture is placed.

3.12.2.3 Placing

Spread heavy-duty topping mixture evenly on previously prepared base slab, and bring to correct level with a straightedge, and strike off. Provide topping that is consolidated, floated, and checked for trueness of surface as specified for float finish, except that power-driven floats is the impact type.

3.12.2.4 Finishing

Give trowel finish heavy-duty floor topping surfaces. Provide trowel finish as specified, except that additional troweling after first power troweling must be not less than three hand-troweling operations.

3.13 CURING AND PROTECTION

Curing and protection in accordance with ACI 301 Section 5, unless otherwise specified. Begin curing immediately following form removal. Avoid damage to concrete from vibration created by blasting, pile driving, movement of equipment in the vicinity, disturbance of formwork or protruding reinforcement, and any other activity resulting in ground vibrations. Protect concrete from injurious action by sun, rain, flowing water, frost, mechanical injury, tire marks, and oil stains. Do not allow concrete to dry out from time of placement until the expiration of the specified curing period. Do not use membrane-forming compound on surfaces where appearance would be objectionable, on any surface to be painted, where coverings are to be bonded to the concrete, or on concrete to which other concrete is to be bonded. If forms are removed prior to the expiration of the curing period, provide another curing procedure specified herein for the remaining portion of the curing period. Provide moist curing for those areas receiving liquid chemical sealer, hardener, or epoxy coating. Allow curing compound/sealer installations to cure prior to the installation of materials that adsorb VOCs.

3.13.1 Requirements for Type III, High-Early-Strength Portland Cement

The curing periods are required to be not less than one-fourth of those specified for portland cement, but in no case less than 72 hours.

3.13.2 Curing Periods

ACI 301 Section 5, except 10 days for retaining walls, pavement or chimneys. Begin curing immediately after placement. Protect concrete

from premature drying, excessively hot temperatures, and mechanical injury; and maintain minimal moisture loss at a relatively constant temperature for the period necessary for hydration of the cement and hardening of the concrete. The materials and methods of curing are subject to approval by the Contracting Officer.

3.13.3 Curing Formed Surfaces

Accomplish curing of formed surfaces, including undersurfaces of girders, beams, supported slabs, and other similar surfaces by moist curing with forms in place for full curing period or until forms are removed. If forms are removed before end of curing period, accomplish final curing of formed surfaces by any of the curing methods specified above, as applicable.

3.13.4 Curing Unformed Surfaces

a. Accomplish initial curing of unformed surfaces, such as monolithic slabs, floor topping, and other flat surfaces, by membrane curing.

b. Accomplish final curing of unformed surfaces by any of curing methods specified, as applicable.

c. Accomplish final curing of concrete surfaces to receive liquid floor hardener of finish flooring by moisture-retaining cover curing.

3.13.5 Temperature of Concrete During Curing

When temperature of atmosphere is 41 degrees F and below, maintain temperature of concrete at not less than 55 degrees F throughout concrete curing period or 45 degrees F when the curing period is measured by maturity. When necessary, make arrangements before start of concrete placing for heating, covering, insulation, or housing as required to maintain specified temperature and moisture conditions for concrete during curing period.

When the temperature of atmosphere is 80 degrees F and above or during other climatic conditions which cause too rapid drying of concrete, make arrangements before start of concrete placing for installation of wind breaks, of shading, and for fog spraying, wet sprinkling, or moisture-retaining covering of light color as required to protect concrete during curing period.

Changes in temperature of concrete must be uniform and not exceed 37 degrees F in any one hour nor 80 degrees F in any 24-hour period.

3.13.6 Protection from Mechanical Injury

During curing period, protect concrete from damaging mechanical disturbances, particularly load stresses, heavy shock, and excessive vibration and from damage caused by rain or running water.

3.13.7 Protection After Curing

Protect finished concrete surfaces from damage by construction operations.

3.14 FIELD QUALITY CONTROL

3.14.1 Aggregate Testing

3.14.1.1 Fine Aggregate

At least once during each shift when the concrete plant is operating, there shall be one sieve analysis and fineness modulus determination in accordance with ASTM C136/C136M and COE CRD-C 104 for the fine aggregate or for each fine aggregate if it is batched in more than one size or classification. The location at which samples are taken may be selected by the Contractor as the most advantageous for control. However, the Contractor is responsible for delivering fine aggregate to the mixer within specification limits. When the amount passing on any sieve is outside the specification limits, the fine aggregate shall be immediately resampled and retested. If there is another failure on any sieve, the fact shall be immediately reported to the Contracting Officer, concreting shall be stopped, and immediate steps taken to correct the grading.

3.14.1.2 Coarse Aggregate

At least once during each shift in which the concrete plant is operating, there shall be a sieve analysis in accordance with ASTM C136/C136M for each size of coarse aggregate. The location at which samples are taken may be selected by the Contractor as the most advantageous for production control. However, the Contractor shall be responsible for delivering the aggregate to the mixer within specification limits. A test record of samples of aggregate taken at the same locations shall show the results of the current test as well as the average results of the five most recent tests including the current test. The Contractor may adopt limits for control coarser than the specification limits for samples taken other than as delivered to the mixer to allow for degradation during handling. When the amount passing any sieve is outside the specification limits, the coarse aggregate shall be immediately resampled and retested. If the second sample fails on any sieve, that fact shall be reported to the Contracting Officer. Where two consecutive averages of 5 tests are outside specification limits, the operation shall be considered out of control and reported to the Contracting Officer. Concreting shall be stopped and immediate steps shall be taken to correct the grading.

3.14.2 Concrete Sampling

ASTM C172/C172M. Collect samples of fresh concrete to perform tests specified. ASTM C31/C31M for making test specimens.

3.14.3 Concrete Testing

3.14.3.1 Slump Tests

ASTM C143/C143M. Take concrete samples during concrete placement/discharge. The maximum slump may be increased as specified with the addition of an approved admixture provided that the water-cementitious material ratio is not exceeded. Perform tests at commencement of concrete placement, when test cylinders are made, and for each batch (minimum) or every 20 cubic yards (maximum) of concrete.

3.14.3.2 Temperature Tests

Test the concrete delivered and the concrete in the forms. Perform tests

in hot or cold weather conditions (below 50 degrees F and above 80 degrees F) for each batch (minimum) or every 20 cubic yards (maximum) of concrete, until the specified temperature is obtained, and whenever test cylinders and slump tests are made.

3.14.3.3 Compressive Strength Tests

ASTM C39/C39M. Make eight 6 inch by 12 inch test cylinders for each set of tests in accordance with ASTM C31/C31M, ASTM C172/C172M and applicable requirements of ACI 305R and ACI 306R. Take precautions to prevent evaporation and loss of water from the specimen. Test two cylinders at 7 days, two cylinders at 28 days, two cylinders at 56 days and hold two cylinder in reserve. Take samples for strength tests of each mix design of concrete placed each day not less than once a day, nor less than once for each 100 cubic yards of concrete for the first 500 cubic yards, then every 500 cubic yards thereafter, nor less than once for each 5400 square feet of surface area for slabs or walls. For the entire project, take no less than five sets of samples and perform strength tests for each mix design of concrete placed. Each strength test result must be the average of two cylinders from the same concrete sample tested at 28 days . Concrete compressive tests must meet the requirements of this section, the Contract Document, and ACI 301. Retest locations represented by erratic core strengths. Where retest does not meet concrete compressive strength requirements submit a mitigation or remediation plan for review and approval by the contracting officer. Repair core holes with nonshrink grout. Match color and finish of adjacent concrete.

3.14.3.4 Air Content

ASTM C173/C173M or ASTM C231/C231M for normal weight concrete . Test air-entrained concrete for air content at the same frequency as specified for slump tests.

3.14.3.5 Unit Weight of Structural Concrete

ASTM C567/C567M and ASTM C138/C138M. Determine unit weight of lightweight and normal weight concrete. Perform test for every 20 cubic yards maximum.

3.14.3.6 Strength of Concrete Structure

The strength of the concrete structure will be considered to be deficient if any of the following conditions are identified:

a. Failure to meet compressive strength tests as evaluated.

b. Reinforcement not conforming to requirements specified.

c. Concrete which differs from required dimensions or location in such a manner as to reduce strength.

d. Concrete curing and protection of concrete against extremes of temperature during curing, not conforming to requirements specified.

e. Concrete subjected to damaging mechanical disturbances, particularly load stresses, heavy shock, and excessive vibration.

f. Poor workmanship likely to result in deficient strength.

Where the strength of the concrete structure is considered deficient

submit a mitigation or remediation plan for review and approval by the contracting officer.

3.14.3.7 Non-Conforming Materials

Factors that indicate that there are non-conforming materials include (but not limited to) excessive compressive strength, inadequate compressive strength, excessive slump, excessive voids and honeycombing, concrete delivery records that indicate excessive time between mixing and placement, or excessive water was added to the mixture during delivery and placement. Any of these indicators alone are sufficient reason for the Contracting Officer to request additional sampling and testing.

Investigations into non-conforming materials must be conducted at the Contractor's expense. The Contractor must be responsible for the investigation and must make written recommendations to adequately mitigate or remediate the non-conforming material. The Contracting Officer may accept, accept with reduced payment, require mitigation, or require removal and replacement of non-conforming material at no additional cost to the Government.

3.14.3.8 Testing Concrete Structure for Strength

When there is evidence that strength of concrete structure in place does not meet specification requirements or there are non-conforming materials, make cores drilled from hardened concrete for compressive strength determination in accordance with ASTM C42/C42M, and as follows:

a. Take at least three representative cores from each member or area of concrete-in-place that is considered potentially deficient. Location of cores will be determined by the Contracting Officer.

b. Test cores after moisture conditioning in accordance with ASTM C42/C42M if concrete they represent is more than superficially wet under service.

c. Air dry cores, (60 to 80 degrees F with relative humidity less than 60 percent) for 7 days before test and test dry if concrete they represent is dry under service conditions.

d. Strength of cores from each member or area are considered satisfactory if their average is equal to or greater than 85 percent of the 28-day design compressive strength of the class of concrete.

Fill core holes solid with patching mortar and finished to match adjacent concrete surfaces.

Correct concrete work that is found inadequate by core tests in a manner approved by the Contracting Officer.

3.15 REPAIR, REHABILITATION AND REMOVAL

Before the Contracting Officer accepts the structure the Contractor must inspect the structure for cracks, damage and substandard concrete placements that may adversely affect the service life of the structure. A report documenting these defects must be prepared which includes recommendations for repair, removal or remediation must be submitted to the Contracting Officer for approval before any corrective work is accomplished.

3.15.1 Crack Repair

Prior to final acceptance, all cracks in excess of 0.02 inches wide must be documented and repaired. The proposed method and materials to repair the cracks must be submitted to the Contracting Officer for approval. The proposal must address the amount of movement expected in the crack due to temperature changes and loading.

3.15.2 Repair of Weak Surfaces

Weak surfaces are defined as mortar-rich, rain-damaged, uncured, or containing exposed voids or deleterious materials. Concrete surfaces with weak surfaces less than 1/4 inch thick must be diamond ground to remove the weak surface. Surfaces containing weak surfaces greater than 1/4 inch thick must be removed and replaced or mitigated in a manner acceptable to the Contracting Officer.

3.15.3 Failure of Quality Assurance Test Results

Proposed mitigation efforts by the Contractor must be approved by the Contracting Officer prior to proceeding.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 04 20 00

UNIT MASONRY
11/15, CHG 2: 05/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 216.1	(2014) Code Requirements for Determining Fire Resistance of Concrete and Masonry Construction Assemblies
ACI SP-66	(2004) ACI Detailing Manual

ASTM INTERNATIONAL (ASTM)

ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A167	(2011) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A185/A185M	(2007) Standard Specification for Steel Welded Wire Reinforcement, Plain, for Concrete
ASTM A615/A615M	(2022) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A641/A641M	(2019) Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire
ASTM A951/A951M	(2011) Standard Specification for Steel Wire for Masonry Joint Reinforcement
ASTM A996/A996M	(2016) Standard Specification for Rail-Steel and Axle-Steel Deformed Bars for Concrete Reinforcement
ASTM A1064/A1064M	(2024) Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM B370	(2022) Standard Specification for Copper Sheet and Strip for Building Construction

ASTM C67/C67M	(2025) Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile
ASTM C90	(2021) Standard Specification for Loadbearing Concrete Masonry Units
ASTM C207	(2024) Standard Specification for Hydrated Lime for Masonry Purposes
ASTM C216	(2021) Standard Specification for Facing Brick (Solid Masonry Units Made from Clay or Shale)
ASTM C270	(2025b) Standard Specification for Mortar for Unit Masonry
ASTM C476	(2023) Standard Specification for Grout for Masonry
ASTM C494/C494M	(2019; E 2022) Standard Specification for Chemical Admixtures for Concrete
ASTM C641	(2017) Standard Test Method for Iron Staining Materials in Lightweight Concrete Aggregates
ASTM C1019	(2019) Standard Test Method for Sampling and Testing Grout
ASTM C1384	(2012a) Standard Specification for Admixtures for Masonry Mortars
ASTM C1611/C1611M	(2021) Standard Test Method for Slump Flow of Self-Consolidating Concrete

THE MASONRY SOCIETY (TMS)

TMS MSJC	(2016) Masonry Standard Joint Committee's (MSJC) Book - Building Code Requirements and Specification for Masonry Structures, Containing TMS 402/ACI 530/ASCE 5, TMS 602/ACI 530.1/ASCE 6, and Companion Commentaries

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Reinforcement Detail Drawings; G

SD-03 Product Data

Hot Weather Procedures; G

Cold Weather Procedures; G

Clay or Shale Brick; G

Cementitious Materials; G

SD-04 Samples

Mock-Up Panel; G

Clay or Shale Brick; G

Concrete Masonry Units (CMU); G

Admixtures for Masonry Mortar; G

Anchors, Ties, and Bar Positioners; G

Joint Reinforcement; G

Clay Masonry Expansion-Joint Materials; G

SD-05 Design Data

Masonry Compressive Strength; G

Fire-Rated Concrete Masonry Units

Bracing Calculations; G

SD-06 Test Reports

Efflorescence Test

Fire-Rated Concrete Masonry Units

Field Testing of Grout

SD-07 Certificates

Special Masonry Inspector Qualifications

Clay or Shale Brick

Concrete Masonry Units (CMU)

Cementitious Materials

Admixtures for Masonry Mortar

Admixtures for Grout

Anchors, Ties, and Bar Positioners

Joint Reinforcement

Insulation

SD-08 Manufacturer's Instructions

Admixtures for Masonry Mortar

Admixtures for Grout

SD-10 Operation and Maintenance Data

Take-Back Program

SD-11 Closeout Submittals

Recycled Content of Clay Units; S

Recycled Content of Cement; S

1.3 QUALITY ASSURANCE

1.3.1 Masonry Mock-Up Panels

1.3.1.1 Mock-Up Panel Location

After material samples are approved and prior to starting masonry work, construct a mock-up panel for each type and color of masonry required. At least 48 hours prior to constructing the panel or panels, submit written notification to the Contracting Officer. Do not build-in mock-up panels as part of the structure; locate mock-up panels where directed. Construct portable mock-up panels or locate in an area where they will not be disrupted during construction.

1.3.1.2 Mock-Up Panel Configuration

Construct mock-up panels L-shaped or otherwise configured to represent all of the wall elements. Construct panels of the size necessary to demonstrate the acceptable level of workmanship for each type of masonry represented on the project. Provide a straight panel or a leg of an L-shaped panel of minimum size 8 feet long by 6 feet high.

1.3.1.3 Mock-Up Panel Composition

Show full color range, texture, and bond pattern of the masonry work. Demonstrate mortar joint tooling; grouting of reinforced vertical cores, collar joints, bond beams, and lintels; positioning, securing, and lapping of reinforcing steel; positioning and lapping of joint reinforcement (including prefabricated corners); and cleaning of masonry work during the construction of the panels. Also include installation or application procedures for anchors, wall ties, CMU control joints, brick expansion joints, flashing, brick soldier, row lock courses and weeps. Include a a masonry bonded corner\. When the panel represents reinforced masonry, include a 2 by 2 foot opening placed at least 2 feet above the panel base and 2 feet away from all free edges, corners, and control joints. Provide required reinforcing around this opening as well as at wall corners and control joints.

1.3.1.4 Mock-Up Panel Construction Method

Where cavity walls are required, demonstrate and receive approval for the method of construction; i.e., either bring up the two wythes together or separately, with the insulation and appropriate ties placed within the specified tolerances across the cavity. Demonstrate provisions to preclude mortar or grout droppings in the cavity and to provide a clear open air space of the dimensions shown on the drawings. Where masonry is to be grouted, demonstrate and receive approval on the method that will be used to bring up the masonry wythes; support the reinforcing bars; and grout cells, bond beams, lintels, and collar joints using the requirements specified herein. When water-repellent is specified to be applied to the masonry, apply the approved product to the mock-up panel. Construct panels on a properly designed concrete foundation.

1.3.1.5 Mock-Up Panel Purpose

The completed panels is used as the standard of workmanship for the type of masonry represented. Do not commence masonry work until the mock-up panel for that type of masonry construction has been completed and approved. Protect panels from the weather and construction operations until the masonry work has been completed and approved. Perform cleaning procedures on the mockup and obtain approval of the Contracting Officer prior to cleaning the building. After completion of the work, completely remove the mock-up panels, including all foundation concrete, from the construction site.

1.3.2 Special Masonry Inspector Qualifications

Refer to Section 01 45 35 SPECIAL INSPECTIONS for qualifications and responsibilities of the masonry special inspector.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver, store, handle, and protect material to avoid chipping, breakage, and contact with soil or contaminating material. Store and prepare materials in already disturbed areas to minimize project site disturbance and size of project site.

1.4.1 Masonry Units

Cover and protect masonry units from precipitation. Conform to handling and storage requirements of TMS MSJC.

1.4.2 Reinforcement, Anchors, and Ties

Store steel reinforcing bars, coated anchors, ties, and joint reinforcement above the ground. Maintain steel reinforcing bars and uncoated ties free of loose mill scale and loose rust.

1.4.3 Cementitious Materials, Sand and Aggregates

Deliver cementitious and other packaged materials in unopened containers, plainly marked and labeled with manufacturers' names and brands. Store cementitious material in dry, weathertight enclosures or completely cover. Handle cementitious materials in a manner that will prevent the inclusion of foreign materials and damage by water or dampness. Store sand and aggregates in a manner to prevent contamination and segregation.

1.5 PROJECT/SITE CONDITIONS

Conform to TMS MSJC for hot and cold weather masonry erection.

1.5.1 Hot Weather Procedures

When ambient air temperature exceeds 100 degrees F, or exceeds 90 degrees F and the wind velocity is greater than 8 mph, comply with TMS MSJC Article 1.8 D for: preparation prior to conducting masonry work; construction while masonry work is in progress; and protection for newly completed masonry.

1.5.2 Cold Weather Procedures

When ambient temperature is below 40 degrees F, comply with TMS MSJC Article 1.8 C for: preparation prior to conducting masonry work; construction while masonry work is in progress; and protection for newly completed masonry.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

2.1.1 Design - Specified Compressive Strength of Masonry

The specified compressive strength of masonry, f'm, is 1,500 PSI.

2.1.2 Performance - Verify Masonry Compressive Strength

Verify specified compressive strength of masonry using the "Unit Strength Method" of TMS MSJC. Submit calculations and certifications of unit and mortar strength.

2.2 MANUFACTURED UNITS

2.2.1 General Requirements

Do not change the source of materials, which will affect the appearance of the finished work, after the work has started except with Contracting Officer's approval. Submit test reports from an approved independent laboratory. Certify test reports on a previously tested material as the same materials as that proposed for use in this project. Submit certificates of compliance stating that the materials meet the specified requirements.

2.2.2 Clay or Shale Brick

2.2.2.1 General

2.2.2.1.1 Sample Submittal

Submit brick samples as specified, showing the color range and texture of clay or shale brick. Limit units used on the project to those that conform to the approved sample. Submit sample of colored mortar with applicable masonry unit and color samples of three stretcher units and one unit for each type of special shape.

Brick is red flashed wirecut as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC.

2.2.2.1.2 Uniformity

Manufacture bricks at one time and from the same run. Deliver clay or shale brick units factory-blended to provide a uniform appearance and color range in the completed wall.

2.2.2.1.3 Recycled Content

Provide clay units containing a minimum of 5 percent post-consumer recycled content, and a minimum of 20 percent post-industrial recycled content.

2.2.2.1.4 Efflorescence Test

Test clay brick that will be exposed to weathering for efflorescence in accordance with ASTM C67/C67M. Schedule tests far enough in advance of starting masonry work to permit retesting if necessary. Units meeting the definition of "effloresced" are subject to rejection.

2.2.2.2 Solid Clay or Shale Brick

Provide solid clay or shale brick that conforms to ASTM C216, Type FBX. Provide brick with minimum five unit average compressive strength of 3,000 psi. Where brick cores, recesses, or deformation would be exposed to view, provide 100 percent solid units. Provide brick with texture and color tange to match the brick indicated.

Provide brick with specified sizes.

a. Modular size, 3-5/8 inches thick, 2-1/4 inches high, and 7-5/8 inches long.

2.2.3 Concrete Units

2.2.3.1 Aggregates

Test lightweight aggregates, and blends of lightweight and heavier aggregates in proportions used in producing the units, for stain-producing iron compounds in accordance with ASTM C641,visual classification method. Do not incorporate aggregates for which the iron stain deposited on the filter paper exceeds the "light stain" classification.

Use industrial waste by-products (air-cooled slag, cinders, or bottom ash), ground waste glass and concrete, granulated slag, and expanded slag in aggregates.

2.2.3.2 Concrete Masonry Units (CMU)

2.2.3.2.1 Recycled Content

Provide units with a minimum of 10 percent post-consumer recycled content, or a minimum of 40 percent post-industrial recycled content, based on mass, cost, or volume.

2.2.3.2.2 Size

Provide units with specified dimension of 7.625 inches wide, 7.625 inches

high, and 15.625 inches long. Provide a variety of standard wythe widths and shapes. Furnish bullnose, corner, double corner, sill, cap and header units. Units must have a regular, consistent texture.

2.2.3.2.3 Surfaces

Provide units with exposed surfaces that are smooth and of uniform texture.

2.2.3.2.4 Weather Exposure

Provide concrete masonry units with water-repellant admixture added during manufacture where units will be exposed to weather.

2.2.3.2.5 Unit Types

a. Hollow Load-Bearing Units: ASTM C90, lightweight . Provide load-bearing units for exterior walls, foundation walls, load-bearing walls, and shear walls.

b. bolid Load-Bearing Units: ASTM C90, lightweight or normal weight units. Provide solid units as indicated.

2.2.3.2.6 Jamb Units

Provide jamb units of the shapes and sizes to conform with wall units. Solid units may be incorporated in the masonry work where necessary to fill out at corners, gable slopes, and elsewhere as approved.

2.2.3.3 Architectural Units

Provide architectural units with patterned face shell: split faced.

Provide units that are integrally colored during manufacture.

Architectural masonry is gray split faced as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC.

2.2.3.4 Fire-Rated Concrete Masonry Units

For indicated fire-rated construction, provide concrete masonry units of minimum equivalent thickness for the fire rating indicated and the corresponding type of aggregates indicated in TABLE I. Units containing more than one of the aggregates listed in TABLE I will be rated by linear interpolation based on the percent by dry-rodded volume of each aggregate used in manufacturing the units.

TABLE I
FIRE-RATED CONCRETE MASONRY UNITS

Aggregate Type	Minimum Equivalent Thickness for Fire-Resistance Rating, inch						
	1/2 hour	3/4 hour	1 hour	1-1/2 hour	2 hours	3 hours	4 hours
Calcareous or siliceous gravel (other than limestone)	2.0	2.4	2.8	3.6	4.2	5.3	6.2

TABLE I
FIRE-RATED CONCRETE MASONRY UNITS

Aggregate Type	Minimum Equivalent Thickness for Fire-Resistance Rating, inch						
Limestone, cinders, or air-cooled slag	1.9	2.3	2.7	3.4	4.0	5.0	5.9
Expanded clay, expanded shale, or expanded slate	1.8	2.2	2.6	3.3	3.6	4.4	5.1
Expanded slag or pumice	1.5	1.9	2.1	2.7	3.2	4.0	4.7

Determine equivalent thickness in accordance with ACI 216.1. Where walls are to receive plaster or be faced with brick, or otherwise form an assembly; include the thickness of plaster or brick or other material in the assembly in determining the equivalent thickness. Submit calculation results.

2.3 EQUIPMENT

2.3.1 Vibrators

Maintain at least one spare vibrator on site at all times.

2.3.2 Grout Pumps

Pumping through aluminum tubes is not permitted.

2.4 MATERIALS

2.4.1 Mortar Materials

2.4.1.1 Cementitious Materials

Provide cementitious materials that conform to those permitted by ASTM C270.

2.4.1.2 Hydrated Lime and Alternates

Provide lime that conforms to one of the materials permitted by ASTM C207 for use in combination with portland cement, hydraulic cement, and blended hydraulic cement. Do not use lime in combination with masonry cement or mortar cement.

2.4.1.3 Admixtures for Masonry Mortar

In cold weather, use a non-chloride based accelerating admixture that conforms to ASTM C1384, unless Type III portland cement is used in the mortar.

In showers and kitchens, use mortar that contains a water-repellent admixture that conforms to ASTM C1384. Provide a water-repellent admixture, conforming to ASTM C1384 and of the same brand and manufacturer as the block's integral water-repellent, in the mortar used to place concrete masonry units that have an integral water-repellent admixture.

2.4.1.4 Aggregate and Water

Provide aggregate (sand) and water that conform to materials permitted by ASTM C270.

2.4.2 Grout and Ready-Mix Grout Materials

2.4.2.1 Cementitious Materials for Grout

Provide cementitious materials that conform to those permitted by ASTM C476.

2.4.2.2 Admixtures for Grout

Water-reducing admixtures that conform to ASTM C494/C494M Type F or G and viscosity-modifying admixtures that conform to ASTM C494/C494M Type S are permitted for use in grout. Other admixtures require approval by the Contracting Officer.

In cold weather, a non-chloride based accelerating admixture may be used subject to approval by the Contracting Officer; use accelerating admixture that is non-corrosive and conforms to ASTM C494/C494M, Type C.

2.4.2.3 Aggregate and Water

Provide fine and coarse aggregates and water that conform to materials permitted by ASTM C476.

2.5 MORTAR AND GROUT MIXES

2.5.1 Mortar Mix

a. Provide mortar Type S unless specified otherwise herein. Do not use masonry cement in the mortar. Do not use air-entrainment in the mortar.

b. Mortar is standard gray as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC.

c. For field-batched mortar, measure component materials by volume. Use measuring boxes for materials that do not come in packages, such as sand, for consistent batching. Mix cementitious materials and aggregates between 3 and 5 minutes in a mechanical batch mixer with a sufficient amount of water to produce a workable consistency. Do not hand mix mortar unless approved by the Contracting Officer. Maintain workability of mortar by remixing or retempering. Discard mortar that has begun to stiffen or is not used within 2-1/2 hours after initial mixing.

d. For preblended mortar, follow manufacturer's mixing instructions.

2.5.2 Grout and Ready Mix Grout Mix

Use grout that conforms to ASTM C476. Use conventional grout with a slump between 8 and 11 inches. Use self-consolidating grout with slump flow of 24 to 30 inches and a visual stability index (VSI) not greater than 1. Provide minimum grout strength of 3,000 psi in 28 days, as tested in accordance with ASTM C1019. Do not change proportions and do not use materials with different physical or chemical characteristics in grout for the work unless additional evidence is furnished that grout meets the

specified requirements. Use ready-mixed grout that conforms to ASTM C476.

2.6 ACCESSORIES

2.6.1 Grout Barriers

Grout barriers for vertical cores that consist of fine mesh wire, fiberglass, or expanded metal.

2.6.2 Anchors, Ties, and Bar Positioners

2.6.2.1 General

a. Fabricate anchors and ties without drips or crimps. Size anchors and ties to provide a minimum of 5/8 inch mortar cover from each face of masonry.

b. Fabricate steel wire anchors and ties shall from wire conforming to ASTM A1064/A1064M and hot-dip galvanize in accordance with ASTM A153/A153M.

c. Fabricate joint reinforcement in conformance with ASTM A951/A951M. Hot dip galvanize joint reinforcement in exterior walls and in interior walls exposed to moist environment in conformance with ASTM A153/A153M. Galvanize joint reinforcement in other interior walls in conformance with ASTM A641/A641M; coordinate with paragraph JOINT REINFORCEMENT below.

d. Submit two anchors, ties and bar positioners of each type used, as samples.

2.6.2.2 Wire Mesh Anchors

Provide wire mesh anchors of 1/4 inch mesh galvanized hardware cloth, conforming to ASTM A185/A185M, with length not less than 12 inches, at intersections of interior non-bearing masonry walls.

2.6.2.3 Wall Ties for Multi-Wythe Masonry Construction

Provide rectangular-shaped wall ties, fabricated of hot-dipped galvanized W2.8 diameter steel wire. Provide rectangular wall ties no less than 4 inches wide.

Provide adjustable type wall ties, if approved for use, that consist of two essentially U-shaped elements fabricated of minimum W2.8 diameter steel wire or pintle type ties that are inserted to eyes of horizontal joint reinforcement, hot-dip galvanized. Provide adjustable ties with double pintle legs and allows a maximum offset of 1-1/4 inch between each element of the tie and maximum distance between connecting parts no more than 1/16 inch. Form the pintle and eye elements shall be formed so that both can be in the same plane. Wall ties may also be of a continuous type conforming to paragraph JOINT REINFORCEMENT.

2.6.2.4 Adjustable Anchors

2.6.2.4.1 Anchorage to Structural Steel

Provide hot-dip galvanized adjustable anchors of W.2.8 diameter for connecting masonry walls to the structural steel frame. Provide zinc-rich

paint for touching up paint after welding galvanized anchors to structural steel.

2.6.2.5 Veneer Anchor Screws

Provide screws for attachment of veneer anchors to cold-formed steel framing members of size No. 12. Self tapping veneer anchors consist of a zinc alloy barrel, flanged head and eye with interchangeable corrosion resistant, self drilling threaded screws selected for the substrate encountered. Coordinate barrel shaft lengths with insulation thickness penetrated, allowing shoulders to seat directly on structural substrates below while flanged heads cover fastener holes. Furnish rubber washers beneath flanged heads to create insulation surface seals. Provide length of screws such that the screws penetrate the holding member by not less than 5/8 inch.

2.6.2.6 Bar Positioners

Factory-fabricate bar positioners, used to prevent displacement of reinforcing bars during the course of construction, from 9 gauge steel wire or equivalent, and hot-dip galvanized. Bar positioners must be suitable for intended use and be corrosion resistant steel. Bar positioners not fully contained within the wythe must be hot-dip galvanized.

2.6.3 Joint Reinforcement

Factory fabricate joint reinforcement in conformance with ASTM A951/A951M, welded construction. Provide ladder type joint reinforcement, having one longitudinal wire in the mortar bed of each face shell for hollow units and one wire for solid units and with all wires a minimum of 9 gauge. Size joint reinforcement to provide a minimum of 5/8 inch cover from each face. Space crosswires not more than 16 inches. Provide joint reinforcement for straight runs in flat sections not less than 10 feet long. Provide joint reinforcement with factory formed corners and intersections. If approved for use, joint reinforcement may be furnished with adjustable wall tie features. Submit one piece of each type used, including corner and wall intersection pieces, showing at least two cross wires.

2.6.4 Reinforcing Steel Bars

Reinforcing steel bars and rods shall conform to ASTM A615/A615M or ASTM A996/A996M, Grade 60.

2.6.5 Clay Masonry Expansion-Joint Materials

Provide backer rod and sealant, adequate to accommodate joint compression and extension equal to 50 percent of the width of the joint. Provide the backer rod of compressible rod stock of closed cell polyethylene foam, polyurethane foam, butyl rubber foam, or other flexible, nonabsorptive material as recommended by the sealant manufacturer. Provide sealant in conformance with Section 07 92 00 JOINT SEALANTS with a maximum volatile organic compound (VOC) content of 600 grams/liter.

Submit one piece of each type of material used.

2.6.6 Through Wall Flashing and Weeps

2.6.6.1 General

Provide self-adhesive rubberized sheet on formable stainless steel or copper flashing except that flashing indicated to terminate in reglets shall be metal flashing.

2.6.6.2 Copper or Stainless Steel Flashing

Provide copper sheet, complying with ASTM B370, minimum 16 ounce weight; or stainless steel, ASTM A167, Type 304 or 316, 0.015 inch thick, No. 2D finish.

2.6.6.3 Rubberized Flashing

Provide self-adhesive rubberized asphalt sheet flashing consisting of 32-mil thick pliable and highly adhesive rubberized asphalt compound bonded completely and integrally to 8-mil thick, high density, cross-laminated polyethylene film to produce an overall thickness of 40 mils. Provide rubberized, asphalt-based mastic and surface conditioner that are each approved by flashing manufacturer for use with flashing material. Continuously support self adhered through wall flashing with formable stainless steel flashing. Formable miscellaneous flashing and sheet metal is 0.019 inch, 26 gauge, UNS S30400 Type 304 stainless steel sheet coil complying with ASTM A 240 and ASTM A 666. Fasteners are stainless steel.

2.6.6.4 Weep Ventilators

Provide weep ventilators that are prefabricated from stainless steel or plastic. Provide inserts with grill or louver-type openings designed to allow the passage of moisture from cavities and to prevent the entrance of insects, and with a rectangular closure strip to prevent mortar droppings from clogging the opening. Provide ventilators with compressible flanges to fit in a standard 3/8 inch wide mortar joint and with height equal to the nominal height of the unit.

Provide similar ventilators in head joint relief vents.

2.6.6.5 Metal Drip Edge

Provide stainless steel drip edge, 15-mil thick, hemmed edges, with down-turned drip at the outside edge and upturned dam at the inside edge for use with membrane flashings.

2.6.7 RIGID BOARD-TYPE INSULATION

Provide rigid board-type insulation as specified in Section 07 21 13 BOARD AND BLOCK INSULATION.

PART 3 EXECUTION

3.1 EXAMINATION

Prior to start of work, verify the applicable conditions as set forth in TMS MSJC, inspection.

3.2 PREPARATION

3.2.1 Stains

Protect exposed surfaces from mortar and other stains. When mortar joints are tooled, remove mortar from exposed surfaces with fiber brushes and wooden paddles. Protect base of walls from splash stains by covering adjacent ground with sand, sawdust, or polyethylene.

3.2.2 Loads

Do not apply uniform loads for at least 12 hours or concentrated loads for at least 72 hours after masonry is constructed. Provide temporary bracing as required.

3.2.3 Concrete Surfaces

Where masonry is to be placed, clean concrete of laitance, dust, dirt, oil, organic matter, or other foreign materials and slightly roughen to provide a surface texture with a depth of at least 1/8 inch. Sandblast, if necessary, to remove laitance from pores and to expose the aggregate.

3.2.4 Bracing

Provide bracing and scaffolding necessary for masonry work. Design bracing to resist wind pressure as required by OSHA and local codes and submit bracing calculations, sealed by a registered professional engineer. Do not remove bracing in less than 10 days.

3.3 ERECTION

3.3.1 General

a. Coordinate masonry work with the work of other trades to accommodate built-in items and to avoid cutting and patching. Lay masonry units in running bond pattern. Lay facing courses level with back-up courses, unless the use of adjustable ties has been approved in which case the tolerances is plus or minus 1/2 inch. Adjust each unit to its final position while mortar is still soft and has plastic consistency.

b. Remove and clean units that have been disturbed after the mortar has stiffened, and relay with fresh mortar. Keep air spaces, cavities, chases, expansion joints, and spaces to be grouted free from mortar and other debris. Select units to be used in exposed masonry surfaces from those having the least amount of chipped edges or other imperfections detracting from the appearance of the finished work.

c. When necessary to temporarily discontinue the work, step (rack) back the masonry for joining when work resumes. Toothing may be used only when specifically approved by the Contracting Officer. Before resuming work, remove loose mortar and thoroughly clean the exposed joint. Cover the top of walls subjected to rain or snow with nonstaining waterproof covering or membrane when work is not in process. Extend the covering a minimum of 610 mm 2 feet down on each side of the wall and hold securely in place.

d. Ensure that units being laid and surfaces to receive units are free of water film and frost. Lay solid units in a nonfurrowed full bed of

mortar. Bevel mortar for veneer wythes and slope down toward the cavity side. Shove units into place so that the vertical joints are tight. Completely fill vertical joints between solid units with mortar, except where indicated at control, expansion, and isolation joints. Place hollow units so that mortar extends to the depth of the face shell at heads and beds, unless otherwise indicated. Mortar will be permitted to protrude up to 1/2 inch into the space or cells to be grouted. Provide means to prevent mortar from dropping into the space below or clean grout spaces prior to grouting.

e. In multi-wythe construction with collar joints no more than 3/4 inch wide, bring up the inner wythe not more than 16 inches ahead of the outer wythe. Fill collar joints with mortar during the laying of the facing wythe, and filling shall not lag the laying of the facing wythe by back-buttering each unit as it is laid.

3.3.1.1 Jointing

Tool mortar joints when the mortar is thumbprint hard. Tool horizontal joints after tooling vertical joints. Brush mortar joints to remove loose and excess mortar.

3.3.1.1.1 Tooled Joints

Tool mortar joints in exposed exterior and interior masonry surfaces concave, using a jointer that is slightly larger than the joint width so that complete contact is made along the edges of the unit. Perform tooling so that the mortar is compressed and the joint surface is sealed. Use a jointer of sufficient length to obtain a straight and true mortar joint. No exterior joints are to be left un-tooled.

3.3.1.1.2 Flush Joints

Flush cut mortar joints in concealed masonry surfaces and joints at electrical outlet boxes in wet areas. Finish flush cut joints by cutting off the mortar flush with the face of the wall. Point joints in unparged masonry walls below grade tight. For architectural units, such as fluted units, completely fill both the head and bed joints and flush cut.

3.3.1.1.3 Door and Window Frame Joints

On the exposed interior side of exterior frames, joints between frames and abutting masonry walls shall be raked to a depth of 3/8 inch. On the exterior side of exterior frames, joints between frames and abutting masonry walls shall be raked to a depth of 3/8 inch.

3.3.1.1.4 Joint Widths

a. Construct brick masonry with mortar joint widths equal to the difference between the specified and nominal dimensions of the unit, within tolerances permitted by TMS MSJC.

b. Provide 3/8 inch wide mortar joints in concrete masonry.

c. caintain mortar joint widths within tolerances permitted by TMS MSJC

3.3.1.2 Cutting and Fitting

Use full units of the proper size wherever possible, in lieu of cut

units. Locate cut units where they would have the least impact on the architectural aesthetic goals of the facility. Perform cutting and fitting, including that required to accommodate the work of others, by masonry mechanics using power masonry saws. Concrete masonry units may be wet or dry cut. Before being placed in the work, dry wet-cut units to the same surface-dry appearance as uncut units being laid in the wall. Provide cut edges that are clean, true and sharp.

a. Carefully make openings in the masonry so that wall plates, cover plates or escutcheons required by the installation will completely conceal the openings and will have bottoms parallel with the masonry bed joints. Provide reinforced masonry lintels above openings over 12 inches wide for pipes, ducts, cable trays, and other wall penetrations, unless steel sleeves are used.

b. Do not reduce masonry units in size by more than one-third in height and one-half in length. Do not locate cut products at ends of walls, corners, and other openings.

3.3.1.3 Unfinished Work

Rack back unfinished work for joining with new work. Toothing may be resorted to only when specifically approved by the Contracting Officer. Remove loose mortar and thoroughly clean the exposed joints before laying new work.

3.3.1.4 Clay Masonry Expansion Joints

Provide clay masonry expansion joints as indicated. Construct by filling with a compressible foam pad. Ensure that no mortar or other noncompressible materials are within the joint. Install backer rod and sealant in accordance with Section 07 92 00 JOINT SEALANTS.

3.3.1.5 Control Joints

Provide control joints in concrete masonry as indicated. Construct by raking out mortar within the head joint. Form a continuous vertical joint at control joint locations, including through bond beams, by utilizing half blocks in alternating courses on each side of the joint. Interrupt the control joint key in courses containing continuous bond beam reinforcement. Do not interrupt the horizontal reinforcement and grout at the control joint.

Where mortar was placed in the joint, rake both faces of the control joints to a depth of 3/4 inch. Install backer rod and sealant on both faces in accordance with Section 07 92 00 JOINT SEALANTS.

3.3.2 Clay or Shale Brick Masonry

3.3.2.1 Brick Placement

Blend all brick at the jobsite from several cubes to produce a uniform appearance when installed. An observable "banding" or "layering" of colors or textures caused by improperly mixed brick is unacceptable. Lay brick facing with the better face exposed. Lay brick in running bond with each course bonded at corners, unless otherwise indicated. Lay molded brick with the frog side down. Do not lay brick that is cored, recessed, or has other deformations in a manner that allows those deformations to be exposed to view; lay 100 percent solid units in these areas. Completely

fill head and bed joints of solid units with mortar. Lay hollow units with mortar joints as specified for concrete masonry units.

3.3.2.2 Wetting of Units

Wetting of clay, shale brick, or hollow brick units having an initial rate of absorption of more than 1 gram per minute per square inch of bed surface shall be in conformance with ASTM C67/C67M. Ensure that each unit is nearly saturated when wetted but surface dry when laid.

Test clay or shale brick daily on the job, prior to laying, as follows: Using a wax pencil, draw a circle the size of a quarter on five randomly selected bricks. Apply 20 drops of water with a medicine dropper to the surface within the circle on each brick. If the average time that the water is completely absorbed in the five bricks is less than 1-1/2 minutes, wet bricks represented by the five bricks tested.

3.3.2.3 Brick Sills

Lay brick on edge, slope not less than 3/4 inch downward to the outside, and project not less than 1/2 inch beyond the face of the wall to form a wash and drip. Fill all joints solidly with mortar and tool.

3.3.3 Composite Walls

Tie masonry wythes together with joint reinforcement or with unit wall ties. Embed wall ties at least 1-1/2 inch into mortar of solid units and at least 1/2 inch into the mortar of the outer face shell of hollow units. Provide at least one tie every 2.67 square feet for wire size W1.7 and at least one tie every 4.50 square feet for wire size W2.8. Space ties at a maximum of 36 inches horizontally and 24 inches vertically. Do not cross expansion joints or control joints with ties. Fill collar joints between masonry facing and masonry backup solidly with grout.

3.3.4 Cavity Walls (Multi-Wythe Noncomposite Walls

Provide a continuous cavity as indicated. Bevel mortar beds away from cavity to prevent projection into cavity when bricks are shoved in place. Keep cavities clear and clean of mortar droppings. At the bottom of cavity walls, in the course immediately above the through-wall flashing, temporarily omit one brick every 4 feet. Clean mortar droppings and debris out of the cavity through the temporary openings at least once each day masonry is laid, and more often when required to keep the cavities clean. Fill in the openings with bricks and mortar after the wall is complete and the cavity has been inspected and found clean. Install an air and moisture barrier on the cavity face of interior wythe.

Securely tie the two wythes together with horizontal joint reinforcement, or provide ties to connect the masonry wythes in sufficient quantity to comply with the following requirements: maximum wall area per tie of 1.77 SF, and maximum vertical spacing of 1 foot, 4 inches, and maximum horizontal spacing of 1 foot, 4 inches. Provide additional ties around openings larger than 16 inches in either direction. Space ties around perimeter of opening at a maximum of 3 feet on center. Place ties within 12 inchesof openings. Ties with drips are not permitted.

3.3.5 ANCHORAGE

3.3.5.1 Anchorage to Structural Steel

Masonry shall be anchored to vertical structural steel framing with adjustable steel wire anchors spaced not over 16 inches on centers vertically, and if applicable, not over 24 inches on centers horizontally.

3.3.5.2 Anchorage at Intersecting Walls

Provide wire mesh anchors at maximum 16 inches spacing at intersections of interior non-bearing masonry walls.

Anchor structural masonry walls with horizontal joint reinforcement spaced no more than 1 foot, 4 inches feet on center, unless the drawings indicate a movement joint at the intersection.

3.3.6 Lintels

3.3.6.1 Masonry Lintels

Construct masonry lintels with lintel units filled solid with grout in all courses and reinforced with a minimum of two No. 4 bars in the bottom course unless otherwise indicated. Extend lintel reinforcement beyond each side of masonry opening 40 bar diameters or 24 inches, whichever is greater. Support reinforcing bars in place prior to grouting and locate 1/2 inch above the bottom inside surface of the lintel unit.

3.3.6.2 Precast Concrete and Steel Lintels

Provide steel lintels as shown on the Drawings. Set lintels in a full bed of mortar with faces plumb and true. Provide steel lintels with a minimum bearing length of 8 inches unless otherwise indicated. In partially grouted masonry, provide fully grouted units under the full lintel bearing length, unless otherwise indicated.

3.3.7 Sills and Copings

Set sills and copings in a full bed of mortar with faces plumb and true. Slope sills and copings to drain water. Mechanically anchor copings and sills.

3.4 INSTALLATION

3.4.1 Bar Reinforcement Installation

3.4.1.1 Preparation

Submit detail drawings showing bar splice locations. Identify bent bars on a bending diagram and reference and locate such bars on the drawings. Show wall dimensions, bar clearances, and wall openings. Utilize bending details that conform to the requirements of ACI SP-66. No approval will be given to the shop drawings until the Contractor certifies that all openings, including those for mechanical and electrical service, are shown. If, during construction, additional masonry openings are required, resubmit the approved shop drawings with the additional openings shown along with the proposed changes. Clearly highlight location of these additional openings. Provide wall elevation drawings with minimum scale of 1/4 inch per foot. Submit drawings including plans, elevations, and

details of wall reinforcement; details of reinforcing bars at corners and wall intersections; offsets; tops, bottoms, and ends of walls; control and expansion joints; lintels; and wall openings.

Clean reinforcement of loose, flaky rust, scale, grease, mortar, grout, and other coatings that might destroy or reduce its bond prior to placing grout. Do not use bars with kinks or bends not shown on the approved shop drawings. Place reinforcement prior to grouting. Unless otherwise indicated, extend vertical wall reinforcement to within 2 inches of tops of walls.

3.4.1.2 Positioning Bars

a. Accurately place vertical bars within the cells at the positions indicated on the drawings. A minimum clearance of 1/2 inch shall be maintained between the bars and masonry units. Provide minimum clearance between parallel bars of 1/2 inch between the bars and masonry units for coarse grout and a minimum clearance of 1/4 inch between the bars and masonry units for fine grout. Provide minimum clearance between parallel bars of 1 inch or one diameter of the reinforcement, whichever is greater. Vertical reinforcement may be held in place using bar positioners located near the ends of each bar and at intermediate intervals of not more than 192 diameters of the reinforcement or by other means to prevent displacement beyond permitted tolerances. As masonry work progresses, secure vertical reinforcement to prevent displacement beyond allowable tolerances.

b. Wire column and pilaster lateral ties in position around the vertical reinforcing bars. Place lateral ties in contact with the vertical reinforcement and do not place in horizontal mortar bed joints.

c. Position horizontal reinforcing bars as indicated. Stagger splices in adjacent horizontal bars, unless otherwise indicated.

d. Form splices by lapping bars as indicated. Do not cut, bend or eliminate reinforcing bars. Foundation dowel bars may be field-bent when permitted by TMS MSJC.

3.4.1.3 Splices of Bar Reinforcement

Lap splice reinforcing bars as indicated. When used, provide welded or mechanical connections that develop at least 125 percent of the specified yield strength of the reinforcement.

3.4.2 Placing Grout

3.4.2.1 General

Fill cells containing reinforcing bars with grout. Solidly grout hollow masonry units in walls or partitions supporting plumbing, heating, or other mechanical fixtures, voids at door and window jambs, and other indicated spaces. Solidly grout cells under lintel bearings on each side of openings for full height of openings. Solidly grout walls below grade, lintels, and bond beams. Units other than open end units may require grouting each course to preclude voids in the units.

Discard site-mixed grout that is not placed within 1-1/2 hours after water is first added to the batch or when the specified slump is not met without adding water after initial mixing. Discard ready-mixed grout that does not

meet the specified slump without adding water other than water that was added at the time of initial discharge. Allow sufficient time between grout lifts to preclude displacement or cracking of face shells of masonry units. Provide a grout shear key between lifts when grouting is delayed and the lower lift loses plasticity. If blowouts, flowouts, misalignment, or cracking of face shells should occur during construction, tear down the wall and rebuild.

3.4.2.2 Vertical Grout Barriers for Multi-Wythe Composite Walls

In multi-wythe composite walls, provide grout barriers in the collar join not more than 30 feet apart, or as required, to limit the horizontal flow of grout for each pour.

3.4.2.3 Horizontal Grout Barriers

Embed horizontal grout barriers in mortar below cells of hollow units receiving grout.

3.4.2.4 Grout Holes and Cleanouts

3.4.2.4.1 Grout Holes

Provide grouting holes in slabs, spandrel beams, and other in-place overhead construction. Locate holes over vertical reinforcing bars or as required to facilitate grout fill in bond beams. Provide additional openings spaced not more than 16 inches on centers where grouting of hollow unit masonry is indicated. Fom such openings not less than 4 inches in diameter or 3 by 4 inches in horizontal dimensions. Upon completion of grouting operations, plug and finish grouting holes to match surrounding surfaces.

3.4.2.4.2 Cleanouts for Hollow Unit Masonry Construction

For hollow masonry units. provide cleanout holes at the bottom of every grout pour in cores containing vertical reinforcement when the height of the grout pour exceeds 5 feet 4 inches. Where all cells are to be grouted, construct cleanout courses using bond beam units in an inverted position to permit cleaning of all cells. Provide cleanout holes at a maximum spacing of 32 inches where all cells are to be filled with grout.

Establish a new series of cleanouts if grouting operations are stopped for more than 4 hours. Provide cleanouts not less than 3 by 3 inch by cutting openings in one face shell. Manufacturer's standard cutout units may be used at the Contractor's option. Do not cleanout holes until masonry work, reinforcement, and final cleaning of the grout spaces have been completed and inspected. For walls which will be exposed to view, close cleanout holes in an approved manner to match surrounding masonry.

3.4.2.4.3 Cleanouts for Multi-Wythe Composite Masonry Construction

Provide cleanouts for construction of walls that incorporate a grout filled cavity between solid masonry wythes, provide cleanouts at the bottom of every pour by omitting every other masonry unit from one wythe. Establish a new series of cleanouts if grouting operations are stopped for more than 4 hours. Do not plug cleanout holes until masonry work, reinforcement, and final cleaning of the grout spaces have been completed and inspected. For walls which will be exposed to view, close cleanout holes in an approved manner to match surrounding masonry.

3.4.2.5 Grout Placement

A grout pour is the total height of masonry to be grouted prior to erection of additional masonry. A grout lift is an increment of grout placement within a grout pour. A grout pour is filled by one or more lifts of grout.

a. Lay masonry to the top of a pour permitted by TMS MSJC Table 7, based on the size of the grout space and the type of grout. Prior to grouting, remove masonry protrusions that extend 1/2 inch or more into cells or spaces to be grouted. Provide grout holes and cleanouts in accordance with paragraph GROUT HOLES AND CLEANOUTS above when the grout pour height exceeds 5 feet 4 inches. Hold reinforcement, bolts, and embedded connections rigidly in position before grouting is started. Do not prewet concrete masonry units.

b. Place grout using a hand bucket, concrete hopper, or grout pump to fill the grout space without segregation of aggregate. Operate grout pumps to produce a continuous stream of grout without air pockets, segregation, or contamination.

c. If the masonry has cured at least 4 hours, grout slump is maintained between 10 to 11 inches, and no intermediate reinforced bond beams are placed between the top and bottom of the pour height, place conventional grout in lifts not exceeding 12 feet 8 inches. For the same curing and slump conditions but with intermediate bond beams, limit conventional grout lift to the bottom of the lowest bond beam that is more than 5 feet 4 inches above the bottom of the lift, but do not exceed 12 feet 8 inches. If masonry has not cured at least 4 hours or grout slump is not maintained between 10 to 11 inches, place conventional grout in lifts not exceeding 5 feet 4 inches.

d. Consolidate conventional grout lift and reconsolidate after initial settlement before placing next lift. For grout pours that are 12 inches or less in height, consolidate and reconsolidate grout by mechanical vibration or puddling. For grout pours that are greater than 12 inches in height, consolidate and reconsolidate grout by mechanical vibration. Apply vibrators at uniformly spaced points not further apart than the visible effectiveness of the machine. Limit duration of vibration to time necessary to produce satisfactory consolidation without causing segregation. If previous lift is not permitted to set, dip vibrator into previous lift. Do not insert vibrators into lower lifts that are in a semi-solidified state. If lower lift sets prior to placement of subsequent lift, form a grout key by terminating grout a minimum of 1-1/2 inch below a mortar joint. Vibrate each vertical cell containing reinforcement in partially grouted masonry. Do not form grout keys within beams.

e. If the masonry has cured 4 hours, place self-consolidating grout (SCG) in lifts not exceeding the pour height. If masonry has not cured for at least 4 hours, place SCG in lifts not exceeding 5 feet 4 inches. Do not mechanically consolidate self-consolidating grout. Place self-consolidating grout in accordance with manufacturer's recommendations.

f. Upon completion of each day's grouting, remove waste materials and debris from the equipment, and dispose of outside the masonry.

3.4.3 Joint Reinforcement Installation

Install joint reinforcement at 16 inches on center unless otherwise indicated. Lap joint reinforcement not less than 6 inches. Install prefabricated sections at corners and wall intersections. Place the longitudinal wires of joint reinforcement in mortar beds to provide not less than 5/8 inch cover to either face of the unit.

3.4.4 Bond Beams

Reinforce and grout bond beams as indicated and as described in paragraphs above. Install grout barriers under bond beam units to retain the grout as required, unless wall is fully grouted or solid bottom units are used. For high lift grouting in partially grouted masonry, provide grout retaining material on the top of bond beams to prevent upward flow of grout. Ensure that reinforcement is continuous, including around corners, except through control joints or expansion joints, unless otherwise indicated.

3.4.5 Flashing and Weeps

a. Install through-wall flashing at obstructions in the cavity and where indicated on Drawings. Ensure continuity of the flashing at laps and inside and outside corners by splicing in a manner approved by the flashing manufacturer. Ensure that the top edge of the flashing is sealed by attaching a termination bar and applying compatible sealant at the top edge of the termination bar. Terminate the horizontal leg of the flashing terminating the fabric flashing 1/2 inch short of the outside face of masonry and adhering the flashing to a sheet metal drip edge. Provide sealant below the drip edge of through-wall flashing.

b. Wherever through-wall flashing occurs, provide weep holes to drain flashing to exterior at acceptable locations as indicated. Provide weeps of weep ventilators. Locate weeps not more than 24 inches on centers in mortar joints of the exterior wythe directly on the horizontal leg of through-wall flashing over foundations, bond beams, and any other horizontal interruptions of the cavity. Place weep holes perfectly horizontal or slightly canted downward to encourage water drainage outward and not inward. Other methods may be used for providing weeps when spacing is reduced to 16 inches on center and approved by the Contracting Officer. Maintain weeps free of mortar and other obstructions.

3.5 APPLICATION

3.5.1 Insulation

Insulate cavity walls (multi-wythe noncomposite masonry walls), where shown, by installing board-type insulation on the cavity side of the inner wythe. Apply board type insulation directly to the masonry or thru-wall flashing with adhesive. Neatly fit insulation between obstructions without impaling insulation on ties or anchors. Apply insulation in parallel courses with vertical joints breaking midway over the course below and in moderate contact with adjoining units without forcing. Cut to fit neatly against adjoining surfaces.

3.5.2 Interface with Other Products

3.5.2.1 Built-In Items

Fill spaces around built-in items with mortar. Point openings around flush-mount electrical outlet boxes in wet locations with mortar. Embed anchors, ties, wall plugs, accessories, flashing, pipe sleeves and other items required to be built-in as the masonry work progresses. Fully embed anchors, ties and joint reinforcement in the mortar. Fill cells receiving anchor bolts and cells of the first course below bearing plates with grout, unless otherwise indicated.

3.5.2.2 Door and Window Frame Joints

On the exposed interior and exterior sides of exterior frames, rake joints between frames and abutting masonry walls to a depth of 3/8 inch.

3.5.2.3 Bearing Plates

Set bearing plates for beams, joists, joist girders and similar structural members to the proper line and elevation with damp-pack bedding mortar, except where non-shrink grout is indicated. Provide bedding mortar and non-shrink grout.

3.5.3 Tolerances

Lay masonry plumb, true to line, with courses level within the tolerances of TMS MSJC, Article 3.3 F.

3.6 FIELD QUALITY CONTROL

3.6.1 Tests

3.6.1.1 Field Testing of Grout

a. Perform grout testing at the following frequency: one time per day of placement. For each required grout property to be evaluated, provide a minimum of three specimens.

b. Sample and test conventional and self-conslidating grout for compressive strength and temperature in accordance with ASTM C1019.

c. Evaluate slump in conventional grout in accordance with ASTM C1019.

d. Evaluate slump flow and visual stability index of self-consolidating grout in accordance with ASTM C1611/C1611M.

3.6.1.2 Clay Brick Efflorescence Test

Test clay brick that will be exposed to weathering for efflorescence in accordance with ASTM C67/C67M. Schedule tests far enough in advance of starting masonry work to permit retesting if necessary. Units meeting the definition of "effloresced" are subject to rejection.

3.6.2 Special Inspection

Perform special inspections and testing in accordance with Section 01 45 35 SPECIAL INSPECTIONS.

3.7 POINTING AND CLEANING

After mortar joints have attained their initial set, but prior to hardening, completely remove mortar and grout daubs and splashings from masonry-unit surfaces that will be exposed. Before completion of the work, rake out defects in joints of masonry to be exposed, fill with mortar, and tool to match existing joints. Immediately after grout work is completed, remove scum and stains that have percolated through the masonry work using a low pressure stream of water and a stiff bristled brush. Do not clean masonry surfaces, other than removing excess surface mortar, until mortar in joints has hardened. Leave masonry surfaces clean, free of mortar daubs, dirt, stain, and discoloration, including scum from cleaning operations, and with tight mortar joints throughout. Do not use metal tools and metal brushes for cleaning.

3.7.1 Dry-Brushing Concrete Masonry

Dry brush exposed concrete masonry surfaces at the end of each day's work and after any required pointing, using stiff-fiber bristled brushes.

3.7.2 Clay Brick Surfaces

Clean exposed clay brick masonry surfaces to obtain surfaces free of stain, dirt, mortar and grout daubs, efflorescence, and discoloration or scum from cleaning operations. Perform cleaning in accordance with the approved cleaning procedure demonstrated on the mockup.

After cleaning, examine the sample panel of similar material for discoloration or stain as a result of cleaning. If the sample panel is discolored or stained, change the method of cleaning to ensure that the masonry surfaces in the structure will not be adversely affected. Water-soak exposed masonry surfaces and then clean with a proprietary masonry cleaning agent specifically recommended for the color and texture by the clay brick manufacturer and manufacturer of the cleaning product. Apply the solution with stiff fiber brushes, followed immediately by thorough rinsing with clean water. Use proprietary cleaning agents in conformance with the cleaning product manufacturer's printed recommendations. Remove efflorescence in conformance with the brick manufacturer's recommendations.

3.8 CLOSE-OUT TAKE-BACK PROGRAM

Collect information from manufacturer for take-back program options. Set aside masonry units, full and partial to be returned to manufacturer for recycling into new product. When such a service is not available, seek local recyclers to reclaim the materials. Submit documentation that includes contact information, summary of procedures, and the limitations and conditions applicable to the project. Indicate manufacturer's commitment to reclaim materials for recycling and/or reuse.

3.9 PROTECTION

Protect facing materials against staining. Cover top of walls with nonstaining waterproof covering or membrane to protect from moisture intrusion when work is not in progress. Continue covering the top of the unfinished walls until the wall is waterproofed with a complete roof or parapet system. Extend covering a minimum of 2 feet down on each side of the wall and hold securely in place. Before starting or resuming work, clean top surface of masonry in place of loose mortar and foreign material.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 04 73 00

CAST STONE SCULPTURE
12/25

PART 1 GENERAL

1.1 SCOPE

Provide labor, material, equipment and services necessary for, and reasonably incidental to, furnishing and installing cast stone sculpture work indicated within the Instruments of Service. Incorporate related accessories and specialties to accomplish a complete and proper installation. Coordinate and schedule this work with the work of other trades to ultimately provide superior workmanship in the finished product.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C33/C33M	(2024a) Standard Specification for Concrete Aggregates
ASTM C67/C67M	(2025) Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile
ASTM C91/C91M	(2018) Standard Specification for Masonry Cement
ASTM C144	(2025) Standard Specification for Aggregate for Masonry Mortar
ASTM C150/C150M	(2024) Standard Specification for Portland Cement
ASTM C207	(2024) Standard Specification for Hydrated Lime for Masonry Purposes
ASTM C270	(2025b) Standard Specification for Mortar for Unit Masonry
ASTM C476	(2023) Standard Specification for Grout for Masonry
ASTM C595/C595M	(2025) Standard Specification for Blended Hydraulic Cements
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM C979/C979M	(2024) Standard Specification for Pigments for Integrally Colored Concrete
ASTM C1194	(2024) Standard Test Method for

	Compressive Strength of Architectural Cast Stone
ASTM C1195	(2021) Standard Test Method for Absorption of Architectural Cast Stone
ASTM C1107/C1107M	(2020) Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)
ASTM C1184	(2023) Standard Specification for Structural Silicone Sealants

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

CAST STONE; G

Provide material mix designs indicating cement, aggregate and pigment proportions.

SD-04 Samples

CAST STONE; G

Cast stone color is White.

Furnish two samples of each selected color and finish that is representative of the installation.

SD-05 Design Data

CAST STONE; G

Include dimensioned, camera ready line art of sculptures.

SD-10 Operation and Maintenance Data

MAINTENANCE; G

PART 2 PRODUCTS

2.1 MATERIALS

Furnish CAST STONE indicated.

2.1.1 Mixes

Cast stone mixes are proportioned cements combined with natural or manufactured sands, crushed stone, well graded natural gravel, mineral coloring pigments and admixtures. Mixes are varied to achieve desired appearances and physical properties of bas relief sculptural elements. Employ dry machine casting, vibrant dry tamp casting and wet casting without preference to best suit applications encountered. Cured castings

have a nominal 1 inch thickness. Profiles specified are the minimum cross sections to be provided. Increase cross sections to achieve required surface areas and accommodate means of attachment.

Cast Stone	**Performance**	**Standard**
Compressive strength at 28 days	4,000 PSI	ASTM C1194
Water absorption	Less than 4%	ASTM C1195

The cast stone matrix consists of white cement conforming to ASTM C150/C150M, Type I portland cement. Fine aggregates are graded and washed natural sands, or manufactured granite, quartz or limestone sands, complying with ASTM C33/C33M. Coarse aggregates are graded and washed natural gravels or crushed, graded quartz, limestone or other durable stone complying with ASTM C33/C33M. Inorganic pigments are natural or synthetic iron oxide types complying with ASTM C979/C979M and guaranteed lime proof. Non metallic, alkali resistant glass fiber reinforcement material is incorporated into larger castings for enhanced structural integrity. Admixtures are employed to achieve required properties for air entrainment, low permeability, accelerated cure, increased flexural strength, enhanced compressive strength and weathering resistance. Aggregates and glass fibers are 18 to 22% post consumer material.

2.1.2 Anchors

Concealed anchors, when required, are threaded rods embedded in lugs of commercially available hot dipped galvanized steel, brass or stainless steel. Furnish the recommended construction adhesives for embedments.

2.1.3 Mortar

Mortar complies with ASTM C270, Type S and has a twenty-eight day minimum compressive strength of 1,800 PSI. Portland cement, Type I or II complies with ASTM C150/C150M. Use prepackaged mortar that only requires sand and potable water additives. Sand complies with ASTM C144. Hydrated lime conforms to ASTM C207, Type S and blended hydraulic cements conform with ASTM C595/C595M. Mixes have a freeze and thaw resistance with a 35% maximum loss of compressive strength and a 1% maximum loss of dry weight in accordance with ASTM C91/C91M and ASTM C67/C67M. Mortar performance is based on property specifications.

2.1.4 Grout

Non shrink grout for cast stone sculpture bedding and similar structural applications complies with ASTM C476 or ASTM C1107/C1107M. Grout is a non staining, non metallic, shrink resistant, premixed portland cement type achieving a three day compressive strength of 3,000 PSI.

2.1.5 Weathertight Sealant

Weathertight sealant for exterior applications is a silicone type complying with ASTM C920, Type S, Grade NS, Class 25, Use NT, M, G and A and ASTM C1184. Sealant is a one component, neutral cure, moisture curing sealant with exceptional movement capability resulting in highly flexible, durable and weather resistant seals.

2.1.6 Performance Coordination

Furnish fasteners, accessories and options as recommended by the manufacturer for the specific applications and substrates encountered within the work.

PART 3 EXECUTION

3.1 INSTALLATION

Set surface units using tiling techniques. Wet cast stone thoroughly with clean, potable water. Screw dowels into blind lugs. Drill and fill blind dowel holes with non shrink grout. Place cast stone sculptures in a 0.375 inch, full mortar bedding. Rake perimeter joints to create 0.375 inch pockets. Seal surface unit perimeters with weathertight sealant.

Keep adjacent surfaces damp for twenty-four hours to achieve the initial bedding set.

Remove mortar splashes and smears using a sponge and clean water.

3.2 MAINTENANCE AND CLEANING

Submit the recommended maintenance practices for each type of installation provided.

Clean sculptural cast stone with a fiber bristled brush, powdered soap and water. Rinse thoroughly with clean water. Do not use acid washes or chemical cleaners.

-- End of Section --

SECTION 05 12 00

STRUCTURAL STEEL
08/18, CHG 2: 05/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 303	(2016) Code of Standard Practice for Steel Buildings and Bridges
AISC 325	(2017) Steel Construction Manual
AISC 326	(2009) Detailing for Steel Construction
AISC 360	(2016) Specification for Structural Steel Buildings
AISC DESIGN GUIDE 10	(1997) Erection Bracing of Low-Rise Structural Steel Buildings

AMERICAN SOCIETY FOR NONDESTRUCTIVE TESTING (ASNT)

ANSI/ASNT CP-189	(2020) ASNT Standard for Qualification and Certification of Nondestructive Testing Personnel

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B46.1	(2020) Surface Texture, Surface Roughness, Waviness and Lay

AMERICAN WELDING SOCIETY (AWS)

AWS A2.4	(2012) Standard Symbols for Welding, Brazing and Nondestructive Examination
AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding Code - Steel
AWS QC1	(2016) Specification for AWS Certification of Welding Inspectors

ASTM INTERNATIONAL (ASTM)

ASTM A6/A6M	(2021) Standard Specification for General Requirements for Rolled Structural Steel Bars, Plates, Shapes, and Sheet Piling
ASTM A29/A29M	(2020) Standard Specification for General Requirements for Steel Bars, Carbon and

	Alloy, Hot-Wrought
ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A143/A143M	(2007; R 2020) Standard Practice for Safeguarding Against Embrittlement of Hot-Dip Galvanized Structural Steel Products and Procedure for Detecting Embrittlement
ASTM A307	(2023) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM A500/A500M	(2023) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A563	(2015) Standard Specification for Carbon and Alloy Steel Nuts
ASTM A780/A780M	(2020) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A992/A992M	(2020) Standard Specification for Structural Steel Shapes
ASTM B695	(2021) Standard Specification for Coatings of Zinc Mechanically Deposited on Iron and Steel
ASTM C827/C827M	(2016) Standard Test Method for Change in Height at Early Ages of Cylindrical Specimens of Cementitious Mixtures
ASTM C1107/C1107M	(2020) Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)
ASTM F436/F436M	(2019) Standard Specification for Hardened Steel Washers Inch and Metric Dimensions
ASTM F844	(2019) Standard Specification for Washers, Steel, Plain (Flat), Unhardened for General Use
ASTM F959/F959M	(2017a) Standard Specification for Compressible-Washer-Type Direct Tension Indicators for Use with Structural

	Fasteners, Inch and Metric Series
ASTM F1136/F1136M	(2011) Standard Specification for Zinc/Aluminum Corrosion Protective Coatings for Fasteners
ASTM F1554	(2020) Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength
ASTM F2329/F2329M	(2015) Standard Specification for Zinc Coating, Hot-Dip, Requirements for Application to Carbon and Alloy Steel Bolts, Screws, Washers, Nuts, and Special Threaded Fasteners
ASTM F2833	(2011; R 2017) Standard Specification for Corrosion Protective Fastener Coatings with Zinc Rich Base Coat and Aluminum Organic/Inorganic Type
ASTM F3125/F3125M	(2019) Standard Specification for High Strength Structural Bolts and Assemblies, Steel and Alloy Steel, Heat Treated, Inch Dimensions 120 ksi and 150 ksi Minimum Tensile Strength, and Metric Dimensions 830 MPa and 1040 MPa Minimum Tensile Strength

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC PA 1	(2016) Shop, Field, and Maintenance Coating of Metals
SSPC Paint 20	(2019) Zinc-Rich Primers (Type I, Inorganic, and Type II, Organic)
SSPC Paint 29	(2002; E 2004) Zinc Dust Sacrificial Primer, Performance-Based
SSPC SP 3	(2018) Power Tool Cleaning
SSPC SP 6/NACE No.3	(2007) Commercial Blast Cleaning

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-301-01	(2023; with Change 6, 2026) Structural Engineering

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR Part 1926, Subpart R	Steel Erection

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Erection and Erection Bracing Drawings; G

SD-02 Shop Drawings

Fabrication Drawings Including Details of Connections; G

SD-03 Product Data

Shop Primer

Welding Electrodes and Rods

Direct Tension Indicator Washers

Non-Shrink Grout

Tension Control Bolts

Recycled Content for Structural Steel; S

Recycled Content for Structural Steel Tubing; S

Recycled Content for Steel Pipe; S

SD-05 Design Data

Design Calculations for Steel Connections; G

SD-06 Test Reports

Class B Coating

Bolts, Nuts, and Washers

Weld Inspection Reports

Direct Tension Indicator Washer Inspection Reports

Bolt Testing Reports

Embrittlement Test Reports

SD-07 Certificates

Steel

Bolts, Nuts, and Washers

Galvanizing

Welding Procedures and Qualifications

Welding Electrodes and Rods

Certified Welding Inspector

NDT Technician

Welding Procedure Specifications (WPS)

1.3 QUALITY ASSURANCE

1.3.1 Preconstruction Submittals

1.3.1.1 Erection and Erection Bracing Drawings

Submit for record purposes. Indicate the sequence of erection, temporary shoring and bracing. The erection drawings must conform to AISC 303. Erection drawings must be reviewed, stamped and sealed by a registered professional engineer.

1.3.2 Fabrication Drawing Requirements

Submit fabrication drawings for approval prior to fabrication. Prepare in accordance with AISC 303, AISC 326 and AISC 325. Fabrication drawings must not be reproductions of contract drawings. Sign and seal fabrication drawings by a registered professional engineer. Include complete information for the fabrication and erection of the structure's components, including the location, type, and size of bolts, welds, member sizes and lengths, connection details, blocks, copes, and cuts. Use AWS A2.4 standard welding symbols. Clearly highlight any deviations from the details shown on the contract drawings highlighted on the fabrication drawings. Explain the reasons for any deviations from the contract drawings.

1.3.3 Delegated Connection Design

Design structural steel connection indicated in the contract documents per AISC 303, Option 3, using the connection loads indicated. Submit design calculations for steel connections signed and sealed by a registered professional engineer.

1.3.4 Certifications

1.3.4.1 Welding Procedures and Qualifications

Prior to welding, submit certification for each welder stating the type of welding and positions qualified for, the code and procedure qualified under, date qualified, and the firm and individual certifying the qualification tests. If the qualification date of the welder or welding operator is more than 6 months old, the welding operator's qualification certificate must be accompanied by a current certificate by the welder attesting to the fact that he has been engaged in welding since the date of certification, with no break in welding service greater than 6 months.

Conform to all requirements specified in AWS D1.1/D1.1M.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide the structural steel system, including shop primer galvanizing, complete and ready for use. Provide structural steel systems including

design, materials, installation, workmanship, fabrication, assembly, erection, inspection, quality control, and testing in accordance with AISC 303, AISC 360, and UFC 3-301-01 except as modified in this contract.

2.2 STEEL

2.2.1 Structural Steel

Wide flange and WT shapes, ASTM A992/A992M. Angles, Channels and Plates, ASTM A36/A36M. Provide structural steel containing a minimum of 80 percent recycled content. Submit data identifying percentage of recycled content for structural steel.

2.2.2 Structural Steel Tubing

ASTM A500/A500M, Grade C. Provide structural steel tubing containing a minimum of 25 percent recycled content. Submit data identifying percentage of recycled content for structural steel tubing.

2.2.3 Steel Pipe

ASTM A53/A53M, Type E or S, Grade B, weight class STD (Standard) or as indicated. Provide steel pipe containing a minimum of 50 percent recycled content. Submit data identifying percentage of recycled content for steel pipe.

2.3 BOLTS, NUTS, AND WASHERS

Submit the certified manufacturer's mill reports which clearly show the applicable ASTM mechanical and chemical requirements together with the actual test results for the supplied fasteners.

2.3.1 Common Grade Bolts

2.3.1.1 Bolts

ASTM A307, Grade A, plain finish mechanically deposited zinc coating. The bolt heads and the nuts of the supplied fasteners must be marked with the manufacturer's identification mark, the strength grade and type specified by ASTM specifications.

2.3.1.2 Nuts

ASTM A563, Grade A, heavy hex style.

2.3.1.3 Washers

ASTM F844.

2.3.2 High-Strength Bolts

High strength bolts and nuts must be shipped together in the same shipping container. Fasteners indicated to be galvanized shall be tested by the supplier to show that the galvanized nut with the supplied lubricant provided may be rotated from the snug tight condition well in excess of the rotation required for pretentioned installation without stripping. The supplier shall supply nuts that have been lubricated and tested with the supplied bolts.

2.3.2.1 Bolts

ASTM F3125/F3125M, Grade A325M A325 , Type 1 Heavy Hex Head Style, plain finish .

2.3.2.2 Nuts

ASTM A563, Grade and Style as specified in the applicable ASTM bolt standard.

2.3.2.3 Direct Tension Indicator Washers

ASTM F959/F959M. Submit product data for direct tension indicator washers.

2.3.2.4 Washers

ASTM F436/F436M, plain carbon steel.

2.3.3 Tension Control Bolts

ASTM F3125/F3125M, Grade F2280, Type 1, twistoff style assemblies consisting of steel structural bolts with splined ends, heavy-hex carbon steel nuts, and hardened carbon steel washers. Assembly finish must be plain. Submit product data for tension control bolts.

2.3.4 Foundation Anchorage

2.3.4.1 Anchor Rods

ASTM F1554 Gr 36 , Class 1A.

2.3.4.2 Anchor Nuts

ASTM A563, Grade A, hex style.

2.3.4.3 Anchor Washers

ASTM F844.

2.3.4.4 Anchor Plate Washers

ASTM A36/A36M.

2.4 STRUCTURAL STEEL ACCESSORIES

2.4.1 Welding Electrodes and Rods

AWS D1.1/D1.1M. Submit product data for welding electrodes and rods.

2.4.2 Non-Shrink Grout

ASTM C1107/C1107M, with no ASTM C827/C827M shrinkage. Grout must be nonmetallic. Submit product data for non-shrink grout.

2.4.3 Welded Shear Stud Connectors

ASTM A29/A29M, Grades 1010 through 1020. AWS D1.1/D1.1M, Table 7.1, Type B.

2.5 GALVANIZING

ASTM F2329/F2329M, ASTM F1136/F1136M, ASTM F2833 or ASTM B695 for threaded parts or ASTM A123/A123M for structural steel members, as applicable, unless specified otherwise galvanize after fabrication where practicable.

2.6 FABRICATION

Fabrication must be in accordance with the applicable provisions of AISC 325. Fabrication and assembly must be done in the shop to the greatest extent possible. Punch, subpunch and ream, or drill bolt holes perpendicular to the surface of the member.

Compression joints depending on contact bearing must have a surface roughness not in excess of 500 micro inch as determined by ASME B46.1, and ends must be square within the tolerances for milled ends specified in ASTM A6/A6M.

Shop splices of members between field splices will be permitted only where indicated on the Contract Drawings. Splices not indicated require the approval of the Contracting Officer.

2.6.1 Markings

Prior to erection, identify members by a painted erection mark. Connecting parts assembled in the shop for reaming holes in field connections must be match marked with scratch and notch marks. Do not locate erection markings on areas to be welded. Do not locate match markings in areas that will decrease member strength or cause stress concentrations.

2.6.2 Shop Primer

SSPC Paint 20 or SSPC Paint 29, (zinc rich primer). Shop prime structural steel, except as modified herein, in accordance with SSPC PA 1. Do not prime steel surfaces embedded in concrete, galvanized surfaces, surfaces to receive sprayed-on fireproofing, or surfaces within 0.5 inch of the toe of the welds prior to welding (except surfaces on which metal decking and shear studs are to be welded). If flash rusting occurs, re-clean the surface prior to application of primer. Apply primer to a minimum dry film thickness of 2.0 mil. Submit shop primer product data.

Prime slip critical surfaces with a Class B coating in accordance with AISC 325. Submit test report for Class B coating.

Prior to assembly, prime surfaces which will be concealed or inaccessible after assembly. Do not apply primer in foggy or rainy weather; when the ambient temperature is below 45 degrees F or over 95 degrees F; or when the primer may be exposed to temperatures below 40 degrees F within 48 hours after application, unless approved otherwise by the Contracting Officer. Repair damaged primed surfaces with an additional coat of primer.

2.6.2.1 Cleaning

SSPC SP 6/NACE No.3, except steel exposed in spaces above ceilings, attic spaces, furred spaces, and chases that will be hidden to view in finished construction may be cleaned to SSPC SP 3 when recommended by the shop primer manufacturer. Maintain steel surfaces free from rust, dirt, oil, grease, and other contaminants through final assembly.

2.7 DRAINAGE HOLES

Drill adequate drainage holes to eliminate water traps. Hole diameter must be 1/2 inch and location indicated on the detail drawings. Hole size and locations must not affect the structural integrity.

PART 3 EXECUTION

3.1 ERECTION

a. Erection of structural steel, except as indicated in item b. below, must be in accordance with the applicable provisions of AISC 325, AISC 303 and 29 CFR Part 1926, Subpart R.

b. For low-rise structural steel buildings (60 feet tall or less and a maximum of 2 stories), erect the structure in accordance with AISC DESIGN GUIDE 10.

After final positioning of steel members, provide full bearing under base plates and bearing plates using nonshrink grout. Place nonshrink grout in accordance with the manufacturer's instructions.

3.1.1 STORAGE

Store the material out of contact with the ground in such manner and location as to minimize deterioration.

3.2 CONNECTIONS

Except as modified in this section, design connections indicated in accordance with AISC 360. Build connections into existing work. Do not tighten anchor bolts set in concrete with impact torque wrenches. Holes must not be cut or enlarged by burning. Bolts, nuts, and washers must be clean of dirt and rust, and lubricated immediately prior to installation.

3.2.1 Common Grade Bolts

Tighten ASTM A307 bolts to a "snug tight" fit. "Snug tight" is the tightness that exists when plies in a joint are in firm contact. If firm contact of joint plies cannot be obtained with a few impacts of an impact wrench, or the full effort of a man using a spud wrench, contact the Contracting Officer for further instructions.

3.2.2 High-Strength Bolts

Provide direct tension indicator washers in all ASTM F3125/F3125M, Grade A325 and Grade A490 bolted connections. Bolts must be installed in connection holes and initially brought to a snug tight fit. After the initial tightening procedure, fully tension bolts, progressing from the most rigid part of a connection to the free edges.

Fastener components shall be protected from dirt and moisture in closed containers at the site of the installation. Fastener components that are not incorporated into the work shall be returned to protected storage at the end of the work shift.

3.2.2.1 Installation of Direct Tension Indicator Washers (DTIW)

Where possible, install the DTIW under the bolt head and tighten the nut.

If the DTIW is installed adjacent to the turned element, provide a flat washer between the DTIW and nut when the nut is turned for tightening, and between the DTIW and bolt head when the bolt head is turned for tightening. In addition to the LIW, provide flat washers under both the bolt head and nut when ASTM F3125/F3125M, Grade A490 bolts are used.

3.2.3 Tension Control Bolts

Bolts must be installed in connection holes and initially brought to a snug tight fit. After the initial tightening procedure, fully tension bolts, progressing from the most rigid part of a connection to the free edges.

3.3 GAS CUTTING

Use of gas-cutting torch in the field for correcting fabrication errors is not permitted on any major member in the structural framing. Use of a gas cutting torch will be permitted on minor members not under stress only after approval has been obtained from the Contracting Officer.

3.4 WELDING

Welding must be in accordance with AWS D1.1/D1.1M. Provide AWS D1.1/D1.1M qualified welders, welding operators, and tackers.

Develop and submit the Welding Procedure Specifications (WPS) for all welding, including welding done using prequalified procedures. Submit for approval all WPS, whether prequalified or qualified by testing.

3.4.1 Removal of Temporary Welds, Run-Off Plates, and Backing Strips

Remove only from finished areas. Remove backing strips from bottom flange of moment connections, backgouge the root pass to sound weld metal and reinforce with a 5/16 inch fillet weld minimum.

3.5 SHOP PRIMER REPAIR

Repair shop primer in accordance with the paint manufacturer's recommendation for surfaces damaged by handling, transporting, cutting, welding, or bolting.

3.5.1 Field Priming

Field prime steel exposed to the weather, or located in building areas without HVAC for control of relative humidity. After erection, the field bolt heads and nuts, field welds, and any abrasions in the shop coat must be cleaned and primed with paint of the same quality as that used for the shop coat.

3.6 GALVANIZING REPAIR

Repair damage to galvanized coatings using ASTM A780/A780M zinc rich paint for galvanizing damaged by handling, transporting, cutting, welding, or bolting. Do not heat surfaces to which repair paint has been applied.

3.7 FIELD QUALITY CONTROL

Perform field tests, and provide labor, equipment, and incidentals required for testing. Notify the Contracting Officer in writing of

defective welds, bolts, nuts, and washers within 7 working days of the date of the inspection.

3.7.1 Welds

3.7.1.1 Visual Inspection

AWS D1.1/D1.1M. Furnish the services of AWS-certified welding inspectors for fabrication and erection inspection and testing and verification inspections. A Certified Welding Inspector must perform visual inspection on 100 percent of all welds. Document this inspection in the Visual Weld Inspection Log. Submit certificates indicating that certified welding inspectors meet the requirements of AWS QC1.

3.7.1.2 Nondestructive Testing

Nondestructive testing must be in accordance with AWS D1.1/D1.1M. Ultrasonic testing must be performed in accordance with Table 6.2 of AWS D1.1/D1.1M. Test locations must be selected by the Contracting Officer. All personnel performing NDT must be certified in accordance with ANSI/ASNT CP-189 in the method of testing being performed. Submit certificates showing compliance with ANSI/ASNT CP-189 for all NDT technicians. If more than 20 percent of welds made by a welder contain defects identified by testing, then all groove welds made by that welder must be tested by ultrasonic testing, and all fillet welds made by that welder must be inspected by magnetic particle testing (MT) or dye penetrant testing (PT) as approved by the Contracting Officer. When groove welds made by an individual welder are required to be tested, magnetic particle or dye penetrant testing may be used only in areas inaccessible to ultrasonic testing. Retest all repaired areas. Submit weld inspection reports.

Testing frequency: Provide the following types and number of tests:

Test Type	Number of Tests
Ultrasonic	100 percent of CJP Welds

3.7.2 Direct Tension Indicator Washers

3.7.2.1 Direct Tension Indicator Washer Compression

Test direct tension indicator washers in place to verify that they have been compressed sufficiently to provide the 0.015 inch gap, as required by ASTM F959/F959M. Submit direct tension indicator washer inspection reports.

3.7.3 High-Strength Bolts

3.7.3.1 Testing Bolt, Nut, and Washer Assemblies

Test a minimum of 3 bolt, nut, and washer assemblies from each mill certificate batch in a tension measuring device at the job site prior to the beginning of bolting start-up. Demonstrate that the bolts and nuts, when used together, can develop tension not less than the provisions specified in AISC 360, depending on bolt size and grade. The bolt tension must be developed by tightening the nut. A representative of the manufacturer or supplier must be present to ensure that the fasteners are properly used, and to demonstrate that the fastener assemblies supplied

satisfy the specified requirements. Submit bolt testing reports.

3.7.3.2 Inspection

Inspection procedures must be in accordance with AISC 360. Confirm and report to the Contracting Officer that the materials meet the project specification and that they are properly stored. Confirm that the faying surfaces have been properly prepared before the connections are assembled. Observe the specified job site testing and calibration, and confirm that the procedure to be used provides the required tension. Monitor the work to ensure the testing procedures are routinely followed on joints that are specified to be fully tensioned.

3.7.3.3 Testing

The Government has the option to perform nondestructive tests on 5 percent of the installed bolts to verify compliance with pre-load bolt tension requirements. Provide the required access for the Government to perform the tests. The nondestructive testing will be done in-place using an ultrasonic measuring device or any other device capable of determining in-place pre-load bolt tension. The test locations must be selected by the Contracting Officer. If more than 10 percent of the bolts tested contain defects identified by testing, then all bolts used from the batch from which the tested bolts were taken, must be tested at the Contractor's expense. Retest new bolts after installation at the Contractor's expense.

3.7.4 Testing for Embrittlement

ASTM A143/A143M for steel products hot-dip galvanized after fabrication. Submit embrittlement test reports.

3.7.5 Inspection and Testing of Steel Stud Welding

Perform verification inspection and testing of steel stud welding conforming to the requirements of AWS D1.1/D1.1M, Stud Welding Clause. The Contracting Officer will serve as the verification inspector. Bend test studs that do not show a full 360 degree weld flash or have been repaired by welding as required by AWS D1.1/D1.1M, Stud Welding Clause. Studs that crack under testing in the weld, base metal or shank will be rejected and replaced by the Contractor at no additional cost.

-- End of Section --

SECTION 05 21 00

STEEL JOIST FRAMING
05/15, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding Code - Steel

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2024) International Building Code

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC PA 1	(2016) Shop, Field, and Maintenance Coating of Metals
SSPC Paint 15	(1999; E 2004) Steel Joist Shop Primer/Metal Building Primer
SSPC SP 2	(2018) Hand Tool Cleaning

STEEL JOIST INSTITUTE (SJI)

SJI LOAD TABLES	(2020) Standard Specifications Load Tables and Weight Tables for Steel Joists and Joist Girders - 45th Edition

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926	Safety and Health Regulations for Construction
29 CFR 1926.757	Steel Erection; Open Web Steel Joists

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Welder Qualification

SD-02 Shop Drawings

Steel Joist Framing; G

SD-03 Product Data

Recycled Content Of Steel Products; S

SD-05 Design Data

Design Calculations; G

SD-06 Test Reports

Erection Inspection

Welding Inspections

SD-07 Certificates

Certification of Compliance

1.3 QUALITY ASSURANCE

Perform all work in compliance with the requirements set forth in 29 CFR 1926.

1.3.1 Drawing Requirements

Submit drawings of steel joist framing including fabrication, specifications for shop painting, and identification markings of joists . Show joist type and size, layout in plan, all applicable loads, deflection criteria, and erection details including methods of anchoring, framing at openings, type, size, and location and connections for and spacing of bridging, requirements for field welding, and details of accessories as applicable. Show profiles for nonstandard joist configurations.

1.3.2 Certification of Compliance

Prior to construction commencement, submit certification for welder qualification, in compliance with AWS D1.1/D1.1M, welding operation, and tacker, stating the type of welding and positions qualified for, the code and procedure qualified under, date qualified, and the firm and individual certifying the qualification tests. Submit certification of compliance for the following:

a. Steel Joist Institute Member Fabricator

b. 29 CFR 1926

c. 29 CFR 1926.757

d. Statement from steel joist manufacturer, that work was performed in accordance with approved construction documents and with SJI standard specifications, in accordance with ICC IBC Section 1704.2.5.2.

1.4 DELIVERY, STORAGE, AND HANDLING

Handle, transport, and store joists in a manner to prevent damage affecting their structural integrity. Verify piece count of all joist products upon delivery and inspect all joists products for damage. Report any damage to the joist supplier. Store all items off the ground in a well drained location protected from the weather and easily accessible for inspection and handling. Store joists with top chord down and with joists in a vertical position. Store deep joists horizontally if they were shipped on their sides.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Designate steel joists on the drawings in accordance with the standard designations of the Steel Joist Institute. Joists of other standard designations or joists with properties other than those shown may be substituted for the joists designated provided the structural properties are equal to or greater than those of the joists shown and provided all other specified requirements are met.

2.2 STEEL JOISTS

Provide steel joists conforming to SJI LOAD TABLES. Design joists designated K, KCS, LH and DLH to support the loads given in the applicable standard load tables of SJI LOAD TABLES. Submit design calculations for special steel joists, net uplift loads, non-SJI standard details, and field splices. Include cover letter signed and sealed by the joist manufacturer's registered design professional.

2.2.1 Steel Joist Camber

Camber joists according to SJI LOAD TABLES.

2.2.2 Special Steel Joists

Provide special joists and connections capable of withstanding the design loads indicated with a live-load deflection less than L/360 for roof joists and L/360 for floor joists.

2.2.3 Steel Joist Substitutes and Outriggers

Provide joist substitutes and outriggers conforming to SJI LOAD TABLES with steel angle or channel members.

2.3 RECYCLED CONTENT

Provide products with an average recycled content of steel products of postconsumer recycled content plus one half of preconsumer recycled content not less than 25 percent.

2.4 ACCESSORIES AND FITTINGS

2.4.1 Bridging

Provide bridging of material, size, and type required by SJI LOAD TABLES for type of joist, chord size, spacing and span. Furnish additional erection bridging if required for stability.

2.4.2 Bearing Plates

Fabricate steel bearing plats from ASTM A36/A36M steel of size and thickness indicated.

2.4.3 Ceiling Extensions

Furnish ceiling extensions, either bottom-chord elements or a separate extension unit of enough strength to support ceiling construction. Extend ends to within 1/2 inch of finished wall surface unless otherwise indicated.

2.5 SHOP PAINTING

SSPC Paint 15. Shop prime joists, except as modified herein, in accordance with SSPC PA 1. Clean joists in accordance with SSPC SP 2 before priming. If flash rusting occurs, re-clean the surface prior to application of primer. For joists which require finish painting under Section 09 90 00 PAINTS AND COATINGS, the primer paint must be compatible with the finish paint.

PART 3 EXECUTION

3.1 ERECTION

Install joists in conformance with SJI LOAD TABLES for the joist series indicated, and the requirements of 29 CFR 1926 and 29 CFR 1926.757. Handle and set joists avoiding damage to the members. Place the "tag end" of joists as shown on the joists placement plans. Ensure that square-end joists are erected right side up. Distribute temporary loads so that joist capacity is not exceeded. Remove damaged joists from the site, except when field repair is approved and such repairs are satisfactorily made in accordance with the manufacturer's recommendations. Do not repair, field modify, or alter any joists without specific written instructions from the Designer of Record and/or joist manufacturer.

Install and connect bridging concurrently with joist erection, before construction loads are applied. Do not apply loads to bridging. Anchor ends of bridging lines at top and bottom chords if terminating at walls or beams. Do not cut away vertical leg of bridging where bridging makes an elevation transition; weld a separate piece of bridging at the transition. Perform all welding in accordance with AWS D1.1/D1.1M.

3.2 BEARING PLATES

Provide bearing plates to accept full bearing after the supporting members have been plumbed and properly positioned, but prior to placing superimposed loads. The area under the plate must be damp-packed solidly with bedding mortar, except where nonshrink grout is indicated on the drawings. Provide bedding mortar and grout as specified in Section 03 30 00 CAST-IN-PLACE CONCRETE.

3.3 PAINTING

3.3.1 Touch-Up Painting

After erection of joists , touch-up connections and areas of abraded shop coat with paint of the same type used for the shop coat.

3.3.2 Field Painting

Paint joists requiring a finish coat in conformance with the requirements of Section 09 90 00 PAINTS AND COATINGS.

3.4 VISUAL INSPECTIONS

Perform the following visual inspections:

a. Verify that all joists are spaced properly.

b. Verify that there is sufficient joist bearing on steel beams, concrete, and masonry.

c. Verify all bridging lines are properly spaced and anchored.

d. Verify that damage has not occurred to the joists during erection.

e. Verify the joists are aligned vertically and there is no lateral sweep in the joists.

f. Where concentrated loads are present on the joists verify that they are located in accordance with the joists placement plan.

g. Verify welding of bridging and joist seats in accordance with AWS D1.1/D1.1M, Section 6. Perform erection inspection and field welding inspections with AWS certified welding inspectors.

h. Verify proper bolting of diagonal bridging and joist seats where the bolts are snug-tight.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 05 30 00

STEEL DECKS
05/15, CHG 2: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI D100	(2017) Cold-Formed Steel Design Manual

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding Code - Steel
AWS D1.3/D1.3M	(2018) Structural Welding Code - Sheet Steel

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A780/A780M	(2020) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A792/A792M	(2025a) Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process
ASTM A1008/A1008M	(2021a) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM D746	(2014) Standard Test Method for Brittleness Temperature of Plastics and Elastomers by Impact
ASTM D1056	(2020) Standard Specification for Flexible

	Cellular Materials - Sponge or Expanded Rubber
ASTM D1149	(2007; R 2012) Standard Test Method for Rubber Deterioration - Surface Ozone Cracking in a Chamber
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/
FM DS 1-28R	(1998) Data Sheet: Roof Systems

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC Paint 20	(2019) Zinc-Rich Primers (Type I, Inorganic, and Type II, Organic)

STEEL DECK INSTITUTE (SDI)

ANSI/SDI C	(2017) Standard for Composite Steel Floor Deck - Slabs
ANSI/SDI NC	(2017) Standard for Non-Composite Steel Floor Deck
ANSI/SDI QA/QC	(2017) Standard for Quality Control and Quality Assurance for Installation of Steel Deck
SDI DDM04	(2015; Errata 1-3 2016; Add 1 2015; Add 2 20162006) Diaphragm Design Manual; 4th Edition
SDI DDP	(1987; R 2000) Deck Damage and Penetrations
SDI MOC3	(2016) Manual of Construction with Steel Deck (3rd Edition)

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-301-01	(2023; with Change 6, 2026) Structural Engineering

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926	Safety and Health Regulations for Construction

UL SOLUTIONS (UL)

UL 580	(2006; Reprint Apr 2024) UL Standard for Safety Tests for Uplift Resistance of Roof Assemblies

UL Fire Resistance (2014) Fire Resistance Directory

1.2 SUBMITTALS

Government approval is required for submittals. with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fabrication Drawings; G

SD-03 Product Data

Accessories

Deck Units

Galvanizing Repair Paint
Mechanical Fasteners
Touch-Up Paint

Welding Equipment

Welding Rods and Accessories

Recycled Content of Steel Products; S

SD-04 Samples

Metal Roof Deck Units

Flexible Closure Strips

SD-05 Design Data

Deck Units; G

SD-07 Certificates

Powder-Actuated Tool Operator

Welder Qualifications

Welding Procedures

Fire Safety

Wind Storm Resistance

Manufacturer's Certificate

1.3 QUALITY ASSURANCE

1.3.1 Deck Units

Furnish deck units and accessory products from a manufacturer regularly engaged in manufacture of steel decking. Provide manufacturer's certificates attesting that the decking material meets the specified requirements.

1.3.2 Certification of Powder-Actuated Tool Operator

Provide manufacturer's certificate attesting that the operators are authorized to use the low velocity powder-actuated tool.

1.3.3 Qualifications for Welding Work

Follow Welding Procedures of AWS D1.3/D1.3M for sheet steel and AWS D1.1/D1.1M for stud welding.
Submit qualified Welder Qualifications in accordance with AWS D1.3/D1.3M for sheet steel and AWS D1.1/D1.1M for stud welding, or under an equivalent approved qualification test. Perform tests on test pieces in positions and with clearances equivalent to those actually encountered. If a test weld fails to meet requirements, perform an immediate retest of two test welds until each test weld passes. Failure in the immediate retest will require the welder be retested after further practice or training, performing a complete set of test welds.

Submit manufacturer's catalog data for Welding Equipment and Welding Rods and Accessories.

1.3.4 Regulatory Requirements

1.3.4.1 Fire Safety

Test roof deck as a part of a roof deck construction assembly of the type used for this project, listing as fire classified in the UL Fire Resistance, or listing as Class I construction in the FM APP GUIDE, and so labeled.

1.3.4.2 Wind Storm Resistance

Provide roof construction assembly capable of withstanding a nominal uplift pressure of 60 pounds per square foot when tested in accordance with the uplift pressure test described in the FM DS 1-28R or as described in UL 580 and in general compliance with UFC 3-301-01.

1.3.5 Fabrication Drawings

Show type and location of units, location and sequence of connections, bearing on supports, methods of anchoring, attachment of accessories, adjusting plate details, cant strips, ridge and valley plates, metal closure strips, size and location of holes to be cut and reinforcement to be provided, the manufacturer's erection instructions and other pertinent details.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver deck units to the site in a dry and undamaged condition. Store and handle steel deck in a manner to protect it from corrosion, deformation, and other types of damage. Do not use decking for storage or

as working platform until units have been fastened into position. Exercise care not to damage material or overload decking during construction. The maximum uniform distributed storage load must not exceed the design live load. Stack decking on platforms or pallets and cover with weathertight ventilated covering. Elevate one end during storage to provide drainage. Maintain deck finish at all times to prevent formation of rust. Repair deck finish using touch-up paint. Replace damaged material.

1.5 DESIGN REQUIREMENTS FOR ROOF DECKS

1.5.1 Properties of Sections

Properties of metal roof deck sections must comply with engineering design width as limited by the provisions of AISI D100.

1.5.2 Allowable Loads

Indicate total uniform dead and live load for detailing purposes.

PART 2 PRODUCTS

2.1 DECK UNITS

Submit manufacturer's design calculations, or applicable published literature for the structural properties of the proposed deck units.

Provide products with an average recycled content of steel products so postconsumer recycled content plus one half of preconsumer recycled content not less than 25 percent.

2.1.1 Roof Deck

Conform to ASTM A792/A792M or ASTM A1008/A1008M for deck used in conjunction with insulation and built-up roofing. Fabricate roof deck units of the steel design thickness required by the design drawings and galvanized . Furnish sample of Metal Roof Deck Units used to illustrate actual cross section dimensions and configurations.

2.1.2 Composite Deck

Conform to ASTM A653/A653M or ASTM A1008/A1008M for composite deck assembly. Fabricate deck used as the tension reinforcing in composite deck of the steel design thickness required by the design drawings. Zinc-coat in conformance with ASTM A653/A653M, G60 coating class.

2.1.3 Length of Deck Units

Provide deck units of sufficient length to span three or more spacings where possible.

2.1.4 Touch-Up Paint

Provide a high zinc-dust content paint for regalvanizing welds in galvanized steel conforming to ASTM A780/A780M.

Provide touch-up paint for shop-painted units of the same type used for the shop painting , and touch-up paint for zinc-coated units of an approved galvanizing repair paint with a high-zinc dust content .

Touch-up welds with paint conforming to SSPC Paint 20 in accordance with ASTM A780/A780M. Maintain finish of deck units and accessories by using touch-up paint whenever necessary to prevent the formation of rust.

2.2 ACCESSORIES

Provide accessories of same material as deck, unless specified otherwise. Provide manufacturer's standard type accessories, as specified.

2.2.1 Adjusting Plates

Provide adjusting plates, or segments of deck units, of same thickness and configuration as deck units in locations too narrow to accommodate full size units. Provide factory cut plates of predetermined size where possible.

2.2.2 End Closures

Fabricated of sheet metal by the deck manufacturer. Provide end closures minimum 0.0295 inch thick to close open ends at parapets, end walls, eaves, and openings through deck.

2.2.3 Partition Closures

Provide closures for closing voids above interior walls and partitions that are perpendicular to the direction of the configurations. Provide rubber, plastic, or sheet steel closures above typical partitions.

2.2.4 Flexible Closure Strips for Roof Decks

Provide strips made of vulcanized, closed-cell, synthetic rubber material specified and premolded to the configuration required to provide tight-fitting closures at open ends and sides of steel roof decking.

Conforming to ASTM D1056, Grade 2A1, with the following additional properties:

Brittleness temperature of minus 40 degrees F when tested in accordance with ASTM D746.

Flammability resistance with a flame spread rating of less than 25 when tested in accordance with ASTM E84.

Resistance to ozone must be "no cracks" after exposure of a sample kept under a surface tensile strain of 25 percent to an ozone concentration of 100 parts per million of air by volume in air for 100 hours at 104 degrees F and tested in accordance with ASTM D1149.

Provide a elastomeric type adhesive as recommended by the manufacturer of the flexible closure strips.

2.2.5 Closure Plates for Composite Deck

Support and retain concrete at each floor level. Provide edge closures at all edges of the slab of sufficient strength and stiffness to support the wet concrete. Provide metal closures for all openings in composite steel deck 1/4 inch and over.

2.2.6 Sheet Metal Collar

Where deck is cut for passage of pipes, ducts, columns, etc., and deck is to remain exposed, provide a neatly cut sheet metal collar to cover edges of deck. Do not cut deck until after installation of supplemental supports.

2.2.7 Cover Plates

Sheet metal to close panel edge and end conditions, and where panels change direction or butt. Polyethylene-coated, self-adhesive, 2 inch wide joint tape may be provided in lieu of cover plates on flat-surfaced decking butt joints.

Fabricate cover plates for abutting floor deck units from the specified structural-quality steel sheets not less than nominal 18 gagethick before galvanizing. Provide 6 inch wide cover plates and form to match the contour of the floor deck units.

2.2.8 Access Hole Covers

Sheet metal, minimum 0.0474 inch thick.

2.2.9 Hanger

Provide clips or loops for utility systems of one or more of the following types:

a. Lip tabs or integral tabs where noncellular decking or flat plate of cellular section is 0.0474 inch thick or more, and a structural concrete fill is used over deck.

b. Slots or holes punched in decking for installation of pigtails.

c. Tabs driven from top side of decking and arranged so as not to pierce electrical cells.

d. Decking manufacturer's standard as approved by the Contracting Officer.

2.2.10 Cant Strips for Roof Decks

Fabricate cant strips from the specified commercial-quality steel sheets not less than nominal 0.0358 inch thick before galvanizing. Bend strips to form a 45-degree cant not less than 5 inch wide, with top and bottom flanges a minimum 3 inch wide. Length of strips 10 feet.

2.2.11 Ridge and Valley Plates for Roof Decks

Fabricate plates from the specified structural-quality steel sheets, not less than nominal 0.0358 inch thick before galvanizing. Provide plates of minimum 4-1/2 inch wide and bent to provide tight fitting closures at ridges and valleys. Provide a minimum length of ridge and valley plates of 10 feet.

2.2.12 Metal Closure Strips for Roof Decks

Fabricate strips from the specified commercial-quality steel sheets not less than nominal 0.0358 inch thick before galvanizing. Provide strips from the configuration required to provide tight-fitting closures at open

ends and sides of steel roof decking.

2.2.13 Galvanized Steel Angles for Roof Decks

Provide hot-rolled carbon steel angles conforming to ASTM A36/A36M, and hot-dip galvanized in accordance with ASTM A123/A123M.

2.2.14 Mechanical Fasteners

Provide mechanical fasteners, such as powder actuated fasteners, pneumatically driven fasteners or self-drilling screws, for anchoring the deck to structural supports and adjoining units that are designed to meet the loads indicated.

2.2.15 Miscellaneous Accessories

Furnish the manufacturer's standard accessories to complete the deck installation. Furnish metal accessories of the same material as the deck and with the minimum design thickness as follows: saddles, 0.0474 inch welding washers, 0.0598 inch other metal accessories, 0.0358 inch unless otherwise indicated.

PART 3 EXECUTION

3.1 EXAMINATION

Prior to installation of decking units and accessories, examine worksite to verify that as-built structure will permit installation of decking system without modification.

3.2 INSTALLATION

Install steel deck units in accordance with 29 CFR 1926, Subpart R – Steel Erection, ANSI/SDI QA/QC, and approved shop drawings. Place units on structural supports, properly adjusted, leveled, and aligned at right angles to supports before permanently securing in place. Damaged deck and accessories including material which is permanently stained or contaminated, deformed, or with burned holes shall not be installed. Extend deck units over three or more supports unless absolutely impractical. Report inaccuracies in alignment or leveling to the Contracting Officer and make necessary corrections before permanently anchoring deck units. Locate deck ends over supports only. Lap 2 inch deck ends. Do not use unanchored deck units as a work or storage platform. Permanently anchor units placed by the end of each working day. Do not support suspended ceilings, light fixtures, ducts, utilities, or other loads by steel deck unless indicated. Distribute loads by appropriate means to prevent damage.

3.2.1 Attachment

Immediately after placement and alignment, and after correcting inaccuracies, permanently fasten steel deck units to structural supports and to adjacent deck units by welding with normal 5/8 inchdiameter puddle welds, as indicated on the design drawings and in accordance with manufacturer's recommended procedure. Clamp or weight deck units to provide firm contact between deck units and structural supports while performing welding . Attachment of adjacent deck units by button-punching is prohibited.

3.2.1.1 Welding

Perform welding in accordance with AWS D1.3/D1.3M using methods and electrodes recommended by the manufacturers of the base metal alloys being used. Ensure only operators previously qualified by tests prescribed in AWS D1.3/D1.3M make welds. Immediately recertify, or replace qualified welders, that are producing unsatisfactory welding. Conform to the recommendations of the Steel Deck Institute and the steel deck manufacturer for location, size, and spacing of fastening. Do use welding washers at the connections of the deck to supports. Do not use welding washers at sidelaps. Holes and similar defects will not be acceptable. Attach all partial or segments of deck units to structural supports in accordance with Section 2.5 of SDI DDM04. . Immediately clean welds by chipping and wire brushing. Heavily coat welds, cut edges and damaged portions of coated finish with zinc-dust paint conforming to ASTM A780/A780M .

3.2.1.2 Sidelap Fastening

Lock sidelaps between adjacent floor deck units together by welding or screws as indicated.

3.2.2 Openings

Cut or drill all holes and openings required and be coordinated with the drawings, specifications, and other trades. Frame and reinforce openings through the deck in conformance with SDI DDP. Reinforce holes and openings 6 to 12 inch across by 0.0474 inch thick steel sheet at least 12 inch wider and longer than the opening and be fastened to the steel deck at each corner of the sheet and at a maximum of 6 inch on center. Reinforce holes and openings larger than 12 inch by steel channels or angles installed perpendicular to the steel joists and supported by the adjacent steel joists. Install steel channels or angles perpendicular to the deck ribs and fasten to the channels or angles perpendicular to the steel joists. Deck manufacturer shall approve holes or openings larger than 6 inch in diameter prior to drilling or cutting.

3.2.3 Deck Damage

SDI MOC3, for repair of deck damage.

3.2.4 Touch-Up Paint

3.2.4.1 Roof Deck

After roof decking installation, wire brush, clean, and touchup paint the scarred areas on top and bottom surfaces of metal roof decking. The scarred areas include welds, weld scars, bruises, and rust spots. Touchup galvanized surfaces with galvanizing repair paint. Touchup painted surfaces with repair paint of painted surfaces.

3.2.4.2 Floor Deck

For floor decking installation, wire brush, clean, and touchup paint the scarred areas on the top and bottom surfaces of the metal floor decking and on the surface of supporting steel members. Include welds, weld scars, bruises, and rust spots for scarred areas. Touched up the galvanized surfaces with galvanizing repair paint. Touch up the painted surfaces with paint for the repair of painted surfaces.

3.2.5 Accessory Installation

3.2.5.1 Adjusting Plates

Provide in locations too narrow to accommodate full-size deck units and install as shown on shop drawings.

3.2.5.2 End Closures

Provide end closure to close open ends of cells at columns, walls, and openings in deck.

3.2.5.3 Closures Above Partitions

Provide for closing voids between cells over partitions that are perpendicular to direction of cells. Provide a one-piece closure strip for partitions 4 inch nominal or less in thickness and two-piece closure strips for wider partitions.

3.2.5.4 Cover Plates

Provide metal cover plates, or joint tape, at joints between cellular decking sheets to be used as electrical raceways.

3.2.5.5 Access Hole Covers

Provide access hole covers to seal holes cut in decking to facilitate welding of the deck to structural supports.

3.2.5.6 Hangers

Provide as indicated to support utility system . Space devices as indicated .

3.2.6 Concrete Work

Prior to placement of concrete, inspect installed decking to ensure that there has been no permanent deflection or other damage to decking. Replace decking which has been damaged or permanently deflected as approved by the Contracting Officer. Place concrete on metal deck in accordance with Construction Practice of ANSI/SDI C or ANSI/SDI NC.3.2.7 Preparation of Fire-Proofed Surfaces

Provide deck surfaces, both composite and noncomposite, which are to receive sprayed-on fireproofing, galvanized and free of all grease, mill oil, paraffin, dirt, salt, and other contaminants which impair adhesion of the fireproofing. Complete any required cleaning prior to steel deck installation using a cleaning method that is compatible with the sprayed-on fireproofing.

3.3 ROOF SUMP PANS

Place sump pans over openings in roof decking and fusion welded to top surface of roof decking. Do not exceed spacing of welds of 12 inch with not less than one weld at each corner. Field cut opening in the bottom of each roof sump pan to receive the roof drain as part of the work of this section.

3.4 CANT STRIPS FOR ROOF DECKS

Provide strips to be fusion welded to surface of roof decking, secured to wood nailers by galvanized screws or to steel framing by galvanized self-tapping screws or welds. Do not exceed spacing of welds and fasteners of 12 inch. Lap end joints a minimum 3 inch and secure with galvanized sheet metal screws spaced a maximum 4 inch on center.

3.5 RIDGE AND VALLEY PLATES FOR ROOF DECKS

Provide plates to be fusion welded to top surface of roof decking. Lap end joints a minimum 3 inch. For valley plates, provide endlaps to be in the direction of water flow.

3.6 CLOSURE STRIPS FOR ROOF DECKS

Provide closure strips at open, uncovered ends and edges of the roof decking and in voids between roof decking and top of walls and partitions where indicated. Install closure strips in position in a manner to provide a weathertight installation.

3.7 ROOF INSULATION SUPPORT FOR ROOF DECKS

Provide metal closure strips for support of roof insulation where rib openings in top surface of metal roof decking occur adjacent to edges and openings. Weld metal closure strips in position.

3.8 CLEANING AND PROTECTION FOR ROOF DECKS

Upon completion of the deck, sweep surfaces clean and prepare for installation of the roofing.

3.9 FIELD QUALITY CONTROL

3.9.1 Deck Weld Inspection

Visual inspect welds in accordance with AWS D1.3/D1.3M.

3.9.2 Decks Not Receiving Concrete

Inspect the decking top surface for distortion after installation. For roof decks not receiving concrete, verify distortion by placing a straight edge across three adjacent top flanges. The maximum allowable gap between the straight edge and the top flanges should not exceed manufacturing and construction tolerances of supporting members. When gap is more than the allowable, provide corrective measures or replacement. Reinspect decking after performing corrective measures or replacement.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 05 40 00

COLD-FORMED METAL FRAMING
05/15, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 318	(2014; Errata 1-2 2014; Errata 3-5 2015; Errata 6 2016; Errata 7-9 2017) Building Code Requirements for Structural Concrete (ACI 318-14) and Commentary (ACI 318R-14)

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI S100	(2012) North American Specification for the Design of Cold-Formed Steel Structural Members
AISI S110	(2007; Suppl 1; Reaffirmed 2012) Standard for Seismic Design of Cold-Formed Steel Structural Systems - Special Bolted Moment Frames
AISI S200	(2007) North American Standard for Cold-Formed Steel Framing - General Provision
AISI S201	(2007) North American Standard for Cold-Formed Steel Framing - Product Data
AISI S202	(2011) Code of Standard Practice for Cold-formed Steel Structural Framing
AISI S211	(2007) North American Standard for Cold-Formed Steel Framing - Wall Stud Design
AISI S212	(2007) North American Standard for Cold-Formed Steel Framing - Header Design
AISI S213	(2007; Suppl 1 2009) North American Standard for Cold-Formed Steel Framing - Lateral Design
AISI S214	(2012) North American Standard for Cold-Formed Steel Framing – Truss Design

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding

Code - Steel

AWS D1.3/D1.3M (2018) Structural Welding Code - Sheet Steel

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M (2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM A153/A153M (2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware

ASTM A307 (2023) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength

ASTM A370 (2021) Standard Test Methods and Definitions for Mechanical Testing of Steel Products

ASTM A653/A653M (2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process

ASTM A1003/A1003M (2015) Standard Specification for Steel Sheet, Carbon, Metallic- and Nonmetallic-Coated for Cold-Formed Framing Members

ASTM C955 (2017) Standard Specification for Cold-Formed Steel Structural Framing Members

ASTM C1007 (2020) Standard Specification for Installation of Load Bearing (Transverse and Axial) Steel Studs and Related Accessories

ASTM C1513 (2018) Standard Specification for Steel Tapping Screws for Cold-Formed Steel Framing Connections

ASTM E119 (2024) Standard Test Methods for Fire Tests of Building Construction and Materials

ASTM E329 (2025b) Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection

ASTM E488/E488M (2022) Standard Test Methods for Strength of Anchors in Concrete Elements

ASTM F1554 (2020) Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield

	Strength
ASTM F1941	(2010) Standard Specification for Electrodeposited Coatings on Threaded Fasteners (Unified Inch Screw Threads (UN/UNR))
ASTM F2329/F2329M	(2015) Standard Specification for Zinc Coating, Hot-Dip, Requirements for Application to Carbon and Alloy Steel Bolts, Screws, Washers, Nuts, and Special Threaded Fasteners

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2024) International Building Code

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-301-01	(2023; with Change 6, 2026) Structural Engineering

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Framing Components; G

SD-03 Product Data

Steel Studs, Joists, Tracks, Bracing, Bridging and Accessories

Recycled Content of Steel Products

SD-05 Design Data

Metal Framing Calculations; G

SD-07 Certificates

Load-Bearing Cold-Formed Metal Framing

Welds

1.3 DELIVERY, STORAGE, AND HANDLING

Steel framing and related accessories shall be stored and handled in accordance with the AISI S202, "Code of Standard Practice for Cold-Formed Steel Structural Framing".

1.4 LOAD-BEARING COLD-FORMED METAL FRAMING

Include top and bottom tracks, bracing, fastenings, and other accessories necessary for complete installation. Framing members shall have the

structural properties indicated. Where physical structural properties are not indicated, they shall be as necessary to withstand all imposed loads. Design framing in accordance with AISI S100.

Submit mill certificates or test reports from independent testing agency, qualified in accordance with ASTM E329, showing that the steel sheet used in the manufacture of each cold-formed component complies with the minimum yield strengths and uncoated steel thickness specified. Test reports shall be based on the results of three coupon tests in accordance with ASTM A370.

1.5 MAXIMUM DEFLECTION

Deflections of structural members shall not exceed the more restrictive of the limitations of ICC IBC and UFC 3-301-01 or as indicated on the design drawings

1.6 QUALITY ASSURANCE

a. Engineering Responsibility: Preparation of Shop Drawings, design calculations, and other structural data by a registered professional engineer.

b. Testing Agency Qualifications: An independent testing agency, acceptable to authorities having jurisdiction, qualified according to ASTM E329 for testing indicated.

c. Product Tests: Mill certificates or data from a qualified independent testing agency indicating steel sheet complies with requirements, including base-metal thickness, yield strength, tensile strength, total elongation, chemical requirements, and metallic-coating thickness.

d. Welding Qualifications: Qualify procedures and personnel according to the following:

(1) AWS D1.1/D1.1M, "Structural Welding Code - Steel".

(2) AWS D1.3/D1.3M, "Structural Welding Code - Sheet Steel".

e. Fire-Test-Response Characteristics: Where indicated, provide cold-formed metal framing identical to that of assemblies tested for fire resistance per ASTM E119 by, and displaying a classification label from, a testing and inspecting agency acceptable to authorities having jurisdiction.

f. AISI Specifications and Standards: Comply with:

(1) AISI S100, "North American Specification for the Design of Cold-Formed Steel Structural Members".

(2) AISI S110, "Standard for Seismic Design of Cold-Formed Steel Structural Systems - Special Bolted Moment Frames".

(3) AISI S200, "North American Standard for Cold-Formed Steel Framing - General Provision".

(4) AISI S201, "North American Standard for Cold-Formed Steel Framing - Product Data".

(5) AISI S202, "Code of Standard Practice for Cold-Formed Steel Structural Framing".

(6) AISI S211, "North American Standard for Cold-Formed Steel Framing - Wall Stud Design".

(7) AISI S212, "North American Standard for Cold-Formed Steel Framing - Header Design".

(8) AISI S213, "North American Standard for Cold-Formed Steel Framing - Lateral Design".

(9) AISI S214, "North American Standard for Cold-Formed Steel Framing - Truss Design".

1.6.1 Drawing Requirements

Submit framing components to show sizes, thicknesses, layout, material designations, methods of installation, and accessories including the following:

a. Cross sections, plans, and/or elevations showing component types and locations for each framing application; including shop coatings and material thicknesses for each framing component.

b. Connection details showing fastener type, quantity, location, and other information to assure proper installation.

c. Drawings depicting panel configuration, dimensions, components, locations, and construction sequence if the Contractor elects to install prefabricated/prefinished frames.

Sign and seal fabrication drawings by a registered professional engineer.

1.6.2 Design Data Required

Submit metal framing calculations with design criteria and structural loading to verify sizes, thickness, and spacing of members and connections signed and sealed by a registered professional engineer. Show methods and practices used in installation.

PART 2 PRODUCTS

2.1 STEEL STUDS, JOISTS, TRACKS, BRACING, BRIDGING AND ACCESSORIES

Framing components shall comply with ASTM C955 and the following.

a. Provide products with an average recycled content of steel products so postconsumer recycled content plus one half of preconsumer recycled content not less than 25 percent.

b. Steel Sheet: ASTM A1003/A1003M, Structural Grade, Type H, metallic coated, of grade and coating weight as follows:

(1) Grade: As required by structural performance.

(2) Coating: G60 (Z180), A60 (ZF180), AZ50 (AZ150), or GF30 (ZGF90).

c. Steel Studs: Manufacturer's standard C-shaped steel studs, of web depths indicated, punched, with stiffened flanges, and as follows:

(1) Minimum Base-Metal Thickness: 0.0428 inch.

(2) Flange Width: 1-5/8 inches.

d. Steel Track: Manufacturer's standard U-shaped steel track, of web depths indicated, unpunched, with straight flanges, and as follows:

(1) Minimum Base-Metal Thickness: 0.0428 inch.

(2) Flange Width: 1-1/4 inches.

e. Roof Truss Members: Manufacturer's standard C-shaped steel sections, of web depths indicated, unpunched, with stiffened flanges, and as follows:

(1) Minimum Base-Metal Thickness: 0.0428 inch.

(2) Flange Width: 1-5/8 inches, minimum at top and bottom chords connecting to sheathing or directly fastened construction.

2.1.1 Studs and Joists of 54 mils (0.054 Inch) and Heavier

Galvanized steel, ASTM A653/A653M and ASTM A1003/A1003M, SS Grade 50, G60 .

2.1.2 Studs and Joists of 43 mils (0.043 Inch) and Lighter

Studs and Joists of 43 mils (0.043 Inch) and Lighter, Track, and Accessories (All thicknesses): Galvanized steel, ASTM A653/A653M and ASTM A1003/A1003M, SS, Grade 33 33,000 psi G60.

2.1.3 Sizes, Thickness, Section Modulus, and Other Structural Properties

Size and thickness as required.

2.2 MARKINGS

Studs and track shall have product markings stamped on the web of the section. The markings shall be repeated throughout the length of the member at a maximum spacing of 4 feet on center and shall be legible and easily read. The product marking shall include the following:

a. An ICC number.

b. Manufacturer's identification.

c. Minimum delivered uncoated steel thickness.

d. Protective coating designator.

e. Minimum yield strength.

2.3 CONNECTIONS

2.3.1 Steel-To-Concrete Connections

a. Anchor Rods: ASTM F1554, Grade 36; galvanized per ASTM A153/A153M.

b. Post-Installed Concrete Anchors: Adhesive or expansion anchors fabricated from corrosion-resistant materials with allowable load capacities in accordance with ICC-ES AC193 and ACI 318 greater than or equal to the design load as determined by testing per ASTM E488/E488M conducted by a qualified testing agency.

c. Power-Actuated Fasteners: Fabricated from corrosion-resistant materials with allowable load capacities in accordance with ICC-ES AC 70 greater than or equal to the design load as determined by testing per ASTM E1190 conducted by a qualified testing agency.

2.3.2 Steel-To-Steel Connections

a. Screws: ASTM C1513, corrosion-resistant-coated, self-drilling, self-tapping steel screws of the type and size indicated. Provide low-profile head beneath sheathing and manufacturer's standard elsewhere. Electroplated to a minimum of 5 micron zinc coating per ASTM F1941 or hot-dipped galvanized per ASTM A123/A123M or ASTM A153/A153M.

b. Bolts: ASTM A307 coated by hot-dip process per ASTM F2329/F2329M or zinc-coated by mechanical-deposition process per ASTM B695, Class 55.

c. Welding Electrodes: Comply with AWS standards.

2.4 PLASTIC GROMMETS

Supply plastic grommets for stud webs as recommended by stud manufacturer, to protect electrical wires and plumbing piping. Prevent metal-to-metal contact between wiring/piping and studs.

2.5 SEALER GASKET

Closed-cell neoprene foam, 1/4-inch thick, selected from manufacturer's standard widths to match width of bottom track on concrete slab or foundation.

PART 3 EXECUTION

3.1 TRUSS FABRICATION

a. Fabricate cold-formed steel trusses and accessories plumb, square, and true to line, and with connections securely fastened, according to referenced AISI's specifications and standards, manufacturer's written instructions, and requirements in this Section.

b. Truss must be fabricated either on site or off site prior to erection.

c. Fabricate trusses using jigs or templates.

d. Splices can only occur at joints.

e. Cut truss members by sawing or shearing: do not torch cut.

f. Fasten cold-formed steel truss members by welding, screw fastening, clinch fastening, pneumatic pin fastening, or riveting as standard with fabricator.

g. Fasten other materials to cold-formed steel trusses by welding, bolting, pneumatic pin fastening, or screw fastening, according to Shop Drawings.

h. Reinforce, stiffen, and brace trusses to withstand handling, delivery, and erection stresses. Lift fabricated trusses to prevent damage or permanent distortion.

3.2 FASTENING

Fasten framing members together by welding or by using self-drilling, self-tapping screws. Electrodes and screw connections shall be as required and indicated in the design calculations.

3.2.1 Welds

All welding shall be performed in accordance with AWS D1.3/D1.3M, as modified by AISI S100. All welders, welding operations, and welding procedures shall be qualified according to AWS D1.3/D1.3M. Submit certified copies of welder qualifications test records showing qualification in accordance with AWS D1.3/D1.3M. All welds shall be cleaned and coated with rust inhibitive galvanizing paint. Do not field weld materials lighter than 43 mils.

3.2.2 Screws

Screws shall be of the self-drilling self-tapping type, size, and location as required. Screw penetration through joined materials shall not be less than three exposed threads. Minimum spacings and edge distances for screws shall be as specified in AISI S100. Screws covered by sheathing materials shall have low profile heads.

3.2.3 Anchors

Anchors shall be of the type, size, and location as required.

3.2.4 Powder-Actuated Fasteners

Powder-actuated fasteners shall be of the type, size, and location as required.

3.3 INSTALLATION

Install cold-formed framing in accordance with ASTM C1007 and AISI S200.

Install cold-formed steel framing according to AISI S202 and to manufacturer's written instructions unless more stringent requirements are indicated.

3.3.1 Tracks

Provide accurately aligned runners at top and bottom of studs. Install sealer gasket under bottom of track on concrete slab or foundation. Anchor tracks as indicated in design calculations. Butt weld joints in tracks or splice with stud inserts. Fasteners shall be at least 3 inches from the edge of concrete slabs.

3.3.2 Studs

Cut studs square and set with firm bearing against webs of top and bottom tracks. Position studs vertically in tracks and space as indicated in design. Do not splice studs. Provide at least two studs at jambs of doors and other openings 2 feet wide or larger. Provide jack studs over openings, as necessary, to maintain indicated stud spacing. Provide tripled studs at corners, positioned to receive interior and exterior finishes. Fasten studs to top and bottom tracks by welding or screwing both flanges to the tracks. Framed wall openings shall include headers and supporting components as shown on the drawings. Headers shall be installed in all openings that are larger than the stud spacing in a wall. In curtain wall construction, provide for vertical movement where studs connect to the structural frame. Provide horizontal bracing in accordance with the design calculations and AISI S100. Bracing shall be not less than the following:

LOAD	HEIGHT	BRACING
Wind load only	Up to 10 feet	One row at mid-height
	Over 10 feet	Rows 5'-0" o.c. maximum
Axial load	Up to 10 feet	Two rows at 1/3 points
	Over 10 feet	Rows 3'-4" o.c. maximum

3.3.3 Joists and Trusses

a. Provide a stud directly under each joist or truss. The maximum spacing of studs as indicated shall be maintained.

b. Install, bridge, and brace cold-formed steel trusses according to AISI S200, AISI S214, AISI's "Code of Standard Practice for Cold-Formed Steel Structural Framing," and manufacturer's written instructions unless more stringent requirements are indicated.

c. Install temporary bracing and supports. Maintain braces and supports in place, undisturbed, until entire integrated supporting structure has been completed and permanent connections to framing are secured.

d. Do not alter, cut, or remove framing members or connections of trusses.

3.3.4 Erection Tolerances

a. Framing members which will be covered by finishes such as wallboard, plaster, or ceramic tile set in a mortar setting bed, shall be within the following limits:

(1) Layout of walls and partitions: 1/4 inch from intended position;

(2) Plates and runners: 1/4 inch in 8 feet from a straight line;

(3) Studs: 1/4 inch in 8 feet out of plumb, not cumulative; and

(4) Face of framing members: 1/4 inch in 8 feet from a true plane.

b. Framing members which will be covered by ceramic tile set in dry-set mortar, latex-portland cement mortar, or organic adhesive shall be within the following limits:

(1) Layout of walls and partitions: 1/4 inch from intended position;

(2) Plates and runners: 1/8 inch in 8 feet from a straight line;

(3) Studs: 1/8 inch in 8 feet out of plumb, not cumulative; and

(4) Face of framing members: 1/8 inch in 8 feet from a true plane.

-- End of Section --

SECTION 05 50 13

MISCELLANEOUS METAL FABRICATIONS
05/17, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF45	(2003; Reaffirmed 2009) Designation System for Aluminum Finishes

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 303	(2016) Code of Standard Practice for Steel Buildings and Bridges

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2022) Nuts for General Applications: Machine Screw Nuts, and Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B18.6.2	(2020) Square Head Set Screws and Slotted Headless Set Screws (Inch Series)
ASME B18.6.3	(2013; R 2017) Machine Screws, Tapping Screws, and Machine Drive Screws (Inch Series)
ASME B18.21.1	(2009; R 2016) Washers: Helical Spring-Lock, Tooth Lock, and Plain Washers (Inch Series)
ASME B18.21.2M	(1999; R 2014) Lock Washers (Metric Series)
ASME B18.22M	(1981; R 2017) Metric Plain Washers

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.3	(2020) Safety Requirements for Powder-Actuated Fastening Systems American National Standard for Construction and Demolition Operations

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding Code - Steel

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A47/A47M	(1999; R 2022; E 2022) Standard Specification for Ferritic Malleable Iron Castings
ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2023) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM A500/A500M	(2023) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A924/A924M	(2022a) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM B26/B26M	(2018; E 2018) Standard Specification for Aluminum-Alloy Sand Castings
ASTM B108/B108M	(2019) Standard Specification for Aluminum-Alloy Permanent Mold Castings
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B209M	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric)
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B221M	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)

ASTM C1513	(2018) Standard Specification for Steel Tapping Screws for Cold-Formed Steel Framing Connections
ASTM D1187/D1187M	(1997; E 2011; R 2011) Asphalt-Base Emulsions for Use as Protective Coatings for Metal
ASTM E488/E488M	(2022) Standard Test Methods for Strength of Anchors in Concrete Elements
ASTM F1554	(2020) Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength

MASTER PAINTERS INSTITUTE (MPI)

MPI 79	(2016) Primer, Alkyd, Anti-Corrosive for Metal

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC SP 3	(2018) Power Tool Cleaning
SSPC SP 6/NACE No.3	(2007) Commercial Blast Cleaning

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

1.2 SUBMITTALS

Government approval is required for submittals. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Bollards/Pipe Guards

Each Downspout Terminations Type; G

Recycled Content; S

1.3 QUALIFICATION OF WELDERS

Qualify welders in accordance with AWS D1.1/D1.1M. Use procedures, materials, and equipment of the type required for the work.

1.4 DELIVERY, STORAGE, AND PROTECTION

Protect from corrosion, deformation, and other types of damage. Store items in an enclosed area free from contact with soil and weather. Remove and replace damaged items with new items.

1.5 MISCELLANEOUS REQUIREMENTS

1.5.1 Fabrication Drawings

Submit fabrication drawings showing layout(s), connections to structural system, and anchoring details as specified in AISC 303.

1.5.2 Installation Drawings

Submit templates, erection, and installation drawings indicating thickness, type, grade, class of metal, and dimensions. Show construction details, reinforcement, anchorage, and installation in relation to the building construction.

PART 2 PRODUCTS

2.1 RECYCLED CONTENT

Provide products with recycled content.

2.2 MATERIALS

Provide exposed fastenings of compatible materials (avoid contact of dissimilar metals). Coordinate color and finish with the material to which fastenings are applied.

2.2.1 Structural Carbon Steel

Provide in accordance with ASTM A36/A36M.

2.2.2 Structural Tubing

Provide in accordance with ASTM A500/A500M.

2.2.3 Steel Pipe

Provide in accordance with ASTM A53/A53M, Type E or S, Grade B.

2.2.4 Fittings for Steel Pipe

Provide standard malleable iron fittings in accordance with ASTM A47/A47M.

2.2.5 Anchor Bolts

Provide in accordance with ASTM F1554. Where exposed, provide anchor bolts of the same material, color, and finish as the metal to which they are applied.

2.2.5.1 Adhesive Anchors

Provide adhesive anchors sized and fabricated for the conditions encountered. Design values are as tested in accordance with ASTM E488/E488M.

2.2.5.2 Lag Screws and Bolts

Provide in accordance with ASME B18.2.1, type and grade best suited for the purpose.

2.2.5.3 Toggle Bolts

Provide in accordance with ASME B18.2.1.

2.2.5.4 Bolts, Nuts, Studs and Rivets

Provide in accordance with ASME B18.2.2 or ASTM A307.

2.2.5.5 Powder Actuated Fasteners

Follow safety provisions in accordance with ASSP A10.3.

2.2.5.6 Screws

Provide in accordance with ASME B18.2.1, ASME B18.6.2, ASME B18.6.3 and ASTM C1513.

2.2.5.7 Washers

Provide plain washers in accordance with ASME B18.22M, ASME B18.21.1. Provide beveled washers for American Standard beams and channels, square or rectangular, tapered in thickness, and smooth. Provide lock washers in accordance with ASME B18.21.2M, ASME B18.21.1.

2.2.6 Aluminum Alloy Products

Provide in accordance with ASTM B209M, ASTM B209 for sheet plate, ASTM B221M, ASTM B221M, ASTM B221 for extrusions and ASTM B26/B26M or ASTM B108/B108M for castings. Provide aluminum extrusions at least 1/8 inch thick and aluminum plate or sheet at least 0.050 inch thick.

2.3 FABRICATION FINISHES

2.3.1 Galvanizing

Hot-dip galvanize items specified to be zinc-coated, after fabrication where practicable. Provide galvanizing in accordance with ASTM A123/A123M, ASTM A153/A153M, ASTM A653/A653M or ASTM A924/A924M, Z275 G90.

2.3.2 Galvanize

Anchor bolts, grating fasteners, washers, and parts or devices necessary for proper installation, unless indicated otherwise.

2.3.3 Shop Cleaning and Painting

2.3.3.1 Surface Preparation

Blast clean ferrous metal fabrication surfaces in accordance with SSPC SP 6/NACE No.3. Surfaces that will be exposed in spaces above ceiling or in attic spaces, crawl spaces, furred spaces, and chases may be cleaned in accordance with SSPC SP 3 in lieu of being blast cleaned. Wash cleaned surfaces which become contaminated with rust, dirt, oil, grease, or other contaminants with solvents until thoroughly clean. Steel to be embedded in concrete must be free of dirt and grease prior to embed. Do not paint or galvanize bearing surfaces, including contact surfaces within slip critical joints. Shop coat these surfaces with rust prevention.

2.3.3.2 Pretreatment, Priming and Painting

Apply pre-treatment, primer, and paint in accordance with manufacturer's printed instructions.

2.3.4 Nonferrous Metal Surfaces

Protect by plating, anodic, or organic coatings.

2.3.5 Aluminum Surfaces

2.3.5.1 Surface Condition

Before finishes are applied, remove roll marks, scratches, rolled-in scratches, kinks, stains, pits, orange peel, die marks, structural streaks, and other defects which will affect uniform appearance of finished surfaces.

2.3.5.2 Aluminum Finishes

Unexposed sheet, plate and extrusions may have mill finish as fabricated. Sandblast castings' finish, medium, AA DAF45. Unless otherwise specified, provide all other aluminum items with an anodized finish in compliance with AAMA 611, or better. Provide a coating thickness not less than that specified for protective and decorative type finishes for items used in interior locations or architectural Class I type finish for items used in exterior locations. Provide in accordance with AA DAF45. Provide a polished satin finish on items to be anodized.

2.4 BOLLARDS/PIPE GUARDS

Provide galvanized, standard weight steel pipe in accordance with ASTM A53/A53M. Anchor posts in concrete as indicated and fill solidly with concrete with minimum compressive strength of 2500 psi.

2.5 DOWNSPOUT TERMINATIONS

Provide cast iron downspout boot with cleanout access and manufacturer's standard cast iron strap of the sizes required to receive downspouts encountered. Castings transition to round outlets of diameters indicated for connection to horizontal piping encountered. Furnish 90 degree, straight, offset and angular shoe transitions. Boots have a minimum of four pre punched or lug fastening flanges for wall substrate anchoring. Secure with 0.625 inch stainless steel bolts, washers and metal tube spacers matching the downspout bracket internal stand off material. Typical installations require boots 3 feet, 0 inches in length and have approximately 1 foot, 8 inches exposed above grade. Provide extensions to accommodate greater exposed lengths. Factory prime iron castings for field finishing.

2.6 MISCELLANEOUS PLATES AND SHAPES

Provide items that do not form a part of the structural steel framework, such as lintels, sill angles,miscellaneous mountings and frames. Provide lintels fabricated from structural steel shapes over openings in masonry walls and partitions. Construct to have at least 8 in bearing on masonry at each end.

Provide angles and plates in accordance with ASTM A36/A36M, for embedment

as indicated. Galvanize embedded items exposed to the elements in accordance with ASTM A123/A123M.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Install items at locations indicated in accordance with manufacturer's instructions. Verify all field dimensions prior to fabrication. Include materials and parts necessary to complete each assembly, whether indicated or not. Miss-alignment and miss-sizing of holes for fasteners is cause for rejection. Conceal fastenings where practicable. Joints exposed to weather must be watertight.

3.2 WORKMANSHIP

Provide miscellaneous metalwork that is true and accurate in shape, size, and profile. Make angles and lines continuous and straight. Make curves consistent, smooth and unfaceted. Provide continuous welding along the entire area of contact except where tack welding is permitted. Do not tack weld exposed connections. Unless otherwise indicated and approved, provide a smooth finish on exposed surfaces. Provide countersuck rivets where exposed. Provide coped and mitered corner joints aligned flush and without gaps.

3.3 ANCHORAGE, FASTENINGS, AND CONNECTIONS

Provide anchorage as necessary, whether indicated or not, for fastening miscellaneous metal items securely in place. Include slotted inserts, expansion shields, powder-driven fasteners, toggle bolts (when approved for concrete), through bolts for masonry, headed shear studs, machine and carriage bolts for steel, through bolts, lag bolts, and screws for wood. Do not use wood plugs. Provide non-ferrous attachments for non-ferrous metal. Provide exposed fastenings of compatible materials (avoid contact of dissimilar metals), that generally match in color and finish the surfaces to which they are applied. Conceal fastenings where practicable. Provide all fasteners flush with the surfaces they fasten, unless indicated otherwise.

3.4 BUILT-IN WORK

Where necessary and not otherwise indicated, form built-in metal work for anchorage with concrete or masonry. Provide built-in metal work in ample time for securing in place as the work progresses.

3.5 WELDING

Perform welding, welding inspection, and corrective welding in accordance with AWS D1.1/D1.1M. Use continuous welds on all exposed connections. Grind visible welds smooth in the finished installation. Provide welded headed shear studs in accordance with AWS D1.1/D1.1M, Clause 7, except as otherwise specified. Provide in accordance with the safety requirements of EM 385-1-1.

3.6 DISSIMILAR METALS

Where dissimilar metals are in contact, protect surfaces with a coating in accordance with MPI 79 to prevent galvanic or corrosive action. Where aluminum is in contact with concrete, plaster, mortar, masonry, wood, or

absorptive materials subject to wetting, protect in accordance with ASTM D1187/D1187M, asphalt-base emulsion. Clean surfaces with metal shavings from installation at the end of each work day.

3.7 INSTALLATION OF BOLLARDS/PIPE GUARDS

Set bollards/pipe guards vertically in concrete piers. Fill hollow cores with concrete having a compressive strength of 3000 psi.

3.8 INSTALLATION OF DOWNSPOUT TERMINATIONS

Locate cast iron downspout boot bolts in masonry joints. Provide pipe fittings to accommodate shoe transitions. Align tops at a consistent elevation. Secure downspouts terminations to downspouts and substrate per manufacturer's instructions.

-- End of Section --

SECTION 06 41 16.00 10

PLASTIC-LAMINATE-CLAD ARCHITECTURAL CABINETS
08/10, CHG 1: 11/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A161.2	(1998) Decorative Laminate Countertops, Performance Standards for Fabricated High Pressure

ASTM INTERNATIONAL (ASTM)

ASTM F547	(2022) Standard Terminology of Nails for Use with Wood and Wood-Base Materials

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.9	(2020) Cabinet Hardware

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI/NEMA LD 3	(2005) Standard for High-Pressure Decorative Laminates

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

UL ENVIRONMENT (ULE)

ULE Greenguard	UL Greenguard Certification Program

WINDOW AND DOOR MANUFACTURERS ASSOCIATION (WDMA)

ANSI/WDMA I.S.1A	(2013) Interior Architectural Wood Flush Doors

WOODWORK INSTITUTE (WI)

NAAWS 3.1	(2017; 2018 Errata Edition) North American Architectural Woodwork Standards

1.2 SYSTEM DESCRIPTION

Work in this section includes laminate clad custom casework cabinets and vanity aprons as shown on the drawings and as described in this specification. This Section includes high-pressure laminate surfacing and cabinet hardware. Comply with EPA requirements in accordance with Section

01 33 29 SUSTAINABILITY REPORTING. All exposed and semi-exposed surfaces, whose finish is not otherwise noted on the drawings or finish schedule, must be sanded smooth and must receive a clear finish of polyurethane. Wood finish may be shop finished or field applied in accordance with Section 09 90 00 PAINTS AND COATINGS.

1.3 SUSTAINABILITY REPORTING

See Section 01 33 29 SUSTAINABILITY REPORTING for project sustainablility information.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Shop Drawings

Installation

SD-03 Product Data

Wood Materials

Finish Schedule

SD-04 Samples

Plastic Laminates

Cabinet Hardware

SD-07 Certificates

Quality Assurance

Laminate Clad Casework

Certification

1.5 QUALITY ASSURANCE

1.5.1 General Requirements

Unless otherwise noted on the drawings, all materials, construction methods, and fabrication must conform to and comply with the custom grade quality standards as outlined in NAAWS 3.1, Section for laminate clad cabinets. These standards must apply in lieu of omissions or specific requirements in this specification. Contractors and their personnel engaged in the work must be able to demonstrate successful experience with work of comparable extent, complexity and quality to that shown and specified. Submit a quality control statement which illustrates compliance with and understanding of NAAWS 3.1 requirements, in general,

and the specific NAAWS 3.1 requirements provided in this specification. The quality control statement must also certify a minimum of ten years Contractor's experience in laminate clad casework fabrication and construction. The quality control statement must provide a list of a minimum of five successfully completed projects of a similar scope, size, and complexity.

1.5.2 Sustainable Design Certification

Product must be third party certified in accordance with ULE Greenguard, SCS Scientific Certification Systems Indoor Advantage or equal. Certification shall be performed annually and must be current.

1.6 DELIVERY, STORAGE, AND HANDLING

Casework may be delivered knockdown or fully assembled. Deliver all units to the site in undamaged condition, stored off the ground in fully enclosed areas, and protected from damage. The storage area must be well ventilated and not subject to extreme changes in temperature or humidity.

1.7 SEQUENCING AND SCHEDULING

Coordinate work with other trades. Units must not be installed in any room or space until painting, and ceiling installation are complete within the room where the units are located. Floor cabinets must be installed before finished flooring materials are installed.

PART 2 PRODUCTS

2.1 WOOD MATERIALS

2.1.1 Lumber

a. All framing lumber must be kiln-dried Grade III to dimensions as shown on the drawings. Frame front, where indicated on the drawings, must be nominal 3/4 inch hardwood.

b. Standing or running trim casework components, which are specified to receive a transparent finish, must be maple hardwood species, plain sawn. AWI grade must be custom. Location, shape, and dimensions must be as indicated on the drawings.

2.1.2 Panel Products

2.1.2.1 Plywood

All plywood panels used for framing purposes must be veneer core hardwood plywood, NAAWS 3.1 Grade AA. Nominal thickness of plywood panels must be as indicated in this specification and on the drawings.

2.2 HIGH PRESSURE DECORATIVE LAMINATE (HPDL)

All plastic laminates must meet the requirements of ANSI/NEMA LD 3 and ANSI A161.2 for high-pressure decorative laminates. Design, colors, surface finish and texture, and locations must be as indicated on the drawings. Submit two samples of each plastic laminate pattern and color. Samples must be a minimum of 5 by 7 inches in size. Plastic laminate types and nominal minimum thicknesses for casework components must be as indicated in the following paragraphs.

2.2.1 Horizontal General Purpose Standard (HGS) Grade

Horizontal general purpose standard grade plastic laminate must be 0.048 inches (plus or minus 0.005 inches) in thickness. This laminate grade is intended for horizontal surfaces where postforming is not required.

2.2.2 Vertical General Purpose Standard (VGS) Grade

Vertical general purpose standard grade plastic laminate must be 0.028 inches (plus or minus 0.004 inches) in thickness. This laminate grade is intended for exposed exterior vertical surfaces of casework components where postforming is not required.

2.2.3 Cabinet Liner Standard (CLS) Grade

Cabinet liner standard grade plastic laminate must be 0.020 inches in thickness. This laminate grade is intended for light duty semi-exposed interior surfaces of casework components.

2.2.4 Backing Sheet (BK) Grade

Undecorated backing sheet grade laminate is formulated specifically to be used on the backside of plastic laminated panel substrates to enhance dimensional stability of the substrate. Backing sheet thickness must be 0.020 inches. Backing sheets must be provided for all laminated casework components where plastic laminate finish is applied to only one surface of the component substrate.

2.3 EDGE BANDING

Edge banding for casework doors and drawer fronts must be PVC vinyl and must be 0.020 inch thick. Material width must be as indicated on the drawings. Color and pattern must match exposed door and drawer front laminate pattern and color.

2.4 CABINET HARDWARE

Submit one sample of each cabinet hardware item specified to include hinges, pulls, and drawer glides. Cabinet pulls must comply with ABA guidelines. All hardware must conform to ANSI/BHMA A156.9, unless otherwise noted, and must consist of the following components:

2.4.1 Door Hinges

Concealed european hinge type.

2.4.2 Cabinet Pulls

ABA standard U-shaped type pull, BHMA No. B02011.

2.4.3 Drawer Slide

Side mounted type with full extension ball bearing and a minimum 75 pound load capacity. Slides must include a positive stop to avoid accidental drawer removal.

2.4.4 Adjustable Shelf Support System

Recessed mortise mounted metal standards, BHMA No. B04071. Support clips for the standards must be closed type, BHMA no. B04081.

2.5 FASTENERS

Nails, screws, and other suitable fasteners must be the size and type best suited for the purpose and must conform to ASTM F547 where applicable.

2.6 ADHESIVES, CAULKS, AND SEALANTS

2.6.1 Adhesives

Adhesives must be of a formula and type recommended by AWI. Adhesives must be selected for their ability to provide a durable, permanent bond and must take into consideration such factors as materials to be bonded, expansion and contraction, bond strength, fire rating, and moisture resistance. Adhesives must meet local regulations regarding VOC emissions and off-gassing.

2.6.1.1 Wood Joinery

Adhesives used to bond wood members must be a Type II for interior use urea-formaldehyde resin formula. Adhesives must withstand a bond test as described in ANSI/WDMA I.S.1A.

2.6.1.2 Laminate Adhesive

Adhesive used to join high-pressure decorative laminate to wood must be adhesive consistent with AWI and laminate manufacturer's recommendations. PVC edgebanding must be adhered using a polymer-based hot melt glue.

2.6.2 Caulk

Caulk used to fill voids and joints between laminated components and between laminated components and adjacent surfaces must be clear, 100 percent silicone.

2.6.3 Sealant

Sealant must be of a type and composition recommended by the substrate manufacturer to provide a moisture barrier at sink cutouts and all other locations where unfinished substrate edges may be subjected to moisture.

2.7 FABRICATION

Verify field measurements as indicated in the shop drawings before fabrication. Fabrication and assembly of components must be accomplished at the shop site to the maximum extent possible. Construction and fabrication of cabinets and their components must meet or exceed the requirements for AWI custom grade unless otherwise indicated in this specification. Cabinet style, in accordance with NAAWS 3.1, Section 400-G descriptions, must be as indicated on the drawings.

2.7.1 Base and Wall Cabinet Case Body

2.7.1.1 Cabinet Components

Frame members must be glued-together, kiln-dried hardwood lumber. Top corners, bottom corners, and cabinet bottoms must be braced with either hardwood blocks or water-resistant glue and nailed in place metal or plastic corner braces. Cabinet components must be constructed from the following materials and thicknesses:

2.7.1.1.1 Body Members (Ends, Divisions, Bottoms, and Tops)

3/4 inch Plywood panel product

2.7.1.1.2 Face Frames and Rails

3/4 inch panel product

2.7.1.1.3 Shelving

3/4 inch Plywood panel product

2.7.1.1.4 Cabinet Backs

1/4 inch plywood panel product

2.7.1.1.5 Drawer Sides, Backs, and Subfronts

1/2 inch panel product

2.7.1.1.6 Drawer Bottoms

1/4 inch plywood panel product

2.7.1.1.7 Door and Drawer Fronts

3/4-inchplywood panel product

2.7.1.2 Joinery Method for Case Body Members

2.7.1.2.1 Tops, Exposed Ends, and Bottoms

a. Steel "European" assembly screws (1-1/2 inch from end, 5 inch on center, fasteners will not be visible on exposed parts).

b. Doweled, glued under pressure (approx. 4 dowels per 12 inches of joint).

c. Stop dado, glued under pressure, and either nailed, stapled or screwed (fasteners will not be visible on exposed parts).

d. Spline or biscuit, glued under pressure.

2.7.1.2.2 Exposed End Corner and Face Frame Attachment

2.7.1.2.2.1 Mitered Joint

lock miter or spline or biscuit, glued under pressure (no visible fasteners)

2.7.1.2.2.2 Non-Mitered Joint (90 degree)

butt joint glued under pressure (no visible fasteners)

2.7.1.2.3 Cabinet Backs (Wall Hung Cabinets)

Wall hung cabinet backs must not be relied upon to support the full weight of the cabinet and its anticipated load for hanging/mounting purposes. Method of back joinery and hanging/mounting mechanisms should transfer the load to case body members. Fabrication method must be:

2.7.1.2.3.1 Full Bound

Full bound, captured in grooves on cabinet sides, top, and bottom. Cabinet backs for floor standing cabinets must be side bound, captured in grooves; glued and fastened to top and bottom.

2.7.1.2.3.2 Full Overlay

Full overlay, plant-on backs with minimum back thickness of 1/2 inch and minimum No. 12 plated (no case hardened) screws spaced a minimum 3 inches on center. Edge of back must not be exposed on finished sides. Anchor strips are not required when so attached.

2.7.1.2.4 Cabinet Backs (Floor Standing Cabinets)

2.7.1.2.4.1 Full Overlay

Full overlay, plant-on backs with minimum back thickness of 1/2 inch and minimum No. 12 plated (no case hardened) screws spaced a minimum 3 inches on center. Edge of back must not be exposed on finished sides. Anchor strips are not required when so attached.

2.7.1.2.5 Wall Anchor Strips

Wall Anchor Strips must be required for all cabinets with backs less than 1/2 inch thick. Strips must consist of minimum 1/2 inch thick lumber, minimum 2-1/2 inches width; securely attached to wall side of cabinet back - top and bottom for wall hung cabinets, top only for floor standing cabinets.

2.7.2 Cabinet Floor Base

Floor cabinets must be mounted on a base constructed of 3/4 inch veneer core marine grade or salt-treated plywood. Base assembly components must be a moisture-resistant panel product. Finished height for each cabinet base must be as indicated on the drawings. Bottom edge of the cabinet door or drawer face must be flush with top of base.

2.7.3 Cabinet Door and Drawer Fronts

Door and drawer fronts must be fabricated from 3/4 inch medium density fiberboard (MDF). All door and drawer front edges must be surfaced with PVC edgebanding, color and pattern as indicated on the drawings.

2.7.4 Drawer Assembly

2.7.4.1 Drawer Components

Drawer components must consist of a removable drawer front, sides, backs, and bottom. Drawer components must be constructed of the following materials and thicknesses:

2.7.4.1.1 Drawer Sides and Backs For Transparent Finish

1/2 inch thick 7-ply hardwood veneer core plywood (no voids), any species

2.7.4.1.2 Drawer Sides and Backs For Laminate Finish

1/2 inch thick 7-ply hardwood veneer core substrate

2.7.4.1.3 Drawer Bottom

1/4 inch thick plywood panel product for transparent or plastic laminate finish

2.7.4.2 Drawer Assembly Joinery Method

a. Multiple dovetail (all corners) or French dovetail front/dadoed back, glued under pressure.

b. Doweled, glued under pressure.

c. Lock shoulder, glued and pin nailed.

d. Bottoms must be set into sides, front, and back, 1/4 inch deep groove with a minimum 3/8 inch standing shoulder.

2.7.5 Shelving

2.7.5.1 General Requirements

Shelving must be fabricated from 3/4 inch veneer core plywood. All shelving top and bottom surfaces must be finished with HPDL plastic laminate. Shelf edges must be finished in a HPDL plastic laminate.

2.7.5.2 Shelf Support System

The shelf support system must be one of the following:

2.7.5.2.1 Recessed (Mortised) Metal Shelf Standards

Mortise standards flush with the finishes surface of the cabinet interior side walls, two per side. Position and space standards on the side walls to provide a stable shelf surface that eliminates tipping when shelf front is weighted. Install and adjust standards vertically to provide a level, stable shelf surface when clips are in place.

2.7.5.2.2 Pin Hole Method

Drill holes on the interior surface of the cabinet side walls. Evenly space holes in two vertical columns Space the holes in each column at 1 inch increments starting 6 inches from the cabinet interior bottom and extending to within 6 inches of the top interior surface of the cabinet.

Drill holes to provide a level, stable surface when the shelf is resting on the shelf pins. Coordinate hole diameter with pin insert size to provide a firm, tight fit.

2.7.6 Laminate Application

Laminate application to substrates must follow the recommended procedures and instructions of the laminate manufacturer and ANSI/NEMA LD 3, using tools and devices specifically designed for laminate fabrication and application. Provide a balanced backer sheet (Grade BK) wherever only one surface of the component substrate requires a plastic laminate finish. Apply required grade of laminate in full uninterrupted sheets consistent with manufactured sizes using one piece for full length only, using adhesives specified herein or as recommended by the manufacturer. Fit corners and joints hairline. All laminate edges must be machined flush, filed, sanded, or buffed to remove machine marks and eased (sharp corners removed). Clean up at easing must be such that no overlap of the member eased is visible. Fabrication must conform to ANSI A161.2. Laminate types and grades for component surfaces must be as follows unless otherwise indicated on the drawings:

2.7.6.1 Base/Wall Cabinet Case Body

a. Exterior (exposed) surfaces to include exposed and semi-exposed face frame surfaces: HPDL Grade VGS.

b. Interior (semi-exposed) surfaces to include interior back wall, bottom, and side walls: HPDL Grade CLS.

2.7.6.2 Adjustable Shelving

2.7.6.2.1 Top and Bottom Surfaces

HPDL Grade HGS

2.7.6.2.2 All Edges

HPDL Grade HGS

2.7.6.3 Fixed Shelving

2.7.6.3.1 Top and Bottom Surfaces

HPDL Grade HGS

2.7.6.3.2 Exposed Edges

HPDL Grade HGS

2.7.6.4 Door, Drawer Fronts, Access Panels

2.7.6.4.1 Exterior (Exposed) and Interior (Semi-Exposed) Faces

HPDL Grade VGS

2.7.6.4.2 Edges

HPDL Grade HGS

2.7.6.5 Drawer Assembly

All interior and exterior surfaces: HPDL.

2.7.6.6 Tolerances

Flushness, flatness, and joint tolerances of laminated surfaces must meet the NAAWS 3.1 custom grade requirements.

2.7.7 Finishing

2.7.7.1 Filling

No fasteners must be exposed on laminated surfaces. All nails, screws, and other fasteners in non-laminated cabinet components must be countersunk and the holes filled with wood filler consistent in color with the wood species.

2.7.7.2 Sanding

All surfaces requiring coatings must be prepared by sanding with a grit and in a manner that scratches will not show in the final system.

2.7.7.3 Coatings

Types, method of application and location of casework finishes must be in accordance with the finish schedule, drawings and Section 09 90 00 PAINTS AND COATINGS. All cabinet reveals must be painted. Submit descriptive data which provides narrative written verification of all types of construction materials and finishes, methods of construction, etc. not clearly illustrated on the submitted shop drawings. Data must provide written verification of conformance with NAAWS 3.1 for the quality indicated to include materials, tolerances, and types of construction. Both the manufacturer of materials and the fabricator must submit available literature which describes recycled product content, operations and processes in place that support efficient use of natural resources, energy efficiency, emissions of ozone depleting chemicals, management of water and operational waste, indoor environmental quality, and other production techniques supporting sustainable design and products.

PART 3 EXECUTION

3.1 INSTALLATION

Installation must comply with applicable requirements for NAAWS 3.1 custom quality standards. Countertops and fabricated assemblies must be installed level, plumb, and true to line, in locations shown on the drawings. Cabinets and other laminate clad casework assemblies must be attached and anchored securely to the floor and walls with mechanical fasteners that are appropriate for the wall and floor construction.

3.1.1 Anchoring Systems

3.1.1.1 Floor

Base cabinets must utilize a floor anchoring system as detailed on the drawings. Anchoring and mechanical fasteners must not be visible from the finished side of the casework assembly. Cabinet assemblies must be attached to anchored bases without visible fasteners as indicated in the

drawings. Where assembly abuts a wall surface, anchoring must include a minimum 1/2 inch thick lumber or panel product hanging strip, minimum 2-1/2 inch width; securely attached to the top of the wall side of the cabinet back.

3.1.1.2 Wall

Cabinet and vanity apron to be wall mounted must utilize minimum 1/2 inch thick lumber or panel product hanging strips, minimum 2-1/2 inch width; securely attached to the wall side of the cabinet back, both top and bottom.

3.1.2 Hardware

Casework hardware must be installed in types and locations as indicated on the drawings. Where fully concealed European-style hinges are specified to be used with fiberboard doors, the use of plastic or synthetic insertion dowels must be used to receive 3/16 inch "Euroscrews". The use of wood screws without insertion dowels is prohibited.

3.1.3 Doors, Drawers and Removable Panels

The fitting of doors, drawers and removable panels must be accomplished within target fitting tolerances for gaps and flushness in accordance with NAAWS 3.1 custom grade requirements.

3.1.4 Plumbing Fixtures

Install sinks, sink hardware, and other plumbing fixtures in locations as indicated on the drawings and in accordance with Section 22 00 00 PLUMBING, GENERAL PURPOSE.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 06 61 16

SOLID SURFACING FABRICATIONS
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM D570	(2022) Standard Test Method for Water Absorption of Plastics
ASTM D638	(2014) Standard Test Method for Tensile Properties of Plastics
ASTM D696	(2016) Standard Test Method for Coefficient of Linear Thermal Expansion of Plastics Between -30 degrees C and 30 degrees C With a Vitreous Silica Dilatometer
ASTM D790	(2017) Standard Test Methods for Flexural Properties of Unreinforced and Reinforced Plastics and Electrical Insulating Materials
ASTM D2583	(2013a) Indentation Hardness of Rigid Plastics by Means of a Barcol Impressor
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM G21	(2015; R 2021; E 2021) Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

CSA GROUP (CSA)

CSA B45.5-17/IAPMO Z124	(2017; Errata 2017; Errata 2018) Plastic Plumbing Fixtures

INTERNATIONAL CAST POLYMER ASSOCIATION (ICPA)

ICPA SS-1	(2001) Performance Standard for Solid Surface Materials

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI/NEMA LD 3	(2005) Standard for High-Pressure Decorative Laminates

NSF INTERNATIONAL (NSF)

NSF/ANSI 51	(2023) Food Equipment Materials

1.2 SYSTEM DESCRIPTION

a. Work under this section includes items utilizing solid surfacing material fabrications as indicated on the drawings and as described in this specification. Do not change source of supply for materials after work has started, if the appearance of finished work would be affected.

b. In most instances, installation of solid surfacing material fabricated components and assemblies requires strong correctly located structural support provided by other trades. To provide a stable, sound, secure installation, close coordination is required between the solid surfacing material fabricator/installer and other trades to ensure that necessary structural wall support, cabinet counter top structural support, proper clearances, and other supporting components are provided for the installation of wall panels, counter tops, shelving, and all other solid surfacing material fabrications to the degree and extent recommended by the solid surfacing material manufacturer.

c. Provide appropriate staging areas for solid surfacing material fabrications. Allow variation in component size and location of openings of plus or minus 1/8 inch.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Fabrication Drawings; G

Installation; G

Shower Wall Panel And Pan System; G

SD-03 Product Data

Solid Polymer; G

Indoor air quality for solid surface seam and sealant products; S

Shower Wall Panel And Pan System; G

SD-04 Samples

Material; G

Counter Tops; G

SD-06 Test Reports

Test Report Results

SD-07 Certificates

Qualifications

Indoor Air Quality for solid surface fabrication products; S

SD-10 Operation and Maintenance Data

Solid Polymer, Data Package 1; G

1.4 QUALITY ASSURANCE

1.4.1 Qualifications

To ensure warranty coverage, provide manufacturer certified solid surfacing fabricators to fabricate the solid surfacing material being utilized. Mark all fabrications with the fabricator's certification label affixed in an inconspicuous location. Minimum of 5 years of experience working with solid surfacing materials is required of fabricators. Submit solid surfacing material manufacturer's certification attesting to fabricator qualification approval.

1.5 DELIVERY, STORAGE, AND HANDLING

Do not deliver materials to project site until areas are ready for installation. Deliver components and materials to the site undamaged, in containers clearly marked and labeled with manufacturer's name. Store materials indoors and take adequate precautions to prevent damage to finished surfaces. Provide protective coverings to prevent physical damage or staining following installation, for duration of project.

1.6 WARRANTY

Provide manufacturer's warranty to repair or replace defective materials, excluding damages caused by physical or chemical abuse or excessive heat, and workmanship for a period of 10 years from date of final acceptance of the work.

PART 2 PRODUCTS

2.1 MATERIAL

Submit detail fabrication drawings and installation drawings of each solid surfacing fabrication indicated. Include elevations, dimensions, clearances, details of construction and anchorage, and details of joints and connections.

Submit manufacturers' descriptive product data for each type of solid

polymer fabrication indicated. Include manufacturers' literature, finishes, profiles and thicknesses of materials.

Submit manufacturers' operations and maintenance data for each type of solid polymer fabrication in accordance with Section 01 78 23 OPERATIONS AND MAINTENANCE DATA.

2.1.1 Solid Surfacing Material

Provide solid polymer that is a homogeneous filled solid polymer; not coated, laminated or of a composite construction, complying with ICPA SS-1. Provide material that meets or exceeds the minimum physical and performance properties specified. Superficial damage to a depth of 0.01 inch must be repairable by sanding or polishing. Material thickness is 1/4 inch. Submit a minimum 4 inch by 4 inch sample of each color and pattern for approval; include full range of color and pattern variation. Retain approved samples as a standard for this work. Submit test report results from an independent testing laboratory attesting that the submitted solid surfacing materials meet or exceed each of the specified performance requirements.

a. Horizontal Surfaces: 1/2 inch thick material

b. Vertical Surfaces: 1/4 inch thick material

c. Provide materials that meet the emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type). Provide certification or validation of indoor air quality for solid surface fabrication products.

2.1.2 Cast, 100 Percent Acrylic Polymer Solid Surfacing Material

Cast, 100 percent acrylic solid polymer material composed of acrylic polymer, mineral fillers, and pigments. Provide acrylic polymer that meets or exceeds the following minimum performance requirements:

PROPERTY	REQUIREMENT (min. or max.)	TEST PROCEDURE
Tensile Strength	4000 psi (max.)	ASTM D638
Hardness	55-Barcol Impressor (min.)	ASTM D2583
Thermal Expansion	.000023 in/in/F (max.)	ASTM D696
Boiling Water Surface Resistance	No Change	ANSI/NEMA LD 3-3.05
High Temperature Resistance	No Change	ANSI/NEMA LD 3-3.06
Impact Resistance (Ball drop)		ANSI/NEMA LD 3-303
1/4 inch sheet	36-inches, 1/2 lb ball, no failure	

PROPERTY	REQUIREMENT (min. or max.)	TEST PROCEDURE
1/2 inch sheet	140-inches, 1/2 lb ball, no failure	
3/4 inch sheet	200-inches, 1/2 lb ball, no failure	
Mold & Mildew Growth	No growth	ASTM G21
Bacteria Growth	No growth	ASTM G21
Liquid Absorption (Weight in 24 hrs.)	0.1 percent max.	ASTM D570
Flammability		ASTM E84
Flame Spread	25 max.	
Smoke Developed	30 max.	
Sanitation	"Food Contact" approval	NSF/ANSI 51
Flexural Strength	6,800 psi (min.)	ASTM D790

2.1.3 Material Patterns and Colors

Provide pattern and color for all solid surfacing material components and fabrications as indicated; colors listed are not intended to limit the selection of equal colors from other manufacturers. Provide products with consistent patterned color throughout thickness of the product.

2.1.4 Surface Finish

Provide a uniform appearance on exposed finished surfaces and edges. Exposed surface finish is matte; gloss rating of 5-20,semigloss; gloss rating of 25-50,polished; gloss rating of 55-80.

2.2 ACCESSORY PRODUCTS

Provide accessory products, as specified below, as manufactured by the solid surfacing material manufacturer or as approved by the solid surfacing material manufacturer for use with the solid surfacing materials being specified.

2.2.1 Adhesives

Provide a two-part seam adhesive kit to create permanent, inconspicuous, non-porous, hard seams and joints by chemical bond between solid surfacing materials and components to create a monolithic appearance of the fabrication. Provide adhesive approved by the solid surfacing material manufacturer. Color-match adhesive to the surfaces being bonded where solid-colored, solid surfacing materials are being bonded together. Provide clear or color matched seam adhesive where particulate patterned, solid surfacing materials are being bonded together.

2.2.2 Seam and Sealant Emissions

Provide seam and other accessory materials that meet the emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type). Provide validation of indoor air quality for solid surface seam and sealant products.

2.2.3 Silicone Sealant

Provide silicone sealant, mildew-resistant, single-component, nonsag, plus 25 percent and minus 25 percent movement capability, acid-curing; ASTM C920, Type S, Grade NS, Class 25, Use NT; clear formulation; approved for use by the solid surfacing material manufacturer.

2.2.4 Mounting Hardware

Provide mounting hardware, including sink/bowl clips, inserts and fasteners for attachment of undermount sinks and lavatories.

2.3 FABRICATIONS

Provide factory or shop fabricate components to sizes and shapes indicated, to the greatest extent practical, in accordance with approved Shop Drawings and manufacturer's requirements. Provide factory cutouts for sinks, lavatories, and plumbing fixtures where indicated on the drawings. Contours and radii must be routed to template, with edges smooth. Defective and inaccurate work will be rejected. Submit product data indicating product description, fabrication information, and compliance with specified performance requirements for solid surfacing material, joint adhesive, sealants, and heat reflective tape. Both the manufacturer of materials and the fabricator are required to submit a detailed description of operations and processes in place that support efficient use of natural resources, energy efficiency, emissions of ozone depleting chemicals, management of water and operational waste, indoor environmental quality, and other production techniques supporting sustainable design and products.

2.3.1 Joints and Seams

Form joints and seams between solid surfacing material components using manufacturer's approved seam adhesive. Provide inconspicuous joints in appearance without voids to create a monolithic appearance.

2.3.2 Edge Finishing

Rout and finish component edges to a smooth, uniform appearance and finish. Provide edge shapes and treatments, including any inserts, as detailed on the drawings. Rout all cutouts, then sand all edges smooth. Repair or reject defective or inaccurate work.

2.3.3 Counter Top Splashes

Fabricate backsplashes and end splashes from 1/2 inch thick solid surfacing material to be 4 inches high in conformance with dimensions and shapes as indicated. Provide backsplashes and end splashes for all counter tops, at locations indicated. Shop fabricate backsplashes and provide loose, to be field attached.

2.3.3.1 End Splashes

Provide end splashes loose for installation at the jobsite after horizontal surfaces to which they are to be attached have been installed.

2.3.4 Window Stools

Fabricate window stools from 1/2 inch thick solid surfacing material; dimensions, edge shape, and other details as selected from manufacturer's available pre-fabricated standards, equal to the width of the window opening by a 1/2 inch overhang of the window sill depth. Provide bullnose edge profiles where exposed.

2.3.5 Counter Tops

Fabricate all solid surfacing material, counter top components from 1/2 inch thick material. Indicate details, dimensions, locations, and quantities on the drawings. Provide counter tops with 4 inch loose at all locations. Attach 2 inch wide reinforcing strip of solid surfacing material under each horizontal counter top seam. Submit a minimum 1 foot wide by 6 inch deep, full size sample for each type of counter top shown on the project drawings; include the edge profile and backsplash as detailed on the drawings and at least one seam. Retain approved sample as standard for this work. Provide square edge profile where exposed.

2.3.5.1 Counter Tops with Sinks

a. Provide stainless steel sink; include cutouts to template for counter tops with sinks as furnished by the sink manufacturer. Provide manufacturer's standard sink mounting hardware for stainless steel undermount installation. Seal between sink and counter top with specified silicone sealant. Provide sink, faucet, and plumbing requirements in accordance with Section 22 00 00 PLUMBING,GENERAL PURPOSE.

b. Provide manufacturer's standard solid polymer sinks, pre-molded product specifically designed for attachment to solid surfacing material counter tops. See paragraph SOLID POLYMER SINKS for additional requirements.

2.3.6 Solid Polymer Bowls

Provide solid polymer bowls that are a standard product of the solid polymer manufacturer, in compliance with CSA B45.5-17/IAPMO Z124 requirements, designed specifically to be installed in solid surfacing material counter tops. Provide bowls of the same polymer composition as the adjoining counter top. Bowl design must support a seam adhesive flush installation method.

2.3.7 Shower Wall Panel And Pan System

Provide tub/shower wall enclosures with a system of solid surfacing material components. Shower wall panel and pan system to include: prefabricated shower pan base and wall panels and shampoo shelf; dimensions of all components are as indicated. Form panels from manufacturer's standard 1/4 inch thick sheet product. Provide panels full width and height with seams occurring only at the inside corners of the enclosure. Provide shampoo shelf of configuration, shape, and location as indicated.

Prefabricated shower bases are of the sizes encountered and molded with drains at a low point. Pans are a 0.5 inch thick, adhered to a 2 inch extruded polystyrene core and have a maximum slope of 0.5 inches per foot. The maximum pan size is a nominal 8 feet, 0 inches by 5 feet, 4 inches. Drain locations vary and extend at least 8 inches from adjoining walls. Coordinate drain locations with piping rough in locations encountered. Furnish matching fiberglass reinforced perimeter flanges with extruded polystyrene cores to accommodate drain piping and fittings within bases. Provide 3 inch wide by 1 inch high, internal lip curbs at exposed base edges. Pans have an 80 grit, slip resistant surface. Furnish epoxy weld sealant, gaskets, edge reinforcement and similar recommended accessories to provide a watertight installation.

Shower base assemblies comply with ASTM E84. Shower base and wall panels are Glacier White.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Components

Install all components and fabricated units plumb, level, and rigid. Make field joints between solid surfacing material components using solid surfacing material manufacturer's approved seam adhesives, to provide a monolithic appearance with joints inconspicuous in the finished work. Attach metal or vitreous china sinks and lavatory bowls to counter tops using solid surfacing material manufacturer's recommended clear silicone sealant and mounting hardware. Install solid polymer sinks and bowls using a color-matched seam adhesive.

3.1.1.1 Loose Counter Top Splashes

Mount loose splashes in the locations noted on the drawings. Adhere loose splashes to the counter top with a color matched silicone sealant when the solid surfacing material components are solid colors. Use a clear silicone sealant to provide adhesion of particulate patterned solid surfacing material splashes to counter tops.

3.1.1.2 Wall Panels & Panel Systems

Installation of wall panels and system components to substrates must include the use of a specified panel adhesive. Use specified seam adhesive to adhere all solid surfacing material components to each other with the exception of expansion joints and inside corners. All inside corners and expansion joints between solid surfacing material components must be joined with specified silicone sealant. All joints between solid surfacing material components and non-solid polymer surfaces must be sealed with specified silicone sealant.

3.1.1.3 Shower Wall Panel System

Assemble and test drain piping for watertightness. Remove perimeter flange extruded polystyrene core material to closely fit piping. Apply edge reinforcements and gaskets. Use a 0.75 inch notched trowel to apply a bed of modified thin set mortar to receiving substrates. Set perimeter flanges within bedding. Seal the flange perimeter with weathertight

sealant. Attach the drain body and outlet to the shower base. Use a 0.75 inch notched trowel to apply a bed of modified thin set mortar to the exposed extruded polystyrene core of the perimeter flange. Prepare the drain outlet and receiving piping for a watertight fit. Set shower bases within bedding. Seal the shower base to flange joint with weathertight sealant. Remove excess sealant. Seal the shower base to wall joint with epoxy weld for a weathertight joint. Reference Wall Panels & Panel Systems for shower wall assemblies. Provide
watertight panel joints.

3.1.2 Silicone Sealant

Use specified silicone sealant to seal all expansion joints between solid surfacing material components and all joints between solid surfacing material components and other adjacent surfaces such as walls, floors, ceiling, and plumbing fixtures. Provide sealant bead smooth and uniform in appearance and minimum size necessary to bridge any gaps between the solid surfacing material and the adjacent surface. Provide continuous bead and run the entire length of the joint being sealed.

3.1.3 Plumbing

Make plumbing connections to sinks and lavatories.

3.2 CLEAN-UP

Components must be cleaned after installation and covered to protect against damage during completion of the remaining project items. Damaged components must be repaired or replaced at the Contractor's sole expense.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 06 82 14

DECORATIVE FIBERGLASS REINFORCED PLASTIC (FRP)

PART 1 GENERAL

This Section includes new fiberglass reinforced plastic (FRP) wall panels.

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2022) Nuts for General Applications: Machine Screw Nuts, and Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B18.6.2	(2020) Square Head Set Screws and Slotted Headless Set Screws (Inch Series)
ASME B18.6.3	(2013; R 2017) Machine Screws, Tapping Screws, and Machine Drive Screws (Inch Series)
ASME B18.21.1	(2009; R 2016) Washers: Helical Spring-Lock, Tooth Lock, and Plain Washers (Inch Series)
ASME B18.21.2M	(1999; R 2014) Lock Washers (Metric Series)

AMERICAN SOCIETY OF SAFETY PROFESSIONALS (ASSP)

ASSP A10.3	(2020) Safety Requirements for Powder-Actuated Fastening Systems American National Standard for Construction and Demolition Operations

ASTM INTERNATIONAL (ASTM)

ASTM A307	(2023) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM C1107/C1107M	(2020) Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)
ASTM D256	(2024) Standard Test Methods for Determining the Izod Pendulum Impact Resistance of Plastics
ASTM D430	(2006; R 2012) Standard Test Methods for

	Rubber Deterioration - Dynamic Fatigue
ASTM D570	(2022) Standard Test Method for Water Absorption of Plastics
ASTM D638	(2014) Standard Test Method for Tensile Properties of Plastics
ASTM D790	(2017) Standard Test Methods for Flexural Properties of Unreinforced and Reinforced Plastics and Electrical Insulating Materials
ASTM D1148	(2013; R 2018) Standard Test Method for Rubber Deterioration—Discoloration from Ultraviolet (UV) or UV/Visible Radiation and Heat Exposure of Light-Colored Surfaces
ASTM D2583	(2013a) Indentation Hardness of Rigid Plastics by Means of a Barcol Impressor
ASTM D3273	(2021) Standard Test Method for Resistance to Growth of Mold on the Surface of Interior Coatings in an Environmental Chamber
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E488/E488M	(2022) Standard Test Methods for Strength of Anchors in Concrete Elements

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.23	(Nov 2016) Ladders
29 CFR 1926	Safety and Health Regulations for Construction

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualifications of Manufacturer; G

SD-02 Shop Drawings

Installation Drawings; G

SD-03 Product Data

Anchorage Materials; G

Adhesives; G

Resins; G

Hardeners; G

Manufacturer's Sample Warranty

FRP Wall Paneling

SD-06 Test Reports

Ultraviolet Test Reports

Thermal Expansion Test Reports

Flame Spread Test Reports

SD-08 Manufacturer's Instructions

Manufacturer's Instructions

SD-09 Manufacturer's Field Reports

Manufacturer's Certification of Installation

SD-11 Closeout Submittals

Manufacturer's Warranty

1.3 QUALITY CONTROL

1.3.1 Qualifications of Manufacturer

Submit Qualifications Of Manufacturer documentation certifying that the Fiberglass Reinforced Plastic (FRP) manufacturer has a minimum of 10 years of experience in manufacturing FRP products.

Provide the manufacturer's sample warranty for all FRP products against defects in material and workmanship for a minimum of 1 year.

1.4 DELIVERY, HANDLING, AND STORAGE

Deliver all manufactured materials in original, unbroken pallets, packages, containers, or bundles bearing the label of the manufacturers, clearly marked and identified relative to the complete system. Provide all adhesives, resins and their catalysts and hardeners in clearly marked or noted crates or boxes. Store all manufactured materials in dry indoor facilities with a constant temperature range between 60 and 75 degrees F for 48 hours prior to installation.

Handle all materials to prevent abrasion, cracking, chipping, twisting, or other deformations, and other types of damage.

1.5 PROJECT CONDITIONS

a. Environmental Limitations: Building are to be fully enclosed prior to installation with sufficient heat (70°) and ventilation consistent with good working conditions for finish work

b. During installation and for not less than 48 hours before, maintain an ambient temperature and relative humidity within limits required by type of adhesive used and recommendation of adhesive manufacturer.

c. Provide ventilation to disperse fumes during application of adhesive as recommended by the adhesive manufacturer.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

2.1.1 Installation Drawings

Submit templates and erection and installation drawings indicating thickness, type, and dimensions. Show construction details, reinforcement, anchorage, and installation with relation to the building construction.

Include plans, elevations, sections, details, and attachments to other work. Indicate for installed products to comply with design loads.

2.1.2 Product Data

Submit the manufacturer's catalog data including two copies of manufacturer's specifications, load tables, dimension diagrams, and anchor details for the following items:

a. FRP Wall Paneling

b. Anchorage Materials

c. Adhesives

d. Resins

e. Hardeners

2.1.3 Design Requirements

Provide fiberglass reinforced thermosetting polyester resin panel sheets complying with ASTM D 5319.Provide FRP products that have a flame spread rating of 25 or less as specified in ASTM E84, Tunnel Test. Submit 3 copies of Flame Spread Test Reports to the Contracting Officer. Ensure that rails, posts, and kick plates are integrally pigmented yellow. Submit 3 copies of Ultraviolet Test Reports for FRP material, similar to the requirements of ASTM D1148 for rubber deterioration, and ASTM D430, to the Contracting Officer. Submit testing data relating to Thermal Expansion Test Reports.

Provide structural shapes in the guardrail system to meet minimum longitudinal mechanical properties as follows:

Tensile Strength	ASTM D638	- 8.0 x 10^3 psi

Tensile Modulus	ASTM D638	9.43 x 10^3 psi
Flexural Strength	ASTM D790	1.7 x 10^4 psi
Flexural Modulus	ASTM D790	6.0 x 10^5 psi
Water Absorption	ASTM D570	0.17%
Barcol Hardness (scratch resistance)	ASTM D2583	22
Izod Impact Strength	ASTM D256	7.0 ft. lbs.
Mold & Mildew	ASTM D3273	Pass

2.2 FABRICATION

Perform fabrication of the handrail post/rail connection such that the rails are unbroken and continuous through the post without the use of packs or splices. Install the bottom rail through the post at a prepared hole made to fit the outside dimensions of the rail, and the top rail fit into a machined, u-shaped pocket formed into the top of the post such that the rail is located at the center of the post. Radius all exposed corners to eliminate sharp edges. Join the rails to the post through a combination of bonding and riveting. Ensure that no sharp, protruding edges remain after assembly of the handrail. Space the posts no more than 72 inches apart. Attach post bases according to the construction contract drawings. Reinforce post bases to a height of 8 1/2 inches. Coat all field-fabricated and shop-fabricated cuts with a vinyl ester resin to provide maximum corrosion resistance.

2.3 MATERIALS

2.3.1 Fasteners

Provide Type 316 stainless-steel concealed fasteners, unless unavoidable or standard for railings indicated.

2.3.2 Anchors

Provide cast-in-place epoxy mechanical anchors, fabricated from corrosion-resistant materials with capability to sustain, without failure, a load equal to six times the design load imposed when installed in unit masonry and equal to four times the design load imposed when installed in concrete, as determined by testing as specified in ASTM E488/E488M.

2.3.3 Grout And Anchoring Cement

Provide factory-packaged, nonshrink, nonmetallic grout complying with ASTM C1107/C1107M; or water-resistant, nonshrink anchoring cement; recommended by the manufacturer for exterior use. Ensure that all other adhesives conform to the manufacturer's recommendations and instructions.

2.3.4 Component Connections

2.3.4.1 Lag Screws and Bolts

Provide lag screws and bolts conforming to ASME B18.2.1, of the type and grade best suited for the purpose.

2.3.4.2 Toggle Bolts

Provide toggle bolts conforming to ASME B18.2.1.

2.3.4.3 Bolts, Nuts, Studs, and Rivets

Provide bolts, nuts, studs, and rivets conforming to ASME B18.2.2 and ASTM A307.

2.3.4.4 Powder-Driven Fasteners

Follow safety provisions of ASSP A10.3 .

2.3.4.5 Screws

Provide screws conforming to ASME B18.2.1, ASME B18.6.2, and ASME B18.6.3.

2.3.4.6 Washers

Provide plain washers conforming to ASME B18.21.1. Provide beveled washers for American Standard beams and channels, square or rectangular, tapered in thickness, and smooth. Provide lock washers conforming to ASME B18.21.2M and ASME B18.21.1.

PART 3 EXECUTION

3.1 INSTALLATION

Install items in accordance with 29 CFR 1910.23 and 29 CFR 1926 at locations indicated, according to the manufacturer's instructions. Verify all measurements and take all field measurements necessary before fabrication. Include all materials and parts necessary to complete each item, even though such work is not definitely shown or specified. Perform cutting, drilling, and fitting required for installing railings. Set railings accurately in location, alignment, and elevation. Submit 2 signed copies of Manufacturer's Certification of Installation.

3.1.1 Anchorage, Fastenings, and Connections

Provide anchorage where necessary for fastening miscellaneous FRP items securely in place. Include for anchorage not otherwise specified or indicated slotted inserts, expansion shields, and powder-driven fasteners, when approved for concrete; toggle bolts and through-bolts for masonry; machine and carriage bolts for steel; through-bolts and screws. Conceal fastenings where practicable.

3.1.2 Workmanship

Ensure that FRP work is well formed to shape and size, with sharp lines and angles and true curves. Ensure that drilling and punching produces clean true lines and surfaces. Ensure that exposed surfaces of work-in-place to have smooth finishes. Mill joints where tight fits are

required. Ensure that corner joints are coped or mitered, well formed, and in true alignment. Accurately set work to established lines and elevations and securely fasten in place. Ensure that the installation is in accordance with the manufacturer's installation instructions and the approved drawings, cuts, and details.

3.2 CLOSEOUT ACTIVITIES

3.2.1 Warranty

Submit 2 signed copies of the Manufacturer's Warranty 30 calendar days before final inspection.

3.2.2 Manufacturer's Instructions

Submit the manufacturer's instructions for shipping and handling, and procedures for erection, care, and maintenance upon completion of installation.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 21 13

BOARD AND BLOCK INSULATION
08/23, CHG 1: 08/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C272/C272M	(2018; R 2024) Standard Test Method for Water Absorption of Core Materials for Sandwich Constructions
ASTM C578	(2023) Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation
ASTM C930	(2019; R 2025) Standard Classification of Potential Health and Safety Concerns Associated with Thermal Insulation Materials and Accessories
ASTM D1621	(2016; R2023) Standard Test Method for Compressive Properties of Rigid Cellular Plastics
ASTM D1709	(2024) Standard Test Methods for Impact Resistance of Plastic Film by the Free-Falling Dart Method
ASTM D3833/D3833M	(1996; R 2019) Standard Test Method for Water Vapor Transmission of Pressure-Sensitive Tapes
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E96/E96M	(2024a) Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials
ASTM E154/E154M	(2008; R 2025) Standard Test Methods for Water Vapor Retarders Used in Contact with Earth Under Concrete Slabs, on Walls, or as Ground Cover
ASTM E1745	(2017; R 2023) Standard Specification for Water Vapor Retarders Used in Contact with Soil or Granular Fill under Concrete Slabs

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC (2024) International Building Code

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Manufacturer's Standard Details; G

SD-03 Product Data

Environmental Data for Materials; G

Block or Board Insulation; G

Vapor Retarder; G

Pressure Sensitive Tape; G

Accessories including sealants; G

Recycled Content for Block or Board Insulation; S

SD-07 Certificates

Indoor Air Quality For Block Or Board Insulation; S

SD-08 Manufacturer's Instructions

Insulation Installation and Handling

Adhesive

SD-11 Closeout Submittals

Draft Guarantee; G

Final Guarantee; G

Draft Warranty; G

Final Warranty; G

1.3 MANUFACTURER'S DETAILS

Submit manufacturer's standard details indicating methods of attachment and spacing, transition and termination details, and installation details. Include verification of existing conditions.

1.4 PRODUCT DATA

Include environmental data for materials descriptions, recommendations for product shelf life and precautions for flammability and toxicity. Include

data to verify compatibility of sealants with insulation.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver materials to the site in original sealed wrapping bearing manufacturer's name and brand designation, specification number, type, grade, R-value, and class. Store and handle to protect from damage. Do not allow insulation materials to become wet, soiled, crushed, or covered with ice or snow. Comply with manufacturer's recommendations for handling, storing, and protecting of materials before and during installation.

1.5.2 Storage

Inspect materials delivered to the site for damage and store out of weather in manufacturer's original packaging. Store only in dry locations, not subject to open flames or sparks, and easily accessible for inspection and handling. Keep materials wrapped and separated from off-gassing materials (such as drying paints and adhesives). Do not use materials that have visible moisture or biological growth. Comply with manufacturer's recommendations for handling, storage, and protection of materials before and during installation.

1.6 SAFETY PRECAUTIONS

1.6.1 Other Safety Considerations

Comply with the safety requirements of ASTM C930.

1.7 SPECIAL WARRANTIES

1.7.1 Guarantee

Guarantee insulation installation against failure due to ultraviolet light exposure for a period of three years from the date of Beneficial Occupancy or Substantial Completion. Submit draft guarantee and final guarantee in accordance with Sections 01 78 00 CLOSEOUT SUBMITTALS.

1.7.2 Warranty

Provide manufacturer's material warranty for all system components for a period of three years from the date of Beneficial Occupancy or Substantial Completion. Submit draft warranty and final warranty in accordance with Sections 01 78 00 CLOSEOUT SUBMITTALS.

PART 2 PRODUCTS

2.1 BLOCK OR BOARD INSULATION

Provide insulation with the following physical properties and in accordance with the following standards:

a. Extruded Preformed Cellular Polystyrene (XPS): ASTM C578 REV A, TypeIV

2.1.1 Thermal Resistance

Provide a wall R-value of 15 and a perimeter of slab R-value of 15.

2.1.2 Fire Protection Requirements

a. Flame spread index of 75 or less when tested in accordance with ASTM E84.

b. Smoke developed index of 150 or less when tested in accordance with ASTM E84.

c. Provide insulated assemblies in accordance ICC IBC Chapter Fire and Smoke Protection Features.

2.1.3 Other Material Properties

Provide thermal insulating materials with the following properties:

a. Rigid cellular plastics: Compressive Resistance at Yield: Not less than 25 pounds per square inch (psi) when measured according to ASTM D1621.

b. Water Vapor Permeance: Not more than 1.5 Perms or less when measured according to ASTM E96/E96M, desiccant method, in the thickness required to provide the specified thermal resistance, including facings, if any.

c. Water Absorption: Not more than 0.3 percent by total immersion, by volume, when measured according to ASTM C272/C272M.

2.1.4 Recycled Materials

Provide thermal insulation containing recycled materials to the extent practicable, provided that the material meets all other requirements of this section. The minimum required recycled material contents (by weight, not volume) are:

Phenolic Rigid Foam:	5 percent

Provide data identifying percentage of recycled content for block or board insulation.

2.1.5 Indoor Air Quality

Provide certification of indoor air quality for block or board insulation.

2.1.6 Prohibited Materials

Do not provide materials containing asbestos.

2.2 VAPOR RETARDER

2.2.1 Vapor Retarder under Floor Slab

Heavy duty vapor barrier is a coextruded polyolefin membrane that controls moisture, radon, methane, oil byproducts and sulfates complying with ASTM E1745, Class A. Sheeting weighs 7.14 pounds per 100 square feet and has a 15 mil thickness. Furnish the recommended seaming and hole patch tape.

a. Water vapor permeance: 0.2 Perm or less when tested in accordance with ASTM E96/E96M.

b. Puncture resistance: Minimum of 2200 grams when tested according to ASTM D1709.

c. Tensile strength: Minimum of 45.0 lbf/in. when tested in accordance with ASTM E154/E154M.

2.3 PRESSURE SENSITIVE TAPE

As recommended by manufacturer of vapor retarder(s). Match water vapor permeance rating for each vapor retarder specified. Provide tape in accordance with ASTM D3833/D3833M.

2.4 ACCESSORIES

2.4.1 Adhesive

As recommended by insulation manufacturer.

2.4.2 Mechanical Fasteners

Corrosion resistant fasteners as recommended by the insulation manufacturer.

PART 3 EXECUTION

3.1 EXISTING CONDITIONS

Prior to installation, ensure all areas that will be in contact with the insulation are dry and free of projections that could cause voids, compressed insulation, or punctured vapor retarders. For foundation perimeter or under slab applications, check that subsurface fill is flat, smooth, dry, and well tamped. Do not proceed with installation if moisture or other conditions are present and notify the Contracting Officer of such conditions. Do not proceed with the work until conditions have been corrected and verified to be dry.

3.2 PREPARATION

3.2.1 Blocking Around Heat Producing Devices

Provide noncombustible blocking at all spaces between heat producing devices and the floors through which they pass.

3.3 INSTALLATION

3.3.1 Insulation Installation and Handling

Provide insulation in accordance with the manufacturer's printed installation instructions. Keep material dry and free of extraneous materials.

3.3.2 Electrical Wiring

Do not install insulation in a manner that would enclose electrical conductors, that are not installed in conduit, between two layers of insulation.

3.3.3 Continuity of Insulation

Butt tightly against adjoining boards and obstructions. Provide continuity and integrity of insulation at corners, walls and floors. Avoid creating thermal bridges and voids. Provide and verify continuity of insulative barrier throughout the building enclosure.

3.3.4 Coordination

Verify final installed insulation thicknesses comply with thicknesses indicated and with the approved insulation submittal(s).

3.4 INSTALLATION ON WALLS

3.4.1 Installation on Masonry Walls

Apply board directly to masonry with adhesive or fasteners. Fit between obstructions without impaling board on ties or anchors. Apply in parallel courses with joints breaking midway over course below. Place boards in moderate contact with adjoining insulation without forcing and without gaps. Cut and shape as required to fit around wall penetrations, projections or openings to accommodate conduit or other utilities. Seal around cutouts with sealant. Install insulation in wall cavities so that it leaves at least a nominal one inch air space outside of the insulation to allow for cavity drainage.

3.4.2 Adhesive Attachment to Concrete and Masonry Walls

Apply adhesive to wall and completely cover wall with insulation.

a. Spot method: Provide at least six spots having diameter of approximately 4 inches, located at each corner and mid points of each of the longer sides of each board.

b. Use only full back method for pieces of one square foot or less.

c. Butt all edges of insulation and seal edges with tape.

3.4.3 Mechanical Attachment on Concrete and Masonry Walls

Cut insulation to cover walls. Apply adhesive to wall and set clip or other mechanical fastener in adhesive as recommended by manufacturer. After curing of adhesive, install insulation over fasteners and bend split prongs to provide a flush condition with the insulation. Butt all edges of insulation and seal with tape.

3.5 PERIMETER AND UNDER SLAB INSULATION

Install perimeter thermal insulation where heated spaces are adjacent to exterior walls, slab edges in slab-on-grade, or floating slab construction.

3.5.1 Manufacturer's Instructions

Layout insulation, tape edges, provide vapor retarder and other required accessories to protect against vermin, insects, and damage in accordance with manufacturer's printed instructions.

3.5.2 Insulation on Vertical Surfaces

Provide thermal insulation below slab and on edges of slabs-on-grade. Fasten insulation with adhesive or mechanical fasteners.

3.5.3 Insulation Under Slab

Provide insulation horizontally under entire slab on grade Turn insulation up at slab edge, and extend full height of slab. Install insulation on top of vapor retarder and turn retarder up over the outside edge of insulation to top of slab.

3.6 VAPOR RETARDER

Apply vapor retarder continuous across all surfaces. Overlap all joints at least 6 inches and seal with pressure sensitive tape. Seal at sills, header, windows, doors and utility penetrations. Repair punctures or tears with pressure sensitive tape.

3.7 ACCESS PANELS AND DOORS

Attach insulation to all access panels and all access doors in insulated floors. Use insulation with same R-Value as that for the floor in which each panel occurs.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 21 16

MINERAL FIBER BLANKET INSULATION
11/11, CHG 4: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C665	(2017) Standard Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing
ASTM C930	(2019; R 2025) Standard Classification of Potential Health and Safety Concerns Associated with Thermal Insulation Materials and Accessories
ASTM D5359	(2015) Standard Specification for Glass Cullet Recovered from Waste for Use in Manufacture of Glass Fiber
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.134	Respiratory Protection

UL SOLUTIONS (UL)

UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Blanket Insulation

Recycled Content for Insulation Materials; S

Accessories

SD-07 Certificates

Indoor Air Quality for Insulation Materials; S

SD-08 Manufacturer's Instructions

Insulation

1.3 CERTIFICATIONS

Submit required indoor air quality certifications and validations in one submittal package.

1.3.1 Insulation Products

Provide product certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification by other third-party programs. Provide current product certification from certification body.

1.3.2 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 Delivery

Deliver materials to site in original sealed wrapping bearing manufacturer's name and brand designation, specification number, type, grade, R-value, and class. Store and handle to protect from damage. Do not allow insulation materials to become wet, soiled, crushed, or covered with ice or snow. Comply with manufacturer's recommendations for handling, storing, and protecting of materials before and during installation.

1.4.2 Storage

Inspect materials delivered to the site for damage; unload and store out of weather in manufacturer's original packaging. Store only in dry locations, not subject to open flames or sparks, and easily accessible for inspection and handling.

1.5 SAFETY PRECAUTIONS

1.5.1 Respirators

Provide installers with dust/mist respirators, training in their use, and protective clothing, all approved by National Institute for Occupational

Safety and Health (NIOSH)/Mine Safety and Health Administration (MSHA) in accordance with 29 CFR 1910.134.

1.5.2 Other Safety Concerns

Consider other safety concerns and measures as outlined in ASTM C930.

PART 2 PRODUCTS

2.1 Acoustical BLANKET INSULATION

ASTM C665, Type I, blankets without membrane coverings and a flame spread rating of 25 or less and a smoke developed rating of 50 or less when tested in accordance with ASTM E84.

2.1.1 Thermal Resistance Value (R-VALUE)

The R-Value is 3 per inch.

2.1.2 Recycled Materials

Provide insulation materials containing the following minimum percentage of recycled material content by weight:

Fiberglass: 20 percent glass cullet complying with ASTM D5359

Provide data identifying percentage of recycled content for insulation materials.

2.1.3 Prohibited Materials

Do not provide asbestos-containing materials.

2.1.4 Reduced Volatile Organic Compounds (VOC) for Insulation Materials

Provide certification of indoor air quality for insulation materials.

2.2 Fire BLANKET INSULATION

Rated wall assembly sound attenuation fire blankets, or mineral wool, consists of inorganic fibers derived from basalt, bonded and formed to a thickness and a width corresponding to the stud spacing and cavity depth. Insulation complies with ASTM C 665, Type I and ASTM E 136, Non Combustible. Material has a density of 2.5 PCF, NRC of 1.2 for a 4 inch thickness, and an R-value of 3.7 per inch. When tested in accordance with ASTM E 84, material has a flame spread rating of 0 and smoke developed rating of 0.

2.3 ACCESSORIES

2.3.1 Mechanical Fasteners

Corrosion resistant fasteners as recommended by the insulation manufacturer.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Insulation

Install and handle insulation in accordance with manufacturer's instructions. Keep material dry and free of extraneous materials. Any materials that show visual evidence of biological growth due to presence of moisture must not be installed on the building project. Ensure personal protective clothing and respiratory equipment is used as required. Observe safe work practices.

Place insulation in permanent contact with the six surfaces that enclose each cavity, and provide a thickness and width corresponding to the cavity depth and shape. Specified insulation R-values are minimums. Provide greater thicknesses and R-values to fully fill cavities without compression.

3.1.1.1 Electrical wiring

Do not install insulation in a manner that would sandwich electrical wiring between two layers of insulation.

3.1.1.2 Continuity of Insulation

Install blanket insulation to butt tightly against adjoining blankets and to studs and any obstructions. Provide continuity and integrity of insulation at corners, and floor. Avoid creating thermal bridges.

3.1.1.3 Insulation without Affixed Vapor Retarder

Provide snug friction fit to hold insulation in place. Stuff pieces of insulation into cracks between trusses, joists, studs and other framing, such as at attic access doors, door and window heads, jambs, and sills, band joists, and headers.

3.1.1.4 Sizing of Blankets

Provide only full width blankets when insulating between studs. Size width of blankets for a snug fit where trusses, joists or studs are irregularly spaced.

-- End of Section --

SECTION 07 27 10.00 10

BUILDING AIR BARRIER SYSTEM
08/19, CHG 1: 02/20

PART 1 GENERAL

1.1 SUMMARY

This Section specifies the construction and quality control of the installation of an air barrier system. Construct the air barrier system indicated, taking responsibity for the means, methods, and workmanship of the installation of the air barrier system. The air barrier must be contiguous and connected across all surfaces of the enclosed air barrier envelope indicated. The maximum leakage requirements of individual air barrier components and materials are specified in the other specification sections covering these items.

This section also defines the maximum allowable leakage of the final air barrier system. The workmanship must be adequate to meet the maximum allowable leakage requirements of this specification. Test the assembled air barrier system to demonstrate that the building envelope is properly sealed and insulated. Passing the air barrier system leakage test and thermography test will result in system acceptance. Conform air barrier system leakage and thermography testing and reporting to the requirements of Section 01 91 19 BUILDING ENCLOSURE COMMISSIONING.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referenced within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D4541	(2022) Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers
ASTM E96/E96M	(2024a) Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials
ASTM E2178	(2021a) Standard Test Method for Determining Air Leakage Rate and Calculation of Air Permeance of Building Materials
ASTM E2357	(2018) Standard Test Method for Determining Air Leakage Rate of Air Barrier Assemblies

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 285	(2023) Standard Fire Test Method for Evaluation of Fire Propagation Characteristics of Exterior Wall Assemblies Containing Combustible

Components

1.3 DEFINITIONS

The following terms as they apply to this section:

1.3.1 Air Barrier Accessory

Products designated to maintain air tightness between air barrier materials, air barrier assemblies and air barrier components, to fasten them to the structure of the building, or both (e.g., sealants, tapes, backer rods, transition membranes, fasteners, strapping, primers).

1.3.2 Air Barrier Assembly

The combination of air barrier materials and air barrier accessories that are designated and designed within the environmental separator to act as a continuous barrier to the movement of air through the environmental separator.

1.3.3 Air Barrier Component

Pre-manufactured elements such as windows, doors, dampers and service elements that are installed in the environmental separator.

1.3.4 Air Barrier Envelope

The combination of air barrier assemblies and air barrier components, connected by air barrier accessories that are designed to provide a continuous barrier to the movement of air through an environmental separator. There may be more than one air barrier envelope in a single building. Also known as Air Barrier System.

1.3.5 Air Barrier Material

A building material that is designed, tested and/or produced to provide the primary resistance to airflow through an air barrier assembly of a wall system.

1.3.6 Air Barrier System

Same as AIR BARRIER ENVELOPE.

1.3.7 Air Leakage Rate

The rate of airflow (CFM) driven through a unit surface area (sq.ft.) of an assembly or system by a unit static pressure difference (Pa) across the assembly. (example: 0.25 CFM/sq.ft. @ 75 Pa)

1.3.8 Air Leakage

The total airflow (CFM) driven through the air barrier system by a unit static pressure difference (Pa) across the air barrier envelope. (example: 6500 CFM @ 75 Pa)

1.3.9 Air Permeance

The tested rate of airflow (CFM) through a unit area (sq.ft.) of a material driven by unit static pressure difference (Pa) across the

material (example: 0.004 CFM/sq.ft. @ 75 Pa) as established by ASTM E2178.

1.3.10 Environmental Separator

The parts of a building that separate the controlled interior environment from the uncontrolled exterior environment, or that separate spaces within a building that have dissimilar environments. Also known as the Control Layer.

1.3.11 Vapor Permeance

Vapor permeance is separated into three classes based on the water vapor permeance of a material as tested via ASTM E96/E96M

Class I Vapor Barrier/Retarder	0.1 perm or less
Class II Vapor Barrier/Retarder	0.1 perm to 1.0 perm
Class III Vapor Barrier/Retarder	1.0 perm to 10 perm

1.4 PREPARATORY PHASE OR PRECONSTRUCTION CONFERENCE

Organize pre-construction conferences between the air barrier inspector and the sub-contractors involved in the construction of or penetration of the air barrier system to discuss where the work of each sub-contractor begins and ends, the sequence of installation, and each sub-contractor's responsibility to ensure airtight joints, junctures, penetrations and transitions between materials. Discuss the products, and assemblies of products specified in the different sections to be installed by the different sub-contractors.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Air Barrier System Shop Drawings; G, Manufacturer produced warranted air barrier system

SD-03 Product Data

Air Barrier System Product Data; G

SD-04 Samples

Material Samples For Air Barrier System; G

SD-05 Design Data

Design Data And Calculations For The Air Barrier System; G, Manufacturer produced warranted air barrier system

SD-06 Test Reports

Design Review Report; G

Testing and Inspection; G

SD-07 Certificates

Air Barrier Inspector; G

1.6 AIR BARRIER ENVELOPE SURFACE AREA AND LEAKAGE REQUIREMENTS

The building air barrier systems must meet the following leakage requirements. The allowable leakage rate and the maximum leakage are at a differential test pressure of 75 Pa.

Air Barrier Envelope 1, Building A1	
Surface Area	184,340 square feet
Architectural Only Test:	
Allowable leakage rate	0.25 CFM/sq.ft
Maximum leakage	46,085 total CFM
Architectural Plus HVAC System Test:	
Allowable leakage rate	0.30 CFM/sq.ft
Maximum leakage	55,302 total CFM

Air Barrier Envelope 2, Buildin A2-1	
Surface Area	138,945 square feet
Architectural Only Test:	
Allowable leakage rate	0.25 CFM/sq.ft
Maximum leakage	34,736 total CFM
Architectural Plus HVAC System Test:	
Allowable leakage rate	0.30 CFM/sq.ft
Maximum leakage	41,684

Air Barrier Envelope 4, Building A2-2	
Surface Area	138,945 square feet
Architectural Only Test:	

Allowable leakage rate	0.25 CFM/sq.ft
Maximum leakage	34,736 total CFM
Architectural Plus HVAC System Test:	
Allowable leakage rate	0.30 CFM/sq.ft
Maximum leakage	41,684

Air Barrier Envelope 4, Building A3	
Surface Area	44,203 square feet
Architectural Only Test:	
Allowable leakage rate	0.25 CFM/sq.ft
Maximum leakage	11,051 total CFM
Architectural Plus HVAC System Test:	
Allowable leakage rate	0.30 CFM/sq.ft
Maximum leakage	13,261

1.7 AIR BARRIER INSPECTOR

Employ a designated Air Barrier Inspector on this project. The Air Barrier Inspector performs a Design Review, oversees quality control testing specified in these specifications, performs quality control air barrier inspection as specified, interfaces with the designer and product manufacturer's representatives to assure all installation requirements are met, and verifies that the constructed work is in accordance with both the manufacturer's recommendations for products used, the content of this specification and other contract drawings or docouments. Qualification for the Air Barrier Inspector are as follows:

a. Training and certification as an Air Barrier Auditor from the Air Barrier Association of America (ABAA) or other third party air barrier association.

b. Or, provide documentation in resume format that demonstrates that the individual proposed has the experience, knowledge, skills and abilities to fulfill the above stated duties as the air barrier inspector.

c. It is acceptable that this individual be employed by the firm who will be performing the building pressurization test or another independent third party entity, provided they meet the above requirements but is not a member of the installing contractor or firm.

Provide copies of Air Barrier Inspector qualifications 30 days after Notice to Proceed.

1.8 DESIGN REVIEW

Review the Contract Plans and Specifications and advise the Contracting Officer of any deficiencies that would prevent the construction of an effective air barrier system. Provide a Design Review Report individually listing each deficiency and the corresponding proposed corrective action necessary for proper air barrier system. Provide copies of the Design Review Report not later than 14 days after approval of the Air Barrier Inspector Qualifications. Submit design data and calculations for the Air Barrier System for a manufacturer produced warranted air barrier system.

PART 2 PRODUCTS

2.1 AIR BARRIER

Provide air barrier system of compatible parts from one or several manufacturers coordinated by the contractor or provide a single warranted system provided by a primary manufacturer. The air barrier system as part of a tested exterior wall assembly must meet the conditions of acceptance as tested in accordance with NFPA 285. Materials used for roof assembly air barrier must conform to the appropriate UL and FM wind and fire requirements for the specified roof assemblies.

If a complete air barrier system from a single manufacturer is utilized, whether warranted on not warranted, the air barrier system must conform to ASTM E2357.

Materials in the following categories as used in the air barrier system or assembly of the exterior wall system are tested and are required to conform to ASTM E2178: Self-adhered sheet membranes, fluid applied membranes, spray polyurethane foam, mechanically fastened commercial building wrap, factory bonded membranes to sheathing, and adhesive backed commercial building wrap and accessory products.

Other materials used as an air barrier such as concrete, glass, wood, metal or gypsum board may or may not conform to ASTM E2178 but are acceptable provided that when integrated into the air barrier system or assemblies that they are not subject to material or environmental induced degradation in their final produced state and once incorporated in the permanent construction.

All materials used must be identifiable through manufacturer testing data and/or literature to be compatible with all the attached or adjoining materials or substrates used in the system.

Provide Air Barrier System Shop Drawings, Material Samples for Air Barrier System and Air Barrier System Product Data.

PART 3 EXECUTION

3.1 QUALITY CONTROL

3.1.1 Documentation and Reporting

Document the entire installation process on daily job site reports. These reports include information on the Installer, substrates, substrate preparation, products used, ambient and substrate temperature, the location of the air barrier installation, the results of the quality control procedures, and testing results.

3.1.2 Quality Control Testing And Inspection

Conduct the following tests and inspections as applicable in the presence of the Contracting Officer during installation of the air barrier system, and submit quality control reports as indicated below.

a. Provide a Daily Report of Observations with a copy to the Contracting Officer.

b. Inspect to assure continuity of the air barrier system throughout the building enclosure and that all gaps are covered, the covering is structurally sound, and all penetrations are sealed allowing for no infiltration or exfiltration through the air barrier system.

c. Inspect to assure structural support of the air barrier system to withstand design air pressures.

d. Inspect to assure masonry surfaces receiving air barrier materials are smooth, clean, and free of cavities, protrusions and mortar droppings, with mortar joints struck flush or as required by the manufacturer of the air barrier material.

e. Inspect and test to assure site conditions for application temperature, and dryness of substrates are within guidelines.

f. Inspect to assure substrate surfaces are properly primed if applicable and in accordance with manufacturer's instructions. Priming must extend at least 2 inches beyond the air barrier material to make it obvious that the primer was applied to the substrate before the air barrier material.

g. Inspect to assure laps in materials are at least a 2-inch minimum, shingled in the correct direction or mastic applied in accordance with manufacturer's recommendations, and with no fishmouths.

h. Inspect to assure that a roller has been used to enhance adhesion. Identify any defects such as fishmouths, wrinkles, areas of lost adhesion, and improper curing. Note the intended remedy for the deficiencies.

i. Measure application thickness of liquid applied materials to assure that manufacturer's specifications for the specific substrate are met.

j. Inspect to assure that the correct materials are installed for compatibility.

k. Inspect to assure proper transitions for change in direction and structural support at gaps.

l. Inspect to assure proper connection between assemblies (membrane and sealants) for cleaning, preparation and priming of surfaces, structural support, integrity and continuity of seal.

m. Perform adhesion tests for fluid-applied and self-adhered air barrier membranes to assure that the manufacturer's specified adhesion strength properties are met. Determine the bond strength of coatings to substrate in accordance with ASTM D4541.

n. Provide cohesion tests for spray polyurethane foam (SPF). Perform adhesion tests as follows: Using a coring tool remove a sample and determine the relative adhesion quality of the foam. If the foam is hard to remove and leaves small bits of foam on the substrate it is called cohesive foam failure and is considered the best adhesion. If the foam comes away from the substrate with some force but is clean, it is called a mechanical bond. If it comes away easily from the substrate, the adhesion is poor. Cohesive foam failure and a good mechanical bond are acceptable.

o. Provide written test reports of all tests performed.

3.2 REPAIR AND PROTECTION

Upon completion of inspection, testing, sample removal and similar services, repair damaged construction and restore substrates, coatings and finishes. Protect construction exposed by or for quality control service activities, and protect repaired construction.

-- End of Section --

SECTION 07 27 26

FLUID-APPLIED MEMBRANE AIR BARRIERS
08/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR BARRIER ASSOCIATION OF AMERICA (ABAA)

ABAA Accreditation	Accreditation
ABAA QAP	Quality Assurance Program

ASTM INTERNATIONAL (ASTM)

ASTM C1305/C1305M	(2016) Standard Test Method for Crack Bridging Ability of Liquid-Applied Waterproofing Membrane
ASTM D412	(2016; R 2021) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D4263	(1983; R 2018) Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D4541	(2022) Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers
ASTM D5590	(2017; R 2021) Standard Test Method for Determining the Resistance of Paint Films and Related Coatings to Fungal Defacement by Accelerated Four-Week Agar Plate Assay
ASTM E96/E96M	(2024a) Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials
ASTM E283/E283M	(2019) Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Skylights, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E331	(2000; R 2023) Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference
ASTM E2178	(2021a) Standard Test Method for

	Determining Air Leakage Rate and Calculation of Air Permeance of Building Materials
ASTM E2357	(2018) Standard Test Method for Determining Air Leakage Rate of Air Barrier Assemblies

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 285	(2023) Standard Fire Test Method for Evaluation of Fire Propagation Characteristics of Exterior Wall Assemblies Containing Combustible Components

1.2 RELATED REQUIREMENTS

Coordinate the requirements of other building enclosure sections to provide a complete building air barrier system. Submit all materials, components and assemblies of the air barrier system together as one complete submittal package.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualifications of Manufacturer; G

Qualifications of Installer; G

SD-02 Shop Drawings

Fluid-Applied Membrane Air Barrier Shop Drawings; G

SD-03 Product Data

Fluid-Applied Membrane Air Barrier; G

Transition Membrane; G

Primers, Adhesives, and Mastics; G

Reinforcement; G

Safety Data Sheets; G

SD-06 Test Reports

Capillary Moisture Test; G

Field Peel Adhesion Test; G

Flame Propagation of Wall Assemblies; G

Site Inspections Reports; G

SD-08 Manufacturer's Instructions

Fluid-Applied Membrane Air Barrier Manufacturer's Printed Instructions; G

Primers, Adhesives, and Mastics Printed Manufacturer's Instructions; G

1.4 MISCELLANEOUS REQUIREMENTS

For fluid-applied membrane air barriers provide the following:

1.4.1 Shop Drawings

Submit fluid-applied membrane air barrier shop drawings showing locations and extent of barrier assemblies, transition membranes, details of all typical conditions, intersections with other envelope assemblies and materials, and membrane counterflashings. Show details for bridging of gaps in construction, treatment of inside and outside corners, expansion joints, methods of attachment of materials covering the self-adhered barrier without compromising the barrier. Indicate how miscellaneous penetrations such as conduit, pipes, electric boxes, brick ties, and similar items will be sealed.

1.4.2 Product Data

Submit manufacturer's technical data indicating compliance with performance and environmental requirements. Submit fluid-applied membrane air barrier manufacturer's printed instructions for evaluating, preparing, and treating substrates, temperature and other limitations of installation conditions, safety requirements for installation, and Safety Data Sheets. Also, submit primers, adhesives and mastics printed manufacturer's instructions for installation conditions and safety requirements. Indicate flame and smoke spread ratings for all products.

1.4.3 Test Reports

Submit test reports indicating that capillary moisture tests and field peel adhesion tests on all substrate materials have been performed and the changes made, if required, in order to achieve successful and lasting adhesion. Submit test reports for flame propagation of wall assemblies tested in accordance with NFPA 285.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver and store materials in sufficient quantity to allow for uninterrupted flow of work. Inspect materials delivered to the site for damage and store out of weather. Deliver materials to the jobsite in their original unopened packages, clearly marked with the manufacturer's name, brand designation, description of contents, and shelf life of containerized materials. Store and handle to protect from damage.

1.5.2 Storage

Inspect materials delivered to the site for damage; unload and store out of weather in manufacturer's original packaging. Store only in dry locations, not subject to open flames or sparks, and easily accessible for inspection and handling. Protect stored materials from direct sunlight.

1.6 CAPILLARY MOISTURE TEST

Perform a capillary moisture test by plastic sheet method in accordance with ASTM D4263 on the substrate materials. Perform test after curing period as recommended by the air barrier manufacturer. Record mode of failure and area which failed in accordance with ASTM D4263. Once the air barrier material manufacturer has established a minimum adhesion or moisture level for the product on the particular substrate, indicate on the inspection report whether this requirement has been met. Where the manufacturer has not declared a minimum adhesion or moisture value for their product and substrate combination, the inspector must record actual values.

1.7 FIELD PEEL ADHESION TEST

Perform a field peel adhesion test. Test the applied product for adhesion in accordance with manufacturer's recommendations. Perform test after curing period recommended by the manufacturer. Record mode of failure and area which failed in accordance with ASTM D4541. When the manufacturer has established a minimum adhesion level for the product on the particular substrate, the inspection report must indicate whether this requirement has been met. Where the manufacturer has not declared a minimum adhesion value for their product/substrate combination, the inspector must record actual values.

1.8 AIR BARRIER TESTING

Perform air barrier testing in accordance with accepted practices.

1.9 QUALITY ASSURANCE

1.9.1 Qualifications of Manufacturer

Submit documentation verifying that manufacturer of fluid-applied membrane air barrier is currently accredited by the Air Barrier Association of America (ABAA Accreditation https://www.airbarrier.org/).

1.9.2 Qualifications of Installer

Submit documentation verifying that installers of the fluid-applied membrane air barrier are currently certified in accordance with the ABAA QAP Quality Assurance Program (https://www.airbarrier.org/qap/).

1.10 PRECONSTRUCTION MEETING

Conduct a preconstruction meeting a minimum of two weeks prior to commencing work specified in this specification Section. Agenda must include, at a minimum, sequence of construction, coordination with substrate preparation, materials approved for use, compatibility of materials, coordination with installation of adjacent and covering materials, and details of construction. Attendance is required by representatives of related trades including covering materials, substrate

materials, adjacent materials, and materials and components of the fluid-applied membrane air barrier.

1.11 ENVIRONMENTAL CONDITIONS

1.11.1 Temperature

Install fluid-applied membrane air barrier within the range of ambient and substrate temperatures as recommended in writing by the fluid-applied membrane air barrier manufacturer. Do not apply fluid-applied membrane air barrier to a damp or wet substrate. Do not apply during inclement weather or when ice, frost, surface moisture, or visible dampness is present on surfaces to be covered, or when precipitation is imminent.

1.11.2 Exposure to Weather

Protect fluid-applied membrane air barrier products from direct exposure to rain, snow, sunlight, mist, and other extreme weather conditions. Replace, at no additional cost to the Government, barrier products that have been exposed to ultraviolet (sun)light longer than allowed by manufacturer's written requirements.

PART 2 PRODUCTS

2.1 FLUID-APPLIED MEMBRANE AIR BARRIER

Provide a fluid-applied, vapor retarding, air barrier. This barrier must exhibit no visible water leakage when tested in accordance with ASTM E331 and must perform as a liquid water drainage plane with thru-wall flashing to discharge incidental condensation and water penetration to the exterior of the building enclosure. Provide products suitable for use within temperature ranges specified by manufacturer for the location of the project. Install fluid applied membranes on vertical gypsum sheathing substrates.

2.1.1 Physical Properties

a. Air Permeance (ASTM E2178): less than 0.004 CFM per sf at 1.57 psf.

b. Air Leakage (ASTM E2357, ASTM E283/E283M): Less than 0.04 CFM per sf at 1.57 psf at one inch.

c. Water Vapor Permeance (Vapor Impermeable Membrane) (ASTM E96/E96M, desiccant method A): 0.1 perms or less.

d. Pull Adhesion (ASTM D4541): Not less than 15 psi.

e. Elongation (ASTM D412): Not less than 300 percent.

f. Low temperature Flexibility and Crack Bridging (ASTM C1305/C1305M): Pass at minus 15 degrees F.

g. Solids by Volume: minimum 50 percent.

h. Flame propagation of wall assemblies (NFPA 285): Pass

i. Resistance to Mold, Mildew and Fungal Growth (ASTM D5590): 0, No growth.

2.2 PRIMERS, ADHESIVES, AND MASTICS

Provide primers, adhesives, mastics, sealants and other accessories as recommended by manufacturer of fluid-applied membrane air barrier for a complete installation.

2.3 TRANSITION MEMBRANE

Provide the recommended transition membranes.

2.4 SHEET METAL FLASHING

Provide as specified in Section 07 60 00 FLASHING AND SHEET METAL.

2.5 JOINT SEALANTS

Provide as specified in Section 07 92 00 JOINT SEALANTS.

2.6 REINFORCEMENT

Provide fiberglass mesh tape, or fluid-applied air barrier manufacturer's approved comparable equivalent product, reinforcement at seams, edges, projections and penetrations. Reinforce all joints exceeding 1/4 inch with fiberglass mesh.

PART 3 EXECUTION

3.1 EXAMINATION

Before installing fluid-applied membrane air barrier, examine substrates, areas, and conditions under which fluid-applied membrane air barrier assemblies will be applied, with installer present, for compliance with requirements. Ensure the following conditions are met:

a. Surfaces are sound, dry, even, and free of oil, grease, dirt, excess mortar or other contaminants detrimental to the adhesion of the membranes.

b. Fill voids, gaps and spalled areas in substrate to provide an even plane. Strike masonry joints full flush.

c. Verify substrate is visibly dry and free of moisture. Test for capillary moisture by plastic sheet method in accordance with ASTM D4263 and take suitable measures until substrate passes moisture test.

d. Verify sealants used in substrates, and in joints between substrates, are compatible with fluid-applied membrane air barrier.

3.2 PREPARATION

Clean, prepare, and treat substrate in accordance with manufacturer's written instructions. Ensure clean, dust-free, and dry substrate for fluid-applied membrane air barrier application.

a. Remove dust, dirt and other contaminants from joints and cracks before coating surfaces.

b. Prepare, treat, and seal vertical and horizontal surfaces at

terminations and penetrations through fluid-applied membrane air barrier.

c. At changes in substrate plane, provide transition material (bead of sealant, mastic, extruded silicone sealant, membrane counterflashing or other material recommended by manufacturer) under transition membrane to eliminate all sharp 90-degree inside corners and to make a smooth transition from one plane to another.

d. Provide mechanically fastened non-corrosive metal sheet to span gaps in substrate plane and to make a smooth transition from one plane to the other. Continuously support membrane with substrate.

e. For exterior sheathing substrates, ensure that exterior sheathing is stabilized, with corners and edges fastened with appropriate screws. Treat all joints in accordance with the air barrier manufacturer's instructions prior to application of air barrier material. Allow sufficient time for joint treatments to fully cure before application of transition membranes and fluid-applied membrane air barrier.

f. Mask off and cover adjacent surfaces to protect from spillage and overspray.

3.3 INSTALLATION

3.3.1 Installation of Transition Membrane

Install transition membrane materials in accordance with the details on the drawings and the following:

a. Install transition membrane at all required locations (such as at any voids, gaps, or interstitial spaces that the fluid-applied air barrier cannot adequately protect) prior to installation of the fluid-applied membrane air barrier.

b. Verify transition membrane is fully adhered to substrate and that its surface is clean, dry and wrinkle free prior to installation of the fluid-applied membrane air barrier.

c. Verify transition membrane completely covers all transition areas and provides continuity of the finished fluid-applied membrane air barrier without gaps or cracks.

3.3.2 Installation of Flashing

Counterflash upper edge of thru-wall flashing and fluid-applied air barrier. Counter flashing is specified in Section 07 60 00 FLASHING AND SHEET METAL. See applicable wall-type Sections for thru-wall flashing requirements.

3.3.3 Installation of Fluid-Applied Membrane Air Barrier

Install materials in accordance with manufacturer's recommendations and the following:

a. Apply fluid-applied membrane air barrier in single or dual coat application by spray or roller. Apply fluid-applied membrane air barrier within manufacturer's recommended temperature range for application.

b. Apply fluid-applied membrane air barrier in manner and at rate and wet film thickness recommended by manufacturer to yield a finished dry film thickness of not less than 45 mils.

c. Apply fluid-applied membrane air barrier around all penetrations ensuring a complete and continuous air barrier. Lap fluid-applied membrane air barrier a minimum of 3 inch over transition membrane to seal leading edge.

d. Seal membrane terminations, heads of mechanical fasteners, masonry tie fasteners, around penetrations, HVAC assemblies, plumbing and electrical assemblies, doors, windows, louvers, and other assemblies penetrating the fluid-applied membrane air barrier with a termination sealant recommended by the fluid-applied membrane air barrier manufacturer.

e. Notify the Contracting Officer and Testing Agency upon completion of fluid-applied membrane air barrier installation. Air barrier materials and assemblies must remain exposed until tested and inspected in accordance with the ABAA protocol.

f. Do not allow materials to come in contact with chemically incompatible materials.

3.3.4 Installation of Reinforcement

Install reinforcement at projections, corners, joints, and penetrations where applicable.

3.4 FIELD QUALITY CONTROL

3.4.1 Site Inspections and Testing

Provide site inspections and testing in accordance with accepted practices.

a. Conduct inspections and testing at 5, 50, and 95 percent completion of this scope of work. Forward written inspection reports to the Contracting Officer within five working days of the inspection and test being performed.

b. If the inspections reveal defects, promptly remove and replace defective work at no additional expense to the Government.

3.5 PROTECTION AND CLEANING

3.5.1 Protection

Protect fluid-applied membrane air barrier assemblies from damage during application and remainder of construction in accordance with manufacturer's written instructions.

Coordinate installation, testing, and inspection procedures to ensure exposure period does not exceed that recommended by the product manufacturer. Remove and replace, at no additional cost to the government, membrane products that exceed manufacturer's allowed exposure limits.

3.5.2 Cleaning of Adjacent Surfaces

Clean excess product from adjacent construction using cleaning agents and procedures as recommended in writing by the manufacturer of each type of affected construction and as acceptable to same.

3.6 CLEANUP OF SPILLS

Conduct cleanup of uncured product spillage in accordance with manufacturer's written safe handling instructions.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 42 13

METAL WALL PANELS
05/11, CHG 2: 02/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 501.1	(2017) Standard Test Method for Water Penetration of Windows, Curtain Walls and Doors Using Dynamic Pressure
AAMA 800	(2016) Voluntary Specifications and Test Methods for Sealants

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI S100	(2012) North American Specification for the Design of Cold-Formed Steel Structural Members
AISI SG03-3	(2002; Suppl 2001-2004; R 2008) Cold-Formed Steel Design Manual Set

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7-16	(2017; Errata 2018; Supp 1 2018) Minimum Design Loads and Associated Criteria for Buildings and Other Structures

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A606/A606M	(2018) Standard Specification for Steel Sheet and Strip, High-Strength, Low-Alloy, Hot-Rolled and Cold-Rolled, with Improved Atmospheric Corrosion Resistance
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A755/A755M	(2018) Standard Specification for Steel Sheet, Metallic Coated by the Hot-Dip

	Process and Prepainted by the Coil-Coating Process for Exterior Exposed Building Products
ASTM A792/A792M	(2025a) Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process
ASTM A924/A924M	(2022a) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM A1008/A1008M	(2021a) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM D522/D522M	(2017) Mandrel Bend Test of Attached Organic Coatings
ASTM D523	(2014; R 2018) Standard Test Method for Specular Gloss
ASTM D610	(2008; R 2019) Standard Practice for Evaluating Degree of Rusting on Painted Steel Surfaces
ASTM D714	(2002; R 2017) Standard Test Method for Evaluating Degree of Blistering of Paints
ASTM D822	(2013; R 2018) Filtered Open-Flame Carbon-Arc Exposures of Paint and Related Coatings
ASTM D968	(2017) Standard Test Methods for Abrasion Resistance of Organic Coatings by Falling Abrasive
ASTM D1056	(2020) Standard Specification for Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM D1308	(2002; R 2013) Effect of Household Chemicals on Clear and Pigmented Organic Finishes
ASTM D1654	(2008; R 2016; E 2017) Standard Test Method for Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments
ASTM D1667	(2017) Standard Specification for Flexible

	Cellular Materials - Poly (Vinyl Chloride) Foam (Closed-Cell)
ASTM D2244	(2016) Standard Practice for Calculation of Color Tolerances and Color Differences from Instrumentally Measured Color Coordinates
ASTM D2247	(2015) Testing Water Resistance of Coatings in 100% Relative Humidity
ASTM D2794	(1993; R 2019) Standard Test Method for Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact)
ASTM D3359	(2017) Standard Test Methods for Rating Adhesion by Tape Test
ASTM D3363	(2005; E 2011; R 2011; E 2012) Film Hardness by Pencil Test
ASTM D4214	(2007; R 2015) Standard Test Method for Evaluating the Degree of Chalking of Exterior Paint Films
ASTM D4587	(2011; R 2019; E 2019) Standard Practice for Fluorescent UV-Condensation Exposures of Paint and Related Coatings
ASTM D5894	(2016) Standard Practice for Cyclic Salt Fog/UV Exposure of Painted Metal, (Alternating Exposures in a Fog/Dry Cabinet and a UV/Condensation Cabinet)
ASTM E72	(2022) Conducting Strength Tests of Panels for Building Construction
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E283	(2019) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E331	(2000; R 2023) Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference
ASTM E1592	(2025) Standard Test Method for Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference
ASTM G152	(2013; R 2021) Standard Practice for Operating Open Flame Carbon Arc Light

	Apparatus for Exposure of Nonmetallic Materials
ASTM G153	(2013; R 2021) Standard Practice for Operating Enclosed Carbon Arc Light Apparatus for Exposure of Nonmetallic Materials

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)

MBMA MBSM	(2018) Metal Building Systems Manual

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM AMP 500	(2006) Metal Finishes Manual

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1793	(2012) Architectural Sheet Metal Manual, 7th Edition

UL SOLUTIONS (UL)

UL Bld Mat Dir	(updated continuously online) Building Materials Directory

1.2 DEFINITIONS

Metal Wall Panel: Metal wall panels, attachment system components and accessories necessary for a complete weather-tight wall system.

1.3 DESCRIPTION OF WALL PANEL SYSTEM

Factory color finished, metal wall panel system with concealed fastening attachment. Panel profile must be flush face, smooth surfaced.

1.3.1 Metal Wall Panel General Performance

Comply with performance requirements, conforming to AISI S100, without failure due to defective manufacture, fabrication, installation, or other defects in construction. Wall panels and accessory components must conform to the following standards:

ASTM A1008/A1008M
ASTM A123/A123M
ASTM A36/A36M
ASTM A653/A653M
ASTM A606/A606M
ASTM A755/A755M for metallic coated steel sheet for exterior coil pre-painted applications.
ASTM A924/A924M for metallic coated steel sheet
ASTM D522/D522M for applied coatings
UL Bld Mat Dir

1.3.2 Structural Performance

Maximum calculated fiber stress must not exceed the allowable value in the AISI or AA manuals; a one third overstress for wind is allowed. Midspan

deflection under maximum design loads is limited to L/180. Contract drawings show the design wind loads and the extent and general assembly details of the metal siding. Contractor must provide design for members and connections not shown on the drawings. Siding panels and accessories must be the products of the same manufacturer.

Provide metal wall panel assemblies complying with the load and stress requirements in accordance with ASTM E1592. Wind Load force due to wind action governs the design for panels.

Wall systems and attachments are to resist the wind loads as determined by ASTM E72 and ASCE 7-16 in the geographic area where the construction will take place, in pounds per square foot. Submit electronic copies of wind load tests to the Contracting Officer.

Marine Corps Base Camp Lejeune must resist a 144 mile per hour, ultimate design wind speed, 54 PSF, Risk Category II, Surface Roughness Category C, Exposure Category C lateral load. Comply with UFC 3-301-01 and ASCE 7 as applicable for building system designs and components.

Supplement delegated design shop drawings with metal wall panel assembly structural computations. Tie general manufacturer data of components utilized to project specific conditions. Specify fastening patterns and connections.

1.3.3 Air Infiltration

Air leakage must conform to the limits through the wall assembly area when tested according to ASTM E283.

1.3.4 Water Penetration Under Static Pressure

No water penetration when tested according to ASTM E331.

1.3.5 Water Penetration Under Dynamic Pressure

No evidence of water leakage when tested according to AAMA 501.1.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Submit Documentation for the following items:

Qualification of Manufacturer; G
Qualification of Installation Contractor; G
Sample Warranty; G

SD-02 Shop Drawings

Installation Drawings ; G

SD-03 Product Data

Recycled Content;

Submit Manufacturer's data indicating percentage of recycle material in wall panels to verify sustainable acquisition compliance.

Submit Manufacturer's catalog data for the following items:

Wall Panels; G
Factory Color Finish; G
Closure Materials
Pressure Sensitive Tape
Sealants and Caulking
Galvanizing Repair Paint
Enamel Repair Paint
Accessories

SD-04 Samples

Submit as required each of the following samples:

Wall Panels; G, 12 inches long by actual panel width
Fasteners
Metal Closure Strips, 10 inches long of each type

Submit manufacturer's color charts and chips, approximately 4 by 4 inches, showing full range of colors, textures and patterns available for wall panels with factory applied finishes.

SD-05 Design Data

Wind load design analysis; G

As applicable, submit the following wind load design analysis data, to include, but not limited to:

wind speed
exposure category,co-efficient,importance factor
type of facility
negative pressures for each zone
methods and requirements of attachment

SD-06 Test Reports

Submit test reports for the following in accordance with the referenced articles in this section.

Leakage Tests; G
Wind Load Tests; G
Coating; G Tests
Chalking; G Tests

SD-07 Certificates

Submit certificates for the following items showing conformance with referenced standards contained in this section:

Coil Stock
Fasteners
Galvanizing Repair Paint
Enamel Repair Paint

SD-08 Manufacturer's Instructions

Include detailed application instructions and standard manufacturer drawings altered as required by these specifications.

Installation; G of Wall panels

SD-09 Manufacturer's Field Reports

Submit copies of the Manufacturer's Field Reports

SD-11 Closeout Submittals

Warranty; G
Maintenance Instructions; G

20 year "No Dollar Limit" warranty for labor and material

1.5 QUALITY ASSURANCE

1.5.1 Pre-Installation Conference

Upon notification of submittal receipt and approval by the Contracting Officer; and prior to the commencement of the work, the Contractor must attend a pre-installation conference to review the following:

a. Drawings and Specifications.

b. Qualification of Installer.

c. Sustainable acquisition

d. Approved Warranty

e. Sample wall panels, 12 inches long by actual panel width

f. Sample metal closure strips, 10 inches long of each type

g. Color charts and chips

h. Coatings and base metal tests, chalking tests

i. Construction schedule, availability of materials, Installer's personnel, equipment and facilities required to progress with the work without delay.

j. Methods and procedures related to installation of wall panels, including manufacturer's written instructions. Explicitly identify in writing, differences between manufacturer's instructions and the specified requirements.

k. Support conditions for compliance with requirements, including alignment between and attachment to structural members.

l. Flashing, special siding details, wall penetrations, openings, and condition of other construction that will affect metal wall panels.

m. Governing regulations and requirements for insurance, certificates, and tests and inspections if applicable.

n. Temporary protection requirements for metal wall panel assembly during and after installation.

o. Wall panel observation and repair procedures after metal wall panel installation. Provide detailed written instructions including copies of Safety Data Sheets for maintenance and repair materials, and manufacturer's maintenance instructions.

1.5.1.1 Installation Drawings

Installation shop drawings for wall panels, flashing, accessories, and anchorage systems must indicate completely dimensioned structural frame and erection layouts, openings in the wall, special framing details, and construction details at corners, building intersections and flashing, location and type of mastic and metal filler strips.

1.5.1.2 Wind Load Design Analysis

Wind design analysis must include wall plan delineating dimensions and attachment patterns for each zone. Wind design analysis must be prepared and sealed by Licensed Project Engineer in the geographic area where the construction will take place.

1.5.2 Manufacturer's Technical Representative

The representative must have authorization from manufacturer to approve field changes and be thoroughly familiar with the products and installations in the geographical area where construction will take place.

1.5.3 Qualification of Manufacturer

Certify that metal wall panel system manufacturer has a minimum of five (5) years experience in manufacturing metal wall system and accessory products.

Manufacturer must also provide engineering services by an authorized engineer; currently licensed in the geographical area where construction will take place, having a minimum of four (4) years experience as an engineer knowledgeable in wind load design analysis, protocols and procedures per MBMA MBSM, "Metal Building Systems Manual"; ASCE 7-16, and ASTM E1592.

Provide certified engineering calculations, using the products submitted, for Wind load requirements in accordance with ASCE 7-16.

1.5.3.1 Manufacturer's Certificates

Also provide the following certifications from the manufacturer:

Coil Stock
Fasteners
Galvanizing Repair Paint
Enamel Repair Paint

Submit certification from coil stock manufacturer or supplier that the machinery used will form the provided coil stock without warping, waviness, or rippling that is not a part of the panel profile, and without damage, abrasion or marring of the finish coating.

Provide evidence that products used within this specification are manufactured in the United States.

1.5.4 Certified Qualification of Installation Contractor

The installation contractor must be approved and certified by the metal wall panel manufacturer prior to beginning the installation of the metal wall panel system. Subcontracting by Certified Contractor for the metal wall panel work is not permitted.

1.5.5 Single Source

Obtain each type of metal wall panels, clips, closure materials and other accessories from the standard products of the single source from a single manufacturer to operate as a complete system for the intended use.

1.5.6

Manufacturer's Maintenance Instructions

Provide manufacturer's detailed written instructions including copies of Safety Data Sheets for maintenance and repair materials.

1.6 DELIVERY, HANDLING, AND STORAGE

Deliver and protect package components, sheets, metal wall panels, and other manufactured items to prevent damage or deformation during transportation and handling.

Unload, store, and erect metal wall panels in a manner to prevent bending, warping, twisting, and surface damage.

Stack and store metal wall panels horizontally on platforms or pallets, covered with suitable weather-tight and ventilated covering to ensure dryness, with positive slope for drainage of water. Do not store metal wall panels in contact with other materials that might cause staining, denting, or other surface damage.

Retain strippable protective covering on metal wall panel until actual installation.

1.7 PROJECT CONDITIONS

1.7.1 Field Measurements

Verify locations of wall framing and opening dimensions by field measurements before metal wall panel fabrication and indicate measurements on Shop Drawings.

1.7.2 Weather Limitations

Proceed with installation preparation only when existing and forecasted weather conditions permit Work to proceed without water entering into wall system or building.

1.8 WARRANTY

Warranty must conform to the Sample Warranty as reviewed and approved by the Contracting Officer.

1.8.1 20 Year "No Dollar Limit" Warranty for Labor and Material

Furnish manufacturer's no-dollar-limit warranty for the metal wall panel system. The warranty period is to be no less than twenty (20) years from the date of Government acceptance of the work. The warranty is to be issued directly to the Government. The warranty is to provide that if within the warranty period the metal wall panel system shows evidence of corrosion, perforation, rupture or excess weathering due to deterioration of the wall panel system resulting from defective materials and correction of the defective workmanship is to be the responsibility of the metal wall panel system manufacturer. Repairs that become necessary because of defective materials and workmanship while metal wall panel system is under warranty are to be performed within 24 hours after notification, unless additional time is approved by the Contracting Officer. Failure to perform repairs within 24 hours of notification will constitute grounds for having emergency repairs performed by others and not void the warranty.

PART 2 PRODUCTS

2.1 FABRICATION

Unless approved otherwise, fabricate and finish metal wall panels and accessories at the factory to greatest extent possible, by manufacturer's standard procedures and processes and as necessary to fulfill indicated and specified performance requirements. Comply with indicated profiles and with dimensional and structural requirements. See section 01 33 29 SUSTAINABILITY REQUIREMENTS AND REPORTING for cumulative total recycled content requirements.

Provide panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel. Fabricate metal wall panel side laps with factory-installed captive gaskets or separator strips that provide a tight seal and prevent metal-to-metal contact, in a manner that will seal weather-tight and minimize noise from movements within panel assembly.

2.1.1 Sheet Metal Accessories

Fabricate flashing and trim to comply with recommendations in SMACNA 1793 that apply to the design, dimensions, metal, and other characteristics of item indicated:

a. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.

b. End Seams: fabricate nonmoving end seams with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints for additional strength.

c. Sealed Joints: form non-expansion but movable joints in metal to accommodate elastomeric sealant to comply with SMACNA 1793.

d. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of accessories exposed to view.

e. Fabricate cleats and attachment devices of size and metal thickness recommended by SMACNA 1793 or by metal wall panel manufacturer for application, but not less than thickness of metal being secured.

2.2 PANEL MATERIALS

2.2.1 Steel Sheet

Roll-form steel wall panels to the specified profile, with 24 gauge and depth as indicated. Material must be plumb and true, and within the tolerances listed:

a. Galvanized Steel Sheet conforming to ASTM A653/A653M and AISI SG03-3.

b. Aluminum-Zinc Alloy-coated Steel Sheet conforming to ASTM A792/A792M and AISI SG03-3.

c. Individual panels must be continuous length to cover the entire length of any unbroken wall area with no joints or seams and formed without warping, waviness, or ripples that are not part of the panel profile and free of damage to the finish coating system.

d. Provide panels with thermal expansion and contraction consistent with the type of system specified.

1. Profile and coverage to be a minimum height and width from manufacturer's standard for the indicated wall area.

2. Profile to be a 1-1/2 inch depth with 12 inch coverage and concealed fasteners.

3. Smooth, flat Surface Texture.

2.2.2 Factory Color Finish

Comply with NAAMM AMP 500 for recommendations for applying and designating finishes. Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved samples and are assembled or installed to minimize contrast.

All panels are to receive a factory-applied polyvinylidene fluoride finish consisting of a baked-on top-coat with a manufacturer's recommended prime coat conforming to the following:

2.2.2.1 Metal Preparation

Carefully prepare all metal surface for painting on a continuous process coil coating line by alkali cleaning, hot water rinsing, application of chemical conversion coating, cold water rinsing, sealing with acid rinse, and thorough drying.

2.2.2.2 Prime Coating

Apply a base coat of epoxy paint, specifically formulated to interact with the top-coat, to the prepared surfaces by roll coating to a dry film

thickness of 0.20 plus 0.05 mils. Prime coat must be oven cured prior to application of finish coat.

2.2.2.3 Exterior Finish Coating

Roll coat the finish coating over the primer by roll coating to dry film thickness of 0.80 plus 5 mils (3.80 plus 0.50 mils for Vinyl Plastisol) for a total dry film thickness of 1.00 plus 0.10 mils (4.00 plus 0.10 mils for Vinyl Plastisol). Oven-cure finish coat.

2.2.2.4 Interior Finish Coating

Apply a wash-coat on the reverse side over the primer by roll coating to a dry film thickness of 0.30 plus 0.05 mils for a total dry film thickness of 0.50 plus 0.10 mils. Oven-cured the wash coat.

2.2.2.5 Color

MMetal walL panel is Slate Gray, Federal Standard AMS-STD-595A 36173 as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC. .

Metal soffit panel is Slate Gray, Federal Standard AMS-STD-595A 36173 as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, MARSOC.

2.2.2.6 Physical Properties

Coating must conform to the industry and manufacturer's standard performance criteria as listed by the following certified test reports:

General:	ASTM D5894 and ASTM D4587
Abrasion:	ASTM D968
Adhesion:	ASTM D3359
Chalking:	ASTM D4214
Chemical Pollution:	ASTM D1308
Color Change and Conformity:	ASTM D2244
Creepage:	ASTM D1654
Cyclic Corrosion Test:	ASTM D5894
Flame Spread:	ASTM E84
Flexibility:	ASTM D522/D522M
Formability:	ASTM D522/D522M
Gloss at 60 and 85 degrees:	ASTM D523

Humidity:	ASTM D2247 and ASTM D714
Oxidation:	ASTM D610
Pencil Hardness:	ASTM D3363
Reverse Impact:	ASTM D2794
Salt Spray:	ASTM B117
Weatherometer:	ASTM G152, ASTM G153 and ASTM D822

2.3 MISCELLANEOUS METAL FRAMING

Cold-formed metallic-coated steel sheet conforming to ASTM A653/A653M and specified in Section 05 40 00 COLD-FORMED METAL FRAMING unless otherwise indicated.

Zee furring and girts are 0.048 inch, 18 gauge steel with web depths of 4 inches to 1 foot, 8 inches and flanges of 2 inches to 4.5 inches. Hat channels are simialr.

Vented hat channel is 0.048 inch, 18 gauge galvanized steel complying with ASTM A 653, Class G90 with 1.5 inch flanges, 2.5 inch top width and 1 inch height. Provide factory punched holes in flanges, and two rows of 0.1875 inch by 1.75 inch slotted holes spaced 2.5 inches on center on both returns. Slots provide 3.5 square inches of ventilation per linear foot of channel.

2.3.1 Fasteners for Miscellaneous Metal Framing

Type, material, corrosion resistance, size and sufficient length to penetrate the supporting member a minimum of 1 inch with other properties required to fasten miscellaneous metal framing members to supporting members and substrates in accordance with the wall panel manufacturer's and ASCE 7-16 requirements.

2.4 FASTENERS

2.4.1 General

2.4.1.1 Exposed Fasteners

Provide corrosion resistant fasteners for wall panels, made of coated steel, aluminum, 300 - series corrosion resisting stainless steel, or nylon capped steel compatible with the sheet panel or flashing and of a type and size recommended by the manufacturer to meet the performance requirements and design loads.

Fasteners for accessories must be the manufacturer's standard. Provide an integral metal washer matching the color of attached material with compressible sealing EPDM gasket approximately 3/32 inch thick.

2.4.1.2 Hidden Fasteners

Provide corrosion resistant fasteners recommended by the manufacturer to meet the performance requirements and design loads.

2.4.1.3 Screws

Screws to be corrosion resistant coated steel, aluminum and/or 300 - series stainless steel being the type and size recommended by the manufacturer to meet the performance requirements.

2.4.1.4 Rivets

Rivets to be closed-end type, corrosion resistant coated steel, aluminum or stainless steel where watertight connections are required.

2.4.1.5 Attachment Clips

Fabricate clips from steel hot-dipped galvanized in accordance with ASTM A653/A653M, Z275 G 90 or Series 300 stainless steel. Size, shape, thickness and capacity as required meeting the insulation thickness and design load criteria specified.

2.5 ACCESSORIES

2.5.1 General

All accessories must be compatible with the metal wall panels. Sheet metal flashing, trim, metal closure strips, caps and similar metal accessories must not be less than the minimum thickness specified for the wall panels. Exposed metal accessories/finishes to match the panels furnished, except as otherwise indicated. Molded foam rib, ridge and other closure strips must be non-absorbent closed-cell or solid-cell synthetic rubber or pre-molded neoprene to match configuration of the panels.

2.5.2 Rubber Closure Strips

Provide closed-cell, expanded cellular rubber conforming to ASTM D1056 and ASTM D1667; extruded or molded to the configuration of the specified wall panel and in lengths supplied by the wall panel manufacturer.

2.5.3 Metal Closure Strips

Provide factory fabricated steel closure strips to be the same gauge, color, finish and profile of the specified wall panel.

2.5.4 Joint Sealants

2.5.4.1 Sealants and Caulking

Provide approved gun type sealants for use in hand- or air-pressure caulking guns at temperatures above 40 degrees F (or frost-free application at temperatures above 10 degrees F with minimum solid content of 85 percent of the total volume. Sealants must dry with a tough, durable surface skin which permit remaining soft and pliable underneath, providing a weather-tight joint. No migratory staining is permitted on painted or unpainted metal, stone, glass, vinyl, or wood.

Prime all joints receiving sealants with a compatible one-component or

two-component primer as recommended by the wall panel manufacturer.

2.5.4.2 Shop-Applied

Sealant for shop-applied caulking must be non-curing butyl compliant with AAMA 800 to ensure the sealant's plasticity at the time of field erection.

2.5.4.3 Field-Applied

Sealant for field-applied caulking must be an approved gun grade, non-sag one component polysulfide or two-component polyurethane with an initial maximum Shore A durometer hardness of 25, and conforming to ASTM C920, Type II. Color to match panel colors.

2.5.4.4 Pressure Sensitive Tape

Provide pressure sensitive tape sealant, 100 percent solid with a release paper backing; permanently elastic, non-sagging, non-toxic and non-staining as approved by the wall panel manufacturer.

2.6 SHEET METAL FLASHING AND TRIM

2.6.1 Fabrication

Shop fabricate sheet metal flashing and trim where practicable to comply with recommendations in SMACNA 1793 that apply to design, dimensions, metal, and other characteristics of item indicated. Obtain field measurements for accurate fit before shop fabrication.

Fabricate sheet metal flashing and trim without excessive oil canning, buckling, and tool marks and true to line and levels indicated, with exposed edges folded back to form hems.

2.7 REPAIR OF FINISH PROTECTION

Repair paint for color finish enameled wall panel must be compatible paint of the same formula and color as the specified finish furnished by the wall panel manufacturer. Provide repair paint matching the specified wall panels.

PART 3 EXECUTION

3.1 EXAMINATION

Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal wall panel supports, and other conditions affecting performance of the Work.

Examine primary and secondary wall framing to verify that rafters, purlins, angles, channels, and other structural panel support members and anchorages have been installed within alignment tolerances required by metal wall panel manufacturer, UL, ASTM, ASCE 7-16 and as required for the geographical area where construction will take place.

Examine solid wall sheathing to verify that sheathing joints are supported by framing or blocking and that installation is within flatness tolerances required by metal wall panel manufacturer.

Examine roughing-in for components and systems penetrating metal wall

panels to verify actual locations of penetrations relative to seam locations of metal wall panels before metal wall panel installation.

Submit to the Contracting Officer a written report, endorsed by Installer, listing conditions detrimental to performance of the Work. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

Clean substrates of substances harmful to insulation, including removing projections capable of interfering with insulation attachment. Miscellaneous framing installation, including sub-purlins, girts, angles, furring, and other miscellaneous wall panel support members and anchorage must be according to metal wall panel manufacturer's written instructions.

3.3 WALL PANEL INSTALLATION

Provide full length metal wall panels, from sill to eave as indicated, unless otherwise indicated or restricted by shipping limitations. Anchor metal wall panels and other components of the Work securely in place, with provisions for thermal and structural movement in accordance with MBMA MBSM.

Erect wall panel system in accordance with the approved erection drawings, the printed instructions and safety precautions of the manufacturer.

Sheets are not to be subjected to overloading, abuse, or undue impact. Bent, chipped, or defective sheets shall not be applied.

Sheets must be erected true and plumb and in exact alignment with the horizontal and vertical edges of the building, securely anchored, and with the indicated eave, and sill.

Work is to allow for thermal movement of the wall panel, movement of the building structure, and to provide permanent freedom from noise due to wind pressure.

Field cutting metal wall panels by torch is not permitted.

3.3.1 Steel Wall Panels

Use stainless-steel fasteners for exterior surfaces and galvanized steel fasteners for interior surfaces.

3.3.2 Anchor Clips

Anchor metal wall panels and other components of the Work securely in place, using manufacturer's approved fasteners according to manufacturers' written instructions.

3.3.3 Metal Protection

Where dissimilar metals will contact each other or corrosive substrates, protect against galvanic action by painting contact surfaces with bituminous coating, by applying rubberized-asphalt underlayment to each contact surface, or by other permanent separation as recommended by metal wall panel manufacturer.

3.3.4 Joint Sealers

Install gaskets, joint fillers, and sealants where indicated and where required for weatherproof performance of metal wall panel assemblies. Provide types of gaskets, fillers, and sealants indicated or, if not indicated, types recommended by metal wall panel manufacturer.

3.4 FASTENER INSTALLATION

Anchor metal wall panels and other components of the Work securely in place, using manufacturer's approved fasteners according to manufacturers' written instructions.

3.5 FLASHING, TRIM AND CLOSURE INSTALLATION

3.5.1 General Requirements

Comply with performance requirements, manufacturer's written installation instructions, and SMACNA 1793. Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams to form permanently watertight and weather resistant.

Install sheet metal work is to form weather-tight construction without waves, warps, buckles, fastening stresses or distortion, and allow for expansion and contraction. Cutting, fitting, drilling, and other operations in connection with sheet metal required to accommodate the work of other trades is to be performed by sheet metal mechanics.

3.5.2 Metal Flashing

Install exposed metal flashing at building corners, sills and eaves, junctions between metal siding and walling. Exposed metal flashing must be the same material, color, and finish as the specified metal wall panel.

Fasten flashing at a minimum of 8 inches on center, except where flashing is held in place by the same screws that secure covering sheets.

Flashing is to be furnished in at least 8 foot lengths. Exposed flashing is to have 1 inch locked and blind-soldered end joints, and expansion joints at intervals of not more than 16 feet.

Exposed flashing and flashing subject to rain penetration to be bedded in the specified joint sealant.

Isolate flashing which is in contact with dissimilar metals by means of the specified asphalt mastic material to prevent electrolytic deterioration.

Form drips to the profile indicated, with the edge folded back 1/2 inch to form a reinforced drip edge.

3.5.3 Closures

Install metal closure strips at open ends of corrugated or ribbed pattern walls, and at intersection of wall and wall unless open ends are concealed with formed eave flashing; and in other required areas.

Install mastic closure strips at intersection of the wall with metal

walling; top and bottom of metal siding; heads of wall openings; and in other required locations.

3.6 WORKMANSHIP

Make lines, arises, and angles sharp and true. Free exposed surfaces from visible wave, warp, buckle, and tool marks. Fold back exposed edges neatly to form a 1/2 inch hem on the concealed side. Make sheet metal exposed to the weather watertight with provisions for expansion and contraction.

Make surfaces to receive sheet metal plumb and true, clean, even, smooth, dry, and free of defects and projections which might affect the application. For installation of items not shown in detail or not covered by specifications conform to the applicable requirements of SMACNA 1793. Provide sheet metal flashing in the angles formed where roof decks abut walls, curbs, ventilators, pipes, or other vertical surfaces and wherever indicated and necessary to make the work watertight.

3.7 ACCEPTANCE PROVISIONS

3.7.1 Erection Tolerances

Erect metal wall panels straight and true with plumb vertical lines correctly lapped and secured in accordance with the manufacturer's written instructions.

3.7.2 Leakage Tests

Finished application of metal wall panels are to be subject to inspection and test for leakage by request of the Contracting Officer, Architect/Engineer. Conduct inspection and tests at no cost to the Government.

Inspection and testing is to be made promptly after erection to permit correction of defects and the removal and replacement of defective materials.

3.7.3 Repairs to Finish

Scratches, abrasions, and minor surface defects of finish may be repaired with the specified repair materials. Finished repaired surfaces must be uniform and free from variations of color and surface texture.

Repaired metal surfaces that are not acceptable to the project requirements and/or Contracting Officer are to be immediately removed and replaced with new material.

3.7.4 Paint-Finish Metal Siding

Paint-finish metal siding will be tested for color stability by the Contracting Officer during the manufacturer's specified guarantee period.

Panels that indicate color changes, fading, or surface degradation, determined by visual examination, must be removed and replaced with new panels at no expense to the Government.

New panels will be subject to the specified tests for an additional year from the date of their installation.

3.8 FIELD QUALITY CONTROL

3.8.1 Construction Monitoring

Make visual inspections as necessary to ensure compliance with specified requirements. Additionally, verify the following:

a. Materials comply with the specified requirements.

b. All materials are properly stored, handled and protected from damage. Damaged materials are removed from the site.

c. Framing and substrates are in acceptable condition, in compliance with specification, prior to application of wall panels.

d. Panels are installed without buckles, ripples, or waves and in uniform alignment and modulus.

e. Side laps are formed, sealed, fastened or seam locked as required.

f. The proper number, type, and spacing of attachment clips and fasteners are installed.

g. Installer adheres to specified and detailed application parameters.

h. Associated flashing and sheet metal are installed in a timely manner in accord with the specified requirements.

Provide electronic copies of Manufacturer's Field Reports to the Contracting Officer 2 weeks prior to project close-out.

3.9 CLEAN-UP AND DISPOSAL

Clean all exposed sheet metal work at completion of installation. Remove metal shavings, filings, nails, bolts, and wires from work area. Remove grease and oil films, excess sealants, handling marks, contamination from steel wool, fittings and drilling debris and scrub the work clean. Exposed metal surfaces must be free of dents, creases, waves, scratch marks, solder or weld marks, and damage to the finish coating.

Collect and place scrap/waste materials in containers. Promptly dispose of demolished materials. Do not allow demolished materials to accumulate on-site; transport demolished materials from government property and legally dispose of them.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 60 00

FLASHING AND SHEET METAL
05/17, CHG 2: 11/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 2605	(2022) Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels

ASTM INTERNATIONAL (ASTM)

ASTM A480/A480M	(2020a) Standard Specification for General Requirements for Flat-Rolled Stainless and Heat-Resisting Steel Plate, Sheet, and Strip
ASTM B32	(2020) Standard Specification for Solder Metal
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B370	(2022) Standard Specification for Copper Sheet and Strip for Building Construction

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1793	(2012) Architectural Sheet Metal Manual, 7th Edition

1.2 GENERAL REQUIREMENTS

Finished sheet metal assemblies must form a weathertight enclosure without waves, warps, buckles, fastening stresses or distortion, while allowing for expansion and contraction without damage to the system. The sheet metal installer is responsible for cutting, fitting, drilling, and other operations in connection with sheet metal modifications required to accommodate the work of other trades. Coordinate installation of sheet metal items used in conjunction with roofing with roofing work to permit continuous, uninterrupted roofing operations.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Exposed Sheet Metal Coverings

Gutters; G

Downspouts; G

Drip Edges; G

Recycled Content; S

SD-04 Samples

Finish Samples

SD-08 Manufacturer's Instructions

Instructions for Installation

Quality Control Plan

SD-10 Operation and Maintenance Data

Cleaning and Maintenance

1.4 MISCELLANEOUS REQUIREMENTS

1.4.1 Product Data

Indicate thicknesses, dimensions, fastenings, anchoring methods, expansion joints, and other provisions necessary for thermal expansion and contraction. Scaled manufacturer's catalog data may be submitted for factory fabricated items.

1.4.2 Finish Samples

Submit two color charts and two finish sample chips from manufacturer's standard color and finish options for each type of finish indicated.

1.4.3 Operation and Maintenance Data

Submit detailed instructions for installation and quality control during installation, cleaning and maintenance, for each type of assembly indicated.

1.5 DELIVERY, HANDLING, AND STORAGE

Package and protect materials during shipment. Uncrate and inspect materials for damage, dampness, and wet-storage stains upon delivery to the job site. Remove from the site and replace damaged materials that cannot be restored to like-new condition. Handle sheet metal items to

avoid damage to surfaces, edges, and ends. Store materials in dry, weather-tight, ventilated areas until installation.

PART 2 PRODUCTS

2.1 RECYCLED CONTENT

Provide products with recycled content. Provide data for each product with recycled content, identifying percentage of recycled content.

2.2 MATERIALS

Do not use lead, lead-coated metal, or galvanized steel. Provide materials, thicknesses, and configurations in accordance with SMACNA 1793 for each material. Different items need not be of the same metal, except that if copper is selected for any exposed item, all exposed items must be copper, and that contact between dissimilar metals must be avoided.

Furnish sheet metal items in 8 to 10 foot lengths. Single pieces less than 8 feet long may be used to connect to factory-fabricated inside and outside corners, and at ends of runs. Factory fabricate corner pieces with minimum 12 inch legs. Provide accessories and other items essential to complete the sheet metal installation. Provide accessories made of the same or compatible materials as the items to which they are applied. Fabricate sheet metal items of the materials specified below and to the gage, thickness, or weight shown in Table I at the end of this section. Where more than one material is listed for a particular item in Table I, each is acceptable and may be used, except as follows:

2.2.1 Exposed Sheet Metal Items

Must be of the same material. Consider the following as exposed sheet metal: gutters, including hangers; downspouts; cap, stepped, base, and eave flashings and related accessories.

2.2.2 Drainage

Do not use copper for an exposed item if drainage from that item will pass over exposed masonry, stonework or other metal surfaces.

2.2.3 Copper, Sheet and Strip

Provide in accordance with ASTM B370, cold-rolled temper, H 00 (standard).

2.2.4 Stainless Steel

Provide in accordance with ASTM A480/A480M, Type 302 or 304, 2D Finish, fully annealed, dead-soft temper.

2.2.5 Aluminum Alloy Sheet and Plate

Provide in accordance with ASTM B209 form alloy, and temper appropriate for use. Provide material not less than 0.040-in in thickness.

Furnish aluminum with an organic coating treatment conforming to AAMA 2605 to obtain a 70% PVDF coating.

2.2.5.1 Alclad

When fabricated of aluminum, fabricate the following items with Alclad 3003, Alclad 3004, or Alclad 3005, clad on one side unless otherwise indicated.

a. Gutters, downspouts, and hangers

b. Gravel stops and fascia

c. Flashing

2.2.6 Prefinished Steel

Prefinished steel sheet coil is 0.024 inch, 24 gauge conforming to ASTM A 653, Class G90 and AAMA 621.

2.2.6.1 Organic Coating

Furnish prefinished steel with an organic coating treatment conforming to AAMA 2605 to obtain a 70% PVDF coating.

2.2.7 Finishes

Provide exposed exterior sheet metal and aluminum with a baked on, factory applied color coating of polyvinylidene fluoride (PVF2) or approved equal fluorocarbon coating. Dry film thickness of coatings must be 0.8 to 1.3 mils. Color is to match sheet metal roofing and wall panels for newly constructed buildigs. Field applications of color coatings are prohibited and will be rejected.

2.2.8 Aluminum Alloy, Extruded Bars, Rods, Shapes, and Tubes

ASTM B221.

2.2.9 Solder

Provide in accordance with ASTM B32, 95-5 tin-antimony.

2.2.10 Fasteners

Use stainless steel fasteners to fasten. Confirm compatibility of fasteners and items to be fastened to avoid galvanic corrosion due to dissimilar materials.

Finish exposed rivets and fasteners to match substrate colors encountered.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Metal Fascias and Soffits

3.1.2 Workmanship

Make lines and angles sharp and true. Free exposed surfaces from visible wave, warp, buckle, and tool marks. Fold back exposed edges neatly to form a 1/2 inch hem on the concealed side. Make sheet metal exposed to

the weather watertight with provisions for expansion and contraction.

Make surfaces to receive sheet metal plumb and true, clean, even, smooth, dry, and free of defects and projections. For installation of items not shown in detail or not covered by specifications conform to the applicable requirements of SMACNA 1793, Architectural Sheet Metal Manual. Provide sheet metal flashing in the angles required to accommodate terminations, edges and wherever indicated and necessary to make the work watertight. Join sheet metal items together as shown in Table II.

3.1.3 Nailing

Confine nailing of sheet metal generally to sheet metal having a maximum width of 18 inches. Confine nailing of flashing to one edge only. Space nails evenly not over 3 inch on center and approximately 1/2 inch from edge unless otherwise specified or indicated. Face nailing will not be permitted. Where sheet metal is applied to other than wood surfaces, include in shop drawings, the locations for sleepers and nailing strips required to secure the work. Secure flashing at one-half the normal interval to ensure a wind-resistant installation.

3.1.4 Cleats

Provide cleats for sheet metal 18 inches and over in width. Cleats are continuous. Unless otherwise specified, provide cleats of 2 inches wide and of the same material and thickness as the sheet metal being installed. Secure one end of the cleat with two nails and the cleat folded back over the nailheads. Lock the other end into the seam. Pre-tin cleats for soldered seams.

3.1.5 Bolts, Rivets, and Screws

Install bolts, rivets, and screws where indicated or required. Provide compatible washers where required to protect surface of sheet metal and to provide a watertight connection. Provide mechanically formed joints in aluminum sheets 0.040 inches or less in thickness.

3.1.6 Seams

Straight and uniform in width and height with no solder showing on the face.

3.1.6.1 Flat-lock Seams

Finish not less than 3/4 inch wide.

3.1.6.2 Lap Seams

Finish soldered seams not less than one inch wide. Overlap seams not soldered, not less than 3 inches.

3.1.6.3 Loose-Lock Expansion Seams

Not less than 3 inches wide; provide minimum one inch movement within the joint. Completely fill the joints with the specified sealant, applied at not less than 1/8 inch thick bed.

3.1.6.4 Standing Seams

Not less than one inch high, double locked without solder.

3.1.6.5 Flat Seams

Make seams in the direction of the flow.

3.1.7 Soldering

Where soldering is specified, apply to copper and stainless steel items. Pre-tin edges of sheet metal before soldering is begun. Seal the joints in aluminum sheets of 0.040 inch or less in thickness with specified sealants. Do not solder aluminum.

3.1.8 Mechanical Fastening

Aluminum 0.040 inch or less in thickness must be butted and the space backed with formed flashing plate; or lock joined, mechanically fastened, and filled with sealant as recommended by the aluminum manufacturer.

3.1.8.1 Mechanical Fastening of Aluminum

Use No. 12, aluminum alloy, sheet metal screws or other suitable aluminum alloy or stainless steel fasteners. Drive fasteners in holes made with a No. 26 drill in securing side laps, end laps, and flashings. Space fasteners 12 inches maximum on center. Where end lap fasteners are required to improve closure, locate the end lap fasteners not more than 2 inches from the end of the overlapping sheet.

3.1.9 Protection from Contact with Dissimilar Materials

3.1.9.1 Copper or Copper-bearing Alloys

Paint with heavy-bodied bituminous paint surfaces in contact with dissimilar metal, or separate the surfaces by means of moistureproof building felts.

3.1.9.2 Aluminum

Do not allow aluminum surfaces in direct contact with other metals except stainless steel, zinc, or zinc coating. Where aluminum contacts another metal, paint the dissimilar metal with a primer followed by two coats of aluminum paint. Where drainage from a dissimilar metal passes over aluminum, paint the dissimilar metal with a non-lead pigmented paint.

3.1.9.3 Metal Surfaces

Paint surfaces in contact with mortar, concrete, or other masonry materials with alkali-resistant coatings such as heavy-bodied bituminous paint.

3.1.10 Expansion and Contraction

Provide expansion and contraction joints at not more than 32 foot intervals for aluminum and at not more than 40 foot intervals for other metals. Provide an additional joint where the distance between the last expansion joint and the end of the continuous run is more than half the required interval. Space joints evenly. Join extruded aluminum gravel

stops and fascia by expansion and contraction joints spaced not more than 12 feet apart.

3.1.11 Counterflashing

Except where indicated or specified otherwise, insert counterflashing above roof decks, extend down vertical surfaces over upturned vertical leg of base flashings not less than 3 inches. Fold the exposed edges of counterflashings 1/2 inch. Where stepped counterflashings are required, they may be installed in short lengths a minimum of 8 inches by 8 inches or may be of the preformed single piece type. Provide end laps in counterflashings not less than 3 inches and make it weathertight with plastic cement. Do not make lengths of metal counterflashings exceed 10 feet. Form flashings to the required shapes before installation. Factory form corners not less than 12 inches from the angle. Secure the flashings in the reglets with lead wedges and space not more than 18 inches apart; on short runs, place wedges closer together. Fill caulked-type reglets or raked joints which receive counterflashing with caulking compound. Turn up the concealed edge of counterflashings built into masonry or concrete walls not less than 1/4 inch and extend not less than 2 inches into the walls. Install counterflashing to provide a spring action against base flashing.

3.1.12 Metal Reglets

Keep temporary cores in place during installation. Ensure factory fabricated caulked type or friction type, reglets have a minimum opening of 1/4 inch and a minimum depth of 1-1/4 inch, when installed.

3.1.12.1 Caulked Reglets

Wedge flashing in reglets with lead wedges every 18 inches, caulked full and solid with an approved compound.

3.1.12.2 Friction Reglets

Install flashing snap lock receivers at 24 inches on center maximum. When flashing has been inserted the full depth of the slot, caulk the slot, lock with wedges, and fill with sealant.

3.1.13 Gravel Stops and fascia

Prefabricate in the shapes and sizes indicated and in lengths not less than 8 feet. Extend flange at least 4 inches onto roofing. Provide prefabricated, mitered corners internal and external corners. Install gravel stops and fascia after all plies of the roofing membrane have been applied, but before the flood coat of bitumen is applied. Prime roof flange of gravel stops and fascia on both sides with an asphalt primer. After primer has dried, set flange on roofing membrane and strip-in. Nail flange securely to wood nailer with large-head, barbed-shank roofing nails 1.5 inch long spaced not more than 3 inches on center, in two staggered rows.

3.1.13.1 Edge Strip

Hook the lower edge of fascia at least 3/4 inch over a continuous strip of the same material bent outward at an angle not more than 45 degrees to form a drip. Nail hook strip to a wood nailer at 6 inches maximum on center. Where fastening is made to concrete or masonry, use screws spaced

12 inches on center driven in expansion shields set in the concrete or masonry. Where horizontal wood nailers are slotted to provide for insulation venting, install strips to prevent obstruction of vent slots. Where necessary, install strips over 1/16 inch thick compatible spacer or washers.

3.1.13.2 Joints

Leave open the section ends of gravel stops and fascia 1/4 inch and backed with a formed flashing plate, mechanically fastened in place and lapping each section end a minimum of 4 inches set laps in plastic cement. Face nailing will not be permitted. Install prefabricated aluminum gravel stops and fascia in accordance with the manufacturer's printed instructions and details.

3.1.14 Metal Drip Edges

Provide a metal drip edge, designed to allow water run-off to drip free of underlying construction, at eaves and rakes prior to the application of roofing.

3.1.15 Gutters

The hung type of shape indicated and supported on underside by brackets that permit free thermal movement of the gutter. Provide gutters in sizes indicated complete with mitered corners, end caps, outlets, brackets, and other accessories necessary for installation. Bead with hemmed edge or reinforce the outer edge of gutter with a stiffening bar not less than 3/4 by 3/16 inch of material compatible with gutter. Fabricate gutters in sections not less than 8 feet. Lap the sections a minimum of one inch in the direction of flow or provide with concealed splice plate 6 inches minimum. Join the gutters, other than aluminum, by riveted and soldered joints. Join aluminum gutters with riveted sealed joints. Provide expansion-type slip joints midway between outlets. Install gutters below slope line of the roof so that snow and ice can slide clear. Support gutters on adjustable hangers spaced not more than 30 inches on center or with continuous cleats and counterflashing. Adjust gutters to slope uniformly to outlets, with high points occurring midway between outlets. Fabricate hangers and fastenings from compatible metals.

3.1.16 Downspouts

Space supports for downspouts . Types, shapes and sizes are indicated. Provide complete including elbows and offsets. Provide downspouts in approximately 10 foot lengths. Provide end joints to telescope not less than 1/2 inch and lock longitudinal joints. Provide gutter outlets with wire ball strainers for each outlet. Provide strainers to fit tightly into outlets and be of the same material used for gutters. Keep downspouts not less than one inch away from walls. Fasten to the walls at top, bottom, and at an intermediate point not to exceed 5 feet on center with leader straps or concealed rack-and-pin type fasteners. Form straps and fasteners of metal compatible with the downspouts.

3.1.16.1 Terminations

Neatly fit into the drainage connection the downspouts terminating in drainage lines and fill the joints with a portland cement mortar cap sloped away from the downspout. Provide downspouts terminating in splash blocks with elbow-type fittings. Provide splash pans as specified.

3.1.17 Sheet Metal Covering on Flat, Sloped, or Curved Surfaces

Except as specified or indicated otherwise, cover and flash all minor flat, sloped, or curved surfaces such as crickets, bulkheads, dormers and small decks with metal sheets of the material used for flashing; maximum size of sheets, 16 by 18 inches. Fasten sheets to sheathing with metal cleats. Lock seams and solder. Lock aluminum seams as recommended by aluminum manufacturer. Provide an underlayment of roofing felt for all sheet metal covering.

3.1.18 Flashing at Roof Penetrations and Equipment Supports

Provide metal flashing for all pipes, ducts, and conduits projecting through the roof surface and for equipment supports, guy wire anchors, and similar items supported by or attached to the roof deck. Goose-necks, rain hoods, power roof ventilators, and similar items are specified in other sections.

3.2 PAINTING

Touch ups in the field may be applied only after metal substrates have been cleaned and pretreated in accordance with manufacturer's written instructions and products.

Field-paint sheet metal for separation of dissimilar materials.

3.3 CLEANING

Clean exposed sheet metal work at completion of installation. Remove grease and oil films, handling marks, contamination from steel wool, fittings and drilling debris, and scrub-clean. Free the exposed metal surfaces of dents, creases, waves, scratch marks, and solder or weld marks.

3.4 REPAIRS TO FINISH

Scratches, abrasions, and minor surface defects of finish may be repaired in accordance with the manufacturer's printed instructions and as approved. Repair damaged surfaces caused by scratches, blemishes, and variations of color and surface texture. Replace items which cannot be repaired.

3.5 FIELD QUALITY CONTROL

Establish and maintain a Quality Control Plan for sheet metal used in conjunction with roofing to assure compliance of the installed sheet metalwork with the contract requirements. Remove work that is not in compliance with the contract and replace or correct. Include quality control, but not be limited to, the following:

a. Observation of environmental conditions; number and skill level of sheet metal workers; condition of substrate.

b. Verification that specified material is provided and installed.

c. Inspection of sheet metalwork, for proper size(s) and thickness(es), fastening and joining, and proper installation.

3.5.1 Procedure

Submit for approval prior to start of roofing work. Include a checklist of points to be observed. Document the actual quality control observations and inspections. Furnish a copy of the documentation to the Contracting Officer at the end of each day.

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES

Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch		
Downspouts and leaders	16	.032	.015		
Downspout clips and anchors	-	.040 clip .125 anchor	-		
Downspout straps, 2-inch	48 (a)	.060	.050		
Conductor heads	16	.032	.015		
Scupper lining	20	.032	.015		
Strainers, wire diameter or gage	No. 9 gage	.144 diameter	.109 diameter		
Flashings:					
Base	20	.040	.018		
Counter-flashing	16	.032	.015		
Eave	16	-	.015		

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES

Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch		
		-			
		-			
Stepped	16	.032	.015		
Pipe vent sleave					
Coping	16	.040			
Extrusions	-	.075	-		
Sheets, smooth	20	.050	.018		
Edge strip	24	.050	.025		
Gutters:					
Gutter section	16	.032	.015		
Continuous cleat	16	.032	.015		
Hangers, dimensions	1 inch by 1/8 inch (a)	1 inch by .(inch	1 inch by .0 inch		
Joint Cover plates (See Table II)	16	.032	.015		
		-			
(a) Brass.					

TABLE I. SHEET METAL WEIGHTS, THICKNESSES, AND GAGES					
Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch		

TABLE II. SHEET METAL JOINTS			
	TYPE OF JOINT		
Item Designation	Copperl and Stainless Steel	Aluminum	Remarks
Flashings			
Base	One inch 3 inch lap for expansion joint	One inch flat locked, soldered; sealed; 3 inch lap for expansion joint	Aluminum manufacturer's recommended hard setting sealant for locked aluminum joints. Fill each metal expansion joint with a joint sealing compound.

TABLE II. SHEET METAL JOINTS			
TYPE OF JOINT			
Item Designation	Copperl and Stainless Steel	Aluminum	Remarks
		--	
Eave	One inch flat locked, cleated. One inch loose locked, sealed expansion joint, cleated.	One inch flat locked, locked, cleated one inch loose locked, sealed expansion joints, cleated	Same as base flashing.
Stepped	3 inch lap	3 inch lap	--
Edge strip	Butt	Butt	--
Gravel stops:			
Extrusions	--	Butt with 1/2 inch space	Use sheet flashing beneath and a cover plate
Sheet, smooth	Butt with 1/4 inch space	Butt with 1/4 inch space	Use sheet flashing backup plate.
Gutters	1.5 inch lap, riveted and soldered	One inch flat locked riveted and sealed	Aluminum producers recommended hard setting sealant for locked aluminum joints.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 84 00

FIRESTOPPING
05/10, CHG 1: 08/13

PART 1 GENERAL

1.1 SUMMARY

Furnish and install tested and listed firestopping systems, combination of materials, or devices to form an effective barrier against the spread of flame, smoke and gases, and maintain the integrity of fire resistance rated walls, partitions, floors, and ceiling-floor assemblies, including through-penetrations and construction joints and gaps.

a. Through-penetrations include the annular space around pipes, tubes, conduit, wires, cables and vents.

b. Construction joints include those used to accommodate expansion, contraction, wind, or seismic movement; do not allow firestopping material to interfere with the required movement of the joint.

c. Gaps requiring firestopping include gaps between the curtain wall and the floor slab and between the top of the fire-rated walls and the roof or floor deck above and at the intersection of shaft assemblies and adjoining fire resistance rated assemblies.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E119	(2024) Standard Test Methods for Fire Tests of Building Construction and Materials
ASTM E814	(2013a; R 2017) Standard Test Method for Fire Tests of Penetration Firestop Systems
ASTM E1399/E1399M	(1997; R 2022) Standard Test Method for Cyclic Movement and Measuring the Minimum and Maximum Joint Widths of Architectural Joint Systems
ASTM E1966	(2015; R 2019) Standard Test Method for Fire-Resistive Joint Systems
ASTM E2307	(2020) Standard Test Method for Determining Fire Resistance of Perimeter Fire Barrier Systems Using Intermediate-Scale, Multi-story Test

Apparatus

FM GLOBAL (FM)

FM 4991	(2013) Standard for the Approval of Firestop Contractors
FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/

UL SOLUTIONS (UL)

UL 723	(2018; Reprint Jun 2025) UL Standard for Safety Test for Surface Burning Characteristics of Building Materials
UL 1479	(2015; Reprint May 2021) Fire Tests of Through-Penetration Firestops
UL 2079	(2015; Reprint Jul 2020) Tests for Fire Resistance of Building Joint Systems
UL Fire Resistance	(2014) Fire Resistance Directory

1.3 SEQUENCING

Coordinate the specified work with other trades. Apply firestopping materials, at penetrations of pipes and ducts, prior to insulating, unless insulation meets requirements specified for firestopping. Apply firestopping materials. at building joints and construction gaps, prior to completion of enclosing walls or assemblies. Locate cast-in-place firestop devices and install in place before concrete placement. Install pipe, conduit or cable bundles through cast-in-place device after concrete placement but before area is concealed or made inaccessible. Firestop material must be inspected and approved prior to final completion and enclosing of any assemblies that may conceal installed firestop.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Firestopping System; G

SD-03 Product Data

Firestopping Materials; G

SD-06 Test Reports

Inspection; G

SD-07 Certificates

Inspector Qualifications; G

Firestopping Materials

Installer Qualifications; G

1.5 QUALITY ASSURANCE

1.5.1 Installer Qualifications

All firestopping systems must be performed by one experienced firestop contractor. Experienced firestop contractor is deifined as the following:

a. FM Research approved in accordance with FM 4991, or

b. Operating as a UL Certified Firestop Contractor.

Individual building system subcontractors, such as Mechanical, Electrical, Plumbing, Gypsum Wall, etc., are not permitted to install firestopping systems.

A single complete submittal including Shop Drawings, Product Data, and UL details must be provided for all firestopping systems throughout entire project.

1.5.2 Inspector Qualifications

The Firestopping Inspector must meet all of the following:

1. Be completely independent of, and divested from, the Firestopping Installer, the manufacturer, and the supplier of any material or item being inspected, and

2. Not be a competitor of the Firestopping Installer, the contractor, the manufactuer, or supplier of any material or item being inspected, and

3. Have a minimum of two years' experience in construction field inspections of firestopping systems, products, and assemblies.

In addition, the Firestopping Inspector must meet one of the following:

1. Passed the UL Firestop exam within the last three years, or

2. Passed the FM Firestop exam within the last three years, or

3. Passed the International Firestop Council (IFC) exam within the last three years, or

4. Completed the International Code Council (ICC) Firestopping Credential of Learning Achievement within the last three years, or

5. Be a registered Professional Engineer who has passed the National Council of Examiners for Engineering and Surveying (NCEES) Fire Protection Engineer exam. Submit documentation demonstrating experience in construction field inspections of firestopping systems, products, and assemblies for a minimum of 3 relevant projects. Include a description of the project and date of construction completion.

Include in the qualifications subbmittal a notarized statement asserting compliance with the requirements stated in this paragraph.

1.6 DELIVERY, STORAGE, AND HANDLING

Deliver materials in the original unopened packages or containers showing name of the manufacturer and the brand name. Store materials off the ground, protected from damage and exposure to elements and temperatures in accordance with manufacturer requirements. Remove damaged or deteriorated materials from the site. Use materials within their indicated shelf life.

PART 2 PRODUCTS

2.1 FIRESTOPPING SYSTEM

Submit detail drawings including manufacturer's descriptive data, typical details conforming to UL Fire Resistance or other details certified by another nationally recognized testing laboratory, installation instructions or UL listing details for a firestopping assembly in lieu of fire-test data or report. For those firestop applications for which no UL tested system is available through a manufacturer, submit a manufacturer's engineering judgment, derived from similar UL system designs or other tests for review and approval prior to installation. Submittal must indicate the firestopping material to be provided for each type of application. When more than a total of 5 penetrations and/or construction joints are to receive firestopping, provide drawings that indicate location, "F" "T" and "L" ratings, and type of application.

Submit a written report with the floor plans indicating locations and types of penetrations, and types of firestopping used at each location. Record type by UL list printed numbers.

2.2 FIRESTOPPING MATERIALS

Provide firestopping materials, supplied from a single domestic manufacturer, consisting of commercially manufactured, asbestos-free, nontoxic products FM APP GUIDE approved, or UL listed, for use with applicable construction and penetrating items, complying with the following minimum requirements:

2.2.1 Fire Hazard Classification

Provide material that has a flame spread of 25 or less, and a smoke developed rating of 50 or less, when tested in accordance with ASTM E84 or UL 723. Provide an approved firestopping material as listed in UL Fire Resistance or by a nationally recognized testing laboratory.

2.2.2 Toxicity

Provide material that is nontoxic and carcinogen free to humans at all stages of application or during fire conditions and does not contain hazardous chemicals or require harmful chemicals to clean material or equipment.

2.2.3 Fire Resistance Rating

Firestop systems must be UL Fire Resistance listed or FM APP GUIDE approved with "F" rating at least equal to fire-rating of fire wall or floor in which penetrated openings are to be protected. Where required, firestop systems must also have "T" rating at least equal to the fire-rated floor in which the openings are to be protected.

2.2.3.1 Through-Penetrations

Firestopping materials for through-penetrations, as described in paragraph SUMMARY, must provide "F", "T" and "L" fire resistance ratings in accordance with ASTM E814 or UL 1479. Provide fire resistance ratings as follows:

2.2.3.1.1 Penetrations of Fire Resistance Rated Walls and Partitions

F Rating = Rating of wall or partition being penetrated.

2.2.3.2 Construction Joints and Gaps

Fire resistance ratings of construction joints, as described in paragraph SUMMARY, and gaps such as those between floor slabs and curtain walls must be the same as the construction in which they occur. Provide construction joints and gaps with firestopping materials and systems that have been tested in accordance with ASTM E119, ASTM E1966 or UL 2079 to meet the required fire resistance rating. Provide curtain wall joints with firestopping materials and systems that have been tested in accordance with ASTM E2307 to meet the required fire resistance rating. Systems installed at construction joints must meet the cycling requirements of ASTM E1399/E1399M or UL 2079. Provide a minimum class II movement capability for all joints at the intersection of the top of a fire resistance rated wall and the underside of a fire-rated floor, floor ceiling, or roof ceiling assembly.

2.2.4 Material Certification

Submit certificates attesting that firestopping material complies with the specified requirements. Provide certification of compliance with UL 1479 for all intumescent firestop materials used in through penetration systems.

All materials must bear a Listing Label. Manufacturer's container labels must include the manufacturer's name, product name, and product description. Other components of the firestop shall also be identifiable by labeling or other method as approved by the DFPE.

PART 3 EXECUTION

3.1 PREPARATION

The installer must notify the inspector of the arrival of the materials. Prior to installation, the Inspector must verify that all materials received for the installation meet the requirements of the approved Firestopping Materials.

Areas to receive firestopping must be free of dirt, grease, oil, or loose materials which may affect the fitting or fire resistance of the firestopping system. For cast-in-place firestop devices, formwork or metal deck to receive device prior to concrete placement must be sound and capable of supporting device. Prepare surfaces as recommended by the manufacturer.

3.2 INSTALLATION

Completely fill void spaces with firestopping material regardless of geometric configuration, subject to tolerance established by the

manufacturer. Firestopping systems for filling floor voids 4 inches or more in any direction must be capable of supporting the same load as the floor is designed to support or be protected by a permanent barrier to prevent loading or traffic in the firestopped area. Install firestopping in accordance with manufacturer's written instructions. Provide tested and listed firestop systems in the following locations, except in floor slabs on grade:

a. Penetrations of duct, conduit, tubing, cable and pipe through floors and through fire-resistance rated walls, partitions, and ceiling-floor assemblies.

b. Penetrations of vertical shafts such as pipe chases, elevator shafts, and utility chutes.

c. Gaps at the intersection of floor slabs and curtain walls, including inside of hollow curtain walls at the floor slab.

d. Gaps at perimeter of fire-resistance rated walls and partitions, such as between the top of the walls and the bottom of roof decks.

e. Construction joints in floors and fire rated walls and partitions.

f. Other locations where required to maintain fire resistance rating of the construction.

3.2.1 Insulated Pipes and Ducts

Cut and remove thermal insulation where pipes or ducts pass through firestopping, unless insulation meets requirements specified for firestopping. Replace thermal insulation with a material having equal thermal insulating and firestopping characteristics.

3.2.2 Fire Dampers

Install and firestop fire dampers in accordance with Section 23 30 00 HVAC AIR DISTRIBUTION. Firestop installed with fire damper must be tested and approved for use in fire damper system. Firestop installed with fire damper must be tested and approved for use in fire damper system.

3.2.3 Data and Communication Cabling

Seal cabling for data and communication applications with re-enterable firestopping products and devices.

3.2.3.1 Re-Enterable Devices

Provide firestopping devices that are pre-manufactured modular devices, containing built-in self-sealing intumescent inserts. Allow for cable moves, additions or changes without the need to remove or replace any firestop materials. Devices must be capable of maintaining the fire resistance rating of the penetrated membrane at 0 percent to 100 percent visual fill of penetrants; while maintaining "L" rating of <10 cfm/sf measured at ambient temperature and 400 degrees F at 0 percent to 100 percent visual fill.

3.2.3.2 Re-Sealable Products

Provide firestopping pre-manufactured modular products, containing

self-sealing intumescent inserts. Allow for cable moves, additions or changes. Provide devices capable of maintaining the fire resistance rating of the penetrated membrane at 0 percent to 100 percent visual fill of penetrants.

3.3 INSPECTION

For Navy project, install one of each type of penetration and have it inspected and accepted prior to the installation of the remainder of the penetrations by one of the following:

a. The Midlant Division, Naval Facilities Engineering Command, Fire Protection Engineer (DFPE).

b. The Firestopping Inspector, witnessed by a designated Government representative.

c. The Firestopping Inspector, with a detailed Inspection Form submitted to the Midlant Division, Naval Facilities Engieering Command, Fire Protection Engineer (DFPE) for review and approval within two days of the inspection. The Inspection Form must include:

1) General project identification information

2) Name of Firestopping Inspector

3) Location of system with a partial floor plan to highlight location

4) UL system or Engieering Judgement and rating

5) Description of rated assembly being penetrated and type of penetrant

6) Photographs of destructive samples taken or photographs of steps taken during the installation

7) Measurement of cut samples must be shown in photographs with a ruler. Provide photographs of the joint or penetration prior firestopping, after firestopping, and intermediate steps. Photographs may be provided in electronic (.jpg or .pdf) format. Photographs must provide sufficient angles and detail to show conformance with requirements of the system.

8) General observations

9) Statement of compliance or non-compliance

The means of inspection must be coordianted with the DFPE prior to the inspection. At this inspection, the manufacturer's technical representative of the firestopping material must be present. The manufacturer's technical representative may be the Firestopping Installer.

3.3.1 Inspection Standards

3.3.1.1 The Firestopping Inspector must verify that the materials and systems used for firestopping and fire resistive joint systems are listed and labeled for the use intended.

3.3.1.2 The Firestopping Inspector must verify that the required firestop

systems and fire resistive joint systems have been installed.

3.3.1.3 The Firestopping Inspector must verify compliance of the firestop systems and fire resistive joint systems by observing the installation process and by taking and recording measurements of the substrates and materials being installed or by destructive examination of completed installations.

3.3.1.4 Inspection frequency of firestop systems and fire resistive joint systems will depend on the method of inspection and the scope of the project.

3.3.1.4.1 The method of inspection for firestop systems must be one of the following:

a. The Firestopping Inspector must be on site during installation and randomly witness a minimum of 10% of each type of firestop system being installed, or

b. The Firestopping Inspector must conduct a post installation inspection, which requires destructive type verification of the firestop system and repair of the firestop system. A minimum of 2%, but not less than one, of each type of firestop system must be inspected per floor or for each area of a floor when a floor is larger than 10,000 SF. An area consists of 10,000 SF or less.

3.3.1.4.2 The method of inspection for fire resistive joint systems must be one of the following:

a. The Firestopping Inspector must be on site during installation and randomly witness a minimum of 5% of total lineal feet of each type of fire resistive joint system being installed, or

b. The Firestopping Inspector must conduct a post installation inspection in accordance with one of the following, except for mechanical systems, which must be inspected in accordance with paragraph 3.3.1.4.2.a above:

    1) Destructive type verification of the fire resistive joint system and repair of the joint system, or

    2) Disassembly and verification of the components and re-installation of the joint system, or

    3) Visual inspection and verification of the component or entire joint system, where a visual inspection establishes conformance; or

    4) Other appropriate methods showing compliance with the approval process or the manufacturers' instructions.

Inspection must consist of a minimum of one sampling per type of joint system per 500 lineal feet.

3.3.1.5 Prior to construction, the Firestopping Inspector must coordinate with the NAVFAC DFPE to determine the types of firestop systems and subsequently the number of each type that is to be inspected. The determination of a "type" will typically be a function of a unique combination of parameters, including penetrant type (for example, metal

pipe, plastic pipe, cabling), firestop material or device (for example, intumescent caulk, collar, sealant), penetrated substrate (for example, gypsum wall, concrete floor, composite floor deck), and rating of penetrated item.

3.3.1.6 Any type of firestop system that does not comply with this specification will require repair or replacement and re-inspection of that firestop system plus one full additional inspection, of the number specified herein, of that type firestop system. If non-compliance occurs on 10% or more of the quantity of firestop products or firestop systems, then inspection of those particular type firestop systems must cease. The Firestopping Installer must inspect their own work, and repair or replace those like firestops within the area prior to re-commencement of inspections by the Firestopping Inspector.

3.3.1.7 The Firestopping Inspection must maintain inspection forms. All observed deficiencies must be documented and marked on the inspection forms. In addition, the Firestopping Inspector must physically identify the location where a required firestop system has been omitted or where the inspection results indicate that the installed firestop system does not comply with the inspection documents. The Inspection forms must include the following:

a) General project identification information

b) Name of Firestopping Inspector

c) Location of system with a partial floor plan to highlight location

d) UL system or Engineering Judgement and rating

e) Description of rated assembly being penetrated and type of penetrant

f) Photographs of destructive samples taken or photographs of steps taken during the installation

g) Measurement of cut samples must be shown in photographs with a ruler. Provide photographs of the joint or penetration prior firestopping; after firestopping; and intermediate steps. Photographs may be provided in electronic (.jpeg or .pdf) format. Photographs must provide sufficient angles and detail to show conformance with requirements of the system.

h) General observations

i) Statement of compliance or non-compliance

Submit the inspection forms to the DFPE for surveillance within two days of the inspection.

3.3.2 Inspection Reports

Submit inspection report stating that firestopping work has been inspected and found to be applied according to the manufacturer's recommendations and the specified requirements.

3.3.2.1 The report must contain a cover page with the following:

a. The project name, location, and contract number;

b. The name and address of the Firestopping Inspector;

c. The name and address of the Firestopping Installer (s), as well as the prime contractor, if different; and

d. Report date.

3.3.2.2 The report must include drawings indicating locations and types of all penetrations and fire resistive joint systems and types of firestopping used at each location; type must be identified by UL listed printed numbers. Annotated inspected systems with a unique designator that correlates with the Inspection Forms. The drawings must include smoke barriers and partitions and indicate the methods and materials used to protect penetrations.

3.3.2.3 Include UL system details or Engineering Judgements, annotated to identify specific ratings and assembly components.

3.3.2.4 The report must contain a summary page with the following:

a. Types and quantity of each firestop system and fire resistive joint system on the project.

b. The verification method used to ascertain compliance.

c. The quantity of each firestop system and fire resistive joint system inspected on the project and a notarized written statement by the Firestopping Inspector that the number of firestop systems and fire resistive joint systems inspected comply with this specification.

d. Percentages of deficiencies for each type of firestop system and fire resistive joint system referenced.

e. A total number of deficiencies, expressed as a percentage of the total number of firestop systems and fire resistive joint systems inspected.

f. Narrative of inspection observations and description of means and methods used to correct deficiencies. Include a description of deviations from the design documents.

g. Additional information, as determined by the Firestopping Inspector, required to adequately convey compliance.

3.3.2.5 The report must contain copies of all Inspection Forms generated during the inspection process, arranged chronologically.

3.3.2.6 Submit a Final Inspection Report at least 14 days prior to Government acceptance testing for review and approval.

3.3.3 Acceptance

3.3.3.1 The Government may require additional destructive testing at the time of Government acceptance testing. Systems that are subject to destructive testing must be replaced, at no cost to the Government, by the project's qualified Firestopping Installer. Confirmation that the system replaced complies must be provided by the Firestopping Inspector.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 07 92 00

JOINT SEALANTS
08/16, CHG 3: 11/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C509	(2006; R 2021) Standard Specifiaction for Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM C734	(2015; R 2019) Low-Temperature Flexibility of Latex Sealants After Artificial Weathering
ASTM C919	(2022) Standard Practice for Use of Sealants in Acoustical Applications
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM C1193	(2013) Standard Guide for Use of Joint Sealants
ASTM C1311	(2014) Standard Specification for Solvent Release Agents
ASTM C1521	(2013) Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints
ASTM D217	(2019b) Standard Test Methods for Cone Penetration of Lubricating Grease
ASTM D1056	(2020) Standard Specification for Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2022) Adhesive and Sealant Applications

UL SOLUTIONS (UL)

UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Sealants; G

Primers; G

Bond Breakers; G

Backstops; G

SD-06 Test Reports

Field Adhesion; G

SD-07 Certificates

Indoor Air Quality For Interior Sealants; S

Indoor Air Quality For Interior Floor Joint Sealants; S

Indoor Air Quality For Interior Acoustical Sealants; S

1.3 PRODUCT DATA

Include storage requirements, shelf life, curing time, instructions for mixing and application, and accessories. Provide manufacturer's Safety Data Sheets (SDS) for each solvent, primer and sealant material proposed.

1.4 CERTIFICATIONS

1.4.1 Indoor Air Quality Certifications

Submit required indoor air quality certifications in one submittal package.

1.4.1.1 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by

UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body.. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.5 ENVIRONMENTAL CONDITIONS

Apply sealant when the ambient temperature is between 40 and 90 degrees F.

1.6 DELIVERY AND STORAGE

Deliver materials to the jobsite in unopened manufacturers' sealed shipping containers, with brand name, date of manufacture, color, and material designation clearly marked thereon. Label elastomeric sealant containers to identify type, class, grade, and use. Handle and store materials in accordance with manufacturer's printed instructions. Prevent exposure to foreign materials or subjection to sustained temperatures exceeding 90 degrees F or lower than 0 degrees F. Keep materials and containers closed and separated from absorptive materials such as wood and insulation.

1.7 QUALITY ASSURANCE

1.7.1 Compatibility with Substrate

Verify that each sealant is compatible for use with each joint substrate in accordance with sealant manufacturer's printed recommendations for each application.

1.7.2 Joint Tolerance

Provide joint tolerances in accordance with manufacturer's printed instructions.

1.7.3 Adhesion

Provide in accordance with ASTM C1193 or ASTM C1521.

PART 2 PRODUCTS

2.1 SEALANTS

Provide sealant products that have been tested, found suitable, and documented as such by the manufacturer for the particular substrates to which they will be applied.

2.1.1 Interior Sealants

Provide ASTM C920, Type S or M, Grade NS, Class 12.5, Use NT. Provide sealant products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide certification or validation of indoor air quality for interior sealants. Location(s) and color(s) of sealant for the following. Note, color "as selected" refers to manufacturer's full range of color options

LOCATION	COLOR
a. Small voids between walls or partitions and adjacent lockers, casework, shelving, door frames, built-in or surface mounted equipment and fixtures, and similar items.	As selected
b. Perimeter of frames at doors, windows, and access panels which adjoin exposed interior concrete and masonry surfaces.	As selected
c. Joints of interior masonry walls and partitions which adjoin columns, pilasters, concrete walls, and exterior walls unless otherwise detailed.	As selected
d. Joints between edge members for acoustical tile and adjoining vertical surfaces.	AAs selected
e. Interior locations, not otherwise indicated or specified, where small voids exist between materials specified to be painted.	As selected
f. Joints formed where non-planar tile surfaces meet.	As Selected
g. Joints formed between tile floors and tile base cove; joints between tile and dissimilar materials; joints occurring where substrates change.	As selected
h. Behind escutcheon plates at valve pipe penetrations and showerheads in showers.	As selected

2.1.2 Exterior Sealants

For joints in vertical surfaces, provide ASTM C920, Type S or M, Grade NS, Class 25, Use NT. For joints in horizontal surfaces, provide ASTM C920, Type S or M, Grade P, Class 25, Use T. Provide location(s) and color(s) of sealant as follows. Note, color "as selected" refers to manufacturer's full range of color options:

LOCATION	COLOR
a. Joints and recesses formed where frames and subsills of windows, doors, louvers, and vents adjoin masonry, concrete, or metal frames. Use sealant at both exterior and interior surfaces of exterior wall penetrations.	Match adjacent surface color

LOCATION	COLOR
b. Expansion and control joints.	As selected
c. Interior face of expansion joints in exterior concrete or masonry walls where metal expansion joint covers are not required.	As selected
d. Voids where items pass through exterior walls.	As selected
e. Metal-to-metal joints where sealant is indicated or specified.	As selected
f. Joints between ends of fascia, flashings, and adjacent walls.	As selected

2.1.3 Floor Joint Sealants

ASTM C920, Type S or M, Grade P, Class 25, Use T. Provide sealant products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide certification or validation of indoor air quality for interior floor joint sealants. Provide location(s) and color(s) of sealant as follows. Note, color "as selected" refers to manufacturer's full range of color options:

LOCATION	COLOR
a. Seats of metal thresholds for exterior doors.	As selected
a. Control and expansion joints in floors, slabs, ceramic tile, and walkways.	As selected

2.1.4 Acoustical Sealants

Rubber or polymer based acoustical sealant in accordance with ASTM C919 to have a flame spread of 25 or less and a smoke developed rating of 50 or

less when tested in accordance with ASTM E84. Provide non-staining acoustical sealant with a consistency of 250 to 310 when tested in accordance with ASTM D217. Acoustical sealant must remain flexible and adhesive after 500 hours of accelerated weathering as specified in ASTM C734. Provide sealant products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide certification or validation of indoor air quality for interior acoustical sealants.

2.2 PRIMERS

Non-staining, quick drying type and consistency as recommended by the sealant manufacturer for the particular application. Provide primers for interior applications that meet the indoor air quality requirements of the paragraph SEALANTS above.

2.3 BOND BREAKERS

Type and consistency as recommended by the sealant manufacturer to prevent adhesion of the sealant to the backing or to the bottom of the joint. Provide bond breakers for interior applications that meet the indoor air quality requirements of the paragraph SEALANTS above.

2.4 BACKSTOPS

Provide neoprene, butyl, polyurethane, or polyethylene foams free from oil or other staining elements as recommended by sealant manufacturer. Provide 25 to 33 percent oversized backing for closed cell material, unless otherwise indicated. Provide backstop material that is compatible with sealant. Do not use oakum or other types of absorptive materials as backstops.

2.4.1 Rubber

Provide in accordance with ASTM D1056, Type 2, closed cell, Class A, round cross section for cellular rubber sponge backing.

2.4.2 Synthetic Rubber

Provide in accordance with ASTM C509, Option I, Type I preformed rods or tubes for synthetic rubber backing.

2.4.3 Neoprene

Provide in accordance with ASTM D1056, closed cell expanded neoprene cord Type 2, Class C, Grade 2C2 neoprene backing.

2.4.4 Butyl Rubber Based

Provide in accordance with ASTM C1311, from a single component, with solvent release. color as selected from manufacturer's full range of color choices.

2.4.5 Silicone Rubber Base

Provide in accordance with ASTM C920, from a single component, with solvent release, Non-sag, Type S, Grade NS, Class 25. Color as selected

from manufacturer's full range of color choices.

2.5 CLEANING SOLVENTS

Provide type(s) recommended by the sealant manufacturer and in accordance with environmental requirements herein. Protect adjacent aluminum surfaces from solvents. Provide solvents for interior applications that meet the indoor air quality requirements of the paragraph SEALANTS above.

PART 3 EXECUTION

3.1 FIELD QUALITY CONTROL

Perform a field adhesion test in accordance with manufacturer's instructions and ASTM C1193, Method A or ASTM C1521, Method A, Tail Procedure. Remove sealants that fail adhesion testing; clean substrates, reapply sealants, and re-test. Test sealants adjacent to failed sealants. Submit field adhesion test report indicating tests, locations, dates, results, and remedial actions taken.

3.2 SURFACE PREPARATION

Prepare surfaces according to manufacturer's printed installation instructions. Clean surfaces from dirt, frost, moisture, grease, oil, wax, lacquer, paint, or other foreign matter that would destroy or impair adhesion. Remove oil and grease with solvent; thoroughly remove solvents prior to sealant installation. Wipe surfaces dry with clean cloths. When resealing an existing joint, remove existing caulk or sealant prior to applying new sealant. For surface types not listed below, provide in accordance with sealant manufacturer's printed instructions for each specific surface.

3.2.1 Steel Surfaces

Remove loose mill scale by sandblasting or, if sandblasting is impractical or would damage finished work, scraping and wire brushing. Remove protective coatings by sandblasting or using a residue free solvent. Remove resulting debris and solvent residue prior to sealant installation.

3.2.2 Aluminum Surfaces

Remove temporary protective coatings from surfaces that will be in contact with sealant. When masking tape is used as a protective coating, remove tape and any residual adhesive prior to sealant application. For removing protective coatings and final cleaning, use non-staining solvents recommended by the manufacturer of the item(s) containing aluminum surfaces.

3.2.3 Concrete and Masonry Surfaces

Where surfaces have been treated with curing compounds, oil, or other such materials, remove materials by sandblasting or wire brushing. Remove laitance, efflorescence and loose mortar from the joint cavity. Remove resulting debris prior to sealant installation.

3.3 SEALANT PREPARATION

Do not add liquids, solvents, or powders to sealants. Mix multicomponent elastomeric sealants in accordance with manufacturer's printed

instructions.

3.4 APPLICATION

3.4.1 Joint Width-To-Depth Ratios

Acceptable Ratios:

JOINT WIDTH	JOINT DEPTH	
	Minimum	Maximum
For metal, glass, or other nonporous surfaces:		
1/4 inch (minimum)	1/4 inch	1/4 inch
over 1/4 inch	1/2 of width	Equal to width
For wood, concrete, masonry, stone:		
1/4 inch (minimum)	1/4 inch	1/4 inch
over 1/4 inch to 1/2 inch	1/4 inch	Equal to width
over 1/2 inch to 1 inch	1/2 inch	5/8 inch
Over 1 inch	prohibited	

Unacceptable Ratios: Where joints of acceptable width-to-depth ratios have not been provided, clean out joints to acceptable depths and grind or cut to acceptable widths without damage to the adjoining work. Grinding is prohibited at metal surfaces.

3.4.2 Unacceptable Sealant Use

Do not install sealants in lieu of other required building enclosure weatherproofing components such as flashing, drainage components, and joint closure accessories, or to close gaps between walls, floors, roofs, windows, and doors, that exceed acceptable installation tolerances. Remove sealants that have been used in an unacceptable manner and correct building enclosure deficiencies to comply with contract documents requirements.

3.4.3 Masking Tape

Place masking tape on the finished surface on one or both sides of joint cavities to protect adjacent finished surfaces from primer or sealant smears. Remove masking tape within 10 minutes of joint filling and tooling.

3.4.4 Backstops

Provide backstops dry and free of tears or holes. Tightly pack the back or bottom of joint cavities with backstop material to provide joints in specified depths. Provide backstops where indicated and where backstops are not indicated but joint cavities exceed the acceptable maximum depths specified in JOINT WIDTH-TO-DEPTH RATIOS Table.

3.4.5 Primer

Clean out loose particles from joints immediately prior to application of. Apply primer to joints in concrete masonry units, wood, and other porous surfaces in accordance with sealant manufacturer's printed instructions. Do not apply primer to exposed finished surfaces.

3.4.6 Bond Breaker

Provide bond breakers to surfaces not intended to bond in accordance with, sealant manufacturer's printed instructions for each type of surface and sealant combination specified.

3.4.7 Sealants

Provide sealants compatible with the material(s) to which they are applied. Do not use a sealant that has exceeded its shelf life or has jelled and cannot be discharged in a continuous flow from the sealant gun. Apply sealants in accordance with the manufacturer's printed instructions with a gun having a nozzle that fits the joint width. Work sealant into joints so as to fill the joints solidly without air pockets. Tool sealant after application to ensure adhesion. Apply sealant uniformly smooth and free of wrinkles. Upon completion of sealant application, roughen partially filled or unfilled joints, apply additional sealant, and tool smooth as specified. Apply sealer over sealants in accordance with the sealant manufacturer's printed instructions.

3.5 PROTECTION AND CLEANING

3.5.1 Protection

Protect areas adjacent to joints from sealant smears. Masking tape may be used for this purpose if removed 5 to 10 minutes after the joint is filled and no residual tape marks remain.

3.5.2 Final Cleaning

Upon completion of sealant application, remove remaining smears and stains and leave the work in a clean and neat condition.

a. Masonry and Other Porous Surfaces: Immediately remove fresh sealant that has been smeared on adjacent masonry, rub clean with a solvent, and remove solvent residue, in accordance with sealant manufacturer's printed instructions. Allow excess sealant to cure for 24 hour then remove by wire brushing or sanding. Remove resulting debris.

b. Metal and Other Non-Porous Surfaces: Remove excess sealant with a solvent moistened cloth. Remove solvent residue in accordance with solvent manufacturer's printed instructions.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 08 11 13

STEEL DOORS AND FRAMES
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding Code - Steel

ASTM INTERNATIONAL (ASTM)

ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A879/A879M	(2012; R 2017) Standard Specification for Steel Sheet, zinc Coated by the Electrolytic Process for Applications Requiring Designation of the Coating Mass on Each Surface
ASTM A924/A924M	(2022a) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM C578	(2023) Standard Specification for Rigid, Cellular Polystyrene Thermal Insulation
ASTM C591	(2022) Standard Specification for Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
ASTM C612	(2014; R 2019) Standard Specification for Mineral Fiber Block and Board Thermal Insulation
ASTM D2863	(2019) Standard Test Method for Measuring the Minimum Oxygen Concentration to Support Candle-Like Combustion of Plastics (Oxygen Index)

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.115	(2016) Hardware Preparation in Steel Doors and Steel Frames

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80	(2025) Standard for Fire Doors and Other Opening Protectives
NFPA 105	(2022) Standard for Smoke Door Assemblies and Other Opening Protectives
NFPA 252	(2022) Standard Methods of Fire Tests of Door Assemblies

STEEL DOOR INSTITUTE (SDI/DOOR)

SDI/DOOR 113	(2013; R2018) Standard Practice for Determining the Steady-State Thermal Transmittance of Steel Door and Frame Assemblies
SDI/DOOR A250.6	(2015) Recommended Practice for Hardware Reinforcing on Standard Steel Doors and Frames
SDI/DOOR A250.8	(2017) Specifications for Standard Steel Doors and Frames
SDI/DOOR A250.11	(2012) Recommended Erection Instructions for Steel Frames

UL SOLUTIONS (UL)

UL 10C	(2016; Reprint May 2021) UL Standard for Safety Positive Pressure Fire Tests of Door Assemblies

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Doors; G

Frames; G

Accessories

Schedule of Doors; G

Schedule of Frames; G

SD-03 Product Data

Doors; G

Recycled Content for Steel Door Product; S

Frames; G

Recycled Content for Steel Frame Product; S

Accessories

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver doors, frames, and accessories undamaged and with protective wrappings or packaging. Provide temporary steel spreaders securely fastened to the bottom of each welded frame. Store doors and frames on platforms under cover in clean, dry, ventilated, and accessible locations, with 1/4 inch airspace between doors. Remove damp or wet packaging immediately and wipe affected surfaces dry. Replace damaged materials with new.

PART 2 PRODUCTS

2.1 STANDARD STEEL DOORS

SDI/DOOR A250.8, except as specified otherwise. Prepare doors to receive door hardware as specified in Section 08 71 00 DOOR HARDWARE. Undercut where indicated. Provide exterior doors with top edge closed flush and sealed to prevent water intrusion. Provide doors at 1-3/4 inch thick, unless otherwise indicated. Provide door material that uses a minimum of 25 percent recycled content. Provide data indicating percentage of recycled content for steel door product.

2.1.1 Classification - Level, Performance, Model

2.1.1.1 Heavy Duty Doors

SDI/DOOR A250.8, Level 2, physical performance Level B, Model 2, with core construction as required by the manufacturer, of size(s) and design(s) indicated. Where vertical stiffener cores are required, the space between the stiffeners must be filled with board insulation.

2.1.1.2 Maximum Duty Doors

SDI/DOOR A250.8, Level 4, physical performance Level A, Model 2 with core construction as required by the manufacturer for indicated exterior doors, of size(s) and design(s) indicated. Where vertical stiffener cores are required, the space between the stiffeners must be filled with board insulation.

2.2 ACCESSORIES

2.2.1 Astragals

For pairs of exterior steel doors which will not have aluminum astragals or removable mullions, as specified in Section 08 71 00 DOOR HARDWARE provide overlapping steel astragals with the doors.

2.2.2 Moldings

Provide moldings around glass of interior and exterior doors and louvers of interior doors. Provide nonremovable moldings on outside of exterior doors and on corridor side of interior doors. Other moldings may be stationary or removable. Secure inside moldings to stationary moldings,

or provide snap-on moldings.

2.3 INSULATION CORES

Provide insulating cores at all exterior doors, and provide an apparent U-factor of .48 in accordance with SDI/DOOR 113 and conforming to:

a. Rigid Cellular Polyisocyanurate Foam: ASTM C591, Type I or II, foamed-in-place or in board form, with oxygen index of not less than 22 percent when tested in accordance with ASTM D2863; or

b. Rigid Polystyrene Foam Board: ASTM C578, Type I or II; or

c. Mineral board: ASTM C612, Type I.

2.4 STANDARD STEEL FRAMES

SDI/DOOR A250.8, Level 4 for exterior doors and Level 2 for interior doors . Form frames to sizes and shapes indicated, with welded corners. . Provide frame product that uses a minimum of 25 percent recycled content. Provide data indicating percentage of recycled content for steel frame product.

2.4.1 Welded Frames

Continuously weld frame faces at corner joints. Mechanically interlock or continuously weld stops and rabbets. Grind welds smooth.

Weld frames in accordance with the recommended practice of the Structural Welding Code Sections 1 through 6, AWS D1.1/D1.1M and in accordance with the practice specified by the producer of the metal being welded.

2.4.2 Mullions and Transom Bars

Provide mullions and transom bars of closed or tubular construction with heads and jambs butt-welded together. Bottom of door mullions must have adjustable floor anchors and spreader connections.

2.4.3 Stops and Beads

Provide formed and loose stops and beads from 20 gage steel. Provide for glazed and other openings in standard steel frames. Secure beads to frames with oval-head, countersunk Phillips self-tapping sheet metal screws or concealed clips and fasteners. Space fasteners approximately 12 to 16 inch on center. Miter molded shapes at corners. Butt or miter square or rectangular beads at corners.

2.4.4 Anchors

Provide anchors to secure the frame to adjoining construction. Provide steel anchors, zinc-coated not lighter than 18 gage.

2.4.4.1 Wall Anchors

Provide at least three anchors for each jamb. For frames which are more than 7.5 feet in height, provide one additional anchor for each jamb for each additional 2.5 feet or fraction thereof.

a. Masonry: Provide anchors of corrugated or perforated steel straps

or 3/16 inch diameter steel wire, adjustable or T-shaped;

b. Stud partitions: Weld or otherwise securely fasten anchors to backs of frames. Design anchors to be fastened to closed steel studs with sheet metal screws, and to open steel studs by wiring or welding;

2.4.4.2 Floor Anchors

Provide floor anchors drilled for 3/8 inch anchor bolts at bottom of each jamb member.

2.5 FIRE AND SMOKE DOORS AND FRAMES

Provide fire and smoke doors and frames in accordance with NFPA 80 and NFPA 105 and this specification. Include insulated core materials in fire doors where required.

2.5.1 Labels

Provide fire doors and frames bearing the label of Underwriters Laboratories (UL), Factory Mutual Engineering and Research (FM), or Warnock Hersey International (WHI) attesting to the rating required. Testing must be in accordance with NFPA 252 or UL 10C. Provide labels that are metal with raised letters, bearing the name or file number of the door and frame manufacturer. Labels must be permanently affixed at the factory to frames and to the hinge edge of the door. Do not paint door and labels.

2.5.2 Astragal on Fire and Smoke Doors

On pairs of labeled fire doors, conform to NFPA 80 and UL requirements. On smoke control doors, conform to NFPA 105.

2.6 EXTERIOR FRAMES

Provide thermal insulation in all exterior frames. Provide frames of a minimum Level 4, with frames of a minimum thickness of 0.067 inch, 14 gage.

2.7 HARDWARE PREPARATION

Drill and tap doors and frames to receive finish hardware. Prepare doors and frames for hardware in accordance with the applicable requirements of SDI/DOOR A250.8 and SDI/DOOR A250.6. For additional requirements refer to ANSI/BHMA A156.115. Drill and tap for surface-applied hardware at the project site. Build additional reinforcing for surface-applied hardware into the door at the factory. Punch door frames, with the exception of frames that will have weatherstripping, to receive a minimum of two rubber door silencers on lock side of single doors and one silencer for each leaf at heads of double doors. Set lock strikes out to provide clearance for silencers.

2.8 FINISHES

2.8.1 Hot-Dip Zinc-Coated and Factory-Primed Finish

Fabricate doors and frames from hot dipped zinc coated steel, alloyed type, that complies with ASTM A924/A924M and ASTM A653/A653M. The coating weight must meet or exceed the minimum requirements for coatings having

0.4 ounces per square foot, total both sides, i.e., A40. Repair damaged zinc-coated surfaces by the application of zinc dust paint. Thoroughly clean and chemically treat to insure maximum paint adhesion. Factory prime as specified in SDI/DOOR A250.8.

2.8.2 Electrolytic Zinc-Coated Anchors and Accessories

Provide electrolytically deposited zinc-coated steel in accordance with ASTM A879/A879M, Commercial Quality, Coating Class A. Phosphate treat and factory prime zinc-coated surfaces as specified in SDI/DOOR A250.8.

2.9 FABRICATION AND WORKMANSHIP

Provide finished doors and frames that are strong and rigid, neat in appearance, and free from defects, waves, scratches, cuts, dents, ridges, holes, warp, and buckle. Provide molded members that are clean cut, straight, and true, with joints coped or mitered, well formed, and in true alignment. Dress exposed welded and soldered joints smooth. Design door frame sections for use with the wall construction indicated. Corner joints must be well formed and in true alignment. Conceal fastenings where practicable. Design frames in exposed masonry walls or partitions to allow sufficient space between the inside back of trim and masonry to receive caulking compound.

2.10 PROVISIONS FOR GLAZING

Scheduled interior doors receive 0.25 inch glass and scheduled exterior doors receive 1 inch insulated glass composites. Glass is specified in Section 08 81 00, GLAZING.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Frames

Set frames in accordance with SDI/DOOR A250.11. Plumb, align, and brace securely until permanent anchors are set. Anchor bottoms of frames with expansion bolts or powder-actuated fasteners. Build in or secure wall anchors to adjoining construction.

3.1.2 Doors

Hang doors in accordance with clearances specified in SDI/DOOR A250.8. After erection and glazing, clean and adjust hardware.

3.1.3 Fire and Smoke Doors and Frames

Install fire doors and frames, including hardware, in accordance with NFPA 80. Install fire rated smoke doors and frames in accordance with NFPA 80 and NFPA 105.

3.2 PROTECTION

Protect doors and frames from damage. Repair damaged doors and frames prior to completion and acceptance of the project or replace with new, as directed. Wire brush rusted frames until rust is removed. Clean thoroughly. Apply an all-over coat of rust-inhibitive paint of the same

type used for shop coat.

3.3 CLEANING

Upon completion, clean exposed surfaces of doors and frames thoroughly. Remove mastic smears and other unsightly marks.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 08 11 16

ALUMINUM DOORS AND FRAMES
05/17, CHG 2: 11/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 90.1 - IP	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B209M	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric)
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B221M	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)
ASTM E283	(2019) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E331	(2000; R 2023) Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference
ASTM E1886	(2019) Standard Test Method for Performance of Exterior Windows, Curtain Walls, Doors, and Impact Protective Systems Impacted by Missile(s) and Exposed to Cyclic Pressure Differentials
ASTM E1996	(2017) Standard Specification for Performance of Exterior Windows, Curtain Walls, Doors, and Impact Protective

Systems Impacted by Windborne Debris in Hurricanes

NATIONAL FENESTRATION RATING COUNCIL (NFRC)

NFRC 100 (2020) Procedure for Determining Fenestration Product U-Factors

NFRC 200 (2020) Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence

1.2 PERFORMANCE REQUIREMENTS

1.2.1 Structural Calculations

1.2.2 Wind Borne Debris

Provide impact resistant door assemblies meeting the Windborne-Debris-Impact Resistant Performance requirements of ASTM E1996 and ASTM E1886 as follows:

(1) Pass missile-impact tests when tested according to ASTM E1886 and meeting performance requirements according to ASTM E1996 for missiles A and D in Table 2.

1.2.3 Air Infiltration

When tested in accordance with ASTM E283, air infiltration per door leaf cannot exceed 0.6 cubic feet per minute per square foot of fixed area at a test pressure of 6.24 pounds per square foot.

1.2.4 Water Penetration

When tested in accordance with ASTM E331, there can be no water penetration at a pressure of 2.86 pounds per square foot of fixed area.

1.2.5 Thermal Transmittance, Solar Heat Gain, Visible Light Transmittance

Provide products bearing NFRC Project Label Certificates for Fenestration verifying compliance with requirements for each assembly indicated. An NFRC Bid Report, or approved equal, for field assembled exterior doors may be submitted in lieu of Project Label Certificates for Fenestration if such reports are created in accordance with NFRC CAMP procedures and are provided by the manufacturer. Such alternate reports may be submitted with shop drawings, however, NFRC validated Project Label Certificates for Fenestration are required as a Closeout Submittal. Contact NFRC for information on NFRC 100 and NFRC 200 Compliance and Monitoring Program (CAMP) rating requirements: http://www.nfrc.org/industry/certification/compliance-and-monitoring-program-camp/

1.2.5.1 U-Factor

Provide exterior glazed assemblies, including aluminum entrances doors with greater than 50 percent glazed area, certified by the NFRC as having a whole window U-factor of 0.77 or less as determined in accordance with ASHRAE 90.1 - IP and as verified in accordance with NFRC 100.

1.2.5.2 Solar Heat Gain Coefficient (SHGC)

Provide exterior glazed assemblies, including aluminum entrances doors with greater than 50 percent glazed area, certified by the National Fenestration Rating Council with a whole window SHGC of 0.25 or less as determined in accordance with ASHRAE 90.1 - IP and as verified in accordance with NFRC 200.

1.2.5.3 Visible Light Transmittance (VLT)

Provide exterior glazed assemblies, including aluminum entrances doors with greater than 50 percent glazed area, certified by the NFRC with a whole window VLT of 75% or greater as determined in accordance with ASHRAE 90.1 - IP and as verified in accordance with NFRC 200.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

For Each Type of Door and Frame Assembly; G

SD-03 Product Data

For Each Type of Door and Frame Assembly; G

Recycled Content of Aluminum Material; S

SD-04 Samples

Finish Samples; G

SD-05 Design Data

Structural Calculations for Deflection and Antiterrorism; G

SD-06 Test Reports

Air Infiltration; G

Water Penetration; G

SD-07 Certificates

NFRC Project Label Certificates for Fenestration; G

SD-08 Manufacturer's Instructions

Installation of Each Type of Door and Frame Assembly; G

SD-10 Operation and Maintenance Data

Adjustments, Cleaning, and Maintenance; G

SD-11 Closeout Submittals

NFRC Project Label Certificates for Fenestration; G

1.4 DELIVERY, STORAGE, AND HANDLING

Inspect materials delivered to the site for damage. Unload and store with minimum handling. Provide storage space in dry location with adequate ventilation, free from dust or water, and easily accessible for inspection and handling. Stack materials on non-absorptive strips or wood platforms. Do not cover doors and frames with tarps, polyethylene film, or similar coverings. Protect finished surfaces during shipping and handling using manufacturer's standard method. Do not apply coatings or lacquers to surfaces to which caulking and glazing compounds must adhere.

1.5 QUALITY CONTROL

1.5.1 Shop Drawing

Indicate elevations and sections for each type of door and frame assembly. Show sizes and details of each assembly, frame construction, thickness and gages of metal, details of door and frame construction, proposed method(s) of anchorage, glazing details, provisions for an location of hardware, mullion details, method and materials for flashing and weatherstripping, miscellaneous trim, installation details, and other related items necessary for a complete representation of all components.

Procure cut sheets for GFGI hardware from the Government. Coordinate GFGI hardware items with furnished hardware items indicated in applicable hardware sets. Use templates to prepare doors and frames for GFGI hardware selections.

1.5.2 Finish Samples

Submit two finish sample chips for each type of finish indicated.

1.5.3 Operation and Maintenance Data

Submit detailed instructions for installation, adjustments, cleaning, and maintenance of each type of assembly indicated.

PART 2 PRODUCTS

2.1 DOORS AND FRAMES

Provide swing-type aluminum doors and frames of size, design, and location indicated. Provide doors complete with frames, framing members , trim, and accessories. Coordinate side lites, window walls, adjacent curtainwall with Section 08 41 13 ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS.

2.2 MATERIALS

2.2.1 Anchors

Stainless steel or steel with hot-dipped galvanized finish.

2.2.2 Weatherstripping

Continuous wool pile, silicone treated, or type recommended by door manufacturer.

2.2.3 Aluminum Alloy for Doors and Frames

ASTM B221M, ASTM B221, Alloy 6063-T5 for extrusions. ASTM B209M, ASTM B209, alloy and temper best suited for aluminum sheets and strips. Provide aluminum materials that include a minimum of 30 percent recycled content. Provide data indicating percentage of recycled content of aluminum material.

2.2.4 Fasteners

Hard aluminum or stainless steel.

2.2.5 Structural Steel

ASTM A36/A36M.

2.2.6 Finisht

Give aluminum extrusions for heavy commercial applications a pretreatment to enhance adhesion followed by a caustic etch or alkaline wash for cleaning and degreasing. Apply a phosphate spray or chromate conversion treatment to protect against humidity and corrosive chemicals. Furnish an organic coating treatment conforming to AAMA 2605 to obtain a 70% PVDF coating. Provide a two coat application consisting of 0.2 mils of primer with a 1.0 mil topcoat that achieves a 1.2 mil thickness.

Aluminum doors and frames are slate gray as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC.

2.3 FABRICATION

2.3.1 Aluminum Frames

Extruded aluminum shapes with contours approximately as indicated. Provide removable glass stops and glazing beads for frames accommodating fixed glass. Use countersunk stainless steel Phillips screws for exposed fastenings, and space not more than 12 inches on center. Mill joints in frame members to a hairline fit, reinforce, and secure mechanically.

2.3.2 Aluminum Doors

Of type, size, and design indicated and minimum 1-3/4 inch thick. minimum wall thickness, 0.125 inch, except beads and trim, 0.050 inch. Door sizes shown are nominal; include standard clearances as follows: 0.093 inch at hinge and lock stiles, 0.125 inch between meeting stiles, 0.125 inch at top rails, 0.187 inch between bottom and threshold, and 0.687 inch between bottom and floor. Provide bevel single-acting doors 0.063 or 0.125 inch at lock, hinge, and meeting stile edges.

2.3.2.1 Full Glazed Stile and Rail Doors

Provide doors with stiles and rails as indicated. Fabricate from extruded aluminum hollow seamless tubes or from a combination of open-shaped members interlocked or welded together. Fasten top and bottom rail together by means of welding or by 3/8 or 1/2 inch diameter cadmium-plated

tensioned steel tie rods. Provide an adjustable mechanism of jack screws or other methods in the top rail to allow for minor clearance adjustments after installation.

2.3.3 Welding and Fastening

Provide door corner construction consisting of mechanical clip fastening, SIGMA deep penetration plug welds and 1 1/8 inch long fillet welds inside and outside all four corners. Provide a hook-in type exterior glazing stop with EPDM glazing gaskets reinforced with non-stretchable cord. Provide an interior glazing stop that is mechanically fastened to the door member and that incorporates a silicone-compatible spacer used with silicone sealant.

Where possible, locate welds on unexposed surfaces. Dress welds on exposed surfaces smoothly. Select welding rods, filler wire, and flux to produce a uniform texture and color in finished work. Remove flux and spatter from surfaces immediately after welding. Exposed screws or bolts will be permitted only in inconspicuous locations, and must have countersunk heads. Weld concealed reinforcements for hardware in place.

2.3.4 Weatherstripping

Equip meeting stiles on pairs of doors with an adjustable astragal using wool pile with a polymeric fin. Door weatherstripping consists of a thermoplastic elastomer weatherstripping on a tubular shape with a semi-rigid polymeric backing. Provide on stiles and rails of doors. Fit into slots which are integral with doors or frames. Provide EPDM blade gasket sweep strips in an aluminum extrusions applied to bottom rails with concealed fasteners. Color metal sweep components to match mounting surface aluminum finishes. Weatherstripping must be replaceable without special tools, and adjustable at meeting rails of pairs of doors. During installation, verify doors swing freely and close positively. Provide weatherstripping that meets specified performance tests. Refer to paragraph AIR INFILTRATION for air leakage requirements and testing.

2.3.5 Anchors

On the backs of subframes, provide anchors of the sizes and shapes indicated for securing subframes to adjacent construction. Anchor transom bars at ends and mullions at head and sill. Reinforce and anchor freestanding door frames to floor and wall constructions. Place anchors near top and bottom of each jamb and at intermediate points not more than 25 inch apart.

2.3.6 Provisions for Hardware

Coordinate with Section 08 71 00 DOOR HARDWARE. Deliver hardware templates and hardware (except field-applied hardware) to the door manufacturer for use in fabrication of aluminum doors and frames. Cut, reinforce, drill, and tap doors and frames at the factory to receive template hardware. Provide doors to receive surface-applied hardware, except push plates, kick plates, and mop plates, with reinforcing only; drill and tap in the field. Provide hardware reinforcements of stainless steel or steel with hot-dipped galvanized finish, and secure with stainless steel screws.

2.3.6.1 Thresholds

Thresholds are 4 inch wide aluminum extrusions and ANSI 117.1 compliant.

2.3.6.2 Offset Pivot Hinges

Offset pivot hinges are cast aluminum. Bronze, self lubricating bearings are press fit into frames, and internal pivots are stainless steel complying with ANSI A 156.4, Grade 1. Hardware incorporates a means of adjusting clearances. Color pivot hinges to match the door.

2.3.6.3 Extruded Push and Pull Bars

Pulls are 1 inch diameter, styled extruded aluminum fabrications with canted offset handle. Mounting is 9 inches on center, handicap accessible and enables easy access to lock cylinders. Push bars are similar, with unique styling that directs occupants to push on the correct door sides.

2.3.6.4 Retail Deadlocks

Concealed retail deadlock for narrow or wide stile doors has a 1.5 inch backset and a corrosion resistant, steel plated case measuring 1 inch wide by 6 inches high by 2.25 inches in depth. Face plate dimensions are 1 inch wide by 6.875 high. Furnish a box strike with trim plate to receive an eight ply, laminated stainless steel bolt that has a 1.375 inch throw. The center bolt ply has an alumina ceramic core that defeats hacksaw attacks including rod type super hacksaws. Bolts measure 0.625 inches thick by 1.375 inches high by 2.875 inches in length. Deadlock receives 1.15625 inch diameter by 1 inch long back to back mortise cylinders or thumb turn with 1.15625 inch diameter by 1 inch long mortise cylinder.

2.3.6.5 Two Point Flushbolts

Auto release, two point flush bolt is installed on the inactive leaf of a door pair. Headers and thresholds are pinned with 0.375 inch, hexagonal stainless steel bolts directed by guides and having a 0.71875 inch throw. Bolt strikes are 0.5 inch holes in aluminum headers and thresholds. The assembly incorporates a device that prevents the entry of the active door bolt unless vertical bolts are engaged. Vertical bolts cannot be disengaged unless the active door bolt is unlocked. An hourglass shaped turn reveals a red lettered indicator of LOCKED when the inactive leaf is secure.

2.3.7 Provisions for Glazing

Design glazing beads to receive thickness indicated for each glazed assembly. Insulating glass conmposites for exterior locations have a 1 inch thicness. Glass for interior locations has a 0.25 inch thickness. Coordinate requirements with Section 08 81 00 GLAZING.

PART 3 EXECUTION

3.1 INSTALLATION

Plumb, square, level, and align frames and framing members to receive doors, adjoining side lites, and adjoining window walls. Anchor frames to adjacent construction as indicated and in accordance with manufacturer's

printed instructions and the approved shop drawings. Install anchorage that complies with applicable structural requirements. Anchor bottom of each frame to rough floor construction with 3/32 inch thick minimum stainless steel angle clips secured to back of each jamb and to floor construction; use stainless steel bolts and expansion rivets for fastening clip anchors. Hang doors to produce clearances specified in paragraph ALUMINUM DOORS. After erection and glazing, adjust doors and hardware to operate properly.

3.2 Thresholds

Set thresholds in a bed of mastic and secure the thresholds. Protect aluminum members in contact with masonry, steel, concrete, or dissimilar materials using nylon pads or a bituminous coating. Shim and brace the aluminum system before anchoring the system to the structure. Verify that weep holes are open, and the metal joints are sealed in accordance with the manufacturer's installation instructions. Seal metal-to-metal joints using a sealant recommended by the system manufacturer.

3.3 PROTECTION FROM DISSIMILAR MATERIALS

3.3.1 Dissimilar Metals

Where aluminum surfaces come in contact with metals other than stainless steel, zinc, or small areas of white bronze, protect from direct contact to dissimilar metals.

3.3.1.1 Protection

Provide one of the following systems to protect surfaces in contact with dissimilar metals:

a. Paint the dissimilar metal with one coat of heavy-bodied bituminous paint.

b. Apply elastomeric sealant between aluminum and dissimilar metals in accordance with Section 07 92 00 JOINT SEALANTS.

c. Paint dissimilar metals with one coat of primer and one coat of aluminum paint.

d. Use a non-absorptive tape or gasket in permanently dry locations.

3.3.2 Drainage from Dissimilar Metals

In locations where drainage from dissimilar metals has direct contact with aluminum, provide protective paint to prevent aluminum discoloration.

3.3.3 Masonry and Concrete

Provide aluminum surfaces in contact with mortar, concrete, or other masonry materials with one coat of heavy-bodied bituminous paint.

3.4 SEALING AROUND ASSEMBLIES

Seal all penetrations of the air barrier by sealing around door openings as necessary to achieve compliance with air leakage requirements indicated in the air barrier sections of the specifications, the requirements of Section 07 27 10.00 10 BUILDING AIR BARRIER SYSTEM, and Section 01 91 19

BUILDING ENCLOSURE COMMISSIONING. Flash all doors with corrosion resistant flashing to prevent water intrusion.

3.5 CLEANING

Upon completion of installation, clean door and frame surfaces in accordance with door manufacturer's written recommended procedure. Do not use abrasive, caustic, or acid cleaning agents.

3.6 PROTECTION

Protect doors and frames from damage and from contamination by other materials such as cement mortar. Prior to completion and acceptance of the work, restore damaged doors and frames to original condition, or replace with new ones.

3.7 HARDWARE SETS

3.7.1 A1, BATTALION HEADQUARTERS ALUMINUM DOOR HARDWARE SCHEDULE

Secure Exterior Openings

Door No. 101B, 101C
HWS-A1.1 B2BAC Ext Entrance Pair

	6 each Offset Pivot Hinge	Slate Gray
Section 08 71 00	2 each FMC Closer, C02211 jamb mounted slide track arm, spring stop, pull side mount	630
GFGI	2 each Shear Lock, with integral DPS monitoring	628
GFGI	1 each Exit Sensor, PIR	White
GFGI	1 each Mushroom Push Button, Red, EXIT momentary release of shear locks, single gang wall mounted	628
	2 each Bent Bar Push	Slate Gray
	2 each Bent Bar Pull	Slate Gray
Section 08 71 00	1 each 76" Drip Ledge	MIL
	1 each 6070 Weatherstrip	Slate Gray
	2 each 36" Bottom Sweep	Slate Gray
	1 each 72" Threshold	MIL
Section 08 71 00	2 each Floor Stop, L02131	626
GFGI	2 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 174

Note: Furnish filler bars or a special aluminum frame head with stop dimensions to accommodate mortised shear locks

Note: Integrate the hardware set with fire alarm equipment. Sheer locks fail safe upon fire alarm notification

Secure Interior Openings

Door No. 113A, 158A
HWS-A1.2 AC Suite Pair

	6 each	Offset Pivot Hinge	Slate Gray
Section 08 71 00	2 each	FMC Closer, C02211 jamb mounted slide track arm, spring stop, pull side mount	630
GFGI	2 each	Shear Lock, integral DPS monitoring	628
GFGI	1 each	Exit Sensor, PIR	White
GFGI	1 each	Mushroom Push Button, Red, EXIT momentary release of shear locks, single gang wall mounted	628
	2 each	Bent Bar Push	Slate Gray
	2 each	Bent Bar Pull	Slate Gray
	1 each	6070 Weatherstrip	Slate Gray
Section 08 71 00	2 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed device

Note: Access control equipment is located in Comm 174

Note: Integrate the hardware set with fire alarm equipment. Sheer locks fail safe upon fire alarm notification

Note: Furnish filler bars or a special aluminum frame head with stop dimensions to accommodate mortised shear locks

3.7.2 A2-1, CO BUILDING ALUMINUM DOOR HARDWARE SCHEDULE

Heavy Duty Exterior Openings

Door No. 100A
HWS-A2-1.1 Exterior Entrance Pair

	6 each	Offset Pivot Hinge	Slate Gray
Section 08 71 00	2 each	FMC Closer, C02231 with spring stop, stop mounted slide track arm push side mount	630
Active Leaf RHR			
	1 each	Concealed Retail Deadlock entry by keyed trim, public use while retracted	628
	1 each	Thumbturn	628
Section 08 71 00	1 each	Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Inactive Leaf LHR			
	1 each	Auto Release, Two Point Flush Bolt	626
Section 08 71 00	1 each	Dust Proof Strike, L04021	626
	2 each	Bent Bar Push	Slate Gray
	2 each	Bent Bar Pull	Slate Gray
Section 08 71 00	1 each	76" Drip Ledge	MIL
	1 each	6070 Weatherstrip	Slate Gray

	1 each	Brush Astragal	Black
	2 each	36" Bottom Sweep	Slate Gray
	1 each	72" Threshold	MIL
Section 08 71 00	2 each	Floor Stop, L02131	626

Secure Interior Openings

Door No. 100B, 102A
HWS-A2-1.2 B2BAC Foyer, Lobby Pair

	6 each	Offset Pivot Hinge	Slate Gray
Section 08 71 00	2 each	FMC Closer, C02211 jamb mounted slide track arm, spring stop, pull side mount	630
GFGI	2 each	Shear Lock, with integral DPS monitoring	628
GFGI	1 each	Exit Sensor, PIR	White
GFGI	1 each	Mushroom Push Button, Red, EXIT momentary release of shear locks, single gang wall mounted	628
	2 each	Bent Bar Push	Slate Gray
	2 each	Bent Bar Pull	Slate Gray
	1 each	6070 Weatherstrip	Slate Gray
Section 08 71 00	2 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	2 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Note: Furnish filler bars or a special aluminum frame head with stop dimensions to accommodate mortised shear locks

Note: Integrate the hardware set with fire alarm equipment. Sheer locks fail secure upon fire alarm notification

3.7.3 A2-2, CO BUILDING ALUMINUM DOOR HARDWARE SCHEDULE

Heavy Duty Exterior Openings

Door No. 100A
HWS-A2-2.1 Exterior Entrance Pair

	6 each	Offset Pivot Hinge	Slate Gray
Section 08 71 00	2 each	FMC Closer, C02231 with spring stop, stop mounted slide track arm push side mount	630
Active Leaf RHR			
	1 each	Concealed Retail Deadlock entry by keyed trim, public use while retracted	628
	1 each	Thumbturn 628	
Section 08 71 00	1 each	Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Inactive Leaf LHR			

	1 each Auto Release, Two Point Flush Bolt	626
Section 08 71 00	1 each Dust Proof Strike, L04021	626
	2 each Bent Bar Push	Slate Gray
	2 each Bent Bar Pull	Slate Gray
Section 08 71 00	1 each 76" Drip Ledge	MIL
	1 each 6070 Weatherstrip	Slate Gray
	1 each Brush Astragal	Black
	2 each 36" Bottom Sweep	Slate Gray
	1 each 72" Threshold	MIL
Section 08 71 30	2 each Floor Stop, L02131	626

Secure Interior Openings

Door No. 100B, 102A
HWS-A2-2.2 B2BAC Foyer, Lobby Pair

	6 each Offset Pivot Hinge	Slate Gray
Section 08 71 00	2 each FMC Closer, C02211 jamb mounted slide track arm, spring stop, pull side mount	630
GFGI	2 each Shear Lock, with integral DPS monitoring	628
GFGI	1 each Exit Sensor, PIR	White
GFGI	1 each Mushroom Push Button, Red, EXIT momentary release of shear locks, single gang wall mounted	628
	2 each Bent Bar Push	Slate Gray
	2 each Bent Bar Pull	Slate Gray
	1 each 6070 Weatherstrip	Slate Gray
Section 08 71 00	2 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	2 each DPDT Balanced Magnetic Switch	MIL
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Note: Furnish filler bars or a special aluminum frame head with stop dimensions to accommodate mortised shear locks

Note: Integrate the hardware set with fire alarm equipment. Sheer locks fail secure upon fire alarm notification

-- End of Section --

SECTION 08 14 00

WOOD DOORS
08/16, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN FOREST FOUNDATION (AFF)

ATFS STANDARDS	(2015) American Tree Farm System Standards of Sustainability 2015-2020

ASTM INTERNATIONAL (ASTM)

ASTM E90	(2023) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements
ASTM E2226	(2015; R 2019b) Standard Practice for Application of Hose Stream

CALIFORNIA AIR RESOURCES BOARD (CARB)

CARB 93120	(2007) Airborne Toxic Control Measure (ATCM) to Reduce Formaldehyde Emissions from Composite Wood Products

CSA GROUP (CSA)

CSA Z809-08	(R2013) Sustainable Forest Management

FOREST STEWARDSHIP COUNCIL (FSC)

FSC STD 01 001	(2015) Principles and Criteria for Forest Stewardship

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80	(2025) Standard for Fire Doors and Other Opening Protectives
NFPA 105	(2022) Standard for Smoke Door Assemblies and Other Opening Protectives
NFPA 252	(2022) Standard Methods of Fire Tests of Door Assemblies

PROGRAMME FOR ENDORSEMENT OF FOREST CERTIFICATION (PEFC)

PEFC ST 2002:2013	(2015) PEFC International Standard Chain of Custody of Forest Based Products

Requirements

SUSTAINABLE FOREST INITIATIVE (SFI)

SFI 2015-2019	(2015) Standards, Rules for Label Use, Procedures and Guidance

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 770	Formaldehyde Standards for Composite Wood Products

UL SOLUTIONS (UL)

UL 10B	(2008; Reprint Oct 2024) Fire Tests of Door Assemblies

WINDOW AND DOOR MANUFACTURERS ASSOCIATION (WDMA)

ANSI/WDMA I.S.1A	(2013) Interior Architectural Wood Flush Doors
ANSI/WDMA I.S.6A	(2013) Interior Architectural Stile and Rail Doors

WOODWORK INSTITUTE (WI)

NAAWS 3.1	(2017; 2018 Errata Edition) North American Architectural Woodwork Standards

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Doors; G

Submit drawings or catalog data showing each type of door unit . Indicate within drawings and data the door types and construction, sizes, thickness, and glazing.

SD-03 Product Data

Doors; G

Recycled Content for Door Cores; S

Accessories

Water-resistant Sealer

Sample Warranty

Sound Transmission Class Rating; G

Fire Resistance Rating; G

SD-04 Samples

Door Finish Color; G

Submit a minimum of three color selection samples , minimum 3 by 5 inches in size representing wood stain.

SD-06 Test Reports

Cycle-Slam

Hinge Loading Resistance

Submit cycle-slam test report for doors tested in accordance with ANSI/WDMA I.S.1A, and hinge loading resistance test report for doors tested in accordance with ANSI/WDMA I.S.6A.

SD-07 Certificates

Certificates of Grade

Certified Sustainably Harvested Flush Wood Doors; S

Indoor Air Quality for Particleboard and Agrifiber Door Cores: S

SD-11 Closeout Submittals

Warranty

1.3 CERTIFICATIONS

1.3.1 Certified Wood Grades

Provide certificates of grade from the grading agency on acoustical doors and fire doors.

1.3.2 Certified Sustainably Harvested Wood

Provide wood certified as sustainably harvested by FSC STD 01 001, ATFS STANDARDS, CSA Z809-08, SFI 2015-2019, or other third party program certified by PEFC ST 2002:2013. Provide a letter of Certification of Sustainably Harvested Wood signed by the wood supplier. Identify certifying organization and their third party program name and indicate compliance with chain-of-custody program requirements. Submit sustainable wood certification data; identify each certified product on a line item basis. Submit copies of invoices bearing certification numbers.

1.3.3 Indoor Air Quality Certification

1.3.3.1 Composite Wood, Wood Structural Panel and Agrifiber Products

For purposes of this specification, composite wood and agrifiber products include particleboard, medium density fiberboard (MDF), wheatboard, strawboard, panel substrates, and door cores. Provide products certified to meet requirements of both 40 CFR 770 and CARB 93120. Provide current product certification documentation from certification body.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver doors to the site in an undamaged condition and protect against damage and dampness. Stack doors flat under cover. Support on blocking, a minimum of 4 inch thick, located at each end and at the midpoint of the door. Store doors in a well-ventilated building so that they will not be exposed to excessive moisture, heat, dryness, direct sunlight, or extreme changes of temperature and humidity. Do not store in a building under construction until concrete, masonry work, and plaster are dry. Replace defective or damaged doors with new ones.

1.5 WARRANTY

Warrant doors free of defects as set forth in the door manufacturer's standard door warranty.

PART 2 PRODUCTS

2.1 DOORS

Provide doors of the types, sizes, and designs indicated free of urea-formaldehyde resins.

2.1.1 Flush Doors

Conform to ANSI/WDMA I.S.1A for flush doors. Hardwood stile edge bands of doors receives a natural finish, compatible with face veneer. Provide mill option for stile edge of doors scheduled to be painted. No visible finger joints will be accepted in stile edge bands. Provide certified sustainably harvested flush wood doors.

2.1.1.1 Interior Flush Doors

Provide particleboard or agrifiber core, Type II flush doors conforming to ANSI/WDMA I.S.1A with faces of good grade white oak. Hardwood veneers must be quarter sliced, slip matched. Door cores must have a minimum recycled content of 45 percent. Provide data identifying percentage of recycled content for door cores. Products must contain no added urea-formaldehyde resins. Provide certification of indoor air quality for particleboard and agrifiber door cores.

2.1.2 Acoustical Doors

ANSI/WDMA I.S.1A, solid core, constructed to provide various Sound Transmission Class ratings when tested in accordance with ASTM E90. Reference 08 34 73 SOUND CONTROL DOOR ASSEMBLIES.

2.1.3 Composite-Type Fire Doors

Provide doors specified or indicated to have a fire resistance rating conforming to the requirements of UL 10B, ASTM E2226, or NFPA 252 for the class of door indicated. Affix a permanent metal label with raised or incised markings indicating testing agency's name and approved hourly fire rating to hinge edge of each door.

Incorporate factory installed edge seals into door constructions certified in accordance with Category A, positive pressure fire door testing. Assemblies are Category G gasketing. Provide gasketing complying with NFPA 80 for fire rated openings encountered. Gasketing complies with ANSI

156.22, UL 1784 and UL 10C. Door pairs receive steel edges and astragals or concealed intumescent seals.

2.2 ACCESSORIES

2.2.1 Door Light Openings

Provide glazed openings with the manufacturer's standard wood moldings. Provide moldings for doors to receive natural finish of the same wood species and color as the wood face veneers. Use lip type moldings for flush doors.

2.2.2 Additional Hardware Reinforcement

Provide the minimum lock blocks to secure the specified hardware. The measurement of top, bottom, and intermediate rail blocks are a minimum 125 mm 5 inch by full core width. Comply with the manufacturer's labeling requirements for reinforcement blocking, but not mineral material similar to the core.

2.3 FABRICATION

2.3.1 Quality and Construction

Identify the standard on which the construction of the door was based .

2.3.2 Adhesives and Bonds

ANSI/WDMA I.S.1A. Use Type II bond for interior doors. Provide a nonstaining adhesive on doors with a natural finish.

2.3.3 Prefitting

Provide factory prefitted doors for the specified hardware, door frame and door-swing indicated. Machine and size doors at the factory by the door manufacturer in accordance with the standards under which the doors are produced and manufactured. The work includes sizing, beveling edges, mortising, and drilling for hardware and providing necessary beaded openings for glass. Provide the door manufacturer with the necessary hardware samples, and frame and hardware schedules to coordinate the work.

2.3.4 Finishes

2.3.4.1 Field Painting

Factory seal doors. Door finish color WD-1.

2.3.4.2 Factory Finish

At the contractor's option, provide doors finished at the factory by the door manufacturer as follows: WDMA System TR-8 (UV cured acrylated polyester/urethane) or TR-2 (catalyzed lacquer) or TR-4 (conversion varnish) factory finish systems that utilize water-based stains and finishes with ultraviolet UV protection. The coating is NAAWS 3.1 premium, medium rubbed sheen, closed grain effect. Use stain when required to produce the finish specified for color. Seal edges, cutouts, trim, and wood accessories, and apply two coats of finish compatible with the door face finish. Touch-up finishes that are scratched or marred, or

where exposed fastener holes are filled, in accordance with the door manufacturer's instructions. Match color and sheen of factory finish using materials compatible for field application.

2.3.5 Water-Resistant Sealer

Provide manufacturer's standard water-resistant sealer compatible with the specified finish.

2.4 SOURCE QUALITY CONTROL

Meet or exceed the following minimum performance criteria of stiles of "B" and "C" label fire doors utilizing standard mortise leaf hinges:

a. Cycle-slam: Heavy Duty Doors: 500,000 cycles with no loose hinge screws or other visible signs of failure when tested in accordance with the requirements of ANSI/WDMA I.S.1A.

b. Hinge loading resistance: Averages of ten test samples not less than Heavy Duty doors: 475 pounds force when tested for direct screw withdrawal in accordance with ANSI/WDMA I.S.6A using a No. 12, 1-1/4 inch long, steel, fully threaded wood screw. Drill 5/32 inch pilot hole, use 1-1/2 inch opening around screw for bearing surface, and engage screw full, except for last 1/8 inch. Do not use a steel plate to reinforce screw area.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

Before installation, seal top and bottom edges of doors with the approved water-resistant sealer. Seal cuts made on the job immediately after cutting using approved water-resistant sealer. Fit, trim, and hang doors with a 1/16 inch minimum, 1/8 inch maximum clearance at sides and top, and a 3/16 inch minimum, 1/4 inch maximum clearance over thresholds. Provide 3/8 inch minimum, 7/16 inch maximum clearance at bottom where no threshold occurs. Bevel edges of doors at the rate of 1/8 inch in 2 inch. Door warp must not exceed 1/4 inch when measured in accordance with ANSI/WDMA I.S.1A.

3.1.1 Fire and Smoke Doors

Install fire doors in accordance with NFPA 80. Install smoke doors in accordance with NFPA 105. Do not paint over labels.

-- End of Section --

SECTION 08 31 00

ACCESS DOORS AND PANELS
05/17, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding Code - Steel

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A666	(2015) Standard Specification for Annealed or Cold-Worked Austenitic Stainless Steel Sheet, Strip, Plate and Flat Bar
ASTM A1008/A1008M	(2021a) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM E90	(2023) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements
ASTM E119	(2024) Standard Test Methods for Fire Tests of Building Construction and Materials
ASTM E413	(2022) Classification for Rating Sound Insulation
ASTM E1332	(2016) Standard Classification for Rating Outdoor-Indoor Sound Attenuation

MASTER PAINTERS INSTITUTE (MPI)

MPI 79	(2016) Primer, Alkyd, Anti-Corrosive for Metal

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 252	(2022) Standard Methods of Fire Tests of Door Assemblies
NFPA 288	(2017) Standard Methods of Fire Tests of Horizontal Fire Door Assemblies Installed in Horizontal Fire Resistance-Rated Assemblies

UL SOLUTIONS (UL)

UL 10B	(2008; Reprint Oct 2024) Fire Tests of Door Assemblies
UL 263	(2011; Reprint Aug 2021) UL Standard for Safety Fire Tests of Building Construction and Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Access Doors And Panels; G

SD-03 Product Data

Access Doors And Panels; G

Hardware Including Locks and Keys; G

Accessories; G

Recycled Content; S

SD-04 Samples

Finishes; G

SD-06 Test Reports

Fire-rating(s) of Assemblies; G

Acoustical Ratings of Assemblies; G

1.3 MISCELLANEOUS REQUIREMENTS

For access doors and panels provide the following:

1.3.1 Shop Drawings

For field assembled access doors and panels, provide plans, elevations, sections, and details for each type of access door and panel assembly. Indicate frame, surface and edge construction, materials, and

accessories. Indicate types of finished surfaces and details for panel edge conditions. Provide a door schedule with a unique number for each access door and panel, specific location in the project, location of hinges and hardware for each door. Indicate acoustical ratings of assemblies as sound transmission class (STC) ratings, fire-rating(s) of assemblies and locations.

1.3.2 Product Data

For shop assembled access doors and panels, provide literature indicating sizes, types, frame and edge construction, finishes, hardware, accessories such as gaskets, seals and weatherstripping, and location of each door and panel in the project. Indicate acoustical ratings of assemblies and fire-ratings of assemblies. Provide details of adjoining work for each condition indicated.

1.3.3 Finish Samples

Submit two color charts from manufacturer's standard color and finish options for each type of frame and panel assembly finish indicated.

1.3.4 Test Reports

Provide test reports for acoustical assemblies when tested in accordance with ASTM E90 and classified in accordance with ASTM E413 and ASTM E1332. Provide test reports for fire-rated assemblies when tested in accordance with NFPA 252 or UL 10B for fire-rated access door assemblies installed vertically and NFPA 288 for fire-rated access door assemblies installed horizontally.

1.4 PERFORMANCE REQUIREMENTS

1.4.1 Structural Requirements

Provide floor access assemblies to support live loads indicated for floors. Deflection must not exceed 1/180 of span.

1.4.2 Acoustical Requirements

Provide access panels with a minimum sound transmission class (STC) that maintains the acoustical performance of substrates encountered. Provide gasketing in accordance with manufacturer's written recommendations.

1.4.3 Fire-Rating Requirements

Provide access panels with a minimum fire-rating that maintains the fire rating of substrates encountered.

1.5 DELIVERY, STORAGE, AND PROTECTION

Protect from corrosion, deformation, and other types of damage. Store items in an enclosed area free from contact with soil and weather. Remove and replace damaged items with new items.

PART 2 PRODUCTS

2.1 RECYCLED CONTENT

Provide products with recycled content. Provide data for each product

with recycled content, identifying percentage of recycled content.

2.2 MATERIALS

2.2.1 Steel Plates, Shapes, and Bars

Provide in accordance with ASTM A36/A36M.

2.2.2 Sheet Steel

Provide cold rolled steel sheet substrate in accordance with ASTM A1008/A1008M, Commercial Steel (CS), exposed.

2.2.3 Stainless Steel

Provide in accordance with ASTM A666, type 302 or 304. Provide stainless steel finishes in damp areas.

2.2.4 Metallic Coated Steel Sheet

Provide in accordance with ASTM A653/A653M, Commercial Steel (CS), Type B; with minimum G60 (Z180) or A60 (ZF180) metallic coating. Furnish galvanized steel finishes in dry areas.

2.2.5 Hardware

Provide automatic closing devices. Provide latch releases operable from insides of doors. Provide anchors in accordance with applicable fire test parameters.

2.2.6 Hinges

Provide concealed spring hinges, 175 degrees of opening, with non-removable hinge pins. Provide hinges of same steel as door and frame or in accordance with manufacturer's written recommendations. If providing non-continuous hinges, provide in numbers required to maintain alignment of door panel with frame. Provide coatings as necessary to permanently protect dissimilar metals from contact with one another; see Part 3 herein for more information.

2.2.7 Locks

Unless otherwise indicated, provide flush screwdriver operated cam lock. Provide stainless steel bushings to protect holes in surface finishes for screwdriver to access lock.

2.2.8 Accessories

Provide anchors in size, number and location on four sides to secure access door to substrate. Provide anchors in types as recommended by manufacturer's written installation instructions for each substrate indicated. Provide shims, bushings, clips, gaskets, and other devices as necessary for a complete installation.

2.3 FABRICATION

2.3.1 Thickness, Size, Edges

Fabricate frames for access doors of steel not lighter than 16 gage with

welded joints and anchorage for securing to adjacent construction. Provide doors a minimum of 24 by 24 inches and of not lighter than 16 gage steel, with stiffened edges and welded attachments. Provide with eased (lightly rounded) edges, without burrs, snags or sharpness and exposed welds ground smooth.

2.3.2 Welding

Provide in accordance with AWS D1.1/D1.1M.

2.4 ACCESS ASSEMBLY TYPES

Unless indicated otherwise, provide flush-face steel access doors and panels with steel frames and flanges.

2.4.1 Fire-rated Doors

2.4.1.1 Door Construction

Provide ceiling access door construction in accordance with ASTM E119 or UL 263. Provide wall access doors in accordance with NFPA 252 or UL 10B.

2.4.1.2 Labels

Provide class B opening according to UL 10B or test by another nationally recognized laboratory, approved by the Contracting Officer. Provide fire-rating as indicated herein, with a maximum temperature rise of 216 degrees F.

2.4.1.3 Door Panel and Frame

Steel sheet, with mineral fiber insulation core, insulated sandwich type construction.

2.4.2 Acoustical Doors

Manufacturer's standard assembly rated in accordance with STC requirements indicated herein. Acoustical insulating materials must have a flame spread rating of no more than 25.

2.5 FINISHES

Provide galvanized steel frames and panel surfaces with a powder coated finish. Provide manufacturer's standard two coat finish system consisting of one coat primer and one thermoset topcoat. Provide dry film thickness in 2 mils minimum. Provide stainless steel frames and panels with a No. 4 Brushed finish. Provide exposed fastenings that approximately match the color and finish of the each material to which fastenings are applied.

PART 3 EXECUTION

3.1 PREPARATION

Field verify all measurements prior to fabrication. Verify access door locations and sizes provide required maintenance access to installed building services components. Protect existing construction and completed work from damage during installation.

3.2 GENERAL INSTALLATION REQUIREMENTS

Install items at locations indicated, in accordance with manufacturer's written instructions. Include materials and parts as necessary for a complete installation of each item. Conceal fastenings where practicable. Poor matching of holes to fasteners is cause for rejection of the work.

3.3 ACCESS LOCATIONS

Install removable access panels directly below each valve, flow indicator, damper, air splitter or other utility requiring access that is located above ceilings, other than at acoustical panel ceilings, and that would otherwise not be accessible. Install access doors and panels permitting access to service valves, traps, dampers, cleanouts, and other mechanical, electrical and conveyor control items concealed in walls and partitions.

3.4 ACCESS LOCATIONS IN WET AREAS

When possible, avoid locating access panels in wet areas. When such locations cannot be avoided, provide moisture resistant assemblies as indicated in Part I herein.

3.5 DISSIMILAR MATERIALS

Where dissimilar metals are in contact, protect surfaces with a coating in accordance with MPI 79 to prevent galvanic or corrosive action.

3.6 ADJUSTMENT

Adjust hardware so that door panel opens freely. Adjust door when closed center door panel in frame.

3.7 ENVIRONMENTAL CONDITIONS

Do not paint surfaces when damp or exposed to weather, when surface temperature is below 45 degrees F or over 95 degrees F, unless approved by the Contracting Officer.

-- End of Section --

SECTION 08 33 23

STEEL OVERHEAD COILING DOORS
08/20, CHG 1: 02/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7-16	(2017; Errata 2018; Supp 1 2018) Minimum Design Loads and Associated Criteria for Buildings and Other Structures

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B29.400	(2001; (R 2008) (R 2013) (R 2018)) Combination, "H" Type Mill Chains, and Sprockets

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A47/A47M	(1999; R 2022; E 2022) Standard Specification for Ferritic Malleable Iron Castings
ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2023) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A780/A780M	(2020) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings

ASTM A924/A924M	(2022a) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM E330/E330M	(2014; R 2021) Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference
ASTM F568M	(2007) Standard Specification for Carbon and Alloy Steel Externally Threaded Metric Fasteners

DOOR AND ACCESS SYSTEM MANUFACTURERS ASSOCIATION (DASMA)

ANSI/DASMA 108	(2017) Standard Method for Testing Sectional Garage Doors, Rolling Doors and Flexible Doors: Determination of Structural Performance Under Uniform Static Air Pressure Difference

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA ICS 1	(2022) Standard for Industrial Control and Systems: General Requirements
NEMA ICS 2	(2000; R 2020) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA MG 1	(2021) Motors and Generators
NEMA ST 1	(1988; R 1994; R 1997) Specialty Transformers (Except General Purpose Type)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

UL SOLUTIONS (UL)

UL 325	(2017; Reprint Sep 2025) UL Standard for Safety Door, Drapery, Gate, Louver, and Window Operators and Systems

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Overhead Coiling Doors; G

Counterbalancing Mechanism; G

Electric Door Operators; G

Guides; G

Mounting Brackets; G

Hood; G

Installation Drawings; G

SD-03 Product Data

Overhead Coiling Doors; G

Hardware; G

Counterbalancing Mechanism; G

Electric Door Operators; G

Recycled content for steel curtain slats; S

SD-05 Design Data

Overhead Coiling Doors

Hardware; G

Counterbalancing Mechanism; G

Electric Door Operators; G

Wind Loading; G

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals, Data Package 2; G

SD-11 Closeout Submittals

Warranty; G

1.3 QUALITY CONTROL

1.3.1 Warranty

Furnish a written guarantee that the helical spring and counterbalance mechanism are free from defects in material and workmanship for not less than 2 years after completion and acceptance of the project.

Warrant that upon notification by the Government, any defects in material, workmanship, and door operation are immediately correct within the same time period covered by the guarantee, at no cost to the Government.

1.3.2 Operation And Maintenance Submittals

Submit 6 copies of the operation and maintenance manuals 30 calendar days prior to testing the Overhead Coiling Door Assemblies. Update and resubmit data for final approval no later than 30 calendar days prior to cContract completion.

Submit Operation and Maintenance Manuals for Overhead Coiling Door Assemblies, including the following items:

Electric Door OperatorsHood

Counterbalancing Mechanism

Painting

Provide operation and maintenance manuals which are consistent with manufacturer's standard brochures, schematics, printed instructions, operating procedures, and safety precautions.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver doors to the jobsite wrapped in a protective covering with the brands and names clearly marked thereon. Store doors in an adequately ventilated dry location that is free from dirt and dust, water, or other contaminants. Store in a manner that permits easy access for inspection and handling. Handle doors carefully to prevent damage. Remove damaged items that cannot be restored to like-new condition and provide new items.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide overhead coiling doors with interlocking slats, complete with anchoring and door hardware, guides, hood, and operating mechanisms, and designed for use on openings as indicated. Doors must be spring counterbalanced, rolling type, and designed for use on interior openings, as indicated. Doors must be operated by hand chain with gear or sprocket reduction. Doors to be surface-mounted type with guides at jambs set back a sufficient distance to provide a clear opening when door is in open position. Mount doors as indicated

2.1.1 Design Requirements

2.1.1.1 Door Detail Shop Drawings

Provide installation drawings for door assemblies which show: elevations of each door type, shape and thickness of materials, finishes, details of joints and connections, details of guides and fittings, rough opening dimensions, location and description of hardware, anchorage locations, and counterbalancing mechanism and door operator details. Include a schedule showing the location of each door with the drawings.

Procure cut sheets for GFGI hardware from the Government. Coordinate GFGI hardware items with furnished hardware items indicated in applicable

hardware sets. Use templates to prepare doors and frames for GFGI hardware selections.

2.1.2 Performance Requirements

2.1.2.1 Wind Loading

Design and fabricate door assembly to withstand the wind loading pressure of at least 54 pounds per square foot in accordace with ANSI/DASMA 108. Provide test data showing compliance with ASTM E330/E330M. Sound engineering principles may be used to interpolate or extrapolate test results to door sizes not specifically tested. Ensure that the complete assembly meets or exceeds the requirements of ASCE 7-16.

Marine Corps Base Camp Lejeune must resist a 144 mile per hour, ultimate design wind speed, 54 PSF, Risk Category II, Surface Roughness Category C, Exposure Category B lateral load. Comply with UFC 3-301-01 and ASCE 7 as applicable for building system designs and components.

Submit a DELEGATED DESIGN demonstrating compliance

Furnish overhead curtain assemblies that resist lateral loads. Assembly design responsibility is delegated to the Contractor and incorporates specific properties and structural capabilities of selected products and manufacturers.

Supplement delegated design shop drawings with overhead curtain assembly structural computations. Tie general manufacturer data of appurtenant members utilized to project specific conditions. Specify fastening patterns and connections.

2.1.2.2 Operational Cycle Life

Design all portions of the door, hardware and operating mechanism that are subject to movement, wear, or stress fatigue to operate through a minimum number of 10 cycles per day. One complete cycle of door operation is defined as when the door is in the closed position, moves to the fully open position, and returns to the closed position.

2.2 COMPONENTS

2.2.1 Overhead Coiling Doors

2.2.1.1 Curtain Materials and Construction

Provide curtain slats fabricated from Grade A steel sheets conforming to ASTM A653/A653M, with the additional requirement of a minimum yield point of 33,000 psi. Provide 22 gauge sheets, Grade 40 steel with galvanized steel zinc coating in conformance with ASTM A653/A653M and ASTM A924/A924M. Fill slat cavities with CFC free, foamed in place polyurethane insulation having an R value of 7.7 and an STC 21. Air leakage is less than 1 CFM per square foot. Provide steel curtain slats containing a minimum of 20 percent recycled content. Submit data identifying percentage of recycled content for steel curtain slats.

Fabricate doors from interlocking cold-rolled slats, with section profiles as specified, designed to withstand the specified wind loading. Ensure the provided slats are continuous without splices for the width of the

door.

2.2.1.2 Curtain Bottom Bar

Install curtain bottom bars as pairs of angles or using extrusions from the manufacturer's standard steel extrusions not less than 2.0 by 2.0 inches by 0.188 inch. Ensure steel extrusions conform to ASTM A36/A36M. Galvanize angles and fasteners in accordance with ASTM A653/A653M and ASTM A924/A924M. Coat welds and abrasions with paint conforming to ASTM A780/A780M.

Provide two minimum 2 inch by 2 inch by 1/8 inch structural steel angles.

2.2.1.3 Endlocks (and Windlocks)

Provide endlocks of Grade B cast steel conforming to ASTM A47/A47M, galvanized in accordance with ASTM A153/A153M. Secure locks at every other curtain slat. In addition to endlocks, exterior doors which have a design wind load of more than 20 pounds per square foot, must have windlocks of manufacturer's standard design. Windlocks must prevent curtain from leaving guide because of deflection from wind pressure or other forces.

2.2.1.4 Weather Stripping

Provide a hood baffle inside the hood that is a minimum 1/16 inch thick sheet of vinyl, neoprene rubber or equivalent. Provide guide weather stripping that is a minimum 1/16 inch thick sheet of vinyl, neoprene rubber, or equivalent.

Provide bottom bar weather-stripping that is a minimum 1/16 inch thick sheet of vinyl, neoprene rubber, or equivalent.

2.2.1.5 Locking Devices

Provide a locking device assembly which includes cylinder lock, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.

2.2.2 Hardware

Ensure that all hardware conforms to ASTM A153/A153M, ASTM A307, and ASTM F568M.

2.2.2.1 Guides

Fabricate curtain jamb guides from the manufacturer's standard angles or channels of same material and finish as curtain slats unless otherwise indicated. Ensure curtain operates smoothly. Slot bolt holes for track adjustment. Securely attach guides to adjoining construction with not less than 3/8 inch diameter bolts, spaced near each end and not over 30 inches apart.

Ensure guides are roll-formed steel channel bolted to angle or structural grade, three angle assembly of steel to form a slot of sufficient depth to retain curtains in guides to achieve 20 psf windload standard. Guides may be provided with integral windlock bars and removable bottom bar stops.

2.2.2.2 Hood

Provide a hood with a minimum 24-gauge galvanized sheet metal, flanged at top for attachment to header and flanged at bottom to provide longitudinal stiffness. The hood encloses the curtain coil and counterbalance mechanism.

Hoods for openings more than 12 feet in width must have intermediate support brackets to prevent excessive sag. Provide a weather baffle at the lintel or inside the hood of each exterior door.

2.2.3 Counterbalancing Mechanism

Counterbalance doors by means of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted, around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed or self-lubricating bearings for rotating members.

2.2.3.1 Brackets

Provide the manufacturer's standard mounting brackets with one located at each end of the counterbalance barrel conforming to ASTM A36/A36M. Provide brackets of hot-rolled steel.

2.2.3.2 Counterbalance Barrels

Curtain must roll up on a barrel supported at head of opening on brackets and be balanced by a torsion spring system in the barrel. Fabricate spring barrel of manufacturer's standard hot-formed, structural-quality, welded or seamless carbon-steel pipe, conforming to ASTM A53/A53M or equivalent. Ensure the barrel is of sufficient diameter and wall thickness to support rolled-up curtain without distortion of slats. Limit barrel deflection to not more than 0.03 inch per foot of span under full load.

a. Barrel

Provide steel pipe capable of supporting curtain load with maximum deflection of 0.03 inches per foot of width.

b. Spring Balance

Provide an oil-tempered, heat-treated steel helical torsion spring assembly designed for proper balance of door. Ensure that effort to operate manually operated units does not exceed 25 lbs. At least 80 percent of the door weight must be counterbalanced at any position. Provide wheel for applying and adjusting spring torque.

2.2.4 Electric Door Operators

Provide electrical wiring and door operating controls conforming to the applicable requirements of NFPA 70 and UL 325. The door manufacturer must furnish automatic control and safety devices, including extra flexible type SO cable and spring-loaded automatic takeup reel or equivalent device, as required for proper operation of the doors. Conduit, wiring, and mounting of controls are specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

Electric door-operator assemblies need to be the sizes and capacities recommended and provided by the door manufacturer for specified doors. Furnish complete assemblies with electric motors and factory-prewired motor controls, starter, gear reduction units, solenoid-operated brakes, clutch, remote-control stations, manual or automatic control devices, and accessories as required for proper operation of the doors.

Design the operators so that motors may be removed without disturbing the limit-switch adjustment and affecting the emergency auxiliary operators.

Provide a manual operator of crank-gear or chain-gear mechanisms with a release clutch to permit manual operation of doors in case of power failure. Arrange the emergency manual operator so that it may be put into and out of operation from floor level, and its use does not affect the adjustment of the limit switches. Provide an electrical or mechanical device that automatically disconnects the motor from the operating mechanism when the emergency manual operating mechanism is engaged.

2.2.4.1 Electric Motors

Provide motors which are the high-starting-torque, reversible, constant-duty electrical type with overload protection of sufficient torque and horsepower to move the door in either direction from any position. Ensure they produce a door-travel speed of not less than 8 nor more than 12 inches per second without exceeding the horsepower rating.

Provide motors which conform to NEMA MG 1 designation, temperature rating, service factor, enclosure type, and efficiency to the requirements specified. Motors must be suitable for operation on current of the characteristics indicated. Install motors in approved locations.

2.2.4.2 Motor Bearings

Select bearings with bronze-sleeve or heavy-duty ball or roller antifriction type with full provisions for the type of thrust imposed by the specific duty load.

Pre-lubricate and factory seal bearings in motors less than 1/2 horsepower.

Equip motors coupled to worm-gear reduction units with either ball or roller bearings.

Equip bearings in motors 1/2 horsepower or larger with lubrication service fittings. Fit lubrication fittings with color-coded plastic or metal dust caps.

In any motor, bearings that are lubricated at the factory for extended duty periods do not need to be lubricated for a given number of operating hours. Display this information on an appropriate tag or label on the motor with instructions for lubrication cycle maintenance.

2.2.4.3 Motor Starters, Controls, and Enclosures

Provide each door motor with: a factory-wired, unfused, disconnect switch; a reversing, across-the-line magnetic starter with thermal overload protection; 24-volt operating coils with a control transformer limit

switch; and a safety interlock assembled in a NEMA ICS 6 type enclosure as specified herein. Ensure control equipment conforms to NEMA ICS 1 and NEMA ICS 2.

Provide adjustable switches, electrically interlocked with the motor controls and set to stop the door automatically at the fully open and fully closed position.

2.2.4.4 Control Enclosures

Provide control enclosures that conform to NEMA ICS 6 for NEMA Type 4and general purpose NEMA Type 1 as applicable to selected mounting locations.

2.2.4.5 Transformer

Provide starters with 230/460 to 115 volt control transformers with one secondary fuse when required to reduce the voltage on control circuits to 24volts or less. Provide a transformer conforming to NEMA ST 1.

2.2.4.6 Sensing-Edge Device

Provide each door with a pneumatic or electric sensing device that meets UL 325, extends the full width of the door, and is located within a U-section neoprene or rubber astragal, mounted on the bottom rail of the bottom door section. Device needs to immediately stop and reverse the door upon contact with an obstruction in the door opening or upon failure of the device or any component of the control system and cause the door to return to its user-defined open position. Any momentary door-closing circuit must be automatically locked out and the door must be operable manually or with constant pressure controls until the failure or damage has been corrected. A sensing device is not a substitute for a limit switch.

Connect sensing device to the control circuit through a retracting cord and reel.

2.2.4.7 Remote-Control Stations

Remote control stations must be at least 5 feet above the floor line, and all switches must be located so that the operator will have complete visibility of the door at all times. Provide interior remote control stations that are full-guarded, momentary-contact three-button, heavy-duty, surface-mounted NEMA ICS 6 type enclosures as specified. Mark buttons "OPEN," "CLOSE," and "STOP." The "OPEN" and "STOP" buttons must be of the type requiring only momentary pressure to operate. The "CLOSE" button must be of the type either requiring constant pressure to maintain the closing motion of the door or momentary pressure when installed with a monitored entrapment detection device which, upon failure of the device or any component of the control system, cause the door to return to its full open position. When the door is in motion and the "STOP" button is pressed, ensure the door stops instantly and remains in the stopped position. From the stopped position, the door may then be operated in either direction by the "OPEN" or "CLOSE" buttons. When the door is in motion, and the "CLOSE" button of the constant pressure type is released, the door must stop and remain in the stop position or reverse to the user set up position; from the stop position, the door may then be operated in either direction by the "OPEN" or "CLOSE" buttons. Controls must be adjustable to automatically stop the doors at their fully open and closed positions. Open and closed positions must be readily adjustable.

Provide exterior control stations that are full-guarded, momentary-contact three-button standard-duty, surface-mounted, weatherproof type, NEMA ICS 6, Type 4 enclosures, key-operated, with the same operating functions as specified herein for interior remote-control stations.

2.2.4.8 Speed-Reduction Units

Provide speed-reduction units consisting of hardened-steel worm and bronze worm gear assemblies or planetary gear reducers running in oil or grease and inside a sealed casing, coupled to the motor through a flexible coupling. Drive shafts need to rotate on ball- or roller-bearing assemblies that are integral with the unit.

Provide minimum ratings of speed reduction units in accordance with AGMA provisions for class of service.

Ground worm gears to provide accurate thread form; machine teeth for all other types of gearing. Surface harden all gears.

Provide antifriction type bearings equipped with oil seals.

2.2.4.9 Chain Drives

Provide roller chains that are a power-transmission series steel roller type conforming to ASME B29.400, with a minimum safety factor of 10 times the design load.

Heat-treat or otherwise harden roller-chain side bars, rollers, pins, and bushings.

Provide high-carbon steel chain sprockets with machine-cut hardened teeth, finished bore and keyseat, and hollow-head setscrews.

2.2.4.10 Brakes

Provide 360-degree shoe brakes or shoe and drum brakes. Ensure the brakes are solenoid-operated and electrically interlocked to the control circuit to set automatically when power is interrupted.

2.2.4.11 Clutches

Ensure clutches are friction type or adjustable centrifugal type.

2.2.4.12 Weather/Smoke Seal Sensing Edge

Provide automatic stop control by an automatic sensing switch within neoprene astragal extending the full width of door bottom bar.

Provide an electric sensing edge device. Ensure the door immediately stops downward travel when contact occurs before door fully closes. Provide a self-monitoring sensing edge connection to the motor operator.

2.2.5 Surface Finishing

Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes. Noticeable variations in the same metal component are not acceptable.

Variations in appearance of adjoining components are acceptable if they are within the range of approved samples and are assembled or installed to minimize contrast.

2.2.5.1 Galvanized and Shop-Primed Finish

Surfaces specified must have a zinc coating, a phosphate treatment, and a shop prime coat of rust-inhibitive paint. The galvanized coating must conform to ASTM A653/A653M, coating designation Z275 (G90), for steel sheets, and ASTM A123/A123M for iron and steel products. The weight of coatings for products must be as designated in Table I of ASTM A123/A123M for the thickness of base metal to be coated. The prime coat must be a type especially developed for materials treated by phosphates and adapted to application by dipping or spraying. Repair damaged zinc-coated surfaces by the materials and methods conforming to ASTM A780/A780M and spot prime. At the option of the Contractor, a two-part system including bonderizing, baked-on epoxy primer, and baked-on enamel top coat may be applied to slats and hoods before forming, in lieu of prime coat specified.

2.2.5.2 Baked-Enamel or Powder-Coat Finish

Manufacturer's standard baked-on finish consisting of prime coat and thermosetting topcoat. Comply with the coating manufacturer's written instructions for cleaning, pretreatment, application, and minimum dry film thickness.

Give galvalume steel and hot dipped galvanized steel sheet coil a pretreatment to enhance adhesion followed by a caustic etch or alkaline wash for cleaning and degreasing. Apply a phosphate spray or chromate conversion treatment to protect against humidity and corrosive chemicals. Furnish an acrylic, polyester baked enamel or powder coating treatment conforming AAMA 2603. Bake the treatment using a temperature and time relationship that ensures thorough curing and a tough, durable finish. Provide a one coat application that achieves a 0.8 mil thickness.

Overhead coiling door is slate gray as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC.

PART 3 EXECUTION

3.1 INSTALLATION

Install overhead coiling door assembly, anchors and inserts for guides, brackets, motors, switches, hardware, and other accessories in accordance with approved detail drawings and manufacturer's written instructions. Upon completion of installation, ensure doors are free from all distortion.

Install overhead coiling doors, motors, hoods, and operators at the mounting locations as indicated for each door in the Contract Documents and as required by the manufacturer.

Install overhead coiling doors, switches, and controls along accessible routes in compliance with regulatory requirements for accessibility and as required by the manufacturer.

3.2 ADJUSTING AND CLEANING

3.2.1 Acceptance Provisions

After installation, adjust the hardware and moving parts. Lubricate bearings and sliding parts as recommended by manufacturer to provide smooth operating functions for ease movement, free of warping, twisting, or distortion of the door assembly.

Adjust seals to provide a weather-tight fit around entire perimeter.

Engage a factory-authorized service representative to perform startup service and checks according to the manufacturer's written instructions.

Test the door opening and closing operation when activated by controls system. Adjust controls and safeties. Replace damaged and malfunctioning controls and equipment. Reset the door-closing mechanism after a successful test.

Test and make final adjustment of new doors at no additional cost to the Government.

3.2.1.1 Maintenance and Adjustment

Not more than 90 calendar days after completion and acceptance of the project, examine, lubricate, test, and re-adjust doors as required for proper operation.

3.2.1.2 Cleaning

Clean doors in accordance with manufacturer's approved instructions.

3.3 HARDWARE SETS

3.3.1 A1, BATTALION HEADQUARTERS OVERHEAD COILING DOOR HARDWARE SCHEDULE

Secure Exterior Openings

Door No. 202B, 202C
HWS-A1.3 BMS Motor Overhead Door

	1 each Door Control	
GFGI	2 each DPDT Balanced Magnetic Switch	MIL

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access overhead curtain components

Note: Furnish electric metallic tubing raceway, cabling and blank stainless steel coverplates to receive Government furnished and installed devices

Exterior Openings

Door No. 177B, 192B, 192C, 193B, 203B, 219B
HWS-A1.4 Motor Overhead Door

1 each Door Control	

Note: Furnish electric metallic tubing raceway, cabling, equipment and

programming to support connected devices and operate overhead curtain components

3.3.2 A2-1, CO BUILDING OVERHEAD COILING DOOR HARDWARE SCHEDULE

Secure Exterior Openings

Door No. 132B, 133A, 134C, 135A, 136C, 147A, 148B, 149A, 150B, 151A
HWS-A2-1.3 BMS Motor Overhead Door
1 each Door Control
GFGI 2 each DPDT Balanced Magnetic Switch MIL

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access overhead curtain components

Note: Furnish electric metallic tubing raceway, cabling and blank stainless steel coverplates to receive Government furnished and installed devices

Exterior Openings

Door No. 142A
HWS-A2-1.4 Motor Overhead Door
1 each Door Control

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate overhead curtain components

3.3.3 A2-2, CO BUILDING OVERHEAD COILING DOOR HARDWARE SCHEDULE

Secure Exterior Openings

Door No. 132B, 133A, 134C, 135A, 136C, 147A, 148B, 149A, 150B, 151A
HWS-A2-2.3 BMS Motor Overhead Door
1 each Door Control
GFGI 2 each DPDT Balanced Magnetic Switch MIL

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access overhead curtain components

Note: Furnish electric metallic tubing raceway, cabling and blank stainless steel coverplates to receive Government furnished and installed devices

Exterior Openings

Door No. 142A

HWS-A2-2.4 Motor Overhead Door
1 each Door Control

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate overhead curtain components

3.3.4 A3, CO STORAGE OVERHEAD COILING DOOR HARDWARE SCHEDULE

Exterior Openings

Door No. 101E, 108C, 109B
HWS-A3.1 Motor Overhead Door
1 each Door Control

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate overhead curtain components

-- End of Section --

SECTION 08 34 02

BULLET-RESISTANT COMPONENTS
08/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF45	(2003; Reaffirmed 2009) Designation System for Aluminum Finishes

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 611	(2014) Voluntary Specification for Anodized Architectural Aluminum
AAMA 2605	(2022) Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM C1036	(2021) Standard Specification for Flat Glass
ASTM C1048	(2018) Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass
ASTM D256	(2024) Standard Test Methods for Determining the Izod Pendulum Impact Resistance of Plastics
ASTM D570	(2022) Standard Test Method for Water Absorption of Plastics
ASTM D635	(2018) Standard Test Method for Rate of Burning and/or Extent and Time of Burning of Plastics in a Horizontal Position
ASTM D638	(2014) Standard Test Method for Tensile

	Properties of Plastics
ASTM D792	(2013) Density and Specific Gravity (Relative Density) of Plastics by Displacement
ASTM D882	(2012) Tensile Properties of Thin Plastic Sheeting
ASTM D905	(2008; E 2009) Strength Properties of Adhesive Bonds in Shear by Compression Loading
ASTM D1003	(2013) Haze and Luminous Transmittance of Transparent Plastics
ASTM D1044	(2019) Standard Test Method for Resistance of Transparent Plastics to Surface Abrasion by the Taber Abraser
ASTM D1922	(2015; R 2020) Propagation Tear Resistance of Plastic Film and Thin Sheeting by Pendulum Method
ASTM D3595	(2025) Standard Specification for Polychlorotrifluoroethylene (PCTFE) Extruded Plastic Film
ASTM D3951	(2018) Commercial Packaging
ASTM D4093	(1995; R 2014) Photoelastic Measurements of Birefringence and Residual Strains in Transparent or Translucent Plastic Materials
ASTM D5420	(2016) Standard Test Method for Impact Resistance of Flat, Rigid Plastic Specimen by Means of a Strike Impacted by a Falling Weight (Gardner Impact)
ASTM E169	(2016; R 2022) Standard Practices for General Techniques of Ultraviolet-Visible Quantitative Analysis
ASTM E204	(1998; R 2007) Identification of Material by Infrared Absorption Spectroscopy, Using the ASTM Coded Band and Chemical Classification Index
ASTM E1300	(2024) Standard Practice for Determining Load Resistance of Glass in Buildings
ASTM F428	(2019; R 2024) Intensity of Scratches on Aerospace Glass Enclosures
ASTM F520	(2021) Standard Test Method for Environmental Resistance of Aerospace Transparencies to Artificially Induced Exposures

ASTM F548	(2019; R 2024) Standard Test Method for Intensity of Scratches on Aerospace Transparent Plastics
ASTM F735	(2022; E 2022) Standard Test Method for Abrasion Resistance of Transparent Plastics and Coatings Using the Oscillating Sand Method
ASTM F791	(1996; R 2013) Stress Crazing of Transparent Plastics
ASTM G155	(2025) Standard Practice for Operating Xenon Arc Lamp Apparatus for Exposure of Materials

GLASS ASSOCIATION OF NORTH AMERICA (GANA)

GANA Glazing Manual	(2008) Glazing Manual

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM HMMA 840	(2017) Guide Specifications for Receipt, Storage and Installation of Hollow Metal Doors and Frames

UL SOLUTIONS (UL)

UL 752	(2023) UL Standard for Safety Bullet-Resisting Equipment

1.2 SYSTEM DESCRIPTION

1.2.1 Design Requirements

Provide bullet resistant components conforming to the requirements specified for the particular items and, as much as possible, complete assemblies by a single manufacturer.

1.2.2 Performance Requirements

Specify all bullet resistant items to the threat specified. Operate movableand operable components smoothly and freely. When a reference for performance is listed, conform to referenced requirements.

1.2.3 Submittal Requirement Details

Submit the followin:

a. Manufacturer's descriptive data and installation instructions. Include cleaning instructions as recommended by the plastic sheet manufacturer.

b. Lists including schedule of all components to be incorporated in the work with manufacturer's model or catalog numbers, specification and drawing reference numbers, warranty information, threat level certified and number of items provided.

c. Evidence that standard products essentially duplicate items that have been satisfactorily in use for two years or more, including name of purchasers, locations of installations, dates of installations, and service organizations.

d. Manufacturer's certificates attesting that all components conform to the requirements on drawings and in specifications. Include testing reports from independent testing laboratories indicating conformance to regulatory requirements.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation; G

SD-03 Product Data

Bullet Resistant Components; G

SD-07 Certificates

Bullet Resistant Components

SD-10 Operation and Maintenance Data

Bullet Resistant Components; G

1.4 QUALITY ASSURANCE

Provide Bullet-resistant components at locations shown on the drawings. Bullet-resistant components UL SPSA\ of UL 752.\

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver components to the job site with the brand, name, and model number clearly marked thereon. Deliver, store and handle all components so as not to be damaged or deformed, and in accordance with ASTM D3951. Handle items carefully to prevent damage to the faces, edges, corners, ends, and glazing. Clean, repair, or replace abraded, scarred, or rusty areas immediately upon detection. Replace damaged components that cannot be restored to like-new condition. Store components and equipment in a dry location on platforms or pallets that are ventilated adequately, free of dust, water, and other contaminants, and stored in a manner which permits easy access for inspection and handling.

1.6 SCHEDULING

Glaze bullet-resistant windows, except factory-glazed units, after all concrete, masonry, ceiling, electrical, mechanical, plumbing and adjacent finish work iscomplete to avoid damage to the glazing material. Cover factory-glazed windows to protect them from damage during adjacent finish work.

1.7 WARRANTY

Furnish manufacturer's warranty for 5 years for glazing materials. Provide for replacement and installation of glazing if delamination, discoloration, or cracking, or crazing occurs.

PART 2 PRODUCTS

2.1 MATERIALS AND COMPONENTS

Provide materials and components which are the standard products of a manufacturer regularly engaged in the manufacture of such products, unless otherwise indicated and detailed on the drawings, and that essentially duplicate items that have been in satisfactory use for at least two years prior to bid opening. Provide components supported by a service organization that is, in the opinion of the Contracting Officer, reasonably convenient to the site, or by the manufacturer. Where components are detailed on the drawings and do not conform to a manufacturer's standard product, provide components that are constructed of manufacturer's standard materials which conform to the specified ballistic standard or test. Provide bullet-resistant component assemblies of size and type indicated and provide at locations shown. Design all items included for exterior installation to resist water penetration or entrapment.

2.2 BULLET-RESISTANT STEEL WINDOWS

Fabricate window assemblies from aluminum extrusions with internal armoring and bullet-resistant glazing materials specified herein; the entire assembly must meet or exceed the specified regulatory requirements. Provide welded frame units of sizes and shapes indicated on the drawings with minimum frame face dimensions of 2 inches. Furnish glazing material with window assembly for onsite installation, or furnish factory glazed window units. Entire assembly must be furnished by same manufacturer. Weld exterior (attack side) glazing stops or integral to frame. Provide removable interior (protected side) glazing stops attached with high-strength alloy steel machine screws with tamper-resistant heads.

Aluminum framing is Slate Grey.

2.2.1 Glazing Materials

Provide factory fabricated units designed to be bullet-resistant to the specified test standard in paragraph COMPONENT TEST REQUIREMENTS. Glazing material must be laminated polycarbonate with a low-spall protected (interior) face. Low-spall interior face must meet or exceed requirements for spall resistance defined in UL 752. Provide glazing material conforming to applicable requirements contained in ASTM C1036, ASTM C1048, and ASTM E1300. Test glazing materials in accordance with the applicable sections of the following testing procedures: ASTM D905, ASTM D1003, ASTM F428, ASTM F548, ASTM D4093, and ASTM F520. Apply a hardcoat to all plastic glazing exposed to the interior or exterior environment.

2.2.1.1 Polycarbonate Plastic Sheets

Provide bullet-resistant laminated polycarbonate sheets, ultraviolet stabilized, high abrasion resistant sheets conforming to ASTM D3595. Test polycarbonate materials in accordance with the applicable sections of the

following testing procedures: ASTM D256, ASTM D5420, ASTM D792, ASTM F735, ASTM D1003, ASTM D635, ASTM D638, ASTM D1044, ASTM D882, ASTM D1922, ASTM D570, ASTM F520, ASTM E169, ASTM E204, ASTM G155, and ASTM F791. Do not use polyvinyl butyral in contact with polycarbonate because its plasticizer may craze polycarbonate.

2.2.2 Adhesive Interlayer Materials

Provide adhesive interlayer materials for bonding laminates (glass-glass, glass-plastic, or plastic-plastic bonds) that are chemically compatible with the surfaces being bonded. Interlayer materials may be polyvinyl butyral, cast-in-place urethane, proprietary materials, sheet form urethane and other materials. Do not use polyvinyl butyral to bond polycarbonate. Provide adhesives in accordance with ASTM D905 and manufacturer's recommendations.

2.2.3 Sealants

Furnish sealants for glazings that are chemically compatible with the glazing materials they contact with no deleterious effects to the glazing materials or to the adhesives used in laminates. Sealants must be in accordance with glazing manufacturer's recommendations and GANA Glazing Manual.

2.2.4 Deal Trays

Provide nominal 12-3/4 inch wide by 1-5/8 inch high opening in sill of window frame. Provide deal tray welded subassembly of window assembly conforming to specified requirements for entire window assembly. Provide opening configuration of deal tray that prevents ballistic penetration or spall from the threat weapon, and resists lead spray from a shotgun blast. Provide tray opening that prevents insertion of the muzzle of a firearm. Finish is brushed stainless steel.

2.3 BULLET-RESISTANT SPEAKING APERTURES

Fabricate speaking apertures to allow passage of voice at normal speaking volume without distortion, to resist the specified threat level for indoor use, and designed to prevent direct aim by the insertion of the muzzle of any firearm. Finish is brushed stainless steel.

2.4 Fiberglass Sheet

Fiberglass sheet has a nominal thickness of 0.3125 to 0.4375 inches, weighs 4.0 tp 4.8 pounds per square foot and conmplies with UL-3, SPSA. Fiberglass sheets consist of multiple layers of starch and oil woven, roving ballistic grade fiberglass cloth impregnated with a thermoset polyester resin. Raw materials placed in a hydraulic hot press and compressed into flat panels as large as 4 feet, 0 inches by 8 feet, 0 inches. Uniform fiber to resin ratios create ply delamination characteristics that encapsulate projectiles.

2.5 ACCESSORIES

Provide all accessories for the installation or erection of above components into the surrounding structure. Anchorage must be as strong and bullet-resistant as the components. Install/erect in accordance with manufacturer's recommended instructions.

2.6 LABELING

Plainly and permanently label bullet-resistant equipment in accordance with regulatory requirements. Provide label that is compatible with plastic or coating, visible only on protected side, after installation, including the following information:

a. Manufacturer's name or identifying symbol

b. Model Number, Control Number, or equivalent

c. Date of manufacture by week, month or quarter and year. This may be abbreviated or be in a traceable code such as the lot number.

d. Correct mounting position including threat side and secure side (by removable label on glazing material).

e. Code indicating bullet-resistant rating and test standard used (by removable label on glazing material).

2.7 SHOP/FACTORY FINISHING

Furnish all ferrous metal components, except stainless steel, primed for painting unless indicated otherwise. Perform finish painting in accordance with Section 09 90 00 PAINTS AND COATINGS, unless otherwise indicated. When anodic coatings are specified, the coatings must conform to AAMA 611, with coating thickness not less than that specified for protective and decorative type finish in AA DAF45. Apply a polished satin finish pretreatment and a clear lacquer overcoat to anodized items. Shop finish all factory or manufactured components as indicated.

Give aluminum extrusions for heavy commercial applications a pretreatment to enhance adhesion followed by a caustic etch or alkaline wash for cleaning and degreasing. Apply a phosphate spray or chromate conversion treatment to protect against humidity and corrosive chemicals. Furnish an organic coating treatment conforming to AAMA 2605 to obtain a 70% PVDF coating. Provide a two coat application consisting of 0.2 mils of primer with a 1.0 mil topcoat that achieves a 1.2 mil thickness.

2.7.1 Ferrous Metal

Clean surfaces of ferrous metal, except galvanized and stainless steel surfaces, and shop coat with the manufacturer's standard protective coating other than a bituminous protective coating, compatible with finish coats. Prior to shop painting, clean surfaces with solvents to remove grease and oil, and with power wire-brushing or sandblasting to remove loose rust, loose mill scale and other foreign substances. Do not shop paint surfaces of items to be embedded in concrete.

2.7.2 Galvanizing

Items specified to be galvanized must be hot-dip processed after fabrication. Galvanize in accordance with ASTM A123/A123M or ASTM A653/A653M as applicable.

PART 3 EXECUTION

3.1 EXAMINATION

Field verify dimensions of rough openings for components, and that surfaces of openings are plumb, true, and provide required clearances. Protect surrounding work prior to installation of bullet-resistant components. Restore surrounding work which is damaged as a result of the installation of bullet-resistant components to like-new condition prior to acceptance of the work described herein. Examine existing work to ensure that it is ready for installation or erection of the components. Check and correct components for racking, twisting, and other malformation prior to installation. Set frames true, plumb and aligned for proper installation. Examine all surfaces and connections for damage prior to installation.

3.2 INSTALLATION

Provide finished work that is rigid, neat in appearance and free from defects. Install equipment plumb, level, and secured rigidly in place. Install frames conforming to NAAMM HMMA 840. Install hardware in strict compliance with approved printed instructions and detail drawings provided by the manufacturer. The Contractor is responsible for proper installing of the door assembly so that operating clearances and bearing surfaces conform to manufacturer's instructions. Install all other components in accordance with approved manufacturer's recommended instructions. Test all operable parts of components for smooth, trouble-free operation, in the presence of the Contracting Officer. Show proposed layout and anchorage of components and appurtenances, and relationship to other parts of work including clearances for operation and maintenance. Show conformance to all requirements, including fabrication details, sizes, thickness of materials, anchorage, finishes, hardware location and installation.

3.3 FASTENERS

Fasteners exposed to view must match in color and finish and must harmonize with the material to which fasteners are applied.

3.4 CORROSION PROTECTION - DISSIMILAR MATERIALS

Give contact surfaces between dissimilar metals and aluminum surfaces in contact with concrete, masonry, pressure-treated wood or absorptive materials subject to wetting, a protective coating.

3.5 ADJUSTING/CLEANING

Clean all components in accordance with manufacturer's instructions.

-- End of Section --

SECTION 08 34 73

SOUND CONTROL DOOR ASSEMBLIES
11/19, CHG 1: 02/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS D1.3/D1.3M	(2018) Structural Welding Code - Sheet Steel

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A108	(2013) Standard Specification for Steel Bar, Carbon and Alloy, Cold-Finished
ASTM A568/A568M	(2019a) Standard Specification for Steel, Sheet, Carbon, Structural, and High-Strength, Low-Alloy, Hot-Rolled and Cold-Rolled, General Requirements for
ASTM A1008/A1008M	(2021a) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM A1011/A1011M	(2018a) Standard Specification for Steel Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength
ASTM C143/C143M	(2020) Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C476	(2023) Standard Specification for Grout for Masonry
ASTM D1056	(2020) Standard Specification for Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM D6386	(2016a) Standard Practice for Preparation of Zinc (Hot-Dip Galvanized) Coated Iron and Steel Product and Hardware Surfaces for Painting

ASTM E90	(2023) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements
ASTM E336	(2025) Standard Test Method for Measurement of Airborne Sound Attenuation between Rooms in Buildings
ASTM E413	(2022) Classification for Rating Sound Insulation
ASTM E1289	(2008; R 2022) Standard Specification for Reference Specimen for Sound Transmission Loss
ASTM F476	(2014) Standard Test Methods for Security of Swinging Door Assemblies

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191	Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines

UL SOLUTIONS (UL)

UL 634	(2007; Reprint Sep 2025) Connectors and Switches for Use with Burglar-Alarm Systems

WOODWORK INSTITUTE (WI)

NAAWS 3.1	(2017; 2018 Errata Edition) North American Architectural Woodwork Standards

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fabrication Drawings

SD-03 Product Data

Hollow Metal Sound Retardant Doors; G

Door Frames; G

Door Hardware; G

Door Frame Sound Infill; G

Intumescent Seals and Gasketing; G

Thresholds; G

Astragals; G

SD-06 Test Reports

Wind Loading Tests; G

Water Leakage Tests; G

Acoustical Tests; G

Air Infiltration Tests; G

Positive Pressure Tests; G

SD-07 Certificates

Hollow Metal Sound Retardant Doors; G

Wood Sound Retardant Doors; G

Door Frames; G

Door Hardware; G

Thresholds; G

Astragals; G

Assembly Test Reports

1.3 QUALITY CONTROL

Ensure work within this section is designed and furnished by one manufacturer, who has been engaged in the manufacture of Sound Retardant Door systems for at least five years prior to the start of this work.

Provide acoustic assemblies manufactured by a single source specializing in the production of this type work for a minimum of five years.

1.3.1 Compliance and Labeling

1.3.1.1 Compliance with Accessibility Requirements

Americans with Disabilities Act/Architectural Barriers Act (ADA/ABA) 36 CFR 1191

Accessibility Guidelines for Buildings and Facilities (ADAAG) 36 CFR 1191

1.3.1.2 Category A Positive Pressure Fire Door Construction

Where requirements for positive pressure are met, include for doors all requirements as part of the door construction per Category A guidelines as published by ITS/Warnock-Hersey. Intumescent is not allowed on the frame. Applying smoke gasketing around the perimeter of the frame to meet the "S" smoke rating is permissible in instances where smoke control is required.

1.3.1.3 Labeling

Ensure all positive pressure door assemblies carry the fire label for the complete opening, clearly identifying the:

a. Manufacturer

b. Third party testing and certification agency

c. Fire door rating

d. Installation limitations

e. Compatible frame, hardware component ratings

f. Compatible lite or vision panel component ratings

g. Required building code information, including temperature and smoke rating

g. STC rating if required.

Provide documentation of ABA/ADA accessibility compliance of applicable components, as required by 36 CFR 1191 Appendix D - Technical.

1.4 DELIVERY, STORAGE, AND HANDLING

Ship all doors in the manufacturer's undamaged individual cartons, securely bundled and wrapped with moisture-resistant covers and stored in accordance with the manufacturer's printed instructions in a dry, clean, and ventilated area.

Store all materials on planks in a dry location. Store doors and frames vertically with an airspace between. Store doors on the edge to eliminate any potential damage to the door bottom seal. Cover all material to protect from damage but in a manner to allow proper circulation.

Maintain relative humidity in the building between 30 and 65 percent. Maintain the ambient temperature at 60 degrees F minimum at the time of installation of wood doors.

Perform final adjustment of seals when temperatures and humidity conditions replicate the interior conditions that will exist when the building is occupied.

1.5 WARRANTY

Manufacturer's warranty for 5 years from date of supply, covering material and workmanship. Failures include, but are not limited to, the following:

a. Failure to meet sound rating requirements

b. Faulty operation of sound seals

c. Deterioration of metals, metal finishes, and other materials beyond normal use or weathering.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide sound retardant door assemblies of the thickness, width, and height indicated, complete with perimeter seals, seal housings, gasketing, automatic door bottoms, thresholds, door frames, and astragals as required to conform to the specified STC per ASTM E90 and ASTM E1289.

Submit fabrication drawings for Hollow Metal Sound Retardant Doors, Wood Sound Retardant Doors, Door Frames and Door Frame Sound Infill.

Submit certificates showing conformance with the referenced standards in this section, and manufacturer's catalog data including STC ratings and UL fire rating, where applicable, for the following items: Hollow metal sound retardant doors; wood sound retardant doors; door frames; door hardware; intumescent seals and gasketing; thresholds; and astragals.

Provide assemblies that are complete with metal frame, wood door(s), sealing system, and Cam-lift hinges (when required).

2.1.1 Design Requirements

2.1.1.1 Door Design

Provide sound Retardant Wood Swinging Doors that are a 1-3/4-inch thickness construction with sizes as indicated on drawings. No visible seams are permitted on door faces. Provide face gauges, internal sound retardant core and perimeter door edge construction per manufacturer's standard for the specified STC rating. No lead or asbestos is permitted in door construction to achieve STC performance. Provide face veneer species cut and color as selected from manufacturer's full range of available colors and patterns. No lead or asbestos is permitted in door construction to achieve performance requirements.

2.1.1.2 Frame Design

Provide sound Retardant Metal Frames conforming to ASTM A1008/A1008M, not less than 0.0747-inch thick, and free from pitting, scale, stretcher strains, fluting, and surface defects with integral trim and shipped with temporary spreader. Knockdown frames are not acceptable.

Provide frames with 2 inch faces, profiles and dimensions as indicated, with mitered reinforced corners, welded the full depth of frame and trim, with exposed surfaces ground smooth and flush. Close contact edges to hairline joints.

2.1.2 Performance Requirements

2.1.2.1 STC (Sound Transmission Classification) Rating

Provide doors with aHWS STC 40, 45 and 55.

2.1.2.2 Walls, Openings and Hardware

Openings have an STC indicated in the hardware sets that identifies laboratory tested STC doors and laboratory tested STC hardware installed in laboratory tested STC wall types. Field testing of wall types must achieve an FSTC acoustical performance as measured by ASTM E336 and

ASTM E413.

Acoustical Opening	HWS STC	Door STC	Hardware STC	Wall STC	Wall FSTC
Single leaf	40	40	44	40	35
Single leaf	45	45	44	45	40
Double leaf	45	45	47	45	40
Single leaf	55	54	53	55	50
Double leaf	55	54	44	55	50

2.2 FABRICATION

Provide doors that are minimum 16 gauge, 1 3/4 inch thick with welded, seamless construction. No visible joints are permitted on the exposed faces or edges. Join door skins at vertical edges by continuous welds, ground and dressed smooth to provide a flush finish. Reinforce top and bottom with 16 gauge continuous inverted steel channels spot welded to both faces. Finish both top and bottom to provide a smooth flush condition. Bevel both vertical edges 1/8 inch in 2 inches.

Clean and sand to smooth finish all doors to remove handling and storage marks, raised grain, minor surface marks and abrasions which are to receive a job site finish.

2.2.1 Hollow Metal Sound Retardant Doors

2.2.1.1 Construction

Conform to ASTM A1008/A1008M for door construction utilizing steel facing sheets. Conform stretcher level flatness to ASTM A568/A568M; not less than 0.0598 inch thick; free from pitting, scale, and surface defects; separated by a core construction designed to meet the required STC; and tested and rated in accordance with ASTM E90.

Provide doors that have flush seamless face sheets and vertical edges, with continuous welded and smooth joints. Provide edges that are flush or rabbeted as required for perimeter seals.

Provide door surfaces that are visually flat and free from warp, waviness, and other surface irregularities and defects. Maximum allowable warp or twist-can not exceed 1/8 inch when measured with a 7 foot straightedge along the diagonal and not exceed 1/16 inch when measured with a 7 foot straightedge in the width or in any position along the length of the door.

Provide hardware reinforcement that is steel drilled, tapped to template requirements and welded in place. Provide minimum thicknesses as follows:

a. Butts, 0.1494 inch

b. Lock strike, 0.1196 inch

c. Surface applied hardware 0.0747 inch

Provide doors, including sound retardant type, to bear the UL label fire rating and the specified STC for conditions encountered.

2.2.1.2 Coating

Thoroughly clean all mill scale, rust, oil, grease, dirt, and other

foreign materials from surfaces before the application of the shop coat of paint.

After cleaning, provide galvanized surfaces free of paint in accordance with ASTM D6386, Method A, B, C, or D.

Apply to clean prepared dry surfaces one shop coat of rust inhibitive metallic oxide or synthetic resin primer by brush, dipping, or other approved method to provide a continuous minimum dry film thickness (dft) of 0.9 mil.

Shop paint the exposed door surfaces, including surfaces that are galvanized.

Shop paint the concealed exterior door surfaces except galvanized surfaces.

2.2.2 Wood Sound Retardant Doors

Construct doors with wood veneer facings separated by a core construction designed to meet the required STC. Test, rate, and label in accordance with ASTM E90.

Comply with the NAAWS 3.1, "Guide Specifications and Quality Certification Program," for custom grade constructions and to the requirements specified.

Perform beveling, prefitting, machining, mortising, and routing for hardware, perimeter seals, and door bottom cutouts at the mill.

Furnish custom grade door facings with standard thickness face veneers conforming to NAAWS 3.1, Type 1 for stain and transparent job site-applied finish.

2.2.2.1 Faces

Single-ply wood veneer not less than 1/50 inch thick.

a. Species: White oak.

b. Cut: Rift cut.

c. Match between Veneer Leaves: Slip match.

d. Assembly of Veneer Leaves on Door Faces: Center-balance match.

e. Pair and Set Match: Provide for doors hung in same opening.

f. Room Match: Match door faces within each separate room or area of building. Corridor-door faces do not need to match where they are separated by 10 feet or more.

g. Room Match: Provide door faces of compatible color and grain within each separate room or area of building.

h. Transom Match: End match.

2.2.3 Door Finishing

Conform factory finishing of Sound Retardant Wood Swinging Doors in accordance with AWI Quality Standards. Provide factory finish of a

water-base stain and ultraviolet (UV) cured polyurethane sealer to comply with EPA Title 5 guidelines for Volatile Organic Compound (VOC) emissions limitations. Conform finish to meet or exceed performance standards of NAAWS 3.1 catalyzed polyurethane.

2.3 COMPONENTS

2.3.1 Frames

Construct frames for Sound Retardant Wood Swinging Doors from formed sheet steel or structural shapes and bars. Provide sheet steel that is commercial quality, level, cold rolled steel conforming to ASTM A1008/A1008Mor hot rolled, pickled and oiled steel conforming to ASTM A1011/A1011M. Comply steel shapes with ASTM A36/A36M and steel bars with ASTM A108, Grade 1018.

2.3.2 Door Frame Sound Infill

Grout: Comply with ASTM C476, with a slump of not more than 4 inches as measured according to ASTM C143/C143M.

Corrosion-Resistant Coating: Cold-applied asphalt mastic, compounded for 15 mil dry film thickness per coat. Provide inert-type noncorrosive compound free of asbestos fibers, sulfur components, and other deleterious impurities.

2.3.3 Hardware Reinforcements

Factory mortise, reinforce, drill and tap frames for all mortise hardware as required by hardware manufacturer's template. Provide necessary reinforcement plates as required for surface mounted hardware; installer to perform all field drilling and tapping. Provide dust cover boxes on all frame mortises. Provide minimum thicknesses as follows:

a. Butts, 3/16 inch

b. Lock strike, 0.1196 inch

c. Surface applied hardware 0.0747 inch

2.3.4 Jamb Anchors

Provide number and spacing of anchors as follows:

2.3.4.1 Masonry Type

Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:

a) Two anchors per jamb up to 60 inches in height.

b) Three anchors per jamb from 60 to 90 inches in height.

c) Four anchors per jamb from 90 to 96 inches in height.

d) Four anchors per jamb plus one additional anchor per jamb for each 24 inches, or fraction thereof, more than 96 inches in height.

2.3.4.2 Stud-Wall Type

Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:

a) Three anchors per jamb up to 60 inches in height.

b) Four anchors per jamb from 60 to 90 inches in height.

c) Five anchors per jamb from 90 to 96 inches in height.

d) Five anchors per jamb plus one additional anchor per jamb for each 24 inches, or fraction thereof, more than 96 inches in height.

e) Two anchors per head for frames more than 42 inches wide and mounted in metal-stud partitions.

2.3.5 Door Hardware

Procure cut sheets for GFGI hardware from the Government. Coordinate GFGI hardware items with furnished hardware items indicated in applicable hardware sets. Use templates to prepare doors and frames for GFGI hardware selections.

Furnish tested acoustical hardware sets consisting of hinges, automatic door bottom; threshold; head and jamb gaskets; and head and jamb spring weatherstripping that achieves sound attenuation levels stipulated.

Provide the following STC related hardware with the door; cam-lift hinges, perimeter seals, astragals, door bottoms, thresholds and hardware standoff brackets.

Include on Fabrication drawings a finish hardware schedule for each door and a hollow metal door frame schedule for each door indicating profile, dimensions, hardware reinforcement, and frame anchorage. Also indicate perimeter seals, door-bottom devices and other hardware items that are assembled in the shop.

Refer to Section 08 71 00 DOOR HARDWARE for remaining hardware requirements.

2.3.5.1 Cam Lift Hinges

Cam lift hinges raise doors above floor finishes 0.375 inches at 180 degrees opening and lower doors for a tight threshold seal with their swing. Hinges comply with ASTM F476, are compatible with sound attenuating doors and are rated for extra heavy duty usage. Two hinges support door assemblies weighing 825 pounds. Hinges are handed and fabricated of stainless steel with a 0.5 inch stainless steel pin. Furnish a security pin to prevent forced entry. Cams have a 1.1875 inch outside diameter. Plugs are hardened steel with bottom grease fitting for easy lubrication. Minimum frame head clearance is 0.1875 inches. Hollow metal frame hinge reinforcement is 0.375 inches, 000 gauge. Dimensions are 5 inches wide by 5 inches high by a 0.25 inch in thickness.

Electrified cam lift hinges pass low voltage power and signaling from door frames to doors via a flexible connector complying with UL 634. Connectors are a standard 12 wire configuration that includes two 20 AWG red and black conductors rated for 4.0 continuous amps at 24 VDC and 0.5

second surge per pair rated at 16.0 amps at 24 VDC. The remaining ten multicolored conductors are 28 AWG, rated for 1.0 continuous amps at 24 VDC and a 0.5 second surge per pair rated at 1.0 amps at 24 VDC. Factory terminated conductors receive quick connecting Molex plugs and pins. Hinges are non lifting, non load bearing and non handed hollow stainless steel shells designed to match functional cam lift hinges. Dimensions are 5 inches wide by 5 inches high by a 0.25 inch in thickness.

2.3.5.2 STC 47 Pair Tested Hardware Set

Tested hardware set is a door pair sealing system consisting of cam hinges, automatic door bottom; threshold; head and jamb gaskets; and bottom spring seals that maintains an STC 47. Tested hardware set for a single leaf door uses the same components and maintains an STC 47.

Tested hardware set head and jamb gasketing is a surface mounted stop complying with BHMA R3B254 that incorporates compressive, solid neoprene perimeter seals. Stops are fabricated from extruded aluminum and incorporate stainless steel screws with an adjusting range of 0.031 inches. Dimensions are 1.25 inches wide by 0.914 inches deep.

Tested hardware set door bottom is a heavy duty, surface mounted, automatic type complying with BHMA R3B3341. Double neoprene seal bottom edge has a drop ranging from 0.375 inches to 0.875 inches. Door bottoms are fabricated from extruded aluminum and incorporate a locking screw. An adjustable plunger compresses against the door frame to activate a concealed flat spring mechanism, dropping the seal smoothly. The plunger is released upon door opening causing the seal to automatically retract. Assemblies are non handed and for push side installation only. Dimensions are 1.901 inches wide by 0.916 inches deep by the width of the door.

Tested hardware set meeting stile astragal is aluminum with center neoprene bulb and finger for double sealing. Attach to the active leaf. Astragals are 1.625 inches in width, 0.387 inches in depth and comply with BHMA R3B634.

Tested hardware set threshold is 0.125 inch aluminum incorporating a 0.375 inch rabbet with extruded neoprene bulb and finger for double sealing. Thresholds are 3.687 inches in width, provide a smooth surface for receiving door bottom seals and comply with BHMA J16300.

2.3.5.3 STC 53 Tested Hardware Set

Tested hardware set is an EMI and RFI door sealing system consisting of cam hinges, automatic door bottom; threshold; head and jamb gaskets; and head and jamb spring seals that achieves sound attenuation ranging from 111 dB at 10 MHz to 73 dB at 1,000 MHz and maintains an STC 53.

Tested hardware set head and jamb gasketing is a surface mounted stop complying with BHMA R3L154 that incorporates magnet and solid neoprene perimeter seals. Stops are fabricated from extruded aluminum and incorporate a snap on cover that accesses sound energy absorber media. Dimensions are 2 inches wide by 0.848 inches deep.

Tested hardware set spring seal is 0.006 inch, 34 gauge bronze spring with hemmed edges that complies with BHMA R1K155. Springs have a width of 1.125 inches.

Tested hardware set door bottom is a heavy duty, surface mounted,

automatic type complying with BHMA R3B3341. Double neoprene seal bottom edge has a drop ranging from 0.375 inches to 0.875 inches. Door bottoms are fabricated from extruded aluminum and incorporate a locking screw. An adjustable plunger compresses against the door frame to activate a concealed flat spring mechanism, dropping the seal smoothly. The plunger is released upon door opening causing the seal to automatically retract. Assemblies are non handed and for push side installation only. Dimensions are 1.901 inches wide by 0.916 inches deep by the width of the door.

Tested hardware set threshold is 0.125 inch bronze incorporating a 0.375 inch rabbet with extruded neoprene bulb and finger for double sealing. Thresholds are 3.687 inches in width, provide a smooth surface for receiving door bottom seals and comply with BHMA J16300.

Self adhering weatherstripping for use with spring seals consists of 0.5 inch by 0.5 inch intumescent, semi rigid gasketing with pressure sensitive adhesive backing for corner mounting between jambs and stops. Each leg end has a 0.25 inch flexible blade that receives the door edge.

2.3.6 Head and Jamb Seals

Provide a closed-cell, expanded cellular rubber Seal material conforming to ASTM D1056, Type S, Grade SBE-42 or SCE-42 for heads and jambs.

Install seals in formed steel or extruded aluminum shapes designed to receive and hold seals and to provide concealed adjustable attachment to door frames. Provide concealed adjustment screws that are not more than 12 inches on center and provide at least 3/8 inch adjustment.

2.3.7 Door Bottoms

Neoprene or silicone gasket held in place by metal housing; mortised into bottom edge of door.

2.3.7.1 Automatic Door Bottoms

Neoprene or silicone gasket, held in place by metal housing, that automatically drops to form seal when door is closed; mounted to bottom edge of door with screws.

Mounting: Mortised or semimortised into bottom of door as required by testing to achieve STC rating indicated.

2.3.8 Thresholds

Provide metal thresholds where indicated. Provide thresholds that are extruded aluminum, 6063-T5 alloy, mill finish, not less than 1/8 inch thick, with integral seal grooves formed to the indicated section.

Provide flat, smooth, unfluted thresholds as recommended by manufacturer; fabricated from aluminum.

a. Finish: Clear anodic finish.

2.3.9 Astragals

Provide steel astragals for the inactive leaf of each pair of doors, as indicated. Surface mount to the door by welded connections or by countersunk, flat-head screws, within integral groove to receive perimeter

seal material.

2.4 TESTS, INSPECTIONS, AND VERIFICATIONS

2.4.1 Sound Transmission Classification

Provide test reports prepared by a nationally recognized, independent laboratory for Acoustical Tests, Air Infiltration Tests, Wind Loading Tests, and Water Leakage Tests indicating that the sound transmission classification (STC) of the proposed door, based on tests at 16 third-octave band frequencies from 125 to 4,000 hertz, is no less than the specified STC when tested in accordance with ASTM E90, and that the door tested is hung in substantially the type of wall and frame as indicated and is fully operable with hardware and perimeter seals installed.

2.4.2 Positive Pressure

Provide test reports, prepared by a nationally recognized, independent laboratory for Positive Pressure Tests, for all fire rated door assemblies, including Intumescent Seals,Gasketing, and Door Bottoms.

Incorporate factory installed edge seals into wood door constructions certified in accordance with Category A, positive pressure fire door testing. Assemblies are Category G gasketing. Provide gasketing complying with NFPA 80 for fire rated openings encountered. Gasketing complies with ANSI 156.22, UL 1784 and UL 10C. Door pairs receive steel edges and astragals or concealed intumescent seals.

2.4.3 Cam Lift Hinges

When required to achieve STC, manufacturer to furnish laboratory test data certifying hinges have been cycled a minimum of 1,000,000 while supporting a minimum door weight of 350 pounds.

Full-mortise template type that raises the door 1/2 inch when door is fully open; with hardened pin; fabricated from stainless steel.

2.4.4 Guarantee

Provide written guarantee that each door delivered to the project is equal in construction, sound transmission classification (STC), and positive pressure test rating where applicable, with appropriate labeling and markings, to that of the sample door tested. Clearly state in written guarantee that each door assembly, when installed in accordance with the manufacturer's printed instructions, has an in-place STC within 3 decibels of the specimen tested. Submit the following test data and Certificates with the written Guarantee:

a. Wind Loading Tests

b. Water Leakage Tests

c. Acoustical Tests

d. Air Infiltration Tests

e. Positive Pressure Tests

PART 3 EXECUTION

3.1 PREPARATION

Upon receipt of material, thoroughly inspect all frames, doors and accessories. Verify quantities and tag numbers according to the packing list provided. Report all discrepancies, deficiencies and/or damages immediately to Contracting Officer.

Prior to installation check all doors and frames for correct size and swing. Verify that frames are plumb, square and aligned without twist in accordance with tolerances published by NAAMM/HMMA and SDI.

3.1.1 Frame Painting and Cleaning

Clean thoroughly all surfaces of all mill scale, rust, oil, grease, dirt, and other foreign materials before the application of the shop coat of paint.

Apply one shop coat of rust inhibitive metallic oxide or synthetic resin primer applied to clean, dry, and prepared surfaces by brush, dipping, or other approved method to provide a continuous minimum dry film thickness of 0.9 mil.

3.2 INSTALLATION

3.2.1 Frame

Install frames plumb and true with not more than 1/32 inch deviation in vertical alignment in 8 feet. Anchor to the wall in accordance with the manufacturer's instructions. Grout frames solid with mortar in masonry, concrete, and plaster wall construction. Spot grout frames in dry wall partitions with mortar at the jamb anchor clips; fill the space between metal frame and stud partition solidly with fiberglass or mineral wool insulation.

Field splices may be required after installation because of shipping limitations. Field weld splices by certified welders per manufacturer's instructions and in accordance with AWS D1.3/D1.3M.

3.2.2 Door

Install and adjust all doors, hardware, and seals in accordance with the approved drawings, hardware schedules, and the printed instructions of the door manufacturer.

Install and adjust perimeter seals and automatic door bottom seals to provide positive compression contact with the entire sealing surface with no gaps, openings, or breaks. Hinges or hardware which distort or pinch the perimeter seal during operation of the door will be rejected.

Install door bottom devices to seal the space between the door bottoms and the finished floor and the space between the seal and seal housing.

Field apply perimeter seal housings with mitered corners and with flush, aligned hairline joints.

Install components to manufacturer's written instructions. Coordinate with wall construction for anchor placement. Set frames plumb, square,

level and at correct elevation. Adjust operable parts for correct clearances and function. Install and adjust perimeter and bottom acoustic seals.

3.3 FIELD QUALITY CONTROL

Provide third party testing in accordance with ASTM E336. Verify in writing that installed product performs no less than five (5) ASTC or NIC rating points below the specified laboratory STC rating. Examine, adjust, and retest any installation not meeting that criteria until compliance is obtained.

3.3.1 Testing and Performance

Provide assemblies that are identical to those tested at an independent acoustical laboratory qualified under the National Voluntary Laboratory Accreditation Program (NVLAP) by the National Institute for Science and Technology (NIST) in accordance with ASTM E90 and ASTM E413. For the assembly test reports include the laboratory name, test report number and date of test.

3.4 HARDWARE SETS

3.4.1 A1, BATTALION HEADQUARTERS ACOUSTICAL HARDWARE SCHEDULE

Secure Exterior STC Openings

Door No. 202A, 202D
HWS-A1.5 B2BAC, Opn Stor Entrance, STC 45

Section 08 71 00	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each Power Transfer	689
Section 08 71 00	1 each FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630 / Black
Section 08 71 00	1 each Rim Cylinder Housing, F26	630
Section 08 71 00	1 each 7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each FF-L-2740B Weather Resistant Enclosure	Gray
Section 08 71 00	1 each Dummy Pair no SFIC	630
Section 08 71 00	1 each Strike Filler Plate	630
Section 08 71 00	1 each 48" Drip Ledge	MIL
Section 08 71 00	1 each 44" Bottom Sweep	MIL
	1 each 3870 Acoustical Gasket	Clear Anodized
	1 each 44" Automatic Door Bottom	Clear Anodized
	1 each 44" Rabbeted Threshold, J16300	MIL
Section 08 71 00	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Communications 199

Door No. 179A, 179B
HWS-A1.6 B2BAC, Opn Stor Entrance, STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630 / Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each	FF-L-2740B Weather Resistant Enclosure	Gray
Section 08 71 00	1 each	Dummy Pair no SFIC	630
Section 08 71 00	1 each	Strike Filler Plate	630
Section 08 71 00	1 each	48" Drip Ledge	MIL
Section 08 71 00	1 each	44" Bottom Sweep	MIL
	1 each	3870 Acoustical Gasket	Clear Anodized
	1 each	44" Automatic Door Bottom	Clear Anodized
	1 each	44" Rabbeted Threshold, J16300	MIL
Section 08 71 00	1 each	Floor Stop, L02131	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 174

Door No. 225A
HWS-A1.7 B2BAC, Opn Stor Entrance, STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630 / Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each	FF-L-2740B Weather Resistant Enclosure	Gray
Section 08 71 00	1 each	Dummy Pair	630

		no SFIC	
Section 08 71 00	1 each	Strike Filler Plate	630
Section 08 71 00	1 each	48" Drip Ledge	MIL
Section 08 71 00	1 each	44" Bottom Sweep	MIL
	1 each	3870 Acoustical Gasket	Clear Anodized
	1 each	44" Automatic Door Bottom	Clear Anodized
	1 each	44" Rabbeted Threshold, J16300	MIL
Section 08 71 00	1 each	Floor Stop, L02131	626
Section 08 71 00	1 each	Power Supply	
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 120

HWS-A1.8 Not used

Door No. 225B
HWS-A1.9 BMS Exterior Entrance, STC 45

Section 08 71 00	4 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	FMC Closer, C02021	630
		parallel arm for mortise hinges,	
		STC 45 and less	
Section 08 71 00	1 each	Lever Storeroom, F86	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	48" Drip Ledge	MIL
	1 each	6070 Acoustical Gasket	Clear Anodized
	2 each	36" Automatic Door Bottom	Clear Anodized
	1 each	44" Rabbeted Threshold, J16300	MIL
Section 08 71 00	1 each	44" Bottom Sweep	MIL
Section 08 71 00	1 each	Floor Stop, L02131	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 120

Secure Non Rated STC Openings

Door No. 173A
HWS-A1.10 AC Suite Pair, STC 45

Section 08 71 00	5 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	2 each	FMC Closer, C02021	630
		parallel arm for mortise hinges,	
		STC 45 and less	
	Active Leaf RHR		
Section 08 71 00	1 each	Lever Storeroom, F86	630

Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	Flat Overlapping Astragal	630
Inactive Leaf LHR			
Section 08 71 00	1 each	Door Coordinator, Type 21	622
Section 08 71 00	1 each	Automatic Flush Bolt Set, Type 25	630
Section 08 71 00	1 each	Dust Proof Strike, L04021	626
	1 each	6070 Acoustical Gasket	Clear Anodized
	2 each	36" Automatic Door Bottom	Clear Anodized
	1 each	72" 3 Inch Saddle Threshold	MIL
Section 08 71 00	2 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	2 each	DPDT Balanced Magnetic Switch	MIL
GFGI	1 each	Electric Strike	630
GFGI	1 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Secure Comm 174

HWS-A1.11 Not used

Door No. 205A
HWS-A1.12 AC SCIF Mantrap I/S STC 55

	3 each	4.5 x 4.5 Cam Lift Hinge, A5141	630
Section 08 71 00	1 each	FMC Closer, C02011 flat form arm for cam hinges, more than STC 45	630
Section 08 71 00	1 each	Lever Storeroom, F86	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
	1 each	3070 Head and Jamb Gasket, R3L154, magnetic and neoprene seal	Clear Anodized
	1 each	3070 1.125 inch Spring Seal, R1K155	612
	1 each	36" Automatic Door Bottom, R3B3341	Clear Anodized
	1 each	36" Threshold, J16300	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
Section 08 71 00	1 each	Power Sequencer retract electric strike on Mantrap outside door only when Mantrap inside door is secured	
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	1 each	Electric Strike	630
GFGI	1 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway, pull strings and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 218

Door No. 101A, 103B
HWS-A1.13 B2BAC Opn Stor, STC 45

Section 08 71 00	2 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each Power Transfer	689
Section 08 71 00	1 each FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630 / Black
Section 08 71 00	1 each Rim Cylinder Housing, F26	630
Section 08 71 00	1 each 7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each Dummy Pair no SFIC	630
Section 08 71 00	1 each Strike Filler Plate	630
	1 each 3070 Acoustical Gasket	Clear Anodized
	1 each 36" Automatic Door Bottom	Clear Anodized
	1 each 36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 174

Door No. 112A
HWS-A1.14 AC Office STC 40

Section 08 71 00	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each Lever Storeroom, F86	630
Section 08 71 00	1 each 7 Pin SFIC, F24, E09241	630
	1 each 3070 Acoustical Gasket	Clear Anodized
	1 each 36" Automatic Door Bottom	Clear Anodized
	1 each 36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each Wall Stop, L02251 or Floor Stop, L02161	626
Section 08 71 00	1 each Power Supply	
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 174

Door No. 173B, 176A
HWS-A1.15 AC Conf, Classroom, Suite STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	Lever Storeroom, F86	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	1 each	Electric Strike	630
GFGI	1 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 174

Door No. 114A, 132A
HWS-A1.16 AC Conf, Classroom, Suite STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	Lever Storeroom, F86	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	1 each	Electric Strike	630
GFGI	1 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 120

Door No. 119A
HWS-A1.17 Mid Corridor STC 45

Section 08 71 00	4 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	Dummy Pair no cylinder	630

Section 08 71 00	1 each Strike Filler Plate	630
	1 each 3870 Acoustical Gasket	Clear Anodized
	1 each 44" Automatic Door Bottom	Clear Anodized
	1 each 44" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Access control equipment is located in Comm 120

Secure 45 Minute Rated, STC Openings

Door No. 164B
HWS-A1.18 B2B AC Op Stor Off, 45 Min, STC 45

Section 08 71 00	2 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each Power Transfer	689
Section 08 71 00	1 each FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630 / Black
Section 08 71 00	1 each Rim Cylinder Housing, F26	630
Section 08 71 00	1 each 7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each Dummy Pair no SFIC	630
Section 08 71 00	1 each Strike Filler Plate	630
	1 each 3070 Acoustical Gasket	Clear Anodized
	1 each 36" Automatic Door Bottom	Clear Anodized
	1 each 36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 174

Heavy Duty Non Rated, STC Openings

Door No. 103A, 106A, 107A
HWS-A1.19 Suite, Office, Conference STC 40

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	Lever Entry, F109	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 104A, 113B, 130A, 185A
HWS-A1.20 Suite, Office, Conference STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	Lever Entry, F109	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626

3.4.2 A2-1, CO BUILDING ACOUSTICAL HARDWARE SCHEDULE

Secure Exterior STC Openings

Door No. 104B, 153A
HWS-A2-1.5 B2BAC Entrance, STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	Lever Institution, F87	630
Section 08 71 00	2 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	Strike Filler Plate	630
Section 08 71 00	1 each	48" Drip Ledge	MIL
Section 08 71 00	1 each	44" Bottom Sweep	MIL
	1 each	3870 Acoustical Gasket	Clear Anodized
	1 each	44" Automatic Door Bottom	Clear Anodized
	1 each	44" Rabbeted Threshold, J16300	MIL
Section 08 71 00	1 each	Floor Stop, L02131	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	1 each	Electric Strike	630
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric

strike fails safe upon fire alarm notification

Note: Access control equipment is located in Communications 113

Secure Non Rated STC Openings

Door No. 104A
HWS-A2-1.6 B2BAC Mid Corridor, STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630/Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each	Dummy Pair no SFIC	630
Section 08 71 00	1 each	Strike Filler Plate	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 105A
HWS-A2-1.7 B2BAC Opn Stor, STC 45

Section 08 71 00	2 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630/Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each	Dummy Pair no SFIC	630
Section 08 71 00	1 each	Strike Filler Plate	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized

	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 110A, 114A, 118A, 122A, 126A, 156A, 160A, 164A, 168A, 172A, 176A
HWS-A2-1.8 B2BAC Opn Stor, STC 45

Section 08 71 00	2 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630/Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each	Dummy Pair no SFIC	630
Section 08 71 00	1 each	Strike Filler Plate	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Door No. 153B
HWS-A2-1.9 B2BAC Mid Corridor, STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	LMK10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630/Black

Section 08 71 00	1 each Rim Cylinder Housing, F26	630
Section 08 71 00	1 each 7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each Dummy Pair no SFIC	630
Section 08 71 00	1 each Strike Filler Plate	630
	1 each 3070 Acoustical Gasket	Clear Anodized
	1 each 36" Automatic Door Bottom	Clear Anodized
	1 each 36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Heavy Duty Non Rated, STC Openings

Door No. 106A, 180A
HWS-A2-1.10 Suite, Office, Conference STC 45

Section 08 71 00	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
Section 08 71 00	1 each FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each Lever Entry, F109	630
Section 08 71 00	1 each 7 Pin SFIC, F24, E09241	630
	1 each 3070 Acoustical Gasket	Clear Anodized
	1 each 36" Automatic Door Bottom	Clear Anodized
	1 each 36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each Wall Stop, L02251 or Floor Stop, L02161	626

3.4.3 A2-2, CO BUILDING ACOUSTICAL HARDWARE SCHEDULE

Secure Exterior STC Openings

Door No. 104B, 153A
HWS-A2-2.5 B2BAC Entrance, STC 45

Section 08 71 00	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each Lever Institution, F87	630
Section 08 71 00	2 each 7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each Strike Filler Plate	630
Section 08 71 00	1 each 48" Drip Ledge	MIL
Section 08 71 00	1 each 44" Bottom Sweep	MIL
	1 each 3870 Acoustical Gasket	Clear Anodized
	1 each 44" Automatic Door Bottom	Clear Anodized
	1 each 44" Rabbeted Threshold, J16300	MIL

Section 08 71 00	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Access control equipment is located in Communications 113

Secure Non Rated STC Openings

Door No. 104A

HWS-A2-2.6	B2BAC Mid Corridor, STC 45	
Section 08 71 00	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each Power Transfer	689
Section 08 71 00	1 each FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630/Black
Section 08 71 00	1 each Rim Cylinder Housing, F26	630
Section 08 71 00	1 each 7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each Dummy Pair no SFIC	630
Section 08 71 00	1 each Strike Filler Plate	630
	1 each 3070 Acoustical Gasket	Clear Anodized
	1 each 36" Automatic Door Bottom	Clear Anodized
	1 each 36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 105A

HWS-A2-2.7 B2BAC Opn Stor, STC 45		
Section 08 71 00	2 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each Power Transfer	689
Section 08 71 00	1 each FMC Closer, C02021 parallel arm for mortise hinges,	630

		STC 45 and less	
Section 08 71 00	1 each	LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630/Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each	Dummy Pair no SFIC	630
Section 08 71 00	1 each	Strike Filler Plate	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 110A, 114A, 118A, 122A, 126A, 156A, 160A, 164A, 168A, 172A, 176A
HWS-A2-2.8 B2BAC Opn Stor, STC 45

Section 08 71 00	2 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630/Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each	Dummy Pair no SFIC	630
Section 08 71 00	1 each	Strike Filler Plate	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Door No. 153B
HWS-A2-2.9 B2BAC Mid Corridor, STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
Section 08 71 00	1 each	BB ETW 4.5 x 4.5 Butt NRP, A5112	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	LKM10K Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630/Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
Section 08 71 00	1 each	Dummy Pair no SFIC	630
Section 08 71 00	1 each	Strike Filler Plate	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	2 each	Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Heavy Duty Non Rated, STC Openings

Door No. 106A, 180A
HWS-A2-2.10 Suite, Office, Conference STC 45

Section 08 71 00	3 each	BB 4.5 x 4.5 Butt Hinge, A5111	630
Section 08 71 00	1 each	FMC Closer, C02021 parallel arm for mortise hinges, STC 45 and less	630
Section 08 71 00	1 each	Lever Entry, F109	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
	1 each	3070 Acoustical Gasket	Clear Anodized
	1 each	36" Automatic Door Bottom	Clear Anodized
	1 each	36" 3 Inch Saddle Threshold	MIL
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 08 41 13

ALUMINUM-FRAMED ENTRANCES AND STOREFRONTS
08/18, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF45	(2003; Reaffirmed 2009) Designation System for Aluminum Finishes

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 800	(2016) Voluntary Specifications and Test Methods for Sealants
AAMA 1503	(2009) Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7-16	(2017; Errata 2018; Supp 1 2018) Minimum Design Loads and Associated Criteria for Buildings and Other Structures

ASTM INTERNATIONAL (ASTM)

ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM E283	(2019) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E330/E330M	(2014; R 2021) Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference
ASTM E783	(2002; R 2018) Standard Test Method for Field Measurement of Air Leakage Through Installed Exterior Windows and Doors
ASTM E1105	(2015; R 2023) Standard Test Method for Field Determination of Water Penetration of Installed Exterior Windows, Skylights,

	Doors, and Curtain Walls, by Uniform or Cyclic Static Air Pressure Difference
ASTM E1424	(1991; R 2016) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure and Temperature Differences Across the Specimen
ASTM E1886	(2019) Standard Test Method for Performance of Exterior Windows, Curtain Walls, Doors, and Impact Protective Systems Impacted by Missile(s) and Exposed to Cyclic Pressure Differentials
ASTM E1996	(2017) Standard Specification for Performance of Exterior Windows, Curtain Walls, Doors, and Impact Protective Systems Impacted by Windborne Debris in Hurricanes

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.10	(2017) Power Operated Pedestrian Doors

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2024) International Building Code

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS TT-P-645	(Rev C; Notice 1) Primer, Paint, Zinc-Molybdate, Alkyd Type

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation Drawings; G

Fabrication Drawings; G

SD-03 Product Data

Finish; G

Recycled Content of Aluminum Material; S

SD-06 Test Reports

Deflection

Air Infiltration

Condensation Resistance and Thermal Transmittance

Water Infiltration

SD-08 Manufacturer's Instructions

Manufacturer's Instructions

SD-11 Closeout Submittals

Manufacturer's Product Warranty

1.3 QUALITY CONTROL

1.3.1 Qualifications

1.3.1.1 Installer Qualifications

Provide documentation of the installer's experience in performing the work specified in this section.

Ensure that the installers are specialized in work similar to that required for this project, and that they are acceptable to product manufacturer.

1.3.1.2 Manufacturer Qualifications

Ensure that manufacturers meet the requirements specified in this section and project drawings.

Ensure that the manufacturer is capable of providing field service representation during construction, approving acceptable installers and approving application methods.

1.3.2 Single-Source Responsibility

When aluminum entrances are part of a building enclosure system, that includes storefront framing, windows, a curtain wall system, and related products, provide building enclosure system products from a single-source manufacturer.

Use a single source manufacturer with sole responsibility for providing design, structural engineering, and custom fabrication for door portal systems and for supplying components, materials, and products. Do not use products provided from numerous sources for assembly at the site. Ensure that the following work items and components are fabricated or supplied by a single source are:

a. Door assemblies.

b. Glazed walls.

c. Door operating hardware as scheduled. Appurenant items are specified and procured in Section 08 71 00 DOOR HARDWARE and conveyed to the glazing trade for installation.

d. Glass as specified in Section 08 81 00 GLAZING.

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 Ordering

To avoid construction delays, comply with the manufacturer's lead-time requirements and instructions for ordering.

1.4.2 Packing, Shipping, Handling and Unloading

Deliver materials in the manufacturer's original, unopened, undamaged containers with identification labels intact.

1.4.3 Storage and Protection

Store materials in a way that protects them from exposure to harmful weather conditions. Avoid damaging the storefront material and components during handling. Protect storefront material against damage from elements, construction activities, and other hazards before, during, and after storefront installation.

Do not use adhesive papers or sprayed coatings that become firmly bonded when exposed to sunlight. Do not leave coating residue on surfaces.

1.5 PROJECT / SITE CONDITIONS

1.5.1 Field Measurements

Verify actual measurements or openings by taking field measurements before fabrication; record these measurements on shop drawings. To avoid construction delays, coordinate field measurements, and fabrication schedule with construction progress.

1.6 WARRANTY

Provide a written manufacturer's warranty, executed by a company official, warranting against defects in materials and products for 2 years from the date of shipment. Warrant that the door corner construction is for the life of the project. Provide a written installer's warranty, warranting work to be watertight and free from defective materials, defective workmanship, and glass breakage as a result of defective design, and agreeing to replace components that fail within 2 years.

The warranty states the following:

a. Watertight and airtight system installation is completed within specified tolerances.

b. The completed installation remains free of rattles, wind whistles and noise caused by thermal movement and wind pressure.

c. System is structurally sound and free from distortion.

d. Glass and glazing gaskets will not break or "pop" from frames as a result of design, wind load pressure, movement caused by expansion or contraction, or structural loading.

e. Glazing sealants and gaskets remain free of abnormal deterioration or dislocation as a result of sunlight, weather, or oxidation.

Provide written warranty stating that the organic coating finish will not fade more than 10 percent or show chalking, yellowing, peeling, cracking, pitting, corroding or variations in color, or gloss deterioration beyond the manufacturer's descriptive standards for 20 years from the shipment date and agreeing to promptly correct defects.

Provide a written thermal integrity warranty for 2 years from ship date against thermal barrier system failure resulting from the following:

a. Longitudinal and transverse thermal barrier shrinkage.

b. Thermal barrier cracking.

c. Structural failure of the thermal barrier material.

d. Loss of adhesion or loss of prescribed edge pressure on glazing material, resulting in excessive air and water infiltration.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide aluminum entrances, with glass and glazing, door hardware, and components.

Aluminum entrances include impact resistance entrances; wide stile, 6 inch vertical face dimension, 1 3/4 inch depth, for interior structural silicone glaze, for high-traffic/impact-resistant applications.:

2.1.1 Design Requirements for Aluminum (Entrances and Components)

Provide a door portal system designed to withstand the following loads without breakage, loss, failure of seals, product deterioration, or other defects.

Submit a DELEGATED DESIGN with sealed calculations and shop drawings prepared by a registered professional engineer. Furnish storefront systems that resist stipulated loads. Assembly design responsibility is delegated to the Contractor and incorporates specific properties and structural capabilities of selected products and manufacturers.

Supplement delegated design shop drawings with storefront system structural computations. Tie general manufacturer data of appurtenant members utilized to project specific conditions. Specify fastening patterns and connections.

a. Dead and Live Loads: Determined by ASCE 7-16 and calculated in accordance with applicable codes.

b. Seismic Loads: Design and install the system to comply with the seismic requirements for the project location in accordance with Section 1613 of the International Building Code, ICC IBC.

c. Wind Loads: Design and install the system so that the effects of wind load acting inward and outward normal to the plane of the wall are in accordance with ASTM E330/E330M.

Marine Corps Base Camp Lejeune must resist a 144 mile per hour, ultimate design wind speed, 54 PSF, Risk Category II, Surface

Roughness Category C, Exposure Category C lateral load. Comply with UFC 3-301-01 and ASCE 7 as applicable for building system designs and components.

d. Thermal Loads And Movement:

(1) Ambient Temperature Range: 120 degrees F

(2) Material Surfaces Range: 180 degrees F

e. Water and Air Resistance: Provide weatherstripping, exterior gaskets, sealants, and other accessories to resist water and air penetration.

f. Impact-Protective Systems Provide an impact-protective system in accordance with ASTM E1886 and ASTM E1996.

2.1.1.1 Material Standard

ASTM B221; 6063-T5 alloy and tempered.

2.1.1.2 Recycled Content

Provide aluminum framed entrances and storefronts that have a minimum of 20 percent recycled content based upon the aluminum billet used in the original material. Provide data indicating percentage of recycled content of aluminum material.

2.1.1.3 Sealants

Provide either ethylene propylene diene monomer (EPDM) elastomeric extrusions or thermoplastic elastomer glazing gaskets. Structural silicone sealant is required.

Internal Sealants: Provide sealants that according to the manufacturer will remain permanently elastic, tacky, non-drying, non-migrating, and weather tight.

2.1.1.4 Thermal Barrier

Use a rigid, structural thermal barrier to separate all exterior aluminum from interior aluminum. For purposes of this specification, a structural thermal barrier is defined as a system that transfers shear during bending and, therefore, promotes composite action between the exterior and interior extrusions. Do not use a nonstructural thermal barrier. Ensure that the thermal barrier provides a structural connection between the two sides of the door.

2.2 FABRICATION

Provide the following information when submitting fabrication drawings for custom fabrications:

a. Indicate elevations, detailed design, dimensions, member profiles, joint locations, arrangement of units, and member connections.

b. Show the following items:

(1) Details of special shapes.

(2) Reinforcing.

(3) Anchorage system.

(4) Interfacing with building construction.

(5) Provisions for expansion and contraction.

(6) Thermal breaks.

c. Indicate typical glazing details, locations of various types and thickness of glass and internal sealant requirements as recommended by the sealant manufacturer.

d. Clearly indicate locations of exposed fasteners and joints.

e. Clearly show where and how the manufacturer's system deviates from Contract drawings and these specifications.

2.2.1 Entrance System Fabrication

Accurately fit and secure joints and corners. Make joints hairline in appearance. Remove burrs and smooth edges. Prepare components with internal reinforcement for door hardware. Arrange fasteners and attachments so that they are concealed from view.

Separate dissimilar metals with protective coating or pre-formed separators to prevent contact and corrosion.

2.2.2 Shop Assembly

Fabricate and assemble units with joints only at the intersection of aluminum members with hairline joints; rigidly secure these units, and seal them in accordance with the manufacturer's recommendations.

2.2.2.1 Welding

Conceal welds on aluminum members in accordance with AWS recommendations or methods recommended by the manufacturer. Members showing welding bloom or discoloration on finish or material distortion will be rejected by the Contacting Officer.

2.2.3 Finish

Before fabrication, clean the units and give them a AA-M-10-C22-A42 (color) anodized finish in accordance with the requirements of the AA DAF45.

Give aluminum extrusions for heavy commercial applications a pretreatment to enhance adhesion followed by a caustic etch or alkaline wash for cleaning and degreasing. Apply a phosphate spray or chromate conversion treatment to protect against humidity and corrosive chemicals. Furnish an organic coating treatment conforming to AAMA 2605 to obtain a 70% PVDF coating. Provide a two coat application consisting of 0.2 mils of primer with a 1.0 mil topcoat that achieves a 1.2 mil thickness.

Aluminum storefront is slate gray as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC.

2.2.4 Fabrication Tolerance

Fabricate and assemble units with joints only at intersection of aluminum members with hairline joints; rigidly secure these units, and seal them in accordance with the manufacturer's recommendations.

Fabricate aluminum entrances in accordance with the entrance manufacturer's prescribed tolerances.

2.2.4.1 Material Cuts

Square to 1/32 inch off square, over largest dimension; proportionate amount of 1/32 inch on the two dimensions.

2.2.4.2 Maximum Offset at Consecutive Members

1/64 inch in alignment between two consecutive members in line, end to end.

2.2.4.3 Maximum Offset at Glazing Pocket Corners

1/64 inch between framing members at glazing pocket corners.

2.2.4.4 Joints

Between adjacent members in same assembly: Joints are hairline and square to the adjacent member.

2.2.4.5 Variation

In squaring diagonals for doors and fabricated assemblies: 1/16 inch.

2.2.4.6 Flatness

For doors and fabricated assemblies: plus/minus 1/16 inch of neutral plane.

2.3 MATERIALS

2.3.1 Sealants

Refer to Section 07 92 00 JOINT SEALANTS. Ensure that all sealants conform to AAMA 800.

2.3.2 Glass

Refer to Section 08 81 00 GLAZING.

2.4 ACCESSORIES

2.4.1 Fasteners

Provide stainless steel fasteners colored to match substrates encountered in areas where the fasteners are exposed.

Use non-corrosive and compatible fasteners with components being fastened. Do not use exposed fasteners, except where unavoidable for application of hardware.

In areas where fasteners are not exposed, use aluminum, non-magnetic stainless steel, or other materials warranted by the manufacturer.

For exposed locations, provide countersunk Phillips head screws when items with a matching finish are fastened. For concealed locations, provide the manufacturer's standard fasteners.

Provide nuts or washers that have been designed with a means to prevent disengagement; do not deform fastener threads.

2.4.2 Perimeter Anchors

When steel anchors are used, provide insulation between steel material and aluminum material to prevent galvanic action.

2.4.2.1 Inserts and Anchorage Devices

Provide manufacturer's standard formed or fabricated assemblies, steel or aluminum, of shapes, plates, bars, or tubes. Shop-coat steel assemblies after fabrication with an alkyd zinc chromate primer complying with FS TT-P-645.

PART 3 EXECUTION

3.1 EXAMINATION

3.1.1 Site Verification of Conditions

Verify that the condition of substrate previously installed under other sections is acceptable for product installation in accordance with the manufacturer's instructions.

Verify that openings are sized to receive the storefront system and that the sill plate is level in accordance with the manufacturer's acceptable tolerances.

3.2 PREPARATION

Field-verify dimensions before fabricating components for the door portal assembly.

Coordinate the erection of door portal with installation of surrounding glass wall and door assemblies. Ensure that the door portals can provide support and anchorage for assembly components.

Coordinate electrical requirements for doors to ensure proper power source, conduit, wiring, and boxes.

3.2.1 Adjacent Surfaces Protection

Protect adjacent work areas and finish surfaces from damage during product installation.

3.2.2 Aluminum Surface Protection

Protect aluminum surfaces from contact with lime, mortar, cement, acids, and other harmful contaminants.

3.3 INSTALLATION

Submit installation drawings for review and approval.

Install the entrance system in accordance with the manufacturer's instructions and the AAMA storefront and entrance guide specifications manual. Attach the entrance system to the structure, allowing it to be adjusted to accommodate construction tolerances and other irregularities. Provide alignment attachments and shims to permanently fasten the system to the building structure. Align the assembly so that it is plumb and level, and free of warp and twist. Maintain assembly dimensional tolerances aligning with adjacent work.

3.3.1 Tolerances

Ensure that tolerances for wall thickness and other cross-sectional dimensions of entrance members are nominal and in compliance with Aluminum Standards and Data, published by the Aluminum Association.

3.3.2 Related Products Installation Requirements

3.3.2.1 Sealants (Perimeter)

Refer to Section 07 92 00 JOINT SEALANTS.

3.3.2.2 Glass

Refer to Section 08 81 00 GLAZING.

3.4 FIELD QUALITY CONTROL

3.4.1 Air Infiltration

Test air infiltration in accordance with ASTM E783

Submit certified test reports showing compliance with specified performance characteristics as follows:

a. For single-acting offset pivot, butt hung, or continuous geared hinge entrances in the closed and locked position, test the specimen in accordance with ANSI/BHMA A156.10, and ASTM E283 at a pressure differential of 1.57 psf for pairs of doors; ensure that maximum infiltration for a pair of 7 foot by 8 foot entrance doors and frame is 1.2 cfm/square foot.

b. Ensure the maximum allowable infiltration for a completed storefront system does not exceed 0.06 cfm/square foot when tested in accordance with ASTM E1424 at a differential static pressure of 6.24 psf.

3.4.2 Wind Loads

Provide a completed storefront system capable of withstanding wind pressure loads, normal to the wall plane indicated, as follows:

a. Exterior Walls

(1) Positive Pressure: 54 psf

(2) Negative Pressure: 54 psf

3.4.3 Deflection

Submit certified test reports showing that the maximum allowable deflection in a member when tested in accordance with ASTM E330/E330M with allowable stress is L/175 or 3/4 inches maximum.

3.4.4 Condensation Resistance and Thermal Transmittance

Submit certified test reports showing compliance with specified performance characteristics as follows:

a. U-Value Requirements:

(1) Perform test in accordance with the AAMA 1503 procedure and on the configuration specified therein.

(2) Thermal Transmittance ("U" Value) maximum 0.65 (6250) BTU/hr/sf/deg F at 15 mph exterior wind.

b. CRF Class Requirements:

(1) Perform a test in accordance with AAMA 1503.

(2) Condensation Resistance Factor Requirements (CRF) minimum 60.

3.4.5 Water Infiltration

Submit certified test reports showing that the system is designed to provide no uncontrolled water when tested in accordance with ASTM E1105 at a static pressure of 8 psf.

3.5 ADJUSTING AND CLEANING

3.5.1 Field Testing

Perform water penetration field testing in accordance with ASTM E1105 to assure that the specified water penetration resistance properties are met.

3.5.2 Protection

Protect the installed product's finish surfaces from damage during construction. Protect the aluminum storefront system from damage from grinding and polishing compounds, plaster, lime, acid, cement, or other harmful contaminants.

3.5.3 Cleaning

Repair or replace damaged installed products. Clean installed products in accordance with manufacturer's instructions before acceptance remove excess mastic, mastic smears, and other foreign materials. Remove construction debris from the project site and legally dispose of this debris.

3.6 WARRANTY

Submit 3 signed copies of the manufacturer's product warranty for the entrance system as follows:

a. Stipulate warranty periods as stated in paragraphs describing WARRANTY

in Part 1 above.

Ensure that the Warranty's language is identical to the "As Approved" version of the sample warranty submitted to and returned from the Contracting Officer.

-- End of Section --

SECTION 08 41 60

TRANSLUCENT FIBERGLASS WALLS
12/22

PART 1 GENERAL

1.1 SCOPE

Provide labor, material, equipment and services necessary for, and reasonably incidental to, furnishing and installing aluminum framing work indicated within the Instruments of Service. Incorporate related accessories and specialties to accomplish a complete and proper installation. Coordinate and schedule this work with the work of other trades to ultimately provide superior workmanship in the finished product.

Unless otherwise so qualified, engage a competent glazing trade having five years of experience with work of a similar type, scope and scale to perform this installation.

Standards as specified by the AAMA and AA govern the work, as applicable.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA/WDMA/CSA 101/I.S.2/A440	(2017) North American Fenestration Standard/Specification for Windows, Doors, and Skylights
AAMA 503	(2014) Field Testing of Newly Installed Storefronts, Curtain Walls, and Sloped Glazing Systems
AAMA 800	(2016) Voluntary Specifications and Test Methods for Sealants
AAMA 1503	(2009) Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections
AAMA 2605	(2022) Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI 300	Ref Title

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7	(2017) Minimum Design Loads for Buildings and Other Structures

ASTM INTERNATIONAL (ASTM)

ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B456	(2017) Standard Specification for Electrodeposited Coatings of Copper Plus Nickel Plus Chromium and Nickel Plus Chromium
ASTM B633	(2019) Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel
ASTM C297/C297M	(2016) Flatwise Tensile Strength of Sandwich Constructions
ASTM C509	(2006; R 2021) Standard Specifiaction for Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM C864	(2005; R 2015) Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers
ASTM C1199	(2014) Standard Test Method For Measuring The Steady-State Thermal Transmittance Of Fenestration Systems Using Hot Box Methods
ASTM C1363	(2019) Standard Test Method for Thermal Performance of Building Materials and Envelope Assemblies by Means of a Hot Box Apparatus
ASTM D572	(2004; R 2019) Rubber Deterioration by Heat and Oxygen
ASTM D635	(2018) Standard Test Method for Rate of Burning and/or Extent and Time of Burning of Plastics in a Horizontal Position
ASTM D1002	(2010; R 2019) Apparent Shear Strength of Single-Lap-Joint Adhesively Bonded Metal Specimens by Tension Loading (Metal-to-Metal)
ASTM D1037	(2012) Evaluating Properties of Wood-Base Fiber and Particle Panel Materials
ASTM D2244	(2016) Standard Practice for Calculation of Color Tolerances and Color Differences from Instrumentally Measured Color Coordinates
ASTM E72	(2022) Conducting Strength Tests of Panels for Building Construction

ASTM E283	(2019) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen
ASTM E331	(2000; R 2023) Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference
ASTM E783	(2002; R 2018) Standard Test Method for Field Measurement of Air Leakage Through Installed Exterior Windows and Doors
ASTM E972	(2021) Standard Test Method for Solar Photometric Transmittance of Sheet Materials Using Sunlight
ASTM E1105	(2015; R 2023) Standard Test Method for Field Determination of Water Penetration of Installed Exterior Windows, Skylights, Doors, and Curtain Walls, by Uniform or Cyclic Static Air Pressure Difference
ASTM E1423	2021) Standard Practice for Determining Steady State Thermal Transmittance of Fenestration Systems

UL SOLUTIONS (UL)

UL 723	(2018; Reprint Jun 2025) UL Standard for Safety Test for Surface Burning Characteristics of Building Materials

1.3 SUBMITTALS

Submit certificates of compliance, manufacturer product information and shop drawings.

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Delegated Design

Furnish translucent fiberglass wall systems that resist uplift and lateral loads. Marine Corps Base Camp Lejeune must resist a 144 mile per hour, ultimate design wind speed, 54 PSF, Risk Category II, Surface Roughness Category C, Exposure Category C lateral load. Comply with UFC 3-301-01, NCSBC and ASCE 7 as applicable for building system designs and components.

Assembly design responsibility is delegated to the Contractor and incorporates specific properties and structural capabilities of selected products and manufacturers.

Supplement delegated design shop drawings with translucent fiberglass wall system structural computations. Tie general manufacturer data of appurtenant members utilized to project specific conditions. Specify fastening patterns and connections.

SD-03 Product Data

Wall Framing; G

Fiberglass Panels; G

Color; G

SD-04 Samples

Samples; G

Furnish two samples of each selected color that is representative of the installation.

SD-05 Design Data

Wall Framing; G

Fiberglass Panels; G

SD-06 Test Reports

Third Party Material Testing; G

Certification Reports; G

Furnish independent, third party material testing and certification reports indicating that the manufacturer is listed by a recognized building code authority, including the ICBO, which requires quality control inspections and testing by approved agencies for fire, structural and water infiltration performance for translucent fiberglass walls.

SD-07 Certificates

Certificates Of Compliance; G

SD-10 Operation and Maintenance Data; G

Maintenance; G

SD-11 Closeout Submittals

Warranty; G

1.4 WARRANTY

Furnish the standard 2 year warranty of the manufacturer. Coverage is to ensure that translucent fiberglass wall framing is free of water infiltration resulting from manufacturing defects in product design, material and workmanship.

Furnish the standard 2 year warranty of the manufacturer. Coverage is to ensure that translucent fiberglass wall framing finishes do not peel, crack or chalk.

Furnish the standard 10 year warranty of the manufacturer. Coverage is to ensure that translucent fiberglass face sheets retain a stable color and maintain panel bonding integrity.

Furnish the standard 25 year warranty of the manufacturer. Coverage is to ensure that exterior face sheet weathering does not expose fiber reinforcing.

Guarantee translucent fiberglass wall framing for a period of 2 years against leakage and against defects due to faulty installation, workmanship and contract negligence.

1.5 MAINTENANCE

Submit the recommended maintenance practices for each type of installation provided.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Wall Framing

Manufacture aluminum systems in accordance with AAMA/WDMA/CSA 101/I.S.2/A440.

Wall fabrications are prefinished aluminum sheet and extrusions with a heavy commercial finish conforming to per ASTM B221 and AAMA 2605.

The maximum translucent fiberglass wall water penetration rate is 0.0 at a water test pressure of 15.00 PSF at 5.00 gallon hours per square foot in accordance with ASTM E331. The maximum air leakage rate is 0.01 CFM per square foot at 1.56 PSF and 0.01 CFM per square foot at 6.24 PSF in accordance with ASTM E283.

Translucent fiberglass wall parameters are as follows:

1. Wind load: 54 PSF
2. Drift load: 10 PSF
3. Maximum deflection: L/45

Framing, batten and perimeter closures receive sandwich panel assemblies consisting of clamp tight, screw closures of extruded 6063 T5 and 6063 T6 alloy and temper aluminum members with thicknesses in the range of 0.064 inch, 14 gauge to 0.081 inch, 12 gauge as dictated by delegated design. Aluminum sheets and extrusions alloy and temper are determined by fabrication and assembly properties required. Aluminum profiles specified are the minimum cross sections to be provided. Increase cross sections to resist lateral loadings and achieve required heights and spans. Perimeter member closures incorporate a prefabricated thermal break. Sealing tape is factory applied to the serrated edges of closures under controlled conditions. Products employing non structural thermal barriers are not acceptable. Configure sill flashings for the conditions encountered.

Assemble members creating flush, weathertight, hairline joints. Make square cuts. Assemble square intersections. Conceal welds in accordance

with AWS methods. Provide assemblies, components and accessories to accomplish a watertight installation.

Concealed fasteners are zinc plated steel or hardened aluminum alloys. Exposed fasteners are AISI 300 stainless steel. Metal rivets are stainless steel. Select other fastener alloys that do not create electrolysis with substrates. Finish exposed rivets and fasteners to match substrate colors encountered. Provide fastener thread types and lengths suited for substrates encountered.

Anchors, clips and accessories are aluminum or stainless steel complying with ASTM B633 for SC 3 severe service conditions. Reinforcing members are aluminum or stainless steel complying with ASTM B456 for SC 3 severe service conditions. Provide 0.050 inch, 16 gauge aluminum sill flashing with end dams and three point attachments for weathertightness.

Sealants fabricated within extrusions are permanently elastic, non shrinking and non migrating types complying with AAMA 800.

Gaskets are dry glazed elastomers complying with ASTM C509 or marine wrap around EPDM types complying with ASTM C864. Metal gaskets lock securely into glazing reglets and have beveled profiles with finishes matching the substrate of attachment. Internal frame air sealants are silicone in accordance with AAMA 800.

Provide positive drainage to unit exteriors via frame weep slots protected by hooded cover or integral drips.

Spray polyurethane foam is closed cell. Weathertight sealant is silicone.

2.1.2 Fiberglass Panels

Assemble and seal translucent fiberglass panels in the factory.

Translucent fiberglass wall panel composites have a NFRC laboratory tested U-value of 0.15 in accordance with ASTM C1363, ASTM E1423 and ASTM C1199. Panels have a light transmission value of 35% when tested in accordance with ASTM E972, and a SHGC of 0.10. The panel composite thickness is 4.0 inches.

Wall panel fabrications must deflect no more than 1 inch at 30 PSF in 10 feet when tested in accordance with ASTM E72.

Translucent fiberglass panels consist of two face sheets, bonded with a laminate adhesive that is set by heat and pressure to an aluminum grid core. Panel assemblies are flat, and the grid core consists of mechanically interlocked and thermally broken aluminum I beams. Translucent fiberglass panels are designed for architectural applications.

Manufacture face sheets from glass fiber reinforced thermoset resins. Thermoplastic faces such as polycarbonate and acrylic resins are not permitted. Interior face sheets comply with UL 723 and have a flame spread rating no greater than 50 and a smoke developed rating no greater than 300. Burn extent when tested in accordance with ASTM D635 is no greater than 1 inch. Faces do not deform, deflect, drip when subjected to fire or flame, or become detached when subjected to 300 F temperature for one hour. The full thickness of exterior face sheets do not change color more than 3.0 Hunter or CIE Units Delta E as measured by ASTM D2244 after five years of outdoor South Florida weathering at 5 degrees facing south.

Color weatherability is determined by the average of at least three white samples with and without a protective film or coating to insure maximum, long term color stability. Exterior faces have a permanent glass veil erosion barrier integrally embedded to provide maximum long term resistance to fiber exposure. Alternative plastic surface films, coatings or veils are not acceptable unless warranted as an erosion barrier. Exterior face sheets are smooth, 0.070 inches in thickness and interior face sheets are 0.045 inches in thickness. Faces vary less than 10% from the specified thickness and are uniform in color. Face sheets withstand an impact equal to 60 foot pounds without fracture or tear when tested with a free falling, 3.5 inch diameter, 6.37 pound sphere.

The grid core is 6063 T6 or 6005 T5 alloy and temper aluminum with provisions for mechanical interlocking of the muntins to mullions and perimeter members. The gird pattern is symmetrical along the horizontal centerline of each panel. Core members that have high and low intersections that do not allow for continuous, full contact bonding of the face sheets to both sides of each member are not permitted. The width of I beam members is no less than 0.4375 inches, and the grid members created are machined within a 0.002 inches tolerance. The grid core composite is thermally broken with a CRF 80 on the grid line as measured by AAMA 1503. Panels withstand a 1,200 F fire for one hour without collapse or exterior flaming.

Laminate adhesive is a heat and pressure resin type engineered for structural sandwich panel use, and has a twenty-five year record of successful use in the field. The adhesive passes ICBO Acceptable Criteria for Sandwich Panel Adhesives testing requirements. Adhesive bonding lines are straight, cover the entire width of the I beam and have neat, sharp edges. White spots at muntin and mullion intersections do not exceed four occurrences for each 40 square feet of panel, nor are they more than 0.0469 inches in width. Adhesive has a 750 PSI tensile strength in compliance with ASTM C297/C297M following two exposures to six cycles each of aging conditions prescribed by ASTM D1037. Adhesive shear strength is as follows:

Description	Shear Strength	Reference
50% RH at 73 degrees F	540 PSI	ASTM D1002
182 F	100 PSI	ASTM D1002
Accelerated aging at room temperature	800 PSI	ASTM D1002 and ASTM D1037
Accelerated aging at 182 F	250 PSI	ASTM D1002 and ASTM D1037
500 hour oxygen bomb	1,400 PSI	ASTM D1002 and ASTM D572

2.1.3 Color

Wall framing is slate gray as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC.

Give aluminum extrusions for heavy commercial applications a pretreatment to enhance adhesion followed by a caustic etch or alkaline wash for cleaning and degreasing. Apply a phosphate spray or chromate conversion treatment to protect against humidity and corrosive chemicals. Furnish an organic coating treatment conforming to AAMA 2605 to obtain a 70% PVDF coating. Provide a two coat application consisting of 0.2 mils of primer with a 1.0 mil topcoat that achieves a 1.2 mil thickness.

Furnish two samples of each selected color that is representative of the installation.

2.1.4 Accessories

Furnish fasteners, accessories and options as recommended by the manufacturer for the specific applications and substrates encountered within the work.

PART 3 INSTALLATION

3.1 DELEGATED DESIGN

Prepare a Delegated Design for translucent fiberglass wall framing systems.

3.1.1 Execution

Protect aluminum components in cartons or crates during transit and storage. Abide by recommended handling and treatment procedures. Protect exposed surfaces from grinding swarf, abrasive compounds, plaster, lime, acid, cement and other damaging contaminants.

Ship translucent fiberglass panels in rugged containers. Store panels on long edges, several inches above the ground with block separators and under weatherproof covering. Do not field fabricate or field modify panels.

Protect aluminum in contact with dissimilar metals, concrete, masonry and pressure treated blocking from galvanic action and corrosion. Apply a bituminous coating to contact surfaces or separate incongruent materials with sealant, tape or nylon pads. Isolate steel anchors and assembly accessories from aluminum components. Seat sill flashings in sealant beds and seal fastener heads to make weathertight.

Position weep holes and install members to convey water to aluminum framing exteriors. Field install aluminum battens and cap plates. Clean members before applying sealants.

Apply weathertight sealant at inside and outside perimeters of exterior openings.

Field measure to determine sizing, making due allowances for edge clearances.

Confirm that materials are compatible with aluminum components. Confirm that composite sealants are compatible with gaskets. Use matching resilient elastomeric gaskets on frame pocket insides and outsides. Gaskets for panel composites are similar.

Confirm that opening sizes, squareness and corner offsets are acceptable to receive panel composites. Verify face and edge clearances of delivered panels. Conduct work at temperatures above 40 F. Examine channel surfaces, rabbets, backing and removable stops for proper fitting.

Secure translucent fiberglass panel composites into place. Make accommodations for thermal and mechanical movement.

3.1.2 Testing and Certificates

Perform testing is in accordance with AAMA 503. Air infiltration cannot exceed 1.5 times the amount indicated in performance specifications or 0.09 CFM per square foot as measured by ASTM E783. Uncontrolled water infiltration is not permitted when tested at two thirds the specified water penetration static pressure, but not less than 6.24 PSF in accordance with ASTM E1105.

Furnish independent, third party material testing and certification reports indicating that the manufacturer is listed by a recognized building code authority, including the ICBO, which requires quality control inspections and testing by approved agencies for fire, structural and water infiltration performance for translucent fiberglass walls.

3.1.3 Cleaning

Clean interior and exterior face sheets following installation.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 08 71 00

DOOR HARDWARE
02/16, CHG 4: 02/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E283	(2019) Standard Test Method for Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.1	(2021) Butts and Hinges
ANSI/BHMA A156.2	(2017) Bored and Preassembled Locks and Latches
ANSI/BHMA A156.3	(2020) Exit Devices
ANSI/BHMA A156.4	(2013) Door Controls - Closers
ANSI/BHMA A156.5	(2020) Cylinder and Input Devices for Locks
ANSI/BHMA A156.6	(2021) Architectural Door Trim
ANSI/BHMA A156.7	(2016) Template Hinge Dimensions
ANSI/BHMA A156.8	(2021) Door Controls - Overhead Stops and Holders
ANSI/BHMA A156.13	(2022) Mortise Locks & Latches Series 1000
ANSI/BHMA A156.16	(2018) Auxiliary Hardware
ANSI/BHMA A156.18	(2020) Materials and Finishes
ANSI/BHMA A156.21	(2019) Thresholds
ANSI/BHMA A156.22	(2021) Gasketing
ANSI/BHMA A156.24	(2012) Delayed Egress Locking Systems
ANSI/BHMA A156.25	(2013) Electrified Locking Devices
ANSI/BHMA A156.36	(2010) Auxiliary Locks

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 72	(2025; TIA 25-1; TIA 25-2; TIA 25-3; TIA 25-4; ERTA 25-1; ERTA 25-2) National Fire Alarm and Signaling Code
NFPA 80	(2025) Standard for Fire Doors and Other Opening Protectives
NFPA 101	(2024) Life Safety Code
NFPA 252	(2022) Standard Methods of Fire Tests of Door Assemblies

STEEL DOOR INSTITUTE (SDI/DOOR)

SDI/DOOR A250.8	(2017) Specifications for Standard Steel Doors and Frames

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191	Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines

UL SOLUTIONS (UL)

UL Bld Mat Dir	(updated continuously online) Building Materials Directory

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Manufacturer's Detail Drawings; G

Verification of Existing Conditions; G

Hardware Schedule; G

Keying System; G

SD-03 Product Data

Hardware Items; G

SD-08 Manufacturer's Instructions

Installation

SD-10 Operation and Maintenance Data

Hardware Schedule Items, Data Package 1; G

SD-11 Closeout Submittals

Key Bitting

1.3 SHOP DRAWINGS

Submit manufacturer's detail drawings indicating all hardware assembly components and interface with adjacent construction. Indicate power components and wiring coordination for electrified hardware. Base shop drawings on verified field measurements and include verification of existing conditions.

1.4 PRODUCT DATA

Indicate fire-ratings at applicable components. Provide documentation of ABA/ADA accessibility compliance of applicable components, as required by 36 CFR 1191 Appendix D - Technical.

1.5 HARDWARE SCHEDULE

Provide Hardware Item List and Hardware Schedule containing the following information, and additional information as needed to identify the complete make up of each hardware set and its application to each opening:

1.5.1 Hardware Item List:

a. Hardware Type

b. Item Number

c. Quantity

d. Size(s)

e. Reference Publication / Type Number

f. Manufacturer's Name / Catalog Number

g. Key Control Symbols

h. UL Mark (If fire rated and listed)

i. BHMA Finish(es)

j. Remarks

1.5.2 Hardware Schedule

a. Hardware Set Number

b. Opening Number(s)

c. Opening Description (single/double leaf, hand, size, door/frame material)

d. Fire Rating

e. Sound Rating

f. Hardware Items

g. Quantity

h. Size

i. BHMA Finish

j. Remarks

In addition, submit hardware schedule data package 1 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.6 KEY BITTING CHART REQUIREMENTS

1.6.1 Requirements

Submit key bitting charts to the Contracting Officer prior to completion of the work. Include:

a. Complete listing of all keys (e.g. AA1 and AA2).

b. Complete listing of all key cuts (AA1-123456, AA2-123458).

c. Tabulation showing which key fits which door.

d. Copy of floor plan showing doors and door numbers.

e. Listing of 20 percent more key cuts than are presently required in each master system.

1.7 QUALITY ASSURANCE

1.7.1 Hardware Manufacturers and Modifications

Provide, as far as feasible, locks, hinges and closers of one lock, hinge or closer manufacturer's make. Modify hardware as necessary to provide features indicated or specified.

1.7.2 Key Shop Drawings Coordination Meeting

Prior to the submission of the key shop drawing, the Contracting Officer, Contractor, Door Hardware Subcontractor, using Activity and Base Locksmith must meet to discuss and coordinate key requirements for the facility. Confirm keyways utilized and provide compatible cylinders and cores. Confirm hardware set components and functions.

Procure cut sheets for GFGI hardware from the Government. Coordinate GFGI hardware items with furnished hardware items indicated in applicable hardware sets. Provide single sourced, high security lock eqress hardware

items as stipulated in Paragraph 2.3.6.2. Use templates to prepare doors and frames for GFGI hardware selections.

1.8 DELIVERY, STORAGE, AND HANDLING

Deliver hardware in original individual containers, complete with necessary appurtenances including fasteners and instructions. Mark each individual container with item number as shown on hardware schedule. Deliver permanent keys and removable cores to the Contracting Officer, either directly or by certified mail. Deliver construction master keys with the locks.

PART 2 PRODUCTS

2.1 TEMPLATE HARDWARE

Hardware applied to doors must be manufactured using a template. Provide templates to door and frame manufacturers in accordance with ANSI/BHMA A156.7 for template hinges. Coordinate hardware items to prevent interference with other hardware.

2.2 HARDWARE FOR FIRE DOORS AND EXIT DOORS

Provide all hardware necessary to meet the requirements of NFPA 72 for door alarms, NFPA 80 for fire doors, NFPA 101 for exit doors, NFPA 252 for fire tests of door assemblies, ABA/ADA accessibility requirements, and all other requirements indicated, even if such hardware is not specifically mentioned in paragraph HARDWARE SCHEDULE. Provide Underwriters Laboratories, Inc. labels for such hardware in accordance with UL Bld Mat Dir or equivalent labels in accordance with another testing laboratory approved in writing by the Contracting Officer.

2.3 HARDWARE ITEMS

Clearly and permanently mark with the manufacturer's name or trademark, hinges, locks, latches, exit devices, bolts and closers where the identifying mark is visible after the item is installed. For closers with covers, the name or trademark may be beneath the cover. Coordinate electrified door hardware components with corresponding components provided.

2.3.1 Hinges

Provide in accordance with ANSI/BHMA A156.1. Provide hinges that are 4-1/2 by 4-1/2 inch unless otherwise indicated. Construct loose pin hinges for interior doors and reverse-bevel exterior doors so that pins are non-removable when door is closed. Other anti-friction bearing hinges may be provided in lieu of ball bearing hinges.

2.3.2 Locks and Latches

a. At exterior locations provide locksets of full stainless steel type 302 or 304 construction including fronts, strike, escutcheons, knobs, bolts and all interior working parts. Marine Grade I, fully non-ferrous.

b. In non-air-conditioned interior environments or humid interior environments, provide interior locksets on the same Marine Grade I, fully non-ferrous as exterior locksets.

2.3.2.1 Bored Locks and Latches

Provide in accordance with ANSI/BHMA A156.2, Series 4000, Grade 1.

2.3.2.2 Auxiliary Locks

Provide in accordance with ANSI/BHMA A156.36, Grade 1.

2.3.3 Exit Devices

Provide in accordance with ANSI/BHMA A156.3, Grade 1. Provide adjustable strikes for rim type and vertical rod devices. Provide open back strikes for pairs of doors with mortise and vertical rod devices. Provide touch bars in lieu of conventional crossbars and arms. Provide escutcheons not less than 7 by 2-1/4 inch.

Use stainless steel or bronze base metal with stainless steel finishes. Also include stainless steel fasteners and screws.

2.3.4 Cylinders and Cores

Provide cylinders and cores for new locks, including locks provided under other sections of this specification. Provide cylinders and cores with seven pin tumblers. Provide cylinders from the products of one manufacturer, and provide cores from the products of one manufacturer. Rim cylinders, mortise cylinders, and levers of bored locksets have interchangeable cores which are removable by special control keys. Stamp each interchangeable core with a key control symbol in a concealed place on the core.

2.3.5 Electrified Hardware

Comply with the requirements of NFPA 70 for wiring of electrified hardware.

2.3.5.1 High Security Lock Egress Hardware

Combination electromechanical lock conforms to Style 1, FF-L-2740B. When combined with single motion egress hardware, electromechanical locks are used to secure open storage spaces. Locks have an internal power source using electromechanical technology. Three levels of combinations are possible: Single mode has 1 million combinations; Dual mode has 500 billion combinations; and Supervisor/Subordinate has 2 million combinations. The direct dial does not need to be cleared before entering a combination. Once the dial stops turning, power shuts down after 40 seconds. Memory is non volatile. A backlit LCD function provides a limited view of displayed information. Combinations are changed by entering the correct code or serial number in combination with the mechanical change key. Features include a true scramble, random number view, no day locking and no back dialing. Locks automatically reset when the bolt is thrown or 40 seconds after turning stops. Assemblies fail secure when subjected to manipulation by high voltage, robot, X-ray, magnetic, vibration and radio frequency attack methods. A non resettable audit function records each lock opening. Unsuccessful combinations are also recorded after three incorrect attempts, where the audit function resets after a correct opening. Ten to fourteen combination errors result in a three minute timeout. Fifteen or more errors result in a four minute timeout. Both the error count and penalty time reset upon receipt of a valid combination. Pedestrian door deadbolt applications have four strike configurations, a deadbolt base plate on the inside door face and a dial

ring mounting plate on the outside door face. Open storage electromechanical lock is Series CDX-10 Type 1F High Security Electronic Lock as manufactured by www.dormakaba.com.

Electromechanical Lock	Performance	Standard
Case and bolt strength, two directions	600 pounds	
Operating temperature range	-10 to 155 F	FF-L-2740B
Electromagnetic pulse, high altitude nuclear blast	Passes	FF-L-2740B
Cycle test	Passes	FF-L-2740B
Humidity, 10 days, 86 to140 F @ 98% RH	Passes	MIL-STD-810, Method 507.3, Procedure III
Vibration	Passes	MIL-STD-810
Salt spray, 72 hours of exposure	Operational	UL 768
Stress chamber, 7 days, 194 F	Passes	UL 768

Single motion egress hardware conforms to FF-L-2890C and accepts FF-L-2740B high security locks. Type II locks are for access control system integration. The combination lock provides the first level of security. The electrified lock and access control provides the second level of security. The key override function bypasses the access control device in the event of power loss or equipment malfunction. The key override function does not bypass the combination lock. Locks are non handed, have four strike configurations and are rated for 90 minutes. Hardware has three tier monitoring. A deadbolt switch monitors the request to exit device. A combination lock switch monitors the combination lock bolt. An entry switch monitors the lever handle. Access control integration hardware is Series LKM10K, Type II as manufactured by Lockmasters, Incorporated, www.lockmasters.com.

Provide in accordance with ANSI/BHMA A156.25, Grade 1. Provide facility interface devices that use dc power to energize solenoids. Provide solenoids, resisters, and signal switches in accordance with paragraph ELECTRIC STRIKES AND FRAME MOUNTED ACTUATORS.

2.3.5.1.1 Power Transfer Hinges

Provide electric through wire butt hinges with the appropriate number of power transfer wires to operate connected hardware items. Certify hinges for 3.5 Amps continuous duty usage and 16.0 Amps for intermittent duty usage.

Power transfers have steel housings and flexible tubes that bring power from doors to frames. The narrow, shallow channel accepts up to 0.3125 inch diameter wire bundle and easily mortises into door edges. Transfers flex to accommodate up to 120 degree door swings.

Provide power transfer hinges with each electrified lock that route power and monitoring signals from the lockset to the door frame. Coordinate power transfer hinges with door frames.

2.3.5.2 Card Readers and Keypad Access Control Hardware

Card readers, keypad access contols and similar electrified hardware items are furnished and installed by the Government. Reference the various hardware schedules for GFGI items.

2.3.5.3 Delayed Egress Locking System

Provide in accordance with ANSI/BHMA A156.24, Grade 1.

2.3.6 Keying System

Provide an extension of the existing keying system. Existing locks were manufactured by Best, www.bestaccess.com and have interchangeable cores. Provide construction interchangeable cores. Provide key cabinet as specified. Provide SFIC Series 7 pin, TB Keyway as manufactured by Best, www.bestaccess.com. Coordinate with the Camp Lejeune Base Locksmith to resolve keying, procurement, shipping and installation procedures.

2.3.7 Lock Trim

Provide cast, forged, or heavy wrought construction and commercial plain design for lock trim.

2.3.7.1 Lever Handles

Provide lever handles. Provide in accordance with ANSI/BHMA A156.3 for mortise locks of lever handles for exit devices. Provide lever handle locks with a breakaway feature (such as a weakened spindle or a shear key) to prevent irreparable damage to the lock when force in excess of that specified in ANSI/BHMA A156.13 is applied to the lever handle. Provide lever handles return to within 1/2 inch of the door face.

2.3.8 Keys

Furnish one file key, one duplicate key, and one working key for each key change and for each master keying system. Furnish one additional working key for each lock of each keyed-alike group. Furnish great grand master keys, construction master keys, and control keys for removable cores. Furnish a quantity of key blanks equal to 20 percent of the total number of file keys. Stamp each key with appropriate key control symbol and "U.S. property - do not duplicate." Do not place room number on keys.

2.3.9 Door Bolts

Provide in accordance with ANSI/BHMA A156.16. Provide dustproof strikes for bottom bolts. Provide automatic latching flush bolts in accordance with ANSI/BHMA A156.3, Type 25.

2.3.10 Closers

Provide in accordance with ANSI/BHMA A156.4, Series C02000, Grade 1, with PT 4C. Provide with brackets, arms, mounting devices, fasteners, full metal covers and other features necessary for the particular application. Size closers in accordance with manufacturer's printed recommendations, or provide multi-size closers, Sizes 1 through 6, and list sizes in the Hardware Schedule. Provide manufacturer's 10 year warranty.

Use stainless steel inside bracketed or door mounted closers on exterior doors. Non-ferrous closers, such as aluminum or cast bronze, are permissible where door utilization is minimal. On interior doors use closers of 302 or 304 stainless steel or non-ferrous materials. On surface-mounted closers use or apply rust inhibiting finish on all ferrous parts. Also apply this finish on concealed closers.

2.3.10.1 Closer

Non handed, surface applied door closers are UL listed and comply with ANSI/BHMA A156.4, Grade 1. Closers comply with barrier free accessibility requirements. Units have spring power and backcheck positioning adjustments. The backcheck function prevents uncontrolled door opening by automatically adjusting resistance in proportion to door opening speeds. Resistance is unnoticeable for slowly opened doors; however, the backcheck fully engages when doors are opened forcefully. Two separate temperature sensing, non critical adjustment valves control sweep and latch closing speeds. A parallel arm by flat form type is typical unless substrates encountered require otherwise. Maximum door opening ranges from 100 degrees to 180 degrees depending on arm configuration. Closers have a full metal cover.

2.3.10.2 Track Arm Closer

Non handed, surface applied, track arm door closers are UL listed and comply with ANSI/BHMA A156.4, Grade 1. Closers comply with barrier free accessibility requirements. Closers have steel cams, rollers and adjustable spring combined with track arm assemblies. Units have hydraulic delayed action, spring power and backcheck positioning adjustments. Hold open functions are adjustable for opening degree and force. Spring stop track arms assist in door stopping and opening degree is field selectable. Two separate temperature sensing, non critical adjustment valves control sweep and latch closing speeds. Maximum door opening ranges from 110 degrees to 175 degrees depending on arm configuration.

2.3.10.3 Door Closer and Coordinator

Surface applied door closer and coordinators have two separate temperature compensating, non critical adjustment valves to control sweep and latch closing speeds. An adjustable hydraulic backcheck is effective from a 65 degree door position. Adjustable delayed action is effective from 125 through 70 degree door positions. The closer is a field adjustable, spring powered size complying with barrier free opening force requirements. The coordinator mechanism controls sequential closing for pairs of doors.

2.3.10.4 Identification Marking

Engrave each closer with manufacturer's name or trademark, date of manufacture, and manufacturer's size designation in locations that will be visible after installation.

2.3.11 Overhead Holders

Provide in accordance with ANSI/BHMA A156.8.

Overhead door holders have a stop function limiting the degree of door swing while providing a cushioned stop, and a slot screw operated hold open function. Holders comply with ANSI A156.8, Grade 1. Extruded track channels are aluminum, slide blocks are solid brass and steel arms are zinc plated. A soffit plate and parallel arm bracket link power transfer between doors and frames. Door openings are held in 5 degree increments ranging from 85 degrees through 110 degrees of swing.

2.3.12 Door Protection Plates

Provide in accordance with ANSI/BHMA A156.6.

Push, pull, kick and mop plates are 0.050 inches in thickness with square corners, four beveled edges and countersunk screw holes.

2.3.12.1 Sizes of Mop and Kick Plates

2 inch less than door width for single doors; 1 inch less than door width for pairs of doors. Provide 8 inch kick plates for flush doors. Provide 4 inch mop plates.

2.3.13 Door Stops and Silencers

Provide in accordance with ANSI/BHMA A156.16. Silencers Type L03011. Provide three silencers for each single door, two for each pair.

2.3.14 Thresholds

Provide in accordance with ANSI/BHMA A156.21. Use J35100, with vinyl or silicone rubber insert in face of stop, for exterior doors opening out, unless specified otherwise.

2.3.15 Weatherstripping Gasketing

Provide in accordance with ANSI/BHMA A156.22. Provide the type and function designation where specified in paragraph HARDWARE SCHEDULE. Provide a set to include head and jamb seals, sweep strips, and, for pairs of doors, astragals. Air leakage of weatherstripped doors not to exceed 1.25 cubic feet per minute of air per square foot of door area when tested in accordance with ASTM E283. Provide weatherstripping with one of the following:

2.3.15.1 Extruded Aluminum Retainers

Extruded aluminum retainers not less than 0.050 inch wall thickness with vinyl, neoprene, silicone rubber, or polyurethane inserts. Provide clear (natural) anodized aluminum.

2.3.15.2 Interlocking Type

Zinc or bronze not less than 0.018 inch thick.

2.3.15.3 Spring Tension Type

Spring bronze or stainless steel not less than 0.008 inch thick.

2.3.16 Rain Drips

Provide in accordance with ANSI/BHMA A156.22. Provide extruded aluminum rain drips, not less than 0.08 inch thick, clear anodized finish. Provide rain drips with a 2 inch overlap on each side of each exterior door that is not protected by an awning, roof, eave or other horizontal projection. Set drips in sealant and fasten with stainless steel screws.

2.3.16.1 Overhead Rain Drips

Approximately 1-1/2 inch high by 2-1/2 inch projection. Align bottom with

door frame rabbet.

2.3.17 Auxiliary Hardware (Other than locks)

Provide in accordance with ANSI/BHMA A156.16, Grade 1.

2.3.18 Special Tools

Provide special tools, such as spanner and socket wrenches and dogging keys, as required to service and adjust hardware items.

2.4 FASTENERS

Provide fasteners of type, quality, size, and quantity appropriate to the specific application. Fastener finish to match hardware. Provide stainless steel or nonferrous metal fasteners in locations exposed to weather. Verify metals in contact with one another are compatible and will avoid galvanic corrosion when exposed to weather.

2.5 FINISHES

Provide in accordance with ANSI/BHMA A156.18. Provide hardware in BHMA 630 finish (satin stainless steel), unless specified otherwise. Provide hinges in stainless steel with BHMA 630 finish. Furnish exit devices in BHMA 630 finish. Match exposed parts of concealed closers to lock and door trim. Match hardware finish for aluminum doors to the doors.

2.6 KEY CABINET AND CONTROL SYSTEM

Provide in accordance with ANSI/BHMA A156.5, Type required to yield a capacity (number of hooks) 50 percent greater than the number of key changes used for door locks.

PART 3 EXECUTION

3.1 INSTALLATION

Provide hardware in accordance with manufacturers' printed installation instructions. Fasten hardware to wood surfaces with full-threaded wood screws or sheet metal screws. Provide machine screws set in expansion shields for fastening hardware to solid concrete and masonry surfaces. Provide toggle bolts where required for fastening to hollow core construction. Provide through bolts where necessary for satisfactory installation.

3.1.1 Electrified Hardware

3.1.1.1 High Security Lock Operations

Gain entry to doors with single motion egress hardware for high security locks by first dialing in the combination until the high security lock bolt is retracted. The dial will come to a dead stop.

Egress hardware is locked until a badge or PIN is accepted. A green light above the key cylinder illuminates to give a visual indication that the lever trim is released. Visual activation illumination is not available for rated components. Rotate the trim to retract the egress hardware latch bolt and open the door. The egress hardware latch bolt will engage when the door closes.

Secure doors with single motion egress hardware by spinning off the for high security combination lock. The key override cannot function until the combination lock bolt is retracted.

3.1.1.2 Access Control Bypass

Gain entry to doors with single motion egress hardware for high security locks by first dialing in the combination until the high security lock bolt is retracted. The dial will come to a dead stop.

Egress hardware remains locked until the key is inserted into the key override cylinder. Turn the key in either direction to release the lever trim. Rotate the trim to retract the egress hardware latch bolt and open the door. Remove the key once the door is open, and the egress hardware latch bolt engages when the door closes. The key override acts as a manual access control function.

3.1.2 Weatherstripping Installation

Provide full contact, weathertight seals that allow operation of doors without binding the weatherstripping.

3.1.2.1 Stop Applied Weatherstripping

Fasten in place with color matched sheet metal screws not more than 9 inch on center after doors and frames have been finish painted.

3.1.2.2 Interlocking Type Weatherstripping

Provide interlocking, self adjusting type on heads and jambs and flexible hook type at sills. Nail weatherstripping to door 1 inch on center and to heads and jambs at 4 inch on center.

3.1.2.3 Spring Tension Type Weatherstripping

Provide spring tension type on heads and jambs. Provide bronze nails with bronze. Provide stainless steel nails with stainless steel. Space nails not more than 1-1/2 inch on center.

3.1.3 Threshold Installation

Extend thresholds the full width of the opening and notch end for jamb stops. Set thresholds in a full bed of sealant and anchor to floor with cadmium-plated, countersunk, steel screws in expansion sleeves. For aluminum thresholds placed on top of concrete surfaces, coat the underside surfaces that are in contact with the concrete with fluid applied waterproofing as a separation measure prior to placement.

3.2 FIRE DOORS AND EXIT DOORS

Provide hardware in accordance with NFPA 72 for door alarms, NFPA 80 for fire doors, NFPA 101 for exit doors, and NFPA 252 for fire tests of door assemblies.

3.3 HARDWARE LOCATIONS

Provide in accordance with SDI/DOOR A250.8, unless indicated or specified otherwise.

a. Kick Plates: Push side of single-acting doors. Both sides of double-acting doors.

b. Mop Plates: Bottom flush with bottom of door.

3.4 KEY CABINET AND CONTROL SYSTEM

Locate where directed. Tag one set of file keys and one set of duplicate keys. Place other keys in appropriately marked envelopes, or tag each key. Provide complete instructions for setup and use of key control system. On tags and envelopes, indicate door and room numbers or master or grand master key.

3.5 FIELD QUALITY CONTROL

After installation, protect hardware from paint, stains, blemishes, and other damage until acceptance of work. Submit notice of testing 15 days before scheduled, so that testing can be witnessed by the Contracting Officer. Adjust hinges, locks, latches, bolts, holders, closers, and other items to operate properly. Demonstrate that permanent keys operate respective locks, and give keys to the Contracting Officer. Correct, repair, and finish, errors in cutting and fitting and damage to adjoining work.

3.6 HARDWARE SETS

Provide selected hardware items in other sections under this section. Deliver Hardware templates and hardware, except field applied hardware, to the door and frame manufacturers for use in fabricating doors and frames.

3.6.1 LOCATION OF HARDWARE SETS

Location of Hardware Sets	A1 HWS	A2-1 HWS
Section 08 11 16	A1.1-A1.2	A2-1.1-A2-1.2
Section 08 33 23	A1.3-A1.4	A2-1.3-A2-1.4
Section 08 34 73	A1.5-A1.20	A2-1.5-A2-1.10
Section 08 71 00	A1.21-A1.46	A2-1.11-A2-1.30
Section 10 22 13	A1.47-A1.48	
Section 13 47 00	A1.49-A1.50	

Location of Hardware Sets	A2-2 HWS	A3 HWS
Section 08 11 16	A2-2.1-A2-2.2	
Section 08 33 23	A2-2.3-A2-2.4	A3.1
Section 08 34 73	A2-2.5-A2-2.10	
Section 08 71 00	A2-2.11-A2-2.30	A3.2-A3.11
Section 10 22 13	A2-2.31-A2-2.32	A3.12

AC = Access Control; B2B = Back to Back; BB = Ball Bearing; ETW = Electric Through Wire; FMC = Full Metal Cover; GFGI = Government Furnished, Government Installed; HD = Heavy Duty; MIL = Mill Finished Aluminum; NRP = Non Removable Pin; LHR = Left Hand Reverse; RHR = Right Hand Reverse; SFIC = Small Format Interchangeable Core; TPE = Thermoplastic Elastomer

3.6.2 DOOR HARDWARE SCHEDULE

3.6.2.1 A1, BATALLION HEADQUARTERS DOOR HARDWARE SCHEDULE

Secure Exterior Openings

Door No. 192A, 192D, 193A, 194A, 194B
HWS-A1.21 AC Entrance

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 52" Drip Ledge	MIL
	1 each 4070 Weatherstrip	MIL
	1 each 48" Bottom Sweep	MIL
	1 each 48" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 199

Heavy Duty Exterior Openings

Door No. 178A
HWS-A1.22 Exterior Electrical>800 Amps Pair

	6 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	2 each Overhead Door Holder, C02511 stop mounted slide track arm, push side mount	626
	Active Leaf RHR	
	1 each Exit Device w/ Pull, EDF03 entry by keyed trim, public use by dogged bar	630
Best	1 each Rim Cylinder Housing, F26	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Section 08 11 13	1 each Flat Overlapping Astragal	Galvanealed
	Inactive Leaf LHR	
	2 each 12" Lever Ext Flush Bolt, L14251	626
	1 each Dust Proof Strike, L04021	626
	1 each 76" Drip Ledge	MIL
	1 each 6070 Weatherstrip	MIL
	2 each 36" Bottom Sweep	MIL
	1 each 72" Threshold, J35100	MIL
	2 each Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 193C
HWS-A1.23 Exterior Entrance

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm push side mount	630
	1 each Lever Entry, F109	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 52" Drip Ledge	MIL
	1 each 4070 Weatherstrip	MIL
	1 each 48" Bottom Sweep	MIL
	1 each 48" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626

Door No. 177A, 203A, 219A
HWS-A1.24 Exterior Elec/Mech/Tel Com

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each Overhead Door Holder, C02511 stop mounted slide track arm, push side mount	626
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 48" Drip Ledge	MIL
	1 each 3870 Weatherstrip	MIL
	1 each 44" Bottom Sweep	MIL
	1 each 44" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 158B
HWS-A1.25 Exterior Egress

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm push side mount	630
	1 each Lever Egress, F111	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626

Secure Interior Openings

Door No. 199A
HWS-A1.26 B2BAC Opn Stor Comm

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
Kaba Mas	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Verify a requirement for a High Security Lockset for Combination Electromechanical Lock Egress

Note: Access control equipment is located in Comm 199

Door No. 174A
HWS-A1.27 B2BAC Opn Stor Comm

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
Kaba Mas	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Verify a requirement for a High Security Lockset for Combination Electromechanical Lock Egress

Note: Access control equipment is located in Comm 174

Door No. 120A
HWS-A1.28 B2BAC Opn Stor Comm

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
Kaba Mas	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Verify a requirement for a High Security Lockset for Combination Electromechanical Lock Egress

Note: Access control equipment is located in Comm 120

Door No. 218A
HWS-A1.29 B2BAC Opn Stor Comm

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
Kaba Mas	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Verify a requirement for a High Security Lockset for Combination Electromechanical Lock Egress

Note: Access control equipment is located in Comm 218

Door No. 122A
HWS-A1.30 B2BAC Opn Stor Office, Suite

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Access control equipment is located in Comm 120

Door No. 121A, 122B, 127A, 147A, 149A
HWS-A1.31 AC Suite, Office

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 120

Door No. 110A, 164A, 170A, 180A, 188A
HWS-A1.32 AC Suite, Office

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 174

Door No. 200A, 201A
HWS-A1.33 AC Suite, Office

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630

	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 199

Heavy Duty Non Rated Openings

Door No. 215A, 227A
HWS-A1.34 Elec/Mech/Tel Com

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 155A, 157A
HWS-A1.35 Gang Head

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Strike Filler Plate	600
	1 each 4 x 16 Beveled Push Plate, J301	630
	1 each 4 x 16 Beveled Pull Plate, J405	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 102A, 115A, 146A, 169A, 195A, 196A, 197A, 198A, 220A, 221A
HWS-A1.36 Head, Unixex

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Privacy, F76A no SFIC	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 148A, 222A
HWS-A1.37 Janitor

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630

Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
	1 each Lever Door Holder, L01381	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 226A
HWS-A1.38 Wellness

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Privacy, F76A no SFIC	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 105A, 116A, 117A, 118A, 124A, 125A, 126A, 129A, 131A, 134A, 135A, 137A, 138A, 139A, 140A, 141A, 150A, 151A, 152A, 153A, 161A, 165A, 166A, 167A, 171A, 172A, 181A, 182A, 183A, 184A, 186A, 187A, 190A, 191A, 207A, 208A, 209A, 210A, 214A, 224A
HWS-A1.39 Suite, Office

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Entry, F109	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 154A, 163A, 168A, 189A, 211A
HWS-A1.40 Conference, Team, Breakout

	3 each BB1199 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Passage, F75 no SFIC	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 123A, 128A, 136A, 212A, 213A, 223A
HWS-A1.41 Storage, File

	3 each BB9 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 133A, 142A, 143A, 144A, 145A
HWS-A1.42 Exam

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Passage, F75 630 no SFIC	
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Heavy Duty Smoke Rated Openings

Door No. 111A
HWS-A1.43 Duty, Sleeping, Smoke, 20 Minutes

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Passage, F75 no SFIC	630
Section 08 14 00	1 each Category A Edge Seal, UL 10C	
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Heavy Duty 45 Minute Rated Openings

Door No. 204A
HWS-A1.44 Mech Pair, 45 Min Rating

	6 each BB1199 4.5 x 4.5 Butt Hinge, A5111	630
	2 each 8916 x AF89P FMC Closer, C02021	630
	1 each 2040 Door Coordinator, Type 21 stop mounted	622
Active Leaf RHR		
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Inactive Leaf LHR		
Section 08 11 13	1 each Flat Overlapping Astragal	Primed Steel
	1 each Constant Latching Bolt Set, Type 27	630
	1 each Dust Proof Strike, L04021	626
	2 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 6070 Category B Edge Seal, UL 10C	Charcoal
	2 each Wall Stop, L02251 or Floor Stop, L02161	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Sitework

HWS-A1.45 Cantilever Gate

	1 each Motorized Gate Control	
GFGI	2 each Card Reader, Pedestal Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Confirm GFGI access control equipment location

Note: Locks fail secure

Note: Provide a 2 inch square, steel tube pedestal with 70% PVDF finish and NEMA 4 enclosure to accommodate card reader equipment. Mount one card reader and pedestal that is driver side accessible on each side of the gate

Note: Quantity of 3

Sitework

HWS-A1.46 Single Turnstile

Turnstile	1 each Turnstile Control	
GFGI	2 each Card Reader, Turnstile Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Confirm GFGI access control equipment location

Note: Locks fail secure

Note: Provide NEMA 4 enclosures to accommodate card reader equipment outside the building footprint

Note: Quantity of 2

3.6.2.2 A2-1, CO BUILDING DOOR HARDWARE SCHEDULE

Secure Exterior Openings

Door No. 130D
HWS-A2-1.11 AC Entrance

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 46" Drip Ledge	MIL
	1 each 3670 Weatherstrip	MIL
	1 each 42" Bottom Sweep	MIL
	1 each 42" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 144D
HWS-A2-1.12 AC Entrance

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Lever Storeroom, F86	630

Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 46" Drip Ledge	MIL
	1 each 3670 Weatherstrip	MIL
	1 each 42" Bottom Sweep	MIL
	1 each 42" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Door No. 132A, 133B, 134A, 135C, 136A
HWS-A2-1.13 AC Entrance

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 147B, 148A, 148B, 150A, 151C
HWS-A2-1.14 AC Entrance

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Heavy Duty Exterior Openings

Door No. 141A
HWS-A2-1.15 Exterior Electrical>800 Amps Pair

	6 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	2 each	Overhead Door Holder, C02511	626
		stop mounted slide track arm, push side mount	
Active Leaf RHR			
	1 each	Exit Device w/ Pull, EDF03	630
		entry by keyed trim,	
		public use by dogged bar	
Best	1 each	Rim Cylinder Housing, F26	630
Best	1 each	7 Pin SFIC, F24, E09241	630
Section 08 11 13	1 each	Flat Overlapping Astragal	Galvanealed
Inactive Leaf LHR			
	2 each	12" Lever Ext Flush Bolt, L14251	626
	1 each	Dust Proof Strike, L04021	626
	1 each	76" Drip Ledge	MIL
	1 each	6070 Weatherstrip	MIL
	2 each	36" Bottom Sweep	MIL
	1 each	72" Threshold, J35100	MIL
	2 each	Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 142B
HWS-A2-1.16 Exterior Elec/Mech/Tel Com

	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each	Overhead Door Holder, C02511	626
		stop mounted slide track arm, push side mount	
	1 each	Lever Storeroom, F86	630
Best	1 each	7 Pin SFIC, F24, E09241	630
	1 each	40" Drip Ledge	MIL
	1 each	3070 Weatherstrip	MIL
	1 each	36" Bottom Sweep	MIL
	1 each	36" Threshold, J35100	MIL
	1 each	Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Secure Interior Openings

Door No. 113A
HWS-A2-1.17 B2BAC Opn Stor Comm

	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each	FMC Closer, C02021	630
Kaba Mas	1 each	CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray

	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Verify a requirement for a High Security Lockset for Combination Electromechanical Lock Egress

Note: Access control equipment is located in Comm 113

Door No. 175A
HWS-A2-1.18 B2BAC Opn Stor Comm

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
Kaba Mas	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Verify a requirement for a High Security Lockset for Combination Electromechanical Lock Egress

Note: Access control equipment is located in Comm 175

Door No. 132C, 133C, 134B, 135B, 136B
HWS-A2-1.19 AC Team, Suite, Office

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630

Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 147C, 148C, 149C, 150C, 151B
HWS-A2-1.20 AC Team, Suite, Office

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Secure 45 Minute Rated Openings

Door No. 130A, 130B, 130C
HWS-A2-1.21 AC Team, 45 Min Rating

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Section 08 14 00	1 each Category A Edge Seal, UL 10C	
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 144A, 144B, 144C
HWS-A2-1.22 AC Team, 45 Min Rating

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Section 08 14 00	1 each Category A Edge Seal, UL 10C	
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices
Note: Access control equipment is located in Comm 175

Heavy Duty Non Rated Openings

Door No. 142A, 143A, 152A
HWS-A2-1.23 Elec/Mech/Tel Com

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 138A, 139A, 145A, 155A
HWS-A2-1.24 Gang Head

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Strike Filler Plate	600
	1 each 4 x 16 Beveled Push Plate, J301	630
	1 each 4 x 16 Beveled Pull Plate, J405	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 182A
HWS-A2-1.25 Head, Unisex

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Privacy, F76A no SFIC	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 140A, 154A
HWS-A2-1.26 Janitor

	4 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
	1 each Lever Door Holder, L01381	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 103A
HWS-A2-1.27 Wellness

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Privacy, F76A no SFIC	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 105B, 107A, 108A, 109A, 111A, 112A, 115A, 116A, 117A, 119A, 120A, 121A, 123A, 124A, 125A, 127A, 128A, 129A, 157A, 158A, 159A, 161A, 162A, 163A, 165A, 166A, 167A, 169A, 170A, 171A, 173A, 174A, 176B, 177A, 178A, 179A
HWS-A2-1.28 Suite, Office

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Entry, F109	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Heavy Duty 45 Minute Rated Openings

Door No. 181A
HWS-A2-1.29 Mech Pair, 45 Min Rating

	6 each BB1199 4.5 x 4.5 Butt Hinge, A5111	630
	2 each 8916 x AF89P FMC Closer, C02021	630
	1 each 2040 Door Coordinator, Type 21 stop mounted	622
Active Leaf RHR		
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Inactive Leaf LHR		
Section 08 11 13	1 each Flat Overlapping Astragal	Primed Steel
	1 each Constant Latching Bolt Set, Type 27	630
	1 each Dust Proof Strike, L04021	626
	2 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 6070 Category B Edge Seal, UL 10C	Charcoal
	2 each Wall Stop, L02251 or Floor Stop, L02161	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Sitework

HWS-A2-1.30 Turnstile	Double Turnstile 2 each Turnstile Control	
Section 08 71 00	1 each Power Supply	
GFGI	4 each Card Reader, Turnstile Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Confirm GFGI access control equipment location

Note: Locks fail secure

Note: Provide NEMA 4 enclosures to accommodate card reader equipment outside the building footprint

Note: Quantity of 1

3.6.2.3 A2-2, CO BUILDING DOOR HARDWARE SCHEDULE

Secure Exterior Openings

Door No. 130D
HWS-A2-2.11 AC Entrance

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 46" Drip Ledge	MIL
	1 each 3670 Weatherstrip	MIL
	1 each 42" Bottom Sweep	MIL
	1 each 42" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 144D
HWS-A2-2.12 AC Entrance

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with	630

	spring stop, stop mounted slide track arm, push side mount	
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 46" Drip Ledge	MIL
	1 each 3670 Weatherstrip	MIL
	1 each 42" Bottom Sweep	MIL
	1 each 42" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Door No. 132A, 133B, 134A, 135C, 136A
HWS-A2-2.13 AC Entrance

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 147B, 148A, 148B, 150A, 151C
HWS-A2-2.14 AC Entrance

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626

GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Heavy Duty Exterior Openings

Door No. 141A
HWS-A2-2.15 Exterior Electrical>800 Amps Pair

	6 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	2 each Overhead Door Holder, C02511 stop mounted slide track arm, push side mount	626
Active Leaf RHR		
	1 each Exit Device w/ Pull, EDF03 entry by keyed trim, public use by dogged bar	630
Best	1 each Rim Cylinder Housing, F26	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Section 08 11 13	1 each Flat Overlapping Astragal	Galvanealed
Inactive Leaf LHR		
	2 each 12" Lever Ext Flush Bolt, L14251	626
	1 each Dust Proof Strike, L04021	626
	1 each 76" Drip Ledge	MIL
	1 each 6070 Weatherstrip	MIL
	2 each 36" Bottom Sweep	MIL
	1 each 72" Threshold, J35100	MIL
	2 each Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 142B
HWS-A2-2.16 Exterior Elec/Mech/Tel Com

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each Overhead Door Holder, C02511 stop mounted slide track arm, push side mount	626
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Secure Interior Openings

Door No. 113A
HWS-A2-2.17 B2BAC Opn Stor Comm

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
Kaba Mas	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Verify a requirement for a High Security Lockset for Combination Electromechanical Lock Egress

Note: Access control equipment is located in Comm 113

Door No. 175A
HWS-A2-2.18 B2BAC Opn Stor Comm

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
Kaba Mas	1 each CDX-10 Type 1F High Security Electronic Lock, Style 1, FF-L-2740B	Gray
	1 each Dummy Pair no SFIC	630
	1 each Strike Filler Plate	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Verify a requirement for a High Security Lockset for Combination Electromechanical Lock Egress

Note: Access control equipment is located in Comm 175

Door No. 132C, 133C, 134B, 135B, 136B

HWS-A2-2.19 AC Team, Suite, Office

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 147C, 148C, 149C, 150C, 151B
HWS-A2-2.20 AC Team, Suite, Office

	4 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Secure 45 Minute Rated Openings

Door No. 130A, 130B, 130C
HWS-A2-2.21 AC Team, 45 Min Rating

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Section 08 14 00	1 each Category A Edge Seal, UL 10C	
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 113

Door No. 144A, 144B, 144C
HWS-A2-2.22 AC Team, 45 Min Rating

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Section 08 14 00	1 each Category A Edge Seal, UL 10C	
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	1 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 175

Heavy Duty Non Rated Openings

Door No. 142A, 143A, 152A
HWS-A2-2.23 Elec/Mech/Tel Com

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 138A, 139A, 145A, 155A
HWS-A2-2.24 Gang Head

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Strike Filler Plate	600
	1 each 4 x 16 Beveled Push Plate, J301	630
	1 each 4 x 16 Beveled Pull Plate, J405	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 182A
HWS-A2-2.25 Head, Unisex

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Privacy, F76A no SFIC	630

	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 140A, 154A
HWS-A2-2.26 Janitor

	4 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
	1 each Lever Door Holder, L01381	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 103A
HWS-A2-2.27 Wellness

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Privacy, F76A no SFIC	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 105B, 107A, 108A, 109A, 111A, 112A, 115A, 116A, 117A, 119A, 120A, 121A, 123A, 124A, 125A, 127A, 128A, 129A, 157A, 158A, 159A, 161A, 162A, 163A, 165A, 166A, 167A, 169A, 170A, 171A, 173A, 174A, 176B, 177A, 178A, 179A
HWS-A2-2.28 Suite, Office

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Entry, F109	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Heavy Duty 45 Minute Rated Openings

Door No. 181A
HWS-A2-2.29 Mech Pair, 45 Min Rating

	6 each BB1199 4.5 x 4.5 Butt Hinge, A5111	630
	2 each 8916 x AF89P FMC Closer, C02021	630
	1 each 2040 Door Coordinator, Type 21 stop mounted	622
Active Leaf RHR		
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Inactive Leaf LHR		
Section 08 11 13	1 each Flat Overlapping Astragal	Primed Steel
	1 each Constant Latching Bolt Set, Type 27	630
	1 each Dust Proof Strike, L04021	626

	2 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 6070 Category B Edge Seal, UL 10C	Charcoal
	2 each Wall Stop, L02251 or Floor Stop, L02161	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Sitework

HWS-A2-2.30 Cantilever Gate

	1 each Motorized Gate Control	
Section 08 71 00	1 each Power Supply	
GFGI	2 each Card Reader, Pedestal Mounted	Black

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed deviceS

Note: Confirm GFGI access control equipment location

Note: Locks fail secure

Note: Provide a 2 inch square, steel tube pedestal with 70% PVDF finish and NEMA 4 enclosure to accommodate card reader equipment. Mount one card reader and pedestal that is driver side accessible on each side of the gate

Note: Quantity of 1

3.6.2.4 A3 CO STORAGE DOOR HARDWARE SCHEDULE

Secure Exterior Openings

Door No. 101D, 108D
HWS-A3.2 B2BAC Opn Stor

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each FMC Closer, C02231 with spring stop, stop mounted slide track arm, push side mount	630
	1 each Dummy Pair no SFIC	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL
GFGI	1 each Electric Strike	630
GFGI	2 each Card Reader, Wall Mounted	Black

Note: Furnish electric metallic tubing raceway to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Integrate the hardware set with fire alarm equipment. Electric strike fails safe upon fire alarm notification

Note: Access control equipment is located in Comm 113

Heavy Duty Exterior Openings

Door No. 112A
HWS-A3.3 Exterior Elec/Mech/Tel Com Pair

	6 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	2 each	Overhead Door Holder, C02511 stop mounted slide track arm, push side mount	626
Active Leaf RHR			
	1 each	Lever Storeroom, F86	630
Best	1 each	7 Pin SFIC, F24, E09241	630
Section 08 11 13	1 each	Flat Overlapping Astragal	Galvanealed
Inactive Leaf LHR			
	2 each	12" Lever Ext Flush Bolt, L14251	626
	1 each	Dust Proof Strike, L04021	626
	1 each	76" Drip Ledge	MIL
	1 each	6070 Weatherstrip	MIL
	2 each	36" Bottom Sweep	MIL
	1 each	72" Threshold, J35100	MIL
	2 each	Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 111A
HWS-A3.4 Exterior Electrical>800 Amps Pair

	6 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	2 each	Overhead Door Holder, C02511 stop mounted slide track arm, push side mount	626
Active Leaf RHR			
	1 each	Exit Device w/ Pull, EDF03 entry by keyed trim, public use by dogged bar	630
Best	1 each	Rim Cylinder Housing, F26	630
Best	1 each	7 Pin SFIC, F24, E09241	630
Section 08 11 13	1 each	Flat Overlapping Astragal	Galvanealed
Inactive Leaf LHR			
	2 each	12" Lever Ext Flush Bolt, L14251	626
	1 each	Dust Proof Strike, L04021	626
	1 each	76" Drip Ledge	MIL
	1 each	6070 Weatherstrip	MIL
	2 each	36" Bottom Sweep	MIL
	1 each	72" Threshold, J35100	MIL
	2 each	Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 101A, 101B, 101C, 101F, 101G, 108A, 108B
HWS-A3.5 Entrance

	3 each	BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each	FMC Closer, C02231 with	630

	spring stop, stop mounted slide track arm push side mount	
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626

Door No. 109A
HWS-A3.6 Exterior Elec/Mech/Tel Com

	3 each BB 4.5 x 4.5 Butt Hinge, NRP, A5111	630
	1 each Overhead Door Holder, C02511 stop mounted slide track arm, push side mount	626
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 40" Drip Ledge	MIL
	1 each 3070 Weatherstrip	MIL
	1 each 36" Bottom Sweep	MIL
	1 each 36" Threshold, J35100	MIL
	1 each Floor Stop, L02131	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Heavy Duty Non Rated Openings

Door No. 110A
HWS-A3.7 Elec/Mech/Tel Com Pair

	6 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	2 each Overhead Door Holder, C02511 stop mounted slide track arm, push side mount	626
	Active Leaf RHR	
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
Section 08 11 13	1 each Flat Overlapping Astragal	Galvanealed
	Inactive Leaf LHR	
	2 each 12" Lever Ext Flush Bolt, L14251	626
	1 each Dust Proof Strike, L04021	626
	2 each Silencer, L03011	Grey
	2 each Wall Stop, L02251 or Floor Stop, L02161	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 113A, 117A, 119A
HWS-A3.8 Elec/Mech/Tel Com

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Note: Trim is to have an abrasive texture to indicate a potentially

hazardous environment to the blind

Door No. 115A, 118A
HWS-A3.9 Head, Unixex

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Privacy, F76A no SFIC	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

Door No. 114A
HWS-A3.10 Janitor

	4 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each FMC Closer, C02021	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	1 each 8 x 34 Beveled Kick Plate, J102	630
	1 each 4 x 34 Beveled Mop Plate, J103	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626
	1 each Lever Door Holder, L01381	626

Note: Trim is to have an abrasive texture to indicate a potentially hazardous environment to the blind

Door No. 116A
HWS-A3.11 Storage

	3 each BB 4.5 x 4.5 Butt Hinge, A5111	630
	1 each Lever Storeroom, F86	630
Best	1 each 7 Pin SFIC, F24, E09241	630
	3 each Silencer, L03011	Grey
	1 each Wall Stop, L02251 or Floor Stop, L02161	626

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 08 81 00

GLAZING
05/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 800	(2016) Voluntary Specifications and Test Methods for Sealants

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z97.1	(2015) Safety Glazing Materials Used in Buildings - Safety Performance Specifications and Methods of Test

ASTM INTERNATIONAL (ASTM)

ASTM C509	(2006; R 2021) Standard Specifiaction for Elastomeric Cellular Preformed Gasket and Sealing Material
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM C1021	(2008; R 2014) Standard Practice for Laboratories Engaged in Testing of Building Sealants
ASTM C1036	(2021) Standard Specification for Flat Glass
ASTM C1048	(2018) Standard Specification for Heat-Strengthened and Fully Tempered Flat Glass
ASTM C1087	(2016) Standard Test Method for Determining Compatibility of Liquid-Applied Sealants with Accessories Used in Structural Glazing Systems
ASTM C1281	(2016) Standard Specification for Preformed Tape Sealants for Glazing Applications
ASTM D395	(2016; E 2017) Standard Test Methods for Rubber Property - Compression Set
ASTM D2287	(2019) Nonrigid Vinyl Chloride Polymer and Copolymer Molding and Extrusion Compounds

ASTM E1300	(2024) Standard Practice for Determining Load Resistance of Glass in Buildings

GLASS ASSOCIATION OF NORTH AMERICA (GANA)

GANA Glazing Manual	(2008) Glazing Manual
GANA Sealant Manual	(2008) Sealant Manual
GANA Standards Manual	(2008) Engineering Standards Manual

INSULATING GLASS MANUFACTURERS ALLIANCE (IGMA)

IGMA TB-3001	(2001) Guidelines for Sloped Glazing
IGMA TM-3000	(1990; R 2016) North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial & Residential Use

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

16 CFR 1201	Safety Standard for Architectural Glazing Materials

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Insulating Glass

Glazing Accessories

Sealants

Joint Backer

Rated Glazing

SD-04 Samples

Insulating Glass

Glazing Tape

Sealing Tapes

SD-08 Manufacturer's Instructions

Setting and Sealing Materials

Glass Setting

SD-11 Closeout Submittals

Warranty for Insulated Glass Units

1.3 SYSTEM DESCRIPTION

Fabricate and install watertight and airtight glazing systems to withstand thermal movement and wind loading without glass breakage, gasket failure, deterioration of glazing accessories, or defects in the work. Glazed panels must comply with the safety standards, in accordance with ANSI Z97.1, and comply with indicated wind/snow loading in accordance with ASTM E1300.

1.4 QUALITY CONTROL

Submit two 8 by 10 inch samples of each of the following: tinted glass and insulating glass units.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver products to the site in unopened containers, labeled plainly with manufacturers' names and brands. Store glass and setting materials in safe, enclosed dry locations and do not unpack until needed for installation. Handle and install materials in a manner that will protect them from damage.

1.6 ENVIRONMENTAL REQUIREMENTS

Do not start glazing work until the outdoor temperature is above40 degrees F and rising, unless procedures recommended by the glass manufacturer and approved by the Contracting Officer are made to warm the glass and rabbet surfaces. Provide ventilation to prevent condensation of moisture on glazing work during installation. Do not perform glazing work during damp or rainy weather.

1.7 WARRANTY

1.7.1 Warranty for Insulated Glass Units

Warranty insulating glass units against development of material obstruction to vision (such as dust, fogging, or film formation on the inner glass surfaces) caused by failure of the hermetic seal, other than through glass breakage, for a 10-year period following acceptance of the work. Provide new units for any units failing to comply with terms of this warranty within 45 working days after receipt of notice from the Government.

PART 2 PRODUCTS

2.1 PRODUCT SUSTAINABILITY CRITERIA

2.2 GLASS

ASTM C1036, unless specified otherwise. In doors and sidelights, provide safety glazing material conforming to 16 CFR 1201.

2.2.1 Clear Glass

For interior glazing (i.e., pass and observation windows), 1/4 inch thick

tempered clear glass should be used.

2.2.2 Tempered Glass

ASTM C1048, Kind FT (fully tempered), Condition A (uncoated), Type I, Class 2 (tinted heat absorbing), Quality q3, 0.25 inch thick, 0.25 percent shading coefficient conforming to ASTM C1048 and GANA Standards Manual. Color must be clear or gray as scheduled.

2.2.3 Rated Glazing

Rated glazing is a clear, wireless ceramic type listed for use in non impact locations with fire ratings ranging from 0.33 to 3.0 Hours. Glazing passes the hose stream test and positive pressure test standards. Each lite bears a permanent, factory applied UL label. Typical glazing thickness is 0.1875 inches, with visible transmission of 88% and visible reflection of 9%.

2.3 INSULATING GLASS UNITS

Glazing for exterior windows is a 1 inch insulated glass composite consisting of an exterior layer of 0.25 thick, tinted, tempered glass; 0.5 inch air space; and an interior layer of 0.25 inch thick, clear, laminated annealed float glass with a 0.25 SHGC and U-value of 0.30 or better. Laminated float glass is an 0.125 inch thick glass with 0.030 inch vinyl interlayer and 0.125 inch thick glass with Solar E coating on Surface 3. Tinting requires heat strengthened glass complying with ASTM C1048. Glazing is large missile, impact resistant glass complying with ASTM E 1886 and ASTM E 1996.

Exterior glass tinting is gray.

2.4 SETTING AND SEALING MATERIALS

Provide as specified in the GANA Glazing Manual, IGMA TM-3000, IGMA TB-3001, and manufacturer's recommendations, unless specified otherwise herein. Do not use metal sash putty, nonskinning compounds, nonresilient preformed sealers, or impregnated preformed gaskets. Materials exposed to view and unpainted must be gray or neutral color. Sealant testing must be performed by a testing agency qualified according to ASTM C1021.

Submit glass manufacturer's recommendations for setting and sealing materials and for installation of each type of glazing material specified.

2.4.1 Sealants

Provide elastomeric sealants.

2.4.1.1 Elastomeric Sealant

ASTM C920, Type S, Grade NS, Class 12.5, Use G. Use for channel or stop glazing metal sash. Sealants must be chemically compatible with setting blocks, edge blocks, and sealing tapes, with sealants used in manufacture of insulating glass units. Color of sealant must be white.

2.4.2 Joint Backer

Joint backer must have a diameter size at least 25 percent larger than joint width; type and material as recommended in writing by glass and

sealant manufacturer.

2.4.3 Glazing Tapes

2.4.3.1 Back-Bedding Mastic Glazing Tapes

Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C1281 and AAMA 800 for products indicated below:

a. AAMA 804.3 tape, where indicated.

b. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.

c. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.

2.4.4 Sealing Tapes

Preformed, semisolid, PVC-based material of proper size and compressibility for the particular condition, complying with ASTM D2287. Use only where glazing rabbet is designed for tape and tape is recommended by the glass or sealant manufacturer. Provide spacer shims for use with compressible tapes. Tapes must be chemically compatible with the product being set.

2.4.5 Setting Blocks and Edge Blocks

Closed-cell neoprene setting blocks must be dense extruded type conforming to ASTM C509 and ASTM D395, Method B, Shore A durometer between 70 and 90. Edge blocking must be Shore A durometer of 50 (plus or minus 5). Provide silicone setting blocks when blocks are in contact with silicone sealant. Profiles, lengths and locations must be as required and recommended in writing by glass manufacturer. Block color must be black.

2.4.6 Accessories

Provide as required for a complete installation, including glazing points, clips, shims, angles, beads, and spacer strips. Provide noncorroding metal accessories. Provide primer-sealers and cleaners as recommended by the glass and sealant manufacturers. Use ASTM C1087 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of glazing sealants to surface.

PART 3 EXECUTION

Any materials that show visual evidence of biological growth due to the presence of moisture must not be installed on the building project.

3.1 PREPARATION

Preparation, unless otherwise specified or approved, must conform to applicable recommendations in the GANA Glazing Manual, GANA Sealant Manual, IGMA TB-3001, IGMA TM-3000, and manufacturer's recommendations. Determine the sizes to provide the required edge clearances by measuring the actual opening to receive the glass. Grind smooth in the shop glass edges that

will be exposed in finish work. Leave labels in place until the installation is approved, except remove applied labels on insulating glass units as soon as glass is installed. Securely fix movable items or keep in a closed and locked position until glazing compound has thoroughly set.

3.2 GLASS SETTING

Shop glaze or field glaze items to be glazed using glass of the quality and thickness specified or indicated. Glazing, unless otherwise specified or approved, must conform to applicable recommendations in the GANA Glazing Manual, GANA Sealant Manual, IGMA TB-3001, IGMA TM-3000, and manufacturer's recommendations. Handle and install glazing materials in accordance with manufacturer's instructions. Use beads or stops which are furnished with items to be glazed to secure the glass in place. Verify products are properly installed, connected, and adjusted.

3.2.1 Sheet Glass

Cut and set with the visible lines or waves horizontal.

3.3 CLEANING

Clean glass surfaces and remove labels, paint spots, and other defacement as required to prevent staining. Glass must be clean at the time the work is accepted.

3.4 PROTECTION

Protect glass work immediately after installation. Identify glazed openings with suitable warning tapes, cloth or paper flags, attached with non-staining adhesives. Remove and replace glass units which are broken, chipped, cracked, abraded, or otherwise damaged during construction activities with new units.

-- End of Section --

SECTION 08 91 00

ALUMINUM METAL LOUVERS
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL, INC. (AMCA)

AMCA 500-L	(2015) Laboratory Methods of Testing Louvers for Rating
AMCA 511	(2010; R 2016) Certified Ratings Program for Air Control Devices

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 2605	(2022) Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels

ASTM INTERNATIONAL (ASTM)

ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Wall Louvers

SD-03 Product Data

Metal Wall Louvers

SD-04 Samples

Wall Louver Samples; G

1.3 DELIVERY, STORAGE, AND PROTECTION

Deliver materials to the site in an undamaged condition. Carefully store materials off the ground to provide proper ventilation, drainage, and protection against dampness. Louvers must be free from nicks, scratches, and blemishes. Replace defective or damaged materials with new.

1.4 DETAIL DRAWINGS

Show all information necessary for fabrication and installation of wall louvers. Indicate materials, sizes, thicknesses, fastenings, and profiles.

1.5 COLOR SAMPLES

Colors of finishes for wall louver samples must closely approximate colors indicated.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Aluminum Sheet

ASTM B209, alloy 3003 or 5005 with temper as required for forming.

2.1.2 Extruded Aluminum

ASTM B221, alloy 6063-T5 or -T52.

2.2 METAL WALL LOUVERS

Wind driven rain resistant type, with bird screens and made to withstand a wind load of not less than 54 pounds per square foot. Wall louvers must bear the AMCA certified ratings program seal for air performance and water penetration in accordance with AMCA 500-L and AMCA 511. The rating must show a water penetration of 0.20 or less ounce per square foot of free area at a free velocity of 800 feet per minute.

2.2.1 Extruded Aluminum Louvers

Fabricated of extruded 6063-T5 or -T52 aluminum with a wall thickness of not less than 0.081 inch.

2.2.2 Mullions and Mullion Covers

Same material and finish as louvers. Provide mullions where indicated. Furnish concealed mullions at 5 feet on center for larger fabrications. Provide mullion covers on both faces of joints between louvers.

2.2.3 Screens and Frames

For aluminum louvers, provide 1/2 inch square mesh, 14 or 16 gage aluminum or 1/4 inch square mesh, 16 gage aluminum bird screening. Mount screens in removable, rewirable frames of same material and finish as the louvers.

2.3 FASTENERS AND ACCESSORIES

Provide stainless steel screws and fasteners for aluminum louvers. Provide other accessories as required for complete and proper installation.

2.4 FINISHES

2.4.1 Aluminum

Exposed aluminum surfaces must be factory finished with an organic coating.

Louver is Slate Gray, AMS 595A 36173 as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, MARSOC.

2.4.1.1 Organic Coating

Clean and prime exposed aluminum surfaces. Provide a superior performance finish in accordance with AAMA 2605 with total dry film thickness of not less than 1.2 mil.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Wall Louvers

Install using stops or moldings, flanges, strap anchors, or jamb fasteners as appropriate for the wall construction and in accordance with manufacturer's recommendations.

3.1.2 Screens and Frames

Attach frames to louvers with screws or bolts.

3.2 PROTECTION FROM CONTACT OF DISSIMILAR MATERIALS

3.2.1 Aluminum

Where aluminum contacts metal other than zinc, paint the dissimilar metal with a primer and two coats of aluminum paint.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 09 22 00

SUPPORTS FOR PLASTER AND GYPSUM BOARD
02/10, CHG 2: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A463/A463M	(2015; R 2020; E 2020) Standard Specification for Steel Sheet, Aluminum-Coated, by the Hot-Dip Process
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM C645	(2014; E 2015) Nonstructural Steel Framing Members
ASTM C754	(2020) Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Metal Support Systems

Recycled Content for Metal Support Systems; S

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the job site and store in ventilated dry locations permitting easy access for inspection and handling. If materials are stored outdoors, stack materials off the ground, supported on a level platform, and fully protected from the weather. Handle materials carefully to prevent damage. Remove damaged items and provide new items.

PART 2 PRODUCTS

2.1 MATERIALS

Provide steel materials for metal support systems with galvanized coating

ASTM A653/A653M, G-60; aluminum coating ASTM A463/A463M, T1-25; or a 55-percent aluminum-zinc coating.

Provide metal support systems containing a minimum of 20 percent recycled content. Provide data identifying percentage of recycled content for metal support systems.

2.1.1 Materials for Attachment of Gypsum Wallboard

2.1.1.1 Suspended Ceiling Systems

ASTM C645.

Suspended ceiling assemblies consist of main runners or carrying channels that are 0.060 inch, 16 gauge cold rolled channels 1.5 inches deep with 0.5 inch flanges. Cross furring members are 0.048 inch, 18 gauge cold rolled channels 0.875 inches deep with 0.5 inch flanges. Cross furring members attach to main runners with 18 gauge galvanized tie wire or prefabricated clips. Suspend ceiling assemblies with 0.106 inch, 12 gauge hangers. Specified parameters are minimums. Provide recommended gauges, cross section dimensions, spacing, wire gauges, hanger patterns and fastener patterns.

2.1.1.2 Non-load Bearing Wall Framing and Furring

ASTM C645, but not thinner than 0.033 inch thickness for receiving abuse resistant gypsum board

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Systems for Attachment of Gypsum Wallboard

3.1.1.1 Suspended Ceiling Systems

ASTM C754, except provide framing members 16 inches o.c. unless indicated otherwise.

3.1.1.2 Non-load Bearing Wall Framing and Furring

ASTM C754, except as indicated otherwise.

3.2 ERECTION TOLERANCES

Provide framing members which will be covered by finish materials such as wallboard within the following limits:

a. Layout of walls and partitions: 1/4 inch from intended position;

b. Plates and runners: 1/4 inch in 8 feet from a straight line;

c. Studs: 1/4 inch in 8 feet out of plumb, not cumulative; and

d. Face of framing members: 1/4 inch in 8 feet from a true plane.

Provide framing members which will be covered by ceramic tile set in dry-set mortar, latex-portland cement mortar, or organic adhesive within the following limits:

a. Layout of walls and partitions: 1/4 inch from intended position;

b. Plates and runners: 1/8 inch in 8 feet from a straight line;

c. Studs: 1/8 inch in 8 feet out of plumb, not cumulative; and

d. Face of framing members: 1/8 inch in 8 feet from a true plane.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 09 29 00

GYPSUM BOARD
08/16, CHG 4: 02/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A108.11	(1992; Reaffirmed 2005) Specifications for Interior Installation of Cementitious Backer Units

ASTM INTERNATIONAL (ASTM)

ASTM C475/C475M	(2017; R 2022) Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board
ASTM C840	(2020) Standard Specification for Application and Finishing of Gypsum Board
ASTM C954	(2018) Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs from 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness
ASTM C1002	(2020) Standard Specification for Steel Self-Piercing Tapping Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs
ASTM C1047	(2019) Standard Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base
ASTM C1177/C1177M	(2017) Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing
ASTM C1396/C1396M	(2017) Standard Specification for Gypsum Board
ASTM C1629/C1629M	(2018a) Standard Classification for Abuse-Resistant Nondecorated Interior Gypsum Panel Products and Fiber-Reinforced Cement Panels
ASTM D412	(2016; R 2021) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension

ASTM D624	(2000; R 2020) Standard Test Method for Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers
ASTM D1037	(2012) Evaluating Properties of Wood-Base Fiber and Particle Panel Materials
ASTM D1149	(2007; R 2012) Standard Test Method for Rubber Deterioration - Surface Ozone Cracking in a Chamber
ASTM D2394	(2017) Standard Test Methods for Simulated Service Testing of Wood and Wood-Base Finish Flooring
ASTM D5420	(2016) Standard Test Method for Impact Resistance of Flat, Rigid Plastic Specimen by Means of a Strike Impacted by a Falling Weight (Gardner Impact)
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E336	(2025) Standard Test Method for Measurement of Airborne Sound Attenuation between Rooms in Buildings
ASTM E695	(2003; R 2015; E 2015) Measuring Relative Resistance of Wall, Floor, and Roof Construction to Impact Loading

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/

GYPSUM ASSOCIATION (GA)

GA 214	(2010) Recommended Levels of Gypsum Board Finish
GA 216	(2010) Application and Finishing of Gypsum Panel Products
GA 253	(2012) Application of Gypsum Sheathing

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

UL SOLUTIONS (UL)

UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings
UL Fire Resistance	(2014) Fire Resistance Directory

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Cementitious Backer Units

Glass Mat Covered or Reinforced Gypsum Sheathing

Glass Mat Covered or Reinforced Gypsum Sheathing Sealant

Abuse Resistant Gypsum Board

Accessories

Submit for each type of gypsum board and for cementitious backer units.

Gypsum Board

Recycled Content for Gypsum Board; S

Recycled Content for Paper Facing and Gypsum Cores; S

VOC Content of Joint Compound; S

SD-06 Test Reports

ASTM E90 Factory Test Report; G

ASTM E336 Field Test Report; G

SD-07 Certificates

Asbestos Free Materials; G

Certify that gypsum board types, gypsum backing board types, cementitious backer units, and joint treating materials do not contain asbestos.

Indoor Air Quality for Gypsum Board; S

SD-08 Manufacturer's Instructions

Safety Data Sheets

SD-10 Operation and Maintenance Data

Manufacturer Maintenance Instructions

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality Certifications

Submit required indoor air quality certifications in one submittal package.

1.3.1.1 Ceiling and Wall Systems

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 Delivery

Deliver materials in the original packages, containers, or bundles with each bearing the brand name, applicable standard designation, and name of manufacturer, or supplier.

1.4.2 Storage

Keep materials dry by storing inside a sheltered building. Where necessary to store gypsum board and cementitious backer units outside, store off the ground, properly supported on a level platform, and protected from direct exposure to rain, snow, sunlight, and other extreme weather conditions. Provide adequate ventilation to prevent condensation. Store per manufacturer's recommendations for allowable temperature and humidity range. Do not store gypsum wallboard with materials which have high emissions of volatile organic compounds (VOCs) or other contaminants. Do not store panels near materials that may offgas or emit harmful fumes, such as kerosene heaters, fresh paint, or adhesives. Do not use materials that have visible moisture or biological growth.

1.4.3 Handling

Neatly stack gypsum board and cementitious backer units flat to prevent sagging or damage to the edges, ends, and surfaces.

1.5 QUALIFICATIONS

Furnish type of gypsum board work specialized by the installer with a minimum of 3 years of documented successful experience.

1.6 SCHEDULING

The gypsum wallboard must be taped, finished and primed before the installation of the highly-emitting materials.

Commence application only after the area scheduled for gypsum board work is completely weathertight. The heating, ventilating, and

air-conditioning systems must be complete and in operation prior to application of the gypsum board. If the mechanical system cannot be activated before gypsum board is begun, the gypsum board work may proceed in accordance with an approved plan to maintain the environmental conditions specified below. Apply gypsum board prior to the installation of finish flooring and acoustic ceiling.

1.7 ENVIRONMENTAL REQUIREMENTS

Do not expose the gypsum board to excessive sunlight prior to gypsum board application. Maintain a continuous uniform temperature of not less than 50 degrees F and not more than 80 degrees F for at least one week prior to the application of gypsum board work, while the gypsum board application is being done, and for at least one week after the gypsum board is set. Shield air supply and distribution devices to prevent any uneven flow of air across the plastered surfaces. Provide ventilation to exhaust moist air to the outside during gypsum board application, set, and until gypsum board jointing is dry. In glazed areas, keep windows open top and bottom or side to side 3 to 4 inches. Reduce openings in cold weather to prevent freezing of joint compound when applied. For enclosed areas lacking natural ventilation, provide temporary mechanical means for ventilation. In unglazed areas subjected to hot, dry winds or temperature differentials from day to night of 20 degrees F or more, screen openings with cheesecloth or similar materials. Avoid rapid drying. During periods of low indoor humidity, provide minimum air circulation following gypsum boarding and until gypsum board jointing complete and is dry.

1.8 FIRE RESISTIVE CONSTRUCTION

Comply with specified fire-rated assemblies for design numbers indicated per UL Fire Resistance or FM APP GUIDE.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to specifications, standards and requirements specified. Provide gypsum board types, cementitious backing unitsand joint treating materials manufactured from asbestos free materials only. Submit Safety Data Sheets and manufacturer maintenance instructions for gypsum materials including adhesives.

2.1.1 Gypsum Board

ASTM C1396/C1396M. Gypsum board must contain a minimum of 10 percent post-consumer recycled content, or a minimum of 40 percent post-industrial recycled content. Provide data identifying percentage of recycled content for gypsum board. Paper facings must contain a minimum of 100 percent recycled paper content. Gypsum cores must contain a minimum of 95 percent post-industrial recycled gypsum content. Provide data identifying percentage of recycled content for paper facing and gypsum cores. Provide gypsum wall board and panels meeting the emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type). Provide certification or validation of indoor air quality for gypsum board.

2.1.2 Glass Mat Covered or Reinforced Gypsum Sheathing

Exceeds physical properties of ASTM C1396/C1396M and ASTM C1177/C1177M.

Provide 5/8 inch, gypsum sheathing. Provide gypsum board of with a noncombustible water-resistant core, with glass mat surfaces embedded to the gypsum core or reinforcing embedded throughout the gypsum core. Warrant gypsum sheathing board for at least twelve months against delamination due to direct weather exposure. Provide continuous, asphalt impregnated, building felt to cover exterior face of sheathing. Seal all joints, seams, and penetrations with compatible sealant or joint compound.

2.1.2.1 Glass Mat Covered or Reinforced Gypsum Sheathing Sealant

Provide sealant compatible with glass mat covered or reinforced gypsum sheathing, rubber washers for masonry veneer anchors, and other associated cavity wall components such as anchors and through wall flashing. Provide sealants for glass mat covered or reinforced gypsum sheathing board edge seams and veneer anchor penetrations recommended by the glass mat covered or reinforced gypsum sheathing manufacturer and have the following performance requirements:

a. ASTM D412: Tensile Strength, 80 psi
b. ASTM D412: Ultimate Tensile Strength (maximum elongation), 170 psi
c. ASTM D624: Tear Strength, dieB, 27 ppi
d. ASTM D1149: Joint Movement Capability after 14 Days cure, plus or minus 50 percent.

2.1.3 Abuse Resistant Gypsum Board

48 inch wide, 5/8 inch thick, tapered edges.
Reinforced gypsum panel with imbedded fiber mesh or lexan backing tested in accordance with the following tests. Hard body impact test must attain a Level 2 performance in accordance with ASTM C1629/C1629M. Provide fasteners that meet manufacturer requirements and specifications stated within this section. Abuse resistant gypsum board, when tested in accordance with ASTM E84, have a flame spread rating of 75 or less and a smoke developed rating of 100 or less.

Furnish abuse resistant fire rated and acoustical gypsum board where scheduled. Furnish abuse resistant and mold resistant gypsum board in heads and showers.

2.1.3.1 Soft Body Impact Test

ASTM E695 or ASTM D2394 for impact penetration and deformation. ASTM E695 using a 60 lb leather bag filled with steel pellets, resisting no less than 300 ft. lb. cumulative impact energy before failure or ASTM D2394 using 5.5 inch hemispherical projectile resisting no less than 264 ft. lb. before failure. Provide test specimen stud spacing a minimum 16 inch on center.

2.1.3.2 Hard Body Impact Test

Comply with hard body impact test in accordance with ASTM C1629/C1629M Classification Level 2.

2.1.3.3 Surface Abrasion Test

Comply with test surface abrasion test in accordance with ASTM C1629/C1629M.

2.1.3.4 Indentation Test

ASTM D5420 or ASTM D1037 for indentation resistance. ASTM D5420 using a 32 oz weight with a 5/8 inch hemispherical impacting head dropped once 3 feet creating not more than 0.137 inch indentation or ASTM D1037 using no less than 470 lb weight applied to the 0.438 inch diameter ball to create not more than a 0.0197 inch indentation depth.

2.1.4 Cementitious Backer Units

In accordance with the Tile Council of America (TCA) Handbook.

2.1.5 Joint Treatment Materials

ASTM C475/C475M. Product must be low emitting VOC types with VOC limits not exceeding 50 g/L. Provide data identifying VOC content of joint compound. Use all purpose joint and texturing compound containing inert fillers and natural binders, including lime compound. Pre-mixed compounds must be free of antifreeze, vinyl adhesives, preservatives, biocides and other slow releasing compounds.

2.1.5.1 All-Purpose Compound

Specifically formulated and manufactured to serve as both a taping and a finishing compound and compatible with tape, substrate and fasteners.

2.1.5.2 Joint Tape

Use cross-laminated, tapered edge, reinforced paper, or fiber glass mesh tape recommended by the manufacturer.

2.1.6 Fasteners

2.1.6.1 Screws

ASTM C1002, Type "G", Type "S" or Type "W" steel drill screws for fastening gypsum board to gypsum board, wood framing members and steel framing members less than 0.033 inch thick. ASTM C954 steel drill screws for fastening gypsum board to steel framing members 0.033 to 0.112 inch thick. Provide cementitious backer unit screws with a polymer coating.

2.1.7 Accessories

ASTM C1047. Fabricate from corrosion protected steel designed for intended use. Accessories manufactured with paper flanges are not acceptable. Flanges must be free of dirt, grease, and other materials that may adversely affect bond of joint treatment.

2.1.8 Water

Provide clean, fresh, and potable water.

PART 3 EXECUTION

3.1 EXAMINATION

3.1.1 Framing and Furring

Verify that framing and furring are securely attached and of sizes and

spacing to provide a suitable substrate to receive gypsum board and cementitious backer units. Verify that all blocking, headers and supports are in place to support plumbing fixtures and to receive soap dishes, grab bars, towel racks, and similar items. Do not proceed with work until framing and furring are acceptable for application of gypsum board and cementitious backer units.

3.1.2 Building Construction Materials

Do not install building construction materials that show visual evidence of biological growth.

3.2 APPLICATION OF GYPSUM BOARD

Apply gypsum board to framing and furring members in accordance with ASTM C840 or GA 216 and the requirements specified. Apply gypsum board with separate panels in moderate contact; do not force in place. Stagger end joints of adjoining panels. Neatly fit abutting end and edge joints. Use gypsum board of maximum practical length; select panel sizes to minimize waste. Cut out gypsum board to make neat, close, and tight joints around openings. In vertical application of gypsum board, provide panels in lengths required to reach full height of vertical surfaces in one continuous piece. Lay out panels to minimize waste; reuse cutoffs whenever feasible. Treat edges of cutouts for plumbing pipes, screwheads, and joints with water-resistant compound as recommended by the gypsum board manufacturer. Provide type of gypsum board for use in each system specified herein as indicated.

3.2.1 Application of Gypsum Board to Steel Framing and Furring

Apply in accordance with ASTM C840, System VIII or GA 216.

3.2.2 Exterior Application

Apply exterior gypsum board (such as at soffits) in accordance with ASTM C840, System XI or GA 216.

3.2.3 Glass Mat Covered or Fiber Reinforced Gypsum Sheathing

Apply glass mat covered or fiber reinforced gypsum sheathing in accordance to gypsum association publications GA 253. Follow gypsum sheathing manufacturer's requirements of design details for joints and fasteners and be properly installed to protect the substrate from moisture intrusion. Do not leave exposed surfaces of the glass mat covered or fiber reinforced gypsum sheathing beyond the manufacturer's recommendation without a weather barrier cladding. Seal all joints, seams, and penetrations with a compatible silicone sealant or joint compound.

3.2.4 Control Joints

Install expansion and contraction joints in ceilings and walls in accordance with ASTM C840, System XIII or GA 216.

3.2.5 Application of Abuse Resistant Gypsum Board

Apply in accordance with applicable system of ASTM C840 as specified or GA 216. Follow manufacturers written instructions on how to cut, drill and attach board.

3.3 APPLICATION OF CEMENTITIOUS BACKER UNITS

3.3.1 Application

In wet areas (tubs, shower enclosures, saunas, steam rooms, gang shower rooms), apply cementitious backer units in accordance with ANSI A108.11. Place a 15 lb asphalt impregnated, continuous felt paper membrane behind cementitious backer units, between backer units and studs or base layer of gypsum board. Place membrane with a minimum 6 inch overlap of sheets laid shingle style.

3.3.2 Joint Treatment

ANSI A108.11.

3.4 FINISHING OF GYPSUM BOARD

Tape and finish gypsum board in accordance with ASTM C840, GA 214 and GA 216. Finish above ceilings to Level 1 in accordance with GA 214. Unless otherwise specified, finish all gypsum board to Level 5 in accordance with GA 214. Provide joint, fastener depression, and corner treatment. Tool joints as smoothly as possible to minimize sanding and dust. Do not use self-adhering fiber glass mesh tape with conventional drying type joint compounds; use setting or hardening type compounds only. Provide treatment for water-resistant gypsum board as recommended by the gypsum board manufacturer. Protect workers, building occupants, and HVAC systems from gypsum dust.

3.4.1 Uniform Surface

Wherever gypsum board is to receive eggshell, semigloss or gloss paint finish, or where severe, up or down lighting conditions occur, finish gypsum wall surface in accordance to GA 214 Level 5. In accordance with GA 214 Level 5, apply a thin skim coat of joint compound to the entire gypsum board surface, after the two-coat joint and fastener treatment is complete and dry.

3.5 SEALING

Seal openings around pipes, fixtures, and other items projecting through gypsum board and cementitious backer units as specified in Section 07 92 00 JOINT SEALANTS. Apply material with exposed surface flush with gypsum board or cementitious backer units.

3.5.1 Sealing for Glass Mat or Reinforced Gypsum Board Sheathing

Apply silicone sealant in a 3/8 inch bead to all joints and trowel flat. Apply enough of the same sealant to all fasteners penetrating through the glass mat gypsum board surface to completely cover the penetration when troweled flat. Do not place construction and materials behind sheathing until a visual inspection of sealed joints during daylight hours has been completed by Contracting Officer.

3.6 FIRE-RESISTANT ASSEMBLIES

Wherever fire-rated construction is indicated, provide materials and application methods, including types and spacing of fasteners, wall and ceiling framing in accordance with the specifications contained in UL Fire Resistance for the Design Number(s) indicated. Joints of

fire-rated gypsum board enclosures must be closed and sealed in accordance with UL test requirements or GA requirements. Seal penetrations through rated partitions and ceilings tight in accordance with tested systems.

3.7 SOUND RATED ASSEMBLIES

When sound rated assemblies are required, provide materials and application methods, including panels, insulation, types and spacing of fasteners, and wall framing in accordance with the contract document and the description of the assembly in the ASTM E90 Factory Test Report. Seal partitions continuously with acoustical foam or sealant (both sides) and finished to match wall wherever it abuts another element such as the floor, ceiling, wall, column, mullion, or another system or assembly.

3.8 PATCHING

Patch surface defects in gypsum board to a smooth, uniform appearance, ready to receive finishes.

3.9 SOUND RATED ASSEMBLY FIELD TESTING

Provide third party testing of sound rated assemblies tested in accordance with ASTM E336. Provide the ASTM E336 Field Test Report verifying that the installed assemblies perform no less than five ASTC rating points below the ASTM E90 Factory Test Report. Examine, modify adjust, and retest any installation not meeting the STC Rating until compliance is obtained.

-- End of Section --

SECTION 09 30 10

CERAMIC, QUARRY, AND GLASS TILING
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI A108/A118/A136.1	(2024) American National Standard Specifications for the Installation of Ceramic Tile
ANSI A137.1	(2019) American National Standards Specifications for Ceramic Tile

ASTM INTERNATIONAL (ASTM)

ASTM A1064/A1064M	(2024) Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM C33/C33M	(2024a) Standard Specification for Concrete Aggregates
ASTM C144	(2025) Standard Specification for Aggregate for Masonry Mortar
ASTM C150/C150M	(2024) Standard Specification for Portland Cement
ASTM C206	(2014; R 2022) Standard Specification for Finishing Hydrated Lime
ASTM C207	(2024) Standard Specification for Hydrated Lime for Masonry Purposes
ASTM C373	(2018; R 2023)Standard Test Methods for Determination of Water Absorption and Associated Properties by Vacuum Method for Pressed Ceramic Tiles and Glass Tiles and Boil Method for Extruded Ceramic Tiles and Non-tile Fired Ceramic Whiteware Products
ASTM C648	(2020) Standard Test Method for Breaking Strength of Ceramic Tile
ASTM C847	(2018; R 2024) Standard Specification for Metal Lath
ASTM C1026	(2023) Standard Test Method for Measuring

	the Resistance of Ceramic and Glass Tile to Freeze-Thaw Cycling
ASTM C1027	(2009; R 2017) Standard Test Method for Determining Visible Abrasion Resistance of Glazed Ceramic Tile

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

MARBLE INSTITUTE OF AMERICA (MIA)

MIA Design Manual	(2016) Dimension Stone Design Manual

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2022) Adhesive and Sealant Applications

TILE COUNCIL OF NORTH AMERICA (TCNA)

TCNA Hdbk	(2017) Handbook for Ceramic, Glass, and Stone Tile Installation

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191	Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines

UL SOLUTIONS (UL)

UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings; G

SD-03 Product Data

Porcelain Tile; G

Recycled Content for Porcelain Tile; S

Mosaic Tile; G

Recycled Content for Mosaic Tile; S

Glazed Ceramic Wall Tile; G

Recycled Content for Glazed Ceramic Wall Tile; S

Transition Strips; G

Metal Strips; G

Setting-Bed; G

Mortar, Grout, and Adhesive; G

Reinforcing Wire Fabric

Cementitious Backer Units; G

Waterproof Membrane; G

Crack Isolation Membrane; G

SD-04 Samples

Tile; G

Accessories; G

Transition Strips; G

Metal Strips; G

Grout; G

SD-07 Certificates

Indoor Air Quality for Adhesives; S

Indoor Air Quality for Sealants; S

Water Absorption Rates

SD-08 Manufacturer's Instructions

Manufacturer's Approved Cleaning Instructions

SD-10 Operation and Maintenance Data

Porcelain Tile, Data Package 1;

Mosaic Tile, Data Package 1; G

Glazed Ceramic Wall Tile, Data Package 1; G

Transition Strips, Data Package 1; G

Metal Strips, Data Package 1; G

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality Certifications

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body.When product does not have certification, provide validation that product meets the indoor air quality product requirements cited in this Section.

1.3.2 Water Absorption Rates Certification

Provide certification for each tile type indicating compliance with the following water absorption (wa) rates per ANSI A137.1 criteria as tested per ASTM C373 requirements.

a. Porcelain and Mosaic Tile (Impervious): Provide water absorption (wa) of 0.5 percent or less.

b. Ceramic Wall Tile (Non-Vitreous): Provide maximum water absorption (wa) of 7.0 percent.

1.4 QUALITY ASSURANCE

Provide installers having a minimum of two years of experience with a company specializing in performing the type of work described. Each type and color of tile to be provided from a single source. Each type and color of mortar, adhesive, and grout to be provided from the same source.

1.5 DELIVERY, STORAGE, AND HANDLING

Ship tiles in sealed packages and clearly marked with the grade, type of tile, producer identification, and country of origin. Deliver materials to the project site in manufacturer's original unopened containers with seals unbroken and labels and hallmarks intact. Protect materials from weather, and store them under cover in accordance with manufacturer's printed instructions. Store and handle tiles per manufacturer's instructions for gauged porcelain tile and gauged porcelain tile panels/slabs.

1.6 ENVIRONMENTAL REQUIREMENTS

Do not perform ceramic tile work unless the substrate and ambient temperature is at least 50 degrees F and rising. Maintain temperature above 50 degrees F while the work is being performed and for at least 7 days after completion of the work. When temporary heaters are used, ventilate the area to the outside to avoid carbon dioxide damage to new tilework.

1.7 WARRANTY

Provide manufacturer's warranty to repair or replace defective tiling materials and workmanship, including tile, mortar and grout products and installation as a system, for a period of one year from date of final acceptance of the work.

1.8 EXTRA MATERIALS

Supply an extra 2 percent of each type tile used in clean and marked cartons.

PART 2 PRODUCTS

2.1 TILE

Provide tiles that comply with ANSI A137.1 and are standard grade tiles. Provide a minimum breaking strength of 125 lbs. for wall tile and 250 lbs. for floor tile in accordance with ASTM C648. Provide exterior building tile for cold climate projects that is approved by the manufacturer for exterior use when tested in accordance with ASTM C1026. Provide floor tiles with a minimum wet dynamic coefficient of friction (DCOF) value of 0.42when tested in accordance with ANSI A137.1 requirements. Provide glazed floor tile with a Class V-Heavy Commercial classification as rated by the manufacturer when tested in accordance with ASTM C1027 for visible abrasion resistance as related to foot traffic. For materials like tile, accessories, and transition strips submit samples of sufficient size to show color range, pattern, type and joints.

Submit manufacturers' descriptive product data for each type of ceramic, quarry. Include manufacturers' literature, finishes, profiles and thicknesses of materials.

Submit manufacturers' operations and maintenance data for each type o ceramic tiling indicated in accordance with Section 01 78 23 OPERATIONS AND MAINTENANCE DATA.

2.1.1 Porcelain Tile

Provide unglazed through body (surface color and pattern go all the way through the tile body) or glazed color body (body of tile is stained to match the glaze color), rectified porcelain tile and trim pieces. Provide tile with a V2 aesthetic classification. Blend tiles in factory and in a packages to have same color range and continuous blend for installation. Provide nominal tile size(s) as indicated on drawings.

Provide porcelain tiling materials that contain a minimum of 10 percent recycled content. Provide data identifying percentage of recycled content for porcelain tile.

2.1.2 Mosaic Tile

Furnish unglazed mosaic tile composed of porcelain. Provide tile with a V2 aesthetic classification. Blend tiles in factory and in a packages to have same color range and continuous blend for installation. Provide nominal tile size(s) of 2 by 2 inch a mixture of standard sizes in a stock pattern.

Provide mosaic tiling materials that contain a minimum of 3 percent recycled content. Provide data identifying percentage of recycled content for mosaic tile.

2.1.3 Glazed Ceramic Wall Tile

Provide glazed, rectified ceramic wall tile that has square edges and trim with lead-free matte finish. Provide nominal tile size(s) as indicated on the drawings.

Provide glazed ceramic wall tile materials that contain a minimum of 3 percent recycled content. Provide data identifying percentage of recycled content for glazed ceramic wall tile.

2.2 SETTING-BED

Submit manufacturer's catalog data. Compose the setting-bed of the following materials:

2.2.1 Aggregate for Concrete Fill

Conform to ASTM C33/C33M for aggregate fill. Do not exceed one-half the thickness of concrete fill for maximum size of coarse aggregate.

2.2.2 Portland Cement

Conform to ASTM C150/C150M for cement, Type I, white for wall mortar and gray for other uses.

2.2.3 Sand

Conform to ASTM C144 for sand.

2.2.4 Hydrated Lime

Conform to ASTM C206 for hydrated lime, Type S or ASTM C207, Type S.

2.2.5 Metal Lath

Conform to ASTM C847 for flat expanded type metal lath, and weighing a minimum 2.5 pound/square yard.

2.2.6 Reinforcing Wire Fabric

Conform to ASTM A1064/A1064M for wire fabric. Provide 2 by 2 inch mesh, 16/16 wire.

2.3 WATER

Provide potable water.

2.4 MORTAR, GROUT, AND ADHESIVE

Provide non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide aerosol adhesives used on the interior of the building meeting either emissions requirements of CDPH SECTION 01350

(limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of GS-36. For products located on the interior of the building (inside of the weatherproofing system, provide certification or validation of indoor air quality for adhesives. Provide bond coat, mortar, and grout supplied from the same manufacturer.

2.4.1 Dry-Set Portland Cement Mortar

TCNA Hdbk.

2.4.2 Furan Mortar

TCNA Hdbk.

2.4.3 Latex-Portland Cement Mortar

TCNA Hdbk.

2.4.4 Ceramic Tile Grout

TCNA Hdbk; petroleum-free and plastic-free standard cement commercial portland cement grout.

2.4.5 Organic Adhesive

TCNA Hdbk, Type I. Water-resistant. Comply with ANSI A108/A118/A136.1.

2.4.6 Epoxy Resin Grout

TCNA Hdbk. Water cleanable epoxy conforming to ANSI A108/A118/A136.1; provide manufacturer proportioned and packaged kit having hardener, resin and colored filler and horizontal and vertical grade products as applicable.

2.4.7 Urethane Grout

TCNA Hdbk; premixed, urethane, water-based grout with color consistency and antimicrobial protection; no color fading, streaking or shading, chemical and stain resistant; and UV stable.

2.4.8 Sealants

Comply with applicable regulations regarding toxic and hazardous materials and as specified. Provide sealant that does not change the color or alter the appearance of the grout. Refer to Section 07 92 00 JOINT SEALANTS.

Provide sealants used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. For products located on the interior of the building (inside of the weatherproofing system), provide certification or validation of indoor air quality for sealants.

2.5 SUBSTRATES

Refer to Section 09 29 00 GYPSUM BOARD for cementitious backer units.

2.5.1 Cementitious Backer Units

Provide cementitious backer unit, for use as tile substrate as indicated, in accordance with TCNA Hdbk. Furnish 1/2 inch thick cementitious backer units.

2.6 MISCELLANEOUS TRIMS

2.6.1 Transition Strips

Provide anodized aluminum transitions between tile and carpet or resilient flooring. Provide types as recommended by flooring manufacturer for both edges and transitions of flooring materials specified. Categorize marble Group A as classified by MIA Design Manual. P Provide transition strips that comply with 36 CFR 1191 requirements.

2.6.2 Metal Strips

Provide trim shapes, height to match tile and setting thickness, designed specifically for flooring, and wall applications. Provide anodized aluminum cove strip where floor tile abuts wall tile for sanitary transition and elimination of cove tile base. Provide extruded square anodized aluminum edging at tile surfaces with exposed outside and inside corners. Provide profiles appropriate for finished floor and wall materials as indicated.

2.7 WATERPROOF MEMBRANE

2.7.1 General

Manufacturer's standard product that complies with ANSI A108/A118/A136.1 and is recommended by the manufacturer for the application indicated. Include reinforcement and accessories recommended by manufacturer.

2.7.2 Chlorinated-Polyethylene Shower Waterproof Membrane

Nonplasticized, chlorinated polyethylene faced on both sides with nonwoven polyester fabric; 0.040inch nominal thickness.

2.8 CRACK ISOLATION MEMBRANE

2.8.1 General

Manufacturer's standard product that complies with ANSI A108/A118/A136.1 and is recommended by the manufacturer for the application indicated. Include reinforcement and accessories recommended by manufacturer.

2.8.2 Chlorinated-Polyethylene Crack Isolation Membrane

Nonplasticized, chlorinated polyethylene faced on both sides with nonwoven polyester fabric; 0.030 inch nominal thickness.

2.9 COLOR, TEXTURE, AND PATTERN

Provide color, pattern and texture as indicated; colors listed are not intended to limit the selection of equal colors from other manufacturers.

PART 3 EXECUTION

3.1 PREPARATORY WORK AND WORKMANSHIP

Inspect surface to receive tile in conformance to the requirements of TCNA Hdbk for surface conditions for the type setting bed specified and for workmanship. Provide variations of tiled surfaces that fall within maximum values shown below:

TYPE	WALLS	FLOORS
Dry-Set Mortar	1/8 inch in 8 ft.	1/8 inch in 10 ft.
Organic Adhesives	1/8 inch in 8 ft.	1/16 inch in 3 ft.
Latex-Portland Cement Mortar	1/8 inch in 8 ft.	1/8 inch in 10 ft.
Epoxy	1/8 inch in 8 ft.	1/8 inch in 10 ft.

3.2 GENERAL INSTALLATION REQUIREMENTS

Do not start tile work until roughing in for mechanical and electrical work has been completed and tested, and built-in items requiring membrane waterproofing have been installed and tested. Close space, in which tile is being set, to traffic and other work. Keep closed until tile is firmly set. Do not start floor tile installation in spaces requiring wall tile until after wall tile has been installed. Apply tile in colors and patterns indicated in the area shown on the drawings. Install tile with the respective surfaces in true even planes to the elevations and grades shown. Provide special shapes as required for sills, jambs, recesses, offsets, external corners, and other conditions to provide a complete and neatly finished installation. Solidly back tile bases and coves with mortar. Do not walk or work on newly tiled floors without using kneeling boards or equivalent protection of the tiled surface. Keep traffic off horizontal portland cement mortar installations for at least 72 hours. Keep all traffic off epoxy installed floors for at least 40 hours after grouting, and heavy traffic off for at least 7 days, unless otherwise specifically authorized by manufacturer. Dimension and draw detail drawings at a minimum scale of 1/4 inch = 1 foot. Include drawings of pattern at inside corners, outside corners, termination points and location of all equipment items such as thermostats, switch plates, mirrors and toilet accessories mounted on surface. Submit drawings showing ceramic tile pattern elevations and floor plans. Submit manufacturer's preprinted installation instructions.

Do not install building construction materials that show visual evidence of biological growth.

3.3 INSTALLATION OF SUBSTRATES

3.3.1 Cementitious Backer Units

Install in accordance with manufacturer's written instructions.

3.4 INSTALLATION OF WALL TILE

Install wall tile in accordance with the TCNA Hdbk, method and with grout

joints as recommended by the manufacturer for the type of tile. Install thinner wall tile flush with thicker wall tile applied on same wall and provide installation materials as recommended by the tile and setting materials manufacturer's to achieve flush installation.

3.4.1 Workable or Cured Mortar Bed

Install tile over workable mortar bed or a cured mortar bed at the option of the Contractor. Install a 4 mil polyethylene membrane, metal lath, and scratch coat. Conform to TCNA Hdbk method for workable mortar bed, materials, and installation of tile. Conform to TCNA Hdbk method for cured mortar bed and materials.

3.4.2 Dry-Set Mortar and Latex-Portland Cement Mortar

Use latex-portland cement to install tile in accordance with TCNA Hdbk method . Use latex-portland cement when installing porcelain ceramic tile.

3.4.3 Organic Adhesive

Comply with the requirements of TCNA Hdbk method for organic adhesive installation of ceramic tile.

3.4.4 Ceramic Tile Grout

Prepare and install ceramic tile grout in accordance with TCNA Hdbk method. Provide and apply manufacturer's standard product for sealing grout joints in accordance with manufacturer's recommendations.

3.4.5 Epoxy Resin Grout

Prepare and install epoxy resin grout in accordance with TCNA Hdbk method .

3.4.6 Urethane Grout

Prepare and install urethane grout in accordance with TCNA Hdbk method .

3.5 INSTALLATION OF FLOOR TILE

Install floor tile in accordance with TCNA Hdbk method specified herein and with grout joints as recommended by the manufacturer for the type of tile. Install shower receptors in accordance with TCNA Hdbk method B415.

3.5.1 Workable or Cured Mortar Bed

Install floor tile over a workable mortar bed or a cured mortar bed at the option of the Contractor. Conform to TCNA Hdbk method for workable mortar bed materials and installation. Conform to TCNA Hdbk method for cured mortar bed materials and installation. Provide minimum 1/4 inch to maximum 3/8 inch joints in uniformed width.

3.5.2 Dry-Set and Latex-Portland Cement

Use latex-portland cement mortar to install tile directly over properly cured, plane, clean concrete slabs in accordance with TCNA Hdbk method . Use latex-portland cement when installing porcelain ceramic tile.

3.5.3 Ceramic Tile Grout

Prepare and install ceramic tile grout in accordance with TCNA Hdbk method . Provide and apply manufacturer's standard product for sealing grout joints in accordance with manufacturer's recommendations.

3.5.4 Waterproof and Crack Isolation Membranes

Install as indicated in accordance with manufacturer's written instructions.

3.5.5 Concrete Fill

Provide a 3500 psi concrete fill mix to dry as consistency as practicable. Compose concrete fill by volume of 1 part Portland cement to 3 parts fine aggregate to 4 parts coarse aggregate, and mix with water to as dry a consistency as practicable. Spread, tamp, and screed concrete fill to a true plane, and pitch to drains or levels as shown. Thoroughly damp concrete fill before applying setting-bed material. Reinforce concrete fill with one layer of reinforcement, with the uncut edges lapped the width of one mesh and the cut ends and edges lapped a minimum 2 inch. Tie laps together with 18 gauge wire every 10 inch along the finished edges and every 6 inch along the cut ends and edges. Provide reinforcement with support and secure in the centers of concrete fills. Provide a continuous mesh; except where expansion joints occur, cut mesh and discontinue across such joints. Provide reinforced concrete fill under the setting-bed where the distance between the under-floor surface and the finished tiles floor surface is a minimum of 2 inches, and of the same thickness that the mortar setting-bed over the concrete fill with the thickness required in the specified TCNA Hdbk method .

3.6 INSTALLATION OF MISCELLANEOUS TRIMS

3.6.1 Transition Strips

Install transition strips where indicated, in a manner similar to that of the ceramic tile floor and as recommended by the manufacturer. Provide thresholds full width of the opening. Install head joints at ends not exceeding 1/4 inch in width and grouted full.

3.6.2 Metal Trims

Install trim where indicated. Embed anchoring leg in setting mortar in accordance with manufacturer's instructions. During grouting of tile joints, immediately wipe grout from finish surface.

3.7 EXPANSION JOINTS

Form and seal joints as specified in Section 07 92 00 JOINT SEALANTS.

3.7.1 Walls

Provide expansion joints at control joints in backing material. Wherever backing material changes, install an expansion joint to separate the different materials.

3.7.2 Floors

Provide expansion joints over construction joints, control joints, and

expansion joints in concrete slabs in accordance with TCNA Hdbk method EJ171 type to suit conditions. Provide expansion joints where tile abuts restraining surfaces such as perimeter walls, curbs and columns and at intervals of 20 to 25 feet each way in large interior floor areas and 8 to 12 feet each way in large exterior areas or areas exposed to direct sunlight or moisture. Extend expansion joints through setting-beds and fill.

3.8 CLEANING AND PROTECTING

Upon completion, thoroughly clean tile surfaces in accordance with manufacturer's approved cleaning instructions. Do not use acid for cleaning glazed tile. Clean floor tile with resinous grout or with factory mixed grout in accordance with printed instructions of the grout manufacturer. After the grout has set, provide a protective coat of a noncorrosive soap or other approved method of protection for tile wall surfaces. Cover tiled floor areas with building paper before foot traffic is permitted over the finished tile floors. Provide board walkways on tiled floors that are to be continuously used as passageways by workmen. Replace damaged or defective tiles.

-- End of Section --

SECTION 09 51 00

ACOUSTICAL CEILINGS
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A1008/A1008M	(2021a) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM A489	(2018; E 2018) Standard Specification for Carbon Steel Eyebolts
ASTM A641/A641M	(2019) Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B633	(2019) Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel
ASTM C423	(2009a) Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method
ASTM C635/C635M	(2022) Standard Specification for Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-In Panel Ceilings
ASTM C636/C636M	(2013) Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels
ASTM C834	(2017) Standard Specification for Latex Sealants
ASTM E1264	(2022) Standard Classification for Acoustical Ceiling Products
ASTM E1414/E1414M	(2021a) Standard Test Method for Airborne Sound Attenuation Between Rooms Sharing a

	Common Ceiling Plenum
ASTM E1477	(1998a; R 2017; E 2018) Standard Test Method for Luminous Reflectance Factor of Acoustical Materials by Use of Integrating-Sphere Reflectometers
ASTM E795	(2016) Standard Practices for Mounting Test Specimens During Sound Absorption Tests
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2022) Adhesive and Sealant Applications

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval.Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Approved Detail Drawings; G

SD-03 Product Data

Acoustical Ceiling Systems; G

Recycled Content for Type III Ceiling Tiles

SD-04 Samples

Acoustical Units; G

Acoustical Ceiling Tiles; G

SD-06 Test Reports

Ceiling Attenuation Class and Test; G

SD-07 Certificates

Indoor Air Quality for Type III Ceiling Tiles

Indoor Air Quality for Sealants

1.3 DELIVERY, STORAGE. AND HANDLING

Deliver materials to the site in the manufacturer's original unopened containers with brand name and type clearly marked. Carefully handle and store materials in dry, watertight enclosures. Immediately before installation, store acoustical units for not less than 24 hours at the same temperature and relative humidity as the space where they will be installed in order to assure proper temperature and moisture acclimation.

1.4 ENVIRONMENTAL REQUIREMENTS

Maintain a uniform temperature of not less than 60 degrees F nor more than 85 degrees F and a relative humidity of not more than 70 percent for 24 hours before, during, and 24 hours after installation of acoustical units.

1.5 SCHEDULING

Complete and dry interior finish work such as plastering, concrete and terrazzo work before ceiling installation. Complete mechanical, electrical, and other work above the ceiling line; install and start operating heating, ventilating, and air conditioning systems in order to maintain temperature and humidity requirements.

1.6 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a one year period. Include an agreement to repair or replace acoustical panels that fail within the warranty period in the standard performance guarantee or warranty. Failures include, but are not limited to, sagging and warping of panels; rusting and manufacturers defects of grid system. For acoustic ceiling baffles, provide manufacturer's standard warranty that the covers the product for up to three years.

1.7 EXTRA MATERIALS

Furnish spare tiles, from the same lot as those installed, of each color at the rate of 5 tiles for each 1000 tiles installed.

1.8 OTHER SUBMITTAL REQUIREMENTS

Submit the following:

a. Manufacturer's catalog showing UL classification of fire-rated ceilings giving materials, construction details, types of floor and roof constructions must be protected, and UL design number and fire protection time rating for each required floor or roof construction and acoustic ceiling assembly.

b. Reports by an independent testing laboratory attesting that acoustical ceiling systems meet specified sound transmission requirements. Data attesting to conformance of the specified system to Underwriters Laboratories requirements for the fire endurance rating listed in UL Fire Resistance may be submitted in lieu of test reports.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide sound controlling units mechanically mounted on a ceiling suspension system for acoustical treatment. The unit size, texture, finish, and color must be as specified. The location and extent of acoustical treatment must be as shown on the approved detail drawings. Submit drawings showing suspension system, method of anchoring and fastening, details, and reflected ceiling plan. Coordinate with paragraph RECLAMATION PROCEDURES for reclamation of mineral fiber acoustical ceiling panels must be removed from the job site.

2.1.1 Ceiling Attenuation Class and Test

Provide a ceiling system with an attenuation class (CAC) of 40 for ACT-1 and 35 for ACT-2 when determined in accordance with ASTM E1414/E1414M. Provide fixture attenuators over light fixtures and other ceiling penetrations, and provide acoustical blanket insulation adjacent to partitions, as required to achieve the specified CAC. Provide test ceiling continuous at the partition and assembled in the suspension system in the same manner that the ceiling will be installed on the project.

2.1.2 Ceiling Sound Absorption

Determine the Noise Reduction Coefficient (NRC) in accordance with ASTM C423 Test Method.

2.1.3 Light Reflectance

Determine light reflectance factor in accordance with ASTM E1477 Test Method.

2.2 ACOUSTICAL UNITS

Submit two samples of each type of acoustical unit and each type of suspension grid tee section showing texture, finish, and color. Conform acoustical units to ASTM E1264, Class A, and the following requirements:

2.2.1 Units for Exposed-Grid System ACG-1

2.2.1.1 Type

III (non-asbestos mineral fiber with painted finish). Provide Type III Acoustical Ceiling Tiles containing a minimum of 55 percent recycled content. Provide data identifying percentage of recycled content for Type III ceiling tiles. Provide certification of indoor air quality for Type III Ceiling Tiles.

2.2.1.2 Flame Spread

Class A, 25 or less

2.2.1.3 Pattern

Pattern E

2.2.1.4 Minimum NRC

0.75 in all rooms and areas when tested on mounting Type E-400 of ASTM E795.

2.2.1.5 Minimum Light Reflectance Coefficient

0.85 or greater

2.2.1.6 Nominal Size

24 by 24 inch

2.2.1.7 Edge Detail

Tegular

2.2.1.8 Finish

Factory-applied standard finish.

2.2.1.9 Minimum CAC

35

2.2.2 Units for Exposed-Grid System ACG-2

2.2.2.1 Type

III (non-asbestos mineral fiber with painted finish). Provide Type III Acoustical Ceiling Tiles containing a minimum of 70 percent recycled content. Provide data identifying percentage of recycled content for Type III ceiling tiles. Provide certification of indoor air quality for Type III Ceiling Tiles.

2.2.2.2 Flame Spread

Class A, 25 or less

2.2.2.3 Pattern

Pattern E

2.2.2.4 Minimum NRC

0.85 when tested on mounting Type E-400 of ASTM E795

2.2.2.5 Minimum Light Reflectance Coefficient

0.85 or greater

2.2.2.6 Nominal Size

24 by 24 inch

2.2.2.7 Edge Detail

Square Tegular

2.2.2.8 Finish

Factory-applied color finish

2.2.2.9 Minimum CAC

35

2.2.3 Acoustical Ceiling Baffles

Ceiling baffles must be 3" thick - 6 lb. per cubic foot density PET. Manufactures standard baffle construction and baffle felt must comply with the following:

1. Facing Material: Polyester Felt (PET)
2. Baffle Thickness: nominal 3" thick
3. NRC Value: 1.5
4. Connection: Feltlock to unistrut
5. Baffle Length: As indicated, up to 10 feet long.
6. Fire Rating: ASTM E84 Class A
7. Mounting: Type J conforms to ASTM C423
8. Minumum Recycled Content: 55%

2.2.4 Unit Acoustical Absorbers

Absorbers must be individually mounted sound absorbing plaques composed of glass fibers or non-asbestos mineral fibers and having a NRC range of not less than 0.60 - 0.70 when tested in accordance with ASTM C423 and reported as a 4 frequency average.

2.3 SUSPENSION SYSTEM

Provide standard exposed-grid suspension system as shown on drawings conforming to ASTM C635/C635M for intermediate-duty systems. Provide surfaces exposed to view of galvanized steel with a factory-applied baked polyester white paint or black finish. Provide finish color as shown on drawings. Provide wall molding having a flange of not less than 9/16 inch. Provide inside and outside corner caps standardmitered corners. Suspended ceiling framing system must have the capability to support the finished ceiling, light fixtures, air diffusers, and accessories, as shown. Provide a suspension system with a maximum deflection of 1/360 of the span length.

2.4 HANGERS

Provide hangers and attachment capable of supporting a minimum 300 pound ultimate vertical load without failure of supporting material or attachment.

2.4.1 Wires

Conform wires to ASTM A641/A641M, Class 1, 0.08 inch (12 gauge) in diameter.

2.4.2 Straps

Provide straps of 1 by 3/16 inch galvanized steel conforming to ASTM A653/A653M, with a light commercial zinc coating or ASTM A1008/A1008M with an electrodeposited zinc coating conforming to ASTM B633, Type RS.

2.4.3 Rods

Provide 3/16 inch diameter threaded steel rods, zinc or cadmium coated.

2.4.4 Eyebolts

Provide eyebolts of weldless, forged-carbon-steel, with a straight-shank in accordance with ASTM A489. Eyebolt size must be a minimum 1/4 inch, zinc coated.

2.4.5 Anchorage Devices

Comply with ASTM C636/C636M for anchorage devices for eyebolts . Where aluminum is in contact with concrete, coat aluminum with bituminous paint or where exposed, with a chromatic primer and 2-coats of enamel paint.

2.5 ACCESS PANELS

Provide access panels that match adjacent acoustical units, designed and equipped with suitable framing and fastenings for removal and replacement without damage. Size panel must be not less than 12 by 12 inch or more than 12 by 24 inch.

a. Attach an identification plate of 0.032 inch thick aluminum, 3/4 inch in diameter, stamped with the letters "AP" and finished the same as the unit, near one corner on the face of each access panel.

b. Identify ceiling access panel by a number utilizing white identification plates or plastic buttons with contrasting numerals. Provide plates or buttons of minimum 1 inch diameter and securely attached to one corner of each access unit. Provide a typewritten card framed under glass listing the code identification numbers and corresponding system descriptions listed above. Mount the framed card where directed and furnish a duplicate card to the Contracting Officer. Code identification system is as follows:

1 Fire detection/alarm system

2 Air conditioning controls

3 Plumbing system

4 Heating and steam systems

5 Air conditioning duct system

6 Sprinkler system

7 Telephone junction boxes

2.6 FINISHES

Use manufacturer's standard textures, patterns and finishes as specified for acoustical units and suspension system members. Treat ceiling suspension system components to inhibit corrosion.

2.7 COLORS AND PATTERNS

Use colors and patterns for acoustical units and suspension system components as specified in the drawings.

2.8 ACOUSTICAL SEALANT

Conform acoustical sealant to ASTM C834, nonstaining. Provide sealants used on the interior of the building (defined as inside of the weatherproofing system) that meet either emissions requirements of CDPH SECTION 01350 (use the office or classoom requirements, regardless of space type) or VOC content requirements of SCAQMD Rule 1168.Provide certification of indoor air quality for Sealants.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

Examine surfaces to receive directly attached acoustical units for unevenness, irregularities, and dampness that would affect quality and execution of the work. Rid areas, where acoustical units will be cemented, of oils, form residue, or other materials that reduce bonding capabilities of the adhesive. Complete and dry interior finish work such as plastering, concrete, and terrazzo work before installation. Complete and approve mechanical, electrical, and other work above the ceiling line prior to the start of acoustical ceiling installation. Provide acoustical work complete with necessary fastenings, clips, and other accessories required for a complete installation. Do not expose mechanical fastenings in the finished work. Lay out hangers for each individual room or space. Provide hangers to support framing around beams, ducts, columns, grilles, and other penetrations through ceilings. Keep main runners and carrying channels clear of abutting walls and partitions. Provide at least two main runners for each ceiling span. Wherever required to bypass an object with the hanger wires, install a sususpension system so that all hanger wires will be plumb.

3.1.1 Suspension System

Install suspension system in accordance with ASTM C636/C636M and as specified herein. Do not suspend hanger wires or other loads from underside of steel decking.

3.1.1.1 Plumb Hangers

Install hangers plumb and not pressing against insulation covering ducts and pipes. Where lighting fixtures are supported from the suspended ceiling system, provide hangers at a minimum of four hangers per fixture and located not more than 6 inch from each corner of each fixture.

3.1.1.2 Splayed Hangers

Where hangers must be splayed (sloped or slanted) around obstructions, offset the resulting horizontal force by bracing, countersplaying, or other acceptable means.

3.1.2 Wall Molding

Provide wall molding where ceilings abut vertical surfaces. Miter corners where wall moldings intersect or install corner caps. Secure wall molding not more than 3 inch from ends of each length and not more than 16 inch on centers between end fastenings. Provide wall molding springs at each acoustical unit in semi-exposed or concealed systems.

3.1.3 Acoustical Units

Install acoustical units in accordance with the approved installation instructions of the manufacturer. Ensure that edges of acoustical units are in close contact with metal supports, with each other, and in true alignment. Arrange acoustical units so that units less than one-half width are minimized. Hold units in exposed-grid system in place with manufacturer's standard hold-down clips, if units weigh less than 1 psf or if required for fire resistance rating.

3.1.4 Caulking

Seal all joints around pipes, ducts or electrical outlets penetrating the ceiling. Apply a continuous ribbon of acoustical sealant on vertical web of wall or edge moldings.

3.2 CEILING ACCESS PANELS

Locate ceiling access panels directly under the items which require access.

3.3 CLEANING

Following installation, clean dirty or discolored surfaces of acoustical units and leave them free from defects. Remove units that are damaged or improperly installed and provide units as directed.

3.4 RECLAMATION PROCEDURES

Neatly stack ceiling tile, designated for recycling by the Contracting Officer, on 4 by 4 foot pallets not higher than 4 foot. Panels must be completely dry. Shrink wrap and symmetrically stack pallets on top of each other without falling over.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 09 65 00

RESILIENT FLOORING
08/10, CHG 3: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D2240	(2015; E 2017) Standard Test Method for Rubber Property - Durometer Hardness
ASTM D4078	(2002; R 2015) Water Emulsion Floor Polish
ASTM E648	(2019a) Standard Test Method for Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source
ASTM F1344	(2021a) Standard Specification for Rubber Floor Tile
ASTM F1482	(2021) Standard Practice for Installation and Preparation of Panel Type Underlayments to Receive Resilient Flooring
ASTM F1700	(2020) Standard Specification for Solid Vinyl Floor Tile
ASTM F1859	(2021a) Standard Specification for Rubber Sheet Floor Covering Without Backing
ASTM F1861	(2021) Standard Specification for Resilient Wall Base
ASTM F1869	(2022) Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride
ASTM F1913	(2004; R 2014) Vinyl Sheet Floor Covering Without Backing
ASTM F2170	(2019a) Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes
ASTM F3191	Standard Practice for Field Determination of Substrate Water Absorption (Porosity) for Substrated to Recieve Resilient Flooring
ASTM F710	(2021) Standard Practice for Preparing

	Concrete Floors to Receive Resilient Flooring

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

UNDERWRITERS LABORATORIES (UL)

UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Resilient Flooring and Accessories; G

SD-03 Product Data

Resilient Flooring and Accessories; G

Adhesives

Luxury Vinyl Tile

Wall Base

Luxury Vinyl Tile

Homogeneous Sheet Vinyl

Rubber Tile

SD-04 Samples

Luxury Vinyl Tile; G

Homogeneous Sheet VinyL; G

SD-06 Test Reports

Moisture, Alkalinity and Bond Tests; G

SD-07 Certificates

Indoor Air Quality for Wall Base

Indoor Air Quality for Adhesives

Indoor Air Quality For Luxury Vinyl Tile

Indoor Air Quality For Rubber Tile

SD-08 Manufacturer's Instructions

Surface Preparation; G

Installation; G

SD-10 Operation and Maintenance Data

Resilient Flooring and Accessories; G

1.3 CERTIFICATES

1.3.1 Indoor Air Quality

Submit required indoor air quality certifications and validations in one submittal package.

1.3.1.1 Floor Covering Materials

Provide Luxury Vinyl Tile and wall base products certified to meet indoor air quality requirements by FLOORSCORE, UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification by other third-party programs. Provide current product certification documentation from certification body.

1.3.1.2 Adhesives, Caulking and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the building site in original unopened containers bearing the manufacturer's name, style name, pattern color name and number, production run, project identification, and handling instructions. Store materials in a clean, dry, secure, and well-ventilated area free from strong contaminant sources and residues with ambient air temperature maintained above 65 degrees F and below 85 degrees F, stacked according to manufacturer's recommendations. Remove resilient flooring products from packaging to allow ventilation prior to installation. Protect materials from the direct flow of heat from hot-air registers, radiators and other heating fixtures and appliances. Observe ventilation and safety procedures specified in the MSDS. Do not store rubber surface products with materials that have a high capacity to adsorb volatile organic compound (VOC) emissions. Do not store exposed rubber surface materials in occupied spaces.

1.5 ENVIRONMENTAL REQUIREMENTS

Maintain areas to receive resilient flooring at a temperature above 65 degrees F and below 85 degrees F for 3 days before application, during

application and 2 days after application, unless otherwise directed by the flooring manufacturer for the flooring being installed. Maintain a minimum temperature of 55 degrees F thereafter. Provide adequate ventilation to remove moisture from area and to comply with regulations limiting concentrations of hazardous vapors.

1.6 SCHEDULING

Schedule resilient flooring application after the completion of other work which would damage the finished surface of the flooring.

1.7 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a one year period.

1.8 EXTRA MATERIALS

Provide extra flooring material of each color and pattern at the rate of 5 tiles for each 1000 tiles installed. Provide extra wall base material composed of 20 linear feet of each type, color and pattern. Package all extra materials in original properly marked containers bearing the manufacturer's name, brand name, pattern color name and number, production run, and handling instructions. Provide extra materials from the same lot as those installed. Leave extra stock at the site in location assigned by Contracting Officer.

PART 2 PRODUCTS

2.1 LUXURY VINYL TILE

Conform to ASTM F1700 Class III, Type B, printed film with a minimum wear layer thickness (22 mil) and minimum overall thickness 0.197 inch (embossed)for LVT-1. Conform to ASTM F1700 Class III, Type B, printed film with a minimum wear layer thickness (30 mil) and minimum overall thickness 0.120 inch (embossed)for LVT-2 and LVT-3. Provide tile size as indicated on the drawings. Provide tile with a factory protective finish that enhances cleanability and durability.

Provide Luxury Vinyl Tile that is lead free, mercury free, PFAS free, and phthalate Free.

Provide certification of indoor air quality for Luxury Vinyl Tile.

2.2 HOMOGENEOUS SHEET VINYL

Conform to ASTM F1913, Standard Specification for Vinyl Sheet Floor Covering without Backing. Sheet must have a minimum overall thickness 0.080 inch, with an abrasion resistant surface that does not require polishing or waxing.

2.3 RUBBER TILE

Conform to ASTM F1344 Class 1 homogeneous, Type B (through mottled), 24 inch square. Provide smooth surface. Provide 0.125 inch overall thickness. ASTM D2240 Type A durometer hardness Grade 1, minimum of 85 and not less than required by ASTM F1859. With synthetic rubber, high quality additives, and colorants to meet the performance requirements of

ASTM F 1344.

Provide certification of indoor air quality for Rubber Tile

2.4 WALL BASE

Conform to ASTM F1861, TP (thermoplastic rubber), Style A (straight - installed with carpet), and straight wall base with rubber quarter round installed with resilient flooring. Provide 4 inch high and a minimum 1/8 inch thick wall base with single straight notched profile. Provide 6 inch high wall base in all Command Suites. See architectural drawings for details and locations. Provide job formed corners in matching height, shape, and color.

Provide certification of indoor air quality for Wall Base.

2.5 WALL BASE AT CASEWORK

Conform to ASTM F1861, Type TS (vulcanized thermostat rubber) or TP (thermoset rubber), Style A (straight - installed with carpet), and Style B coved installed with resilient flooring. Provide 4 inch high and a minimum 1/8 inch thick reveal base with a 45 degree angular top and a 7/32 inch wide surface reveal. At expansion joint locations in the floor (each floor level) provide a sanitary toe wall base. See architectural drawings for details. Provide job formed corners in matching height, shape, and color.

2.6 MOULDING

Provide tapered mouldings of rubber and types as recommended by flooring manufacturer for both edges and transitions of flooring materials specified. Provide vertical lip on moulding of maximum 1/4 inch. Provide bevel change in level between 1/4 and 1/2 inch with a slope no greater than 1:2.

2.7 ADHESIVES

Provide adhesives for flooring, base and accessories that are required by the manufacturer and comply with local indoor air quality standards. Adhesive performance requirements must be in compliance with requirements for maximum moisture RH content ASTM F2170, and/or MVE ASTM F1869 per the floor covering manufacturer. Adhesive must be able to tolerate a maximun RH of 90%. Submit manufacturer's descriptive data, documentation stating physical characteristics, and mildew and germicidal characteristics.

Provide certification or validation of indoor air quality for adhesives.

2.7.1 Sheet Vinyl Adhesive

Sheet vinyl adhesive must be applied to a clean, dry and structurally sound substrate that is free of dust, paint, oil and old adhesive. Adhesive and substrate must be acclimated between 65 degrees F and 85 degrees F for 48 hours before and after installation, with RH between 40% and 60%. Adhesive must be solvent-free and allow immediate welding at seams. Sheet vinyl adhesive requires a 100 lb 3 section roller, used in both directions for a proper bond.

2.7.2 Luxury Vinyl Tile Adhesive

Luxury Vinyl Tile adhesive must be applied to a clean, dry and structurally sound substrate that is free of dust, paint, oil and old adhesive.Adhesive and substrate must be acclimated between 65 degrees F and 85 degrees F for 48 hours before and after installation, with RH between 40% and 60%. Adhesive coverage and trowel size must be based on substrate porosity and absorbency in conformance with ASTM F3191. Substrate pH levels must range from 7 to 9. If a moisture/pH resistant cementitious underlayment is required, refer to the maufacturer for best recommendations.

2.8 SURFACE PREPARATION MATERIALS

Provide surface preparation materials, such as floor crack fillers as required by the flooring manufacturer for the subfloor conditions. Comply with ASTM F1482 for panel type underlayment products under a concrete substrate.

2.9 POLISH/FINISH

Provide polish finish as recommended by the manufacturer and conform to ASTM D4078 for polish.

2.10 CAULKING AND SEALANTS

Provide caulking and sealants in accordance with Section 07 92 00 JOINT SEALANTS.

2.11 MANUFACTURER'S COLOR, PATTERN AND TEXTURE

Provide color, pattern and texture for resilient flooring and accessories as indicated on the drawings. Color listed is not intended to limit the selection of equal colors from other manufacturers. Provide floor patterns as specified on the on the drawings. Provide flooring in any one continuous area or replacement of damaged flooring in continuous area from same production run with same shade and pattern. Submit scaled drawings indicating patterns (including location of patterns and colors) and dimensions. Submit manufacturer's descriptive data and three samples of each indicated color and type of flooring, base, mouldings, and accessories sized a minimum 2-1/2 by 4 inch. Submit Data Package 1 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

2.12 FIRE RESISTANCE TESTING REQUIREMENTS

Provide a minimum average critical radiant flux of 0.22 or 0.45 watts per square centimeter for flooring in corridors and exits when tested in accordance with ASTM E648.

PART 3 EXECUTION

3.1 EXAMINATION

Examine and verify that site conditions are in agreement with the design package. Report all conditions that will prevent a proper installation. Do not take any corrective action without written permission from the Government. Work will proceed only when conditions have been corrected and accepted by the installer. Submit manufacturer's printed installation instructions for all flooring materials and accessories, including

preparation of substrate, seaming techniques, and recommended adhesives.

3.2 SURFACE PREPARATION

Provide a smooth, true, level plane for surface preparation of the flooring, except where indicated as sloped. Floor must be flat to within 3/16 inch in 10 feet. Prepare subfloor in accordance with flooring manufacturer's recommended instructions. Prepare the surfaces of lightweight concrete slabs (as defined by the flooring manufacturer) as recommended by the flooring manufacturer. Comply with ASTM F710 for concrete subfloor preparation. Floor fills or toppings may be required as recommended by the flooring manufacturer. Install underlayments, when required by the flooring manufacturer, in accordance with manufacturer's recommended printed installation instructions. Comply with ASTM F1482 for panel type underlayments. Before any work under this section is begun, correct all defects such as rough or scaling concrete, chalk and dust, cracks, low spots, high spots, and uneven surfaces. Repair all damaged portions of concrete slabs as recommended by the flooring manufacturer. Remove concrete curing and sealer compounds from the slabs, other than the type that does not adversely affect adhesion. Remove paint, varnish, oils, release agents, sealers, waxes, and adhesives, as required by the flooring product in accordance with manufacturer's printed installation instructions.

3.3 MOISTURE, ALKALINITY AND BOND TESTS

Prior to installation, determine the suitability of the concrete subfloor for receiving the resilient flooring with regard to moisture content and pH level by moisture and alkalinity tests. Conduct moisture testing in accordance with ASTM F1869 or ASTM F2170, unless otherwise recommended by the flooring manufacturer. A Moisture Vapor Barrier is recommed for use on floors with moisture up to 15 lbs./1000 square feet / 24 hours (ASTM F1869) or 95% RH (ASTM F2170). Conduct alkalinity testing as recommended by the flooring manufacturer. Determine the compatibility of the resilient flooring adhesives to the concrete floors by a bond test in accordance with the flooring manufacturer's recommendations. Concrete substrate must be structurally sound, solid, and meet industry standards as defined in ACI Committee 201 Report "Guide to Durable Concrete". Surface must be free of moisture-sensitive patching and leveling materials, adhesives, coatings, curing compounds, concrete sealers, efflorescence, dust, grease, oils and any other materials or contaminants that can act as bond breakers. Submit copy of test reports for moisture and alkalinity content of concrete slab, and bond test stating date of test, person conducting the test, and the area tested.

3.3.1 Moisture Mitigation

Perform moisture and pH testing in accordance with project specifications. Where test results indicate moisture content above allowable thresholds or a pH of 12.0 or higher, furnish and install a manufacturer-approved moisture mitigation product/system.

3.4 GENERAL INSTALLATION

Do not install building construction materials that show visual evidence of biological growth or until substrate has been properly prepared. Examine substrates and conditions for compliance with requirements for maximum moisture RH content ASTM F2170, and/or MVE ASTM F1869 per the floor covering manufacturer. Verify slab has not been contaminated.

Record and document the following:
1. Perform water bead test and photographically record contact angle of waterbead meniscus to the floor to ensure concrete is hydrophilic.
2. Record alkalinity testing per ASTM F710.
3. Record ambient air RH, dew point and temperature.
4. Record ambient air RH, dew point and temperature
5. Record slab temperature.
6. If substrate preparation is the responsibility of another installer,notify Architect of unsatisfactory preparation before proceeding.
7. Proceed with installation only after unsatisfactory conditions have been corrected. Installation of moisture control system indicates acceptance of surfaces and conditions.

3.5 PLACING LUXURY VINYL TILES

Install luxury vinyl tile flooring and accessories in accordance with manufacturer's printed installation instructions. Prepare and apply adhesives in accordance with manufacturer's directions for installation method specified. Keep tile lines and joints square, symmetrical, tight, and even. Keep each floor in true, level plane, except where slope is indicated. Vary edge width as necessary to maintain full-size tiles in the field, no edge tile to be less than one-half the field tile size, except where irregular shaped rooms make it impossible. Cut flooring to fit around all permanent fixtures, built-in furniture and cabinets, pipes, and outlets. Cut, fit, and scribe edge tile to walls and partitions after field flooring has been applied.

3.6 PLACING WALL BASE

Install wall base in accordance with manufacturer's printed installation instructions. Prepare and apply adhesives in accordance with manufacturer's printed directions. Tighten base joints and make even with adjacent resilient flooring. Fill voids along the top edge of base at masonry walls with caulk. Roll entire vertical surface of base with hand roller, and press toe of base with a straight piece of wood to ensure proper alignment. Avoid excess adhesive in corners.

3.7 CLEANING

Immediately upon completion of installation of flooring in a room or an area, dry and clean the flooring and adjacent surfaces to remove all surplus adhesive. Clean flooring as recommended in accordance with manufacturer's printed maintenance instructions and within the recommended time frame. As required by the manufacturer, apply the recommended number of coats and type of polish and finish in accordance with manufacturer's written instructions.

3.8 PROTECTION

From the time of installation until acceptance, protect flooring from damage as recommended by the flooring manufacturer. Remove and replace flooring which becomes damaged, loose, broken, or curled and wall base which is not tight to wall or securely adhered.

-- End of Section --

SECTION 09 66 23

RESINOUS MATRIX TERRAZZO FLOORING
08/16, CHG 1: 08/18

PART 1 GENERAL

1.1 SUMMARY

Apply resinous terrazzo flooring, in the colors indicated, in the areas shown on the detail drawings. Submit two 4 x 4 inches, (minimum) samples of each color of resinous terrazzo and two 6 inches lengths, of each type of strip. Flooring must be an epoxy terrazzo system that conforms to the requirements specified in paragraphs 2.01A and B of NTMA Info Guide .

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D56	(2016a) Standard Test Method for Flash Point by Tag Closed Cup Tester

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 99	(2021; TIA 20-1) Health Care Facilities Code

NATIONAL TERRAZZO AND MOSAIC ASSOCIATION (NTMA)

NTMA Info Guide	(2017) Terrazzo Reference Guide

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1113	(2016) Architectural Coatings

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings; G

Strips; G

Control Joint Strips; G

SD-03 Product Data

Resin

Mixing, Proportioning, and Installation

Cleaning and Sealing

SD-04 Samples

Resinous Terrazzo Flooring

SD-06 Test Reports

Certified Test Reports; G

SD-07 Certificates

Qualifications of Installer; G

1.4 QUALITY ASSURANCE

Applicator must be approved by the resin manufacturer and shall have a minimum of 3 years experience in the application of the materials to be used and must have completed 8 successful installations within the past 2 years. Furnish a written statement from the manufacturer detailing the Qualifications of Installer.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the project site in manufacturer's original unopened containers. Keep materials in a clean, dry, area with temperatures controlled between 50 and 90 degrees F.

1.6 ENVIRONMENTAL REQUIREMENTS

Maintain areas to receive terrazzo at a temperature above 50 degrees F for 2 days prior to installation and for 7 days following installation.

PART 2 PRODUCTS

2.1 PRIMER

Primer must be a material recommended by the resin manufacturer which will penetrate the pores of the substrate and bond with the topping to form a permanent monolithic bond between the substrate and the topping. Primer products used on the interior of the building (defined as inside of the weatherproofing system) must meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1113.

2.2 RESIN

Resin for the specified terrazzo flooring must conform to the requirements shown in NTMA Info Guide.

2.3 FILLERS

Fillers, if required, must be inert mineral or cellulosic material as recommended by the manufacturer and best suited for the resin binder used. Fillers must be furnished in the quantity necessary to impart the required color and physical characteristics.

2.4 MARBLE CHIPS

Marble chips must be of domestic origin of sizes and colors to match NTMA Info Guide color on the drawings. Chips must be a range of sizes up to and including the NTMA Standard No. 0 and Standard No. 1 for 1/4 inch thick floors and Standard No. 0 through Standard No. 2 for 3/8 inch thick floors.

2.5 STRIPS

Submit drawings indicating the type, size, and layout of divider strips and control joint strips.

2.5.1 Divider Strips

Divider strips must be as deep as required, 16 gauge and of zinc and finished in a satin anodized color as indicated on the drawings.

2.5.2 Control Joint Strips

Control joint strips must be as deep as required, 16 gauge and of zinc and finished in a satin anodized color as indicated on the drawings.

2.6 GROUT

Grout must be as recommended by the manufacturer of the resin.

2.7 SEALER

Sealer must have a pH factor between 7 and 10 and must be a penetrating type specially prepared for use on terrazzo. The sealer must not discolor or amber the terrazzo and must produce a slip resistant surface. Flash point of sealer must be a minimum of 80 degrees F when tested in accordance with ASTM D56.

PART 3 EXECUTION

3.1 PREPARATION OF CONCRETE SUBFLOOR

Do not commence installation of the floor topping until the concrete substrate has cured for at least 28 calendar days. Prepare the concrete surfaces in accordance with the instructions of the resin manufacturer.

3.2 MIXING, PROPORTIONING, AND INSTALLATION

Mixing, proportioning, and installing must be in accordance with the approved instructions of the manufacturer. Chips must be applied with a double broadcast system. Install strips in locations indicated. Apply the topping to give a finish thickness of 3/8 inch. Bases shall be precast 4 foot long pieces and shall be 4 inch high.

3.3 TESTING

Between 30 and 45 days after flooring installation is completed, and prior to its use, test the conductive resinous terrazzo flooring in accordance with paragraph 12-4.1.3.8(b)(7) of NFPA 99. The resistance of the conductive floor at any one location must be more than 5,000 ohms in areas with 110 volts service, more than 10,000 ohms in areas with 220 volt service, and average less than 1,000,000 ohms and more than 25,000 ohms in all areas. Submit certificates indicating conformance with specified requirements. Accompany certificates with certified test reports showing that the conductive resinous terrazzo floor has been tested and meets the requirements specified.

3.4 CLEANING AND SEALING

Wash the terrazzo with a neutral cleaner and where required, clean with a fine abrasive to remove any stains or cement smears. Rinse the cleaned surfaces. When dry, apply a terrazzo sealer in accordance with the manufacturer's directions. Submit maintenance literature for terrazzo cleaning and sealing.

3.5 PROTECTION

cover and protect the terrazzo work from damage until completion of the work of all other trades.

-- End of Section --

SECTION 09 67 23.13

STANDARD RESINOUS FLOORING
11/19

PART 1 GENERAL

1.1 ADMINISTRATIVE REQUIREMENTS

1.1.1 Pre-Installation Meetings

Pre-installation Conference: Conduct conference at Project site.

1.1.2 Product Data

Within 30 days of contract award, submit manufacturer's catalog data for the following items:

a. Epoxy-Resin Binder/Matrix

b. Cured Epoxy Binder

c. Aggregate

d. Surface Sealing Coat

1.1.3 Design Mix Data

Within 30 days of contract award, submit design mix data for the following items, including a complete list of ingredients and admixtures:

a. Epoxy Resin

b. Amine Curing Agent

c. Non-Silica Aggregates

d. Conductive Element

Ensure applicable test reports verify the mix has been successfully tested and meets design requirements.

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation Drawings; G

Fabrication Drawings; G

SD-03 Product Data

Manufacturer's Catalog Data; G

SD-04 Samples

Hardboard Mounted Epoxy Flooring; G

SD-05 Design Data

Design Mix Data; G

SD-07 Certificates

Listing of Product Installations

Referenced Standards Certificates

SD-11 Closeout Submittals

Warranty; G

1.3 DELIVERY, STORAGE, AND HANDLING

Protect materials from weather, soil, and damage during delivery, storage, and construction. Deliver materials in original packages, containers, or bundles bearing brand name and name of material.

Maintain materials used in the installation of floor topping at a temperature between 65 and 85 degrees F.

1.4 QUALITY CONTROL

Prior to commencement of work, submit referenced standards certificates for the following, showing conformance with the referenced standards contained in this section:

The ROICC reserves the right to randomly core the floor for thickness verification. The correction of any deficiencies are the responsibility of the Contractor. Areas found to be in compliance shall be repaired at the expense of the Government.

1.4.1 Qualifications

Submit a listing of product installations for heavy duty epoxy flooring including identification of at least 5 units, similar to those proposed for use, that have been in successful service for a minimum period of 5 years. Identify purchaser, address of installation, service organization, and date of installation.

Ensure floor system applicators are experienced in the application of troweled aggregate thin-set floor topping.

1.4.2 Sampling

Submit hardboard mounted epoxy flooring samples not less than 12 inch square for each required color.

Provide panels showing nominal thickness of finished toppings, color, and texture of finished surfaces. Finished floor toppings and the approved samples are to match in color and texture.

1.5 WARRANTY

Submit a 2 year written warranty for all materials and installation work.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Submit installation drawings for heavy duty epoxy flooring systems clearly designating the areas of application and the installation plan. Include in the installation plan, methods to control sand and dust if sand blasting is required.

Submit fabrication drawings for heavy duty epoxy flooring Systems consisting of fabrication and assembly details to be performed in the factory.

2.2 RESINOUS FLOORING

Resinous flooring spec shall be a nominal 1/4" thick system comprised of a high performance, four-component,high solids epoxy.

2.2.1 Physical Properties

Provide flooring system in which physical properties of topping including aggregate, when tested in accordance with standards or procedures referenced below, are as follows:

Compressive Strength (ASTM C579)_____9,500 psi
Tensile Strength (ASTM C307)_____1,700 psi
Hardness (ASTM D2240/Shore D Durometer) _____75-80
Resistance to Yellowing as measured using ASTM D2244 after 1000 consecutive hours UV exposure in QUV, ASTM G154, <10 increase of yellow units (CIE Lab) if pigmented topcoat.

2.2.2 Static Control Properties

Surface Resistance .....0.025 to 1.0 megaohms
(Test Method, ESD-S7.1)
Spark Generation..... No visible sparks
(NFGS-09965)

PART 3 EXECUTION

3.1 PREPARATION

Prior to applying resinous flooring material, inspect substrate and immediately report any unsatisfactory conditions that exist and repair.

3.1.1 Safety Precautions

Prior to application in confined spaces of toppings and coatings containing flammable or toxic properties, institute safety precautions recommended by the manufacturer of the product.

Erect "NO SMOKING" signs, and prohibit smoking or use of spark- or flame-producing devices within 50 feet of any mixing or placing operation

involving flammable materials.

Provide the personnel required to handle, mix, or apply toppings containing toxic or flammable properties with such items of personal protective equipment and apparel for eye, skin, and respiratory protection as are recommended by the manufacturer of the product. Ensure all personnel are trained in the appropriate use and wearing of personal protection equipment.

3.1.2 Protection of Adjacent Surfaces

In addition to the protection of adjacent surfaces during installation, provide areas used to store and mix materials with a protective covering under the materials. After application of the sealer coats, protect finished flooring during the remainder of the construction period. In areas of expected minimum or moderate traffic, cover floors with 70 pound kraft paper, a 30-30-30 waterproof kraft paper or an approved substitute, with strips taped together and edges secured to prevent roll-up. Place vegetable fiberboard, plywood, or other suitable material that does not mar the flooring over the paper to protect areas used as passages by workmen and areas subject to floor damage because of subsequent building operations. Upon completion of construction, remove the protection, clean flooring and, where necessary, repair, reseal, or both, at no additional cost to the Government.

3.1.3 Concrete Subfloor

3.1.3.1 Existing Concrete Floors

Concrete preparation shall be by mechanical means and include use of a scabbler, scarifier or shot blast machine for removal of bond inhibiting materials such as curing compounds or laitance. Fill all cracks with an elastomeric jointing compound compatible with the resinous flooring system used.

3.2 APPLICATION

3.2.1 Areas of Application

Anchor plates set with the top surface at or above the finished epoxy floor level do not require coverage with this flooring material. Extend flooring under equipment, except when the equipment base is indicated to be flush against the structural floor. Cover and/or mask surfaces not to receive the epoxy floor topping, such as equipment or cabinets installed prior to surface-preparation efforts and adjacent to the flooring installation.

3.2.2 Application of Prime Coat and Troweling

Combine the epoxy binder components A and B in the proportions specified by the manufacturer to form a clear compatible system immediately on mixing. Cure combined components to a clear film possessing a glossy, non-greasy surface at relative humidities less than 80 percent, having the following properties after curing 24 hours at 77 degrees F, followed by 24 hours at 125 degrees F:

Ensure that the prepared subfloor surface is dry and at a temperature of not less than 60 degrees F when application of the floor topping is initiated. Immediately before application of the prime/scratch coat on

the prepared surface, remove dust or other loose particles by blowing with compressed air or vacuum cleaned. Use only an air compressor equipped with an efficient oil-water trap to prevent oil contamination or wetting of surface.

Apply a thin roller coat of the epoxy binder specified to the prepared subfloor as a prime coat. As an aid to placing, compacting, and finishing the floor topping, form a scratch coat by sprinkling a minimum quantity of the walnut shell aggregate on the prime coat surface immediately following the prime coat application. Prior to application of the prime/scratch coat, fill cracks in the concrete per manufacturer's instructions, and make provisions to keep control or expansion joints open.

Place the floor topping prior to final gelling of the prime/scratch coat. Immediately after the materials are mixed as specified, dump the mixture in the placement area and spread to prolong troweling life. Screed or rough trowel placed materials to the specified thickness and then compact by the use of a smooth roller prior to finish troweling to a nominal thickness of 3/16 inch plus or minus 1/16 inch. Ensure all finished surfaces are free of ridges, hollows (bird-baths), trowel marks, and smoothness varies no more than 1/8 inch when tested with an 8 foot straightedge. Make provisions to maintain the work areas in a relatively dust-free environment during curing of the topping.

3.2.3 Sealer Coat

After the floor topping has set firmly (approximately 6 to 16 hours depending on subfloor temperature) in a relatively dust-free environment, apply two thin coats of the sealer coat, by means of brush, roller, squeegee, or notched trowel to provide a pore-free, easy-to-clean surface. At the time of sealer application, ensure that the surface is dust-free. Depending on relative humidity, allow the applied sealer to cure to a tack-free condition in 2 to 4 hours. Do not apply second coat until after the initial coat has cured to a tack-free, hard film. Maintain topping areas in a relatively dust-free environment during curing of the sealer coats.

3.3 FIELD QUALITY CONTROL

3.3.1 Repairing

Remove and replace damaged or unacceptable portions of completed work with new work to match adjacent surfaces at no additional cost to the Government.

3.4 ADJUSTING AND CLEANING

Clean surfaces of the new work, and adjacent surfaces soiled as a result of the work. Remove all equipment, surplus materials, and rubbish associated with the work from the site.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 09 68 00

CARPET TILE
11/17, CHG 2: 08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF TEXTILE CHEMISTS AND COLORISTS (AATCC)

AATCC 16	(2004; E 2008; E 2010) Colorfastness to Light
AATCC 134	(2016) Electrostatic Propensity of Carpets
AATCC 174	(2016) Antimicrobial Activity Assessment of New Carpets

ASTM INTERNATIONAL (ASTM)

ASTM D297	(2015; R 2019) Rubber Products - Chemical Analysis
ASTM D3278	(1996; R 2011) Flash Point of Liquids by Small Scale Closed-Cup Apparatus
ASTM D3574	(2017) Standard Test Methods for Flexible Cellular Materials—Slab, Bonded, and Molded Urethane Foams
ASTM D3676	(2013) Rubber Cellular Cushion Used for Carpet or Rug Underlay
ASTM D5793	(2018) Standard Test Method for Binding Sites Per Unit Length or Width of Pile Yarn Floor Coverings
ASTM D5848	(2020) Standard Test Method for Mass Per Unit Area of Pile Yarn Floor Coverings
ASTM D6859	(2011) Standard Test Method for Pile Thickness of Finished Level Pile Yarn Floor Coverings
ASTM D7330	(2015) Standard Test Method for Assessment of Surface Appearance Change in Pile Floor Coverings Using Standard Reference Scales

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile

	Organic Chemical Emissions from Indoor Sources using Environmental Chambers

CARPET AND RUG INSTITUTE (CRI)

CRI 104	(2015) Carpet Installation Standard for Com mercial Carpet
CRI 105	(2015) Carpet Installation Standard for Residential Carpet
CRI GLP QM	(2017) Green Label Plus Quality Manual
CRI Test Method 103	(2015) Standard Test Method for the Evaluation of Texture Appearance Retention of Carpet Standards Program

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1113	(2016) Architectural Coatings
SCAQMD Rule 1168	(2022) Adhesive and Sealant Applications

UNDERWRITERS LABORATORIES (UL)

UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation Drawings; G

SD-03 Product Data

Carpet Tile; G

Recycled Content for Carpeting

Moldings; G

Indoor Air Quality for Aerosol Adhesives

Indoor Air Quality for Non-Aerosol Adhesives

Indoor Air Quality for Concrete Primer

SD-04 Samples

Moldings; G

Carpet Tile;; G

SD-06 Test Reports

Moisture and Alkalinity Tests; G

SD-07 Certificates

Indoor Air Quality for Carpet

SD-08 Manufacturer's Instructions

Surface Preparation

SD-10 Operation and Maintenance Data

Cleaning and Protection

SD-11 Closeout Submittals

Warranty

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality Certifications

1.3.1.1 Floor Covering Materials

Provide carpet tile with an attached cushion certified to meet indoor air quality requirements by UL 2818 (GreenGuard) Gold, SCS Global Services Indoor Advantage Gold, CRI GLP QM or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the site in the manufacturer's original wrappings and packages clearly labeled with the manufacturer's name, brand name, size, dye lot number, and related information. Remove materials from packaging and store them in a clean, dry, well ventilated area protected from damage, soiling, and moisture, and maintain at a temperature above 60 degrees F for 2 days prior to installation. Do not store carpet near materials that may off gas or emit harmful fumes, such as kerosene heaters, fresh paint, or adhesives.

1.5 AMBIENT CONDITIONS

Maintain areas in which carpeting is to be installed at a temperature above 60 degrees F and below 90 degrees F for 2 days before installation, during installation, and for 2 days after installation. Provide temporary ventilation during work of this section. Maintain a minimum temperature of 55 degrees F thereafter for the duration of the contract.

1.6 WARRANTY

Provide manufacturer's standard performance guarantees or warranties including minimum ten year wear warranty, two year material and workmanship and ten year tuft bind and delamination.

PART 2 PRODUCTS

2.1 CARPET TILE

Furnish first quality carpet that is free of visual blemishes, streaks, poorly dyed areas, fuzzing of pile yarn, spots or stains, and other physical and manufacturing defects. Provide carpet materials and treatments as reasonably nonallergenic and free of other recognized health hazards. Provide a static control construction on all grade carpets which gives adequate durability and performance. Submit manufacturer's catalog data and printed documentation stating physical characteristics, durability, resistance to fading, and flame resistance characteristics for each type of carpet material and installation accessory. Submit manufacturer's Product Data for 1) Carpet, 2) Moldings, and 3) Carpet Cushion. Also, submit Samples of the following:

a. Carpet: Two full sized "Production Quality" samples of each carpet proposed for use, showing quality, pattern, and color specified

b. Carpet Cushion: Two samples minimum 6 by 6 inches

2.1.1 Recycled Content

Carpet tile must contain a minimum of 40 percent recycled content. Provide data identifying percentage of recycled content for carpeting.

2.1.2 Indoor Air Quality Requirements

Products must meet emissions requirements of CDPH SECTION 01350. Provide certification or validation of indoor air quality for carpet.

2.1.3 Physical Characteristics for Modular Tile Carpet

2.1.3.1 Carpet Construction

Tufted Textured Loop

2.1.3.2 Type

Modular tile (refer to drawing for sizes).

2.1.3.3 Pile Type

Multilevel loop

2.1.3.4 Pile Fiber

Commercial 100 percent branded (federally registered trademark) nylon continuous filament.

2.1.3.5 Gauge or Pitch

Minimum 1/10 inch in accordance with ASTM D5793

2.1.3.6 Stitches or Rows/Wires

Minimum 14 per square inch

2.1.3.7 Pile Density

Minimum 7,000 ounces per square yard. This does not include weight of backings. Determine weight in accordance with ASTM D5848.

2.1.3.8 Pile Thickness

Minimum 0.33 inch in accordance with ASTM D6859

2.1.3.9 Dye Method

Solution dyed

2.1.3.10 Backing Materials

Provide primary backing materials like those customarily used and accepted by the trade for each type of carpet. Provide secondary backing to suit project requirements of those customarily used and accepted by the trade for each type of carpet .

2.1.3.11 Attached Cushion

Provide an attached cushion mechanically frothed polyurethane with minimum weight of 18 oz/sq. yard in accordance with ASTM D3574, minimum thickness of 0.125 inch, and maximum compression resistance of 5 psi, and compression set of 15 percent in accordance with ASTM D3676. Do not exceed the maximum ash content of 50 percent when tested in accordance with ASTM D297. Cushion must be PVC free.

2.2 PERFORMANCE REQUIREMENTS

2.2.1 Texture Appearance Retention Rating (TARR)

Provide carpet with a greater than or equal to 3.5 (Severe) TARR traffic level classification in accordance with ASTM D7330 or CRI Test Method 103.

2.2.2 Static Control

Provide static control to permanently regulate static buildup to less than 3.0 kV when tested at 20 percent relative humidity and 70 degrees F in accordance with AATCC 134.

2.2.3 Colorfastness to Light

Comply colorfastness to light with AATCC 16, Test Option E "Water-Cooled Xenon-Arc Lamp, Continuous Light" and with a minimum 4 grey scale rating after 40 hours.

2.2.4 Antimicrobial

Nontoxic antimicrobial treatment in accordance with AATCC 174 Part I (qualitative), guaranteed by the carpet manufacturer to last the life of the carpet.

2.3 ADHESIVES AND CONCRETE PRIMER

Comply with applicable regulations regarding toxic and hazardous materials. Provide water resistant, mildew resistant, nonflammable, and nonstaining adhesives and concrete primers for carpet installation as required by the carpet manufacturer. Provide release adhesive for modular tile carpet as recommended by the carpet manufacturer. Provide adhesives flashpoint of minimum 140 degrees F in accordance with ASTM D3278. Non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) must meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) must meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of GS-36. Provide validation of indoor air quality for aerosol adhesives. Provide validation of indoor air quality for non-aerosol adhesives. Concrete primer products used on the interior of the building (defined as inside of the weatherproofing system) must meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1113. Provide validation of indoor air quality for concrete primer.

2.4 MOLDINGS

Provide carpet moldings where floor covering material changes or carpet edge does not abut a vertical surface. Provide transitions according to the drawings.

2.5 COLOR, TEXTURE, AND PATTERN

Provide color, texture, and pattern in accordance with the drawings.

PART 3 EXECUTION

3.1 SURFACE PREPARATION

Do not install carpet on surfaces that are unsuitable and will prevent a proper installation. Prepare subfloor in accordance with flooring manufacturer's recommended instructions. Repair holes, cracks, depressions, or rough areas using material recommended by the carpet or adhesive manufacturer. Free floor of any foreign materials and sweep clean. Before beginning work, test subfloor with glue and carpet to determine "open time" and bond. Submit three copies of the manufacturer's printed Installation instructions for the carpet, including Surface Preparation, seaming techniques, and recommended adhesives.

3.2 MOISTURE AND ALKALINITY TESTS

Test concrete slab for moisture content and excessive alkalinity in accordance with CRI 104/CRI 105. Submit three copies of reports of Moisture and Alkalinity Tests including content of concrete slab stating date of test, person conducting the test, and the area tested.

3.3 PREPARATION OF CONCRETE SUBFLOOR

Do not commence installation of the carpeting until concrete substrate is at least 90 days old. Prepare the concrete surfaces in accordance with the carpet manufacturer's instructions. Match carpet, when required, and adhesives to prevent off-gassing to a type of curing compounds, leveling agents, and concrete sealer.

3.4 INSTALLATION

Perform all work by manufacturer's approved installers. Conduct installation in accordance with the manufacturer's printed instructions and CRI 104/CRI 105. Protect edges of carpet meeting hard surface flooring with molding and install in accordance with the molding manufacturer's printed instructions. Follow ventilation, personal protection, and other safety precautions recommended by the adhesive manufacturer. Continue ventilation during installation and for at least 72 hours following installation. Do not permit traffic or movement of furniture or equipment in carpeted area for 24 hours after installation. Complete other work which would damage the carpet prior to installation of carpet. Submit three copies of Installation Drawings for 1) Carpet, 2) Carpet Cushion, and 3) Moldings indicating areas receiving carpet, carpet types, patterns, direction of pile, location of seams, and locations of edge molding.

Do not install building construction materials that show visual evidence of biological growth.

3.4.1 Modular Tile Installation

Install modular tiles with manufacturer approved adhesive tab system permanent vinyl-compatible adhesive and snug joints. Refer to drawings for installation method. Comply with manufacturer installation instructions for required drying time of releasable adhesive so it sets up properly. Provide accessibility to the subfloor where required.

3.5 CLEANING AND PROTECTION

Submit three copies of carpet manufacturer's maintenance instructions describing recommended type of cleaning equipment and material, spotting and cleaning methods, and cleaning cycles.

3.5.1 Cleaning

As specified in Section 01 78 00 CLOSEOUT SUBMITTALS. After installation of the carpet, remove debris, scraps, and other foreign matter. Remove soiled spots and adhesive from the face of the carpet with appropriate spot remover. Cut off and remove protruding face yarn. Vacuum carpet clean.

3.5.2 Protection

Protect the installed carpet from soiling and damage with heavy, reinforced, nonstaining kraft paper, plywood, or hardboard sheets. Lap and secure edges of kraft paper protection to provide a continuous cover. Restrict traffic for at least 48 hours. Remove protective covering when directed by the Contracting Officer.

3.6 REMNANTS

Manage waste as specified in the Waste Management Plan. Provide remnants remaining from the installation, consisting of scrap pieces more than 2 feet in dimension with more than 6 square feet total to local non-profit such as Habitat for Humanity as directed by the Government.

3.7 MAINTENANCE

3.7.1 Extra Materials

Provide extra material from same dye lot consisting of uncut carpet tiles for future maintenance. Provide a minimum of three percent of total square yards of each carpet type, pattern, and color. Furnish three percent extra of total adhesive tabs.

-- End of Section --

SECTION 09 69 13

RIGID GRID ACCESS FLOORING
11/15, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7-16	(2017; Errata 2018; Supp 1 2018) Minimum Design Loads and Associated Criteria for Buildings and Other Structures

ASTM INTERNATIONAL (ASTM)

ASTM A780/A780M	(2020) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM E648	(2019a) Standard Test Method for Critical Radiant Flux of Floor-Covering Systems Using a Radiant Heat Energy Source
ASTM F150	(2006; R 2013) Standard Test Method for Electrical Resistance of Conductive and Static Dissipative Resilient Flooring

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

CEILINGS AND INTERIOR SYSTEMS CONSTRUCTION ASSOCIATION (CISCA)

CISCA Access Floors	(2007) Recommended Test Procedures for Access Floors

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

ICC EVALUATION SERVICE, INC. (ICC-ES)

ICC-ES AC300	(2014) Acceptance Criteria for Access Floors

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2024) International Building Code

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 99	(2021; TIA 20-1) Health Care Facilities Code
NFPA 253	(2011) Standard Method of Test for Critical Radiant Flux of Floor Covering Systems Using a Radiant Heat Energy Source

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2022) Adhesive and Sealant Applications

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-301-01	(2023; with Change 6, 2026) Structural Engineering

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detailed Installation Drawings; G

Fabrication Drawings; G

SD-03 Product Data

Access Flooring System; G

Recycled Content of Access Flooring System; S

Indoor Air Quality For Pedestal Adhesive; S

Indoor Air Quality For Adhesives; S

SD-04 Samples

Floor Panels

Floor Covering; G

Panel Support System

Cut Outs; G

SD-05 Design Data

Seismic Calculations

SD-06 Test Reports

Factory Tests

Concentrated Load

Uniform Live Load

Rolling Load

Impact Load

Ultimate Load

Stringer Load

Pedestal Axial Load

Bonding Strength of Pedestal Adhesive

Electrical Resistance

Field Tests

SD-07 Certificates

Compliance with ICC-ES AC300

Compliance with ICC IBC

Certificate of Compliance

Qualification of Manufacturer

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G

SD-11 Closeout Submittals

Lifting Device

Warranty; G

1.3 SPARE PARTS

Provide 4 floor panels complete with specified floor covering for future use. Provide extra carpet tile from same dye lot consisting of uncut tiles for future maintenance. Provide a minimum of 3 percent of total square yards of each carpet type, pattern, and color. Furnish 5 percent extra of total adhesive tabs and 1 percent extra of total components required for installing carpet tile.

1.4 QUALITY CONTROL

1.4.1 Qualification of Manufacturer

Access flooring manufacturer must have at least 5 years experience in manufacturing access flooring systems. Certify that the manufacturer of the access flooring system meets requirements specified under paragraph entitled QUALIFICATION OF MANUFACTURER.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver materials to site in undamaged condition, in original containers or packages, complete with accessories and instructions. Label packages with manufacturer's name and brand designations. Package materials covered by specific references bearing specification number, type and class as applicable.

1.5.2 Storage

Store all materials in original protective packaging in a safe, dry, and clean location. Store panels at temperatures between 40 and 90 degrees F, and between 20 and 70 percent humidity. Replace defective or damaged materials.

1.5.3 Handling

Handle and protect materials in a manner to prevent damage during the entire construction period.

1.6 WARRANTY

Minimum manufacturer warranty must have no dollar limit, cover full system, and must have a minimum duration of 5 years. Include an agreement to repair or replace floor panels, pedestals or stringers that fail within the warranty period in the standard performance guarantee or warranty. Failures include, but are not limited to, sagging and warping of panels; rusting and manufacturers defects of panels or support system. For carpet tile provide manufacturer's standard performance guarantees or warranties including a minimum two years for material and workmanship and ten years for wear, static control, tuft bind and delamination.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

a. Provide for self-alignment of floor panels, adjustable pedestals and readily removable floor panels covered as specified.

b. Lateral stability of floor support system must be independent of panels. Provide a finished assembly that is rigid and free of vibration, noises, and rocking panels.

c. Submit certificate of compliance attesting that the installed access floor system meets specification requirements, including all special equipment loads and specific electrical and or cable requirements for the complete access flooring system including, but not limited to the following:

(1) Compliance with ICC-ES AC300 and Compliance with ICC IBC Acceptance Criteria for Access Floors.

(2) Load-bearing capabilities of pedestals, floor panels, and pedestal adhesive resisting force.

(3) Supporting independent laboratory test reports. For panel, stringer and pedestal load test results include concentrated loads at center of panel, panel edge midpoint, ultimate loads and

uniform loads.

(4) Floor electrical characteristics.

(5) Material requirements.

(6) An elevated floor system free of defects in materials, fabrication, finish, and installation, that will remain so for a period of not less than 5 years after completion.

d. Submit manufacturer's product data for access flooring system consisting of descriptive data, catalog cuts, and installation instructions. Include in the data information about any design and production techniques, total system including all accessories and finish coatings of under-floor components, procedures and policies used to conserve energy, reduce material, improve waste management or incorporate green building/recycled products into the manufacturer of their components or products. Include cleaning and maintenance instructions. Systems which contain zinc electroplated anti-corrosion coatings are prohibited.

2.1.1 Design Requirements

Provide a nominal 1 foot, 0 inch rigid grid access flooring for Building A1, Classroom 173.

Conduct floor panel testing in accordance with CISCA Access Floors. When tested as specified, make all deflection and deformation measurements at the point of load application on the top surface of the panel. Floor panels must be capable of supporting the following loads:

a. Concentrated load of2000 pounds on one square inch, at any point on panel, without a top-surface deflection more than 0.10 inch, and a permanent set not to exceed 0.01 inch in any of the specified tests. Testing must be in accordance with CISCA Access Floors, Section 1 Concentrated Loads with test panels being supported by understructure to be used with installed system instead of steel support blocks.

b. Uniform live load of 350 psf, without a top-surface deflection more than 0.06 inch, and a permanent set not to exceed 0.01 inch in any of the specified tests, when tested in accordance with CISCA Access Floors, Section 7 Uniform Load Test with test panels being supported by understructure to be used with installed system instead of steel support blocks.

c. A rolling load of 1100 pounds applied through hard rubber surfaced wheel 6 inch diameter by 2 inch wide for 10,000 cycles over the same path. Permanent set at conclusion of test must not exceed 0.040 inch when tested in accordance with CISCA Access Floors, Section 3 Rolling Loads.

d. A rolling load of 1500 pounds applied through a 3 inch diameter by 1-13/16 inch wide caster for 10 cycles over the same path, without developing a local overall surface deformation greater than 0.04 inch. In accordance with CISCA Access Floors, Section 3 Rolling Loads, the permanent deformation limit under rolling load must be satisfied in all of the specified tests.

e. An impact load of 200 pounds anywhere on the panel dropped from a

height of 36 inches onto a 1 square inch area without failure of the system, according to CISCA Access Floors, Section 8 Drop Impact Load Test.

f. Ultimate Load. Panels must meet manufactures published Ultimate Load rating of 4000 pounds when tested in accordance with CISCA Access Floors, Section 2 Ultimate Loading.

g. Safety Factor. Panels must provide a minimum Safety Factor of 5 times the uniform load specified above in accordance with ICC-ES AC300.

h. Recycled Content. Provide Access Flooring System (panels, stringers and pedestals) containing a minimum of 20 percent recycled content. Provide data identifying percentage of recycled content of access flooring system.

2.1.2 Allowable Tolerances

2.1.2.1 Floor Panel Flatness

Plus or minus 0.035 inches on diagonal on top of panel or underneath edge.

2.1.2.2 Floor Panel Length

Plus or minus 0.015 inch.

2.1.2.3 Floor Panel Squareness

Plus or minus 0.02 inch in panel length.

2.1.3 Stringers

Provide stringers capable of supporting a 450 pound concentrated load at midspan without permanent deformation in excess of 0.010 inch, when tested in accordance with CISCA Access Floors, Section 4 Stringer Load Testing.

2.1.4 Pedestals

Pedestals must be capable of supporting a 5000 pound axial load without permanent deformation, when tested in accordance with CISCA Access Floors, Section 5 Pedestal Axial Load Test.

2.1.5 Bonding Strength of Pedestal Adhesive

Adhesive for anchoring pedestal bases must have a bonding strength capable of resisting an overturning moment of 1,000 lbf-in when a force is applied to the top of the pedestal in any direction, when tested in accordance with CISCA Access Floors, Section 6 Pedestal Overturning Moment Test. Pedestal adhesive must meet emissions requirement of CDPH SECTION 01350 (use the office or classroom requirements, regardless of space type). Provide validation of indoor air quality for pedestal adhesive.

2.1.6 Bond Strength of Factory Installed Covering

Bond strength of floor covering must be sufficient to permit handling of the panels by use of the panel lifting device, and to withstand moving caster loads up to800 pounds, without separation of the covering from the panel.

2.1.7 Seismic Calculations

2.1.7.1 Navy Project Specific Requirements

Submit seismic calculations for lateral bracing, sealed by a Professional Engineer. Document that access flooring system complies with seismic requirements of ICC IBC and ASCE 7-16 for Occupancy Importance Factor (Ip) of 1.5, and seismic horizontal force (Fp) determined in accordance with UFC 3-301-01 and Section 1615 of the ICC IBC and ASCE 7-16, Minimum Design Loads for buildings and other structures.

2.2 FLOOR PANELS

2.2.1 Floor System Drawings And Planer Quality

a. Submit Fabrication Drawings for elevated floor systems consisting of fabrication and assembly details to be performed in the factory.

b. Indicate on Location Drawings exact location of pedestals, ventilation openings, cable cutouts, and the panel installation pattern.

c. Provide Detail Drawings showing details of the pedestals, pedestal-floor interlocks, floor panels, panel edging, floor openings, floor opening edging, floor registers, floor grilles, cable cutout treatment, perimeter base, expansion, and peripheral support facilities.

d. Design and workmanship of the floor, as installed, must be completely planar within plus or minus 0.060 inch in 10 feet, 0.100 inch for the entire floor, and 0.030 inch across panel joints.

e. Floor-panel joint-width tolerances must not exceed 0.017 inch as measured with a feeler gage at any point in any joint when the panels are installed and as long as the air leakage requirements specified in this section are met.

f. Submit 1 complete samples of floor panels.

2.2.2 Detailed Installation Drawings

Submit Detailed Installation Drawings that as a minimum indicate the following:

a. Location of panels

b. Layout of supports, panels, and cutout locations

c. Stair, handrail, and ramp framing

d. Sizes and details of components

e. Details at floor perimeter and height above structural floor

f. Method of anchorage to structural subfloor

g. Lateral bracing

h. Typical cutout details

i. Gasketing, return air grilles, supply air registers, and perforated panels. Include air transfer capacity of grilles, registers and panels

j. Description of factory coating

k. Floor finishes

l. Location of connection to building grounding electrode

2.2.3 Panel Construction

a. Base access floor system on a 24 by 24 inch square module providing minimum of 12 inch clearance between structural floor and underside of panel and stringer. Fabricate so accurate job cutting and fitting may be done using standard sizes for perimeters and around columns.

b. Do not expose metal on finished top surface of panels. Provide cutouts and cutout closures to accommodate utility systems and equipment intercabling. Reinforce cutouts to meet design load requirements. Provide extra support pedestals at each corner of cutout for cutout panels that do not meet specified design load requirements.

c. Panel design must provide for convenient panel removal for underfloor servicing and for openings for new equipment. Use panels of uniform dimensions within specified tolerances. Permanently mark panels to indicate load rating and model number.

d. Machine square floor panels to within plus or minus 0.015 inch with edge straightness plus or minus 0.0025 inch. If plastic edging is applied to the panel, the tolerances apply to the panel before the plastic edging is applied.

2.2.3.1 Cementitious-Filled Formed Steel (Composite Panels)

a. Provide composite panels of die-formed steel construction totally enclosing the panel, including the top surface. The void spaces between the top sheet and the formed steel bottom sheet must be completely filled with an incombustible cementitious or concrete material. Seal cut edges in accordance with manufacturer's recommendations. Gravity held panels with bolted stringer understructure: Fasten end of each stringer and mid-point of each 4 foot stringer positively to pedestal heads, using manufacturer's standard screws. Provide screws that are removable from top.

b. Grid supported panels must be further tested by supporting them at two opposite edges and applying a 500-pound load at the center of a panel selected; the panel must be similarly tested while supported at the other two edges. Weld failure at any point under this loading is not acceptable. This additional test must be applied to one panel per 500 square feet of floor in the system, but in no case less than two panels. When any weld fails, the number of panels designated by the Contracting Officer must be similarly tested; replace those panels that have a weld failure at no cost to the Government.

2.2.4 Floor Covering

Surface floor panels with carpet tile installed in the field. Provide finish flooring materials in corridors and exits with a critical radiant

flux of not less than 0.45 watts per square centimeter (Class 1) when tested in accordance with ASTM E648 or NFPA 253. The electrical resistance must remain stable over the life expectancy of the floor covering. Any anti-static agent used in the manufacturing process must be an integral part of the material, not surface applied. Bolt heads or similar attachments must not rise above the traffic surface.

2.2.4.1 Carpet Tile

Reference Section 09 68 00 CARPETING for carpet tile specification requirements includingrecyled content, volitale organic compound (VOC) limits, and additional flammability testing requirements for carpet tile. Carpet tile must be field installed and comply with the following:

a. Installation method on level surfaces must allow carpet tile to be easily removed and replaced in the field and must be installed in accordance with manufacturer's recommended installation instructions.

b. Install carpet tile on secure and level surfaces with the access flooring manufacturer's recommended installation method and components for a one to one alignment with floor panels (one carpet tile to one floor panel); equal to Tate PosiTile or Haworth CarpetLok. This installation method requires the removal of only one carpet tile to access one raised access panel. Carpet tile size for a one-to-one installation must be slightly smaller than a standard 24 inch by 24 inch tile, coordinate required size with the raised access flooring manufacturer. Factory applied carpet tile with perimeter edge strip and field applied one to one carpet tile installation over raised access floor panels with permanent or releasable adhesive are not acceptable installation methods.

2.2.5 Adhesives

Provide adhesives as recommended by the manufacturer. Provide non-aerosol adhesive products that meet either emissions requirements of CDPH SECTION 01350 (use the requirements for either office or classroom, regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide aerosol adhesives that meet either emissions requirements of CDPH SECTION 01350 (use the requirements for office or classroom, regardless of space type) or VOC content requirements of GS-36. Provide validation of indoor air quality for adhesives.

2.2.6 Lifting Device

At turn over provide one floor panel lifting device standard with the floor manufacturer, for each individual floor area (room or corridor). Furnish a minimum of two devices.

2.3 PANEL SUPPORT SYSTEM

Design support system to allow for 360 degree clearance in laying out cable and cutouts for service to machines and so that panel and stringer together take up maximum of 2 inches. Submit one sample of suspension system proposed for use.

2.3.1 Pedestals

Provide pedestals made of steel or aluminum or a combination thereof. Ferrous materials must have a factory-applied corrosion-resistant finish.

Provide pedestal base plates with a minimum of 16 square inches of bearing surface and a minimum of 1/8 inch thickness. Pedestal shafts must be threaded to permit height adjustment within a range of approximately 2 inches, to permit overall floor adjustment within plus or minus 0.10 inch of the required elevation, and to permit leveling of the finished floor surface within 0.062 inch in 10 feet in all directions. Provide locking devices to positively lock the final pedestal vertical adjustments in place. Pedestal caps must interlock with stringers to preclude tilting or rocking of the panels.

2.3.2 Stringers

Provide stringers of rolled steel or extruded aluminum, to interlock with the pedestal heads to prevent lateral movement. Provide stringers that can be added or removed after floor is in place.

2.3.3 Gaskets

Provide continuous gasketing at contact surfaces between panel and stringers to deaden sound and seal off the underfloor cavity from above for air tightness, and to maintain panel alignment.

2.4 FACTORY TESTS

Factory test access flooring, using an independent laboratory, at the same position and maximum design elevation and in the same arrangement as shown on the drawings for installation so as to duplicate service conditions as much as possible.

2.4.1 Load Tests

Conduct floor panel, stringer, and pedestal testing in accordance with CISCA Access Floors to determine deformation and permanent set of panels and sytem due to concentrated, Uniform, rolling, impact and ultimate loading when panels are supported by actual understructure.

2.4.2 Bond Strength of Covering

Conduct test for bond strength of covering in accordance with CISCA Access Floors for rolling loads, except as specified. Panels must be tested with specified hard surface flooring and on the pedestals and stringers as specified for the installed floor. Brace the supports as necessary to prevent sideways movement during the test. Impose a test load of800 pounds on the test assembly through a 3 inches in diameter and 1 inch wide hard plastic caster. Roll the caster completely across the center of the panel. The panel must withstand 20 passes of the caster with no delamination or separation of the covering.

2.5 CUT OUTS

Provide cable cutouts finished with rigid polyvinylchloride or molded polypropylene edging to conform to the appearance level of the floor surface and to cover raw edges of the cutout panel. Extrusion must be of a configuration to permit its effective and convenient use when new cable openings are required. Provide at least 24 feet of additional extrusion for future use. Submit 2 color samples for cut outs.

a. Provide non-metallic adapter for openings less than 4 inches wide. Secure adapter adhesively in cutout to preclude removal from panel.

Provide at least two adapters per 1000 square feet for future use.

b. Openings larger than 4 inches wide must use rigid polyvinylchloride or molded polypropylene edging. Perform cutting of panels, including cutouts, outside of the building.

c. When size of cutout reduces the performance requirement of panel, provide intermediate stringers adjacent to cutouts.

PART 3 EXECUTION

3.1 INSTALLATION

Install access flooring at the location and elevation and in the arrangement shown on the approved detailed installation drawings. The floor system must be of the rigid grid stringer type, complete with all supplemental items, and be the standard product of a manufacturer specializing in access flooring systems.

Install the floor system in accordance with the manufacturer's instructions. Open ends of the floor, where the floor system does not abut wall or other construction, must have positive anchorage and rigid support. Maintain areas to receive access flooring between 60 and 90 degrees F, and between 20 and 70 percent humidity for 24 hours prior to and during installation.

3.1.1 Preparation for Installation

Clear out all debris in the area in which the floor system is to be installed. Thoroughly clean structural floor surfaces and remove all dust. Install floor coatings, required for dust or vapor control, prior to installation of pedestals, only if the pedestal adhesive will not damage the coating. If the coating and adhesive are not compatible, apply the coating after the pedestals have been installed and the adhesive has cured.

3.1.2 Pedestals

Pedestals must be accurately spaced, and set plumb and in true alignment. Set base plates in full and firm contact with the structural floor, and secured to the structural floor with adhesive or steel expansion anchors in accordance with manufacturer's instructions.

3.1.3 Stringers

Interlock stringers with the pedestal caps to preclude lateral movement, spaced uniformly in parallel lines at the indicated elevation.

3.1.4 Auxiliary Framing

Provide auxiliary framing or pedestals around columns and other permanent construction, at sides of ramps, at open ends of the floor, and beneath panels that are substantially cut to accommodate utility systems. Use special framing for additional lateral support as shown on the approved detailed installation drawings. Provide additional pedestals and stringers designed to specific heights and lengths to meet structural irregularities and design loads. Connect auxiliary framing to main framing.

3.1.5 Panels

Interlock panels with supports in a manner that will preclude lateral movement. Fasten perimeter panels, cutout panels, and panels adjoining columns, stairs, and ramps to the supporting components to form a rigid boundary for the interior panels. Level floors within the specified tolerances. Cut edges of Exposed edges of composite panels must be coated with a silicone rubber sealant or with an adhesive recommended by the panel manufacturer. Secure extruded vinyl edging in place at all cut edges of all panel cut-outs to prevent abrasion of cables.

3.1.6 Carpet Tile

Reference carpet tile paragraph in FLOOR COVERING for carpet tile installation requirements.

3.1.7 Resilient Base

Provide base at vertical wall intersections. Apply the base after the floor system has been completely installed. Install wall base in accordance with manufacturer's printed installation instructions. Prepare and apply adhesives in accordance with manufacturer's printed directions. Tighten base joints and make even with adjacent flooring. Fill voids along the top edge of base at masonry walls with caulk. Roll entire vertical surface of base with hand roller, and press toe of base with a straight piece of wood to ensure proper alignment. Avoid excess adhesive in corners.

3.1.8 Repair of Zinc Coating

Repair zinc coating that has been damaged, and cut edges of zinc-coated components and accessories, by the application of a galvanizing repair paint conforming to ASTM A780/A780M. Areas to be repaired must be thoroughly cleaned prior to application of the paint.

3.2 FIELD TESTS

Submit certified copies of test reports from an approved testing laboratory, attesting that the proposed floor system components meet the performance requirements specified.

3.2.1 Acceptance Tests

Conduct acceptance tests after installation of floor system. Make at least one test for each 1000 square feet of floor area. Conduct tests in presence of Contracting Officer and representatives of manufacturer and installer. Submit certified copies of test reports from an approved testing laboratory, attesting that the proposed floor system components meet the performance requirements specified.

3.2.2 Grounding

Ground the access flooring system for safety hazard and static suppression. Provide positive contact between components for safe, continuous electrical grounding of entire floor system. Total system resistance from wearing surface of floor to building grounding electrode must be within range of 0.5 to 20,000 megohms.

3.2.2.1 Joint Resistance

Electrical joint resistance between individual stringer and pedestal junctions must be less than 0.1 milliohms. Electrical resistance between stringers and floor panels, as mounted in normal use, must be less than 3 ohms when tested in accordance with ASTM F150.

3.2.3 Electrical Resistance

Conduct testing of electrical resistance, in the completed installation, in the presence of the Contracting Officer in accordance with NFPA 99, modified by placing one electrode on the center of the panel surface and connecting the other electrode to the metal flooring support. Take measurements at five or more locations. Each measurement must be the average of five readings of 15 seconds duration at each location. During the tests, relative humidity must be 45 to 55 percent and temperature set at 69 to 75 degrees F. Select panels used in the testing at random and include two panels most distant from the ground connection. Measure electrical resistance with instruments that are accurate within 2 percent and that have been calibrated within 60 days prior to the performance of the resistance tests. The metal-to-metal resistance from panel to supporting pedestal must not exceed 10 ohms. The resistance between the wearing surface of the floor covering and the ground connection, as measured on the completed installation, must be in accordance with paragraph FLOOR COVERING.

3.3 CLEANING AND PROTECTION

3.3.1 Cleaning

Keep the space below the completed floor free of all debris. Before any traffic or other work on the completed raised floor is started, clean the completed floor in accordance with the floor covering manufacturer's instructions.

3.3.2 Protection

Protect traffic areas of raised floor systems with a covering of building paper, fiberboard, or other suitable material to prevent damage to the surface. Cover cutouts with material of sufficient strength to support the loads to be encountered. Place plywood or similar material on the floor to serve as runways for installation of heavy equipment not in excess of design load capacity. Maintain protection until the raised floor system is accepted.

3.3.3 Surplus Material Removal

Clean surfaces of the work, and adjacent surfaces soiled as a result of the work. Remove all installation equipment, surplus materials, and rubbish from the work site.

3.4 OPERATION AND MAINTENANCE MANUALS

Submit maintenance instructions for proper care of the floor panel surface. When conductive flooring is specified, also submit maintenance instructions to identify special cleaning and maintenance requirements to maintain "conductivity" properties of the panel finish.

-- End of Section --

SECTION 09 72 00

WALL PROTECTION & DIGITALLY PRINTED WALL GRAPHICS
08/17, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

GYPSUM ASSOCIATION (GA)

GA 214	(2010) Recommended Levels of Gypsum Board Finish

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 286	(2019) Standard Methods of Fire Tests for Evaluating Contribution of Wall and Ceiling Interior Finish to Room Fire Growth

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2022) Adhesive and Sealant Applications

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS CCC-W-408	(Rev D; Notices 1, 2, 3) Wallcovering, Vinyl Coated

UL SOLUTIONS (UL)

UL 723	(2018; Reprint Jun 2025) UL Standard for Safety Test for Surface Burning

Characteristics of Building Materials

UL 2818 (2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Wallcoverings and Accessories; G

Primer and Adhesive

SD-04 Samples

Wallcoverings and Accessories; G

SD-07 Certificates

Indoor Air Quality; S

SD-08 Manufacturer's Instructions

Wallcoverings and Accessories

SD-10 Operation and Maintenance Data

Wallcoverings and Accessories; G

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality Certifications

Submit required indoor air quality certifications and validations in one submittal package.

1.3.1.1 Fabrics and Wallcoverings

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body.

1.3.1.2 Primers and Adhesives

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver the material to the site in manufacturer's original wrappings and packages and clearly label with the manufacturer's name, brand name, pattern and color name and number, dye lot number, size, and other related information. Store in a safe, dry, clean, and well-ventilated area at temperatures not less than 50 degrees F and within a relative humidity range of 30 to 60 percent. Store wallcovering material in a flat position and protected from damage, soiling, and moisture. Do not open containers until needed for installation, unless verification inspection is required.

1.5 ENVIRONMENTAL REQUIREMENTS

Comply with wall protection manufacturer's printed installation instructions for minimum temperature of area to receive requirements for conditioning adhesive and wallcovering. Provide a minimum 50 degrees F area temperature, 72 hours prior to installation, during installation, and until the adhesive dries. Observe ventilation and safety procedures.

1.6 WARRANTY

Provide manufacturer's standard performance guarantees or warranties.

1.7 EXTRA MATERIALS

Provide one linear foot of full-width wall protection of each pattern and color for each 100 linear feet of wallcovering installed. Provide the same manufacturer, type, pattern, color, and lot number of extra stock as the installed wall protection. Provide full rolls, packed for storage and marked with content, manufacturer's name, pattern and color name and number and dye lot number. Leave extra stock at the site at a location as directed by the Contracting Officer.

PART 2 PRODUCTS

2.1 WALLCOVERINGS AND ACCESSORIES

Provide wall protection and accessories material designed specifically for the specified use. Provide vinyl wall protection with a mercury, cadmium, lead, and chromium free base. Protect wall protection with abrasion-resistant treatments.

2.1.1 Product Data

a. Wall Protection: Submit manufacturer's descriptive data, documenting physical characteristics, flame resistance, mildew and germicidal characteristics for wallcovering.

b. Primer and Adhesive: Submit manufacturer's descriptive data, documenting physical characteristics, mildew and germicidal characteristics.

2.1.2 Samples

2.1.2.1 Wall Protection

Provide three samples of each indicated type, pattern, and color of wall protection. Provide minimum 3 yards long by the width specified, of each

type to be installed in the work, as required to illustrate pattern repeat, material weight, color, shade, decorative design, and embossing when required.

2.1.3 Certificates

Submit manufacturer's statement attesting that the product furnished meets or exceeds specification requirements. Date the statement after the award of the contract, state Contractor's name and address, name the project and location, and list the requirements being certified. Include these certificates:

(1) Certified laboratory test reports of the physical properties for vinyl wallcovering, as specified.

(2) Certificates of Compliance for UL fire hazard classification listing, as specified.

(3) Certificates of Compliance for contact adhesive.

2.1.4 Manufacturer's Instructions

Submit preprinted installation instructions for wall protection and accessories, adhesives and primers. Include substrate preparation and material application in the instructions.

2.1.5 Operations and Maintenance Data

a. Submit Data Package 1 in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

b. Submit three copies of manufacturer's maintenance instructions for each type of vinyl wall protection and accessory describing recommended type of cleaning equipment and materials, spotting and cleaning methods, and cleaning cycles. Instructions to also include preventative maintenance, recommended cleaning materials and precautions in the use of cleaning materials that may be detrimental to the wall protection surface and accessories when improperly applied.

2.2 DIGITALLY PRINTED WALL GRAPHIC

MATERIALS

2.2.1 WALL GRAPHIC

Type II conforming to Federal Specification CCC-W-408A and WA-101-A using test methods given in Federal Specification CCC-T-191 b excepted as otherwise specified

1. Total Weight: 21 ounces per linear yard.
2. Backing Weight: 3.1 ounces per linear yard.
3. Vinyl Weight: 17.9 ounces per linear yard
4. Thickness: 0.018 to 0.026 inches
5. Fabric backing and content: Poly-Cotton Woven

2.3 VINYL WALL PROTECTION

Provide 100% vinyl coated wall protection. Conform to FS CCC-W-408 for vinyl wall protection, Type III (Heavy Duty) with a minimum total weight of

35 ounces/linear yard. Provide width of 52inch. Test vinyl wall protection in accordance with NFPA 286 or meet the requirements of Class A when tested in accordance with ASTM E84 or UL 723. Wall protection must have a polyester backing.

Provide Vinyl Wall Protection containing solvent-free inks.

Provide certification of indoor air quality for vinyl wall protection.

2.4 PRIMER AND ADHESIVE

Provide a type primer and adhesive recommended by the wallcovering manufacturer, containing a non-mercury based mildewcide, and complying with local indoor air quality standards. Primer must permit removal of the wallcovering and protect the wall surface during removal. Do not damage gypsum wallboard facing paper during removal of wallcovering. Provide a strippable type adhesive. When substrate color variations show through vinyl wallcovering, provide a white pigmented primer as recommended by the wallcovering manufacturer used to conceal the variations. Provide a recommended type adhesive to install corner guards and wainscot cap by the manufacturer of the corner guards and wainscot cap.

Provide primers and non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) that meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide aerosol adhesives used on the interior of the building that meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for primer; also, provide certification or validation of indoor air quality for adhesives.

2.5 COLOR, TEXTURE, AND PATTERN

Provide color, texture and pattern in accordance with the drawings. Color listed is not intended to limit the selection of equal colors from other manufacturers.

PART 3 EXECUTION

3.1 EXAMINATION

Inspect all areas and conditions under which wallcoverings are to be installed. Notify the Contracting Officer, in writing, of any conditions detrimental to the proper and timely completion of the installation. Work will proceed only when conditions have been corrected and accepted by the installer.

3.2 SURFACE PREPARATION

Do not apply wallcovering to surfaces that are rough, that contain stains which will bleed through the wallcovering, or that are otherwise unsuitable for proper installation. Fill cracks and holes; sand rough spots smooth. Finish walls to receive presentation dry erase wallcovering to a Level 4 gypsum wallboard finish in accordance with GA 214 unless Level 5 is recommended by the wallcovering manufacturer. Wall surfaces should be clean, smooth, and free from any marks, mildew, and

imperfections. Any loose paint, existing wallcoverings, or other surface materials should be removed. Any mold or mildew must be removed from the hanging surfaces prior to installation. Walls should not contain in excess of 4% residual moisture content. A moisture meter should be used to determine moisture content. Moisture infiltration and accumulation can lead to mold or mildew growth and must be corrected prior to the installation of the wallcovering. If you
are unsure if moisture problems are present, consult a qualified professional before proceeding. A wallcovering primer (Roman-PRO 977 Ultra Prime is recommended) is required and it is never recommended to apply wallcovering directly to paint. Gypsum board finish should comply with AWCI Specification, Level 4 or higher although a Level 5 finish is ideal. Use only a lead pencil for marking walls and back of wallcovering. Do not use ballpoint or marking pen, they will bleed through the surface. Do not install wallcovering unless a temperature between 70° F and 100° F, with a relative humidity level of 50% or less is maintained in both areas of installation and storage for at least 72 hours prior to, during, and after installation. Make sure that all surfaces to receive wallcovering are protected from damage during installation.

3.3 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

3.3.1 Wall Protection

Install wall protection in accordance with the manufacturer's printed installation instructions. Remove glue and adhesive spillage from wallcovering face and seams with a remover recommended by the manufacturer.

3.3.2 Wall Graphic

Install wall graphics in accordance with the manufacturer's printed installation instructions.

3.4 CLEAN-UP

Upon completion of the work, clean wallcovering free of dirt, soiling, stain, or residual film. Remove and clean surplus materials, rubbish, and debris resulting from the wallcovering installation.

-- End of Section --

SECTION 09 90 00

PAINTS AND COATINGS
02/21

PART 1 GENERAL

1.1 RELATED REQUIREMENTS

1.1.1 Painting Included

Where a space or surface is indicated to be painted, include the following unless indicated otherwise.

a. Surfaces behind portable objects and surface mounted articles readily detachable by removal of fasteners, such as screws and bolts.

b. New factory finished surfaces that require identification or color coding and factory finished surfaces that are damaged during performance of the work.

c. Existing coated surfaces that are damaged during performance of the work.

1.1.1.1 Exterior Painting

Includes new surfaces, existing coated surfaces, and existing uncoated surfaces, of buildings and appurtenances. Also included are existing coated surfaces made bare by cleaning operations.

1.1.1.2 Interior Painting

Includes new surfaces, existing uncoated surfaces, and existing coated surfaces of buildings and appurtenances as indicated and existing coated surfaces made bare by cleaning operations. Where a space or surface is indicated to be painted, include the following items, unless indicated otherwise.

a. Exposed columns, girders, beams, joists, and metal deck; and

b. Other contiguous surfaces.

1.1.2 Painting Excluded

Do not paint the following unless indicated otherwise.

a. Surfaces concealed and made inaccessible by panelboards, fixed ductwork, machinery, and equipment fixed in place.

b. Surfaces in concealed spaces. Concealed spaces are defined as enclosed spaces above suspended ceilings, furred spaces, attic spaces, crawl spaces, elevator shafts and chases.

c. Steel to be embedded in concrete.

d. Copper, stainless steel, aluminum, anodized aluminum, brass, and lead except existing coated surfaces.

e. Hardware, fittings, and other factory finished items.

1.1.3 Mechanical and Electrical Painting

Includes field coating of interior and exterior new and existing surfaces.

a. Where a space or surface is indicated to be painted, include the following items unless indicated otherwise.

(1) Exposed piping, conduit, and ductwork;

(2) Supports, hangers, air grilles, and registers;

(3) Miscellaneous metalwork and insulation coverings.

b. Do not paint the following, unless indicated otherwise:

(1) New zinc-coated, aluminum, and copper surfaces under insulation

(2) New aluminum jacket on piping

(3) New interior ferrous piping under insulation.

1.1.3.1 Fire Extinguishing Sprinkler Systems

Clean, pretreat, prime, and paint new fire extinguishing sprinkler systems including valves, piping, conduit, hangers, supports, miscellaneous metalwork, and accessories. Apply coatings to clean, dry surfaces, using clean brushes.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH 0100	(2017; Suppl 2020) Documentation of the Threshold Limit Values and Biological Exposure Indices

ASTM INTERNATIONAL (ASTM)

ASTM D235	(2002; R 2012) Mineral Spirits (Petroleum Spirits) (Hydrocarbon Dry Cleaning Solvent)
ASTM D523	(2014; R 2018) Standard Test Method for Specular Gloss
ASTM D4214	(2007; R 2015) Standard Test Method for Evaluating the Degree of Chalking of Exterior Paint Films
ASTM D4263	(1983; R 2018) Standard Test Method for Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D4444	(2013; R 2018) Standard Test Method for

	Laboratory Standardization and Calibration of Hand-Held Moisture Meters
ASTM D6386	(2016a) Standard Practice for Preparation of Zinc (Hot-Dip Galvanized) Coated Iron and Steel Product and Hardware Surfaces for Painting
ASTM F1869	(2022) Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride

CENTERS FOR DISEASE CONTROL AND PREVENTION (CDC)

Intelligence Bulletin 65	(2013) Occupational Exposure to Carbon Nanotubes and Nanofibers

MASTER PAINTERS INSTITUTE (MPI)

MPI 4	(2016) Interior/Exterior Latex Block Filler
MPI 9	(2016) Alkyd, Exterior Gloss (MPI Gloss Level 6)
MPI 11	(2016) Latex, Exterior Semi-Gloss, MPI Gloss Level 5
MPI 23	(2015) Primer, Metal, Surface Tolerant
MPI 45	(2016) Primer Sealer, Interior Alkyd
MPI 47	(2016) Alkyd, Interior, Semi-Gloss (MPI Gloss Level 5)
MPI 50	(2015) Primer Sealer, Latex, Interior
MPI 57	(2012) Varnish, Interior, Polyurethane, Oil Modified, Satin
MPI 72	(2016) Polyurethane, Two-Component, Pigmented, Gloss (MPI Gloss Level 6-7)
MPI 76	(2016) Primer, Alkyd, Quick Dry, for Metal
MPI 77	(2015) Epoxy, Gloss
MPI 79	(2016) Primer, Alkyd, Anti-Corrosive for Metal
MPI 90	(2012) Stain, Semi-Transparent, for Interior Wood
MPI 94	(2016) Alkyd, Exterior, Semi-Gloss (MPI Gloss Level 5)
MPI 101	(2016) Primer, Epoxy, Anti-Corrosive, for Metal
MPI 107	(2016) Primer, Rust-Inhibitive, Water Based

MPI 116	(2012) Block Filler, Epoxy
MPI 134	(2015) Primer, Galvanized, Water Based
MPI 140	(2016) Latex, Interior, High Performance Architectural, (MPI Gloss Level 4)
MPI 144	(2016) Latex, Interior, Institutional Low Odor/VOC, (MPI Gloss Level 2)
MPI 145	(2016) Latex, Interior, Institutional Low Odor/VOC, (MPI Gloss Level 3)
MPI 149	(2016) Primer Sealer, Interior, Institutional Low Odor/VOC
MPI 153	(2016) Light Industrial Coating, Interior, Water Based, Semi-Gloss (MPI Gloss Level 5)
MPI ASM	(2019) Architectural Painting Specification Manual
MPI GPS-1-14	(2014) Green Performance Standard GPS-1-14
MPI GPS-2-14	(2014) Green Performance Standard GPS-2-14
MPI MRM	(2015) Maintenance Repainting Manual

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC 7/NACE No.4	(2007) Brush-Off Blast Cleaning
SSPC Glossary	(2011) SSPC Protective Coatings Glossary
SSPC PA 1	(2016) Shop, Field, and Maintenance Coating of Metals
SSPC SP 1	(2015) Solvent Cleaning
SSPC SP 2	(2018) Hand Tool Cleaning
SSPC SP 3	(2018) Power Tool Cleaning
SSPC SP 6/NACE No.3	(2007) Commercial Blast Cleaning
SSPC SP 10/NACE No. 2	(2015) Near-White Blast Cleaning
SSPC VIS 1	(2002; E 2004) Guide and Reference Photographs for Steel Surfaces Prepared by Dry Abrasive Blast Cleaning
SSPC VIS 3	(2004) Guide and Reference Photographs for Steel Surfaces Prepared by Hand and Power Tool Cleaning

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational

Health (SOH) Requirements

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-STD-101	(2014; Rev C) Color Code for Pipelines and for Compressed Gas Cylinders

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FED-STD-313	(2018) Material Safety Data, Transportation Data and Disposal Data for Hazardous Materials Furnished to Government Activities

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000	Air Contaminants

1.3 DEFINITIONS

1.3.1 Qualification Testing

Qualification testing is the performance of all test requirements listed in the product specification. This testing is accomplished by MPI to qualify each product for the MPI Approved Product List, and may also be accomplished by Contractor's third-party testing lab if an alternative to Batch Quality Conformance Testing by MPI is desired.

1.3.2 Batch Quality Conformance Testing

Batch quality conformance testing determines that the product provided is the same as the product qualified to the appropriate product specification. This testing must be accomplished by an MPI testing lab.

1.3.3 Coating

SSPC Glossary; (1) A liquid, liquefiable, or mastic composition that is converted to a solid protective, decorative, or functional adherent film after application as a thin layer; (2) Generic term for paint, lacquer, enamel.

1.3.4 DFT or dft

Dry film thickness, the film thickness of the fully cured, dry paint or coating.

1.3.5 DSD

Degree of Surface Degradation, the MPI system of defining degree of surface degradation. Five levels are generically defined under the Assessment sections in the MPI MRM, MPI Maintenance Repainting Manual.

1.3.6 EXT

MPI short term designation for an exterior coating system.

1.3.7 INT

MPI short term designation for an interior coating system.

1.3.8 Loose Paint

Paint or coating that can be removed with a dull putty knife.

1.3.9 mil / mils

The English measurement for 0.001 in or one one-thousandth of an inch.

1.3.10 MPI Gloss Levels

MPI system of defining gloss. Seven gloss levels (G1 to G7) are generically defined under the Evaluation sections of the MPI Manuals. Traditionally, Flat refers to G1/G2, Eggshell refers to G3, Semigloss refers to G5, and Gloss refers to G6.

Gloss levels are defined by MPI as follows:

Gloss Level	Description	Units at 60 degree angle	Units at 80 degree angle
G1	Matte or Flat	0 to 5	10 max
G2	Velvet	0 to 10	10 to 35
G3	Eggshell	10 to 25	10 to 35
G4	Satin	20 to 35	35 min
G5	Semi-Gloss	35 to 70	
G6	Gloss	70 to 85	
G7	High Gloss		

Gloss is tested in accordance with ASTM D523. Historically, the Government has used Flat (G1 / G2), Eggshell (G3), Semi-Gloss (G5), and Gloss (G6).

1.3.11 MPI System Number

The MPI coating system number in each MPI Division found in either the MPI Architectural Painting Specification Manual or the Maintenance Repainting Manual and defined as an exterior (EXT/REX) or interior system (INT/RIN).

1.3.12 Paint

SSPC Glossary; (1) Any pigmented liquid, liquefiable, or mastic composition designed for application to a substrate in a thin layer that is converted to an opaque solid film after application. Used for protection, decoration, identification, or to serve some other functional purposes; (2) Application of a coating material.

1.3.13 REX

MPI short term designation for an exterior coating system used in repainting projects or over existing coating systems.

1.3.14 RIN

MPI short term designation for an interior coating system used in repainting projects or over existing coating systems.

1.4 SCHEDULING

Allow paint, polyurethane, varnish, and wood stain installations to cure prior to the installation of materials that adsorb VOCs.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Samples of specified materials may be taken and tested for compliance with specification requirements.

SD-02 Shop Drawings

Piping Identification

SD-03 Product Data

Coating; G

Product Data Sheets

SD-04 Samples

Color; G

SD-07 Certificates

Indoor Air Quality for Paints and Primers

SD-08 Manufacturer's Instructions

Application Instructions

Mixing

Manufacturer's Safety Data Sheets

SD-10 Operation and Maintenance Data

Coatings, Data Package 1; G

1.6 QUALITY ASSURANCE

1.6.1 Regulatory Requirements

1.6.1.1 Environmental Protection

In addition to requirements specified elsewhere for environmental

protection, provide coating materials that conform to the restrictions of the local Air Pollution Control District and regional jurisdiction. Notify Contracting Officer of any paint specified herein which fails to conform.

1.6.1.2 Lead Content

Do not use coatings having a lead content over 0.06 percent by weight of nonvolatile content.

1.6.1.3 Chromate Content

Do not use coatings containing zinc-chromate or strontium-chromate.

1.6.1.4 Asbestos Content

Provide asbestos-free materials.

1.6.1.5 Mercury Content

Provide materials free of mercury or mercury compounds.

1.6.1.6 Silica

Provide abrasive blast media containing no free crystalline silica.

1.6.1.7 Human Carcinogens

Provide materials that do not contain ACGIH 0100 confirmed human carcinogens (A1) or suspected human carcinogens (A2).

1.6.1.8 Carbon Based Fibers / Tubes

Materials must not contain carbon based fibers such as carbon nanotubes or carbon nanofibers. Intelligence Bulletin 65 ranks toxicity of carbon nanotubes on a par with asbestos.

1.6.2 Coating Contractor's Qualification

Submit the name, address, telephone number, and e-mail address of the Contractor that will be performing all surface preparation and coating application. Submit evidence that key personnel have successfully performed surface preparation and application of coatings on a minimum of three similar projects within the past three years. List information by individual and include the following:

a. Name of individual and proposed position for this work.

b. Information about each previous assignment including:

Position or responsibility

Employer (if other than the Contractor)

Name of facility owner

Mailing address and telephone number of facility owner

Name of individual in facility owner's organization who can be contacted as a reference

Location, size and description of structure

Dates work was carried out

Description of work carried out on structure

1.6.3 Approved Products List

The current MPI, "Approved Product List" which lists paint by brand, label, product name and product code as of the date of Contract award, will be used to determine compliance with the submittal requirements of this specification. The Contractor may choose to use a subsequent MPI "Approved Product List", however, only one list may be used for the entire Contract and each coating system is to be from a single manufacturer. Provide all coats on a particular substrate from a single manufacturer. No variation from the MPI Approved Products List is acceptable.

1.6.4 Paints and Coatings Indoor Air Quality Certifications

Provide paint and coating products certified to meet indoor air quality requirements by MPI GPS-1-14, MPI GPS-2-14 or provide certification by other third-party programs. Provide current product certification documentation from certification body.

Provide certification of Indoor Air Quality for Paints and Primers. Submit required indoor air quality certifications in one submittal package.

1.7 PACKAGING, LABELING, AND STORAGE

Provide paints in sealed containers that legibly show the Contract specification number, designation name, formula or specification number, batch number, color, quantity, date of manufacture, manufacturer's formulation number, manufacturer's directions including any warnings and special precautions, and name and address of manufacturer. Furnish pigmented paints in containers not larger than 5 gallons. Store paints and thinners in accordance with the manufacturer's written directions, and as a minimum, stored off the ground, under cover, with sufficient ventilation to prevent the buildup of flammable vapors, and at temperatures between 40 to 95 degrees F. Do not store paint, polyurethane, varnish, or wood stain products with materials that have a high capacity to absorb VOC emissions. Do not store paint, polyurethane, varnish, or wood stain products in occupied spaces.

1.8 SAFETY AND HEALTH

Comply with applicable Federal, State, and local laws and regulations, and with the ACCIDENT PREVENTION PLAN, including the Activity Hazard Analysis as specified in Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS and in Appendix A of EM 385-1-1. Include in the Activity Hazard Analysis the potential impact of painting operations on painting personnel and on others involved in and adjacent to the work zone.

1.8.1 Toxic Materials

To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

a. The applicable manufacturer's Safety Data Sheets (SDS) or local regulation.

b. 29 CFR 1910.1000.

c. ACGIH 0100, threshold limit values.

Submit manufacturer's Safety Data Sheets for coatings, solvents, and other potentially hazardous materials, as defined in FED-STD-313.

1.9 ENVIRONMENTAL REQUIREMENTS

Comply, at minimum, with manufacturer recommendations for space ventilation during and after installation. Isolate area of application from rest of building when applying high-emission paints or coatings.

1.9.1 Coatings

Do not apply coating when air or substrate conditions are:

a. Less than 5 degrees F above dew point;

b. Below 50 degrees F or over 95 degrees F, unless specifically pre-approved by the Contracting Officer and the product manufacturer. Do not, under any circumstances, violate the manufacturer's application recommendations.

1.9.2 Post-Application

Vacate space for as long as possible after application. Wait a minimum of 48 hours before occupying freshly painted rooms. Maintain one of the following ventilation conditions during the curing period, or for 72 hours after application:

a. Supply 100 percent outside air 24 hours a day.

b. Supply airflow at a rate of 6 air changes per hour, when outside temperatures are between 55 degrees F and 85 degrees F and humidity is between 30 percent and 60 percent.

c. Supply airflow at a rate of 1.5 air changes per hour, when outside air conditions are not within the range stipulated above.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to the coating specifications and standards referenced in PART 3. Submit Product Data Sheets for specified coatings and solvents. Provide preprinted cleaning and maintenance instructions for all coating systems. Submit Manufacturer's Instructions on Mixing: Detailed mixing instructions, minimum and maximum application temperature and humidity, pot life, and curing and drying times between coats.

2.2 COLOR SELECTION OF FINISH COATS

Provide colors of finish coats as indicated or specified. Allow Contracting Officer to select colors not indicated or specified.

Manufacturers' names and color identification are used for the purpose of color identification only. Named products are acceptable for use only if they conform to specified requirements. Products of other manufacturers are acceptable if the colors are approximately the colors indicated and the product conforms to specified requirements.

Provide color, texture, and pattern of wall coating systems as indicated. Submit manufacturer's samples of paint colors. Cross reference color samples to color scheme as indicated. Submit color stencil codes. Tint each coat progressively darker to enable confirmation of the number of coats.

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED

Prior to surface preparation and coating applications, remove, mask, or otherwise protect hardware, hardware accessories, machined surfaces, radiator covers, plates, lighting fixtures, public and private property, and other such items not to be coated that are in contact with surfaces to be coated. Following completion of painting, reinstall removed items by workmen skilled in the trades. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 SURFACE PREPARATION

Remove dirt, splinters, loose particles, grease, oil, and other foreign matter and substances deleterious to coating performance as specified for each substrate before application of paint or surface treatments. Remove oil and grease prior to mechanical cleaning. Schedule cleaning so that dust and other contaminants will not fall on wet, newly painted surfaces. Refer to MPI ASM and MPI MRM for additional more specific substrate preparation requirements.

3.2.1 Additional Requirements for Preparation of Surfaces With Existing Coatings

Before application of coatings, perform the following on surfaces covered by soundly-adhered coatings, defined as those which cannot be removed with a putty knife:

a. Test existing finishes for lead before sanding, scraping, or removing. If lead is present, refer to paragraph Toxic Materials.

b. Wipe previously painted surfaces to receive solvent-based coatings with a clean, dry cloth saturated with mineral spirits, ASTM D235 or as specified in MPI MRM. Wipe the surfaces dry with a clean, dry, lint free cloth. Wipe immediately preceding the application of the first coat of any coating, unless specified otherwise.

c. Sand existing glossy surfaces to be painted to reduce gloss. Brush, and wipe clean with a damp cloth to remove dust.

d. The requirements specified are minimum. Comply also with the application instructions of the paint manufacturer and specific surface preparation requirements as outlined in MPI MRM Exterior Surface Preparation and Interior Surface Preparation.

e. Thoroughly clean previously painted surfaces of all grease, dirt, dust

or other foreign matter.

f. Remove blistering, cracking, flaking and peeling or otherwise deteriorated coatings.

g. Remove chalk so that when tested in accordance with ASTM D4214, the chalk resistance rating is no less than 8.

h. Roughen slick surfaces. Repair damaged areas such as, but not limited to, nail holes, cracks, chips, and spalls with suitable material to match adjacent undamaged areas.

i. Feather and sand smooth edges of chipped paint.

j. Clean rusty metal surfaces in accordance with SSPC requirements. Use solvent, mechanical, or chemical cleaning methods to provide surfaces suitable for painting.

k. Provide new, proposed coatings that are compatible with existing coatings.

3.2.2 Existing Coated Surfaces with Minor Defects

Sand, spackle, and treat minor defects to render them smooth. Minor defects are defined as scratches, nicks, cracks, gouges, spalls, alligatoring, chalking, and irregularities due to partial peeling of previous coatings. Remove chalking by sanding so that when tested in accordance with ASTM D4214, the chalk rating is not less than 8.

3.2.3 Substrate Repair

a. Repair substrate surface damaged during coating removal;

b. Sand edges of adjacent soundly-adhered existing coatings so they are tapered as smooth as practical to areas involved with coating removal; and

c. Clean and prime the substrate as specified.

3.3 PREPARATION OF METAL SURFACES

3.3.1 Existing and New Ferrous Surfaces

a. Ferrous Surfaces including Shop-coated Surfaces and Small Areas That Contain Rust, Mill Scale and Other Foreign Substances: Solvent clean in accordance with SSPC SP 1 to remove oil and grease. Where shop coat is missing or damaged, clean according to SSPC SP 2, or SSPC SP 3. Brush-off blast remaining surface in accordance with SSPC 7/NACE No.4. Use inhibitor as recommended by coating manufacturer to prevent premature rusting. Protect shop-coated ferrous surfaces from corrosion by treating and touching up corroded areas immediately upon detection.

b. Surfaces With More Than 20 Percent Rust, Mill Scale, and Other Foreign Substances: Clean entire surface in accordance with SSPC SP 6/NACE No.3.

3.3.2 Final Ferrous Surface Condition:

3.3.2.1 Tool Cleaned Surfaces

Comply with SSPC SP 2 and SSPC SP 3. Use as a visual reference, photographs in SSPC VIS 3 for the appearance of cleaned surfaces.

3.3.2.2 Abrasive Blast Cleaned Surfaces

Comply with SSPC 7/NACE No.4, SSPC SP 6/NACE No.3, and SSPC SP 10/NACE No. 2. Use as a visual reference, photographs in SSPC VIS 1 for the appearance of cleaned surfaces.

3.3.3 Galvanized Surfaces

a. New or Existing Galvanized Surfaces With Only Dirt and Zinc Oxidation Products: Clean with solvent, steam, or non-alkaline detergent solution in accordance with SSPC SP 1. Completely remove coating by brush-off abrasive blast if the galvanized metal has been passivated or stabilized. Do not "passivate" or "stabilize" new galvanized steel to be coated. If the absence of hexavalent stain inhibitors is not documented, test as described in ASTM D6386, Appendix X2, and remove by one of the methods described therein.

3.4 PREPARATION OF CONCRETE AND CEMENTITIOUS SURFACE

3.4.1 Concrete and Masonry

a. Curing: Allow concrete, stucco and masonry surfaces to cure at least 30 days before painting, and concrete slab on grade to cure at least 90 days before painting.

b. Surface Cleaning: Remove the following deleterious substances.

(1) Dirt, Chalking, Grease, and Oil: Wash new and existing uncoated surfaces with a solution composed of 1/2 cup trisodium phosphate, 1/4 cup household detergent, and 4 quarts of warm water. Then rinse thoroughly with fresh water. Wash existing coated surfaces with a suitable detergent and rinse thoroughly. For large areas, water blasting may be used.

(2) Fungus and Mold: Wash new, existing coated, and existing uncoated surfaces with a solution composed of 1/2 cup trisodium phosphate, 1/4 cup household detergent, one quart 5 percent sodium hypochlorite solution and 3 quarts of warm water. Rinse thoroughly with fresh water.

(3) Paint and Loose Particles: Remove by wire brushing.

(4) Efflorescence: Remove by scraping or wire brushing followed by washing with a 5 to 10 percent by weight aqueous solution of hydrochloric (muriatic) acid. Do not allow acid to remain on the surface for more than five minutes before rinsing with fresh water. Do not acid clean more than 4 square feet of surface, per workman, at one time.

c. Cosmetic Repair of Minor Defects: Repair or fill mortar joints and minor defects, including but not limited to spalls, in accordance with manufacturer's recommendations and prior to coating application.

d. Allowable Moisture Content: Latex coatings may be applied to damp surfaces, but not to surfaces with droplets of water. Do not apply epoxies to damp vertical surfaces as determined by ASTM D4263 or horizontal surfaces that exceed 3 lbs of moisture per 1000 square feet in 24 hours as determined by ASTM F1869. In all cases follow manufacturer's recommendations. Allow surfaces to cure a minimum of 30 days before painting.

3.4.2 Gypsum Board, Plaster, and Stucco

3.4.2.1 Surface Cleaning

Verify that plaster and stucco surfaces are free from loose matter and that gypsum board is dry. Remove loose dirt and dust by brushing with a soft brush, rubbing with a dry cloth, or vacuum-cleaning prior to application of the first coat material. A damp cloth or sponge may be used if paint is water-based.

3.4.2.2 Repair of Minor Defects

Prior to painting, repair joints, cracks, holes, surface irregularities, and other minor defects with patching plaster or spackling compound and sand smooth.

3.4.2.3 Allowable Moisture Content

Latex coatings may be applied to damp surfaces, but not surfaces with droplets of water. Do not apply epoxies to damp surfaces as determined by ASTM D4263.

3.5 PREPARATION OF WOOD SURFACES

3.5.1 New and Existing Coated Wood Surfaces, Except Floors:

a. Surface Cleaning: Clean wood surfaces of foreign matter. Verify that surfaces are free from dust and other deleterious substances and in a condition approved by the Contracting Officer prior to receiving paint or other finish. Do not use water to clean uncoated wood. Scrape to remove loose coatings. Lightly sand to roughen the entire area of previously enamel-coated wood surfaces.

b. Removal of Fungus and Mold: Wash existing coated surfaces with a solution composed of 3 ounces (2/3 cup) trisodium phosphate, one ounce (1/3 cup) household detergent, one quart 5 percent sodium hypochlorite solution and 3 quarts of warm water. Rinse thoroughly with fresh water.

c. Do not exceed 12 percent moisture content of the wood as measured by a moisture meter in accordance with ASTM D4444, Method A, unless otherwise authorized.

d. Prime or touch up wood surfaces adjacent to surfaces to receive water-thinned paints before applying water-thinned paints.

e. Cracks and Nailheads: Set and putty stop nailheads and putty cracks after the prime coat has dried.

f. Cosmetic Repair of Minor Defects:

(1) Knots and Resinous Wood: Prior to application of coating, cover knots and stains with two or more coats of 3-pound-cut shellac varnish, plasticized with 5 ounces of castor oil per gallon. Scrape away existing coatings from knotty areas, and sand before treating. Prime before applying any putty over shellacked area.

(2) Open Joints and Other Openings: Fill with whiting putty, linseed oil putty. Sand smooth after putty has dried.

(3) Checking: Where checking of the wood is present, sand the surface, wipe and apply a coat of pigmented orange shellac. Allow to dry before paint is applied.

g. Prime Coat For New Exterior Surfaces: Prime coat wood doors before wood becomes dirty or warped.

3.5.2 Interior Wood Surfaces, Stain Finish

Sand interior wood surfaces to receive stain. Fill oak and other open-grain wood to receive stain with a coat of wood filler not less than 8 hours before the application of stain; remove excess filler and sand the surface smooth.

3.6 APPLICATION

3.6.1 Coating Application

a. Comply with applicable federal, state and local laws enacted to ensure compliance with Federal Clean Air Standards. Apply coating materials in accordance with SSPC PA 1. SSPC PA 1 methods are applicable to all substrates, except as modified herein.

b. At the time of application, paint must show no signs of deterioration. Maintain uniform suspension of pigments during application.

c. Unless otherwise specified or recommended by the paint manufacturer, paint may be applied by brush, roller, or spray. Use trigger operated spray nozzles for water hoses. Use rollers for applying paints and enamels of a type designed for the coating to be applied and the surface to be coated. Wear protective clothing and respirators when applying oil-based paints or using spray equipment with any paints.

d. Only apply paints, except water-thinned types, to surfaces that are completely free of moisture as determined by sight or touch.

e. Thoroughly work coating materials into joints, crevices, and open spaces. Pay special attention to ensure that all edges, corners, crevices, welds, and rivets receive a film thickness equal to that of adjacent painted surfaces.

f. Apply each coat of paint so that dry film is of uniform thickness and free from runs, drops, ridges, waves, pinholes or other voids, laps, brush marks, and variations in color, texture, and finish. Completely hide all blemishes.

g. Touch up damaged coatings before applying subsequent coats. Broom clean and clear dust from interior areas before and during the

application of coating material.

h. Apply paint to new fire extinguishing sprinkler systems including valves, piping, conduit, hangers, supports, miscellaneous metal work, and accessories. Shield sprinkler heads with protective coverings while painting is in progress. Remove sprinkler heads which have been painted and replace with new sprinkler heads. Unfinished spaces include attic spaces, spaces above suspended ceilings, crawl spaces, pipe chases, mechanical equipment room, and space where walls or ceiling are not painted or not constructed of a prefinished material. Upon completion of painting, remove protective covering from sprinkler heads.

i. Piping in Unfinished Areas: Provide primed surfaces with one coat of red alkyd gloss enamel (MPI 9) applied to a minimum dry film thickness of 1.0 mil in attic spaces, spaces above suspended ceilings, crawl spaces, pipe chases, mechanical equipment room, and spaces where walls or ceiling are not painted or not constructed of a prefinished material.

j. Piping in Finished Areas: Provide primed surfaces with two coats of paint to match adjacent surfaces, except provide valves and operating accessories with one coat of red alkyd gloss enamel (MPI 9) applied to a minimum dry film thickness of 1.0 mil or two component gloss polyurethane (MPI 72) in exterior applications.

k. Provide labeling on the surfaces of all feed and cross mains to show the pipe function such as "Sprinkler System", "Fire Department Connection", "Standpipe". For pipe sizes 4-inch and larger provide white painted stenciled letters and arrows, a minimum of 2 in in height and visible from at least two sides when viewed from the floor. For pipe sizes less than 4-inch, provide white painted stenciled letters and arrows, a minimum of 0.75 in in height and visible from the floor.

l. All fire suppression system valves must be marked with permanent tags indicating normally open or normally closed.

m. Drying Time: Allow time between coats, as recommended by the coating manufacturer, to permit thorough drying, but not to present topcoat adhesion problems. Provide each coat in specified condition to receive next coat.

n. Primers, and Intermediate Coats: Do not allow primers or intermediate coats to dry more than 30 days, or longer than recommended by manufacturer, before applying subsequent coats. Follow manufacturer's recommendations for surface preparation if primers or intermediate coats are allowed to dry longer than recommended by manufacturers of subsequent coatings. Cover each preceding coat or surface completely by ensuring visually perceptible difference in shades of successive coats.

o. Finished Surfaces: Provide finished surfaces free from runs, drops, ridges, waves, laps, brush marks, and variations in colors.

p. Thermosetting Paints: Apply topcoats over thermosetting paints (epoxies and urethanes) within the overcoat window recommended by the manufacturer.

3.6.2 Mixing and Thinning of Paints

Reduce paints to proper consistency by adding fresh paint, except when thinning is mandatory to suit surface, temperature, weather conditions, application methods, or for the type of paint being used. Obtain written permission from the Contracting Officer to use thinners. Verify that the written permission includes quantities and types of thinners to use.

When thinning is allowed, thin paints immediately prior to application with not more than one pint of suitable thinner per gallon. The use of thinner does not relieve the Contractor from obtaining complete hiding, full film thickness, or required gloss. Thinning cannot cause the paint to exceed limits on volatile organic compounds. Do not mix paints of different manufacturers.

3.6.3 Two-Component Systems

Mix two-component systems in accordance with manufacturer's instructions. Follow recommendation by the manufacturer for any thinning of the first coat to ensure proper penetration and sealing for each type of substrate.

3.6.4 Coating Systems

a. Systems by Substrates: Apply coatings that conform to the respective specifications listed in the following Tables:

Table for Exterior Applications	
MPI Division	Substrate Application
MPI Division 5	Exterior Ferrous Paint Table

Table for Interior Applications	
MPI Division	Substrate Application
MPI Division 4	Interior Concrete Masonry Units Paint Table
MPI Division 5	Interior Ferrous Paint Table

Table for Interior Applications	
MPI Division 6	Interior Wood Paint Table
MPI Division 9	Interior Gypsum Board Paint Table

b. Minimum Dry Film Thickness (DFT): Apply paints, primers, varnishes, enamels, undercoats, and other coatings to a minimum dry film thickness of 1.5 mil each coat unless specified otherwise in the Tables. Coating thickness, where specified, refers to the minimum dry film thickness.

c. Coatings for Surfaces Not Specified Otherwise: Coat unspecified surfaces the same as surfaces having similar conditions of exposure.

d. Existing Surfaces Damaged During Performance of the Work, Including New Patches In Existing Surfaces: Coat surfaces with the following:

(1) One coat of primer.

(2) One coat of undercoat or intermediate coat.

(3) One topcoat to match adjacent surfaces.

e. Existing Coated Surfaces To Be Painted: Apply coatings conforming to the respective specifications listed in the Tables herein, except that pretreatments, sealers and fillers need not be provided on surfaces where existing coatings are soundly adhered and in good condition. Do not omit undercoats or primers.

3.7 COATING SYSTEMS FOR METAL

Apply coatings of Tables in MPI Division 5 for Exterior and Interior.

a. Apply specified ferrous metal primer to steel surfaces on the same day that surface is cleaned, to surfaces that meet all specified surface preparation requirements at time of application.

b. Inaccessible Surfaces: Prior to erection, use one coat of specified primer on metal surfaces that will be inaccessible after erection.

c. Shop-primed Surfaces: Touch up exposed substrates and damaged coatings to protect from rusting prior to applying field primer.

d. Surface Previously Coated with Epoxy or Urethane: Apply MPI 101, 1.5 mils DFT immediately prior to application of epoxy or urethane coatings.

e. Pipes and Tubing: The semitransparent film applied to some pipes and tubing at the mill is not to be considered a shop coat. Overcoat these items with the specified ferrous-metal primer prior to application of finish coats.

f. Exposed Nails, Screws, Fasteners, and Miscellaneous Ferrous Surfaces. On surfaces to be coated with water thinned coatings, spot prime exposed nails and other ferrous metal with latex primer MPI 107.

3.8 COATING SYSTEMS FOR CEMENTITIOUS SUBSTRATES

Apply coatings of Tables in MPI Division 4 for Exterior and Interior.

3.9 COATING SYSTEMS FOR WOOD

a. Apply coatings of Tables in MPI Division 6 for Exterior and Interior.

b. Prior to erection, apply two coats of specified primer to treat and prime wood surfaces which will be inaccessible after erection.

c. Apply stains in accordance with manufacturer's printed instructions.

3.10 PIPING IDENTIFICATION

Piping Identification, Including Surfaces In Concealed Spaces: Provide in accordance with MIL-STD-101. Place stenciling in clearly visible locations. On piping not covered by MIL-STD-101, stencil approved names or code letters, in letters a minimum of 1/2 inch high for piping and a minimum of 2 inches high elsewhere. Stencil arrow-shaped markings on piping to indicate direction of flow using black stencil paint.

3.11 INSPECTION AND ACCEPTANCE

In addition to meeting previously specified requirements, demonstrate mobility of moving components, including swinging and sliding doors, cabinets, and windows with operable sash, for inspection by the Contracting Officer. Perform this demonstration after appropriate curing and drying times of coatings have elapsed and prior to invoicing for final payment.

3.12 WASTE MANAGEMENT

As specified in the Waste Management Plan and as follows. Do not use kerosene or any such organic solvents to clean up water based paints. Properly dispose of paints or solvents in designated containers. Close and seal partially used containers of paint to maintain quality as necessary for reuse. Store in protected, well-ventilated, fire-safe area at moderate temperature. Place materials defined as hazardous or toxic waste in designated containers. Coordinate with manufacturer for take-back program. Set aside scrap to be returned to manufacturer for recycling into new product. When such a service is not available, contact local recyclers to reclaim the materials. Where local options exist for leftover paint recycling, collect all waste paint by type and provide for delivery to recycling or collection facility for reuse by local organizations.

3.13 PAINT TABLES

All DFT's are minimum values.

3.13.1 Exterior Paint Tables

3.13.1.1 MPI Division 5: Exterior Ferrous and Non-Ferrous Paint Table

A. Steel / Ferrous Surfaces

(1) New Steel that has been hand or power tool cleaned to SSPC SP 2 or SSPC SP 3

Alkyd					
New	Existing, uncoated	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1Q-G5 (Semigloss	MPI REX 5.1D-G5 (Semigloss)	MPI 23	MPI 94	MPI 94	5.25 mils
Topcoat: Coating to match adjacent surfaces.					

B. Exterior Galvanized Surfaces

(1) New Galvanized surfaces

Waterborne Primer / Latex				
New Galvanized Surfaces	Primer	Intermediate	Topcoat	System DFT
EXT 5.3H-G5 (Semigloss)	MPI 134	MPI 11	MPI 11	4.5 mils
Topcoat: Coating to match adjacent surfaces.				

C. Exterior Surfaces, Other Metals (Non-Ferrous)

(1) Surfaces adjacent to painted surfaces; Mechanical, Electrical, Fire extinguishing sprinkler systems including valves, conduit, hangers, supports, exposed copper piping, and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment

Alkyd				
New	Primer	Intermediate	Topcoat	System DFT
MPI EXT 5.1D-G5 (Semigloss)	MPI 79	MPI 94	MPI 94	5.25 mils
Topcoat: Coating to match adjacent surfaces.				

3.13.2 Interior Paint Tables

3.13.2.1 MPI Division 4: Interior Concrete Masonry Units Paint Table

A. New and uncoated Existing Concrete Masonry

High Performance Architectural Latex					
New, uncoated Existing	Filler	Primer	Intermediate	Topcoat	System DFT

MPI INT 4.2D-G4 (Satin)	MPI 4	N/A	MPI 140	MPI 140	11 mils
Fill all holes in masonry surface					

B. New Concrete masonry units in toilets, restrooms, shower areas, and other high humidity areas

Epoxy					
New, uncoated Existing	Filler	Primer	Intermediate	Topcoat	System DFT
MPI INT 4.2G-G6 (Gloss)	MPI 116	N/A	MPI 77	MPI 77	10 mils
Fill all holes in masonry surface					

3.13.2.2 MPI Division 5: Interior Ferrous and Non-Ferrous Paint Table

A. Interior Steel / Ferrous Surfaces

(1) Metal, Mechanical, Electrical, Fire extinguishing sprinkler systems including valves, conduit, hangers, supports, Surfaces adjacent to painted surfaces (Match surrounding finish), and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment

Alkyd				
New	Primer	Intermediate	Topcoat	System DFT
MPI INT 5.1E-G5 (Semigloss)	MPI 76	MPI 47	MPI 47	5.25 mils

Topcoat: Coating to match adjacent surfaces.				

3.13.2.3 MPI Division 6: Interior Wood Paint Table

A. Interior New Wood Doors; Natural Finish or Stained

Natural finish, oil-modified polyurethane					
New		Primer	Intermediate	Topcoat	System DFT
MPI INT 6.3K-G4		MPI 57	MPI 57	MPI 57	4 mils

\	\	\	\	\	
Note: Sand between all coats per manufacturers recommendations.					

Stained, oil-modified polyurethane						
New	Existing, previously finished or stained	Stain	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.3E-G4	MPI RIN 6.3E-G4	MPI 90	MPI 57	MPI 57	MPI 57	4 mils
\	\	\	\	\	\	\
Note: Sand between all coats per manufacturers recommendations.						

B. New Wood Doors; Pigmented finish

Alkyd				
New, uncoated Existing	Primer	Intermediate	Topcoat	System DFT
MPI INT 6.3B-G5 (Semigloss)	MPI 45	MPI 47	MPI 47	4.5 mils
Note: Sand between all coats per manufacturers recommendations.				

3.13.2.4 MPI Division 9: InteriorGypsum Board\ Paint Table

A. Interior New Wallboard not otherwise specified

Institutional Low Odor / Low VOC Latex, New

Institutional Low Odor / Low VOC Latex				
New	Primer	Intermediate	Topcoat	System DFT
MPI INT 9.2M-G2 (Flat)	MPI 149	MPI 144	MPI 144	4 mils

MPI INT 9.2M-G3 (Eggshell)	MPI 149	MPI 145	MPI 145	4 mils
Topcoat: Coating to match adjacent surfaces. Use flat sheens, Ceiling White color, for ceilings. Use eggshell sheens for walls.				

B. Interior New Wallboard in toilets, restrooms, shower areas, and other high humidity areas not otherwise specified

Waterborne Light Industrial Coating					
New	Existing, previously painted	Primer	Intermediate	Topcoat	System DFT
MPI INT 9.2L-G5(Semigloss)	MPI RIN 9.2L-G5 (Semigloss)	MPI 50	MPI 153	MPI 153	4 mils
Topcoat: Coating to match adjacent surfaces.					

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 10 11 00

VISUAL DISPLAY UNITS
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

UL SOLUTIONS (UL)

UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 DEFINITIONS

The term visual display unit when used herein includes presentation boards, markerboards, tackboards, board cases, display track systems, horizontal sliding units, copyboards, interactive whiteboards, and projection screens; submit manufacturer's descriptive data and catalog cuts plus manufacturer's installation instructions, and cleaning and maintenance instructions. Provide visual display units from manufacturer's standard product line. Submit certificate of compliance signed by Contractor attesting that visual display units conform to the requirements specified.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Projection Screen; G

SD-07 Certificates

Indoor air quality for projection screen; S

SD-08 Manufacturer's Instructions

Manufacturer's Cleaning Instructions

Manufacturer's Printed Installation Instructions

SD-10 Operation and Maintenance Data

Visual Display Units, Data Package 1; G

1.4 CERTIFICATIONS

1.4.1 Indoor Air Quality

1.4.1.1 Indoor Air Quality for Visual Display Products

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party program that products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the building site in the manufacturer's original unopened containers and store them in a clean dry area with temperature maintained above 50 degrees F. Stack materials according to manufacturer's recommendations. Allow visual display units to acclimate to the building temperature for 24 hours prior to installation.

1.6 WARRANTY

Provide manufacturer's warranty to repair or replace defective materials and workmanship for period of 5 years from date of final acceptance of the work.

PART 2 PRODUCTS

2.1 PROJECTION SCREEN

Provide motorized projection screen with 120V motor that is lubricated for life, quick reversal type, has overload protector, integral gears, and preset accessible limit switches. Provide recessed mounted projection screens with an operable closure door and access panel. Provide flame retardant, mildew resistant, white matte screen with blackthat is tab tensioned. Tab tensioned screens have a vinyl surface that is stretchable. Bottom of screen fabric is weighted with a metal rod. Provide roller of rigid metal at least 3 inches in diameter mounted on sound absorbing supports. Motor is end mounted design. Provide screen with a 3 position control switch to stop or reverse screen at any point. Install the switch in a flush electrical box with cover plate, location(s) as shown on the Electrical drawings. All conduit and wiring from the control switch to the projection screen is furnished and installed by the Contractor. Provide ceiling recessed case of extruded aluminum Screen is UL listed. Comply with electrical work requirements in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide projection screens that meet the

emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type).

Provide certification of indoor air quality for projection screens.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install items that show visual evidence of biological growth. Perform installation and assembly in accordance with manufacturer's printed installation instructions. Use concealed fasteners. Attach visual display units to the walls with suitable devices to anchor each unit. Furnish and install trim items, accessories and miscellaneous items in total, including but not limited to hardware, grounds, clips, backing materials, adhesives, brackets, and anchorages incidental to or necessary for a sound, secure, complete and finished installation. Do not initiate installation until completion of room painting and finishing operations. Install visual display units in locations and at mounting heights indicated. Install visual display units level and plumb, and if applicable align doors and adjust hardware. Repair or replace damaged units as directed by the Contracting Officer.

3.2 CLEANING

Clean writing surfaces in accordance with manufacturer's cleaning instructions.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 10 14 00.10

EXTERIOR SIGNAGE
08/17, CHG 1: 11/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WELDING SOCIETY (AWS)

AWS C1.1M/C1.1	(2012) Recommended Practices for Resistance Welding
AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding Code - Steel

ASTM INTERNATIONAL (ASTM)

ASTM B26/B26M	(2018; E 2018) Standard Specification for Aluminum-Alloy Sand Castings
ASTM B108/B108M	(2019) Standard Specification for Aluminum-Alloy Permanent Mold Castings
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

1.2 GENERAL REQUIREMENTS

All exterior signage must be provided by a single manufacturer. Exterior signage must be of the design, detail, sizes, types, and message content shown on the drawings, must conform to the requirements specified, and must be provided at the locations indicated. Submit exterior signage schedule in electronic media with spread sheet format. Spread sheet must include sign location, sign type, and message. Signs must be complete with lettering, framing as detailed, and related components for a complete installation. Each sample must consist of a complete sign panel with letters and symbols. Samples may be installed in the work, provided each sample is identified and location recorded. Submit three color samples for each material requiring color and 12 inch square sample of sign face color sample.

1.2.1 Wind Load Requirements

Exterior signage must be designed to withstand 154 mph windload. Submit

design analysis and supporting calculations performed in support of specified signage.

1.2.2 Character Proportions and Heights

Letters and numbers on indicated signs for handicapped-accessible buildings must have a width-to-height ratio between 3:5 and 1:1 and a stroke-width-to-height ratio between 1:5 and 1:10. Characters and numbers on indicated signs must be sized according to the viewing distance from which they are to be read. The minimum height is measured using an upper case letter "X". Lower case characters are permitted.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Approved Detail Drawings; G

SD-03 Product Data

Installation

Exterior Signage; G

Wind Load Requirements

SD-04 Samples

Exterior Signage; G

SD-10 Operation and Maintenance Data

Protection and Cleaning; G

1.4 QUALIFICATIONS

Signs, plaques, and dimensional letters must be the standard product of a manufacturer regularly engaged in the manufacture of the products. Items of equipment must essentially duplicate equipment that has been in satisfactory use at least 2 years prior to bid opening.

1.5 DELIVERY AND STORAGE

Materials must be wrapped for shipment and storage, delivered to the jobsite in manufacturer's original packaging, and stored in a clean, dry area in accordance with manufacturer's instructions.

1.6 WARRANTY

Manufacturer's standard performance guarantees or warranties that extend beyond a one year period must be provided.

PART 2 PRODUCTS

2.1 ALUMINUM ALLOY PRODUCTS

Aluminum alloy products must conform to ASTM B209 for sheet or plate, ASTM B221 for extrusions and ASTM B26/B26M or ASTM B108/B108M for castings. Aluminum extrusions must be provided at least 1/8 inch thick and aluminum plate or sheet at least 16 gauge thick. Welding for aluminum products must conform to AWS C1.1M/C1.1.

2.2 VINYL SHEETING FOR GRAPHICS

Vinyl sheeting must be 5 to 7 year premium type and must be in accordance with the flammability requirements of ASTM E84 and must be a minimum 0.003 inch film thickness. Film must include a precoated pressure sensitive adhesive backing, Class 1, or positionable pressure sensitive adhesive backing, Class 3.

2.3 ANCHORS AND FASTENERS

Exposed anchor and fastener materials must be compatible with metal to which applied and must match in color and finish and must be non-rusting, non-corroding, and non-staining. Exposed fasteners must be tamper-proof.

2.4 SHOP FABRICATION AND MANUFACTURE

2.4.1 Factory Workmanship

Work must be assembled in the shop, as far as practical, ready for installation at the site. Work that cannot be shop assembled must be given a trial fit in the shop to ensure proper field assembly. Holes for bolts and screws must be drilled or punched. Drilling and punching must produce clean, true lines and surfaces. Welding to or on structural steel must be in accordance with AWS D1.1/D1.1M. Exposed surfaces of work must have a smooth finish and exposed riveting must be flush. Fastenings must be concealed where practical. Joints exposed to the weather must be formed to exclude water. Drainage and weep holes must be included as required to prevent condensation buildup.

2.4.2 Dissimilar Materials

Where dissimilar metals are in contact, or where aluminum is in contact with concrete, mortar, masonry, wet or pressure-treated wood, or absorptive materials subject to wetting, the surfaces must be protected with a coat of asphalt varnish or a coat of zinc-molybdate primer to prevent galvanic or corrosive action.

2.5 COLOR, FINISH, AND CONTRAST

Color must be as indicated on the drawings. Color listed is not intended to limit the selection of equal colors from other manufacturers. For buildings required to be handicapped-accessible, the characters and background of signs must be eggshell, matte, or other non-glare finish. Characters and symbols must contrast with their background - either light characters on a dark background or dark characters on a light background.

PART 3 EXECUTION

3.1 INSTALLATION

Signs must be installed in accordance with approved manufacturer's instructions at locations shown on the approved detail drawings; submit drawings showing elevations of each type of sign; dimensions, details, and methods of mounting or anchoring; shape and thickness of materials; and details of construction. A schedule showing the location, each sign type, and message must be included. Signs must be installed plumb and true at mounting heights indicated, and by method shown or specified. Signs mounted on other surfaces must not be installed until finishes on such surfaces have been completed. Submit manufacturer's installation instructions and cleaning instructions.

3.1.1 Anchorage

Anchorage and fastener materials must be in accordance with approved manufacturer's instructions for the indicated substrate. Anchorage not otherwise specified or indicated must include slotted inserts, expansion shields, and powder-driven fasteners when approved for concrete; toggle bolts and through bolts for masonry; machine carriage bolts for steel; lag bolts and screws for wood.

3.1.2 Protection and Cleaning

The work must be protected against damage during construction. Clean in accordance with manufacturer's instructions. Submit 6 copies of maintenance instructions listing routine maintenance procedures, possible breakdowns and repairs, and troubleshooting guides.

-- End of Section --

SECTION 10 14 00.20

INTERIOR SIGNAGE
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF45	(2003; Reaffirmed 2009) Designation System for Aluminum Finishes
AA PK-1	(2015) Pink Sheets: Designations and Chemical Composition Limits for Aluminum Alloys in the Form of Castings & Ingot

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 2604	(2017a) Voluntary Specification, Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels

AMERICAN WELDING SOCIETY (AWS)

AWS D1.2/D1.2M	(2014; Errata 1 2014; Errata 2 2020) Structural Welding Code - Aluminum

ASTM INTERNATIONAL (ASTM)

ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes

INTERNATIONAL CODE COUNCIL (ICC)

ICC A117.1 COMM	(2017) Standard And Commentary Accessible and Usable Buildings and Facilities

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101	(2024) Life Safety Code

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191	Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act

(ABA) Accessibility Guidelines

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings; G

SD-03 Product Data

Installation; G

Warranty; G

SD-04 Samples

Interior Signage; G

Software; G

SD-10 Operation and Maintenance Data

Approved Manufacturer's Instructions; G

Protection and Cleaning; G

1.3 EXTRA MATERIALS

Provide 3 extra frames and extra stock of the following: blank plates of each color and size for each sign type. Provide 3 extra changeable message strips for each sign type. Provide 3 paper inserts per sign and one copy of the software for user produced signs and inserts after project completion and equipment necessary for removal of signage parts and pieces.

1.4 QUALITY ASSURANCE

1.4.1 Samples

Submit interior signage samples of each of the following sign types showing typical quality, workmanship and color: Directional sign, Standard Room sign, Changeable message strip sign. The samples may be installed in the work, provided each sample is identified and location recorded.

1.4.2 Detail Drawings

Submit detail drawings showing elevations of each type of sign, dimensions, details and methods of mounting or anchoring, mounting height, shape and thickness of materials, and details of construction. Include a schedule showing the location, each sign type, and message.

1.5 DELIVERY, STORAGE, AND HANDLING

Materials must be packaged to prevent damage and deterioration during shipment, handling, storage and installation. Product must be delivered to the jobsite in manufacturer's original packaging and stored in a clean, dry area in accordance with manufacturer's instructions.

1.6 WARRANTY

Warrant the interior signage for a period of 2 years against defective workmanship and material. Warranties must be signed by the authorized representative of the manufacturer. Submit warranty accompanied by the document authenticating the signer as an authorized representative of the guarantor. Guarantee that the signage products and the installation are free from any defects in material and workmanship from the date of delivery.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Signs, plaques, directories, and dimensional letters must be the standard product of a manufacturer regularly engaged in the manufacture of such products that essentially duplicate signs that have been in satisfactory use at least 2 years prior to bid opening. Obtain signage from a single manufacturer with edges and corners of finished letterforms and graphics true and clean.

2.2 ROOM IDENTIFICATION/DIRECTIONAL SIGNAGE SYSTEM

2.2.1 Standard Room Signs

Signs must incorporate an ABS plastic face with applied graphics including all tactile requirements in adherence to ABA and ADA requirements. All signs must have matching appearance and construction utilizing the same manufacturing process to assure consistent look and quality and must conform to the following:

a. Signage must utilize an acrylic sphere for Grade II Braille inserted directly into a scratch resistant, high pressure laminate sign face. Braille dots are to be pressure fit in high tolerance drilled holes. Braille dots must be half hemispherical domes, protruding a minimum of 0.025".

b. End caps must be aluminum style corners.

c. Tactile Lettering must be precision machined, raised 1/32", matte PETG and subsurface colored for scratch resistance.

2.2.2 Changeable Message Strip Signs

Changeable message strip signs must be of same construction as standard room signs to include a clear sleeve that will accept a paper or plastic insert identifying changeable text. The insert must be prepared typeset message mounted on paper card stock. Provide paper and software for creating text and symbols for computers identified by owner for Owner production of paper inserts after project completion. Clear sleeve must be removable without any special tools.

2.2.3 Type of Mounting For Signs

Mounting for framed, hanging, and projecting signs must be by mechanical fasteners. Surface mounted signs must be mounted with countersunk mounting holes in plaques and mounting screws. All signs must be provided with appropriate mounting hardware for the wall substrate. Hardware must be finished and architectural in appearance. Some signs may be mounted on glass. A blank backer is required.

2.2.4 Graphics

Signage graphics for modular signs must conform to the following:

2.2.4.1 Subsurface Copy

Copy is transferred to the back face of clear acrylic sheeting forming the panel face to produce precisely formed opaque image. This method bonds all sign elements (color, graphics, lettering, Braille and substrate) into a single unit.

2.2.4.2 First Surface Copy Direct Print or Silkscreened (Non-Tactile)

Message may be applied to panel using the silkscreen process. Silkscreened images must be executed with photo screens prepared from original art. Handcut screens will not be accepted. Original art is defined as artwork that is a first generation reproduction of the specified art. Edges and corners must be clean.

2.2.4.3 Surface Applied Photopolymer

Integral graphics and Braille achieved by photomechanical stratification processes. Photopolymer used for ADA compliant graphics must be of the type that has a minimum durometer reading of 90. Tactile graphics must be raised 1/32 inch from the first surface of plaque by photomechanical stratification process.

2.2.5 Character Proportions and Heights

Letters and numbers on signs conform to 36 CFR 1191.

2.2.6 Tactile Letters, Symbols and Braille

Raised letters and numbers on signs must conform to 36 CFR 1191.

2.3 STAIR SIGNAGE

Provide signs on stairs serving three or more stories with special signage within the enclosure at each floor landing conforming to NFPA 101. Indicate the floor level, the terminus of the top and bottom of the stair enclosure, and the identification of the stair enclosure. Also, state the floor level of, and the direction to, exit discharge. Locate the signage inside the enclosure in a position that is visible when the door is in the open or closed position and install in conformance with 36 CFR 1191. The floor level designation must also be tactile in accordance with ICC A117.1 COMM.

2.4 BUILDING DIRECTORIES

Building directories must be lobby directories or floor directories, and

must be provided with a changeable directory listing consisting of the areas, offices and personnel located within the facility. Dimensions, details, and materials of sign and message content must be as shown on the drawings.

2.5 ALUMINUM ALLOY PRODUCTS

Aluminum extrusions must be at least 1/8 inch thick, and aluminum plate or sheet must be at least 0.0508 inch thick. Extrusions must conform to ASTM B221; plate and sheet must conform to ASTM B209. Where anodic coatings are specified, alloy must conform to AA PK-1 alloy designation 514.0. Exposed anodized aluminum finishes must be as shown. Welding for aluminum products must conform to AWS D1.2/D1.2M.

2.6 ANODIC COATING

Anodized finish must conform to AA DAF45 as follows:

a. Clear (natural) designation AA-M10-C22-A31, Architectural Class II 0.4 mil or thicker.

2.7 ORGANIC COATING

Organic coating must conform to AAMA 2604, with total dry film thickness not less than 1.2 mils.

2.8 FABRICATION AND MANUFACTURE

2.8.1 Factory Workmanship

Holes for bolts and screws must be drilled or punched. Drilling and punching must produce clean, true lines and surfaces. Exposed surfaces of work must have a smooth finish and exposed riveting must be flush. Fastenings must be concealed where practicable.

2.8.2 Dissimilar Materials

Where dissimilar metals are in contact, the surfaces will be protected to prevent galvanic or corrosive action.

2.9 COLOR, FINISH, AND CONTRAST

Color must be as indicated on the drawings. Finish of all signs must be eggshell, matte, or other non-glare finish as required in handicapped-accessible buildings.

2.10 TYPEFACE

ADA-ABA compliant font for Room Signs.

PART 3 EXECUTION

3.1 INSTALLATION

Signs must be installed plumb and true and in accordance with approved manufacturer's instructions at locations shown on the detail drawings. Submit six copies of operating instructions outlining the step-by-step procedures required for system operation. The instructions must include simplified diagrams for the system as installed, the manufacturer's name,

model number, service manual, parts list, and brief description of all equipment and their basic operating features. Each set must be permanently bound and must have a hard cover. The following identification must be inscribed on the covers: the words "OPERATING AND MAINTENANCE INSTRUCTIONS", name and location of the facility, name of the Contractor, and contract number. Mounting height and mounting location must conform to 36 CFR 1191. Required blocking must be installed. Signs on doors or other surfaces must not be installed until finishes on such surfaces have been installed. Signs installed on glass surfaces must be installed with matching blank back-up plates in accordance with manufacturer's instructions.

Do not install items that show visual evidence of biological growth.

3.1.1 Anchorage

Anchorage must be in accordance with approved manufacturer's instructions. In high humidity interior spaces (for example, bathrooms, locker rooms, pools, trainers) and unconditioned spaces, use corrosion-resistant anchors/fasteners or with approval by the manufacturer, waterproof silicone adhesive. Anchorage not otherwise specified or shown must include slotted inserts, expansion shields, and powder-driven fasteners when approved for concrete; toggle bolts and through bolts for masonry; machine carriage bolts for steel; lag bolts and screws for wood. Exposed anchor and fastener materials must be compatible with metal to which applied and must have matching color and finish. At interior applications in heavy traffic areas, firmly attach signage to structure walls with tamper-proof fasteners.

a. Signs mounted to painted gypsum board surfaces must be removable for painting maintenance.

b. Mount signs mounted to lay-in ceiling grids with clip connections to ceiling tees.

c. Install signs mounted on metal surfaces with magnetic tape.

d. Install signs mounted on fabric surfaces with hook and loop tape or pin mount.

3.1.2 Protection and Cleaning

Protect the work against damage during construction. Hardware and electrical equipment must be adjusted for proper operation. Glass, frames, and other sign surfaces must be cleaned at completion of sign installation in accordance with the manufacturer's approved instructions and the requirements of Section 01 78 23 OPERATION AND MAINTENANCE DATA, Package 1. Submit six copies of maintenance instructions listing routine procedures, repairs, and guides.

-- End of Section --

SECTION 10 21 13

TOILET COMPARTMENTS
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ALUMINUM ASSOCIATION (AA)

AA DAF45	(2003; Reaffirmed 2009) Designation System for Aluminum Finishes

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A167	(2011) Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
ASTM A385/A385M	(2020) Standard Practice for Providing High-Quality Zinc Coatings (Hot-Dip)
ASTM D7611/D7611M	(2013; E 2014) Standard Practice for Coding Plastic Manufactured Articles for Resin Identification

INTERNATIONAL CODE COUNCIL (ICC)

ICC A117.1	(2017) Standard And Commentary Accessible and Usable Buildings and Facilities

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-60003	(Basic; Notice 1) Partitions, Toilet, Complete

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191	Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G"

classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Fabrication Drawings

Installation Drawings; G

SD-03 Product Data

Cleaning and Maintenance Instructions

Colors And Finishes

Anchoring Devices and Fasteners

Hardware and Fittings

Brackets

Door Hardware

Toilet Enclosures

Urinal Screens

Pilaster Shoes

Finishes; G

SD-04 Samples

Colors and Finishes; G

Hardware and Fittings

Anchoring Devices and Fasteners

SD-07 Certificates

Warranty

SD-10 Operation and Maintenance Data

Plastic Identification; G

1.3 CERTIFICATIONS

1.4 REGULATORY REQUIREMENTS

Comply with to ICC A117.1 code for access for the handicapped operation of toilet compartment door and hardware.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver materials in the manufacturer's original unopened packages with the brand, item identification, and project reference clearly marked.

Store components in a dry location that is adequately ventilated; free from dust, water, other contaminants, and damage during delivery, storage, and construction.

1.6 WARRANTY

Provide manufacturer's warranty to repair or replace defective materials and workmanship for a period of one year from date of final acceptance of the work.

PART 2 PRODUCTS

2.1 SYSTEM REQUIREMENTS

Provide a complete and usable toilet partition system, including toilet enclosures, room entrance screens, urinal screens, system of panels, hardware, and support components. Furnish the partition system from a single manufacturer, with a standard product as shown in the most recent catalog data. Submit Fabrication Drawings for toilet partitions and urinal screens consisting of fabrication and assembly details to be performed in the factory. Submit manufacturer's Cleaning and Maintenance Instructions in accordance with Section 01 78 23 OPERATIONS AND MAINTENANCE DATA.

2.1.1 Plastic Identification

Verify that plastic products to be incorporated into the project are labeled in accordance with ASTM D7611/D7611M. Where products are not labeled, provide product data indicating polymeric information in the Operation and Maintenance Manual.

Type 2	High Density Polyethylene (HDPE)

2.2 MATERIALS

2.2.1 Solid Polyethylene Panels (Finish 5)

Provide high density polyethylene (HDPE) suitable for exposed application. Waterproof, non-absorbent and graffiti resistant textured surface with a Flame Spread Index of 75 or less, and a Smoke Developed Index of 450 or less.

2.2.2 Anchoring Devices and Fasteners

Provide steel anchoring devices and fasteners hot-dipped galvanized after fabrication, in conformance with ASTM A385/A385M and ASTM A123/A123M. Conceal all galvanized anchoring devices.

2.2.3 Brackets

Provide two-ear panel wall brackets, T-style, 1 inch stock. Provide stirrup style panel-to-pilaster brackets.

2.2.4 Hardware and Fittings

2.2.4.1 General Requirements

Provide hardware for the toilet partition system that complies with CID A-A-60003 for the specified type and style of partitions. Provide hardware finish highly resistant to alkalis, urine, and other common toilet room acids. Comply with 36 CFR 1191 of latching devices and hinges for handicap compartments; provide stainless steel devices and hinges with door latches that operate without either tight grasping or twisting of the wrist of the operator. Submit three samples of each item, including anchoring devices and fasteners. Approved hardware samples may be installed in the work if properly identified.

Material	Conformance Standard
Corrosion-resistant steel	ASTM A167, Type 302

2.2.4.2 Finishes

a. Provide stainless steel with a No. 4 finish.

f. Provide exposed fasteners that match the hardware and fittings.

2.2.5 Door Hardware

2.2.5.1 Hinges

Adjust hinges to hold in-swinging doors open at any angle up to 90 degrees and outswinging doors up to 10 degrees. Provide continuous, self-lubricating hinges with the indicated swing. Provide hinges that are surface-mounted type and have the following type of return movement:

a. Gravity return movement

2.2.5.2 Latch and Pull

Provide latch and pull that is a combination rubber-faced door strike and

keeper equipped with emergency access. Provide surface mounted latch.

2.2.5.3 Coat Hooks

Provide coat hooks that are combination units with hooks and rubber tipped pins.

2.3 PARTITION PANELS AND DOORS

Fabricate partition panels, and pilasters of materials and construction listed:

Provide plastic (HDPE) partition panels, doors and pilasters not less than 1 inch thick.

Provide solid polyethylene toilet partitions and screens with recycled content of 30 percent minimum.

2.3.1 Toilet Enclosures

Provide toilet enclosures that comply with CID A-A-60003, Type I, Style C, overhead braced. Furnish width, length, and height of toilet enclosures as shown. Finish surface of panels are solid polyethylene (Finish 5); water resistant; graffiti resistant; non-absorbent radius beveled edges. Reinforce panels indicated to receive toilet paper holders or grab bars for mounting of the items required, and provide cut outs for through partition toilet accessories. Provide grab bars to withstand a bending stress, shear stress, shear force, and a tensile force induced by 250 lbf. Grab bars cannot rotate within their fittings.

2.3.2 Urinal Screens

Provide urinal screens that comply with CID A-A-60003, Type III, Style A, floor supported. Provide finish for surface of screens as solid polyethylene (Finish 5); water resistant; graffiti resistant; non-absorbent with radius beveled edges; with manufacturer's standard post design of materials matching the thickness and construction of pilasters. Furnish width and height of urinal screens as shown. Provide thickness to match toilet compartment panel construction. Secure wall hung urinal screens with 42 inches long, continuous flanges. Fabricate screens from the same types of panels and pilasters as the toilet partitions. Use corrosion-resistant steel fittings and fasteners.

2.4 OVERHEAD-BRACED PARTITIONS

Provide pilasters in sizes indicated that are manufacturer's standard corrosion-resistant supports, leveling mechanism, and anchors at pilasters to suit floor conditions. Provide shoes at pilasters to conceal supports and leveling mechanism. Provide anchoring device at the bottom of the pilaster consisting of a channel-shaped floor stirrup fabricated from not less than 0.0635 inch thick material and a leveling bolt. Secure the stirrup to the pilaster with not less than a 3/16 inch bolt and nut after the pilaster is leveled. Secure the stirrup to the floor with not less than two lead expansion shields and sheetmetal screws. Fabricate overhead brace from a continuous extruded aluminum tube not less than 1 inch wide by 1-1/2 inch high, 0.125 inch wall thickness. Finish is AA-C22A31 in accordance with AA DAF45. Set and secure brace into the top of each pilaster. Provide shoes at pilasters to conceal supports and leveling

mechanism.

2.5 PILASTER SHOES

Provide shoes at pilasters to conceal floor-mounted anchorage. Provide one piece molded HDPE pilaster shoes. Height is a minimum 3 inches.

2.6 HARDWARE

Provide hardware for the toilet partition system that complies with CID A-A-60003 for the specified type and style of partitions. Provide hardware pre-drilled by manufacturer. Use a hardware finish that is highly resistant to alkalis, urine, and other common toilet room acids. Hardware includes: chrome plated nonferrous cast pivot hinges, gravity type, adjustable for door close positioning; nylon bearings; chrome plated aluminum door latch; door strike and keeper with rubber bumper; and cast alloy chrome plated coat hook and bumper. Provide latching devices and hinges for handicap compartments complying with 36 CFR 1191 and stainless steel door latches that operate without either tight grasping or twisting of the wrist of the operator. Use stainless steel, tamper proof type screws and bolts. Wall mounting brackets are continuous, full height, stainless steel, in accordance with toilet compartment manufacturer's instructions.. Provide floor-mounted anchorage consisting of corrosion-resistant anchoring assemblies with threaded rods, lock washers, and leveling adjustment nuts at pilasters for structural connection to floor.

2.7 COLORS AND FINISHES

2.7.1 Colors

Provide color as indicated; colors listed are not intended to limit the selection of equal colors from other manufacturers. Reference the Instruments of Service for HDP-1/.

Color of pilaster shoes matches the core of solid plastic compartments and screens. Submit three samples showing color and a finished edge on two adjacent sides and core construction, each not less than 12 inch square.

2.7.2 Finishes

2.7.2.1 Finishes No. 4, No 4A and No. 5

Provide manufacturer's standard solid polyethylene (Finish 5) formed under high pressure rendering a single component section not less than 1 inch thick. Colors extend throughout the panel thickness.

PART 3 EXECUTION

3.1 PREPARATION

Take field measurements prior to the preparation of drawing and fabrication to ensure proper fits. Verify that field measurements, surfaces, substrates and conditions are as required, and ready to receive work. Verify correct spacing of plumbing fixtures. Verify correct location of built in framing, anchorage, and bracing. Report in writing to Contracting Officer prevailing conditions that adversely affect satisfactory execution of the work of this section. Do not proceed with work until unsatisfactory conditions have been corrected.

3.2 INSTALLATION

Do not install items that show visual evidence of biological growth. Install partitions rigid, straight, plumb, and level, with the panels centered between the fixtures. Provide a panel clearance of not more than 1/2 inch and secure the panels to walls and pilasters with continuous full height wall brackets. Locate wall brackets so that holes for wall bolts occur in masonry or tile joints. Secure panels to pilasters with brackets matching the wall brackets. Provide for adjustment due to minor floor variations. Locate head rail joints at pilaster center lines. Install adjacent components for consistency of line and plane. Equip each door with hinges, one door latch, and one coat hook and bumper. Align hardware to uniform clearance at vertical edges of doors.

a. Secure panels to hollow plastered walls with toggle bolts using not less than 1/4-20 screws of the length required for the wall thickness. Provide toggle bolts with a load-carrying strength of not less than 600 pounds per anchor.

b. Secure panels to ceramic tile on hollow plastered walls or hollow concrete-masonry walls with toggle bolts using not less than 1/4-20 screws of the length required for the wall thickness. Provide toggle bolts with a load-carrying strength of not less than 600 pounds per anchor.

c. Secure panels to solid masonry or concrete with lead or brass expansion shields designed for use with not less than 1/4-20 screws, with a shield length of not less than 1-1/2 inches. Provide expansion shields with a load-carrying strength of not less than 600 pounds per anchor.

d. Submit Installation Drawings for toilet partitions, room entrance screens, and urinal screens showing plans, elevations, details of construction, hardware, reinforcing and blocking, fittings, mountings and escutcheons. Indicate on drawings the type of partition, location, mounting height, cutouts, and reinforcement required for toilet-room accessories.

3.3 OVERHEAD-BRACED PARTITIONS

Secure pilasters to the floor with the anchorage device specified. Make all leveling devices readily accessible for leveling, plumbing, and tightening the installation. Secure overhead brace to the pilaster face with not less than two fasteners per face. Expansion shields have a minimum 2 inch penetration into the concrete slab. Make tops of doors parallel with the overhead brace when doors are in a closed position.

3.4 FINAL ADJUSTMENT

After completion of the installation, make final adjustments to the pilaster-leveling devices, door hardware, and other working parts of the partition assembly. Doors have a uniform vertical edge clearance of approximately 3/16 inch and rest open at approximately 30 degrees when unlatched.

3.5 CLEANING

Clean all surfaces and adjacent surfaces soiled as a result of the work,

in an approved manner compliant with the manufacturer's recommended cleaning and protection from damage procedures until accepted. Remove all equipment, tools, surplus materials, and work debris from the site.

-- End of Section --

SECTION 10 22 13

WIRE MESH PARTITIONS
08/16, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISI SG03-3	(2002; Suppl 2001-2004; R 2008) Cold-Formed Steel Design Manual Set

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Wire Mesh Partitions

Show layout, details, materials, dimensions, finishes, and all information necessary for fabrication and installation.

SD-03 Product Data

Wire Mesh Partitions

Submit for each type of partition, door, and window.

Recycled Content for Metal Post and Framing Materials; S

Recycled Content for Wire Materials; S

1.3 DELIVERY, STORAGE, AND HANDLING

Deliver materials in manufacturer's original, unopened containers or packaging with labels intact and legible. Deliver, store, and handle materials so as to prevent damage. Replace damaged or defective materials with new.

1.4 DESCRIPTION OF WORK

Wire mesh partitions must be all wire type, normal duty for normal industrial use. Provide partitions complete with fasteners, capping bars, adjustable floor sockets, bracing, doors, service windows, hardware, and other items necessary for a complete, useable, and rigid installation.

Furnish wire mesh partitions for Building A1, Battalion/Dept Storage 193. Nominal partition height is 14 feet, 0 inches with wire mesh caps.

Furnish wire mesh partitions for Building A3, Open Storage 108. Nominal partition height is 22 feet, 0 inches with the top of the wall extending to the structure above.

PART 2 PRODUCTS

2.1 MATERIALS

Metal post and framing materials listed below must contain a minimum of 15 percent post-consumer recycled content and wire materials must contain a minimum of 50 percent post-industrial recycled content. Provide data identifying percentage of recycled content for metal post and framing materials. Also provide data identifying percentage of recycled content for wire materials.

2.1.1 Steel Shapes, Plates, and Bars

ASTM A36/A36M.

2.1.2 Cold-Formed Steel

AISI SG03-3.

2.1.3 Wire Mesh

Carbon steel wire, woven diamond mesh, intermediate crimped.

2.1.4 Floor Sockets

Cast or forged steel or ductile iron, adjustable, approximately 2-1/2 inches high.

2.2 NORMAL DUTY PARTITIONS

2.2.1 Wire Mesh

10 gage wire, 1-1/2 inch mesh.

2.2.2 Vertical Frames

1-1/4 by 5/8 inch cold-rolled C section channels or 1-1/4 by 5/8 by 1/8 inch channels. Provide only C channels where frames are installed toe to toe without posts.

2.2.3 Horizontal Frames

1 by 5/8 inch channels.

2.2.4 Center Reinforcing Bar

One 1 by 1/2 by 1/8 inch channel with all wires woven through, or two 1 by 3/8 by 1/8 inch channels bolted together with mesh in between.

2.2.5 Capping Bar

2-1/4 by one by 1/8 inch channel or 2 by 1/4 inch flat bar.

2.2.6 Corner Posts

Structural steel angles, 1-1/4 by 1-1/4 by 1/8 inch.

2.2.7 Line Posts

Unless otherwise indicated, provide partitions more than 12 feet high with flat bar line posts bolted between vertical frame channels. Sizes of posts must be as follows:

Partition Height	Size of Posts
12 feet to 14 feet 8 inches	1-3/4 by 5/16 inch or 2 by 1/4 inch
14 feet 8 inches to 19 feet 8 inches	2-1/2 by 5/16 inch
19 feet 8 inches to 23 feet 8 inches	3 by 5/16 inch

2.3 SLIDING DOORS

Frames must be 1-1/2 by 3/4 by 1/8 inch channels with 1-1/2 by 1/8 inch flat bar cover all around. Provide two four-wheel, roller bearing hangers and steel box track for each door.

Building A1 sliding doors have a nominal 3 foot, 0 inch by 7 foot, 0 inch clear opening.

Building A3 sliding doors have a nominal 6 foot, 0 inch by 7 foot, 0 inch clear opening.

2.4 DOOR OPENING FRAMES

Provide frames the same size and shape as the vertical frames for the mesh panels.

2.5 LOCKS

Provide each door with a mortise type lock with a seven-pin tumbler lock cylinder on the outside and a recessed knob on the inside.

2.6 SERVICE WINDOWS

Slide up type, mounted in standard mesh panel reinforced with channel tracks. Opening must be 24 inches wide by 15 inches high unless otherwise indicated. Provide two spring loaded latches, operable only from the inside, to lock window in open and closed positions.

2.7 FABRICATION

2.7.1 Standard Panels

Wire must be woven into diamond mesh, intermediate crimped, and securely clinched to frames. Joints must be mortised and tenoned. Wire must be continuous at center reinforcing bars, either woven through a single channel or bolted between two channels. Panel vertical frames must have 1/4 inch bolt holes 12 inches o.c. for normal duty partitions.

2.7.2 Sheet Metal Base Panels

Upper portion must be as specified for standard panels, except that the wire must be clinched into the center reinforcing bar. Form sheet steel to fit between the panel frames and securely bolt to the frames.

2.7.3 Doors

Construction must be similar to that specified for panels. Wire mesh must be the same as that used in the adjacent partition panels.

2.7.4 Finish

Thoroughly clean ferrous metal, treat with phosphate, and paint with gray enamel in the shop.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Wire Mesh Partitions

Install plumb, level, and true to line, within a tolerance of 1/8 inch in 10 feet or the height or run of the partition, if less than 10 feet. Anchor floor sockets to the floor with expansion bolts. Bolt vertical frames and posts together with 1/4 inch bolts 12 inches o.c. for normal duty partitions. Secure top frames to a continuous capping bar with 1/4 inch diameter U bolts not more than 28 inches o.c.

3.1.2 Doors

Install in accordance with the manufacturers' recommendations. Adjust as required so that doors and hardware operate freely and properly.

3.1.3 Bracing

Brace free standing partitions more than 20 feet in length, at intervals not greater than 20 feet with a steel channel brace connected to the capping bar and anchored to the building wall or framing member.

3.1.4 Touch-Up

Clean and paint scratches, abrasions, and other damage to shop painted surfaces to match the shop-applied finish.

Repair minor surface rust areas. Clean and prime with rust inhibitive primer paint. Apply final paint to match shop-applied finishes.

3.2 HARDWARE SETS

3.2.1 A1, BATALLION HEADQUARTERS WIRE MESH PARTITION HARDWARE SCHEDULE

Interior Openings

HWS-A1.47	Sliding Door Leaf	193 Battalion/ Dept Storage
	2 each Four Wheel, Ball Bearing Trucks	626
	1 each Recessed Knob	630
Section 08 71 00	1 each Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each SFIC, F24, E09241	630

Note: Quantity of 12

HWS-A1.48	Sliding Door Leaf, FF&E E22	194 Individual Cage Storage
	2 each Four Wheel, Ball Bearing Trucks	626
	1 each Recessed Knob	630
Section 08 71 00	1 each Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each SFIC, F24, E09241	630

Note: Quantity of 54

3.2.2 A2-1, CO BUILDING WIRE MESH PARTITION HARDWARE SCHEDULE

Interior Openings

HWS-A2-1.31	Sliding Door Leaf, FF&E E23	130 & 140 Individual Cage Storage
	2 each Four Wheel, Ball Bearing Trucks	626
	1 each Recessed Knob	630
Section 08 71 00	1 each Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each SFIC, F24, E09241	630

Note: Quantity of 137

HWS-A2-1.32	Sliding Door Leaf, FF&E E24	130 & 140 Individual Cage Storage
	2 each Four Wheel, Ball Bearing Trucks	626
	1 each Recessed Knob	630
Section 08 71 00	1 each Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each SFIC, F24, E09241	630

Note: Quantity of 48

3.2.3 A2-2, CO BUILDING WIRE MESH PARTITION HARDWARE SCHEDULE

Interior Openings

HWS-A2-2.31	Sliding Door Leaf, FF&E E23	130 & 140 Individual Cage Storage
	2 each Four Wheel, Ball Bearing Trucks	626
	1 each Recessed Knob	630
Section 08 71 00	1 each Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each SFIC, F24, E09241	630

Note: Quantity of 137

HWS-A2-2.32	Sliding Door Leaf, FF&E E24	130 & 140 Individual Cage Storage
	2 each Four Wheel, Ball Bearing Trucks	626
	1 each Recessed Knob	630
Section 08 71 00	1 each Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each SFIC, F24, E09241	630

Note: Quantity of 48

3.2.4 A3, CO STORAGE WIRE MESH PARTITION HARDWARE SCHEDULE

Interior Openings

HWS-A3.12	Sliding Door Pair	108 Open Storage
	4 each Four Wheel, Ball Bearing Trucks	626
	1 each Recessed Knob	630
Section 08 71 00	1 each Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each SFIC, F24, E09241	630
	1 each Slide Bolt Set	626

Note: Quantity of 1

-- End of Section --

SECTION 10 26 00

WALL AND DOOR PROTECTION
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A240/A240M	(2025a) Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE J1545	(2005; R 2021) Instrumental Color Difference Measurement for Exterior Finishes, Textiles and Colored Trim

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2022) Adhesive and Sealant Applications

UNDERWRITERS LABORATORIES (UL)

UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Corner Guards; G

SD-03 Product Data

Corner Guards; G

SD-04 Samples

Finish; G

SD-06 Test Reports

Corner Guards

SD-07 Certificates

Corner Guards

Indoor air quality for adhesives

1.3 CERTIFICATIONS

1.3.1 Indoor Air Quality

1.3.1.1 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party program that products meet the requirements of this section. Provide current product certification documentation from certification body When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein..

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the project site in manufacturer's original unopened containers with seals unbroken and labels and trademarks intact. Keep materials dry, protected from weather and damage, and stored under cover. Materials must be stored at approximately 70 degrees F for at least 48 hours prior to installation.

1.5 WARRANTY

Provide manufacturer's standard performance guarantees or warranties that extend beyond a 1 year period.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

To the maximum extent possible corner guards must be the standard products of a single manufacturer and must be furnished as detailed. Drawings show general configuration of products required, and items differing in minor details from those shown will be acceptable.

2.2 CORNER GUARDS

2.2.1 Resilient Corner Guards

Corner guard units must be mechanically fastened, flush mounted type, radius formed to profile shown. Corner guards must extend from floor to 8 feet high. Mounting hardware, cushions, and base plates must be furnished. Assembly must consist of a snap-on corner guard formed from high impact resistant resilient material, mounted on a continuous aluminum retainer. Extruded aluminum retainer must conform to ASTM B221, alloy 6063, temper T5 or T6. Provide aluminum components that contain a minimum of 35 percent recycled content. Flush mounted type guards must act as a stop for adjacent wall finish material. Factory fabricated end closure caps must be furnished for top and bottom of surface mounted corner guards. Flush mounted corner guards installed in fire rated wall must maintain the rating of the wall. Insulating materials that are an integral part of the corner guard system must be provided by the manufacturer of the corner guard system. Exposed metal portions of fire rated assemblies must have a paintable surface.

2.2.2 Stainless Steel Corner Guards

Stainless steel corner guards must be fabricated of 16 gauge thick material conforming to ASTM A240/A240M, type 302 or 304. Corner guards must extend from floor to 8 feet high. Edges of corner guards must be finished to a smooth edge with no cut, unfinished edges showing. Install corner guards in locations as shown on the drawings. Refer to drawings for finish. Corner guards must be mechanically fastened.

2.3 TRIM, FASTENERS AND ANCHORS

Provide stainless steel trim, fasteners and anchors for stainless steel corner guards. All trim, fasteners and anchors must be concealed after installation.

2.4 FINISH

Submit three samples indicating color and texture of materials requiring color and finish.

2.4.1 Stainless Steel Finish

Finish for stainless steel must be in accordance with ASTM A240/A240M, Type 302 or 304, finish number 4.

2.4.2 Resilient Material Finish

Finish for resilient material must be stipple texture with colors in accordance with SAE J1545.

2.5 ADHESIVES

Adhesive for metal material must be in accordance with manufacturers recommendations. Corner guards must be mechanically fastened. All mounting hardware must be hidden with finished product. Provide sealants and non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) that meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) the VOC content requirements of SCAQMD Rule 1168, or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for adhesives.

2.6 COLOR

Color must be as indicated on the drawings. Color listed is not intended to limit the selection of equal colors from other manufacturers.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install items that show visual evidence of biological growth.

3.1.1 Corner Guards

Material must be mounted at location indicated in accordance with manufacturer's recommendations.

3.1.2 Stainless Steel Guards

a. Mount guards on external corners of interior walls, partitions and columns as in accordance with manufacturer's recommendations for a mechanically fastened installation.

b. Where corner guards are installed on walls, partitions or columns finished with plaster or ceramic tile on steel or wood stud, anchor corner guards with number 10 1 1/2 inch S/S flat head wood screws. Coat back surfaces of corner guards, where shown, with a non-flammable, sound deadening material. Corner guards must overlap finish plaster surfaces.

c. Where corner guards are installed on exposed structural glazed facing tile units or masonry wall, partitions or columns, anchor corner guards with number 10 X 1 1/2 inch S/S flat head wood screw and AF-8 plastic anchors. Grout spaces solid between guards and backing with portland cement and sand mortar.

d. Where corner guards are installed on gypsum board, clean surfaces and anchor guards with a neoprene solvent-type contact adhesive specifically manufactured for use on gypsum board construction. Remove excess adhesive from the guard edges and allow to cure undisturbed for 24 hours.

e. For wall guards, space brackets at no more than 3 feet on centers and anchor to the wall in accordance with the manufacturer's installation instructions.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 10 28 13

TOILET ACCESSORIES
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-STD-1691 (1994; Rev F) Construction and Material Schedule for Military Medical and Dental Facilities

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Product Schedule

Submit product Schedule indicating types, quantities, sizes, and installation locations by room for each toilet accessory item required. Identify locations using room designations indicated on the drawings.

SD-03 Product Data

Recycled content for stainless steel toilet accessories; S

Sanitary Napkin Disposal (SND), SS, Surface Mounted; G

Grab Bar (GB36) (GB42), 1-1/4 inch Dia., SS, 2 Wall, W/C Accessible; G

Grab Bar: L-Shaped (GBL), 1-1/4 inch Dia., SS, 2 Wall, Shower Use; G

Shelf, Mop and Broom Holder (MHS), SS, Surf Mntd; G

Robe Hook (RH); G, Security

Shower Curtain Rod (SCR), 1 inch Diameter, W/Curtain & Hooks; G

Toilet Tissue Dispenser (TTD), SS, 2-Roll, Surface Mntd; G

Mirror (WM); G

Foam Soap Dispenser (SD); G

Towel Bar (TB), 1 inch Diameter, SS, Surface Mounted; G

Semi Recessed Waste Receptacle and Paper Towel Dispenser (ITDW); G

Shower Seat (FSS); G

Electric Hand Dryer (HD); G

Submit catalog numbers, literature, data sheets, construction details, profiles, anchoring and mounting requirements ,including cutouts in other work and substrate preparation, electrical characteristics, and other pertinent data for each toilet accessory item to evaluate function, materials, dimensions and appearance.

SD-10 Operation and Maintenance Data

Sanitary Napkin Disposal (SND), SS, Surface Mounted; G

Grab Bar (GB36) (GB42) Grab Bar, 1-1/4 inch Dia., SS, 2 Wall, W/C Accessible; G

Grab Bar: L-Shaped (GBL), 1-1/4 inch Dia., SS, 2 Wall, Shower Use; G

Shelf, Mop and Broom Holder (MHS), SS, Surf MntdG

Robe Hook (RH), Security; G

Shower Curtain Rod (SCR), 1 inch Diameter, W/Curtain & Hooks; G

Toilet Tissue Dispenser (TTD), SS, 2-Roll, Surface Mntd; G

Mirror (WM); G

Foam Soap Dispenser (SD); G

Towel Bar (TB), 1 inch Diameter, SS, Surface Mounted; G

Semi Recessed Waste Receptacle and Paper Towel Dispenser (ITDW); G

Shower Seat (FSS); G

Electric Hand Dryer (HD); G

Submit Data Package 1 for each toilet accessory item , and Data Package 2 for each electrical toilet accessory item, in accordance with Section 01 78 23 OPERATIONS AND MAINTENANCE DATA.

1.3 DELIVERY, STORAGE, AND HANDLING

Wrap toilet accessories for shipment and storage, then deliver to the jobsite in manufacturer's original packaging, and store in a clean, dry area protected from construction damage and vandalism.

1.4 WARRANTY

Provide manufacturer's warranty to repair or replace defective materials and workmanship for a period of one year from date of final acceptance of the work..

PART 2 PRODUCTS

2.1 ACCESSORY ITEMS

Provide toilet accessories where indicated in accordance with Contractor-provided product schedule. Conform to the requirements for accessory items specified herein which are based on MIL-STD-1691 Joint Schedule Numbers (JSN). Provide each accessory item complete with the necessary mounting plates of sturdy construction with corrosion resistant surface.

Provide stainless steel products listed herein manufactured from materials containing a minimum of 50 percent recycled content. Provide data identifying percentage of recycled content for stainless steel toilet accessories.

2.1.1 Anchors and Fasteners

Provide corrosion-resistant anchors and fasteners capable of developing a restraining force commensurate with the strength of the accessory to be mounted and suited for use with the supporting construction. Provide oval heads exposed fasteners with finish to match the accessory. Provide fasteners proposed for use for each type of wall construction and mounting.

2.1.2 Finishes

Except where noted otherwise, provide the following finishes on metal:

Metal	Finish
Stainless steel	No. 4 satin finish
Carbon steel, copper alloy, and brass	Chromium plated, bright

2.1.3 Sanitary Napkin Disposal (SND) , SS, Surface Mounted

Surface mounted sanitary napkin receptacle. Unit made of stainless steel with satin finish and all welded construction. Unit has piano hinge attached at the top and an integral finger depression for opening. For use with disposable paper liners, available separately. Unit may be attached to wall or toilet partition.

Approximate size: 7 inches wide by 4 inches deep by 10 inches high.

2.1.4 Grab Bar(GB36) (GB42) Grab Bar, 1-1/4 Inch Diameter, SS, 2 Wall, W/C Accessible

Grab bar of 1-1/4 inch diameter satin finish stainless steel with peened gripping surface for use in toilet stall/room. Snap-on flange covers for concealed mounting are stainless steel and equipped with two screw holes for attachment to wall. Grab bars designed to meet and exceed ADA

requirements for structural strength. Grab bars designed to withstand loads of 900 pounds when properly installed. Clearance from wall to grab bar is 1-1/2 inches to meet ADA and ANSI codes.

2.1.5 Grab Bar: L-Shaped (GBL), 1-1/4 Inch Diameter, SS, 2 Wall, Shower Use

Grab bar of 1-1/4 inch diameter satin finish stainless steel with peened gripping surface. Snap-on flange covers for concealed mounting stainless steel. Bent ends of tubing pass through the flanges and are Heliarc welded for maximum strength. Grab bars designed to meet and exceed ADA requirements for structural strength. Grab bars designed to withstand loads of 900 pounds when properly installed. Clearance from wall to grab bar is 1-1/2 inches to meet ADA and ANSI codes.

2.1.6 Shelf, Mop and Broom Holder (MHS), SS, Surf Mounted

Surface mounted mop/broom holder with shelf made of 18 gauge stainless steel with all exposed surfaces in satin finish. Unit has shelf 8 inches deep with shelf support brackets of satin finish stainless steel welded to mounting base, and a minimum of 3 hooks/3 holders. Mop holders have spring-loaded rubber cams and hold mop or broom handle with a diameter between 5/8 inch and 1 inch.

Approximate size: 36 inches wide by 8 inches deep.

2.1.7 Robe Hook (RH), Security

Surface mounted safety hook made of stainless steel and secured to wall with tamper resistant mounting screws, exposed mounting. Mounting hardware to be included. Hook designed to snap down when it exceeds load limit. Robe Hook (RHA) is similar, but mounted at an accessible height.

2.1.8 Shower Curtain Rod (SCR), 1 Inch Diameter, W/Curtain & Hooks

Shower Curtain Rod with concealed mounting. Shower curtain rod made of satin finish stainless steel, 1 inch diameter, with flanges included, and have white vinyl shower curtain, 72 inches high, and stainless steel curtain hooks. Shower curtain has corrosion resistant grommets, reinforced heading, and treated with antibacterial and flame retardant agents. Shower hooks are stainless steel. Length as indicated on drawings.

2.1.9 Toilet Tissue Dispenser (TTD), SS, 2-Roll, Surface Mounted

Concealed surface mounted double roll toilet tissue dispenser of satin finish stainless steel. Spindle to be free-spinning for non-controlled delivery, chrome-plated high impact resistant plastic and equipped with heavy-duty internal spring. Unit accommodates standard core toilet paper rolls up to 5-1/2 inches diameter. Mounting hardware included.

Approximate size: 13.5 inches wide, 2 inches high and the spindle brackets project 3.825 inches.

2.1.10 Mirror (WM)

Mirror frames are 0.050 inch, 18 gauge Type 304 stainless steel angles fabricated into 0.75 inch by 0.625 inch channels with mitered, heilarc welded corners that are ground and polished smooth. Concealed members are corrosion protected steel. Fabricate mirror backs with 0.036 inch, 20

gauge back panels incorporating 0.050 inch, 18 gauge mounting brackets interlocked with frame tops and bottoms. Place filler material at mirror edges, and between mirrors and back panels. Mirrors are first quality, electrolytic copper backing on 0.25 inch plate or float glass, complying with ASTM C 1036 and ASTM C 1503.

Approximate size: 1 foot, 6 inches wide by 3 feet, 0 inches high.

2.1.11 Foam Soap Dispenser (SD) Surface Mounted

Foam soap dispensers have chrome plated, ABS plastic valves incorporated into 0.038 inch, 20 gauge Type 304 stainless steel bodies and backs. Wall plates are stainless steel. Units have 40 fluid ounces of capacity, and are top filled through locked openings. Surface mount with a vertical orientation. Valves actuate with no more than 5 pounds of pressure. Furnish tamper resistant sight level indicators. Provide two keys per unit.

Approximate size: 4.8125 inches wide by 8.25 inches high by 2.825 inches deep and valves project 1.6875 inches.

2.1.12 Towel Bar (TB), 25 mm (1 inch) Diameter, SS, Surface Mounted

Surface mounted satin finish stainless steel towel bar of 1 inch diameter. Support posts fabricated of heavy solid cast brass with satin finish. Stainless steel set screw keeps bar from rotating in posts. Clearance between towel bar and wall is 1-1/2 inches.

2.1.13 Semi Recessed Waste Receptacle and Paper Towel Dispenser (ITDW)

Semi recessed waste receptacle and paper towel dispenser units hold 800 multi-fold or 600 C-fold paper towels. Waste receptacles accommodate 12 gallon liners. Unit doors, frames, waste containers and cabinets are 18-8 alloy, Type 304 stainless steel. Unit doors and backs are 0.050 inch, 18 guage, and other fabrications are 0.031 inch, 22 gauge. Exposed surfaces are protected by PVC film. Doors are fabricated of double pan construction with fiberboard filler, have full length, 0.1875 inch diameter multi staked, stainless steel piano hinges and are fit with tumbler locks. Provide two keys per unit. Towel dispensing slots have hemmed edges for user safety. Waste containers have hemmed edges and are secured with tumbler locks. Face trims are 1 inch in width and formed from a single piece free of miters, welds and open seams with a 0.25 inch square return to walls. Structural components are of welded construction. Cabinet fasteners and spot welds are concealed. Labeling provides operating instructions.

Outside flange dimensions are 1 foot, 5.25 inches wide, 4 feet, 8 inches high and recessed 1.25 inches into wall substrates. Units project 2.75 inches from wall faces.

2.1.14 Shower Seat (FSS)

Shower seats are ell shaped. Seat frame and support legs are 1 inch diameter and 1.25 inch square 0.050 inch, 18 gauge, Type 304 stainless steel with welded construction. Edges and corners are radiused and smooth. Mounting flanges are 0.188 inch, 7 gauge and guide brackets and arm supports are 0.063 inches, 16 gauge. Seat planks are 0.5 inch solid phenolic. Support arms fold upward into a vertical, retracted position without need for latches or fittings to retain the position. Guide

brackets control seat raising and lowering with a stainless steel spring mechanism. Dimensions are 2 feet, 9 inches wide and projecting 1 foot, 10.825 inches.

2.1.15 Electric Hand Dryer (HD)

Surface mounted automatic sensing electric hand dryers have a one piece, heavy duty die cast zinc alloy cover with rib reinforcement that is light weight, unbreakable, rustproof and fastened to a wall plate with two chrome plated, tamper proof bolts. Cover finish is epoxy enamel, stainless steel or chrome plated. Internal parts are coated in accordance with UL requirements, and the entire mechanism is internally grounded. Units are 11.4375 inches wide by 1 foot, 0.3125 inches tall by 6.6875 inches in depth. Motors are thermally protected, series commutated with through flow discharge vacuum motor and blower. Heating elements are constructed of nichrome and wire mounted inside the blower housing for vandal proofing. Thermostats automatically reset, opening whenever air flow is cut off and closing when air flow is resumed. A heating element warms outlet air to expedite drying. Control assemblies are activated by an infrared optical sensor located next to the air outlet. Dryers operate as long as hands are under the outlet. Assemblies include adjustable speed and sound control mechanisms, heat control settings and filter sensors that alert to clogged filters. There is a 35 second lockout feature if the hands are not removed. Sensors are equipped with red LED indicators that flash error codes to assist in troubleshooting. Recess mounted automatic sensing electric hand dryer is similar, and equipped with a 0.031 inch, 22 gauge wall box with flange and 0.063 inch, 16 gauge dryer mounting plate made from 0.050 inch, 18 gauge Type 304 stainless steel. Joints are welded and ground smooth. Inside box dimensions are 1 foot, 2.375 inches wide by 2 feet, 0.125 inches high and recessed 3.375 inches.

Electric Hand Dryer	Performance
Motor rating	0.625 HP and 24,000 RPM
Air velocity 4 inches below the outlet	20,000 linear FPM, maximum
Heating element, 4 inches below the outlet ambient room temperature, maximum	970 watts, 146 F at 72 F
Adjustable sound level	66 to 75 dB
Adjustable velocity	13,000 to 20,000 linear FPM
Adjustable heat	72 to 135 F
Flow rate	42 to 63 CFM

PART 3 EXECUTION

3.1 INSTALLATION

Do not install items that show visual evidence of biological growth. Provide the same finish for the surfaces of fastening devices exposed after installation as the attached accessory. Provide oval exposed screw heads. Install accessories at the location and height indicated. Protect exposed surfaces of accessories with strippable plastic or by other means until the installation is accepted. After acceptance of accessories, remove and dispose of strippable plastic protection. Coordinate accessory manufacturer's mounting details with other trades as their work progresses. Use sealants for brackets, plates, anchoring devices and similar items in showers (a silicone sealant specified in Section 07 92 00 JOINT SEALANTS) as they are set to provide a watertight installation. After installation, thoroughly clean exposed surfaces and restore damaged

work to its original condition or replace with new work.

3.1.1 Surface Mounted Accessories

Mount on concealed backplates, unless specified otherwise. Conceal fasteners on accessories without backplates. Install accessories with corrosion-resistant fasteners as required by the construction. Install backplates in the same manner, or provide with lugs or anchors set in mortar, as required by the construction. Fasten accessories mounted on gypsum board and plaster walls without solid backing into the metal or wood studs, or to backplates secured to metal studs.

3.2 CLEANING

Clean material in accordance with manufacturer's recommendations. Do not use alkaline or abrasive agents. Take precautions to avoid scratching or marring exposed surfaces.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 10 44 16

FIRE EXTINGUISHERS
11/19

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Cabinets; G

Wall Brackets; G

SD-03 Product Data

Cabinets; G

Wall Brackets; G

Replacement Parts List; G

SD-04 Samples

Equipment Samples; G

1.2 DELIVERY, STORAGE, AND HANDLING

Protect materials from weather, soil, and damage during delivery, storage, and construction.

Deliver materials in their original packages, containers, or bundles bearing the brand name and the name and type of the material.

1.2.1 Samples

Provide the following equipment samples: One full-sized sample of each type of cabinet being installed; three samples of wall brackets and accessories of each type being used.

Use approved samples for installation, with proper identification and storage.

1.3 PROJECT SCHEDULE

Coordinate final fire protection cabinet schedule with fire extinguishers to ensure proper fit and function. Use same designations indicated on Drawings.

PART 2 PRODUCTS

Submit fabrication drawings consisting of fabrication and assembly details

performed in the factory and product data for the following items: Fire Extinguishers; Accessories, cabinets, Wall Brackets.

2.1 EQUIPMENT

2.1.1 Cabinets

2.1.1.1 Material

Provide enameled steel cabinets.

2.1.1.2 Type

Provide semi-recessed cabinet for a 6 inch wall.

2.1.1.3 Size

Dimension cabinets to accommodate the specified fire extinguishers.

2.1.2 Wall Brackets

Provide running-board fire extinguisher wall brackets.

Provide wall bracket and accessories as approved.

2.1.2.1 Identification

Provide lettering complying with authorities having jurisdiction for letter style, size, spacing, and location. Locate as indicated by the drawings.

Identify bracket-mounted fire extinguishers with the words "FIRE EXTINGUISHER" in red letter decals applied to mounting surface.

Orientation: Vertical.

PART 3 EXECUTION

3.1 INSTALLATION

Install Fire Extinguishers where indicated on the drawings. Verify exact locations prior to installation.

Provide extinguishers which are fully charged and ready for operation upon installation. Provide extinguishers complete with Manufacturer's Warranty with Inspection Tag attached.

Install fire extinguishers in locations indicated and in compliance with requirements of authorities having jurisdiction.

Comply with the manufacturer's recommendations for all installations.

3.2 PROTECTION

3.2.1 Repairing

Remove and replace damaged and unacceptable portions of completed work with new work at no additional cost to the Government.

Submit replacement parts list indicating specified items replacement part, replacement cost, and name, address and contact for replacement parts distributor.

3.2.2 Cleaning

Clean all surfaces of the work, and adjacent surfaces which are soiled as a result of the work. Remove from the site all construction equipment, tools, surplus materials and rubbish resulting from the work.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 10 50 00

MISCELLANEOUS SPECIALTIES
02/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this section to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 611	(2014) Voluntary Specification for Anodized Architectural Aluminum

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability Notebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Cell phone locker; G

Emergency Key Boxes; G

SD-03 Product Data

Cell phone locker; G

Emergency Key Boxes; G

1.3 SCOPE

Provide labor, material, equipment and services necessary for, and reasonably incidental to, furnishing and installing miscellaneous specialty work indicated within the Instruments of Service. Incorporate related accessories and specialties to accomplish a complete and proper installation. Coordinate and schedule this work with the work of other trades to ultimately provide superior workmanship in the finished product

PART 2 PRODUCTS

2.1 CELL PHONE LOCKER

Surface mounted cell phone lockers are premanufactured assemblies with smooth outside surfaces, flanged doors with welded corners, continuous concealed hinges and lock cams with pry protection bars. Doors and frames are 0.051 inch, 16 gauge aluminum, and shelves and frames are 0.040 inches, 18 gauge aluminum. Aluminum receives a powder coat or anodized

finish. Preassembled units have continuously hinged front panels secured with a master keyed panel lock enabling easy access to individual locker contents. Unit master keys are keyed alike. Individual locker doors are standard A size, 6.5 inches wide by 5.25 inches height with resettable combination locks. A master control key overrides the combination and opens an individual locker. Compartments are 5 inches deep. Custom engrave individual locker doors with sequential, black infilled numerals for the entirety of the installation. Aluminum enclosures and pedestals are colored to match. Furnish an installation with 35 cell phone lockers.

2.2 EMERGENCY KEY BOXES

Recessed high security industrial and government emergency key boxes hold up to ten keys or one access card. Provide recess mounting kits. Housings are 0.25 inch, 100% welded steel. Doors are a 0.5 inch thick with interior gasket seals and stainless steel hinges. Locks have 0.125 inch thick stainless steel dust covers with tamper switch mounting capability. Housings are 4 inches high by 5 inches wide by 3.25 inches deep. Flanges are 7 inches wide by 7 inches high. Boxes and locks are UL listed. Locks are double action, rotating tumblers with hardened steel pins accessed by biased key cuts. Provide Camp Lejeune Fire Department keying.

PART 3 EXECUTION

3.1 PREPARATION

Prepare rough openings to accommodate premanufactured assemblies and the recommended means of attachment.

3.2 INSTALLATION

Give aluminum extrusions for commercial applications a pretreatment to enhance adhesion followed by a caustic etch or alkaline wash for cleaning and degreasing. Apply a phosphate spray or chromate conversion treatment to protect against humidity and corrosive chemicals. Furnish an anodized treatment conforming to AAMA 611 to obtain an architectural Class I coating. Provide a two coat application that achieves a 0.7 mil thickness.

Furnish fasteners, accessories and options as recommended by the manufacturer for the specific applications and substrates encountered within the work.

Install miscellaneous specialties plumb, level and within plane of receiving substrates. Adjust movable parts for smooth operation.

3.2.1 Emergency Key Box Installation

Typical exterior key box wall mounting is adjacent to the main entry providing access to the fire alarm annunciator.

Recess mount key boxes at a height of 4 feet, 8 inches above the finished floor as measured to the top of the box.

The General Contractor coordinates with the AHJ to procure key boxes. Confirm AHJ preferences for mounting locations and heights prior to installation.

3.2.2 Cell Phone Locker Installation

Mount cell phone lockers at a height of 5 feet, 0 inches above the finished floor as measured to the top of the unit.

3.3 Maintenance

Submit the recommended maintenance practices for each type of installation to be provided.

Clean cell phone locker aluminum surfaces with mild dish detergent. Do not use harsh abrasives. Lubricate locks with graphite lubricants.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 10 56 00

PALLET STORAGE RACKS
10/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 2603	(2002) Voluntary Specification, Performance Requirements and Test Procedures for Pigmented Organic Coatings on Aluminum Extrusions and Panels

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for ontractor Quality Control approval. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Pallet Storage Racks; G

PART 2 PRODUCTS

2.1 PALLET STORAGE RACKS

Pallet storage rack color is to be Grey.

2.1.1 Design Requirements

Rack storage systems shall accommodate pallets that are 3 feet, 4 inches in width by 4 feet, 0 inches in depth by 4 feet, 0 inches in height including the height of the pallet. Each pallet shall have a maximum weight of 2,500 pounds.

Design foot plate connections to resist lateral loading and overturning.

2.2 MATERIALS

Pallet rack systems are to be of a selective storage type allowing direct and individual access to each pallet. Structural assemblies consist of 0.375 inch foot plates and uprights with diagonal bracing that support two beams per storage tier above the finish floor. Storage at the lowest tier is on the floor. Beams shall accommodate two pallets. Connectors rigidly secure beam ends to uprights. Rack systems are fabricated from steel and utilize a combination of bolted, welded and lock key connections to support the loading encountered.

Tiers	Nominal Beam Width	Nominal Upright Height	Nominal Upright Depth
Two Tier	8 feet	10 feet	4 feet

Give steel profiles for interior applications a caustic etch and acrylic or polyester baked enamel or powder coating treatment conforming AAMA 2603. Provide an application that achieves a 0.2 mil thickness.

Furnish fasteners, accessories and options as recommended by the manufacturer for the specific applications and substrates encountered within the work.

PART 3 EXECUTION

3.1 INSTALLATION

Install pallet rack systems level and plumb.

-- End of Section --

SECTION 12 00 01.00 20

FURNITURE, FIXTURES AND EQUIPMENT (FF&E) PACKAGE
02/23

PART 1 GENERAL

1.1 CONTRACTOR'S FURNITURE, FIXTURES AND EQUIPMENT (FF&E) HANDLING AND ADMINISTRATION RATE (HAR)

The HAR accounts for all administrative costs, overhead, FF&E subcontractor bonding fees deemed necessary by the Contractor, administration of subcontracts, profit, and any other costs associated with, and related to, the coordination and processing of the procurement and installation of FF&E. Offerors must propose a HAR for the FF&E not to exceed 5 percent. Do not include costs associated with INTERIOR DESIGN SERVICES in the HAR. The proposed HAR percentage is a fixed rate and will be incorporated into the contract award. The HAR will not be adjusted regardless of fluctuations from the estimate amount for the FF&E.

The Government will indicate the FF&E estimate in the FF&E Option Item in the Price Schedule based on the Concept FF&E Design. The Government estimated price is to provide Offerors with the projected magnitude of effort and includes the actual estimated cost of the FF&E including freight, installation, and other applicable vendor charges. The Government estimated price is only an estimated amount and must not be altered by the Contractor during the solicitation process.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

FC 1-300-09N	(2024) Navy and Marine Corps Design
UFC 3-120-10	(2018; with Change 2, 2021) Interior Design

1.3 DEFINITIONS - FF&E TURNKEY EFFORT

The Furnishings, Fixtures, and Equipment Package may include, but is not limited to; systems and modular furniture, workstations, desks, seating, storage, filing, visual display items, accessories, artwork, command graphics, training and conference furniture, soft window treatments (draperies, valances, and cornices), shop equipment, fitness equipment, Child Development Center furniture, appliances, portable weapons cabinets, dorm and quarters furnishings and other miscellaneous items to support facility functions. For NAVFAC PACIFIC projects, the term Collateral Equipment (CEQ) Package may be used interchangeably with the term FF&E Package.

The project may also include Specialty CEQ Package for which the Activity may assist in specifying items, which may include, but not limited to: Audio Visual (AV) equipment, commercial kitchen equipment, medical equipment and wharf equipment. For the purposes of this specification, if a Specialty CEQ Package is required, the same requirements identified for

the FF&E Package apply to the Specialty CEQ Package or as outlined by project-specific UFC or requiring Agency.

1.3.1 FF&E Option Item

As an option, provide procurement and installation coordination of the approved complete and usable Final FF&E Package.

a. The Specialty CEQ Package will be identified as a separate Option Item, priced separately from the FF&E and funded as a separate Option.

b. The Government is not obligated to award the FF&E Option Item. Should the Government choose to award the FF&E Option, the Item(s) will be awarded as a negotiated option to the contract or task order. The Contractor's proposed HAR will be applied to all vendor and supplier costs for the FF&E.

c. The Government will provide separate funding for procurement and installation coordination of the FF&E Package. Construction funds will not be used. Upon receipt of required funding, the Contracting Officer will authorize the Contractor, as an option to the construction contract, to provide the Government-approved Final FF&E Package exactly as specified and complying with priorities found in the Federal Acquisition Regulation (FAR) 8.404 Use of Federal Supply Schedules. The amount of the option will be the actual cost of these items from the Federal Government price schedules and, when necessary, Open Market sources. The option amount will also include shipping, freight, handling, installation, vendor design fees, project management fees, applicable sales tax, Contractor's FF&E Handling and Administration Rate percentage as applied to the Final FF&E or Specialty CEQ total cost(s) and the NAVFAC required bond fee.

d. If awarded, the FF&E Option Item will be awarded at least six months prior to the contract completion date. A minimum of six months is required for the Contractor to purchase, deliver and install the product without impacting the overall completion date of the project. The Contractor's schedule must assume the award of the FF&E as an option. Government Fiscal Year funding availability must be considered and incorporated into the FF&E Schedule. No schedule extensions will be granted if the option item is awarded at least six months prior to the contract completion date. If the Government decides to negotiate and award the option item with less than six months prior to the contract completion date, the Contractor may be entitled to a contract extension and extended field overhead. A contract extension and extended field overhead will only be granted in those cases where the Contractor demonstrates that the accepted Final FF&E Package was submitted within the approved schedule deadlines, sufficient lead time is not available, and the Government's award of the FF&E Option Item is within the last six months of the contract.

e. The FF&E Option Item (and any Specialty Equipment and Audio Visual (A/V) Option Item(s)) are exempt from NAVFAC Procedures, Guidance and Instruction (NPGI) 17.202(a)(ii) option restriction to award within 365 days of contract award. Per NPGI 17.202(a)(ii), Note 2, "Options for Collateral Equipment (CEQ) to include Furniture, Fixtures and Equipment (FF&E) and Audio-Visual (A/V) are not limited to the 365 day time period from date of award. Written approval for a longer period to exercise options for FF&E and A/V is not required."

1.3.2 Authorization for Use of Government Supply Sources

The Contracting Officer will authorize the Contractor to purchase the required products through the specified sources and will provide a letter of authorization to the Contractor in accordance with FAR 51.102 Authorization to use Government supply sources (e)(1) through (5) citing the name of the furniture dealer(s) and other information to use when accessing the Federal Government supply sources. The Contractor must procure and coordinate the installation of the approved Final FF&E Package exactly as specified.

1.3.3 Buy American Act (BAA) and Trade Agreement Act (TAA)

All products under the FF&E Option Item are subject to the rules and regulations governing the acquisition of foreign supplies, e.g., Buy American Act (BAA) (FAR 25.1 Buy American-Supplies). This also includes all supplies procured through Government Supply Sources. Solicitations are required to meet the Trade Agreement Act (TAA) Designated Countries (FAR 25.4 Trade Agreements), as part of the BAA. In addition to the applicable BAA clauses and provisions for construction materials, the Contracting Officer must also insert the appropriate BAA or TAA clauses and provisions for supplies. The Contractor is responsible for ensuring the FF&E is compliant with the BAA or TAA.

1.3.4 Prohibition on Procurement of Certain Items Containing Perfluorooctane Sulfonate (PFOS) or Perfluorooctanoic Acid (PFOA)

Effective April 1, 2023, in accordance with section 333 of the William M. (Mac) Thornberry National Defense Authorization Act for Fiscal Year 2021, the Department of Defense must not procure any covered items that contain PFOS or PFOA. The Contractor must not provide any covered items containing PFOS or PFOA in performance of this contract, task order, delivery order, or blanket purchase agreement order. A covered item means the following:

a. Nonstick cookware or cooking utensils for use in galleys or dining facilities.

b. Upholstered furniture, carpets, and rugs that have been treated with stain-resistant coatings.

1.3.5 Procurement and Installation

The Contractor must coordinate the building completion date with the installation dealer(s) specified in the FF&E Package. It is recommended that the Contractor order the products once the option is awarded to avoid incurring additional costs. Production and delivery dates should be requested of manufacturers or dealers at the time of order placement to coincide with the Beneficial Occupancy Date (BOD). The Contractor must anticipate possible manufacturer price increases if order placement is delayed. Any costs incurred due to manufacturer price increases as a result of order placement delays will be the burden of the Contractor.

1.3.6 Deposits

The Contractor must anticipate providing a deposit of between 30 percent and 50 percent of the product costs when placing the orders with the manufacturer's dealerships. The Government will not fund deposits.

1.3.7 Construction Wage Rate Requirements Statute

Prior to the Interior Designer sending out the Best Value Determination (BVD) Request for Quote (RFQ) Packages to vendors, the NAVFAC Contracting Officer, Contract Specialist, Project Manager, Design Manager, NAVFAC Interior Designer and Collateral Equipment Manager must identify a determination as to whether the FF&E and Specialty CEQ installation is covered by the Construction Wage Rate Requirements statute. The BVD RFQ Packages must identify any items with installation that is subject to the Construction Wage Rate Requirements statute.

1.3.7.1 Construction Wage Rate Requirements Statute is Not Applicable

The Construction Wage Rate Requirements Statute is Not Applicable if the FF&E assembly and installation work is:

a. Segregable from the construction of the facility (i.e., procured in a separate FF&E Option (Item)); and

b. The assembly and installation work is performed by the FF&E vendor or dealer or subcontractor(s); and

c. The onsite FF&E work does not include a substantial amount of construction work; and

d. The workforce for the FF&E installation and delivery is separate and distinct from the labor workforce performing the construction effort by the Contractor.

If the above a. through d. are true, the Construction Wage Rate Requirements Statute is not applicable to FF&E installed by General Services Administration (GSA), other Government Supply Sources or Open Market.

1.3.7.2 Construction Wage Rate Requirements Statute is Applicable

The Construction Wage Rate Requirements Statute is Applicable if the FF&E assembly and installation work is:

a. Performed by the Contractor; and

b. Is not physically or functionally separate from the other construction work required by the contract; and

c. Is not capable of being performed on a segregated basis from the other construction work required by the contract.

-OR-

d. The assembly and installation work is performed by the FF&E vendor or dealer or subcontractor(s); and

e. The onsite FF&E work does include a substantial amount of construction work.

If the above a. through c. are true or d. through e. are true, the Construction Wage Rate Requirements statute would be applicable to the installation of all FF&E that is installed and attached to the facility.

1.3.8 Taxes

1.3.8.1 Exemptions

Exemptions for certain state or local taxes may be available to the Contractor and its subcontractors. The Contractor must take maximum advantage of all exemptions, including obtaining a resale permit from state and local taxation authorities whether available directly to the Contractor or based on an exemption afforded the Government. The responsibility for paying applicable taxes rests with the Contractor. Applicable state and local taxes to the FF&E Package must be included with the subcontractor's quote, if required by the state or locality.

1.3.8.2 Construction Contract Requirements

As prescribed in FAR 29.401-3 Federal, State, and local taxes, the Contracting Officer must insert FAR clause 52.229-3, Federal, State and Local Taxes, in the construction contract. In accordance with this clause:

a. The contract price includes all applicable Federal, State, and local taxes and duties; and

b. The Government must, without liability, furnish evidence appropriate to establish exemption from any Federal, State, or local tax when the Contractor requests such evidence and a reasonable basis exists to sustain the exemption.

1.3.9 Performance and Payment Bonds

1.3.9.1 No Bond Requirement for FF&E at Time of Construction Contract Award

FAR 28.102-1(a) requires that performance and payment bonds be included in all construction contracts exceeding the Simplified Acquisition Threshold (SAT), except under the conditions listed. Since the FF&E Option Item is not part of the original contract award, the Contractor is not required to secure bond for the FF&E at the time the basic construction contract is awarded.

1.3.9.2 Additional Bond at FF&E Option Item Award

FAR 28.102-2(d) requires the Government to secure additional bond from the Contractor for any contract price increases. An increase to the original contract bond is required at the time of the FF&E Option Item award to protect the Government against the Contractor not providing FF&E ordered and to ensure that the FF&E vendor(s) receive payment if the Contractor goes out of business. The increased cost of the Government required bond must come from the FF&E funding source and is not a part of the Contractor's HAR.

1.3.9.3 Bonds Required by the Contractor

If the Contractor requires bonding from the FF&E subcontractor(s), the cost must be covered in the Contractor's HAR.

1.3.10 Item Unique Identification (IUID) and Valuation

Item Unique Identification (IUID) and valuation is a system of marking and valuing items delivered to Department of Defense (DoD) that enhances logistics, contracting, and financial business transactions. Utilize the

IUID policy for all DoD contracts that require the delivery of items. An item is a single article or a single unit formed by a grouping of subassemblies, components or constituent parts. In accordance with DFARS 211.274-2 Policy for item unique identification, IUID is required for all delivered items for which the Government's unit acquisition cost is $5,000 or more. Items identified by the requiring activity to be serially managed, mission essential, controlled inventory or for other reasons requiring permanent identification, must be marked with a unique item identifier.

1.3.10.1 IUID

The two main steps involved in IUID requirements are:

a. Item marking, and

b. Delivery of data about items as a part of the acceptance and delivery process.

1.3.10.2 Data Matrix Requirements

Item marking requires that qualifying items contain a data matrix either directly inscribed on the individual item or on a permanent label or data plate attached to the item. Delivery of data is executed by submitting to the IUID Registry information such as: description of the item, its value, and the date of acceptance by the government. The IUID Registry is the repository established to capture and store all IUID data.

1.3.10.3 Government's Unit Acquisition Cost

In accordance with DFARS 211.274-3 Policy for valuation, Contractors must be required to identify the Government's unit acquisition cost for all items delivered even if none of the criteria for placing a unique item identification mark applies.

1.4 ADMINISTRATIVE REQUIREMENTS

1.4.1 FF&E Pre-Installation Walk-Through

The Contractor must coordinate and participate in a walk-through to ensure that the building interior is substantially complete in all areas scheduled to receive FF&E to include floor, wall and ceiling finishes and building systems located on or in the ceilings. Attendees must include the FF&E vendor(s) in-person (if geographically feasible) or virtually and the NAVFAC Construction Manager. Approval by the NAVFAC Construction Manager to proceed with the FF&E installation is required. The walk-through date must occur prior to the commencement of the FF&E installation and accommodate sufficient time in the construction schedule for transportation of FF&E to the job site upon approval by the NAVFAC Construction Manager.

1.4.2 Sequencing

The Contractor must coordinate the building completion, occupancy, and furniture installation dates with the installation dealer(s) specified in the FF&E Package. Any costs associated with or delaying furniture shipments to accommodate the construction schedule is the responsibility of the Contractor.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

The NAVFAC Interior Designer is required to receive a copy of all submittals with a "G" Classification.

SD-01 Preconstruction Submittals

FF&E and CEQ Schedule and Schedule Updates; G

Contractor's Interior Designer's Qualifications; G

SD-04 Samples

Interior Finish Construction Submittals; G

Post Option Award FF&E and CEQ Finish Submittals; G

Post Option Award FF&E And CEQ Finish Submittals

SD-05 Design Data

FF&E and CEQ Basis of Design Packages; G

FF&E and CEQ BVD Request for Quotation (RFQ) Packages; G

BVD Bid Packages Results; G

Pre-Final FF&E and CEQ Packages "Over the Shoulder"; G

Pre-Final FF&E and CEQ Packages; G

Final FF&E and CEQ Packages; G

SD-10 Operation and Maintenance Data

Warranty and Maintenance Information; G

SD-11 Closeout Submittals

Punch List(s) Submittal; G

1.6 QUALITY CONTROL

1.6.1 Installation Qualifications

All FF&E must be installed by the manufacturer's dealer of record and not by the Contractor. In addition, installation dealer(s) must be located within a 250 mile radius of the project site unless approved by the NAVFAC Interior Designer.

1.7 DELIVERY, STORAGE, AND HANDLING

FF&E must be shipped to and stored at the vendor or dealer's conditioned

warehouse, until all items are received unless dealer has coordinated just-in-time delivery with the Contractor. Vendor or dealer is responsible for any orders arriving before or after the agreed upon delivery and installation date with the Contractor, including storage of items.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 INTERIOR DESIGN SERVICES

Provide Interior Design FF&E services and deliverables in accordance with FC 1-300-09N, UFC 3-120-10, Interior Design Procedures: Furniture Fixtures and Equipment (FF&E) located at https://www.wbdg.org/navy/ffe-criteria-templates/navfac-id-procedures-ffe and as further defined in the paragraphs below. Utilize NAVFAC templates, criteria and procedures documents located at https://www.wbdg.org/navy/ffe-criteria-templates.

3.1.1 SYSTEM DESCRIPTION: CONTRACTOR'S INTERIOR DESIGN SERVICES

The FF&E and CEQ Concept Design Packages submittal (approximately 35 percent), as prepared by the A/E's Interior Designer, was sufficiently developed to fully integrate with the building systems (e.g., electrical, mechanical) to include product sizes and communications, data, and electrical requirements. The Contractor must hire a different Interior Designer to validate the FF&E and CEQ Concept Design Packages requirements with the Activity or End User and NAVFAC Interior Designer and make any necessary revisions.

Provide and comply with Interior Design Procedures: Furniture Fixtures and Equipment (FF&E) CHAPTER(s) 1 through 4 and specific Design, Meeting and Submittal deliverables identified below and as defined for the Contractor's Interior Designer in CHAPTER 5 ID SERVICES - DESIGN BID BUILD (DBB) - PROCESS 1. The Contractor may not hire the A/E's Interior Designer who prepared the Concept Design Package submittal. All required effort by the Contractor's Interior Designer described above must be included in the Construction Base Price and is separate and excluded from the FF&E Option Item.

3.1.1.1 Contractor's Interior Designer's Qualifications

Provide the services of an Interior Designer. Qualification of Interior Designer is based on education, experience and examination. The Contractor's Interior Designer must have completed a program accredited by the Council for Interior Design Accreditation (CIDA) or equal accreditation program of academic training in Interior Design. For all Interior Design Services, the Interior Designer must have attained National Council for Interior Design Qualification (NCIDQ) certification and state licensure, certification or registration. In addition, the Contractor's Interior Designer must have experience as the primary Interior Designer on projects, to include NAVFAC projects, of similar type, size, scope and complexity to this contract project. Experience using GSA contracts is required. Writing non-proprietary, technical performance criteria and the evaluation of vendor proposals for competitive furniture and specialty equipment Best Value Determinations

(BVDs) is required and must be clearly indicated in the resume. The Contractor must obtain the services of equipment specialists to provide design services and assist the Interior Designer with the development of non-proprietary performance criteria for any specialty equipment. **The Contractor may not hire the A/E's Interior Designer or A/E's equipment specialist(s)**.

The Contractor, the Contractor's Interior Designer, Design Firm owners, and any Equipment Specialists must NOT have any affiliation or partnership with any furniture, fixture, and equipment products, manufacturers, furniture or equipment vendor or dealerships used on this project in order to avoid any organizational conflict of interest. For the Contractor's Interior Designer's Qualifications submittal, provide a detailed resume, client references and documentation of the Contractor's Interior Designer's qualifications and significant interior design experience to the NAVFAC Contracting Officer and Interior Designer for approval PRIOR to the Pre-Construction Conference (PRECON). The Government will approve or disapprove the Contractor's Interior Designer based on the provided documentation and past performance.

3.1.1.2 Concept FF&E and CEQ Packages

The FF&E and CEQ Concept Packages indicating the salient characteristics for all required FF&E items and Computer Aided Design and Drafting (CADD)/BIM drawings, will be provided by the NAVFAC Contracting Officer upon request. The Contractor must request to receive the package prior to the PRECON.

3.1.1.3 FF&E and CEQ Schedule and Schedule Updates Submittal

For all projects, including fast track projects and renovations, the Contractor is responsible for sufficiently scheduling all FF&E and CEQ meetings and deliverables early enough to:

a. Obtain the required government approvals,

b. Meet all FF&E and CEQ funding, award, ordering and installation lead times and deadlines, and

c. Complete the FF&E and CEQ installation by the Beneficial Occupancy Date (BOD).

All submittal due dates for the FF&E and Specialty CEQ must be noted in the FF&E Schedule and Schedule Updates Submittal and reflected in the Contractor's construction schedule. Provide a FF&E Schedule and Schedule Updates Submittal for all FF&E and Specialty CEQ services and deliverables to the NAVFAC Construction Manager, Interior Designer and Contracting Officer seven business days after the Interior Design Orientation Meeting. Submit FF&E Schedule and Schedule Updates Submittal to the NAVFAC Interior Designer within seven days of any construction schedule revisions.

All submittal due dates for the FF&E and specialty equipment must be reflected in the Contractor's construction schedule. Submit proposed changes to the NAVFAC Interior Designer for review. The Contracting Officer must approve all revisions or deviations.

3.1.1.4 Services

The Contractor's Interior Designer and any Equipment Specialists are

responsible for developing Final FF&E and Specialty CEQ Packages required in the project.

3.1.1.4.1 Validation of Requirements

The Contractor's Interior Designer and Equipment Specialist(s) must meet with the Activity at the PRECON to discuss the function of each area, validate all FF&E and CEQ requirements, make any necessary changes and additions to the Concept FF&E and CEQ Packages and recommend any adjustments or revisions to the interior building finishes and building infrastructure.

3.1.1.4.2 Building Infrastructure and Systems

The Contractor's Interior Designer is responsible for ordering samples of all interior building finishes required for coordination. The FF&E and CEQ Package(s) must be fully integrated with the design, construction, and schedule of all building finishes and all building infrastructure and systems (such as heating, ventilation and air conditioning (HVAC), plumbing, fire protection, communications, electrical, data, architecture). All electrical, data and communications outlets, switches, fire extinguishers, thermostats, sprinkler heads and Architectural Barriers Act (ABA) clearances must be accommodated for and be fully accessible once equipment is installed. The Contractor's Interior Designer and Equipment Specialist(s) must work with the Contractor and the electrical, telecommunication, and mechanical subcontractors to coordinate all infrastructure with the recommended vendors to include connection of power, data, communications, waterlines and gas lines, and calibration, testing and training prior to facility turnover and operation.

Provide coordination with the building infrastructure and provide revisions to the building infrastructure if required to support the FF&E Package and Specialty CEQ Package. Provide dimensioned locations on plans and elevations for multi-user telecommunications outlet assemblies (MUTOAs), junction boxes, wall outlets and floor boxes based on sizes, layouts and configurations of the equipment items in the FF&E Package and any Specialty CEQ Package.

3.1.1.4.3 Government-Furnished, Government Installed Equipment (GFGI) and Government-Furnished, Contractor-Installed Equipment (GFCI)

The FF&E and CEQ plans included in each submittal must take into consideration all FF&E or CEQ to include specialty CEQ, existing and future Government-Furnished, Government Installed (GFGI) Equipment and Government-Furnished, Contractor-Installed Equipment (GFCI). These items may include, but are not limited to, multi-function devices, printers, shredders, safes and vending machines.

3.1.1.4.4 Inventory of Existing FF&E or CEQ

The Activity will supply the Contractor's Interior Designer with a complete list of any existing FF&E or CEQ, to include e.g., sizes, utility requirements and weight, to be relocated or used in the new or renovated facility. The Contractor's Interior Designer is responsible for incorporating this equipment into the FF&E plan.

3.1.2 FF&E MEETINGS, PRESENTATIONS AND SUBMITTALS FOR THE INTERIOR DESIGN SERVICES

The Contractor's Interior Designer must attend all design meetings, site visits, walk-throughs, coordinate required mock-ups, obtain Activity and NAVFAC approvals and provide a complete and functional FF&E Package. All meetings must be coordinated with advance notice to the FF&E vendor(s), and NAVFAC Interior Designer, so that schedule and travel can be coordinated. Each submittal must demonstrate thorough interaction with the Activity's functional requirements and complete coordination with the facility design and the Structural Interior Design (SID).

These are minimum requirements and the Contractor must be prepared to provide all additional meetings and submittals that may be necessary to support the Interior Design effort and FF&E coordination. Submit any revisions or deviations caused by discontinued items or NAVFAC required changes to the NAVFAC Interior Designer for review. The Contracting Officer must approve all revisions and deviations.

3.1.2.1 Interior Design Orientation Meeting

The Interior Design Orientation Meeting must occur at the PRECON, or within seven days of the PRECON, at Camp Lejeune located in Jacksonville, NC. This meeting must occur within seven days of PRECON meeting. This meeting must include a validation of FF&E requirements with the Activity and a walk-through of the Activity's existing facility(s) or similar facility. Submit minutes of this meeting to the NAVFAC Interior Designer within seven business days of this meeting and include the preliminary schedule for the FF&E Meetings and Submittals.

3.1.2.2 "Over the Shoulder" Review Meeting of the FF&E Basis of Design Package Submittal

3.1.2.2.1 "Over the Shoulder" Basis of Design Review and Presentation Meeting

The "Over the Shoulder" Review of the Basis of Design Meeting will be held virtually. The presentation to be held at Camp Lejeune. If the meeting is held virtually, submit one hard copy and one digital copy of the presentation to the NAVFAC Interior Designer prior to the meeting.

The Contractor's Interior Designer must present the FF&E Basis of Design Package Submittal to the NAVFAC Interior Designer prior to presenting to the Activity. The submittal may be presented in a "loose" format or binder for NAVFAC approval prior to the Activity presentation. No presentation boards are required.

3.1.2.2.2 FF&E and CEQ Basis of Design Packages Submittal

Provide FF&E Basis of Design Package Submittal in accordance with Interior Design Procedures: Furniture, Fixtures and Equipment (FF&E).

3.1.2.3 FF&E Basis of Design Package Submittal Presentation to the Activity

This FF&E Basis of Design Presentation will be held at the Activity's location in Camp Lejeune, NC. After implementing all feedback from the NAVFAC Interior Designer, the Contractor's Interior Designer must present the FF&E Basis of Design Package Submittal to the Activity for feedback and approval. This meeting must include a walk-through of the Activity's

existing facility(s) or similar facility. Minutes of this meeting with photos of the approved FF&E product must be submitted to the NAVFAC Interior Designer within seven business days.

During this meeting, a detailed, functional review of the entire project must occur, with the FF&E presentation to follow, to ensure that all current FF&E requirements have been validated and captured. The submittal may be presented to the Activity in a "loose" format or binder. No presentation boards are required.

3.1.2.4 "Over the Shoulder" Review Meeting of the BVD Request for Quotation (RFQ) Package Prior to Bid.

Meet with the NAVFAC ID for an "over-the-shoulder" review of the BVD Request for Quotation Package meeting. Hold meeting virtually.

3.1.2.5 FF&E and CEQ BVD Request for Quotation (RFQ) Packages Submittal

Provide FF&E BVD Request for Quotation (RFQ) Package Submittal in accordance with Interior Design Procedures: Furniture, Fixtures and Equipment (FF&E).

3.1.2.6 BVD Bid Packages Results Submittal and "Over the Shoulder" Review Meeting

The Contractor's Interior Designer must schedule an "Over the Shoulder" virtual meeting to review the results of the responses to each BVD RFQ Package and discuss the best value vendor recommendation(s). If clarifications, updates or revisions are required, documentation must be revised and resubmitted. The Contractor's Interior Designer must submit one hard copy in a 3-ring binder and one book-marked PDF copy of this submittal to the NAVFAC Interior Designer. Book-marked PDF copies must also be sent to the NAVFAC Construction Manager, Asset Management Branch (AMD) or Supply Management Division (SMD) (USMC projects), and the NAVFAC Contracting Officer.

3.1.2.7 Pre-Final FF&E and CEQ Packages Submittal Review Meeting

The meeting is to occur at the Activity, located at Camp Lejeune, located in Jacksonville, NC. The Contractor's Interior Designer must present the Pre-Final FF&E and CEQ Packages "Over the Shoulder" Submittal for NAVFAC and Activity approval. The submittal may be presented in a "loose" format or binder. No presentation boards required.

3.1.2.8 Pre-Final FF&E and CEQ Packages Submittal

Provide the following number of Pre-Final FF&E Package Submittals; Three binder copies and five electronic copies total, as follows:

a. One binder copy and one electronic copy for the NAVFAC Interior Designer

b. One binder copy and one electronic copy for the Activity

c. One binder copy and one electronic copy for Asset Management Branch (AMD) or Supply Management Division (SMD) (USMC projects)

d. One electronic copy for the Facilities Engineering and Acquisition Division (FEAD) or Resident Officer in Charge of Construction (ROICC)

e. One electronic copy for the NAVFAC Project Manager

3.1.2.9 Final FF&E and CEQ Packages Submittal

Provide the Final FF&E Package Submittal 9 months prior to BOD, following the receipt of review comments on the Pre-Final FF&E Package Submittal and as determined by the approved FF&E schedule developed and incorporated into the Contractor's Schedule.

Submit the Final FF&E Submittal in a 3-ring binder for review and approval. Provide the following number of Final FF&E submittals; Four binder copies and five electronic copies total, as follows:

a. One binder copy and one electronic copy for the NAVFAC Interior Designer

b. One binder copy and one electronic copy for the Activity

c. One binder copy and one electronic copy for Asset Management Branch (AMD) or Supply Management Division (SMD) (USMC projects)

d. One binder copy and one electronic copy for the Facilities Engineering and Acquisition Division (FEAD) or Resident Officer in Charge of Construction (ROICC)

e. One electronic copy for the NAVFAC Project Manager

3.1.2.10 Interior Finish Construction Submittals

Some building interior finishes (Structural Interior Design) may need to be revised to coordinate with the Final FF&E Package. Submit any revisions or deviations to the building interior finishes to the NAVFAC Interior Designer for review. The Contracting Officer must approve any changes to the building interior finishes.

3.2 POST-AWARD FF&E OPTION ITEM CHANGES

3.2.1 Requests for Price Changes

The FF&E Option has been priced, negotiated, and awarded based on specific line items as detailed in the approved Final FF&E Submittal. These items have been approved considering color, specific type and quality of material, price, and usable life. The Government will expect and require the Contractor to provide exactly those items. Any requests to change FF&E items that will cause a price change must be submitted in writing for approval by the NAVFAC Contracting Officer and Interior Designer before purchase and installation.

3.2.2 Requests for Item Changes

Should changes become necessary, careful consideration is required to ensure that equivalent quality, price and other aspects of the items are maintained. Any adjustments must be negotiated. Provide BVD documentation for each substituted item if the extended cost for the item exceeds the micro-purchase threshold (MPT). If multiple items from the same SIN must be substituted, include in the same BVD. Unexpired vendor quotes from the original FF&E RFQ may be used in the new BVD, provided that they are the same SIN and all quotes are from the same procurement

category, i.e., GSA or Open Market. The Contractor must coordinate with the NAVFAC Interior Designer and Collateral Equipment Manager, in consultation with the Activity, for any changes to the FF&E. The Contracting Officer must approve any changes.

3.2.3 Post Option Award FF&E and CEQ Finish Submittals

FF&E finishes may need to be revised due to discontinued product finishes. Submit any revisions or deviations to the FF&E finishes to the NAVFAC Interior Designer for review. The Contracting Officer must approve any changes to the FF&E finishes.

3.2.4 Validation of Pricing

The Contractor must validate pricing with the FF&E vendor(s) prior to FF&E Option award. Cost increases due to authorized GSA schedule price increases must be allowed prior to the FF&E Option award to purchase the FF&E. Reimbursement for price increases after FF&E Option award will not be considered.

3.2.5 Progress Payments

Per FAR 52.232-5 Payments under Fixed-Price Construction Contracts, the Contracting Officer may authorize a progress payment on the FF&E ordered as material delivered to the Contractor, at locations other than the site if:

a. Consideration is specifically authorized by this contract; and

b. The Contractor furnishes satisfactory evidence, including a copy of the order acknowledgment and proof of payment, that it has acquired title to such material, the material is stored in a secure, climate controlled location, and that the material will be used to perform this contract.

3.3 INSTALLATION

The FF&E Package includes the installation of all furniture and furnishings as specified in the Final FF&E Package. The FF&E installation dealer(s) specified in the FF&E Package must receive, store as required, transport to the project site, off load, inside deliver, unpack, assemble, install, clean, and dispose of all the trash for all FF&E. It is the Contractor's responsibility to coordinate the building completion, occupancy, and furniture installation dates with the installation dealer(s) specified in the FF&E Package. Any costs associated with or delaying furniture shipments to accommodate the construction schedule is the responsibility of the Contractor.

3.3.1 FF&E Pre-Installation Walk-Through

The Contractor must coordinate and participate in a walk-through to ensure that the building interior is substantially complete in all areas scheduled to receive FF&E to include floor, wall and ceiling finishes and building systems located on or in the ceilings. Attendees must include the NAVFAC Construction Manager and the FF&E vendor(s) in-person (if geographically feasible) or virtually. Approval by the NAVFAC Construction Manager to proceed with the FF&E installation is required. The walk-through date must occur prior to the commencement of the FF&E installation and accommodate sufficient time in the construction schedule

for transportation of FF&E to the job site upon approval by the NAVFAC Construction Manager.

3.3.2 Walk Through(s) and Punch List(s) Submittal

The Contractor, Contractor's Interior Designer, NAVFAC Interior Designer, FF&E vendor(s) or dealer(s) representative and installation superintendent, other specialty consultants (if applicable), NAVFAC Construction Manager, Asset Management Branch (AMD) or Supply Management Division (SMD) (USMC projects), and the Activity will attend one punch list site visits. The site visit must be held at the installation dealer's 98 percent completion and must identify and record all punch list items in the Punch List(s) Submittal. The site visit must be held at the installation dealer's 100 percent completion and must confirm that all punch list items have been resolved.

The Contractor must repair, to the Government's satisfaction, all damage to any facility finish that is a result of the furniture/CEQ installation and correct all punch list items for the FF&E/CEQ. Any damage or loss of FF&E/CEQ after installation will be the responsibility of the Contractor and not the FF&E/CEQ vendor or installer. Daily installation walk-throughs by the Contractor and the FF&E/CEQ installation dealer are encouraged to document any damage and identify the responsible party(s).

3.4 INSTALLATION WARRANTY

Install all movable furnishings in accordance with the manufacturer's instructions and warranty requirements. All movable furnishings must be level and aligned. All doors, drawers and accessories must be level and aligned to open, close and otherwise operate smoothly and securely.

All FF&E and Specialty CEQ must be installed by the manufacturer's dealer of record and not by the Contractor.

3.5 CLOSEOUT SUBMITTALS

3.5.1 Warranty And Maintenance Information

Provide to the Contracting Officer at the final FF&E walk-thru one electronic copy and one binder copy of all ordering documentation, including but not limited to, quotes, purchase orders, factory order numbers (FO), IUID, and warranty and maintenance information for all products.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 12 24 13

ROLLER WINDOW SHADES
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM G21	(2015; R 2021; E 2021) Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 701	(2023; ERTA 1 2023) Standard Methods of Fire Tests for Flame Propagation of Textiles and Films

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

UL SOLUTIONS (UL)

UL 325	(2017; Reprint Sep 2025) UL Standard for Safety Door, Drapery, Gate, Louver, and Window Operators and Systems
UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES

SD-02 Shop Drawings

Detailed Drawings; G

Location Schedule; G

SD-03 Product Data

Window Shades; G

Recycled Content for various fiber components; S

SD-04 Samples

Window Shades; G

SD-06 Test Reports

Flammability Requirements; G

SD-07 Certificates

Indoor Air Quality for roller window shades; S

Qualifications

SD-10 Operation and Maintenance Data

Window Shades, Data Package 1; G

SD-11 Closeout Submittals

Submit Data Package 1 for roller window shades, and Data Package 2 for electrical operators, in accordance with Section 01 78 23 OPERATIONS AND MAINTENANCE DATA.

1.3 CERTIFICATES

1.3.1 Indoor Air Quality Certifications

1.3.1.1 Roller Window Shades

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide validation by other third-party program that products meet the requirements of this paragraph. Provide current product certification documentation from certification body.

1.4 QUALITY ASSURANCE

1.4.1 Qualifications

1.4.1.1 Installer's Qualifications

Installer trained and certified by the manufacturer with a minimum of ten years of experience in installing products comparable to those specified in this section.

1.4.2 Flammability Requirements

Passes in accordance with NFPA 701 small and large-scale vertical burn. Materials tested are identical to products proposed for use.

1.4.3 Electrical Requirements

NFPA Article 100 listed and labeled in accordance with UL 325 or other testing agency acceptable to authorities having jurisdiction, marked for intended use, and tested as a system. Individual testing of components is not acceptable in lieu of system testing.

1.4.4 Anti-Microbial Requirements

'No Growth' per ASTM G21 results for fungi ATCC9642, ATCC 9644, ATCC9645.

1.5 DELIVERY, STORAGE, AND HANDLING

Deliver components to the jobsite in the manufacturer's original packaging with the brand or company name, item identification, and project reference clearly marked. Store components in a dry location that is adequately ventilated and free from dust, water, or other contaminants and has easy access for inspection and handling. Store materials flat in a clean dry area with temperature maintained above 50 degrees F. Do not open containers until needed for installation unless verification inspection is required. Handle and store shades in accordance with manufacturer's recommendations.

1.6 WARRANTY

Provide manufacturer's warranty to repair or replace defective materials and workmanship for a period of 10 years from date of final acceptance of the work.

PART 2 PRODUCTS

2.1 WINDOW SHADES

Submit drawings showing plans, elevations, sections, product details, installation details, operational clearances, wiring diagrams and relationship to work. Submit a location schedule showing location, size and quantity of shades. Include the use of same room designations as indicated on the drawings.

Provide product data composed of catalog cuts, brochures, and operating and maintenance instructions on each product to be used. Include styles, profiles and features.

Furnish samples of each type and color of roller shade fabric and roller shade channel. Provide shade material minimum 6 by 6 inches in size. Mark face of material to indicate interior faces.

Mock up: Install shade in area designated by Contracting Officer. Do not proceed with remaining work until the Contracting Officer approves workmanship and operation. Rework mock up as required to produce acceptable work. The approved shade can be used in the installation.

Submit fire resistance data, flame spread and smoke contribution data.

Provide roller tube that operates smoothly and of sufficient diameter and thickness to prevent excessive deflection. Provide brackets that are appropriate for outside mount. Provide shade cloth meeting the performance described in NFPA 701, small scale test. Treat steel features for corrosion resistance.

Provide Various Fiber Components with a minimum of 60 percent recycled content. Provide data identifying percentage of recycled content for various fiber components.
Provide certification of indoor air quality for roller window shades.

2.1.1 Manufacturer's Qualifications

Obtain motor-controlled roller shades through one source from a single manufacturer with a minimum of twenty years of experience and minimum of three projects of similar scope and size in manufacturing products comparable to those specified in this section. Furnish manual and motorized shades produced by the same manufacturer to provide matching appearance.

2.1.2 Manually Operated Shades with Single Rollers

2.1.2.1 Spring Operating Mechanisms

Provide with positive locking mechanism that can stop shade movement at each half-turn of roller and with manufacturer's standard pull.

2.1.2.2 Rollers

Provide corrosion-resistant steel or extruded-aluminum tubes of diameters and wall thicknesses required to accommodate operating mechanisms and weights and widths of shade bands indicated without deflection. Provide with permanently lubricated drive-end assemblies and idle-end assemblies designed to facilitate removal of shade cloth for service.

a. Roller Drive-End Location: Right side of interior face of shade.

b. Direction of Shade cloth Roll: Regular, from back (exterior face) of roller.

c. Shade cloth-to-Roller Attachment: Manufacturer's standard method. Adhesive attachment is not acceptable.

2.1.2.3 Mounting Hardware

Provide corrosion resistant brackets or endcaps compatible with roller assembly, operating mechanism, installation accessories, and mounting location and conditions indicated. Provide hardware that allows for field adjustment or removal of shade roller tube and other operable hardware component without removal of brackets and end or center supports.

2.1.2.4 Shade Cloth

a. Shade Material: Light-filtering fabric: Openness 3 percent Light-blocking fabric.

b. Shade Cloth Bottom (Hem) Bar: Steel or extruded aluminum. Provide shade bar enclosed in sealed pocket of shade band material.

2.1.2.5 Installation Accessories

a. Front Fascia: L-shaped aluminum extrusion to conceal shade roller and hardware that snaps onto end caps without requiring exposed fasteners of any kind. Fascia can be mounted continuously across two or more shade bands. Provide manufacturers standard height fascia as required to conceal roller and shade band assembly when shade is fully open.

b. Exposed Headbox: Rectangular, extruded-aluminum enclosure including front fascia, top and back covers, endcaps, and removable bottom closure. Provide manufacturers standard height fascia as required to

conceal roller and shade band assembly when shade is fully open.

c. Endcaps: Extruded aluminum with universal design suitable for mounting to window mullions. Provide size compatible with roller size. Provide end cap covers matching fascia/headbox finish.

d. Recessed Shade Pocket: Rectangular, extruded-aluminum enclosure designed for recessed ceiling installation; with front, top, and back formed as one piece, end plates, and removable bottom closure panel. Provide manufacturers standard height fascia as required to conceal roller and shade band assembly when shade is fully open. Provide pocket with lip at lower edge to support acoustical ceiling panel.

e. Closure Panel and Wall Clip: Removable aluminum panel designed for installation at bottom of site-constructed ceiling recess or pocket and for snap-in attachment to wall clip without fasteners.

2.1.3 Manually Operated Shades with Dual Rollers

2.1.3.1 Spring Operating Mechanisms

Provide with positive locking mechanism that can stop shade movement at each half-turn of roller and with manufacturer's standard pull.

2.1.3.2 Rollers

Provide corrosion-resistant steel or extruded-aluminum tubes of diameters and wall thicknesses required to accommodate operating mechanisms and weights and widths of shade bands indicated without deflection. Provide with permanently lubricated drive-end assemblies and idle-end assemblies designed to facilitate removal of shade bands for service.

a. Dual Shade-Roller Mounting Configuration: Side by Side.

b. Inside Roller: Drive-End Location: As indicated on drawings. Direction of Shade cloth Roll: Regular, from back (exterior face) of roller.

c. Outside Roller: Drive-End Location: As indicated. Direction of Shade cloth Roll: Regular, from back (exterior face) of roller.

d. Shade cloth-to-Roller Attachment: Manufacturer's standard method. Adhesive attachment is not acceptable.

2.1.3.3 Mounting Hardware

Provide corrosion resistant brackets or endcaps compatible with roller assembly, operating mechanism, installation accessories, and mounting location and conditions indicated. Provide hardware that allows for field adjustment or removal of shade roller tube and other operable hardware component without removal of brackets and end or center supports.

2.1.3.4 Inside Shade Cloth

a. Shade Material: Light-filtering fabric: Openness 3 percent.

b. Shade Cloth Bottom (Hem) Bar: Steel or extruded aluminum. Provide shade bar enclosed in sealed pocket of shade cloth material, exposed with endcaps and integral light seal at bottom where it meets the sill.

2.1.3.5 Outside Shade Cloth

a. Shade Material: Light-blocking fabric.

b. Shade Cloth Bottom (Hem) Bar: Steel or extruded aluminum. Provide shade bar enclosed in sealed pocket of shade cloth material, exposed with endcaps and integral light seal at bottom where it meets the sill.

2.1.3.6 Installation Accessories

a. Front Fascia: L-shaped aluminum extrusion to conceal shade roller and hardware that snaps onto end caps without requiring exposed fasteners of any kind. Fascia can be mounted continuously across two or more shade bands. Provide manufacturers standard height fascia as required to conceal roller and shade band assembly when shade is fully open.

b. Exposed Headbox: Rectangular, extruded-aluminum enclosure including front fascia, top and back covers, endcaps, and removable bottom closure. Provide manufacturers standard height fascia as required to conceal roller and shade band assembly when shade is fully open.

c. Endcaps: Extruded aluminum with universal design suitable for mounting to window mullions. Provide size compatible with roller size. Provide end cap covers matching fascia/headbox finish.

d. Recessed Shade Pocket: Rectangular, extruded-aluminum enclosure designed for recessed ceiling installation; with front, top, and back formed as one piece, end plates, and removable bottom closure panel. Provide manufacturers standard height fascia as required to conceal roller and shade band assembly when shade is fully open. Provide pocket with lip at lower edge to support acoustical ceiling panel.

e. Closure Panel and Wall Clip: Removable aluminum panel designed for installation at bottom of site-constructed ceiling recess or pocket and for snap-in attachment to wall clip without fasteners.

2.1.3.7 Room Darkening Shades

Provide room darkening (black-out) window shades designed to eliminate all visible light gaps when shades are fully closed, and conform with the following:

a. Provide roller tube made of aluminum. Provide shop fabricated light traps, consisting of a head box to house the shade roller, and U-shaped channels to serve as guides for the shade along the sides and to receive the bottom edge of the shade along the sill.

b. Provide light trap made of sheet steel having a minimum thickness of 22 gauge or anodized, extruded, aluminum. Provide legs of the channels not less than 1-3/4 inches long and separated by the minimum distance that permits free operation of the shade. Edges of light trap coming into contact with the shade cloth are smooth pile light seal. The exposed face of the head box is hinged or removable for access to the shade roller. The interior or unexposed surfaces of the light trap have a finish coat of flat black enamel. The exposed portions of the light trap have a factory-applied priming coat of gray paint.

c. Provide type of cloth for blackout purposes. Provide shade from a single piece of PVC polyester with acrylic backing.

d. Fit the bottom edge of the shade with a steel operating bar. Shades to engage positively with bottom rail through operating bar. Paint bars with flat black enamel.

2.2 COLOR

Provide color, pattern and texture for metal trim and shade fabric as indicated; colors listed are not intended to limit the selection of equal colors from other manufacturers.

PART 3 EXECUTION

3.1 FIELD MEASUREMENTS

After becoming familiar with details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing the work.

3.2 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

Provide roller window shades, complete with necessary brackets, fittings, and hardware as indicated.

Perform installation in accordance with the approved detailed drawings and manufacturer's installation instructions. Install units level, plumb, secure, and at proper height and location relative to window units. Provide and install supplementary or miscellaneous items in total, including clips, brackets, or anchorages incidental to or necessary for a sound, secure, and complete installation. Do not start installation until completion of room painting and finishing operations.

3.3 CLEAN-UP

Upon completion of the installation, clean window treatments and exposed components as recommended by manufacturer. Adjust window treatment for form and appearance and proper operating condition. Repair or replace damaged units as directed by the Contracting Officer. Isolate metal parts from direct contact with concrete, mortar, or dissimilar metals. Ensure shades installed in recessed pockets can be removed without disturbing the pocket. The entire shade, when retracted, is contained inside the pocket. For shades installed outside the jambs and mullions, overlap each jamb and mullion 0.75 inch or more when the jamb and mullion sizes permit. Include all hardware, brackets, anchors, fasteners, and accessories necessary for a complete, finished installation.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 13 34 19

METAL BUILDING SYSTEMS
08/20, CHG 1: 02/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ARCHITECTURAL MANUFACTURERS ASSOCIATION (AAMA)

AAMA 2605	(2022) Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 325	(2017) Steel Construction Manual
AISC 360	(2016) Specification for Structural Steel Buildings

AMERICAN IRON AND STEEL INSTITUTE (AISI)

AISC/AISI 121	(2007) Standard Definitions for Use in the Design of Steel Structures
AISI D100	(2017) Cold-Formed Steel Design Manual

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7	(2017) Minimum Design Loads for Buildings and Other Structures
ASCE 7-16	(2017; Errata 2018; Supp 1 2018) Minimum Design Loads and Associated Criteria for Buildings and Other Structures

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 90.1 - IP	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings
ASHRAE 90.1 - SI	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings

AMERICAN WELDING SOCIETY (AWS)

AWS A5.1/A5.1M	(2012) Specification for Carbon Steel Electrodes for Shielded Metal Arc Welding
AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding

Code - Steel

AWS D1.3/D1.3M (2018) Structural Welding Code - Sheet Steel

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M (2019) Standard Specification for Carbon Structural Steel

ASTM A53/A53M (2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

ASTM A123/A123M (2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM A193/A193M (2025) Standard Specification for Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service and Other Special Purpose Applications

ASTM A307 (2023) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength

ASTM A463/A463M (2015; R 2020; E 2020) Standard Specification for Steel Sheet, Aluminum-Coated, by the Hot-Dip Process

ASTM A475 (2022) Standard Specification for Metallic-Coated Steel Wire Strand

ASTM A500/A500M (2023) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes

ASTM A501/A501M (2021) Standard Specification for Hot-Formed Welded and Seamless Carbon Steel Structural Tubing

ASTM A529/A529M (2019) Standard Specification for High-Strength Carbon-Manganese Steel of Structural Quality

ASTM A563 (2015) Standard Specification for Carbon and Alloy Steel Nuts

ASTM A563M (2007; R 2013) Standard Specification for Carbon and Alloy Steel Nuts (Metric)

ASTM A572/A572M (2021; E 2021) Standard Specification for High-Strength Low-Alloy Columbium-Vanadium Structural Steel

ASTM A606/A606M (2018) Standard Specification for Steel Sheet and Strip, High-Strength, Low-Alloy,

	Hot-Rolled and Cold-Rolled, with Improved Atmospheric Corrosion Resistance
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A755/A755M	(2018) Standard Specification for Steel Sheet, Metallic Coated by the Hot-Dip Process and Prepainted by the Coil-Coating Process for Exterior Exposed Building Products
ASTM A780/A780M	(2020) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A792/A792M	(2025a) Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process
ASTM A924/A924M	(2022a) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process
ASTM A992/A992M	(2020) Standard Specification for Structural Steel Shapes
ASTM A1008/A1008M	(2021a) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM A1011/A1011M	(2018a) Standard Specification for Steel Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength
ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B221M	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric)
ASTM C518	(2021) Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus

ASTM C665	(2017) Standard Specification for Mineral-Fiber Blanket Thermal Insulation for Light Frame Construction and Manufactured Housing
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM C1363	(2019) Standard Test Method for Thermal Performance of Building Materials and Envelope Assemblies by Means of a Hot Box Apparatus
ASTM D522/D522M	(2017) Mandrel Bend Test of Attached Organic Coatings
ASTM D523	(2014; R 2018) Standard Test Method for Specular Gloss
ASTM D714	(2002; R 2017) Standard Test Method for Evaluating Degree of Blistering of Paints
ASTM D822	(2013; R 2018) Filtered Open-Flame Carbon-Arc Exposures of Paint and Related Coatings
ASTM D968	(2017) Standard Test Methods for Abrasion Resistance of Organic Coatings by Falling Abrasive
ASTM D1056	(2020) Standard Specification for Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM D1308	(2002; R 2013) Effect of Household Chemicals on Clear and Pigmented Organic Finishes
ASTM D1667	(2017) Standard Specification for Flexible Cellular Materials - Poly (Vinyl Chloride) Foam (Closed-Cell)
ASTM D2244	(2016) Standard Practice for Calculation of Color Tolerances and Color Differences from Instrumentally Measured Color Coordinates
ASTM D2247	(2015) Testing Water Resistance of Coatings in 100% Relative Humidity
ASTM D2794	(1993; R 2019) Standard Test Method for Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact)
ASTM D3363	(2005; E 2011; R 2011; E 2012) Film Hardness by Pencil Test
ASTM D5359	(2015) Standard Specification for Glass

	Cullet Recovered from Waste for Use in Manufacture of Glass Fiber
ASTM DEFONLINE	(2008) ASTM Online Dictionary of Engineering Science and Technology
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E1592	(2025) Standard Test Method for Structural Performance of Sheet Metal Roof and Siding Systems by Uniform Static Air Pressure Difference
ASTM E1646	(1995; R 2018) Standard Test Method for Water Penetration of Exterior Metal Roof Panel Systems by Uniform Air Pressure Difference
ASTM E1680	(2016) Standard Test Method for Rate of Air Leakage Through Exterior Metal Roof Panel Systems
ASTM F436/F436M	(2019) Standard Specification for Hardened Steel Washers Inch and Metric Dimensions
ASTM F844	(2019) Standard Specification for Washers, Steel, Plain (Flat), Unhardened for General Use
ASTM F1554	(2020) Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength
ASTM F1852	(2014) Standard Specification for "Twist Off" Type Tension Control Structural Bolt/Nut/Washer Assemblies, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength
ASTM F3125/F3125M	(2019) Standard Specification for High Strength Structural Bolts and Assemblies, Steel and Alloy Steel, Heat Treated, Inch Dimensions 120 ksi and 150 ksi Minimum Tensile Strength, and Metric Dimensions 830 MPa and 1040 MPa Minimum Tensile Strength
ASTM G152	(2013; R 2021) Standard Practice for Operating Open Flame Carbon Arc Light Apparatus for Exposure of Nonmetallic Materials
ASTM G153	(2013; R 2021) Standard Practice for Operating Enclosed Carbon Arc Light Apparatus for Exposure of Nonmetallic Materials

FM GLOBAL (FM)

FM 4471	(2025) Class I Panel Roofs

METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA)

MBMA MBSM	(2018) Metal Building Systems Manual

NATIONAL ASSOCIATION OF ARCHITECTURAL METAL MANUFACTURERS (NAAMM)

NAAMM AMP 500	(2006) Metal Finishes Manual

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1793	(2012) Architectural Sheet Metal Manual, 7th Edition

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC Paint 15	(1999; E 2004) Steel Joist Shop Primer/Metal Building Primer
SSPC Painting Manual	(2002) Good Painting Practice, Steel Structures Painting Manual, Volume 1
SSPC SP 2	(2018) Hand Tool Cleaning

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-110-03	(2012; with Change 5, 2020) Roofing
UFC 3-301-01	(2023; with Change 6, 2026) Structural Engineering

UL SOLUTIONS (UL)

UL 580	(2006; Reprint Apr 2024) UL Standard for Safety Tests for Uplift Resistance of Roof Assemblies

1.2 GENERAL REQUIREMENTS

1.2.1 Design Parameters

Design and construct pre-engineered metal buildings of size, shape, height, fenestration, siting, and configuration indicated. Coordinate site utility services, accessibility requirements, vehicular and pedestrian access, mechanical, electrical, plumbing and fire protection requirements, interior construction and finishes, and such other items as may be necessary for a complete, functional building.

1.2.2 Structural Performance

Provide metal building systems capable of withstanding the effects of gravity loads and the following loads and stresses within the limits and conditions indicated.

1.2.2.1 Engineering

Design metal building systems conforming to procedures described in MBMA MBSM.

1.2.2.2 Design Loads

Design and construct to the requirements of UFC 3-301-01, Structural Engineering.

1.2.3 Thermal Performance

Provide insulated metal panel assemblies with the following maximum U-factors when assemblies are tested or calculated according to ASHRAE 90.1 - SI ASHRAE 90.1 - IP Appendix A, and minimum R-values for opaque elements when tested according to ASTM C1363 or ASTM C518.

1.2.3.1 Metal Roof Panel Assemblies

a. U-Factor: U-0.034 maximum

b. R-Value: R-29 minimum

Roof insulation consists of two layers of unfaced fiberglass insulation, with the upper layer having an R-value of 19 and the lower layer having an R-value of 10. The installed thickness is 9 inches for an 8.5 inch purlin and achieves a total installed R-value of 29. Size layer thicknesses and widths to completely fill cavity depths and shapes.

1.2.4 Air Infiltration for Metal Roof Panels

Air leakage through assembly must not exceed 0.04 cfm/sq.ft. of roof area when lab tested according to ASTM E1680 at negative test-pressure difference of 1.57 lb/sq.ft..

1.2.5 Water Penetration for Metal Roof Panels

No water penetration when tested according to ASTM E1646 at test-pressure difference of 2.86 lbf/sq.ft.

1.2.6 Specular Gloss

Finished roof surfaces to have a specular gloss value of 30 plus or minus 5 at an angle of 60 degrees when measured in accordance with ASTM D523.

1.2.7 Wind-Uplift Resistance

Design for wind-uplift resistance in accordance with UFC 3-301-01.

Submit a DELEGATED DESIGN with sealed calculations and shop drawings prepared by a registered professional engineer.

Furnish metal building systems that resist dead, live, uplift and lateral

loads. Marine Corps Base Camp Lejeune must resist a 144 mile per hour, ultimate design wind speed, 54 PSF, Risk Category II, Surface Roughness Category C, Exposure Category C lateral load. Comply with UFC 3-301-01, NCSBC and ASCE 7 as applicable for building system designs and components. Assembly design responsibility is delegated to the Contractor and incorporates specific properties and structural capabilities of selected products and manufacturers.

Primary steel structures have a lateral drift of L/400.

Supplement delegated design shop drawings with metal building system structural computations. Tie general manufacturer data of appurtenant members utilized to project specific conditions. Specify fastening patterns and connections.

Submit metal building design reactions for gravity loads, uplift, shear and thrust. Individually specify dead, live and wind load reactions.

Primary member cross sections, secondary member cross sections and clear dimensions are minimums. Provide greater member cross sections, lateral bracing and cross bracing as dictated by a delegated design. Coordinate the delegated design with the Instruments of Service to accommodate scheduled personnel doors, overhead doors, windows and similar penetrations.

Design members for both balanced and unbalanced live load conditions. Design and detail column bases as pinned supports and assume they are incapable of transferring moment.

Assume roof and wall panels provide no diaphragm strength in resisting lateral loads. Frame door, window and other wall and roof openings with continuous secondary members.

Design for wind loads in accordance with ASCE 7 and UFC 3-110-03. Comply with the pressurization standards of UL 580, Class 90. Comply with the pressurization standards of FM 4471, Class 1-120 for roof slopes with a 1.75:12 pitch or more. Divide metal roof panel systems supported by either solid decking or purlins into field, edge and corner pressure zones. Stipulate requirements for additional structural members and fasteners. Evaluate pressure zones in accordance with the load sequence stipulated by ASTM E1592. Resist the design pressures indicated, and determine panel bending and clip to panel strength. Interpolate capacities for gauge, span and loading. Account for prying forces from eccentric clip loading when computing uplift loads on fasteners. Calculate fastener holding strength based on substrate thickness or length of embedment. Use safety factors appropriate for the material properties involved. The construction assembly must match the pull out resistance determined by ASTM E1592, but may be attached to either solid decking or purlin substrates as permitted by UFC 3-110-03.

1.2.8 Erection Plan

Provide plans and a written erection/lifting procedure with required plans clearly showing the intended sequence and method of erection in accordance with EM 385-1-1 "Safety - Safety and Health Requirements". Indicate required crane lifting requirements, temporary support structures, member size and locations of braced or guyed temporary supports, and locations of bracing or guys anchor points. Clearly define the required framing sequence and conditions necessary to ensure the structure is maintained in

a properly braced and stable condition throughout the complete erection process.

1.3 DEFINITIONS

a. Bay: Dimension between main frames measured normal to frame (at centerline of frame) for interior bays, and dimension from centerline of first interior main frame measured normal to end wall (outside face of end-wall girt) for end bays.

b. Clear Span: Distance between supports of beams, girders, or trusses (measured from lowest level of connecting area of a column and a rafter frame or knee).

c. Eave Height: Vertical dimension from finished floor to eave (the line along the sidewall formed by intersection of the planes of the roof and wall).

d. Terminology Standard: Refer to MBMA "Metal Building Systems Manual" for definitions of terms for metal building system construction not otherwise defined in this Section or in referenced standards.

1.4 SYSTEM DESCRIPTION

General: Provide a complete, integrated set of mutually dependent components and assemblies that form a metal building system capable of withstanding structural and other loads, thermally induced movement, and exposure to weather without failure or infiltration of water into building interior. Include primary and secondary framing, metal panels, and accessories complying with requirements indicated.

Provide metal building system of size and with spacing, slopes, and spans indicated.

1.4.1 Primary Frame Type

a. Rigid Clear Span: Solid-member, structural-framing system without interior columns.

1.4.2 Secondary Frame Type

Provide manufacturer's standard purlins.

1.4.3 Eave Height

Eave height must be as indicated by nominal height on Drawings.

1.4.4 Bay Spacing

Bay Spacing must be as indicated in the drawings.

1.4.5 Roof Slope

Roof slope must be as indicated in the drawings.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for

Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Manufacturer's Qualifications; G

SD-02 Shop Drawings

Detail Drawings; G

Erection Plan; G

SD-03 Product Data

Manufacturer's Catalog Data; G

Recycled Content for Structural Steel Shapes and Plates; S

Recycled Content for Steel Pipe; S

Recycled Content for Steel Sheet Materials; S

Recycled Content for Insulation Materials; S

SD-04 Samples

Coil Stock, 12 inches long by the actual panel width; G

Roof Panels, 12 inches long by actual panel width; G

Fasteners; G

Metal Closure Strips 10 inches long of each type; G

Insulation, approximately 8 by 11 inches; G

Color, 4 by 4 inches; G

SD-05 Design Data

Manufacturer's Descriptive and Technical Literature; G

Manufacturer's Building Design Analysis; G

Lateral Force Calculations; G

SD-06 Test Reports

Test Reports; G

Coatings and Base Metals; G

Factory Color Finish Performance Requirements; G

SD-07 Certificates

System Components; G

Coil Stock Certificates; G

Aluminized Steel Repair Paint; G

Galvanizing Repair Paint; G

Enamel Repair Paint; G

Qualification of Manufacturer; G

Qualification of Erector; G

SD-08 Manufacturer's Instructions

Installation of Roof panels; G

Shipping, Handling, and Storage; G

1.6 QUALITY ASSURANCE

1.6.1 Pre-Erection Conference

After submittals are received and approved but before metal building system work, including associated work, is performed, the Contracting Officer will hold a pre-erection conference to review the following:

a. The detail drawings, specifications, and manufacturer's descriptive and technical literature.

b. Finalize construction schedule and verify availability of materials, erector's personnel, equipment, and facilities needed to make progress and avoid delays.

c. Methods and procedures related to metal building system erection, including, but not limited to: qualification of manufacturer, qualification of erector, manufacturer's catalog data, manufacturer's building design analysis,lateral force calculations, written instructions and test reports. Lateral force calculations must include all analysis and confirmation of system components required to transfer lateral forces to the foundation.

d. Support conditions for compliance with requirements, including alignment between and erection of structural members.

e. Flashing, special roofing and siding details, roof penetrations, openings, and condition of other construction that will affect the metal building system, including coatings and base metals, factory color finish performance requirements, system components, and coil stock certificates.

f. Governing regulations and requirements for, certificates, insurance, tests and inspections if applicable.

g. Temporary protection requirements for metal panel assembly during and after installation.

h. Samples of roof panels, aluminized steel repair paint, galvanizing repair paint, and enamel repair paint.

1.6.1.1 Pre-Roofing Installation Conference

After structural framing system erection and approval but before roofing, siding, insulation and vapor barrier work, including associated work, is performed; the Contracting Officer will hold a pre-roofing and siding conference to review the following:

a. Examine purlins and formed shapes conditions for compliance with requirements, including flatness and attachment to structural members.

b. Review structural limitations of purlins and formed shapes during construction and after roofing.

c. Review flashings, special roof details, roof drainage, roof penetrations, roof equipment curbs, and condition of other construction that will affect the metal building system.

d. Review temporary protection requirements for metal roof panels' assembly during and after installation.

e. Review roof observation and repair procedures after metal building system erection.

1.6.2 Manufacturer's Technical Representative

The representative must have authorization from manufacturer to approve field changes and be thoroughly familiar with the products, erection of structural framing and installation of roof panels in the geographical area where construction will take place.

1.6.3 Manufacturer's Qualifications

Metal building system manufacturer must have a minimum of five years experience as a qualified manufacturer and a member of MBMA of metal building systems and accessory products.

Provide engineering services by an authorized currently licensed engineer in the geographical area where construction will take place, having a minimum of four years experience as an engineer knowledgeable in building design analysis, protocols and procedures for the "Metal Building Systems Manual" (MBMA MBSM); ASCE 7-16, the building code in the geographic area where the construction will take place and ASTM E1592. Provide certified engineering calculations using the products submitted for:

a. Roof Wind Loads with basic wind speed, exposure category, co-efficient, importance factor, designate type of facility, negative pressures for each zone, methods and requirements of attachment.

b. Roof Dead and Live Loads

c. Collateral Loads

d. Foundation Loads

e. Roof Snow Load

f. Seismic Loads

1.6.4 Qualification of Erection Contractor

An experienced erector who has specialized in erecting and installing work similar in material, design, and extent to that indicated for this Project and must be approved and certified by the metal building system manufacturer.

1.6.5 Single Source

Obtain primary and secondary components and structural framing members, each type of metal roof panel assemblies, clips, closures and other accessories from the standard products of the single source from a single manufacturer to operate as a complete system for the intended use.

1.6.6 Welding

Qualify procedures and personnel according to AWS A5.1/A5.1M, AWS D1.1/D1.1M, and AWS D1.3/D1.3M.

1.6.7 Structural Steel

Comply with AISC 325, AISC 360, for design requirements and allowable stresses.

1.6.8 Cold-Formed Steel

Comply with AISC/AISI 121 and AISI D100 for design requirements and allowable stresses.

1.6.9 Fabrication

Fabricate and finish metal panels and accessories at the factory to greatest extent possible, by manufacturer's standard procedures and processes and as necessary to fulfill indicated performance requirements. Comply with indicated profiles with dimensional and structural requirements. Provide metal panel profile, including major ribs and intermediate stiffening ribs, if any, for full length of panel. Aluminum and aluminum-alloy sheet and plate must conform to ASTM B209. Fabricate metal panel side laps with factory-installed captive gaskets or separator strips that provide a tight seal and prevent metal-to-metal contact, in a manner that will seal weather-tight and minimize noise from movements within panel assembly.

Sheet Metal Accessories: Fabricate flashing and trim to comply with recommendations in SMACNA 1793 that apply to the design, dimensions, metal, and other characteristics of item indicated:

a. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.

b. End Seams: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints for additional strength.

c. Sealed Joints: Form non-expansion but movable joints in metal to accommodate elastomeric sealant to comply with SMACNA standards.

d. Conceal fasteners and expansion provisions where possible. Exposed

fasteners are not allowed on faces of accessories exposed to view.

e. Fabricate cleats and attachment devices of size and metal thickness recommended by SMACNA or by metal building system manufacturer for application, but not less than thickness of metal being secured.

1.6.10 Finishes

Comply with NAAMM AMP 500 for recommendations for applying and designating finishes.

Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

1.7 SHIPPING, HANDLING AND STORAGE

1.7.1 Delivery

Package and deliver components, sheets, metal panels, and other manufactured items so as not to be damaged or deformed and protected during transportation and handling.

1.7.2 Storage

Stack and store metal panels horizontally on platforms or pallets, covered with suitable weather-tight and ventilated covering to ensure dryness, with positive slope for drainage of water. Store in a manner to prevent bending, warping, twisting, and surface damage. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage. Retain strippable protective covering on metal panel for entire period up to metal panel installation.

1.7.3 Protection of Materials

Protect foam-plastic insulation as follows:

a. Do not expose to sunlight, except to extent necessary for period of installation and concealment.

b. Protect against ignition at all times. Do not deliver foam-plastic insulation materials to project site before installation time.

Complete installation and concealment of plastic materials as rapidly as possible in each area of construction to minimize ultraviolet exposure.

1.8 PROJECT CONDITIONS

1.8.1 Weather Limitations

Proceed with installation preparation only when existing and forecasted weather conditions permit Work to proceed without water entering into existing panel system or building.

1.8.2 Field Measurements

1.8.2.1 Established Dimensions for Foundations

Comply with established dimensions on approved anchor-bolt plans, established foundation dimensions, and proceed with fabricating structural framing. Do not proceed without verifying field measurements. Coordinate anchor-bolt installation to ensure that actual anchorage dimensions correspond to established dimensions.

1.8.2.2 Established Dimensions for Metal Panels

Where field measurements cannot be made without delaying the Work, either establish framing and opening dimensions and proceed with fabricating metal panels without field measurements, or allow for field trimming metal panels. Coordinate construction to ensure that actual building dimensions, locations of structural members, and openings correspond to established dimensions.

1.8.2.3 Verification Record

Verify locations of all framing and opening dimensions by field measurements before metal panel fabrication and indicate measurements on Shop Drawings.

1.9 COORDINATION

Coordinate final design and placement of foundation between structural engineer of record, geotechnical engineer, MBMA and Contractor. Coordinate size and location of concrete foundations and casting of anchor-bolt inserts into foundation walls and footings. Concrete, reinforcement, and formwork requirements are specified in section on CAST-IN-PLACE CONCRETE.

Coordinate metal panel assemblies with rain drainage work, flashing, trim, and construction of supports and other adjoining work to provide a leak-proof, secure, and non-corrosive installation.

PART 2 PRODUCTS

2.1 STRUCTURAL FRAMING MATERIALS

2.1.1 Steel Shapes and Plates

Wide flange and WT shapes: ASTM A992/A992M; ASTM A572/A572M or ASTM A529/A529M. Angles, Channels and Plates: ASTM A36/A36M, ASTM A572/A572M or ASTM A529/A529M. Provide structural steel shapes and plates containing a minimum of 80 percent recycled content. Submit data identifying percentage of recycled content for structural steel shapes and plates.

2.1.2 Steel Pipe

ASTM A36/A36M, ASTM A53/A53M, ASTM A572/A572M or ASTM A529/A529M. Provide steel pipe containing a minimum of 50 percent recycled content. Submit data identifying percentage of recycled content for steel pipe.

2.1.3 Cold-Formed and Hot Formed Hollow Structural Sections

Cold formed: ASTM A500/A500M or ASTM B221, ASTM B221M. Hot-formed: ASTM A501/A501M.

2.1.4 Structural-Steel Sheet

Hot-rolled, ASTM A1011/A1011M or cold-rolled, ASTM A1008/A1008M.

2.1.5 Metallic-Coated Steel Sheet

ASTM A653/A653M, ASTM A606/A606M.

2.1.6 Metallic-Coated Steel Sheet Pre-painted with Coil Stock Coating

Steel sheet metallic coated by the hot-dip process and pre-painted by the coil-coating process to comply with ASTM A755/A755M.

a. Zinc-Coated (Galvanized) Steel Sheet: ASTM A653/A653M, and ASTM A123/A123M.

b. Aluminum-Zinc Alloy-Coated Steel Sheet: ASTM A792/A792M, and ASTM A463/A463M.

2.1.7 High-Strength Bolts, Nuts, and Washers

ASTM F3125/F3125M, heavy hex steel structural bolts; ASTM A563 heavy hex carbon-steel nuts; and ASTM F436/F436M hardened carbon-steel washers.

Finish: Plain.

Tension-Control, High-Strength Bolt-Nut-Washer Assemblies: ASTM F1852, heavy-hex-head steel structural bolts with spline.

Finish: Plain.

2.1.8 Non-High-Strength Bolts, Nuts, and Washers

ASTM A307, ASTM A563, and ASTM F844.

Finish: Plain.

2.1.9 Anchor Rods

ASTM F1554.

a. Configuration: Straight.

b. Nuts: ASTM A563 hex carbon steel.

c. Plate Washers: ASTM A36/A36M carbon steel.

d. Washers: ASTM F436/F436M hardened carbon steel.

e. Finish: Plain.

2.1.10 Threaded Rods

ASTM A193/A193M.

a. Nuts: ASTM A563MASTM A563 hex carbon steel.

b. Washers: ASTM A36/A36M carbon steel.

c. Finish: Plain.

2.1.11 Primer

SSPC-Paint 15, Type I, red oxide.

2.2 FABRICATION

2.2.1 General

Comply with MBMA MBSM - "Metal Building Systems Manual": Chapter IV, Section 9, "Fabrication and Erection Tolerances."

2.3 STRUCTURAL FRAMING

2.3.1 General

Clean all framing members to remove loose rust and mill scale. Provide 1 shop coat of primer to an average dry film thickness of 1 mil according to SSPC SP 2. Balance of painting and coating procedures must conform to SSPC Paint 15 and SSPC Painting Manual.

2.3.2 Primary Framing

Manufacturer's standard structural primary framing system includes transverse and lean-to frames; rafter, rakes, and canopy beams; and corner columns; and wind bracing designed to withstand required loads and specified requirements. Provide frames with attachment plates, bearing plates, and splice members. Provide frame span and spacing indicated.

Shop fabricate framing components by welding or by using high-strength bolts to the indicated size and section with base-plates, bearing plates, stiffeners, and other items required. Cut, form, punch, drill, and weld framing for bolted field erection.

a. Rigid Clear-Span Frames: I-shaped frame sections fabricated from shop-welded, built-up steel plates or structural-steel shapes. Interior columns are not permitted.

d. Exterior Column Type: Tapered.

e. Rafter Type: Uniform depth.

2.3.3 Secondary Framing

Manufacturer's standard secondary framing members, including purlins, eave struts, flange bracing, base members, gable angles, clips, headers, jambs, and other miscellaneous structural members. Fabricate framing from cold-formed, structural-steel sheet or roll-formed, metallic-coated steel sheet pre-painted with coil coating, unless otherwise indicated.

Shop fabricate framing components by roll-forming or break-forming to the

indicated size and section with base-plates, bearing plates, stiffeners, and other plates required for erection. Cut, form, punch, drill, and weld secondary framing for bolted field connections to primary framing.

a. Purlins: C or Z-shaped sections; fabricated from steel sheet, built-up steel plates, or structural-steel shapes; minimum depth as required to comply with system performance requirements.

c. Eave Struts: Unequal-flange, C-shaped sections; fabricated from steel sheet, built-up steel plates, or structural-steel shapes; to provide adequate backup for metal panels.

d. Flange Bracing: Structural-steel angles or cold-formed structural tubing to stiffen primary frame flanges.

e. Sag Bracing: Structural-steel angles.

g. Purlin and s: Steel sheet. Provide galvanized clips where clips are connected to galvanized framing members.

j. Miscellaneous Structural Members: Manufacturer's standard sections fabricated from cold-formed, structural-steel sheet; built-up steel plates; or zinc-coated (galvanized) steel sheet; designed to withstand required loads.

2.3.4 Bracing

Provide adjustable wind bracing as follows:

a. Rods: ASTM A36/A36M; ASTM A572/A572M; or ASTM A529/A529M.

b. Cable: ASTM A475, extra-high-strength grade, zinc-coated; with threaded end anchors.

c. Angles: Fabricated from structural-steel shapes to match primary framing, of size required to withstand design loads.

d. Rigid Portal Frames: Fabricate from shop-welded, built-up steel plates or structural-steel shapes to match primary framing; of size required to withstand design loads.

e. Fixed-Base Columns: Fabricate from shop-welded, built-up steel plates or structural-steel shapes to match primary framing; of size required to withstand design loads.

f. Diaphragm Action of Metal Panels: Design metal building to resist wind forces through diaphragm action of metal panels.

g. Bracing: Provide wind bracing using any method specified above, at manufacturer's option, provided bracing does not obstruct openings or open walls as illustrated in the Instruments of Service.

2.4 PANEL MATERIALS

2.4.1 Steel Sheet

a. Roof panels are 0.024 inch, 24 gauge galvanized steel and fabricated with 50,000 PSI sheet coil conforming to ASTM A653/A653M, Grade C, Class G90, and ASTM A924/A924M galvanized or ASTM A792/A792M, CS Type B or C galvalume. Prefabricate machine seamed roof panels with 350 degree double lock standing seams. Cleats and bearing plates are heavy gauge galvanized steel, aluminum, stainless steel or similar non corrosive, compatible metal formed into panel clips. Panel clips accommodate thermal movement by floating 1 inch parallel and perpendicular to seams. Rigid insulation thermal blocks extend perpendicular to and 1 inch beyond each side of purlins, have a compressive strength of 25 PSI and an R-value of 5. Furnish factory installed sealant or vinyl weatherseal along panel lap lengths. Provide sealants, mastics, gaskets, fillers, closure strips and similar accessories at end laps, side laps, rakes, eaves and penetrations. Shop fabricated flashing and trims match panel metals and finishes. Furnish roof panel transitions and accessories including ridge cap, flashing, rake and eave trims.

2.4.1.1 Panel Fabrication

oll-form steel panels to the specified profile, with gauge and depth as indicated. Steel sheets must contain a minimum recycled content of 25 percent. Provide data identifying percentage of recycled content for steel sheet materials. Material must be plumb and true, and within the tolerances listed:

a. Galvanized Steel Sheet conforming to ASTM A653/A653M and AISI D100.

b. Individual panels to have continuous length to cover the entire length of any unbroken roof slope with no joints or seams and formed without warping, waviness, or ripples that are not part of the panel profile and free of damage to the finish coating system.

c. Provide panels with thermal expansion and contraction consistent with the type of system specified;

profile and coverage to be a minimum height of 2.25 inches with 350 degree machine rolled seam and width from manufacturer's standard.

Smooth, flat Surface Texture.

2.4.2 Finish

All panels are to receive a factory-applied polyvinylidene fluoride finish conforming to AAMA 2605 and consisting of a baked-on top-coat with a manufacturer's recommended prime coat conforming to the following:

a. Metal Preparation: All metal is to have the surfaces carefully prepared for painting on a continuous process coil coating line by alkali cleaning, hot water rinsing, application of chemical conversion coating, cold water rinsing, sealing with acid rinse, and thorough drying.

b. Prime Coating: A base coat of epoxy paint, specifically formulated to interact with the top-coat, is to be applied to the prepared surfaces by roll coating to a dry film thickness of 0.20 plus 0.05 mils. This prime coat must be oven cured prior to application of finish coat.

c. Exterior Finish Coating: Apply the finish coating over the primer by roll coating to dry film thickness of 0.80 plus 0.05 mils for a total dry film thickness of 1.00 plus 0.10 mils. This finish coat must be oven-cured.

d. Interior Finish Coating: Apply a wash-coat on the reverse side over the primer by roll coating to a dry film thickness of 0.30 plus 0.05 mils for a total dry film thickness of 0.50 plus 0.10 mils. The wash-coat must be oven-cured.

e. Color: Roof panel is slate gray as indicated in the Marine Corps Base Camp Lejeune, Base Exterior Architectural Plan, Stone Bay, MARSOC.

f. Physical Properties: Coating must conform to the industry and manufacturer's standard performance criteria as listed by the following certified test reports:

Chalking: ASTM DEFONLINE
Color Change and Conformity: ASTM D2244
Weatherometer: ASTM G152, ASTM G153 and ASTM D822
Humidity: ASTM D2247 and ASTM D714
Salt Spray: ASTM B117
Chemical Pollution: ASTM D1308
Gloss at 60 degrees: ASTM D523
Pencil Hardness: ASTM D3363
Reverse Impact: ASTM D2794
Flexibility: ASTM D522/D522M
Abrasion: ASTM D968
Flame Spread: ASTM E84

2.4.3 Repair Of Finish Protection

Repair paint for enameled metal panel must be compatible paint of the same formula and color as the specified finish furnished by the metal panel manufacturer, conforming to ASTM A780/A780M.

2.5 FASTENERS

2.5.1 General

Type, material, corrosion resistance, size and sufficient length to penetrate the supporting member a minimum of 1 inch with other properties required to fasten miscellaneous metal framing members to substrates in accordance with the metal panel manufacturer's and ASCE 7-16 requirements.

Finish exposed rivets and fasteners to match substrate colors encountered.

2.5.2 Exposed Fasteners

Fasteners for metal panels to be corrosion resistant coated steel, aluminum, stainless steel, or nylon capped steel compatible with the sheet panel or flashing and of a type and size recommended by the manufacturer

to meet the performance requirements and design loads. Fasteners for accessories to be the manufacturer's standard. Provide an integral metal washer matching the color of attached material with compressible sealing EPDM gasket approximately 3/32 inch thick.

2.5.3 Screws

Screws to be corrosion resistant coated steel, aluminum or stainless steel being the type and size recommended by the manufacturer to meet the performance requirements.

2.5.4 Rivets

Rivets to be closed-end type, corrosion resistant coated steel, aluminum or stainless steel where watertight connections are required.

2.5.5 Attachment Clips

Fabricate clips from steel hot-dipped galvanized in accordance with ASTM A653/A653M or Series 300 stainless steel. Size, shape, thickness and capacity as required meeting the insulation thickness and design load criteria specified.

2.6 ACCESSORIES

2.6.1 General

All accessories to be compatible with the metal panels; sheet metal flashing, trim, metal closure strips, caps and similar metal accessories must not be less than the minimum thickness specified for the metal panels. Exposed metal accessories/finishes to match the panels, except as otherwise indicated. Molded foam rib, ridge and other closure strips to be non-absorbent closed-cell or solid-cell synthetic rubber or pre-molded neoprene to match configuration of the panels.

2.6.2 Insulation

Glass-Fiber Blanket Insulation: ASTM C665, Type I, blankets without membrane coverings. Provide insulation materials containing the following minimum percentage of recycled content by weight: 20 percent glass cullet complying with ASTM D5359. Provide data identifying percentage of recycled content for insulation materials.

2.6.2.1 Polyethylene Vapor Retarder

Install polyethylene vapor retarder membrane over entire roofsurface. Use fully compatible polyethylene tape to seal the edges of the sheets to provide a vapor tight membrane. Lap sheets not less than 6 inch. Provide sufficient material to avoid inducing stresses in sheets due to stretching or binding. All tears or punctures visible in the finished surface, at any time during the construction process, must be sealed with polyethylene tape. Vapor retarder color is black.

2.6.3 Rubber Closure Strips

Closed-cell, expanded cellular rubber conforming to ASTM D1056 and ASTM D1667; extruded or molded to the configuration of the specified metal panel and in lengths supplied by the metal panel manufacturer.

2.6.4 Metal Closure Strips

Factory fabricated closure strips to be the same material, thickness, color, finish and profile of the specified panel.

2.6.5 2.6.6 Joint Sealants

2.6.5.1 Sealants

Sealants are to be an approved gun type for use in hand or air-pressure caulking guns at temperatures above 40 degrees F(or frost-free application at temperatures above 10 degrees F with minimum solid content of 85 percent of the total volume. Sealant is to dry with a tough, durable surface skin which permits it to remain soft and pliable underneath, providing a weather-tight joint. No migratory staining is permitted on painted or unpainted metal, stone, glass, vinyl, or wood.

Prime all joints to receive sealants with a compatible one-component or two-component primer as recommended by the metal panel manufacturer.

2.6.5.2 Shop-Applied

Sealant for shop-applied caulking must be an approved gun grade, non-sag one component polysulfide or silicone conforming to ASTM C920, Type II, and with a curing time to ensure the sealant's plasticity at the time of field erection.

2.6.5.3 Field-Applied

Sealant for field-applied caulking must be an approved gun grade, non-sag one component polysulfide or two-component polyurethane with an initial maximum Shore A durometer hardness of 25, and conforming to ASTM C920, Type II. Color to match panel colors.

2.6.5.4 Tape Sealant

Pressure sensitive, 100 percent solid with a release paper backing; permanently elastic, non-sagging, non-toxic and non-staining as approved by the metal panel manufacturer.

2.7 SHEET METAL FLASHING AND TRIM

2.7.1 Fabrication

Shop fabricate sheet metal flashing and trim where practicable to comply with recommendations in SMACNA 1793 that apply to design, dimensions, metal, and other characteristics of item indicated. Obtain field measurements for accurate fit before shop fabrication.

Fabricate sheet metal flashing and trim without excessive oil canning, buckling, and tool marks and true to line and levels indicated, with exposed edges folded back to form hems.

2.8 FINISHES

2.8.1 General

Comply with NAAMM AMP 500 for recommendations for applying and designating finishes.

2.8.2 Appearance of Finished Work

Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 EXECUTION

3.1 EXAMINATION

Before erection proceeds, examine with the erector present, the concrete foundation dimensions, concrete and masonry bearing surfaces, anchor bolt size and placement, survey slab elevation, locations of bearing plates, and other embedments to receive structural framing with the metal building manufacturer's templates and drawings before erecting any steel components for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

Examine primary and secondary framing to verify that rafters, purlins, angles, channels, and other structural and metal panel support members and anchorages have been installed within alignment tolerances required by metal building manufacturer, UL, ASTM, ASCE 7-16 and as required by the building code for the geographical area where construction will take place.

Examine roughing-in for components and systems penetrating metal roof panels to verify actual locations of penetrations relative to seam locations of metal panels before metal roof panel installation.

Submit to the Contracting Officer a written report, endorsed by Erector, listing conditions detrimental to performance of the Work.

Proceed with erection only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

Provide temporary shoring, guys, braces, and other supports during erection to keep the structural framing secure, plumb, and in alignment against temporary construction loading or loads equal in intensity of the building design loads. Remove temporary support systems when permanent structural framing, connections, and bracing are in place, unless otherwise indicated.

Clean substrates of substances harmful to insulation, including removing projections capable of interfering with insulation attachment and performance.

Miscellaneous Framing: Install sub-purlins, girts, angles, furring, and other miscellaneous support members or anchorage for the metal roof panels, doors, windows, roof curbs, ventilators and louvers according to metal building manufacturer's written instructions.

3.3 ERECTION OF STRUCTURAL FRAMING

Erect metal building system according to manufacturer's written erection instructions, approved shop drawings and other erection documents in

accordance with MBMA MBSM - "Metal Building Systems Manual".

Do not field cut, drill, or alter structural members without written approval from metal building system manufacturer's professional engineer and the Contracting Officer.

Set structural framing accurately in locations and to elevations indicated and according to AISC 325 specifications. Maintain structural stability of frame during erection.

Clean and roughen concrete and masonry bearing surfaces prior to setting plates. Clean bottom surface of plates.

Align and adjust structural framing before permanent bolt-up and connections. Perform necessary adjustments and alignment to compensate for changes or discrepancies in elevations.

Maintain erection tolerances of structural framing in accordance with AISC 360.

3.4 METAL PANEL INSTALLATION

Provide metal panels of full length from eave to eave as indicated, unless otherwise indicated or restricted by shipping limitations. Anchor metal panels and other components of the Work securely in place, in accordance with MBMA MBSM.

Erect panel system in accordance with the approved erection drawings, the printed instructions and safety precautions of the metal building manufacturer.

Sheets are not to be subjected to overloading, abuse, or undue impact. Do not install bent, chipped, or defective sheets.

Sheets must be erected true and in exact alignment with the horizontal and vertical edges of the building, securely anchored, and with the indicated eave, and sill.

Work is to allow for thermal movement of the panel, movement of the building structure, and to provide permanent freedom from noise due to wind pressure.

Field cutting metal panels by torch is not permitted.

3.5 METAL PANEL FASTENER INSTALLATION

Anchor metal panels and other components of the Work securely in place, using manufacturer's approved fasteners according to manufacturers' written instructions.

3.6 FLASHING, TRIM AND CLOSURE INSTALLATION

a. Comply with performance requirements, manufacturer's written installation instructions, and SMACNA 1793. Provide concealed fasteners where possible, and set units true to line and level as indicated. Install work with laps, joints, and seams that will be permanently watertight and weather resistant.

b. Sheet metalwork is to be accomplished to form weather-tight

construction without waves, warps, buckles, fastening stresses or distortion, and allow for expansion and contraction. Cutting, fitting, drilling, and other operations in connection with sheet metal required to accommodate the work of other trades is to be performed by sheet metal mechanics.

3.7 ACCESSORY INSTALLATION

3.7.1 General

Install accessories with positive anchorage to building and weather-tight mounting, and provide for thermal expansion. Coordinate installation with flashings and other components.

3.7.2 Dissimilar Metals

Where dissimilar metals contact one another or corrosive substrates are present, protect against galvanic action by painting dissimilar metal surfaces with bituminous coating, by applying rubberized-asphalt underlayment to each surface, or by other permanent separation techniques as recommended by the metal building manufacturer.

3.7.3 Gutters and Downspouts

Comply with performance requirements, manufacturer's written installation instructions, and install sheet metal roof drainage items to produce complete roof drainage system according to SMACNA 1793 recommendations and as indicated. Coordinate installation of roof perimeter flashing with installation of roof drainage system.

3.7.4 Insulation

Comply with performance requirements and manufacturer's written installation instructions. Install insulation concurrently with metal panel installation, in thickness indicated to cover entire roof area.

3.7.5 Accessories and Specialties

Install accessories and specialties complete with necessary hardware, anchors, dampers, weather guards, rain caps, and equipment supports.

3.8 CLEAN-UP AND PROTECTION

3.8.1 Structural Framing

Clean all exposed structural framing at completion of installation. Remove metal shavings, filings, bolts, and wires from work area. Remove grease and oil films, excess sealants, handling marks, contamination from steel wool, fittings and drilling debris and scrub the work clean. Exposed metal surfaces to be free of dents, creases, waves, scratch marks, solder or weld marks, and damage to the finish coating.

3.8.2 Metal Panels

Clean all exposed sheet metal work at completion of installation. Remove metal shavings, filings, nails, bolts, and wires from work area. Remove protective coverings/films, grease and oil films, excess sealants, handling marks, contamination from steel wool, fittings and drilling debris and scrub the work clean. Exposed metal surfaces to be free of

dents, creases, waves, scratch marks, solder or weld marks, and damage to the finish coating.

3.8.3 Touch-Up Painting

After erection, promptly clean, prepare, and prime or re-prime field connections, rust spots, and abraded surfaces of prime-painted structural framing and accessories. Clean and touch-up paint with manufacturer's touch-up paint.

-- End of Section --

SECTION 13 47 00

ELECTROMAGNETIC BARRIERS
10/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-STD 202	Test Method Standard, Electronic and Electrical Component Pas

ASTM INTERNATIONAL (ASTM)

ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B221	(2021) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM C1224	(2020) Standard Specification for Reflective Insulation for Building Applications
ASTM C1338	(2019) Standard Test Method for Determining Fungi Resistance of Insulation Materials and Facings
ASTM C1371	(2022) Standard Test Method for Determination of Emittance of Materials Near Room Temperature Using Portable Emissometers
ASTM D1000	(2017) Standard Test Methods for Pressure-Sensitive Adhesive-Coated Tapes Used for Electrical and Electronic Applications
ASTM D2261	(2013; R 2017) Standard Test Method for Tearing Strength of Fabrics by the Tongue (Single Rip) Procedure (Constant Rate-of-Extension Tensile Testing Machine)
ASTM D3310	(2014) Standard Test Method for Determining Corrosivity of Adhesive Materials
ASTM D4935	(2018) Standard Test Method for Measuring the Electromagnetic Shielding

	Effectiveness of Planar Materials
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E90	(2023) Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements
ASTM E96/E96M	(2024a) Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials
ASTM E336	(2025) Standard Test Method for Measurement of Airborne Sound Attenuation between Rooms in Buildings
ASTM E413	(2022) Classification for Rating Sound Insulation
ASTM F476	(2014) Standard Test Methods for Security of Swinging Door Assemblies
ASTM E1408	(2020) Standard Practice for Subcutaneous Screening Test for Implant Materials

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.13	(2022) Mortise Locks & Latches Series 1000

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 299	(2006; R 2012) Standard Method for Measuring the Effectiveness of Electromagnetic Shielding Enclosures

INTELLIGENCE COMMUNITY STANDARD (ICS)

ICD/ICS 705	Technical Specifications for Construction and Management of Sensitive Compartmented Information Facilities
ICS 705-1	(2010) Physical and Technical Security Standard for Sensitive Compartmented Information Facilities
ICS 705-2	Standards for Accreditation and Reciprocal Use of Sensitive Compartmented Information Facilities

UL SOLUTIONS (UL)

UL 510	(2020; Dec 2022) UL Standard for Safety Polyvinyl Chloride, Polyethylene and Rubber Insulating Tape

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Work Plan; G

SD-03 Product Data

Radiant Barrier Foil; G

Conductive Foil Tape; G

Backing Adhesive; G

Coatings; G

1.3 MAINTENANCE MATERIAL SUBMITTALS

For maintenance, replacements and repairs, furnish one roll of foil tape and one perimeter set of conductive door gasket material from the same shipment as the installed electromagnetic barrier work.

1.4 DESIGN CRITERIA

The facility is classified as an open storage type. A six sided electromagnetic barrier installation that utilizes the metal cap decking for a sixth side is required. The accreditation barrier is also the perimeter electromagnetic barrier.

1. Open Storage allows secure compartmented information to be openly stored and processed, and does not require approved storage when not in use

1.5 WORK PLAN

1.5.1 Preparation

Prepare substrates in accordance with requirements for electromagnetic barrier work encountered. Evaluate work in place and confirm substrates are suitable for receiving scheduled work. Select preparation methods, accessories and fasteners that are compatible with substrates and finish materials. Describe installation tolerances, joining methods, patterns and edge treatments.

1.5.2 Shielding Expert

Provide a shielding expert to perform quality assurance and quality control work to meet installation, testing and accreditation requirements. Ensure installation workmanship and methods conform to the requirements of CNSSAM TEMPEST/1-13, CNSSI No. 7003, DoDM 5105.21, Volume 1, DoDM 5105.21, Volume 2, DoDM 5105.21, Volume 3, ICD/ICS 705, ICS 705-1, ICS 705-2, NSTISSAM TEMPEST/2-95, NSTISSAM TEMPEST/1-92, NSTISSI No. 7000

and UFC 4-010-05 as applicable to the work.

The shielding expert instructs the trades on proper material installation and assembly methods prior to construction of sample assemblies. Following training, contractor quality assurance and quality control personnel are capable of monitoring electromagnetic barrier construction, performing daily testing and compiling resultant documentation. Use technical consultants to manage ongoing work, plan for future work and repair deficiencies in work completed. Discuss electromagnetic barrier construction protocols at weekly safety and tool box meetings.

1.5.3 Third Party Testing and Laboratory Consultant

Provide an independent, third party testing and laboratory consultant for sample assembly testing, work progress inspections, electromagnetic barrier testing, STC testing and grounding testing. The Accrediting Officer performs a final series of tests to determine work acceptance for accreditation purposes.

1.5.4 Penetration Sample Assemblies

Furnish electromagnetic barrier penetration sample assemblies utilizing materials, accessories and methods required for the work. Assembly sizes are 8 feet, 0 inch leg by 8 feet, 0 inch leg by 8 feet, 0 inches high and located as directed. Incorporate examples of a secure door, Faraday shielded man bar and similar openings encountered. Incorporate examples of a duct, cold water, sprinkler, electrical, data and similar penetrations encountered. Ground each penetration. Test for radio frequency attenuation. Remove defective installations, replace and retest until acceptable results are achieved.

Demonstrate execution of electromagnetic barrier penetration work. Modify techniques, methods and procedures to provide superior workmanship. Furnish sample assembly TESTING REPORTING to the Accrediting Officer and Architect. Do not proceed with permanent electromagnetic barrier constructions until sample assemblies are tested and approved by the Accrediting Officer.

1.5.5 STC Sample Assemblies

Furnish STC wall and ceiling constructions sample assemblies utilizing materials, accessories and methods required for the work. Assembly sizes are 8 feet, 0 inch leg by 8 feet, 0 inch leg by 8 feet, 0 inches high and located as directed. Incorporate examples of an acoustical door and similar openings encountered. Incorporate examples of a duct, cold water, sprinkler, electrical, data and similar penetrations encountered. Ground each penetration. Test for sound attenuation. Remove defective installations, replace and retest until acceptable results are achieved.

Demonstrate execution of STC work. Modify techniques, methods and procedures to provide superior workmanship. Furnish sample assembly TESTING REPORTING to the Accrediting Officer and Architect. Do not proceed with permanent STC constructions until sample assemblies are tested and approved by the Accrediting Officer.

1.5.6 Construction Conference

Schedule a Electromagnetic Barrier and STC Construction Conference to review substrates and material assemblies.

Coordinate with the Accrediting Officer, who is to attend the Installation Conference, and outline procedures for interim and final inspections for compliance.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Floor and Wall Surfaces

2.1.1.1 Perforated Foil

Radiant barrier foil is a micro perforated, vapor permeable, heavy duty flexible sheet comprised of a single layer of woven polyethylene bonded to and sandwiched between two layers of highly reflective aluminum surfacing.

Radiant Barrier Foil	**Performance**	**Standard**
Bleeding and delamination	None	ASTM C1224
Pliability	No cracking	ASTM C1224
Fungi resistance	Passes	ASTM C1338
Emissivity	0.03	ASTM C1371
Tensile strength, MD	14.93 pounds	ASTM D2261
Tear resistance, XMD	15.13 pounds	ASTM D2261
Corrosiveness	Passes	ASTM D3310
Interior finish classification	Class A	ASTM E84
Flame spread rating	0	ASTM E84
Smoke developed rating	Less than 20	ASTM E84
Water vapor permeability	2.69 perms	ASTM E96/E96M
Shielding, 100 Mhz to 10 Ghz	67 dB	IEEE 299
Reflectivity	0.97	

2.1.1.2 Conductive Foil Tape

Conductive foil tape has a 3 mil thickness with minimum 3 inch width, composed of a 2 mil flat aluminum backing coated on one side with a non corrosive, electrically conductive, pressure sensitive acrylic adhesive with removable liner. Tape allows for easy handling, die cutting and soldering. Common uses include EMI and RFIn shielding applications in the electronics industry and for static charge draining, seaming shielded rooms, cable wrapping and surface contact to non solderable materials. Adhesive requires no moisture, solvents, heat or other manner of preparation to affect application. Foil tape meets the flame retardant requirements of UL 510UL 510A. Shielding effectiveness is 69 dB within the range of 300 kHz to 2.5 GHz when tested in accordance with ASTM D4935. Adhesion strength is 25 ounces per inch and breaking strength of 14 pounds per inch when tested in accordance with ASTM D1000. Electrical resistance is 0.010 Ohms per square inch when tested in accordance with MIL-STD 202, Method 307..

2.1.1.3 Foil Backing Adhesive

Foil backing adhesive is a high tack, high coverage, fast drying, synthetic elastomer multipurpose spray adhesive with 25% solids by weight.

2.1.2 Grounding Wire

Grounding wire is No. 10 AWG solid copper wire. Grounding clamps create a

mechanical bond through toothed connectors that positively engage the receiving surface. Welds are also acceptable. Pressure type clamps are not permitted.

2.1.3 Wall Openings

2.1.3.1 Shielded Door and Frame

Electromagnetic barrier shielded door and frame assemblies attenuate at least 60 dB of electric field, microwave and planewave energy from 1 kHz through 18 GHz conforming with IEEE 299, NSA 65-6 and MIL-STD-285. Assemblies also achieve sound attenuation of at least 50 STC in compliance with ASTM E90, ASTM E1408, ASTM E413, JUIAF, JAFAN, DCID 6/9 and ICPM 2006-700-7. Flush doors ae 3 inches in thickness and have provisions for RF gasket contact. Exterior doors have 0.063 inch, 16 gauge stainless steel faces. Interior doors have 0.053 to 0.060 inch, 16 gauge, galvanized steel conforming to ASTM A653/A653M, Class G60, 0.60 ounces per SF with a continuous contact flange to interface with wall and floor shielding materials. Frames are 0.067 to 0.075 inch, 14 gauge galvanized steel conforming to ASTM A653/A653M, Class G60, 0.60 ounces per SF with a continuous contact flange to interface with wall and floor shielding materials. Frame insulation is No. 8 density mineral wool. Custom fabricate frame profiles and anchors for wall thicknesses encountered. Full profile, mitered frame face joints are reinforced, welded, dressed flush and ground smooth for seamless appearances. Doors and frames are reinforced in accordance with HMMA standards, have fire ratings up to 1.5 hours and a 20 minute smoke rating. Threshold is a 0.25 inch stainless steel plate. Factory mount a formed, stainless steel retainer that is conductive with the frame and incorporating a monel wire mesh foam core gasket enhanced with flexible, non woven metallized fabric. Frames include factory mounted radial bearing cam lift hinges, latches, locksets, panic devices, security and power operating hardware as scheduled. Other hardware items not identified are furnished and installed by others. Doors and frames are shop primed except for designated RF contact points.

Shielded door finish is Primed Steel; Wood Veneer, White Oak species matching the veneer in Section 08 14 00, WOOD DOORS.

Mortise locks comply with ANSI/BHMA A156.13, Series 1000, Grade 1 and are UL listed. Levers are solid castings with no plastic inserts and about 4.75 inches in length. Latchbolts fully retract with no more than 40? rotation. Lock cases are 6.0625 inches by 3.875 inches by 1.25 inches and fabricated from 0.090 inch, 13 gauge heavy duty wrought steel. Backsets are 2.75 inches. Armored stainless steel fronts, 8 inches by 1.25 inches, comply with ANSI A115.1 and adjust from flat to an 0.125 inch bevel in 2 inches. Deadbolts are stainless steel and have a 0.5625 inch by 1.25 inch cross section with a minimum 1 inch throw. Guardbolts are non handed, stainless steel. Stainless steel latchbolts are 1.625 inches by 0.75 inches with anti friction throw and field reversible installation. Stop works are a rocker type, stainless steel with handed cases and trims. Hubs are forged of sintered copper infiltrated iron and house springs are high carbon steel. Lever, escutcheon and turn trims are fabricated from forged brass. Sectional trim utilizes concealed screws. Cylinders have 1.25 inch standard escutcheons. Rose and escutcheon designs are contemporary and smooth. Strikes are an ANSI lip type measuring 4.875 inches by 1.25 inches.

Provide cylinders with small format interchangeable cores.

Cam lift hinges comply with ASTM F476. Electrified cam lift hinges are similar.

Spring seal is bronze.

Door bottom is a heavy duty, surface mounted, automatic type complying with BHMA R3B3341.

Perimeter gaskets for door and frame fabrications are conductive.

2.1.4 Penetrations

2.1.4.1 Galvanized Sheet Metal

Sheet metal is ASTM A653/A653M, Class G185, 1.85 ounces per SF, Grade 33, hot dipped galvanized, 0.027 inches, 23 gauge thickness.

2.1.4.2 Non Conductive Transition

Non conductive transition material between ducts and louvers is resistant to UV degradation, weathering, oxidation and permanent deformation.

2.1.4.3 Faraday Bars

Faraday bars are steel grid fabrications with openings less than 96 square inches. Louver bird screens are 0.625 inch by 0.040 inch expanded and flattened aluminum complying with ASTM B221. Provide an insect screen, 18 by 16 mesh of 0.011 inch aluminum, in addition to the bird screen.

2.1.5 Accessories

2.1.5.1 Electro Conductive Coatings

Electro conductive interior and exterior coatings are a pure acrylic dispersion paint with 54% to 58% solids by volume, 0.1 to 0.2 grams VOC per liter and a semi gloss finish. The coating protects against high frequency electromagnetic fields and low frequency electric fields. Screening attenuation at 1 GHz is 37 dB for the first coat and 44 dB for the second when tested in accordance with ASTM D4935 and IEEE 299. Do not thin. Clean with water. Furnish a compatible primer.

2.1.5.2 Miscellaneous Items

Furnish fasteners, accessories and options as recommended by the manufacturer for the specific applications and substrates encountered within the work.

2.1.6 Walls, Openings and Hardware

Openings have an STC indicated in the hardware sets that identifies a laboratory tested STC doors and laboratory tested STC hardware installed in laboratory tested STC wall types. Field testing of wall types must achieve an FSTC acoustical performance as measured by ASTM E336 and ASTM E413.

Electromagnetic Shielded Opening	HWS STC	Door STC	Hardware STC	Wall STC	Wall FSTC
Single leaf	55	50	53	55	50

PART 3 EXECUTION

3.1 CONTRACT COORDINATION

The hardware trade coordinates doors, frames and hinge positions with gasketing to enable door closing without gasket displacement or dislodgment. Maintain a continuous mechanical seal at door perimeters. Coordinate gasket insert thicknesses with threshold, automatic door bottom and sweep extrusions. Maintain electromagnetic barrier continuity and STC performance.

The electrical trade locates jambs, penetrations and similar applications requiring protection in the accreditation barrier, and provides conduit penetrations through concrete slabs, adjacent to walls and within hollow metal door jambs. Install grounding wires that are connected to grounding loops. Do not ground to building steel framing. The concrete trade places concrete and ensures grounds remain accessible for continued installation. The General Contractor protects exposed ends of grounds and coordinates the electrical, framing and masonry trades to complete grounding distribution and testing.

3.2 INSTALLATION

3.2.1 Work Plan

Summarize electromagnetic barrier and STC procedures and preparations for conditions encountered in a WORK PLAN.

3.2.2 Attentuation Requirements

Provide electromagnetic barrier protection to prevent generated electromagnetic and radio frequency interference from penetrating inside secure spaces or emitting outside secure spaces. Achieve radio frequency attenuation through a combination of materials and standoff that is equal to or greater than 100 meters of free space over the frequency range of 30 MHz to 6 GHz.

Install electromagnetic protection to eliminate corrosive and electrolytic action between dissimilar materials, and between metals and cementitious materials.

3.2.3 Floor and Wall Surfaces

Sandwich radiant barrier foil between concrete slabs and finish flooring. Install radiant barrier foil on accreditation barrier walls.

Seal and secure accreditation barrier penetrations with radiant barrier foil.

Apply foil backing adhesive to substrates. Unroll radiant barrier foil into the backing adhesive without buckles or voids. Smooth foil to substrates and eliminate air bubbles with a stiff bristled brush or a flexible broad knife. Remove surface contaminants and tape foil perimeters and seams. Smoothly apply tape without buckles or voids, and make full contact with substrates. Apply firm pressure to the center of tapes, and transfer to edges to ensure sealing. Transition foil from walls to metal decking. Extend foil at least 8 inches over decking, smoothly conform to fluting profiles and tape seams and edges.

3.2.4 Wall Openings

Connect door jambs that fall within the accreditation barrier to the building grounding loop. Locate jambs, provide conduit penetrations through concrete slabs and remove coatings from frame contact surfaces to maintain bonding continuity. Provide two grounds for single leaf doors and four grounds for double leaf doors. Mechanically bond grounding wires to jambs. Mechanically bond thresholds to adjoining jambs. Alternatively, provide one ground for single leaf thresholds and two grounds spaced no closer than 1 foot, 6 inches for double leaf thresholds. Terminate jamb gaskets at threshold surfaces. Tightly fit doors to frames. Remove coatings from door and frame gaskets to maintain bonding continuity. Adjust door closers to actively bring gasketing in contact with both the door and the frame, maintaining electromagnetic barrier continuity. Daylight must not penetrate from one side of the installation to the other along the four edges of door perimeters.

3.2.5 Penetrations

Provide grounding points where electromagnetic barriers are penetrated. Typical penetrations requiring grounding include sprinkler piping, water piping, ductwork and conduit. Consult the shielding expert for treatment of chiller line penetrations. Grounds are less than 3 feet, 0 inches in length, and of the shortest lengths possible. Acceptable grounding planes include steel columns, beams, purlins, girts and metal decks. Do not share electromagnetic barrier grounding planes with information technology grounding planes. Bond penetrations with a minimum of two ground wires. Space grounds such that they are no closer than 1 foot, 6 inches or more distant than 3 feet, 0 inches. Consult the shielding expert for ground distances exceeding 3 feet, 0 inches, and for large diameter penetrations requiring more than two grounds. Dielectrically decouple penetrations and dual ground on both the controlled and uncontrolled side of the envelope plane. Extend non metallic material the full thickness of the plane penetrated. Visible penetration terminations on the uncontrolled side of the envelope, but within the secure fence line, are not required to have two external grounds.

Install Faraday bar fabrications within openings greater than 96 square inches. Typical penetrations requiring fabrications include duct penetrations, louvers and storm drainage piping. Mechanically bond each cross member of bar fabrications that fall within the accreditation barrier. Center fabrications horizontally and vertically within openings. Bond fabrications to the building grounding loop with a minimum of two ground wires. Space grounds along fabrication perimeters such that no two are closer than 1 foot, 6 inches or more distant than 3 feet, 0 inches. For louver installations, sandwich bird and insect screens between the inside of louvers and Faraday bars. Mechanically bond bird and insect screens to Faraday bar perimeters. Provide an inspection port adjacent to Faraday bar fabrications on the controlled side of ductwork.

3.2.6 Accessories

3.2.6.1 Electro Conductive Coatings

Use electro conductive paint for applications that are difficult to access, or applications where attenuation performance is superior to mechanical bonding.

3.2.7 Testing

Test grounding clamps, welds and mechanical bonds prior to concealment. Test grounding points with a multimeter. Achieve a resistance of 20 milliohms or less between grounding connections and the grounded structure. Correct deficiencies, reconnect and retest until the minimum reading is achieved.

Tie electromagnetic barrier elements to the building grounding loop. Test the grounding loop with a 500 Volt megger. Achieve a loop resistance of 3 Ohms or less, and preferably a maximum of 1 Ohm. Correct deficiencies and retest until the minimum reading is achieved.

Provide TESTING REPORTING for recordkeeping.

3.3 HARDWARE SCHEDULE

AC = Access Control; B2BAC = Back to Back Access Control; BB = Ball Bearing; DPDT = Double Pole, Double Throw; EDF = Exit Device Function; Elev = Elevation; EMI = Electro Magnetic Interference; ETW = Electric Through Wire; FMC = Full Metal Cover; GFGI = Government Furnished, Government Installed; HD = Heavy Duty; HT = Hospital Tip; I/S = Inside; LHR = Left Hand Reverse; MIL = Mill Finished Aluminum; NRP = Non Removable Pin; O/S = Outside; RHR = Right Hand Reverse; RFIn = Radio Frequency Interference; SFIC = Small Format Interchangeable Core; STC = Sound Transmission Class; TPE = Thermoplastic Elastomer

3.3.1 HARDWARE SETS

3.3.1.1 A1, BATALLION HEADQUARTERS ELECTROMAGNETIC BARRIERS HARDWARE SCHEDULE

Secure Exterior RFIn and STC Openings

Door No. 217A
HWS-A1.49 Alarm Egress, RFIn, STC 55

	2 each 5 x 5 Cam Lift Hinge, A5141	630
	1 each ETW 5 x 5 Cam Lift Hinge, A5141	630
Section 08 71 00	1 each Power Transfer	689
Section 08 71 00	1 each FMC Closer, C02021 flat form arm for cam hinges, jamb drop with backplate, push side mount, more than STC 45	630
	1 each Alarm Exit Device, EDF01, Type 4 B x DA x LM, direct hardwired, latch monitoring	630
Section 08 71 00	1 each Mortise Cylinder Housing, F25, E09251	630
Section 08 71 00	1 each 7 Pin SFIC, F24, E09241 control and silence alarm by key	630
Section 08 71 00	1 each 40" Drip Ledge	MIL
	1 each Head and Jamb Gasket, R3L154, magnetic and neoprene seal	Clear Anodized
	1 each 3070 1.125 inch Spring Seal, R1K155	612
	1 each 36" Automatic Door Clear Anodized Bottom, R3B3341	
	1 each 36" Threshold, 0.25 inch plate	630
Section 08 71 00	1 each 36" Bottom Sweep	MIL
Section 08 71 00	1 each Floor Stop, L02131	626
GFGI	1 each DPDT Balanced Magnetic Switch	MIL

Note: Shielded door and frame assembly is an EMI and RFIn door sealing system that requires grounding continuity of hardware items and grounding of hollow metal frames

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway, pull strings and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 218

Secure Non Rated RFIn and STC Openings

Door No. 205B
HWS-A1.50 B2BAC Opn Str Mantrap O/S RFIn, STC 55

	2 each	5 x 5 Cam Lift Hinge, A5141	630
	1 each	ETW 5 x 5 Cam Lift Hinge, A5141	630
Section 08 71 00	1 each	Power Transfer	689
Section 08 71 00	1 each	FMC Closer, C02021 flat form arm for cam hinges, jamb drop with backplate, push side mount, more than STC 45	630
Section 08 71 00	1 each	Type II High Security Lockset with AC Key Bypass, FF-L-2890C	630 / Black
Section 08 71 00	1 each	Rim Cylinder Housing, F26	630
Section 08 71 00	1 each	7 Pin SFIC, F24, E09241	630
Section 08 71 00	1 each	Combination Electromechanical Lock, Style 1, FF-L-2740B	Black
	1 each	3 inch Door Thickness, Lever Active Dummy with lockcase no cylinder / no SFIC	630
	1 each	3070 Head and Jamb Gasket, R3L154, magnetic and neoprene seal	Clear Anodized
	1 each	3070 1.125 inch Spring Seal, R1K155	612
	1 each	36" Automatic Door Bottom, R3B3341	Clear Anodized
	1 each	36" Threshold, 0.25 inch plate	630
Section 08 71 00	1 each	Wall Stop, L02251 or Floor Stop, L02161	626
GFGI	1 each	DPDT Balanced Magnetic Switch	MIL
GFGI	3 each	Card Reader, Wall Mounted	Black
GFGI	1 each	IDS Keypad, Wall Mounted	

Note: Shielded door and frame assembly is an EMI and RFIn door sealing system that requires grounding continuity of hardware items and grounding of hollow metal frames

Note: Furnish electric metallic tubing raceway, cabling, equipment and programming to support connected devices and operate access control components

Note: Furnish electric metallic tubing raceway, pull strings and blank stainless steel coverplates to receive Government furnished and installed devices

Note: Access control equipment is located in Comm 218

3.4 ELECTROMAGNETIC BARRIERS COATINGS SCHEDULE

1. Multipurpose Electro Conductive Coating:

1st Coat:	2 mil DFT	Primer
2nd Coat:	6 mil DFT	Waterborne Acrylic
3rd Coat:	6 mil DFT	Waterborne Acrylic
4th Coat:	2 mil DFT	Plastic Bonded, Water Based Emulsion

-- End of Section --

VOLUME 2 of 2
Division 1 - 33

eProjects Work Order
Number: 1701820
Appropriation:

P-1550 SOF MARINE RAIDER
BATTALION / COMPANY / TEAM FACILITIES

At the

MARINE CORPS BASE CAMP LEJEUNE, NC

DESIGNED BY:

NAVFAC MID-ATLANTIC
9742 MARYLAND AVENUE
NORFOLK, VIRGINIA 23511-3095

SPECIFICATION PREPARED BY:

Architectural: MBF Architects
Civil: Stantec
Structural: Kaydos-Daniels Engineering
Interior Design: Within Interior Design
Mechanical/Plumbing/Electrical: Crenshaw Consulting Eng.
Fire Prot.: Jensen Hughes
Audio Video: Thorburn

Specification: Darden J. Eure, III, MBF Architects

Date: 8 May 2026

SPECIFICATION APPROVED BY:

For Commander, NAVFAC MID-ATLANTIC:
Date:

This page is intentionally left blank.

VOLUME 2 - TABLE OF CONTENTS
Division 21 - 33

DIVISION 21 - FIRE SUPPRESSION

21 13 13	08/20	WET PIPE SPRINKLER SYSTEMS, FIRE PROTECTION
21 13 16	08/20	DRY PIPE SPRINKLER SYSTEMS, FIRE PROTECTION
21 30 00	04/08, CHG 1: 08/13	FIRE PUMPS

DIVISION 22 - PLUMBING

22 00 00	05/24, CHG 1: 11/24	PLUMBING, GENERAL PURPOSE

DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

23 03 00.00 20	08/24 MCBCL	BASIC MECHANICAL MATERIALS AND METHODS
23 05 48.19	05/18, CHG 2: 08/20	BRACING FOR HVAC
23 05 93	05/25	TESTING, ADJUSTING, AND BALANCING FOR HVAC
23 07 00	08/24	THERMAL INSULATION FOR MECHANICAL SYSTEMS
23 08 00	05/23, CHG 1: 08/24	COMMISSIONING OF MECHANICAL AND PLUMBING SYSTEMS
23 09 00	02/25 MCBCL	INSTRUMENTATION AND CONTROL FOR HVAC
23 09 13	02/25 MCBCL	INSTRUMENTATION AND CONTROL DEVICES FOR HVAC
23 09 23.02	02/25 MCBCL	BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS
23 11 20	05/20	FACILITY GAS PIPING
23 21 13.00 20	04/06, CHG 2: 11/19	LOW TEMPERATURE WATER (LTW) HEATING SYSTEM
23 23 00	08/21	REFRIGERANT PIPING
23 25 00	05/21	CHEMICAL TREATMENT OF WATER FOR MECHANICAL SYSTEMS
23 30 00	02/25	HVAC AIR DISTRIBUTION
23 52 43.00 20	05/15, CHG 2: 08/18	LOW PRESSURE WATER HEATING BOILERS (UNDER 800,000 BTU/HR OUTPUT)
23 64 10	05/25	WATER CHILLERS, VAPOR COMPRESSION TYPE
23 64 26	08/09, CHG 5: 11/19	CHILLED WATER PIPING SYSTEMS
23 81 00	05/24	DECENTRALIZED UNITARY HVAC EQUIPMENT
23 82 00.00 20	02/16, CHG 1: 08/18	TERMINAL HEATING UNITS

DIVISION 25 - INTEGRATED AUTOMATION

25 05 11.00	11/17	CYBERSECURITY FOR FACILITY-RELATED CONTROL SYSTEMS - ISOLATED SYSTEMS

DIVISION 26 - ELECTRICAL

26 08 00	11/21	APPARATUS INSPECTION AND TESTING
26 12 19.10	05/19, CHG 1: 11/19	THREE-PHASE, LIQUID-FILLED PAD-MOUNTED TRANSFORMERS
26 13 00	05/21, CHG 1: 05/22	SF6/HIGH-FIREPOINT FLUIDS INSULATED PAD-MOUNTED SWITCHGEAR
26 20 00	08/19, CHG 3: 11/21	INTERIOR DISTRIBUTION SYSTEM
26 24 13	08/21	SWITCHBOARDS
26 27 14.00 20	02/21, CHG 1: 05/21	ELECTRICITY METERING

26 28 01.00 10	08/21	COORDINATED POWER SYSTEM PROTECTION
26 29 23	02/20, CHG 1: 05/21	ADJUSTABLE SPEED DRIVE (ASD) SYSTEMS UNDER 600 VOLTS
26 32 15.00	05/20	ENGINE-GENERATOR SET STATIONARY 15-2500 KW, WITH AUXILIARIES
26 36 23	05/20, CHG 1: 08/21	AUTOMATIC TRANSFER SWITCHES AND BY-PASS/ISOLATION SWITCH
26 41 00	11/13	LIGHTNING PROTECTION SYSTEM
26 51 00	05/20, CHG 2: 11/21	INTERIOR LIGHTING
26 56 00	08/21	EXTERIOR LIGHTING

DIVISION 27 - COMMUNICATIONS

27 10 00	01/24	BUILDING TELECOMMUNICATIONS CABLING SYSTEM (MCBCL)

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

28 31 76	08/20	INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE

DIVISION 31 - EARTHWORK

31 00 00	08/23	EARTHWORK
31 11 00	11/18	CLEARING AND GRUBBING
31 31 16.13	08/22	CHEMICAL TERMITE CONTROL

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 01 16.71	11/22	COLD MILLING ASPHALT PAVING
32 01 19.61	11/19	SEALING OF JOINTS IN RIGID PAVEMENT
32 11 23	05/22	AGGREGATE BASE COURSE
32 12 16.16	11/20	ROAD-MIX ASPHALT PAVING
32 13 13.06	05/20	PORTLAND CEMENT CONCRETE PAVEMENT FOR ROADS AND SITE FACILITIES
32 16 19	05/18	CONCRETE CURBS, GUTTERS AND SIDEWALKS
32 17 23	08/16, CHG 5: 11/18	PAVEMENT MARKINGS
32 17 23.16	11/24	ROAD AND PARKING LOT PAVEMENT MARKINGS
32 31 13	11/21	CHAIN LINK FENCES AND GATES
32 92 23	04/06, CHG 1: 08/21	SODDING
32 93 00	08/17, CHG 1: 08/21	EXTERIOR PLANTS

DIVISION 33 - UTILITIES

33 01 30.16	11/21	TV INSPECTION OF SEWER LINES
33 05 07.13	02/24	UTILITY DIRECTIONAL DRILLING
33 11 00	02/18, CHG 1: 02/22	WATER UTILITY DISTRIBUTION PIPING
33 30 00	05/18	SANITARY SEWERAGE
33 31 23.00 10	08/18	SANITARY SEWER FORCE MAIN PIPING
33 32 16	11/19	PACKAGED UTILITY WASTEWATER PUMPING STATIONS
33 40 00	11/21	STORMWATER UTILITIES
33 61 14	02/10	EXTERIOR BURIED PREINSULATED WATER PIPING
33 71 02	08/21	UNDERGROUND ELECTRICAL DISTRIBUTION
33 82 00	08/22	TELECOMMUNICATIONS OUTSIDE PLANT (OSP)

SECTION 21 13 13

WET PIPE SPRINKLER SYSTEMS, FIRE PROTECTION
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.1	(2020) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250
ASME B16.3	(2021) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.4	(2021) Gray Iron Threaded Fittings; Classes 125 and 250
ASME B16.21	(2021) Nonmetallic Flat Gaskets for Pipe Flanges

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

ASSE 1013	(2021) Performance Requirements for Reduced Pressure Principle Backflow Prevention Assemblies
ASSE 1015	(2021) Performance Requirements for Double Check Backflow Prevention Assemblies

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C104/A21.4	(2022) Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water
AWWA C110/A21.10	(2021) Ductile-Iron and Gray-Iron Fittings
AWWA C111/A21.11	(2017) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C203	(2025) Coal-Tar Protective Coatings and Linings for Steel Water Pipe and Fittings
AWWA M14	(2015) Manual: Recommended Practice for Backflow Prevention and Cross-Connection Control

ASTM INTERNATIONAL (ASTM)

ASTM A47/A47M	(1999; R 2022; E 2022) Standard Specification for Ferritic Malleable Iron Castings

ASTM A53/A53M (2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

ASTM A135/A135M (2021) Standard Specification for Electric-Resistance-Welded Steel Pipe

ASTM A153/A153M (2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware

ASTM A183 (2014; R 2020) Standard Specification for Carbon Steel Track Bolts and Nuts

ASTM A536 (1984; R 2019; E 2019) Standard Specification for Ductile Iron Castings

FM GLOBAL (FM)

FM APP GUIDE (updated on-line) Approval Guide https://www.approvalguide.com/

INTELLIGENCE COMMUNITY STANDARD (ICS)

ICS 705-1 (2010) Physical and Technical Security Standard for Sensitive Compartmented Information Facilities

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-71 (2018) Gray Iron Swing Check Valves, Flanged and Threaded Ends

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 13 (2022; ERTA 3 2022) Standard for the Installation of Sprinkler Systems

NFPA 24 (2022) Standard for the Installation of Private Fire Service Mains and Their Appurtenances

NFPA 291 (2022) Recommended Practice for Fire Flow Testing and Marking of Hydrants

NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES (NICET)

NICET 1014-7 (2012) Program Detail Manual for Certification in the Field of Fire Protection Engineering Technology (Field Code 003) Subfield of Automatic Sprinkler System Layout

UNDERWRITERS LABORATORIES (UL)

UL 199 (2020) UL Standard for Safety Automatic

	Sprinklers for Fire-Protection Service
UL 312	(2022) UL Standard for Safety Check Valves for Fire-Protection Service
UL 405	(2013; Bul. 2020) UL Standard for Safety Fire Department Connection Devices
UL 668	(2004; Reprint Oct 2021) UL Standard for Safety Hose Valves for Fire-Protection Service
UL Fire Prot Dir	(2012) Fire Protection Equipment Directory

1.2 SYSTEM DESCRIPTION

Provide wet pipe sprinkler system(s) in all areas of the building. Except as modified herein, the system must meet the requirements of NFPA 13. Pipe sizes which are not indicated on the Contract drawings must be determined by hydraulic calculations.

1.2.1 Hydraulic Design

1.2.1.1 Basis for Calculations

A waterflow test was performed on 25 September 2025 and resulted in a static pressure of 76 psi with a residual pressure of 49 psi while flowing 1,060 gpm. Perform a fire hydrant flow test prior to shop drawing submittal in accordance with NFPA 291. Results must include hydrant elevations relative to the building and hydrant number/identifiers for the tested hydrants, including which were flowed, which had a gauge. This information must be presented in a tabular form if multiple hydrants were flowed. The results must be included with the hydraulic calculations. Hydraulic calculations must be based on the flow test required to be performed in this paragraph, verified by the NAVFAC Midlant Fire Protection Engineer, and approved by Contracting Officer. Hydraulic calculations must be based upon the Hazen-Williams formula with a "C" value noted in NFPA 13 for piping. Hydraulic calculations must be based on operation of the fire pump provided in Section 21 30 00 FIRE PUMPS. The minimum residual pressure in a service lateral (lead-in) at the design flow rate must be 20 psi at the suction side of the fire pump.

1.2.1.2 Hydraulic Calculations

a. Water supply curves and system requirements must be plotted on semi-logarithmic graph (N^1.85) paper so as to present a summary of the complete hydraulic calculation.

b. Provide a summary sheet listing sprinklers in the design area and their respective hydraulic reference points, elevations, minimum discharge pressures and minimum flows. Elevations of hydraulic reference points (nodes) must be indicated.

c. Documentation must identify each pipe individually and the nodes connected thereto. Indicate the diameter, length, flow, velocity, friction loss, number and type fittings, total friction loss in the pipe, equivalent pipe length and Hazen-Williams coefficient for each pipe.

d. Where the sprinkler system is supplied by interconnected risers, the sprinkler system must be hydraulically calculated using the hydraulically most demanding single riser. The calculations must not assume the simultaneous use of more than one riser.

e. All calculations must include the backflow preventer manufacturer's stated friction loss at the design flow or 12 psi for reduced pressure backflow preventer, whichever is greater.

f. All calculations must be performed back to the actual location of the flow test, taking into account the direction of flow in the service main at the test location.

g. For gridded systems, calculations must show peaking of demand area friction loss to verify that the hydraulically most demanding area is being used. A flow diagram indicating the quantity and direction of flows must be included.

1.2.1.3 Design Criteria

Hydraulically design the system to discharge a minimum density as indicated on the drawings. Hydraulic calculations must be in accordance with the Area/Density Method of NFPA 13. Add an allowance for exterior hose streams as indicated on the drawings to the sprinkler system demand at the fire hydrant shown on the drawings closest to the point where the water service enters the building.

1.2.2 Sprinkler Coverage

Sprinklers must be uniformly spaced on branch lines. Provide coverage throughout 100 percent of the building. This includes, but is not limited to, telephone rooms, electrical equipment rooms (regardless of the fire resistance rating of the enclosure), boiler rooms, switchgear rooms, transformer rooms, attached electrical vaults and other electrical and mechanical spaces. Coverage per sprinkler must be in accordance with NFPA 13. Provide sprinklers below all obstructions in accordance with NFPA 13.

1.2.3 Qualified Fire Protection Engineer (QFPE)

The QFPE in this section is the same as FPQC in Section 01 45 00. Wherever "Qualified Fire Protection Engineer (QFPE)" or "QFPE" appears in this section substitute with "Fire Protection Quality Control Specialist (FPQC)". Services of the QFPE must include:

a. Reviewing SD-02, SD-03, and SD-05 submittal packages for completeness and compliance with the provisions of this specification. Working (shop) drawings and calculations must be prepared by, or prepared under the immediate supervision of, the QFPE. The QFPE must affix their professional engineering stamp with signature to the shop drawings, calculations, and material data sheets, indicating approval prior to submitting the shop drawings to the DFPE.

b. Provide a letter documenting that the SD-02, SD-03, and SD-05 submittal package has been reviewed and noting all outstanding comments.

c. Performing in-progress construction surveillance prior to installation of ceilings (rough-in inspection).

d. Witnessing pre-Government and final Government functional performance testing and performing a final installation review.

e. Signing applicable certificates under SD-07.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Partial submittals and submittals not fully complying with NFPA 13 and this specification section must be returned disapproved without review. SD-02, SD-03 and SD-05 must be submitted simultaneously.

Shop drawings (SD-02), product data (SD-03) and calculations (SD-05) must be prepared by the designer and combined and submitted as one complete package. The QFPE must review the SD-02/SD-03/SD-05 submittal package for completeness and compliance with the Contract provisions prior to submission to the Government. The QFPE must provide a Letter of Confirmation that they have reviewed the submittal package for compliance with the contract provisions. This letter must include their professional engineer stamp and signature. Partial submittals and submittals not reviewed by the QFPE must be returned disapproved without review.

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualified Fire Protection Engineer (QFPE); G

Sprinkler System Designer; G

Sprinkler System Installer; G

SD-02 Shop Drawings

Shop Drawing; G

SD-03 Product Data

Pipe; G

Fittings; G

Valves, including gate, check, butterfly, and globe; G

Relief Valves; G

Sprinklers ; G

Pipe Hangers and Supports ; G

Sprinkler Alarm Switch; G

Valve Supervisory (Tamper) Switch; G

Fire Department Connection; G

Backflow Prevention Assembly; G

Air Vent; G

Hose Valve; G

Nameplates; G

SD-05 Design Data

Hydraulic Calculations; G

SD-06 Test Reports

Test Procedures; G

SD-07 Certificates

Verification of Compliant Installation; G

Request for Government Final Test; G

SD-10 Operation and Maintenance Data

Operating and Maintenance (O&M) Instructions; G

Spare Parts Data; G

SD-11 Closeout Submittals

As-built drawings

1.4 QUALITY ASSURANCE

1.4.1 Preconstruction Submittals

Within 36 days of contract award but no less than 14 days prior to commencing work on site, the prime Contractor must submit the following for review and approval. SD-02, SD-03 and SD-05 submittals received prior to the review and approval of the qualifications will be returned Disapproved Without Review.

1.4.1.1 Shop Drawing

One copy of the shop drawings, no later than 28 days prior to the start of system installation. Working drawings conforming to the requirements prescribed in NFPA 13 and must be no smaller than the Contract Drawings. Each set of drawings must include the following:

a. A descriptive index with drawings listed in sequence by number. A legend sheet identifying device symbols, nomenclature, and conventions used in the package.

b. Floor plans drawn to a scale not less than 1/8-inch equals 1-foot clearly showing locations of devices, equipment, risers, and other details required to clearly describe the proposed arrangement.

c. Actual center-to-center dimensions between sprinklers on branch lines and between branch lines; from end sprinklers to adjacent walls; from

walls to branch lines; from sprinkler feed mains, cross mains and branch lines to finished floor and roof or ceiling. A detail must show the dimension from the sprinkler and sprinkler deflector to the ceiling in finished areas.

d. Longitudinal and transverse building sections showing typical branch line and cross main pipe routing, elevation of each typical sprinkler above finished floor and elevation of "cloud" or false ceilings in relation to the building ceilings.

e. Plan and elevation views which establish that the equipment will fit the allotted spaces with clearance for installation and maintenance.

f. Riser layout drawings drawn to a scale of not less than 1/2-inch equals 1-foot to show details of each system component, clearances between each other and from other equipment and construction in the room.

g. Details of each type of riser assembly, pipe hanger, and restraint of underground water main at point-of-entry into the building, and electrical devices and interconnecting wiring. The dimension from the edge of vertical piping to the nearest adjacent wall(s) must be indicated on the drawings when vertical piping is located in stairs or other portions of the means of egress.

h. Details of each type of pipe hanger and related components.

i. Include fire pump curve with shop drawings and hydraulic calculations.

1.4.1.2 Product Data

One copy of annotated catalog data to show the specific model, type, and size of each item. Catalog cuts must also indicate the NRTL listing. The data must be highlighted to show model, size, options, and other pertinent information, that are intended for consideration. Data must be adequate to demonstrate compliance with all contract requirements. Product data for all equipment must be combined into a single submittal.

1.4.1.3 Hydraulic Calculations

Calculations must be as outlined in NFPA 13 except that calculations must be performed by computer using software intended specifically for fire protection system design using the design data shown on the drawings. Include fire pump curve with submittal.

1.4.1.4 Operating and Maintenance (O&M) Instructions

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA as supplemented and modified by this specification section.

Provide six manuals and one pdf version on electronic media. The manuals must include the manufacturer's name, model number, parts list, list of parts and tools that should be kept in stock by the owner for routine maintenance, troubleshooting guide, and recommended service organization (including address and telephone number) for each item of equipment.

Submit spare parts data for each different item of material and equipment specified. The data must include a complete list of parts and supplies, and a list of parts recommended by the manufacturer to be replaced after

1-year and 3 years of service. Include a list of special tools and test equipment required for maintenance and testing of the products supplied.

1.4.2 Qualifications

1.4.2.1 Sprinkler System Designer

The sprinkler system designer must be certified as a Level III Technician by National Institute for Certification in Engineering Technologies (NICET) in the Water-Based Systems Layout subfield of Fire Protection Engineering Technology in accordance with NICET 1014-7.

1.4.2.2 Sprinkler System Installer

The sprinkler system installer must be regularly engaged in the installation of the type and complexity of system specified in the contract documents, and must have served in a similar capacity for at least three systems that have performed in the manner intended for a period of not less than 6 months.

1.4.3 Regulatory Requirements

Equipment and material must be listed or approved. Listed or approved, as used in this Section, means listed, labeled or approved by a Nationally Recognized Testing Laboratory (NRTL) such as UL Fire Prot Dir or FM APP GUIDE. The omission of these terms under the description of an item or equipment described must not be construed as waiving this requirement. All listings or approvals by testing laboratories must be from an existing ANSI or UL published standard. The recommended practices stated in the manufacturer's literature or documentation are mandatory requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

Protect all equipment delivered and placed in storage from the weather, excessive humidity and temperature variations, dirt and dust, or other contaminants. All pipes must be either capped or plugged until installed.

1.6 EXTRA MATERIALS

Spare sprinklers and wrench(es) must be provided as spare parts in accordance with NFPA 13.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

2.1.1 Standard Products

Provide materials, equipment, and devices listed for fire protection service when so required by NFPA 13 or this specification. Select material from one manufacturer, where possible, and not a combination of manufacturers, for a classification of material. Material and equipment must be standard products of a manufacturer regularly engaged in the manufacture of the products for at least 2 years prior to bid.

2.1.2 Nameplates

Major components of equipment must have the manufacturer's name, address,

type or style, model or serial number, catalog number, date of installation, installing Contractor's name and address, and the contract number provided on a new name plate permanently affixed to the item or equipment. Nameplates must be etched metal or plastic, permanently attached by screws to control units, panels or adjacent walls.

2.1.3 Identification and Marking

Pipe and fitting markings must include name or identifying symbol of manufacturer and nominal size. Pipe must be marked with ASTM designation. Valves and equipment markings must have name or identifying symbol of manufacturer, specific model number, nominal size, name of device, arrow indicating direction of flow, and position of installation (horizontal or vertical), except if valve can be installed in either position. Markings must be included on the body casting or on an etched or stamped metal nameplate permanently on the valve or cover plate.

2.1.4 Pressure Ratings

Valves, fittings, couplings, alarm switches, and similar devices must be rated for the maximum working pressures that can be experienced in the system, but in no case less than 175 psi.

2.2 UNDERGROUND PIPING COMPONENTS

2.2.1 Pipe

Pipe must comply with NFPA 24. Minimum pipe size is 6 inches. Piping more than 5 feet outside the building walls must comply with Section 33 11 00 WATER UTILITY DISTRIBUTION PIPING. A continuous section of welded stainless steel fire water service piping from a point outside the building perimeter to a flanged fitting at least 1-foot above the finished floor within the building is acceptable.

2.2.2 Fittings and Gaskets

Fittings must be ductile-iron conforming to AWWA C110/A21.10 with cement mortar lining conforming to AWWA C104/A21.4. Gaskets must be suitable in design and size for the pipe with which such gaskets are to be used. Gaskets for ductile-iron pipe joints must conform to AWWA C111/A21.11.

2.2.3 Buried Utility Warning and Identification Tape

Provide detectable aluminum foil plastic backed tape or detectable magnetic plastic tape manufactured specifically for warning and identification of buried piping. Tape must be detectable by an electronic detection instrument. Provide tape, 3 inches minimum width, color coded for the utility involved with warning and identification imprinted in bold block letters continuously and repeatedly over the entire tape length. Warning and identification must read "CAUTION BURIED WATER PIPING BELOW" or similar wording. Use permanent code and letter coloring unaffected by moisture and other substances contained in trench backfill material.

2.3 ABOVEGROUND PIPING COMPONENTS

2.3.1 Steel Piping Components

2.3.1.1 Steel Pipe

Except as modified herein, steel pipe must be black as permitted by NFPA 13 and conform to the applicable provisions of ASTM A53/A53M, ASTM A135/A135M or ASTM A153/A153M.

Steel pipe must be minimum Schedule 40 for sizes 2 inches and less; and minimum Schedule 10 for sizes larger than 2 inches. Steel piping with wall thickness less than Schedule 40 must not be threaded. Grooved pipe must be cut-grooved.

2.3.1.2 Fittings

Fittings must be welded, threaded, or grooved-end type. Threaded fittings must be cast-iron conforming to ASME B16.4, malleable-iron conforming to ASME B16.3 or ductile-iron conforming to ASTM A536. Plain-end fittings with mechanical couplings, fittings that use steel gripping devices to bite into the pipe, steel press fittings and field welded fittings are not permitted. Fittings, mechanical couplings, and rubber gaskets must be supplied by the same manufacturer. Threaded fittings must use Teflon tape or manufacturer's approved joint compound. Reducing couplings are not permitted except as allowed by NFPA 13.

2.3.1.3 Grooved Mechanical Joints and Fittings

Joints and fittings must be designed for not less than 175 psi service and the product of the same manufacturer. Field welded fittings must not be used. Fitting and coupling housing must be malleable-iron conforming to ASTM A47/A47M, Grade 32510; ductile-iron conforming to ASTM A536, Grade 65-45-12. Rubber gasketed grooved-end pipe and fittings with mechanical couplings are permitted in pipe sizes 2 inches and larger. Gasket must be the flush type that fills the entire cavity between the fitting and the pipe. Nuts and bolts must be heat-treated steel conforming to ASTM A183 and must be cadmium-plated or zinc-electroplated.

2.3.1.4 Flanges

Flanges must conform to NFPA 13 and ASME B16.1. Gaskets must be non-asbestos compressed material in accordance with ASME B16.21, 1/16-inch thick, and full face or self-centering flat ring type.

2.3.2 Flexible Sprinkler Hose

The use of flexible hose is not permitted.

2.3.3 Pipe Hangers and Supports

Provide galvanized pipe hangers and supports in accordance with NFPA 13.

2.3.4 Valves

Provide valves of types approved for fire service. Valves must open by counterclockwise rotation.

2.3.4.1 Control Valve

Manually operated sprinkler control/gate valve must be outside stem and yoke (OS&Y) type or butterfly type and must be listed.

2.3.4.2 Check Valves

Check valves must comply with UL 312. Check valves 4 inches and larger must be of the swing type, have a clear waterway and meet the requirements of MSS SP-71, for Type 3 or 4. Inspection plate must be provided on valves larger than 6 inches.

2.3.4.3 Hose Valve

Valve must comply with UL 668.

2.3.5 Riser Check Valves

Provide riser check valve, pressure gauges and main drain.

2.4 ALARM INITIATING AND SUPERVISORY DEVICES

2.4.1 Sprinkler Alarm Switch

Vane or pressure-type flow switch(es). Connection of switch must be by the fire alarm installer. Vane type alarm actuating devices must have mechanical diaphragm controlled retard device adjustable from 10 to 60 seconds and must instantly recycle.

2.4.2 Valve Supervisory (Tamper) Switch

Switch must be integral to the control valve or suitable for mounting to the type of control valve to be supervised open. The switch must be tamper resistant and contain SPDT (Form C) contacts arranged to transfer upon removal of the housing cover or closure of the valve of more than two rotations of the valve stem.

2.5 BACKFLOW PREVENTION ASSEMBLY

Reduced-pressure principle valve assembly backflow preventer complying with ASSE 1013, ASSE 1015 and AWWA M14. Each check valve must have a drain. Backflow prevention assemblies must have current "Certificate of Approval from the Foundation for Cross-Connection Control and Hydraulic Research, FCCCHR List" and be listed for fire protection use. Listing of the specific make, model, design, and size in the FCCCHR List is acceptable as the required documentation.

2.5.1 Backflow Preventer Test Connection

Test connection must consist of a series of listed hose valves with 2 1/2-inch National Standard male hose threads with cap and chain.

2.6 FIRE DEPARTMENT CONNECTION

Fire department connection must be projecting type with cast-brass body, matching escutcheon lettered "Auto Spkr" with a polished-brass finish. The connection must have individual self-closing clapper, cap with drip drain and chain. Female inlets must have 5-inch diameter Storz connection on a 30 degree galvanized elbow downward facing (non-swivel).. Comply

with UL 405.

2.7 SPRINKLERS

Sprinklers must comply with UL 199 and NFPA 13. Sprinklers with internal O-rings are not acceptable. Sprinklers in high heat areas including attic spaces or in close proximity to unit heaters must have temperature classification in accordance with NFPA 13. Extended coverage sprinklers are permitted for loading docks, residential occupancies and high-piled storage applications only.

2.7.1 Pendent Sprinkler

Pendent sprinkler must be recessed quick-response type with minimum nominal K-factor of 5.6. Pendent sprinklers must have a white polyester finish. Assembly must include an integral escutcheon.

2.7.2 Upright Sprinkler

Upright sprinkler must be brass quick-response type and have a minimum nominal K-factor of 5.6.

2.7.3 Corrosion-Resistant Sprinkler

Corrosion-resistant sprinkler must be the pendent type installed in locations as indicated. Corrosion-resistant coatings must be factory-applied by the sprinkler manufacturer.

2.8 ACCESSORIES

2.8.1 Sprinkler Cabinet

Provide spare sprinklers in accordance with NFPA 13 and must be placed in a suitable metal or plastic cabinet of sufficient size to accommodate all the spare sprinklers and wrenches in designated locations. Spare sprinklers must be representative of, and in proportion to, the number of each type and temperature rating of the sprinklers installed as required by NFPA 13. At least one wrench of each type required must be provided.

2.8.2 Pendent Sprinkler Escutcheon

Escutcheon must be one-piece metallic type with a depth of less than 3/4-inch and suitable for installation on pendent sprinklers. The escutcheon must have a factory finish that matches the pendent sprinkler.

2.8.3 Pipe Escutcheon

Provide split hinge metal plates for piping entering walls, floors, and ceilings in exposed spaces. Provide polished stainless steel plates or chromium-plated finish on copper alloy plates in finished spaces. Provide paint finish on metal plates in unfinished spaces.

2.8.4 Sprinkler Guard

Listed guard must be a steel wire cage designed to encase the sprinkler and protect it from mechanical damage. Guards must be provided on sprinklers located within 7 feet of the floor.

2.8.5 Relief Valve

Relief valves must be listed and installed at the riser in accordance with NFPA 13.

2.8.6 Air Vent

Air vents must be of the automatic type and piped to drain to the building exterior.

2.8.7 Identification Sign

Valve identification sign must be minimum 6 inches wide by 2 inches high with enamel baked finish on minimum 18 gage steel or 0.024-inch aluminum with red letters on a white background or white letters on red background. Wording of sign must include, but not be limited to "main drain", "auxiliary drain", "inspector's test", "alarm test", "alarm line", and similar wording as required to identify operational components. Where there is more than one sprinkler system, signage must include specific details as to the respective system.

PART 3 EXECUTION

3.1 VERIFYING ACTUAL FIELD CONDITIONS

Before commencing work, examine all adjoining work on which the contractor's work that is dependent for perfect workmanship according to the intent of this specification section, and report to the Contracting Officer's Representative a condition that prevents performance of first class work. No "waiver of responsibility" for incomplete, inadequate or defective adjoining work will be considered unless notice has been filed before submittal of a proposal.

3.2 INSTALLATION

The installation must be in accordance with the applicable provisions of NFPA 13, NFPA 24 and publications referenced therein. Locate sprinklers in a consistent pattern with ceiling grid, lights, and air supply diffusers. Install sprinkler system over and under ducts, piping and platforms when such equipment can negatively affect or disrupt the sprinkler discharge pattern and coverage.

a. Piping offsets, fittings, and other accessories required must be furnished to provide a complete installation and to eliminate interference with other construction.

b. Wherever the contractor's work interconnects with work of other trades the Contractor must coordinate with other Contractors to insure all Contractors have the information necessary so that they may properly install all necessary connections and equipment. Identify all work items needing access (dampers and similar equipment) that are concealed above hung ceilings by permanent color coded pins/tabs in the ceiling directly below the item.

c. Provide required supports and hangers for piping, conduit, and equipment so that loading will not exceed allowable loadings of structure. Submittal of a bid must be a deemed representation that the contractor submitting such bid has ascertained allowable loadings and has included in his estimates the costs associated in furnishing

required supports.

3.2.1 Waste Removal

At the conclusion of each day's work, clean up and stockpile on site all waste, debris, and trash which may have accumulated during the day as a result of work by the contractor and of his presence on the job. Sidewalks and streets adjoining the property must be kept broom clean and free of waste, debris, trash and obstructions caused by work of the contractor, which will affect the condition and safety of streets, walks, utilities, and property.

3.3 UNDERGROUND PIPING INSTALLATION

The fire protection water main must be laid, and joints anchored, in accordance with NFPA 24. Minimum depth of cover must be 3 feet or the frost line, whichever is deeper. The supply line must terminate inside the building with a flanged piece, the bottom of which must be set not less than 1-foot above the finished floor. A blind flange must be installed temporarily on top of the flanged piece to prevent the entrance of foreign matter into the supply line. A concrete thrust block must be provided at the elbow where the pipe turns up toward the floor. In addition, joints must be anchored in accordance with NFPA 24. Buried steel components must be provided with a corrosion protective coating in accordance with AWWA C203. Piping more than 5 feet outside the building walls must meet the requirements of Section 33 11 00 WATER UTILITY DISTRIBUTION PIPING.

3.4 ABOVEGROUND PIPING INSTALLATION

The methods of fabrication and installation of the aboveground piping must fully comply with the requirements and recommended practices of NFPA 13 and this specification section.

3.4.1 Protection of Piping Against Earthquake Damage

Seismic restraint is not required.

3.4.2 Piping in Exposed Areas

Install exposed piping without diminishing exit access widths, corridors or equipment access. Exposed horizontal piping, including drain piping, must be installed to provide maximum headroom.

3.4.3 Piping in Finished Areas

In areas with suspended or dropped ceilings and in areas with concealed spaces above the ceiling, piping must be concealed above ceilings. Piping must be inspected, hydrostatically tested and approved before being concealed. Risers and similar vertical runs of piping in finished areas must be concealed.

3.4.4 Pendent Sprinklers

a. Drop nipples to pendent sprinklers must consist of minimum 1-inch pipe with a reducing coupling into which the sprinkler must be threaded.

b. Where sprinklers are installed below suspended or dropped ceilings, drop nipples must be cut such that sprinkler ceiling plates or

escutcheons are of a uniform depth throughout the finished space. The outlet of the reducing coupling must not extend below the underside of the ceiling.

c. Recessed pendent sprinklers must be installed such that the distance from the sprinkler deflector to the underside of the ceiling must not exceed the manufacturer's listed range and must be of uniform depth throughout the finished area.

d. Pendent sprinklers in suspended ceilings must be located in the center of the tile (plus or minus 2 inches).

3.4.5 Upright Sprinklers

Riser nipples or "sprigs" to upright sprinklers must contain no fittings between the branch line tee and the reducing coupling at the sprinkler.

3.4.6 Pipe Joints

Pipe joints must conform to NFPA 13, except as modified herein. Not more than four threads must show after joint is made up. Welded joints will be permitted, only if welding operations are performed as required by NFPA 13 at the Contractor's fabrication shop, not at the project construction site. Flanged joints must be provided where indicated or required by NFPA 13. Grooved pipe and fittings must be prepared in accordance with the manufacturer's latest published specification according to pipe material, wall thickness and size. Grooved couplings, fittings and grooving tools must be products of the same manufacturer. For copper tubing, pipe and groove dimensions must comply with the tolerances specified by the coupling manufacturer. The diameter of grooves made in the field must be measured using a "go/no-go" gauge, vernier or dial caliper, narrow-land micrometer, or other method specifically approved by the coupling manufacturer for the intended application. Groove width and dimension of groove from end of pipe must be measured and recorded for each change in grooving tool setup to verify compliance with coupling manufacturer's tolerances.

3.4.7 Reducers

Reductions in pipe sizes must be made with one-piece tapered reducing fittings. When standard fittings of the required size are not manufactured, single bushings of the face or hex type will be permitted. Where used, face bushings must be installed with the outer face flush with the face of the fitting opening being reduced. Bushings cannot be used in elbow fittings, in more than one outlet of a tee, in more than two outlets of a cross, or where the reduction in size is less than 1/2-inch.

3.4.8 Pipe Penetrations

a. Cutting structural members for passage of pipes or for pipe-hanger fastenings will not be permitted. Pipes that must penetrate concrete or masonry walls or concrete floors must be core-drilled and provided with pipe sleeves. Each sleeve must be Schedule 40 galvanized steel, ductile-iron or cast-iron pipe and extend through its respective wall or floor and be cut flush with each wall surface. Sleeves must provide required clearance between the pipe and the sleeve per NFPA 13. The space between the sleeve and the pipe must be firmly packed with mineral wool insulation.

b. Where pipes and sleeves penetrate fire walls, fire partitions, or floors, pipes/sleeves must be firestopped in accordance with Section 07 84 00 FIRESTOPPING.

c. In penetrations that are not fire-rated or not a floor penetration, the space between the sleeve and the pipe must be sealed at both ends with plastic waterproof cement that will dry to a firm but pliable mass or with a mechanically adjustable segmented elastomer seal.

d. All penetrations through the boundary of rooms/areas identified as secure space area must meet ICS 705-1.

3.4.9 Escutcheons

Escutcheons must be provided for pipe penetration in finished areas of ceilings, floors and walls. Escutcheons must be securely fastened to the pipe at surfaces through which piping passes.

3.4.10 Inspector's Test Connection

Unless otherwise indicated, the test connection must consist of 1-inch pipe connected at the riser as a combination test and drain valve; a test valve located approximately 7 feet above the floor; a smooth bore brass outlet equivalent to the smallest orifice sprinkler used in the system; and a painted metal identification sign affixed to the valve with the words "Inspector's Test". All test connection piping must be inside of the building and penetrate the exterior wall at the location of the discharge orifice only. The discharge orifice must be located outside the building wall no more than 2 feet above finished grade, terminated at a hard surface or concrete splash block to prevent erosion. Discharge to the exterior must not interfere with exiting from the facility. Water discharge or runoff must not cross the path of egress from the building. Do not discharge to the roof. Discharge to floor drains, janitor sinks or similar fixtures is not permitted.

Provide concrete splash blocks at all drain and inspector's test connection discharge locations if not discharging to a concrete surface. Splash blocks must be large enough to mitigate erosion and not become dislodged during a full flow of the drain. Ensure all discharged water drains away from the facility and does not cause property damage.

3.4.11 Backflow Preventer

Locate within the building or in a heated enclosure in locations subject to freezing. For heated enclosures, provide a low temperature supervisory alarm connected to the facility fire alarm system. Heat trace is not permitted to be used.

Install backflow preventers so that the bottom of the assembly is a minimum of 6 inches above the finished floor/grade. Install horizontal backflow preventers so that the bottom of the assembly is no greater than 24 inches above the finished floor/grade. Install vertical backflow preventers so that the upper operating handwheel is no more than 6 feet above the finished floor/grade. Clearance around control valve handles must be minimum 6 inches above grade/finished floor and away from walls.

3.4.11.1 Test Connection

Provide downstream of the backflow prevention assembly UL 668 hose valves

with 2.5-inch National Standard male hose threads with cap and chain. Provide one valve for each 250 gpm of system demand or fraction thereof. Provide a permanent sign in accordance with paragraph entitled "Identification Signs" which reads, "Test Valve". Indicate location of test header. If an exterior connection, provide a control valve inside a heated mechanical room to prevent freezing.

3.4.12 Drains

a. Main drain piping must be provided to discharge at a safe point outside the building, no more than 2 feet above finished grade. Terminate at a hard surface or a concrete splash block. Discharge to the exterior must not interfere with exiting from the facility. Water discharge or runoff must not cross the path of egress from the building.

b. Auxiliary drains must be provided as required by NFPA 13. Auxiliary drains are permitted to discharge to a floor drain if the drain is sized to accommodate full flow (min 40 gpm). Discharge to service sinks or similar plumbing fixtures is not permitted.

3.4.13 Installation of Fire Department Connection

Connection must be mounted on the exterior wall approximately 3 feet above finished grade. The piping between the connection and the check valve must be provided with an automatic drip in accordance with NFPA 13 and piped to drain to the outside.

3.4.14 Identification Signs

Signs must be affixed to each control valve, inspector test valve, main drain, auxiliary drain, test valve, and similar valves as appropriate or as required by NFPA 13. Main drain test results must be etched into main drain identification sign. Hydraulic design data must be etched into the nameplates and permanently affixed to each sprinkler riser as specified in NFPA 13. Provide labeling on the surfaces of all feed and cross mains to show the pipe function (e.g., "Sprinkler System", "Fire Department Connection", "Standpipe") and normal valve position (e.g. "Normally Open", "Normally Closed"). For pipe sizes 4-inch and larger provide white painted stenciled letters and arrows, a minimum of 2 inches in height and visible from at least two sides when viewed from the floor. For pipe sizes less than 4-inch, provide white painted stenciled letters and arrows, a minimum of 0.75-inch in height and visible from the floor.

3.4.15 Sprinkler Gauge

Install sprinkler gauge installation labels on each sprinkler gauge. Label must indicate date installed and test or replace date.

3.5 ELECTRICAL

Except as modified herein, electric equipment and wiring must be in accordance with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Alarm signal wiring connected to the building fire alarm control system must be by the fire alarm installer.

3.6 PAINTING

Color code mark piping red.

3.7 FIELD QUALITY CONTROL

3.7.1 Test Procedures

Submit detailed test procedures, prepared and signed by the NICET Level III Fire Sprinkler Technician, and the representative of the installing company, and reviewed by the QFPE 60 days prior to performing system tests. Detailed test procedures must list all components of the installed system. Test procedures must include sequence of testing, time estimate for each test, and sample test data forms. The test data forms must be in a check-off format (pass/fail with space to add applicable test data; similar to the forms in NFPA 13). The test procedures and accompanying test data forms must be used for the pre-Government testing and the Government final testing.

a. Provide space to identify the date and time of each test. Provide space to identify the names and signatures of the individuals conducting and witnessing each test.

3.7.2 Pre-Government Testing

3.7.2.1 Verification of Compliant Installation

Conduct inspections and tests to ensure that equipment is functioning properly. Tests must meet the requirements of paragraph entitled "Minimum System Tests" and "System Acceptance" as noted in NFPA 13. The Contractor and QFPE must be in attendance at the pre-Government testing to make necessary adjustments. After inspection and testing is complete, provide a signed Verification of Compliant Installation letter by the QFPE that the installation is complete, compliant with the specification and fully operable. The letter must include the names and titles of the witnesses to the pre-Government tests. Provide all completion documentation as required by NFPA 13 and the test reports noted below.

a. NFPA 13 Aboveground Material and Test Certificate

b. NFPA 13 Underground Material and Test Certificate

3.7.2.2 Request for Government Final Test

When the verification of compliant installation has been completed, submit a formal request for Government final test to the Designated Fire Protection Engineer (DFPE). Government final testing will not be scheduled until the DFPE has received copies of the request for Government final testing and Verification of Compliant Installation letter with all required reports. Government final testing will not be performed until after the connections to the installation fire alarm reporting system have been completed and tested to confirm communications are fully functional. Submit request for test at least 15 calendar days prior to the requested test date.

3.7.3 Correction of Deficiencies

If equipment was found to be defective or non-compliant with contract requirements, perform corrective actions and repeat the tests. Tests must be conducted and repeated if necessary until the system has been demonstrated to comply with all contract requirements.

3.7.4 Government Final Tests

The tests must be performed in accordance with the approved test procedures in the presence of the DFPE. Furnish instruments and personnel required for the tests. The following must be provided at the job site for Government Final Testing:

a. The manufacturer's technical representative.

b. The contractor's Qualified Fire Protection Engineer (QFPE).

c. Marked-up red line drawings of the system as actually installed.

Government Final Tests will be witnessed by the Designated Fire Protection Engineer and Qualified Fire Protection Engineer (QFPE). At this time, all required tests noted in the paragraph "Minimum System Tests" must be repeated at their discretion.

3.8 MINIMUM SYSTEM TESTS

The system, including the underground water mains, and the aboveground piping and system components, must be tested to ensure that equipment and components function as intended. The underground and aboveground interior piping systems and attached appurtenances subjected to system working pressure must be tested in accordance with NFPA 13 and NFPA 24.

3.8.1 Underground Piping

3.8.1.1 Flushing

Underground piping must be flushed at a minimum of 10 fps in accordance with NFPA 24.

3.8.1.2 Hydrostatic Test

New underground piping must be hydrostatically tested in accordance with NFPA 24.

3.8.2 Aboveground Piping

3.8.2.1 Hydrostatic Test

Aboveground piping must be hydrostatically tested in accordance with NFPA 13. There must be no drop in gauge pressure or visible leakage when the system is subjected to the hydrostatic test. The test pressure must be read from a gauge located at the low elevation point of the system or portion being tested.

3.8.2.2 Backflow Prevention Assembly Forward Flow Test

Each backflow prevention assembly must be tested at system flow demand, including all applicable hose streams, as specified in NFPA 13. The Contractor must provide all equipment and instruments necessary to conduct a complete forward flow test, including 2.5-inch diameter hoses, playpipe nozzles or flow diffusers, calibrated pressure gauges, and pitot tube gauge. The Contractor must provide all necessary supports to safely secure hoses and nozzles during the test. At the system demand flow, the pressure readings and pressure drop (friction loss) across the assembly must be recorded. A metal placard must be provided on the backflow

prevention assembly that lists the pressure readings both upstream and downstream of the assembly, total pressure drop, and the system test flow rate determined during the preliminary testing. The pressure drop must be compared to the manufacturer's data and the readings observed during the final inspections and tests.

3.8.3 Main Drain Flow Test

Following flushing of the underground piping, a main drain test must be made to verify the adequacy of the water supply. Static and residual pressures must be recorded on the certificate specified in paragraph SUBMITTALS.

3.9 SYSTEM ACCEPTANCE

Following acceptance of the system, as-built drawings and O&M manuals must be delivered to the Contracting Officer for review and acceptance. Submit six sets of detailed as-built drawings. The drawings must show the system as installed, including deviations from both the project drawings and the approved shop drawings. These drawings must be submitted within two weeks after the final acceptance test of the system. At least one set of as-built (marked-up) drawings must be provided at the time of, or prior to the final acceptance test.

a. The drawings must be prepared electronically and sized no less than the contract drawings. Furnish one set of PDFs and CDs or DVDs containing software back-up and CAD based drawings in latest version of AutoCAD DXF and portable document formats of as-built drawings and schematics.

b. Provide operating and maintenance (O&M) instructions.

3.10 ONSITE TRAINING

Conduct a training course for the responding fire department and operating and maintenance personnel as designated by the Contracting Officer. Training must be performed on two separate days (to accommodate different shifts of Fire Department personnel) for a period of 4 hours of normal working time and must start after the system is functionally complete and after the final acceptance test. The on-site training must cover all of the items contained in the approved Operating and Maintenance Instructions.

-- End of Section --

SECTION 21 13 16

DRY PIPE SPRINKLER SYSTEMS, FIRE PROTECTION
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.1	(2020) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250
ASME B16.3	(2021) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.4	(2021) Gray Iron Threaded Fittings; Classes 125 and 250
ASME B16.21	(2021) Nonmetallic Flat Gaskets for Pipe Flanges

ASTM INTERNATIONAL (ASTM)

ASTM A47/A47M	(1999; R 2022; E 2022) Standard Specification for Ferritic Malleable Iron Castings
ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A135/A135M	(2021) Standard Specification for Electric-Resistance-Welded Steel Pipe
ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A183	(2014; R 2020) Standard Specification for Carbon Steel Track Bolts and Nuts
ASTM A536	(1984; R 2019; E 2019) Standard Specification for Ductile Iron Castings

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-71	(2018) Gray Iron Swing Check Valves, Flanged and Threaded Ends

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 13	(2022; ERTA 3 2022) Standard for the Installation of Sprinkler Systems
NFPA 291	(2022) Recommended Practice for Fire Flow Testing and Marking of Hydrants

NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES (NICET)

NICET 1014-7	(2012) Program Detail Manual for Certification in the Field of Fire Protection Engineering Technology (Field Code 003) Subfield of Automatic Sprinkler System Layout

UNDERWRITERS LABORATORIES (UL)

UL 199	(2020) UL Standard for Safety Automatic Sprinklers for Fire-Protection Service
UL 312	(2022) UL Standard for Safety Check Valves for Fire-Protection Service
UL Fire Prot Dir	(2012) Fire Protection Equipment Directory

1.2 SYSTEM DESCRIPTION

Provide dry pipe sprinkler system(s) in areas indicated on the drawings. Except as modified herein, the system must meet the requirements of NFPA 13. Dry pipe systems must utilize nitrogen.Pipe sizes which are not indicated on the Contract drawings must be determined by hydraulic calculations.

1.2.1 Hydraulic Design

1.2.1.1 Basis for Calculations

A waterflow test was performed on 25 September 2025 and resulted in a static pressure of 76 psi with a residual pressure of 49 psi while flowing 1,060 gpm. Perform a fire hydrant flow test prior to shop drawing submittal in accordance with NFPA 291. Results must include hydrant elevations relative to the building and hydrant number/identifiers for the tested hydrants, including which were flowed, which had a gauge. This information must be presented in a tabular form if multiple hydrants were flowed. The results must be included with the hydraulic calculations. Hydraulic calculations must be based on the flow test required to be performed in this paragraph, verified by the NAVFAC Midlant Fire Protection Engineer, and approved by Contracting Officer. Hydraulic calculations must be based upon the Hazen-Williams formula with a "C" value noted in NFPA 13 for piping. A "C" value of 120 is permitted to be used in hydraulic calculations when nitrogen is utilized. Hydraulic calculations must be based on operation of the fire pump provided in

Section 21 30 00 FIRE PUMPS. The minimum residual pressure in a service lateral (lead-in) at the design flow rate must be 20 psi at the suction side of the fire pump.

1.2.1.2 Hydraulic Calculations

a. Water supply curves and system requirements must be plotted on semi-logarithmic graph (N^1.85) paper so as to present a summary of the complete hydraulic calculation.

b. Provide a summary sheet listing sprinklers in the design area and their respective hydraulic reference points, elevations, minimum discharge pressures and minimum flows. Elevations of hydraulic reference points (nodes) must be indicated.

c. Documentation must identify each pipe individually and the nodes connected thereto. Indicate the diameter, length, flow, velocity, friction loss, number and type fittings, total friction loss in the pipe, equivalent pipe length and Hazen-Williams coefficient for each pipe.

d. Where the sprinkler system is supplied by interconnected risers, the sprinkler system must be hydraulically calculated using the hydraulically most demanding single riser. The calculations must not assume the simultaneous use of more than one riser.

e. All calculations must include the backflow preventer manufacturer's stated friction loss at the design flow or 12 psi for reduced pressure backflow preventer, whichever is greater.

f. All calculations must be performed back to the actual location of the flow test, taking into account the direction of flow in the service main at the test location.

1.2.1.3 Design Criteria

Hydraulically design the system to discharge a minimum density as indicated on the drawings. Hydraulic calculations must be in accordance with the Area/Density Method of NFPA 13. Add an allowance for exterior hose streams as indicated on the drawings to the sprinkler system demand at the fire hydrant shown on the drawings closest to the point where the water service enters the building.

1.2.2 Sprinkler Coverage

Sprinklers must be uniformly spaced on branch lines. Provide coverage throughout 100 percent of the areas noted on the Contract drawings. This includes, but is not limited to, telephone rooms, electrical equipment rooms (regardless of the fire resistance rating of the enclosure), boiler rooms, switchgear rooms, transformer rooms, attached electrical vaults and other electrical and mechanical spaces. Coverage per sprinkler must be in accordance with NFPA 13. Provide sprinklers below all obstructions in accordance with NFPA 13.

1.2.3 System Volume Limitations

Where the volume of an individual system piping exceeds 500 gallons, provide the dry pipe valve with a quick-opening device. The maximum system capacity controlled by one dry pipe valve must not exceed 750

gallons, unless it complies with the dry pipe system water delivery calculations noted in NFPA 13.

1.2.4 Qualified Fire Protection Engineer (QFPE)

The QFPE in this section is the same as FPQC in Section 01 45 00. Wherever "Qualified Fire Protection Engineer (QFPE)" or "QFPE" appears in this sectionm substitute with "Fire Protection Quality Control Specialist (FPQC)". Services of the QFPE must include:

a. Reviewing SD-02, SD-03, and SD-05 submittal packages for completeness and compliance with the provisions of this specification. Working (shop) drawings and calculations must be prepared by, or prepared under the immediate supervision of, the QFPE. The QFPE must affix their professional engineering stamp with signature to the shop drawings, calculations, and material data sheets, indicating approval prior to submitting the shop drawings to the DFPE.

b. Provide a letter documenting that the SD-02, SD-03, and SD-05 submittal package has been reviewed and noting outstanding comments.

c. Performing in-progress construction surveillance prior to installation of ceilings (rough-in inspection).

d. Witnessing pre-Government and final Government functional performance testing and performing a final installation review.

e. Signing applicable certificates under SD-07.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Partial submittals and submittals not fully complying with NFPA 13 and this specification section must be returned disapproved without review. SD-02, SD-03 and SD-05 must be submitted simultaneously.

Shop drawings (SD-02), product data (SD-03) and calculations (SD-05) must be prepared by the designer and combined and submitted as one complete package. The QFPE must review the SD-02/SD-03/SD-05 submittal package for completeness and compliance with the Contract provisions prior to submission to the Government. The QFPE must provide a Letter of Confirmation that they have reviewed the submittal package for compliance with the contract provisions. This letter must include their professional engineer stamp and signature. Partial submittals and submittals not reviewed by the QFPE must be returned disapproved without review.

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualified Fire Protection Engineer (QFPE); G

Sprinkler System Designer; G

Sprinkler System Installer; G

Nitrogen Generation System Commissioning Technician ; G

SD-02 Shop Drawings

Shop Drawing; G

SD-03 Product Data

Pipe; G

Fittings; G

Valves, including gate, check, butterfly, and globe; G

Relief Valves; G

Sprinklers ; G

Pipe Hangers and Supports ; G

Sprinkler Alarm Switch; G

Valve Supervisory (Tamper) Switch; G

High/Low-Nitrogen Pressure Supervisory Switch; G

Nitrogen Generation System; G

Nameplates; G

Dry Pipe Valve; G

SD-05 Design Data

Hydraulic Calculations; G

SD-06 Test Reports

Test Procedures; G

SD-07 Certificates

Verification of Compliant Installation; G

Request for Government Final Test; G

SD-10 Operation and Maintenance Data

Operating and Maintenance (O&M) Instructions; G

Spare Parts Data; G

SD-11 Closeout Submittals

As-built drawings

1.4 QUALITY ASSURANCE

1.4.1 Preconstruction Submittals

Within 36 days of contract award but no less than 14 days prior to commencing work on site, the prime Contractor must submit the following for review and approval. SD-02, SD-03 and SD-05 submittals received prior to the review and approval of the qualifications must be returned Disapproved Without Review. All resultant delays are the sole responsibility of the prime Contractor.

1.4.1.1 Shop Drawing

One copy of the shop drawings, no later than 28 days prior to the start of system installation. Working drawings conforming to the requirements prescribed in NFPA 13 and must be no smaller than the Contract Drawings. Each set of drawings must include the following:

1. A descriptive index with drawings listed in sequence by number. A legend sheet identifying device symbols, nomenclature, and conventions used in the package.

2. Floor plans drawn to a scale not less than 1/8-inch equals 1-foot clearly showing locations of devices, equipment, risers, electrical power connections and other details required to clearly describe the proposed arrangement.

3. Actual center-to-center dimensions between sprinklers on branch lines and between branch lines; from end sprinklers to adjacent walls; from walls to branch lines; from sprinkler feed mains, cross mains and branch lines to finished floor and roof or ceiling. A detail must show the dimension from the sprinkler and sprinkler deflector to the ceiling in finished areas.

4. Longitudinal and transverse building sections showing typical branch line and cross main pipe routing, elevation of each typical sprinkler above finished floor and elevation of "cloud" or false ceilings in relation to the building ceilings.

5. Plan and elevation views which establish that the equipment will fit the allotted spaces with clearance for installation and maintenance.

6. Riser layout drawings drawn to a scale of not less than 1/2-inch equals 1-foot to show details of each system component, clearances between each other and from other equipment and construction in the room.

7. Details of each type of riser assembly, pipe hanger, and restraint of underground water main at point-of-entry into the building, and electrical devices and interconnecting wiring. The dimension from the edge of vertical piping to the nearest adjacent wall(s) must be indicated on the drawings when vertical piping is located in stairs or other portions of the means of egress.

8. Details of each type of pipe hanger and related components.

9. Include fire pump curve with shop drawings and hydraulic calculations.

10. The calculated volume of each system.

1.4.1.2 Product Data

One copy of annotated catalog data to show the specific model, type, and size of each item. Catalog cuts must also indicate the NRTL listing. The data must be highlighted to show model, size, options, and other pertinent information, that are intended for consideration. Data must be adequate to demonstrate compliance with all contract requirements. Product data for all equipment must be combined into a single submittal.

1.4.1.3 Hydraulic Calculations

Calculations must be as outlined in NFPA 13 except that calculations must be performed by computer using software intended specifically for fire protection system design using the design data shown on the drawings. Include fire pump curve with submittal.

1.4.1.4 Operating and Maintenance (O&M) Instructions

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA as supplemented and modified by this specification section.

Provide six manuals and one pdf version on electronic media. The manuals must include the manufacturer's name, model number, parts list, list of parts and tools that should be kept in stock by the owner for routine maintenance, simplified wiring and controls diagrams, troubleshooting guide, and recommended service organization (including address and telephone number) for each item of equipment.

Submit spare parts data for each different item of material and equipment specified. The data must include a complete list of parts and supplies, and a list of parts recommended by the manufacturer to be replaced after 1-year and 3 years of service. Include a list of special tools and test equipment required for maintenance and testing of the products supplied.

1.4.2 Qualifications

1.4.2.1 Sprinkler System Designer

The sprinkler system designer must be certified as a Level III Technician by National Institute for Certification in Engineering Technologies (NICET) in the Water-Based Systems Layout subfield of Fire Protection Engineering Technology in accordance with NICET 1014-7.

1.4.2.2 Sprinkler System Installer

The sprinkler system installer must be regularly engaged in the installation of the type and complexity of system specified in the contract documents, and must have served in a similar capacity for at least three systems that have performed in the manner intended for a period of not less than 6 months.

1.4.2.3 Nitrogen Generation System Commissioning Technician

Commissioning technician of nitrogen generation system(s) must have one of the following qualifications. Qualifications must be provided prior to preliminary inspection and tests.

a. Commissioning of nitrogen generation system must be carried out by technician employed by and certified by the nitrogen generation system

manufacturer.

b. In lieu of manufacturer's commissioning technician, the fire sprinkler contractor must provide proof their commissioning technician has manufacturer's certified training for the equipment being installed and proof of at least five previous installations of manufacturer's equipment where the contractor's commissioning technician has successfully conducted commissioning under the direct supervision of the manufacturer's commissioning representative. Contractor must provide proof the five supervised commissioning occurred AFTER contractor's commissioning agent has obtained the certified training. Commissioning carried out prior to factory training, or without supervision of manufacturer's technician or commissioning of other manufacturer's equipment does not qualify as applicable experience. Conduct preliminary inspections and testing does not qualify as applicable experience.

1.4.3 Regulatory Requirements

Equipment and material must be listed or approved. Listed or approved, as used in this Section, means listed, labeled or approved by a Nationally Recognized Testing Laboratory (NRTL) such as UL Fire Prot Dir or FM APP GUIDE. The omission of these terms under the description of an item of equipment described must not be construed as waiving this requirement. All listings or approvals by testing laboratories must be from an existing ANSI or UL published standard. The recommended practices stated in the manufacturer's literature or documentation are mandatory requirements.

1.5 DELIVERY, STORAGE, AND HANDLING

Protect all equipment delivered and placed in storage from the weather, excessive humidity and temperature variations, dirt and dust, or other contaminants. All pipes must be either capped or plugged until installed.

1.6 EXTRA MATERIALS

Spare sprinklers and wrench(es) must be provided as spare parts in accordance with NFPA 13.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

2.1.1 Standard Products

Provide materials, equipment, and devices listed for fire protection service when so required by NFPA 13 or this specification. Select material from one manufacturer, where possible, and not a combination of manufacturers, for a particular classification of materials. Material and equipment must be the standard products of a manufacturer regularly engaged in the manufacture of the products for at least 2 years prior to bid.

2.1.2 Nameplates

Major components of equipment must have the manufacturer's name, address, type or style, model or serial number, catalog number, date of installation, installing Contractor's name and address, and the contract

number provided on a new name plate permanently affixed to the item or equipment. Nameplates must be etched metal or plastic, permanently attached by screws to control units, panels or adjacent walls.

2.1.3 Identification and Marking

Pipe and fitting markings must include name or identifying symbol of manufacturer and nominal size. Pipe must be marked with ASTM designation. Valves and equipment markings must have name or identifying symbol of manufacturer, specific model number, nominal size, name of device, arrow indicating direction of flow, and position of installation (horizontal or vertical), except if valve can be installed in either position. Markings must be included on the body casting or on an etched or stamped metal nameplate permanently on the valve or cover plate.

2.1.4 Pressure Ratings

Valves, fittings, couplings, alarm switches, and similar devices must be rated for the maximum working pressures that can be experienced in the system, but in no case less than 175 psi.

2.2 ABOVEGROUND PIPING COMPONENTS

2.2.1 Steel Piping Components

2.2.1.1 Steel Pipe

Except as modified herein, steel pipe must be black as permitted by NFPA 13 and conform to the applicable provisions of ASTM A53/A53M, ASTM A135/A135M or ASTM A153/A153M.

Steel pipe must be minimum Schedule 40 for sizes 2 inches and less; and minimum Schedule 10 for sizes larger than 2 inches. Steel piping with wall thickness less than Schedule 40 must not be threaded. Grooved pipe must be cut-grooved.

2.2.1.2 Fittings

Fittings must be welded, threaded, or grooved-end type. Threaded fittings must be cast-iron conforming to ASME B16.4, malleable-iron conforming to ASME B16.3 or ductile-iron conforming to ASTM A536. Plain-end fittings with mechanical couplings, fittings that use steel gripping devices to bite into the pipe, steel press fittings and field welded fittings are not permitted. Fittings, mechanical couplings, and rubber gaskets must be supplied by the same manufacturer. Threaded fittings must use Teflon tape or manufacturer's approved joint compound. Reducing couplings are not permitted except as allowed by NFPA 13.

2.2.1.3 Grooved Mechanical Joints and Fittings

Joints and fittings must be designed for not less than 175 psi service and the product of the same manufacturer. Field welded fittings must not be used. Fitting and coupling housing must be malleable-iron conforming to ASTM A47/A47M, Grade 32510; ductile-iron conforming to ASTM A536, Grade 65-45-12. Rubber gasketed grooved-end pipe and fittings with mechanical couplings are permitted in pipe sizes 2 inches and larger. Gasket must be of silicon compound and listed for dry fire protection systems. Gasket must be the flush type that fills the entire cavity between the fitting and the pipe. Nuts and bolts must be heat-treated steel conforming to

ASTM A183 and must be cadmium-plated or zinc-electroplated.

2.2.1.4 Flanges

Flanges must conform to NFPA 13 and ASME B16.1. Gaskets must be non-asbestos compressed material in accordance with ASME B16.21, 1/16-inch thick, and full face or self-centering flat ring type.

2.2.2 Pipe Hangers and Supports

Provide galvanized pipe hangers and supports in accordance with NFPA 13.

2.2.3 Valves

Provide valves of types approved for fire service. Valves must open by counterclockwise rotation.

2.2.3.1 Control Valve

Manually operated sprinkler control/gate valve must be outside stem and yoke (OS&Y) type or butterfly type and must be listed.

2.2.3.2 Check Valves

Check valves must comply with UL 312. Check valves 4 inches and larger must be of the swing type, have a clear waterway and meet the requirements of MSS SP-71, for Type 3 or 4. Inspection plate must be provided on valves larger than 6 inches.

2.3 DRY PIPE VALVE ASSEMBLY

The dry pipe valve must be a listed, latching differential type be complete with trim piping, valves, fittings, pressure gauges, priming water fill cup, velocity drip check, drip cup, and other ancillary components as required for proper operation. The assembly must include a quick-opening device by the same manufacturer as the dry pipe valve for systems over 500 gallons in capacity and in all cases when needed to achieve the timed test requirements in part 3 of this specification section.

2.4 SUPERVISORY NITROGEN SYSTEM

Provide a nitrogen supply system in accordance with NFPA 13. The connection pipe from the nitrogen generator must not be less than 1/2-inch in diameter and must enter the system above the priming water level of the dry pipe valve. Install a check valve in the system supply nitrogen piping from the generator. A shutoff valve of the renewable disc type must be installed upstream of this check valve. The nitrogen supply system must be sized to pressurize the sprinkler system to 40 psi within 20 minutes.

2.4.1 Nitrogen Generation System

The nitrogen generation system (NGS) must be installed with a compressor sized appropriately for the application and capable of achieving system pressure within 30 minutes in accordance with the requirements of NFPA 13. The nitrogen generation system must be designed to achieve a nitrogen concentration of 98% or greater and maintain that concentration within the fire sprinkler system continuously. The output nitrogen quality must be

confirmed by using a gas stream analyzer. Where multiple dry pipe sprinkler risers are present, provide a manifold adjacent to the dry pipe sprinkler risers. Manifold system must include automatic vent and air maintenance devices for each sprinkler system riser. Nitrogen generation system requires a dedicated, hardwired 120V AC power supply.

2.4.1.1 Design of Nitrogen Generation System

Design the system so all equipment is installed within the confines of the riser room with the exception of a connection for a manual or automatic gas analyzer. Provide a system that is capable of delivering a minimum of 98 percent nitrogen composition throughout all of the system piping within 14 days from the commencement of the inerting process. Provide membrane type nitrogen generators that provide "instant on-instant off" nitrogen gas production without the need for nitrogen storage tanks. The complete nitrogen generator system must be self-contained and skid mounted with "drop-in" operability with a simple one step direct connection of the nitrogen gas supply line to each zone/riser. Provide an automatic "fill and purge" breathing process. This must be done while the sprinkler system is fully functional and must not alter the design performance of the sprinkler system. A process that involves continuous venting of the piping network is not permitted. Air maintenance devices used in conjunction with the nitrogen generation system must be listed for use on sprinkler systems. At the riser and at the end of each zone, provide a connection for a manual gas analyzer.

2.4.1.2 Nitrogen Air Compressor

Air compressors to be used in conjunction with the nitrogen generator must be capable of the following:

a. Capable of producing a continuous stream of compressed air at 100+ psig.

b. Capable of automatic cut in and cut out.

c. Equipped with an on-board after-cooler.

d. Equipped with an on-board automatic water blow down system.

e. Equipped with vibration dampening system.

f. Equipped with an air storage tank to provide continuous delivery of compressed air to the nitrogen generator.

g. Rated for continuous duty service.

h. Compressors less than 3.0 hp must be an oil-less design.

i. Oil-less compressors must be such that the manufacturer has designed the oil-less compressor to provide 5000 hours of continuous duty service before requiring a gasket and seal rebuild.

2.4.1.3 Nitrogen Venting Device

The functional component of the nitrogen venting device for use in the "fill and purge" breathing process must:

a. Be NRTL listed for use on sprinkler systems.

b. Not require plumbing to drain.

c. Close automatically at the completion of the nitrogen inerting process without manual intervention.

d. Be installed on each zone in the riser room.

2.4.1.4 Supervision of Nitrogen Generator

Nitrogen generator must be able to provide the following monitoring options:

a. Power supply "on" for nitrogen generators.

b. Power supply "on" for compressor.

c. Amp draw for compressor.

d. Line pressure (psig).

e. Nitrogen purity at discharge (sample port for use with manual gas analyzer).

2.4.2 Nitrogen Pressure Maintenance Device

Device must be a pressure regulator that automatically reduces supply air pressure to the minimum pressure required to be maintained in the piping system. The device must have a cast bronze body and valve housing complete with diaphragm assembly, spring, filter, ball check to prevent backflow, 1/16-inch restriction to prevent rapid pressurization of the system, and adjustment screw. The device must be capable of reducing maximum inlet pressure of 100 psi to a fixed outlet pressure adjustable to 10 psi.

2.5 ALARM INITIATING AND SUPERVISORY DEVICES

2.5.1 Sprinkler Alarm Switch

Pressure-type flow switch(es). Connection of switch must be by the fire alarm installer.

2.5.2 High/Low-Nitrogen Pressure Supervisory Switch

Each dry pipe valve must be provided with a nitrogen pressure switch connected to the control unit. The pressure switch must supervise the nitrogen pressure in the system and set to activate at 10 psi above the dry pipe valve trip point pressure (low) and 10 psi above normal nitrogen pressure (high). The switch must have an adjustable range between 5 and 80 psi. The switch must have screw terminal connection and capable of being wired for normally open or normally closed circuit.

2.5.3 Valve Supervisory (Tamper) Switch

Switch must be integral to the control valve or suitable for mounting to the type of control valve to be supervised open. The switch must be tamper resistant and contain SPDT (Form C) contacts arranged to transfer upon removal of the housing cover or closure of the valve of more than two rotations of the valve stem.

2.6 SPRINKLERS

Sprinklers must comply with UL 199 and NFPA 13. Sprinklers with internal O-rings are not acceptable. Sprinklers in high heat areas including attic spaces or in close proximity to unit heaters must have temperature classification in accordance with NFPA 13. Extended coverage sprinklers are permitted for loading docks, residential occupancies and high-piled storage applications only.

2.6.1 Upright Sprinkler

Upright sprinkler must be brass quick-response type with a minimum nominal K-factor of 5.6.

2.7 ACCESSORIES

2.7.1 Sprinkler Cabinet

Provide spare sprinklers in accordance with NFPA 13 and must be placed in a suitable metal or plastic cabinet of sufficient size to accommodate all the spare sprinklers and wrenches in designated locations. Spare sprinklers must be representative of, and in proportion to, the number of each type and temperature rating of the sprinklers installed as required by NFPA 13. At least one wrench of each type required must be provided.

2.7.2 Pendent Sprinkler Escutcheon

Escutcheon must be one-piece metallic type with a depth of less than 3/4-inch and suitable for installation on pendent sprinklers. The escutcheon must have a factory finish that matches the pendent sprinkler.

2.7.3 Pipe Escutcheon

Provide split hinge metal plates for piping entering walls, floors, and ceilings in exposed spaces. Provide polished stainless steel plates or chromium-plated finish on copper alloy plates in finished spaces. Provide paint finish on metal plates in unfinished spaces.

2.7.4 Sprinkler Guard

Listed guard must be a steel wire cage designed to encase the sprinkler and protect it from mechanical damage. Guards must be provided on sprinklers located within 7 feet of the floor.

2.7.5 Relief Valve

Relief valves must be listed and installed at there riser in accordance with NFPA 13.

2.7.6 Identification Sign

Valve identification sign must be minimum 6 inches wide by 2 inches high with enamel baked finish on minimum 18 gage steel or 0.024-inch aluminum with red letters on a white background or white letters on red background. Wording of sign must include, but not be limited to "main drain", "auxiliary drain", "inspector's test", "alarm test", "alarm line", and similar wording as required to identify operational components. Where there is more than one sprinkler system, signage must include specific

details as to the respective system.

PART 3 EXECUTION

3.1 VERIFYING ACTUAL FIELD CONDITIONS

Before commencing work, examine all adjoining work on which the contractor's work that is dependent for perfect workmanship according to the intent of this specification section, and report to the Contracting Officer's Representative a condition which prevents performance of first class work. No "waiver of responsibility" for incomplete, inadequate or defective adjoining work will be considered unless notice has been filed before submittal of a proposal.

3.2 INSTALLATION

The installation must be in accordance with the applicable provisions of NFPA 13 and publications referenced therein. Locate sprinklers in a consistent pattern with ceiling grid, lights, and air supply diffusers. Install sprinkler system over and under ducts, piping and platforms when such equipment can negatively affect or disrupt the sprinkler discharge pattern and coverage.

a. Piping offsets, fittings, and other accessories required must be furnished to provide a complete installation and to eliminate interference with other construction.

b. Wherever the contractor's work interconnects with work of other trades the Contractor must coordinate with other Contractors to insure all Contractors have the information necessary so that they may properly install all necessary connections and equipment. Identify all work items needing access (dampers and similar equipment) concealed above hung ceilings by permanent color coded pins/tabs in the ceiling directly below the item.

c. Provide required supports and hangers for piping, conduit, and equipment so that loading will not exceed allowable loadings of structure. Submittal of a bid must be a deemed representation that the contractor submitting such bid has ascertained allowable loadings and has included in his estimates the costs associated in furnishing required supports.

3.2.1 Waste Removal

At the conclusion of each day's work, clean up and stockpile on site all waste, debris, and trash which may have accumulated during the day as a result of work by the contractor and of his presence on the job. Sidewalks and streets adjoining the property must be kept broom clean and free of waste, debris, trash and obstructions caused by work of the contractor, which will affect the condition and safety of streets, walks, utilities, and property.

3.3 ABOVEGROUND PIPING INSTALLATION

The methods of fabrication and installation of the aboveground piping must fully comply with the requirements and recommended practices of NFPA 13 and this specification section.

3.3.1 Protection of Piping Against Earthquake Damage

Seismic restraint is not required.

3.3.2 Piping in Exposed Areas

Install exposed piping without diminishing exit access widths, corridors or equipment access. Exposed horizontal piping, including drain piping, must be installed to provide maximum headroom.

3.3.3 Piping in Finished Areas

In areas with suspended or dropped ceilings and in areas with concealed spaces above the ceiling, piping must be concealed above ceilings. Piping must be inspected, hydrostatically tested and approved before being concealed. Risers and similar vertical runs of piping in finished areas must be concealed.

3.3.4 Upright Sprinklers

Riser nipples or "sprigs" to upright sprinklers must contain no fittings between the branch line tee and the reducing coupling at the sprinkler.

3.3.5 Pipe Joints

Pipe joints must conform to NFPA 13, except as modified herein. Not more than four threads must show after joint is made up. Welded joints will be permitted, only if welding operations are performed as required by NFPA 13 at the Contractor's fabrication shop, not at the project construction site. Flanged joints must be provided where indicated or required by NFPA 13. Grooved pipe and fittings must be prepared in accordance with the manufacturer's latest published specification according to pipe material, wall thickness and size. Grooved couplings, fittings and grooving tools must be products of the same manufacturer. For copper tubing, pipe and groove dimensions must comply with the tolerances specified by the coupling manufacturer. The diameter of grooves made in the field must be measured using a "go/no-go" gauge, vernier or dial caliper, narrow-land micrometer, or other method specifically approved by the coupling manufacturer for the intended application. Groove width and dimension of groove from end of pipe must be measured and recorded for each change in grooving tool setup to verify compliance with coupling manufacturer's tolerances.

3.3.6 Reducers

Reductions in pipe sizes cannot be made with one-piece tapered reducing fittings. When standard fittings of the required size are not manufactured, single bushings of the face or hex type will be permitted. Where used, face bushings must be installed with the outer face flush with the face of the fitting opening being reduced. Bushings must not be used in elbow fittings, in more than one outlet of a tee, in more than two outlets of a cross, or where the reduction in size is less than 1/2-inch.

3.3.7 Pipe Penetrations

a. Cutting structural members for passage of pipes or for pipe-hanger fastenings will not be permitted. Pipes that must penetrate concrete or masonry walls or concrete floors must be core-drilled and provided with pipe sleeves. Each sleeve must be Schedule 40 galvanized steel,

ductile-iron or cast-iron pipe and extend through its respective wall or floor and be cut flush with each wall surface. Sleeves must provide required clearance between the pipe and the sleeve per NFPA 13. The space between the sleeve and the pipe must be firmly packed with mineral wool insulation.

b. Where pipes and sleeves penetrate fire walls, fire partitions, or floors, pipes/sleeves must be firestopped in accordance with Section 07 84 00 FIRESTOPPING.

c. In penetrations that are not fire-rated or not a floor penetration, the space between the sleeve and the pipe must be sealed at both ends with plastic waterproof cement that will dry to a firm but pliable mass or with a mechanically adjustable segmented elastomer seal.

3.3.8 Escutcheons

Escutcheons must be provided for pipe penetration in finished areas of ceilings, floors and walls. Escutcheons must be securely fastened to the pipe at surfaces through which piping passes.

3.3.9 Inspector's Test Connection

Unless otherwise indicated, the test connection must consist of 1-inch pipe connected to the remote branch line; a test valve located approximately 7 feet above the floor; a smooth bore brass outlet equivalent to the smallest orifice sprinkler used in the system; and a painted metal identification sign affixed to the valve with the words "Inspector's Test". All test connection piping must be inside of the building and penetrate the exterior wall at the location of the discharge orifice only. The discharge orifice must be located outside the building wall no more than 2 feet above finished grade, terminated at a hard surface or concrete splash block to prevent erosion. Discharge to the exterior must not interfere with exiting from the facility. Water discharge or runoff must not cross the path of egress from the building. Do not discharge to the roof. Discharge to floor drains, janitor sinks or similar fixtures is not permitted.

Provide concrete splash blocks at all drain and inspector's test connection discharge locations if not discharging to a concrete surface. Splash blocks must be large enough to mitigate erosion and not become dislodged during a full flow of the drain. Ensure all discharged water drains away from the facility and does not cause property damage.

3.3.10 Drains

a. Main drain piping must be provided to discharge at a safe point outside the building, no more than 2 feet above finished grade. Terminate at a hard surface or a concrete splash block. Discharge to the exterior must not interfere with exiting from the facility. Water discharge or runoff must not cross the path of egress from the building.

b. Auxiliary drains must be provided as required by NFPA 13. Auxiliary drains are permitted to discharge to a floor drain if the drain is sized to accommodate full flow (min 40 gpm). Discharge to service sinks or similar plumbing fixtures is not permitted.

3.3.11 Identification Signs

Signs must be affixed to each control valve, inspector test valve, main drain, auxiliary drain, test valve, and similar valves as appropriate or as required by NFPA 13. Main drain test results must be etched into main drain identification sign. Hydraulic design data must be etched into the nameplates and permanently affixed to each sprinkler riser as specified in NFPA 13. Provide labeling on the surfaces of all feed and cross mains to show the pipe function (e.g., "Sprinkler System", "Fire Department Connection", "Standpipe") and normal valve position (e.g. "Normally Open", "Normally Closed"). For pipe sizes 4-inch and larger provide white painted stenciled letters and arrows, a minimum of 2 inches in height and visible from at least two sides when viewed from the floor. For pipe sizes less than 4-inch, provide white painted stenciled letters and arrows, a minimum of 0.75-inch in height and visible from the floor.

3.3.12 Sprinkler Gauge

Install sprinkler gauge installation labels on each sprinkler gauge. Label must indicate date installed and test or replace date.

3.4 ELECTRICAL

Except as modified herein, electric equipment and wiring must be in accordance with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Alarm signal wiring connected to the building fire alarm control system must be by the fire alarm installer.

3.5 PAINTING

Color code mark piping red.

3.6 FIELD QUALITY CONTROL

3.6.1 Test Procedures

Submit detailed test procedures, prepared and signed by the NICET Level III Fire Sprinkler Technician, and the representative of the installing company, and reviewed by the QFPE 60 days prior to performing system tests. Detailed test procedures must list all components of the installed system. Test procedures must include sequence of testing, time estimate for each test, and sample test data forms. The test data forms must be in a check-off format (pass/fail with space to add applicable test data; similar to the forms in NFPA 13 .) The test procedures and accompanying test data forms must be used for the pre-Government testing and the Government final testing.

a. Provide space to identify the date and time of each test. Provide space to identify the names and signatures of the individuals conducting and witnessing each test.

3.6.2 Pre-Government Testing

3.6.2.1 Verification of Compliant Installation

Conduct inspections and tests to ensure that equipment is functioning properly. Tests must meet the requirements of paragraph entitled "Minimum System Tests" and "System Acceptance" as noted in NFPA 13. The Contractor and QFPE must be in attendance at the pre-Government testing to make

necessary adjustments. After inspection and testing is complete, provide a signed Verification of Compliant Installation letter by the QFPE that the installation is complete, compliant with the specification and fully operable. The letter must include the names and titles of the witnesses to the pre-Government tests. Provide all completion documentation as required by NFPA 13 and the test reports noted below.

a. NFPA 13 Aboveground Material and Test Certificate

3.6.2.2 Request for Government Final Test

When the verification of compliant installation has been completed, submit a formal request for Government final test to the Designated Fire Protection Engineer (DFPE). Government final testing will not be scheduled until the DFPE has received copies of the request for Government final testing and Verification of Compliant Installation letter with all required reports. Government final testing will not be performed until after the connections to the installation fire alarm reporting system have been completed and tested to confirm communications are fully functional. Submit request for test at least 15 calendar days prior to the requested test date.

3.6.3 Correction of Deficiencies

If equipment was found to be defective or non-compliant with contract requirements, perform corrective actions and repeat the tests. Tests must be conducted and repeated if necessary until the system has been demonstrated to comply with all contract requirements.

3.6.4 Government Final Tests

The tests must be performed in accordance with the approved test procedures in the presence of the DFPE. Furnish instruments and personnel required for the tests. The following must be provided at the job site for Government Final Testing:

a. The manufacturer's technical representative.

b. The contractor's Qualified Fire Protection Engineer (QFPE).

c. Marked-up red line drawings of the system as actually installed.

Government Final Tests will be witnessed by the Designated Fire Protection Engineer and Qualified Fire Protection Engineer (QFPE). At this time, all required tests noted in the paragraph "Minimum System Tests" must be repeated at their discretion.

3.7 MINIMUM SYSTEM TESTS

The system, including the aboveground piping and system components, must be tested to ensure that equipment and components function as intended. The aboveground interior piping systems and attached appurtenances subjected to system working pressure must be tested in accordance with NFPA 13.

3.7.1 Aboveground Piping

3.7.1.1 Hydrostatic Test

Aboveground piping must be hydrostatically tested in accordance with NFPA 13. There must be no drop in gauge pressure or visible leakage when the system is subjected to the hydrostatic test. The test pressure must be read from a gauge located at the low elevation point of the system or portion being tested.

3.7.1.2 Air Pressure Test

As specified in NFPA 13, an air pressure leakage test at 50 psi must be conducted for 24 hours. There must be no drop in gauge pressure in excess of 1.5 psi for the 24 hours. This air pressure test is in addition to the required hydrostatic test.

3.7.2 Dry Pipe Valve Trip Test

Each dry pipe valve must be trip-tested by reducing normal system nitrogen pressure through operation of the inspector's test connection. Systems equipped with quick-opening devices must first be tested without the operation of the quick-opening device and then with it in operation. Test results will be witnessed and recorded. Test results must include the number of seconds elapsed between the time the test valve is opened and tripping of the dry valve; trip-point nitrogen pressure of the dry pipe valve; water pressure prior to valve tripping; and number of seconds elapsed between time the inspector's test valve is opened and water reaches the orifice. The delivery of water from the dry pipe valve to the system test connection must not exceed 60 seconds, regardless of system size. Water delivery times must be measured starting at the normal nitrogen pressure on the system.

3.7.3 Main Drain Flow Test

Following flushing of the underground piping, a main drain test must be made to verify the adequacy of the water supply. Static and residual pressures must be recorded on the certificate specified in paragraph SUBMITTALS.

3.7.4 Supervisory Nitrogen System Test

System supervisory nitrogen pressure must be reduced from the normal system pressure to the point at which a low-pressure alarm is sounded. Nitrogen pressure must be restored to verify trouble signal restoration. Automatic start/stop features of nitrogen generator must be tested.

3.8 SYSTEM ACCEPTANCE

Following acceptance of the system, as-built drawings and O&M manuals must be delivered to the Contracting Officer for review and acceptance. Submit six sets of detailed as-built drawings. The drawings must show the system as installed, including deviations from both the project drawings and the approved shop drawings. These drawings must be submitted within two weeks after the final acceptance test of the system. At least one set of as-built (marked-up) drawings must be provided at the time of, or prior to the final acceptance test.

a. The drawings must be prepared electronically and sized no less than

the contract drawings. Furnish one set of PDFs and CDs or DVDs containing software back-up and CAD based drawings in latest version of AutoCAD, DXF and portable document formats of as-built drawings and schematics.

b. Provide operating and maintenance (O&M) instructions.

3.9 ONSITE TRAINING

Conduct a training course for the responding fire department and operating and maintenance personnel as designated by the Contracting Officer. Training must be performed on two separate days (to accommodate different shifts of Fire Department personnel) for a period of 4 hours of normal working time and must start after the system is functionally complete and after the final acceptance test. The on-site training must cover all of the items contained in the approved Operating and Maintenance Instructions.

-- End of Section --

SECTION 21 30 00

FIRE PUMPS
04/08, CHG 1: 08/13

PART 1 GENERAL

1.1 SUMMARY

Except as modified in this Section or on the drawings, install fire pumps in conformance with NFPA 20, NFPA 70, and NFPA 72. In the event of a conflict between specific provisions of this specification and applicable NFPA standards, this specification governs. Devices and equipment for fire protection service must be UL Fire Prot Dir listed or FM APP GUIDE approved. Interpret all reference to the authority having jurisdiction to mean the Contracting Officer or the Midlant Division, Naval Facilities Engineering Systems Command, Fire Protection Engineer for Navy projects.

1.2 SEQUENCING

1.2.1 Primary Fire Pump

Provide primary fire pump that automatically operates when the pressure drops to 108 psi , or manually when the starter is operated. Provide pump that automatically shut down after a running time of 10 minutes unless manually shutdown. The fire pump must automatically stop operating when the system pressure reaches 123 psi and after the fire pump has operated for the minimum pump run time specified herein.

1.2.2 Pressure Maintenance Pump

Operate pressure maintenance pump when the system pressure drops to 113 psi. Stop pump automatically when the system pressure reaches 123 psi and after the pump has operated for the minimum pump run time specified herein.

1.3 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.3	(2021) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.5	(2020) Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard
ASME B16.18	(2021) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.22	(2021) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.26	(2024) Cast Copper Alloy Fittings for Flared Copper Tubes

ASME B16.39 (2025) Malleable Iron Threaded Pipe Unions; Classes 150, 250, and 300

ASME B31.1 (2024) Power Piping

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C110/A21.10 (2021) Ductile-Iron and Gray-Iron Fittings

AWWA C111/A21.11 (2017) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings

AWWA C606 (2022) Grooved and Shouldered Joints

ASTM INTERNATIONAL (ASTM)

ASTM A47/A47M (1999; R 2022; E 2022) Standard Specification for Ferritic Malleable Iron Castings

ASTM A53/A53M (2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

ASTM A183 (2014; R 2020) Standard Specification for Carbon Steel Track Bolts and Nuts

ASTM A194/A194M (2024) Standard Specification for Carbon Steel, Alloy Steel, and Stainless Steel Nuts for Bolts for High-Pressure or High-Temperature Service, or Both

ASTM A449 (2014; R 2020) Standard Specification for Hex Cap Screws, Bolts, and Studs, Steel, Heat Treated, 120/105/90 ksi Minimum Tensile Strength, General Use

ASTM A536 (1984; R 2019; E 2019) Standard Specification for Ductile Iron Castings

ASTM A795/A795M (2021) Standard Specification for Black and Hot-Dipped Zinc-Coated (Galvanized) Welded and Seamless Steel Pipe for Fire Protection Use

ASTM B42 (2025) Standard Specification for Seamless Copper Pipe, Standard Sizes

ASTM B62 (2017; R 2025) Standard Specification for Composition Bronze or Ounce Metal Castings

ASTM B75/B75M (2020) Standard Specification for Seamless Copper Tube

ASTM B88 (2022) Standard Specification for Seamless Copper Water Tube

ASTM B135/B135M (2017) Standard Specification for Seamless Brass Tube

ASTM D2000	(2018; R 2024) Standard Classification System for Rubber Products in Automotive Applications
ASTM D3308	(2012; R 2022) Standard Specification for PTFE Resin Skived Tape
ASTM F436	(2011) Hardened Steel Washers

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 00001	(2024) Motors and Generators

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 20	(2025; TIA 25-1) Standard for the Installation of Stationary Pumps for Fire Protection
NFPA 24	(2022) Standard for the Installation of Private Fire Service Mains and Their Appurtenances
NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 72	(2025; TIA 25-1; TIA 25-2; TIA 25-3; TIA 25-4; ERTA 25-1; ERTA 25-2) National Fire Alarm and Signaling Code
NFPA 1963	(2019) Standard for Fire Hose Connections

UL SOLUTIONS (UL)

UL 448	(2025) UL Standard for Safety Centrifugal Stationary Pumps for Fire-Protection Service
UL Fire Prot Dir	(2012) Fire Protection Equipment Directory

1.4 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

The Midlant Division, Naval Facilities Engineering Systems Command, Fire Protection Engineer, will review and approve all submittals in this section requiring Government approval.

SD-01 Preconstruction Submittals

Fire Protection Specialist; G

No later than 14 days after the Notice to Proceed and prior to the submittal of the fire pump installation drawings

SD-02 Shop Drawings

Installation Drawings; G

As-Built Drawings; G

Piping Layout; G

Pump Room; G

SD-03 Product Data

Catalog Data; G

Spare Parts

Preliminary Tests

At least 14 days prior to the proposed date and time to begin Preliminary Tests

Field Tests; G

At least 2 weeks before starting field tests

Manufacturer's Representative; G

Field Training; G

Navy Formal Inspection and Tests

SD-06 Test Reports

Preliminary Tests

One copy of the completed Preliminary Tests Reports, no later that 7 days after the completion of the Preliminary Tests.

Navy Formal Inspection and Tests; G

SD-07 Certificates

Fire Protection Specialist

No later than 14 days after the Notice to Proceed and prior to the submittal of the fire pump installation drawings

Qualifications of Welders

Qualifications of Installer

Preliminary Test Certification

Final Test Certification

SD-10 Operation and Maintenance Data

Operating and Maintenance Instructions; G

At least 14 days prior to conducting field training

1.5 EXTRA MATERIALS

Submit Spare Parts data for each different item of equipment and material specified. Include a complete list of parts and supplies, with current unit prices and source of supply, and a list of parts recommended by the manufacturer to be replaced after 1 year and 3 years of service. Include a list of special tools and test equipment required for maintenance and testing of the products supplied by the Contractor.

1.6 QUALITY ASSURANCE

1.6.1 Fire Protection Specialist

The Fire Protection Specilaist in this section is the same as FPQC in Section 01 45 00. Wherever "Fire Protection Specialist" appears in this section substitute with "Fire Protection Quality Control Specialist (FPQC).

1.6.2 Qualifications of Welders

Submit certificates of each welder's qualifications prior to site welding; certifications more than one year old are not acceptable.

1.6.3 Qualifications of Installer

Prior to installation, submit data for approval showing that the Contractor has successfully installed fire pumps and associated equipment of the same type and design as specified herein, or that he has a firm contractual agreement with a subcontractor having such required experience. Include the names and locations of at least two installations where the Contractor, or the subcontractor referred to above, has installed such systems. Indicate the type and design of each system and certify that each system has performed satisfactorily in the manner intended for a period of not less than 18 months.

1.6.4 Preliminary Test Certification

When preliminary tests have been completed and corrections made, submit a signed and dated certificate with a request for a formal inspection and tests.

1.6.5 Final Test Certification

Concurrent with the Final Acceptance Test Report, submit certification by the Fire Protection Specialist that the fire pump installation is in accordance with the contract requirements, including signed approval of the Preliminary and Final Acceptance Test Reports.

1.6.6 Manufacturer's Representative

Perform work specified in this section under the supervision of and

certified by a representative of the fire pump manufacturer. Submit the name and documentation of certification of the proposed Manufacturer's Representative, concurrent with submittal of the Fire Protection Specialist Qualifications. Engage the Manufacturer's Representative regularly in the installation of the type and complexity of fire pump(s) specified in the Contract documents. The representative is an individual who has served in a similar capacity for at least three systems that have performed in the manner intended for a period of not less than 6 months.

1.7 DELIVERY, STORAGE, AND HANDLING

Protect all equipment delivered and placed in storage from the weather, excessive humidity and temperature variations, dirt and dust, or other contaminants. Additionally, either cap or plug all pipes until installed.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

a. Provide materials and equipment that are standard products of a manufacturer regularly engaged in the manufacture of such products and that essentially duplicates items that have been in satisfactory use for at least 2 years prior to bid opening.

b. Submit manufacturer's catalog data included with the Fire Pump Installation Drawings for each separate piece of equipment proposed for use in the system. Indicate the name of the manufacturer of each item of equipment, with data annotated to indicate model to be provided. In addition, provide a complete equipment list that includes equipment description, model number and quantity. Catalog data for material and equipment includes, but is not limited to, the following:

(1) Fire pumps, drivers and controllers including manufacturer's certified shop test characteristic curve for each pump. Shop test curve may be submitted after approval of catalog data but must be submitted prior to the final tests.

(2) Pressure maintenance pump and controller.

(3) Piping components.

(4) Valves, including gate, check, globe and relief valves.

(5) Gauges.

(6) Hose valve manifold test header and hose valves.

(7) Associated devices and equipment.

c. Provide a nameplate that identifies the manufacturer's name, address, type or style, model or serial number, and catalog number for all equipment. Affix standard nameplates securely in a conspicuous place and easy to read to pumps and motors. Provide nameplates and markings in accordance with UL 448. Provide electric motor nameplates with the minimum information required by NFPA 70, Section 430-7.

2.2 FIRE PUMP

Provide electric motor driven fire pump. Provide pump capacity rated at 750 gpm with a rated net pressure of 40 psi. Furnish no less than 150 percent of rated flow capacity at not less than 65 percent of rated net pressure. Provide centrifugal horizontal split case fire pump. Equip horizontal pump with automatic air release devices. Use maximum rated pump speed of 2100 rpm when driving the pump at rated capacity. Provide pump that is automatic start and automatic stop. Provide pump conforming to the requirements of UL 448. Ensure fire pump discharge and suction gauges are oil-filled type.

2.3 REQUIREMENTS FOR FIRE PROTECTION SERVICE

2.3.1 General Requirements

Provide Materials and Equipment that have been tested by Underwriters Laboratories, Inc. and are listed in UL Fire Prot Dir or approved by Factory Mutual and listed in FM APP GUIDE. Where the terms "listed" or "approved" appear in this specification, such means listed in UL Fire Prot Dir or FM APP GUIDE.

2.3.2 Alarms

Provide audible and visual alarms as required by NFPA 20 on the controller. Provide remote supervision as required by NFPA 20, in accordance with NFPA 72 under Section 28 31 76 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE. Activate alarm signal upon the following conditions: electric motor controller has operated into a pump running condition, loss of electrical power to electric motor starter, and phase reversal on line side of motor starter, and low temperature. Provide alarm silencing switch and red signal lamp, with signal lamp arranged to come on when switch is placed in OFF position.

2.4 UNDERGROUND PIPING COMPONENTS

2.4.1 Pipe and Fittings

Provide outside-coated, cement mortar-lined, ductile-iron pipe (with a rated working pressure of 175 psi) conforming to NFPA 24 for piping under the building and less than 5 feet outside of the building walls. Anchor the joints in accordance with NFPA 24; provide concrete thrust block at the elbow where the pipe turns up toward the floor, and restrain the pipe riser with steel rods from the elbow to the flange above the floor. Provide minimum pipe size of 6 inches. Provide minimum cover depth as required by NFPA 24, but no less than 3 feet. Piping more than 5 feet outside of the building walls must be provided under Section 33 11 00 WATER UTILITY DISTRIBUTION PIPING.

2.4.2 Fittings and Gaskets

Provide ductile iron fittings conforming to AWWA C110/A21.10. Provide gaskets that are suitable in design and size for the pipe with which such gaskets are to be used. Provide gaskets for ductile iron pipe joints conforming to AWWA C111/A21.11.

2.4.3 Buried Utility Warning and Identification Tape

Provide detectable aluminum foil plastic-backed tape or detectable

magnetic plastic tape manufactured specifically for warning and identification of buried piping for all buried piping. Ensure tape is detectable by an electronic detection instrument. Provide tape in rolls, 3 inches minimum width, color-coded for the utility involved and imprinted in bold black letters continuously and repeatedly over the entire tape length. Warning and identification must be "CAUTION BURIED WATER PIPING BELOW" or similar wording. Use permanent code and lettering that is unaffected by moisture and other substances contained in the trench backfill material. Bury tape at a depth of 12 inches below the top surface of earth or the top surface of the subgrade under pavement.

2.5 ABOVEGROUND PIPING COMPONENTS

2.5.1 Pipe Sizes 2.5 inches and Larger

2.5.1.1 Pipe

Provide piping consisting of ASTM A53/A53M, Weight Class STD (Standard), Schedule 40 (except for Schedule 30 for pipe sizes 8 inchesand greater in diameter), Type E or Type S, Grade A; black steel pipe. Join steel pipe by means of flanges welded to the pipe or mechanical grooved joints only. Do not join piping by welding or weld fittings. Plain-end fittings with mechanical couplings, fittings that use steel gripping devices to bite into the pipe, and segmented welded fittings are not permitted. Rubber gasketed groove-end pipe and fittings with mechanical couplings must be permitted in pipe sizes larger than 2-inches. Steel piping with wall thickness less than Schedule 30 must not be threaded. Side outlet tees using rubber gasketed fittings are not permitted. Galvanize suction piping on the inside in accordance with NFPA 20.

2.5.1.2 Grooved Mechanical Joints and Fittings

Provide joints and fittings that are designed for no less than 175 psi service and are the product of the same manufacturer. Provide malleable iron fitting and coupling houses conforming to ASTM A47/A47M, Grade 32510; ductile iron conforming to ASTM A536, Grade 65-45-12. Provide flush type gasket that fills the entire cavity between the fitting and the pipe. Provide cadmium plated or zinc electroplated, heat-treated steel nuts and bolts conforming to ASTM A183.

2.5.1.3 Flanges

Provide ASME B16.5, Class 150 flanges. Provide flanges at valves, connections to equipment, and where indicated.

2.5.1.4 Gaskets

Provide AWWA C111/A21.11, cloth inserted red rubber gaskets.

2.5.1.5 Bolts

Provide ASTM A449, Type 1 bolts. Do not extend bolts less than three full threads beyond the nut with bolts tightened to the required torque.

2.5.1.6 Nuts

Provide ASTM A194/A194M, Grade 7 nuts.

2.5.1.7 Washers

Provide washers meeting the requirements of ASTM F436. Provide flat circular washers under all bolt heads and nuts.

2.5.2 Piping Sizes 2 inches and Smaller

2.5.2.1 Steel Pipe

Provide ASTM A795/A795M, Weight Class STD (Standard), Schedule 40, Type E or Type S, Grade A, zinc-coated steel pipe with threaded end connections. Provide ASME B16.3, Class 150, zinc-coated threaded fittings. Provide ASME B16.39, Class 150, zinc-coated unions.

2.5.2.2 Copper Tubing

Provide copper tubing that is ASTM B88, Type L or K, soft annealed. Provide ASME B16.26, flared joint fittings. Provide pipe nipples consisting of ASTM B42 copper pipe with threaded end connections.

2.5.3 Pipe Hangers and Supports

Provide adjustable hangers and supports that are UL listed UL Fire Prot Dir or FM approved FM APP GUIDE. Finish of rods, nuts, washers, hangers, and supports must be zinc-plated after fabrication. Pipe hangers and supports must be provided in accordance with NFPA 20.

2.5.4 Valves

Provide valves that are UL listed UL Fire Prot Dir or FM approved FM APP GUIDE for fire protection service and with flange or threaded end connections.

2.5.4.1 Gate Valves and Control Valves

Provide outside screw and yoke (O.S.&Y.) type gate valves and control valves which open by counterclockwise rotation. Butterfly-type control valves are permitted in accordance with NFPA 20.

2.5.4.2 Tamper Switch

Equip the suction control valves, the discharge control valves, valves to test header and flow meter, and the by-pass control valves with valve tamper switches for monitoring by the fire alarm system.

2.5.4.3 Check Valve

Check valve must be clear open, swing type check valve with flange or threaded inspection plate.

2.5.4.4 Relief Valve

Provide pilot operated or spring operated type relief valve conforming to NFPA 20. Provide a means of detecting water motion in the relief lines where the discharge is not visible within the pump house.

2.5.4.5 Circulating Relief Valve

Provide an adjustable circulating relief valve for each fire pump in

accordance with NFPA 20.

2.5.5 Hose Valve Manifold Test Header

Construct linear test header of steel pipe. Provide ASME B16.5, Class 150 flanged inlet connection to hose valve manifold assembly. Provide approved bronze hose gate valve with 2.5 inch National Standard male hose threads with cap and chain; locate 3 feet above grade in the horizontal position for each test header outlet. Ensure welding is metallic arc process in accordance with ASME B31.1.

2.5.6 Pipe Sleeves

Provide a pipe sleeve at each location where piping passes entirely through walls, ceilings, roofs, and floors, including pipe entering buildings from the exterior. Secure sleeves in position and location during construction. Provide sleeves of sufficient length to pass through entire thickness of walls, ceilings, and floors. Provide one inch minimum clearance between exterior of piping or pipe insulation, and interior of sleeve or core-drilled hole. Firmly pack space with mineral wool insulation. Seal space at both ends of the sleeve or core-drilled hole with plastic waterproof cement which will dry to a firm but pliable mass, or provide a mechanically adjustable segmented elastomeric seal. In fire walls and fire floors, provide a fire seal between the pipe and the sleeve in accordance with Section 07 84 00 FIRESTOPPING.

a. Sleeves in Masonry and Concrete Walls, Ceilings, Roofs, and Floors: Provide hot-dip galvanized steel, ductile-iron, or cast-iron pipe sleeves. Core drilling of masonry and concrete may be provided in lieu of pipe sleeves provided that cavities in the core-drilled hole be completely grouted smooth.

b. Sleeves in Other Than Masonry and Concrete Walls, Ceilings, Roofs, and Floors: Provide galvanized steel sheet pipe not less than 0.90 psf.

2.5.7 Escutcheon Plates

Provide one-piece or split-hinge metal plates for piping entering floors, walls, and ceilings in exposed areas. Provide polished stainless steel or chromium-plated finish on copper alloy plates in finished spaces. Provide paint finish on plates in unfinished spaces. Secure plates in place.

2.6 ELECTRIC MOTOR DRIVER

Provide motors, controllers, contactors, and disconnects with their respective pieces of equipment, as specified herein and provide electrical connections under Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide controllers and contactors with a maximum of 120-volt control circuits, and auxiliary contacts for use with the controls furnished. When motors and equipment furnished are larger than sizes indicated, include the cost of providing additional electrical service and related work under this section. Provide motor conforming to NEMA MG 00001 Design B type. Provide premium efficiency type integral size motors in accordance with NEMA MG 00001. Provide motor horsepower of sufficient size so that the nameplate horsepower rating will not be exceeded throughout the entire published pump characteristic curve. The motor and fire pump controller must be fully compatible.

2.7 FIRE PUMP CONTROLLER

Provide automatic type controller which is UL listed UL Fire Prot Dir or FM approved FM APP GUIDE for fire pump service. Arrange pump for automatic start and stop, and manual push-button stop. Accomplish automatic stopping only after all starting causes have returned to normal and after a minimum pump run time has elapsed. Provide controllers that are completely terminally wired, ready for field connections, and mounted in a NEMA Type 2 drip-proof enclosure arranged so that controller current carrying parts will not be less than 12 inches above the floor. Provide controller with voltage surge arresters installed in accordance with NFPA 20. Equip controller with a bourdon tube pressure switch or a solid state pressure switch with independent high and low adjustments, automatic starting relay actuated from normally closed contacts, visual alarm lamps and supervisory power light. Equip controller with a thermostat switch with adjustable setting to monitor the pump room temperature and to provide an alarm when temperatures falls below 40 degrees F. Thermostat must be mounted on the exterior of the controller. Provide controller which is factory-equipped with a heater operated by thermostat to prevent moisture in the cabinet.

2.7.1 Controller for Electric Motor Driven Fire Pump

Controller must be electronic soft start starting type. Design controller for 25 HP at 208 volts. Provide controller with a short circuit rating of 10,000 amps r.m.s. symmetrical at 208 volts a.c. Controller must monitor pump running, loss of a phase or line power, phase reversal, and pump room temperature. Display alarms individually in front of panel by lighting of visual lamps. Label each lamp with rigid etched plastic labels. Equip controller with terminals for remote monitoring of pump running, pump power supply trouble (loss of power or phase and phase reversal), and pump room trouble (pump room temperature), and for remote start. Limited service fire pump controllers are not permitted, except for fire pumps driven by electric motors rated less than 15 hp. Equip controller with a 7-day electric pressure recorder with 24-hour spring wound back-up. Provide a readout of the system pressure from 0 to 15 hp, time, and date. Controller must require the pumps to run for ten minutes for pumps with driver motors under 200 horsepower and for 15 minutes for pumps with motors 200 horsepower and greater, prior to automatic shutdown. Automatic shutdown must occur after reaching the stop pressure and the expiration of the minimum run-timer. Equip the controller with an externally operable isolating switch which manually operates the motor circuit. Provide means in the controller for measuring current for all motor circuit conductors.

2.8 PRESSURE SENSING LINE

Provide a completely separate pressure sensing line for each fire pump and for the jockey pump. Arrange the sensing line in accordance with Figure A.4.32(a) of NFPA 20. Provide sensing line of 1/2 inchH58 brass tubing complying with ASTM B135/B135M. Equip the sensing line with two restrictive orifice unions each. Provide restricted orifice unions consisting of ground-face unions with brass restricted diaphragms drilled for a 3/32 inch. Mount restricted orifice unions in the horizontal position, no less than 5 feet apart on the sensing line. Provide two test connections for each sensing line. Test connections consist of two brass 1/2 inch globe valves and 1/4 inch gauge connection tee arranged in accordance with NFPA 20. Equip one of the test connections with a 0 to 300 psi water oil-filled gauge. Connect sensing line to the pump discharge piping between the discharge piping control valve and the check valve.

2.9 PRESSURE MAINTENANCE PUMP

2.9.1 General

Provide pressure maintenance pump that is electric motor driven, in-line vertical shaft, centrifugal type with a rated discharge of 10 gpm at 50 psig. Pump must draft from the suction supply side of the suction pipe gate valve of the fire pump and discharge into the system at the downstream side of the pump discharge gate valve. Provide an approved indicating gate valve of the outside screw and yoke (O.S.&Y.) type in the maintenance pump discharge and suction piping. Provide oil-filled water pressure gauge and approved check valve in the maintenance pump discharge piping. Provide swing type check valve with removable inspection plate.

2.9.2 Pressure Maintenance Pump Controller

Arrange pressure maintenance pump controller for automatic and manual starting and stopping and equip with a "manual-off-automatic" switch. Provide controller which is completely prewired, ready for field connections, and wall-mounted in a NEMA Type 2 drip-proof enclosure. Equip the controller with a bourdon tube pressure switch or a solid state pressure switch with independent high and low adjustments for automatic starting and stopping. Provide a sensing line connected to the pressure maintenance pump discharge piping between the control valve and the check valve. Provide sensing line conforming to paragraph, PRESSURE SENSING LINE. The sensing line must be completely separate from the fire pump sensing lines. Provide an adjustable run timer to prevent frequent starting and stopping of the pump motor. Set the run timer for 2 minutes.

2.10 JOINTS AND FITTINGS FOR COPPER TUBE

Provide wrought copper and bronze solder-joint pressure fittings conforming to ASME B16.22 and ASTM B75/B75M. Provide cast copper alloy solder-joint pressure conforming conform to ASME B16.18. Provide cast copper alloy fittings for flared copper tube conforming to ASME B16.26 and ASTM B62. Brass or bronze adapters for brazed tubing may be used for connecting tubing to flanges and to threaded ends of valves and equipment. Extracted brazed tee joints produced with an acceptable tool and installed as recommended by the manufacturer may be used. Provide grooved mechanical joints and fittings that are designed for no less than 125 psig service and are the product of the same manufacturer. Provide ductile iron grooved fitting and mechanical coupling housing conforming to ASTM A536. Use gaskets in grooved joints consisting of molded synthetic polymer of pressure responsive design and conforming to ASTM D2000 for circulating medium up to 239 degrees F. Provide grooved joints conforming to AWWA C606 Use steel coupling nuts and bolts in grooved joints conforming to ASTM A183.

2.11 PUMP BASE PLATE AND PAD

Provide a common base plate for the horizontal-shaft fire pump for mounting pump and driver unit. Construct the base plate of cast iron with raised lip tapped for drainage or welded steel shapes with suitable drainage. Provide each base plate for the horizontal fire pumps with a 1 inchgalvanized steel drain line piped to the nearest floor drain. For vertical shaft pumps, provide pump head with a cast-iron base plate which serves as the sole plate for mounting the discharge head assembly. Mount pump units and bases on a raised 6 inches reinforced concrete pad that is an integral part of the reinforced concrete floor.

2.12 HOSE VALVE MANIFOLD LINEAR TEST HEADER

Connect hose valve test header by ASME B16.5, Class 150 flange inlet connection. Provide UL listed UL Fire Prot Dir or FM approved FM APP GUIDE bronze hose gate valves with 2.5 inches American National Fire Hose Connection Screw Standard Threads (NH) in accordance with NFPA 1963. Provide number of valves in accordance with NFPA 20. Equip each hose valve with a cap and chain, and locate no more than 3 feet and no less than 2 feet above grade.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing the work.

3.2 INSPECTION BY FIRE PROTECTION SPECIALIST

Periodically perform a thorough inspection of the fire pump installation, including visual observation of the pump while running, to assure that the installation conforms to the contract requirements. Excessive vibration, leaks (oil or water), unusual noises, overheating, or other potential problems are not acceptable. Inspection includes piping and equipment clearance, access, supports, and guards. Bring any discrepancy to the attention of the Contracting Officer in writing, no later than three working days after the discrepancy is discovered. The Fire Protection Specialist must witness the preliminary and final acceptance tests and, after completion of the inspections and a successful final acceptance test, sign test results and certify in writing that the installation the fire pump installation is in accordance with the contract requirements.

3.3 INSTALLATION

Provide equipment, materials, workmanship, fabrication, assembly, erection, installation, examination, inspection and testing in accordance NFPA 20, except as modified herein. In addition, install the fire pump and engine in accordance with the written instructions of the manufacturer.

3.3.1 Installation Drawings

Submit Fire Pump Installation Drawings consisting of a detailed plan view, detailed elevations and sections of the pump room, equipment and piping, drawn to a scale of not less than 1/2 inch = 1 foot. Indicate equipment, piping, and associated pump equipment to scale. Indicate all clearance, such as those between piping and equipment; between equipment and walls, ceiling and floors; and for electrical working distance clearance around all electrical equipment. Include a legend identifying all symbols, nomenclatures, and abbreviations. Indicate a complete piping and equipment layout including elevations and/or section views of the following:

a. Fire pumps, controllers, piping, valves, and associated equipment.

b. Sensing line for each pump including the pressure maintenance pump.

c. Restraint of underground water main at entry-and exit-points to the

building including details of pipe clamps, tie rods, mechanical retainer glands, and thrust blocks.

d. A one-line schematic diagram indicating layout and sizes of all piping, devices, valves and fittings.

e. A complete point-to-point connection drawing of the pump power, control and alarm systems, as well as interior wiring schematics of each controller.

3.3.2 Pump Room Configuration

Provide detail plan view of the pump room including elevations and sections showing the fire pumps, associated equipment, and piping. Submit working drawings on sheets not smaller than 24 by 36 inches; include data for the proper installation of each system. Show piping schematic of pumps, devices, valves, pipe, and fittings. Show point to point electrical wiring diagrams. Show piping layout and sensing piping arrangement. Include:

a. Pumps, drivers, and controllers

b. Hose valve manifold test header

c. Circuit diagrams for pumps

d. Wiring diagrams of each controller

3.3.3 Accessories

Furnish tank supports, piping offsets, fittings, and required accessories as specified to provide a complete installation and to eliminate interference with other construction.

3.4 PIPE AND FITTINGS

Piping must be inspected, tested and approved before burying, covering, or concealing. Provide fittings for changes in direction of piping and for all connections. Make changes in piping sizes using tapered reducing pipe fittings. Do not use bushings.

3.4.1 Cleaning of Piping

Interior and ends of piping must be clean and free of any water or foreign material. Keep piping clean during installation by means of plugs or other approved methods. When work is not in progress, securely close open ends of the piping so that no water or foreign matter will enter the pipes or fittings. Inspect piping before placing in position.

3.4.2 Threaded Connections

Provide jointing compound for pipe threads consisting of polytetrafluoroethylene (PTFE) pipe thread tape conforming to ASTM D3308 and apply to male threads only. Provide exposed ferrous pipe threads with one coat of zinc molybdate primer applied to a minimum of dry film thickness of 1 mil.

3.4.3 Pipe Hangers and Supports

Provide additional hangers and supports for concentrated loads in aboveground piping, such as for valves and risers.

3.4.3.1 Vertical Piping

Support piping at each floor, at no more than 10 foot intervals.

3.4.3.2 Horizontal Piping

Space horizontal piping supports as follows:

MAXIMUM SPACING (FEET)										
Nominal Pipe Size (inches)	1 and Under	1.25	1.5	2	2.5	3	3.5	4	5	6+
Copper Tube	6	7	8							
Steel Pipe	7	8	9	10	11	12	13	14	16	17

3.4.4 Underground Piping

Install underground piping and fittings in conformance to NFPA 24. Anchor joints in accordance with NFPA 24. Provide concrete thrust block at elbow where pipe turns up towards floor, and restrain the pipe riser with steel rods from the elbow to the flange above the floor. After installation in accordance with NFPA 24, clean rods and nuts thoroughly and coat with asphalt or other corrosion-retard material approved by the Contracting Officer. Provide minimum cover depth of 3 feet.

3.4.5 Grooved Mechanical Joint

Prepare grooves according to the coupling manufacturer's instructions. Use grooved fittings, couplings, and grooving tools which are products of the same manufacturer. Ensure pipe and groove dimensions comply with the tolerances specified by the coupling manufacturer. Measure the diameter of grooves made in the field using a "go/no-go" gauge, vernier or dial caliper, narrow-land micrometer, or other method specifically approved by the coupling manufacturer for the intended application. Measure groove width and dimension of groove from end of pipe for each change in grooving tool setup to verify compliance with coupling manufacturer's tolerances. Do not use grooved joints in concealed locations, such as behind solid walls or ceilings, unless an access panel is shown on the drawings for servicing or adjusting the joint.

3.4.6 Identification Signs

Signs must be affixed to each valve as required by NFPA 13 including the fire pump test header. Valve identification signs must be minimum 6

inches wide by 2 inches high with enamel baked finish on a minimum 18 gauge steel or 0.024 inch aluminum with red letters on a white background or white letters on a red background.

3.5 ELECTRICAL WORK

Provide electric motor and controls in accordance with NFPA 20, NFPA 72 and NFPA 70, unless more stringent requirements are specified herein or are indicated on the drawings. Provide electrical wiring and associated equipment in accordance with NFPA 20 and Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide wiring in rigid metal conduit or intermediate metal conduit, except electrical metallic tubing conduit may be provided in dry locations not enclosed in concrete or where not subject to mechanical damage.

3.6 PIPE COLOR CODE MARKING

Color code marking of piping as specified in Section 09 90 00 PAINTS AND COATINGS.

3.7 FLUSHING

Flush the fire pump suction and discharge piping at 150 percent of rated capacity of each pump. Where the pump installation consists of more than one pump, the flushing is the total quantity of water flowing when all pumps are discharging at 150 percent of their rated capacities. The new pumps may be used to attain the required flushing volume. Do not flush underground piping using the fire pumps. Continue flushing operations until water is clear, but no less than 10 minutes. Submit a signed and dated flushing certificate before requesting field testing.

3.8 FIELD TESTS

Submit system diagrams that show the layout of equipment, piping, and storage units, and typed condensed sequence of operation, wiring and control diagrams, and operation manuals explaining preventative maintenance procedures, methods of checking the system for normal, safe operation, and procedures for safely starting and stopping the system must be framed under glass or laminated plastic. After approval, post these items where directed.

3.8.1 Hydrostatic Test

Hydrostatically test piping at 225 psigfor a period of 2-hours, or at least 50 psiin excess of the maximum pressure, when the maximum pressure in the system is in excess of 175 psi in accordance with NFPA 20.

3.8.2 Preliminary Tests

Submit proposed procedures for Preliminary Tests prior to the proposed date and time to begin Preliminary Tests. The Manufacturer's Representative must take all readings and measurements. The Manufacturer's Representative, a representative of the fire pump controller manufacturer, must witness the complete operational testing of the fire pump and drivers. The fire pump controller manufacturer's representative must be an experienced technician employed by the respective manufacturers and capable of demonstrating operation of all features of respective components including trouble alarms and operating features. Thoroughly inspect and test fire pumps, drivers and equipment

to insure that the system is correct, complete, and ready for operation. Ensure that pumps are operating at rated capacity, pressure and speed. Include manual starting and running to ensure proper operation and to detect leakage or other abnormal conditions, flow testing, automatic start testing, testing of automatic settings, sequence of operation check, test of required accessories; test of pump alarms devices and supervisory signals, operational test of relief valves, and test of automatic power transfer, if provided. Pumps must run without abnormal noise, vibration or heating. If any component or system was found to be defective, inoperative, or not in compliance with the contract requirements during the tests and inspection, make corrections and repeat the entire preliminary. Submit Preliminary Tests Reports, to include both the Contractor's Material and Test Certificate for Underground Piping and the Contractor's Material and Test Certificate for Aboveground Piping. All items in the Report must be signed by the Fire Protection Specialist and the Manufacturer's Representative.

3.8.3 Navy Formal Inspection and Tests

The Midlant Division, Naval Facilities Engineering Systems Command, Fire Protection Engineer will witness formal tests and approve all systems before they are accepted. Submit the request for formal inspection at least 15 days prior to the date the inspection is to take place. An experienced technician regularly employed by the pump installer must be present during the inspection. Where pumps are engine driven, an experienced technician regularly employed by the engine manufacturer capable of demonstrating that all engine trouble alarms and operating features perform as required must be present. Submit proposed date and time to begin Navy Formal Inspection and Tests, with the Acceptance Procedures. Provide notification at least 14 days prior to the proposed start of the test. Include a copy of the Contractor's Material & Test Certificates. Submit one copy of the completed Navy Formal Inspection and Tests Reports, no later that 7 days after the completion of the tests. All items in the reports must be signed by the Fire Protection Specialist and the Manufacturer's Representative. Test reports in booklet form (each copy furnished in a properly labeled three ring binder) showing all field tests and measurements taken during the preliminary and final testing, and documentation that proves compliance with the specified performance criteria, upon completion of the installation and final testing of the installed system. Indicate the final position of the controls and pressure switches in each test report. Include the description of the hydrostatic test conducted on the piping and flushing of the suction and discharge piping. Include a copy of the manufacturer's certified pump curve for each fire pump in the report.

3.8.3.1 Full Water Flow Test

Include a full water flow test in the acceptance test. The securing of all hoses and nozzles during the tests is the responsibility of the Contractor. Conduct water flow testing in a safe manner with no destruction to the existing facility or new construction. Tests include 100 and 150 percent capacity flows and pressures, and no-flow pressures for compliance with manufacturer's characteristic curves. At this inspection repeat the required tests as directed.

3.8.3.2 Correcting Defects

Correct defects in the work, and make additional tests until the Contractor has demonstrated that the system complies with the contract

requirements.

3.8.3.3 Documentation of Test

Manufacturer's certified shop test characteristic curves for each pump being tested must be furnished by the Contractor at the time of the pump acceptance test.

3.8.4 Test Equipment

Provide all equipment and instruments necessary to conduct a complete final test, including 2.5 inch diameter hoses, playpipe nozzles, pitot tube gauges, portable digital tachometer, voltage and ampere meters, and calibrated oil-filled water pressure gauges. Provide all necessary supports to safely secure hoses and nozzles during the test. The Government will furnish water for the tests.

3.9 SYSTEM STARTUP

Fully enclose or properly guard coupling, rotating parts, gears, projecting equipment, etc. so as to prevent possible injury to persons that come in close proximity of the equipment. Conduct testing of the fire pumps in a safe manner and ensure that all equipment is safely secured. Use hoses and nozzles to conduct flow tests that are in excellent condition and safely anchor and secure to prevent any misdirection of the hose streams.

Post operating instructions for pumps, drivers, controllers, and flow meters.

3.10 CLOSEOUT ACTIVITIES

3.10.1 Field Training

Conduct a training course for operating and maintenance personnel as designated by the Contracting Officer. Submit the proposed schedule for field training at least 14 days prior to the start of related training. Provide training for a period of 8 hours of normal working time and start after the fire pump installation is functionally complete and after the Final Acceptance Test. Cover all of the items contained in the approved Operating and Maintenance Instructions. Submit manuals listing step-by-step procedures required for system startup, operation, shutdown, and routine maintenance. Include the manufacturer's name, model number, parts list, list of parts and tools that should be kept in stock by the owner for routine maintenance including the name of a local supplier, simplified wiring and controls diagrams, troubleshooting guide, and recommended service organization (including address and telephone number) for each item of equipment. Submit Data Package 3 for fire pumps and drivers in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA. Submit service organization that is capable of providing 4 hour onsite response to a service call on an emergency basis.

3.10.2 As-Built Drawings

Submit As-Built Drawings, no later than 14 days after completion of the Final Tests. Update the Fire Pump Installation Drawings to reflect as-built conditions after all related work is completed and prepare drawings on reproducible full-size mylar film.

3.11 PROTECTION

Carefully remove materials so as not to damage material which is to remain. Replace existing work damaged by the Contractor's operations with new work of the same construction.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 22 00 00

PLUMBING, GENERAL PURPOSE
05/24, CHG 1: 11/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

ANSI/AHRI 1160 I-P	(2022) Performance Rating of Heat Pump Pool Heaters

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z21.10.1/CSA 4.1	(2019; R 2024) Gas Water Heaters Vol. I, Storage Water Heaters with Input Ratings of 75,000 Btu Per Hour or Less
ANSI Z21.10.3/CSA 4.3	(2019; R 2024) Gas-Fired Water Heaters Vol.III, Storage Water Heaters With Input Ratings Above 75,000 Btu Per Hour, Circulating and Instantaneous
ANSI Z21.22/CSA 4.4	(2015; R 2020) Relief Valves for Hot Water Supply Systems

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ANSI/ASHRAE 18	(2008; R 2013) Methods Of Testing For Rating Drinking Water Coolers With Self-Contained Mechanical Refrigeration
ASHRAE 146	(2020) Method of Testing and Rating Pool Heaters (ANSI Approved)

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME A112.1.2	(2012; R 2017; R 2022) Air Gaps in Plumbing Systems (For Plumbing Fixtures and Water-Connected Receptors)
ASME A112.6.1M	(1997; R 2017) Floor Affixed Supports for Off-the-Floor Plumbing Fixtures for Public Use
ASME A112.6.3	(2022) Floor Drains
ASME A112.14.1	(2003; R 2017; R 2022) Backwater Valves
ASME A112.19.2/CSA B45.1	(2024) Standard for Vitreous China Plumbing Fixtures and Hydraulic

	Requirements for Water Closets and Urinals
ASME A112.19.3/CSA B45.4	(2022) Stainless Steel Plumbing Fixtures
ASME A112.19.5	(2022) Flush Valves and Spuds for Water Closets, Urinals, and Tanks
ASME A112.36.2M	(2022) Cleanouts
ASME B1.20.1	(2013; R 2018) Pipe Threads, General Purpose (Inch)
ASME B16.5	(2020) Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard
ASME B16.15	(2024) Cast Copper Alloy Threaded Fittings Classes 125 and 250
ASME B16.18	(2021) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.22	(2021) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.34	(2021) Valves - Flanged, Threaded and Welding End
ASME B16.50	(2021) Wrought Copper and Copper Alloy Braze-Joint Pressure Fittings
ASME B31.1	(2024) Power Piping
ASME B31.5	(2022) Refrigeration Piping and Heat Transfer Components
ASME B40.100	(2022) Pressure Gauges and Gauge Attachments
ASME BPVC SEC IV	(2017) BPVC Section IV-Rules for Construction of Heating Boilers
ASME CSD-1	(2024) Control and Safety Devices for Automatically Fired Boilers

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

ASSE 1001	(2021) Performance Requirements for Atmospheric Type Vacuum Breakers
ASSE 1003	(2020) Performance Requirements for Water Pressure Reducing Valves for Domestic Water Distribution Systems - (ANSI approved 2010)
ASSE 1010	(2021) Performance Requirements for Water Hammer Arresters
ASSE 1011	(2017) Performance Requirements for Hose Connection Vacuum Breakers

ASSE 1012	(2023) Performance Requirements for Backflow Preventer with an Intermediate Atmospheric Vent
ASSE 1013	(2021) Performance Requirements for Reduced Pressure Principle Backflow Prevention Assemblies
ASSE 1016	(2017) Performance Requirements for Automatic Compensating Valves for individual Showers and Tub/Shower Combinations
ASSE 1017	(2023) Performance Requirements for Temperature Actuated Mixing Valves for Hot Water Distribution Systems - (ANSI approved 2010)
ASSE 1018	(2023) Performance Requirements for Trap Seal Primer Valves - Potable Water Supplied (ANSI Approved 2002
ASSE 1019	(2023) Performance Requirements for Wall Hydrant with Backflow Protection and Freeze Resistance
ASSE 1020	(2020; R 2025) Performance Requirements for Pressure Vacuum Breaker Assemblies
ASSE 1037	(2015; R 2020) Performance Requirements for Pressurized Flushing Devices for Plumbing Fixtures
ASSE 1044	(2023) Performance Requirements for Trap Seal Primer - Drainage Types and Electric Design Types
ASSE 1069	(2020) Performance Requirements for Automatic Temperature Control Mixing Valves
ASSE 1070	(2020) Performance Requirements for Water Temperature Limiting Devices

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA 10084	(2017) Standard Methods for the Examination of Water and Wastewater
AWWA B300	(2024) Hypochlorites
AWWA B301	(2024) Liquid Chlorine
AWWA C203	(2025) Coal-Tar Protective Coatings and Linings for Steel Water Pipe and Fittings
AWWA C651	(2023) Standard for Disinfecting Water Mains

AWWA C652 (2019) Disinfection of Water-Storage Facilities

AWWA C700 (2020) Cold-Water Meters - Displacement Type, Metal Alloy Main Case

AWWA C701 (2019) Cold-Water Meters - Turbine Type for Customer Service

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8/A5.8M (2019) Specification for Filler Metals for Brazing and Braze Welding

AWS B2.2/B2.2M (2016) Specification for Brazing Procedure and Performance Qualification

ASTM INTERNATIONAL (ASTM)

ASTM A105/A105M (2023) Standard Specification for Carbon Steel Forgings for Piping Applications

ASTM A193/A193M (2025) Standard Specification for Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service and Other Special Purpose Applications

ASTM A515/A515M (2017; R2022) Standard Specification for Pressure Vessel Plates, Carbon Steel, for Intermediate- and Higher-Temperature Service

ASTM A516/A516M (2017) Standard Specification for Pressure Vessel Plates, Carbon Steel, for Moderate- and Lower-Temperature Service

ASTM A733 (2016; R 2022) Standard Specification for Welded and Seamless Carbon Steel and Austenitic Stainless Steel Pipe Nipples

ASTM B32 (2020) Standard Specification for Solder Metal

ASTM B88 (2022) Standard Specification for Seamless Copper Water Tube

ASTM B88M (2020) Standard Specification for Seamless Copper Water Tube (Metric)

ASTM B117 (2019) Standard Practice for Operating Salt Spray (Fog) Apparatus

ASTM B370 (2022) Standard Specification for Copper Sheet and Strip for Building Construction

ASTM B584 (2022) Standard Specification for Copper Alloy Sand Castings for General Applications

ASTM B813	(2024) Standard Specification for Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube
ASTM B828	(2023) Standard Practice for Making Capillary Joints by Soldering of Copper and Copper Alloy Tube and Fittings
ASTM C564	(2020a) Standard Specification for Rubber Gaskets for Cast Iron Soil Pipe and Fittings
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM D638	(2014) Standard Test Method for Tensile Properties of Plastics
ASTM D1004	(2021) Initial Tear Resistance of Plastic Film and Sheeting
ASTM D1248	(2016) Standard Specification for Polyethylene Plastics Extrusion Materials for Wire and Cable
ASTM D2564	(2020) Standard Specification for Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems
ASTM D2665	(2014) Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Drain, Waste, and Vent Pipe and Fittings
ASTM D2855	(2020) Standard Practice for the Two-Step (Primer and Solvent Cement) Method of Joining Poly (Vinyl Chloride) (PVC) or Chlorinated Poly (Vinyl Chloride) (CPVC) Pipe and Piping Components with Tapered Sockets
ASTM D3138	(2004; R 2016) Standard Specification for Solvent Cements for Transition Joints Between Acrylonitrile-Butadiene-Styrene (ABS) and Poly(Vinyl Chloride) (PVC) Non-Pressure Piping Components
ASTM D3139	(2019) Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals
ASTM D3212	(2020) Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals
ASTM D3311	(2017) Standard Specification for Drain, Waste, and Vent (DWV) Plastic Fittings Patterns
ASTM D4551	(2017) Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic

	Flexible Concealed Water-Containment Membrane
ASTM D4586/D4586M	(2007; R 2018) Standard Specification for Asphalt Roof Cement, Asbestos-Free
ASTM E1	(2014; R 2025) Standard Specification for ASTM Liquid-in-Glass Thermometers
ASTM E96/E96M	(2024a) Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials
ASTM F409	(2022) Standard Specification for Thermoplastic Accessible and Replaceable Plastic Tube and Tubular Fittings
ASTM F477	(2014; R 2021) Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe
ASTM F891	(2024) Standard Specification for Coextruded Poly (Vinyl Chloride) (PVC) Plastic Pipe with a Cellular Core
ASTM F1760	(2016; R 2025) Standard Specification for Coextruded Poly(Vinyl Chloride) (PVC) Non-Pressure Plastic Pipe Having Reprocessed-Recycled Content

COPPER DEVELOPMENT ASSOCIATION (CDA)

CDA A4015	(2016; 14/17) Copper Tube Handbook

INTERNATIONAL CODE COUNCIL (ICC)

ICC A117.1	(2017) Standard And Commentary Accessible and Usable Buildings and Facilities
ICC IPC	(2024) International Plumbing Code

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-25	(2018) Standard Marking System for Valves, Fittings, Flanges and Unions
MSS SP-58	(2025) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation
MSS SP-67	(2022) Butterfly Valves
MSS SP-70	(2011) Gray Iron Gate Valves, Flanged and Threaded Ends
MSS SP-71	(2018) Gray Iron Swing Check Valves, Flanged and Threaded Ends

MSS SP-72 (2010a) Ball Valves with Flanged or Butt-Welding Ends for General Service

MSS SP-78 (2011) Cast Iron Plug Valves, Flanged and Threaded Ends

MSS SP-80 (2019) Bronze Gate, Globe, Angle, and Check Valves

MSS SP-85 (2011) Gray Iron Globe & Angle Valves Flanged and Threaded Ends

MSS SP-110 (2010) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250 (2020) Enclosures for Electrical Equipment (1000 Volts Maximum)

NEMA MG 00001 (2024) Motors and Generators

NEMA MG 11 (1977; R 2012) Energy Management Guide for Selection and Use of Single Phase Motors

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 54 (2024) National Fuel Gas Code

NFPA 90A (2024) Standard for the Installation of Air Conditioning and Ventilating Systems

NSF INTERNATIONAL (NSF)

NSF 372 (2022) Drinking Water System Components - Lead Content

NSF/ANSI 14 (2024) Plastics Piping System Components and Related Materials

NSF/ANSI/CAN 61 (2024) Drinking Water System Components - Health Effects

PLASTIC PIPE AND FITTINGS ASSOCIATION (PPFA)

PPFA Fire Man (2016) Firestopping: Plastic Pipe in Fire Resistive Construction

PLUMBING AND DRAINAGE INSTITUTE (PDI)

PDI WH 201 (2010) Water Hammer Arresters Standard

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE J1508 (2023) Hose Clamp Specifications

U.S. DEPARTMENT OF ENERGY (DOE)

Energy Star	Energy Star Energy Efficiency Labeling System (FEMP)

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

PL 93-523	(1974; A 1999) Safe Drinking Water Act

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

10 CFR 430	Energy Conservation Program for Consumer Products
21 CFR 175	Indirect Food Additives: Adhesives and Components of Coatings
40 CFR 141.80	National Primary Drinking Water Regulations; Control of Lead and Copper; General Requirements

UL SOLUTIONS (UL)

UL 174	(2004; Reprint Nov 2024) UL Standard for Safety Household Electric Storage Tank Water Heaters
UL 399	(2017; Reprint May 2019) UL Standard for Safety Drinking Water Coolers
UL 499	(2014; Reprint Feb 2025) UL Standard for Safety Electric Heating Appliances
UL 1951	(2025) UL Standard for Safety Electric Plumbing Accessories

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Plumbing System; G

SD-03 Product Data

Backflow Prevention Assemblies; G

Fixtures

Shower Faucets; G

Flush Valve Water Closets

Flush Valve Urinals

Wall Hung Lavatories

Integral Lavatories

Kitchen Sinks

Water Heaters; G

Energy Star Label for Gas Storage Water Heater; S

Pumps; G

Vibration-Absorbing Features; G

Plumbing System

Thermostatic Mixing Valves

Temperature Controlled Mixing Valve

Point-Of-Use Mixing Valve

Automatic Temperature and Pressure Compensating Valve

Single Supply Line Automatic Temperature Control

SD-06 Test Reports

Tests, Flushing and Disinfection

Test of Backflow Prevention Assemblies; G.

SD-07 Certificates

Bolts

SD-10 Operation and Maintenance Data

Plumbing System; G

1.3 SHOP DRAWINGS

Submit Plumbing System Detail drawings consisting of schedules, performance charts, instructions, diagrams, and other information to illustrate the requirements and operations of systems that are not covered by the Plumbing Code. Submit Plumbing System Detail drawings for the complete plumbing system including piping layouts and locations of connections; dimensions for roughing-in, foundation, and support points; schematic diagrams and wiring diagrams or connection and interconnection diagrams. Detail drawings must indicate clearances required for maintenance and operation. Where piping and equipment are to be supported other than as indicated, details must include loadings and proposed support methods. Mechanical drawing plans, elevations, views, and details, must be drawn to scale.

1.4 STANDARD PRODUCTS

Specified equipment must essentially duplicate equipment that has performed satisfactorily at least 2 years prior to bid opening. Standard

products must have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year use must include applications of equipment and materials under similar circumstances and of similar size. The product must have been for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2 year period.

Where equipment is specified to conform to requirements of the ASME Boiler and Pressure Vessel Code, the design, fabrication, and installation must conform to the code and a certificate must be submitted for the equipment.

1.4.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturer's factory or laboratory tests, can be shown.

1.4.2 Service Support

The equipment items must be supported by service organizations. Submit a certified list of qualified permanent service organizations for support of the equipment which includes their addresses and qualifications. These service organizations must be reasonably convenient to the equipment installation and able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.4.3 Manufacturer's Nameplate

Each item of equipment must have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

1.4.4 Modification of References

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction", or words of similar meaning, to mean the Contracting Officer.

1.4.4.1 Definitions

For the International Code Council (ICC) Codes referenced in the contract documents, advisory provisions must be considered mandatory, the word "should" must be interpreted as "must." Reference to the "code official" must be interpreted to mean the "Contracting Officer." For Navy owned property, references to the "owner" must be interpreted to mean the "Contracting Officer." For leased facilities, references to the "owner" must be interpreted to mean the "lessor." References to the "permit holder" must be interpreted to mean the "Contractor."

1.4.4.2 Administrative Interpretations

For ICC Codes referenced in the contract documents, the provisions of Chapter 1, "Administrator," do not apply. These administrative requirements are covered by the applicable Federal Acquisition Regulations (FAR) included in this contract and by the authority granted to the

Officer in Charge of Construction to administer the construction of this project. References in the ICC Codes to sections of Chapter 1, must be applied appropriately by the Contracting Officer as authorized by his administrative cognizance and the FAR.

1.5 DELIVERY, STORAGE, AND HANDLING

Handle, store, and protect equipment and materials to prevent damage before and during installation in accordance with the manufacturer's recommendations, and as approved by the Contracting Officer. Replace damaged or defective items.

1.6 REGULATORY REQUIREMENTS

Unless otherwise required herein, plumbing work must be in accordance with ICC IPC.

1.7 PROJECT/SITE CONDITIONS

The Contractor must become familiar with details of the work, verify dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

1.8 INSTRUCTION TO GOVERNMENT PERSONNEL

Furnish the services of competent instructors to give full instruction to the designated Government personnel in the adjustment, operation, and maintenance, including pertinent safety requirements, of the specified equipment or system. Instructors must be thoroughly familiar with all parts of the installation and must be trained in operating theory as well as practical operation and maintenance work. Submit Plumbing System Operation and Maintenance Data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

Instruction must be given during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished must be as specified in the individual section. When more than 4 man-days of instruction are specified, use approximately half of the time for classroom instruction. Use other time for instruction with the equipment or system. When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instruction to acquaint the operating personnel with the changes or modifications.

1.9 ACCESSIBILITY OF EQUIPMENT

Install all work so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible. Install concealed valves, expansion joints, controls, dampers, and equipment requiring access, in locations freely accessible through access doors.

PART 2 PRODUCTS

2.1 MATERIALS

Materials for various services must be in accordance with TABLES I and II.
Pipe schedules must be selected based on service requirements. Pipe fittings must be compatible with the applicable pipe materials. Plastic

pipe, fittings, and solvent cement must meet NSF/ANSI 14 and must be NSF listed for the service intended. . Material or used in any potable water system intended for human consumption be certified in accordance with NSF 372 with the exception of brazing materials. In line devices such as water meters, building valves, check valves, meter stops, valves, fittings and back flow preventers must comply with PL 93-523 and NSF/ANSI/CAN 61, Section 8. End point devices such as drinking water fountains, lavatory faucets, kitchen and bar faucets, residential ice makers, supply stops and end point control valves used to dispense water for drinking must meet the requirements of NSF/ANSI/CAN 61, Section 9. Plastic pipe must not be installed in air plenums. Plastic pipe must not be installed in a pressure piping system in buildings greater than three stories including any basement levels.

2.1.1 Pipe Joint Materials

Solder containing lead must not be used with copper pipe. Joints and gasket materials must conform to the following:

a. Brazing Material: Brazing material must conform to AWS A5.8/A5.8M, BCuP-5.

b. Brazing Flux: Flux must be in paste or liquid form appropriate for use with brazing material. Flux must be as follows: lead-free; have a 100 percent flushable residue; contain slightly acidic reagents; contain potassium borides; and contain fluorides.

c. Solder Material: Solder metal must conform to ASTM B32.

d. Solder Flux: Flux must be liquid form, non-corrosive, and conform to ASTM B813, Standard Test 1.

e. PTFE Tape: PTFE Tape, for use with Threaded Metal or Plastic Pipe.

f. Flexible Elastomeric Seals: ASTM D3139, ASTM D3212 or ASTM F477.

g. Solvent Cement for Transition Joints between ABS and PVC Nonpressure Piping Components: ASTM D3138.

h. Plastic Solvent Cement for PVC Plastic Pipe: ASTM D2564 and ASTM D2855.

i. Flanged fittings including, but not limited to, flanges, bolts, nuts and bolt patterns must be in accordance with ASME B16.5 class 150 and must have the manufacturer's trademark affixed in accordance with MSS SP-25. Flange material must conform to ASTM A105/A105M. Blind flange material must conform to ASTM A516/A516M cold service and ASTM A515/A515M for hot service. Bolts must be high strength or intermediate strength with material conforming to ASTM A193/A193M. Submit written certification by the bolt manufacturer that the bolts furnished comply with the specified requirements.

j. Copper tubing must conform to ASTM B88, Type K, L or M.

2.1.2 Miscellaneous Materials

Miscellaneous materials must conform to the following:

a. Water Hammer Arrester: PDI WH 201. Water hammer arrester must be diaphragm or piston type.

b. Copper, Sheet and Strip for Building Construction: ASTM B370.

c. Asphalt Roof Cement: ASTM D4586/D4586M.

d. Hose Clamps: SAE J1508.

e. Supports for Off-The-Floor Plumbing Fixtures: ASME A112.6.1M.

f. Metallic Cleanouts: ASME A112.36.2M.

g. Plumbing Fixture Setting Compound: A preformed flexible ring seal molded from hydrocarbon wax material. The seal material must be nonvolatile nonasphaltic and contain germicide and provide watertight, gastight, odorproof and verminproof properties.

h. Coal-Tar Protective Coatings and Linings for Steel Water Pipelines: AWWA C203.

i. Hypochlorites: AWWA B300.

j. Liquid Chlorine: AWWA B301.

k. Gauges - Pressure and Vacuum Indicating Dial Type - Elastic Element: ASME B40.100.

l. Thermometers: ASTM E1. Mercury must not be used in thermometers.

2.1.3 Pipe Insulation Material

Insulation must be as specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.2 PIPE HANGERS, INSERTS, AND SUPPORTS

Pipe hangers, inserts, and supports must conform to MSS SP-58.

2.3 VALVES

Valves must be provided on supplies to equipment and fixtures. Valves 2-1/2 inches and smaller must be bronze with threaded bodies for pipe and solder-type connections for tubing. Valves 3 inches and larger must have flanged iron bodies and bronze trim. Pressure ratings must be based upon the application. Grooved end valves may be provided if the manufacturer certifies that the valves meet the performance requirements of applicable MSS standard." Valves must conform to the following standards:

Description	Standard
Butterfly Valves	MSS SP-67

Cast-Iron Gate Valves, Flanged and Threaded Ends	MSS SP-70
Cast-Iron Swing Check Valves, Flanged and Threaded Ends	MSS SP-71
Ball Valves with Flanged Butt-Welding Ends for General Service	MSS SP-72
Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends	MSS SP-110
Cast-Iron Plug Valves, Flanged and Threaded Ends	MSS SP-78
Bronze Gate, Globe, Angle, and Check Valves	MSS SP-80
Steel Valves, Socket Welding and Threaded Ends	ASME B16.34
Cast-Iron Globe and Angle Valves, Flanged and Threaded Ends	MSS SP-85
Backwater Valves	ASME A112.14.1
Vacuum Relief Valves	ANSI Z21.22/CSA 4.4
Water Pressure Reducing Valves	ASSE 1003
Water Heater Drain Valves	ASME BPVC SEC IV, Part HLW-810: Requirements for Potable-Water Heaters Bottom Drain Valve
Trap Seal Primer Valves	ASSE 1018
Temperature and Pressure Relief Valves for Hot Water Supply Systems	ANSI Z21.22/CSA 4.4
Temperature and Pressure Relief Valves for Automatically Fired Hot Water Boilers	ASME CSD-1 Safety Code No., Part CW, Article 5

2.3.1 Backwater Valves

Backwater valves must be either separate from the floor drain or a combination floor drain, P-trap, and backwater valve, as indicated on

drawings. Valves must have cast-iron bodies with cleanouts large enough to permit removal of interior parts. Valves must be of the flap type, hinged or pivoted, with revolving disks. Hinge pivots, disks, and seats must be nonferrous metal. Disks must be slightly open in a no-flow no-backwater condition. Cleanouts must extend to finished floor and be fitted with threaded countersunk plugs.

2.3.2 Wall Faucets

Wall faucets with vacuum-breaker backflow preventer must be brass with 3/4 inch male inlet threads, hexagon shoulder, and 3/4 inch hose connection. Faucet handle must be securely attached to stem.

2.3.3 Wall Hydrants (Frostproof)

ASSE 1019 with vacuum-breaker backflow preventer must have a recessed box, with locking cover. A brass or bronze operating rod must be provided within a galvanized iron casing of sufficient length to extend through the wall so that the valve is inside the building, and the portion of the hydrant between the outlet and valve is self-draining. A brass or bronze valve with coupling and union elbow having metal-to-metal seat must be provided. Valve rod and seat washer must be removable through the face of the hydrant. The hydrant must have 3/4 inch exposed hose thread on spout and 3/4 inch male pipe thread on inlet.

2.3.4 Outlet Boxes

2.3.4.1 Ice Maker Box

One-piece, recessed, high impact plastic box with quarter turn shut-off valves, 1/2 inch supply.

2.3.5 Relief Valves

Water heaters and hot water storage tanks must have a combination pressure and temperature (P&T) relief valve. The pressure relief element of a P&T relief valve must have adequate capacity to prevent excessive pressure buildup in the system when the system is operating at the maximum rate of heat input. The temperature element of a P&T relief valve must have a relieving capacity which is at least equal to the total input of the heaters when operating at their maximum capacity. Relief valves must be rated according to ANSI Z21.22/CSA 4.4. Relief valves for systems where the maximum rate of heat input is less than 200,000 Btuh must have 3/4 inch minimum inlets, and 3/4 inch outlets. Relief valves for systems where the maximum rate of heat input is greater than 200,000 Btuh must have 1 inch minimum inlets, and 1 inch outlets. The discharge pipe from the relief valve must be the size of the valve outlet.

2.3.6 Thermostatic Mixing Valves

Each valve must be constructed to control the mixing of hot and cold water and to deliver water at a desired temperature regardless of pressure or input temperature changes. The control element must be of an approved type. The body must be of heavy cast bronze, and interior parts must be brass, bronze, corrosion-resisting steel or copper. The valve must be equipped with necessary stops, check valves, unions, and sediment strainers on the inlets.

2.3.7 Temperature Controlled Mixing Valve

Provide an ASSE 1017 temperature controlled (master mixing valve) to lower temperature per UFC 3-420-01 immediately downstream of the water heater storage tank as close to the fixture(s) as possible in order to reduce the amount of stored tempered water in the pipes in accordance with ASSE 1017.

2.3.8 Point-of-Use Mixing Valve

Provide a point-of-use mixing valve in accordance with ASSE 1070 at lavatories, hand-wash sinks, and washfountain locations. Point-of-use mixing valve must limit the tempered water to not greater than 110 degrees F.

2.3.9 Automatic Temperature and Pressure Compensating Valve

Provide automatic temperature and pressure compensating valve installed at each individual shower or tub/shower combination in accordance with ASSE 1016. The compensating valve must be integrated with each individual shower or tub/shower combination valve and must be installed at point of use. The valve must be equipped with a device to limit the maximum temperature to 120 degrees F.

2.3.10 Single Supply Line Automatic Temperature Control

Provide ASSE 1069 automatic temperature control valve on single supply line to gang showers or sitz baths to provide tempered water control to multiple fixtures. Valves must be installed where end user does not have means to adjust temperature setting. Temperature setting must be set as indicated with a maximum set point of 120 degrees F.

2.4 FIXTURES

Submit list of fixtures with manufacturer, model, and flow rate. Water closet replacements in major renovations may have a flush valve of up to 1.6 GPF to accommodate existing plumbing capacity. Fixtures for use by the physically handicapped must be in accordance with ICC A117.1. Vitreous China, nonabsorbent, hard-burned, and vitrified throughout the body must be provided. Porcelain enameled ware must have specially selected, clear white, acid-resisting enamel coating evenly applied on surfaces. No fixture will be accepted that shows cracks, crazes, blisters, thin spots, or other flaws. Fixtures must be equipped with appurtenances such as traps, faucets, stop valves, and drain fittings. Each fixture and piece of equipment requiring connections to the drainage system, except grease interceptors, must be equipped with a trap. Brass expansion or toggle bolts capped with acorn nuts must be provided for supports, and polished chromium-plated pipe, valves, and fittings must be provided where exposed to view. Fixtures with the supply discharge below the rim must be equipped with backflow preventers. Internal parts of flush valves and flushometer valves, shower mixing valves, shower head face plates, pop-up stoppers of lavatory waste drains, and pop-up stoppers and overflow tees and shoes of bathtub waste drains .

2.4.1 Lavatories

Vitreous china lavatories must be provided with two integral molded lugs on the back-underside of the fixture and drilled for bolting to the wall in a manner similar to the hanger plate. Provide public faucet with a maximum flow rate of 0.5 gpm at a maximum flowing pressure of 60 psi.

2.4.2 Automatic Controls

Provide hard wired automatic, sensor operated faucets and flush valves to comply with ASSE 1037 and UL 1951 for lavatory faucets, urinals, and water closets. Flushing and faucet systems must consist of solenoid-activated valves with light beam sensors. Flush valve for water closet must include an override pushbutton. Flushing devices must be provided as described in paragraph FIXTURES AND FIXTURE TRIMMINGS.

2.4.3 Flush Valve Water Closets

2.4.3.1 Flush Valve Water Closet Type and Mount

ASME A112.19.2/CSA B45.1, white vitreous china, siphon jet, elongated bowl, floor-mounted, floor outlet. Top of toilet seat height above floor must be 14 to 15 inches, except 17 to 19 inches for wheelchair water closets. Provide wax bowl ring including plastic sleeve. Provide white solid plastic elongated open-front seat.

2.4.3.2 Flush Valve Water Closet Flush and Flow

Water flushing volume of the water closet and flush valve combination must not exceed 1.28 gallons per flush. Water closets must meet the EPA WaterSense product definition and must be EPA WaterSense labeled products.

2.4.3.3 Flush Valve Water Closet Control Valve

Provide large diameter flush valve including angle control-stop valve, vacuum breaker, tail pieces, slip nuts, and wall plates; exposed to view components must be chromium-plated or polished stainless steel. Flush valves must be nonhold-open type. Mount flush valves not less than 11 inches above the fixture. Mounted height of flush valve must not interfere with the hand rail in ADA stalls. Provide solenoid-activated flush valves including electrical-operated light-beam-sensor to energize the solenoid.

2.4.4 Flush Valve Urinals

ASME A112.19.2/CSA B45.1, white vitreous china, wall-mounted, wall outlet, siphon jet, integral trap, and extended side shields. Provide urinal with the rim 24 inches above the floor. Water flushing volume of the urinal and flush valve combination must not exceed 0.125 gallons per flush. Urinals must be EPA WaterSense labeled products.

Provide ASME A112.6.1M concealed chair carriers with vertical steel pipe supports. Provide large diameter flush valve including angle control-stop valve, vacuum breaker, tail pieces, slip nuts, and wall plates; exposed to view components must be chromium-plated or polished stainless steel. Flush valves must be nonhold-open type. Mount flush valves not less than 11 inches above the fixture. Provide solenoid-activated flush valves including electrical-operated light-beam-sensor to energize the solenoid.

2.4.5 Wheelchair Flush Valve Type Urinals

ASME A112.19.2/CSA B45.1, white vitreous china, ASME A112.19.3/CSA B45.4 302 stainless steel, wall-mounted, wall outlet, blowout action, integral trap, elongated projecting bowl, a minimum of 13.5 inches long from wall

to front of flare, and ASME A112.19.5 trim. Provide large diaphragm (not less than 2.625 inches upper chamber inside diameter at the point where the diaphragm is sealed between the upper and lower chambers), nonhold-open flush valve of chrome plated cast brass conforming to ASTM B584, including vacuum breaker and angle (control-stop) valve with back check. The water flushing volume of the flush valve and urinal combination must not exceed 0.125 gallon per flush. Urinals must be EPA WaterSense labeled products.

Furnish urinal manufacturer's certification of conformance. Provide ASME A112.6.1M concealed chair carriers. Mount urinal with front rim a maximum of 17 inches above floor and flush valve handle a maximum of 44 inches above floor for use by handicapped on wheelchair. Provide solenoid-activated flush valves including electrical-operated light-beam-sensor to energize the solenoid.

2.4.6 Wall Hung Lavatories

ASME A112.19.2/CSA B45.1, white vitreous china, type, minimum dimensions of 19 inches wide by 17 inches front to rear, with supply openings for use with top mounted centerset faucets, and openings for concealed arm carrier installation. Provide aerator with faucet. Provide lavatory faucets and accessories meeting the flow rate and product requirements of the paragraph LAVATORIES. Provide ASME A112.6.1M concealed chair carriers with vertical steel pipe supports and concealed arms for the lavatory. Mount lavatory with the front rim 34 inches above floor and with 29 inches minimum clearance from bottom of the front rim to floor. Provide top-mounted solenoid-activated lavatory faucets including electrical-operated light-beam-sensor to energize the solenoid. Provide piping covers for P-traps, valves, and exposed drain piping per ADA requirement.

2.4.7 Integral Lavatories

Solid surface counter with integral lavatory bowl. See Interiors for further specifications. Bowl shall be provided with supply openings for use with top mounted centerset faucets. Provide aerator with faucet. Water flow rate shall not exceed 0.5 gpm when measured at a flowing water pressure of 60 psi. Mount counter with the top surface 34 inches above floor and with 29 inches minimum clearance from bottom of the counter face to floor. Provide top mounted washerless centerset lavatory faucets.

2.4.8 Kitchen Sinks

ASME A112.19.3/CSA B45.4, single compartment, 20 gage stainless steel with integral mounting rim for flush installation, minimum dimensions of 30 inches wide by 21 inches front to rear, with undersides fully sound deadened, with supply openings for use with top mounted washerless sink faucets with hose spray, and with 3.5 inch drain outlet. Provide aerator with faucet. Water flow rate must not exceed 2.2 gpm when measured at a flowing water pressure of 60 psi. Provide stainless steel drain outlets and stainless steel cup strainers. Provide separate 1.5 inch P-trap and drain piping to vertical vent piping from each compartment. Provide top mounted washerless sink faucets with hose spray.

2.4.9 Wheelchair Drinking Water Cooler

ANSI/ASHRAE 18, UL 399, NSF/ANSI/CAN 61, ADA and ICC A117.1. Dual height water cooler with more than a single thickness of metal between the

potable water and the refrigerant in the heat exchanger, wall-mounted bubbler style with ASME A112.6.1M concealed chair carrier, air-cooled condensing unit, 8 gph minimum capacity, stainless steel splash receptor, and all stainless steel cabinet, with 27 inch minimum knee clearance from front bottom of unit to floor and 36 inch maximum spout height above floor for ADA side and 38 inches to 43 inches above floor for standing person side and bottle filler. Bubblers must also be controlled by push levers, by push bars, or touch pads one on each side or one on front and both sides of the cabinet.

2.4.10 Shower Faucets

Provide ball joint self-cleaning shower heads. Provide WaterSense labeled showerhead with a maximum flow rate of 1.75 gpm.

2.4.11 Precast Terrazzo Mop Sinks

Terrazzo must be made of marble chips cast in white portland cement to produce 3000 psi minimum compressive strength 7 days after casting. Terrazzo can include stainless steel curb cap additions with minimum dimensions of 24 inches wide by 24 inches length by 12 inches height. Provide floor or wall outlet copper alloy body drain cast integral with terrazzo, with polished stainless steel strainers. Provide back mounted washerless service sink faucets with vacuum breaker and 0.75 inch external hose threads.

2.5 BACKFLOW PREVENTERS

Backflow prevention devices must be approved by the State or local regulatory agencies. If there is no State or local regulatory agency requirements, the backflow prevention devices must be listed by the Foundation for Cross-Connection Control & Hydraulic Research, or any other approved testing laboratory having equivalent capabilities for both laboratory and field evaluation of backflow prevention devices and assemblies. Reduced pressure principle assemblies, double check valve assemblies, atmospheric (nonpressure) type vacuum breakers, and pressure type vacuum breakers must be meet the above requirements.

Backflow preventers with intermediate atmospheric vent must conform to ASSE 1012. Reduced pressure principle backflow preventers must conform to ASSE 1013. Hose connection vacuum breakers must conform to ASSE 1011. Pipe applied atmospheric type vacuum breakers must conform to ASSE 1001. Pressure vacuum breaker assembly must conform to ASSE 1020. Air gaps in plumbing systems must conform to ASME A112.1.2.

2.6 DRAINS

2.6.1 Floor and Shower Drains

Floor and shower drains must consist of a galvanized body, integral seepage pan, and adjustable perforated or slotted chromium-plated bronze, nickel-bronze, or nickel-brass strainer, consisting of grate and threaded collar. Floor drains must be cast iron except where metallic waterproofing membrane is installed. Drains must be of double drainage pattern for embedding in the floor construction. The seepage pan must have weep holes or channels for drainage to the drainpipe. The seepage pan and weep holes must not be filled or plugged and have pervious materials (such as pea gravel) or a weep hole protection device to allow drainage. The strainer must be adjustable to floor thickness. A clamping

device for attaching flashing or waterproofing membrane to the seepage pan without damaging the flashing or waterproofing membrane must be provided when required. Drains must be provided with threaded connection. Between the drain outlet and waste pipe, a neoprene rubber gasket conforming to ASTM C564 may be installed, provided that the drain is specifically designed for the rubber gasket compression type joint. Floor and shower drains must conform to ASME A112.6.3. Provide drain with trap primer connection, trap primer, and connection piping. Primer must meet ASSE 1018.

2.6.1.1 Metallic Shower Pan Drains

Where metallic shower pan membrane is installed, polyethylene drain with corrosion-resistant screws securing the clamping device must be provided. Polyethylene drains must have fittings to adapt drain to waste piping. Polyethylene for floor drains must conform to ASTM D1248. Drains must have separate cast-iron "P" trap, circular body, seepage pan, and strainer, unless otherwise indicated.

2.6.1.2 Drains and Backwater Valves

Drains and backwater valves installed in connection with waterproofed floors or shower pans must be equipped with bolted-type device to securely clamp flashing.

2.6.2 Shower Faucets and Drain Fittings

Provide single control pressure equalizing shower faucets with body mounted from behind the wall with threaded connections. Provide ball joint self-cleaning shower heads. Provide WaterSense labeled showerhead with a maximum flow rate of 1.75 gpm. Provide shower valve with ball type control handle.

2.6.3 Area Drains

Area drains must be plain pattern with polished stainless steel perforated or slotted grate and bottom outlet. The drain must be circular or square with a 12 inch nominal overall width or diameter and 10 inch nominal overall depth. Drains must be cast iron with manufacturer's standard coating. Grate must be easily lifted out for cleaning. Outlet must be suitable for inside caulked connection to drain pipe. Drains must conform to ASME A112.6.3.

2.6.4 Boiler Room Drains

Boiler room drains must have combined drain and trap, hinged grate, removable bucket, and threaded brass cleanout with brass backwater valve. The removable galvanized cast-iron sediment bucket must have rounded corners to eliminate fouling and must be equipped with hand grips. Drain must have a minimum water seal of 4 inches. The grate area must be not less than 100 square inches.

2.6.5 Trap Seal Protection

2.6.5.1 Potable Water-Supplied Trap Seal Valve

Trap must be supplied with a source of potable water. The trap seal primer valve must conform to ASSE 1018. The discharge from the valve must connect to the trap seal on the inlet side of the trap.

2.6.5.2 Waste Water-Supplied Trap Seal Device

Trap will be supplied with a source of waste water conforming to ASSE 1044. The discharge from the device must connect to the trap above the trap seal on the inlet side of the trap.

2.7 SHOWER PAN

Shower pan may be copper, or nonmetallic material.

2.7.1 Sheet Copper

Sheet copper must be 16 ounce weight.

2.7.2 Plasticized Polyvinyl Chloride Shower Pan Material

Material must be sheet form. The material must be 0.040 inch minimum thickness of plasticized polyvinyl chloride or chlorinated polyethylene and must be in accordance with ASTM D4551.

2.7.3 Nonplasticized Polyvinyl Chloride (PVC) Shower Pan Material

Material must consist of a plastic waterproofing membrane in sheet form. The material must be 0.040 inch minimum thickness of nonplasticized PVC and must have the following minimum properties:

a. or ASTM D638:

Ultimate Tensile Strength:	2600 psi
Ultimate Elongation:	398 percent
100 Percent Modulus:	445 psi

b. ASTM D1004:

Tear Strength:	300 pounds per inch

c. ASTM E96/E96M:

Permeance:	0.008 perms

d. Other Properties:

Specific Gravity:	1.29
PVC Solvent:	Weldable
Cold Crack:	minus 53 degrees F
Dimensional stability	212 degrees F minus 2.5 percent
Hardness, Shore A:	89

2.8 TRAPS

Unless otherwise specified, traps must be plastic per ASTM F409. Traps must be without a cleanout. Provide traps with removable access panels for easy clean-out at sinks and lavatories. Tubes must be copper alloy with walls not less than 0.032 inch thick within commercial tolerances, except on the outside of bends where the thickness may be reduced slightly in manufacture by usual commercial methods. Inlets must have rubber washer and copper alloy nuts for slip joints above the discharge level. Swivel joints must be below the discharge level and must be of metal-to-metal or metal-to-plastic type as required for the application.

Nuts must have flats for wrench grip. Outlets must have internal pipe thread, except that when required for the application, the outlets must have sockets for solder-joint connections. The depth of the water seal must be not less than 2 inches. The interior diameter must be not more than 1/8 inch over or under the nominal size, and interior surfaces must be reasonably smooth throughout. A copper alloy "P" trap assembly consisting of an adjustable "P" trap and threaded trap wall nipple with cast brass wall flange must be provided for lavatories. The assembly must be a standard manufactured unit and may have a rubber-gasketed swivel joint.

2.9 WATER HEATERS

Water heater types and capacities must be as indicated. Each water heater must have replaceable anodes. Each primary water heater must have controls with an adjustable range that includes 90 to 160 degrees F. Each gas-fired water heater and booster water heater must have controls with an adjustable range that includes 120 to 180 degrees F. Hot water systems utilizing recirculation systems must be tied into building off-hour controls. The thermal efficiencies and standby heat losses must conform to TABLE III in PART 3 of this Section for each type of water heater specified. The only exception is that storage water heaters and hot water storage tanks having more than 500 gallons storage capacity need not meet the standard loss requirement if the tank surface area is insulated to R-12.5 and if a standing light is not used. Plastic materials polyetherimide (PEI) and polyethersulfone (PES) are forbidden to be used for vent piping of combustion gases. A factory pre-charged expansion tank must be installed on the cold water supply to each water heater. Expansion tanks must be specifically designed for use on potable water systems and must be rated for 200 degrees F water temperature and 150 psi working pressure. The expansion tank size and acceptance volume must be as indicated.

2.9.1 Automatic Storage Type

Heaters must be complete with control system, temperature gauge, and pressure gauge, and must have ASME rated combination pressure and temperature relief valve.

2.9.1.1 Gas-Fired Type

Gas-fired water heaters must conform to ANSI Z21.10.1/CSA 4.1 when input is 75,000 BTU per hour or less or ANSI Z21.10.3/CSA 4.3 for heaters with input greater than 75,000 BTU per hour. Provide Energy Star labeled gas storage water heater. Provide data identifying Energy Star label for gas storage water heater.

2.9.1.2 Electric Type

Electric type water heaters must conform to UL 174 with dual heating elements. Each element must be 2.0 KW. The elements must be wired so that only one element can operate at a time.

2.9.2 Electric Instantaneous Water Heaters (Tankless)

UL 499 and UL listed flow switch activated, tankless electric instantaneous water heater for wall mounting below sink or lavatory. Temperature rise at Flow Rate: as indicated on drawings.

2.9.3 Phenolic Resin Coatings for Heater Tubes

The phenolic resin coating system must be applied at either the coil or coating manufacturer's factory in accordance with manufacturer's standard proven production process. The coating system must be a product specifically intended for use on the material the water heating tubes/coils are made of and must be acceptable for use in potable water systems. The coating system must be capable of withstanding temperatures up to 400 degrees F dry bulb; and meet the requirements of 21 CFR 175.

The entire exterior surface of each coil must be coated with phenolic resin coating system.

2.9.3.1 Standard Product

Provide a phenolic resin coating system that is a standard product of a manufacturer regularly engaged in the manufacturing of products that are of a similar material, design, and workmanship.

Standard products are defined as components and equipment that have been in satisfactory commercial or industrial use in similar applications of similar size for at least 2 years before bid opening. Prior to this 2 year period, these standard products were sold on the commercial market using advertisements in manufacturers' catalogs or brochures. These manufacturers' catalogs, or brochures must have been copyrighted documents or be identified with a manufacturer's document number.

2.9.3.2 Expansion Tank

Provide a potable water expansion tank of steel construction with a NSF/ANSI/CAN 61 Butyl diaphragm separating the air chamber from the water containing container. Tank must have a stainless steel inlet connector. Diaphragm must be FDA approved. Maximum operating temperature 200 degrees F, Maximum Working Pressure: 150 PSIG (10.3 bar).

2.10 PUMPS

2.10.1 Circulating Pumps

Domestic hot water circulating pumps must be electrically driven, single-stage, centrifugal, with mechanical seals, suitable for the intended service. Pump and motor must be supported by the piping on which it is installed. The shaft must be one-piece, heat-treated, corrosion-resisting steel with impeller and smooth-surfaced housing of bronze.

2.10.1.1 Circulating Pump Enclosure

Motor must be totally enclosed, fan-cooled and must have sufficient horsepower for the service required. Each pump motor must be equipped with an across-the-line magnetic controller in a NEMA 250, Type 1 enclosure with "START-STOP" switch in cover.

2.10.1.2 Circulating Pump Size and Efficiency

Integral size motors must be premium efficiency type in accordance with NEMA MG 00001. Pump motors smaller than 1 hp Fractional horsepower pump motors must have integral thermal overload protection in accordance with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Guards must shield exposed

moving parts.

2.10.2 Flexible Connectors

Flexible connectors must be provided at the suction and discharge of each pump that is 1 hp or larger. Connectors must be constructed of neoprene, rubber, or braided bronze, with Class 150 standard flanges. Flexible connectors must be line size and suitable for the pressure and temperature of the intended service.

2.11 DOMESTIC WATER SERVICE METER

The requirements for metering and submetering are specified in Section 33 11 00 WATER UTILITY DISTRIBUTION PIPING.

Cold water meters 2 inches and smaller must be positive displacement type conforming to AWWA C700. Cold water meters 2-1/2 inches and larger must be turbine type conforming to AWWA C701. Water meters must be positive displacement, type. Meter register may be round or straight reading type, as provided by the local utility. Meter must be provided with a pulse generator, remote readout register and all necessary wiring and accessories. Meters must be connected to the base wide energy and utility monitoring and control system (if this system exists) using the installation's advanced metering protocols.

2.12 ELECTRICAL WORK

Provide electrical motor driven equipment specified complete with motors, motor starters, and controls as specified herein and in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide internal wiring for components of packaged equipment as an integral part of the equipment. Provide high efficiency type, single-phase, fractional-horsepower alternating-current motors, including motors that are part of a system, corresponding to the applications in accordance with NEMA MG 11. Provide motors in accordance with NEMA MG 00001 and of sufficient size to drive the load at the specified capacity without exceeding the nameplate rating of the motor.

2.12.1 Electrical Requirements for Motors

Motors must be rated for continuous duty with the enclosure specified. Motor duty requirements must allow for maximum frequency start-stop operation and minimum encountered interval between start and stop. Motor torque must be capable of accelerating the connected load within 20 seconds with 80 percent of the rated voltage maintained at motor terminals during one starting period. Motor bearings must be fitted with grease supply fittings and grease relief to outside of the enclosure.

2.12.2 Electrical Requirements for Controllers and Contactors

Controllers and contactors must have auxiliary contacts for use with the controls provided. Manual or automatic control and protective or signal devices required for the operation specified and any control wiring required for controls and devices specified, but not shown, must be provided. For packaged equipment, the manufacturer must provide controllers, including the required monitors and timed restart.

2.12.3 Electrical Requirements for Power Wiring

Power wiring and conduit for field installed equipment must be provided

under and conform to the requirements of Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

2.13 MISCELLANEOUS PIPING ITEMS

2.13.1 Escutcheon Plates

Provide one piece or split hinge metal plates for piping entering floors, walls, and ceilings in exposed spaces. Provide chromium-plated on copper alloy plates or polished stainless steel finish in finished spaces. Provide paint finish on plates in unfinished spaces.

2.13.2 Pipe Sleeves

Provide where piping passes entirely through walls, ceilings, roofs, and floors. Sleeves are not required where supply drain, waste, and vent (DWV) piping passes through concrete floor slabs located on grade, except where penetrating a membrane waterproof floor. For multiple pipe penetrations through load bearing masonry or concrete walls, minimum spacing must be 6" inches center of pipe to center of pipe.

2.13.2.1 Sleeves in Masonry and Concrete

Provide steel pipe sleeves or schedule 40 PVC plastic pipe sleeves. Sleeves are not required where drain, waste, and vent (DWV) piping passes through concrete floor slabs located on grade. Core drilling of masonry and concrete may be provided in lieu of pipe sleeves when cavities in the core-drilled hole are completely grouted smooth.

2.13.2.2 Sleeves Not in Masonry and Concrete

Provide 26 gage galvanized steel sheet or PVC plastic pipe sleeves.

2.13.3 Pipe Hangers (Supports)

Provide MSS SP-58 Type 1 with adjustable type steel support rods, except as specified or indicated otherwise. Attach to steel joists with Type 19 or 23 clamps and retaining straps. Attach to Steel W or S beams with Type 21, 28, 29, or 30 clamps. Attach to steel angles and vertical web steel channels with Type 20 clamp with beam clamp channel adapter. Attach to horizontal web steel channel and wood with drilled hole on centerline and double nut and washer. Attach to concrete with Type 18 insert or drilled expansion anchor. Provide Type 40 insulation protection shield for insulated piping.

2.13.4 Nameplates

Provide 0.125 inch thick melamine laminated plastic nameplates, black matte finish with white center core, for equipment, gages, thermometers, and valves; valves in supplies to faucets will not require nameplates. Accurately align lettering and engrave minimum of 0.25 inch high normal block lettering into the white core. Minimum size of nameplates must be 1.0 by 2.5 inches. Key nameplates to a chart and schedule for each system. Frame charts and schedules under glass and place where directed near each system. Furnish two copies of each chart and schedule.

PART 3 EXECUTION

3.1 GENERAL INSTALLATION REQUIREMENTS

Piping located in air plenums must conform to NFPA 90A requirements. Piping located in shafts that constitute air ducts or that enclose air ducts must be noncombustible in accordance with NFPA 90A. Installation of plastic pipe where in compliance with NFPA may be installed in accordance with PPFA Fire Man. The plumbing system must be installed complete with necessary fixtures, fittings, traps, valves, and accessories. Submit diagrams, instructions, and other sheets proposed for posting for Plumbing System. Submit for Plumbing System manufacturer's recommendations for the installation of bell and spigot and hubless joints for cast iron soil pipe. Water and drainage piping must be extended 5 feet outside the building, unless otherwise indicated. A full port ball valve and drain must be installed on the water service line inside the building approximately 6 inches above the floor from point of entry. Piping must be connected to the exterior service lines or capped or plugged if the exterior service is not in place. Sewer and water pipes must be laid in separate trenches, except when otherwise shown. Exterior underground utilities must be at least 12 inches below the average local frost depth or as indicated on the drawings. If trenches are closed or the pipes are otherwise covered before being connected to the service lines, the location of the end of each plumbing utility must be marked with a stake or other acceptable means. Valves must be installed with control no lower than the valve body. Avoid the use of combination double wye and one-eighth bend fittings in the horizontal orientation below grade or below slab.

3.1.1 Water Pipe, Fittings, and Connections

3.1.1.1 Utilities

The piping must be extended to fixtures, outlets, and equipment. The hot-water and cold-water piping system must be arranged and installed to permit draining. The supply line to each item of equipment or fixture, except faucets, flush valves, or other control valves which are supplied with integral stops, must be equipped with a shutoff valve to enable isolation of the item for repair and maintenance without interfering with operation of other equipment or fixtures. Supply piping to fixtures, faucets, hydrants, shower heads, and flushing devices must be anchored to prevent movement.

3.1.1.2 Cutting and Repairing

The work must be carefully laid out in advance, and unnecessary cutting of construction must be avoided. Damage to building, piping, wiring, or equipment as a result of cutting must be repaired by mechanics skilled in the trade involved.

3.1.1.3 Protection of Fixtures, Materials, and Equipment

Pipe openings must be closed with caps or plugs during installation. Fixtures and equipment must be tightly covered and protected against dirt, water, chemicals, and mechanical injury. Upon completion of the work, the fixtures, materials, and equipment must be thoroughly cleaned, adjusted, and operated. Safety guards must be provided for exposed rotating equipment.

3.1.1.4 Mains, Branches, and Runouts

Piping must be installed as indicated. Pipe must be accurately cut and worked into place without springing or forcing. Structural portions of the building must not be weakened. Aboveground piping must run parallel with the lines of the building, unless otherwise indicated. Branch pipes from service lines may be taken from top, bottom, or side of main, using crossover fittings required by structural or installation conditions. Supply pipes, valves, and fittings must be kept a sufficient distance from other work and other services to permit not less than 1/2 inch between finished covering on the different services. Bare and insulated water lines must not bear directly against building structural elements so as to transmit sound to the structure or to prevent flexible movement of the lines. Water pipe must not be buried in or under floors unless specifically indicated or approved. Changes in pipe sizes must be made with reducing fittings. Use of bushings will not be permitted except for use in situations in which standard factory fabricated components are furnished to accommodate specific accepted installation practice. Change in direction must be made with fittings, except that bending of pipe 4 inches and smaller will be permitted, provided a pipe bender is used and wide sweep bends are formed. The center-line radius of bends must be not less than six diameters of the pipe. Bent pipe showing kinks, wrinkles, flattening, or other malformations will not be acceptable.

3.1.1.5 Pipe Drains

Pipe drains indicated must consist of 3/4 inch hose bibb with renewable seat and full port ball valve ahead of hose bibb. At other low points, 3/4 inch brass plugs or caps must be provided. Disconnection of the supply piping at the fixture is an acceptable drain.

3.1.1.6 Expansion and Contraction of Piping

Allowance must be made throughout for expansion and contraction of water pipe. Each hot-water and hot-water circulation riser must have expansion loops or other provisions such as offsets and changes in direction where indicated and required. Risers must be securely anchored as required or where indicated to force expansion to loops. Branch connections from risers must be made with ample swing or offset to avoid undue strain on fittings or short pipe lengths. Horizontal runs of pipe over 50 feet in length must be anchored to the wall or the supporting construction about midway on the run to force expansion, evenly divided, toward the ends. Sufficient flexibility must be provided on branch runouts from mains and risers to provide for expansion and contraction of piping. Flexibility must be provided by installing one or more turns in the line so that piping will spring enough to allow for expansion without straining. If mechanical grooved pipe coupling systems are provided, the deviation from design requirements for expansion and contraction may be allowed pending approval of Contracting Officer.

3.1.1.7 Thrust Restraint

Plugs, caps, tees, valves and bends deflecting 11.25 degrees or more, either vertically or horizontally, in waterlines 4 inches in diameter or larger must be provided with thrust blocks, where indicated, to prevent movement. Thrust blocking must be concrete of a mix not leaner than: 1 cement, 2-1/2 sand, 5 gravel; and having a compressive strength of not less than 2000 psi after 28 days. Blocking must be placed between solid ground and the fitting to be anchored. Unless otherwise indicated or

directed on drawings, the base and thrust bearing sides of the thrust block must be poured against undisturbed earth. The side of the thrust block not subject to thrust must be poured against forms. The area of bearing will be as indicated on drawings. Blocking must be placed so that the joints of the fitting are accessible for repair. Steel rods and clamps, protected by galvanizing or by coating with bituminous paint, must be used to anchor vertical down bends into gravity thrust blocks.

3.1.1.8 Commercial-Type Water Hammer Arresters

Commercial-type water hammer arresters must be provided on hot- and cold-water supplies and must be located as generally indicated, with precise location and sizing to be in accordance with PDI WH 201. Water hammer arresters, where concealed, must be accessible by means of access doors or removable panels. Commercial-type water hammer arresters must conform to ASSE 1010. Vertical capped pipe columns will not be permitted.

3.1.2 Compressed Air Piping (Non-Oil Free)

Compressed air piping must have supply lines and discharge terminals legibly and permanently marked at both ends with the name of the system and the direction of flow.

3.1.3 Joints

Installation of pipe and fittings must be made in accordance with the manufacturer's recommendations. Mitering of joints for elbows and notching of straight runs of pipe for tees will not be permitted. Joints must be made up with fittings of compatible material and made for the specific purpose intended.

3.1.3.1 Threaded

Threaded joints must have American Standard taper pipe threads conforming to ASME B1.20.1. Only male pipe threads must be coated with graphite or with an approved graphite compound, or with an inert filler and oil, or must have a polytetrafluoroethylene tape applied.

3.1.3.2 Unions and Flanges

Unions, flanges and mechanical couplings must not be concealed in walls, ceilings, or partitions. Unions must be used on pipe sizes 2-1/2 inches and smaller; flanges must be used on pipe sizes 3 inches and larger.

3.1.3.3 Copper Tube and Pipe

a. Brazed. Brazed joints must be made in conformance with AWS B2.2/B2.2M, ASME B16.50, and CDA A4015 with flux and are acceptable for all pipe sizes. Copper to copper joints must include the use of copper-phosphorus or copper-phosphorus-silver brazing metal without flux. Brazing of dissimilar metals (copper to bronze or brass) must include the use of flux with either a copper-phosphorus, copper-phosphorus-silver or a silver brazing filler metal.

b. Soldered. Soldered joints must be made with flux and are only acceptable for piping 2 inches and smaller. Soldered joints must conform to ASME B31.5 and CDA A4015. Soldered joints must not be used in compressed air piping between the air compressor and the receiver.

c. Copper Tube Extracted Joint. Mechanically extracted joints must be made in accordance with ICC IPC.

3.1.3.4 Plastic Pipe

PVC pipe must have joints made with solvent cement elastomeric, threading, (threading of Schedule 80 Pipe is allowed only where required for disconnection and inspection; threading of Schedule 40 Pipe is not allowed), or mated flanged.

3.1.4 Dissimilar Pipe Materials

Connections between ferrous and non-ferrous copper water pipe must be made with dielectric unions or flange waterways. Dielectric waterways must have temperature and pressure rating equal to or greater than that specified for the connecting piping. Waterways must have metal connections on both ends suited to match connecting piping. Dielectric waterways must be internally lined with an insulator specifically designed to prevent current flow between dissimilar metals. Dielectric flanges must meet the performance requirements described herein for dielectric waterways. Connecting joints between plastic and metallic pipe must be made with transition fitting for the specific purpose.

3.1.5 Pipe Sleeves and Flashing

Pipe sleeves must be furnished and set in their proper and permanent location.

3.1.5.1 Sleeve Requirements

Unless indicated otherwise, provide pipe sleeves meeting the following requirements:

a. Secure sleeves in position and location during construction. Provide sleeves of sufficient length to pass through entire thickness of walls, ceilings, roofs, and floors.

b. A modular mechanical type sealing assembly may be installed in lieu of a waterproofing clamping flange and caulking and sealing of annular space between pipe and sleeve. The seals must consist of interlocking synthetic rubber links shaped to continuously fill the annular space between the pipe and sleeve using galvanized steel bolts, nuts, and pressure plates. The links must be loosely assembled with bolts to form a continuous rubber belt around the pipe with a pressure plate under each bolt head and each nut. After the seal assembly is properly positioned in the sleeve, tightening of the bolt must cause the rubber sealing elements to expand and provide a watertight seal between the pipe and the sleeve. Each seal assembly must be sized as recommended by the manufacturer to fit the pipe and sleeve involved.

c. Sleeves must not be installed in structural members, except where indicated or approved. Rectangular and square openings must be as detailed. Each sleeve must extend through its respective floor, or roof, and must be cut flush with each surface, except for special circumstances. Pipe sleeves passing through floors in wet areas such as mechanical equipment rooms, lavatories, kitchens, and other plumbing fixture areas must extend a minimum of 4 inches above the finished floor.

d. Unless otherwise indicated, sleeves must be of a size to provide a minimum of 1/4 inch clearance between bare pipe or insulation and inside of sleeve or between insulation and inside of sleeve. Sleeves in bearing walls and concrete slab on grade floors must be steel pipe or cast-iron pipe. Sleeves in nonbearing walls or ceilings may be steel pipe, cast-iron pipe, galvanized sheet metal with lock-type longitudinal seam, or plastic.

e. Except as otherwise specified, the annular space between pipe and sleeve, or between jacket over insulation and sleeve, must be sealed as indicated with sealants conforming to ASTM C920 and with a primer, backstop material and surface preparation as specified in Section 07 92 00 JOINT SEALANTS. The annular space between pipe and sleeve, between bare insulation and sleeve or between jacket over insulation and sleeve must not be sealed for interior walls which are not designated as fire rated.

f. Sleeves through below-grade walls in contact with earth must be recessed 1/2 inch from wall surfaces on both sides. Annular space between pipe and sleeve must be filled with backing material and sealants in the joint between the pipe and masonry wall as specified above. Sealant selected for the earth side of the wall must be compatible with dampproofing/waterproofing materials that are to be applied over the joint sealant. Pipe sleeves in fire-rated walls must conform to the requirements in Section 07 84 00 FIRESTOPPING.

3.1.5.2 Flashing Requirements

Pipes passing through roof must be installed through a 16 ounce copper flashing, each within an integral skirt or flange. Flashing must be suitably formed, and the skirt or flange must extend not less than 8 inches from the pipe and must be set over the roof or floor membrane in a solid coating of bituminous cement. The flashing must extend up the pipe a minimum of 10 inches. For cleanouts, the flashing must be turned down into the hub and caulked after placing the ferrule. Pipes passing through pitched roofs must be flashed, using lead or copper flashing, with an adjustable integral flange of adequate size to extend not less than 8 inches from the pipe in all directions and lapped into the roofing to provide a watertight seal. The annular space between the flashing and the bare pipe or between the flashing and the metal-jacket-covered insulation must be sealed as indicated. Flashing for dry vents must be turned down into the pipe to form a waterproof joint. Pipes, up to and including 10 inches in diameter, passing through roof or floor waterproofing membrane may be installed through a cast-iron sleeve with caulking recess, anchor lugs, flashing-clamp device, and pressure ring with brass bolts. Flashing shield must be fitted into the sleeve clamping device. Pipes passing through wall waterproofing membrane must be sleeved as described above. A waterproofing clamping flange must be installed.

3.1.5.3 Waterproofing

Waterproofing at floor-mounted water closets must be accomplished by forming a flashing guard from soft-tempered sheet copper. The center of the sheet must be perforated and turned down approximately 1-1/2 inches to fit between the outside diameter of the drainpipe and the inside diameter of the cast-iron or steel pipe sleeve. The turned-down portion of the flashing guard must be embedded in sealant to a depth of approximately 1-1/2 inches; then the sealant must be finished off flush to floor level between the flashing guard and drainpipe. The flashing guard of sheet

copper must extend not less than 8 inches from the drainpipe and must be lapped between the floor membrane in a solid coating of bituminous cement. If cast-iron water closet floor flanges are used, the space between the pipe sleeve and drainpipe must be sealed with sealant and the flashing guard must be upturned approximately 1-1/2 inches to fit the outside diameter of the drainpipe and the inside diameter of the water closet floor flange. The upturned portion of the sheet fitted into the floor flange must be sealed.

3.1.5.4 Optional Counterflashing

Instead of turning the flashing down into a dry vent pipe, or caulking and sealing the annular space between the pipe and flashing or metal-jacket-covered insulation and flashing, counterflashing may be accomplished by utilizing the following:

a. A standard roof coupling for threaded pipe up to 6 inches in diameter.

b. A tack-welded or banded-metal rain shield around the pipe.

3.1.5.5 Pipe Penetrations of Slab on Grade Floors

Where pipes, fixture drains, floor drains, cleanouts or similar items penetrate slab on grade floors, except at penetrations of floors with waterproofing membrane as specified in paragraphs FLASHING REQUIREMENTS and WATERPROOFING, a groove 1/4 to 1/2 inch wide by 1/4 to 3/8 inch deep must be formed around the pipe, fitting or drain. The groove must be filled with a sealant as specified in Section 07 92 00 JOINT SEALANTS.

3.1.5.6 Pipe Penetrations

Provide sealants for all pipe penetrations. All pipe penetrations must be sealed to prevent infiltration of air, insects, and vermin.

3.1.6 Fire Seal

Where pipes pass through fire walls, fire-partitions, fire-rated pipe chase walls or floors above grade, a fire seal must be provided as specified in Section 07 84 00 FIRESTOPPING.

3.1.7 Supports

3.1.7.1 General

Hangers used to support piping 2 inches and larger must be fabricated to permit adequate adjustment after erection while still supporting the load. Pipe guides and anchors must be installed to keep pipes in accurate alignment, to direct the expansion movement, and to prevent buckling, swaying, and undue strain. Piping subjected to vertical movement when operating temperatures exceed ambient temperatures must be supported by variable spring hangers and supports or by constant support hangers. In the support of multiple pipe runs on a common base member, a clip or clamp must be used where each pipe crosses the base support member. Spacing of the base support members must not exceed the hanger and support spacing required for an individual pipe in the multiple pipe run. Threaded sections of rods must not be formed or bent.

3.1.7.2 Pipe Hangers, Inserts, and Supports

Installation of pipe hangers, inserts and supports must conform to MSS SP-58 except as modified herein.

a. Types 5, 12, and 26 must not be used.

b. Type 3 must not be used on insulated pipe.

c. Type 18 inserts must be secured to concrete forms before concrete is placed. Continuous inserts which allow more adjustment may be used if they otherwise meet the requirements for type 18 inserts.

d. Type 19 and 23 C-clamps must be torqued per MSS SP-58 and must have both locknuts and retaining devices furnished by the manufacturer. Field-fabricated C-clamp bodies or retaining devices are not acceptable.

e. Type 20 attachments used on angles and channels must be furnished with an added malleable-iron heel plate or adapter.

f. Type 24 may be used only on trapeze hanger systems or on fabricated frames.

g. Type 39 saddles must be used on insulated pipe 4 inches and larger when the temperature of the medium is 60 degrees F or higher. Type 39 saddles must be welded to the pipe.

h. Type 40 shields must:

(1) Be used on insulated pipe less than 4 inches.

(2) Be used on insulated pipe 4 inches and larger when the temperature of the medium is 60 degrees F or less.

(3) Have a high density insert for all pipe sizes. High density inserts must have a density of 8 pcf or greater.

i. Horizontal pipe supports must be spaced as specified in MSS SP-58 and a support must be installed not over 1 foot from the pipe fitting joint at each change in direction of the piping. Pipe supports must be spaced not over 5 feet apart at valves. Operating temperatures in determining hanger spacing for PVC or CPVC pipe must be 120 degrees F for PVC and 180 degrees F for CPVC. Horizontal pipe runs must include allowances for expansion and contraction.

j. Vertical pipe must be supported at each floor, except at slab-on-grade, at intervals of not more than 15 feet nor more than 8 feet from end of risers, and at vent terminations. Vertical pipe risers must include allowances for expansion and contraction.

k. Type 35 guides using steel, reinforced polytetrafluoroethylene (PTFE) or graphite slides must be provided to allow longitudinal pipe movement. Slide materials must be suitable for the system operating temperatures, atmospheric conditions, and bearing loads encountered. Lateral restraints must be provided as needed. Where steel slides do not require provisions for lateral restraint the following may be used:

(1) On pipe 4 inches and larger when the temperature of the medium is

60 degrees F or higher, a Type 39 saddle, welded to the pipe, may freely rest on a steel plate.

(2) On pipe less than 4 inches a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.

(3) On pipe 4 inches and larger carrying medium less that 60 degrees F a Type 40 shield, attached to the pipe or insulation, may freely rest on a steel plate.

l. Pipe hangers on horizontal insulated pipe must be the size of the outside diameter of the insulation. The insulation must be continuous through the hanger on all pipe sizes and applications.

m. Where there are high system temperatures and welding to piping is not desirable, the type 35 guide must include a pipe cradle, welded to the guide structure and strapped securely to the pipe. The pipe must be separated from the slide material by at least 4 inches or by an amount adequate for the insulation, whichever is greater.

n. Hangers and supports for plastic pipe must not compress, distort, cut or abrade the piping, and must allow free movement of pipe except where otherwise required in the control of expansion/contraction.

3.1.7.3 Structural Attachments

Attachment to building structure concrete and masonry must be by cast-in concrete inserts, built-in anchors, or masonry anchor devices. Inserts and anchors must be applied with a safety factor not less than 5. Supports must not be attached to metal decking. Supports must not be attached to the underside of concrete filled floor or concrete roof decks unless approved by the Contracting Officer. Masonry anchors for overhead applications must be constructed of ferrous materials only.

3.1.8 Welded Installation

Plumbing pipe weldments must be as indicated. Changes in direction of piping must be made with welding fittings only; mitering or notching pipe to form elbows and tees or other similar type construction will not be permitted. Branch connection may be made with either welding tees or forged branch outlet fittings. Branch outlet fittings must be forged, flared for improvement of flow where attached to the run, and reinforced against external strains. Beveling, alignment, heat treatment, and inspection of weld must conform to ASME B31.1. Weld defects must be removed and repairs made to the weld, or the weld joints must be entirely removed and rewelded. After filler metal has been removed from its original package, it must be protected or stored so that its characteristics or welding properties are not affected. Electrodes that have been wetted or that have lost any of their coating must not be used.

3.1.9 Pipe Cleanouts

Pipe cleanouts must be the same size as the pipe except that cleanout plugs larger than 4 inches will not be required. A cleanout installed in connection with cast-iron soil pipe must consist of a long-sweep 1/4 bend or one or two 1/8 bends extended to the place shown. An extra-heavy cast-brass or cast-iron ferrule with countersunk cast-brass head screw plug must be caulked into the hub of the fitting and must be flush with the floor. Cleanouts in connection with other pipe, where indicated, must

be T-pattern, 90-degree branch drainage fittings with cast-brass screw plugs, except plastic plugs must be installed in plastic pipe. Plugs must be the same size as the pipe up to and including 4 inches. Cleanout tee branches with screw plug must be installed at the foot of soil and waste stacks, at the foot of interior downspouts, on each connection to building storm drain where interior downspouts are indicated, and on each building drain outside the building. Cleanout tee branches may be omitted on stacks in single story buildings with slab-on-grade construction or where less than 18 inches of crawl space is provided under the floor. Cleanouts on pipe concealed in partitions must be provided with chromium plated bronze, nickel bronze, nickel brass or stainless steel flush type access cover plates. Round access covers must be provided and secured to plugs with securing screw. Square access covers may be provided with matching frames, anchoring lugs and cover screws. Cleanouts in finished walls must have access covers and frames installed flush with the finished wall. Cleanouts installed in finished floors subject to foot traffic must be provided with a chrome-plated cast brass, nickel brass, or nickel bronze cover secured to the plug or cover frame and set flush with the finished floor. Heads of fastening screws must not project above the cover surface. Where cleanouts are provided with adjustable heads, the heads must be plastic.

3.1.10 Condensate Drain Piping for Tropical Environments

Condensate drain piping materials must be rated for Drain, Waste and Vent service. Above grade use Polyvinyl Chloride (PVC) drain, waste and vent pipe and fittings, ASTM D2665, (Sch 40) ASTM F1760. Condensate piping must maintain a horizontal slope in the direction of discharge of not less than one-eighth unit vertical in 12 units horizontal (1 percent). Do not use PVC above grade in mechanical rooms, fire riser rooms, generator rooms or other high-abuse areas. The following condensate pipe diameters must be sized in accordance with equipment capacity refrigeration shown below:

EQUIPMENT CAPACITY	MINIMUM CONDENSATE PIPE DIAMETER
Up to 5 tons	1 inch
Over 5 tons to 40 tons	1-1/4 inch
Over 40 tons to 90 tons	1-1/2 inch
Over 90 tons to 125 tons	2 inch
Over 125 tons to 250 tons of refrigeration	2-1/2 inch

3.2 WATER HEATERS AND HOT WATER STORAGE TANKS

3.2.1 Relief Valves

No valves must be installed between a relief valve and its water heater or storage tank. The P&T relief valve must be installed where the valve actuator comes in contact with the hottest water in the heater. Whenever possible, the relief valve must be installed directly in a tapping in the tank or heater; otherwise, the P&T valve must be installed in the hot-water outlet piping. A vacuum relief valve must be provided on the cold water supply line to the hot-water storage tank or water heater and mounted above and within 6 inches above the top of the tank or water

heater.

3.2.2 Installation of Gas-Fired Water Heater

Installation must conform to NFPA 54 for gas fired. Storage water heaters that are not equipped with integral heat traps and having vertical pipe risers must be installed with heat traps directly on both the inlet and outlet. Circulating systems need not have heat traps installed. An acceptable heat trap may be a piping arrangement such as elbows connected so that the inlet and outlet piping make vertically upward runs of not less than 24 inches just before turning downward or directly horizontal into the water heater's inlet and outlet fittings. Commercially available heat traps, specifically designed by the manufacturer for the purpose of effectively restricting the natural tendency of hot water to rise through vertical inlet and outlet piping during standby periods may also be approved.

3.2.3 Heat Traps

Piping to and from each water heater and hot water storage tank must be routed horizontally and downward a minimum of 24 inches before turning in an upward direction.

3.2.4 Connections to Water Heaters

Connections of metallic pipe to water heaters must be made with dielectric unions or flanges. Use of dielectric nipples is prohibited unless internally lined and specifically designed to limit current flow between dissimilar metals.

3.2.5 Expansion Tank

A pre-charged expansion tank must be installed on the cold water supply between the water heater inlet and the cold water supply shut-off valve. The Contractor must adjust the expansion tank air pressure, as recommended by the tank manufacturer, to match incoming water pressure.

3.2.6 Direct Fired and Domestic Water Heaters

Notify the Contracting Officer when any direct fired domestic water heater over 400,000 BTU/hour is operational and ready to be inspected and certified.

3.3 FIXTURES AND FIXTURE TRIMMINGS

Polished chromium-plated pipe, valves, and fittings must be provided where exposed to view. Angle stops, straight stops, stops integral with the faucets, or concealed type of lock-shield, and loose-key pattern stops for supplies with threaded, sweat or solvent weld inlets must be furnished and installed with fixtures. Where connections between copper tubing and faucets are made by rubber compression fittings, a beading tool must be used to mechanically deform the tubing above the compression fitting. Exposed traps and supply pipes for fixtures and equipment must be connected to the rough piping systems at the wall, unless otherwise specified under the item. Floor and wall escutcheons must be as specified. Drain lines and hot water lines of fixtures for handicapped personnel must be insulated and do not require polished chrome finish. Plumbing fixtures and accessories must be installed within the space shown.

3.3.1 Fixture Connections

Where space limitations prohibit standard fittings in conjunction with the cast-iron floor flange, special short-radius fittings must be provided. Connections between earthenware fixtures and flanges on soil pipe must be made gastight and watertight with a closet-setting compound or neoprene gasket and seal. Use of natural rubber gaskets or putty will not be permitted. Fixtures with outlet flanges must be set the proper distance from floor or wall to make a first-class joint with the closet-setting compound or gasket and fixture used.

3.3.2 Flushometer Valves

Flushometer valves must be secured to prevent movement by anchoring the long finished top spud connecting tube to wall adjacent to valve with approved metal bracket. Flushometer valves for water closets must be installed 39 inches above the floor, except at water closets intended for use by the physically handicapped where flushometer valves must be mounted at approximately 30 inches above the floor and arranged to avoid interference with grab bars. In addition, for water closets intended for handicap use, the flush valve handle must be installed on the wide side of the enclosure. Bumpers for water closet seats must be installed on the flushometer stop.

3.3.3 Height of Fixture Rims Above Floor

Lavatories must be mounted with rim 31 inches above finished floor. Wall-hung drinking fountains and water coolers must be installed with rim 42 inches above floor. Wall-hung service sinks must be mounted with rim 28 inches above the floor. Installation of fixtures for use by the physically handicapped must be in accordance with ICC A117.1.

3.3.4 Shower Bath Outfits

The area around the water supply piping to the mixing valves and behind the escutcheon plate must be made watertight by caulking or gasketing.

3.3.5 Fixture Supports

Fixture supports for off-the-floor lavatories, urinals, water closets, and other fixtures of similar size, design, and use, must be of the chair-carrier type. The carrier must provide the necessary means of mounting the fixture, with a foot or feet to anchor the assembly to the floor slab. Adjustability must be provided to locate the fixture at the desired height and in proper relation to the wall. Support plates, in lieu of chair carrier, must be fastened to the wall structure only where it is not possible to anchor a floor-mounted chair carrier to the floor slab.

3.3.5.1 Support for Solid Masonry Construction

Chair carrier must be anchored to the floor slab. Where a floor-anchored chair carrier cannot be used, a suitable wall plate must be imbedded in the masonry wall.

3.3.5.2 Support for Concrete-Masonry Wall Construction

Chair carrier must be anchored to floor slab. Where a floor-anchored chair carrier cannot be used, a suitable wall plate must be fastened to

the concrete wall using through bolts and a back-up plate.

3.3.5.3 Support for Steel Stud Frame Partitions

Chair carrier must be used. The anchor feet and tubular uprights must be of the heavy duty design; and feet (bases) must be steel and welded to a square or rectangular steel tube upright. Wall plates, in lieu of floor-anchored chair carriers, must be used only if adjoining steel partition studs are suitably reinforced to support a wall plate bolted to these studs.

3.3.6 Backflow Prevention Devices

Plumbing fixtures, equipment, and pipe connections must not cross connect or interconnect between a potable water supply and any source of nonpotable water. Backflow preventers must be installed where indicated and in accordance with at all other locations necessary to preclude a cross-connect or interconnect between a potable water supply and any nonpotable substance. In addition backflow preventers must be installed at all locations where the potable water outlet is below the flood level of the equipment, or where the potable water outlet will be located below the level of the nonpotable substance. Backflow preventers must be located so that no part of the device will be submerged. Backflow preventers must be of sufficient size to allow unrestricted flow of water to the equipment, and preclude the backflow of any nonpotable substance into the potable water system. Bypass piping must not be provided around backflow preventers. Access must be provided for maintenance and testing. Each device must be a standard commercial unit.

3.3.7 Access Panels

Access panels must be provided for concealed valves and controls, or any item requiring inspection or maintenance. Access panels must be of sufficient size and located so that the concealed items may be serviced, maintained, or replaced.

3.3.8 Sight Drains

Sight drains must be installed so that the indirect waste will terminate 2 inches above the flood rim of the funnel to provide an acceptable air gap.

3.3.9 Traps

Each trap must be placed as near the fixture as possible, and no fixture must be double-trapped. Traps installed on cast-iron soil pipe must be cast iron. Traps installed on steel pipe or copper tubing must be recess-drainage pattern, or brass-tube type. Traps installed on plastic pipe may be plastic conforming to ASTM D3311. Traps for acid-resisting waste must be of the same material as the pipe.

3.3.10 Shower Pans

Before installing shower pan, subfloor must be free of projections such as nail heads or rough edges of aggregate. Drain must be a bolt-down, clamping-ring type with weepholes, installed so the lip of the subdrain is flush with subfloor.

3.3.10.1 General

The floor of each individual shower, the shower-area portion of combination shower and drying room, and the entire shower and drying room where the two are not separated by curb or partition, must be made watertight with a shower pan fabricated in place. The shower pan material must be cut to size and shape of the area indicated, in one piece to the maximum extent practicable, allowing a minimum of 6 inches for turnup on walls or partitions, and must be folded over the curb with an approximate return of 1/4 of curb height. The upstands must be placed behind any wall or partition finish. Subflooring must be smooth and clean, with nailheads driven flush with surface, and must be sloped to drain. Shower pans must be clamped to drains with the drain clamping ring.

3.3.10.2 Nonplasticized Polyvinyl Chloride (PVC) Shower Pans

Nonplasticized PVC must be turned up behind walls or wall surfaces a distance of not less than 6 inches in room areas and 3 inches above curb level in curbed spaces with sufficient material to fold over and fasten to outside face of curb. Corners must be pig-ear type and folded between pan and studs. Only top 1 inch of upstand must be nailed to hold in place. Nails must be galvanized large-head roofing type. Approved duct tape must be used on metal framing or studs to secure pig-ear fold and membrane. Where no backing is provided between studs, the membrane slack must be taken up by pleating and stapling or nailing to studding at top inch of upstand. To adhere the membrane to vertical surfaces, the back of the membrane and the surface to which it is to be applied must be coated with adhesive that becomes dry to the touch in 5 to 10 minutes, after which the membrane must be pressed into place. Trim for drain must be exactly the size of drain opening. Bolt holes must be pierced to accommodate bolts with a tight fit. Adhesive must be used between pan and subdrain. Clamping ring must be bolted firmly. A small amount of gravel or porous materials must be placed at weepholes so that holes remain clear when setting bed is poured. Membrane must be solvent welded with PVC solvent cement. Surfaces to be solvent welded must be clean (free of grease and grime). Sheets must be laid on a flat surface with an overlap of about 2 inches. Top edge must be folded back and surface primed with a PVC primer. PVC cement must be applied and surfaces immediately placed together, while still wet. Joint must be lightly rolled with a paint roller, then as the joint sets must be rolled firmly but not so hard as to distort the material. In long lengths, about 2 or 3 feet at a time must be welded. On wood subflooring, two layers of 15 pound felt must be installed prior to installation of shower pan to ensure a smooth surface installation.

3.4 VIBRATION-ABSORBING FEATURES

Mechanical equipment, pumps, must be isolated from the building structure by approved vibration-absorbing features, unless otherwise shown. Submit details of vibration-absorbing features, including arrangement, foundation plan, dimensions and specifications. Each foundation must include an adequate number of standard isolation units. Each unit must consist of machine and floor or foundation fastening, together with intermediate isolation material, and must be a standard product with printed load rating. Piping connected to mechanical equipment must be provided with flexible connectors.

3.5 WATER METER REMOTE READOUT REGISTER

The remote readout register must be mounted at the location indicated or as directed by the Contracting Officer.

3.6 IDENTIFICATION SYSTEMS

3.6.1 Identification Tags

Identification tags made of brass, engraved laminated plastic, or engraved anodized aluminum, indicating service and valve number must be installed on valves, except those valves installed on supplies at plumbing fixtures. Tags must be 1-3/8 inch minimum diameter, and marking must be stamped or engraved. Indentations must be black, for reading clarity. Tags must be attached to valves with No. 12 AWG, copper wire, chrome-plated beaded chain, or plastic straps designed for that purpose.

3.6.2 Pipe Color Code Marking

Color code marking of piping must be as specified in Section 09 90 00 PAINTS AND COATINGS.

3.6.3 Color Coding Scheme for Locating Hidden Utility Components

Scheme must be provided in buildings having suspended grid ceilings. The color coding scheme must identify points of access for maintenance and operation of operable components which are not visible from the finished space and installed in the space directly above the suspended grid ceiling. The operable components must include valves, dampers, switches, linkages and thermostats. The color coding scheme must consist of a color code board and colored metal disks. Each colored metal disk must be approximately 3/8 inch in diameter and secured to removable ceiling panels with fasteners. The fasteners must be inserted into the ceiling panels so that the fasteners will be concealed from view. The fasteners must be manually removable without tools and must not separate from the ceiling panels when panels are dropped from ceiling height. Installation of colored metal disks must follow completion of the finished surface on which the disks are to be fastened. The color code board must have the approximate dimensions of 3 foot width, 30 inches height, and 1/2 inch thickness. The board must be made of wood fiberboard and framed under glass or 1/16 inch transparent plastic cover. Unless otherwise directed, the color code symbols must be approximately 3/4 inch in diameter and the related lettering in 1/2 inch high capital letters. The color code board must be mounted and located in the mechanical or equipment room. The color code system must be as indicated below:

Color	System	Item	Location

3.7 ESCUTCHEONS

Escutcheons must be provided at finished surfaces where bare or insulated piping, exposed to view, passes through floors, walls, or ceilings, except in boiler, utility, or equipment rooms. Escutcheons must be fastened securely to pipe or pipe covering and must be satin-finish, corrosion-resisting steel, polished chromium-plated zinc alloy, or polished chromium-plated copper alloy. Escutcheons must be either

one-piece or split-pattern, held in place by internal spring tension or setscrew.

3.8 PAINTING

Painting of pipes, hangers, supports, and other iron work, either in concealed spaces or exposed spaces, is specified in Section 09 90 00 PAINTS AND COATINGS.

3.8.1 Painting of New Equipment

New equipment painting must be factory applied or shop applied, and must be as specified herein, and provided under each individual section.

3.8.1.1 Factory Painting Systems

Manufacturer's standard factory painting systems may be provided subject to certification that the factory painting system applied will withstand 125 hours in a salt-spray fog test, except that equipment located outdoors must withstand 500 hours in a salt-spray fog test. Salt-spray fog test must be in accordance with ASTM B117, and for that test the acceptance criteria must be as follows: immediately after completion of the test, the paint must show no signs of blistering, wrinkling, or cracking, and no loss of adhesion; and the specimen must show no signs of rust creepage beyond 0.125 inch on either side of the scratch mark.

The film thickness of the factory painting system applied on the equipment must not be less than the film thickness used on the test specimen. If manufacturer's standard factory painting system is being proposed for use on surfaces subject to temperatures above 120 degrees F, the factory painting system must be designed for the temperature service.

3.8.1.2 Shop Painting Systems for Metal Surfaces

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except metal surfaces subject to temperatures in excess of 120 degrees F must be cleaned to bare metal.

Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Color of finish coat must be aluminum or light gray.

a. Temperatures Less Than 120 Degrees F: Immediately after cleaning, the metal surfaces subject to temperatures less than 120 degrees F must receive one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of one mil; and two coats of enamel applied to a minimum dry film thickness of one mil per coat.

b. Temperatures Between 120 and 400 Degrees F: Metal surfaces subject to temperatures between 120 and 400 degrees F must receive two coats of 400 degrees F heat-resisting enamel applied to a total minimum thickness of 2 mils.

c. Temperatures Greater Than 400 Degrees F: Metal surfaces subject to

temperatures greater than 400 degrees F must receive two coats of 600 degrees F heat-resisting paint applied to a total minimum dry film thickness of 2 mils.

3.9 TESTS, FLUSHING AND DISINFECTION

Submit test reports in booklet form showing all field tests performed to adjust each component and all field tests performed to prove compliance with the specified performance criteria, completion and testing of the installed system. Each test report must indicate the final position of controls.

3.9.1 Plumbing System

The following tests must be performed on the plumbing system in accordance with ICC IPC, except that the drainage and vent system final test must include the smoke test. The Contractor has the option to perform a peppermint test in lieu of the smoke test. If a peppermint test is chosen, the Contractor must submit a testing procedure and reasons for choosing this option in lieu of the smoke test to the Contracting Officer for approval.

a. Drainage and Vent Systems Test. The final test must include a smoke test.

b. Building Sewers Tests.

c. Water Supply Systems Tests.

3.9.1.1 Test of Backflow Prevention Assemblies

Certification of proper operation must be submitted and must be as accomplished in accordance with state regulations by an individual certified by the state to perform such tests. If no state requirement exists, the Contractor must have the manufacturer's representative test the device to ensure the unit is properly installed and performing as intended. The Contractor must provide written documentation of the tests performed and signed by the individual performing the tests. Backflow prevention assembly must be tested using gauges specifically designed for the testing of backflow prevention assemblies.

Backflow prevention assembly test gauges must be tested annually for accuracy in accordance with the requirements of State or local regulatory agencies. If there is no State or local regulatory agency requirements, gauges must be tested annually for accuracy in accordance with the requirements of University of Southern California's Foundation of Cross Connection Control and Hydraulic Research or the American Water Works Association Manual of Cross Connection (Manual M-14), or any other approved testing laboratory having equivalent capabilities for both laboratory and field evaluation of backflow prevention assembly test gauges. Report form for each assembly must include, as a minimum, the following:

Data on Device	Data on Testing Firm
Type of Assembly	Name

Manufacturer	Address
Model Number	Certified Tester
Serial Number	Certified Tester No.
Size	Date of Test
Location	
Test Pressure Readings	Serial Number and Test Data of Gauges

If the unit fails to meet specified requirements, the unit must be repaired and retested.

3.9.1.2 Shower Pans

After installation of the pan and finished floor, the drain must be temporarily plugged below the weep holes. The floor area must be flooded with water to a minimum depth of 1 inch for a period of 24 hours. Any drop in the water level during test, except for evaporation, will be reason for rejection, repair, and retest.

3.9.2 Defective Work

If inspection or test shows defects, such defective work or material must be replaced or repaired as necessary and inspection and tests must be repeated. Repairs to piping must be made with new materials. Caulking of screwed joints or holes will not be acceptable.

3.9.3 System Flushing

3.9.3.1 During Flushing

Before operational tests or disinfection, potable water piping system must be flushed with potable water. Sufficient water must be used to produce a water velocity that is capable of entraining and removing debris in all portions of the piping system. This requires simultaneous operation of all fixtures on a common branch or main in order to produce a flushing velocity of approximately 4 fps through all portions of the piping system. In the event that this is impossible due to size of system, the Contracting Officer (or the designated representative) must specify the number of fixtures to be operated during flushing. Contractor must provide adequate personnel to monitor the flushing operation and to ensure that drain lines are unobstructed in order to prevent flooding of the facility. Contractor must be responsible for any flood damage resulting from flushing of the system. Flushing must be continued until entrained dirt and other foreign materials have been removed and until discharge water shows no discoloration. All faucets and drinking water fountains, to include any device considered as an end point device by NSF/ANSI/CAN 61, Section 9, must be flushed a minimum of 0.25 gallons per 24 hour period, ten times over a 14 day period.

3.9.3.2 After Flushing

System must be drained at low points. Strainer screens must be removed, cleaned, and replaced. After flushing and cleaning, systems must be

prepared for testing by immediately filling water piping with clean, fresh potable water. Any stoppage, discoloration, or other damage to the finish, furnishings, or parts of the building due to the Contractor's failure to properly clean the piping system must be repaired by the Contractor. When the system flushing is complete, the hot-water system must be adjusted for uniform circulation. Flushing devices and automatic control systems must be adjusted for proper operation according to manufacturer's instructions. Flow rates on fixtures must not exceed those stated in PART 2 of this Section. Unless more stringent local requirements exist, lead levels must not exceed limits established by 40 CFR 141.80 (c)(1). The water supply to the building must be tested separately to ensure that any lead contamination found during potable water system testing is due to work being performed inside the building.

3.9.4 Operational Test

Upon completion of flushing and prior to disinfection procedures, the Contractor must subject the plumbing system to operating tests to demonstrate satisfactory installation, connections, adjustments, and functional and operational efficiency. Such operating tests must cover a period of not less than 8 hours for each system and must include the following information in a report with conclusion as to the adequacy of the system:

a. Time, date, and duration of test.

b. Water pressures at the most remote and the highest fixtures.

c. Operation of each fixture and fixture trim.

d. Operation of each valve, hydrant, and faucet.

e. Pump suction and discharge pressures.

f. Temperature of each domestic hot-water supply.

g. Operation of each floor drain by flooding with water.

h. Operation of each vacuum breaker and backflow preventer.

3.9.5 Disinfection

After all system components are provided and operational tests are complete, the entire domestic hot- and cold-water distribution system must be disinfected. Before introducing disinfecting chlorination material, entire system must be flushed with potable water until any entrained dirt and other foreign materials have been removed.

Water chlorination procedure must be in accordance with AWWA C651 and AWWA C652 as modified and supplemented by this specification. The chlorinating material must be hypochlorites or liquid chlorine. The chlorinating material must be fed into the water piping system at a constant rate at a concentration of at least 50 parts per million (ppm). Feed a properly adjusted hypochlorite solution injected into the system with a hypochlorinator, or inject liquid chlorine into the system through a solution-feed chlorinator and booster pump until the entire system is completely filled.

3.9.5.1 Water Chlorination Monitoring

Test the chlorine residual level in the water at 6 hour intervals for a continuous period of 24 hours. If at the end of a 6 hour interval, the chlorine residual has dropped to less than 25 ppm, flush the piping including tanks with potable water, and repeat the above chlorination procedures. During the chlorination period, each valve and faucet must be opened and closed several times. After the second 24 hour period, verify that no less than 25 ppm chlorine residual remains in the treated system. The 24 hour chlorination procedure must be repeated until no less than 25 ppm chlorine residual remains in the treated system.

3.9.5.2 Water Chlorination Flushing

Upon the specified verification, the system including tanks must then be flushed with potable water until the residual chlorine level is reduced to less than one part per million. During the flushing period, each valve and faucet must be opened and closed several times.

3.9.5.3 Sample Testing

Take additional samples of water in disinfected containers, for bacterial examination, at locations specified by the Contracting Officer. Test these samples for total coliform organisms (coliform bacteria, fecal coliform, streptococcal, and other bacteria) in accordance with AWWA 10084. The testing method used must be EPA approved for drinking water systems and must comply with applicable local and state requirements.

3.9.5.4 Disinfection Acceptance

Disinfection must be repeated until bacterial tests indicate the absence of coliform organisms (zero mean coliform density per 100 milliliters) in the samples for at least 2 full days. The system will not be accepted until satisfactory bacteriological results have been obtained.

3.10 POSTED INSTRUCTIONS

Framed instructions under glass or in laminated plastic, including wiring and control diagrams showing the complete layout of the entire system, must be posted where directed. Condensed operating instructions explaining preventive maintenance procedures, methods of checking the system for normal safe operation, and procedures for safely starting and stopping the system must be prepared in typed form, framed as specified above for the wiring and control diagrams and posted beside the diagrams. The framed instructions must be posted before acceptance testing of the systems.

3.11 PERFORMANCE OF WATER HEATING EQUIPMENT

Standard rating condition terms are as follows:

DP = Draw pattern

EF = Energy factor, minimum overall efficiency.

ET = Minimum thermal efficiency with 70 degrees F delta T.

SL = Standby loss is maximum (Btu/h) based on a 70 degrees F temperature difference between stored water and ambient requirements.

UEF = Uniform energy factor

V = Rated volume in gallons

Q = Nameplate input rate in kW (Btu/h)

3.11.1 Storage Water Heaters

3.11.1.1 Electric

a. Storage capacity more than or equal to 20 gallons and less than or equal to 55 gallons with a draw pattern (DP) of: very small must have a uniform energy factor (UEF) of 0.8808 - (0.0008 x V), low must have a uniform energy factor (UEF) of 0.9254 - (0.0003 x V), medium must have a uniform energy factor (UEF) of 0.9307 - (0.0002 x V), high must have a uniform energy factor (UEF) of 0.9349 - (0.0001 x V) per 10 CFR 430.

3.11.1.2 Gas

a. Storage capacity more than 55 gallons and less than or equal to 100 gallons with a draw pattern (DP) of: very small must have a uniform energy factor (UEF) of 0.6470 - (0.0006 x V), low must have a uniform energy factor (UEF) of 0.7689 - (0.0005 x V), medium must have a uniform energy factor (UEF) of 0.7897 - (0.0004 x V), high must have a uniform energy factor (UEF) of 0.8702 - (0.0003 x V) per 10 CFR 430.

b. Storage capacity less than or equal to 120 gallons with input rating more than 75,000 Btu/h and less than 105,000 Btu/h with a draw pattern (DP) of: very small must have a uniform energy factor (UEF) of 0.2674 - (0.0009 x V), low must have a uniform energy factor (UEF) of 0.5362 - (0.0012 x V), medium must have a uniform energy factor (UEF) of 0.6002 - (0.0011 x V), high must have a uniform energy factor (UEF) of 0.6597 - (0.0009 x V) per 10 CFR 430.

3.11.2 Instantaneous Water Heater

3.11.2.1 Electric

a. Storage capacity less than 2 gallons with a draw pattern (DP) of: very small must have a uniform energy factor (UEF) of 0.91, low must have a uniform energy factor (UEF) of 0.91, medium must have a uniform energy factor (UEF) of 0.91, high must have a uniform energy factor (UEF) of 0.92 per 10 CFR 430.

3.12 TABLES

TABLE I

PIPE AND FITTING MATERIALS FOR DRAINAGE, WASTE, VENT AND CONDENSATE DRAIN PIPING SYSTEMS

Item #	Pipe and Fitting Materials	SERVICE A	SERVICE B	SERVICE C	SERVICE D	SERVICE E	SERVICE F	SERVICE G
20	Polyvinyl Chloride plastic drain, waste and vent pipe and fittings, ASTM D2665, ASTM F891, (Sch 40) ASTM F1760	X	X	X	X	X	X	X

SERVICE:

A - Underground Building Soil, Waste and Storm Drain
B - Aboveground Soil, Waste, Drain In Buildings
C - Underground Vent
D - Aboveground Vent
E - Interior Rainwater Conductors Aboveground
F - Corrosive Waste And Vent Above And Belowground
G - Condensate Drain Aboveground

* - Hard Temper

TABLE II

PIPE AND FITTING MATERIALS FOR PRESSURE PIPING SYSTEMS

Item #	Pipe and Fitting Materials	SERVICE A	SERVICE B	SERVICE C	SERVICE D
8	Seamless copper water tube, ASTM B88, ASTM B88M	X**	X**	X**	X***
10	Wrought copper and bronze solder-joint pressure fittings, ASME B16.22 for use with Item 8	X	X	X	X

TABLE II

PIPE AND FITTING MATERIALS FOR PRESSURE PIPING SYSTEMS

Item #	Pipe and Fitting Materials	SERVICE A	SERVICE B	SERVICE C	SERVICE D
11	Cast copper alloy solder-joint pressure fittings, ASME B16.18 for use with Item 8	X	X	X	X
33	Fittings: brass or bronze; ASME B16.15, and ASME B16.18 ASTM B828	X	X		
36	Nipples, pipe threaded ASTM A733	X	X	X	
	SERVICE: A - Cold Water Service Aboveground B - Hot and Cold Water Distribution 180 degrees F Maximum Aboveground C - Compressed Air Lubricated				

TABLE III

STANDARD RATING CONDITIONS AND MINIMUM PERFORMANCE RATINGS FOR WATER HEATING EQUIPMENT

FUEL	STORAGE CAPACITY OR RATING CONDITION	INPUT RATING	TEST PROCEDURE	REQUIRED PERFORMANCE	
A. STORAGE WATER HEATERS					
Elect.	≥20 gal and ≤55 gal		10 CFR 430	DP	UEF
				Very Small	0.8808 - (0.0008 x V)
				Low	0.9254 - (0.0003 x V)
				Medium	0.9307 - (0.0002 x V)
				High	0.9349 - (0.0001 x V)
Elect.	>55 gal and ≤120 gal		10 CFR 430	DP	UEF
				Very Small	1.9236 - (0.0011 x V)
				Low	2.0440 - (0.0011 x V)
				Medium	2.1171 -
				High	2.2418 -
Elect. Heat Pump		≤24 Amps and ≤250 Volts	10 CFR 430	Rating Condition	UEF
				Integrated heat pump water heater (HPWH)	UEF ≥3.3 and First Hour Rating ≥45 gal/h
				Integrated HPWH, >120 V/15 Amp Circuit or Split-System HPWH	UEF >2.2 and First Hour Rating ≥45 gal/h
Elect. Heat Pump		>12 kW	10 CFR 430	HPWH COP ≥3.0	

TABLE III

STANDARD RATING CONDITIONS AND MINIMUM PERFORMANCE RATINGS FOR WATER HEATING EQUIPMENT

FUEL	STORAGE CAPACITY OR RATING CONDITION	INPUT RATING	TEST PROCEDURE	REQUIRED PERFORMANCE	
Gas	≥20 gal and ≤55 gal		10 CFR 430	DP	UEF
				Very Small	0.3456 - (0.0020 x V)
				Low	0.5982 - (0.0019 x V)
				Medium	0.6483 - (0.0017 x V)
				High	0.6920 - (0.0013 x V)
Gas	>55 gal and ≤100 gal		10 CFR 430	DP	UEF
				Very Small	0.6470 -
				Low	0.7689 -
				Medium	0.7897 - (0.0004 x V)
				High	0.8072 - (0.0003 x V)
Gas	≤120 gal	75,000 Btu/h	10 CFR 430	DP	UEF
				Very Small	0.2674 - (0.0009 x V)
				Low	0.5362 - (0.0012 x V)
				Medium	0.6002 - (0.0011 x V)
				High	0.6597 - (0.0009 x V)
Oil	≤50 gal		10 CFR 430	DP	UEF
				Very Small	0.2509 - (0.0012 x V)
				Low	0.5330 -
				Medium	0.6078 - (0.0016 x V)
				High	0.6815 - (0.0014 x V)

TABLE III

STANDARD RATING CONDITIONS AND MINIMUM PERFORMANCE RATINGS FOR WATER HEATING EQUIPMENT

FUEL	STORAGE CAPACITY OR RATING CONDITION	INPUT RATING	TEST PROCEDURE	REQUIRED PERFORMANCE	
Oil	≤120 gal	>105,000 Btu/h and ≤ 140,000 Btu/h	10 CFR 430	DP	UEF
				Very Small	0.2932 - (0.0015 x V)
				Low	0.5596 - (0.0018 x V)
				Medium	0.6194 - (0.0016 x V)
				High	0.6740 - (0.0013 x V)
B. Unfired Hot Water Storage, R-12.5 min.					
C. Instantaneous Water Heater					
Elect.	<2 gal		10 CFR 430	DP	UEF
				Very Small	0.91
				Low	0.91
				Medium	0.91
				High	0.92
Gas	<2 gal and >50,000 Btu/h		10 CFR 430	DP	UEF
				Very Small	0.80
				Low	0.81
				Medium	0.81
				High	0.81
Gas	4,000 (btu/h)/gal and 10 gal max.	200,000 Btu/h min.	ANSI Z21.10.3/C	ET = 80 percent	
Gas	4,000 (btu/h)/gal and 10 gal max.	200,000 Btu/h min.	ANSI Z21.10.3/C	ET = 80 percent SL = (Q/800+110x(V^^1/2))	
Oil	4,000 (btu/h)/gal and 2 gal max.	50,000 Btu/h min. 210,000 Btu/h max.	10 CFR 430	ET = 80 percent and EF = 0.59-0.0005V	
Oil	4,000 (btu/h)/gal and 10 gal max.	210,000 Btu/h min.	ANSI Z21.10.3/C	ET = 80 percent	

TABLE III

STANDARD RATING CONDITIONS AND MINIMUM PERFORMANCE RATINGS FOR WATER HEATING EQUIPMENT

FUEL	STORAGE CAPACITY OR RATING CONDITION	INPUT RATING	TEST PROCEDURE	REQUIRED PERFORMANCE
Oil	4,000 (btu/h)/gal and 10 gal max.	210,000 Btu/h min.	ANSI Z21.10.3/C	ET = 78 percent SL = (Q/800+110x(V^^1/2)) max.
D. Pool Heater				
Gas or Oil	All	All	ASHRAE 146	ET = 82 percent
Heat Pump All	All	All	ANSI/AHRI 1160	COP = 4.0

TERMS:

DP = Draw Pattern
EF = Energy factor, minimum overall efficiency.
ET = Minimum thermal efficiency with 70 degrees F delta T.
SL = Standby loss is maximum Btu/h based on a 70 degree F temperature difference between stored water and ambient requirements.
UEF = Uniform energy factor
V = Rated storage volume in gallons
Q = Nameplate input rate in Btu/h

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 03 00.00 20

BASIC MECHANICAL MATERIALS AND METHODS
08/24 MCBCL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus

INTERNATIONAL CODE COUNCIL (ICC)

ICC IFGC	(2021) International Fuel Gas Code
ICC IMC	(2024) International Mechanical Code
ICC IPC	(2024) International Plumbing Code

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 1	(2021) Motors and Generators
NEMA MG 10	(2017) Energy Management Guide for Selection and Use of Fixed Frequency Medium AC Squirrel-Cage Polyphase Induction Motors
NEMA MG 11	(1977; R 2012) Energy Management Guide for Selection and Use of Single Phase Motors

1.2 SUBMITTALS

Government approval is required for all submittals.

1.3 RELATED REQUIREMENTS

This section applies to all sections of Divisions: 21, FIRE SUPPRESSION; 22, PLUMBING; and 23, HEATING, VENTILATING, AND AIR CONDITIONING of this project specification, unless specified otherwise in the individual section.

1.4 QUALITY ASSURANCE

1.4.1 Material and Equipment Qualifications

Provide materials and equipment that are standard products of manufacturers regularly engaged in the manufacture of such products, which are of a similar material, design and workmanship. Standard products must have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year use must include applications of equipment and

materials under similar circumstances and of similar size. The product must have been for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2 year period.

1.4.2 Alternative Qualifications

Products having less than a two-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturer's factory or laboratory tests, can be shown.

1.4.3 Service Support

The equipment items must be supported by service organizations. Submit a certified list of qualified permanent service organizations for support of the equipment which includes their addresses and qualifications. These service organizations must be reasonably convenient to the equipment installation and able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.4.4 Manufacturer's Nameplate

For each item of equipment, provide a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

1.4.5 Modification of References

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction", or words of similar meaning, to mean the Contracting Officer.

1.4.5.1 Definitions

For the International Code Council (ICC) Codes referenced in the contract documents, advisory provisions must be considered mandatory, the word "should" is interpreted as "must." Reference to the "code official" must be interpreted to mean the "Contracting Officer." For Navy owned property, references to the "owner" must be interpreted to mean the "Contracting Officer." For leased facilities, references to the "owner" must be interpreted to mean the "lessor." References to the "permit holder" must be interpreted to mean the "Contractor."

1.4.5.2 Administrative Interpretations

For ICC Codes referenced in the contract documents, the provisions of Chapter 1, "Administrator," do not apply. These administrative requirements are covered by the applicable Federal Acquisition Regulations (FAR) included in this contract and by the authority granted to the Officer in Charge of Construction to administer the construction of this project. References in the ICC Codes to sections of Chapter 1, must be applied appropriately by the Contracting Officer as authorized by his administrative cognizance and the FAR.

1.5 DELIVERY, STORAGE, AND HANDLING

Handle, store, and protect equipment and materials to prevent damage before and during installation in accordance with the manufacturer's recommendations, and as approved by the Contracting Officer. Replace damaged or defective items.

1.6 ELECTRICAL REQUIREMENTS

Furnish motors, controllers, disconnects and contactors with their respective pieces of equipment. Motors, controllers, disconnects and contactors must conform to and have electrical connections provided under Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Furnish internal wiring for components of packaged equipment as an integral part of the equipment. Controllers and contactors shall have a maximum of 120 volt control circuits, and must have auxiliary contacts for use with the controls furnished. When motors and equipment furnished are larger than sizes indicated, the cost of additional electrical service and related work must be included under the section that specified that motor or equipment. Power wiring and conduit for field installed equipment must be provided under and conform to the requirements of Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

1.6.1 Motor Voltage

Provide motors rated for the voltage supplied. Motors shall be suitable for use at 90% to 110% of the nominal supplied voltage and shall have a service factor of at least 1.1 at that nominal supplied voltage. Motors indicated to be "Usable at 208 Volts" or "Usable at 200 Volts" are not permitted to be utilized on electrical systems with a nominal supplied voltage of 208 volts.

1.6.2 Single Phase Motor Efficiency

Unless otherwise specified, single-phase fractional-horsepower alternating-current motors must be high efficiency types corresponding to the applications listed in NEMA MG 11.

1.6.3 Poly Phase Motor Efficiency

Unless other specified polyphase squirrel-cage induction motors must be premium efficiency with continuous ratings that meet or exceed energy efficient ratings in accordance with Table 12-12 of NEMA MG 1 and corresponding to the applications listed in NEMA MG 10

1.6.4 Three-Phase Motor Protection

Provide controllers for motors rated three horsepower and larger with electronic phase-voltage monitors designed to protect motors from phase-loss, undervoltage, and overvoltage. Provide protection for motors from immediate restart by a time adjustable restart relay.

1.7 INSTRUCTION TO GOVERNMENT PERSONNEL

When specified in other sections, furnish the services of competent instructors to give full instruction to the designated Government personnel in the adjustment, operation, and maintenance, including pertinent safety requirements, of the specified equipment or system. Instructors must be thoroughly familiar with all parts of the installation

and must be trained in operating theory as well as practical operation and maintenance work.

Instruction must be given during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished must be as specified in the individual section. When more than 4 man-days of instruction are specified, use approximately half of the time for classroom instruction. Use other time for instruction with the equipment or system.

When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instruction to acquaint the operating personnel with the changes or modifications.

1.8 ACCESSIBILITY

Install all work so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible. Install concealed valves, expansion joints, controls, dampers, and equipment requiring access, in locations freely accessible through access doors.

1.9 EQUIPMENT INVENTORY UPDATE

Submit information for each piece of equipment removed and supplied for use of Camp Lejeune to update the Maximo equipment inventory. For the purposes of this paragraph, inventoried equipment is defined as equipment listed on the Maximo Equipment Inventory Update form.

1.9.1 Requirements

The contractor shall prepare and submit one Maximo Equipment Inventory Update form for each individual item of inventoried equipment that is demolished, removed, replaced, or installed. (ex: three new condensing units would require the submission of three Equipment Inventory Update forms. The replacement of two existing air handling units with two new air handling units would require the submission of two Equipment Inventory Update forms). The contractor shall prepare and submit a VAV/TAB Room Number List for each VAV/Tab model installed in a single building. Only one Maximo Equipment Inventory Update form is required for each model of VAV or TAB in a single building.

1.9.1.1 Demolition of all equipment in a structure or facility

When all the inventoried equipment in a building or structure is demolished or removed, and not replaced, an Equipment Inventory Update form is not required.

1.9.2 Standards

The contractor shall provide accurate, complete, and legible information on all required forms. All required forms shall be completed and delivered to the Contracting Officer on or before the Beneficial Occupancy Date. All information on Equipment Inventory Update forms shall be obtained by visual inspection of equipment data plate(s).

1.9.3 Form Preparation

Each required Maximo Equipment Inventory Update form shall contain the

following information:

(1) The name and telephone number of an individual who can be contacted for clarification or additional information pertaining to the data on the form.

(2) The date of data collection

(3) The building or structure identification number and the specific location of the equipment within the structure (ex: 3d deck mech room)

(4) A check adjacent to the description of the new or replacement item, and a check adjacent to the supplemental description if applicable (ex: circulating pump and HVAC or steam)

(5) The Maximo number or serial number of the demolished or removed item, if applicable

(6) All applicable data from the equipment data plate

Each Room Number List form shall contain the following information:

(1) The name and telephone number of the individual providing the information

(2) The date the form was completed

(3) The building or structure identification number

(4) A check in the box adjacent to each applicable room number

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

3.1 Manufacturer's Recommendations

All material and equipment shall be installed in accordance with the manufacturer's recommendations for the intended purpose. Use the more stringent methods when manufacturer's recommendations, and plan & specification requirements differ. The contractor shall notify the government of any conflicts between manufacturer's recommendations and plans & specification requirements.

3.2 International Construction Codes

All material, equipment and installation shall be in accordance with the ICC IFGC, ICC IPC, and ICC IMC unless noted otherwise on the drawings and/or specifications. The contractor shall notify the government of any conflicts between ICC code requirements and contract requirements.

3.3 PAINTING OF NEW EQUIPMENT

New equipment painting must be factory applied or shop applied, and must be as specified herein, and provided under each individual section.

3.3.1 Factory Painting Systems

Manufacturer's standard factory painting systems may be provided subject to certification that the factory painting system applied will withstand 125 hours in a salt-spray fog test, except that equipment located outdoors must withstand 500 hours in a salt-spray fog test. Salt-spray fog test must be in accordance with ASTM B117, and for that test the acceptance criteria must be as follows: immediately after completion of the test, the paint must show no signs of blistering, wrinkling, or cracking, and no loss of adhesion; and the specimen must show no signs of rust creepage beyond 0.125 inch on either side of the scratch mark.

The film thickness of the factory painting system applied on the equipment must not be less than the film thickness used on the test specimen. If manufacturer's standard factory painting system is being proposed for use on surfaces subject to temperatures above 120 degrees F, the factory painting system must be designed for the temperature service.

3.3.2 Shop Painting Systems for Metal Surfaces

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except metal surfaces subject to temperatures in excess of 120 degrees F must be cleaned to bare metal.

Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Color of finish coat must be aluminum or light gray.

a. Temperatures Less Than 120 Degrees F: Immediately after cleaning, the metal surfaces subject to temperatures less than 120 degrees F must receive one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of 1 mil; and two coats of enamel applied to a minimum dry film thickness of 1 mil per coat.

b. Temperatures Between 120 and 400 Degrees F: Metal surfaces subject to temperatures between 120 and 400 degrees F must receive two coats of 400 degrees F heat-resisting enamel applied to a total minimum

thickness of 2 mils.

c. Temperatures Greater Than 400 Degrees F: Metal surfaces subject to temperatures greater than 400 degrees F must receive two coats of 600 degrees F heat-resisting paint applied to a total minimum dry film thickness of 2 mils.

MAXIMO EQUIPMENT INVENTORY UPDATE

Employee: _____ Phone: _____ Date: ____/____/____

Bldg: _____ Specific Location: _____

__ AC, Computer Room
__ AC, Package
__ AC, Package Terminal
__ Assembly, Trap line
__ Backflow Preventer
__ Boiler
__ Chiller, Air Cooled Recip
__ Chiller, Air Cooled Screw
__ Chiller, Air Cooled Scroll
__ Chiller, Water Cooled Recip
__ Chiller, Water Cooled Screw
__ Compressor, Control Air
__ Compressor, Industrial Air
__ Dryer, Refrigerated Air
__ Exchanger, Heat
__ Evaporator, Freezer
__ Evaporator, Refrigerator
__ Fan, Exhaust
__ Generator
__ Heater, Space
__ Heater, Unit
__ Heat Pump, Geo-Thermal
__ Heat Pump, Indoor Unit
__ Heat Pump, Outdoor Unit
__ Heat Pump, Package
__ Heat Pump, Package Terminal
__ Pump, Circulating, Chilled Water
__ Pump, Circulating, Domestic Water
__ Pump, Circulating, Dual Temp Water
__ Pump, Circulating, Heating Water
__ Pump, Condensate
__ Pump, Sump
__ Regulator, Temperature
__ Tank, Hot Water Storage
__ Tower, Cooling
__ Unit, Air Handling
__ Unit, AC Condensing
__ Unit, Freezer Condensing
__ Unit, Refrigerator Condensing
__ Unit, Fan Coil
__ Unit, TAB (Attach Room No. List)
__ Unit, VAV (Attach Room No. List)
__ Valve, Pressure Reducing
__ Valve, Steam Pilot
__ Water Heater

Demolished/Removed Equipment

Maximo no: _____ or Ser no: _____

New Equipment

Manufacturer: _____

Model no: _____

Ser no: _____

Type: __Elec __Oil __LP Gas __Nat Gas __Steam __Water __Air

Motor Data: HP____ Volts____ Phase____ RLA_____ RPM____ Frame____

Tons____ No. of Motors____ no. of Belts____ Belt size(s)____ CFM____

KW____ Refrig type_____ Refrig Qty_____ Filter Size(s)_____

-- End of Section --

SECTION 23 05 48.19

BRACING FOR HVAC
05/18, CHG 2: 08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 355.2	(2007) Qualification of Post-Installed Mechanical Anchors in Concrete and Commentary
ACI 355.4	(2011) Qualification of Post-Installed Adhesive Anchors in Concrete (ACI 355.4) and Commentary

AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC)

AISC 325	(2017) Steel Construction Manual

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7-16	(2017; Errata 2018; Supp 1 2018) Minimum Design Loads and Associated Criteria for Buildings and Other Structures

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C105/A21.5	(2018) Polyethylene Encasement for Ductile-Iron Pipe Systems
AWWA C116/A21.16	(2015) Protective Fusion-Bonded Coatings for the Interior and Exterior Surfaces of Ductile-Iron and Gray Iron Fittings
AWWA C153/A21.53	(2019) Ductile-Iron Compact Fittings for Water Service
AWWA C213	(2015) Fusion-Bonded Epoxy Coating for the Interior and Exterior of Steel Water Pipelines

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2019) Standard Specification for Carbon Structural Steel
ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A325	(2014) Standard Specification for Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength
ASTM A490	(2014a) Standard Specification for Structural Bolts, Alloy Steel, Heat Treated, 150 ksi Minimum Tensile Strength
ASTM A500/A500M	(2023) Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes
ASTM A536	(1984; R 2019; E 2019) Standard Specification for Ductile Iron Castings
ASTM A563	(2015) Standard Specification for Carbon and Alloy Steel Nuts
ASTM A603	(2019) Standard Specification for Zinc-Coated Steel Structural Wire Rope
ASTM D1785	(2015; E 2018) Standard Specification for Poly(Vinyl Chloride) (PVC), Plastic Pipe, Schedules 40, 80, and 120
ASTM D2665	(2014) Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Drain, Waste, and Vent Pipe and Fittings
ASTM E488/E488M	(2022) Standard Test Methods for Strength of Anchors in Concrete Elements
ASTM F891	(2024) Standard Specification for Coextruded Poly (Vinyl Chloride) (PVC) Plastic Pipe with a Cellular Core
ASTM F1554	(2020) Standard Specification for Anchor Bolts, Steel, 36, 55, and 105-ksi Yield Strength

FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA)

FEMA P-414	(January 2004) Installing Seismic Restraints for Duct and Pipe

ICC EVALUATION SERVICE, INC. (ICC-ES)

ICC ES AC193	(2012) Acceptance Criteria for Mechanical Anchors in Concrete Elements

METAL FRAMING MANUFACTURERS ASSOCIATION (MFMA)

MFMA-4	(2004) Metal Framing Standards Publication

NSF INTERNATIONAL (NSF)

NSF/ANSI 61	(2022) Drinking Water System Components - Health Effects

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1981	(2008) Seismic Restraint Manual Guidelines for Mechanical Systems, 3rd Edition

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-301-01	(2023; with Change 6, 2026) Structural Engineering
UFC 4-010-01	(2018;with Change 1, 2020) DoD Minimum Antiterrorism Standards for Buildings

VIBRATION ISOLATION AND SEISMIC CONTROL MANUFACTURERS ASSOCIATION (VISCMA)

VISCMA 412	(2014) Installing Seismic Restraints for Mechanical Equipment

1.2 SYSTEM DESCRIPTION

1.2.1 General Requirements

Apply the requirements for seismic protection measures described in this section and on the drawings to the mechanical equipment and mechanical systems both inside and outside of the building along with exterior utilities and systems listed below. Where there is a conflict between the specifications and the drawings, the specifications will take precedence. Accomplish resistance to lateral forces induced by earthquakes without consideration of friction resulting from gravity loads.

1.2.2 Mechanical Equipment

Mechanical equipment to be seismically protected must include the following items to the extent required on the drawings or in other sections of these specifications:

Equipment/Components with Ip = 1.5

Water Heaters	
	Valves and Fittings for Piping
	Refrigerant Compressors

	Air Handling Units
Condensate Pumps	
Large Commercial Dryers	
	Split System DX Units
Flash Tanks	
	Exhaust, Return and Misc. Fans
	Unitary HVAC Systems
	Instrumentation and Control for HVAC

1.2.3 Mechanical Systems

Mechanical systems to be seismically protected must include the following items to the extent required on the drawings or in this or other sections of these specifications:

a. All Piping and Ducts Inside the Building Except as Specifically Stated Below Under "Items Not Covered By This Section".

b. Chilled Water Distribution Systems Outside of Buildings.

c. Steam, Water Piping Outside of Buildings.

d. All Water Supply Systems Outside of Buildings.

e. Storm and Sanitary Sewer Systems Outside of Buildings.

f. All Process Piping Outside of Buildings.

g. Heat Distribution Systems (Supply, Return, and Condensate Return) Outside of Buildings.

m. Ductwork Outside of Buildings.

1.2.4 Contractor Designed Bracing

Submit copies of the design calculations with the drawings. Calculations must be approved, certified, stamped and signed by a registered

Professional Structural Engineer. Calculations must verify the capability of structural members to which bracing is attached for carrying the load from the brace. Design the bracing in accordance with UFC 3-301-01, , UFC 4-010-01 and additional data furnished by the Contracting Officer. Resistance to lateral forces induced by earthquakes must be accomplished without consideration of friction resulting from gravity loads. UFC 3-301-01 uses parameters for the building, not for the equipment in the building; therefore, corresponding adjustments to the formulas must be required. Loadings determined using UFC 3-301-01 are based on strength design; therefore, AISC 325 Specifications must be used for the design. The bracing for the mechanical equipment designated in paragraph 1.2.2 and systems designated in paragraph 1.2.3 must be developed by the Contractor.

1.2.5 Items Not Covered By This Section

1.2.5.1 Fire Protection Systems

Install seismic protection of piping for fire protection systems as specified in other Sections.

1.2.5.2 Items Requiring No Seismic Restraints

Seismic restraints are not required for the following items:

b. Piping in boiler and mechanical equipment rooms less than 1-1/4 inches nominal pipe size.

c. All other piping equal to or less than 3inches nominal pipe size.

d. Rectangular air handling ducts less than 6 square feet in cross sectional area.

e. Round air handling ducts less than 28 inches in diameter.

f. Piping suspended by individual hangers 12 inches or less in length from the top of pipe to the bottom of the supporting structural member where the hanger is attached, except as noted below.

g. Ducts suspended by hangers 12 inches or less in length from the top of the duct to the bottom of the supporting structural member, except as noted below.

In exemptions f. and g. all hangers must meet the length requirements. If the length requirement is exceeded by one hanger in the run, brace the entire run. Seismically protect interior piping and ducts not listed above in accordance with the provisions of this specification.

Non-critical items may require seismic restraints if adjacent to critical equipment or systems that must remain operational after an earthquake and could be compromised by impact with non-critical adjacent components.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Coupling and Bracing

Flexible Couplings or Joints

Equipment Restraint

Contractor Designed Bracing; G

SD-03 Product Data

Coupling and Bracing; G

Flexible Couplings Or Joints; G

Equipment Restraint; G

Contractor Designed Bracing; G

Snubbers

Anchor Bolts

Vibration Isolators

SD-05 Design Data

Design Calculations

SD-06 Test Reports

Anchor Bolts; G

PART 2 PRODUCTS

2.1 GENERAL DESIGN REQUIREMENTS

Submit detailed seismic restraint drawings for mechanical equipment, duct systems, piping systems and any other mechanical systems along with calculations, catalog cuts, templates, and erection and installation details, as appropriate, for the items listed below. Indicate thickness, type, grade, class of metal, and dimensions; and show construction details, reinforcement, anchorage, and installation with relation to the building construction. Calculations must be stamped, by a registered structural engineer, and verify the capability of structural members to which bracing is attached for carrying the load from the brace. Include drawing for Mission Critical Equipment indicating the equipment location in the facility sufficient to be used for the installation. Design must be based on actual equipment and system layout. Design must include calculated dead loads, static seismic loads and capacity of materials utilized for the connection of the equipment or system to the structure. Analysis must detail anchoring methods.

2.2 EQUIPMENT RESTRAINT

Equipment must be rigidly or flexibly mounted as indicated in the specifications and/or drawings depending on vibration isolation

requirements as follows below.

Roof mounted equipment such as cooling towers and condensers, both vibration isolated and nonisolated, must have support members designed and anchored to building structural steel or concrete as required for seismic restraint and wind loads.

2.2.1 Rigidly (Base and Suspended) Mounted Equipment

HVAC equipment furnished under this contract must be rigidly mounted using cast-in-place anchor bolts or post-installed anchors that are qualified for earthquake loading in accordance with ACI 355.2 and ACI 355.4. Anchor bolts must conform to ASTM F1554. For any rigid equipment which is rigidly anchored, provide flexible joints for piping, ductwork, electrical conduit, etc., that are capable of accommodating displacements equal to the full width of the joint in both orthogonal directions. Suspended equipment bracing attachments should be located just above the center of gravity to minimize swinging. Use the ratio of the overturning moment from seismic forces to the resisting moment due to gravity loads to determine if overturning forces need to be considered in the sizing of anchor bolts. Provide calculations to verify the adequacy of the anchor bolts for combined shear and overturning.

Roof mounted HVAC equipment roof curbs, framing and attachment to equipment and structure must be designed and braced to withstand seismic loads. Designated Seismic Systems (DSS) assigned to Seismic Design Category (SDC) C, D, E, or F and Risk Category IV components needed for continued operation after an earthquake must have two nuts provided on each anchor bolt.

2.2.2 Nonrigid or Flexibly-Mounted Equipment

Select vibration isolation devices so that the maximum movement of equipment from the static deflection point is 1/4 inch. Equipment flexibly mounted on vibration isolators must have a bumper restraint or snubber in each horizontal direction and vertical restraints must be provided where required to resist overturning. Isolator housing and restraints must be constructed of ductile materials. A viscoelastic pad or similar material of appropriate thickness must be used between the bumper and components to limit the impact load. Restraints must be designed to resist the calculated horizontal lateral and vertical forces.

Spring vibration isolators must be seismically rated, restrained isolators for equipment subject to load variations and large external forces. The seismically rated housing must be sized to meet or exceed the force requirements applicable to the project and meet the required isolation criteria. Spring vibration isolator manufacturer's will be a member of VISCMA. Design force, Fp, must be doubled for vibration isolators with an air gap greater than 0.25 inches as specified in ASCE 7-16, Chapter 13. Housed springs must not be used for seismic restraint applications because they cannot resist uplift.

2.3 BOLTS AND NUTS

Hex head bolts, and heavy hexagon nuts must be ASTM A325 or ASTM A490 bolts and ASTM A563 nuts. Provide bolts and nuts galvanized in accordance with ASTM A153/A153M when used underground or exposed to weather.

2.4 FLEXIBLE JOINTS

Flexible joints must have same pressure and temperature ratings as adjoining pipe. Braided hoses must not be used where there is torsional or axial movement unless manufacturer allows it.

2.4.1 Braided Hose Expansion Joint

Braided hose expansion joint(s) must be installed in the locations indicated on the drawings and as required to accommodate any thermal expansion, contraction or seismic movement of the piping system. Joints must consist of two parallel sections of corrugated metal hose, compatible braid, and 180 degree return bend with inlet and outlet connections. Field fabricated loops are not acceptable. Braided hose expansion joint(s) must be installed in the locations indicated on the drawings and as required to accommodate any thermal expansion, contraction or seismic movement of the piping system. Joints must consist of two parallel sections of corrugated metal hose, compatible braid, and 180 degree return bend with inlet and outlet connections. Field fabricated loops must not be acceptable. Braided hose in a 60 degree flexible V loop arrangement must be used for small diameter pipe connections to coils in variable-air-volume (VAV)terminal units and fan coil units installed in suspended ductwork whether braced or unbraced.

All braided hose expansion joints must be manufactured in accordance with the documented manufacturers weld procedure specifications. The procedure qualification record must be used to document the execution of this procedure and must follow the general "guidelines" of ASME Section IX. Each individual welder must conform to the in-house procedure qualification record and be qualified prior to each production lot. The testing of each individual welder must be documented in a welding procedure qualification record.

2.4.1.1 Corrugated Hose

Corrugated hose must be Type 304 stainless steel . Braid must be Type 304 stainless steel for any series 300 stainless steel hose . Fittings materials of construction and end fitting type must be consistent with pipe material and equipment/ pipe connection fittings. Copper fittings must not be attached to stainless steel hose.

2.4.1.2 Flexible Hose Expansion Loops

Flexible hose expansion loops must have a factory supplied, hanger / support lug located at the bottom of the 180deg return. Flexible hose expansion loop(s) must be furnished with a plugged FPT to be used for a drain or air release vent. Flexible hose expansion loop(s) must be rated with an operating pressure which is the same as the adjoining pipe. The operating pressure must be based on burst pressure with a 4 to 1 safety factor. For steam service, the operating pressure must be based on burst pressure with a 8 to 1 safety factor.

2.4.2 Double Ball Flexible Expansion Joint

Install flexible expansion joints manufactured of ductile iron conforming to the material requirements of ASTM A536 and AWWA C153/A21.53 in the locations indicated on the drawings. Provide foundry certification of material upon request. Each flexible expansion joint must be pressure tested prior to shipment against its own restraint to a minimum of 350 psi

(250 psi for flexible expansion joints 2 inch and 30 inches diameter and larger.) A minimum 2:1 safety factor, determined from the published pressure rating, must apply. Factory Mutual Approval for the 3 inch through 12 inch sizes is required. Each flexible expansion joint must consist of an expansion joint designed and cast as an integral part of a ball and socket type flexible joint, having a minimum per ball deflection of: 20°, 2" - 12"; 15°, 14" - 36"; 12°, 42"-48" and 4-inches minimum expansion. Additional expansion sleeves must be available and easily added or removed at the factory or in the field. Both standardized mechanical joint and flange end connections must be available.

2.4.2.1 Internal Surfaces

Line all internal surfaces (wetted parts) with a minimum of 15 mils of fusion bonded epoxy conforming to the applicable requirements of AWWA C213. Sealing gaskets must be constructed of EPDM. The coating must meet NSF/ANSI 61.

2.4.2.2 Exterior Surfaces

Coat exterior surfaces with a minimum of 6 mils of fusion bonded epoxy conforming to the applicable requirements of AWWA C116/A21.16. Include appropriately sized polyethylene sleeves, meeting AWWA C105/A21.5, for direct buried applications.

2.4.3 Double Ball Flexible Expansion Joint Gravity Drain (Non-Pressurized)

Flexible expansion joints gravity drain must be installed in the locations indicated on the drawings and must be manufactured of pvc. All connections whether solvent weld or mechanical must be restrained to allow movement to be transferred to expansion joint. Each ball must allow up to 15 degrees deflection.

End connection outside diameters must be compatible with ASTM D1785, ASTM D2665 and ASTM F891 PVC pipe and are to be solvent welded.

2.5 SWAY BRACING MATERIALS

Material used for members listed in this section and on the drawings, must be structural steel conforming with the following:

a. Plates, rods, and rolled shapes, ASTM A36/A36M.

b. Wire rope, ASTM A603 pre-stretched. Class B galv coating Ferrule clamps must be qualified by testing for use in seismic applications per VISCMA 412. A minimum of two clamps are required on each end of wire rope.

c. Tubes, ASTM A500/A500M, Grade B.

d. Pipes, ASTM A53/A53M, Grade B.

e. Angles, ASTM A36/A36M.

f. Channels (Struts) with in-turned lips and associated hardware for fastening to channels at random points conforming to MFMA-4

2.6 MULTIDIRECTIONAL SEISMIC SNUBBERS

Install multidirectional seismic snubbers employing elastomeric pads on floor- or slab-mounted equipment and large piping as detailed on drawings. These snubbers must provide 1/4 inch free vertical and horizontal movement from the static deflection point. Snubber medium must consist of multiple pads of cotton duct and neoprene or other suitable materials arranged around a flanged steel trunnion so both horizontal and vertical forces are resisted by the snubber medium.

PART 3 EXECUTION

3.1 COUPLING AND BRACING

a. Submit detail drawings, as specified here and throughout this specification, along with catalog cuts, templates, and erection and installation details, as appropriate, for the items listed. Submittals must be complete in detail; must indicate thickness, type, grade, class of metal, and dimensions; and must show construction details, reinforcement, anchorage, and installation with relation to the building construction.

b. Provide coupling installation conforming to the details shown on the drawings. Provisions of this paragraph apply to all piping within a 5 foot line around outside of building unless buried in the ground. Piping grouped for support on trapeze-type hangers must be braced at the most frequent interval as determined by applying the requirements of this specification to each piping run on the common support.

c. Size bracing components as required for the total load carried by the common supports. Bracing rigidly attached to pipe flanges, or similar, must not be used where it would interfere with thermal expansion of piping.

d. Adjust isolators and restraints after piping systems has been filled and equipment is at its operating weight, following the manufacturer's written instructions.

e. Install cables at a 45-degree slope. Where interference is present, the slope may be minimum of 30 degrees or a maximum of 60 degrees per VISCMA 412.

3.2 BUILDING DRIFT

Provide joints capable of accommodating seismic displacements for vertical piping between floors of the building, where pipes pass through a building seismic or expansion joint, or where rigidly supported pipes connect to equipment with vibration isolators. Provide horizontal piping across expansion joints to accommodate the resultant of the drifts of each building unit in each orthogonal direction. For threaded piping, provide swing joints made of the same piping material. For piping with manufactured ball joints the seismic drift must be 0.015 feet per foot of height above the base where the seismic separation occurs; this drift value must be used in place of the expansion given in the manufacturer's selection table.

3.3 FLEXIBLE COUPLINGS OR JOINTS

3.3.1 Building Piping

Provide flexible couplings or joints in building piping at bottom of all pipe risers for pipe larger than 3-1/2 inches in diameter. Laterally brace flexible couplings or joints without interfering with the action of the flexible coupling or joint. Cast iron waste and vent piping need only comply with these provisions when caulked joints are used. Flexible bell and spigot pipe joints using rubber gaskets may be used at each branch adjacent to tees and elbows for underground waste piping inside of building to satisfy these requirements.

3.4 PIPE SLEEVES

Size pipe sleeves in interior non-fire rated walls as indicated on the drawings to provide clearances that will permit differential movement of piping without the piping striking the pipe sleeve.

3.5 SPREADERS

Provide spreaders between adjacent piping runs to prevent contact during seismic activity whenever pipe or insulated pipe surfaces are less than 4 inches apart. Apply spreaders at same interval as sway braces at an equal distance between the sway braces. If rack type hangers are used where the pipes are restrained from contact by mounting to the rack, spreaders are not required for pipes mounted in the rack. Apply spreaders to surface of bare pipe and over insulation on insulated pipes utilizing high-density inserts and pipe protection shields in accordance with the requirements of Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

3.6 SWAY BRACES FOR PIPING

Provide sway braces to prevent movement of the pipes under seismic loading. Provide braces in both the longitudinal and transverse directions, relative to the axis of the pipe. Provide sufficient braces for equipment to resist a horizontal force as specified in UFC 3-301-01 without exceeding safe working stress of bracing components. Provide bracing that does not interfere with thermal expansion requirements for the pipes as described in other sections of these specifications. For seismic analysis of horizontal pipes, the equivalent static force should be considered to act concurrently with the full dead load of the pipe, including contents.

3.6.1 Transverse Sway Bracing

Provide transverse sway bracing for steel and copper pipe at intervals not to exceed those shown on the drawings. All runs (length of pipe between end joints) must have a minimum of transverse bracing at each end. Provide transverse sway bracing for pipes of materials other than steel and copper at intervals not to exceed the hanger spacing as specified in Section 22 00 00 PLUMBING, GENERAL PURPOSE.

3.6.2 Longitudinal Sway Bracing

Provide longitudinal sway bracing at 40 foot intervals unless otherwise indicated. All runs (length of pipe between end joints) must have one longitudinal brace minimum. Construct sway braces in accordance with the drawings. Do not use branch lines, walls, or floors as sway braces.

3.6.3 Vertical Runs

Run is defined as length of pipe between end joints. Do not brace vertical runs of piping no more than 10 foot vertical intervals. Braces for vertical runs must be above the center of gravity of the segment being braced. Flexible couplings should be provided at the bottoms of risers for pipes larger than 3.5 in. (89 mm) in diameter. Flexible couplings and expansion joints should be braced laterally and longitudinally unless such bracing would interfere with the action of the couplings or joints. When pipes enter buildings, flexible couplings should be provided to allow for relative movement between the soil and building. Construct all sway braces in accordance with the drawings. Attach sway braces to the structural system. Do not connect to branch lines, walls, or floors.

3.6.4 Clamps and Hangers

Apply clamps or hangers on uninsulated pipes directly to pipe. Insulated piping must have clamps or hangers applied over insulation in accordance with Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

Hanger rod stiffener angle or strut bracing must be securely attached by a series of attachment clamps manufactured from a one piece metal stamping and must include all require attachment hardware and locking nuts. Attachment clamps made from aluminum or cast iron must not be used in seismic applications. Do not weld vertical braces to hanger rods.

3.7 SWAY BRACES FOR DUCTS

3.7.1 Braced Ducts

Provide bracing details and spacing for rectangular and round ducts in accordance with SMACNA 1981. However, the design seismic loadings for these items must not be less than loadings obtained using the procedures in UFC 3-301-01. Bracing must not attach to duct joints. Use shortest screws possible when penetrating ductwork to minimize airflow noise inside duct.

3.7.2 Unbraced Ducts

Attach hangers for unbraced ducts to the duct within 2 inches of the top of the duct with a minimum of two #10 sheet metal screws in accordance with FEMA P-414. Use shortest screws possible when penetrating ductwork to minimize airflow noise inside duct. Install unbraced ducts with a 6 inch minimum clearance to vertical ceiling hanger wires.

3.8 EQUIPMENT

3.8.1 General

Ensure housekeeping pads have adequate space to mount equipment and seismic restraint devices allowing adequate edge distance and embedment depth for restraint anchor bolts. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength. Install neoprene grommet washers or till the gap with epoxy on equipment anchor bolts where clearance between anchor and equipment support hole exceeds 0.125 inches.

3.8.2 Controls

Ensure that controls for critical equipment that must remain operational after an earthquake are certified per paragraph 3.11 SPECIAL TESTING FOR SEISMIC-RESISTING EQUIPMENT and are served by emergency power as required.

3.9 ANCHOR BOLTS

3.9.1 Cast-in-Place Anchor Bolts

Use templates to locate cast-in-place bolts accurately and securely in formwork. Anchor bolts must have an embedded straight length equal to at least 12 times nominal diameter of the bolt. Anchor bolts that exceed the normal depth of equipment foundation piers or pads must either extend into concrete floor or the foundation or be increased in depth to accommodate bolt lengths.

3.9.2 Drilled-In Anchor Bolts

Drill holes with rotary impact hammer drills Drill bits must be of diameters as specified by the anchor manufacturer. Unless otherwise shown on the Drawings, all holes must be drilled perpendicular to the concrete surface. Where anchors are permitted to be installed in cored holes, use core bits with matched tolerances as specified by the manufacturer. Properly clean cored hole per manufacturer's instructions. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Exercise care in coring or drilling to avoid damaging existing reinforcing or embedded items. Notify the COR if reinforcing steel or other embedded items are encountered during drilling. Take precautions as necessary to avoid damaging prestressing tendons, electrical and telecommunications conduit, and gas lines. Unless otherwise specified, do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength. Perform anchor installation in accordance with manufacturer instructions.

3.9.2.1 Wedge Anchors, Heavy-Duty Sleeve Anchors, and Undercut Anchors

Protect threads from damage during anchor installation. Heavy-duty sleeve anchors must be installed with sleeve fully engaged in part to be fastened. Set anchors to manufacturer's recommended torque, using a torque wrench. Following attainment of 10% of the specified torque, 100% of the specified torque must be reached within 7 or fewer complete turns of the nut. If the specified torque is not achieved within the required number of turns, the anchor must be removed and replaced unless otherwise directed by the Engineer.

3.9.2.2 Cartridge Injection Adhesive Anchors

Where approved for seismic application, clean all holes per manufacturer instructions to remove loose material and drilling dust prior to installation of adhesive. Inject adhesive into holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive. Follow manufacturer recommendations to ensure proper mixing of adhesive components. Sufficient adhesive must be injected in the hole to ensure that the annular gap is filled to the surface. Remove excess adhesive from the surface. Shim anchors with suitable device to center the anchor in the hole. Do not disturb or load anchors before manufacturer specified cure time has elapsed.

3.9.2.3 Capsule Anchors

Where approved for seismic application, perform drilling and setting operations in accordance with manufacturer instructions. Clean all holes to remove loose material and drilling dust prior to installation of adhesive. Remove water from drilled holes in such a manner as to achieve a surface dry condition. Capsule anchors must be installed with equipment conforming to manufacturer recommendations. Do not disturb or load anchors before manufacturer specified cure time has elapsed.

Observe manufacturer recommendations with respect to installation temperatures for cartridge injection adhesive anchors and capsule anchors.

3.10 ANCHOR BOLT TESTING

Test in place expansion and chemically bonded anchors not more than 24 hours after installation of the anchor, conducted by an independent testing agency; testing must be performed on random anchor bolts as described below.

3.10.1 Torque Wrench Testing

Perform torque wrench testing on not less than 50 percent of the total installed applied torque expansion anchors and at least one anchor for every piece of equipment containing more than two anchors. The test torque must equal the minimum required installation torque as required by the bolt manufacturer. Calibrate torque wrenches at the beginning of each day the torque tests are performed. Recalibrate torque wrenches for each bolt diameter whenever tests are run on bolts of various diameters. Apply torque between 20 and 100 percent of wrench capacity. Reach the test torque within one half turn of the nut, except for 3/8 inch sleeve anchors which must reach their torque by one quarter turn of the nut. If any anchor fails the test, test similar anchors not previously tested until 20 consecutive anchors pass. Failed anchors must be retightened and retested to the specified torque; if the anchor still fails the test it must be replaced.

3.10.2 Pullout Testing

Test expansion and chemically bonded anchors by applying a pullout load using a hydraulic ram attached to the anchor bolt. Testing must be in accordance with ASTM E488/E488M or ICC ES AC193. At least 10 percent of each type and size of anchors, but not less than 3 per day must be tested. Apply the load to the anchor without removing the nut; when that is not possible, the nut must be removed and a threaded coupler must be installed of the same tightness as the original nut. Check the test setup to verify that the anchor is not restrained from withdrawing by the baseplate, the test fixture, or any other fixtures. The support for the testing apparatus must be at least 1.5 times the embedment length away from the bolt being tested. Load each tested anchor to 1 times the design tension value for the anchor. The anchor must have no observable movement at the test load. If any anchor fails the test, similar type and size anchors not previously tested must be tested until 10 percent of those type consecutive anchors pass. Remove and replace failed anchors. Fill empty anchor holes and patch failed anchor locations with high-strength non-shrink, nonmetallic grout.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 05 93

TESTING, ADJUSTING, AND BALANCING FOR HVAC
05/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL, INC. (AMCA)

AMCA 203	(1990; R 2011) Field Performance Measurements of Fan Systems

ASSOCIATED AIR BALANCE COUNCIL (AABC)

AABC MN-1	(2016, 7th ed) National Standards for Total System Balance

NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB)

NEBB PROCEDURAL STANDARDS	(2019) Procedural Standard for TAB (Testing, Adjusting and Balancing) of Environmental Systems - Ninth Edition

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70E	(2024) Standard for Electrical Safety in the Workplace

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 016	(2012) HVAC Air Duct Leakage Test Manual - 2nd Edition
SMACNA 1780	(2023) HVAC Systems - Testing, Adjusting and Balancing, 4th Edition

1.2 DEFINITIONS

In some instances, terminology differs between this Contract and the TAB certifying body or the TAB Standard primarily because this section intends to use the industry standards specified, along with additional requirements listed within this section, to produce optimal results.

a. AABC: Associated Air Balance Council

b. Certifying Body: An independent body responsible for issuing a formal recognition, such as a certificate, proving that the certification meets specific national or international requirements.

c. COTR: Contracting Officer's Technical Representative

d. DALT: Duct Air Leakage Testing (of HVAC duct systems such as supply air (SA), return air (RA), exhaust air (EA), relief air (LA), and outdoor air (OA)).

e. DALT Failure: This phrase means "a leakage rate measured during DALT Field Work and Acceptance Testing which exceeds the allowable leakage rate for the duct test pressure and leakage class indicated."

f. Duct System: When applied to DALT, this phrase means "complete duct system, inclusive of all ductwork, plenums, mains, branches, fittings and duct-mounted components and appurtenances, such as manual balancing dampers, control dampers, access doors, fire dampers, and duct-mounted coils, up to, but excluding flexible ducts and air-handling equipment, such as air-handling units (AHUs), dedicated outdoor air system (DOAS) units, fan coil units (FCUs), water source heat pumps (WSHPs), and variable-air volume (VAV) terminal units."

g. HVAC: Heating, ventilating, and air-conditioning

h. Season 1, Season 2: Depending upon when the project HVAC systems are completed and ready for TAB, Season 1 is defined as Cooling Season or Heating Season, thereby defining Season 2 as the other season.

(1) Cooling Season: A 30-day timeframe centered on the expected date of maximum cooling load or expected warmest day of the year, making the timeframe 10-July through 9-August.

(2) Heating Season: A 30-day timeframe centered on the expected date of maximum heating load or expected coldest day of the year, making the timeframe 20-December through 19-January.

i. TAB: Testing, Adjusting, and Balancing (of HVAC and domestic hot-water recirculation systems).

j. TAB Failure: This phrase means "a measurement taken during TAB Field Acceptance Testing which does not fall within the specified Acceptance Tolerance for a specific parameter."

k. TAB Firm: AABC Certified Member Agency, NEBB Certified Firm, TABB Certified Contractor

l. TAB Standard: Standard utilized by TAB Team based on TAB Firm's certifying body:

(1) AABC - National Standards for Total System Balance (AABC MN-1)

(2) NEBB - Procedural Standard for Testing, Adjusting and Balancing of Environmental Systems (NEBB PROCEDURAL STANDARDS)

(3) TABB - HVAC Systems Testing, Adjusting & Balancing Manual (SMACNA 1780)

m. TAB Team Supervisor: AABC Test and Balance Engineer (TBE), NEBB TAB Certified Professional (TAB CP), TABB TAB Certified Supervisor

n. TAB Team: TAB Firm personnel

o. TABB: Testing, Adjusting and Balancing Bureau

1.3 GENERAL REQUIREMENTS

The work includes DALT and TAB of new HVAC and domestic hot-water (DHW) recirculation systems, which are located within, on, under, between, and adjacent to buildings.

Perform TAB in accordance with the requirements of the TAB Standard identified by the TAB Firm's certifying body, as supplemented and modified by this specification section. Perform DALT in compliance with the procedures specified in SMACNA 016, as supplemented and modified by this specification section.

1.3.1 Support Personnel

Ensure the TAB Team Supervisor or TAB Team Field Leader is present full-time on the Contract site for overall management and direct observation of the DALT and TAB Field Work. Certified TAB Team Field Technicians may work independently of direct observation by the TAB Team Supervisor or Field Leader.

Ensure the technical personnel, such as factory representatives and HVAC controls contractor technicians, to operate HVAC equipment are present to enable the TAB Team to accomplish the DALT and the TAB measurement work. Provide the personnel to install field designated test ports and test apparatus connections.

1.3.2 Coordination

Coordinate testing schedules with work in other Sections performed on the components or systems to be tested. Ensure support personnel are present at the times required by the TAB Team and cause no delay in the DALT and the TAB Field Work.

1.4 RELATED REQUIREMENTS

Requirements for climate conditions during building pressure testing are specified in Section 01 91 19 BUILDING ENCLOSURE COMMISSIONING.

Requirements for thermal insulation of ductwork, piping, fittings, and valves are specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

Requirements for coordination with commissioning are specified in Section 23 08 00 COMMISSIONING OF MECHANICAL AND PLUMBING SYSTEMS.

Requirements for calibration and testing of HVAC controls system devices are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

Requirements for Detail Drawings, construction and sealing of HVAC air distribution systems are specified in Section 23 30 00 HVAC AIR DISTRIBUTION.

Requirements for price breakdown of HVAC TAB work are specified in Section 01 20 00 PRICE AND PAYMENT PROCEDURES.

Requirements for construction scheduling related to HVAC TAB work are specified in Section 01 32 17.00 20 COST LOADED NETWORK ANALYSIS SCHEDULES (NAS).

1.5 SUBMITTALS

Unless otherwise specified or directed by the Contracting Officer, provide submittals in electronic format. In addition to the electronic submittal, provide three hard copies of the submittals.

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

TAB Firm And Personnel Qualifications; G

Design Review Report; G

TAB Pre-Field Engineering Plan; G

SD-06 Test Reports

Pre-Final DALT Report; G

Certified Final DALT Report; G

Certified TAB Report of Proportional Balancing; G

Certified TAB Report of Season 1; G

SD-11 Closeout Submittals

Certified TAB Report of Season 2; G

1.6 TAB FIRM AND PERSONNEL QUALIFICATIONS

Engage the services of a qualified TAB Firm to perform DALT and TAB work for this project. Only approved firm and personnel are allowed to perform DALT and TAB work on this Contract. Any firm or individual that has been the subject of disciplinary action by their certifying body within the 5 years preceding Contract Award is not eligible to perform any duties related to DALT and TAB. Comply with the following:

a. Certification: Maintain TAB Firm and personnel certifications for the entire duration of duties specified. Renew Certifications which expire prior to completion of the TAB work in a timely manner so there is no lapse in certification. Provide written notice to the Contracting Officer, with a copy of renewed certificates of the TAB Firm and personnel, prior to expiration of the previous certificate(s). If, for any reason, the TAB Firm or its employee loses subject certification during this Contract, immediately notify the Contracting Officer in writing and comply with the requirements for the replacement of TAB Firm and TAB Team Members. An approved successor must validate all work performed for this project by the TAB Firm or TAB Team Member who lost certification.

b. Replacement of TAB Firm and TAB Team Members: Replacement or substitution of firm or individual members may occur if each complies with the applicable qualifications and is approved by the Contracting

Officer prior to the performance of its duties on this Contract. Submit replacement TAB Firm and Personnel Qualifications in accordance with this section.

Submit the TAB Firm and Personnel Qualifications within 60 calendar days after the date of Contract Award.

1.6.1 TAB Firm

Provide documentation that the TAB Firm is a first tier subcontractor to the prime Contractor and an independent company, not participating in any other work on this Contract or affiliated to any other company participating in work on this Contract, including, but not limited to, design, furnishing equipment, or construction. No work may be performed by a second tier subcontractor.

Provide a copy of current certificate, with expiration date, to certify that the TAB Firm is certified by AABC, NEBB, or TABB in categories and functions of the DALT and TAB field work specified. Designate the single certifying body to be utilized when the firm is certified by more than one.

1.6.2 TAB Personnel

For each TAB Team role below, provide at least one qualified, full-time employee of the TAB Firm for approval. Include the proposed role(s) of each employee with their qualification documentation. It is acceptable for a TAB Team member to perform duties of another TAB Team role if they meet the qualifications of both.

a. TAB Team Supervisor

Provide documentation, including full name and a copy of current certificate, that the TAB Team Supervisor is a AABC TBE, a NEBB TAB CP, or a TABB TAB Certified Supervisor.

b. TAB Team Field Leader

Provide documentation that the TAB Team Field Leader is a certified TAB Technician by AABC, NEBB, or TABB, and has satisfactorily performed full-time supervision of TAB work of others in the field for a minimum of 3 years immediately preceding Contract Award. Include full name, a copy of current certificate, and a list of projects, roles performed, and associated dates.

c. TAB Team Field Technician

Provide documentation that each TAB Team Field Technician is a certified TAB Technician by AABC, NEBB, or TABB, or has satisfactorily performed DALT and TAB work in the field for a minimum of 1 year immediately preceding Contract Award. Include full name, a copy of current certificate when applicable, and a list of projects, roles performed, and associated dates.

1.7 TAB STANDARD

All recommendations and suggested practices contained in the TAB Standard are mandatory. Maintain a hard copy and an electronic PDF file copy of the standard on site.

All quality assurance provisions of the TAB Standard, such as performance guarantees, are part of this Contract. For systems or system components not covered in the TAB Standard, TAB procedures and report forms must be developed by the TAB Team Supervisor and included in the TAB Pre-Field Engineering Plan. Where new procedures and requirements, applicable to the Contract requirements have been published or adopted by the certifying body responsible for the TAB Standard, the more stringent of the requirements and recommendations contained in these procedures and requirements are considered mandatory.

1.8 INSTRUMENTATION

It is the responsibility of the TAB Firm to use instrumentation that meets the requirements of the TAB Standard. Select appropriate instruments to achieve the applicable TAB tolerances. Instrumentation used for taking air wet-bulb temperature readings must provide accuracy of a minimum of plus or minus 5 percent at the measured face velocities. Where the instrument manufacturer calibration recommendations are more stringent than those listed in the TAB Standard, adhere to the manufacturer's recommendations. Instrumentation must be in proper operating condition and must be applied in accordance with the instrumentation's manufacturer recommendations.

All instrumentation must bear a valid National Institute of Standards and Technology (NIST) traceable calibration certificate, dated within one year, during field work and Field Acceptance Testing.

1.9 DESIGN REVIEW

The TAB Team Supervisor must review the Contract Plans and Specifications to advise the Contracting Officer of any omissions and deficiencies that would prevent the effective and accurate TAB of the systems in compliance with the requirements of this section. Accomplish the following:

a. Verify in the documents the presence and location of permanently installed test ports and other devices needed, including gauge cocks, thermometer wells, flow control devices, flow measuring devices, balancing valves, and manual balancing dampers.

b. Confirm the inclusion of the design values necessary to complete the DALT and TAB report forms required for the TAB Pre-Field Engineering Plan.

c. Generate a list of submittals, from those in the Contract Submittal Register of Section 01 33 00 SUBMITTAL PROCEDURES, that relate to the successful accomplishment of all HVAC and DHW recirculation systems TAB.

d. Prepare a report containing a detailed listing of the items identified during the review. Provide the omission and deficiency listing in a tabular format, with each item sequentially numbered and with a reference to the applicable design document. For each omission and deficiency, provide a complete explanation including supporting documentation detailing the design deficiency. If no deficiencies are evident, state so in the report. Include the TAB Related Submittals List in the report.

Submit the Design Review Report to the Contracting Officer for approval within 30 calendar days after approval of the TAB Firm and Personnel

Qualifications.

1.10 TAB PRE-FIELD ENGINEERING PLAN

The TAB Team Supervisor must utilize the TAB Standard, Contract Plans, Contract Specifications, approved contract revisions, and contract change orders to prepare a plan for the DALT and TAB field work, including procedures, report forms, diagrams, instrumentation and other supporting documents in compliance with the following:

a. Project Summary: Provide a detailed narrative describing the DALT and TAB Field Work to be performed, including systems and equipment. Clearly distinguish between DALT information and TAB information.

b. Step-by-Step Procedures: Provide a list of the intended procedural steps for DALT and TAB Field Work from start to finish. Include the following:

(1) The intended procedural steps for TAB work for systems, subsystems, and system components. TAB Standard procedure excerpts may be provided to supplement this requirement.

(2) A description of how each type of data measurement will be obtained.

(3) A complete methodology for accomplishing each seasonal TAB Field Work requirement.

(4) A list of Contractor support personnel required for each step, and tasks they need to perform.

c. Report Forms: Provide the report forms to be used in the DALT and TAB reports to document the DALT and TAB Field Work, with the preliminary information and design values filled in. Utilize contract document design HVAC and DHW systems values. For TAB report forms, use forms inclusive of all data on TAB Standard sample report forms, or generate where no TAB Standard form exists, for all data collection requirements. Ensure report forms contain data fields for each HVAC controls system flow measuring device's calibration, including design flow rate, actual flow rate, controls system reading and factor. For DALT report forms, use forms comparable to the "Air Duct Leakage Test Summary Report Forms" located in SMACNA 016, with an example of design and test data in the plan. Coordinate the key numbering used in the report forms with that used in the TAB Schematic Drawings.

d. TAB Schematic Drawings: Provide the schematic drawings to be used in the required reports, which may include building floor plans, mechanical room plans, equipment schedules, duct system plans, and equipment elevations. Use the contract drawings and, if available, ductwork shop drawings to provide the following:

(1) Air moving equipment and pump schedules.

(2) Thermal energy transfer equipment schedules.

(3) Duct Construction and Leakage Testing Schedule.

(4) Air system plans showing the location and airflow quantities of all supply, return, exhaust, relief, outdoor, and transfer air

terminal devices such as registers, grilles, diffusers, louvers, and rooftop hoods and their respective airflow quantities.

(5) A key numbering system on the drawings which identifies each piece of equipment and each air terminal device contained in the air terminal airflow report sheets. It is acceptable to utilize the contract drawing numbering system when provided for equipment.

(6) A unique number or mark for each water flow measurement fitting and balancing valve. It is acceptable to utilize the contract drawing numbering system when provided for valves and fittings.

(7) Intended TAB measurement locations, including where test ports need to be provided by the Contractor.

For Static Pressure Profile and Duct Traverse Equipment Diagrams, provide diagrams, representative of the actual equipment configuration, developed from TAB Standard forms, contract drawings or approved equipment submittals.

For DALT schematic drawings, provide a representative diagram matching the example DALT report form in this plan.

e. Instrumentation: Provide a list of DALT and TAB instruments for this project. Include the instrument name and description, manufacturer, model number, scale range, published accuracy, most recent calibration date, and what the instrument will be used for on this project. Submit instrument manufacturer's literature to document instrument accuracy performance is in compliance with that specified. Provide a copy of the calibration certificate for each calibrated instrument to be used.

f. Pre-DALT Field Work Checklist: Provide a thorough checklist of the work items and inspections that need to be accomplished before DALT Field Work can be performed. Include signature and date lines for the Contractor's quality control representative and mechanical contractor's representative acknowledging completion of the marked checklist items.

g. Pre-TAB Field Work Checklist: Provide a thorough checklist of the work items and inspections that need to be accomplished before the proportional balancing, heating season, and cooling season TAB Field Work can be performed. Include items such as completion of applicable HVAC controls systems installation, cleaning of hydronic system including but not limited to strainers, and replacement of HVAC system air filters. Provide separate sections of checklist items for proportional balancing, heating season thermal performance testing, and cooling season thermal performance testing TAB Field Work. Each section must include signature and date lines for the Contractor's quality control representative and mechanical contractor's representative acknowledging completion of the marked checklist items.

Submit the TAB Pre-Field Engineering Plan to the Contracting Officer for approval a minimum of 60 calendar days in advance of commencement of DALT TAB field work.

1.11 PRE-DALT/TAB MEETING

Meet with the Contracting Officer's Technical Representative (COTR) to

develop a mutual understanding relative to the details of the DALT and TAB work requirements. Requirements to be discussed include required submittals, work schedules, and field quality control. Ensure that the TAB Team Supervisor and a representative for the sheet metal contractor, mechanical contractor, electrical contractor, and HVAC controls system contractor are present at this meeting. Conduct the Pre-DALT/TAB Meeting a minimum of 30 calendar days in advance of the commencement of ductwork installation.

Provide written notice to the Contracting Officer of the proposed date of the Pre-DALT/TAB Meeting at a minimum of 14 calendar days prior to the proposed date. The notice must include the proposed date and time; required, and optional if any, attendees' names and job titles; a copy of the current submittal register; and a copy of the current network analysis schedule containing the sequencing and durations of the DALT and TAB activities and submittals in this section.

1.12 REPORTS

Format: All submitted documentation must be typed, neat, and organized. Include a dated title page, a certification page, a table of contents identifying the location of each report section, sequentially numbered pages throughout, and all sections bookmarked. Tables, lists, and diagrams must be titled. Hardcopy report forms and report data must be typewritten and bound with a waterproof front and back cover. Handwritten report forms or report data are not acceptable.

Submit the completed report forms approved in the TAB Pre-Field Engineering Plan, and any other data sheets and supporting documentation necessary, to document the required design data; field measurements data; system configuration and settings during testing; design and installation deficiencies; and, required data evaluations. Reports must be completed by the TAB Team, and reviewed and certified by the TAB Team Supervisor.

1.12.1 TAB Reports

Report the data for the Certified TAB Report of Proportional Balancing, Certified TAB Report of Season 1, and Certified TAB Report of Season 2 in compliance with the following requirements:

a. Project Summary: Provide a project narrative, including systems and equipment tested, describing the outcome of the testing and balancing and include a list of items documenting system variations deviating from the design tolerances, any abnormalities discovered, and any outstanding items with proposed corrective action. When applicable, provide notations describing how actual field procedures differed from those approved in the TAB Pre-Field Engineering Plan. If no procedures differed, state so in the report.

b. Certification: Include the TAB Team Supervisor's physical or electronic stamp, issued by the certifying body, and dated signature.

c. Data from TAB Field Work: Prepare the TAB field data using the report forms approved in the TAB Pre-Field Engineering Plan and any other data sheets necessary to document the required final system balance and demonstrate accuracy and repeatability during TAB Field Acceptance Testing. For each unique calibration factor utilized, report the traverse airflow, the flow measuring instrument reading (e.g., flow hood airflow), the resulting correction factor, and the location of

the traverse taken. Include notation on each form with the date the form's data was collected and with any Supporting Document reference number. Provide a detailed explanation wherever a final measurement did not achieve the required value or fall within the required range of values. Include the following:

(1) System Configuration: Clearly identify system configurations and conditions affecting data for all reported data. Include system operational parameters such as device positioning, system diversity, modes of operation, and setpoints necessary to set up and duplicate the system configuration during the TAB Field Acceptance Testing. Include final hydronic differential pressure setpoint, hydronic system fill pressure, glycol percentage, pump and fan motor frequency in maximum, fan motor frequency in minimum, fan brake horsepower, calibration coefficients and factors, control damper positions, and primary air static pressure setpoint.

(2) Static Pressure Profiles: Provide static pressure profiles in accordance with this section. Illustrate pressures in an Equipment Diagram representative of the actual installation. Include design static pressure and differential pressure values for comparison where provided.

(3) Duct Traverses: Provide duct traverse measurement data in accordance with this section. Include individual velocities from the duct traverses taken. Illustrate, in an Equipment Diagram, the actual entering and leaving duct traverse airflows for each piece of air-handling equipment exceeding 2,000 CFM.

(4) Air and Water Systems' Open Paths: Identify air and hydronic system open paths in the report form.

(5) Motor Data: Provide motor current (amperage) and voltage for each phase of motors, including those powered by VFDs. Include current setting for thermal overload protection for motors, including starter or VFD brand, model, enclosure type, installed overload devices, rating(s) or rating range, and setpoints, and revised device ratings and setpoints when applicable.

(6) Seasonal Thermal Performance Data: Include capacity field data and design and calculated capacity, along with ambient outdoor temperature data, on seasonal thermal performance report forms. Include notation to identify system configuration settings that deviate from the design sequences of operation and setpoints when necessary to obtain the design capacity.

d. Flow Measuring Device Calibration: Provide calibration data at each scheduled design volumetric flow rate.

e. Instruments: Provide an updated list of the instruments used to measure the TAB data. Include in the listing each instrument's unique identification number, calibration date, and calibration expiration date. Include a copy of the instrument calibration certificate when updated from the copy in the approved TAB Pre-Field Engineering Plan.

f. Performance Curves: Provide copies of the factory pump curves and fan curves for pumps and fans included on the job, and manufacturer equipment data curves or tables correlating pressure drop and water

flow rate. Include marks or notation indicating the reported final balance values on each curve.

g. Calibration Charts: Provide a factory calibration chart, table, graph, or diagram, as applicable, for each applicable balancing valve and flow measuring device such as a venturi flow meter and an orifice flow meter.

h. TAB Schematic Drawings: Provide updated drawings and diagrams with the final installed locations of all terminals and devices, any numbering changes, and actual test locations including duct traverse and static pressure measurements. Indicate the air terminal device and water coil of the open paths for those identified.

i. Mechanical Equipment Schedules: Include a copy of the mechanical equipment schedules.

j. Supporting Documents: Provide copies of any request for information (RFI) with the RFI response; summaries of implemented change order(s); meeting minutes with participants; electronic mail with addresses; and, other documentation substantiating any deviations of the reported design values from the initial contract design documents. Include this documentation in an appendix to the TAB report with sequential numbering of each separate document for reference in the data presentation forms.

k. Guarantee: Provide documentation substantiating the inclusion of the quality assurance program such as a certificate of conformance or performance guarantee issued by the TAB Firm's certifying body.

1.13 SEQUENCING AND SCHEDULING

1.13.1 Submittal and Work Schedule

This schedule is structured as though the HVAC and DHW systems construction, and thereby the DALT and TAB work, submittals, and field acceptance testing, is going to be completed in a single occurance for the contract, including the seasonal work. All DALT and TAB field work, submittals, and acceptance testing must be planned and completed separately for each occurance. Include the items listed in this schedule in the Network Analysis Schedule (NAS) required by Section 01 32 17.00 20 COST-LOADED NETWORK ANALYSIS SCHEDULES. Ensure sufficient time is scheduled to complete each item, including Government review period for submittals. The order of items listed below does not imply a specified sequence:

a. Submission of TAB Firm and Personnel Qualifications

b. Submission of Design Review Report

c. Submission of TAB Pre-Field Engineering Plan

d. Pre-DALT/TAB Meeting

e. DALT Field Work

f. Submission of Pre-Final DALT Reports

g. DALT Field Acceptance Testing

h. Submission of Certified Final DALT Report

i. Proportional Balancing TAB Field Work

j. Submission of Certified TAB Report of Proportional Balancing

k. Proportional Balancing TAB Field Acceptance Testing

l. Season 1 TAB Field Work

m. Submission of Certified TAB Report of Season 1

n. Season 1 TAB Field Acceptance Testing

o. Season 2 TAB Field Work

p. Submission of Certified TAB Report of Season 2

q. Season 2 TAB Field Acceptance Testing

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 DALT PROCEDURES

3.1.1 Systems Requiring DALT

All duct systems, regardless of duct pressure classification, are subject to DALT including supply, return, exhaust, relief, and outdoor air with exception of transfer air. From each duct system indicated as subject to DALT, the Contracting Officer will randomly select sections of each completed duct system for testing such that the duct selections will not exceed 25 percent of the total measured linear footage of each duct system. Include notation within the associated Advance Notice indicating the specific unit(s) when electing the following for any single unit or quantity of similar units:

a. It is acceptable for an entire duct system associated with a single unit (e.g., 100 percent of AHU-1 supply air ductwork) to be leak tested instead of disassembling that system in order to DALT only the 25 percent duct selection specified. Testing an entire duct system for a unit does not reduce the DALT requirements for any other duct system or selection.

b. It is acceptable for the duct systems (e.g., FCU supply air and return air) for 25 percent of the total quantity of similar terminal units and light-duty air-handling equipment (e.g., WSHPs less than 5 tons cooling capacity, VAVs, and FCUs) to be leak tested instead of disassembling 25 percent of each duct system for each of these units.

3.1.2 Prerequisites for DALT Field Work

Complete the following prior to starting DALT Field Work:

a. Submission and approval of the SD-01 Preconstruction Submittals.

b. Installation and sealing in conformance with the contract documents of those duct systems indicated completed and ready for testing.

c. Confirmation ductwork to be air leakage tested is accessible and not concealed or insulated.

d. Work items and inspections indicated in the Pre-DALT Field Work Checklist.

e. Furnish the TAB Team a copy of the ductwork layout Detail Drawings indicating the completed duct systems available for DALT.

3.1.3 Advance Notice for Pre-Final DALT Field Work

Provide the Contracting Officer with written notification including the proposed date for DALT and a copy of the ductwork layout Detail Drawings with indication and dimensions of the duct systems, or portion thereof, completed and ready for DALT. Include with the notice the signed and dated Pre-DALT Field Work Checklist, with all work items certified by the Contractor and mechanical contractor as completed.

Provide the notice after completion of the installation of duct systems indicated as ready for testing.

3.1.4 Ductwork Selections

From each duct system indicated within the Advance Notice of Pre-Final DALT Field Work, the Contracting Officer will select sections of each completed duct system for testing in accordance with this section. Maintain a hard copy of the drawings indicating ductwork selections on site.

Sealing of the ductwork selections is prohibited, with exception of temporary end caps and connection for test apparatus, from the time the Contractor is notified of the selections until DALT measurements are recorded.

3.1.5 DALT Field Work

Conduct DALT Field work on the ductwork selections in compliance with the procedures specified in SMACNA 016, as supplemented and modified by this section. Use a duct test pressure equivalent to each ductwork selection's pressure classification. Calculate the ductwork selection allowable leakage using the more stringent, lower numerical value, of the duct system leakage class for the duct pressure classification indicated on the drawings or the maximum permitted leakage class defined as follows:

a. Round/Oval Leakage Class = 3 and Rectangular Leakage Class = 4 at duct pressure classification of 4 in. WG and above.

b. Round/Oval Leakage Class = 4 and Rectangular Leakage Class = 8 at duct pressure classification of 2 in. WG and 3 in. WG.

c. Round/Oval Leakage Class = 8 and Rectangular Leakage Class = 16 at duct pressure classification of 1 in. WG.

Complete DALT Field Work on the ductwork selections within 48 hours from receipt of selections, including disconnection, capping, measuring, and

testing of ductwork. If any of the duct sections tested is a DALT failure, terminate testing for that system and report the duct selection as failed and the duct system as DALT terminated in the Pre-Final DALT Report.

3.1.6 Pre-Final DALT Report

Upon completion of the DALT Field Work, prepare a Pre-Final DALT Report. Prepare separate Pre-Final DALT Reports when DALT is not completed in a single event and differentiate these with a sequential numerical suffix such as Pre-Final DALT Report 1.

Submit the Pre-Final DALT Report to the Contracting Officer for approval within two working days of completion of the related DALT Field Work.

3.1.7 Quality Assurance

3.1.7.1 DALT Field Acceptance Testing

In the presence of the Contracting Officer and TAB Team Field Leader, conduct field acceptance testing of a maximum of 50 percent of the duct sections in the approved Pre-Final DALT Report as selected by the Contracting Officer. If any of the duct sections tested is a DALT failure, terminate data checking for that section; the associated Pre-Final DALT Report data for the given duct selection will be disapproved.

Provide the Contracting Officer with written notification of the proposed date for DALT Field Acceptance Testing within 14 calendar days of approval of the Pre-Final DALT Report and a minimum of 7 calendar days in advance of proposed field acceptance testing date.

3.1.7.2 Retesting and Additional Testing

For any duct section indicated as a DALT failure, make the necessary repairs. Repairs must be applied to similar conditions in all untested duct sections. For each DALT failure, and after repairs are completed, conduct DALT on the untested duct selection(s) of the terminated duct system, on the failed section, and one additional duct section as selected by the Contracting Officer. Prepare and resubmit the Pre-Final DALT Report with the original, retesting, and additional selection test results for approval. Reschedule field acceptance testing of the approved revised report with the Contracting Officer.

3.1.8 Certified Final DALT Report

Prepare the Certified Final DALT Report using data furnished by the TAB Team in the Pre-Final DALT Report(s).

Submit the Certified Final DALT Report to the Contracting Officer for approval within 14 calendar days of successful completion of all DALT Field Acceptance Testing.

3.2 TAB PROCEDURES

3.2.1 Systems Requiring TAB

All DHW recirculation, air and hydronic systems are subject to TAB such as the following:

a. Air Systems:

(1) Supply Air (SA)

(2) Return Air (RA)

(3) Outdoor Air (OA)

(4) Exhaust Air (EA)

(5) Relief Air (LA)

(6)

b. Hydronic Systems:

(1) Chilled Water (CHW)

(2) Condenser Water (CW)

(3) Heating Hot-Water (HHW)

(4)

c. Other Systems:

(1) DHW Recirculation

(2)

Each system includes the associated equipment, devices, and components such as:

a. Air systems: AHUs, DOAS units, Heating and Ventilating Units (HVUs), VAV terminal units, FCUs, WSHPs, fans, duct systems, energy recovery systems, exhaust hoods, flow measuring and balancing devices, grilles, registers, and diffusers.

b. Hydronic and DHW systems: chillers, boilers, cooling towers, coils, pumps, piping systems, heat exchangers, energy recovery systems, pressure reducing valves, flow-measuring and balancing devices, and pressure and temperature ports.

c. Other systems: DHW heaters, pressure and temperature ports, flow balancing valves, and thermostatic mixing valves.

3.2.2 TAB Tolerances

3.2.2.1 System Tolerances

System tolerances apply to the design flow rates as specified or indicated in the contract documents. HVAC systems' tolerance is plus or minus 5 percent, except as indicated below:

a. Air Systems:

(1) OA 50 CFM or less: plus 5 CFM to minus zero CFM

(2) EA 50 CFM or less: plus zero CFM to minus 5 CFM

(3) SA and RA of 100 percent recirculating single-zone air-handing equipment: plus or minus 10 percent

(4) SA and RA 50 CFM or less: plus or minus 3 CFM

b. Hydronic Systems:

(1) HW at coils: plus or minus 10 percent

c. Other Systems:

(1) DHW Recirculation: plus or minus 10 percent

3.2.2.2 Acceptance Tolerances

Field Acceptance Testing measurements must remain within the associated System Tolerance of the design flow rate. When the associated System Tolerance is plus or minus 10 percent, Field Acceptance Testing measurements must remain within the associated System Tolerance of the design flow rate and repeat within plus or minus 5 percent of the approved Certified TAB Report data.

3.2.3 Advance Notice for TAB Field Work

Provide the Contracting Officer with written notification including the proposed dates for TAB Field Work and a list of the systems ready for TAB on the proposed start date. Include with the notice the signed and dated Pre-TAB Field Work Checklist, with the applicable work items certified by the Contractor and mechanical contractor as having been completed and working as designed.

Furnish the Advance Notice for Proportional Balancing TAB Field Work, for Season 1 TAB Field Work, and for Season 2 TAB Field Work TAB Field Work prior to start of the TAB Field Work.

3.2.4 Proportional Balancing TAB Field Work

Conduct TAB Field Work in conformance with the TAB Standard, as supplemented and modified by this section. Test, adjust, and balance the HVAC and DHW recirculation systems until measured flow rates (air and water flow) are within the specified System Tolerances. Do not exceed maximum rated revolutions per minute (RPM) and rated full load amperage for equipment during any mode of operation, including with loaded filters and wet cooling coils. Variable speed drives must be capable of controlling to maximum and minimum flows with a drive operational range not less than 25 Hz. Operation exceeding 60 Hz is permitted only for direct-drive plenum fans rated for operation at higher frequencies. Follow the procedures specified in NFPA 70E during electrical measurements on exposed energized conductors or circuits. Additionally, this work includes the following:

a. Adjustment of flow control and balancing devices such as balancing valves, balancing dampers, and sheaves.

b. Adjustment of variable frequency drives and speed controllers.

c. Calibration of each controls system flow measuring device at each

scheduled design volumetric flow rate.

d. Changing out fan sheaves if required to obtain flow rates specified or indicated.

Complete Proportional Balancing TAB Field Work at a minimum of 90 calendar days in advance of the scheduled Beneficial Occupancy Date (BOD).

3.2.4.1 Prerequisites for TAB Field Work

Complete the following prior to starting Field Work:

a. DALT Field Work and obtain approval of the Certified Final DALT Report.

b. Installation of pressure and temperature test ports adjacent to inlet and outlet of every pump, heat exchanger, chiller, boiler, and coil, and as required by the TAB Team Supervisor.

c. Work items and inspections indicated in the Pre-TAB Field Work Checklist, including providing new air filters and cleaning screens of hydronic system strainers.

d. Enclosure of the building envelope according to the contract documents with the Air Barrier Pressure Test completed and the Air Leakage Test Reports and Diagnostic Test Reports approved. Hydronic system TAB field work may commence prior to air barrier test completion.

e. Manufacturer's equipment start-up forms for each piece of equipment to be tested.

f. HVAC controls system installation and start-up for each piece of equipment to be tested.

3.2.4.2 TAB Air Distribution Systems

Balance systems to minimize throttling losses with at least one open path, with fully open balancing dampers from the fan discharge to an outlet and from fan suction to an inlet, for fans greater than 1 hp.

a. Static Pressure Profile Work

Measure and record static pressure profiles under maximum airflow conditions for air systems of 2,000 CFM and greater.

Measure static pressure data for supply, return, relief, exhaust, and outdoor air ducts for the systems. The static pressure measurement data must include, in addition to TAB Standard requirements, the following:

(1) Inlet and discharge static pressures for fans.

(2) Static pressure drop across coils and heat reclaim devices installed in unit cabinetry or the system ductwork.

(3) Static pressure drop across automatic control dampers.

(4) Static pressure drop across air filters, acoustic silencers, moisture eliminators, airflow straighteners, airflow measuring stations, and other pressure drop producing specialty items

installed in unit cabinetry or in the system ductwork. Examples of these specialty items are smoke detectors, white sound generators, RF shielding, wave guides, security bars, blast valves, and duct mounted humidifiers.

Do not report static pressure drop across duct fittings provided for the sole purpose of conveying air, such as elbows with or without turning vanes, transitions, offsets, plenums, manual dampers, and branch take-offs.

(5) Report static pressure drop across louvers.

(6) Report static pressure readings in the duct at the point where the ducts connect to air-handling equipment.

b. Duct Traverse Work

Perform duct traverses, in addition to TAB Standard requirements, for main and each branch main supply, return, exhaust, relief and outdoor air ducts for each piece of air-handling equipment exceeding 1,000 CFM. Include those ducts which lack 7 1/2 duct diameters upstream and 3 duct diameters downstream of straight duct unobstructed by duct fittings, offsets, and elbows. Perform additional duct traverses as shown on the contract drawings. Evaluate the suitability of the duct traverse measurement based on satisfying the qualifications for a satisfactory pitot traverse plane as defined by AMCA 203.

c. Building Pressurization Work

Perform measurements upon completion of air system balancing and during climate conditions suitable for a pressure test in accordance with Section 01 91 19 BUILDING ENCLOSURE COMMISSIONING. Record building differential pressure for all sides of the building on each floor where openings allow measurements by instrumentation. Report all system setup parameters affecting building pressure measurement (e.g., exhaust, relief and outdoor airflow, damper positions, and fan speeds) and indicate wind speed during time of building pressure measurements. Measure in maximum and minimum building systems configuration.

Measurements must occur during building system setup with building exterior doors and windows closed and as follows:

(1) Occupied Mode; air-handling equipment and fans in maximum cooling, maximum design airflow.

(2) Occupied Mode; air-handling equipment with all zones satisfied such as VAVs at minimum design airflow.

Measure differential pressure for the following locations: Any location where differential pressure sensor is located and/or used as control point for fan control..

3.2.4.3 TAB Hydronic and Domestic Hot Water Distribution Systems

Balance systems to minimize throttling losses with at least one path, with fully open balancing valves, from the pump discharge to a terminal device and back to the pump suction, for pumps greater than 1 hp. Measure and record flow rates at all balancing valves and flow measuring devices.

3.2.4.4 Marking of Settings and Test Ports

Upon completing each item of work for TAB Field Work specified and prior to TAB Field Acceptance Testing, the TAB Team is to permanently mark the settings of HVAC adjustment devices including valves, gauges, and dampers so that adjustment can be restored if disturbed at any time. Secure balancing damper handles and set valve memory stops. Label variable frequency drives with final frequency (Hz) and control setpoint. Provide permanent markings clearly indicating the settings on the adjustment devices which result in the data reported on the Certified TAB Report. Permanently and legibly mark and identify the duct test ports. If the ducts have external insulation, make these markings on the exterior side of the insulation. Show the location of test ports on the as-built mechanical drawings with dimensions given where the test port is covered by exterior insulation.

3.2.5 Seasonal Thermal Performance TAB Field Work

Perform operational thermal performance testing of the HVAC systems as soon as all prerequisites are completed, but prior to facility turnover, regardless of the season. In addition, perform thermal performance testing during Season 1 and Season 2 when the outdoor air temperature (OAT) is within the seasonal temperature ranges below for equipment with performance that is OAT dependent. It is acceptable to conduct Season 1 testing prior to the applicable season dates if all prerequisites are complete including OAT within range.

a. Cooling Season: 86 to 96 degrees F dry-bulb temperature.

b. Heating Season: 17 to 27 degrees F dry-bulb temperature.

Complete Season 1 Thermal Performance Testing Field Work a minimum of 60 calendar days in advance of the scheduled BOD.

3.2.5.1 Prerequisites for Season 1 Thermal Performance Field Work

Complete the following prior to starting Field Work:

a. Proportional Balancing TAB Field Work.

b. Work items and inspections indicated in the Pre-TAB Field Work Checklist for the applicable season, including confirming clean filters and strainers.

c. Advance Notice for Season 1 TAB Field Work.

d.

3.2.5.2 Thermal Performance Testing

Conduct thermal performance (capacity) tests to verify thermal energy transfer components, devices, and equipment meet the indicated design capacity. This work includes:

a. Verifying, using the same procedures and instruments for proportional balancing TAB field work, flows (air and water) remain within the

System Tolerances. If the measurements exceed the specified System Tolerances, report these as deficiencies in accordance with this section.

b. Measuring water temperatures through immersion into fluid stream.

c. For ducted units, measuring airflows via duct traverse.

d. Measuring the range, from minimum to maximum, of the outdoor ambient dry-bulb temperature and corresponding dew-point temperature within which the TAB seasonal data was recorded. Record these temperature ranges on each day of seasonal data measurements.

Report all design data, actual field measurements, and capacity calculations for the components, devices, and equipment below.

3.2.5.3 Units with Coils

Report heating and cooling performance tests for heating and cooling coils such as heating hot-water, chilled-water, direct-expansion, and steam coils:

a. For units with capacities greater than 7.5 tons (90,000 BTU/H) cooling, such as factory manufactured units, central built-up units and rooftop units, determine the apparent air-side coil capacity by calculations utilizing direct measurement of airflow, and measurements of entering and leaving wet-bulb and dry-bulb temperatures for cooling capacity and dry-bulb temperatures only for heating capacity. Calculate water-side coil capacity utilizing direct measurements of water flow rate, and entering and leaving water temperatures. Measure and record coil water pressure drop.

   Measure and report dry-bulb temperature and relative humidity within the supply air duct downstream of each cooling coil. Report the corresponding dewpoint temperature.

b. For units with capacities of 7.5 tons (90,000 BTU/H) or less, such as fan coil units, duct mounted reheat coils associated with VAV terminal units, and unitary units, determine the apparent air-side coil capacity by calculations using direct measurement of airflow, single point measurement centered within the airstream of entering and leaving wet-bulb and dry-bulb temperatures for cooling capacity and dry-bulb temperatures only for heating capacity.

3.2.5.4 Units with Heat Recovery Devices

Report heating and cooling energy recovery performance tests for energy recovery devices such as wheels, coils, and fixed plate exchangers.

Report total cooling capacity, heating capacity, and energy recovery effectiveness. For outdoor air and exhaust airstreams measure and report airflows and entering and leaving wet-bulb and dry-bulb temperatures across heat recovery device. For water-side calculations, utilize direct measurements of water flow rate and entering and leaving water temperatures. Measure and record water pressure drops.

3.2.5.5 Thermal Energy Transfer Equipment

Report heating and cooling performance tests for thermal energy transfer

equipment (e.g., boilers, chillers, and cooling towers). Measure and report water flow rates, water-side pressure drops, and entering and leaving water temperatures. Report capacities.

3.2.6 Deficiencies

Strive to meet the intent of this section to maximize the performance of the equipment as designed and installed. However, if deficiencies in equipment or system design or installation prevent TAB work from being accomplished in accordance with this section, the TAB Team Supervisor must submit written notification within five working days from discovery of all such deficiencies for resolution. The TAB Firm must issue notice concurrently to the Contractor for corrective action and to the Contracting Officer for information. Provide a complete explanation, including supporting documentation, detailing the deficiencies and proposed corrective actions in the notification. Where deficiencies are encountered that adversely impact successful completion of:

a. TAB Field Work: Resolve deficiencies prior to submission of the Certified TAB Report.

b. TAB Field Acceptance Testing: The Contractor must, within five working days of the TAB Firm notice, submit written notification directly to the Contracting Officer, with a separate copy to the TAB Firm, of all such deficiencies, the intended or implemented corrective action, and the planned or actual date(s) for completion of each corrective action.

Responsibility for correction of installation deficiencies is the Contractor's.

3.2.7 Certified TAB Reports

Upon completing each item of work for TAB Field Work specified, prepare a TAB Report in accordance with this section using data furnished by the TAB Team. If there are no comments generated during the Certified TAB Report review process, state so in the report.

Submit the Certified TAB Report of Proportional Balancing to the Contracting Officer for approval within 14 calendar days of completion of the Proportional Balancing TAB Field Work.

Submit the Certified TAB Report of Season 1 to the Contracting Officer for approval within 14 calendar days of completion of the Season 1 TAB Field Work.

Provide a copy of the approved Certified TAB Report data in an electronic spreadsheet file, along with all supporting graphs, charts, and curves, within 21 calendar days of receipt of TAB Report approval.

3.2.8 Quality Assurance

3.2.8.1 TAB Field Acceptance Testing

In the presence of the Contracting Officer and TAB Team Field Leader, conduct field acceptance testing of points and areas in the approved Certified TAB Report as selected by the Contracting Officer. The selections include data types such as water and air volumetric flow rates, velocity, pressure, rotational speed (RPM), temperature, and electrical

current recorded in the TAB Report. Measurement and test procedures are the same as required for TAB Field Work. If any of the measurements is a TAB failure, the Contracting Officer may terminate data verification. The sample group will be disapproved and require retesting and additional testing. Conduct TAB Field Acceptance Testing for the Certified TAB Report of Season 1 and for the Certified TAB Report of Season 2 within the applicable Cooling Season or Heating Season.

Provide the Contracting Officer with written notification of the proposed date for Proportional Balancing TAB Field Acceptance Testing within 14 calendar days of approval of the Certified TAB Report of Proportional Balancing and a minimum of 7 calendar days in advance of proposed TAB Field Acceptance Testing date. Provide the Contracting Officer with separate written notification of the proposed date for Season 1 and for Season 2 TAB Field Acceptance Testing within 7 calendar days of approval of the associated Certified TAB Report and a minimum of 7 calendar days in advance of proposed TAB Field Acceptance Testing date.

3.2.8.2 Sample Strategy

Field acceptance testing includes verification of selections using the sample strategy indicated for each Category. For each of the following Categories, the Contracting Officer will select a sample group for testing:

Category 1: 100 percent of the air system equipment such as DOAS units, AHUs (rooftop and central stations), return fans, computer room air-conditioning (CRAC) units, and energy recovery units (ERUs) and 25 percent of the associated air terminal devices.

Category 2: 100 percent of the water system equipment such as chillers, boilers, cooling towers, pumps, DHW heaters, and Category 1 equipment's coils.

Category 3: 25 percent of the air terminal units (e.g., VAV terminal units, FCUs), and of the exhaust fans, supply fans, and relief fans and 100 percent of the selected equipment's air terminal devices.

Category 4: 25 percent of the hydronic and DHW recirculation systems' flow measuring devices (e.g., manual balancing valves and flow meters) and Category 3 equipment's hydronic coils.

Quantity is rounded up to a whole number for a sample size and is a minimum of three units or devices when three or more exist.

3.2.8.3 Retesting and Additional Testing

For any data indicated as a TAB Failure and when the data verification is terminated, make the necessary corrections, conduct TAB Field Work, set and secure balancing devices, and mark settings. Prepare and resubmit the applicable TAB Report with the corrected test results for approval. Reschedule TAB Field Acceptance Testing of the approved revised report with the Contracting Officer. For each TAB Failure, and after the revised report is approved, conduct field acceptance testing of the failed data point, one additional selection by the Contracting Officer from the same Category for each failure, and new selections by the Contracting Officer in the same Category using the Category's sample strategy. If there is insufficient quantity of data in the same Category, the Contracting Officer may select data from a different Category.

3.3 CLOSEOUT ACTIVITIES

3.3.1 Season 2 Thermal Performance TAB Field Work

Perform operational thermal performance testing of the HVAC systems during Season 2 when the OAT is within the seasonal temperature range.

3.3.1.1 Prerequisites for Season 2 Thermal Performance Field Work

Complete the following prior to starting Field Work:

a. Proportional Balancing TAB Field Work.

b. Work items and inspections indicated in the Pre-TAB Field Work Checklist for the applicable season, including confirming clean filters and strainers.

c. Advance Notice for Season 2 TAB Field Work.

d.

3.3.1.2 Season 2 Thermal Performance Testing

Conduct thermal performance (capacity) tests to verify thermal energy transfer components, devices, and equipment meet the indicated design capacity within the parameters for Season 2.

Submit the Certified TAB Report of Season 2 to the Contracting Officer for approval within 14 calendar days of completion of Season 2 Thermal Performance TAB Field Work.

3.4 PREREQUISITE FOR SYSTEMS ACCEPTANCE

Compliance with field acceptance testing requirements of this section is a prerequisite for the final Contracting Officer acceptance of the HVAC systems.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 07 00

THERMAL INSULATION FOR MECHANICAL SYSTEMS
08/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. At the discretion of the Government, the manufacturer of any material supplied will be required to furnish test reports pertaining to any of the tests necessary to assure compliance with the standard or standards referenced in this specification.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 90.1 - IP	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings
ASHRAE 90.1 - SI	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings

ASTM INTERNATIONAL (ASTM)

ASTM A240/A240M	(2025a) Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications
ASTM A580/A580M	(2023) Standard Specification for Stainless Steel Wire
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM C195	(2007; R 2024) Standard Specification for Mineral Fiber Thermal Insulating Cement
ASTM C450	(2008) Standard Practice for Fabrication of Thermal Insulating Fitting Covers for NPS Piping, and Vessel Lagging
ASTM C533	(2017; R 2023) Standard Specification for Calcium Silicate Block and Pipe Thermal Insulation
ASTM C534/C534M	(2025) Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form
ASTM C547	(2022a) Standard Specification for Mineral Fiber Pipe Insulation
ASTM C552	(2022) Standard Specification for Cellular

	Glass Thermal Insulation
ASTM C553	(2024) Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications
ASTM C585	(2010) Standard Practice for Inner and Outer Diameters of Thermal Insulation for Nominal Sizes of Pipe and Tubing
ASTM C591	(2022) Standard Specification for Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
ASTM C592	(2024) Standard Specification for Mineral Fiber Blanket Insulation and Blanket-Type Pipe Insulation (Metal-Mesh Covered) (Industrial Type)
ASTM C610	(2017; R 2023) Standard Specification for Molded Expanded Perlite Block and Pipe Thermal Insulation
ASTM C612	(2014; R 2019) Standard Specification for Mineral Fiber Block and Board Thermal Insulation
ASTM C647	(2008; R 2013) Properties and Tests of Mastics and Coating Finishes for Thermal Insulation
ASTM C755	(2019b) Standard Practice for Selection of Water Vapor Retarders for Thermal Insulation
ASTM C795	(2008; R 2023) Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel
ASTM C916	(2020) Standard Specification for Adhesives for Duct Thermal Insulation
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM C921	(2010; R 2015) Standard Practice for Determining the Properties of Jacketing Materials for Thermal Insulation
ASTM C1126	(2024) Standard Specification for Faced or Unfaced Rigid Cellular Phenolic Thermal Insulation
ASTM C1136	(2023) Standard Specification for Flexible, Low Permeance Vapor Retarders for Thermal Insulation
ASTM C1290	(2016; R 2021) Standard Specification for Flexible Fibrous Glass Blanket Insulation

	Used to Externally Insulate HVAC Ducts
ASTM C1710	(2011) Standard Guide for Installation of Flexible Closed Cell Preformed Insulation in Tube and Sheet Form
ASTM D882	(2012) Tensile Properties of Thin Plastic Sheeting
ASTM D2863	(2019) Standard Test Method for Measuring the Minimum Oxygen Concentration to Support Candle-Like Combustion of Plastics (Oxygen Index)
ASTM D5590	(2017; R 2021) Standard Test Method for Determining the Resistance of Paint Films and Related Coatings to Fungal Defacement by Accelerated Four-Week Agar Plate Assay
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM E96/E96M	(2024a) Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials
ASTM E2231	(2021) Standard Practice for Specimen Preparation and Mounting of Pipe and Duct Insulation Materials to Assess Surface Burning Characteristics

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/

GREEN SEAL (GS)

GS-36	(2013) Adhesives for Commercial Use

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-58	(2025) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation

MIDWEST INSULATION CONTRACTORS ASSOCIATION (MICA)

MICA Insulation Stds	(8th Ed) National Commercial & Industrial Insulation Standards

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 90A	(2024) Standard for the Installation of Air Conditioning and Ventilating Systems
NFPA 90B	(2024) Standard for the Installation of Warm Air Heating and Air Conditioning Systems

SCIENTIFIC CERTIFICATION SYSTEMS (SCS)

SCS	SCS Global Services (SCS) Indoor Advantage

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2022) Adhesive and Sealant Applications

TECHNICAL ASSOCIATION OF THE PULP AND PAPER INDUSTRY (TAPPI)

TAPPI T403 OM	(2022) Bursting Strength of Paper

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-A-3316	(1987; Rev C; Am 2 1990) Adhesives, Fire-Resistant, Thermal Insulation
MIL-A-24179	(1969; Rev A; Am 2 1980; Notice 1 1987; Notice 2 2020) Adhesive, Flexible Unicellular-Plastic Thermal Insulation
MIL-PRF-19565	(1988; Rev C) Coating Compounds, Thermal Insulation, Fire- and Water-Resistant, Vapor-Barrier

UL SOLUTIONS (UL)

UL 94	(2023; Reprint Jan 2024) UL Standard for Safety Tests for Flammability of Plastic Materials for Parts in Devices and Appliances
UL 723	(2018; Reprint Jun 2025) UL Standard for Safety Test for Surface Burning Characteristics of Building Materials
UL 2818	(2022) GREENGUARD Certification Program For Chemical Emissions For Building Materials, Finishes And Furnishings

1.2 SYSTEM DESCRIPTION

1.2.1 General

Provide field-applied insulation and accessories on mechanical systems as specified herein; factory-applied insulation is specified under the piping, duct or equipment to be insulated. Provide insulation of heat distribution systems and chilled water systems outside of buildings as specified in Section 33 61 14 EXTERIOR BURIED PREINSULATED WATER PIPING.

Provide field applied insulation materials required for use on Government-furnished items as listed in the SPECIAL CONTRACT REQUIREMENTS.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Submit the three SD types, SD-02 Shop Drawings, SD-03 Product Data, and SD-08 Manufacturer's Instructions at the same time for each system.

SD-02 Shop Drawings

MICA Plates; G

Pipe Insulation Systems and Associated Accessories

Duct Insulation Systems and Associated Accessories

Equipment Insulation Systems and Associated Accessories

Recycled content for insulation materials; S

SD-03 Product Data

Pipe Insulation Systems; G

Duct Insulation Systems; G

Equipment Insulation Systems; G

SD-04 Samples

Thermal Insulation; G

Display Samples; G

SD-07 Certificates

Indoor air quality for adhesives; S

SD-08 Manufacturer's Instructions

Pipe Insulation Systems; G

Duct Insulation Systems; G

Equipment Insulation Systems; G

1.4 CERTIFICATIONS

1.4.1 Adhesives and Sealants

Provide products certified to meet indoor air quality requirements by UL 2818 (Greenguard) Gold, SCS Global Services Indoor Advantage Gold or provide certification or validation by other third-party programs that

products meet the requirements of this Section. Provide current product certification documentation from certification body. When product does not have certification, provide validation that product meets the indoor air quality product requirements cited herein.

1.5 QUALITY ASSURANCE

1.5.1 Installer Qualification

Qualified installers must have successfully completed three or more similar type jobs within the last 5 years.

1.6 DELIVERY, STORAGE, AND HANDLING

Deliver materials in the manufacturer's unopened containers. Protect materials delivered and placed in storage from weather, humidity, dirt, dust and other contaminants. The Contracting Officer may reject insulation material and supplies that become dirty, dusty, wet, or contaminated by some other means. Attach manufacturer's stamp or label giving the name of the manufacturer and brand, and a description of the material, date codes, and approximate shelf life (if applicable) to packages or standard containers of insulation, jacket material, cements, adhesives, and coatings delivered for use, and samples required for approval. Insulation packages and containers must be asbestos free.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Provide materials which are the standard products of manufacturers regularly engaged in the manufacture of such products and that essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening and is an acceptable product per this specification. Submit a complete list of materials, including manufacturer's descriptive technical literature, performance data, catalog cuts, and installation instructions. Include the product number, k-value, thickness and furnished accessories including adhesives, sealants and jackets for each mechanical system requiring insulation. The product data must be copyrighted, have an identifying or publication number, and have been published prior to the issuance date of this solicitation. Submit materials furnished under this section together in a booklet.

2.1.1 Insulation System

Provide insulation systems in accordance with the approved MICA National Insulation Standards plates as supplemented by this specification. Provide field-applied insulation for heating, ventilating, and cooling (HVAC) air distribution systems and piping systems that are located within, on, under, and adjacent to buildings; and for plumbing systems. Provide CFC and HCFC free insulation.

2.1.2 Surface Burning Characteristics

Unless otherwise specified, insulation must have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Determine flame spread, and smoke developed indexes, by ASTM E84 or UL 723. Test insulation in the same density and installed thickness as the material to be used in the actual construction. Prepare and mount test specimens according to ASTM E2231.

2.2 MATERIALS

Provide insulation that meets or exceed the requirements of ASHRAE 90.1 - IP. Ensure insulation exterior is cleanable, grease resistant, non-flaking and non-peeling. Provide compatible materials that do not contribute to corrosion, soften, or otherwise attack surfaces to which applied in either wet or dry state. Use materials on stainless steel surfaces meeting ASTM C795 requirements. Do not use calcium silicate on chilled or cold water systems. Use asbestos free materials. Provide product recognized under UL 94 (if containing plastic) and listed in FM APP GUIDE.

2.2.1 Adhesives

Provide non-aerosol adhesive products used on the interior of the building (defined as inside of the weatherproofing system) that meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168 (HVAC duct sealants must meet limit requirements of "Other" category within SCAQMD Rule 1168 sealants table). Provide aerosol adhesives used on the interior of the building that meet either emissions requirements of CDPH SECTION 01350 (use the office or classroom requirements, regardless of space type) or VOC content requirements of GS-36. Provide certification or validation of indoor air quality for adhesives.

2.2.1.1 Acoustical Lining Insulation Adhesive

Provide a nonflammable, fire-resistant adhesive conforming to ASTM C916, Type I.

2.2.1.2 Mineral Fiber Insulation Cement

Provide cement in accordance with ASTM C195.

2.2.1.3 Lagging Adhesive

Lagging is the material used for thermal insulation, especially around a cylindrical object. This may include the insulation as well as the cloth/material covering the insulation. To resist mold/mildew, use lagging adhesive meeting ASTM D5590 with 0 growth rating. Provide nonflammable and fire-resistant lagging adhesives that have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Ensure adhesive is MIL-A-3316, Class 1, pigmented white and suitable, as listed by the manufacturer,for bonding fibrous glass cloth to faced and unfaced fibrous glass insulation board; for bonding cotton brattice cloth to faced and unfaced fibrous glass insulation board; for sealing edges of and bonding glass tape to joints of fibrous glass board; for bonding lagging cloth to thermal insulation; or Class 2 for attaching fibrous glass insulation to metal surfaces. Apply lagging adhesives in strict accordance with the manufacturer's recommendations for pipe and duct insulation.

2.2.1.4 Contact Adhesive

Adhesives may be any of, but not limited to, the neoprene based, rubber based, or elastomeric type that have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with

ASTM E84. Ensure adhesive does not adversely affect, initially or in service, the insulation to which it is applied, nor cause any corrosive effect on metal to which it is applied. Ensure that any solvent dispersing medium or volatile component of the adhesive has no objectionable odor and does not contain any benzene or carbon tetrachloride. Ensure dried adhesive does not emit nauseous, irritating, or toxic volatile matters or aerosols when the adhesive is heated to any temperature up to 212 degrees F. The dried adhesive must be nonflammable and fire resistant. Flexible Elastomeric Adhesive: Comply with MIL-A-24179, Type II, Class I. Provide product listed in FM APP GUIDE.

2.2.2 Caulking

ASTM C920, Type S, Grade NS, Class 25, Use A.

2.2.3 Corner Angles

Nominal 0.016 inch aluminum 1 by 1 inch with factory applied kraft backing. Aluminum must be ASTM B209, Alloy 3003, 3105, or 5005.

2.2.4 Fittings

Fabricated Fittings are the prefabricated fittings for flexible elastomeric pipe insulation systems in accordance with ASTM C1710. Together with the flexible elastomeric tubes, they provide complete system integrity for retarding heat gain and controlling condensation drip from chilled-water and refrigeration systems. Flexible elastomeric, fabricated fittings provide thermal protection (0.25 k) and condensation resistance (0.05 Water Vapor Transmission factor). For satisfactory performance, use properly installed protective vapor retarder/barriers and vapor stops on high relative humidity and below ambient temperature applications to reduce movement of moisture through or around the insulation to the colder interior surface.

2.2.5 Finishing Cement

ASTM C450: Mineral fiber hydraulic-setting thermal insulating and finishing cement. All cements that may come in contact with Austenitic stainless steel must comply with ASTM C795.

2.2.6 Fibrous Glass Cloth and Glass Tape

Provide fibrous glass cloth, with 20X20 maximum mesh size, and glass tape with maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Provide tape consisting of 4 inch wide rolls. Provide Class 3 tape that is 4.5 ounces/square yard. Elastomeric Foam Tape: Black vapor-retarder foam tape with acrylic adhesive containing an anti-microbial additive.

2.2.7 Staples

Outward clinching type Type 304 or 316 stainless steel.

2.2.8 Jackets

2.2.8.1 Aluminum Jackets

Provide aluminum jackets consisting of corrugated, embossed or smooth sheet, 0.016 inch nominal thickness; ASTM B209, Temper H14, Temper H16,

Alloy 3003, 5005, or 3105. Do not use corrugated aluminum jacket outdoors. Aluminum jacket securing bands must be Type 304 stainless steel, 0.015 inch thick, 1/2 inch wide for pipe under 12 inch diameter and 3/4 inch wide for pipe over 12 inch and larger diameter. Aluminum jacket circumferential seam bands must be 2 by 0.016 inch aluminum matching jacket material. Ensure bands for insulation below ground are 3/4 by 0.020 inch thick stainless steel, or fiberglass reinforced tape. The jacket may, at the option of the Contractor, be provided with a factory fabricated Pittsburgh or "Z" type longitudinal joint. When the "Z" joint is used, use bands at the circumferential joints that are designed by the manufacturer to seal the joints and hold the jacket in place.

2.2.8.2 Polyvinyl Chloride (PVC) Jackets

Polyvinyl chloride (PVC) jacket and fitting covers must have high impact strength, ultraviolet (UV) resistant rating or treatment and moderate chemical resistance. The minimum thickness for a Standard jacket is 0.020 inch and where high abuse resistance is required use Heavy Duty PVC jacket 0.030 inch. Standard PVC fittings will have an initial core thickness (before thermoforming) of 0.025 inch and heavy duty fittings will have an initial core thickness of 0.030 inch.

2.2.8.3 Vapor Barrier/Weatherproofing Jacket

Provide laminated self-adhesive vapor barrier/weatherproofing jacket, greater than 3 plies standard grade, silver, white, black and embossed or greater than 8 ply (minimum 2.9 mils adhesive); with less than 0.02 permeability when tested in accordance with ASTM E96/E96M, using the water transmission rate test method; heavy duty, white or natural; and UV resistant. Flexible Elastomeric exterior foam with factory applied, UV Jacket made with a cold weather acrylic adhesive. Construction of laminate designed to provide UV resistance, high puncture, tear resistance and excellent Water Vapor Transmission (WVT) rate.

2.2.8.4 Vapor Barrier/Vapor Retarder

Apply the following criteria to determine which system is required.

a. On ducts, equip piping and equipment operating below 85 degrees F or located outside with a vapor barrier.

b. Install ducts, pipes and equipment that are located inside and that always operate above 85 degrees F with a vapor retarder where required as stated in paragraph VAPOR RETARDER REQUIRED.

2.2.9 Vapor Retarder Required

ASTM C921, Type I, minimum puncture resistance 50 Beach units on all surfaces except concealed ductwork, where a minimum puncture resistance of 25 Beach units is acceptable. Minimum tensile strength, 35 pounds/inch width. ASTM C921, Type II, minimum puncture resistance 25 Beach units, tensile strength minimum 20 pounds/inch width. Use jackets on insulation exposed in finished areas that have white finish suitable for painting without sizing. Based on the application, insulation materials that require manufacturer or fabricator applied pipe insulation jackets are cellular glass, when all joints are sealed with a vapor barrier mastic, and mineral fiber. Ensure all non-metallic jackets have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested

in accordance with ASTM E84. Flexible elastomerics require (in addition to vapor barrier skin) vapor retarder jacketing for high relative humidity and below ambient temperature applications.

2.2.9.1 White Vapor Retarder All Service Jacket (ASJ)

ASJ is for use on hot/cold pipes, ducts, or equipment indoors or outdoors if covered by a suitable protective jacket. Provide product which meets all physical property and performance requirements of ASTM C1136, Type I, except a minimum burst strength of 85 psi. ASTM D2863 Limited Oxygen Index (LOI) is a minimum of 31.

In addition, do not use paper or other moisture-sensitive material for the outer exposed surface or the inner-most surface contacting the insulation. Ensure the outer exposed surface is white and has an emittance no less than 0.80.

2.2.9.2 Vapor Retarder/Vapor Barrier Mastic Coatings

2.2.9.2.1 Vapor Barrier

The vapor barrier must be self adhesive (minimum 2 mils adhesive, 3 mils embossed) greater than 3 plies standard grade, silver, white, black and embossed white jacket for use on hot/cold pipes. Ensure permeability is less than 0.02 when tested in accordance with ASTM E96/E96M. Provide products meeting UL 723 or ASTM E84 flame and smoke requirements and that are UV resistant.

2.2.9.2.2 Vapor Retarder

Provide fire and water resistant vapor retarder coating appropriately selected for either outdoor or indoor service. Color must be white. Ensure the water vapor permeance of the compound is in accordance with ASTM C755. Provide nonflammable, fire resistant coating. To resist mold/mildew, provide coating meeting ASTM D5590 with 0 growth rating. Ensure coating meets MIL-PRF-19565 Type II (if selected for indoor service) and is Qualified Products Database listed. Determine all other application and service properties pursuant to ASTM C647.

2.2.9.3 Laminated Film Vapor Retarder

ASTM C1136, Type I, maximum moisture vapor transmission 0.02 perms, minimum puncture resistance 50 Beach units on all surfaces except concealed ductwork; where Type II, maximum moisture vapor transmission 0.02 perms, a minimum puncture resistance of 25 Beach units is acceptable. Provide vapor retarder with a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84. Flexible Elastomeric exterior foam with factory applied UV Jacket. Construction of laminate designed to provide UV resistance, high puncture, tear resistance and an excellent WVT rate.

2.2.9.4 Polyvinylidene Chloride (PVDC) Film Vapor Retarder

Provide PVDC film vapor retarder with a maximum moisture vapor transmission of 0.02 perms, minimum puncture resistance of 150 Beach units, a minimum tensile strength in any direction of 30 lb/inch when tested in accordance with ASTM D882, and a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.2.9.5 Polyvinylidene Chloride Vapor Retarder Adhesive Tape

Requirements must meet the same as specified for Laminated Film Vapor Retarder above.

2.2.9.6 Vapor Barrier/Weather Barrier

Ensure the vapor barrier is greater than 3 ply self adhesive laminate -white vapor barrier jacket- superior performance (permeability less than 0.02 when tested in accordance with ASTM E96/E96M). Provide vapor barrier meeting UL 723 or ASTM E84 25 flame and 50 smoke requirements; and UV resistant. Minimum burst strength 185 psi in accordance with TAPPI T403 OM . Tensile strength 68 lb/inch width (PSTC-1000). Provide tape as specified for laminated film vapor barrier above.

2.2.10 Vapor Retarder Not Required

ASTM C921, Type II, Class D, minimum puncture resistance 50 Beach units on all surfaces except ductwork, where Type IV, maximum moisture vapor transmission 0.10, a minimum puncture resistance of 25 Beach units is acceptable. Provide jacket with a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.2.11 Wire

Soft annealed ASTM A580/A580M Type 302, 304 or 316 stainless steel, 16 or 18 gauge.

2.2.12 Insulation Bands

Provide 1/2 inch wide; 26 gauge stainless steel insulation bands.

2.2.13 Sealants

Choose sealants from the butyl polymer type, the styrene-butadiene rubber type, or the butyl type of sealants. Provide sealants with a maximum permeance of 0.02 perms based on Procedure B for ASTM E96/E96M, and a maximum flame spread index of 25 and a maximum smoke developed index of 50 when tested in accordance with ASTM E84.

2.3 PIPE INSULATION SYSTEMS

Conform insulation materials to Table 1 and minimum insulation thickness as listed in Table 2 and meet or exceed the requirements of ASHRAE 90.1 - SIASHRAE 90.1 - IP. Limit pipe insulation materials to those listed herein and meeting the following requirements:

2.3.1 Recycled Materials

Provide insulation materials containing the following minimum percentage of recycled material content by weight:

Rock Wool: 75 percent slag of weight
Fiberglass: 20 percent glass cullet
Rigid Foam: 9 percent recovered material
Phenolic Rigid Foam: 9 percent recovered material

Provide data identifying percentage of recycled content for insulation

materials.

2.3.2 Aboveground Cold Pipeline (-30 to 60 deg. F)

Provide insulation for outdoor, indoor, exposed or concealed applications, as follows:

2.3.2.1 Cellular Glass

ASTM C552, Type II, and Type III. Supply the insulation from the fabricator with (paragraph WHITE VAPOR RETARDER ALL SERVICE JACKET (ASJ)) ASJ vapor retarder and installed with all longitudinal overlaps sealed and all circumferential joints ASJ taped or supply the insulation unfaced from the fabricator and install with all longitudinal and circumferential joints sealed with vapor barrier mastic.

2.3.2.2 Flexible Elastomeric Cellular Insulation

Closed-cell, foam- or expanded-rubber materials containing anti-microbial additive, complying with ASTM C534/C534M, Grade 1, Type I or II. Type I, Grade 1 for tubular materials. Type II, Grade 1, for sheet materials. Ensure Type I and II have vapor retarder/vapor barrier skin on one or both sides of the insulation, and require an additional exterior vapor retarder covering for high relative humidity and below ambient temperature applications.

2.3.2.3 Polyisocyanurate Insulation

ASTM C591, Type I. Polyisocyanurate insulation may only be used on systems operating at temperatures not to exceed 140 degrees F. Supply the insulation with a factory applied vapor retarder/barrier that complies with Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS. The insulation and all covering must pass the flame spread index of 25 and the smoke developed index of 50 when tested in accordance with ASTM E84.

2.3.3 Aboveground Hot Pipeline (Above 60 deg. F)

Provide insulation for outdoor, indoor, exposed or concealed applications meeting the following requirements. Supply the insulation with manufacturer's recommended factory-applied jacket/vapor barrier.

2.3.3.1 Mineral Fiber

ASTM C547, Types I, II or III, supply the insulation with manufacturer's recommended factory-applied jacket.

2.3.3.2 Calcium Silicate

ASTM C533, Type I indoor only, or outdoors above 250 degrees F pipe temperature. Supply insulation with the manufacturer's recommended factory-applied jacket/vapor barrier.

2.3.3.3 Cellular Glass

ASTM C552, Type II and Type III. Supply the insulation with manufacturer's recommended factory-applied jacket.

2.3.3.4 Flexible Elastomeric Cellular Insulation

Closed-cell, foam- or expanded-rubber materials containing anti-microbial additive, complying with ASTM C534/C534M, Grade 1, Type I or II to 220 degrees F service. Type I for tubular materials. Type II for sheet materials.

2.3.3.5 Phenolic Insulation

ASTM C1126 Type III to 250 degrees F service must comply with ASTM C795. Supply the insulation with manufacturer's recommended factory-applied jacket/vapor barrier.

2.3.3.6 Perlite Insulation

ASTM C610

2.3.3.7 Polyisocyanurate Insulation

ASTM C591, Type I. Supply the insulation with a factory applied vapor retarder/barrier that complies with Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS. The insulation and all covering must pass the flame spread index of 25 and the smoke developed index of 50 when tested in accordance with ASTM E84.

2.3.4 Aboveground Dual Temperature Pipeline

Select insulation for use over a dual temperature pipeline system (Outdoor, Indoor - Exposed or Concealed) in accordance with the most limiting/restrictive case. Find an allowable material from paragraph PIPE INSULATION MATERIALS and determine the required thickness from the most restrictive case. Use the thickness listed in paragraphs INSULATION THICKNESS for cold & hot pipe applications.

2.3.5 Below-ground Pipeline Insulation

For below-ground pipeline insulation, use cellular glass, ASTM C552, type II.

2.4 DUCT INSULATION SYSTEMS

2.4.1 Factory Applied Insulation

Provide factory-applied ASTM C552, cellular glass thermal ASTM C534/C534M Grade 1, Type II, flexible elastomeric closed cell insulation according to manufacturer's recommendations for insulation with insulation manufacturer's standard reinforced fire-retardant vapor barrier, with identification of installed thermal resistance (R) value and out-of-package R value.

2.4.2 Field Applied Insulation

2.4.2.1 General

Calculate the minimum thickness in accordance with ASHRAE 90.1 - IP.

2.4.3 Rigid Insulation

Mineral-Fiber Board Insulation: Mineral or glass fibers bonded with a

thermosetting resin. Comply with ASTM C612, Type IA or Type IB; 3.0 pcf. Provide insulation with factory applied ASJandfactory-applied FSK jacket. Minimum thickness in accordance with ASHRAE 90.1 - IPTables 3 and 4

2.4.4 Blanket Insulation

Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C553, Type II and ASTM C1290, Type III with factory-applied FSK jacket; 3/4 pcf. Minimum thickness in accordance with ASHRAE 90.1 - IPTables 3 and 4.

2.4.5 Duct Insulation Jackets

2.4.5.1 All-Purpose Jacket

Provide insulation with insulation manufacturer's standard reinforced fire-retardant jacket with or without integral vapor barrier as required by the service. In exposed locations, provide jacket with a white surface.

2.4.5.2 Metal Jackets

2.4.5.2.1 Aluminum Jackets

ASTM B209, Temper H14, minimum thickness of 27 gauge (0.016 inch), with factory-applied polyethylene and kraft paper moisture barrier on inside surface. Provide smooth surface jackets for jacket outside dimension 8 inches and larger. Provide corrugated surface jackets for jacket outside dimension 8 inches and larger. Provide stainless steel bands, minimum width of 1/2 inch.

2.4.5.2.2 Stainless Steel Jackets

ASTM A240/A240M; Type 304, minimum thickness of 33 gauge (0.010 inch), smooth surface with factory-applied polyethylene and kraft paper moisture barrier on inside surface. Provide stainless steel bands, minimum width of 1/2 inch.

2.4.5.3 Vapor Barrier/Weatherproofing Jacket

Provide vapor barrier/weatherproofing jacket that is laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) less than 0.02 permeability, (greater than 3 ply, standard grade, silver, white, black and embossed or greater than 8 ply (minimum 2.9 mils adhesive), heavy duty white or natural).

2.4.6 Weatherproof Duct Insulation

Provide ASTM C552, cellular glass thermal insulation ASTM C534/C534M Grade 1, Type II, flexible elastomeric cellular insulation, and weatherproofing as specified in manufacturer's instruction. Multi-ply, Polymeric Blend Laminate Jacketing: Construction of laminate designed to provide UV resistance, high puncture, tear resistance and an excellent WVT rate.

2.5 EQUIPMENT INSULATION SYSTEMS

Insulate equipment and accessories as specified in Tables 5 and 6. In outside locations, provide insulation 1/2 inch thicker than specified. Increase the specified insulation thickness for equipment where necessary to equal the thickness of angles or other structural members to make a

smooth, exterior surface. Submit a booklet containing manufacturer's published installation instructions for the insulation systems. The instructions must be copyrighted, have an identifying or publication number, and have been published prior to the issuance date of this solicitation. A booklet is also required by paragraphs titled: Pipe Insulation Systems and Duct Insulation Systems.

PART 3 EXECUTION

3.1 APPLICATION - GENERAL

Apply insulation to unheated and uncooled piping and equipment. Do not compress flexible elastomeric cellular insulation at joists, studs, columns, ducts, and hangers. The insulation must not pull apart after a one hour period; replace any insulation found to pull apart after one hour.

3.1.1 Display Samples

Submit and display, after approval of materials, actual sections of installed systems, properly insulated in accordance with the specification requirements. Such actual sections must remain accessible to inspection throughout the job and will be reviewed from time to time for controlling the quality of the work throughout the construction site. Identify each material used by indicating on an attached sheet the specification requirement for the material and the material by each manufacturer intended to meet the requirement. The Contracting Officer will inspect display sample sections at the jobsite. Keep approved display sample sections on display at the jobsite during the construction period. Upon completion of construction, the display sample sections will be closed and sealed.

3.1.1.1 Pipe Insulation Display Sections

Include as a minimum an elbow or tee, a valve, dielectric waterways and flanges, a hanger with protection shield and insulation insert, or dowel as required, at support point, method of fastening and sealing insulation at longitudinal lap, circumferential lap, butt joints at fittings and on pipe runs, and terminating points for each type of pipe insulation used on the job, and for hot pipelines and cold pipelines, both interior and exterior, even when the same type of insulation is used for these services.

3.1.1.2 Duct Insulation Display Sections

Display sample sections for rigid and flexible duct insulation used on the job. Use a temporary covering to enclose and protect display sections for duct insulation exposed to weather

3.1.2 Installation

Except as otherwise specified, install material in accordance with the manufacturer's written instructions. Do not apply insulation materials until tests and heat tracing specified in other paragraphs of this specification are completed. Remove material such as rust, scale, dirt and moisture from surfaces to receive insulation. Keep insulaton clean and dry. Do not remove insulation from its shipping containers until the day it is ready to use and return to like containers or equally protect from dirt and moisture at the end of each workday. Thoroughly clean insulation that becomes dirty prior to use. If insulation becomes wet or if cleaning does not restore the surfaces to like new condition, reject

the insulation, and immediately remove from the jobsite. Stagger joints on multi layer insulation. Mix mineral fiber thermal insulating cement with demineralized water when used on stainless steel surfaces. Install insulation, jacketing and accessories in accordance with MICA Insulation Stds plates except where modified herein or on the drawings.

3.1.3 Firestopping

Where pipes and ducts pass through fire walls, fire partitions, above grade floors, and fire rated chase walls, seal the penetration with fire stopping materials as specified in Section 07 84 00 FIRESTOPPING. The protection of ducts at point of passage through firewalls must be in accordance with NFPA 90A and NFPA 90B. All other penetrations, such as piping, conduit, and wiring, through firewalls must be protected with a material or system of the same hourly rating that is listed by UL, FM, or a NRTL.

3.1.4 Installation of Flexible Elastomeric Cellular Insulation

Install flexible elastomeric cellular insulation with seams and joints sealed with rubberized contact adhesive. Do not use flexible elastomeric cellular insulation on surfaces greater than 220 degrees F. Stagger seams when applying multiple layers of insulation. Protect insulation exposed to weather with metal jacketing as recommended by the manufacturer after the adhesive is dry and cured.

3.1.4.1 Adhesive Application

Apply a brush coating of adhesive to both butt ends to be joined and to both slit surfaces to be sealed. Allow the adhesive to set until dry to touch but tacky under slight pressure before joining the surfaces. Ensure insulation seals at seams and joints are not capable of being pulled apart one hour after application. Replace insulation that can be pulled apart one hour after installation.

3.1.4.2 Adhesive Safety Precautions

Use natural cross-ventilation, local (mechanical) pickup, or general area (mechanical) ventilation to prevent an accumulation of solvent vapors, keeping in mind the ventilation pattern must remove any heavier-than-air solvent vapors from lower levels of the workspaces. Gloves and spectacle-type safety glasses are recommended in accordance with safe installation practices.

3.1.5 Welding

Welding is not permitted on piping, duct or equipment without written approval of the Contracting Officer. The capacitor discharge welding process may be used for securing metal fasteners to duct.

3.1.6 Pipes/Ducts/Equipment That Require Insulation

Insulation is required on all pipes, ducts, or equipment, except for omitted items as specified.

3.2 PIPE INSULATION SYSTEMS INSTALLATION

3.2.1 Pipe Insulation

3.2.1.1 General

Install pipe insulation on aboveground hot and cold pipeline systems as specified below to form a continuous thermal retarder/barrier, including straight runs, fittings and appurtenances unless specified otherwise. Install full length units of insulation using a single cut piece to complete a run. Do not use cut pieces or scraps abutting each other. Omit pipe insulation on the following:

a. Air chambers.

b. Adjacent insulation.

c. ASME stamps.

d. Access plates of fan housings.

3.2.1.2 Pipes Passing Through Walls, Roofs, and Floors

Provide continuous pipe insulation through the sleeve.

Provide an aluminum jacket or vapor barrier/weatherproofing self adhesive jacket (minimum 2 mils adhesive, 3 mils embossed) less than 0.0000 permeability, greater than 3 ply standard grade, silver, white, black and embossed with factory applied moisture retarder over the insulation wherever penetrations require sealing.

3.2.1.2.1 Penetrate Interior Walls

Provide aluminum jacket or vapor barrier/weatherproofing - self adhesive jacket (minimum 2 mils adhesive, 3 mils embossed) less than 0.02 permeability, greater than 3 plies standard grade, silver, white, black and embossed which extends 2 inches beyond either side of the wall and secure on each end with a band.

3.2.1.2.2 Penetrating Floors

Extend the aluminum jacket from a point below the backup material to a point 10 inches above the floor with one band at the floor and one not more than 1 inch from the end of the aluminum jacket.

3.2.1.2.3 Penetrating Waterproofed Floors

Extend the aluminum jacket from below the backup material to a point 2 inches above the flashing with a band 1 inch from the end of the aluminum jacket.

3.2.1.2.4 Penetrating Exterior Walls

Continue the aluminum jacket required for pipe exposed to weather through the sleeve to a point 2 inches beyond the interior surface of the wall.

3.2.1.2.5 Penetrating Roofs

Insulate pipe as required for interior service to a point flush with the top of the flashing and sealed with flashing sealant. Tightly butt the insulation for exterior application to the top of flashing and interior insulation. Extend the exterior aluminum jacket 2 inches down beyond the end of the insulation to form a counter flashing. Seal the flashing and counter flashing underneath with metal jacketing/flashing sealant.

3.2.1.2.6 Hot Water Pipes Supplying Lavatories or Other Similar Heated Service

Terminate the insulation on the backside of the finished wall. Protect the insulation termination with two coats of vapor barrier coating with a minimum total thickness of 1/16 inch applied with glass tape embedded between coats (if applicable). Extend the coating out onto the insulation 2 inches and seal the end of the insulation. Overlap glass tape seams 1 inch. Caulk the annular space between the pipe and wall penetration with approved fire stop material. Cover the pipe and wall penetration with a properly sized (well fitting) escutcheon plate. Ensure the escutcheon plate overlaps the wall penetration at least 3/8 inches.

3.2.1.2.7 Domestic Cold Water Pipes Supplying Lavatories or Other Similar Cooling Service

Terminate the insulation on the finished side of the wall (i.e., insulation must cover the pipe throughout the wall penetration). Protect the insulation with two coats of weather barrier mastic (breather emulsion type weatherproof mastic impermeable to water and permeable to air) with a minimum total thickness of 1/16 inch. Extend the mastic out onto the insulation 2 inches and seal the end of the insulation. Caulk the annular space between the outer surface of the pipe insulation and the wall penetration with an approved fire stop material having vapor retarder properties. Cover the pipe and wall penetration with a properly sized (well fitting) escutcheon plate. Ensure the escutcheon plate overlaps the wall penetration by at least 3/8 inches.

3.2.1.3 Pipes Passing Through Hangers

Ensure insulation, whether hot or cold application, is continuous through hangers. Support all horizontal pipes 2 inches and smaller on hangers with the addition of a Type 40 protection shield to protect the insulation in accordance with MSS SP-58. Whenever insulation shows signs of being compressed, or when the insulation or jacket shows visible signs of distortion at or near the support shield, install insulation inserts as specified below for piping larger than 2 inches, or factory insulated hangers (designed with a load bearing core) can be used.

3.2.1.3.1 Horizontal Pipes Larger Than 2 Inches at 60 Degrees F and Above

Supported on hangers in accordance with MSS SP-58, and Section 22 00 00 PLUMBING, GENERAL PURPOSE.

3.2.1.3.2 Horizontal Pipes Larger Than 2 Inches and Below 60 Degrees F

Supported on hangers with the addition of a Type 40 protection shield in accordance with MSS SP-58. Install an insulation insert of cellular glass, prefabricated insulation pipe hangers, or perlite above 80 degrees F above each shield. Ensure insert covers no less than the bottom

180-degree arc of the pipe. Provide inserts that are the same thickness as the insulation, and extend 2 inches on each end beyond the protection shield. When insulation inserts are required in accordance with the above, and the insulation thickness is less than 1 inch, wooden or cork dowels or blocks may be installed between the pipe and the shield to prevent the weight of the pipe from crushing the insulation, as an option to installing insulation inserts. Ensure the insulation jacket is continuous over the wooden dowel, wooden block, or insulation insert.

3.2.1.3.3 Vertical Pipes

Supported with either Type 8 or Type 42 riser clamps with the addition of two Type 40 protection shields in accordance with MSS SP-58 covering the 360-degree arc of the insulation. Install an insulation insert of cellular glass or calcium silicate between each shield and the pipe. Ensure the insert covers the 360-degree arc of the pipe. Provide inserts that are the same thickness as the insulation, and extend 2 inches on each end beyond the protection shield. When insulation inserts are required in accordance with the above, and the insulation thickness is less than 1 inch, wooden or cork dowels or blocks may be installed between the pipe and the shield to prevent the hanger from crushing the insulation, as an option instead of installing insulation inserts. Ensure the insulation jacket is continuous over the wooden dowel, wooden block, or insulation insert. Support the vertical weight of the pipe with hangers located in a horizontal section of the pipe. When the pipe riser is longer than 30 feet, support the weight of the pipe additionally with hangers in the vertical run of the pipe that are directly clamped to the pipe, penetrating the pipe insulation. Use insulated hangers and seal the insulation jacket as indicated herein for anchors in a similar service.

3.2.1.3.4 Inserts

Covered with a jacket material of the same appearance and quality as the adjoining pipe insulation jacket, overlap the adjoining pipe jacket 1-1/2 inches, and seal as required for the pipe jacket. Use jacket material to cover inserts in flexible elastomeric cellular insulation conforming to ASTM C1136, Type 1, and is allowed to be of a different material than the adjoining insulation material.

3.2.1.4 Flexible Elastomeric Cellular Pipe Insulation

Flexible elastomeric cellular pipe insulation shall be permissible on a case by case basis for chilled water piping and domestic cold water piping. Use tubular form flexible elastomeric cellular pipe insulation for pipe sizes 6 inches and less. Grade 1, Do not stretch Type II sheet insulation used on pipes larger than 6 inches around the pipe. On pipes larger than 12 inches, adhere the insulation directly to the pipe on the lower 1/3 of the pipe. Stagger seams when applying multiple layers of insulation. Insulate sweat fittings with miter-cut pieces the same size as on adjacent piping. Insulate screwed fittings with sleeved fitting covers fabricated from miter-cut pieces and overlap and seal to the adjacent pipe insulation. Type II requires an additional exterior vapor retarder/barrier covering for high relative humidity and below ambient temperature applications.

3.2.1.5 Pipes in High Abuse Areas

In high abuse areas such as janitor closets and traffic areas in equipment rooms, kitchens, and mechanical rooms, utilize welded PVC , aluminum or

flexible laminate cladding (comprised of elastomeric, plastic or metal foil laminate) laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) vapor barrier/weatherproofing jacket, - less than 0.02 permeability; (greater than 3 ply, standard grade, silver, white, black and embossed) aluminum jackets. Protect pipe insulation to the 6 foot level.

3.2.1.6 Pipe Insulation Material and Thickness

Pipe insulation materials must be as listed in Table 1 and must meet or exceed the requirements of ASHRAE 90.1 - IP. All refrigerant piping must be insulated in accordance with Section 23 23 00 REFRIGERANT PIPING. Insulate these refrigerant lines according to the temperature of the pipe contents while the Variable Refrigerant Flow (VRF) system is fully operating following the temperature parameters as stated in Table 1 and Table 2 of this specification.

TABLE 1

Insulation Material for Piping

Service					
	Material	Specification	Type	Class	VR/VB Req'd
Chilled Water (Supply & Return Piping, 40 F nominal)					
	Flexible Elastomeric Cellular	ASTM C534/C534M	I		Yes
	Polyisocyanurate	ASTM C591	I	2	Yes
Heating Hot Water Supply & Return, Heated Oil (Max 250 F)					
	Mineral Fiber	ASTM C547	I	1	No
	Calcium Silicate	ASTM C533	I		No
	Cellular Glass	ASTM C552	II	2	No
	Flexible Elastomeric Cellular	ASTM C534/C534M	I	2	No
	Polyisocyanurate Max temp	ASTM C591	I	2	Yes
Cold Domestic Water Piping, Makeup Water, and Condenser Water Piping					
	Cellular Glass	ASTM C552	II	2	No
	Flexible Elastomeric Cellular	ASTM C534/C534M	I		No
Hot Domestic Water Supply & Recirculating Piping (Max 200 F)					
	Mineral Fiber	ASTM C547	I	1	No
	Cellular Glass	ASTM C552	II	2	No
	Flexible Elastomeric Cellular	ASTM C534/C534M	I		No
	Faced Phenolic Foam	ASTM C1126	III		Yes
Refrigerant Suction Piping (35 degrees F nominal)					

TABLE 1

Insulation Material for Piping

Service					
	Material	Specification	Type	Class	VR/VB Req'd
	Flexible Elastomeric Cellular	ASTM C534/C534M	I		No
	Cellular Glass	ASTM C552	II	1	Yes
Exposed Lavatory Drains, Exposed Domestic Water Piping & Drains to Areas for Handicapped Personnel					
	Flexible Elastomeric Cellular	ASTM C534/C534M	I		No
Condensate Drain Located Inside Building					
	Cellular Glass	ASTM C552	II	2	No
	Flexible Elastomeric Cellular	ASTM C534/C534M	I		No

Note: VR/VB = Vapor Retarder/Vapor Barrier. For Chilled Water piping and Domestic Cold Water piping, Flexible Elastomeric insulation is only permissible when rigid insulation is not practical and must be verified by Base Engineering Technician.

TABLE 2

Piping Insulation Thickness (inch)

Service							
	Material	Conductivity K-value (Btu-in/ hr-ft^2-deg F)	Tube And Pipe Size (inch)				
			<1	1-<1.5	1.5-<4	4-<8	> or = >8
Chilled Water (Supply & Return, Dual Temperature Piping, 40 Degrees F nominal)							
	Polyisocyanurate	0.18	0.5	1	1	1	1.5
Heating Hot Water Supply & Return, Heated Oil (Max 250 F)							
	Mineral Fiber	0.27	2.5	2.5	2.5	3	3

TABLE 2

Piping Insulation Thickness (inch)

Service							
	Material	Conductivity K-value (Btu-in/ hr-ft^2-deg F)	Tube And Pipe Size (inch)				
			<1	1-<1.5	1.5-<4	4-<8	> or = >8
	Calcium Silicate	0.37	4	4	4	4	4
	Cellular Glass		3.5	3.5	3.5	4	4
	Faced Phenolic Foam	0.24	2.5	2.5	2.5	3	3
	Polyisocyanurate Max temp 140F	0.23	1	1	1.5	1.5	1.5
Cold Domestic Water Piping, Makeup Water, and Condenser Water							
	Cellular Glass	0.30	1.5	1.5	1.5	1.5	1.5
	Flexible Elastomeric Cellular	0.235	1	1	1	N/A	N/A
Hot Domestic Water Supply & Recirculating Piping (Max 200 F)							
	Mineral Fiber	0.26	1.5	1.5	2	2	2
Refrigerant Suction Piping (35 degrees F nominal)							
	Flexible Elastomeric Cellular	0.235	1	1	1	N/A	N/A
	Cellular Glass	0.29	1.5	1.5	1.5	1.5	1.5
Compressed Air Discharge, Steam and Condensate Return (201 to 250 Degrees F							
	Mineral Fiber	0.27	2.5	2.5	2.5	3	3
	Calcium Silicate	0.37	2.5	3	4	4	4.5

TABLE 2

Piping Insulation Thickness (inch)

Service	Material	Conductivity K-value (Btu-in/ hr-ft^2-deg F)	Tube And Pipe Size (inch)				
			<1	1-<1.5	1.5-<4	4-<8	> or = >8
	Cellular Glass	0.35	2	2.5	3	3	3
Exposed Lavatory Drains, Exposed Domestic Water Piping & Drains to Areas for Handicapped Personnel							
	Flexible Elastomeric Cellular		0.5	0.5	0.5	0.5	0.5
Condensate Drain Located Inside Building							
	Cellular Glass	0.30	1.5	1.5	1.5	1.5	1.5
	Flexible Elastomeric Cellular	0.235	1	1	1	N/A	N/A

3.2.2 Aboveground Cold Pipelines

Insulate the following cold pipelines for minus 30 to plus 60 degrees F in accordance with Table 2 except those piping listed in subparagraph Pipe Insulation in PART 3 as to be omitted. This includes but is not limited to the following:

a. Make-up water.

b. Horizontal and vertical portions of interior roof drains.

c. Refrigerant suction lines.

d. Chilled water.

e. Dual temperature water, i.e. HVAC hot/chilled water.

f. Air conditioner condensate drains.

g. Brine system cryogenics.

h. Condenser water piping where pipe temperature may fall below ambient dew point.

i. Exposed lavatory drains and domestic water lines serving plumbing fixtures for handicap persons.

j. Domestic cold and chilled drinking water.

3.2.2.1 Insulation Material and Thickness

Determine insulation thickness for cold pipelines using Table 2.

3.2.2.2 Factory or Field applied Jacket

Cover insulation with a factory applied vapor retarder jacket/vapor barrier or field applied seal welded PVC jacket or greater than 3 ply laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) vapor barrier/weatherproofing jacket - less than 0.02 permeability, standard grade, sliver, white, black and embossed for use with Mineral Fiber, Cellular Glass, and Phenolic Foam Insulated Pipe. For insulation inside the building, to be protected with an aluminum jacket, PVC jacket or fittings (installed over a vapor retarder jacket), or greater than 3 ply vapor barrier/weatherproofing self-adhesive (minimum 2 mils adhesive, 3 mils embossed) product, less than 0.02 permeability, standard grade, Embossed Silver, White & Black, install the insulation and vapor retarder jacket as specified herein. Install the aluminum jacket, PVC jacket or fittings (installed over a vapor retarder jacket), or greater than 3 ply vapor barrier/weatherproofing self-adhesive (minimum 2 mils adhesive, 3 mils embossed) product, less than 0.02 permeability, standard grade, embossed silver, White & Black, as specified for piping exposed to weather, except sealing of the laps of the aluminum jacket is not required. In high abuse areas such as janitor closets and traffic areas in equipment rooms, kitchens, and mechanical rooms, provide aluminum jackets, PVC jacket or fittings (installed over a vapor retarder jacket), or greater than 3 ply vapor barrier/weatherproofing self-adhesive (minimum 2 mils adhesive, 3 mils embossed) product, less than 0.02 permeability, standard grade, embossed silver, white & black, for pipe insulation to the 6 ft level.

3.2.2.3 Installing Insulation for Straight Runs Hot and Cold Pipe

Apply insulation to the pipe with tight butt joints. Seal all butted joints and ends with joint sealant and seal with a vapor retarder coating, greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape or PVDC adhesive tape.

3.2.2.3.1 Longitudinal Laps of the Jacket Material

Overlap not less than 1-1/2 inches. Provide butt strips 3 inches wide for circumferential joints.

3.2.2.3.2 Laps and Butt Strips

Secure with adhesive and staple on 4 inch centers if not factory self-sealing. If staples are used, seal in accordance with paragraph STAPLES below. Note that staples are not required with cellular glass systems.

3.2.2.3.3 Factory Self-Sealing Lap Systems

May be used when the ambient temperature is between 40 and 120 degrees F during installation. Install the lap system in accordance with manufacturer's recommendations. Use a stapler only if specifically recommended by the manufacturer. Where gaps occur, replace the section or repair the gap by applying adhesive under the lap and then stapling.

3.2.2.3.4 Staples

Coat all staples, including those used to repair factory self-seal lap systems, with a vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - 0.0000 perm adhesive tape. Coat all seams, except those on factory self-seal systems, with vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape.

3.2.2.3.5 Breaks and Punctures in the Jacket Material

Patch by wrapping a strip of jacket material around the pipe and secure it with adhesive, staple, and coat with vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape. Extend the patch not less than 1-1/2 inches past the break.

3.2.2.3.6 Penetrations Such as Thermometers

Fill the voids in the insulation and seal with vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape.

3.2.2.3.7 Flexible Elastomeric Cellular Pipe Insulation

Install by slitting the tubular sections and applying them onto the piping or tubing. Alternately, whenever possible slide un-slit sections over the open ends of piping or tubing. Secure all seams and butt joints and seal with adhesive. When using self seal products, secure only the butt joints with adhesive. Push insulation on the pipe, never pulled. Stretching of insulation may result in open seams and joints. Clean cut all edges. Rough or jagged edges of the insulation are not be permitted. Use proper tools such as sharp knives. Do not stretch Grade 1, Type II sheet insulation around the pipe when used on pipe larger than 6 inches. On pipes larger than 12 inches, adhere sheet insulation directly to the pipe on the lower 1/3 of the pipe.

3.2.2.4 Insulation for Fittings and Accessories

a. Butt pipe insulation tightly to the insulation of the fittings and accessories. Seal the butted joints and ends with joint sealant and seal with a vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape.

b. Place precut or preformed insulation around all fittings and accessories and conform to MICA plates except as modified herein: 5 for anchors; 10, 11, and 13 for fittings; 14 for valves; and 17 for flanges and unions. Insulation must be the same insulation as the pipe insulation, including same density, thickness, and thermal conductivity. Where precut/preformed is unavailable, rigid preformed pipe insulation sections may be segmented into the shape required.

Use insulation of the same thickness and conductivity as the adjoining pipe insulation. If nesting size insulation is used, overlap the insulation 2 inches or one pipe diameter. Elbows insulated using segments must conform to MICA Tables 12.20 "Mitered Insulation Elbow'. Submit a booklet containing completed MICA Insulation Stds plates detailing each insulating system for each pipe, duct, or equipment insulating system, after approval of materials and prior to applying insulation.

(1) Ensure MICA plates detail the materials to be installed and the specific insulation application. Submit all MICA plates required showing the entire insulating system, including plates required to show insulation penetrations, vessel bottom and top heads, legs, and skirt insulation as applicable. Present all variations of insulation systems including locations, materials, vaporproofing, jackets and insulation accessories.

(2) If the Contractor elects to submit detailed drawings instead of edited MICA Plates, ensure the detail drawings are technically equivalent to the edited MICA Plate submittal.

c. Upon completion of insulation installation on flanges, unions, valves, anchors, fittings and accessories, terminations, seams, joints and insulation not protected by factory vapor retarder jackets or PVC fitting covers must be protected with PVDC or greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape or two coats of vapor retarder coating with a minimum total thickness of 1/16 inch, applied with glass tape embedded between coats. Overlap tap seams 1 inch. Extend the coating out onto the adjoining pipe insulation 2 inches. Protect fabricated insulation with a factory vapor retarder jacket with either greater than 3 ply laminate jacket - less than 0.0000 perm adhesive tape, standard grade, silver, white, black and embossed or PVDC adhesive tape or two coats of vapor retarder coating with a minimum thickness of 1/16 inch and with a 2 inch wide glass tape embedded between coats. Where fitting insulation butts to pipe insulation, seal the joints with a vapor retarder coating and a 4 inch wide ASJ tape which matches the jacket of the pipe insulation.

d. Insulate anchors attached directly to the pipe for a sufficient distance to prevent condensation but no less than 6 inches from the insulation surface.

e. Mark insulation to show the location of unions, strainers, and check valves.

3.2.2.5 Optional PVC Fitting Covers

At the option of the Contractor, premolded, one or two piece PVC fitting covers may be used in lieu of the vapor retarder and embedded glass tape. Factory precut insulation inserts or premolded insulation segments must be used under the fitting covers for elbows, tees and other miscellaneous configurations. Insulation inserts must be the same installed insulation thickness. One insert must be installed for each inch of pipe insulation. The installed and compressed insert must have the same thermal performance as the pipe insulation. Premolded insulation segments must be the same insulation as the pipe insulation including same density, thickness, and thermal conductivity. PVC fitting covers must be secured by PVC vapor retarder tape, adhesive, seal welding or with tacks made for securing PVC covers. For above ambient pipe temperatures, secure PVC

covers using tacks. As an option circumferential joints can be covered with PVC vapor retarder tape. For below ambient conditions seal system using PVC vapor retarder tape, and vapor retarder mastic with vapor dams. Longitudinal seams may be sealed with vapor retarder mastic, PVC vapor retarder tape or solvent weld adhesive to obtain a continuous vapor seal. For severe service conditions install PVC jackets over the existing ASJ jacket and seal using a solvent weld adhesive.

3.2.3 Aboveground Hot Pipelines

3.2.3.1 General Requirements

Insulate all hot pipe lines above 60 degrees F, except those piping listed in subparagraph Pipe Insulation in PART 3 as to be omitted, in accordance with Table 2. This includes but is not limited to the following:

a. Domestic hot water supply & re-circulating system.

b. Steam.

c. Condensate & compressed air discharge.

d. Hot water heating.

e. Heated oil.

f. Water defrost lines in refrigerated rooms.

Cover insulation, in accordance with manufacturer's recommendations, with a factory applied Type I jacket or field applied aluminum where required or seal welded PVC.

3.2.3.2 Insulation for Fittings and Accessories

Butt pipe insulation tightly to the insulation of the fittings and accessories. Seal butted joints and ends with joint sealant. Mark insulation to show the location of unions, strainers, check valves and other components that would otherwise be hidden from view by the insulation.

3.2.3.2.1 Precut or Preformed

Place precut insulation inserts or preformed insulation inserts around all fittings and accessories. Insulation inserts must be the same installed insulation thickness as the pipe insulation. One insert must be installed for each inch of pipe insulation thickness. The installed and compressed insert must have the same thermal performance as the pipe insulation. Preformed insulation inserts must be the same insulation as the pipe insulation including same density, thickness, and thermal conductivity.

3.2.3.2.2 Rigid Preformed

Where precut/preformed is unavailable, rigid preformed pipe insulation sections may be segmented into the shape required. Use insulation that is the same thickness and conductivity as the adjoining pipe insulation. If nesting size insulation is used, do not overlap insulation 2 inches or one pipe diameter. Elbows insulated using segments must conform to MICA Tables 12.20 "Mitered Insulation Elbow".

3.2.4 Piping Exposed to Weather

Insulate and jacket piping exposed to weather as specified for the applicable service inside the building. After this procedure, apply a laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) vapor barrier/weatherproofing jacket - less than 0.02 permeability (greater than 3 ply, standard grade, silver, white, black and embossed aluminum jacket, stainless steel or PVC jacket.

PVC jacketing requires no factory-applied jacket beneath it, however apply an all service jacket if factory applied jacketing is not furnished.

3.2.4.1 Aluminum Jacket

Provide chilled water piping exposed to weather with aluminum insulation jacket with SS draw bands. The jacket for hot piping may be factory applied. Overlap the jacket no less than 2 inches at longitudinal and circumferential joints and secure with bands at no more than 12 inch centers. Overlap longitudinal joints down to shed water and locate at 4 or 8 o'clock positions. Seal joints on piping 60 degrees F and below with metal jacketing/flashing sealant while overlapping to prevent moisture penetration. Where jacketing on piping 60 degrees F and below abuts an un-insulated surface, caulk joints to prevent moisture penetration. Seal joints on piping above 60 degrees F with a moisture retarder.

3.2.4.2 Insulation for Fittings

Insulate and finish flanges, unions, valves, fittings, and accessories as specified for the applicable service. Apply two coats of breather emulsion type weatherproof mastic (impermeable to water, permeable to air) recommended by the insulation manufacturer with glass tape embedded between coats. Overlap tap no less than 1 inch and the adjoining aluminum jacket no less than 2 inches. Factory preformed aluminum jackets may be used in lieu of the above. Provide molded PVC fitting covers when PVC jackets are used for straight runs of pipe.PVC fitting covers must be sealed based upon the pipe temperature in combination with ambient conditions and if the pipe insulation will be exposed to severe service conditions. For below ambient conditions, the pipe insulation and insulation fittings must be covered and sealed with a vapor barrier or weatherproofing jacket with a minimum 0.02 permeability as defined per ASTM C1136 before installing the PVC jacket and fitting cover. When in doubt as to the pipe temperature or service conditions, secure the PVC jacket using a weld adhesive using the manufacturer's recommended adhesive.

3.2.4.3 PVC Jacket

Provide ultraviolet resistant PVC jacket that is adhesive welded weather tight with manufacturer's recommended adhesive. Include provision for thermal expansion.

3.2.4.4 Stainless Steel Jackets

ASTM A240/A240M; Type 304, minimum thickness of 33 gauge (0.010 inch), smooth surface with factory-applied polyethylene and kraft paper moisture barrier on inside surface. Provide stainless steel bands, minimum width of 1/2 inch.

3.3 DUCT INSULATION SYSTEMS INSTALLATION

Except for oven hood exhaust duct insulation, install corner angles on external corners of insulation on ductwork in exposed finished spaces before covering with jacket. Air conditioned spaces are defined as those spaces directly supplied with cooled conditioned air (or provided with a cooling device such as a fan-coil unit) and heated conditioned air (or provided with a heating device such as a unit heater, radiator or convector).

3.3.1 Duct Insulation Minimum Thickness

Duct insulation minimum thickness in accordance with Table 4.

Table 4 - Minimum Duct Insulation (inches)

Cold Air Ducts	2.0
Relief Ducts	2.0
Fresh Air Intake Ducts	2.0
Warm Air Ducts	2.0
Relief Ducts	2.0
Fresh Air Intake Ducts	2.0

3.3.2 Insulation and Vapor Retarder/Vapor Barrier for Cold Air Duct

Provide insulation and vapor retarder/vapor barrier for the following cold air ducts and associated equipment.

a. Supply ducts.

b. Return air ducts.

c. Relief ducts.

d. Flexible run-outs (field-insulated).

e. Plenums.

f. Duct-mounted coil casings.

g. Coil headers and return bends.

h. Coil casings.

i. Fresh air intake ducts.

j. Filter boxes.

k. Mixing boxes (field-insulated).

l. Supply fans (field-insulated).

m. Site-erected air conditioner casings.

n. Ducts exposed to weather.

o. Combustion air intake ducts.

p. Exhaust ducts passing through concealed spaces, unconditioned spaces, or semi-heated spaces exhausting conditioned air.

Use insulation for rectangular ducts that is flexible type where concealed, minimum density 3/4 pcf, and rigid type where exposed, minimum density 3 pcf. Provide insulation for both concealed or exposed round/oval ducts that is flexible type, minimum density 3/4 pcf or a semi rigid board, minimum density 3 pcf, formed or fabricated to a tight fit, edges beveled and joints tightly butted and staggered. Provide insulation for all exposed ducts with either a white, paint-able, factory-applied Type I jacket or a field applied vapor retarder/vapor barrier jacket coating finish as specified. Ensure the total field applied dry film thickness is approximately 1/16 inch. Provide insulation on all concealed duct with a factory-applied Type I or II vapor retarder/vapor barrier jacket. Continue duct insulation through sleeves and prepare openings except firewall penetrations. Duct insulation terminating at fire dampers, must be continuous over the damper collar and retaining angle of fire dampers, which are exposed to unconditioned air and which may be prone to condensate formation. Provide duct insulation and vapor retarder/vapor barrier to cover the collar, neck, and un-insulated surfaces of diffusers, registers and grills. Apply vapor retarder/vapor barrier materials to form a complete unbroken vapor seal over the insulation. Seal sheet metal duct in accordance with Section 23 30 00 HVAC AIR DISTRIBUTION.

3.3.2.1 Installation on Concealed Duct

a. For rectangular, oval or round ducts, attach flexible insulation by applying adhesive around the entire perimeter of the duct in 6 inch wide strips on 12 inch centers.

b. For rectangular and oval ducts, 24 inches and larger, additionally secure insulation to bottom of ducts using mechanical fasteners. Space fasteners on 16 inch centers and no more than 16 inches from duct corners.

c. For rectangular, oval and round ducts, provide mechanical fasteners on sides of duct risers for all duct sizes. Space fasteners on 16 inch centers and no more than 16 inches from duct corners.

d. Impale insulation on the mechanical fasteners (self stick pins) where used and press thoroughly into the adhesive. Take care to ensure vapor retarder/vapor barrier jacket joints overlap 2 inches. Do not compress insulation to a thickness less than that specified. Carry insulation over standing seams and trapeze-type duct hangers.

e. Where mechanical fasteners are used, install self-locking washers and trim and bend the pin over.

f. Secure jacket overlaps with staples and tape as necessary to ensure a secure seal. Coat staples, tape and seams with a brush coat of vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate

(minimum 2 mils adhesive, 3 mils embossed) - less than 0.0000 perm adhesive tape.

g. Cover breaks in the jacket material with patches of the same material as the vapor retarder jacket. Do not extend patches less than 2 inches beyond the break or penetration in all directions and secure with tape and staples. Seal staples and tape joints with a brush coat of vapor retarder coating or PVDC adhesive tape or greater than 3 ply laminate (minimum 2 mils adhesive, 3 mils embossed) - less than 0.0000 perm adhesive tape.

h. At jacket penetrations such as hangers, thermometers, and damper operating rods, fill voids in the insulation and seal the penetration with a brush coat of vapor retarder coating or PVDC adhesive tape greater than 3 ply laminate (minimum 2 mils adhesive, 3 mils embossed) - less than 0.0000 perm adhesive tape.

i. Seal insulation terminations and pin punctures and flash with a reinforced vapor retarder coating finish or tape with a brush coat of vapor retarder coating.. Ensure the coating overlaps the adjoining insulation and un-insulated surface 2 inches. Extend pin puncture coatings 2 inches from the puncture in all directions.

j. Where insulation standoff brackets occur, extend insulation under the bracket and terminate the jacket at the bracket.

3.3.2.2 Installation on Exposed Duct Work

a. For rectangular ducts, secure rigid insulation to the duct by mechanical fasteners on all four sides of the duct, space no more than 12 inches apart and no more than 3 inches from the edges of the insulation joints. Provide a minimum of two rows of fasteners for each side of duct 12 inches and larger. Provide one row for each side of duct less than 12 inches. Provide mechanical fasteners that are corrosion resistant as G60 coated galvanized steel, and indefinitely sustain a 50 lb tensile dead load test perpendicular to the duct wall.

b. Form duct insulation with minimum jacket seams. Fasten each piece of rigid insulation to the duct using mechanical fasteners. When the height of projections is less than the insulation thickness, bring insulation up to standing seams, reinforcing, and other vertical projections and do not carry over. Continue vapor retarder/barrier jacket across seams, reinforcing, and projections. When height of projections is greater than the insulation thickness, carry over insulation and jacket . Apply insulation with joints tightly butted. Neatly bevel insulation around name plates and access plates and doors.

c. Impale insulation on the fasteners; install self-locking washers and trim and bend the pin over.

d. Seal joints in the insulation jacket with a 4 inch wide strip of tape. Seal taped seams with a brush coat of vapor retarder coating.

e. Cover breaks and ribs or standing seam penetrations in the jacket material with a patch of the same material as the jacket. Do not extend patches less than 2 inches beyond the break or penetration and secure with tape and staple. Seal staples and joints with a brush coat of vapor retarder coating.

f. At jacket penetrations such as hangers, thermometers, and damper operating rods, fill the voids in the insulation and seal the penetrations with a flashing sealant.

g. Seal and flash insulation terminations and pin punctures with a reinforced vapor retarder coating finish. Ensure coating overlaps the adjoining insulation and un-insulated surface 2 inches. Extend pin puncture coatings 2 inches from the puncture in all directions.

h. Insulation for both concealed or exposed round or oval ducts must be flexible type, minimum density 3/4 pcf or a semi rigid board, minimum density 3 pcf, formed or fabricated to a tight fit, edges beveled and joints tightly butted and staggered. Insulation for all exposed ducts must be provided with either a white, factory-applied Type I jacket or a field applied vapor retarder or vapor barrier jacket coating finish as specified, the total field applied dry film thickness must be approximately 1/16 inch.

i. Insulate oval and round ducts, flexible type, with factory Type I jacket insulation with minimum density of 3/4 pcf, attach in accordance with MICA standards.

3.3.3 Insulation for Warm Air Duct

Provide insulation and vapor barrier for the following warm air ducts and associated equipment:.

a. Supply ducts.

b. Return air ducts.

c. Relief air ducts

d. Flexible run-outs (field insulated).

e. Plenums.

f. Duct-mounted coil casings.

g. Coil-headers and return bends.

h. Coil casings.

i. Fresh air intake ducts.

j. Filter boxes.

k. Mixing boxes.

l. Supply fans.

m. Site-erected air conditioner casings.

n. Ducts exposed to weather.

o. Exhaust ducts passing through concealed spaces, unconditioned spaces, or semi-heated spaces exhausting conditioned air.

Provide insulation for rectangular ducts that is flexible type where

concealed, and rigid type where exposed. Provide insulation on exposed ducts with a white, paint-able, factory-applied Type II jacket, or finish with adhesive finish. Use flexible type insulation for round ducts, with a factory-applied Type II jacket. Provide insulation on concealed duct with a factory-applied Type II jacket. Accomplish adhesive finish where indicated to be used by applying two coats of adhesive with a layer of glass cloth embedded between the coats. Ensure total dry film thickness is approximately 1/16 inch. Continue duct insulation through sleeves and prepare openings. Terminate duct insulation at fire dampers and flexible connections.

3.3.3.1 Installation on Concealed Duct

a. For rectangular, oval and round ducts, attach insulation by applying adhesive around the entire perimeter of the duct in 6 inch wide strips on 12 inch centers.

b. For rectangular and oval ducts 24 inches and larger, secure insulation to the bottom of ducts using mechanical fasteners. Space fasteners on 18 inch centers and no more than 18 inches from duct corner.

c. For rectangular, oval and round ducts, provide mechanical fasteners on sides of duct risers for all duct sizes. Space fasteners on 18 inch centers and no more than 18 inches from duct corners.

d. Impale insulation on the mechanical fasteners where used. Do not compress insulation to a thickness less than that specified. Carry insulation over standing seams and trapeze-type hangers.

e. Install self-locking washers where mechanical fasteners are used and trim and bend the pin over.

f. Do not overlap insulatio jacket less than 2 inches at joints and secure the lap and staple on 4 inch centers.

3.3.3.2 Installation on Exposed Duct

a. For rectangular ducts, secure the rigid insulation to the duct using mechanical fasteners on all four sides of the duct, space no more than 16 inches apart and no more than 6 inches from the edges of the insulation joints. Provide a minimum of two rows of fasteners for each side of duct 12 inches and larger and a minimum of one row for each side of duct less than 12 inches.

b. Form duct insulation with factory-applied jacket with minimum jacket seams, and fasten each piece of rigid insulation to the duct using mechanical fasteners. When the height of projection is less than the insulation thickness, bring insulation up to standing seams, reinforcing, and other vertical projections and do not carry over the projection. Continue jacket across seams, reinforcing, and projections. Where the height of projections is greater than the insulation thickness, carry insulation and jacket over the projection.

c. Impale insulation on the fasteners; install self-locking washers and trim and bend the pin over.

d. Seal joints on jacketed insulation with a 4 inch wide strip of tape and brush with vapor retarder coating.

e. Cover breaks and penetrations in the jacket material with a patch of the same material as the jacket. Extend patches no less than 2 inches beyond the break or penetration and secure with adhesive and staple.

f. Seal insulation terminations and pin punctures with tape and brush with vapor retarder coating.

g. Insulate oval and round ducts, flexible type, with factory Type I jacket insulation, minimum density of 3/4 pcf attach by staples spaced no more than 16 inches and no more than 6 inches from the degrees of joints. Seal joints in accordance with item "d." above.

3.3.4 Ducts Handling Air for Dual Purpose

For air handling ducts for dual purpose below and above 60 degrees F, insulate ducts as specified for cold air duct.

3.3.5 Insulation for Evaporative Cooling Duct

Insulate evaporative cooling supply duct located in spaces not evaporatively cooled. Use material and installation requirements as specified for duct insulation for warm air duct.

3.3.6 Duct Test Holes

After duct systems have been tested, adjusted, and balanced, repair breaks in the insulation and jacket in accordance with the applicable section of this specification for the type of duct insulation to be repaired. After the insulation is repaired, identify on the outside of the insulation with marker, sticker, or other means "TAB test ports."

3.3.7 Duct Exposed to Weather

3.3.7.1 Installation

Insulate and finish ducts exposed to weather as specified for the applicable service for exposed duct inside the building. After the above is accomplished, further finish the insulation as detailed in the following subparagraphs.

3.3.7.2 Round Duct

Laminated self-adhesive (minimum 2 mils adhesive, 3 mils embossed) vapor barrier/weatherproofing jacket - Less than 0.02 permeability, (greater than 3 ply, standard grade, silver, white, black and embossed or greater than 8 ply, heavy duty, white and natural) membrane must be applied overlapping material by 3 inches no bands or caulking needed - see manufacturer's recommended installation instructions. Aluminum jacket with factory applied moisture retarder must be applied with the joints lapped no less than 3 inches and secured with bands located at circumferential laps and at no more than 12 inch intervals throughout. Lap horizontal joints down to shed water and located at 4 or 8 o'clock position. Seal joints with metal jacketing sealant to prevent moisture penetration. Where jacketing abuts an un-insulated surface, seal joints with metal jacketing sealant.

3.3.7.3 Fittings

Finish fittings and other irregular shapes as specified for rectangular

ducts.

3.3.7.4 Rectangular Ducts

Apply two coats of weather barrier mastic reinforced with fabric or mesh for outdoor application to the entire surface. Ensure each coat of weatherproof mastic has a minimum thickness of 1/16 inch. Ensure exterior is a metal jacketing applied for mechanical abuse and weather protection, and secure with screws or vapor barrier/weatherproofing jacket less than 0.02 permeability greater than 3 ply, standard grade, silver, white, black, and embossed or greater than 8 ply, heavy duty white and natural. Apply membrane overlapping material by 3 inches. No bands or caulking needed-see manufacturing recommend installation instructions.

3.4 EQUIPMENT INSULATION SYSTEMS INSTALLATION

3.4.1 General

Provide removable insulation sections to cover parts of equipment that must be opened periodically for maintenance including vessel covers, fasteners, flanges and accessories. Omit equipment insulation on the following:

a. Hand-holes.

b. Boiler manholes.

c. Cleanouts.

d. ASME stamps.

e. Manufacturer's nameplates.

f. Duct Test/Balance Test Holes.

3.4.2 Insulation for Cold Equipment

Cold equipment below 60 degrees F: Furnish insulation on equipment handling media below 60 degrees F including the following:

a. Pumps.

b. Refrigeration equipment parts that are not factory insulated.

c. Drip pans under chilled equipment.

d. Cold water storage tanks.

e. Water softeners.

f. Duct mounted coils.

g. Cold and chilled water pumps.

h. Pneumatic water tanks.

i. Roof drain bodies.

j. Air handling equipment parts that are not factory insulated.

k. Expansion and air separation tanks.

3.4.2.1 Insulation Type

Provide insulation suitable for the temperature encountered. Provide material and thicknesses as shown in Table 5:

TABLE 5

Insulation Thickness for Cold Equipment (inches)

Equipment handling media at indicated temperature		
	Material	Thickness (inches)
35 to 60 degrees F		
	Cellular Glass	1.5
	Flexible Elastomeric Cellular	1
1 to 34 degrees F		
	Cellular Glass	3
	Flexible Elastomeric Cellular	1.5
Minus 30 to 0 degrees F		
	Cellular Glass	3.5
	Flexible Elastomeric Cellular	1.75

3.4.2.2 Pump Insulation

a. Insulate pumps by forming a box around the pump housing. Construct the box by forming the bottom and sides using joints that do not leave raw ends of insulation exposed. Join joints between sides and between sides and bottom by adhesive with lap strips for rigid mineral fiber and contact adhesive for flexible elastomeric cellular insulation. Ensure box conforms to the requirements of MICA Insulation Stds plate No. 49 when using flexible elastomeric cellular insulation. Ensure joints between top cover and sides fit tightly forming a female shiplap joint on the side pieces and a male joint on the top cover, thus making the top cover removable.

b. Protect exposed insulation corners with corner angles.

c. Upon completion of installation of the insulation, including removable sections, apply two coats of vapor retarder coating with a layer of glass cloth embedded between the coats. The total dry thickness of the finish must be 1/16 inch. Provide a parting line between the box and the removable sections allowing the removable sections to be removed without disturbing the insulation coating. Apply flashing sealant to parting line, between equipment and removable section

insulation, and at all penetrations.

3.4.2.3 Other Equipment

a. Form or fabricate insulation to fit the equipment. To ensure a tight fit on round equipment, bevel edges and tightly butt and stagger joints.

b. Secure insulation in place with bands or wires at intervals as recommended by the manufacturer but no more than 12 inch centers except adhere flexible elastomeric cellular with contact adhesive. Protect insulation corners under wires and bands with suitable corner angles.

c. Install cellular glass in accordance with manufacturer's instructions. Seal joints and ends with joint sealant, and seal with a vapor retarder coating.

d. Use removable insulation on heads of heat exchangers. Fabricate removable section joints using a male-female shiplap type joint. Finish the entire surface of the removable section by applying two coats of vapor retarder coating with a layer of glass cloth embedded between the coats. The total dry thickness of the finish must be 1/16 inch.

e. Protect exposed insulation corners with corner angles.

f. Apply insulation on equipment with ribs over 6 by 6 inches by 12 gauge welded wire fabric which has been cinched in place, or if approved by the Contracting Officer, spot weld to the equipment over the ribs. Secure insulation to the fabric with J-hooks and 2 by 2 inches washers or securely band or wire in place on 12 inch centers.

3.4.2.4 Vapor Retarder/Vapor Barrier

Upon completion of installation of insulation, caulk penetrations. Apply two coats of vapor retarder coating or vapor barrier jacket over insulation, including removable sections, with a layer of open mesh synthetic fabric embedded between the coats. Ensure the total dry thickness of the finish is 1/16 inch. Apply flasing sealant or vapor barrier tape to parting line between equipment and removable section insulation.

3.4.3 Insulation for Hot Equipment

Furnish insulation on equipment handling media above 60 degrees F including the following:

a. Converters.

b. Heat exchangers.

c. Hot water generators.

d. Water heaters.

e. Pumps handling media above 130 degrees F.

f. Fuel oil heaters.

g. Hot water storage tanks.

h. Air separation tanks.

i. Surge tanks.

j. Flash tanks.

k. Feed-water heaters.

l. Unjacketed boilers or parts of boilers.

m. Boiler flue gas connection from boiler to stack (if inside).

n. Induced draft fans.

o. Fly ash and soot collectors.

p. Condensate receivers.

3.4.3.1 Insulation

Provide insulation suitable for the temperature encountered. Insulate shell and tube-type heat exchangers for the temperature of the shell medium.

Determine insulation thickness for hot equipment using Table 6:

TABLE 6

Insulation Thickness for Hot Equipment (inches)

Equipment handling steam or media at indicated pressure or temperature limit		
	Material	Thickness (inches)
15 psig or 250 degrees F		
	Rigid Mineral Fiber	2
	Flexible Mineral Fiber	2
	Calcium Silicate/Perlite	4
	Cellular Glass	3
	Faced Phenolic Foam	1.5
	Flexible Elastomeric Cellular (<200 F)	1
200psig or 400 degrees F		
	Rigid Mineral Fiber	3
	Flexible Mineral Fiber	3
	Calcium Silicate/Perlite	4

TABLE 6		
Insulation Thickness for Hot Equipment (inches)		
Equipment handling steam or media at indicated pressure or temperature limit		
	Material	Thickness (inches)
	Cellular Glass	4
600 degrees F		
	Rigid Mineral Fiber	5
	Flexible Mineral Fiber	6
	Calcium Silicate/Perlite	6
	Cellular Glass	6
600 degrees F: Thickness necessary to limit the external temperature of the insulation to 120 F. Submit heat transfer calculations to substantiate insulation and thickness selection.		

3.4.3.2 Insulation of Boiler Stack and Diesel Engine Exhaust Pipe

Inside mechanical Room, bevel insulation neatly around openings and provide sheet metal insulation stop strips around such openings. Apply a skim coat of hydraulic setting cement directly to insulation. Apply a flooding coat of adhesive over hydraulic setting cement, and while still wet, press a layer of glass cloth or tape into adhesive and seal laps and edges with adhesive. Coat glass cloth with adhesive. When dry, apply a finish coat of adhesive at can-consistency so that when dry no glass weave is observed. Provide metal jackets for stacks and exhaust pipes that are located above finished floor and spaces outside mechanical room. Apply metal jackets directly over insulation and secure with 3/4 inch wide metal bands spaced on 18 inch centers. Do not insulate name plates. Provide insulation type and thickness in accordance with the following Table 7.

TABLE 7

Insulation and Thickness for
Boiler Stack and Diesel Engine Exhaust Pipe

	Material	Outside Diameter (Inches)				
		0.25 - 1.25	1 - 1.67	3.5-5	6 - 10	> or = 11 - 36
Service & Surface Temperature Range (Degrees F)						
Boiler Stack (Up to 400 degrees F)						
	Mineral Fiber ASTM C585 Class B-3, ASTM C547 Class 1, or ASTM C612 Class 1	N/A	N/A	3	3.5	4
	Calcium Silicate ASTM C533, Type 1	N/A	N/A	3	3.5	4
	Cellular Glass ASTM C552, Type II	1.5	1.5	1.5	2	2.5
Boiler Stack (401 to 600 degrees F)						
	Mineral Fiber ASTM C547 Class 2, ASTM C592 Class 1, or ASTM C612 Class 3	N/A	N/A	4	4	5
	Calcium Silicate ASTM C533, Type I or II	N/A	N/A	4	4	4
	Mineral Fiber and Cellular Glass Assembly:					
	Mineral Fiber ASTM C547 Class 2, ASTM C592 Class 1, or ASTM C612 Class 3	1	1	1	1	2
	Cellular Glass ASTM C552, Type II	2	2	2	2	2
Boiler Stack (601 to 800 degrees F)						

TABLE 7

Insulation and Thickness for
Boiler Stack and Diesel Engine Exhaust Pipe

	Material	Outside Diameter (Inches)				
		0.25 - 1.25	1 - 1.67	3.5-5	6 - 10	> or = 11 - 36
Service & Surface Temperature Range (Degrees F)						
	Mineral Fiber ASTM C547 Class 3, ASTM C592 Class 1, or ASTM C612 Class 3	N/A	N/A	4	4	6
	Calcium Silicate ASTM C533, Type I or II	N/A	N/A	4	4	6
	Mineral Fiber and Cellular Glass Assembly:					
	Mineral Fiber ASTM C547 Class 2, ASTM C592 Class 1, or ASTM C612 Class 3	2	2	2	3	3
	Cellular Glass ASTM C552, Type II	2	2	2	2	2
Diesel Engine Exhaust (Up to 700 degrees F)						
	Calcium Silicate ASTM C533, Type I or II	3	3.5	4	4	4
	Cellular Glass ASTM C552, Type II	2.5	3.5	4	4.5	6
Diesel Engine Exhaust (700 to 1200 degrees F)						
	Calcium Silicate ASTM C533, Type I or II	N/A	N/A	6.5	6.5	7.5

3.4.3.3 Insulation of Pumps

Insulate pumps by forming a box around the pump housing. Construct the box by forming the bottom and sides using joints that do not leave raw ends of insulation exposed. Band bottom and sides to form a rigid housing that does not rest on the pump. Ensure joints between top cover and sides fit tightly. The top cover must have a joint forming a female shiplap joint on the side pieces and a male joint on the top cover, making the top cover removable. Apply two coats of Class I adhesive over insulation, including removable sections, with a layer of glass cloth embedded between the coats. Provide a parting line between the box and the removable sections allowing the removable sections to be removed without disturbing the insulation coating. The total dry thickness of the finish must be 1/16 inch. Apply caulking to parting line of the removable sections and penetrations.

3.4.3.4 Other Equipment

a. Form or fabricate insulation to fit the equipment. To ensure a tight fit on round equipment, bevel edges and tightly butt and stagger joints.

b. Secure insulation in place with bands or wires at intervals as recommended by the manufacturer but no greater than 12 inch centers except adhere flexible elastomeric cellular. Protect insulation corners under wires and bands with suitable corner angles.

c. On high vibration equipment, set cellular glass insulation in a coating of bedding compound as recommended by the manufacturer, and seal joints with bedding compound. Fill mineral fiber joints with finishing cement.

d. Provide removable insulation on heads of heat exchangers. Fabricate the removable section joint using a male-female shiplap type joint. Finish the entire surface of the removable section as specified.

e. Protect exposed insulation corners with corner angles.

f. On equipment with ribs, such as boiler flue gas connection, draft fans, and fly ash or soot collectors, apply insulation over 6 by 6 inch by 12 gauge welded wire fabric which has been cinched in place, or if approved by the Contracting Officer, spot weld to the equipment over the ribs. Secure insulation to the fabric with J-hooks and 2 by 2 inch washers or securely band or wire in place on 12 inch (maximum) centers.

g. On equipment handling media above 600 degrees F, apply insulation in two or more layers with staggered joints.

h. Upon completion of installation of insulation, caulk penetrations. Apply two coats of adhesive over insulation, including removable sections, with a layer of glass cloth embedded between the coats. The total dry thickness of the finish must be 1/16 inch. Apply caulking to parting line between equipment and removable section insulation.

3.4.4 Equipment Handling Dual Temperature Media

Below and above 60 degrees F: insulate equipment handling dual temperature media as specified for cold equipment.

3.4.5 Equipment Exposed to Weather

3.4.5.1 Installation

Insulate equipment exposed to weather and finish in accordance with the requirements for ducts exposed to weather in paragraph DUCT INSULATION INSTALLATION.

3.4.5.2 Optional Panels

At the option of the Contractor, prefabricated metal insulation panels may be used in lieu of the insulation and finish previously specified. Thermal performance must be equal to or better than that specified for field applied insulation. Provide panels that are the standard catalog product of a manufacturer of metal insulation panels. Provide fastenings, flashing, and support system conforming to published recommendations of the manufacturer for weatherproof installation and that prevent moisture from entering the insulation. Design panels to accommodate thermal expansion and to support a 250 pound walking load without permanent deformation or permanent damage to the insulation. Exterior metal cover sheet must be aluminum and exposed fastenings must be stainless steel or aluminum.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 08 00

COMMISSIONING OF MECHANICAL AND PLUMBING SYSTEMS
05/23, CHG 1: 08/24

PART 1 GENERAL

Building Commissioning is a systematic, quality-focused process for enhancing the delivery of a project that focuses on verifying and documenting that all of the commissioned systems and assemblies are planned, designed, installed, tested, operated, and maintained to meet the project requirements. The purpose is to reduce the cost and performance risks associated with delivering facilities projects, and to increase value to owners, occupants, and users. Comply with specification Section 01 91 00.15 BUILDING COMMISSIONING.

1.1 SEQUENCING AND SCHEDULING

Complete functional performance testing prior to performance verification testing required by Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC. Complete the following prior to starting Functional Performance Tests of mechanical systems:

a. All equipment and systems completed, cleaned, flushed, disinfected, calibrated, tested, and operate in accordance with contract documents and construction plans and specifications

b. Final DALT Report submitted and approved in accordance with Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC

c. Pre-final Testing, Adjusting, and Balancing Report submitted in accordance with Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC

d. The Certificate of Readiness submitted and approved in accordance with Section 01 91 00.15 BUILDING COMMISSIONING

e. Air Leakage Test Reports and Diagnostic Test Reports submitted and approved in accordance with Section 01 91 19 BUILDING ENCLOSURE COMMISSIONING

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Test Equipment; G

SD-06 Test Reports

Pipe Flushing, Testing, And Water Treatment Reports; G

Completed Pre-Functional Checklists; G

Seasonal Test Report; G

Full-Load Test Report; G

Post-Construction Trend Log Report; G,

SD-07 Certificates

Certificate Of Readiness; G

1.3 ACCESSIBILITY REQUIREMENTS

Equipment, systems, and devices for commissioned systems must be accessible. Make necessary modifications if systems and devices are not accessible for inspections and testing.

Assist commissioning team in testing by removing equipment covers, opening access panels, and other required activities that assist with visual oversight. Furnish ladders, flashlights, meters, gauges, or other inspection equipment as necessary.

1.4 COORDINATION

Refer to Section 01 91 00.15 BUILDING COMMISSIONING for requirements pertaining to coordination during the commissioning process. Coordinate with the Commissioning Provider in accordance with Section 01 91 00.15 and in accordance with the Commissioning Plan to schedule inspections as required to support the commissioning process. Furnish additional information requested by the Commissioning Provider. Coordinate scheduling of Functional Performance Testing with the commissioning team. Provide plans, reports, notes, and other documentation to the Commissioning Provider as specified in the commissioning plan, as it is completed.

1.5 PIPE FLUSHING, TESTING, AND WATER TREATMENT REPORTS

Test requirements are specified in Division 22 and 23 piping Sections. Prepare a pipe system cleaning, flushing, and hydrostatic testing log. Provide cleaning, flushing, testing, and water treatment log and final reports.

Include the following in the pipe system cleaning, flushing, and hydrostatic testing log:

a. Minimum flushing water velocity.

b. Water treatment reports.

c. Tracking checklist for managing and ensuring that all pipe sections have been cleaned, flushed, hydrostatically tested, and chemically treated.

1.6 CERTIFICATE OF READINESS

Submit Certificate of Readiness documentation in accordance with Section 01 91 00.15 BUILDING COMMISSIONING for all equipment and systems including start-up reports; completed Pre-Functional Checklists; Testing, Adjusting, and Balancing (TAB) Report; Issues Log; HVAC Controls Start-Up Reports. Do not schedule Functional Performance Tests for the system until the

Certificate of Readiness for that system receives approval by the Government. The CxC, Quality Control Manager, and the Mechanical, Electrical, Controls, and TAB subcontractor representatives must sign and date the Certificate of Readiness.

PART 2 PRODUCTS

2.1 TEST EQUIPMENT

Provide all testing equipment required to perform testing for the systems to be commissioned, except for equipment specific to and used by TAB as required by Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC. Provide a sufficient quantity of two-way radios for each subcontractor. Submit list of Test Equipment and instrumentation to be used for testing including equipment/instrument identification number, equipment application or planned use, manufacturer, make, model, and serial number, and calibration history with certificates. Also list special equipment and proprietary tools specific to a piece of equipment required for testing.

2.1.1 Proprietary Equipment

Provide manufacturer's proprietary test equipment and software required by any equipment manufacturer for programming and start-up, whether specified or not. Provide manufacturer test equipment, demonstrate its use, and assist in the commissioning process as needed. Provide data logging equipment and software required to test equipment.

2.1.2 Calibration and Accuracy

Comply with equipment manufacturer's test equipment calibration procedures and intervals. Recalibrate test instruments immediately after instruments have been repaired resulting from being dropped or damaged. Affix calibration tags to test instruments. Furnish calibration records to Contracting Officer upon request.

Provide all testing equipment of sufficient quality and accuracy to test and measure system performance with the tolerances specified. Unless otherwise noted, the following minimum requirements apply: Provide temperature sensors and digital thermometers with a certified calibration within the past year to an accuracy of 0.5 degrees F and a resolution of plus or minus 0.1 degrees F. Provide pressure sensors with an accuracy of plus or minus 2.0 percent of the value range being measured (not full range of meter) and calibrated within the last year.

PART 3 EXECUTION

3.1 MEETINGS

Attend all meetings in accordance with Section 01 91 00.15 BUILDING COMMISSIONING.

Provide timely updates on construction schedule changes to allow the Commissioning Provider to execute commissioning process efficiently. Notify Contracting Officer of anticipated construction delays to commissioning activities not yet performed or not yet scheduled.

3.2 COMMISSIONING CONSTRUCTION OBSERVATION CHECKLISTS

Commissioning construction observation checklists include Pre-Functional Checklists, Integrated Systems Test Checklists, and Functional Performance Test Checklists. Provide commissioning construction observation checklists for the Interim and Final Construction Phase Commissioning Plan in accordance with Section 01 91 00.15 BUILDING COMMISSIONING.

3.2.1 Pre-Functional Checklists

The Pre-Functional Checklists must include items for physical inspection or testing that demonstrate that installation and start-up of equipment and systems is complete. Refer to paragraph PRE-FUNCTIONAL CHECKS. Pre-functional checklists must be tailored to verify the specific installation requirements and details of the construction documents and manufacturer's instructions.

3.2.2 Functional Performance Test Checklists

Functional Performance Test Checklists must include procedures that explain, step-by-step, the actions and expected results that will demonstrate that the system performs in accordance with the contract. Refer to paragraph FUNCTIONAL PERFORMANCE AND INTEGRATED SYSTEMS TESTING. Include the following sections and details appropriate to the systems being tested in the Functional Performance Test Checklists:

a. Notable system features including information about controls to facilitate understanding of system operation and maintenance

b. Conclusions and recommendations. Conclusions must clearly indicate if system does or does not perform in accordance with contract requirements and specifications. Recommendation must clearly indicate that the system should or should not be approved by the Government.

c. Test conditions including date, beginning and ending time, and beginning and ending outdoor air conditions

d. Attendees

e. Identification of the equipment involved in the test

f. **System feature identification**

g. Point-to-point observations including demonstrating system flow meters and sensors have been calibrated and are correctly displayed on the Operator work station

h. Actuator operation observations demonstrating actuator responses to commands from the control system

i. As-found condition of the system operation

j. List of test items with step numbers along with the corresponding feature or control operation, intended test procedure, expected system response, and pass/fail indication.

k. Space for comments for each test item.

3.2.3 Integrated Systems Test Checklists

Integrated Systems Test Checklists must include test procedures that explain, step-by-step, the actions and expected results that will demonstrate that the interactive operations between systems performs in accordance with the contract. Refer to paragraph FUNCTIONAL PERFORMANCE AND INTEGRATED SYSTEMS TESTING. Include the following sections in the Integrated Systems Test Checklists:

a. Notable features of the interconnected systems organized by discipline including information to facilitate understanding of system operation

b. Conclusions and recommendations. Conclusions must clearly indicate if the systems do or do not perform in accordance with contract requirements and specifications. Recommendation must clearly indicate that the systems should or should not be approved by the Government

c. Test conditions including date and beginning and ending time

d. Identification of the equipment and systems involved in the test

e. List of test items with step numbers along with the corresponding feature or control operation, intended test procedure, expected system response, and pass/fail indication.

f. Space for comments for each test item.

3.3 PRE-FUNCTIONAL CHECKS

Pre-Functional Checks are a type of Commissioning Inspection in accordance with Section 01 91 00.15 BUILDING COMMISSIONING. Complete one Pre-Functional Checklist for each individual item of equipment or system for each system required to be commissioned including, but not limited to, ductwork, piping, equipment, fixtures, and controls. Include manufacturer start-up checklists associated with equipment with the submission of the Pre-Functional Checklists. Provide manufacturer's installation manual for each type of unit. Indicate commissioning team member inspection and validation of each Pre-Functional Checklist item by initials. Validation of each Pre-Functional Checklist item by each team member indicates that item conforms to the contract documents and validated design in their area of responsibility. Commissioning Specialist validation of each Pre-Functional Checklist item indicates that each item has been installed correctly and in accordance with contract documents. Required commissioning team members for Pre-Functional Checks includes the CxC, Mechanical Commissioning Specialist, Quality Control Manager, sub-contractor representative for each trade responsible for construction/installation of the checklist item, and the TAB representative (for items impacting TAB). Submit the initialed and Completed Pre-Functional Checklists no later than 7 calendar days after completion of inspection of all checklists items for each system.

3.4 STARTUP AND INITIAL CHECKOUT

Document start-up and initial testing procedures, and include in the Completed Pre-Functional Checklists submittal, including:

a. Startup tests and factory testing reports.

b. Manufacturer's representative start-up, operating, troubleshooting and maintenance procedures.

c. Perform and clearly document system operational checks and quality control checks as they are completed, and providing a copy to the commissioning team.

d. Correct deficiencies and sign the Certificate of Readiness for each system before functional performance testing

3.5 DUCT AIR LEAKAGE TEST (DALT) REPORT REVIEW AND VERIFICATION

3.5.1 Duct Air Leakage Test (DALT) Report Review

The Mechanical System Technical Commissioning Specialist must review the pre-final DALT Report required by Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC. Identify any deficiencies to the Contracting Officer's Representative and the Contractor's Quality Control Personnel and include in the issues log. All deficiencies must be resolved prior to DALT Report approval.

3.6 TESTING, ADJUSTING, AND BALANCING REPORT REVIEW AND VERIFICATION

3.6.1 Testing, Adjusting, and Balancing (TAB) Report Review

The Mechanical System Technical Commissioning Specialist must review the pre-final TAB Report required by Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC and identify any deficiencies to the Contracting Officer's Representative and the Contractor's Quality Control Personnel and include in the issues log. All deficiencies must be resolved prior to TAB Report approval.

3.6.2 Testing, Adjusting, and Balancing (TAB) Report Verification

The Mechanical System Technical Commissioning Specialist must witness the TAB Field Acceptance Testing specified by Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC and identify any deficiencies to the Contracting Officer's Representative and the Contractor's Quality Control Personnel and include in the issues log. All deficiencies must be resolved prior to TAB Report approval.

3.7 HVAC CONTROLS START-UP AND PERFORMANCE VERIFICATION TEST REVIEW

The Mechanical System Technical Commissioning Specialist must review the Start-Up Testing Report, PVT Procedures and PVT Reports, including endurance testing trend submittals, required by Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC. The Mechanical System Technical Commissioning Specialist must review each submittal and identify any deficiencies to the Contracting Officer's Representative and the Contractor's Quality Control Personnel and include in the issues log. All deficiencies must be resolved prior to final acceptance.

3.8 FUNCTIONAL PERFORMANCE AND INTEGRATED SYSTEMS TESTING

Functional Performance and Integrated Systems Testing are a type of Commissioning Testing in accordance with Section 01 91 00.15 BUILDING COMMISSIONING. Conduct Functional Performance Testing in accordance with Section 01 91 00.15 BUILDING COMMISSIONING and requirements in this Section. Prior to Functional Performance Testing, complete all

prerequisites in accordance with paragraph SEQUENCING AND SCHEDULING. Demonstrate that all system components have been installed, that each control device and item of equipment operates, and that the systems operate and perform, including interactive operation between systems, in accordance with contract documents.

Perform Integrated Systems Tests only after the Functional Performance Tests for each associated system are completed with all deficiencies resolved and after the related Functional Performance Test Checklists have been signed by each commissioning team member.

3.8.1 Test Scheduling and Coordination

Schedule and conduct Initial Functional Performance Tests as soon as all contract work is completed, regardless of the season. Develop and implement means of artificial loading to demonstrate, to a reasonable level of confidence, the ability of the HVAC systems to handle peak seasonal loads. Schedule Functional Performance Tests for each system only after the Certificate of Readiness has been approved by the Government for the system. Correct all deficiencies identified through any prior review, inspection, or test activity before the start of Functional Performance Tests.

Functional Performance Tests and Integrated Systems Tests must be performed with the CxC present. Government reserves the right to witness all tests. Coordinate test schedule with Government representatives.

3.8.2 Preparation

Put equipment and systems into operation and continue operation during each working day of functional performance and integrated systems testing, as required. Verify temperature and pressure taps in accordance with Contract Documents. Provide a pressure/temperature plug at each water sensor which is an input point to control system.

Perform minor adjustments to equipment and systems during Functional Performance Tests as deemed necessary by the commissioning team. Where calibrated DDC sensors cannot be used to record test data, provide measuring instruments, logging devices, and data acquisition equipment to record data for the complete range of test data for the required test period.

3.8.3 Testing Procedures

Provide all necessary materials and system modifications to produce the necessary flows, pressures, temperatures, and other conditions necessary to execute the test according to the specified conditions. At completion of the test, return the affected building equipment and systems to their pre-test condition.

Follow the Functional Performance Test from the approved Final Construction Phase Commissioning Plan. Perform Functional Performance Tests for each item of equipment and each system required to be commissioned. Verify all sensor calibrations, control responses, safeties, interlocks, operating modes, sequences of operation, capacities, and all other performance requirements comply with contract, regardless of the specific items listed within the checklists provided. In general, testing must progress from equipment or components to subsystems to systems to interlocks and connections between systems. Commissioning

Specialists are responsible for determining the order of components and systems to be tested.

Indicate validation of each item of equipment and systems tested by signature of each commissioning team member for each test. The Quality Control Representative, Commissioning Specialists, and Contracting Officer's Representative, if present, must indicate validation after the equipment and systems are free of deficiencies.

3.8.4 Simulating Conditions

Functional performance testing is conducted by simulating conditions at control devices to initiate a control system response. Before testing, calibrate all sensors, transducers and devices. Over-writing control input values through the control system is not acceptable unless approved by the Contracting Officer. Perform each test under conditions that simulate actual conditions as close as is practically possible. Specific examples of simulating conditions are provided below. Do not simulate conditions when damage to the system or building may result.

a. When varying static pressures inside ductwork cannot be simulated within the duct, and where a sensor signals the controls system to initiate sequences at various duct static pressures, it is acceptable to simulate the various pressures with a Pneumatic Squeeze-Bulb Type Signaling Device with gauge temporarily attached to the sensing tube leading to the transmitter. It is not acceptable to reset the various set-points, nor to simulate an electric analog signal (unless approved as noted above).

b. Dirty filter pressure drops can be simulated by partially blocking filter face.

c. Freeze-stat safeties can be simulated by packing portion of sensor with ice.

d. High outside air temperatures can be simulated with a hair blower.

e. Raising entering cooling coil temperatures by activating a heating/preheat coil can be used to simulate entering cooling coil conditions.

f. Do not use signal generators to simulate sensor signals unless approved by the Contracting Officer, as noted above, for special cases.

g. Control set points can be altered. For example, to see the air conditioning compressor lockout work at an outside air temperature below 55 degrees F, when the outside air temperature is above 55 degrees F, temporarily change the lockout set point to be 0 degrees F above the current outside air temperature. Caution: Set points are not to be raised or lowered to a point to cause damage to the components, systems, or the building structure and contents.

h. Test duct mounted smoke detectors in accordance with the manufacturer's recommendations. Perform the tests with air system at minimum airflow condition.

i. Test current sensing relays used for fan and pump status signals to control system to indicate unit failure and run status by resetting the set point on the relay to simulate a lost belt or unit failure

while the unit is running. Confirm that the failure alarm was generated and received at the control system. After the test is conducted, return the set point to its original set-point or a set-point as indicated by the Contracting Officer.

3.8.5 Manufacturer's Representative

Provide a factory trained representative authorized by the equipment manufacturer to perform Functional Performance Testing for the following equipment:

Chillers

Boilers

Ensure the test representative reviews, approves, and signs the completed field test report. Include person's name with signatures.

3.8.6 Integrated Systems Tests

Follow the Integrated Systems Test Checklists from the approved Final Construction Phase Commissioning Plan. Integrated Systems Tests must be performed for the interactive operation between HVAC systems and other systems such as fire protection systems, smoke control systems, or back-up electrical supply. Verify correct interactive operation, acceptable speed of response, and other contract requirements for both normal and failure modes. Examples of Integrated Systems Tests include the correct operation of HVAC systems during emergency system activation or correct operation of uninterruptible power supplies or energy generators and connected systems.

3.8.7 Sample Strategy

Perform Functional Performance Tests using the sample strategy identified herein. Test all central plant equipment, primary air handling units, and process cooling or heating equipment. Test all system-level equipment serving multiple zones. Fifty percent sample testing is allowed for large groups of identical equipment with identical controllers serving single zones such as air terminal units, fan coil units, unitary equipment, and plumbing fixtures. Sample size may be no less than three units. Complete a Functional Performance Test Checklist for each item of equipment or system to be tested. During testing, Government representatives may select the specific equipment or system to be tested for sample sizes less than 100 percent.

3.8.7.1 100 Percent Sample Procedures

Systems or equipment for which 100 percent sample size are tested fail if one or more of the test procedures results in discovery of a deficiency and the deficiency cannot be resolved within 5 minutes during the test.

Re-test to the extent necessary to confirm that the deficiencies have been corrected without negatively impacting the performance of the rest of the system.

3.8.7.2 Less than 100 Percent Sample Procedures

Randomly test each sample group of identical equipment. If 10 percent of the units in the first sample fail the functional performance tests, test a second sample group, the same size as the first sample group. The second

sample must not include any units from the first sample group.

If 10 percent of the units in the second sample fail, test all remaining units. If at any point frequent failures occur the CxC may stop the testing and require the contractor to perform and document a checkout of the remaining units prior to continuing functional testing.

3.9 INTEGRATED SYSTEMS TEST

Perform Integrated Systems Tests only after the Functional Performance Tests for each associated system are completed with all deficiencies resolved and after the related Functional Performance Test Checklists have been signed by each commissioning team member.

3.10 RETESTING REQUIREMENTS

Abort tests if any deficiency prevents successful completion of the test or if any required commissioning team member is not present for the test. Re-test only after all deficiencies identified during the original tests have been corrected.

Contracting Officer may withhold payment equivalent to lost time, re-testing, and aborted tests. These costs may include salary, travel costs, and per diem for Government team members. Correct deficiencies as identified by the commissioning team and retest the systems to be commissioned.

3.11 SYSTEM ACCEPTANCE

Systems may be partially accepted prior to seasonal testing if they comply with all construction contract and accepted design requirements that can be tested during initial Functional Performance Tests. All test procedures must be successful completed prior to full systems acceptance.

3.12 SEASONAL TESTS

Perform Initial Functional Performance Tests as soon as all contract work is completed, but prior to facility turnover, regardless of the season.

In addition to the Initial Functional Performance Tests, perform Functional Performance Tests of HVAC systems during peak heating and cooling seasons during outdoor air condition design extremes. Schedule Seasonal Functional Performance Tests in coordination with the Contracting Officer. Submit Seasonal Test Report within 14 days of test completion. Include seasonal test report in the Updated Final Commissioning Report as specified in Section 01 91 00.15 BUILDING COMMISSIONING

Execute seasonal functional performance testing, witnessed by the Contracting Officer. Correct deficiencies and make adjustments to O&M manuals and as-built drawings for applicable issues identified in any seasonal testing.

3.13 FULL-LOAD TESTS

Perform Initial Functional Performance Tests as soon as all contract work is completed, but prior to facility turnover. In addition to the Initial Functional Performance Tests, perform Functional Performance Tests of HVAC systems under full-load conditions. Develop and implement means of artificial loading to demonstrate the ability of the process cooling

systems to handle peak process loads. Schedule Full-Load Functional Performance Tests in coordination with the Contracting Officer. Submit Full-Load Test Report within 14 days of test completion.

Execute full-load functional performance testing, witnessed by the Contracting Officer. Correct deficiencies and make adjustments to O&M manuals and as-built drawings for applicable issues identified in any full load testing.

3.14 TRAINING

The Mechanical Systems Technical Commissioning Specialist must review the training plan required by Section 01 78 23 OPERATION AND MAINTENANCE DATA and identify any deficiencies to the Contracting Officer's Representative and the Contractor's Quality Control Personnel.

Coordinate, schedule, and document all required training. At a minimum, include the following items in the training report for commissioned systems:

a. Complete commissioning documentation

b. Complete O&M data

c. Complete Training

d. Purpose of equipment.

e. Principle of how the equipment works.

f. Important parts and assemblies.

g. How the equipment achieves its purpose and necessary operating conditions.

h. Most likely failure modes, causes and corrections.

i. On site demonstration.

j. Provide updates to O&M manuals based on field modifications.

k. Provide training of the post-occupancy operations and maintenance staff.

3.15 COMMISSIONING REPORT

Include all completed Pre-Functional Checklists and Functional Performance and Integrated Systems Test Checklists in the Commissioning Report as specified in Section 01 91 00.15 BUILDING COMMISSIONING. Include the approved TAB Report.

3.16 POST-CONSTRUCTION ENDURANCE TEST

Perform an Endurance Test in accordance with the paragraph ENDURANCE TESTING in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC once during the peak heating season and once during the peak cooling season during outdoor air condition extremes with the exception that network bandwidth usage measurement and recording is not required. Use the Temporary Trending Hardware, if necessary, in accordance with Section

23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

The Mechanical System Commissioning Specialists must review the trend logs from the Endurance Tests to ensure that the systems have stable operation and operate as required by the construction contract. The Commissioning Specialists must provide a Post-Construction Trend Log Report that identifies any deficiencies noted in operation, recommendations for correction, and includes a graphical representation of the trends. Provide one Trend Log Report for the peak cooling season and one Trend Log Report for the peak heating season. Submit the Post-Construction Trend Log Reports no later than 14 calendar days following receipt of the trend log data by the Commissioning Specialist. Include the Post-Construction Trend Log Reports in the Updated Final Commissioning Report as specified in Section 01 91 00.15 BUILDING COMMISSIONING

-- End of Section --

SECTION 23 09 00

INSTRUMENTATION AND CONTROL FOR HVAC
02/25 MCBCL

PART 1 GENERAL

1.1 SUMMARY

Provide a complete Direct Digital Control (DDC) system, except for the Front End, suitable for the control of the heating, ventilating and air conditioning (HVAC) and other building-level systems as indicated and shown and in accordance with Section 23 09 13 INSTRUMENTATION AND CONTROL DEVICES FOR HVAC, Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS, and other referenced Sections.

1.1.1 BACnet Direct Digital Control Systems for HVAC Description:

a. All new devices are accessible using a Web browser interface and communicate using ASHRAE 135 BACnet communications without the use of gateways, unless gateways are shown on the design drawings and specifically requested by the Government. Where gateways are allowed, they must support ASHRAE 135, including all object properties and read-write services shown on Government approved interoperability schedules. Manufacturer's products, including design, materials, fabrication, assembly, inspection, and testing shall be in accordance with ASHRAE 135, ASME B31.1, and NFPA 70, except where indicated otherwise.

1.1.2 System Requirements

Provide systems meeting the requirements this Section and other Sections referenced by this Section, and which have the following characteristics:

a. The system implements the control sequences of operation shown in the Contract Drawings using DDC hardware to control mechanical and electrical equipment.

b. The system meet the requirements of this specification as a stand-alone system and does not require connection to any other system.

c. Control sequences reside in DDC hardware in the building. The building control network is not dependent upon connection to a Utility Monitoring and Control System (UMCS) Front End or to any other system for performance of control sequences. To the greatest extent practical, the hardware performs control sequences without reliance on the building network.

d. The hardware is installed such that individual control equipment can be replaced by similar control equipment from other equipment manufacturers with no loss of system functionality.

e. All necessary documentation, configuration information, programming tools, programs, drivers, and other software are licensed to and otherwise remain with the Government such that the Government or their agents are able to perform repair, replacement, upgrades, and expansions of the system without subsequent or future dependence on the Contractor, Vendor or Manufacturer.

f. Sufficient documentation and data, including rights to documentation and data, are provided such that the Government or their agents can execute work to perform repair, replacement, upgrades, and expansions of the system without subsequent or future dependence on the Contractor, Vendor or Manufacturer.

g. Hardware is installed and configured such that the Government or their agents are able to perform repair, replacement, and upgrades of individual hardware without further interaction with the Contractor, Vendor or Manufacturer.

1.1.3 Verification of Dimensions

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

1.1.4 Drawings

The Government will not indicate all offsets, fittings, and accessories that may be required on the drawings. Carefully investigate the mechanical, electrical, and finish conditions that could affect the work to be performed, arrange such work accordingly, and provide all work necessary to meet such conditions.

1.2 RELATED SECTIONS

Related work specified elsewhere:

a. Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS

b. Section 23 09 13 INSTRUMENTATION AND CONTROL DEVICES FOR HVAC

c. Section 25 05 11.00 CYBERSECURITY FOR FACILITY-RELATED CONTROL SYSTEMS - ISOLATED SYSTEMS

d. Section 01 91 00.15 BUILDING COMMISSIONING

1.3 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 135	(2020; Interpretation 1-8 2021; Errata 1-2 2021; Addenda CD 2021; Addenda BY-CE 2022; Interpretation 9-10 2022) BACnet—A Data Communication Protocol for Building Automation and Control Networks
ASHRAE 135.1	(2023) Method of Test for Conformance to BACnet

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B31.1	(2024) Power Piping

ASTM INTERNATIONAL (ASTM)

ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus

CONSUMER ELECTRONICS ASSOCIATION (CEA)

CEA-709.1-D	(2014) Control Network Protocol Specification

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C62.41.1	(2002; R 2008) Guide on the Surges Environment in Low-Voltage (1000 V and Less) AC Power Circuits
IEEE C62.41.2	(2002) Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and Less) AC Power Circuits
IEEE C62.45	(2002; R 2008) Recommended Practice on Surge Testing for Equipment Connected to Low-Voltage (1000 V and Less) AC Power Circuits

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

UL SOLUTIONS (UL)

UL 506	(2017; Reprint Jan 2022) UL Standard for Safety Specialty Transformers
UL 508A	(2018; Reprint Jul 2022) UL Standard for Safety Industrial Control Panels
UL 1449	(2021; Reprint Oct 2025) UL Standard for Safety Surge Protective Devices

1.4 DEFINITIONS

The following list of definitions includes terms used in Sections referenced by this Section and are included here for completeness.The definitions contained in this Section may disagree with how terms are defined or used in other documents, including documents referenced by this Section. The definitions included here are the authoritative definitions for this Section and all Sections referenced by this Section.

1.4.1 BACnet

Building Automation and Control Network; the common name for the

communication standard ASHRAE 135. The standard defines methods and protocol for cooperating building automation devices to communicate over a variety of LAN technologies.

1.4.2 BACnet/IP

An extension of BACnet, Annex J, defines this mechanism using a reserved UDP socket to transmit BACnet messages over IP networks. A BACnet/IP network is a collection of one or more IP subnetworks that share the same BACnet network number. See also "BACnet Broadcast Management Device".

1.4.3 BACnet Internetwork

Two or more BACnet networks, possibly using different LAN technologies, connected with routers. In a BACnet internetwork, there exists only one message path between devices.

1.4.4 BACnet Network

One or more BACnet segments that have the same network address and are interconnected by bridges at the physical and data link layers.

1.4.5 BACnet Segment

One or more physical segments of BACnet devices on a BACnet network, connected at the physical layer by repeaters.

1.4.6 BBMD

BACnet Broadcast Management Device (BBMD). A communications device, typically combined with a BACnet router. A BBMD forwards BACnet broadcast messages to BACnet/IP devices and other BBMDs connected to the same BACnet/IP network. Every IP subnetwork that is part of a BACnet/IP network must have only one BBMD. See also "BACnet/IP".

1.4.7 BAS

Building Automation Systems, including DDC (Direct Digital Controls) used for facility automation and energy management.

1.4.8 BAS Owner

The regional or local user responsible for managing all aspects of the BAS operation, including: network connections, workstation management, technical support, control parameters, and daily operation. The BAS Owner for this project is Camp Lejeune FRCS Cyber Operation Group. Point of contact:

Public Works Division/FRCS Cyber Ops
1110 Ash Street
MCB Camp Lejeune, NC 28547
(910) 450-6891

1.4.9 BIBBs

BACnet Interoperability Building Blocks. A collection of BACnet services used to describe supported tasks. BIBBs are often described in terms of "A" (client) and "B" (server) devices. The "A" device uses data provided by the "B" device, or requests an action from the "B" device.

1.4.10 BI

BACnet International, formerly two organizations: the BACnet Manufacturers Association (BMA) and the BACnet Interest Group - North America (BIG-NA).

1.4.11 BI/BTL

BACnet International/BACnet Testing Laboratories (Formerly BMA/BTL). The organization responsible for testing products for compliance with the BACnet standard, operated under the direction of BACnet International.

1.4.12 Bridge

Network hardware that connects two or more network (or BACnet internetwork) segments at the physical and data link layers. A bridge may also filter messages.

1.4.13 Broadcast

A message sent to all devices on a network segment.

1.4.14 Device

Any control system component, usually a digital controller, that contains a BACnet Device Object and uses BACnet to communicate with other devices. See also "Digital Controller".

1.4.15 Device Object

Every BACnet device requires one Device Object, whose properties represent the network visible properties of that device. Every Device Object requires a unique Object Identifier number on the BACnet internetwork. This number is often referred to as the device instance.

1.4.16 Device Profile

A collection of BIBBs determining minimum BACnet capabilities of a device, defined in ASHRAE Standard 135-2004, Annex L. Standard device profiles include BACnet Operator Workstations (B-OWS), BACnet Building Controllers (B-BC), BACnet Advanced Application Controllers (B-AAC), BACnet Application Specific Controllers (B-ASC), BACnet Smart Actuator (B-SA), and BACnet Smart Sensor (B-SS). Each device used in new construction is required to have a PICS statement listing BIBBs supported.

1.4.17 Digital Controller

An electronic controller, usually with internal programming logic and digital and analog input/output capability, which performs control functions. In most cases, synonymous with a BACnet device described in this specification. See also "Device".

1.4.17.1 Terminal Device Controllers

Terminal device controllers typically are controllers with less control features, may have integrated actuators, and may be mounted directly on equipment (with enclosures).

1.4.17.2 Field Controllers

Field controllers typically have a greater capability for input/output and customization, do not have integral actuators, are mounted in an enclosure not on the equipment and are used for equipment such as VAV air handlers.

1.4.17.3 Plant Controllers

Plant controllers are typically used to control various equipment in mechanical rooms such as pumps, heat exchangers, and chillers.

1.4.17.4 Supervisory Building Controller (SBC)

The Supervisory Building Controller is used to coordinate all equipment in a building, input scheduling, and is used as a connection point for transferring configuration files to the other controllers. The SBC shall communicate with other controllers and equipment through a BACnet MS/TP bus. Depending on approvals and capabilities, the SBC may be used as a point of connection between the Camp Lejeune EMCS network (IP) and the building level control network (BACnet MS/TP).

1.4.18 Direct Digital Control (DDC)

Digital controllers performing control logic. Usually the controller directly senses physical values, makes control decisions with internal programs, and outputs control signals to directly operate switches, valves, dampers, and motor controllers.

1.4.19 DDC System

A network of digital controllers, communication architecture, and user interfaces. A DDC system may include programming, sensors, actuators, switches, relays, factory controls, operator workstations, and various other devices, components, and attributes.

1.4.20 Energy Management & Control System (EMCS)

The EMCS at Camp Lejeune is an enterprise system that actively receives energy and building condition information from multiple sources and provides load shedding, electric metering, alarming, trending, scheduling, set point adjustment and device status of all supervisory building controllers for maintenance personnel. The EMCS receives real time electrical utility pricing data and automatically manages to Camp Lejeune's energy target. The existing EMCS consists of Niagara FX N4 supervisor (JCI FX web supervisor).

1.4.21 Ethernet

A family of local-area-network technologies providing high-speed networking features over various media.

1.4.22 Firmware

Software programmed into read only memory (ROM), flash memory, electrically erasable programmable read only memory (EEPROM), or erasable programmable read only memory (EPROM) chips.

1.4.23 Gateway

Communication hardware and software connecting two or more different protocols, similar to human language translators. The Gateway translates one protocol into equivalent concepts for the other protocol. In BACnet applications, a Gateway has BACnet on one side and non-BACnet protocols on the other side.

1.4.24 Global ID

An identification number assigned to each Supervisory Building Controller. The Global ID includes assigned MSTP Trunk Instance Numbers and a range of BACnet Instance Numbers to be used for the Field Controllers. The Global ID is assigned by the BAS Owner.

1.4.25 Half Router

A device that participates as one partner in a BACnet point-to-point (PTP) connection. Two half-routers in an active PTP connection combine to form a single router.

1.4.26 Hub

A common connection point for devices on a network.

1.4.27 Internet Protocol (IP, TCP/IP, UDP/IP)

A communication method, the most common use is the World Wide Web. At the lowest level, it is based on Internet Protocol (IP), a method for conveying and routing packets of information over various LAN media. Two common protocols using IP are User Datagram Protocol (UDP) and Transmission Control Protocol (TCP). UDP conveys information to well-known "sockets" without confirmation of receipt. TCP establishes "sessions", which have end-to-end confirmation and guaranteed sequence of delivery.

1.4.28 Input/Output (I/O)

Physical inputs and outputs to and from a device, although the term sometimes describes software, or "virtual" I/O. See also "Points".

1.4.29 I/O Expansion Unit

An I/O expansion unit provides additional point capacity to a digital controller.

1.4.30 IP subnet

Internet protocol (IP) identifies individual devices with a 32-bit number divided into four groups from 0 to 255. Devices are often grouped and share some portion of this number. For example, one device has IP address 209.185.47.68 and another device has IP address 209.185.47.82. These two devices share Class C subnet 209.185.47.00

1.4.31 ISSM

Information Systems Security Manager

1.4.32 Local-Area Network (LAN)

A communication network that spans a limited geographic area and uses the same basic communication technology throughout.

1.4.33 LonTalk

CEA-709.1-D. A communication protocol developed by Echelon Corp. LonTalk is not permitted.

1.4.34 MAC Address

Media Access Control address. The physical node address that identifies a device on a Local Area Network.

1.4.35 Master-Slave/Token-Passing (MS/TP)

One of the LAN options for BACnet. MSTP uses twisted-pair wiring for relatively low speed and low cost communication (up to 4,000 ft at 76.8K bps).

1.4.36 Native BACnet Device

A device that uses BACnet as its primary, if not only, method of communication with other BACnet devices without intermediary gateways. A system that uses native BACnet devices at all levels is a native BACnet system.

1.4.37 Network

Communication technology for data communications. BACnet approved network types are BACnet over Internet Protocol (IP), Point to Point (PTP) Ethernet, MS/TP, and LonTalk®. In general, networks within the building, all controllers and equipment will be BACnet MS/TP, unless noted otherwise.

1.4.38 Network Number

A site-specific number assigned to each network segment to identify for routing. This network number must be unique throughout the BACnet internetwork.

1.4.39 Object

The concept of organizing BACnet information into standard components with various associated properties. Examples include analog input objects and binary output objects.

1.4.40 Object Identifier

An object property used to identify the object, including object type and instance. Object Identifiers must be unique within a device.

1.4.41 Object Properties

Attributes of an object. Examples include present value and high limit properties of an analog input object. Properties are defined in ASHRAE 135; some are optional and some are required. Objects are controlled by reading from and writing to object properties.

1.4.42 Peer-to-Peer

Peer-to-peer refers to devices where any device can initiate and respond to communication with other devices. Peer-to-Peer configurations must be reviewed and approved by Camp Lejeune Public Works Department.

1.4.43 Performance Verification Test (PVT)

The procedure for determining if the installed BAS meets design criteria prior to final acceptance. The PVT is performed after installation, testing, and balancing of mechanical systems. The PVT is performed by the Contractor.

1.4.44 PID

Proportional, integral, and derivative control; three parameters used to control modulating equipment to maintain a setpoint. Derivative control is often not required for HVAC systems (leaving "PI" control).

1.4.45 PICS

Protocol Implementation Conformance Statement (PICS), describing the BACnet capabilities of a device. See BACnet, Annex A for the standard format and content of a PICS statement.

1.4.46 Points

Physical and virtual inputs and outputs. See also "Input/Output".

1.4.47 PTP

Point-to-Point protocol connects individual BACnet devices or networks using serial connections like modem-to-modem links.

1.4.48 Repeater

A network component that connects two or more physical segments at the physical layer.

1.4.49 Router

A BACnet router is a component that joins together two or more networks using different LAN technologies. Examples include joining a BACnet Ethernet LAN to a BACnet MS/TP LAN. If a router is connected directly to the MCEN, it must be listed on the approved DIACAP equipment list and must be Marine Corps DADMS listed and approved.

1.4.50 Stand-Alone Control

Refers to devices performing equipment-specific and small system control without communication to other devices or computers for physical I/O, excluding outside air and other common shared conditions. Devices are located near controlled equipment, with physical input and output points limited to 64 or less per device, except for complex individual equipment or systems. Failure of any single device or communications will not cause other network devices to fail. Internal time clocks and onboard scheduling are required to allow for stand-alone control if not connected to a Supervisory Building Controller. BACnet "Smart" actuators (B-SA profile) and sensors (B-SS profile) communicating on a network with a parent device

are exempt from stand-alone requirements. Provide stand-alone control routines to provide for energy saving sequences such as free cooling. Provide stand-alone control routines that operate without connection to the BACnet/IP and MS/TP networks during a loss of communication.

1.4.51 Supervisory Building Controller

Supervisory Controller that is the main interface for the building control system.

1.4.52 TAB

Testing, adjusting, and balancing (of HVAC systems).

1.5 ADMINISTRATIVE REQUIREMENTS

1.5.1 FRCS Required Training

It is the contractor's sole responsibility to ensure any contractor personnel or subcontractor who will be performing any work pertaining to any new or existing SBC:

a. Attend mandatory FRCS provided training at the frequency prescribed by FRCS.

b. Maintain valid credentials throughout the duration of the project.

FRCS training is typically conducted every two weeks at a location designated by FRCS. Contact the BAS Owner to schedule training and to obtain login credentials. The contractor shall bear the sole responsibility for any delays or mobilizations that may occur should the contractor or subcontractor fail to fulfil the qualifications required to maintain valid credentials. FRCS will not provide unscheduled training under any circumstances. Temporary credentials will not be provided.

1.5.2 DDC Pre-Installation Meeting

Prior to starting the installation, meet with the Contracting Officer's Technical Representative (COTR) and the BAS owner to develop a mutual understanding relative to the details of the DDC system requirements. Requirements to be discussed include, but not limited to, required submittals, work schedule, field quality control, BAS Supervisory controller configuration requirements, and project DDC Specification requirements. Ensure that a representative from the controls contractor and the controls contractor's installation team or subcontractor is present. Contractor shall provide minimum fifteen days notice to COTR when scheduling pre-installation meeting.

1.5.3 Pre-PVT Meeting

A Pre-PVT meeting to review the Pre-PVT Checklist is required to coordinate all aspects of the PVT and shall include the Contractor's QA representative, the Contractor's PVT administrator, the Contracting Officer's representative, and the BAS Owner.

1.5.4 Overhead Inspection by BAS Owner

Prior to closing in any ceiling that contains any DDC component above it, meet with the COTR and the BAS Owner for a site inspection. Mutiple

overhead inspections may be required based on construction schedule. Provide minimum 14 days notice to COTR when scheduling each overhead inspection.

1.5.5 Final Inspection by BAS Owner

After receiving approval of the Controls System Operators Manual, meet with the COTR and the BAS Owner for a final site inspection. Provide minimum 14 days notice to COTR when scheduling the final inspection.

1.5.6 Project Sequence

The control system work for this project shall proceed in the following order:

a. Preparatory meeting for controls work.

b. Submit and receive approval on the Shop Drawings, Product Data, and Certificates specified under the paragraph SUBMITTALS.

c. DDC Pre-Installation Meeting.

d. Submit and receive approval for PVT Plan.

e. Pre-PVT Meeting.

f. Perform the control system installation work, including all field check-outs and tuning.

g. Overhead Inspection by BAS Owner.

h. Provide support to TAB personnel as specified under the paragraph TEST AND BALANCE SUPPORT.

i. Perform final tuning of all PID loops after TAB field acceptance testing is complete.

j. Perform the PVT.

k. Submit and receive approval for the PVT Report.

l. Submit and receive approval for As-Built Control Drawings.

m. Submit and receive approval of the Controls System Operators Manual specified under the paragraph CONTROLS SYSTEM OPERATORS MANUALS.

n. Final inspection by BAS Owner.

o. Submit and receive approval for Trends.

p. PVT Report Field Acceptance Test for Season 1.

q. Submit and receive approval on the Training Documentation specified under the paragraph INSTRUCTION TO GOVERNMENT PERSONNEL and VFD Service Support. Submit at least 30 days before training.

r. Deliver the final Controls System Operators Manuals and VFD Service Manuals.

s. Conduct the Phase I Training and VFD on-site/hands-on training.

t. Conduct the Phase II Training.

u. Submit and receive approval of Closeout Submittals.

v. PVT Report Field Acceptance Test for Season 2.

1.6 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Control System Drawings Title Sheet; G

List Of I/O Points; G

Control System Components List; G

Control System Schematics; G

Hvac Equipment Control Ladder Diagrams; G

Sequence Of Operations; G

Component Wiring Diagrams; G

Terminal Strip Diagrams; G

Bacnet Communication Architecture Schematic (Network Riser); G

Control Panel Layout; G

SD-06 Test Reports

Control Contractor's Performance Verification Testing Plan; G

Equipment Supplier's Performance Verification Testing Plan; G

Performance Verification Testing Report; G

Trends; G

Bus Waveform Report; G

SD-07 Certificates

Contractor's Qualifications; G

Contractor's Training Certifications; G

SD-10 Operation and Maintenance Data

Comply with requirements for data packages in Section 01 78 23 OPERATION AND MAINTENANCE DATA and in Section 01 78 24.00 20 FACILITY ELECTRONIC OPERATION AND MAINTENANCE SUPPORT INFORMATION (eOMSI), except as supplemented and modified in this specification.

Controls System Operators Manuals; G, Data Package 4

SD-11 Closeout Submittals

Training Documentation; G

Warranty Information; G

1.7 QUALITY ASSURANCE

1.7.1 Standard Products

Provide material and equipment that are standard manufacturer's products currently in production and supported by a local service organization.

1.7.2 Finish of New Equipment

New equipment finishing shall be factory provided. Manufacturer's standard factory finishing shall be proven to withstand 125 hours in a salt-spray fog test. Equipment located outdoors shall be proven to withstand 500 hours in a salt-spray fog test.

Salt-spray fog test shall be according to ASTM B117, with acceptance criteria as follows: immediately after completion of the test, the finish shall show no signs of degradation or loss of adhesion beyond 0.125 inch on either side of the scratch mark.

1.7.3 Verification of Dimensions

The contractor shall verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing work.

1.7.4 Modification of References

The advisory provisions in ASME B31.1, NFPA 70 and the manufacturer's recommendations are mandatory. Substitute "shall" for "should" wherever it appears and interpret all references to the "authority having jurisdiction" and "owner" to mean the Contracting Officer.

1.7.5 Subcontractor Special Requirements

Perform all work in this section in accordance with the paragraph SUBCONTRACTOR SPECIAL REQUIREMENTS in Section 01 30 00 ADMINISTRATIVE REQUIREMENTS. The paragraph specifies that all contract requirements of this section shall be accomplished directly by a first tier subcontractor. No work required shall be accomplished by a second tier subcontractor.

1.7.6 Contractor's Qualifications

Submit documentation certifying the controls Contractor performing the work has completed at least three DDC systems installations of a similar design to this project, and programmed similar sequences of operation for at least two years. Personnel performing the installation, programming, checkout, commissioning and training shall, at a minimum, have obtained all Contractor's Training Certifications required by the manufacturer for the tasks they are performing. Tasks include any activity required to execute and complete the contracted work. Certifications for each person shall be submitted prior to the beginning of the contracted work.

Certifications shall be made available at any time upon the request from Camp Lejeune.

1.8 DELIVERY, STORAGE, AND HANDLING

Store and protect products from the weather, humidity, and temperature variations, dirt and dust, and other contaminants, within the storage condition limits published by the equipment manufacturer, and as approved by the Contracting Officer. Replace damaged or defective items.

PART 2 PRODUCTS

Provide products meeting the requirements of Section 23 09 13 INSTRUMENTATION AND CONTROL DEVICES FOR HVAC, Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS for BACnet, other referenced Sections, and this Section.

2.1 DDC SYSTEM

a. Provide a networked DDC system for stand-alone control in compliance with the latest revision of the ASHRAE 135. Include all programming, objects, and services required to meet the sequence of control. Provide BACnet MS/TP communications between the DDC system and native BACnet devices furnished with HVAC equipment and plant equipment including boilers, chillers, and variable frequency drives. Devices provided shall be certified in the BACnet Testing Laboratories (BTL) Product Listing and in accordance with ASHRAE 135.1 Method of Test for Conformance to BACnet. Controls provided integral to equipment shall be part of the DDC system and shall fully comply with this specification. Coordinate integration of integral controls into the system as a whole. BACnet over IP is not permitted within the DDC system.

b. Assist the Government in interfacing the new DDC system with the site's existing server and operator workstation and software. Create graphics, scheduling, alarming, and trending.

2.2 GENERAL PRODUCT REQUIREMENTS

Units of the same type of equipment must be products of a single manufacturer. Each major component of equipment must have the manufacturer's name and address, and the model and serial number in a conspicuous place. Materials and equipment must be standard products of a manufacturer regularly engaged in the manufacturing of these and similar products. The standard products must have been in a satisfactory commercial or industrial use for two years prior to use on this project. The two year use must include applications of equipment and materials under similar circumstances and of similar size. DDC Hardware not meeting the two-year field service requirement is acceptable provided it has been successfully used by the Contractor in a minimum of two previous projects. The equipment items must be supported by a service organization. Items of the same type and purpose must be identical, including equipment, assemblies, parts and components.

2.3 OPERATION ENVIRONMENT

Provide continuous protection of components from the following conditions:

a. Pressure: Pressure conditions normally encountered in the installed

location.

b. Vibration: Vibration conditions normally encountered in the installed location.

c. Temperature:

(1) Products installed indoors: Ambient temperatures in the range of 32 to 112 degrees F and temperature conditions outside this range normally encountered at the installed location.

(2) Products installed outdoors or in unconditioned indoor spaces: Ambient temperatures in the range of -35 to +151 degrees F and temperature conditions outside this range normally encountered at the installed location.

d. Humidity: 10 to 95 percent relative humidity, noncondensing and humidity conditions outside this range normally encountered at the installed location.

2.4 WIRELESS CAPABILITY

Wireless networking is not authorized for this project as a default. Do not use any wireless communication unless approved by the ISSM which is done on a case-by-case basis. Any device with wireless communication capability is considered to be using wireless communication, regardless of whether or not the device is actively communicating wirelessly, except when wireless communication has been physically permanently disabled (such as through the removal of the wireless transceiver).

Wireless connections must follow all DoD, USN, and USMC requirements and be approved by the PWD ISSM.

2.4.1 Wireless IP Communications

Do not install wireless IP networks, including:

a. Wireless access points

b. Ad-hoc wireless networks

c. WiFi Direct communication

2.4.2 Non-IP Wireless Communication

Non-IP Wireless networking is not authorized for this project.

2.5 ELECTRICAL POWER AND CONTROL WIRING

2.5.1 Transformers

Transformers shall conform to UL 506. For control power other than terminal level equipment, provide a fuse or circuit breaker on the secondary side of each transformer.

2.5.2 Surge and Transient Protection

Provide each control cabinet with surge and transient power protection. Surge protection is not required for small terminal unit controllers such

as VAV controllers. Surge and transient protection shall consist of the following devices, installed externally to the controllers.

2.5.2.1 Power-Line Surge Protection

Provide surge suppressors on the incoming power at each direct digital controller or grouped terminal controllers and shall be installed externally to the device or devices being protected. Surge suppressors shall be rated in accordance with UL 1449, have a fault indicating light, and conform to the following:

a. The device shall be a transient voltage surge suppressor, hard-wire type individual equipment protector for 120 VAC/1 phase/2 wire plus ground.

b. The device shall react within 5 nanoseconds and automatically reset.

c. The voltage protection threshold, line to neutral, shall be no more than 211 volts.

d. The device shall have an independent secondary stage equal to or greater than the primary stage joule rating.

e. The primary suppression system components shall be pure silicon avalanche diodes.

f. The secondary suppression system components shall be silicon avalanche diodes or metal oxide varistors.

g. The device shall have an indication light to indicate the protection components are functioning.

h. All system functions of the transient suppression system shall be individually fused and not short circuit the AC power line at any time.

i. The device shall have an EMI/RFI noise filter with a minimum attenuation of 13 dB at 10 kHz to 300 MHz.

j. The device shall comply with IEEE C62.41.1 and IEEE C62.41.2, Class "B" requirements and be tested according to IEEE C62.45.

k. The device shall be capable of operating between minus 20 degrees F and plus 122 degrees F.

2.5.2.2 Communication Line Surge Protection

Provide surge and transient protection for all DDC controllers and all DDC network related devices connected to phone lines, network communication lines, lines from exterior equipment, and lines from other buildings including mechanical buildings in accordance with the following:

a. The device shall provide continuous, non-interrupting protection.

b. The protection shall react within 5 nanoseconds using only solid-state silicon avalanche technology.

c. The device shall be installed at the distance recommended by its manufacturer.

d. Include the location of the surge and transient protection devices on the control drawing network riser.

e. The device shall be located in an enclosure.

f. Surge and transient protection devices must be located at the point where the communication line exists the building and at the exterior equipment location.

2.5.3 Wiring

Provide complete electrical wiring for the DDC System, including wiring to transformer primaries. Run all control wiring in rigid or flexible conduit, metallic tubing, or covered metal raceways, unless noted otherwise. Control circuit wiring shall not run in the same conduit as power wiring over 100 volts. Circuits operating at more than 100 volts shall be in accordance with Section 26 20 00, INTERIOR DISTRIBUTION SYSTEM. Run all circuits over 100 volts in conduit, metallic tubing, covered metal raceways, or armored cable. Follow cable manufacturer's recommendations or requirements based on the cable usage, such as outdoors and/or underground.

2.5.3.1 Power Wiring

The following requirements are for field-installed wiring:

a. Wiring for 24 V circuits shall be insulated copper 18 AWG minimum and rated for 300 VAC service.

b. Wiring for 120 V circuits shall be insulated copper 12 AWG minimum and rated for 600 VAC service.

2.5.3.2 Analog Signal Wiring and Binary Wiring

Provide in accordance with control manufacturer's recommendations and the following: Field-installed analog signal wiring shall be 18 AWG single or multiple twisted pair. Each cable shall be 100 percent shielded and have a drain wire. Each wire shall have insulation rated for 300 VAC service. Cables shall have an overall aluminum-polyester or tinned-copper cable-shield tape. All binary input and output wiring shall be 18 AWG.

2.5.3.3 MS/TP Communication Bus

a. Provide system manufacturer's recommended or preferred cabling.

b. Follow cable manufacturer's recommendations or requirements based on the cable usage, such as outdoors and/or underground.

c. Splices in communication cable are not allowed. Segments of communication cable between field devices shall be solid lengths with no splices.

2.5.3.4 Conduit

Except for flexible conduit, all conduit for controls less than 100 volts shall be colored blue. All conduit to be blue must be pre-tinted by the manufacturer. Painting or wrapping of conduit is not permitted. Junction box cover plates, cable/wire trough covers, etc., for controls shall be blue. Fittings and boxes do not need to be blue. The requirement for blue

colored conduit may be waived for designated exposed areas at the discretion of BAS Owner and Public Works Department.

PART 3 EXECUTION

3.1 DESIGN REQUIREMENTS

3.1.1 Control System Drawings Title Sheet

Provide a title sheet for the control system drawing set. Include the project title, project location, contract number, the controls contractor preparing the drawings, an index of the control drawings in the set, and a legend of the symbols and abbreviations used throughout the control system drawings. The Title Block of each drawing must include the Drawing revision, i.e. Submittal, Revision 1, Revision 2, As-Built, etc., including the date.

3.1.2 List of I/O Points

Also known as a Point Schedule, provide for each input and output point physically connected to a digital controller: point name, point description, point type (Analog Output (AO), Analog Input (AI), Binary Output (BO), Binary Input (BI)), point sensor range, point actuator range, point address, BACnet object, associated BIBBS (where applicable), and point connection terminal number and cable type (18/2, 18/3, etc). Typical schedules for multiple identical equipment are allowed unless otherwise requested in design or contract criteria. All points shall adhere to the Camp Lejeune Standard naming conventions.

3.1.3 Control System Components List

Provide a complete list of control system components installed on this project. Include for each controller and device: control system schematic name, control system schematic designation, device description, manufacturer, model, part number, firmware version, serial number, physical location (e.g. Building 4, room 112 overhead), and power requirements (i.e. AC/DC voltage and power draw). For sensors, include point name, sensor range, and operating limits. For valves, include body style, Cv, design flow rate, pressure drop, valve characteristic (linear or equal percentage), and pipe connection size. For actuators, include point name, spring or non-spring return, modulating or two-position action, normal (power fail) position, nominal control signal operating range (0-10 volts DC or 4-20 milliamps), and operating limits.

3.1.4 Control System Schematics

Provide control system schematics. Typical schematics for multiple identical equipment are allowed unless otherwise requested in design or contract criteria. Include the following:

a. Location of each input and output device. Specify room number for remote devices.

b. Flow diagram for each piece of HVAC equipment.

c. Name or symbol for each control system component, such as V-1 for a valve.

d. Setpoints, with differential or proportional band values.

e. Written sequence of operation for the HVAC equipment.

f. Valve and Damper Schedules, with normal (power fail) position.

g. Control cabinet general layout, include all devices, point count, cable type (18/2, 18/3, etc), 24VAC VA power requirement for all devices including those powered from the cabinet.

3.1.5 HVAC Equipment Control Ladder Diagrams

Provide HVAC equipment control ladder diagrams. Indicate required electrical interlocks. Ladder diagram schematics shall include 120 VAC and low voltage devices in each panel. Ladder diagram schematics shall also include all field devices (sensors, relays, actuators, etc.) and any connection point to controlled equipment or devices.

3.1.6 Sequence of Operations

Provide HVAC control system sequence of operation and control logic diagrams in the same format as the Contract Drawings. Within these drawings, refer to devices by their unique identifiers. Submit sequences of operation and control logic diagrams for each HVAC system

3.1.7 Component Wiring Diagrams

Provide a wiring diagram for each type of input device and output device. Indicate how each device is wired and powered; showing typical connections at the digital controller and power supply. Show for all field connected devices such as control relays, motor starters, actuators, sensors, and transmitters.

3.1.8 Terminal Strip Diagrams

Provide a diagram of each terminal strip. Indicate the terminal strip location, termination numbers, and associated point names.

3.1.9 BACnet Communication Architecture Schematic (Network Riser)

Provide a schematic showing the project's entire BACnet communication network complete with wire sizes, including Internet Protocol (IP), Media Access Control (MAC), BACnet network, Device ID, field bus address, BBMDs, any devices using BACnet FDR, and Firmware version / Operating System, LAN devices including routers and bridges, gateways, controllers, workstations, and field interface devices. Show connection to existing networks and include the existing network in the riser diagram. Include all external network capabilities. Include surge protection device at all locations on the riser when the field controller communication trunk is leaving or entering a building and at all external equipment (such as chillers).

3.1.10 Control Panel Layout

Provide a detailed panel layout for each control panel, relay panel, etc. The layout shall include all components to be installed in the panel including controllers, terminal strips, transformers, wireway, etc.

3.2 INSTALLATION

Fully install and test the control system in accordance Section 23 09 13 INSTRUMENTATION AND CONTROL DEVICES FOR HVAC, Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS for BACnet or Niagara BACnet systems, and this Section.

Perform the installation under the supervision of competent technicians regularly employed in the installation of DDC systems. All material and equipment shall be installed in accordance with the manufacturer's recommendations for the intended purpose and NFPA 70. Maintain a copy of the manufacture's recommendations on the Contruction Site. Use the more stringent methods when manufacturer's recommendations, and plans & specification requirements differ. Use the "Preferred" method when alternative methods are given. The word "should" will be considered to mean "shall". Bring any conflicts between manufacturer's recommendations and plans and specification requirements to the Government's attention. All equipment shall be installed level and plumb.

3.2.1 Wiring Criteria

a. Run circuits operating at more than 100 volts in rigid or flexible conduit, metallic tubing, covered metal raceways, or armored cable.

b. Run all control wiring in blue rigid or flexible conduit, blue metallic tubing, or covered metal raceways, unless noted otherwise. All control wiring located inside mechanical rooms shall be in conduit or metallic tubing. All conduit and junction box covers, cable/wire trough covers, etc., shall be blue in color.

c. Do not run binary control circuit wiring in the same conduit as power wiring over 100 volts. Where analog signal wiring requires conduit, do not run in the same conduit with AC power circuits or control circuits operating at more than 100 volts.

d. Provide circuit and wiring protection required by NFPA 70.

e. Minimum conduit size is 3/4-inch. Maximum conduit fill is 40% or the cable manufacturer's recommended amount, whichever is less. Provide insulated throat at all conduit terminations to protect wiring from burrs. Support conduit by pipe straps, wall brackets, threaded rod conduit hangers, or ceiling trapeze. Plastic cable ties are not acceptable. Fasten by wood screws to wood; by toggle bolts on hollow masonry units; by concrete inserts or expansion bolts on concrete or brick; and by machine screws, welded threaded studs, or spring-tension clamps on steel work. Threaded C-clamps may be used on rigid steel conduit only. Do not weld conduits or pipe straps to steel structures. Do not exceed one-fourth proof test load for load applied to fasteners. Provide vibration resistant and shock-resistant fasteners attached to concrete ceiling. The use of masonry screws to support conduit is not permitted.

f. Do not bury aluminum-sheathed cable or aluminum conduit in concrete.

g. Input/output identification: Permanently label each field-installed wire, cable, and pneumatic tube at each end with descriptive text using a commercial wire marking system, minimum 9 point font. Labels shall fully encircle the wire, cable, or tube. The single line text shall run parallel to the wire, cable, or tube and shall be repeated

so as to be viewable without twirling or twisting the wire. Locate the markers within 2 inches of each termination. Label shall include type of network and destination of cable (ex. BACnet/AHU-1). Match the names and I/O number to the project's point list. Similarly label all power wiring serving control devices, including the word "power" and panel board and circuit number, or transformer location in the label. Number each pneumatic tube every six feet. Label all terminal blocks with alpha/numeric labels. All wiring and the methods shall be in accordance with UL 508A.

h. Permanently display controller wiring diagram for each controller on the inside of the control cabinet door. Diagram shall be neatly lettered and taped or adhered with sticky back label.

i. Conduit identification: All conduits shall be labeled within 36 inches from terminations, boxes, bends or wall penetrations. Labels shall be 3/8 inches bold black lettering on white background and indicate what system the conduit contains. Apply labels every 10 feet of line of sight or a distance agreed upon by Camp Lejeune Public Works Department. Provide label for each side of a wall pentration by the conduit. The agreed upon distance shall be for a single building or project only. Label shall be visible and legible, while standing on the floor, from up to three sides with a minimum dimension of 1.9 inches x 4 inches. Conduit that includes power circuits shall be labeled with source panel and circuit, and destination cabinet or equipment. When MSTP is installed within conduit, label conduit with trunk number and to and from device (ie. MSTP-01 From VAV 1-1 to VAV 1-2).

Provide a label at each control panel on the 120 VAC conduit. The label shall contain the source panel and circuit identifier.

Label Example: SF-C, SF-S, SF-O (3 cables, Supply Fan Command, Supply Fan Status, Supply Fan Output).

Label Example: ZN-T/ZN-H/ZN-Q (1 cable, Zone Temperature, Zone Humidity, Zone Quality).

j. Each terminal device shall have its own terminal conduit run. Device boxes or devices or panels shall not be used as "pass thru" for wiring.

k. Conduit to equipment and devices shall be run tight to walls, and ceilings. Avoid conduit on the floor, i.e. conduit shall not block access to or past equipment. Flex conduit is to be used only when EMT or rigid conduit is not able to satisfy the application such as a transition to a sensor or equipment. Flex conduit shall be limited to a maximum length of 3 ft.

l. For controller power, provide new 120 VAC circuits, with ground if not defined on the electrical drawings. Provide each circuit with a dedicated breaker, and run wiring in its own conduit, separate from any control wiring. Connect the controller's ground wire to the electrical panel ground; conduit grounds are not acceptable. Include a label on the 120 VAC circuit conduit at each control panel. The label is to include the source panel and circuit identification. The label size shall be a minimum of 1.9 inches by 4 inches, 3/8 inch black lettering on white background.

m. Supervisory Building Controllers (SBC) shall be powered from a

dedicated transformer for the SBC only. Each control cabinet shall have a dedicated 24 volt transformer. The 120 VAC power branch circuit shall be dedicated to the DDC control system. Factory provided transformers in equipment must be used as a source of power only for the control devices intended by the equipment manufacturer.

n. Surge Protection: Install surge protection according to manufacturer's instructions. Multiple controllers fed from a common power supply may be protected by a common surge protector, properly sized for the total connected devices.

o. All terminations in panels shall be made at a terminal block if not connected directly to a panel device, ie Field Controller, Supervisory Controller, relays, transmitters, etc. No wire nuts are allowed in panels, VAV boxes, control panels, relay panels, raceways, or any other type of enclosure shall follow this requirement. High and low voltage wires must not land on the same terminal block unless they are separated and of a different color and/or clearly identified.

p. Grounding: Ground controllers and cabinets to a good earth ground as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Conduit grounding is not acceptable; all grounding shall have a direct path to the building earth ground. Ground sensor drain wire shields at the controller end.

q. The Contractor shall be responsible for correcting all associated MS/TP and SA bus wiring, auxiliary bus wiring, termination, end of line, and ground loop problems.

r. Run wiring in panel enclosures in covered wire track.

s. Control cabinets, wiring boxes, cable/wiring troughs, panel enclosures, etc., must be clean of all debris, metal shavings, etc.

t. Low voltage cable must not be supported directly from "all thread" rod. If cabling/wiring is permitted to be run without conduit/raceway it must be supported using a retaining device such as a bridle ring or J hook, and where appropriate connected to the all thread rod using a standoff device. Openly installed cabling/wiring must be approved by Camp Lejeune Public Works Department.

u. For serviceability, allow a minimum of 2 inches of exposed wire or cable from any termination point, i.e. between wireway and field controller terminations.

v. Wireway inside panels and junction boxes shall be maximum 40% filled.

3.2.2 Accessibility

Install all equipment so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible. Install digital controllers, data ports, and concealed actuators, valves, dampers, air flow stations and like equipment in locations freely accessible through access doors. Install power surge protection such that it is replaceable without removing other components.

3.2.3 Component Identification Labeling

Using an electronic hand-held label maker with white tape and bold black

block lettering, provide an identification label on the exterior of each new control panel, control device, actuator, and sensor. Also provide labels on the exterior of each new control actuator indicating the (full) open and (full) closed positions. For labels located outdoors, use exterior grade label tape, and provide labels on both the inside and outside of the panel door or device cover. Acceptable alternatives are white plastic labels with engraved bold black block lettering permanently attached to the control panel, control device, actuator, and sensor. Have the labels and wording approved by the BAS Owner prior to installation. Devices with field adjustable setpoints, such as Air Filter Status, Duct Pressure Safety Limit, etc., must have the field adjusted setpoint and date included on the label. Components mounted above a ceiling or service hatch must also have the component identification visible from below. Examples: "A VAV controller, exhaust fan relay, Differential Pressure Transmitter, etc., identification would be included on the ceiling grid, or service hatch, in the area of the controller or field device." Supervisory Controller: Provide a removable label (not permanent marker) with the Global ID(s), IP Address and all login credentials. Niagara JACE should include login credentials for both the Station and Platform.

3.2.4 Network Communication Lines

Network connections by the Government are required for each new supervisory controller back to the telecom room. Provide the Contracting Officer at least 120 days advance notice of need. Provide one inch conduit and two(2) green Cat 6 cables from the point of connection of the BAS to the point of connection to the MCEN (most likely in the telephone equipment room). The conduit for these runs MCEN homeruns shall be the only controls conduit that is not blue in color. For each run, provide an additional 20 feet of extra cable, coiled up in the telecom closet. Cables must be terminated and tested.

3.2.5 Dielectric Isolation

Provide dielectric isolation where dissimilar metals are used for connection and support. Install control system in a matter that provides clearance for control system maintenance by maintaining access space required to calibrate, remove, repair, or replace control system devices. Install control system such that it does not interfere with the clearance requirements for mechanical and electrical system maintenance.

3.2.6 Penetrations in Building Exterior

Make all penetrations through and mounting holes in the building exterior watertight.

3.3 TEST AND BALANCE SUPPORT

The controls contractor shall coordinate with and provide on-site support to the test and balance (TAB) personnel specified under Section 23 05 93 TESTING, ADJUSTING AND BALANCING. This support shall include:

a. On-site operation and manipulation of control systems during the testing and balancing.

b. Control setpoint adjustments for balancing all relevant mechanical systems, including VAV boxes.

c. Tuning control loops and sensors with setpoints and adjustments determined by TAB personnel.

3.4 INTERFACE WITH EXISTING EMCS

Provide 16 hours of assistance to the Government with interfacing the BAS to the Base wide EMCS. The Government will make the final connection of the BAS to the MCEN. This 16 hours does not include completion or corrections to the installed BAS as defined in the contract documents. This 16 hours is for assisting the interface and for making revisions to the BAS that may be needed outside of the contract requirements. Approved As-Build control drawings must be available for the EMCS operator performing the interacing. Graphics shall be created prior to interface with existing EMCS.

3.5 CONTROLS SYSTEM OPERATORS MANUALS

Provide four electronic and printed copies of a Controls System Operators Manual. Manual copies must be placed in the following locations:

a. Submitted to the ROICC.

b. On the submitted and approved notebook computer.

c. In the storage cabinet.

d. Delievered to the BAS Owner.

The manual shall be specific to the project, written to actual project conditions, and provide a complete and concise depiction of the installed work. Provide information in detail to clearly explain all operation requirements for the control system.

Provide with each manual: CDs of the project's control system drawings, control programs, data bases, graphics, and all items listed below. Include gateway back-up data and configuration tools where applicable. Provide CDs in jewel case with printed and dated project-specific labels on both the CD and the case. For text and drawings, use Adobe Acrobat or MS Office file types. When approved by the Government, AutoCAD and Visio files are allowed. Give files descriptive English names and organize in folders.

Provide printed manuals in sturdy 3-ring binders with a title sheet on the outside of each binder indicating the project title, project location, contract number, and the controls contractor name, address, and telephone number. Each binder shall include a table of contents and tabbed dividers, with all material neatly organized. Manuals shall include the following:

a. A copy of the as-built control system (shop) drawings set, with all items specified under the paragraph SUBMITTALS. Indicate all field changes and modifications. As-Built Control Drawings shall be marked "As-Built" on the cover page and in the title block of each page. Revisions must be dated, may be hand or CAD annotated.

b. A copy of the project's mechanical design drawings, including any official modifications and revisions.

c. A copy of the project's approved Product Data submittals provided under the paragraph SUBMITTALS.

d. A copy of the project's approved Equipment Supplier's PVT Plan, Controls Contractor's PVT Plan, and PVT Report.

e. A copy of the project's approved final TAB Report.

f. Printouts of all control system programs, including controller setup pages if used. Include plain-English narratives of application programs, flowcharts, and source code.

g. Printouts of all physical input and output object properties, including tuning values, alarm limits, calibration factors, and set points.

h. A table entitled "AC Power Table" listing the electrical power source for each controller. Include the building electrical panel number, panel location, and circuit breaker number.

i. The DDC manufacturer's hardware and software manuals in both print and CD format with printed project-specific labels. Include installation and technical manuals for all controller hardware, operator manuals for all controllers, programming manuals for all controllers, operator manuals for all workstation software, installation and technical manuals for the workstation and notebook, and programming manuals for the workstation and notebook software.

j. A list of qualified control system service organizations for the work provided under this contract. Include their addresses and telephone numbers.

k. A written statement entitled "Technical Support" stating the control system manufacturer or authorized representative will provide toll-free telephone technical support at no additional cost to the Government for a minimum of two years from project acceptance, will be furnished by experienced service technicians, and will be available during normal weekday working hours. Include the toll-free technical support telephone number.

l. A written statement entitled "Software Upgrades" stating software and firmware patches and updates will be provided upon request at no additional cost to the Government for a minimum of two years from project acceptance. Include a table of all DDC system software and firmware provided under this contract, listing the original release dates, version numbers, part numbers, and serial numbers.

m. Submit any and all updated field controller files, and BACnet Building Controller data base during the acceptance and warranty periods or as a result of a latent defect. Include in Warranty Information.

3.5.1 Storage Cabinets

In each mechanical room provide a wall-mounted storage cabinet with hinged doors. In addition to the number of manuals specified above, provide an additional copy of the manuals in this mechanical room storage cabinet. Provide cabinets large enough to hold the entire set of Controls System Operators Manuals, and the HVAC operation and maintenance manuals provided under Division 23 Heating, Ventilating, and Air Conditioning. Locate cabinets adjacent to DDC control panels where applicable. Have each cabinet's proposed installation site approved in advance by the

Contracting Officer and the BAS Owner. Prominently label each cabinet with the wording "OPERATION AND MAINTENANCE MANUALS." Prominently label each binder with the wording "MECHANICAL ROOM COPY - DO NOT REMOVE."

3.6 PERFORMANCE VERIFICATION TESTING

3.6.1 General

The PVT must demonstrate compliance of the control system work with the contract requirements. The PVT shall be performed by the Controls Contractor and Equipment Suppliers. If the project is phased, provide separate testing for each phase.

3.6.2 PVT and Commissioning

PVT testing is a Government quality assurance function that includes systems trending and field tests. Commissioning is a quality control function that is the Commissioning Team’s responsibility to the extent required by this contract.

3.6.3 PVT of Equipment with Packaged Controls

Controls Contractor and Equipment Supplier(s) must share and coordinate PVT testing responsibilities for equipment provided with on-board factory packaged controls such as boiler controllers, dedicated outside air systems (DOAS’s), and packaged pumping systems.

3.6.3.1 Controls Contractor Responsibilities

The Controls Contractor must provide a PVT Plan separate from Equipment Supplier's Performance Verification Testing Plan and perform PVT testing concurrent with Equipment Suppliers’ testing for equipment provided with on-board factory packaged controls to demonstrate the following:

a. Equipment enabling and disabling.

b. Equipment standard and optional control points necessary to accomplish functionality regardless if specified in contract documents or not.

c. Equipment standard and optional alarms critical to safe operation regardless if specified in contract documents or not.

d. All control points added by Controls Contractor in addition to onboard factory packaged controls regardless if specified in contract documents or not.

3.6.3.2 Equipment Supplier Responsibilities

Each Equipment Supplier must provide PVT Plans separate from Controls Contractor’s Performance Verification Testing Plan and perform PVT testing concurrent with Controls Contractor’s testing for their equipment provided with on-board factory packaged controls to demonstrate the following:

a. Equipment standard and optional control features necessary to accomplish functionality regardless if specified in contract documents or not.

b. Equipment standard and optional operation modes necessary to accomplish functionality regardless if specified in contract documents

or not.

c. Equipment standard and optional alarm conditions for safe operation regardless if specified in contract documents or not.

3.6.4 Sensor Accuracy Checks

Include a one-point accuracy check of each sensor in the PVT procedures.

3.6.5 Performance Verification Testing Plan

Submit a detailed PVT Plan of the proposed testing for Government approval. Develop the PVT Plan specifically for the control system and equipment with packaged controls in this contract. The PVT Plan shall be a clear list of test items arranged in a logical sequence. It shall include each and all sequences of all controllers. Include sequence tested, intended test procedure, required assisted personnel (such as the mechanical contractor), the expected response, and the pass/fail criteria for every component tested. Include pass/fail column for test, and space for comments, signature and date lines for Contractor's PVT administrator and Contractor's QA representative. The PVT plan shall include the prescriptive pre-PVT check list in addition to the Contractor generated controller specific testing sequences. Propose criteria for the trends, i.e., change of state, change of value with the trigger value, time intervals in the PVT Plan submission for approval. Prepare the following PVT plans:

a. Control Contractor's Performance Verification Testing Plan

b. Equipment Supplier's Performance Verification Testing Plan

3.6.6 PVT Sample Size

Test all controllers unless otherwise directed.

3.6.7 Control Contractor's Pre-PVT Checklist

Submit the following as a part of the PVT Plan and the PVT Report. Each item shall include a column for the Contractor's initial/date. This form may be a general form applicable to all controllers and submitted only once in the PVT Plan. Each controller shall have an individual checklist with controller title and identified in the PVT Report.

a. Verify all mechanical installation work is successfully completed and started up by the appropriate personnel.

b. Verify all required control system components, wiring, and accessories are installed.

c. Verify the installed control system architecture matches approved drawings.

d. Verify all control circuits operate at the proper voltage and are free from grounds or faults.

e. Verify all required surge protection is installed.

f. Verify the A/C Power Table specified in the paragraph CONTROLS SYSTEM OPERATORS MANUALS is accurate.

g. Verify all DDC network communications function properly, including uploading and downloading programming changes.

h. Verify each digital controller’s programming is backed up.

i. Verify all wiring, components, and panels are properly labeled.

j. Verify all required points are programmed into devices.

k. Verify all valve and actuator zero and span adjustments are set properly. List each device and span for that device. label device with span setting and adjustment date.

l. Verify all sensor readings are accurate and calibrated. List each sensor, sensor reading, and measured value. Label device with calibrated value and the calibration date.

m. Verify each control valve and actuator goes to normal position upon loss of power. List each device and normal position.

n. Verify each controller works properly in stand-alone mode by disconnecting the BACnet bus.

3.6.8 Conducting PVT

a. Conduct PVT after approval of the PVT Plan. Notify the Contracting Officer of the planned PVT at least 15 days prior to testing. Provide an estimated time table required to perform the testing. Furnish personnel, equipment, instrumentation, and supplies necessary to perform all aspects of the PVT. Ensure that testing personnel are regularly employed in the testing and calibration of DDC systems. Using the project's as-built control system (shop) drawings, the project's mechanical design drawings, and the approved PVT Plan, conduct the PVT.

b. During testing, identify any items that do not meet the contract requirements and if time permits, conduct immediate repairs and re-test. Otherwise, deficiencies shall be investigated, corrected, and re-tested later. Document each deficiency and corrective action taken.

c. If re-testing is required, follow the procedures for the initial PVT. The Government may require re-testing of any control system components affected by the original failed test.

3.6.9 Controller Capability and Labeling

Test the following for each controller:

a. Memory: Demonstrate that programmed data, parameters, and trend/ alarm history collected during normal operation is not lost during power failure.

b. Direct Connect Interface: Demonstrate the ability to connect directly to each type of digital controller with a portable electronic device like a notebook computer or PDA. Show that maintenance personnel interface tools perform as specified in the manufacturer's technical literature.

c. Stand Alone Ability: Demonstrate controllers provide stable and reliable stand-alone operation using default values for values normally read over the network.

d. Wiring and AC Power: Demonstrate the ability to disconnect any controller safely from its power source using the AC Power Table. Demonstrate the ability to match wiring labels easily with the control drawings. Demonstrate the ability to locate a controller's location using the BACnet Communication Architecture Schematic and floor plans.

e. Nameplates and Tags: Show the nameplates and tags are accurate and permanently attached to control panel doors, devices, sensors, and actuators.

3.6.10 Workstation and Software Operation

For every user workstation or notebook provided:

a. Show points lists agree with naming conventions.

b. Show that graphics are complete.

c. Show the UPS operates as specified.

3.6.11 BACnet Communications and Interoperability Areas

a. Data Presentation: On each BACnet Operator Workstation, demonstrate graphic display capabilities.

b. Reading of Any Property: Demonstrate the ability to read and display any used readable object property of any device on the network.

c. Setpoint and Parameter Modifications: Show the ability to modify all setpoints and tuning parameters in the sequence of control or listed on project schedules. Modifications are made with BACnet messages and write services initiated by an operator using workstation graphics, or by completing a field in a menu with instructional text.

d. Peer-to-Peer Data Exchange: Show all BACnet devices are installed and configured to perform BACnet read/write services directly (without the need for operator or workstation intervention), to implement the project sequence of operation, and to share global data.

e. Alarm and Event Management: Show that alarms/events are installed and prioritized according to the BAS Owner. Demonstrate time delays and other logic is set up to avoid nuisance tripping, e.g., no status alarms during unoccupied times or high supply air during cold morning start-up. Show that operators with sufficient privilege can read and write alarm/event parameters for all standard BACnet event types. Show that operators with sufficient privilege can change routing (BACnet notification classes) for each alarm/event including the destination, priority, day of week, time of day, and the type of transition involved (types of transition include but are not limited to the following: TO-OFF NORMAL and TO-NORMAL).

f. Schedule Lists: Show that schedules are configured for start/stop, mode change, occupant overrides, and night setback as defined in the sequence of operations.

g. Schedule Display and Modification: Show the ability to display any schedule with start and stop times for the calendar year. Show that all calendar entries and schedules are modifiable from any connected workstation by an operator with sufficient privilege.

h. Archival Storage of Data: Show that data archiving is handled by the operator workstation/server, and local trend archiving and display is accomplished with BACnet Trend Log objects.

i. Modification of Trend Log Object Parameters: Show that an operator with sufficient privilege can change the logged data points, sampling rate, and trend duration.

j. Device and Network Management: Show the following capabilities:

(1) Display of Device Status Information

(2) Display of BACnet Object Information

(3) Silencing Devices that are Transmitting Erroneous Data

(4) Time Synchronization

(5) Remote Device Reinitialization

(6) Backup and Restore Device Programming and Master Database(s)

(7) Configuration Management of Half-Routers, Routers and BBMDs

3.6.12 Execution of Sequence of Operation

Demonstrate that the HVAC system operates properly through the complete sequence of operation. Use read/write property services to globally read and modify parameters over the internetwork.

3.6.13 Control Loop Stability and Accuracy

For all control loops tested, give the Government trend graphs of the control variable over time, demonstrating that the control loop responds to a 20 percent sudden change of the control variable set point without excessive overshoot and undershoot. If the process does not allow a 20 percent set point change, use the largest change possible. Show that once the new set point is reached, it is stable and maintained. Control loop trend data shall be in real-time with the time between data points 30 seconds or less.

3.6.14 Performance Verification Testing Report

Upon successful completion of the PVT and prior to the Government taking use and possession of the facility, submit a single PVT Report to the Government. Do not submit the report until all problems are corrected and successfully re-tested. The report shall include the annotated PVT Plan used during the PVT. Where problems were identified, explain each problem and the corrective action taken. Include a written certification that the installation and testing of the control system is complete and meets all of the contract's requirements.

3.6.15 PVT Acceptance Testing Season One

Season 1 is determined by the outdoor conditions that are occurring once the project HVAC and DDC controls are initially completed and ready for PVT. Conversely, Season 2 is defined as the opposite outdoor conditions from Season 1. Season 1 could be either the season of maximum heating load, or the season of maximum cooling load. The season of maximum cooling load is the time of year when the outdoor temperature at the project site remains above 85 degrees Fahrenheit dry bulb and 76 degress Fahrenheit wet bulb for at least 8 consecutive hours during the period of DDC data recording. The season of maximum cooling load shall fall within June, July, August, or September. The Season of maximum heating load is the time of year when the outdoor temperature at the project site remains below 45 degrees Fahrenheit for at least 8 consecutive hours during the period of DDC data recording.

After acceptance of the PVT Report and Trends, demonstrate proper and stable operation of the DDC System. Contractor shall provide minimum fifteen days notice to COTR and BAS Owner when scheduling field acceptance testing. During the field acceptance testing, verify, in the presence of the COTR and BAS owner, random selections of sequences reported in the PVT Report. Equipment, controllers, devices, and sequences for field acceptance testing are to be selected by the COTR. As-built control drawings must be for use and verification at acceptance testing. Field acceptance testing includes verification of the PVT for the following equipment groups:

Group 1: All pumps, chillers, boilers, return fans, computer room units, and air handling units (rooftop and central stations).

Group 2: 50 percent of terminals such as VAV and fan coil units.

Group 3: 100 percent of supply fans, and exhaust fans.

If any of the acceptance testing is found to not operate correctly, terminate verification for the given group. Make the necessary corrections and prepare a revised PVT Report and Trends. Reschedule acceptance testing of the revised report with the COTR. After successful field acceptance testing, submit the revised controller files and BACnet Building Controller database within 15 calendar days.

3.6.16 PVT Acceptance Testing Season 2

A minimum of 3 months after initial acceptance of the DDC system and in the opposite season of heating and cooling, demonstrate proper and stable operation of the DDC system. Contractor shall provide minimum fifteen days notice to COTR and BAS Owner when scheduling field acceptance testing. During the field acceptance testing, verify, in the presence of the COTR and BAS owner, random selections of sequences reported in the PVT Report. Equipment, controllers, devices, and sequences for field acceptance testing are to be selected by the COTR. Field acceptance testing includes verification of the PVT for the following equipment groups:

Group 1: All pumps, chillers, boilers, return fans, computer room units, and air handling units (rooftop and central stations).

Group 2: 50 percent of terminals such as VAV and fan coil units.

Group 3: 100 percent of supply fans, and exhaust fans.

If any of the acceptance testing is found to not operate correctly, terminate verification for the given group. Make the necessary corrections and prepare a revised PVT Report. Reschedule acceptance testing of the revised report with the COTR. After successful field acceptance testing, submit the revised controller files and BACnet Building Controller database within 15 calendar days.

3.6.17 Prerequisite for Approval

Compliance with the field acceptance testing requirements of this section is a prerequisite for the final Contracting Officer approval of the PVT Report submitted.

3.7 TRENDS

Trends shall be reported on all points requiring trending as indicated on contract drawings. Trends shall be reported on all central plant equipment and primary air handling unit controllers, and all terminal controllers such as VAV boxes and fan coil units. Include 72 hour trends during which the system is operated continuously. Data from all points must be from a single consecutive 72 hour period without any gaps in time Monday through Friday. Data may not be from Saturday or Sunday unless prior written authorization is obtained from the Contracting Officer.

Unless trending capability exists within the building control system, temporarily install hardware on the building control network to perform trending. Remove the temporary hardware at the completion of all acceptance activities.

Use the building control system Niagara Trend Log Objects to trend all points shown as requiring a trend on the Point Schedule for the entire trending period.

If resubmission is required, all points must be trended. Partial trends will not be accepted.

Additional trends or points shall be provided if requested by Camp Lejeune or a commissioning agent.

Trends shall demonstrate stable operation of the PID loop controls and ability to maintain all temperatures within +/- 1.0 degree F of setpoint. Any alarms that activate during the trending period will result in trend data disapproval regardless of the cause of the alarm.

3.7.1 Trend Report Format

Trend data must be submitted in Microsoft Excel (.xlsx) format. Mutiple workbooks are acceptable, but trend data must be grouped and formatted as follows:

a. Column A on every worksheet must contain the date (MM/DD/YYYY) and time (HH:MM:SS) on every row containing data.

b. For every point, row 1 shall contain the point name (see Attachment 2). Row 2 shall contain the corresponding point name as given on the contract drawings. Row 3 shall contain the unit of measure.

c. All chilled water equipment (e.g. chiller, pumps, etc.) shall be on a

single worksheet.

d. All heating hot water equipment (e.g. boilers, pumps, etc.) shall be on a single worksheet.

e. All domestic hot water equipment (e.g. water heater, recirculation pump, etc.) shall be on a single worksheet.

f. All unitary exhaust fans shall be on a single worksheet.

g. Each central piece of equipment (e.g. AHU, DOAS, RTU, etc.) shall be on its own worksheet.

h. Terminal units such as VAV's and Fan Coil Units shall be grouped by the central unit source and shall be on a single worksheet.

i. Packaged terminal air conditioners or heat pumps shall be grouped by floor and shall be on a single worksheet.

j. VRF units shalled be grouped by branch box serving the fan coils and shall be on a single worksheet.

Trend data from the groups described above must be on separate worksheets. Do not mix equipment from the described groups on a single worksheet.

3.8 BUS WAVEFORM REPORT

3.8.1 Bus Waveform Report

Provide printed waveform of the MS/TP bus(es) after all devices are online and operational. Use an oscilloscope to test and record the wave form of each bus segment complete with graphic scale. This waveform is useful in identifying and troubleshooting bus problems such as inappropriate taps, grounds, end of line terminations and poor connections. Identify each waveform graphic with bus segment name/number, location/building, date and time, and instrument used. Include the resistor sizes needed at each Bus End of Line (EOL). Include a list of the EOL devices. Waveform must be field verified by the BAS Owner prior to BOD.

3.8.2 Bus Waveform Field Acceptance Testing

Contractor shall provide minimum fifteen days notice to COTR and BAS Owner when scheduling field verification. During the field acceptance testing, verify, in the presence of the COTR, the bus waveform. If the bus waveform does not match the report, terminate field acceptance testing. Make the necessary corrections and prepare a revised Bus Waveform Report. Reschedule acceptance testing of the revised report data with the COTR.

3.8.3 Prerequisite for Approval

Compliance with the field acceptance testing requirements of this section is a prerequisite for the final Contracting Officer approval of the Bus Waveform Report submitted.

3.9 TRAINING REQUIREMENTS

Provide a qualified instructor (or instructors) with two years minimum field experience with the installation and programming of similar BACnet DDC systems. Orient training to the specific systems installed.

Coordinate training times and location with the Contracting Officer and BAS Owner after receiving approval of the training course documentation. Training shall take place at the job site or a nearby Government-furnished location. A training day shall occur during normal working hours, last no longer than 8 hours and include a one-hour break for lunch and two additional 15-minute breaks. The project's approved Controls System Operators Manual shall be used as the training text. The Contractor shall ensure the manuals are submitted, approved, and available to hand out to the trainees before the start of training.

3.9.1 Training Documentation

Submit training documentation for review 30 days minimum before training. Documentation shall include an agenda for each training day, objectives, a synopses of each lesson, and the instructor's background and qualifications. The training documentation can be submitted at the same time as the project's Controls System Operators Manual.

3.9.2 Phase I Training - Fundamentals

The Phase I training session shall last one day and be conducted in a classroom environment with complete audio-visual aids provided by the contractor. Provide each trainee a printed 8.5 by 11 inch hard-copy of all visual aids used. Upon completion of the Phase I Training, each trainee should fully understand the project's DDC system fundamentals. Approved As-Built control drawings must be used for training. The training session shall include the following:

a. BACnet fundamentals (objects, services, addressing) and how/where they are used on this project.

b. This project's list of control system components.

c. This project's list of points and objects.

d. This project's device and network communication architecture.

e. This project's sequences of control.

f. Alarm capabilities.

g. Trending capabilities.

h. Troubleshooting communication errors.

i. Troubleshooting hardware errors.

3.9.3 Phase II Training - Operation

Provide Phase II Training shortly after completing Phase I Training. The Phase II training session shall last one day and be conducted at the DDC system workstation, at a notebook computer connected to the DDC system in the field, and at other site locations as necessary. Upon completion of the Phase II Training, each trainee should fully understand the project's DDC system operation. The training session shall include the following:

a. A walk-through tour of the mechanical system and the installed DDC components (components include but are not limited to the following: controllers, valves, dampers, surge protection, switches, thermostats,

and sensors).

b. A discussion of the components and functions at each DDC panel.

c. Logging-in and navigating at each operator interface type.

d. Using each operator interface to find, read, and write to specific controllers and objects.

e. Modifying and downloading control program changes.

f. Modifying setpoints.

g. Creating, editing, and viewing trends.

h. Creating, editing, and viewing alarms.

i. Creating, editing, and viewing operating schedules and schedule objects.

j. Backing-up and restoring programming and data bases.

k. Modifying graphic text, backgrounds, dynamic data displays, and links to other graphics.

l. Creating new graphics and adding new dynamic data displays and links.

m. Alarm and Event management.

n. Adding and removing network devices.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 09 13

INSTRUMENTATION AND CONTROL DEVICES FOR HVAC
02/25 MCBCL

PART 1 GENERAL

1.1 SUMMARY

This section provides for the instrumentation control system components excluding direct digital controllers, network controllers, gateways, etc. that are necessary for a completely functional automatic control system. When combined with a Direct Digital Control (DDC) system, the Instrumentation and Control Devices covered under this section must be a complete system suitable for the control of the heating, ventilating and air conditioning (HVAC), plumbing, and other building-level systems as specified and indicated.

a. Install hardware to perform the control sequences as specified and indicated and to provide control of the equipment as specified and indicated.

b. Install hardware such that individual control equipment can be replaced by similar control equipment from other equipment manufacturers with no loss of system functionality.

c. Install and configure hardware such that the Government or their agents are able to perform repair, replacement, and upgrades of individual hardware without further interaction with the installing Contractor.

1.1.1 Verification of Dimensions

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

1.1.2 Drawings

The Government will not indicate all offsets, fittings, and accessories that may be required on the drawings. Carefully investigate the mechanical, electrical, plumbing, and finish conditions that could affect the work to be performed, arrange such work accordingly, and provide all work necessary to meet such conditions.

1.2 RELATED SECTIONS

Related work specified elsewhere.

Section 01 30 00 ADMINISTRATIVE REQUIREMENTS

Section 23 30 00 HVAC AIR DISTRIBUTION

Section 23 21 13.00 20 LOW TEMPERATURE WATER (LTW) HEATING SYSTEM

Section 23 64 26 CHILLED WATER PIPING SYSTEMS

Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM

1.3 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL, INC. (AMCA)

AMCA 500-D	(2018) Laboratory Methods of Testing Dampers for Rating

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.34	(2021) Valves - Flanged, Threaded and Welding End
ASME B16.5	(2020) Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard

ASTM INTERNATIONAL (ASTM)

ASTM A126	(2004; R 2023) Standard Specification for Gray Iron Castings for Valves, Flanges, and Pipe Fittings

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 90A	(2024) Standard for the Installation of Air Conditioning and Ventilating Systems
NFPA 72	(2025; TIA 25-1; TIA 25-2; TIA 25-3; TIA 25-4; ERTA 25-1; ERTA 25-2) National Fire Alarm and Signaling Code

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1966	(2020) HVAC Duct Construction Standards Metal and Flexible, 4th Edition

1.4 SUBMITTALS

Submit detailed and annotated manufacturer's data, drawings, and specification sheets for each item listed, that clearly show compliance with the project specifications.

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Sensors And Input Hardware; G

Output Hardware; G

Duct Smoke Detectors; G

Variable Frequency (Motor) Drives; G

SD-06 Test Reports

Vfd Start-Up Test Documentation; G

SD-10 Operation and Maintenance Data

Comply with requirements for data packages in Section 01 78 23 OPERATION AND MAINTENANCE DATA and in Section 01 78 24.00 20 FACILITY ELECTRONIC OPERATION AND MAINTENANCE SUPPORT INFORMATION (eOMSI), except as supplemented and modified in this specification.

Vfd Service Manuals; G, Data Package 4

1.5 QUALITY ASSURANCE

Quality Assurance requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

1.6 DELIVERY, STORAGE, AND HANDLING

Delivery, storage, and handling requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

PART 2 PRODUCTS

2.1 EQUIPMENT

2.1.1 General Requirements

All products used to meet this specification must meet the indicated requirements, but not all products specified here will be required by every project. All products must meet the requirements both Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC and this Section.

2.1.2 Operation Environment Requirements

Unless otherwise specified, provide products rated for continuous operation under the following conditions:

2.1.2.1 Pressure

Pressure conditions normally encountered in the installed location.

2.1.2.2 Vibration

Vibration conditions normally encountered in the installed location.

2.1.2.3 Temperature

a. Products installed indoors: Ambient temperatures in the range of 32 to 112 degrees F and temperature conditions outside this range normally

encountered at the installed location.

b. Products installed outdoors or in unconditioned indoor spaces: Ambient temperatures in the range of -35 to +151 degrees F and temperature conditions outside this range normally encountered at the installed location.

2.1.2.4 Humidity

10 to 95 percent relative humidity, non-condensing and also humidity conditions outside this range normally encountered at the installed location.

2.2 WIRELESS CAPABILITY

Wireless capability requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

2.3 SENSORS AND INPUT HARDWARE

Coordinate sensor types with the BAS Owner to keep them consistent with existing installations.

2.3.1 Field-Installed Temperature Sensors

Where feasible, provide the same sensor type throughout the project. Avoid using transmitters unless absolutely necessary.

2.3.1.1 Thermistors

Precision thermistors may be used in applications below 200 degrees F. Sensor accuracy over the application range shall be 0.36 degree F or less between 32 to 150 degrees F. Stability error of the thermistor over five years shall not exceed 0.25 degrees F cumulative. A/D conversion resolution error shall be kept to 0.1 degrees F. Total error for a thermistor circuit shall not exceed 0.5 degrees F.

2.3.1.2 Resistance Temperature Detectors (RTDs)

Provide RTD sensors with platinum elements compatible with the digital controllers. Encapsulate sensors in epoxy, series 300 stainless steel, anodized aluminum, or copper. Temperature sensor accuracy shall be 0.1 percent (1 ohm) of expected ohms (10k ohms) at 32 degrees F. Temperature sensor stability error over five years shall not exceed 0.25 degrees F cumulative. Direct connection of RTDs to digital controllers without transmitters is preferred. When RTDs are connected directly, lead resistance error shall be less than 0.25 degrees F. The total error for a RTD circuit shall not exceed 0.5 degrees F.

2.3.1.3 Temperature Sensor Details

a. Room Type: Provide the sensing element components within a decorative protective cover suitable for surrounding decor. Provide room temperature sensors with timed override button and setpoint adjustment lever.

b. Duct Probe Type: Ensure the probe is long enough to properly sense the air stream temperature.

c. Duct Averaging Type: Continuous averaging sensors shall be one foot in length for each 4 square feet of duct cross-sectional area, and a minimum length of 6 feet.

d. Pipe Immersion Type: Provide minimum three-inch immersion. Provide each sensor with a corresponding pipe-mounted sensor well, unless indicated otherwise. Sensor wells shall be stainless steel when used in steel piping, and brass when used in copper piping. Provide the sensor well with a heat-sensitive transfer agent between the sensor and the well interior.

e. Outside Air Type: Provide the sensing element on the building's north side with a protective weather shade that positions the sensor approximately 3 inches off the wall surface, does not inhibit free air flow across the sensing element, and protects the sensor from snow, ice, and rain.

2.3.2 Supervisory Controller MCEN Network Homerun

All conduits shall be 1 inch inside diameter. No bends in conduit shall exceed 90 degrees. All bends shall be sweeping. Pull boxes shall be installed after every two 90 degree bends, after any number of bends that add up to 180 degrees or greater, or on any straight run exceeding 100 feet. All pull boxes shall be "straight through" (i.e. conduits enter and exit on opposite sides of the pull box.) Pull boxes shall not be substituted for 90 degree bend requirements. All conduits shall have a vinyl bushing installed at termination points, All conduits shall have a ground bushing at the telecommunication distribution area bonded to the telecommunication bonding bus bar. See Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC paragraph Network Communication Lines for additional requirements.

2.3.3 Transmitters

Provide transmitters with 4 to 20 mA or 0 to 10 VDC linear output scaled to the sensed input. Transmitters shall be matched to the respective sensor, factory calibrated, and sealed. Size transmitters for an output near 50 percent of its full-scale range at normal operating conditions. The total transmitter error shall not exceed 0.1 percent at any point across the measured span. Supply voltage shall be 12 to 24 volts AC or DC. Transmitters shall have non-interactive offset and span adjustments. For temperature sensing, transmitter drift shall not exceed 0.03 degrees F a year.

2.3.3.1 Relative Humidity Transmitters

Provide transmitters with an accuracy equal to plus or minus 3 percent from 0 to 90 percent scale, and less than one percent drift per year. Sensing elements shall be the polymer type.

2.3.3.2 Pressure Transmitters

Provide transmitters integral with the pressure transducer. Size transmitters for an output near 50 percent of its full-scale range at normal operating conditions.

2.3.4 Current Transducers

Provide current transducers to monitor motor amperage, unless current

switches are shown on design drawings or point tables. Provide a VFD rated current sensor where applicable.

2.3.5 Motor Run Status

Unless otherwise noted, provide current switches to indicate run status of pumps and fans. Sensitivity of the switch on belt and coupler driven equipment should distinguish between loaded motor and unloaded motor such as a fan with a broken belt. Provide label indicating calibration date affixed to the device.

2.3.6 Pneumatic to Electric Transducers

Pneumatic to electronic transducers shall convert a 0 to 20 psig signal to a proportional 4 to 20 mA or 0 to 10 VDC signal (operator scaleable). Supply voltage shall be 24 VDC. Accuracy and linearity shall be 1.0 percent or better.

2.3.7 Air Quality Sensors

Provide power supply for each sensor.

2.3.7.1 CO2 Sensors

Provide photo-acoustic type CO2 sensors with integral transducers and linear output. The devices shall read CO2 concentrations between 0 and 2000 ppm with full scale accuracy of at least plus or minus 100 ppm.

2.3.7.2 Air Quality Sensors

Provide full spectrum air quality sensors using a hot wire element based on the Taguchi principle. The sensor shall monitor a wide range of gaseous volatile organic components common in indoor air contaminants like paint fumes, solvents, cigarette smoke, and vehicle exhaust. The sensor shall automatically compensate for temperature and humidity, have span and calibration potentiometers, operate on 24 VDC power with output of 0-10 VDC, and have a service rating of 32 to 140 degrees F and 5 to 95 percent relative humidity.

2.3.8 Input Switches

2.3.8.1 Timed Local Overrides

Provide buttons or switches to override the DDC occupancy schedule programming for each major building zone during unoccupied periods, and to return HVAC equipment to the occupied mode. This requirement is waived for zones clearly intended for 24 hour continuous operation.

2.3.8.2 Emergency Shut Down Switches (ATFP)

Anti Terrorism Force Protection emergency shut down switches must be two action to prevent accidental initiation, such as a mushroom push button with a cover. Switches shall have the following attributes:

a. Switches shall not be keyed.

b. Switches shall be blue with a red latching mushroom push button.

c. Switches shall be twist or rotary reset.

2.3.9 Freeze Protection Thermostats

Provide special purpose thermostats with flexible capillary elements 20 feet minimum length for coil face areas up to 40 square feet. Provide longer elements for larger coils at 1-foot of element for every 4 square feet of coil face area, or provide additional thermostats. Provide switch contacts rated for the respective motor starter's control circuit voltage. Include auxiliary contacts for the switch's status condition. A freezing condition at any 18-inch increment along the sensing element's length shall activate the switch. The thermostat shall be equipped with a manual push-button reset switch so that when tripped, the thermostat requires manual resetting before the HVAC equipment can restart. Provide with factory fabricated mounting rings.

2.3.10 Air Flow Measurement Stations

Air flow measurement stations shall have an array of velocity sensing elements and straightening vanes inside a flanged sheet metal casing. The velocity sensing elements shall be the RTD or thermistor type, traversing the ducted air in at least two directions. The air flow pressure drop across the station shall not exceed 0.08 inch water gage at a velocity of 2,000 fpm. The station shall be suitable for air flows up to 5,000 fpm, and a temperature range of 40 to 120 degrees F. The station's measurement accuracy over the range of 125 to 2,500 fpm shall be plus or minus 3 percent of the measured velocity. Station transmitters shall provide a linear, temperature-compensated 4 to 20 mA or 0 to 10 VDC output. The output shall be capable of being accurately converted to a corresponding air flow rate in cubic feet per minute. Transmitters shall be a 2-wire, loop powered device. The output error of the transmitter shall not exceed 0.5 percent of the measurement.

2.3.11 Air Flow Measurement for Terminal Devices

Air flow measurement for terminal devices such as variable air volume boxes, with or without fan power shall have an array of pressure sensing elements than sense total pressure and static pressure. The flow measurement shall be integral to the device controller and shall be by differential pressure sensor. The air flow shall measure flows down to 300 fpm with an accuracy of 5 percent of reading.

2.3.12 Liquid Flow Meters

Insertion electromagnetic flow meter suitable for measuring electrically conductive liquids in hydronic applications. Provide with grounding ring.

a. Accuracy: ± 1.0% of reading from 2 - 20 ft/s, ± 0.02 ft/s below 2 ft/s.

b. Flow Range: 0.1 ft/s to 20 ft/s (200:1 turndown).

c. Liquid Temperature Range: 15°F to 250°F.

d. Wetted Metal Components: 316 Stainless Steel.

e. Liquid Process Connection: Flange.

f. Display: Display gallons per minute. Must be NEMA 4 rated. Display must be able to be read without openiing any enclosure.

2.3.13 Energy Metering

2.3.13.1 Hot Water Solar Collector Meters

BACnet output or may be a combination of temperature sensors and water flow meter monitored by a DDC controller with the DDC system calculating the BTU transfer. Water flow can be measured by orifice or venturi meter selected for the anticipated system flow rate. Temperature sensors shall be placed in both the supply to and the return from the solar collector array.

2.3.13.2 Electrical Meters

Provide enhanced power and energy meter with built-in integrator and power supply for the CTs. Meter shall have onboard data logging capability as well as output to SBC via native BACnet MS/TP. Place meter indoors at building Main Distribution Panel (MDP). This meter shall be provided in addition to any other power meters required by Division 26 (Electrical) or Division 33 (Utilities).

Electrical meter shall monitor and trend the following points:

a. Power (3-phase total & per phase): Real (kW), Reactive (kVAR), and Apparent (kVA)

b. Power Factor: 3-phase average & per phase

c. Present Power Demand: Real (kW), Reactive (kVAR), and Apparent (kVA)

d. Peak Power Demand: Real (kW), Reactive (kVAR), and Apparent (kVA)

e. Current: 3-phase average and per phase

f. Voltage: Line-Line and Line-Neutral (3-phase average & per phase)

g. Frequency

h. Accumulated Net Energy: Real (kWh), Reactive (kVARh), and Apparent (kVAh)

i. Accumulated Real Energy by phase (kWh)

2.4 OUTPUT HARDWARE

2.4.1 Control Dampers

Provide factory manufactured aluminum dampers where indicated. Dampers shall be opposed blade for rectangular applications 10-inches and taller, and single blade for round dampers and rectangular dampers shorter than 10-inches. Control dampers shall comply with SMACNA 1966 except as modified or supplemented by this specification. Published damper leakage rates and respective pressure drops shall have been verified by tests in compliance with AMCA 500-D requirements.

Provide damper assembly frames constructed of minimum thickness galvanized steel channels with mitered and welded corners. Damper axles shall be 0.5 inches minimum diameter plated steel rods supported in the damper frame by stainless steel or bronze bearings. Blades mounted vertically shall be supported by thrust bearings.

Dampers shall be rated for not less than 2000 fpm air velocity. The pressure drop through each damper when full-open shall not exceed 0.04 inches water gage at 1000 fpm face velocity. Damper assemblies in ductwork shall be constructed to meet SMACNA Seal Class "A" construction requirements.

Provide the damper operating linkages outside of the air stream, including crank arms, connecting rods, and other hardware that transmits motion from the damper actuators to the dampers, shall be adjustable. Additionally, operating linkages shall be designed and constructed to have a 2 to 1 safety factor when loaded with the maximum required damper operating force. Linkages shall be brass, bronze, galvanized steel, or stainless steel.

Provide access doors or panels in hard ceilings and walls for access to all concealed damper operators and damper locking setscrews.

For field-installed control dampers, a single damper section shall have blades no longer than 48 inches and no higher than 72 inches. The maximum damper blade width shall be 12 inches. Larger sized dampers shall be built using a combination of sections.

Frames shall be at least 2 inches wide. Flat blades shall have edges folded for rigidity. Blades shall be provided with compressible gasket seals along the full length of the blades to prevent air leakage when closed.

The damper frames shall be provided with jamb seals to minimize air leakage. Seals shall be suitable for an operating temperature range of minus 40 degrees F to 200 degrees F.

The leakage rate of each damper when full-closed shall be no more than 3 cfm per sq. foot of damper face area at 1.0 inches water gage static pressure.

2.4.2 Control Valves

2.4.2.1 Valve Assembly

Valve bodies shall be designed for 125 psig minimum working pressure or 150 percent of the operating pressure, whichever is greater. Valve stems shall be Type 316 stainless steel. Valve leakage ratings shall be 0.01 percent of rated Cv value. Class 125 copper alloy valve bodies and Class 150 steel or stainless steel valves shall meet the requirements of ASME B16.5. Cast iron valve components shall meet the requirements of ASTM A126 Class B or C.

2.4.2.2 Butterfly Valves

Butterfly valves shall be the threaded lug type suitable for dead-end service and for modulation to the fully-closed position, with stainless steel shafts supported by bearings, non-corrosive discs geometrically interlocked with or bolted to the shaft (no pins), and EPDM seats suitable for temperatures from minus 20 degrees F to plus 250 degrees F. Valves shall have a means of manual operation independent of the actuator.

2.4.2.3 Two-Way Valves

Two-way modulating valves shall have an equal percentage characteristic.

2.4.2.4 Three-Way Valves

Three-way valves shall have an equal percentage characteristic.

2.4.2.5 Valves for Chilled Water, Condenser Water, and Glycol Fluid Service

a. Bodies for valves 1-1/2 inches and smaller shall be brass or bronze, with threaded or union ends. Bodies for valves from 2 inches to 3 inches inclusive shall be of brass, bronze, or iron. Bodies for 2 inch valves shall have threaded connections. Bodies for valves from 2-1/2 to 3 inches shall have flanged connections.

b. Internal valve trim shall be brass or bronze, except that valve stems shall be stainless steel.

c. Provide modulating valves sized for 2 psi minimum and 4 psi maximum differential across the valve at the design flow rate.

d. Valves 4 inches and larger shall be butterfly valves, unless indicated otherwise.

2.4.2.6 Valves for Hot Water Service

Valves for hot water service below 250 Degrees F:

a. Bodies for valves 1-1/2 inches and smaller shall be brass or bronze, with threaded or union ends. Bodies for valves from 2 inches to 3 inches inclusive shall be of brass, bronze, or iron. Bodies for 2 inch valves shall have threaded connections. Bodies for valves from 2-1/2 to 3 inches shall have flanged connections.

b. Internal trim (including seats, seat rings, modulation plugs, valve stems, and springs) of valves controlling water above 210 degrees F shall be Type 316 stainless steel.

c. Internal trim for valves controlling water 210 degrees F or less shall be brass or bronze. Valve stems shall be Type 316 stainless steel.

d. Non-metallic parts of hot water control valves shall be suitable for a minimum continuous operating temperature of 250 degrees F or 50 degrees F above the system design temperature, whichever is higher.

e. Provide modulating valves sized for 2 psi minimum and 4 psi maximum differential across the valve at the design flow rate.

f. Valves 4 inches and larger shall be butterfly valves, unless indicated otherwise.

2.4.2.7 Valves for High Temperature Hot Water Service

Valves for hot water service 250 Degrees F and above:

a. Valve bodies shall conform to ASME B16.34 Class 300. Valve and actuator combination shall be normally closed. Bodies shall be carbon steel, globe type with welded ends on valves 1 inch and larger. Valves

smaller than 1 inch shall have socket-weld ends. Packing shall be virgin polytetrafluoroethylene (PTFE).

b. Internal valve trim shall be Type 316 stainless steel.

c. Provide modulating valves sized for 2 psi minimum and 4 psi maximum differential across the valve at the design flow rate.

2.4.3 Actuators

Provide direct-drive electric actuators for all control applications, except where indicated otherwise. All actuators shall include a feedback loop for detecting actuator faults. The actuator shall report actual position back to the control system. Binary actuators shall provide open/closed status, at a minimum. Modulating actuators and process shall provide position feedback expressed (directly or through span conversion) as percent open/closed. Actuator status shall be derived from actuator position; however, effect may be used in cases where direct feedback is not practical such as VAV coils and dampers.

Use airflow sensors as a feedback loop for damper actuators. Use differential temperature as a feedback mechanism for VAV coil valve actuation.

2.4.3.1 Electric Actuators

Each actuator shall deliver the torque required for continuous uniform motion and shall have internal end switches to limit the travel, or be capable of withstanding continuous stalling without damage. Actuators shall function properly within 85 to 110 percent of rated line voltage. Provide actuators with hardened steel running shafts and gears of steel or copper alloy. Fiber or reinforced nylon gears may be used for torques less than 16 inch-pounds. Provide two-position actuators of single direction, spring return, or reversing type. Provide modulating actuators capable of stopping at any point in the cycle, and starting in either direction from any point. Actuators shall be equipped with a switch for reversing direction, and a button to disengage the clutch to allow manual adjustments. Provide the actuator with a hand crank for manual adjustments, as applicable. Thermal type actuators may only be used on terminal fan coil units, terminal VAV units, convectors, and unit heaters. Spring return actuators shall be provided on all control dampers and all control valves except terminal fan coil units, terminal VAV units, convectors, and unit heaters; unless indicated otherwise. Each actuator shall have distinct markings indicating the full-open and full-closed position, and the points in-between. Actuators mounted outdoors shall be outdoor rated so that they do not require a weatherproof enclosure.

2.4.4 Output Signal Conversion

2.4.4.1 Electronic-to-Pneumatic Transducers

Electronic to pneumatic transducers shall convert a 4 to 20 mA or 0 to 10 VDC digital controller output signal to a proportional 0 to 20 psig pressure signal (operator scaleable). Accuracy and linearity shall be 1.0 percent or better. Transducers shall have feedback circuit that converts the pneumatic signal to a proportional 4 to 20 mA or 0 to 10 VDC signal.

2.4.5 Output Switches

2.4.5.1 Control Relays

Field installed and DDC panel relays shall be double pole, double throw, UL listed, with contacts rated for the intended application, indicator light, and dust proof enclosure. The indicator light shall be lit when the coil is energized and off when coil is not energized. Relays shall be the socket type, plug into a fixed base, and replaceable without tools or removing wiring. Encapsulated "PAM" type relays may be used for terminal control applications.

2.5 ELECTRICAL POWER AND CONTROL WIRING

Electrical power and control wiring requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

2.6 FIRE PROTECTION DEVICES

2.6.1 Duct Smoke Detectors

Provide duct smoke detectors in HVAC ducts in accordance with NFPA 72 and NFPA 90A, except as indicated otherwise. Provide UL listed or FM approved detectors, designed specifically for duct installation.

Furnish detectors under Section 28 31 76 INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE and install under this section. Connect new detectors to the building fire alarm panel.

2.7 VARIABLE FREQUENCY (MOTOR) DRIVES

Provide variable frequency drives (VFDs) as indicated. VFDs shall convert 208 or 480 volt (plus or minus 10 percent), three phase, 60 hertz (plus or minus 2Hz), utility grade power to adjustable voltage/frequency, three phase, AC power for stepless motor control from 5 percent to 200 percent of base speed. VFDs shall be UL listed as delivered to the end user. The VFD shall meet the requirements specified in NFPA 70. Each VFD shall also meet the following:

a. The VFD shall use sine coded Pulse Width Modulation (PWM) technology. PWM calculations shall be performed by the VFD microprocessor.

b. The VFD shall be capable of automatic control by a remote 4-20 mA 0 to 10 VDC signal, by network command, or manually by the VFD control panel.

2.7.1 VFD Quality Assurance

VFDs shall be the manufacturer's current standard production unit with at least 10 identical units successfully operating in the field.

2.7.2 VFD Service Support

a. Warranty: Provide the VFDs with a minimum 24-month full parts and labor warranty. The warranty shall start when the contract's HVAC system is accepted by the Government. Include warranty documentation, dates, and contact information with the VFD on-site service manuals.

b. VFD Service Manuals: Provide the VFDs with all necessary installation, operation, maintenance, troubleshooting, service, and repair manuals in English including related factory technical bulletins. Provide the documents factory bound, in sturdy 3-ring binders, or hard bound covers. Provide a title sheet on the outside of each binder indicating the project title, project location, installing contractor, contract number, and the VFD manufacturer, address, and telephone number. Each binder shall include a table of contents and tabbed dividers, with all material neatly organized. The documentation provided shall be specifically applicable to this project, shall be annotated to reflect the actual project conditions, and shall provide a complete and concise depiction of the installed work. Provide a storage cabinet on or near the VFD large enough to hold all of the documentation. Have the cabinet's proposed installation site approved in advance by the Contracting Officer. Prominently label the cabinet "VFD OPERATION AND MAINTENANCE MANUALS." Clearly label each manual with the wording "MECHANICAL ROOM COPY - DO NOT REMOVE".

c. Technical Support: Provide the VFDs with manufacturer's technical telephone support in English, readily available during normal working hours, and free of charge for the life of the equipment.

d. Initial Start-Up: Provide the VFDs with factory-trained personnel for the on-site start-up of the HVAC equipment and associated VFD. The personnel shall be competent in the complete start-up, operation, and repair of the particular model VFD installed. The factory start-up representative shall perform the factory's complete recommended start-up procedures and check-out tests on the VFD. Include a copy of the VFD start-up test documentation with the VFD on-site service manuals.

e. Provide the VFDs with on-site/hands-on training for the user and maintenance personnel. Provide a capable and qualified instructor with minimum two years field experience with the operation and maintenance of similar VFDs. The training shall occur during normal working hours and last not less than 2 hours. Coordinate the training time with the Contracting Officer and the end user. The VFD service manuals shall be used during the training. The contractor shall ensure the manuals are on-site before the start of training. The training shall cover all operational aspects of the VFD.

2.7.3 VFD Features

VFDs shall have the following features:

a. A local operator control keypad capable of:

(1) Remote/Local operator selection with password access.

(2) Run/Stop and manual speed commands.

(3) All programming functions.

(4) Scrolling through all display functions.

b. Digital display capable of indicating:

(1) VFD status.

(2) Frequency.

(3) Motor RPM.

(4) Phase current.

(5) Fault diagnostics in descriptive text.

(6) All programmed parameters.

(7) Load power.

c. Standard PI loop controller with input terminal for controlled variable and parameter settings.

d. User interface terminals for remote control of VFD speed, speed feedback, and an isolated form C SPDT relay, which energizes on a drive fault condition.

e. An isolated form C SPDT auxiliary relay which energizes on a run command.

f. A metal NEMA 1 enclosure for indoors, NEMA 4 with heater for outdoors.

g. An adjustable carrier frequency with 16 KHz minimum upper limit.

h. A built in DC buss reactor with 3 percent minimum impedance to protect the VFDs DC buss capacitors and rectifier section diodes.

i. HOA/Bypass Switches

2.7.4 Programmable Parameters

VFDs shall include the following operator programmable parameters:

a. Upper and lower limit frequency.

b. Acceleration and deceleration rate.

c. Variable torque volts per Hertz curve.

d. Starting voltage level.

e. Starting frequency level.

f. Display speed scaling.

g. Enable/disable auto-restart feature.

h. Enable/disable soft stall feature.

i. Motor overload level.

j. Motor stall level.

k. Jump frequency and hysteresis band.

l. PWM carrier frequency.

2.7.5 Protective Features

VFDs shall have the following protective features:

a. An electronic adjustable inverse time current limit with consideration for additional heating of the motor at frequencies below 45Hz, for the protection of the motor.

b. An electronic adjustable soft stall feature, allowing the VFD to lower the frequency to a point where the motor will not exceed the full-load amperage when an overload condition exists at the requested frequency. The VFD will automatically return to the requested frequency when load conditions permit.

c. A separate electronic stall at 110 percent VFD rated current, and a separate hardware trip at 190 percent current.

d. Ground fault protection that protects the output cables and motor from grounds during both starting and continuous running conditions.

e. The ability to restart after the following faults:

(1) Overcurrent (drive or motor).

(2) Power outage.

(3) Phase loss.

(4) Over voltage/Under voltage.

f. The ability shut down if inadvertently started into a rotating load without damaging the VFD or the motor.

g. The ability to keep a log of a minimum of four previous fault conditions, indicating the fault type and time of occurrence in descriptive text.

h. The ability to sustain 110 percent rated current for 60 seconds.

i. The ability to shutdown safely or protect against and record the following fault conditions:

(1) Over current (and an indication if the over current was during acceleration, deceleration, or running).

(2) Over current internal to the drive.

(3) Motor overload at start-up.

(4) Over voltage from utility power.

(5) Motor running overload.

(6) Over voltage during deceleration.

(7) VFD over heat.

(8) Load end ground fault.

(9) Abnormal parameters or data in VFD EEPROM.

2.7.6 Minimum Operating Conditions

VFDs shall be designed and constructed to operate within the following service conditions:

a. Ambient Temperature Range, 0 to 120 degrees F.

b. Non-condensing relative humidity to 90 percent.

2.7.7 Additional Features

Provide VFDs with the following additional features:

a. BACnet communication interface port.

PART 3 EXECUTION

3.1 INSTALLATION

Perform the installation under the supervision of competent technicians regularly employed in the installation of DDC systems. All material and equipment shall be installed in accordance with the manufacturer's recommendations for the intended purpose and NFPA 70. Maintain a copy of the manufacture's recommendations on the Construction Site. Use the more stringent methods when manufacturer's recommendations, and plans & specification requirements differ. Use the "Preferred" method when alternative methods are given. The word "should" will be considered to mean "shall". Bring any conflicts between manufacturer's recommendations and plans & specification requirements to the Government's attention. All equipment shall be installed level and plumb.

3.1.1 Wiring Criteria

Wiring criteria requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

3.1.2 Accessibility

Accessibility requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

3.1.3 Component Identification Labeling

Component identification labeling requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

3.1.4 Digital Controllers

a. Install as stand alone control devices (see definitions in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC).

b. Locate control cabinets at the locations shown on the drawings. If not shown on the drawings, install in the most accessible space, close to the controlled equipment.

c. Controllers must be installed in a manfacturer's required/recommended enclosure for each type of controller.

d. Provide a dedicated analog output to each output device, such as variable frequency driven pump motors, in an alternating arrangement.

e. Equipment such as VFD's must have hardwired enable (start/stop), speed command, and status points from the controller. Software points are not allowable. Additionally, this equipment shall have a BACnet interface for monitoring.

3.1.5 Hand-Off-Auto Switches

Hand-Off-Auto switches must be physical three position switches. Switches must be accessible from the exterior of any device. Wire safety controls such as smoke detectors, freeze protection thermostats,and emergency shut down switches to protect the equipment during both hand and auto operation.

3.1.6 Emergency Shut Down Switches (ATFP)

Quantity and location as shown on the drawings. Switches must be hardwired such that all fans and dampers that circulate air between rooms, or between inside and outside must shut down/close regardless of equipment HOA switch position and without the use of software. ATFP circuit must be energized to allow equipment to operate; i.e. activation of the emergency shut down switch will de-energize the circuit and open relays at the equipment. Additionally, activation of the switch must signal the DDC system to shut all air moving equipment off/closed and initiate an alarm. Reset of the DDC system must be manual.

3.1.7 Safety and Shutdown Circuit Monitoring

All safety or shutdown circuits, or any circuit that can disable a system, shall be monitored by the DDC system as separate inputs for each circuit. This shall include, but is not limited to, Low Temperature Limit, Duct Mounted Smoke Detector, Discharge Air High Pressure Limit, Boiler Emergency Pushbutton, Carbon Monoxide, Gas Detection, ATFP, etc. Supervisory controller alarm reporting shall be configured for each individual circuit alarm.

3.1.8 Temperature Sensors

Install temperature sensors in locations that are accessible and provide a good representation of sensed media. Installations in dead spaces are not acceptable. Calibrate sensors according to manufacturer's instructions. Only use sensors in their intended application as described by the manufacturer's written instructions.

3.1.9 Room Temperature Sensors

Mount the sensors on interior walls to sense the average room temperature at the locations indicated. Avoid locations near heat sources such as copy machines or locations by supply air outlet drafts. Mount the center of the sensor 54 inches above the floor to meet ADA requirements.

3.1.10 Duct Temperature Sensors

a. Probe Type: Provide a gasket between the sensor housing and the duct wall. Seal the duct penetration air tight. Seal the duct insulation

penetration vapor tight.

b. Averaging Type (and coil freeze protection thermostats): Weave the capillary tube sensing element in a serpentine fashion perpendicular to the flow, across the duct or air handler cross-section, using durable non-metal supports. Prevent contact between the capillary and the duct or air handler internals. Provide a duct access door at the sensor location. The access door shall be hinged on the side, factory insulated, have cam type locks, and be as large as the duct will permit, maximum 18 by 18 inches. For sensors inside air handlers, the sensors shall be fully accessible through the air handler's access doors without removing any of the air handler's internals.

3.1.11 Immersion Temperature Sensors

Provide thermowells for sensors measuring piping, tank, or pressure vessel temperatures. Locate wells to sense continuous flow conditions. Do not install wells using extension couplings. Where piping diameters are smaller than the length of the wells, provide wells in piping at elbows to sense flow across entire area of well. Wells shall not restrict flow area to less than 70 percent of pipe area. Increase piping size as required to avoid restriction. Provide thermal conductivity material within the well to fully coat the inserted sensor.

3.1.12 Outside Air Temperature & Humidity Sensors

Provide outside air temperature and humidity sensors in weatherproof enclosures on the north side of the building, away from exhaust hoods and other areas that may affect the reading. Provide a shield to shade the sensor from direct sunlight.

3.1.13 Energy Meters

Provide and locate energy meters as indicated. Connect each meter output to the DDC system, to measure both instantaneous and accumulated usage.

3.1.14 Damper Actuators

Mount actuators outside the air stream in accessible areas.

3.1.15 Pressure Sensors

Locate pressure sensors as indicated.

-- End of Section --

SECTION 23 09 23.02

BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS
02/25 MCBCL

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 135	(2020; Interpretation 1-8 2021; Errata 1-2 2021; Addenda CD 2021; Addenda BY-CE 2022; Interpretation 9-10 2022) BACnet—A Data Communication Protocol for Building Automation and Control Networks

UL SOLUTIONS (UL)

UL 916	(2015; Reprint Oct 2021) UL Standard for Safety Energy Management Equipment

1.2 DEFINITIONS

For definitions related to this section, see Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

1.3 SUBMITTALS

Submit detailed and annotated manufacturer's data, drawings, and specification sheets for each item listed, that clearly show compliance with the project specifications.

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Direct Digital Controllers; G

Bacnet Gateways; G

Notebook Computer; G

Notebook Computer Software; G

Bacnet Operator Workstation; G

1.4 QUALITY CONTROL

Quality Control requirements are specified in Section 23 09 00

INSTRUMENTATION AND CONTROL FOR HVAC.

PART 2 PRODUCTS

All products used to meet this specification must meet the indicated requirements, but not all products specified here will be required by every project. All products must meet the requirements both Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC and this Section.

2.1 DDC SYSTEM

2.1.1 Supervisory Building Controller (SBC)

ASHRAE 135 building controller that is the main interface for the building control system. Provide a JACE based on the Niagara N4 platform. The JACE (JAVA Application Control Engine) shall be minimally based on a Tridium 8000 with expanded memory and embedded "Niagara Workbench or Workplace" software. The latest software revision available at the time the PVT Report is submitted must be installed.

Any device implementing the Niagara Framework is a Niagara Framework Supervisory Gateway and must meet these requirements. In addition to the general requirements for all DDC Hardware, Niagara Framework Supervisory Gateway Hardware must:

a. Be direct digital control hardware.

b. Have an unrestricted interoperability license and its Niagara Compatibility Statement (NiCS) must follow the Tridium Open NiCS Specification.

c. Manage communications between a field control network and the Niagara Framework Monitoring and Control Software, and between itself and other Niagara Framework Supervisory Gateways. Niagara Framework Supervisory Gateway Hardware must use Fox protocol for communication with other Niagara Framework Components, regardless of the manufacturer of the other components.

d. Be fully programmable using the Niagara Framework Engineering Tool and must support the following:

   (1) Time synchronization, Calendar, and Scheduling using Niagara Scheduling Objects.

   (2) Alarm generation and routing using the Niagara Alarm Service.

   (3) Trending using the Niagara History Service and Niagara Trend Log Objects.

   (4) Integration of field control networks using the Niagara Framework Engineering Tool.

   (5) Configuration of integrated field control system using the Niagara Framework Engineering Tool when supported by the field control system.

e. Meet the following minimum hardware requirements:

(1) Two 10/100/1000 Mbps Ethernet Port(s)

(2) One or more MS/TP ports.

(3) Central Processing Unit of 1000 Mhz or higher.

(4) Embedded operating system.

f. Provide access to field control network data and supervisory functions via web interface and support a minimum of 16 simultaneous users. Note: implementation of this capability may not be required on all projects.

g. Submit a backup of each Niagara Framework Supervisory Gateway. The backup must be sufficient to restore a Niagara Framework Supervisory Gateway to the final as-built condition such that a new Niagara Framework Supervisory Gateway loaded with the backup is indistinguishable in functionality from the original.

2.1.1.1 Niagara Framework Engineering Tool

The Niagara Framework Engineering Tool must be Niagara Workbench or an equivalent Niagara Framework engineering tool software and must:

a. Have an unrestricted interoperability license and its Niagara Compatibility Statement (NiCS) must follow the Tridium Open NiCS Specification.

b. Be capable of performing network configuration for Niagara Framework Supervisory Gateways and Niagara Framework Monitoring and Control Software.

c. Be capable of programming and configuring of Niagara Framework Supervisory Gateways and Niagara Framework Monitoring and Control Software.

d. Be capable of discovery of Niagara Framework Supervisory Gateways and all points mapped into each Niagara Framework Supervisory Gateway and making these points accessible to Niagara Framework Monitoring and Control Software.

2.1.1.2 Supervisory Controller MCEN Network Homerun

See Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC paragraph Network Communication Lines for requirements.

2.1.2 EMCS Interface

The EMCS at Camp Lejeune is comprised of two separate systems. Both of the systems communicate over the basewide Marine Corps Enterprise Network (MCEN). One uses the Johnson Controls Network Automation Engine (NAE), Network Control Engine (NCE), Supervisory Network Engine (SNE) or Supervisory Network Control Engine (SNC) to the ADX server. The second system uses a Niagara FX N4 web supervisor with a JACE in the building communicating using Fox protocol. Because of IT security and permissions, only these systems and equipment are permitted as part of the EMCS.

2.1.2.1 Supervisory Building Controller

Provide a JACE. This will serve as both the Supervisory Building Controller and the connection point between the buildings DDC and the EMCS. Provide a five year service license on all Supervisory Controllers. Provide a reserve of 10% of additional points and additional devices on the Supervisory Controller license at the final project acceptance.

The contractor shall assign the BAS Owner as the owner and manager of all licenses including 3rd party drivers.

2.1.2.2 Palo Alto Firewall

For any building provided with a new Supervisory controller, contractor shall also provide a Palo Alto Firewall Model PAN-PA-220R. Contractor shall also provide a five year government support option for the Palo Alto firewall complete with all licenses.

2.1.3 Direct Digital Controllers

a. Direct digital controllers shall be UL 916 rated.

b. Field Controllers:

(1) Acceptable DDC field controllers are Facility Explorer, Metasys or Distech.

c. Except for VAV's, all direct digital controllerss shall have an on board password protected display screen pre-programmed with the device's associated points. Display screens shall only be accessible after opening an enclosure door. Display screens that are accessible from an enclosure exterior are not permitted.

d. Include BACnet PICS for each controller/device type, including smart sensors (B-SS) and smart actuators (B-SA).

2.1.3.1 I/O Point Limitation

The total number of I/O hardware points used by a single stand-alone digital controller, including I/O expansion units, shall not exceed 64, except for complex individual equipment or systems. Place I/O expansion units in the same cabinet as the digital controller. The field controller must have one spare Configurable Output and one spare Universal Input available per system upon project completion, i.e. AHU, ERU, DOAS, HW System, CHW System and other building primary systems. VAV controllers and programmable thermostats are excluded.

2.1.3.2 Environmental Limits

Controllers shall be suitable for, or placed in protective enclosures suitable for the environment (temperature, humidity, dust, and vibration) where they are located.

2.1.3.3 Stand-Alone Controllers

Provide stand-alone direct digital controllers with internal time clocks if not connected to a Supervisory Building Controller. Each piece of equipment shall be controlled by a single controller to provide stand-alone control in the event of any building communication failure.

All I/O points specified for a piece of equipment shall be integral to its controller and serial connected expansion modules. Provide stable and reliable stand-alone control using default values or other method for values normally read over the network.

2.1.3.4 Internal Clock

Provide internal clocks and scheduling for all Direct Digital Controllers. Provide controllers with BTL listed profiles for all BACnet Building Controllers (B-BC) and BACnet Advanced Application Controllers (B-AAC) using BACnet time synchronization services. This includes but is not limited to VAV Controllers, Fan Coil controllers, Heat Pump controllers and any terminal controllers. BACnet Application specific controllers (B-ASC) will only be accepted for dedicated small exhaust system control such as restroom and mechanical room exhaust fans. Automatically synchronize system clocks daily from an operator-designated controller. The system shall automatically adjust for daylight saving time.

2.1.3.5 Memory

Provide sufficient memory for each controller to support the required control, communication, trends, alarms, and messages. Protect programs residing in memory with EEPROM, flash memory, or by an uninterruptible power source (battery or uninterruptible power supply). The backup power source shall have capacity to maintain the memory during a 72-hour continuous power outage. Rechargeable power sources shall be constantly charged while the controller is operating under normal line power. Batteries shall be replaceable without soldering. Trend and alarm history collected during normal operation shall not be lost during power outages less than 72 hours long.

2.1.3.6 Immunity to Power Fluctuations

Controllers shall operate at 90 percent to 110 percent nominal voltage rating.

2.1.3.7 Transformer

The controller power supply shall be fused or current limiting and rated at 125 percent power consumption. Each transformer must singularly serve the connected load, i.e. do not wire transfomers in parallel on the load side. Transformer shall be mounted in the upper portion of the control panel to
aid in heat dissipation. The 120 volt power feed must also enter in the upper portion of the cabinet - power shall not be brought in from the bottom of the panel.

2.1.3.8 Wiring Terminations

Use screw terminal wiring terminations for all field-installed controllers. Provide field-removable modular terminal strip or a termination card connected by a ribbon cable for all controllers other than terminal units.

2.1.3.9 Input and Output Interface

Provide hard-wired input and output interface for all controllers as follows:

a. Protection: Shorting an input or output point to itself, to another point, or to ground shall cause no controller damage. Input or output point contact with sources up to 24 volts AC or DC for any duration shall cause no controller damage.

b. Binary Inputs: Binary inputs shall monitor on and off contacts from a "dry" remote device without external power, and external 5-24 VDC voltage inputs.

c. Pulse Accumulation Inputs: Pulse accumulation inputs shall conform to binary input requirements and accumulate pulses at a resolution suitable to the application.

d. Analog Inputs: Analog inputs shall monitor low-voltage (0-10 VDC), current (4-20 mA), or resistance (thermistor or RTD) signals.

e. Binary Outputs: Binary outputs shall send a pulsed 24 VDC low-voltage signal for modulation control, or provide a maintained open-closed position for on-off control. Where appropriate, provide a method to select normally open or normally closed operation.

f. Analog Outputs: Analog outputs shall send modulating 0-10 VDC or 4-20 mA signals to control output devices.

g. Tri-State Outputs: Tri-State outputs shall provide three-point floating control of terminal unit electronic actuators.

2.1.3.10 Digital Controller BACnet Internetwork

Provide intermediate gateways, only when requested by the Government and shown on the contract drawings, to connect existing non-BACnet devices to the BACnet internetwork. Controller and operator interface communication shall conform to ASHRAE 135, BACnet. If a controller becomes non-responsive, the remaining controllers shall continue operating and not be affected by the failed controller.

2.1.3.11 Communications Ports

a. Direct-Connect Interface Ports: Provide at least one extra communication port at each local BACnet network for direct connecting a notebook computer or BACnet hand-held terminal so all network BACnet objects and properties may be viewed and edited by the operator.

2.1.3.12 BACnet Gateways

Provide BACnet communication ports, whenever available as a plant equipment OEM standard option, for DDC integration via a single communication cable. Typical BACnet controlled plant equipment includes, but is not limited to, boilers, chillers, and variable frequency motor drives. Include the following information in the submittal:

a. BACnet and workstation display information

b. Bi-directional communication ability

c. Compliance with interoperability schedule

d. Expansion capacity

e. Handling of alarms, events, scheduling and trend data

f. Single device capability (not depending on multiple devices for exchanging information from either side of the gateway)

Provide gateways to connect BACnet to legacy systems, existing non-BACnet devices, and existing non-BACnet DDC controlled plant equipment, only when specifically requested and approved by the Government, and shown on the Government approved BACnet Communication Architecture Schematic. Provide with each gateway an interoperability schedule, showing each point or event on the legacy side that the BACnet "client" will read, and each parameter that the BACnet network will write to. Describe this interoperability in terms of BACnet services, or Interoperability Building Blocks (BIBBS), defined in ASHRAE 135 Annex K. Provide two-year minimum warranty for each gateway, including parts and labor.

The following minimum capabilities are required:

a. Gateways shall be able to read and view all readable object properties listed in the interoperability schedule on the non-BACnet network to the BACnet network and vice versa where applicable.

b. Gateways shall be able to write to all writeable object properties listed in the interoperability schedule on the non-BACnet network from the BACnet network and vice versa where applicable.

c. Gateways shall provide single-pass (only one protocol to BACnet without intermediary protocols) translation from the non-BACnet protocol to BACnet and vice versa.

d. Gateways shall meet the requirements of Data Sharing Read Property (DS-RP-B), Data Sharing Write Property (DS-WP-B), Device Management Dynamic Device Binding-B (DM-DDB-B), and Device Management Communication Control (DM-DCC-B) BIBBs, in accordance with ASHRAE 135.

e. Gateways shall include all hardware, software, software licenses, and configuration tools for operator-to-gateway communications. Provide backup programming and parameters on CD media and the ability to modify, download, backup, and restore gateway configuration.

2.1.3.13 Digital Controller Cabinet

Provide each digital controller including gateways, in a factory fabricated locked cabinet enclosure. Lock shall accept CAT102 keys.

Cabinets located indoors shall protect against dust and have a minimum NEMA 1 rating, except where indicated otherwise. Cabinets located outdoors or in damp environments shall protect against all outdoor conditions and have a minimum NEMA 4 rating. Mechanical rooms that contain steam service or equipment including new steam boiler rooms are considered damp environments. Outdoor control panels and controllers must be able to withstand extreme ambient conditions, without malfunction or failure, whether or not the controlled equipment is running. If necessary, provide a thermostatically controlled panel heater in freezing locations, and an internal ventilating fan in locations exposed to direct sunlight. Cabinets shall have a hinged lockable door and an offset removable metal back plate, except controllers integral with terminal units, like those mounted on VAV boxes. Provide like-keyed locks for all hinged panels provided and a set of two keys at each panel, with one key inserted in the lock. All

devices must be mounted only to the cabinet backplane with adequate space allowed for serviceability and proper heat dissipation from devices. The Supervisory controller cabinet door position (closed/open) shall be monitored with a door switch and BACnet programmable relay such as the Functional Devices RIBTW2401B-BC. An "open" door status shall initiate an alarm to the EMCS Server.

2.1.3.14 Main Power Switch and Receptacle

Provide each control cabinet with a main external power on/off switch located inside the cabinet. Also, provide each cabinet with a separate 120 VAC duplex convenience receptacle.

2.1.4 DDC Software

2.1.4.1 Programming

Provide programming to execute the sequence of operation indicated. Provide all programming, tools, interfaces, cables, etc. to configure and program all controllers. All software shall be licensed to Marine Corps Base, Camp Lejeune Complex for unrestricted use on Camp Lejeune Complex and reproduction for use on Camp Lejeune Complex. Software keys and "dongles" are not permitted. Provide programming routines in simple, easy-to-follow logic with detailed text comments describing what the logic does and how it corresponds to the project's written sequence of operation. All logic programming and control functions shall be closed loop, command and feedback for fault detection and alarming when status does not match the command.

a. Graphic-based programming shall use a library of function blocks made from pre-programmed code designed for BAS control. Function blocks shall be assembled with interconnecting lines, depicting the control sequence in a flowchart. If providing a computer with device programming tools as part of the project, graphic programs shall be viewable in real time showing present values and logical results from each function block.

b. Menu-based programming shall be done by entering parameters, definitions, conditions, requirements, and constraints.

c. For line-by-line and text-based programming, declare variable types (variable types include but are not limited to the following: local, global, real, and integer) at the beginning of the program. Use descriptive comments frequently to describe the programming.

d. If providing a computer with device programming tools as part of the project, provide a means for detecting program errors and testing software strategies with a simulation tool. Simulation may be inherent within the programming software suite, or provided by physical controllers mounted in a NEMA 1 test enclosure. The test enclosure shall contain one dedicated controller of each type provided under this contract, complete with power supply and relevant accessories.

2.1.4.2 Parameter Modification

All writeable object properties, and all other programming parameters needed to comply with the project specification shall be adjustable for devices at any network level, including those accessible with web-browser communication, and regardless of programming methods used to create the

applications.

2.1.4.3 Short Cycling Prevention

Provide setpoint differentials and minimum on/off times to prevent equipment short cycling.

2.1.4.4 Equipment Status Delay

Provide an adjustable delay from when equipment is commanded on or off and when the control program looks to the status input for confirmation.

2.1.4.5 Run Time Accumulation

Use the Elapsed Time Property to provide re-settable run time accumulation for each Binary Output Object connected to mechanical loads greater than 1 HP, electrical loads greater than 10 KW, or wherever else specified.

2.1.4.6 Timed Local Override

Provide an adjustable override time for each push of a timed local override button.

2.1.4.7 Time Synchronization

Provide time synchronization, including adjustments for leap years, daylight saving time, and operator time adjustments.

2.1.4.8 Scheduling

Provide operating schedules as indicated, with equipment assigned to groups. Changing the schedule of a group shall change the operating schedule of all equipment in the group. Groups shall be capable of operator creation, modification, and deletion. Provide capability to view and modify schedules in a seven-day week format. Provide capability to enter holiday and override schedules one full year at a time.

2.1.4.9 Object Property Override

Allow writeable object property values to accept overrides to any valid value. Where specified or required for the sequence of control, the Out-Of-Service property of Objects shall be modifiable using BACnet's write property service. When documented, exceptions to these requirement are allowed for life, machine, and process safeties.

2.1.4.10 Alarms and Events

Alarms and events shall be capable of having programmed time delays and high-low limits. When a web server is connected to the BACnet internetwork, alarms/events shall report to web server as defined by an authorized operator. Otherwise alarms/events shall be stored within a device on the BACnet network until connected to a user interface device and retrieved. Provide alarms/events in agreement with the point schedule, sequence of operation, and the BAS Owner. At a minimum, provide programming to initiate alarms/events any time a piece of equipment fails to operate, a control point is outside normal range or condition shown on schedules, communication to a device is lost, a device has failed, or a controller has lost its memory.

2.1.4.11 Trending

Provide BACnet trending all object present values, set points, and other parameters indicated for trending on project schedules or at the request of Camp Lejeune or commissioning agents. Trends may be associated into groups, and a trend report may be set up for each group. Trends are stored within a device on the BACnet network, with operator selectable trend intervals from 10 seconds up to 24 hours. The minimum number of consecutive trend values stored at one time shall be 100 per variable. When trend memory is full, the most recent data shall overwrite the oldest data.

The BACnet system shall allow for Change-Of-Value (COV) subscription based trending at user defined thresholds.

The B-BC shall upload trends automatically upon reaching 3/4 of the device buffer limit (via Notification_Threshold property), by operator request, or by time schedule for archiving. Archived and real-time trend data shall be available for viewing numerically and graphically for at the workstation and connected notebook computers.

Additionally, provide daily trend on geothermal well field supply and return temperatures. Allocate sufficient memory to store 24 months data.

2.1.4.12 Device Diagnostics

Each controller shall have diagnostic LEDs for power, communication, and device fault condition. The DDC system shall recognize and report a non-responsive controller.

2.1.4.13 Power Loss

Upon restoration of power, the DDC system shall perform an orderly restart and restoration of control.

2.1.5 Notebook Computer

Provide a notebook computer for each building, complete with the project's installed DDC software, applications database, final archived field controller programs and Supervisory controller database, and graphics to fully troubleshoot and program the project's devices. Provide the notebook computer with aballistic nylon carrying case with shoulder strap, or backpack,and all necessary cables and interface hardware needed for setup and direct communication with the controllers and control system components. Direct communication shall not be through the Supervisory controller.

At a minimum the notebook computer shall include: Common Access Card Reader, Windows based operating system, minimum 2.7 GHz processor base speed with 3 MB Cache, discrete switchable graphics card with minimum 1 GB dedicated memory, 1 Terabyte hard drive, 32 GB DDR3 RAM, 2 USB 3.0 ports, 10/100/1000 network interface card, 802.11 b/g/n WLAN, 17-inch display, keyboard with numeric keypad, 6-hour battery with charger, internal or external 8X DVD+/-R/RW drive with double layer support with DVD creator software, and Microsoft Office Home and Business bundled software. Provide all original licenses, installation media, documentation, and recovery CDs capable of restoring the original configuration. Provide a means to connect the notebook computer directly to the installed field bus. Provide the manufacturer's 3-year accidental damage protection with

3-day on site response for 2 year warranty with the Government listed as the warranty owner.

When submitting the notebook computer, provide itemized list indicating the following information for all components submitted with the notebook computer:

a. Description

b. Quantity

c. Manufacturer

d. Part Number

e. Serial Number

2.1.6 Notebook Computer Software

2.1.6.1 Password Protection

System shall support role based access. At a minimum, OS administrator, auditor, DDC operator and user roles must be defined. The system must be capable of enforcing role based access by location (e.g., Bob may alter operating parameters for Building 1 but not Building 2. Building 2 is Alice's responsibility).

Workstation shall be capable of DoD Common Access Card (CAC) login in addition to traditional username and password.

The lowest level only allow viewing graphics. The second level allows viewing graphics and changing space temperature setpoints. The third level allows the previous level's capability, plus changing operating schedules. The fourth level allows access to all functions except passwords. The highest level provides all administrator rights and allows full access to all programming, including setting new passwords and access levels. Provide the BAS Owner with the highest level password access. Provide automatic log out if no keyboard or mouse activity is detected after a user-defined time delay.

2.1.6.2 Notebook Computer DDC Software

Provide the workstation software with the manufacturer's installation CDs and licenses. Configure the software according to the DDC system manufacturer's specifications, cybersecurity requirements, and in agreement with BACnet Operator Workstation (B-OWS) device standards found in ASHRAE 135, Annex L. Include BACnet PICS for Operator Workstation software.

The workstation software shall permit complete monitoring, modification, archiving, programming and troubleshooting interface with the DDC system including supervisory controller and field controllers. Software shall include, but not limited to, Niagara Workplace, FX Workbench, JCI SCT, CCT/PCT, Distech EC-gfx or any controls manufacturer Supervisory controller and field controller programming software used to program the system. The operator interface with the software shall be menu-driven with appropriate displays and menu commands to manipulate the DDC system's objects, point data, operating schedules, control routines, system configuration, trends, alarms, messages, graphics, and reports. Trends

shall be capable of graphic display in real time, with variables plotted as functions of time. Each alarmed point shall be capable of displaying its alarm history, showing when it went into alarm, if and when it was acknowledged, and when it went out of alarm. The modification of DDC system parameters and object properties shall be accomplished with "fill in the blank" and/or "point and drag" methods. Modifications shall download to the appropriate controllers at the operator's request.

2.1.6.3 Web-Based User Interface (UI) and Graphics

Provide web-based graphics fully compatible with Internet Explorer 9+, Safari, Firefox, and Google Chrome. Web-based user interface shall be browser agnostic and shall not rely on proprietary client side scripting to function.

Graphic displays shall have full-screen resolution when viewed on the workstation and notebook computers. Dynamic data on graphics pages shall refresh within 10 seconds using an Internet connection, or 30 seconds using a dial-up modem connection. Web-based user interface shall not rely on additional third-party browser "plug-in" software like Adobe Flash. Java client side applets may be used if appropriately signed. If Java client side runtimes are used they shall not require deprecated or otherwise unsupported Java runtime environments.

The graphics shall show the present value and object name for each of the project's I/O points on at least one graphic page. Arrange point values and names on the graphic displays in their appropriate physical locations with respect to the floor plan or equipment graphic displayed. Graphics shall allow the operator to monitor current status, view zone and equipment summaries, use point-and-click navigation between graphic pages, and edit setpoints and parameters directly from the screens. Items in alarm shall be displayed using a different color or other obvious visual indicator.
Provide graphics with the following:

a. Graphic Types: Provide at least one graphic display for each piece of HVAC equipment, building floor, and controlled zone. Indicate dynamic point values, operating statuses, alarm conditions, and control setpoints on each display. Provide summary pages where appropriate.

    (1) Building Elevation: For buildings more than one story, provide an elevation view of the building with links to each of the building's floor plans. Simulate the building's architecture and include the building number and floor numbers. If possible, use an actual photograph of the building.

    (2) Building Floor Plans: Provide a floor plan graphic for each of the building's floors and roof with dynamic display of space temperature and other important data. If used, indicate and provide links to sub-plan areas. If possible, use the project's electronic drawing files for the graphic backgrounds. Provide clear names for important areas, such as "Main Conference Room." Include room names and numbers where applicable. Include features such as stairwells, elevators, and main entrances. Where applicable, include the mechanical room, HVAC equipment, and control component locations, with corresponding links to the equipment graphics.

    (3) Sub-plan Areas: Where a building's floor plan is too large to

adequately display on the screen, sub-divide the plan into distinct areas, and provide a separate graphic display for each area. Provide same level of detail requested in building floor plan section above.

(4) HVAC Equipment: Provide a graphic display for each piece of HVAC equipment, such as a fan coil unit, VAV terminal, or air handling unit. Equipment shall be represented by a two or three-dimensional drawing. Where multiple pieces of equipment combine to form a system, such as a central chiller plant or central heating plant, provide one graphic to depict the entire plant. Indicate the equipment, piping, ductwork, dampers, and control valves in the installed location. Include labels for equipment, piping, ductwork, dampers, and control valves. Show the direction of air and water flow. Include dynamic display of applicable object data with clear names in appropriate locations.

(5) Sequence of Operation: Provide a graphic screen displaying the written out full sequence of operation for each piece of HVAC equipment. Provide a link to the sequence of operation displays on their respective equipment graphics. Include dynamic real-time data within the text for setpoints and variables.

b. Graphic Title: Provide a prominent, descriptive title on each graphic page.

c. Dynamic Update: When the workstation is on-line, all graphic I/O object values shall update with change-of-value services, or by operator selected discrete intervals.

d. Graphic Linking: Provide forward and backward linking between floor plans, sub-plans, and equipment.

e. Graphic Editing: Provide installed software to create, modify, and delete the DDC graphics. Include the ability to store graphic symbols in a symbol directory and import these symbols into the graphics.

f. Dynamic Point Editing: Provide full editing capability for deleting, adding, and modifying dynamic points on the graphics.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Demolition

Demolition requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

3.1.2 BACnet Naming and Addressing

Coordinate with the BAS Owner and provide unique naming and addressing consistent with existing buildings already loaded on the EMCS server. All DDC controllers shall have a Camp Lejeune unique instance number and all Supervisory Building Controllers shall have a Camp Lejeune unique name. Names are managed by the Government.

3.1.2.1 MAC Address

Every BACnet device shall have an assigned and documented MAC Address unique to its network. For Ethernet networks, document the MAC Address assigned at its creation. For MS/TP networks, assign addresses from 0-127. Do not use the controls manufacturer reserved addresses for field controllers. This is typically 0-3. Also the BACnet Instance ID for MAC Address 127, Trunk 1, is reserved for the Supervisory controller. Supervisory Controller Global ID and instance numbers are to be obtained from the BAS Owner to ensure duplicates do not occur.

For MS/TP, assign from 01 to 127 unless reserved by the manufacturer. Correlate address with the provided instance number range starting with the lowest number. If there are reserved addresses, do not use the instance number that correlates to those addresses.

Example: Assigned Global ID is 600. If the first trunk address is 04, the instance number will be 158348. If the first trunk address is 05, the instance number will be 158349. If the manufacturer has reserved addresses 01-03, addresses 01-03 and instance numbers 158345-158347 shall not be used.

3.1.2.2 Network Numbering

Assign unique numbers to each new network installed on the BACnet internetwork. Provide ability for changing the network number; either by device switches, network computer, or field operator interface. The BACnet internetwork (all possible connected networks) can contain up to 65,534 possible unique networks.

3.1.2.3 Device Object Identifier Property Number

Assign unique Device "Object_Identifier" property numbers or device instances for each device on the BACnet internetwork. Provide for future modification of the device instance number; either by device switches, network computer, or field interface. Instance numbers must be field assignable. BACnet allows up to 4,194,302 possible unique devices per internetwork.

3.1.2.4 Device Object Name Property Text

Each object on the Camp Lejeune EMCS has a unique point name, which is made up of the object or short name stored in the controller and the equipment identifier, which is stored in the supervisory building controller (SBC). The long point name combines this object name with the name stored in the SBC that describes the controller or location of the object. The device object name property field shall support 32 minimum printable characters. The point name follows the general convention:

Building.Equipment.Object Name

Example: HP512.AHU-3.DA-T. See Attachments one through three for equipment names, object names, object groupings, and area names.

3.1.2.5 Object Name Property Text (Other than Device Objects)

The object name identifies the specific point. Only object names on the approved Camp Lejeune list shall be used. From the example above, the point name is: "DA-T". See Attachment for the approved Camp Lejeune list.

If object name is not in the approved list, then contractor shall send a Request For Information (RFI) to their COTR. The object name property field shall support 32 minimum printable characters.

3.1.2.6 Object Description

The controller shall also store an alpha numeric description of the object name. The controller shall support a minimum of 30 printable characters. From the example above the object description is: "Discharge Air Temperature". Both short names and long names shall be populated in the database.

3.1.2.7 List of Attachments

Attachment 1 - Not Used

Attachment 2 - Object Names

Attachment 3 - NOT USED

Attachment 4 - Niagara BAS Alarms Policy

Attachment 5 - Trend (History)

3.1.3 Minimum BACnet Object Requirements

a. Use of Standard BACnet Objects in accordance with existing Camp Lejeune Standards: For the following points and parameters, use standard BACnet objects, where all relevant object properties can be read using BACnet's Read Property Service, and all relevant object properties can be modified using BACnet's Write Property Service:

(1) All device physical inputs

(2) All device physical outputs

(3) All set points

(4) All PID tuning parameters

(5) All calculated pressures, flow rates, and consumption values

(6) All alarms

(7) All trends

(8) All schedules

(9) All equipment and lighting circuit operating status

b. BACnet Object Description Property: The Object Description property shall support 32 minimum printable characters. For each object, complete the description property field using a brief, narrative, plain English description specific to the object and project application. For example: "HW Pump 1 Proof." Document compliance, length restrictions, and whether the description is writeable in the device PICS.

c. Analog Input, Output, and Value Objects: Support and provide

Description and Device_Type text strings matching signal type and engineering units shown on the points list.

d. Binary Input, Output, and Value Objects: Support and provide Inactive_Text and Active_Text property descriptions matching conditions shown on the points list.

e. Calendar Object: For devices with scheduling capability, provide at least one Calendar Object with ten-entry capacity that incorporates Federal Holidays. All operators may view Calendar Objects; authorized operators may make modifications from a workstation. Enable the writeable Date List property and support all calendar entry data types.

f. Schedule Object: Use Schedule Objects for all building system scheduling. All operators may view schedule entries; authorized operators may modify schedules from a workstation.

g. Loop Object or Equal: Use Loop Objects or equivalent BACnet objects in each applicable field device for PID control. Regardless of program method or object used, allow authorized operators to adjust the Update Interval, Setpoint, Proportional Constant, Integral Constant, and Derivative Constant using BACnet read/write services.

h. Setpoints: All setpoints must be BACnet exposed for auto discovery purposes if needed.

3.1.4 Minimum BACnet Service Requirements

a. Command Priorities

(1) Use commandable BACnet objects to control machinery and systems, providing the priority levels listed below. If the sequence of operation requires a different priority, obtain approval from the Contracting Officer.

Priority Level	Application
1	Manual-Life Safety
2	Automatic-Life Safety
3	(User Defined)
4	(User Defined)
5	Critical Equipment Control
6	Minimum On/Off
7	(User Defined)
8	Manual Operator
9	(User Defined)
10	(User Defined)
11	Load Shedding

Priority Level	Application
12	(User Defined)
13	(User Defined)
14	(User Defined)
15	(User Defined)
16	(User Defined)

b. Alarming

(1) Alarm Priorities: Coordinate alarm and event notification with the BAS Owner.

(2) Notification Class: Enable writeable Priority, Ack Required, and Recipient List properties of Notification Class objects.

(3) Event Notification Message Texts: Use condition specific narrative text and numerical references for alarm and event notification.

c. Updating Displayed Property Values

(1) Allow workstations to display property values at discrete polled intervals, or based on receipt of confirmed and unconfirmed Change of Value notifications. The COV increment shall be adjustable by an operator using BACnet services, and polled intervals shall be adjustable at the operator workstation.

3.1.5 Local Area Networks

Connection of new networks with existing networks will be done by the BAS Owner. Network numbers and device instance numbers shall remain unique when joining networks. Do not change existing network addressing without Government approval. See also "BACnet Naming and Addressing".

3.1.6 BACnet Routers and Protocol Gateways

Provide the quantity of BACnet routers necessary for communications shown on the BACnet Communication Architecture schematic. Provide BACnet routers with BACnet Broadcast Message Device (BBMD) capability on each BACnet internetwork communicating across an IP network. Configure BBMD tables to enable unicast forwarding of broadcast messaging across Layer-3 IP subnets.

3.1.7 Plant Controllers

Equipment such as VFD's, chillers, and boilers shall have hardwired enable(start/stop), and status points from the plant controller, VFD's shall also have a hardwired speed command. Additionally, this equipment shall have a BACnet interface for monitoring.

3.1.8 Digital Controllers

a. Install as stand alone control devices (see definitions in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC).

b. Locate control cabinets at the locations shown on the drawings. If not shown on the drawings, install in the most accessible space, close to the controlled equipment.

c. Controllers must be installed in a manfacturer's required/recommended enclosure for each type of controller.

d. Provide a dedicated analog output to each output device, such as variable frequency driven pump motors in an alternating arrangement.

e. Equipment such as VFD's must have hardwired enable (start/stop), speed command and status points from the controller. Software points are not allowable. Additionally, this equipment shall have a BACnet interface for monitoring.

3.1.9 Wiring Criteria

Wiring criteria requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

3.1.10 Accessibility

Accessibility requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

3.1.11 Component Identification Labeling

Component identification labeling requirements are specified in Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

-- End of Section --

SECTION 23 11 20

FACILITY GAS PIPING
05/20

PART 1 GENERAL

1.1 SUMMARY

This specification section applies to gas piping installed within buildings incidental underground piping under building, above ground steel piping and corrugated stainless steel tubing (CSST) both outside (up to 5 feet beyond exterior walls) and within buildings in compliance with NFPA 54 /AGA Z223.1, "National Fuel Gas Code" , "Fuel Gas Piping".

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN GAS ASSOCIATION (AGA)

AGA ANSI B109.4	(2016) Self-Operated Diaphragm-Type Natural Gas Service Regulators for Nominal Pipe Size 1¼ inches (32 mm) and Smaller with Outlet Pressures of 2 psig (13.8 kPa) and Less
AGA XR0603	(2006; 8th Ed) AGA Plastic Pipe Manual for Gas Service
AGA Z223.1	(2012) National Fuel Gas Code

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z21.15/CSA 9.1	(2009; Addenda A 2012, Addenda B 2013; R 2019) Manually Operated Gas Valves for Appliances, Appliance Connector Valves and Hose End Valves
ANSI Z21.18/CSA 6.3	(2007; R 2017) Gas Appliance Pressure Regulators
ANSI Z21.21/CSA 6.5	(2015) Automatic Valves for Gas Appliances
ANSI Z21.24/CSA 6.10	(2015; Errata 2017) Connectors for Gas Appliances
ANSI Z21.41/CSA 6.9	(2014; R 2019) Quick-Disconnect Devices for Use with Gas Fuel Appliances
ANSI Z21.69/CSA 6.16	(2009; Addenda A 2012; R 2014) Connectors for Movable Gas Appliances
ANSI Z21.80/CSA 6.22	(2019) Line Pressure Regulators

ANSI Z21.93/CSA 6.30 (2017) Excess Flow Valves for Natural Gas and Propane Gas with Pressures up to 5 psig

AMERICAN PETROLEUM INSTITUTE (API)

API RP 2003 (2015; 8th Ed) Protection Against Ignitions Arising out of Static, Lightning, and Stray Currents

API Spec 6D (June 2018, 4th Ed; Errata 1 July 2018; Errata 2 August 2018) Specification for Pipeline and Piping Valves

API Std 598 (2009) Valve Inspecting and Testing

API Std 607 (2016) Fire Test for Quarter-turn Valves and Valves Equipped with Non-metallic Seats

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 25-16 (2016) Earthquake-Activated Automatic Gas Shutoff Devices

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME A13.1 (2020) Scheme for the Identification of Piping Systems

ASME B1.1 (2003; R 2018) Unified Inch Screw Threads (UN and UNR Thread Form)

ASME B1.20.1 (2013; R 2018) Pipe Threads, General Purpose (Inch)

ASME B16.3 (2021) Malleable Iron Threaded Fittings, Classes 150 and 300

ASME B16.5 (2020) Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard

ASME B16.9 (2018) Factory-Made Wrought Buttwelding Fittings

ASME B16.11 (2021) Forged Fittings, Socket-Welding and Threaded

ASME B16.21 (2021) Nonmetallic Flat Gaskets for Pipe Flanges

ASME B16.33 (2012; R 2017) Manually Operated Metallic Gas Valves for Use in Gas Piping Systems Up to 125 psi, (Sizes NPS 1/2 - NPS 2)

ASME B16.39 (2025) Malleable Iron Threaded Pipe Unions; Classes 150, 250, and 300

ASME B18.2.1 (2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)

ASME B18.2.2	(2022) Nuts for General Applications: Machine Screw Nuts, and Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B31.8	(2018; Supplement 2018) Gas Transmission and Distribution Piping Systems
ASME BPVC SEC VIII D1	(2023) BPVC Section VIII-Rules for Construction of Pressure Vessels Division 1

ASTM INTERNATIONAL (ASTM)

ASTM 01.01	(2019) Steel - Piping, Tubing, Fittings
ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A193/A193M	(2025) Standard Specification for Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service and Other Special Purpose Applications
ASTM A194/A194M	(2024) Standard Specification for Carbon Steel, Alloy Steel, and Stainless Steel Nuts for Bolts for High-Pressure or High-Temperature Service, or Both
ASTM A513/A513M	(2019) Standard Specification for Electric-Resistance-Welded Carbon and Alloy Steel Mechanical Tubing
ASTM F2015	(2000; R 2013) Standard Specification for Lap Joint Flange Pipe End Applications

CSA GROUP (CSA)

ANSI LC 1/CSA 6.26	(2019) Fuel Gas Piping Systems Using Corrugated Stainless Steel Tubing (CSST)

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-25	(2018) Standard Marking System for Valves, Fittings, Flanges and Unions
MSS SP-58	(2025) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 54	(2024) National Fuel Gas Code

NFPA 58	(2024; TIA 24-2) Liquefied Petroleum Gas Code
NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-STD-101	(2014; Rev C) Color Code for Pipelines and for Compressed Gas Cylinders

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

49 CFR 192	Transportation of Natural and Other Gas by Pipeline: Minimum Federal Safety Standards

UNDERWRITERS LABORATORIES (UL)

UL FLAMMABLE & COMBUSTIBLE	(2012) Flammable and Combustible Liquids and Gases Equipment Directory

1.3 SYSTEM DESCRIPTION

The gas piping system includes natural gas piping and appurtenances from point of connection with supply system, as indicated, to gas operated equipment within the facility. Submit operation and maintenance data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA, in three separate packages. Section 23 03 00.00 20 BASIC MECHANICAL MATERIALS AND METHODS applies to this section, with additions and modifications specified herein. Provide cathodically protected insulating joints connecting aboveground piping from the meter to the building, with lightning arrestors conforming to API RP 2003, installed where indicated.

1.3.1 Gas Facility System and Equipment Operation

Include shop drawings showing piping layout, locations of system valves, gas line markers and cathodic protection system; step-by-step procedures for system start up, operation and shutdown (index system components and equipment to the system drawings); isolation procedures including valve operation to shutdown or isolate each section of the system (index valves to the system maps and provide separate procedures for normal operation and emergency shutdown if required to be different). Submit Data package No. 4.

1.3.2 Gas Facility System Maintenance

Include maintenance procedures and frequency for system and equipment; identification of pipe materials and manufacturer by locations, pipe repair procedures, and jointing procedures at transitions to other piping material or material from a different manufacturer. Submit Data Package No.4.

1.3.3 Gas Facility Equipment Maintenance

Include identification of valves, shut-offs, disconnects, and other equipment by materials, manufacturer, vendor identification and location; maintenance procedures and recommended tool kits for valves and equipment;

recommended repair methods (i.e., field repair, factory repair, or replacement) for each valve and piece of equipment; and preventive maintenance procedures, possible failure modes and troubleshooting guide. Submit Data Package No. 3.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Gas Piping System; G

SD-03 Product Data

Pipe and Fittings; G

Gas Equipment Connectors; G

Gas Piping System; G

Pressure Regulators; G

Valves; G

SD-06 Test Reports

Testing; G

Pressure Tests; G

Test with Gas; G

SD-07 Certificates

SD-08 Manufacturer's Instructions

SD-10 Operation and Maintenance Data

Gas Facility System and Equipment Operation; G

Gas Facility System Maintenance; G

Gas Facility Equipment Maintenance; G

1.5 QUALITY ASSURANCE

Submit manufacturer's descriptive data and installation instructions for approval for compression-type mechanical joints used in joining dissimilar materials and for insulating joints. Mark all valves, flanges and fittings in accordance with MSS SP-25.

1.5.1 Shop Drawings

Submit drawings for complete Gas Piping System, within 30 days of contract award, showing location, size and all branches of pipeline; location of all required shutoff valves; and instructions necessary for the installation of gas equipment connectors and supports.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

Provide materials and equipment which are the standard products of a manufacturer regularly engaged in the manufacture of the products and that essentially duplicate items that have been in satisfactory use for at least 2 years prior to bid opening. Asbestos or products containing asbestos are not allowed. Submit catalog data and installation instructions for pipe, valves, all related system components, pipe coating materials and application procedures. Conform to NFPA 54 and with requirements specified herein. Provide supply piping to appliances or equipment at least as large as the inlets thereof. Provide pipe and fittings submittal data.

2.2 GAS PIPING SYSTEM AND FITTINGS

2.2.1 Steel Pipe, Joints, and Fittings

a. Pipe: Black carbon steel in accordance with ASTM A53/A53M, Schedule 40 , threaded ends for sizes 2 inches and smaller; otherwise, plain end beveled for butt welding.

b. Threaded Fittings: ASME B16.3, black malleable iron.

c. Socket-Welding Fittings: ASME B16.11, forged steel.

d. Butt-Welding Fittings: ASME B16.9, with backing rings of compatible material.

e. Unions: ASME B16.39, black malleable iron.

f. Flanges and Flanged Fittings: ASME B16.5 steel flanges or convoluted steel flanges conforming to ASME BPVC SEC VIII D1, with flange faces having integral grooves of rectangular cross sections which afford containment for self-energizing gasket material.

2.2.2 Steel Tubing, Joints and Fittings

Provide steel tubing conforming to ASTM 01.01, and ASTM A513/A513M, with tubing joints made up with gas tubing fittings recommended by the tubing manufacturer.

2.2.3 Sealants for Steel Pipe Threaded Joints

Provide joint sealing compound as listed in UL FLAMMABLE & COMBUSTIBLE, Class 20 or less. For taping, use tetrafluoroethylene tape conforming to UL FLAMMABLE & COMBUSTIBLE.

2.2.4 Flange Gaskets

Provide gaskets of nonasbestos compressed material in accordance with ASME B16.21, 1/16 inch thickness, full face or self-centering flat ring type, containing aramid fibers bonded with styrene butadiene rubber (SBR) or nitrile butadiene rubber (NBR) suitable for a maximum 600 degree F service, to be used for hydrocarbon service.

2.2.5 Pipe Threads

Provide pipe threads conforming to ASME B1.20.1.

2.2.6 Escutcheons

Provide chromium-plated steel or chromium-plated brass escutcheons, either one piece or split pattern, held in place by internal spring tension or set screw.

2.2.7 Insulating Pipe Joints

2.2.7.1 Insulating Joint Material

Provide insulating joint material between flanged or threaded metallic pipe systems where shown to control galvanic or electrical action.

2.2.7.2 Threaded Pipe Joints

Provide threaded pipe joints of steel body nut type dielectric unions with insulating gaskets.

2.2.7.3 Flanged Pipe Joints

Provide joints for flanged pipe consisting of full face sandwich-type flange insulating gasket of the dielectric type, insulating sleeves for flange bolts, and insulating washers for flange nuts. Provide lap joint flange pipe ends conforming to ASTM F2015.

2.2.8 Flexible Connectors

a. Provide flexible connectors for connecting gas utilization equipment to building gas piping conforming to ANSI Z21.24/CSA 6.10 or ANSI Z21.41/CSA 6.9 for quick disconnect devices, and flexible connectors for movable food service equipment conforming to ANSI Z21.69/CSA 6.16.

b. Do not install the flexible connector through the appliance cabinet face. Provide rigid metallic pipe and fittings to extend the final connection beyond the cabinet, except when appliance is provided with an external connection point.

2.3 VALVES

Provide lockable shutoff or service isolation valves as indicated in the

drawings conforming to the following:

2.3.1 Valves 2 Inches and Smaller

Provide valves 2 inches and smaller conforming to ASME B16.33 of materials and manufacture compatible with system materials used.

2.3.2 Valves 2-1/2 Inches and Larger

Provide valves 2-1/2 inches and larger of carbon steel conforming to API Spec 6D, Class 150.

2.4 PIPE HANGERS AND SUPPORTS

Provide pipe hangers and supports conforming to MSS SP-58.

2.5 LINE AND APPLIANCE REGULATORS AND SHUTOFF VALVES

Provide regulators conforming to ANSI Z21.18/CSA 6.3 for appliances , and ANSI Z21.80/CSA 6.22 for line pressure regulators. Provide shutoff valves conforming to ANSI Z21.15/CSA 9.1 for manually controlled gas shutoff valves and ANSI Z21.21/CSA 6.5 for automatic shutoff valves for gas appliances.

2.6 NATURAL GAS SERVICE

2.6.1 Service Regulators

a. Provide ferrous bodied pressure regulators for individual service lines, capable of reducing distribution line pressure to pressures required for users. Provide service regulators conforming to AGA ANSI B109.4 CGA-6.18-M95 with full capacity internal relief and overpressure shutoff. Set pressure relief at a lower pressure than would cause unsafe operation of any connected user.

b. Adjust regulators for liquified petroleum gas to 2.5 to 3 kPa 10 to 12 inches of water column, with pressure relief set at 4 kPa 16 inches of water column.

c. Provide regulator(s) having a single port with orifice diameter no greater than that recommended by the manufacturer for the maximum gas flow rate at the regulator inlet pressure. Provide regulator valve vent of resilient materials designed to withstand flow conditions when pressed against the valve port, capable of regulating downstream pressure within limits of accuracy and limiting the buildup of pressure under no-flow conditions to 50 percent or less of the discharge pressure maintained under flow conditions. Provide a self-contained service regulator, and pipe not exceeding exceed 2 inch size.

2.7 AUTOMATIC GAS SHUT-OFF

Provide low pressure automatic gas shutoff or excess flow valve (EFV) downstream of the point of delivery after the meter/regulator conforming to ANSI Z21.93/CSA 6.30 and UL listed or CSA listed or International Association of Plumbing and Mechanical Officials (IAPMO) listed. The EFV may be either a bypass (automatic reset) or a non-bypass type (manual reset).

2.8 BOLTING (BOLTS AND NUTS)

Stainless steel bolting; ASTM A193/A193M, Grade B8M or B8MA, Type 316, for bolts; and ASTM A194/A194M, Grade 8M, Type 316, for nuts. Dimensions of bolts, studs, and nuts must conform with ASME B18.2.1 and ASME B18.2.2 with coarse threads conforming to ASME B1.1, with Class 2A fit for bolts and studs and Class 2B fit for nuts. Bolts or bolt-studs must extend through the nuts and may have reduced shanks of a diameter not less than the diameter at root of threads. Bolts must have American Standard regular square or heavy hexagon heads; nuts must be American Standard heavy semifinished hexagonal.

2.9 GASKETS

Fluorinated elastomer, compatible with flange faces.

2.10 IDENTIFICATION FOR ABOVEGROUND PIPING

MIL-STD-101 for legends and type and size of characters. For pipes 3/4 inch od and larger, provide printed legends to identify contents of pipes and arrows to show direction of flow. Color code label backgrounds to signify levels of hazard. Make labels of plastic sheet with pressure-sensitive adhesive suitable for the intended application. For pipes smaller than 3/4 inch od, provide brass identification tags 1 1/2 inches in diameter with legends in depressed black-filled characters.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy or areas of conflict before performing the work.

3.2 GAS PIPING SYSTEM

Provide a gas piping system from the point of delivery, defined as the outlet of the meter set assembly , as specified under "Gas Service" within this specification, to the connections to each gas utilization device that is in compliance with NFPA 54..

3.2.1 Protection and Cleaning of Materials and Components

Protect equipment, pipe, and tube openings by closing with caps or plugs during installation. At the completion of all work, thoroughly clean the entire system.

3.2.2 Workmanship and Defects

Piping, tubing and fittings must be clear and free of cutting burrs and defects in structure or threading and must be thoroughly brushed and chip-and scale-blown. Repair of defects in piping, tubing or fittings is not allowed; replace defective items when found.

3.3 PROTECTIVE COVERING

3.3.1 Aboveground Metallic Piping Systems

3.3.1.1 Ferrous Surfaces

Touch up shop primed surfaces with ferrous metal primer. Solvent clean surfaces that have not been shop primed . Mechanically clean surfaces that contain loose rust, loose mill scale and other foreign substances by power wire brushing and prime with ferrous metal primer or vinyl type wash coat. Finish primed surfaces with two coats of exterior oil paint or vinyl paint.

3.4 INSTALLATION

Install the gas system in conformance with the manufacturer's recommendations and applicable provisions of NFPA 54 and AGA XR0603, and as indicated. Perform all pipe cutting without damage to the pipe, with an approved type of mechanical cutter, unless otherwise authorized. Use wheel cutters where practicable. On steel pipe 6 inches and larger, an approved gas cutting and beveling machine may be used. Cut thermoplastic and fiberglass pipe in accordance with AGA XR0603.

3.4.1 Metallic Piping Installation

Bury underground piping a minimum of 18 inches below grade. Make changes in direction of piping with fittings only; mitering or notching pipe to form elbows and tees or other similar type construction is not permitted. Branch connection may be made with either tees or forged branch outlet fittings. Provide branch outlet fittings which are forged, flared for improvement of flow where attached to the run, and reinforced against external strains. Do not use aluminum alloy pipe in exterior locations or underground.

3.4.2 Concealed Piping in Buildings

Do not use combinations of fittings (unions, tubing fittings, running threads, right- and left-hand couplings, bushings, and swing joints) to conceal piping within buildings.

3.4.2.1 Piping and Tubing in Partitions

Locate concealed piping and tubing in hollow, rather than solid, partitions. Protect tubing passing through walls or partitions against physical damage both during and after construction, and provide appropriate safety markings and labels. Provide protection of concealed pipe and tubing in accordance with ANSI LC 1/CSA 6.26.

3.4.3 Aboveground Piping

Run aboveground piping as straight as practicable along the alignment and elevation indicated, with a minimum of joints, and separately supported from other piping system and equipment. Install exposed horizontal piping no farther than 6 inches from nearest parallel wall and at an elevation which prevents standing, sitting, or placement of objects on the piping.

3.4.4 Final Gas Connections

Unless otherwise specified, make final connections with rigid metallic

pipe and fittings. Provide accessible gas shutoff valve and coupling for each gas equipment item.

3.4.5 Seismic Requirements

Support and brace piping and attached valves to resist seismic loads in conformance with ASCE 25-16. CSST tubing and fittings that are seismically qualified in accordance with the FM APP GUIDE: Flexible Piping Systems for Flammable Gases must meet the seismic requirements in accordance with the manufacturer's installation instructions.

3.5 PIPE JOINTS

Design and install pipe joints to effectively sustain the longitudinal pull-out forces caused by contraction of the piping or superimposed loads.

3.5.1 Threaded Metallic Joints

Provide threaded joints in metallic pipe with tapered threads evenly cut and made with UL approved graphite joint sealing compound for gas service or tetrafluoroethylene tape applied to the male threads only. Threaded joints up to 1-1/2 inches in diameter may be made with approved tetrafluoroethylene tape. Threaded joints up to 2 inches in diameter may be made with approved joint sealing compound. After cutting and before threading, ream pipe and remove all burrs. Caulking of threaded joints to stop or prevent leaks is not permitted.

3.5.2 Welded Metallic Joints

Conform beveling, alignment, heat treatment, and inspection of welds to NFPA 54. Remove weld defects and make repairs to the weld, or remove the weld joints entirely and reweld. After filler metal has been removed from its original package, protect and store so that its characteristics or welding properties are not affected adversely. Do not use electrodes that have been wetted or have lost any of their coating.

3.5.3 Solder or Brazed Joints

Make all joints in metallic tubing and fittings with materials and procedures recommended by the tubing supplier. Braze joints with material having a melting point above 1000 degrees F, containing no phosphorous.

3.5.4 Press Connections

Make press connections in accordance with manufacturer's installation instructions using tools approved by the manufacturer. Fully insert the tubing into the fitting and then mark at the shoulder of the fitting. Check the fitting alignment against the mark on the tubing to assure the tubing is fully inserted before the joint is pressed.

3.6 PIPE SLEEVES

Provide pipes passing through concrete or masonry walls or concrete floors or roofs with pipe sleeves fitted into place at the time of construction. Do not install sleeves in structural members except where indicated or approved. Make all rectangular and square openings as detailed. Extend each sleeve through its respective wall, floor or roof, and cut flush with each surface, except in mechanical room floors not located on grade where clamping flanges or riser pipe clamps are used. Extend sleeves in

mechanical room floors above grade at least 4 inches above finish floor. Unless otherwise indicated, use sleeves large enough to provide a minimum clearance of 1/4 inch all around the pipe. Provide steel pipe for sleeves in bearing walls, waterproofing membrane floors, and wet areas . Provide sleeves in nonbearing walls, floors, or ceilings of steel pipe, galvanized sheet metal with lock-type longitudinal seam, or moisture-resistant fiber or plastic. For penetrations of fire walls, fire partitions and floors which are not on grade, seal the annular space between the pipe and sleeve with fire-stopping material and sealant that meet the requirement of Section 07 84 00 FIRESTOPPINGG.

3.7 PIPES PENETRATING WATERPROOFING MEMBRANES

Install pipes penetrating waterproofing membranes as specified in Section 22 00 00 PLUMBING, GENERAL PURPOSE.

3.8 FIRE SEAL

Fire seal all penetrations of fire rated partitions, walls and floors in accordance with Section 07 84 00 FIRESTOPPING.

3.9 ESCUTCHEONS

Provide escutcheons for all finished surfaces where gas piping passes through floors, walls, or ceilings except in boiler, utility, or equipment rooms.

3.10 SPECIAL REQUIREMENTS

Provide drips, grading of the lines, freeze protection, and branch outlet locations as shown and conforming to the requirements of NFPA 54.

3.11 BUILDING STRUCTURE

Do not weaken any building structure by the installation of any gas piping. Do not cut or notch beams, joists or columns. Attach piping supports to metal decking. Do not attach supports to the underside of concrete filled floors or concrete roof decks unless approved by the Contracting Officer.

3.12 PIPING SYSTEM SUPPORTS

Support gas piping systems in buildings with pipe hooks, metal pipe straps, bands or hangers suitable for the size of piping or tubing. Do not support any gas piping system by other piping. Conform spacing of supports in gas piping and tubing installations to the requirements of NFPA 54. Conform the selection and application of supports in gas piping and tubing installations to the requirements of MSS SP-58. In the support of multiple pipe runs on a common base member, use a clip or clamp where each pipe crosses the base support member. Spacing of the base support members is not to exceed the hanger and support spacing required for any of the individual pipes in the multiple pipe run. Rigidly connect the clips or clamps to the common base member. Provide a clearance of 1/8 inch between the pipe and clip or clamp for all piping which may be subjected to thermal expansion.

3.13 ELECTRICAL BONDING AND GROUNDING

Provide a gas piping system within the building that is electrically

continuous and bonded to a grounding electrode as required by NFPA 54, NFPA 58, and NFPA 70.

3.14 SHUTOFF VALVE

Install the main gas shutoff valve controlling the gas piping system to be easily accessible for operation, as indicated, protected from physical damage, and marked with a metal tag to clearly identify the piping system controlled. Install valves approximately at locations indicated. Orient stems vertically, with operators on top, or horizontally. Provide stop valve on service branch at connection to main and shut-off valve on riser outside of building.

3.15 LINE AND APPLIANCE PRESSURE REGULATORS

Install line pressure regulators and appliance regulators in accordance with the manufacturer's requirements and in accordance with NFPA 54. Install each regulator in an accessible location and install shutoff valves ahead of each line and appliance regulator to allow for maintenance. Where vent limiting devices are not included in the regulators, install a vent pipe to the exterior of the building. Terminate all service regulator vents and relief vents in the outside air in rain and insect resistant fittings. Locate the open end of the vent where gas can escape freely into the atmosphere, away from any openings into the building and above areas subject to flooding.

3.16 GAS SERVICE INSTALLATION

Installations must be in accordance with 49 CFR 192 and ASME B31.8. Contractor must submit and use only tested and approved work procedures. Contractor must use only welders and jointers who have been recently qualified by training and test for joining and installing the gas pipe material used on this job. The finished product must be inspected by a person qualified to inspect joints made by the particular procedures used to make joints.

3.17 TESTING

Submit test procedures and reports in booklet form tabulating test and measurements performed; dated after award of this contract, and stating the Contractor's name and address, the project name and location, and a list of the specific requirements which are being certified. Test entire gas piping system to ensure that it is gastight prior to putting into service. Prior to testing, purge the system, clean, and clear all foreign material. Test each joint with an approved gas detector, soap and water, or an equivalent nonflammable solution. Inspect and test each valve in conformance with API Std 598 and API Std 607. Complete testing before any work is covered, enclosed, or concealed, and perform with due regard for the safety of employees and the public during the test. Install bulkheads, anchorage and bracing suitably designed to resist test pressures if necessary, and as directed and or approved by the Contracting Officer. Do not use oxygen as a testing medium.

3.17.1 Pressure Tests

Submit test procedures and reports in booklet form tabulating test and measurements performed; dated after award of this contract, and stating the Contractor's name and address, the project name and location, and a

list of the specific requirements which are being certified. Before appliances are connected, test by filling the piping systems with air or an inert gas to withstand a minimum pressure of 3 pounds gauge for a period of not less than 10 minutes as specified in NFPA 54 without showing any drop in pressure. Do not use Oxygen for test. Measure pressure with a mercury manometer, slope gauge, or an equivalent device calibrated to be read in increments of not greater than 0.1 pound. Isolate the source of pressure before the pressure tests are made.

3.17.2 Test With Gas

Before turning on gas under pressure into any piping, close all openings from which gas can escape. Immediately after turning on the gas, check the piping system for leakage by using a laboratory-certified gas meter, an appliance orifice, a manometer, or equivalent device. Conform all testing to the requirements of NFPA 54. If leakage is recorded, shut off the gas supply, repair the leak , and repeat the tests until all leaks have been stopped.

3.17.3 Purging

After testing is completed, and before connecting any appliances, fully purge all gas piping. Do not purge piping into the combustion chamber of an appliance. Do not purge the open end of piping systems into confined spaces or areas where there are ignition sources unless the safety precautions recommended in NFPA 54 are followed.

3.17.4 Labor, Materials and Equipment

Furnish all labor, materials and equipment necessary for conducting the testing and purging.

3.18 PIPE COLOR CODE MARKING

Provide color code marking of piping as specified in Section 09 90 00 PAINTS AND COATINGS, conforming to ASME A13.1.

-- End of Section --

SECTION 23 21 13.00 20

LOW TEMPERATURE WATER (LTW) HEATING SYSTEM
04/06, CHG 2: 11/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B1.1	(2003; R 2018) Unified Inch Screw Threads (UN and UNR Thread Form)
ASME B1.20.1	(2013; R 2018) Pipe Threads, General Purpose (Inch)
ASME B16.1	(2020) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250
ASME B16.5	(2020) Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard
ASME B16.9	(2018) Factory-Made Wrought Buttwelding Fittings
ASME B16.18	(2021) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.21	(2021) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.22	(2021) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.24	(2022) Cast Copper Alloy Pipe Flanges, Flanged Fittings, and Valves Classes 150, 300, 600, 900, 1500, and 2500
ASME B16.34	(2021) Valves - Flanged, Threaded and Welding End
ASME B16.36	(2020) Orifice Flanges
ASME B16.39	(2025) Malleable Iron Threaded Pipe Unions; Classes 150, 250, and 300
ASME B18.2.2	(2022) Nuts for General Applications: Machine Screw Nuts, and Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B31.9	(2020) Building Services Piping
ASME B40.100	(2022) Pressure Gauges and Gauge

Attachments

ASME BPVC SEC VIII D1 (2023) BPVC Section VIII-Rules for Construction of Pressure Vessels Division 1

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

ASSE 1003 (2020) Performance Requirements for Water Pressure Reducing Valves for Domestic Water Distribution Systems - (ANSI approved 2010)

ASSE 1017 (2023) Performance Requirements for Temperature Actuated Mixing Valves for Hot Water Distribution Systems - (ANSI approved 2010)

AMERICAN WELDING SOCIETY (AWS)

AWS Z49.1 (2021) Safety in Welding, Cutting and Allied Processes

ASTM INTERNATIONAL (ASTM)

ASTM A53/A53M (2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

ASTM A123/A123M (2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM A194/A194M (2024) Standard Specification for Carbon Steel, Alloy Steel, and Stainless Steel Nuts for Bolts for High-Pressure or High-Temperature Service, or Both

ASTM A307 (2023) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength

ASTM B32 (2020) Standard Specification for Solder Metal

ASTM B88 (2022) Standard Specification for Seamless Copper Water Tube

ASTM F1007 (2018) Standard Specification for Pipeline Expansion Joints of the Packed Slip Type for Marine Application

ASTM F1120 (1987; R 2019) Standard Specification for Circular Metallic Bellows Type Expansion Joints for Piping Applications

ASTM D2308 (2007; R 2013) Standard Specification for Thermoplastic Polyethylene Jacket for Electrical Wire and Cable

ASTM F1199 (2021) Standard Specification for Cast (All Temperatures and Pressures) and Welded Pipe Line Strainers (150 psig and 150 degrees F Maximum)

COPPER DEVELOPMENT ASSOCIATION (CDA)

CDA A4015 (2016; 14/17) Copper Tube Handbook

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 515 (2017) Standard for the Testing, Design, Installation, and Maintenance of Electrical Resistance Heat Tracing for Industrial Applications

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-58 (2025) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation

MSS SP-67 (2022) Butterfly Valves

MSS SP-69 (2003; Notice 2012) Pipe Hangers and Supports - Selection and Application (ANSI Approved American National Standard)

MSS SP-70 (2011) Gray Iron Gate Valves, Flanged and Threaded Ends

MSS SP-72 (2010a) Ball Valves with Flanged or Butt-Welding Ends for General Service

MSS SP-80 (2019) Bronze Gate, Globe, Angle, and Check Valves

MSS SP-85 (2011) Gray Iron Globe & Angle Valves Flanged and Threaded Ends

MSS SP-110 (2010) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA ICS 2 (2000; R 2020) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V

NEMA ICS 6 (1993; R 2016) Industrial Control and Systems: Enclosures

NEMA MG 1 (2021) Motors and Generators

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-V-12003 (1980; Rev F; Am 1; CANC Notice 1) Valves,

	Plug, Cast-Iron or Steel, Manually Operated

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-1689	(Rev B) Tape, Pressure-Sensitive Adhesive, (Plastic Film)
CID A-A-50560	(Basic) Pumps, Centrifugal, Water Circulating, Electric-Motor-Driven
CID A-A-59617	(Basic, Notice 1) Unions, Brass or Bronze, Threaded Pipe Connections and Solder-Joint Tube Connections

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.144	Safety Color Code for Marking Physical Hazards
29 CFR 1910.219	Mechanical Power Transmission Apparatus

1.2 RELATED REQUIREMENTS

Section 23 03 00.00 20 BASIC MECHANICAL MATERIALS AND METHODS applies to this section with additions and modifications specified herein.

1.3 SYSTEM DESCRIPTION

Except as specified otherwise, equipment and piping components shall be suitable for use in low temperature water heating system. Except as modified herein, the pressure temperature limitations shall be as specified in the referenced standards and specifications. Pressures in this specification are pressures in pounds per square inch above atmospheric pressure, and temperatures are in degrees Fahrenheit (F).

1.3.1 Hot Water Heating System

Submit plan, elevations, dimensions, capacities, and ratings. Include the following:

d. Pumps

e. Valves

f. Expansion tanks

g. Flow measuring equipment

h. Backflow preventer

i. Air separating tank

l. Converters

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for

Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Hot water heating system

SD-03 Product Data

Pumps

Include pump speed and characteristic curve for performance of impeller selected for each pump. Curves shall indicate capacity vs head, efficiency, and brake power for full range, from shut-off to free delivery.

Expansion tanks

Flow measuring equipment

External air separation tanks

Hot water heating pipe

Combination Strainer And Pump Suction Diffuser

SD-06 Test Reports

Hydrostatic test of piping system

Auxiliary equipment and accessory tests

Submit test reports in accordance with the paragraph entitled "Field Quality Control."

SD-07 Certificates

Backflow preventer certification

Report of prior installations

Welding procedures

Welder's qualifications

1.5 QUALITY ASSURANCE

1.5.1 Standard Commercial Product for Terminal Units

Terminal units provided shall comply with features called out in this specification and shall be the manufacturer's standard commercial product. Additional or better features which are not prohibited by this specification but which are a part of the manufacturer's standard commercial product, shall be included in the terminal units being furnished. A standard commercial product is a product which has been sold or is currently being offered for sale, on the commercial market through advertisements or manufacturer's catalogs, or brochures. Provide Institute of Boiler and Radiator Manufacturer (IBR) or Steel Boiler

Institute (SBI) rating for required capacity.

1.5.2 Welding

1.5.2.1 Report of Prior Installations

Submit a Certificate of Full Approval or a current Certificate of Approval for each design, size, and make of backflow preventer being provided for the project. Certificate shall be from the Foundation for Cross-Connection Control and Hydraulic Research, University of Southern California, and shall attest that this design, size, and make of backflow preventer has satisfactorily passed the complete sequence of performance testing and evaluation for the respective level of approval. A Certificate of Provisional Approval is not acceptable in lieu of the above.

1.5.2.2 Welding Procedures

Before performing welding, submit three copies of welding procedure specification for all metals to be used in the work, together with proof of welder's qualification as outlines in ASME B31.9.

1.5.2.3 Welder's Qualifications

Before welder or operator performs welding, submit three copies of Welder's Performance Qualification Record in conformance with ASME B31.9 showing that the welder was tested under the approved procedure specification submitted by the Contractor. In addition, submit each welder's assigned number, letter, or symbol used to identify the work of the welder.

1.5.2.4 Identification of Welder's Work

Ensure that each welder's assigned number, letter or symbol is affixed immediately upon completion of the weld. To welders making defective welds after passing a qualification test, give a requalification test. Upon failing to pass the test, do not permit welder to work in this contract.

1.5.2.5 Previous Qualifications

Welding procedures, welders, and welding operators previously qualified by test may be accepted for this contract without requalification subject to the approval and provided that all the conditions specified in ASME B31.9 are met before a procedure can be used.

1.5.3 Brazing and Soldering

1.5.3.1 Brazing Procedure

ASME B31.9. Brazing procedure for joints shall be as outlined in CDA A4015.

1.5.3.2 Soldering, Soldering Preparation, and Procedures for Joints

ASME B31.9 and as outlined in CDA A4015.

1.5.4 Backflow Preventer Certification

Submit a Certificate of Full Approval or a current Certificate of Approval for backflow preventers.

1.6 SAFETY STANDARDS

1.6.1 Welding

Safety in welding and cutting of pipe shall conform to AWS Z49.1.

1.6.2 Guards

Couplings, motor shafts, gears and other moving parts shall be guarded, in accordance with OSHA 29 CFR 1910.219. Guards shall be cast iron or expanded metal. Guard parts shall be rigid and removable without disassembling the guarded unit.

PART 2 PRODUCTS

2.1 ELECTRICAL HEAT TRACING

Provide heat trace systems for all exterior pipes, valves, and fittings that are in accordance with IEEE 515 and be UL listed. System include all necessary components, including heaters and controls to prevent freezing.

Provide self-regulating heaters consisting of two 16 AWG tinned-copper bus wires embedded in parallel in a self-regulating polymer core that varies its power output to respond to temperature along its length. Ensure heater is able to be crossed over itself without overheating. Obtain approval before used directly on plastic pipe. Cover heater with a radiation cross-linked modified polyolefin dielectric jacket in accordance with ASTM D2308.

Provide heater with self-regulating factor of at least 90 percent, in order to provide energy conservation and to prevent overheating.

Operate heater on line voltages as shown on plans.

Size Heater according to the following table:

Pipe Size

(Inch, Diameter)	Minus 10 degrees F	Minus 20 degrees F
3 inches or less	5 watts per foot (wpf)	5 wpf
4 inch	5 wpf	8 wpf
6 inch	8 wpf	8 wpf
8 inch	2 strips/5 wpf	2 strips/8 wpf
12 inch	2 strips/8 wpf	2 strips/8 wpf

Control systems by an ambient sensing thermostat set at 40 degrees F either directly or through an appropriate contactor.

2.2 PIPE AND FITTINGS

2.2.1 Hot Water Heating Pipe (Supply and Return)

ASTM A53/A53M electric resistance welded or seamless Schedule 40 Black steel pipe or ASTM B88 Type L hard drawn Copper tubing. Above ground piping 4 inch and smaller must be Type L copper. Piping larger than 4 inches shall be Type L copper or Schedule 40 Black steel pipe.

2.2.2 Fittings

Provide fittings compatible with the pipe being provided and shall conform to the following requirements.

2.2.2.1 Steel, Cast Iron, or Bronze

Sizes 2 1/2 inches and above. Steel fitting butt welding type ASME B16.9 or ASME B16.5 flanged type. Cast iron fittings flanged type ASME B16.1. Bronze fittings up to 8 inch size flanged type ASME B16.24.

2.2.2.2 Fittings for Copper Tubing

ASME B16.18 cast bronze solder joint type or ASME B16.22 wrought copper solder joint type. Fittings may be flared or compression joint type.

2.2.3 Unions

2.2.3.1 Steel Pipe

Provide ASME B16.39, malleable iron unions, threaded connections.

2.2.3.2 Copper Tubing

Provide CID A-A-59617, bronze unions, solder joint end.

2.2.3.3 Dielectric Union

Provide insulated union with galvanized steel female pipe-threaded end and a copper solder joint end conforming with ASME B16.39, Class 1, dimensional, strength and pressure requirements. Union shall have a water-impervious insulation barrier capable of limiting galvanic current to one percent of the short-circuit current in a corresponding bimetallic joint. When dry, insulation barrier shall be able to withstand a 600-volt breakdown test.

2.2.4 Flanges

Remove raised faces when used with flanges having a flat face.

2.2.4.1 Steel Flanges

ASME B16.5 forged steel, welding type.

2.2.4.2 Bronze Screwed Flanges

ASME B16.24.

2.2.5 Drains and Overflows

2.2.5.1 Steel Pipe

ASTM A53/A53M, Seamless Schedule 40, Malleable iron or forged steel fittings, screwed or welded joints.

2.2.5.2 Copper Tubing

ASTM B88, Type L, hard drawn, cast brass or wrought copper fittings, Grade Sb5 solder joints.

2.2.6 Valves

Valves shall have rising stems and shall open when turned counterclockwise.

2.2.6.1 Gate Valves

a. Bronze Gate Valves: MSS SP-80, 2 inches and smaller, wedge disc, inside screw type not less than Class 150. Use solder joint ends with copper tubing.

b. Steel Gate Valves: ASME B16.34, provide with open stem and yoke type with solid wedge or flexible wedge disc and heat and corrosion-resistant steel trim.

c. Cast Iron Gate Valves: MSS SP-70, 2 1/2 inches and larger, open stem and yoke type with bronze trim.

2.2.6.2 Globe and Angle Valves

a. Bronze Globe and Angle Valves: MSS SP-80, 2 inches and smaller, Class 200, except use Class 150 with solder ends for copper tubing. Valves shall have renewable seat and discs except solder end valves which shall have integral seats.

b. Steel Globe and Angle Valves: ASME B16.34, provide with heat and corrosion-resistant trim.

c. Cast Iron Globe and Angle Valves: MSS SP-85, 2 1/2 inches and larger, with bronze trim, tapped drains and brass plug.

2.2.6.3 Check Valves

a. Bronze Check Valves: MSS SP-80, 2 inches and smaller, regrinding swing check type, Class 200.

b. Steel Swing Check Valves: ASME B16.34, regrinding swing check type, Class 200.

(1) Swing check valves shall have bolted caps.

(2) Lift check valves 2 1/2 inches and larger shall have pressure seal caps.

c. Cast Iron Check Valves: ASME B16.34, 2 1/2 inches and larger, bronze trim, non-slam, eccentric disc type for centrifugal pump discharge service.

2.2.6.4 Temperature Regulating Valves

Provide ASSE 1017 copper alloy body with adjustable range thermostat.

2.2.6.5 Water Pressure-Reducing Valves

ASSE 1003.

2.2.6.6 Plug Valves

MIL-V-12003, except that a replaceable valve seat will not be required. Type II - non-lubricated, lift-plug valves.

2.2.6.7 Ball Valves

Flanged or butt-welding ends ball valve shall conform to MSS SP-72, bronze . Threaded, socket-welding, solder joint, grooved and flared ends shall conform to MSS SP-110.

2.2.6.8 Flow Control Balancing Valves

Copper alloy or cast iron body, copper alloy or stainless internal working parts, and integral pointer that indicates the degree of valve opening. Valves shall be suitable for 125 psig at 190 degrees F hot water. Valve shall function as a service valve when in fully closed position. Valve body shall have factory-installed tappings for differential pressure meter connections for verification of pressure differential across valve orifice. Meter connections shall have positive check valves or shutoff valves. Each valve shall have metal tag showing the gallons per minute flow for each differential pressure reading.

2.2.6.9 Butterfly Valves

Conform with MSS SP-67, Type I - Tight shut off valve, and flanged valve ends. Valve body material shall be cast iron and shall be bubble tight for shutoff at 150 psig. Flanged and flangeless type valves shall have Type 300 series corrosion resistant steel stems and corrosion resistant or bronze discs with molded elastomer disc seals. Flow conditions shall be for the regulation from maximum flow to complete shutoff by way of throttling effect. Valves shall be provided in closed system. Valves smaller than 8 inches shall have throttling handles. Valves 8 inches and larger shall have totally enclosed manual gear operators with adjustable balance return stops and indicators. Valves shall have a minimum of 7 locking positions and shall be suitable for water temperatures up to 200 degrees F.

2.2.6.10 Butterfly Valves 2 Inches and Smaller

Valves shall be one-piece and three-piece design with male or female threaded or soldered end connections and shall be bubble tight for shutoff at 150 psig. Stem and disc assembly shall be of 300 series corrosion resistant steel. Disc seal assembly shall be of 300 series corrosion resistant steel. Disc seal shall be suitable for the liquid being used in the system in which the valve is to be installed. Valves shall be suitable for water temperature up to 200 degrees F and shall be capable of operating at the rated pressure of 150 psig. Valves shall be designed for throttling service use by valve lever and indicator adjustment.

2.2.6.11 Relief Valves

Bronze body, teflon seat, stainless steel stem and springs, automatic, direct pressure actuated, capacities ASME certified and labelled.

2.2.6.12 Valve Operating Mechanisms

Provide power operators and extension stems where indicated and as specified.

c. Power Operators: Shall be electric . Power operated valves shall open and close at rates no slower than 10 inches per minute for gate valves and 4 inches per minute for globe and angle valves. Valves shall open fully or close tightly without requiring further attention when the actuating control is moved to the open or close position. A predetermined thrust exerted on the stem during operation resulting from an obstruction in the valve shall cause the motor to automatically stop. Power operators shall be complete with all gearing and controls necessary for the size of valve being provided. Power operators shall be designed to operate on the electric power supply indicated.

d. Extension Stem: Corrosion resisting steel designed for rising and non-rising stems. Provide in length required to connect the valve stem and the operating mechanism and of sufficient cross section to transfer the torque required to operate the valve.

2.2.6.13 Balancing Valves

Balancing valves shall be calibrated bronze body balancing valves with integral ball valve and venturi or valve orifice and valve body pressure taps for flow measurement based on differential pressure readings. Valve pressure taps and meter connections shall have seals and built-in check valves with threaded connections for a portable meter. Meter shall be provided by the same manufacturer and be capable of reading system pressures and shall meet the requirements of the paragraph entitled "Flow Measuring Equipment." Valves shall have internal seals to prevent leakage around rotating element and be suitable for full shut-off rated pressure. Valves shall have an operator with integral pointer and memory stop. Balancing valves shall be selected for the required flows as indicated on the plans.

2.2.7 End Connections

2.2.7.1 Flexible Connectors

Provide flexible pipe connectors on piping connected to equipment. Flexible section shall consist of rubber, tetrafluoroethylene resin, corrosion-resistant steel, bronze, monel, or galvanized steel. Material provided and configuration shall be suitable for pressure, temperature, and circulating medium. Flexible section shall have flanged ends and shall be suitable for service intended. Flexible section may be reinforced with metal retaining rings, with built-in braided wire reinforcement and restriction bolts or with wire braid cover suitable for service intended.

2.2.7.2 Steel Piping

Screwed or socket welded for 2 inches and smaller and flanged or butt

welded for 2 1/2 inches and larger.

a. Screwed Joints With Taper Threads: ASME B1.20.1.

b. Flanged Joints: Bolting and gaskets shall be as follows:

(1) Bolting: Bolt and stud material ASTM A307, Grade B, and nut material ASTM A194/A194M, Grade 2. Bolt, stud, and nut dimensions ASME B18.2.2 threads ASME B1.1coarse type with Class 2A fit for bolts and studs, and Class 2B fit for nuts. Bolts or bolt studs shall extend completely through the nuts and may have reduced shanks of a diameter not less than the diameter at root of threads. Carbon steel bolts shall have American Standard regular square or heavy hexagon heads and shall have American Standard heavy semifinished hexagonal nuts conforming to ASME B18.2.2.

(2) Gaskets: ASME B16.21, Nonasbestos compressed material 1/16 inch thickness full face or self-centering flat ring type and suitable for pressure and temperature of the piping system.

c. Butt Weld Joints: ASME B31.9. Backing rings shall conform to ASME B31.9. Ferrous rings shall not exceed 0.05 percent sulfur; for alloy pipe, backing rings shall be of material compatible with the chemical composition of the parts to be welded and preferably of the same composition. Provide continuous machined or split band backing rings.

d. Socket Weld Joints: ASME B31.9.

2.2.7.3 Joints for Copper Tubing

a. Solder conforming to ASTM B32 alloy grade Sb5 or Sn96. Solder and flux shall be lead free (less than 0.2 percent of lead).

b. Copper Tube Extracted Joint: An extracted mechanical tee joint may be made in copper tube. Make joint with an appropriate tool by drilling a pilot hole and drawing out the tube surface to form a collar having a minimum height of three times the thickness of the tube wall. To prevent the branch tube from being inserted beyond the depth of the extracted joint, provide dimpled depth stops. Notch the branch tube for proper penetration into fitting to assure a free flow joint. Braze extracted joints using a copper phosphorous classification brazing filler metal. Soldered joints shall not be permitted.

2.2.8 Expansion Joints

2.2.8.1 Packless Type

Provide ASTM F1120, Type III with fabricated corrosion-resistant steel bellows.

2.2.8.2 Guided Slip-Tube Type

Provide ASTM F1007, Type IV internally-externally guided, injected semiplastic type packing.

2.2.9 Instrumentation

2.2.9.1 Pressure and Vacuum Gauges

Provide ASME B40.100 with restrictor.

2.2.9.2 Indicating Thermometers

Thermometers shall be dial type with an adjustable angle suitable for the service. Provide thermowell sized for each thermometer in accordance with the thermowell specification. Fluid-filled thermometers (mercury is not acceptable) shall have a nominal scale diameter of 5 inches. Construction shall be stainless-steel case with molded glass cover, stainless-steel stem and bulb. Stem shall be straight, length as required to fit well. Bimetal thermometers shall have a scale diameter of 3 1/2 inches. Case shall be hermetic. Case and stem shall be constructed of stainless steel. Bimetal stem shall be straight and of a length as required to fit the well.

2.2.9.3 Pressure/Temperature Test Ports

Pressure/Temperature Test Ports shall have brass body and EPDM and/or Neoprene valve seals. Ports shall be rated for service between 35 and 275 degrees F and up to 500 psig. Ports shall be provided in lengths appropriate for the insulation thickness specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS and installed to allow a minimum of 12 inches of access for probe insertion. Provide with screw-on cap attached with a strap or chain to prevent loss when removed. Ports shall be 1/4 inch NPT and accept 1/8 inch diameter probes.

2.2.10 Miscellaneous Pipeline Components

2.2.10.1 Air Vent

Provide float type air vent in hydronic systems. Vent shall be constructed of brass or semi-steel body, copper float, and stainless steel valve and valve seat. Design air vent to suit system operating temperature and pressure. Provide isolating valve to permit service without draining the system. Pipe discharge of vent to a drain.

2.2.10.2 Combination Strainer and Pump Suction Diffuser

Angle type body with removable strainer basket and internal straightening vanes, a suction pipe support, and a blowdown outlet and plug. Strainer shall be in accordance with ASTM F1199, except as modified and supplemented by this specification. Unit body shall have arrows clearly cast on the sides indicating the direction of flow.

Strainer screen shall be made of minimum 22 gauge monel, with small perforations numbering not less than 400 per square inch to provide a net free area through the basket of at least 3.30 times that of the entering pipe. Flow shall be into the screen and out through the perforations. Provide an auxiliary disposable fine mesh strainer which shall be removed 30 days after start-up. Provide warning tag for operator indicating scheduled date for removal.

Casing shall have connection sizes to match pump suction and pipe sizes, and be provided with adjustable support foot or support foot boss to relieve piping strains at pump suction. Provide unit casing with blowdown

port and plug. Provide a magnetic insert to remove debris from system.

2.2.10.3 Hangers and Supports

Design and fabrication of pipe hangers, supports, and welding attachments shall conform to MSS SP-58 and ASME B31.9. Hanger types and supports for bare and covered pipe shall conform to MSS SP-69 for the temperature range. If ferrous materials are used, provide hot dipped galvanized hangers, inserts and supports.

2.2.10.4 Pipe Sleeves

Sleeves in masonry and concrete walls, floors, and roof slabs shall be ASTM A53/A53M, Schedule 40 or Standard Weight, hot-dip galvanized steel pipe. Sleeves in partitions shall be zinc-coated sheet steel having a nominal weight of not less than 0.906 pound per square foot.

2.2.10.5 Escutcheon Plates

Provide one piece or split hinge metal plates for piping passing through floors, walls, and ceilings in exposed spaces. Provide polished stainless steel plates or chromium-plated finish on copper alloy plates in finished spaces and paint finish on metal plates in unfinished spaces.

2.3 CENTRAL MECHANICAL EQUIPMENT

2.3.1 Boilers

Provide as specified in Section 23 52 43.00 20 LOW PRESSURE WATER HEATING BOILERS UNDER 800,000 BTU/HR OUTPUT.

2.4 PIPING SYSTEM EQUIPMENT

2.4.1 Pumps

Provide hot water circulating pumps, CID A-A-50560, Service A. Pump casing and flange shall be made of close-grained cast iron. Shaft shall be carbon or alloy steel with lubricated bearings and impeller shall be bronze. Select pumps so that the operating point on selected impeller-curve will lie at or to the left of shutoff side of, and not more than 5 percent below, point of maximum efficiency for impeller. Provide motors of open type conforming to NEMA MG 1 and suitable for electrical characteristic as indicated. Motor starters shall conform to NEMA ICS 2 across the line type with NEMA ICS 6general purpose enclosure.

2.4.2 Expansion Tanks

Provide welded steel, constructed and tested hydrostatically in accordance with ASME BPVC SEC VIII D1. Tank shall be equipped with all necessary fittings. The tank and fittings shall be pressure rated at least equal to the test pressure of the total system. Zinc coat the tank inside and out after fabrication by the hot dip process ASTM A123/A123M.

2.4.3 External Air Separation Tanks

Provide tank constructed of steel, designed for not less than 75 psig, and constructed and tested in accordance with the requirements of ASME BPVC SEC VIII D1. Provide tangential inlet and outlet connections,

flanged for sizes 2 1/2 inches and larger. Each unit shall have an internal design suitable for creating the required vortex and subsequent air separation. Provide with automatic air release device and galvanized steel strainer. Provide a blow down connection with a gate valve and piped to nearest floor drain.

2.4.4 Flow Measuring Equipment

Orifice or venturi type. Flow metering equipment including pitot tubes, venturis, orifice plates, flanges, and indicating meters shall be the product of one and the same manufacturer. Provide flowmeters of permanent type . Flowmeters shall be suitable for service in which they are to be installed. Primary elements of flowmeters shall conform to ASME recommendations for flowmeters. Provide bronze, monel, or stainless steel materials for wetted parts of flow meters.

a. Orifices: Square-edge type, made of corrosion and erosion resistant metal and mounted between pipe flanges having factory-made pressure taps provided with shutoff valves. Orifice flanges shall conform to ASME B16.36.

b. Tubular Flowmeters: Flow measuring elements consisting of venturi tubes or pitot tubes where indicated. Locations and arrangement of piping, both upstream and downstream of flow measuring elements shall conform to the manufacturer's published literature. Provide each flow measuring element with an integral tab, or a metal tag on a corrosion-resistant steel wire, extending outside pipe covering, and stamped or printed in a visible position with manufacturer's name and address; serial number of meter to which it is to be connected; name, number, or location of equipment served; specified rate of flow; and multiplier to be applied to meter reading. Provide taps with shutoff valves and quick connecting hose fittings for portable meters or double ferrule compression fittings for connection to tubing for permanently located meters or recorders. Tubes shall be calibrated in accordance with ASME recommendations.

(1) Venturi Tubes: Certified by the manufacturer for the actual piping configuration and any necessary piping changes required for certification without additional cost to the Government. Throat diameter for each venturi tube shall be designed so that at specified rate of flow the scale reading will fall between 50 percent and 80 percent of full scale value. Select venturi tube sizes from the manufacturer's latest published tables of flow versus differential pressure. Unrecovered head loss at maximum flow shall not exceed 10 percent. Provide bronze or cast iron tubes with bronze-lined throats, with flanged, threaded, or welded ends to suit piping system. Provide bodies of fabricated steel and fittings of the same class as piping in which installed. Two integral meter taps shall be provided in each venturi tube. Connections for attachment to portable flow meter hoses shall be readily accessible and not over 6 feet above a floor or permanent platform.

(2) Pitot Tube Assemblies: Provide corrosion-resistant materials. Tubes shall be capable of measuring liquid flow through tube elements providing an averaged, interpolated flow measurement from a single, fixed position. Provide self cleaning elements and impact tube designed to rotate when turned by the operator to protect pressure-sensing elements of tube when not in use.

Location and total amount of pitot tubes required for system flow measurement shall be as recommended by the manufacturer and as indicated.

c. Meters: Designed for a full scale pressure differential of 50 inches water gage for tubular type or 100 inches water gage for orifice type. Dials shall have square root or linear scales with developed length of not less than 12 inches. Provide flush mounted panel meters that read directly in gallons per minute. Dials of portable meters shall have square root scales reading from 0 to 100 gpm for use with multiplier stamped on orifice or tubular type. Provide meters designed for not less than 200 psi and protected against pressure surges. Meter bodies shall have taps for venting and draining.

(1) Permanently Mounted Meters: Each meter shall be connected completely as indicated and as specified and provided with the following: three valve manifold equalizer lines, two block valves, two vent and drain valves, and an integral pulsation damper. Overall accuracy of meters shall be plus or minus 2 percent of full scale flow over a range from 20 to 100 percent of full scale flow.

2.5 TERMINAL UNITS

2.5.1 Unit Heaters

Provide hot water unit heaters as specified in Section 23 82 00.00 20 TERMINAL HEATING UNITS.

2.5.2 Heating and Ventilating Units

Provide fan-coil units, induction units, unit ventilators, and gravity ventilators as specified in Section 23 30 00 HVAC AIR DISTRIBUTION.

2.6 ELECTRICAL EQUIPMENT

Provide complete with motors, motor starters, thermal overload protection, and controls. Equipment and wiring shall be in accordance with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

2.7 CONTROLS

Provide controls as specified in Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS.

2.8 INSULATION

Provide shop and field applied insulation as specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.9 ASBESTOS PROHIBITION

Asbestos and asbestos containing products are prohibited.

PART 3 EXECUTION

3.1 PREPARATION

Provide storage for equipment and material at the project site. All parts shall be readily accessible for inspection, repair, and renewal. Protect material and equipment from the weather.

3.2 INSTALLATION

Piping fabrication, assembly, welding, soldering, and brazing shall conform to ASME B31.9. Piping shall follow the general arrangement shown. Route piping and equipment within buildings out of the way of lighting fixtures and doors, windows, and other openings. Run overhead piping in buildings in inconspicuous positions. Provide adequate clearances from walls, ceilings, and floors to permit welding of joints and application of insulation. Make provision for expansion and contraction of pipe lines. Make changes in size of water lines with reducing fittings. Do not bury, conceal, or insulate until piping has been inspected, tested, and approved. Do not run piping concealed in walls, partitions, underground, or under the floor except as otherwise indicated. Where pipe passes through building structure, locate pipe joints and expansion joints where they may be inspected. Provide flanged joints where necessary for normal maintenance and where required to match valves and equipment. Furnish gaskets, packing, and thread compounds suitable for the service. Provide long radius ells where possible to reduce pressure drops. Pipe bends in lieu of welding fittings may be used where space permits. Pipe bends shall have a uniform radius of at least five times the pipe diameter and shall be free from appreciable flattening, wrinkling, or thinning of the pipe. Do not use mitering of pipe to form elbows, notching straight runs to form full sized tees, or any similar construction. Make branch connections over 2 inches with welding tees except factory made forged welding branch outlets or nozzles having integral reinforcements conforming to ASME B31.9 may be used, provided the nominal diameter of the branch is at least one pipe size less than the nominal diameter of the run. Branch connections 2 inches and under can be threaded or welded. Run vertical piping plumb and straight and parallel to walls. Provide sleeves for lines passing through building structure. Provide a fire seal where pipes pass through fire wall, fire partitions, fire rated pipe chase walls, or floors above grade. Install piping connected to equipment with flexibility for thermal stresses and for vibration, and support and anchor so that strain from weight and thermal movement of piping is not imposed on the equipment.

3.2.1 Hangers and Supports

Unless otherwise indicated, horizontal and vertical piping attachments shall conform to MSS SP-58. Band and secure insulation protection shields without damaging pipe insulation. Continuous inserts and expansion bolts may be used.

3.2.2 Grading of Pipe Lines

Unless otherwise indicated, install horizontal lines of hot water piping to grade down in the direction of flow with a pitch of not less than one inch in 30 feet, except in loop mains and main headers where the flow may be in either direction.

3.2.3 Pipe Sleeves

Provide sleeves where pipes and tubing pass through masonry or concrete walls, floors, roof, and partitions. Annular space between pipe, tubing, or insulation and the sleeve shall not be less than 1/4 inch. Hold sleeves securely in proper position and location before and during construction. Sleeves shall be of sufficient length to pass through entire thickness of walls, partitions, or slabs. Sleeves in floor slabs shall extend 2 inches above finished floor. Firmly pack space between pipe or tubing and sleeve with oakum and caulk on both ends of the sleeve with plastic waterproof cement which will dry to a firm but pliable mass, or provide a mechanically adjustable segmented elastomeric seal. Seal both ends of penetrations through fire walls and fire floors to maintain fire resistive integrity with UL listed fill, void, or cavity material.

3.2.4 Flashing for Buildings

Provide flashing where pipes pass through building roofs, and make outside walls tight and waterproof.

3.2.5 Unions and Flanges

Provide unions and flanges to permit easy disconnection of piping and apparatus. Each connection having a screwed-end valve shall have a union. Place unions and flanges no farther apart than 100 feet. Install unions downstream of valves and at equipment or apparatus connections. Provide unions on piping under 2 inches in diameter, and provide flanges on piping 2 inches and over in diameter. Provide dielectric unions or flanges between ferrous and non-ferrous piping, equipment, and fittings; except that bronze valves and fittings may be used without dielectric couplings for ferrous-to-ferrous or non-ferrous-to-non-ferrous connections.

3.2.6 Changes in Pipe Size

Provide reducing fittings for changes in pipe size; reducing bushings are not permitted. In horizontal lines, provide eccentric reducing fittings to maintain the top of the lines in the same plane.

3.2.7 Cleaning of Pipe

Thoroughly clean each section of pipe, fittings, and valves free of foreign matter before erection. Prior to erection, hold each piece of pipe in an inclined position and tap along its full length to loosen sand, mill scale and other foreign matter. For pipe 2 inches and larger, draw wire brush, of a diameter larger than that of the inside of the pipe, several times through the entire length of pipe. Before making final connections to apparatus, wash out interior of piping thoroughly with water. Plug or cap open ends of mains during shutdown periods. Do not leave lines open where foreign matter might enter the pipe.

3.2.8 Valves

Install valves in conformance with ASME B31.9. Provide gate valves unless otherwise directed. Install valves with stems horizontal or above. Locate or equip stop valves to permit operation from floor level, or provide with safe access in the form of walkways or ladders. Install valves in positions accessible for operation and repair.

3.2.8.1 Globe Valves

Install globe valves so that the pressure is below the disk and the stem horizontal.

3.2.8.2 Relief Valves

Provide valves on pressure tanks, low pressure side of reducing valves, heat exchangers, and expansion tanks. Select system relief valve so that capacity is greater than make-up pressure reducing valve capacity. Select equipment relief valve capacity to exceed rating of connected equipment. Pipe relief valve outlet to the nearest floor drain.

3.2.9 Pressure Gage

Provide a shut-off valve between pressure gages and the line.

3.2.10 Thermometers

Provide thermometers and thermal sensing elements of control valves with a separable socket. Install separable sockets in pipe lines in such a manner to sense the temperature of flowing the fluid and minimize obstruction to flow.

3.2.11 Strainers

Provide strainers, with meshes suitable for the services, where indicated, or where dirt might interfere with the proper operation of valve parts, orifices, or moving parts of equipment.

3.2.12 Pumps

Select pumps for specified fluid temperatures, are non-overloading in parallel or individual operation, and operate within 25 percent of midpoint of published maximum efficiency curve. Support piping adjacent to pump such that no weight is carried on pump casings. Install close coupled and base mounted pumps on concrete base, with anchor bolts, set and level, and grout in place and provide supports under elbows on pump suction and discharge line sizes 4 inches and over. Lubricate pump before start-up.

3.2.13 Equipment Foundations

Locate equipment foundations as shown on the drawings. Size, weight, and design shall preclude shifting of equipment under operating conditions. Foundations shall meet the requirements of the equipment manufacturer. Concrete shall conform to Section 03 30 00 CAST-IN-PLACE CONCRETE, and grout shall be approved non-shrinking.

3.2.14 Equipment Installation

Install equipment in accordance with installation instructions of the manufacturers. Grout equipment mounted on concrete foundations before installing piping. Install piping in such a manner as not to place a strain on the equipment. Do not bolt flanged joints tight unless they match. Grade, anchor, guide, and support piping without low pockets.

3.2.15 Cleaning of Systems

As installation of the various system components is completed, fill, start, and vent prior to cleaning. Place terminal control valves in open position. Add cleaner to closed system at concentration as recommended by manufacturer. Apply heat while circulating, slowly raising temperature to 160 degrees F and maintain for 12 hours minimum. Remove heat and circulate to 100 degrees F or less; drain systems as quickly as possible and refill with clean water. Circulate for 6 hours at design temperatures, then drain. Refill with clean water and repeat until system cleaner is removed. Use neutralizer agents on recommendation of system cleaner supplier and approval of Contracting Officer. Remove, clean, and replace strainer screens. Inspect, remove sludge, and flush low points with clean water after cleaning process is completed. Include disassembly of components as required. Preliminary or final tests are not permitted until cleaning is approved.

3.2.16 Painting of Piping and Equipment

Provide in accordance with Section 09 90 00 PAINTS AND COATINGS.

3.2.17 Identification of Piping

Identify piping in accordance with OSHA 29 CFR 1910.144, except that labels or tapes may be used in lieu of painting or stenciling. Spacing of identification marking on runs shall not exceed 50 feet. Materials for labels and tapes shall conform to CID A-A-1689, and shall be general purpose type and color class. Painting and stenciling shall conform to Section 09 90 00 PAINTS AND COATINGS.

3.2.18 Heat Trace Cable

Field apply heater tape and cut to fit as necessary, linearly along the length of pipe after piping has been pressure tested and approved by the Contracting Officer. Secure the heater to piping with cable ties . Label thermal insulation on the outside, "Electrical Heat Trace."

Install power connection, end seals, splice kits and tee kit components in accordance with IEEE 515 to provide a complete workable system. Terminate connection to the thermostat and ends of the heat tape in a junction box. Ensure cable and conduit connections are raintight.

3.3 FIELD QUALITY CONTROL

Perform inspections and tests as specified herein to demonstrate that piping and equipment, as installed, is in compliance with contract requirements. Start up and operate the system. During this time, periodically clean the various strainers until no further accumulation of foreign material occurs. Exercise care so that minimum loss of water occurs when strainers are cleaned. Adjust safety and automatic control instruments to place them in proper operation and sequence.

3.3.1 Hydrostatic Test of Piping System

Test piping system hydrostatically using water not exceeding 100 degrees F. Conduct tests in accordance with the requirements of ASME B31.9 and as follows. Test piping system after all lines have been cleaned and before applying insulation covering. Remove or valve off from the system, gages, and other apparatus which may be damaged by the test before the tests are

made. Install calibrated test pressure gage in the system to observe any loss in pressure. Maintain test pressure for a sufficient length of time to enable an inspection of each joint and connection. Perform tests after installation and prior to acceptance.Notify the Contracting Officer in writing 14 days prior to the time scheduled for the tests.

3.3.2 Auxiliary Equipment and Accessory Tests

Observe and check pumps, accessories, and equipment during operational and capacity tests for leakage, malfunctions, defects, noncompliance with referenced standards, or overloading.

3.3.2.1 Backflow Preventers

Backflow preventers shall be tested by locally approved and certified backflow assembly testers. A copy of the test report shall be provided to the Contracting Officer prior to placing the domestic water system into operation, or no later than 5 days after the test.

3.3.2.2 Heat Trace Cable

Test heat trace cable system in accordance with IEEE 515 after installation and before and after installation of the thermal insulation. Test heater cable using a 1000 vdc megger. Minimum insulation resistance is 20 to 1000 megohms regardless of cable length.

3.4 TESTING, ADJUSTING, AND BALANCING

Test, adjust, and balance the hydronic system in accordance with Section 23 05 93 TESTING, ADJUSTING AND BALANCING FOR HVAC.

3.4.1 Markings of Settings

Following final acceptance of the balancing report, the settings of all valves, splitters, dampers, and other adjustment devices shall be permanently marked so that adjustment can be restored if disturbed at anytime.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 23 00

REFRIGERANT PIPING
08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI 710 I-P	(2009) Performance Rating of Liquid-Line Driers
AHRI 720	(2002) Refrigerant Access Valves and Hose Connectors
AHRI 750 I-P	(2016) Performance Rating of Thermostatic Refrigerant Expansion Valves
AHRI 760 I-P	(2014) Performance Rating of Solenoid Valves for Use with Volatile Refrigerants
AHRI 1370 I-P	(2017) Performance Rating of Electronic Expansion Valves

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 15 & 34	(2022) ASHRAE Standard 34-2016 Safety Standard for Refrigeration Systems/ASHRAE Standard 34-2016 Designation and Safety Classification of Refrigerants-ASHRAE Standard 34-2016
ASHRAE 17	(2015) Method of Testing Capacity of Thermostatic Refrigerant Expansion Valves
ASHRAE 90.1 - IP	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.22	(2021) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.26	(2024) Cast Copper Alloy Fittings for Flared Copper Tubes
ASME B31.1	(2024) Power Piping
ASME B31.5	(2022) Refrigeration Piping and Heat Transfer Components

ASME B40.100	(2022) Pressure Gauges and Gauge Attachments

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8/A5.8M	(2019) Specification for Filler Metals for Brazing and Braze Welding
AWS A5.31/A5.31M	(2012) Specification for Fluxes for Brazing and Braze Welding
AWS BRH	(2007; 5th Ed) Brazing Handbook
AWS Z49.1	(2021) Safety in Welding, Cutting and Allied Processes

ASTM INTERNATIONAL (ASTM)

ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B32	(2020) Standard Specification for Solder Metal
ASTM B62	(2017; R 2025) Standard Specification for Composition Bronze or Ounce Metal Castings
ASTM B75/B75M	(2020) Standard Specification for Seamless Copper Tube
ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM B280	(2020) Standard Specification for Seamless Copper Tube for Air Conditioning and Refrigeration Field Service
ASTM B813	(2024) Standard Specification for Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube
ASTM D520	(2025) Standard Specification for Zinc Dust Pigment
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-58	(2025) Pipe Hangers and Supports - Materials, Design and Manufacture,

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Refrigerant Piping System; G

SD-03 Product Data

Refrigerant Piping System

Qualifications

Refrigerant Piping Tests

SD-06 Test Reports

Refrigerant Piping Tests

SD-07 Certificates

Service Organization

SD-10 Operation and Maintenance Data

Maintenance; G

Operation and Maintenance Manuals; G

1.3 QUALITY ASSURANCE

1.3.1 Qualifications

Submit 4 copies of qualified procedures, and list of names and identification symbols of qualified welders and welding operators, prior to non-factory welding operations.

1.3.2 Contract Drawings

Because of the small scale of the drawings, it is not possible to indicate all offsets, fittings, and accessories that may be required. Carefully investigate the plumbing, fire protection, electrical, structural and finish conditions that would affect the work to be performed and arrange such work accordingly, furnishing required offsets, fittings, and accessories to meet such conditions.

1.4 DELIVERY, STORAGE, AND HANDLING

Protect stored items from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Proper protection and care of all material both before and during installation is the Contractor's responsibility. Replace any materials found to be damaged at the Contractor's expense. During installation, cap piping and similar

openings to keep out dirt and other foreign matter.

1.5 MAINTENANCE

1.5.1 General

Submit Data Package 2 plus operation and maintenance data complying with the requirements of Section 01 78 23 OPERATION AND MAINTENANCE DATA and as specified herein.

PART 2 PRODUCTS

2.1 STANDARD COMMERCIAL PRODUCTS

a. Provide materials and equipment which are standard products of a manufacturer regularly engaged in the manufacturing of such products, that are of a similar material, design and workmanship and that have been in satisfactory commercial or industrial use for 2 years prior to bid opening.

b. The 2 year use must include applications of equipment and materials under similar circumstances and of similar size. The 2 years' experience must be satisfactorily completed by a product which has been sold or is offered for sale on the commercial market through advertisements, manufacturer's catalogs, or brochures. Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation, for not less than 6000 hours exclusive of the manufacturer's factory tests, can be shown.

c. Products must be supported by a service organization. System components must be environmentally suitable for the indicated locations. Submit a certified list of qualified permanent service organizations for support of the equipment which includes their addresses and qualifications. The service organizations must be reasonably convenient to the equipment installation and be able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

d. Exposed equipment moving parts, parts that produce high operating temperature, parts which may be electrically energized, and parts that may be a hazard to operating personnel must be insulated, fully enclosed, guarded, or fitted with other types of safety devices. Install safety devices so that proper operation of equipment is not impaired. Welding and cutting safety requirements must be in accordance with AWS Z49.1.

e. Provide the manufacturer's standard catalog data, at least 5 weeks prior to the purchase or installation of a particular component. Highlight the data to show information such as, but not limited to, material, size, options, performance charts, and curves in adequate detail to demonstrate compliance with contract requirements. Include the manufacturer's recommended installation instructions and procedures in the data provided. Provide data for the following components as a minimum:

(1) Piping and Fittings
(2) Valves
(3) Piping Accessories
(4) Pipe Hangers, Inserts, and Supports

2.2 ELECTRICAL WORK

Electrical equipment and wiring must be in accordance with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Field wiring must be in accordance with manufacturer's instructions.

2.3 REFRIGERANT PIPING SYSTEM

Provide refrigerant piping, valves, fittings, and accessories in accordance with ASHRAE 15 & 34 and ASME B31.5, except as specified herein. Refrigerant piping, valves, fittings, and accessories must be compatible with the fluids used and capable of withstanding the pressures and temperatures of the service. Refrigerant piping, valves, and accessories used for refrigerant service must be cleaned, dehydrated, and sealed (capped or plugged) prior to shipment from the manufacturer's plant. Submit drawings, at least 5 weeks prior to beginning construction, provided in adequate detail to demonstrate compliance with contract requirements. Drawings must consist of:

a. Piping layouts which identify all valves and fittings.

b. Plans and elevations which identify clearances required for maintenance and operation.

2.4 PIPE, FITTINGS AND END CONNECTIONS (JOINTS)

2.4.1 Copper Tubing

Provide copper tubing conforming to ASTM B280 annealed or hard drawn as required. Copper tubing must bear the product identification markings in accordance with ASTM B280, "ACR" must be present on copper tubing. Copper tubing must be soft annealed where bending is required and hard drawn where no bending is required. Soft annealed copper tubing must not be used in sizes larger than 1-3/8 inches. Joints must be brazed except that joints on lines 7/8 inchand smaller may be flared. Cast copper alloy fittings for flared copper tube must conform to ASME B16.26 and ASTM B62. Wrought copper and bronze solder-joint pressure fittings must conform to ASME B16.22 and ASTM B75/B75M. Joints and fittings for brazed joint must be wrought-copper or forged-brass sweat fittings. Cast sweat-type joints and fittings are not allowed for brazed joints. Brass or bronze adapters for brazed tubing may be used for connecting tubing to flanges and to threaded ends of valves and equipment.

2.4.2 Solder

Solder must conform to ASTM B32, grade Sb5, tin-antimony alloy for service pressures up to 150 psig. Solder flux must be liquid or paste form, non-corrosive and conform to ASTM B813.

2.4.3 Brazing Filler Metal

Filler metal must conform to AWS A5.8/A5.8M, Type BAg-5 with AWS Type FB3-A or Type FB3-C flux, except Type BCuP-3, BCuP-4, or BCuP-5 may be used for brazing copper-to-copper joints. BAlSi-4 with AWS Type FB1-A flux may be used when joining copper piping to aluminum components.

2.4.4 Brazing Flux

Brazing flux must conform to AWS A5.31/A5.31M, Type FB3-A or Type FB3-C when using Type BAg-5 filler metal. Type FB1-A is to be used with Type BAlSi-4 filler metal.

2.4.5 Press Fittings

Press fittings are not acceptable for use in refrigerant piping systems.

2.5 VALVES

Valves must be designed, manufactured, and tested specifically for refrigerant service. The valve material and all internal components must be compatible with the specific refrigerant and lubricant used. Valve bodies must be of brass or bronze construction. Valves 1 inch and smaller must have brazed or socket welded connections. Do not use threaded end connections, except in pilot pressure or gauge lines where maintenance disassembly is required and welded flanges cannot be used. Internal parts must be removable for inspection or replacement without applying heat or breaking pipe connections. Valve stems exposed to the atmosphere must be stainless steel or corrosion resistant metal plated carbon steel. Direction of flow must be legibly and permanently indicated on the valve body. Control valve inlets must be fitted with integral or adapted strainer or filter where recommended or required by the manufacturer. Purge, charge and receiver valves must be of manufacturer's standard configuration.

2.5.1 Refrigerant Stop Valves

Valve must be the globe or full-port ball type with a back-seating stem especially packed for refrigerant service. Valve packing must be replaceable under line pressure. Provide valve with a wrench operator and a seal cap. Valve must be the straight or angle pattern design as indicated.

2.5.2 Check Valves

Valve must be the swing or lift type as required to provide positive shutoff at the differential pressure indicated. Valve must be provided with resilient seat.

2.5.3 Liquid Solenoid Valves

Provide valves that comply with AHRI 760 I-P and are suitable for continuous duty with applied voltages 15 percent under and 5 percent over nominal rated voltage at maximum and minimum encountered pressure and temperature service conditions. Valves must be direct-acting or pilot-operating type, packless, except that packed stem, seal capped, manual lifting provisions must be furnished. Provide solenoid coils that are moisture-proof, UL approved, totally encapsulated or encapsulated and metal jacketed as required. Valves must have safe working pressure of 610 psi and a maximum operating pressure differential of at least 200 psi at 85 percent rated voltage. Valves must have an operating pressure differential suitable for the refrigerant used.

2.5.4 Expansion Valves

Provide valve conforming to AHRI 750 I-P and ASHRAE 17. Valve must be the

diaphragm and spring-loaded type with internal or external equalizers, and bulb and capillary tubing. Provide valve with an external superheat adjustment along with a seal cap. Internal equalizers may be utilized where flowing refrigerant pressure drop between outlet of the valve and inlet to the evaporator coil is negligible and pressure drop across the evaporator is less than the pressure difference corresponding to 2 degrees F of saturated suction temperature at evaporator conditions. Bulb charge must be determined by the manufacturer for the application and such that liquid will remain in the bulb at all operating conditions. Do not use gas limited liquid charged valves and other valve devices for limiting evaporator pressure without a distributor or discharge tube or effective means to prevent loss of control when bulb becomes warmer than valve body. Pilot-operated valves must have a characterized plug to provide required modulating control. A de-energized solenoid valve may be used in the pilot line to close the main valve in lieu of a solenoid valve in the main liquid line. Provide an isolatable pressure gauge in the pilot line, at the main valve. Automatic pressure reducing or constant pressure regulating expansion valves may be used only where indicted or for constant evaporator loads.

2.5.5 Electronic Expansion Valves

Valve must conform to AHRI 1370 I-P and ASHRAE 17. The valve must prevent the return of liquid to the compressor in the event of power loss or low superheat.

2.5.6 Safety Relief Valves

Valve must be the two-way type, unless indicated otherwise. Valve must bear the ASME code symbol. Valve capacity must be certified by the National Board of Boiler and Pressure Vessel Inspectors. Valve must be of an automatically reseating design after activation.

2.5.7 Evaporator Pressure Regulators, Direct-Acting

Valve must include a diaphragm/spring assembly, external pressure adjustment with seal cap, and pressure gauge port. Valve must maintain a constant inlet pressure by balancing inlet pressure on diaphragm against an adjustable spring load. Pressure drop at system design load must not exceed the pressure difference corresponding to a 2 degrees F change in saturated refrigerant temperature at evaporator operating suction temperature. Spring must be selected for indicated maximum allowable suction pressure range.

2.5.8 Refrigerant Access Valves

Provide refrigerant access valves and hose connections in accordance with AHRI 720.

2.6 PIPING ACCESSORIES

2.6.1 Filter Driers

Driers must conform to AHRI 710 I-P. Sizes 5/8 inch and larger must be the full flow, replaceable core type. Sizes 1/2 inch and smaller must be the sealed type. Cores must be of suitable desiccant that will not plug, cake, dust, channel, or break down, and must remove water, acid, and foreign material from the refrigerant. Constructfilter driers so that none of the desiccant will pass into the refrigerant lines. Minimum

bursting pressure must be 1,500 psi.

2.6.2 Sight Glass and Liquid Level Indicator

2.6.2.1 Assembly and Components

Assembly must be pressure- and temperature-rated and constructed of materials suitable for the service. Glass must be borosilicate type. Ferrous components subject to condensation must be electro-galvanized.

2.6.2.2 Gauge Glass

Gauge glass must include top and bottom isolation valves fitted with automatic checks, and packing followers; red-line or green-line gauge glass; elastomer or polymer packing to suit the service; and gauge glass guard.

2.6.2.3 Bull's-Eye and Inline Sight Glass Reflex Lens

Provide bull's-eye and inline sight glass reflex lens for dead-end liquid service. For pipe line mounting, provide two plain lenses in one body suitable for backlighted viewing.

2.6.2.4 Moisture Indicator

Indicator must be a self-reversible action, moisture reactive, color changing media. Indicator must be furnished with full-color-printing tag containing color, moisture, and temperature criteria. Unless otherwise indicated, the moisture indicator must be an integral part of each corresponding sight glass.

2.6.3 Vibration Dampeners

Dampeners must be of the all-metallic bellows and woven-wire type.

2.6.4 Flexible Pipe Connectors

Connector must be a composite of interior corrugated phosphor bronze or Type 300 Series stainless steel, as required for fluid service, with exterior reinforcement of bronze, stainless steel or monel wire braid. Assembly must be constructed with a safety factor of not less than 4 at300 degrees F. Unless otherwise indicated, the length of a flexible connector must be as recommended by the manufacturer for the service intended.

2.6.5 Strainers

Strainers used in refrigerant service must have brass or cast-iron body, Y-or angle-pattern, cleanable, not less than 60-mesh noncorroding screen of an area to provide net free area not less than ten times the pipe diameter with pressure rating compatible with the refrigerant service. Screens must be stainless steel or monel and reinforced spring-loaded where necessary for bypass-proof construction.

2.6.6 Pressure and Vacuum Gauges

Provide gauges conforming to ASME B40.100 with throttling type needle valve or a pulsation dampener and shut-off valve. Gauge must be a minimum of 3-1/2 inches in diameter with a range from 0 psig to approximately 1.5 times the maximum system working pressure. Select each gauge range so

that at normal operating pressure, the needle is within the middle-third of the range.

2.6.7 Pipe Hangers, Inserts, and Supports

Provide pipe hangers, inserts, guides, and supports conforming to MSS SP-58.

2.6.8 Escutcheons

Escutcheons must be chromium-plated iron or chromium-plated brass, either one piece or split pattern, held in place by internal spring tension or set screws.

2.7 FABRICATION

2.7.1 Factory Coating

Unless otherwise specified, equipment and component items, when fabricated from ferrous metal, must be factory finished with the manufacturer's standard finish, except that items located outside of buildings must have weather resistant finishes that will withstand 3000 hours exposure to the salt spray test specified in ASTM B117 using a 5 percent sodium chloride solution. Immediately after completion of the test, the specimen must show no signs of blistering, wrinkling, cracking, or loss of adhesion and no sign of rust creepage beyond 1/8 inch on either side of the scratch mark. Cut edges of galvanized surfaces where hot-dip galvanized sheet steel is used must be coated with a zinc-rich coating conforming to ASTM D520, Type I.

2.7.2 Factory Applied Insulation

Factory installed insulation must be in accordance with ASHRAE 90.1 - IP. Refrigerant suction lines between the cooler and each compressor must be insulated with not less than 1/2 inch thick unicellular plastic foam. Factory insulated items installed outdoors are not required to be fire-rated. As a minimum, factory insulated items installed indoors must have a flame spread index no higher than 25 and a smoke developed index no higher than 50. Factory insulated items (no jacket) installed indoors and which are located in air plenums, in ceiling spaces, and in attic spaces must have a flame spread index no higher than 25 and a smoke developed index no higher than 50. Flame spread and smoke developed indexes must be determined by ASTM E84. Test insulation in the same density and installed thickness as the material to be used in the actual construction. Test material supplied by a manufacturer with a jacket as a composite material. Provide jackets, facings, and adhesives that have a flame spread index less than 25 and a smoke developed index less than 50 when tested in accordance with ASTM E84.

PART 3 EXECUTION

3.1 INSTALLATION

Pipe and fitting installation must conform to the requirements of ASME B31.1. Cut pipe accurately to measurements established at the jobsite, and work into place without springing or forcing, completely clearing all windows, doors, and other openings. Cutting or other weakening of the building structure to facilitate piping installation is not permitted without written approval. Cut pipe or tubing square, remove by reaming, and permit free expansion and contraction without causing

damage to the building structure, pipe, joints, or hangers.

3.1.1 Directional Changes

Make changes in direction with fittings, except that bending of pipe 4 inches and smaller is permitted, provided a pipe bender is used and wide weep bends are formed. Mitering or notching pipe or other similar construction to form elbows or tees is not permitted. The centerline radius of bends must not be less than 6 diameters of the pipe. Bent pipe showing kinks, wrinkles, flattening, or other malformations will not be accepted.

3.1.2 Functional Requirements

Install piping 1/2 inch/10 feet of pipe in the direction of flow to ensure adequate oil drainage. Properly cap or plug open ends of refrigerant lines or equipment during installation to keep moisture, dirt, or other foreign material out of the system. Piping must remain capped until installation. Equipment piping must be in accordance with the equipment manufacturer's recommendations and the contract drawings. Equipment and piping arrangements must fit into space allotted and allow adequate acceptable clearances for installation, replacement, entry, servicing, and maintenance.

3.1.3 Fittings and End Connections

3.1.3.1 Brazed Connections

Perform brazing in accordance with AWS BRH, except as modified herein. During brazing, fill the pipe and fittings with a pressure regulated inert gas, such as nitrogen, to prevent the formation of scale. Before brazing copper joints, clean both the outside of the tube and the inside of the fitting with a wire fitting brush until the entire joint surface is bright and clean. Do not use brazing flux on copper-to-copper connections. Remove surplus brazing material at all joints. Make steel tubing joints in accordance with the manufacturer's recommendations. Paint joints in steel tubing with the same material as the baked-on coating within 8 hours after joints are made. Protect tubing against oxidation during brazing by continuous purging of the inside of the piping using nitrogen. Support piping prior to brazing and do not spring or force.

3.1.4 Valves

3.1.4.1 General

Install refrigerant stop valves on each side of each piece of equipment such as compressors condensers, evaporators, receivers, and other similar items in multiple-unit installation, to provide partial system isolation as required for maintenance or repair. Install stop valves with stems horizontal unless otherwise indicated. Install ball valves must be installed with stems positioned to facilitate operation and maintenance. Isolating valves for pressure gauges and switches must be external to thermal insulation. Safety switches must not be fitted with isolation valves. Filter dryers having access ports may be considered a point of isolation. Purge valves must be provided at all points of systems where accumulated non-condensable gases would prevent proper system operation. Valves must be furnished to match line size, unless otherwise indicated or approved.

3.1.4.2 Expansion Valves

Install expansion valves with the thermostatic expansion valve bulb located on top of the suction line when the suction line is less than 2-1/8 inches in diameter and at the 4 o'clock or 8 o'clock position on lines larger than 2-1/8 inches. Fasten the bulb securely with two clamps. Insulate ehe bulb . Install the bulb in a horizontal portion of the suction line, if possible, with the pigtail on the bottom. If the bulb must be installed in a vertical line, the bulb tubing must be facing up.

3.1.4.3 Valve Identification

Tag each system valve, including those which are part of a factory assembly. Tags must be in alphanumeric sequence, progressing in direction of fluid flow. Tags must be embossed, engraved, or stamped plastic or nonferrous metal of various shapes, sized approximately 1-3/8 inch diameter, or equivalent dimension, substantially attached to a component or immediately adjacent thereto. Attach tags with nonferrous, heavy duty, bead or link chain, 14 gauge annealed wire, nylon cable bands or as approved. Reference tag numbers in Operation and Maintenance Manuals and system diagrams.

3.1.5 Vibration Dampers

Provide vibration damper in the suction and discharge lines on spring mounted compressors. Install vibration dampers parallel with the shaft of the compressor and anchor firmly at the upstream end on the suction line and the downstream end in the discharge line.

3.1.6 Strainers

Provide strainers immediately ahead of solenoid valves and expansion devices. Strainers may be an integral part of an expansion valve.

3.1.7 Filter Dryer

Provide a liquid line filter dryer on each refrigerant circuit located such that all liquid refrigerant passes through a filter dryer. Size dryers in accordance with the manufacturer's recommendations for the system in which it is installed. Install dryers such that it can be isolated from the system, the isolated portion of the system evacuated, and the filter dryer replaced. Install dryers in the horizontal position except replaceable core filter dryers may be installed in the vertical position with the access flange on the bottom.

3.1.8 Sight Glass

Install a moisture indicating sight glass in all refrigerant circuits down stream of all filter dryers and where indicated. Provide full line size sight glasses.

3.1.9 Discharge Line Oil Separator

Provide discharge line oil separator in the discharge line from each compressor. Connect the oil return line to the compressor as recommended by the compressor manufacturer.

3.1.10 Accumulator

Provide accumulators in the suction line to each compressor.

3.1.11 Flexible Pipe Connectors

Install connectors perpendicular to line of motion being isolated. Fit piping for equipment with bidirectional motion with two flexible connectors, in perpendicular planes. Install reinforced elastomer flexible connectors in accordance with manufacturer's instructions. Provide piping guides and restraints related to flexible connectors as required.

3.1.12 Pipe Hangers, Inserts, and Supports

Pipe hangers, inserts, and supports must conform to MSS SP-58, except as modified herein. Do not use pipe hanger types 5, 12, and 26. Fabricate hangers used to support piping 2 inches and larger to permit adequate adjustment after erection while still supporting the load. Support piping subjected to vertical movement, when operating temperatures exceed ambient temperatures, by variable spring hangers and supports or by constant support hangers.

3.1.12.1 Hangers

Do not use Type 3 on insulated piping. Type 24 may be used only on trapeze hanger systems or on fabricated frames.

3.1.12.2 Inserts

Secure Type 18 inserts to concrete forms before concrete is placed. Continuous inserts which allow more adjustments may be used if they otherwise meet the requirements for Type 18 inserts.

3.1.12.3 C-Clamps

Torque Type 19 and 23 C-clamps in accordance with MSS SP-58 and have both locknuts and retaining devices, furnished by the manufacturer. Field-fabricated C-clamp bodies or retaining devices are not acceptable.

3.1.12.4 Angle Attachments

Furnish Type 20 attachments used on angles and channels with an added malleable-iron heel plate or adapter.

3.1.12.5 Saddles and Shields

Where Type 39 saddle or Type 40 shield are permitted for a particular pipe attachment application, the Type 39 saddle, connected to the pipe, must be used on all pipe 4 inches and larger when the temperature of the medium is 60 degrees F or higher. Use Type 40 shields on all piping less than 4 inches and all piping 4 inches and larger carrying medium less than 60 degrees F. Use a high-density insulation insert of cellular glass under the Type 40 shield for piping 2 inches and larger.

3.1.12.6 Horizontal Pipe Supports

Space horizontal pipe supports as specified in MSS SP-58 and install a support no more than 1 foot from the pipe fitting joint at each change in

direction of the piping. Space pipe supports no more than 5 feet apart at valves. Pipe hanger loads suspended from steel joist with hanger loads between panel points in excess of 50 pounds must have the excess hanger loads suspended from panel points.

3.1.12.7 Vertical Pipe Supports

Support vertical pipe at each floor, except at slab-on-grade, and at intervals of not more than 15 feet not more than 8 feet from end of risers, and at vent terminations.

3.1.12.8 Pipe Guides

Provide Type 35 guides using, steel, reinforced polytetrafluoroethylene (PTFE) or graphite slides where required to allow longitudinal pipe movement. Provide lateral restraints as required. Provide slide materials that are suitable for the system operating temperatures, atmospheric conditions, and bearing loads encountered.

3.1.12.9 Steel Slides

Where steel slides do not require provisions for restraint of lateral movement, an alternate guide method may be used. On piping 4 inches and larger, usea Type 39 saddle. On piping under 4 inches, a Type 40 protection shield may be attached to the pipe or insulation and freely rest on a steel slide plate.

3.1.12.10 High Temperature Guides with Cradles

Where there are high system temperatures and welding to piping is not desirable, the Type 35 guide must include a pipe cradle, welded to the guide structure and strapped securely to the pipe. Separate the pipe from the slide material by at least 4 inches, or by an amount adequate for the insulation, whichever is greater.

3.1.12.11 Multiple Pipe Runs

In the support of multiple pipe runs on a common base member, use a clip or clamp where each pipe crosses the base support member. Spacing of the base support members must not exceed the hanger and support spacing required for an individual pipe in the multiple pipe run.

3.1.12.12 Structural Attachments

Attachment to building structure concrete and masonry must be by cast-in concrete inserts, built-in anchors, or masonry anchor devices. Inserts and anchors must be applied with a safety factor not less than 5. Do not attach supports to metal decking. Construct masonry anchors for overhead applications of ferrous materials only. Provide structural steel brackets required to support piping, headers, and equipment, but not shown, under this section. Specify material used for support under Section 05 12 00 STRUCTURAL STEEL.

3.1.13 Pipe Alignment Guides

Provide pipe alignment guides where indicated for expansion loops, offsets, and bends and as recommended by the manufacturer for expansion joints, not to exceed 5 feet on each side of each expansion joint, and in lines 4 inches or smaller not more than 2 feet on each side of the joint.

3.1.14 Pipe Anchors

Provide anchors wherever necessary or indicated to localize expansion or to prevent undue strain on piping. Provide anchors consisting of heavy steel collars with lugs and bolts for clamping and attaching anchor braces, unless otherwise indicated. Install anchor braces in the most effective manner to secure the desired results using turnbuckles where required. Do not attach supports, anchors, or stays where they will injure the structure or adjacent construction during installation or by the weight of expansion of the pipeline. Where pipe and conduit penetrations of vapor barrier sealed surfaces occur, immediately anchor these items adjacent to each penetrated surface, to provide essentially zero movement within penetration seal. Submit detailed drawings of pipe anchors for approval before installation.

3.1.15 Building Surface Penetrations

Do not install sleeves in structural members except where indicated or approved. Provide galvanized sheet metal sleeves in non-load bearing surfaces conforming to ASTM A653/A653M, Coating Class G-90, 20 gauge. Provide uncoated carbon steel pipe sleeves in load bearing surfaces conforming to ASTM A53/A53M, Standard weight. Apply sealants to moisture and oil-free surfaces and elastomers to not less than 1/2 inch depth. Do not install sleeves in structural members.

3.1.15.1 General Service Areas

Extend each sleeve through its respective wall, floor, or roof, and cut flush with each surface. Provide pipes passing through concrete or masonry wall or concrete floors or roofs with pipe sleeves fitted into place at the time of construction. Provide sleeves that allow a minimum of 1/4 inch all-around clearance between bare pipe and sleeves or between jacketed-insulation and sleeves. Except in pipe chases or interior walls, seal the annular space between pipe and sleeve or between jacket over-insulation and sleeve in accordance with Section 07 92 00 JOINT SEALANTS.

3.1.15.2 Waterproof Penetrations

Install pipes passing through roof or floor waterproofing membrane through a 17 ounce copper sleeve, or a 0.032 inch thick aluminum sleeve, each within an integral skirt or flange. Form flashing sleeve, and extend skirt or flange greater than 8 inches from the pipe and set over the roof or floor membrane in a troweled coating of bituminous cement. Extend the flashing sleeve up the pipe a minimum of 2 inches above the roof or floor penetration. Seal the annular space between the flashing sleeve and the bare pipe or between the flashing sleeve and the metal-jacket-covered insulation as indicated. Seal penetrations by either one of the following methods.

3.1.15.2.1 Waterproofing Clamping Flange

Pipes up to and including 10 inches in diameter passing through roof or floor waterproofing membrane may be installed through a cast iron sleeve with caulking recess, anchor lugs, flashing clamp device, and pressure ring with brass bolts. Clamp waterproofing membrane into place and place sealant in the caulking recess.

3.1.15.2.2 Modular Mechanical Type Sealing Assembly

In lieu of a waterproofing clamping flange and caulking and sealing of annular space between pipe and sleeve or conduit and sleeve, a modular mechanical type sealing assembly may be installed. Provide seals consisting of interlocking synthetic rubber links shaped to continuously fill the annular space between the pipe/conduit and sleeve with corrosion protected carbon steel bolts, nuts, and pressure plates. Loosely assemble links with bolts to form a continuous rubber belt around the pipe with a pressure plate under each bolt head and each nut. After the seal assembly is properly positioned in the sleeve, tighten the bolt to cause the rubber sealing elements to expand and provide a watertight seal between the pipe/conduit and the sleeve. Size each seal assembly as recommended by the manufacturer to fit the pipe/conduit and sleeve involved. The Contractor electing to use the modular mechanical type seals must provide sleeves of the proper diameters.

3.1.15.3 Fire-Rated Penetrations

Seal penetration of fire-rated walls, partitions, and floors as specified in Section 07 84 00 FIRESTOPPING.

3.1.15.4 Escutcheons

Provide escutcheons for finished surfaces where exposed piping, bare or insulated, pass through floors, walls, or ceilings, except in boiler, utility, or equipment rooms. Where sleeves project slightly from floors, use special deep-type escutcheons. Secure escutcheon to pipe or pipe covering.

3.1.16 Access Panels

Provide access panels for all concealed valves, vents, controls, and items requiring inspection or maintenance. Provide access panels of sufficient size and locate so that the concealed items may be serviced and maintained or completely removed and replaced. Provide access panels as specified in Section 08 31 00 ACCESS DOORS AND PANELS.

3.1.17 Field Applied Insulation

Field installed insulation is specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS, except as defined differently herein.

3.1.18 Field Painting

Painting required for surfaces not otherwise specified, and finish painting of items only primed at the factory are specified in Section 09 90 00 PAINTS AND COATINGS.

3.1.18.1 Color Coding

Color coding for piping identification is specified in Section 09 90 00 PAINTS AND COATINGS.

3.1.18.2 Color Coding Scheme

Provide a color coding scheme for locating hidden piping in accordance with Section 22 00 00 PLUMBING, GENERAL PURPOSE.

3.1.19 Identification Tags

Provide identification tags made of brass, engraved laminated plastic or engraved anodized aluminum indicating service and item number on all valves and dampers. Tags must be 1-3/8 inch minimum diameter and marking must be stamped or engraved. Indentations must be black for reading clarity. Attach tags to valves with No. 12 AWG copper wire, chrome-plated beaded chain or plastic straps designed for that purpose.

3.2 CLEANING AND ADJUSTING

Clean uncontaminated system(s) by evacuation and purging procedures currently recommended by refrigerant and refrigerant equipment manufacturers, and as specified herein, to remove small amounts of air and moisture. Systems containing moderate amounts of air, moisture, contaminated refrigerant, or any foreign matter are considered contaminated systems. Restore contaminated systems to clean condition including disassembly, component replacement, evacuation, flushing, purging, and re-charging, using currently approved refrigerant and refrigeration manufacturer's procedures. Restore contaminated systems at no additional cost to the Government as determined by the Contracting Officer. Do not use water in any procedure or test.

3.3 TRAINING COURSE

a. Submit a schedule, at least 2 weeks prior to the date of the proposed training course, which identifies the date, time, and location for the training. Conduct a training course for 6 members of the operating staff as designated by the Contracting Officer. The training period must consist of a total 4 hours of normal working time and start after the system is functionally completed but prior to final acceptance tests.

b. Cover all of the items contained in the approved operation and maintenance manuals.

c. Submit 6 complete copies of an operation manual in bound 8 1/2 by 11 inch booklets listing step-by-step procedures required for system startup, operation, abnormal shutdown, emergency shutdown, and normal shutdown at least 4 weeks prior to the first training course. Include the manufacturer's name, model number, and parts list in the booklets. Include the manufacturer's name, model number, service manual, and a brief description of all equipment and their basic operating features in the manuals.

d. Submit 6 complete copies of maintenance manual in bound 8 1/2 x 11 inch booklets listing routine maintenance procedures, possible breakdowns and repairs, and a trouble shooting guide. Include piping layouts and simplified wiring and control diagrams of the system as installed in the manuals.

3.4 REFRIGERANT PIPING TESTS

After all components of the refrigerant system have been installed and connected, subject the entire refrigeration system to pneumatic, evacuation, and startup tests as described herein. Submit a schedule, at least 2 weeks prior to the start of related testing, for each test. Identify the proposed date, time, and location for each test. Conduct tests in the presence of the Contracting Officer. Water and electricity

required for the tests will be furnished by the Government. Provide all material, equipment, instruments, and personnel required for the test. Provide the services of a qualified technician, as required, to perform all tests and procedures indicated herein. Coordinate field tests with Section 23 05 93 TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS. Submit 6 copies of the tests report in bound 8 1/2 by 11 inch booklets documenting all phases of the tests performed. Include initial test summaries, all repairs/adjustments made, and the final test results in the report.

3.4.1 Preliminary Procedures

Prior to pneumatic testing, isolate equipment which has been factory tested and refrigerant charged as well as equipment which could be damaged or cause personnel injury by imposed test pressure, positive or negative, from the test pressure, or remove from the system. Remove safety relief valves and rupture discs that are not part of factory sealed systems, and cap or plug openings.

3.4.2 Pneumatic Test

Provide pressure control and excess pressure protection at the source of test pressure. Valves must be wide open, except those leading to the atmosphere. Test gas must be dry nitrogen, with minus 70 degree F dewpoint and less than 5 ppm oil. Apply test pressure in two stages before any refrigerant pipe is insulated or covered. In accordance with ASME B31.5, a preliminary test not to exceed 25 psi must be applied as a means of locating major leaks. Every joint being tested must be coated with a thick soap or color indicating solution. The second stage test pressure must be 300 psig on the high side and 150 psig on the low side.. For large systems that are not completely visible, the pressure in the system must be gradually increased to one-half of the test pressure after which the pressure must be increased in steps of one-tenth of the test pressure, until the required test pressure has been reached. The test pressure must be continuously maintained for at least 2 hours, after which it can be reduced to the leak test pressure. A correction factor of 0.3 psi will be allowed for each degree F change between test space initial and final ambient temperature, plus for increase and minus for a decrease. The leak test pressure must be the design pressure, or a pressure specified in the engineering design. To repair leaks, the joint must be taken apart, thoroughly cleaned, and reconstructed as a new joint. Joints repaired by caulking, re-melting, or back-welding/brazing are not acceptable. Following repair, the entire system must be retested using the pneumatic tests described above. Reassemble the entire system once the pneumatic tests are satisfactorily completed.

3.4.3 Evacuation Test

Using high vacuum pump and certified micron gage, reduce absolute pressure on both sides of system simultaneously to 300 microns. After reaching this point charge system with proper refrigerant until pressure of zero psig is obtained. Repeat evacuation-charging procedure for two more cycles, totaling to three evacuation-charging cycles. On final evacuation, secure pump and maintain 300 microns for 2 hours before charging with required final refrigerant.

3.4.4 System Charging and Startup Test

Following satisfactory completion of the evacuation tests, charge the

system with the required amount of refrigerant by raising pressure to normal operating pressure and in accordance with manufacturer's procedures. Following charging, the system must operate with high-side and low-side pressures and corresponding refrigerant temperatures, at design or improved values. Test the entire system tested for leaks. Test fluorocarbon systems with halide torch or electronic leak detectors.

3.4.5 Refrigerant Leakage

If a refrigerant leak is discovered after the system has been charged, the leaking portion of the system must be immediatelyisolated from the remainder of the system and the refrigerant pumped into the system receiver or other suitable container. The refrigerant must not be discharged into the atmosphere.

3.4.6 Contractor's Responsibility

At all times during the installation and testing of the refrigeration system, take steps to prevent the release of refrigerants into the atmosphere. The steps must include, but not be limited to, procedures which will minimize the release of refrigerants to the atmosphere and the use of refrigerant recovery devices to remove refrigerant from the system and store the refrigerant for reuse or reclaim. At no time will the allowable leak rate exceed the leak rates allowed in Section 608 of the Clean Air Act: 30 percent of the full charge per year for industrial refrigeration, 20 percent of the full charge per year for commercial refrigeration, and 10 percent of the full charge per year for comfort cooling. Any system leaks within the first year must be repaired in accordance with the requirements herein at no cost to the Government including material, labor, and refrigerant if the leak is the result of defective equipment, material, or installation.

-- End of Section --

SECTION 23 25 00

CHEMICAL TREATMENT OF WATER FOR MECHANICAL SYSTEMS
05/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B40.100	(2022) Pressure Gauges and Gauge Attachments

ASTM INTERNATIONAL (ASTM)

ASTM D596	(2001; R 2018) Standard Guide for Reporting Results of Analysis of Water
ASTM D2688	(2015; E 2016) Standard Test Method for Corrosivity of Water in the Absence of Heat Transfer (Weight Loss Methods)

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Water Analysis; G

Spare Parts

Field Instructions

Tests; G

Training Course; G

1.3 MAINTENANCE MATERIAL SUBMITTALS

Submit spare parts data for each different item of material and equipment specified, after approval of the detail drawings, not later than 3 months prior to the date of beneficial occupancy. Include a complete list of parts and supplies, with source of supply, with the data.

1.4 QUALITY CONTROL

1.4.1 Safety

Ensure exposed moving parts, parts that produce high operating temperature, parts which may be electrically energized, and parts that may be a hazard to operating personnel are insulated, fully enclosed, guarded, or fitted with other types of safety devices. Install safety devices so that proper operation of equipment is not impaired..

1.4.2 Drawings

Because of the small scale of the drawings, it is not possible to indicate all offsets, fittings, and accessories that may be required. Carefully investigate the plumbing, fire protection, electrical, structural and finish conditions that would affect the work to be performed and arrange such work accordingly, furnishing required offsets, fittings, and accessories to meet such conditions.

1.5 DELIVERY, STORAGE, AND HANDLING

Protect all equipment delivered and placed in storage from the weather, humidity and temperature variations, dirt and dust, or other contaminants.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

2.1.1 Summary

This section covers the provisions and installation procedures necessary for a complete and totally functional water system(s) chemical treatment. Provide and install the system with all necessary System Components, Accessories, Piping Components, and Supplemental Components/Services.
.

2.1.2 Standard Products

a. Provide materials and equipment which are standard products of a manufacturer regularly engaged in the manufacturing of such products, that are of a similar material, design and workmanship and that have been in satisfactory commercial or industrial use for two years' prior to bid opening.

b. Include in the two-year use all applications of equipment and materials under similar circumstances and of similar size. Ensure the two years' experience has been satisfactorily completed by a product which has been sold or is offered for sale on the commercial market through advertisements, manufacturer's catalogs, or brochures. Products having less than a two-year field service record are acceptable if a certified record of satisfactory field operation, for not less than 6000 hours exclusive of the manufacturer's factory tests, can be shown.

c. All products are required to be supported by a service organization. Submit a certified list of qualified permanent service organizations for support of the equipment, including their addresses and qualifications. These service organizations are required to be reasonably convenient to the equipment installation and able to render

satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

d. The selected service organization provides the chemicals required, the concentrations required, and the water treatment equipment sizes and flow rates required. The company provides all chemicals required for the chilled and hot water systems and fills the systems with chemicals to the levels specified. The chemical is required to meet the requirements of this specification as well as the recommendations from the manufacturers of the condenser and cooling tower. Acid treatment chemicals are not allowed to be used.

2.1.3 Water Analysis

Conditions of make-up water to be supplied to the hot and chilled water systems reported in accordance with ASTM D596 are as follows:

Date of Sample	____
Temperature	____ degrees C
Silica (SiO 2)	____ ppm (mg/L)
Insoluble	____ ppm (mg/L)
Iron, total (Fe)	____ ppm (mg/L)
Aluminum (Al)	____ ppm (mg/L)
Calcium (Ca)	____ ppm (mg/L)
Magnesium (Mg)	____ ppm (mg/L)
Carbonate (HCO 3)	____ ppm (mg/L)
Sulfate (SO 4)	____ ppm (mg/L)
Chloride (Cl)	____ ppm (mg/L)
Nitrate (NO 3)	____ ppm (mg/L)
Turbidity	____ ntu
pH	____
Residual Chlorine	____ ppm (mg/L)
Total Alkalinity	____ ppm (mg/L)
Non-Carbonate Hardness	____ ppm (mg/L)
Total Hardness	____ ppm (mg/L)
Dissolved Solids	____ ppm (mg/L)

Conductivity	____ Micromho/cm

2.2 EQUIPMENT

2.2.1 Nameplates

Provide a nameplate for each major component of equipment that includes the manufacturer's name, address, type or style, and catalog or serial number securely attached to the item of equipment.

2.2.2 Gauges

Provide gauges that conform to ASME B40.100, Class 1, 2, or 3, Style X, Type I or III as required, 4-1/2 inches in diameter with phenolic or metal case.

2.3 COMPONENTS

2.3.1 Chilled Water System

Provide a 5 gallon shot feeder on the chilled water piping as indicated. Furnish the feeder with an air vent, gauge glass, funnel, valves, fittings, and piping.

2.3.1.1 Chilled Water Treatment

Treat chilled water with either a borax/nitrite type treatment or a molybdate type treatment.

2.3.1.2 Chilled Water Test Kits

Provide one test kit of each type required to determine the water quality as outlined within the operation and maintenance manuals (e.g. pH and nitrite or molybdate).

2.3.2 Low and Medium Temperature Hot Water

2.3.2.1 Chemical Feeder

Provide a 5 gallon shot feeder on the hot water piping as indicated. Base the size and capacity of feeder upon local requirements and water analysis. Furnish the feeder with an air vent, gauge glass, funnel, valves, fittings, and piping.

2.3.2.2 Low and Medium Temperature Hot Water Treatment

Treat hot water with either a borax/nitrite type treatment or a molybdate type treatment. Both types of treatment are acceptable to use with glycol. Maintain borax/nitrite treatment at the limits of 600 to 1000 ppm nitrite, 40 - 50 ppm copper corrosion inhibitor (TT or MBT) and pH of 8.5 to 9.5. Maintain molybdate treatment at the limits of 100 to 125 ppm molybdate, 40 - 50 ppm copper corrosion inhibitor (TT or MBT) and pH of 8.0 to 9.0.

2.3.2.3 Test Kit Requirements

Provide one test kit of each type required to determine the water quality as outlined within the operation and maintenance manuals (e.g. pH and nitrite or molybdate).

2.3.3 Test Kit

Provide one test kit of each type required to determine the water quality as outlined within the operation and maintenance manuals (e.g. pH, hardness and sulfite).

2.3.4 Supplemental Components/Services

Ensure drain and makeup water piping complies with the requirements of Section 22 00 00 PLUMBING, GENERAL PURPOSE. Connect drains to sanitary sewer systems by means of an indirect waste connection.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy, before performing any work.

3.2 INSTALLATION

Provide all chemicals, equipment and labor necessary to bring all system waters in conformance with the specified requirements. Perform all work in accordance with the manufacturer's published diagrams, recommendations, and equipment warranty requirements.

3.2.1 Piping

Fabricate all connections between dissimilar metals using dielectric unions.

3.3 FIELD QUALITY CONTROL

3.3.1 Tests

If the waters of the mechanical systems are not in conformance with the specified requirements or in accordance with manufacturer's recommendations, the contractor is required to direct the water treatment company to take corrective action to achieve compliance. Perform daily operational tests in the directed frequencies to maintain required control to prevent corrosion, scaling and damage to equipment during operation. Submit test schedules, at least 2 weeks prior to the start of related testing, for the chilled/hot water quality tests. Identify the date, time, frequency and collection location for each test within the schedules.

3.3.2 Chilled Water Testing (monthly)

Perform the following tests on chilled water on a monthly basis.

pH	____
Nitrite or Molybdate	____ ppm (mg/L)
Conductivity	____ micromho/cm

3.3.3 Hot Water Quality Testing

3.3.3.1 Low and Medium Temperature Systems (monthly)

Complete and record monthly testing for the following parameters.

pH	____
Nitrite or Molybdate	____ ppm (mg/L)

3.3.4 Quality Assurance Testing

Conduct QA testing periodically by an independent water treatment lab/consultant to verify to managers that the mechanical and water treatment systems are being maintained properly. Provide the QA evaluation reports to the government COR.

3.3.4.1 Chilled Water Quality Assurance Testing (quarterly)

Perform the following tests quarterly on chilled water.

pH	____
Nitrite or Molybdate	____ ppm (mg/L)
Conductivity	____ micromho/cm
Iron (total, as Fe(2)O(3))	____ ppm (mg/L)
Written evaluation summary	

3.3.4.2 Hot Water Quality Assurance Testing

a. Complete quarterly testing of Low and Medium Temperature Systems and record the following parameters.

pH	____
Nitrite or Molybdate	____ ppm (mg/L)
Iron (total, as Fe(2)O(3))	____ ppm (mg/L)

Written evaluation summary	

b. Have an independent consultant analyze the hot water once a month for a period of 1 year. Include the following information recorded in accordance with ASTM D596 in the monthly report.

pH	____
Sulfite (Na2SO3)	____ ppm (mg/L)
Hardness(as CaCO3)	____ ppm (mg/L)
Iron (total, as Fe(2)O(3))	____ ppm (mg/L)
Written evaluation summary	

3.3.5 Corrosion Testers

Install corrosion coupon and rack systems to verify corrosion control in the systems. Install testers or coupons in flowing system water through a sidestream or rack system. Test both mild steel and copper metal samples in the corrosion testers in accordance with ASTM D2688. Replace and analyze samples every 3 months. Rates of corrosion less than 3 mpy for steel and 0.2 mpy for copper are acceptable. Install corrosion testers on the piping systems of the following systems.

Chilled water system
Hot water loop

3.4 CLOSEOUT ACTIVITIES

3.4.1 Training Course

Submit a schedule, at least 2 weeks prior to the date of the proposed training course that identifies the date, time, and location for the training. Conduct a training course for the operating staff as designated by the Contracting Officer. Conduct the training to include a total of 8 hours of normal working time and start after the system is functionally completed but prior to final acceptance tests. Submit field instructions, at least 2 weeks prior to construction completion, including equipment layout, wiring and control diagrams, piping, valves and control sequences, and typed condensed operation instructions. Include within the condensed operation instructions all preventative maintenance procedures, methods of checking the system for normal and safe operation, and procedures for safely starting and stopping the system. Frame the posted instructions under glass or laminated plastic and post where indicated by the Contracting Officer. Ensure the field instructions cover all of the items contained in the Operation and Maintenance Manuals as well as demonstrations of routine maintenance operations.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 30 00

HVAC AIR DISTRIBUTION
02/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR MOVEMENT AND CONTROL ASSOCIATION INTERNATIONAL, INC. (AMCA)

AMCA 201	(2002; R 2011) Fans and Systems
AMCA 210	(2025) Laboratory Methods of Testing Fans for Certified Aerodynamic Performance Rating
AMCA 300	(2014) Reverberant Room Method for Sound Testing of Fans
AMCA 301	(2014) Methods for Calculating Fan Sound Ratings from Laboratory Test Data
AMCA 500-D	(2018) Laboratory Methods of Testing Dampers for Rating
AMCA 511	(2010; R 2016) Certified Ratings Program for Air Control Devices

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI 260 I-P	(2012) Sound Rating of Ducted Air Moving and Conditioning Equipment
AHRI 410	(2001; Addendum 1 2002; Addendum 2 2005; Addendum 3 2011) Forced-Circulation Air-Cooling and Air-Heating Coils
AHRI 430	(2009) Central-Station Air-Handling Units
AHRI 880 I-P	(2011) Performance Rating of Air Terminals
AHRI 885	(2008; Addendum 2011) Procedure for Estimating Occupied Space Sound Levels in the Application of Air Terminals and Air Outlets
AHRI 1060 I-P	(2014) Performance Rating of Air-to-Air Heat Exchangers for Energy Recovery Ventilation Heat Equipment

AMERICAN BEARING MANUFACTURERS ASSOCIATION (ABMA)

ABMA 9	(2015) Load Ratings and Fatigue Life for

Ball Bearings

ABMA 11 (2014; R 2020) Load Ratings and Fatigue Life for Roller Bearings

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 52.2 (2025) Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size

ASHRAE 62.1 (2016) Ventilation for Acceptable Indoor Air Quality

ASHRAE 70 (2023) Method of Testing the Performance of Air Outlets and Inlets

ASHRAE 84 (2024) Method of Testing Air-to-Air Heat/Energy Exchangers

ASHRAE 90.1 - IP (2019) Energy Standard for Buildings Except Low-Rise Residential Buildings

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M (2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products

ASTM A240/A240M (2025a) Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications

ASTM A924/A924M (2022a) Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process

ASTM B117 (2019) Standard Practice for Operating Salt Spray (Fog) Apparatus

ASTM B766 (2023) Standard Specification for Electrodeposited Coatings of Cadmium

ASTM C534/C534M (2025) Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form

ASTM C553 (2024) Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications

ASTM C1071 (2025) Standard Specification for Fibrous Glass Duct Lining Insulation (Thermal and Sound Absorbing Material)

ASTM D520 (2025) Standard Specification for Zinc

Dust Pigment

ASTM D1654 (2008; R 2016; E 2017) Standard Test Method for Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments

ASTM D3359 (2017) Standard Test Methods for Rating Adhesion by Tape Test

ASTM E84 (2025) Standard Test Method for Surface Burning Characteristics of Building Materials

ASTM E2016 (2022) Standard Specification for Industrial Woven Wire Cloth

ASTM G21 (2015; R 2021; E 2021) Standard Practice for Determining Resistance of Synthetic Polymeric Materials to Fungi

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350 (2017; Version 1.2) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

INTERNATIONAL CODE COUNCIL (ICC)

ICC IMC (2024) International Mechanical Code

INTERNATIONAL ELECTROTECHNICAL COMMISSION (IEC)

IEC 60034-30-1 (2014) Rotating Electrical Machines – Part 30-1: Efficiency Classes of Line Operated AC Motors (IE Code)

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

ISO 21940-11 (2016) Mechanical vibration -- Rotor balancing -- Part 11: Procedures and Tolerances for Rotors with Rigid Behavior

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 00001 (2024) Motors and Generators

NEMA MG 10 (2017) Energy Management Guide for Selection and Use of Fixed Frequency Medium AC Squirrel-Cage Polyphase Induction Motors

NEMA MG 10009 (2022) Energy Management Guide for Selection and Use of Single-Phase Motors

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 80 (2025) Standard for Fire Doors and Other

Opening Protectives

NFPA 90A (2024) Standard for the Installation of Air Conditioning and Ventilating Systems

NFPA 90B (2024) Standard for the Installation of Warm Air Heating and Air Conditioning Systems

NFPA 96 (2024) Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations

NFPA 701 (2023; ERTA 1 2023) Standard Methods of Fire Tests for Flame Propagation of Textiles and Films

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

ANSI/SMACNA 006 (2020) HVAC Duct Construction Standards Metal and Flexible

SMACNA 1819 (2022) Fire, Smoke and Radiation Damper Installation Guide for HVAC Systems, 5th Edition

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168 (2022) Adhesive and Sealant Applications

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 82 Protection of Stratospheric Ozone

UL SOLUTIONS (UL)

UL 6 (2022) UL Standard for Safety Electrical Rigid Metal Conduit-Steel

UL 181 (2013; Reprint Dec 2021) UL Standard for Safety Factory-Made Air Ducts and Air Connectors

UL 555 (2006; Reprint Aug 2016) UL Standard for Safety Fire Dampers

UL 586 (2009; Reprint Sep 2022) UL Standard for Safety High-Efficiency Particulate, Air Filter Units

UL 705 (2017; Reprint Sep 2024) UL Standard for Safety Power Ventilators

UL 900 (2015; Reprint Aug 2022) UL Standard for SafetyStandard for Air Filter Units

UL 1995 (2015; Reprint Aug 2022) UL Standard for Safety Heating and Cooling Equipment

UL Bld Mat Dir	(updated continuously online) Building Materials Directory
UL Fire Resistance	(2014) Fire Resistance Directory

1.2 SYSTEM DESCRIPTION

Furnish ductwork, piping offsets, fittings, and accessories as required to provide a complete installation. Coordinate the work of the different trades to avoid interference between piping, equipment, structural, and electrical work. Provide complete, in place, all necessary offsets in piping and ductwork, and all fittings, and other components, required to install the work as indicated and specified.

1.2.1 Mechanical Equipment Identification

The number of charts and diagrams must be equal to or greater than the number of mechanical equipment rooms. Where more than one chart or diagram per space is required, mount these in edge pivoted, swinging leaf, extruded aluminum frame holders which open to 170 degrees.

1.2.1.1 Charts

Provide chart listing of equipment by designation numbers and capacities such as flow rates, pressure and temperature differences, heating and cooling capacities, horsepower, pipe sizes, and voltage and current characteristics.

1.2.1.2 Diagrams

Submit proposed diagrams, at least 2 weeks prior to start of related testing. provide neat mechanical drawings provided with extruded aluminum frame under 1/8-inch glass or laminated plastic, system diagrams that show the layout of equipment, piping, and ductwork, and typed condensed operation manuals explaining preventative maintenance procedures, methods of checking the system for normal, safe operation, and procedures for safely starting and stopping the system. After approval, post these items where directed.

1.2.2 Service Labeling

1.2.2.1 Equipment Labeling

Label equipment as indicated below with labels made of self-sticking, plastic film designed for permanent installation. Provide labels in accordance with the typical examples below:

SERVICE	LABEL AND TAG DESIGNATION
Air handling unit Number	AHU - #
Dedicated Outdoor Air System Number	DOAS - #
Exhaust Fan Number	EF - #

SERVICE	LABEL AND TAG DESIGNATION
Heat Exchanger Unit Number	HX - #
Unit Heater Number	UH - #

1.2.2.2 Pipe Labeling

Identify similar services with different temperatures or pressures. Where pressures could exceed 125 pounds per square inch, gage, include the maximum system pressure in the label. Color coding of all piping systems must be in accordance with ASME A13.1 . Label and arrow piping in accordance with the following:

a. Each point of entry and exit of pipe passing through walls.

b. Each change in direction, i.e., elbows, tees.

c. In congested or hidden areas and at all access panels at each point required to clarify service or indicated hazard.

d. In long straight runs, locate labels at distances within eyesight of each other not to exceed 75 feet. All labels must be visible and legible from the primary service and operating area.

e.

For Bare or Insulated Pipes	
for Outside Diameters of	Lettering
1/2 thru 1-3/8 inch	1/2 inch
1-1/2 thru 2-3/8 inch	3/4 inch
2-1/2 inch and larger	1-1/4 inch

1.2.2.3 Ductwork Labeling

Label ductwork with 2 inch lettering indicating the type of ductwork, associated air handling device and arrow indiccating direction of airflow. Coordinate ductwork labeling with any duct insulation and painting requirements to assure labeling is visible on final installation. Duct labels are to be black text on white background, produced by either paint/stenciling or made of self-sticking, plastic film designed for permanent installation. Locations of ductwork labels are to be in accordance with the following:

a. Each point of entry and exit of ductwork passing through walls.

b. In congested or hidden areas and at all access panels at each point required to clarify service.

c. In long straight runs, locate labels at distances within eyesight of each other not to exceed 75 feet.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings; G

SD-03 Product Data

Insulated Nonmetallic Flexible Duct Runouts

Pre Manufactured Double Wall Ductwork

Duct Connectors

Duct Access Doors; G

Fire Dampers; G

Manual Balancing Dampers; G

Gravity Backdraft and Relief Dampers; G

Diffusers

Registers and Grilles

Louvers

Air Vents, Penthouses, and Goosenecks

In-Line Centrifugal Fans

Propeller Type Sidewall Fans

Air Handling Units; G

Variable Volume, Single Duct Terminal Units; G,

Reheat Units; G,

Energy Recovery Devices; G

Test Procedures

Diagrams; G

Indoor Air Quality for Duct Sealants; S

SD-06 Test Reports

Performance Tests; G

Damper Acceptance Test; G

SD-07 Certificates

Bolts

Ozone Depleting Substances Technician Certification

SD-08 Manufacturer's Instructions

Manufacturer's Installation Instructions

Operation and Maintenance Training

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G

Fire Dampers; G

Manual Balancing Dampers; G

In-Line Centrifugal Fans; G

Propeller Type Sidewall Fans; G

Air Handling Units; G

Variable Volume, Single Duct Terminal Units; G,

Reheat Units; G,

Energy Recovery Devices; G

SD-11 Closeout Submittals

Indoor Air Quality During Construction; S

1.4 QUALITY ASSURANCE

Except as otherwise specified, approval of materials and equipment is based on manufacturer's published data.

a. Where materials and equipment are specified to conform to the standards of the Underwriters Laboratories, the label of or listing with reexamination in UL Bld Mat Dir, and UL 6 is acceptable as sufficient evidence that the items conform to Underwriters Laboratories requirements. In lieu of such label or listing, submit a written certificate from any nationally recognized testing agency, adequately equipped and competent to perform such services, stating that the items have been tested and that the units conform to the specified requirements. Outline methods of testing used by the specified agencies.

b. Where materials or equipment are specified to be constructed or tested, or both, in accordance with the standards of the ASTM International (ASTM), the ASME International (ASME), or other standards, a manufacturer's certificate of compliance of each item is acceptable as proof of compliance.

c. Conformance to such agency requirements does not relieve the item from

compliance with other requirements of these specifications.

d. Where products are specified to meet or exceed the specified energy efficiency requirement of FEMP-designated or ENERGY STAR covered product categories, equipment selected must have as a minimum the efficiency rating identified under "Energy-Efficient Products" at http://femp.energy.gov/procurement.

1.4.1 Prevention of Corrosion

Protect metallic materials against corrosion. Provide rust-inhibiting treatment and standard finish for the equipment enclosures. Do not use aluminum in contact with earth, and where connected to dissimilar metal. Protect aluminum by approved fittings, barrier material, or treatment. Provide hot-dip galvanized ferrous parts such as anchors, bolts, braces, boxes, bodies, clamps, fittings, guards, nuts, pins, rods, shims, thimbles, washers, and miscellaneous parts not of corrosion-resistant steel or nonferrous materials in accordance with ASTM A123/A123M for exterior locations and cadmium-plated in conformance with ASTM B766 for interior locations. Provide written certification from the bolt manufacturer that the bolts furnished comply with the requirements of this specification. Include illustrations of product markings, and the number of each type of bolt to be furnished in the certification.

1.4.2 Asbestos Prohibition

Do not use asbestos and asbestos-containing products.

1.4.3 Ozone Depleting Substances Technician Certification

All technicians working on equipment that contain ozone depleting refrigerants must be certified as a Section 608 Technician to meet requirements in 40 CFR 82, Subpart F. Provide copies of technician certifications to the Contracting Officer at least 14 calendar days prior to work on any equipment containing these refrigerants.

1.4.4 Detail Drawings

Submit detail drawings showing equipment layout, including assembly and installation details and electrical connection diagrams; ductwork layout showing the location of all supports and hangers, typical hanger details, gauge reinforcement, reinforcement spacing rigidity classification, and static pressure and seal classifications. Include any information required to demonstrate that the system has been coordinated and functions properly as a unit on the drawings and show equipment relationship to other parts of the work, including clearances required for operation and maintenance. Submit drawings showing bolt-setting information, and foundation bolts prior to concrete foundation construction for all equipment indicated or required to have concrete foundations. Submit function designation of the equipment and any other requirements specified throughout this Section with the shop drawings.

1.4.5 Test Procedures

Conduct performance tests as required in Section 23 05 93 Testing, Adjusting and Balancing for HVAC and Section 23 09 00 Instrumentation and Control for HVAC.

1.5 DELIVERY, STORAGE, AND HANDLING

Protect stored equipment at the jobsite from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Additionally, cap or plug all pipes until installed.

PART 2 PRODUCTS

2.1 STANDARD PRODUCTS

Except for the fabricated duct, plenums and casings specified in paragraphs "Metal Ductwork" and "Plenums and Casings for Field-Fabricated Units",
provide components and equipment that are standard products of manufacturers regularly engaged in the manufacturing of products that are of a similar material, design and workmanship. This requirement applies to all equipment, including diffusers, registers, fire dampers, and balancing dampers.

a. Standard products are defined as components and equipment that have been in satisfactory commercial or industrial use in similar applications of similar size for at least two years before bid opening.

b. Prior to this two year period, these standard products must have been sold on the commercial market using advertisements in manufacturers' catalogs or brochures. These manufacturers' catalogs, or brochures must have been copyrighted documents or have been identified with a manufacturer's document number.

c. Provide equipment items that are supported by a service organization. In product categories covered by ENERGY STAR or the Federal Energy Management Program, provide equipment that is listed on the ENERGY STAR Qualified Products List or that meets or exceeds the FEMP-designated Efficiency Requirements.

2.2 IDENTIFICATION PLATES

In addition to standard manufacturer's identification plates, provide engraved laminated phenolic identification plates for each piece of mechanical equipment. Identification plates are to designate the function of the equipment. Submit designation with the shop drawings. Provide identification plates that are layers, black-white-black, engraved to show white letters on black background. Letters must be upper case. Identification plates that are 1-1/2-inches high and smaller must be 1/16-inch thick, with engraved lettering 1/8-inch high; identification plates larger than 1-1/2-inches high must be 1/8-inch thick, with engraved lettering of suitable height. Identification plates 1-1/2-inches high and larger must have beveled edges. Install identification plates using a compatible adhesive.

2.3 EQUIPMENT GUARDS AND ACCESS

Fully enclose or guard belts, pulleys, chains, gears, couplings, projecting setscrews, keys, and other rotating parts exposed to personnel contact according to OSHA requirements. Properly guard or cover with insulation of a type specified, high temperature equipment and piping exposed to contact by personnel or where it creates a potential fire hazard. The requirements for catwalks, operating platforms, ladders, and guardrails are specified in Section 08 31 00 ACCESS DOORS AND PANELS.

2.4 ELECTRICAL WORK

a. Provide motors, controllers, integral disconnects, contactors, and controls with their respective pieces of equipment, except controllers indicated as part of motor control centers. Provide electrical equipment, including motors and wiring, as specified in Section 26 20 00INTERIOR DISTRIBUTION SYSTEM. Provide manual or automatic control and protective or signal devices required for the operation specified and control wiring required for controls and devices specified, but not shown. For packaged equipment, include manufacturer provided controllers with the required monitors and timed restart.

b. For single-phase motors, provide high-efficiency type, including motors that are part of a system, in accordance with NEMA MG 10009 and NEMA MG 00001. Provide premium efficiency type for alternating current motors in accordance with NEMA MG 00001.

c. For polyphase motors, provide either ECM or squirrel-cage medium induction motors. Utilize the best equipment for the given mechanical equipment characteristics, including motors that are part of a system, and that meet the efficiency ratings for premium efficiency motors in accordance with NEMA MG 00001 or NEMA MG 10009. Select premium efficiency polyphase motors in accordance with NEMA MG 10.

d. Provide motors in accordance with NEMA MG 00001 and of sufficient size to drive the load at the specified capacity without exceeding the nameplate rating of the motor. Provide motors rated for continuous duty with the enclosure specified. Provide motor duty that allows for maximum frequency start-stop operation and minimum encountered interval between start and stop. Provide motor torque capable of accelerating the connected load within 20 seconds with 80 percent of the rated voltage maintained at motor terminals during one starting period. Provide motor starters complete with thermal overload protection and other necessary appurtenances. Fit motor bearings with grease supply fittings and grease relief to outside of the enclosure.

e. Where two-speed or variable-speed motors are indicated, solid-state variable-speed controllers are allowed to accomplish the same function. Use solid-state variable-speed controllers for motors rated 10 hp or less and adjustable frequency drives for larger motors. Provide variable frequency drives for motors as specified in Section 26 29 23 ADJUSTABLE SPEED DRIVE SYSTEMS UNDER 600 VOLTS.

2.4.1 Electronically Commutated Motors

Provide ECM Motors of a sufficient size for the duty to be performed while not exceeding the full-load rating when the driven equipment is operating at specified capacity under the most severe loading conditions.

2.4.1.1 Design Requirements

a. Provide Electronically Commutated Motors (ECM) designed as a DC brushless motor for variable speed or constant speed motor control. ECM design must allow for factory setting of the unit's fan flow. ECM must maintain respective constant fan speed at all set points regardless of external pressures that are within design ranges. Motor must be permanently lubricated with ball bearings with an L-10 rated

life of not less than standards in accordance with ABMA 9 or ABMA 11.

b. ECM will be complete with and be operated by a single-phase or three-phase integrated controller/inverter. AC power will be rectified, filtered and then converted to DC power. This will ensure variable speed operation at DC power.

c. ECM controller must be capable of accepting a 0-10VDC or a 4-20mA signal for manual/automatic control.

d. Ensure efficiency is a minimum of 70 percent over the motors entire operating range.

2.4.1.2 Electrically Driven Equipment

When electrically driven equipment differs from that indicated, make adjustments to the motor size, wiring and conduit systems, disconnect devices, and circuit protection to accommodate the equipment installed, at no additional cost to the Government. Provide control and protective devices in accordance with NFPA 70 requirements.

2.4.1.3 Voltage Ratings

Provide at a minimum, motors with the following voltage ratings:

MOTOR SIZE		FED FROM POWER SOURCE	MOTOR VOLTAGE RATING
MOTOR TYPE	HORSE POWER		
Fractional horsepower, single-phase	3/4 and smaller	120/208-volt, 120/240-volt, 480/277-volt, 3-phase, 4-wire	115-volt, 200-volt, 230-volt, 277-volt 1-phase 50/60-hertz
Integer horsepower, single-phase	1	120/208-volt, 120/240-volt, 277/480-volt, 3-phase, 4-wire	115-volt, 200-volt, 230-volt, 277-volt 1-phase 50/60-hertz
Integer horsepower, single-phase	2 and 3	120/208-volt, 120/240-volt, 3-phase, 4-wire	200-volt, 230-volt, 1-phase 50/60-hertz
Integer horsepower, three-phase	1 thru 5	120/208-volt, 120/240-volt, 277/480-volt, 3-phase, 4-wire	200-volt, 230-volt, 460-volt, 3-phase 50/60-hertz
Integer horsepower, three-phase	7.5 and above	277/480-volt, 3-phase, 4-wire	460-volt, 3-phase 50/60-hertz

2.4.1.4 Temperature Rating and Insulation

Provide motors designed for continuous operation at the rated full load in an ambient temperature of 40 degrees C, 104 degrees F, with an insulation level of at least Class B.

2.4.1.5 Motor Enclosures

2.4.1.5.1 Indoor Type Enclosures

a. For motors installed in indoor, clean, dry, non-hazardous locations, provide the following: Open-type drip-proof enclosures.

b. For motors installed in indoor, wet, non-hazardous locations, provide the following: Open splash-proof enclosures.

c. For motors installed in indoor, non-hazardous locations where it is necessary to protect the motor from dirt, moisture, chemical fumes, or other harmful ingredients in the surrounding atmosphere, provide either of the following type of enclosure: Totally enclosed fan-cooled enclosures for exterior cooling by means of a fan or fans integral with the machine.

2.5 ANCHOR BOLTS

Provide anchor bolts for equipment placed on concrete equipment pads or on concrete slabs. Bolts to be of the size and number recommended by the equipment manufacturer and located by means of suitable templates. Installation of anchor bolts must not degrade the surrounding concrete.

2.6 PAINTING

Paint equipment units in accordance with approved equipment manufacturer's standards unless specified otherwise. Field retouch only if approved. Otherwise, return equipment to the factory for refinishing. Paint in accordance with Section 09 90 00 PAINTS AND COATINGS.

2.7 FACTORY PAINTING

Factory paint new equipment, which are not of galvanized construction. Paint with a corrosion resisting paint finish according to ASTM A123/A123M or ASTM A924/A924M. Clean, phosphatize and coat internal and external ferrous metal surfaces with a paint finish which has been tested according to ASTM B117, ASTM D1654, and ASTM D3359. Submit evidence of satisfactory paint performance for a minimum of 125 hours for units to be installed indoors , refer to paragraph Corrosion Protection for Coastal Installations for equipment installed within 5 miles of a sea (salt) water coastline. Provide rating of failure at the scribe mark that is not less than 6, average creepage not greater than 1/8 inch. Provide rating of the inscribed area that is not less than 10, no failure. On units constructed of galvanized steel that have been welded, provide a final shop docket of zinc-rich protective paint on exterior surfaces of welds or welds that have burned through from the interior according to ASTM D520 Type I.

Field paint factory painting that has been damaged prior to acceptance by the Contracting Officer in compliance with the requirements of paragraph FIELD PAINTING OF MECHANICAL EQUIPMENT.

2.8 CORROSION PROTECTION FOR COASTAL INSTALLATIONS

Provide air handling coils with aluminum fins on copper tubes or micro channel coils or otherwise custom treated for corrosion protection. Coils on all outdoor equipment must pass ASTM B117 6000 hour salt spray test as installed unless otherwise noted on plans. For equipment installed within 1000 feet of the ocean corrosion resistance mush pass ASTM B117 6000 hour salt spray test as installed

For packaged equipment (outdoor heat pumps, air conditioning units, air handling units) less than 5 ton capacity, such equipment must be provided with the manufacturer's seacoast/coastal anti-corrosion options.

Heat transfer ratings of equipment must be indicated within the equipment submittals with consideration for the deratings associated with the corrosion protection systems as installed.

2.9 INDOOR AIR QUALITY

Provide equipment and components that comply with the requirements of ASHRAE 62.1 unless more stringent requirements are specified herein.

2.10 DUCT SYSTEMS

2.10.1 Metal Ductwork

Provide metal ductwork construction, including all fittings and components, that complies with ANSI/SMACNA 006, as supplemented and modified by this specification .

a. Construct ductwork meeting the requirements for the duct system static pressure as indicated on the Ductwork Construction and Leakage Testing Table provided on the drawings.

b. Provide radius type elbows with a centerline radius of 1.5 times the width or diameter of the duct where space permits. Otherwise, elbows having a minimum radius equal to the width or diameter of the duct or square elbows with factory fabricated turning vanes are allowed.

c. Provide branch duct supply take-offs and return connections to main ductwork using 45 degree branch connections or conical tap connections as indicated on the drawings.

d. Provide ductwork that meets the requirements of Seal Class A.

e. Provide sealants that conform to fire hazard classification specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS and are suitable for the range of air distribution and ambient temperatures to which it is exposed. Do not use pressure sensitive tape as a sealant. Provide duct sealant products that meet either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or Volatile Organic Compounds (VOC) content requirements of SCAQMD Rule 1168 (HVAC duct sealants are classified as "Other" within the SCAQMD Rule 1168 sealants table). The VOC emittance must be 420 g/l or less. Provide validation of indoor air quality for duct sealants.

f. Make spiral lock seam duct, and flat oval with duct sealant and lock with not less than 3 equally spaced drive screws or other approved

methods indicated in ANSI/SMACNA 006. Apply the sealant to the exposed male part of the fitting collar so that the sealer is on the inside of the joint and fully protected by the metal of the duct fitting. Apply one brush coat of the sealant over the outside of the joint to at least 2 inch band width covering all screw heads and joint gap. Dents in the male portion of the slip fitting collar are not acceptable.

g. Fabricate outdoor air intake ducts and plenums with watertight soldered or brazed joints and seams. Slope bottom of outdoor air intake plenums at 1/2 inch per foot.

2.10.1.1 Insulated Nonmetallic Flexible Duct Runouts

Use flexible duct runouts only where indicated. Runout length is indicated on the drawings, and is not to exceed 5 feet. Provide runouts that are preinsulated, factory fabricated, and that comply with NFPA 90A and UL 181. Provide either field or factory applied vapor barrier. Provide not less than 20 ounce/square yard glass fabric duct connectors coated on both sides with neoprene. Where high velocity units are supplied with vertical air inlets, use a streamlined, vaned and mitered elbow transition piece for connection to the flexible duct or hose. Provide a die-stamped elbow and not a flexible connector as the last elbow to these units other than the vertical air inlet type. Insulated flexible connectors are allowed as runouts. Provide insulated material and vapor barrier that conform to the requirements of Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS. Do not expose the insulation material surface to the air stream.

2.10.1.2 General Service Duct Connectors

Provide a flexible duct connector approximately 6 inches in width where sheet metal connections are made to fans or where ducts of dissimilar metals are connected. For round/oval ducts, secure the flexible material by stainless steel or zinc-coated, iron clinch-type draw bands. For rectangular ducts, install the flexible material locked to metal collars using normal duct construction methods. Provide a composite connector system that complies with NFPA 701 and is classified as "flame-retardant fabrics" in UL Bld Mat Dir.

2.10.2 Duct Access Doors

Provide hinged access doors conforming to ANSI/SMACNA 006 in ductwork and plenums where indicated and at all air flow measuring primaries, automatic dampers, fire dampers, coils, thermostats, and other apparatus requiring service and inspection in the duct system. Provide access doors upstream and downstream of air flow measuring primaries and heating and cooling coils. Provide doors that are a minimum 15 by 18 inches, unless otherwise shown. Where duct size does not accommodate this size door, make the doors as large as practicable. Equip doors 24 by 24 inches or larger with fasteners operable from inside and outside the duct. Use insulated type doors in insulated ducts.

2.10.3 Fire Dampers

Use 1.5 hour rated fire dampers unless otherwise indicated. Provide fire dampers that conform to the requirements of NFPA 90A and UL 555. Perform the fire damper test as outlined in NFPA 90A. Provide automatic operating

fire dampers with a dynamic rating suitable for the maximum air velocity and pressure differential to which it is subjected. Provide fire dampers approved for the specific application, and install according to their listing. Equip fire dampers with a steel sleeve or adequately sized frame installed in such a manner that disruption of the attached ductwork, if any, does not impair the operation of the damper. Equip sleeves or frames with perimeter mounting angles attached on both sides of the wall or floor opening. Construct ductwork in fire-rated floor-ceiling or roof-ceiling assembly systems with air ducts that pierce the ceiling of the assemblies in conformance with UL Fire Resistance. Provide curtain type with damper blades out of the air stream fire dampers. Install dampers that do not reduce the duct or the air transfer opening cross-sectional area. Install dampers so that the centerline of the damper depth or thickness is located in the centerline of the wall, partition or floor slab depth or thickness. Unless otherwise indicated, comply with the installation details given in SMACNA 1819 and in manufacturer's instructions for fire dampers. Perform acceptance testing of fire dampers according to paragraph DAMPER ACCEPTANCE TEST and NFPA 80.

2.10.4 Manual Balancing Dampers

a. Furnish factory manufactured and assembled manual balancing dampers with accessible locking-type quadrant operators. Manufacturer must publish damper data sheets and dampers must be sold on the open market. Use chromium plated operators (with all exposed edges rounded) in finished portions of the building where ductwork is exposed.

b. Furnish stand-off mounting brackets, bases, or adapters, not less than the thickness of the insulation, to provide clearance between the duct surface and the operator. Stand-off mounting items are to be integral with the operator or standard accessory of the damper manufacturer. For duct widths greater than 30 inches, provide locking regulator at each end of the damper shaft.

c. Dampers installed in ductwork with an air velocity over 1500 feet per minute, or pressure class greater than 2 inches must be rated for the design velocity and pressure class indicated.

2.10.4.1 Single Blade Round Dampers

a. May be furnished up to 20 inches in diameter.

b. Provide a minimum 3/8 inch square continuous full length galvanized or plated steel axle shaft that supports the entire blade diameter and extends through the standoff bracket and quadrant operator. Firmly affix the axle shaft to the blade. Spring-loaded positioners are not permitted.

c. Must be factory fabricated in a frame with a minimum length of 6 inches made of galvanized steel with straightening ribs; minimum of 22 gage up to 8 inch diameter, and 20 gage above 8 inch diameter. Damper frames are to be mounted end to end with round duct. Supple the axle shaft on both ends with a pressed in elastomeric bearing/seal, for low infiltration/exfiltration air leakage.

d. Provide galvanized steel damper blade; minimum of 22 gage up to 8 inch diameter, and 20 gage above 8 inch diameter.

2.10.4.2 Single Blade Rectangular Dampers

a. May be furnished up to 12 inches in height for rectangular ducts.

b. Provide square galvanized or plated steel axle shaft(s) that support the blade at both ends and extends through the standoff bracket and quadrant operator; minimum 3/8 inch up to 19 inch blade length, and 1/2 inch over 19 inch blade length. Firmly affix the axle shaft(s) to the blade. Spring-loaded positioners are not permitted. Provide, at the duct wall shaft penetration, an elastomeric seal for low infiltration/exfiltration air leakage.

c. Must be factory fabricated in a frame with a minimum length 3 inches made of galvanized steel; minimum of 24 gage up to 19 inch blade length, and 22 gage over 19 inch blade length. Damper frames are to be mounted inside the duct. Support axle shaft on both ends with a bearing in the frame.

d. Provide damper blades made of galvanized steel with roll formed or broke stiffener(s); minimum of 20 gage up to 19 inch blade length, and 18 gage over 19 inch blade length.

2.10.4.3 Multi-blade Rectangular Dampers

a. Furnish for round ducts larger than 20 inch and rectangular duct greater than 12 inches in height, except flanged duct system. Furnish square to round transitions for application in round duct.

b. Provide 1/2 inch galvanized or plated steel axle shafts that support each blade at both ends. Extend the operator shaft through the standoff bracket and quadrant operator. An elastomeric seal for low infiltration/exfiltration air leakage must be at the duct wall shaft penetration.

c. Must be factory fabricated in a frame with a minimum length of 5 inches made of minimum 16 gage galvanized steel. Damper frames are to be mounted inside the duct. Support axle shafts on both end with a bearing in the frame. Blade linkage must be galvanized or plated steel and concealed in the frame, out of the air stream.

d. Provide opposed blades made of galvanized steel with roll formed or broke stiffeners(s); minimum of 16 gage.

2.10.4.4 Rectangular Dampers for Flanged Duct

a. Provide for flanged duct systems.

b. Must be multi-blade rectangular.

c. Provide 1/2 inch galvanized or plated steel axle shafts that support each blade at both ends. Extend the operator shaft through the standoff bracket and quadrant operator.

d. Must be factory fabricated in a frame with a minimum length of 3 inches made galvanized steel with a thickness to match the duct and at least 16 gage, or 20 gage with additional reinforcing such as a C channel. Mount damper frames end to end with the duct. Support axle shafts on both ends with a pressed in elastomeric bearing/seal for low infiltration/exfiltration air leakage. Provide galvanized or plated

steel blade linkage, concealed in a frame, out of the air stream.

e. Provide opposed blades made of galvanized steel with roll formed or broker stiffeners(s); minimum of 16 gage.

2.10.5 Automatic Balancing Dampers

Provide pressure independent automatic balancing dampers at locations as shown on the plans or in accordance with drawing schedules. Automatic balancing dampers must operate without a required power supply and be field adjustable to design airflows without the use of tools using a slide setpoint indicator on the face of the damper. Automatic balancing dampers must be rated for operation with air temperatures ranging from25 degrees to 140 degrees F. Automatic air balancing dampers must provide airflow within 10 percent of setpoint at air pressures from0.2 inch to 1.2 inch water column when tested in accordance with AMCA 500-D.

2.10.6 Gravity Backdraft and Relief Dampers

Provide gravity balanced backdraft dampers where indicated on plans or as required on equipment schedules. Backdraft dampers must be constructed for horizontal or vertical mounting as required for the application. Backdraft dampers must be testing and rated for the required application in accordance with AMCA 500-D.

Damper blades are to be equipped with neoprene blade seals mechanically locked into the blade edge.

Equip with adjustable counterbalancing weights to allow operation of the blades such that "start to open" occurs at 0.02 inch w.g. and the damper achieves fully open position at 12.5 pascals.

Where backdraft dampers are provided as an accessory option to a fan, such backdraft dampers must be installed meeting all manufacturer's recommendations. The installer must demonstrate that the damper closes once the fan ceases operation.

2.10.7 Diffusers, Registers, and Grilles

Provide factory-fabricated units of aluminum that distribute the specified quantity of air evenly over space intended without causing noticeable drafts, air movement faster than 50 fpm in occupied zone, or dead spots anywhere in the conditioned area. Provide outlets for diffusion, spread, throw, and noise level as required for specified performance. Certify performance according to ASHRAE 70. Provide sound rated and certified inlets and outlets according to ASHRAE 70. Provide units with sound ratings at design conditions not exceeding the ASHRAE Applications Handbook, Noise and Vibration Control Chapter - table "Design Guidelines for HVAC-Related Background Sound in Rooms" refer to drawing air device schedule for maximum permissible sound rating by device. Provide diffusers and registers with volume damper with accessible operator, unless otherwise indicated; or if standard with the manufacturer, an automatically controlled device is acceptable. Where the inlet and outlet openings are located less than 7 feet above the floor, protect them by a grille or screen according to NFPA 90A.

2.10.7.1 Diffusers

Provide diffuser types indicated. Furnish ceiling mounted units with

anti-smudge devices, unless the diffuser unit minimizes ceiling smudging through design features. Provide diffusers with air deflectors of the type indicated. Install ceiling mounted units with rims tight against ceiling. Provide sponge rubber gaskets between ceiling and surface mounted diffusers for air leakage control. Provide suitable trim for flush mounted diffusers. For connecting the duct to diffuser, provide duct collar that is airtight and does not interfere with volume controller. Provide return or exhaust units that are similar to supply diffusers.

2.10.7.2 Perforated Plate Diffusers

Provide adjustable air pattern controls as indicated on the drawings. Provide diffuser faceplates that do not sag or deflect when operating under design conditions.

2.10.7.3 registers And Grilles

Double-deflection supply registers. Provide manufacturer-furnished volume dampers. Provide volume dampers of the group-operated, opposed-blade type and key adjustable by inserting key through face of register. Operating mechanism must not project through any part of the register face. Automatic volume control devices are acceptable. Provide exhaust and return registers as specified for supply registers, except provide exhaust and return registers that have a single set of nondirectional face bars or vanes having the same appearance as the supply registers.

2.10.8 Louvers

Provide louvers for installation in exterior walls that are associated with the air supply and distribution system as specified in Section 08 91 00 METAL WALL LOUVERS.

2.10.9 Air Vents, Penthouses, and Goosenecks

Fabricate air vents, penthouses, and goosenecks from galvanized steel or aluminum sheets with galvanized or aluminum structural shapes. Provide sheet metal thickness, reinforcement, and fabrication that conform to ANSI/SMACNA 006. Accurately fit and secure louver blades to frames. Fold or bead edges of louver blades for rigidity and baffle these edges to exclude driving rain. Provide air vents, penthouses, and goosenecks with bird screen.

2.10.10 Bird Screens and Frames

Provide bird screens that conform to ASTM E2016, No. 2 mesh, aluminum or stainless steel. Provide "medium-light" rated aluminum screens. Provide "light" rated stainless steel screens. Provide removable type frames fabricated from either stainless steel or extruded aluminum.

2.10.11 Pre Manufactured Double Wall Ductwork

For all interior exposed ductwork in finished/occupied spaces as indicated on plans provide double wall pre-insulated ductwork with minimum 24 gauge solid galvanized inner wall. Double wall ductwork and fittings are to be from a single manufacturer. Provide ducts with clear internal dimensions of the inner duct equal to the duct dimensions indicated on the plans. Construct the outer duct of galvanized sheet steel, unless otherwise indicated. Double wall duct must comply with ANSI/SMACNA 006 based on

static pressure class as indicated on the drawings, and be sealed in accordance to SMACNA Seal Class A requirements.

2.10.11.1 Double Wall Duct Insulation

Insulation thickness as installed must meet or exceed the thermal performance requirements of ASHRAE 90.1 - IP. Interstitial insulation may be one of the following:

a) Fibrous glass duct liner complying with ASTM C1071 and NFPA 90A or NFPA 90B. Fibrous glass duct liner insulation must be installed in the interstitial space with spacers that position the inner duct at a uniform distance from the outer duct without compressing the insulation. Provide with antimicrobial coating and cover with polyester film complying with UL 181 Class 1.

b) Flexible elastomeric duct liner complying with ASTM C534/C534M, Type II for sheet materials, and with NFPA 90A or NFPA 90B.

2.10.12 Clothes Dryer Exhaust Ductwork

Ductwork serving clothes dryer exhaust must be constructed of materials in accordance with ICC IMC

2.11 AIR SYSTEMS EQUIPMENT

2.11.1 Fans

Test and rate fans according to AMCA 210. Calculate system effect on air moving devices in accordance with AMCA 201 where installed ductwork differs from that indicated on drawings. Install air moving devices to minimize fan system effect. Where system effect is unavoidable, determine the most effective way to accommodate the inefficiencies caused by system effect on the installed air moving device. The sound power level of the fans must not exceed 85 dBA when tested according to AMCA 300 and rated in accordance with AMCA 301. Provide all fans with an AMCA seal. Connect fans to the motors either directly or indirectly with V-belt drive. Use V-belt drives designed for not less than 140 percent of the connected driving capacity. Provide belt driven fans less than 5 hp with adjustable pitch motor sheaves selected such that the pitch adjustment is at the middle of the adjustment range at fan design condition. Provide fixed pitch motor sheaves for motors 5 hp and above sized to produce fan design condition. Provide replacement sheaves as needed to achieve system air balance. Provide motors for V-belt drives with adjustable rails or bases. Provide removable metal guards for all exposed V-belt drives, and provide speed-test openings at the center of all rotating shafts. Provide fans with personnel screens or guards on both suction and supply ends, except that the screens need not be provided, unless otherwise indicated, where ducts are connected to the fan. Provide fan and motor assemblies with vibration-isolation supports or mountings as indicated on the drawings. Use vibration-isolation units that are standard products with published loading ratings. Select each fan to produce the capacity required at the fan static pressure indicated. Provide units with sound ratings at design conditions that will not result in objectional background noise in accordance with the ASHRAE Applications Handbook, chapter Noise and Vibration Control, table "Design Guidelines for HVAC-Related Background Sound in Rooms" refer to drawing fan schedule for maximum permissible sound rating by device. Obtain the sound power level values according to AMCA 300. Provide power ventilators that conform to UL 705 and have a UL

label.

2.11.1.1 In-Line Centrifugal Fans

Provide in-line fans with centrifugal backward inclined blades, stationary discharge conversion vanes, internal and external belt guards, and adjustable motor mounts. Mount fans in a welded tubular casing. Provide a fan that axially flows the air in and out. Streamline inlets with conversion vanes to eliminate turbulence and provide smooth discharge air flow. Enclose and isolate fan bearings and drive shafts from the air stream. Provide precision, self aligning ball or roller type fan bearings that are sealed against dust and dirt and are permanently lubricated. Provide L50 rated bearing life at not less than 200,000 hours as defined by ABMA 9 and ABMA 11. Provide motors with opendrip-proof enclosure.

2.11.1.2 Propeller Type Sidewall Fans

Provide propeller type fans, assembled on a reinforced metal panel with venturi opening spun into panel. Provide direct or V-belt driven fans with wheels less than 24 inches in diameter and provide V-belt driven fans with wheels 24 inches in diameter and larger. Provide fans with wall mounting collar. Provide lubricated bearings. Equip fans with wheel and motor side metal or wire guards which have a corrosion-resistant finish. Provide drip-proof type motor enclosure. Install motor operated backdraft dampers where indicated.

2.11.2 Coils

Provide fin-and-tube type coils constructed of seamless copper tubes and aluminum fins mechanically bonded or soldered to the tubes... Provide casing and tube support sheets that are not lighter than 16 gauge galvanized steel, formed to provide structural strength. When required, provide multiple tube supports to prevent tube sag. Mount coils for counterflow service. Rate and certify coils to meet the requirements of AHRI 410. Provide factory applied phenolic, vinyl or epoxy/electrodeposition coating.

2.11.2.1 Water Coils

Install water coils with a pitch of not less than 1/8 inch/foot of the tube length toward the drain end. Use headers constructed of cast iron, welded steel or copper. Furnish each coil with a plugged vent and drain connection extending through the unit casing. Provide removable water coils with drain pans. Pressure test coils in accordance with UL 1995.

2.11.3 Air Filters

List air filters according to requirements of UL 900, except list high efficiency particulate air filters of 99.97 percent efficiency by the DOP Test method under the Label Service to meet the requirements of UL 586.

2.11.3.1 Extended Surface Pleated Panel Filters

Provide 2 inch depth, sectional, disposable type filters of the size indicated with a MERV of 8 when tested according to ASHRAE 52.2. Provide initial resistance at 500 fpm that does not exceed 0.36 inches water gauge. Provide UL Class 2 filters, and nonwoven cotton and synthetic fiber mat media. Attach a wire support grid bonded to the media to a moisture resistant fiberboard frame. Bond all four edges of the filter media to

the inside of the frame to prevent air bypass and increase rigidity.

2.11.3.2 Extended Surface Nonsupported Pocket Filters

Provide 30 inch depth, sectional, replaceable dry media type filters of the size indicated with a MERV of 13 when tested according to ASHRAE 52.2. Provide initial resistance at 500 fpm that does not exceed 0.45 inches water gauge. Provide UL Class 1 filters. Provide fibrous glass media, supported in the air stream by a wire or non-woven synthetic backing and secured to a galvanized steel metal header. Provide pockets that do not sag or flap at anticipated air flows. Install each filter with an extended surface pleated panel filter as a prefilter in a factory preassembled, side access housing or a factory-made sectional frame bank, as indicated.

2.11.3.3 Cartridge Type Filters

Provide 12 inch depth, sectional, replaceable dry media type filters of the size indicated with a MERV of 13 when tested according to ASHRAE 52.2. Provide initial resistance at 500 fpm that does not exceed 0.56 inches, water gauge. Provide UL class 1 filters, and pleated microglass paper media with corrugated aluminum separators, sealed inside the filter cell to form a totally rigid filter assembly. Fluctuations in filter face velocity or turbulent airflow have no effect on filter integrity or performance. Install each filter in a factory preassembled side access housing, or a factory-made sectional frame bank, as indicated.

2.11.3.4 Sectional Cleanable Filters

Provide 2 inch thick cleanable filters. Provide viscous adhesive in 5 gallon containers in sufficient quantity for 12 cleaning operations and not less than one quart for each filter section. Provide one washing and charging tank for every 100 filter sections or fraction thereof; with each washing and charging unit consisting of a tank and single drain rack mounted on legs and drain rack with dividers and partitions to properly support the filters in the draining position.

2.11.3.5 Replaceable Media Filters

Provide the dry-media type replaceable media filters, of the size required to suit the application. Provide filtering media that is not less than 2 inches thick fibrous glass media pad supported by a structural wire grid or woven wire mesh. Enclose pad in a holding frame of not less than 16 gauge galvanized steel, equipped with quick-opening mechanism for changing filter media. Base the air flow capacity of the filter on net filter face velocity not exceeding 300 fpm, with initial resistance of 0.13 inches water gauge. Provide MERV that is not less than 8 when tested according to ASHRAE 52.2.

2.11.3.6 Filter Gauges

Provide dial type filter gauges, diaphragm actuated draft for all filter stations, including those filters which are furnished as integral parts of factory fabricated air handling units. Provide gauges that are at least 3-7/8 inches in diameter, with white dials with black figures, and with a minimum range of 1 inch of water beyond the specified final resistance for the filter bank on which each gauge is applied. Provide each gauge with a screw operated zero adjustment and two static pressure tips with integral compression fittings, two molded plastic vent valves, two 5 foot minimum

lengths of 1/4 inch diameter aluminum tubing, and all hardware and accessories for gauge mounting.

2.12 AIR HANDLING UNITS

2.12.1 Factory-Fabricated Air Handling Units

Provide single-zone draw-through type units as indicated. Units must include fans, coils, airtight insulated casing, prefilters, adjustable V-belt drives, belt guards for externally mounted motors, access sections where indicated, combination sectional filter-mixing box, vibration-isolators, and appurtenances required for specified operation. Provide fan and motor assemblies with vibration-isolation supports or mountings as indicated on the drawings. Physical dimensions of each air handling unit must be suitable to fit space allotted to the unit with the capacity indicated. Provide air handling unit that is rated in accordance with AHRI 430 and AHRI certified for cooling.

2.12.1.1 Casings

Provide the following:

a. Casing sections 2 inch double wall type, constructed of a minimum 22 gauge galvanized steel, aluminum, or stainless steel conforming to ASTM A240/A240M, Type 304. Make the inner casing of double wall units a minimum 20 gauge solid galvanized steel . Design and construct casing with an integral insulated structural galvanized steel or aluminum frame such that exterior panels are non-load bearing.

   Incorporate a standing seam or thermoplastic polyolefin (TPO) on the exterior of outdoor unit roofs to ensure a rigid roof construction and prevent water infiltration. Roof assembly must be sloped not less than 1:100 for drainage and is to overhang all walls by 1.5 inch minimum to prevent sheeting from roof to side panels. Rain gutters are to also be provided over all doors shorter than total unit height to direct rain away from door assembly. Where outdoor units are shipped in multiple sections, provide standing-seam joiners at each split with adhesive, hardware, and cover strips for field joining by the installing contractor.

   Unit casing (wall/floor/roof panels and doors) must be able to withstand up to 1.5 times design static pressure, or 8-inch water gauge and not exceed 0.0042 per inch of panel span (L/240) when measured at the panel midpoint. Air leakage to be guaranteed at no more than 1 percent of the design volume at 1.5 times the design operating pressure or 50 cubic feet per minute, whichever is greater. Specified air leakage accomplished without the use of caulk. Total estimated air leakage reported for each unit in cubic feet per minute or as a percentage of supply air.

b. Casing panel inner liners must not extend to the exterior of the unit or contact the exterior frame. A mid-span, no-through-metal, internal thermal break is provided for all unit casing panels . Individually removable exterior panel sections are removable with standard tools. Removal must not affect the structural integrity of the unit. Furnish casings with access sections, according to paragraph AIR HANDLING UNITS, inspection doors, and access doors must be capable of opening a minimum of 90 degrees.

c. Insulated, fully gasketed, double-wall type inspection and access doors, of a minimum 22 gauge galvanized steel, 0.040 inch aluminum, or 22 gauge stainless steel conforming to ASTM A240/A240M. Provide rigid doors with heavy duty hinges and latches. Inspection doors must be a minimum 12 inches wide by 12 inches high. Access doors must be a minimum 24 inches wide, the full height of the unit casing or a minimum of 6 foot, whichever is less. Install a minimum 8 by 8 inches sealed glass window suitable for the intended application in all access doors.

d. Double-wall insulated type drain pan (thickness equal to exterior casing) constructed of 20 gauge stainless steel conforming to ASTM A240/A240M, Type 304, conforming to ASHRAE 62.1. Construct drain pans water tight, treated to prevent corrosion, and designed for positive condensate drainage. When 2 or more cooling coils are used, with one stacked above the other, condensate from the upper coils must not flow across the face of lower coils. Provide intermediate drain pans or condensate collection channels and downspouts, as required to carry condensate to the unit drain pan out of the air stream and without moisture carryover. Construct drain pan to allow for easy visual inspection, including underneath the coil without removal of the coil and to allow complete and easy physical cleaning of the pan underneath the coil without removal of the coil. Provide coils that are individually removable from the casing. Drain connections must be of the same material as the primary drain pan and extend a minimum of 2-1/2 inch beyond the base to ensure adequate room for field piping of condensate traps.

e. Casing insulation that conforms to NFPA 90A. Insulate double-wall casing sections handling conditioned air with not less than 2 inches of the same insulation specified for single-wall casings. Foil-faced insulation is not an acceptable substitute for use with double wall casing. Seal double wall insulation completely by inner and outer panels.

f. Factory applied fibrous glass insulation that conforms to ASTM C1071, except that the minimum thickness and density requirements do not apply, and that meets the requirements of NFPA 90A. Make air handling unit casing insulation uniform over the entire casing. Foil-faced insulation is not an acceptable substitute for use on double-wall access doors and inspection doors and casing sections.

g. Duct liner material, coating, and adhesive that conforms to fire-hazard requirements specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS. Protect exposed insulation edges and joints where insulation panels are butted with a metal nosing strip or coat to meet erosion resistance requirements of ASTM C1071.

h. A latched and hinged inspection door, in the fan and coil sections. Plus additional inspection doors, access doors and access sections where indicated.

2.12.1.2 Heating and Cooling Coils

Provide coils as specified in paragraph AIR SYSTEMS EQUIPMENT.

2.12.1.3 Air Filters

Provide air filters as specified in paragraph AIR SYSTEMS EQUIPMENT for

types and thickness indicated.

2.12.1.4 Fans

Provide the following:

a. Fans that are double-inlet, centrifugal type with each fan in a separate scroll. Dynamically balance fans and shafts prior to installation into air handling unit, then after it has been installed in the air handling unit, statically and dynamically balance the entire fan assembly. Mount fans on steel shafts, accurately ground and finished.

b. Fan bearings that are sealed against dust and dirt and are precision self-aligning ball or roller type, with L50 rated bearing life at not less than 200,000 hours as defined by ABMA 9 and ABMA 11. Provide bearings that are permanently lubricated or lubricated type with lubrication fittings readily accessible at the drive side of the unit. Support bearings by structural shapes, or die formed sheet structural members, or support plates securely attached to the unit casing. Do not fasten bearings directly to the unit sheet metal casing. Furnish fans and scrolls with coating indicated.

c. Fans that are driven by a unit-mounted, or a floor-mounted motor connected to fans by V-belt drive complete with belt guard for externally mounted motors. Furnish belt guards that are the three-sided enclosed type with solid or expanded metal face. Design belt drives for not less than a 1.3 service factor based on motor nameplate rating.

d. Where fixed sheaves are required, the use of variable pitch sheaves is allowed during air balance, but replace them with an appropriate fixed sheave after air balance is completed. Select variable pitch sheaves to drive the fan at a speed that produces the specified capacity when set at the approximate midpoint of the sheave adjustment. Furnish motors for V-belt drives with adjustable bases, and with opensplashproof enclosures.

e. Motor starters of across-the-line type with general-purpose enclosure. Select unit fan or fans to produce the required capacity at the fan static pressure with sound power level as indicated. Obtain the sound power level values according to AMCA 300 or AHRI 260 I-P.

2.12.1.5 Fan Arrays

Air handling units utilizing fan arrays are to comply with the following requirements:

a. Fans require Class II (minimum) construction with single inlet, direct drive ACMA Arrangement 4 fans installed either in a modular fashion in the field or pre-assembled on a prefabricated frame. Fans must be dynamically balanced and internally isolated to minimize vibration. Fan performance rated in accordance with AMCA 210.

b. Fan array plenum type fans driven by variable speed drives unless otherwise indicated; where indicated fans are driven by brushless DC electronically commutated motor (ECM) with external rotor and integrated maintenance free, permanently lubricated ball bearings and

statically and dynamically balanced in accordance with ISO 21940-11. The ECM must be closed, protection level IP 54, thermal class 155; motor efficiency class complies with IEC 60034-30-1 IE3 Premium efficiency.

c. Fan array controller provided by the air handling unit manufacturer to control the fan array modulating individual fan speed and number of active fans to provide the required airflows with minimum energy consumption.

d. Ensure the fan quantity allows achieving design airflow even with at least one fan out of operation. .

e. Ensure that each fan in fan systems with more than one fan is equipped with a backdraft damper. This safety measure helps protect against individual fan failure. .

f. Fan systems having more than one fan, and which do not include backdraft dampers require one blank-off plate, which may be used in the case of failure of a single fan to then replace the fan and prevent backflow through that location.

2.12.1.6 Access Sections and Filter/Mixing Boxes

Provide access sections where indicated and furnish with access doors as shown. Construct access sections and filter/mixing boxes in a manner identical to the remainder of the unit casing and equip with access doors. Design mixing boxes to minimize air stratification and to promote thorough mixing of the air streams.

2.12.1.7 Dampers

Provide dampers integral to factory fabricated air handling units constructed in accordance with 23 09 13 INSTRUMENTATION AND CONTROL DEVICES FOR HVAC. Dampers connecting the air handling unit to the outdoors (outdoor air, exhaust air, relief Air) must be AMCA 511 leakage classification 1A.

2.13 TERMINAL UNITS

2.13.1 Variable Air Volume (VAV) Terminal Units

a. Provide VAV and dual duct terminal units that are the type, size, and capacity shown, mounted in the ceiling or wall cavity, plus units that are suitable for single or dual duct system applications. Provide actuators and controls as specified in paragraph SUPPLEMENTAL COMPONENTS/SERVICES, subparagraph CONTROLS. For each VAV terminal unit, provide a temperature sensor in the unit discharge ductwork.

b. Provide unit enclosures that are constructed of galvanized steel not lighter than 22 gauge or aluminum sheet not lighter than 18 gauge. Provide single or multiple discharge outlets as required. Units with flow limiters are not acceptable. Provide unit air volume that is factory preset and readily field adjustable without special tools. Provide reheat coils as indicated.

c. Attach a flow chart to each unit. Base acoustic performance of the terminal units upon units tested according to AHRI 880 I-P with the calculations prepared in accordance with AHRI 885. Provide sound

power levels as indicated. Show discharge sound power for minimum and 1-1/2 inches water gauge inlet static pressure. Provide with double wall construction for acoustical attenuation. Solid metal liner must completely isolate insulation from airstream within the unit. Acoustical duct lining is not permitted.

d. For VAV terminal units provided with heating coils provide a manufacturer's access door to facilitate with the cleaning of the coil and servicing internal components without disturbing duct connections.

2.13.1.1 Variable Volume, Single Duct Terminal Units

Provide variable volume, single duct, terminal units with a calibrated air volume sensing device, air valve or damper, actuator, and accessory relays. Provide units that control air volume to within plus or minus 5 percent of each air set point volume as determined by the thermostat with variations in inlet pressures from 3/4 to 6 inch water gauge. Provide units with an internal resistance not exceeding 0.4 inch water gauge at maximum flow range. Provide external differential pressure taps separate from the control pressure taps for air flow measurement with a 0 to 1 inch water gauge range.

2.13.1.2 Reheat Units

2.13.1.2.1 Hot Water Coils

Provide fin-and-tube type hot-water coils constructed of seamless copper tubes and copper or aluminum fins mechanically bonded or soldered to the tubes. Provide headers that are constructed of cast iron, welded steel or copper. Provide casing and tube support sheets that are 16 gauge, galvanized steel, formed to provide structural strength. Provide tubes that are correctly circuited for proper water velocity without excessive pressure drop and are drainable where required or indicated. At the factory, test each coil at not less than 250 psi air pressure and provide coils suitable for 200 psi working pressure. Install drainable coils in the air handling units with a pitch of not less than 1/8 inch per foot of tube length toward the drain end. Coils must conform to the provisions of AHRI 410.

2.14 ENERGY RECOVERY DEVICES

Provide energy recovery ventilator unit that is factory-fabricated for indoor installation, consisting of a flat plate cross-flow heat exchanger, cooling coil, supply air fan and motor and exhaust air fan and motor. The casing must be 20 gauge G90, galvanized steel, double wall construction with one inch insulation. Provide fibrous desiccant cross-flow type heat exchanger core capable of easy removal from the unit for sensible and latent heat exchangers. Heat exchanger must include condensate drain pan with means to connect to piping to drain condensate. Sensible only, fixed plate, cross-flow heat exchangers are also an option depending on the design requirements.

2.14.1 Energy Recovery Performance

Energy recover equipment must comply with ASHRAE Design Guide for Dedicated Outdoor Air Systems (DOAS).

The manufacturer must provide certified performance data in accordance with ASHRAE 84 and AHRI 1060 I-P. Independent performance test results

must be used to rate the product in accordance with the AHRI Air-to-Air Energy Recovery Ventilation Equipment Program.

2.14.2 Plate Total Energy Exchanger

Provide enthalpy plate energy exchanger that must transfer both sensible and latent energy between outgoing and incoming air streams in a cross or counter flow arrangement with no moving parts. The enthalpy plate exchanger media must be coated with hydrophilic resin or impregnated with a polymeric desiccant. The material must allow the exchange water by direct vapor transfer using molecular transport without the need of condensation. The frame supporting enthalpy matrix must be constructed of G90 Galvanized material with end caps constructed of 18 gauge galvanized plates. The enthalpy plate exchanger must operate at temperatures between minus 40 degrees F and 140 degrees F. The enthalpy plate exchanger must have a warranty of at least 5 years against manufacturing defects.

The enthalpy plate exchanger must bear the AHRI 1060 Certified Product Seal. Sensible, latent and total effectiveness along with pressure drop, exhaust air transfer ratio (EATR) and outdoor air correction factor (OACF) rating must be clearly documented with performance tests conducted in accordance with ASHRAE 84 and per the official AHRI laboratory. The enthalpy plate exchanger must withstand pressure differentials of minimum 2.5 kPa 10 inches water gauge. Following UL 1995, the enthalpy plate exchanger must be a UL Recognized Component and bear the UL Certification Mark (tested under UL723 with success by the UL laboratory). The exchanger must have a flame spread rating not more than 25 and a smoke developed rating not more than 50 when tested in accordance with ASTM E84. The membrane must not promote the growth of mold or bacteria and must have successfully passed ASTM G21 testing. Provide heat exchanger core capable of easy removal from the unit. Enthalpy plate exchangers must be cleanable outside of cabinet.

2.15 SUPPLEMENTAL COMPONENTS/SERVICES

2.15.1 Chilled Water Piping

The requirements for chilled, condenser, or dual service water piping and accessories are specified in Section 23 64 26 CHILLED WATER PIPING SYSTEMS

2.15.2 Refrigerant Piping

The requirements for refrigerant piping are specified in Section 23 23 00 REFRIGERANT PIPING.

2.15.3 Water or Steam Heating System Accessories

The requirements for water or steam heating accessories such as expansion tanks and steam traps are specified in Section 23 21 13.00 20 LOW TEMPERATURE WATER (LTW) HEATING SYSTEM.

2.15.4 Condensate Drain Lines

Provide and install condensate drainage for each item of equipment that generates cooling coil condensate in accordance with Section 22 00 00 PLUMBING, GENERAL PURPOSE.

2.15.5 Backflow Preventers

The requirements for backflow preventers are specified in Section 22 00 00 PLUMBING, GENERAL PURPOSE.

2.15.6 Insulation

The requirements for shop and field applied insulation are specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.15.7 Controls

The requirements for controls are specified in Section 23 05 93 TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS and Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing the work.

3.2 INSTALLATION

a. Install materials and equipment in accordance with the requirements of the contract drawings and approved manufacturer's installation instructions. Accomplish installation by workers skilled in this type of work. Perform installation so that there is no degradation of the designed fire ratings of walls, partitions, ceilings, and floors.

b. No installation is permitted to block or otherwise impede access to any existing machine or system. Install all hinged doors to swing open a minimum of 120 degrees. Provide an area in front of all access doors that clears a minimum of 3 feet. In front of all access doors to electrical circuits, clear the area the minimum distance to energized circuits as specified in OSHA Standards, part 1910.333 (Electrical-Safety Related work practices)and an additional 3 feet.

c. Except as otherwise indicated, install emergency switches and alarms in conspicuous locations. Mount all indicators, to include gauges, meters, and alarms in order to be easily visible by people in the area.

3.2.1 Condensate Drain Lines

Provide water seals in the condensate drain from all units . Provide a depth of each seal of 2 inches plus the number of inches, measured in water gauge, of the total static pressure rating of the unit to which the drain is connected. Provide water seals that are constructed of 2 tees and an appropriate U-bend with the open end of each tee plugged. Provide pipe cap or plug cleanouts where indicated. Connect drains indicated to connect to the sanitary waste system using an indirect waste fitting. Insulate air conditioner drain lines as specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

3.2.2 Equipment and Installation

Provide frames and supports for tanks, compressors, pumps, valves, air

handling units, fans, coils, dampers, and other similar items requiring supports. Floor mount or ceiling hang air handling units as indicated. Anchor and fasten as detailed. Set floor-mounted equipment on not less than 6 inch concrete pads or curbs doweled in place unless otherwise indicated assuring mounting height accommodates depth of condensate drain water seal (trap) where applicable. Make concrete foundations heavy enough to minimize the intensity of the vibrations transmitted to the piping, duct work and the surrounding structure, as recommended in writing by the equipment manufacturer. In lieu of a concrete pad foundation, build a concrete pedestal block with isolators placed between the pedestal block and the floor. Make the concrete foundation or concrete pedestal block a mass not less than three times the weight of the components to be supported. Provide the lines connected to the pump mounted on pedestal blocks with flexible connectors. Submit foundation drawings as specified in paragraph DETAIL DRAWINGS. Provide concrete for foundations as specified in Section 03 30 00 CAST-IN-PLACE CONCRETE.

3.2.3 Access Panels

Install access panels for concealed valves, vents, controls, dampers, and items requiring inspection or maintenance of sufficient size, and locate them so that the concealed items are easily serviced and maintained or completely removed and replaced. Provide access panels as specified in Section 08 31 00 ACCESS DOORS AND PANELS.

3.2.4 Flexible Duct

Install pre-insulated flexible duct in accordance with the latest printed instructions of the manufacturer to ensure a vapor tight joint. Provide hangers, when required to suspend the duct, of the type recommended by the duct manufacturer and set at the intervals recommended.

3.2.5 Metal Ductwork

Install according to ANSI/SMACNA 006 unless otherwise indicated. Install duct supports for sheet metal ductwork according to ANSI/SMACNA 006, unless otherwise specified. Do not use friction beam clamps indicated in ANSI/SMACNA 006. Anchor risers on high velocity ducts in the center of the vertical run to allow ends of riser to move due to thermal expansion. Erect supports on the risers that allow free vertical movement of the duct. Attach supports only to structural framing members and concrete slabs. Do not anchor supports to metal decking unless a means is provided and approved for preventing the anchor from puncturing the metal decking. Where supports are required between structural framing members, provide suitable intermediate metal framing. Where C-clamps are used, provide retainer clips.

3.2.6 Kitchen Exhaust Ductwork

3.2.6.1 Ducts Conveying Smoke and Grease Laden Vapors

Provide ducts conveying smoke and grease laden vapors that conform to requirements of NFPA 96. Make seams, joints, penetrations, and duct-to-hood collar connections with a liquid tight continuous external weld. Provide duct material that is a minimum 18 gauge, Type 304L or 316L, stainless steel . Include with duct construction an external perimeter angle sized in accordance with ANSI/SMACNA 006, except place welded joint reinforcement on maximum of 24 inch centers; continuously welded companion angle bolted flanged joints with flexible ceramic cloth

gaskets where indicated; pitched to drain at low points; welded pipe coupling-plug drains at low points; welded fire protection and detergent cleaning penetration; steel framed, stud bolted, and flexible ceramic cloth gasketed cleaning access provisions where indicated. Make angles, pipe couplings, frames, bolts, and other required appurtenances from the same material as that specified for the duct unless indicated otherwise.

3.2.6.2 Exposed Ductwork

Provide exposed ductwork that is fabricated from minimum 18 gauge, Type 304L or 316L, stainless steel with continuously welded joints and seams. Pitch ducts to drain at hoods and low points indicated. Match surface finish to hoods.

3.2.6.3 Concealed Ducts Conveying Moisture Laden Air

Fabricate concealed ducts conveying moisture laden air from minimum 18 gauge, Type 300 series, stainless steel . Continuously weld, braze, or solder joints to be liquid tight. Pitch ducts to drain at points indicated. Make transitions to other metals liquid tight, companion angle bolted and gasketed.

3.2.7 Clothes Dryer Exhaust Ductwork

Clothes dryer exhaust duct work to be installed in accordance with ICC IMC and the dryer manufacturer's installation requirements. For single domestic/residential clothes dryer ducts, dryer duct to be supported at 4 foot intervals and secured in place. The insert end of the duct is to extend into the adjoining duct or fitting in the direction of airflow. Ducts are not be joined with screws or fasteners that protrude more than 1/8 inch into the inside of the duct. For multiple clothes dryers refer to ICC IMC for installation requirements.

3.2.8 Dust Control

To prevent the accumulation of dust, debris and foreign material during construction, perform temporary dust control protection. Protect the distribution system (supply and return) with temporary seal-offs at all inlets and outlets at the end of each day's work. Keep temporary protection in place until system is ready for startup.

3.2.9 Insulation

Provide thickness and application of insulation materials for ductwork, piping, and equipment according to Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS. Externally insulate outdoor air intake ducts and plenums up to the point where the outdoor air reaches the conditioning unit.

3.2.10 Duct Test Holes

Provide holes with closures or threaded holes with plugs in ducts and plenums as indicated or where necessary for the use of pitot tube in balancing the air system. Plug insulated duct at the duct surface, patched over with insulation and then marked to indicate location of test hole if needed for future use.

3.2.11 Power Roof Ventilator Mounting

Provide foamed 1/2 inch thick, closed-cell, flexible elastomer insulation

to cover width of roof curb mounting flange. Where wood nailers are used, predrill holes for fasteners.

3.2.12 Power Transmission Components Adjustment

Test V-belts and sheaves for proper alignment and tension prior to operation and after 72 hours of operation at final speed. Uniformly load belts on drive side to prevent bouncing. Make alignment of direct driven couplings to within 50 percent of manufacturer's maximum allowable range of misalignment.

3.3 EQUIPMENT PADS

Provide equipment pads to the dimensions shown or, if not shown, to conform to the shape of each piece of equipment served with a minimum 3-inch margin around the equipment and supports. Allow equipment bases and foundations, when constructed of concrete or grout, to cure a minimum of 28 calendar days before being loaded.

3.4 CUTTING AND PATCHING

Install work in such a manner and at such time that a minimum of cutting and patching of the building structure is required. Make holes in exposed locations, in or through existing floors, by drilling and smooth by sanding. Use of a jackhammer is permitted only where specifically approved. Make holes through masonry walls to accommodate sleeves with an iron pipe masonry core saw.

3.5 CLEANING

Thoroughly clean surfaces of piping and equipment that have become covered with dirt, plaster, or other material during handling and construction before such surfaces are prepared for final finish painting or are enclosed within the building structure. Before final acceptance, clean mechanical equipment, including piping, ducting, and fixtures, and free from dirt, grease, and finger marks. When the work area is in an occupied space such as office, laboratory or warehouse protect all furniture and equipment from dirt and debris. Incorporate housekeeping for field construction work which leaves all furniture and equipment in the affected area free of construction generated dust and debris; and, all floor surfaces vacuum-swept clean.

3.6 PENETRATIONS

Provide sleeves and prepared openings for duct mains, branches, and other penetrating items, and install during the construction of the surface to be penetrated. Cut sleeves flush with each surface. Place sleeves for round duct 15 inches and smaller. Build framed, prepared openings for round duct larger than 15 inches and square, rectangular or oval ducts. Sleeves and framed openings are also required where grilles, registers, and diffusers are installed at the openings. Provide one inch clearance between penetrating and penetrated surfaces except at grilles, registers, and diffusers. Pack spaces between sleeve or opening and duct or duct insulation with mineral fiber conforming with ASTM C553, Type 1, Class B-2.

3.6.1 Sleeves

Fabricate sleeves, except as otherwise specified or indicated, from 20 gauge thick mill galvanized sheet metal. Refer to design details on the

drawings for sleeves in bearing walls or partitions.

3.6.2 Framed Prepared Openings

Fabricate framed prepared openings from 20 gauge galvanized steel, unless otherwise indicated.

3.6.3 Insulation

Provide duct insulation in accordance with Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS continuous through sleeves and prepared openings except firewall penetrations. Terminate duct insulation at fire dampers and flexible connections. For duct handling air at or below 60 degrees F, provide insulation continuous over the damper collar and retaining angle of fire dampers, which are exposed to unconditioned air.

3.6.4 Closure Collars

Provide closure collars of a minimum 4 inches wide, unless otherwise indicated, for exposed ducts and items on each side of penetrated surface, except where equipment is installed. Install collar tight against the surface and fit snugly around the duct or insulation. Grind sharp edges smooth to prevent damage to penetrating surface. Fabricate collars for round ducts 15 inches in diameter or less from 20 gauge galvanized steel. Fabricate collars for square and rectangular ducts, or round ducts with minimum dimension over 15 inches from 18 gauge galvanized steel. Fabricate collars for square and rectangular ducts with a maximum side of 15 inches or less from 20 gauge galvanized steel. Install collars with fasteners a maximum of 6 inches on center. Attach to collars a minimum of 4 fasteners where the opening is 12 inches in diameter or less, and a minimum of 8 fasteners where the opening is 20 inches in diameter or less.

3.6.5 Firestopping

Where ducts pass through fire-rated walls, fire partitions, and fire rated chase walls, seal the penetration with fire stopping materials as specified in Section 07 84 00 FIRESTOPPING.

3.7 FIELD PAINTING OF MECHANICAL EQUIPMENT

Clean, pretreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except clean to bare metal on metal surfaces subject to temperatures in excess of 120 degrees F. Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Provide aluminum or light gray finish coat.

3.7.1 Temperatures less than 120 degrees F

Immediately after cleaning, apply one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of one mil; and two coats of enamel applied to a minimum dry film thickness of one mil per coat to metal surfaces subject to temperatures less than 120 degrees F.

3.7.2 Temperatures between 120 and 400 degrees F

Apply two coats of 400 degrees F heat-resisting enamel applied to a total minimum thickness of two mils to metal surfaces subject to temperatures between 120 and 400 degrees F.

3.7.3 Temperatures greater than 400 degrees F

Apply two coats of 315 degrees C 600 degrees F heat-resisting paint applied to a total minimum dry film thickness of two mils to metal surfaces subject to temperatures greater than 400 degrees F.

3.7.4 Finish Painting

The requirements for finish painting of items only primed at the factory, and surfaces not specifically noted otherwise, are specified in Section 09 90 00 PAINTS AND COATINGS.

3.8 IDENTIFICATION SYSTEMS

Provide identification tags made of brass, engraved laminated plastic, or engraved anodized aluminum, indicating service and item number on all valves and dampers. Provide tags that are 1-3/8 inch minimum diameter with stamped or engraved markings. Make indentations black for reading clarity. Attach tags to valves with No. 12 AWG 0.0808-inch diameter corrosion-resistant steel wire, copper wire, chrome-plated beaded chain or plastic straps designed for that purpose.

3.8.1 Identification of Hidden Utility Components

Provide labeling for equipment installed above the ceiling that requires periodic inspection or servicing. The labeling must be stick-on adhesive type with black lettering on white or clear background with lettering a minimum of 1/2" in height. For lay-in ceiling applications, locate stick-on on ceiling grid T-Bars closest to equipment such that recommended ceiling tile to be removed for servicing/access is direction above the label. For equipment located above hard ceilings, labeling is to be provided on the provided access door. The operable equipment requiring identification include, valves, dampers.

3.9 DUCTWORK LEAK TESTS

The requirements for ductwork leak tests are specified in Section 23 05 93 TESTING, ADJUSTING AND BALANCING FOR HVAC.

3.10 DAMPER ACCEPTANCE TEST

Submit the proposed schedule, at least 2 weeks prior to the start of test. Perform the damper acceptance test in accordance with NFPA 80. Operate all fire dampers and smoke dampers with the air handling and distribution system operating at maximum air flow conditions, prior to the occupancy of the building to verify that they function properly. Test each fire damper with a fusible link by manually releasing the damper. Visually inspect the mechanism. Reset all fire dampers after acceptance testing.

3.11 TESTING, ADJUSTING, AND BALANCING

The requirements for testing, adjusting, and balancing are specified in

Section 23 05 93 TESTING, ADJUSTING AND BALANCING FOR HVAC. Begin testing, adjusting, and balancing only when the air supply and distribution, including controls, has been completed, with the exception of performance tests.

3.12 PERFORMANCE TESTS

Conduct performance tests as required in Section 23 05 93 Testing, Adjusting and Balancing for HVAC and Section 23 09 00 Instrumentation and Control for HVAC.

3.13 CLEANING AND ADJUSTING

Provide a temporary bypass for water coils to prevent flushing water from passing through coils. Thoroughly clean ducts, plenums, and casing of debris and blow free of small particles of rubbish and dust and then vacuum clean before installing outlet faces. Wipe equipment clean, with no traces of oil, dust, dirt, or paint spots. Temporary filters must be provided and used when any air distribution system is in operation during construction. Provide new filters after all construction dirt has been removed from the building, and the ducts, plenums, casings, and other items specified have been vacuum cleaned. Perform and document that proper "Indoor Air Quality During Construction" procedures have been followed; provide documentation showing that after construction ends, and prior to occupancy, new filters were provided and installed. Maintain system in this clean condition until final acceptance. Properly lubricate bearings with oil or grease as recommended by the manufacturer. Tighten belts to proper tension. Adjust control valves and other miscellaneous equipment requiring adjustment to setting indicated or directed. Adjust fans to the speed indicated by the manufacturer to meet specified conditions. Maintain all equipment installed under the contract until close out documentation is received, the project is completed and the building has been documented as beneficially occupied.

3.14 OPERATION AND MAINTENANCE

3.14.1 Operation and Maintenance Manuals

Submit six manuals at least 2 weeks prior to field training. Submit data complying with the requirements specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA. Submit Data Package 3 for the items/units listed under SD-10 Operation and Maintenance Data

3.14.2 Operation And Maintenance Training

Conduct a training course for the members of the operating staff as designated by the Contracting Officer. Make the training period consist of a total of 16 hours of normal working time and start it after all work specified herein is functionally completed and the Performance Tests have been approved. Conduct field instruction that covers all of the items contained in the Operation and Maintenance Manuals as well as demonstrations of routine maintenance operations. Submit the proposed On-site Training schedule concurrently with the Operation and Maintenance Manuals and at least 14 days prior to conducting the training course.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 52 43.00 20

LOW PRESSURE WATER HEATING BOILERS (UNDER 800,000 BTU/HR OUTPUT)
05/15, CHG 2: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z21.13/CSA 4.9	(2022) Gas-Fired Low Pressure Steam and Hot Water Boilers

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME BPVC SEC IV	(2017) BPVC Section IV-Rules for Construction of Heating Boilers
ASME CSD-1	(2024) Control and Safety Devices for Automatically Fired Boilers

ASTM INTERNATIONAL (ASTM)

ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless

NATIONAL BOARD OF BOILER AND PRESSURE VESSEL INSPECTORS (NBBI)

NBBI NB-23 PART 1	(2023) National Board Inspection Code - Part 1 Installation

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 00001	(2024) Motors and Generators

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 31	(2024; TIA 23-1) Standard for the Installation of Oil-Burning Equipment
NFPA 54	(2024) National Fuel Gas Code
NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 211	(2019) Standard for Chimneys, Fireplaces, Vents, and Solid Fuel-Burning Appliances

UL SOLUTIONS (UL)

UL 296	(2017; Reprint Nov 2022) UL Standard for Safety Oil Burners
UL 726	(1995; Reprint Sep 2024) UL Standard for Safety Oil-Fired Boiler Assemblies
UL 795	(2016; Reprint May 2022) UL Standard for Safety Commercial-Industrial Gas Heating Equipment

1.2 RELATED REQUIREMENTS

Section 23 03 00.00 20 BASIC MECHANICAL MATERIALS AND METHODS BASIC MECHANICAL MATERIALS AND METHODS, applies to this section, with the additions and modifications specified herein.

1.3 DESIGN REQUIREMENTS

Boiler must be suitable for installation in the space shown with ample room for opening doors and cleaning and removal and replacement of tubes. Boiler must have an output as indicated. Boiler must be designed and tested in accordance with ASME BPVC SEC IV, ASME CSD-1, NFPA 54, NFPA 31, NFPA 70 and ANSI Z21.13/CSA 4.9. Boiler must be installed in accordance with NBBI NB-23 PART 1. Paint boiler in accordance with manufacturer's recommendations. Provide a thermostatically controlled three-way mixing valve on boiler suitable for operating conditions of the boiler.

1.3.1 Boiler Installation Requirements

1.3.1.1 Location

Install Boiler(s) and associated hot water pumps in a mechanical room inside the facility in accordance with NBBI NB-23 PART 1. Provide ample clearance around boilers to allow access for inspection, maintenance and repair. Passageways around all sides of boilers must have an unobstructed minimum width of 36 inches or the clearances recommended by the boiler manufacturer whichever is greater.

1.3.1.2 Combustion Air

Provide supply of air for combustion and ventilation. In accordance with NFPA 54, NFPA 211 and manufacturer's installation manual, calculate the amount of combustion air necessary to operate the boiler. Install and locate properly sized combustion air dampers and louvers.

1.3.1.3 Sequence of Operation

Local, manual starting of boilers is required. Remote starting and stopping of the boiler by the HVAC control system is not permitted. This is to ensure that an operator witness the initial firing of the boiler at the beginning of each heating season to verify proper operation of the boiler and to promote proper maintenance.

1.3.2 Detail Drawings

1.3.2.1 Drawings

Show boiler hot water isolation valves, emergency disconnect switch, and complete boiler gas train on the contract drawings.

1.3.2.2 Fuel Train / Wiring Diagram

Submit fuel train and wiring diagram.

1.4 SAFETY STANDARDS

Hot water boilers, burners and supplementary control devices, safety interlocks, or limit controls required under this specification, must meet requirements of the following standards as applicable:

a. Oil-Fired Units: UL 726, NFPA 31, NFPA 70, ASME CSD-1.

b. Gas-Fired Units: ASME CSD-1, NFPA 54, NFPA 70, ANSI Z21.13/CSA 4.9 or UL 795.

c. Combination Gas- and Oil-Fired Units: ASME CSD-1, NFPA 54, NFPA 31, NFPA 70, UL 726, ANSI Z21.13/CSA 4.9, UL 795 or UL 296.

d. All Units: ASME BPVC SEC IV, NFPA 70 and ASME CSD-1.

Controls not covered by the above must have a UL label, UL listing mark, or must be listed in the Factory Mutual Approval Guide.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

Submittals for this Section must be delivered to the project Contracting Officer, who will forward two complete sets of copies to the appropriate approving official for review and approval.

SD-02 Shop Drawings

Fuel Train

Wiring Diagram

SD-03 Product Data

Boilers

Boiler Trim and Control Equipment

Stack, Breeching, and Supports

SD-06 Test Reports

Operational Tests

SD-07 Certificates

Boilers

Boiler Trim and Control Equipment

Boiler manufacturer's certificate of boiler performance including evidence that the burners provided must be a make, model, and type certified and approved by the manufacturer of the boiler being provided.

SD-08 Manufacturer's Instructions

Boilers

Feedwater Treatment Feeder

SD-10 Operation and Maintenance Data

Boilers, Data Package 4

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

SD-11 Closeout Submittals

Posted Operating Instructions for Heating Water Boilers

PART 2 PRODUCTS

2.1 BOILERS

Provide hot water heating boiler complete with firing equipment, combustion chamber, insulation with steel jacket, safety and operating controls, integral electrical wiring and other appurtenances, to make the boiler a complete, self-contained, fully-automatic unit, ready for service upon completion of utility connections. Gas fired boilers greater than 300,000 Btuh input must have a thermal efficiency of at least 90 percent when fired at the maximum and minimum capacities which are provided and allowed by the controls.

2.1.1 General Requirements

Design, construction, installation, testing, and operation of boiler and appurtenances must comply with NBBI NB-23 PART 1, ASME BPVC SEC IV, ASME CSD-1, NFPA 54, NFPA 31, ANSI Z21.13/CSA 4.9, and the manufacturer's instructions.

2.1.2 Features

Provide a commercial, full condensing type boiler, with a combustion system consisting of gas valve and combustion blower designed to work in concert and have sealed combustion chamber. The boiler must be capable of a 5:1 turndown ratio to provide maximum system flexibility. Provide direct spark ignition. The boiler must be capable of low gas pressure operation and low NOx operation.

2.1.3 Construction

Construct the boiler with a heavy gauge steel outer jacket assembly, primed, and pre-painted on both sides. The outer jacket assembly must be completely independent of the combustion chamber.

2.1.4 Heat Exchanger

Construct the heat exchanger(s) of 316L stainless steel and be designed for a 160 psi working pressure in accordance with ASME BPVC SEC IV and bear the ASME "H" stamp. The heat exchanger shall be of gasketless design and shall be designed to drain condensation from the heat exchanger assembly. Provide a burner/flame observation port.

2.1.5 Controls

Provide each hot water heating boiler with a digital operating control system with multi-color graphic LCD display and include a BACnet control interface to allow the boiler to be connected to the building DDC system as specified in specification section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS. Provide a control system that includes, as a minimum, the following features:

a. Sequencer for controlling the boilers for "Lead Lag" and "Efficiency Optimization".

b. System pump control for controling a variable speed boiler pump to keep a constant delta T at all modulation rates.

2.2 BOILER TRIM AND CONTROL EQUIPMENT

Provide in accordance with ASME CSD-1 and ASME BPVC SEC IV and additional requirements specified below.

2.2.1 Emergency Disconnect Switch

Provide and locate on wall outside boiler room entrance or just inside door, when boiler room door is on building exterior as required by ASME CSD-1 to allow rapid and complete shutdown of the boiler in the event of an emergency. Emergency switch must be a pushbutton type safety switch as indicated on plans.

2.2.2 Relief Valves

Provide relieving capacity for the full output of boiler installed. Safety relief-valve piping must conform to ASTM A53/A53M, schedule 40 steel pipe and be piped full-size to a floor drain .

2.2.3 Pressure and Altitude Gage or Combination Pressure/Altitude Gage

Provide one located on supply water piping and one on return water piping.

2.2.4 Thermometer

Provide thermometer with a scale equivalent to 1.5 times outlet water temperature. Provide one located on supply water piping and one on return water piping.

2.2.5 Drain Tapping

Provide drain valve and piping to a floor drain .

2.2.6 Make-up Water Station

2.2.6.1 Pressure Reducing Station

Provide a water pressure-reducing valve and relief valve, or a combination of the two in the makeup water line to the boiler to maintain a water pressure of 12 psig in the hot water system. Provide a 3/4 inch globe valve by-pass around this valve.

2.2.6.2 Backflow Preventers

Section 22 00 00 PLUMBING, GENERAL PURPOSE. Locate upstream of by-pass.

2.2.7 Feedwater Treatment Feeder

Provide floor mounted, Type II - Shot-Type Feeder (manual, intermittent feed), as indicated for use with pressures up to 200 psig maximum.

2.2.8 Combustion Regulator

Provide adjustable temperature, thermostatic immersion type that must limit boiler water temperature to a maximum of 250 degrees F. Control must actuate burner through an electric relay system to maintain boiler water temperature within normal prescribed limits at loads within rated capacity of boiler.

2.2.9 Air Vent Valve

Provide with screwed connection, stainless steel disk, and stainless steel seats to vent entrapped air.

2.2.10 High Temperature Limit Switch

Provide adjustable immersible aquastat type with a temperature setting above that of the combustion regulator and below that of the lowest relief valve setting. Aquastat must function to cause a safety shutdown by closing fuel valves, and shutting down burner equipment , activating a red indicating light, and sounding an alarm in the event that boiler water temperature rises to the high temperature limit setting. A safety shutdown due to high temperature must require manual reset before operation can resume and prevent recycling of burner equipment. Pre-set high temperature limit devices that cannot be easily tested are not allowed.

2.2.11 Low Water Level Cutoff Switch

Low water level cutoff must cause a safety shutdown by closing fuel valves, and shutting down burner equipment , activating a red indicating light, and sounding an alarm in the event that water level drops below the lowest safe permissible water level established by the boiler manufacturer and ASME BPVC SEC IV. A safety shutdown due to low water must require manual reset before operation can resume and prevent recycling of burner equipment.

2.2.12 Boiler Safety Control Circuits

Provide boiler safety control circuits, including control circuits for burner and draft fan, must be single-phase, two-wire one-side grounded, and not over 120 volts. Provide safety control switching in ungrounded conductors. Provide overcurrent protection. In addition to circuit grounds, ground metal parts which do not carry current to a grounding conductor.

2.2.13 Indicating Lights

Each safety interlock requiring a manual reset must have an individually labeled red indicating light. Non-recycling control interlocks must have the reset located on the control itself. Red indicating lights on the control panel may be omitted if the burner combustion control system has a Keyboard Display Module installed that will identify the lockout information required in Item c. below. Indicating lights must have colors as follows:

a. Amber: Ignition on

b. Green: Main fuel safety shut-off valves open

c. Red (One for Each): Safety lockout, flame failure, low water level, and high temperature

d. Blue: Draft

2.2.14 Alarm Bell

Provide alarm bell, electrically operated, with a manual disconnect switch. Disconnect switch must be type and wired so that switching off alarm following a safety shutdown will not prevent alarm from sounding again upon recurrence of a subsequent safety shutdown condition.

2.2.15 Post-Combustion Purge

Provide controls and wiring necessary to ensure operation of draft fan for a period of not less than 15 seconds or of sufficient duration to provide four complete air changes in the boiler combustion chamber (whichever is greater) following shutdown of burner upon satisfaction of heat demand and in accordance with ASME CSD-1 . Upon completion of post-combustion purge period, draft fan must automatically shutdown until next restart.

2.2.16 Draft

Comply with boiler manufacturer's recommendations.

2.2.17 Stack, Breeching, and Supports

Provide each boiler with its own dedicated direct vent for both the intake and combustion air. Concentric vents are acceptable but must be done in accordance with the manufacturer's written instructions. The piping must be CPVC or Polypropylene with sealed vent material. The total combined length of the combined exhaust venting length shall not exceed 100 equivalent feet. The total combined length of the combined air intake length shall not exceed 100 equivalent feet.

2.2.18 Stack Thermometer

Provide flue gas dial type thermometer with scale calibrated from 150 to 750 degrees F and mounted in flue gas outlet.

2.3 ELECTRIC MOTORS

Electric motors must meet requirements of NEMA MG 00001. Motors less than 1 hp must meet NEMA High Efficiency requirements. Motors 1 hp and larger must meet NEMA Premium Efficiency requirements. Motors which are an integral part of the packaged boiler system must be the highest efficiency available by the manufacturer of the packaged boiler. Motors must be variable speed.

PART 3 EXECUTION

3.1 EQUIPMENT INSTALLATION

Install equipment in accordance with manufacturer's installation instructions and NBBI NB-23 PART 1. Grout equipment mounted on concrete foundations before installing piping. Install piping in such a manner as not to place a strain on equipment. Do not bolt flanged joints tight unless they match. Grade, anchor, guide, and support piping without low pockets. Feedwater treatment feeders must be mounted so that the top of the feeder is no higher than 48 inches above the finished floor.

3.2 EQUIPMENT FOUNDATIONS

Locate equipment foundations as indicated, designed, and made of sufficient size and weight to preclude shifting of equipment under operating conditions or under abnormal conditions that could be imposed upon the equipment. Foundations must meet requirements of the equipment manufacturer. Concrete and grout must conform to Section 03 30 00 CAST-IN-PLACE CONCRETE.

3.3 FIELD QUALITY CONTROL

Perform and furnish everything required for inspections and tests as specified herein to demonstrate that boiler and auxiliary equipment, as installed, are in compliance with contract requirements. Start-up and operate the system. During this time, clean strainers until no further accumulation of foreign material occurs. Exercise care to minimize loss of water when strainers are cleaned. Adjust safety and automatic control instruments as necessary to place them in proper operation and sequence. Test instrumentation must be calibrated and have full scale readings from 1.5 to 2 times test values.

3.3.1 Operational Tests

Furnish the services of an engineer or technician approved by the boiler manufacturer of installation, startup, operational and safety testing. This person must remain on the job until each boiler has been successfully operated. Furnish and perform everything required for inspections and tests of the boiler and auxiliary equipment. Test instrumentation must be calibrated and have full-scale reading from 1.5 to 2 times test values. Demonstrate proper operability of combustion control, flame safeguard control and safety interlocks. Provide a detailed description of all boiler startup and operational tests in the Commissioning Plan.

3.3.1.1 Preliminary Operational Test

Operate the boilers continuously for a period of at least 8 hours to demonstrate proper operability of the combustion control, flame safeguard control, and safety interlocks.

3.3.1.2 Acceptance Operational Test and Inspection

Prior to requesting an acceptance test, conduct a satisfactory operational test for at least 8 hours, and provide a certified statement that the equipment is installed per all requirements of this guide. Contracting Officer, upon receipt of the notice from the Contractor, will request a boiler inspection by a Naval Facilities Engineering and Expeditionary Warfare Center (EXWC) NAVFAC boiler inspector. Fifteen days advance notice is required for scheduling inspector to conduct acceptance operational test and inspection.

3.4 SCHEDULE

Some metric measurements in this section are based on mathematical conversion of inch-pound measurements, and not on metric measurements commonly agreed on by the manufacturers or other parties. The inch-pound and metric measurements shown are as follows:

Products	Inch-Pound	Metric
a. Alarm Bell Diameter	= 4 inches	= 100 mm
b. Stack Thermometer Scale Range	= 150-750 degrees F	= 66-399 degrees C

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 64 10

WATER CHILLERS, VAPOR COMPRESSION TYPE
05/25

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI 550/590 I-P	(2023) Performance Rating Of Water-Chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle
AHRI 580	(2014; R2022) Performance Rating of Non-condensable Gas Purge Equipment for Use with Low Pressure Centrifugal Liquid Chillers

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ANSI/ASHRAE 15 & 34	(2022) ASHRAE Standard 15-Safety Standard for Refrigeration Systems and ANSI/ASHRAE Standard 34-Designation and Safety Classification of Refrigerants

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME BPVC SEC VIII D1	(2023) BPVC Section VIII-Rules for Construction of Pressure Vessels Division 1

AMERICAN WELDING SOCIETY (AWS)

AWS Z49.1	(2021) Safety in Welding, Cutting and Allied Processes

ASTM INTERNATIONAL (ASTM)

ASTM A307	(2023) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM D520	(2025) Standard Specification for Zinc Dust Pigment
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

ASTM F104 (2011; R 2020) Standard Classification System for Nonmetallic Gasket Materials

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 00001 (2024) Motors and Generators

NEMA MG 10009 (2022) Energy Management Guide for Selection and Use of Single-Phase Motors

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 82 Protection of Stratospheric Ozone

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Verification of Dimensions

System Performance Tests

Demonstrations

Refrigerant

Water Chiller - Field Acceptance Test Plan

Scroll Type Water Chiller

SD-06 Test Reports

Field Acceptance Testing

Water Chiller - Field Acceptance Test Report

Factory Tests

System Performance Tests

Factory Test Schedule; G

Startup Report

SD-07 Certificates

Refrigeration System; G

Refrigeration Technician Certification

SD-08 Manufacturer's Instructions

Water Chiller - Installation Instructions; G

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G

Training Course Schedule; G

SD-11 Closeout Submittals

Indoor Air Quality During Construction; S

1.3 CERTIFICATIONS

1.3.1 Refrigeration Technician Certification

All technicians working on equipment that contain Class I or II refrigerants must be certified as a Section 608 Technician to meet requirements in 40 CFR 82, Subpart F. Provide copies of technician certifications to the Contracting Officer at least 14 calendar days prior to work on any equipment containing these refrigerants.

1.4 SAFETY REQUIREMENTS

Exposed moving parts, parts that produce high operating temperature, parts which may be electrically energized, and parts that may be a hazard to operating personnel must be insulated, fully enclosed, guarded, or fitted with other types of safety devices. Install safety devices so that proper operation of equipment is not impaired. Welding and cutting safety requirements must be in accordance with AWS Z49.1.

1.5 DELIVERY, STORAGE, AND HANDLING

Protect stored items from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Proper protection and care of all material both before and during installation is the Contractor's responsibility. Any materials found to be damaged must be replaced at the Contractor's expense. During installation, piping and similar openings must be capped to keep out dirt and other foreign matter.

1.6 PROJECT REQUIREMENTS

1.6.1 Verification of Dimensions

The Contractor must become familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

PART 2 PRODUCTS

2.1 STANDARD COMMERCIAL PRODUCTS

Materials and equipment must be standard Commercial cataloged products of a manufacturer regularly engaged in the manufacturing of such products, which are of a similar material, design and workmanship. These products must have a two year record of satisfactory field service prior to bid opening. The two year record of service must include applications of equipment and materials under similar circumstances and of similar size. Products having less than a two year record of satisfactory field service is acceptable if a certified record of satisfactory field service for not less than 6000 hours can be shown. The 6000 hour service record must not

include any manufacturer's prototype or factory testing. Satisfactory field service must have been completed by a product that has been, and presently is being sold or offered for sale on the commercial market through the following copyrighted means: advertisements, manufacturer's catalogs, or brochures.

2.2 MANUFACTURER'S STANDARD NAMEPLATES

Major equipment including chillers, compressors, compressor drivers, condensers, water coolers, receivers, refrigerant leak detectors, heat exchanges, fans, and motors must have the manufacturer's name, address, type or style, model or serial number, and catalog number on a plate secured to the item of equipment. Plates must be durable and legible throughout equipment life. Fix plates in prominent locations with nonferrous screws or bolts.

Nameplates are required on major components if the manufacturer needs to provide specific engineering and manufacturing information pertaining to the particular component. Should replacement of this component be required, nameplate information must insure correct operation of the unit after replacement of this component.

2.3 ELECTRICAL WORK

a. Provide motors, controllers, integral disconnects, contactors, and controls with their respective pieces of equipment, except controllers indicated as part of motor control centers. Provide electrical equipment, including motors and wiring, as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Manual or automatic control and protective or signal devices required for the operation specified and control wiring required for controls and devices specified, but not shown, must be provided. For packaged equipment, the manufacturer must provide controllers including the required monitors and timed restart.

b. For single-phase motors, provide high-efficiency type, fractional-horsepower alternating-current motors, electronically commutated motors, including motors that are part of a system, in accordance with NEMA MG 10009.

c. For polyphase motors, provide squirrel-cage medium induction motors, including motors that are part of a system, and that meet the efficiency ratings for premium efficiency motors in accordance with NEMA MG 00001.

d. Provide motors in accordance with NEMA MG 00001 and of sufficient size to drive the load at the specified capacity without exceeding the nameplate rating of the motor. Motors must be rated for continuous duty with the enclosure specified. Motor duty requirements must allow for maximum frequency start-stop operation and minimum encountered interval between start and stop. Motor torque must be capable of accelerating the connected load within 20 seconds with 80 percent of the rated voltage maintained at motor terminals during one starting period. Provide motor starters complete with thermal overload protection and other necessary appurtenances. Motor enclosure type may be either TEAO or TEFC.

e. Use adjustable frequency drives for all variable-speed motor applications. Provide variable frequency drives for motors as

specified in Section 26 29 23 ADJUSTABLE SPEED DRIVE (ASD) SYSTEMS UNDER 600 VOLTS.

f. Provide inverter duty premium efficiency motors for use with variable frequency drives.

g. Provide electrical heat trace system in accordance with Section 23 64 26 CHILLED WATER PIPING SYSTEMS and per manufacturer installation instructions. Provide caution labels on insulation exterior aluminum jacket. Provide a 120v dedicated electrical circuit to supply power to the heat trace system for chiller piping, components and accessories. Electrical jumper from equipment connection is not allowed.

h. Provide one (1) 120v electrical GFICI receptacle for future service and maintenance with 25 feet of the chiller location.

2.4 SELF-CONTAINED WATER CHILLER, VAPOR COMPRESSION TYPE

Unless necessary for delivery purposes, units must be assembled, leak-tested, charged (refrigerant and oil), and adjusted at the factory. In lieu of delivery constraints, a chiller may be assembled, leak-tested, charged (refrigerant and oil), and adjusted at the job site by a factory representative. Unit components delivered separately must be sealed and charged with a nitrogen holding charge. Unit assembly must be completed in strict accordance with manufacturer's recommendations. Parts weighing 50 pounds or more which must be removed for inspection, cleaning, or repair, such as motors, gear boxes, cylinder heads, casing tops, condenser, and cooler heads, must have lifting eyes or lugs. Chiller must include all customary auxiliaries deemed necessary by the manufacturer for safe, controlled, automatic operation of the equipment. Provide chiller with a single point wiring connection for incoming power supply, unless noted otherwise on the drawings. Chiller must operate within capacity range and speed recommended by the manufacturer. Chiller must operate at partial load conditions without increased vibration over normal vibration at full load, and must be capable of continuous operation down to the specified minimum capacity.

2.4.1 Scroll Type Water Chiller

Chiller must be certified for performance per AHRI 550/590 I-P. If specified performance is outside of the Application Rating Conditions of AHRI 550/590 I-P, Table 2 then the chiller's performance must be rated in accordance with AHRI 550/590 I-P. In addition, project specific performance data must be based on the project site elevation above sea level, and clearly noted as such on the submittal. Chiller must conform to ANSI/ASHRAE 15 & 34. As a minimum, chiller must include the following components as defined in paragraph CHILLER COMPONENTS.

a. Refrigerant and oil

b. Structural base

c. Chiller refrigerant circuit per compressor

d. Controls package

e. Scroll, reciprocating, or rotary screw compressor

f. Compressor driver, electric motor

g. Compressor driver connection

h. Water cooler (evaporator)

i. Air-cooled condenser coil

j. Receiver

2.5 CHILLER COMPONENTS

2.5.1 Refrigerant

Refrigerants must be one of the fluorocarbon gases. Refrigerants must have number designations and safety classifications in accordance with ANSI/ASHRAE 15 & 34. CFC-based refrigerants are prohibited. Refrigerants must have an Ozone Depletion Potential (ODP) no greater than 0.0 and a maximum Global Warming Potential (GWP) of 700. Provide SDS sheets for all refrigerants.

2.5.2 Structural Base

Chiller and individual chiller components must be provided with a factory-mounted structural steel base (welded or bolted) or support legs. Chiller and individual chiller components must be isolated from the building structure by means of molded neoprene isolation pads. vibration isolators with published load ratings. Vibration isolators must have isolation characteristics as recommended by the manufacturer for the unit supplied and the service intended.

2.5.3 Chiller Refrigerant Circuit

Chiller refrigerant circuit must be completely piped and factory leak tested in accordance with ANSI/ASHRAE 15 & 34. For multicompressor units, not less than two independent refrigerant circuits must be provided. Circuit must include as a minimum a combination filter and drier, combination sight glass and moisture indicator, an electronic or thermostatic expansion valve with external equalizer or float valve, charging ports, compressor service valves for field-serviceable compressors, and superheat adjustment.

2.5.4 Controls Package

Provide chillers with a complete factory-mounted, microprocessor based operating and safety control system. Controls package must contain as a minimum a digital display, an on-auto-off switch, variable frequency motor controller, disconnect switches, power wiring, and control wiring. Controls package must provide operating controls, monitoring capabilities, programmable setpoints, safety controls, and BAS interfaces as defined below.

2.5.4.1 Operating Controls

Chiller must be provided with the following adjustable operating controls as a minimum.

a. Leaving chilled water temperature control

b. Adjustable timer or automated controls to prevent a compressor from short cycling

c. Automatic lead/lag controls (adjustable) for multi-compressor units

d. Load limiting

e. System capacity control to adjust the unit capacity in accordance with the system load and the programmable setpoints. Controls must automatically re-cycle the chiller on power interruption.

f. Startup and head pressure controls for air-cooled condensers to allow system operation at all ambient temperatures down to 0 degrees F.

g. Fan sequencing for air-cooled condenser

2.5.4.2 Monitoring Capabilities

During normal operations, the control system must be capable of monitoring and displaying the following operating parameters. Access and operation of display must not require opening or removing any panels or doors.

a. Entering and leaving chilled water temperatures

b. Chilled water flow

c. Entering and leaving condenser water pressure

d. Self diagnostic

e. Operation status

f. Operating hours

g. Number of starts

h. Compressor status (on or off)

i. Compressor load (percent)

j. Refrigerant discharge and suction pressures

k. Magnetic bearing levitation status (if applicable)

l. Magnetic bearing temperatures (if applicable)

m. Oil pressure (if applicable)

2.5.4.3 Configurable Setpoints

The control system must be capable of being configured directly at the unit's interface panel. No parameters may be capable of being changed without first entering a security access code. The programmable setpoints must include the following as a minimum:

a. Leaving Chilled Water Temperature

b. Time Clock/Calendar Date

2.5.4.4 Safety Controls with Manual Reset

Chiller must be provided with the following safety controls which automatically shutdown the chiller and which require manual reset.

a. Low chilled water temperature protection

b. High condenser refrigerant discharge pressure protection

c. Low evaporator pressure protection

d. Chilled water flow detection

e. High motor winding temperature protection

f. Low oil flow protection (if applicable)

g. Magnetic bearing controller (MBC), Internal fault (if applicable)

h. MBC, High bearing temperature (if applicable)

i. MBC, Communication fault (if applicable)

j. MBC, Power supply fault (if applicable)

k. Motor current overload and phase loss protection

2.5.4.5 Safety Controls with Automatic Reset

Chiller must be provided with the following safety controls which automatically shutdown the chiller and which provide automatic reset.

a. Over/under voltage protection

b. Chilled water flow interlock

c. MBC, Vibration (if applicable)

d. MBC, No levitation (if applicable)

e. Phase reversal protection

2.5.4.6 Remote Alarm

During the initiation of a safety shutdown, a chiller's control system must be capable of activating a remote alarm bell. In coordination with the chiller, the Contractor must provide an alarm circuit (including transformer if applicable) and a minimum 4 inch diameter alarm bell. Alarm circuit must activate bell in the event of machine shutdown due to the chiller's monitoring of safety controls. The alarm bell must not sound for a chiller that uses low-pressure cutout as an operating control.

2.5.4.7 Utility Monitoring and Control System Interface

Provide a Utility Monitoring and Control System (UMCS) interface meeting the requirements of Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC and the requirements of Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS. The interface must provide

all system operating conditions, capacity controls, and safety shutdown conditions as network points. In addition, the following points must be overridable via the network interface:

a. Unit Start/Stop

b. Leaving Chilled Water Temperature Setpoint

2.5.5 Compressor(s)

2.5.5.1 Scroll Compressor(s)

Compressors must be of the hermetically sealed design. Compressors must be mounted on vibration isolators to minimize vibration and noise. Rotating parts must be statically and dynamically balanced at the factory to minimize vibration. Lubrication system must be centrifugal pump type equipped with a means for determining oil level and an oil charging valve. Crankcase oil heater must be provided. Provide continuous compressor unloading to 10 percent of full-load capacity by way of variable speed compressor motor controller or variable unloading of the scroll.

2.5.6 Compressor Driver, Electric Motor

Components such as motors, starters, variable speed drives, and wiring must be in accordance with paragraph ELECTRICAL WORK. Variable frequency drive must be unit mounted as indicated with variable frequency drive type, wiring, and accessories coordinated with the chiller manufacturer.

2.5.7 Compressor Driver Connections

Each machine driven through speed-increasing gears must be so designed as to assure self-alignment, interchangeable parts, proper lubrication system, and minimum unbalanced forces. Bearings must be of the sleeve or roller type. Gear cases must be oil tight. Shaft extensions must be provided with seals to retain oil and exclude all dust.

2.5.8 Water Cooler (Evaporator)

Cooler must be of the shell-and-coil or shell-and-tube type design. Cooler shell must be constructed of seamless or welded steel. Coil bundles must be totally removable and arranged to drain completely. Tubes must be seamless copper, plain, integrally finned with smooth bore or integrally finned with enhanced bore. Each tube must be individually replaceable. Tubes must be installed into carbon mild steel tube sheets by rolling. Tube baffles must be properly spaced to provide adequate tube support and cross flow. Performance must be based on a water velocity not less than 3 fps nor more than 12 fps and a fouling factor per AHRI 550/590 I-P.

Brazed plate heat exchanger must be constructed of 304 or 316 stainless steel, designed to a refrigerant-side working pressure of 430 psig and a waterside working pressure of 150 psig. Evaporator must be factory tested at 1.1 times maximum allowable refrigerant side working pressure and 1.5 times maximum allowable water side working pressure. Provide cooler heaters to protect the evaporator to an ambient of minus 20 degrees F. Provide cooler with factory-installed flow switches. All water connections must use either flanged or grooved-pipe connections. Factory insulate all cold surfaces.

2.5.9 Air-Cooled Condenser Coil

Condenser coil must be of the extended-surface fin-and-tube type and must be constructed of seamless copper tubes with compatible aluminum fins. Fins must be soldered or mechanically bonded to the tubes and installed in a metal casing. Coils must be circuited and sized for a minimum of 5 degrees F subcooling and full pump-down capacity. Coil must be factory leak and pressure tested after assembly in accordance with ANSI/ASHRAE 15 & 34.

Coil must be entirely coated in accordance with the requirements of paragraph COIL CORROSION PROTECTION.

2.5.10 Receivers

Receiver must bear a stamp certifying compliance with ASME BPVC SEC VIII D1 and must meet the requirements of ANSI/ASHRAE 15 & 34. Inner surfaces must be thoroughly cleaned by sandblasting or other approved means. Each receiver must have a storage capacity not less than 20 percent in excess of that required for the fully-charged system. Each receiver must be equipped with inlet, outlet drop pipe, drain plug, purging valve, relief valves of capacity and setting required by ANSI/ASHRAE 15 & 34, and two bull's eye liquid-level sight glasses. Sight glasses must be in the same vertical plane, 90 degrees apart, perpendicular to the axis of the receiver, and not over 3 inches horizontally from the drop pipe measured along the axis of the receiver. In lieu of bull's eye sight glass, external gauge glass with metal glass guard and automatic closing stop valves may be provided.

2.5.11 Chiller Purge System

Chillers which operate at pressures below atmospheric pressure must be provided with a purge system. Purge system must automatically remove air, water vapor, and non-condensible gases from the chiller's refrigerant while keeping refrigerant emissions below requirements of ASHRAE Std 147. Purge units must be certified per AHRI 580. Purge system must condense, separate, and return all refrigerant back to the chiller. An oil separator must be provided with the purge system if required by the manufacturer. Purge system must not discharge to occupied areas, or create a potential hazard to personnel. Purge system must include a purge pressure gauge, number of starts counter, and an elapsed time meter. Purge system must include lights or an alarm which indicate excessive purge or an abnormal air leakage into chiller.

2.6 ACCESSORIES

2.6.1 Refrigerant Relief Valve/Rupture Disc Assembly

The assembly must be a combination pressure relief valve and rupture disc designed for refrigerant usage. The assembly must be in accordance with ASME BPVC SEC VIII D1 and ANSI/ASHRAE 15 & 34. The assembly must be provided with a pressure gauge assembly that provides local indication if a rupture disc is broken. Rupture disc must be the non-fragmenting type.

2.6.2 Refrigerant Signs

Refrigerant signs must be a medium-weight aluminum type with a baked enamel finish. Signs must be suitable for indoor or outdoor service.

Signs must have a white background with red letters not less than 0.5 inches in height.

2.6.2.1 Installation Identification

Each new refrigerating system must be provided with a refrigerant sign which indicates the following as a minimum:

a. Contractor's name.

b. Refrigerant number and amount of refrigerant.

c. The lubricant identity and amount.

d. Field test pressure applied.

2.6.2.2 Controls and Piping Identification

Refrigerant systems containing more than 110 lb of refrigerant must be provided with refrigerant signs which designate the following as a minimum:

a. Valves or switches for controlling the refrigerant flow and the refrigerant compressor(s).

b. Pressure limiting device(s).

2.6.3 Gaskets

Gaskets must conform to ASTM F104 - classification for compressed sheet with nitrile binder and acrylic fibers for maximum 700 degrees F service.

2.6.4 Bolts and Nuts

Bolts and nuts, except as required for piping applications, must be in accordance with ASTM A307 and rated for prolonged exposure to elements. The bolt head must be marked to identify the manufacturer and the standard with which the bolt complies in accordance with ASTM A307.

2.7 FABRICATION

2.7.1 Factory Coating

Unless otherwise specified, equipment and component items, when fabricated from ferrous metal, must be factory finished with the manufacturer's standard finish, except that items located outside of buildings must have weather resistant finishes that withstands a minimum of 3,000 hours exposure to the salt spray test specified in ASTM B117 using a 5 percent sodium chloride solution. Immediately after completion of the test, the specimen must show no signs of blistering, wrinkling, cracking, or loss of adhesion and no sign of rust creepage beyond 1/8 inch on either side of the scratch mark. Cut edges of galvanized surfaces where hot-dip galvanized sheet steel is used must be coated with a zinc-rich coating conforming to ASTM D520, Type I.

2.7.2 Factory Applied Insulation

Chiller must be provided with factory installed insulation on surfaces subject to sweating including the water cooler, suction line piping, economizer, and cooling lines. Insulation on heads of coolers may be

field applied, however it must be installed to provide easy removal and replacement of heads without damage to the insulation. Where motors are the gas-cooled type, factory installed insulation must be provided on the cold-gas inlet connection to the motor per manufacturer's standard practice. Factory insulated items installed outdoors are not required to be fire-rated. As a minimum, factory insulated items installed indoors must have a flame spread index no higher than 75 and a smoke developed index no higher than 150. Factory insulated items (no jacket) installed indoors and which are located in air plenums, in ceiling spaces, and in attic spaces must have a flame spread index no higher than 25 and a smoke developed index no higher than 50. Flame spread and smoke developed indexes must be determined by ASTM E84. Insulation must be tested in the same density and installed thickness as the material to be used in the actual construction. Material supplied by a manufacturer with a jacket must be tested as a composite material. Jackets, facings, and adhesives must have a flame spread index no higher than 25 and a smoke developed index no higher than 50 when tested in accordance with ASTM E84.

2.7.3 Coil Corrosion Protection

Provide coil with a uniformly applied epoxy electrodeposition phenolic vinyl type coating to all coil surface areas without material bridging between fins. Submit product data on the type coating selected, the coating thickness, the application process used, the estimated heat transfer loss of the coil, and verification of conformance with the salt spray test requirement. Coating must be applied at either the coil or coating manufacturer's factory. Coating process must ensure complete coil encapsulation. Coating must be capable of withstanding a minimum 6,000 hours exposure to the salt spray test specified in ASTM B117 using a 5 percent sodium chloride solution.

2.8 FACTORY TESTS

2.8.1 Chiller Performance Test

The Contractor and proposed chiller manufacturer must be responsible for performing the chiller factory test to validate the specified full load capacity, full load EER, and IPLV in accordance with AHRI 550/590 I-P except as indicated. The Contractor and chiller manufacturer must provide to the Government a certified chiller factory test report in accordance with AHRI 550/590 I-P to confirm that the chiller performs as specified. Tests must be conducted in an AHRI certified test facility in conformance with AHRI 550/590 I-P procedures and tolerances, except as indicated. At a minimum, chiller capacity must be validated to meet the scheduled requirements indicated on the drawings. Tolerance or deviation must be in strict accordance with AHRI 550/590 I-P. Stable operation at minimum load of 10 percent of total capacity must be demonstrated during the factory test.

2.8.1.1 Temperature Adjustments

Temperature adjustments must adhere to AHRI 550/590 I-P to adjust from the design fouling factor to the clean tube condition. Test temperature adjustments must be verified prior to testing by the manufacturer. There must be no exceptions to conducting the test with clean tubes with the temperature adjustments per AHRI 550/590 I-P. The manufacturer must clean the tubes prior to testing to obtain a test fouling factor of 0.0000.

2.8.1.2 Test Instrumentation

The factory test instrumentation must be per AHRI 550/590 I-P and the calibration must be traceable to the National Institute of Standards and Technology.

2.8.1.3 Equipment Adjustments

If the equipment fails to perform within allowable tolerances, the manufacturer must be allowed to make necessary revisions to his equipment and retest as required. The manufacturer must assume all expenses incurred by the Government to witness the retest.

2.9 SUPPLEMENTAL COMPONENTS/SERVICES

2.9.1 Chilled and Condenser Water Piping and Accessories

Chilled and condenser water piping and accessories must be provided and installed in accordance with Section 23 64 26 CHILLED WATER PIPING SYSTEMS.

2.9.2 Temperature Controls

Chiller control packages must be fully coordinated with and integrated into the temperature control system indicated in Section 23 30 00 HVAC AIR DISTRIBUTION and Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC and Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS.

PART 3 EXECUTION

3.1 INSTALLATION

Installation of water chiller systems including materials, installation, workmanship, fabrication, assembly, erection, examination, inspection, and testing must be in accordance with the manufacturer's written installation instructions, including the following:

(1) Water chiller - installation instructions

3.1.1 Installation Instructions

Provide manufacturer's standard catalog data, at least 5 weeks prior to the purchase or installation of a particular component, highlighted to show features such as materials, dimensions, options, performance and efficiency. Data must include manufacturer's recommended installation instructions, and start-up procedures and checklists. Data must be adequate to demonstrate compliance with contract requirements.

All recommendations stated in the installation instructions or other similar manufacturer's published literature must be considered mandatory and part of the contract documents. Any discrepancies to the engineered drawings and specifications must be brought to the attention of the COR.

3.1.2 Vibration Isolation

If vibration isolation is specified for a unit, vibration isolator literature must be included containing catalog cuts and certification that the isolation characteristics of the isolators provided meet the manufacturer's recommendations.

3.1.3 Verification of Dimensions

Provide a letter including the date the site was visited, conformation of existing conditions, and any discrepancies found.

3.1.4 System Performance Test Schedules

Provide a schedule, at least 2 weeks prior to the start of related testing, for the system performance tests. The schedules must identify the proposed date, time, and location for each test.

3.1.5 Certificates

Where the system, components, or equipment are specified to comply with requirements of AGA, NFPA, AHRI, ANSI/ASHRAE, ASME, or UL, proof of such compliance must be provided. The label or listing of the specified agency must be acceptable evidence. In lieu of the label or listing, a written certificate from an approved, nationally recognized testing organization equipped to perform such services, stating that the items have been tested and conform to the requirements and testing methods of the specified agency may be submitted. When performance requirements of this project's drawings and specifications vary from standard AHRI rating conditions, computer printouts, catalog, or other application data certified by AHRI or a nationally recognized laboratory as listed in this Certificates section must be included. If AHRI does not have a current certification program that encompasses such application data, the manufacturer may self certify that his application data complies with project performance requirements in accordance with the specified test standards.

3.1.6 Operation and Maintenance Manuals

Provide six complete copies of an operation manual in bound 8 1/2 by 11 inch booklets listing step-by-step procedures required for system startup, operation, abnormal shutdown, emergency shutdown, and normal shutdown at least 4 weeks prior to the first training course. The booklets must include the manufacturer's name, model number, and parts list. The manuals must include the manufacturer's name, model number, service manual, and a brief description of all equipment and their basic operating features. Six complete copies of maintenance manual in bound 8 1/2 by 11 inch booklets listing routine maintenance procedures, possible breakdowns and repairs, and a trouble shooting guide. The manuals must include piping and equipment layouts and simplified wiring and control diagrams of the system as installed.

3.1.7 Refrigeration System

3.1.7.1 Equipment

Refrigeration equipment and the installation thereof must conform to ANSI/ASHRAE 15 & 34. Necessary supports must be provided for all equipment, appurtenances, and pipe as required, including frames or supports for compressors, pumps, cooling towers, condensers, water coolers, and similar items. Compressors must be isolated from the building structure. If mechanical vibration isolators are not provided, vibration absorbing foundations must be provided. Each foundation must include isolation units consisting of machine and floor or foundation fastenings, together with intermediate isolation material. Other floor-mounted equipment must be set on not less than a 6 inch concrete pad

doweled in place. Concrete foundations for floor mounted pumps must have a mass equivalent to three times the weight of the components, pump, base plate, and motor to be supported. In lieu of concrete pad foundation, concrete pedestal block with isolators placed between the pedestal block and the floor may be provided. Concrete pedestal block must be of mass not less than three times the combined pump, motor, and base weights. Isolators must be selected and sized based on load-bearing requirements and the lowest frequency of vibration to be isolated. Lines connected to pumps mounted on pedestal blocks must be provided with flexible connectors. Foundation drawings, bolt-setting information, and foundation bolts must be furnished prior to concrete foundation construction for all equipment indicated or required to have concrete foundations. Concrete for foundations must be as specified in Section 03 30 00 CAST-IN-PLACE CONCRETE. Equipment must be properly leveled, aligned, and secured in place in accordance with manufacturer's instructions. All recommendations stated in the installation instructions or other similar manufacturer's published literature must be considered mandatory and part of the contract documents. Any discrepancies to the engineered drawings and specifications must be brought to the attention of the COR.

3.1.7.2 Field Refrigerant Charging

a. Initial Charge: Upon completion of all the refrigerant pipe tests, the vacuum on the system must be broken by adding the required charge of dry refrigerant for which the system is designed, in accordance with the manufacturer's recommendations. Contractor must provide the complete charge of refrigerant in accordance with manufacturer's recommendations. Upon satisfactory completion of the system performance tests, any refrigerant that has been lost from the system must be replaced. After the system is fully operational, service valve seal caps and blanks over gauge points must be installed and tightened.

b. Refrigerant Leakage: If a refrigerant leak is discovered after the system has been charged, the leaking portion of the system must immediately be isolated from the remainder of the system and the refrigerant must be pumped into the system receiver or other suitable container. The refrigerant must not be discharged into the atmosphere.

c. Contractor's Responsibility: The Contractor must, at all times during the installation and testing of the refrigeration system, take steps to prevent the release of refrigerants into the atmosphere. The steps must include, but not be limited to, procedures that minimize the release of refrigerants to the atmosphere and the use of refrigerant recovery devices to remove refrigerant from the system and store the refrigerant for reuse or reclaim. At no time must more than 3 ounces of refrigerant be released to the atmosphere in any one occurrence. Any system leaks within the first year must be repaired in accordance with the specified requirements including material, labor, and refrigerant if the leak is the result of defective equipment, material, or installation.

3.1.7.3 Oil Charging

Except for factory sealed units, two complete charges of lubricating oil for each compressor crankcase must be furnished. One charge must be used during the performance testing period, and upon the satisfactory completion of the tests, the oil must be drained and replaced with the second charge.

3.1.8 Field Applied Insulation

Field installed insulation must be as specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS, except as defined differently herein.

3.1.9 Field Painting

Painting required for surfaces not otherwise specified, and finish painting of items only primed at the factory are specified in Section 09 90 00 PAINTS AND COATINGS.

3.2 FACTORY TEST SCHEDULING AND REPORTS

Provide Factory Test Schedule which identify the date, time, and location for each test. Schedules must be submitted for the Chiller Performance Tests. The Chiller Performance Test schedule must also allow the witnessing of the test by a Government Representative.

Six copies of the certified test report must be forwarded to the Government for approval prior to project acceptance. Calibration curves and information sheets for all instrumentation must be included. Provide copies in bound 8 1/2 by 11 inch booklets. Reports must certify the compliance with performance requirements and follow the format of the required testing standard for the Chiller Performance Tests. Test report must include certified calibration report of all test instrumentation. Calibration report must include certification that all test instrumentation has been calibrated within 6 months prior to the test date, identification of all instrumentation, and certification that all instrumentation complies with requirements of the test standard. Test report must be submitted 1 week after completion of the factory test.

3.3 MANUFACTURER'S FIELD SERVICE

The services of a factory-trained representative must be provided for overseeing of the installation, start-up, and initial operation of the chiller including field acceptance testing. Startup report shall be provided upon initial chiller start-up by manufacturer technical representative. The representative must advise on the following:

a. Hermetic machines:

   (1) Testing hermetic water-chilling unit under pressure for refrigerant leaks; evacuation and dehydration of machine to an absolute pressure of not over 300 micrometers.

   (2) Charging the machine with refrigerant.

   (3) Starting the machine.

b. Open Machines:

   (1) Erection, alignment, testing, and dehydrating.

   (2) Charging the machine with refrigerant.

   (3) Starting the machine.

3.4 CLEANING AND ADJUSTING

Equipment must be wiped clean, with all traces of oil, dust, dirt, or paint spots removed. Provide temporary filters for all fans that are operated during construction. Perform and document that proper Indoor Air Quality During Construction procedures have been followed; this includes providing documentation showing that after construction ends, and prior to occupancy, new filters were provided and installed. System must be maintained in this clean condition until final acceptance. Bearings must be properly lubricated with oil or grease as recommended by the manufacturer. Belts must be tightened to proper tension. Control valves and other miscellaneous equipment requiring adjustment must be adjusted to setting indicated or directed. Fans must be adjusted to the speed indicated by the manufacturer to meet specified conditions. At least one week before the official equipment warranty start date, all condenser coils on air-cooled water chillers and split-system water chillers must be cleaned in accordance with the chiller manufacturer's instructions. All recommendations stated in the installation instructions or other similar manufacturer's published literature must be considered mandatory and part of the contract documents. Any discrepancies to the engineered drawings and specifications must be brought to the attention of the COR. This work covers two coil cleanings. The condenser coils must be cleaned with an approved coil cleaner by a service technician, factory trained by the chiller manufacturer. The condenser coil cleaner must not have any detrimental affect on the materials or protective coatings on the condenser coils. Testing, adjusting, and balancing must be as specified in Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC.

3.5 FIELD ACCEPTANCE TESTING

3.5.1 Test Plans

a. Manufacturer's Test Plans: Within 120 calendar days after contract award, submit the following plans:

(1) Water chiller - Field Acceptance Test Plan

Field acceptance test plans must be developed by the chiller manufacturer detailing recommended field test procedures for that particular type and size of equipment. Field acceptance test plans developed by the installing Contractor, or the equipment sales agency furnishing the equipment, is not acceptable.

The Contracting Officer must review and approve the field acceptance test plan for each of the listed equipment prior to commencement of field testing of the equipment. The approved field acceptance tests of the chiller and subsequent test reporting.

b. Coordinated testing: Indicate in each field acceptance test plan when work required by this section requires coordination with test work required by other specification sections. Furnish test procedures for the simultaneous or integrated testing of tower system controls which interlock and interface with controls for the equipment provided under Section 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS.

c. Prerequisite testing: Chillers for which performance testing is dependent upon the completion of the work covered by Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC must have that work completed as a prerequisite to testing work under this section. Indicate in each field acceptance test plan when such prerequisite work is required.

d. Test procedure: Indicate in each field acceptance test plan each equipment manufacturers published installation, start-up, and field acceptance test procedures. Include in each test plan a detailed step-by-step procedure for testing automatic controls provided by the manufacturer.

Each test plan must include the required test reporting forms to be completed by the Contractor's testing representatives. Procedures must be structured to test the controls through all modes of control to confirm that the controls are performing with the intended sequence of control.

Controller must be verified to be properly calibrated and have the proper set point to provide stable control of their respective equipment.

e. Performance variables: Each test plan must list performance variables that are required to be measured or tested as part of the field test.

Include in the listed variables performance requirements indicated on the equipment schedules on the design drawings. Chiller manufacturer must furnish with each test procedure a description of acceptable results that have been verified.

Chiller manufacturer must identify the acceptable limits or tolerance within which each tested performance variable must acceptably operate.

f. Job specific: Each test plan must be job specific and must address the particular cooling towers and particular conditions which exist in this contract. Generic or general preprinted test procedures are not acceptable.

g. Specialized components: Each test plan must include procedures for field testing and field adjusting specialized components, such as hot gas bypass control valves, or pressure valves.

3.5.2 Testing

a. Each water chiller system must be field acceptance tested in compliance with its approved field acceptance test plan and the resulting following field acceptance test report submitted for approval:

(1) Water chiller - Field Acceptance Test Report

b. Manufacturer's recommended testing: Conduct the manufacturer's recommended field testing in compliance with the approved test plan. Furnish a factory trained field representative authorized by and to represent the equipment manufacturer at the complete execution of the field acceptance testing.

c. Operational test: Conduct a continuous 24 hour operational test for each item of equipment. Equipment shutdown before the test period is completed must result in the test period being started again and run for the required duration. For the duration of the test period, compile an operational log of each item of equipment. Log required entries every two hours. Use the test report forms for logging the operational variables.

d. Notice of tests: Conduct the manufacturer's recommended tests and the operational tests; record the required data using the approved reporting forms. Notify the Contracting Officer in writing at least 15 calendar days prior to the testing. Within 30 calendar days after acceptable completion of testing, submit each test report for review and approval.

e. Report forms: Type data entries and writing on the test report forms. Completed test report forms for each item of equipment must be reviewed, approved, and signed by the Contractor's test director. The manufacturer's field test representative must review, approve, and sign the report of the manufacturer's recommended test. Signatures must be accompanied by the person's name typed.

f. Deficiency resolution: The test requirements acceptably met; deficiencies identified during the tests must be corrected in compliance with the manufacturer's recommendations and corrections retested in order to verify compliance.

3.6 SYSTEM PERFORMANCE TESTS

All reports must be signed and submitted in electronic format. In addition, six copies of the report must be provided in bound 8 1/2 by 11 inch booklets.

3.6.1 General Requirements

Before each refrigeration system is accepted, tests to demonstrate the general operating characteristics of all equipment must be conducted by the manufacturer's approved start-up representative experienced in system start-up and testing, at such times as directed. Tests must cover a period of not less than 48 hours for each system and must demonstrate that the entire system is functioning in accordance with the drawings and specifications. Corrections and adjustments must be made as necessary and tests must be re-conducted to demonstrate that the entire system is functioning as specified. Prior to acceptance, service valve seal caps and blanks over gauge points must be installed and tightened. Any refrigerant lost during the system startup must be replaced. If tests do not demonstrate satisfactory system performance, deficiencies must be corrected and the system must be retested. Tests must be conducted in the presence of the Contracting Officer. Water and electricity required for the tests must be furnished by the Government. Any material, equipment, instruments, and personnel required for the test must be provided by the Contractor. Field tests must be coordinated with Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC.

3.6.2 Test Report

The report must document compliance with the specified performance criteria upon completion and testing of the system. The report must indicate the number of days covered by the tests and any conclusions as to

the adequacy of the system. The report must also include the following information and must be taken at least three different times at outside dry-bulb temperatures that are at least 5 degrees F apart:

a. Date and outside weather conditions.

b. The load on the system based on the following:

(1) The refrigerant used in the system.

(2) Condensing temperature and pressure.

(3) Suction temperature and pressure.

(4) Running current, voltage and proper phase sequence for each phase of all motors.

(5) The actual on-site setting of all operating and safety controls.

(6) Chilled water pressure, flow and temperature in and out of the chiller.

3.6.3 Auto-Start Verification

Prior to government acceptance, provide demonstration of auto-restart after an electrical power surge or outage with all applicable Acceptance Engineers, Engineering Technicians, Construction Managers and Prime Contractors in attendance.

3.7 DEMONSTRATIONS

Contractor must conduct a training course for the operating staff as designated by the Contracting Officer. The training period must consist of a total 8 hours of normal working time and start after the system is functionally completed but prior to final acceptance tests. The training course must cover all of the items contained in the approved operation and maintenance manuals as well as demonstrations of routine maintenance operations.

Provide a Training Course Schedule, at least 2 weeks prior to the date of the proposed training course, which identifies the date, time, and location for the training.

-- End of Section --

SECTION 23 64 26

CHILLED WATER PIPING SYSTEMS
08/09, CHG 5: 11/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z21.22/CSA 4.4	(2015; R 2020) Relief Valves for Hot Water Supply Systems

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.1	(2020) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250
ASME B16.18	(2021) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.21	(2021) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B16.22	(2021) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.26	(2024) Cast Copper Alloy Fittings for Flared Copper Tubes
ASME B31.9	(2020) Building Services Piping
ASME B40.100	(2022) Pressure Gauges and Gauge Attachments
ASME BPVC SEC IX	(2017; Errata 2018) BPVC Section IX-Welding, Brazing and Fusing Qualifications

AMERICAN SOCIETY OF SANITARY ENGINEERING (ASSE)

ASSE 1003	(2020) Performance Requirements for Water Pressure Reducing Valves for Domestic Water Distribution Systems - (ANSI approved 2010)

AMERICAN WELDING SOCIETY (AWS)

AWS A5.8/A5.8M	(2019) Specification for Filler Metals for Brazing and Braze Welding
AWS BRH	(2007; 5th Ed) Brazing Handbook

AWS D1.1/D1.1M	(2020; Errata 1 2021) Structural Welding Code - Steel
AWS Z49.1	(2021) Safety in Welding, Cutting and Allied Processes

ASTM INTERNATIONAL (ASTM)

ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B32	(2020) Standard Specification for Solder Metal
ASTM B42	(2025) Standard Specification for Seamless Copper Pipe, Standard Sizes
ASTM B62	(2017; R 2025) Standard Specification for Composition Bronze or Ounce Metal Castings
ASTM B75/B75M	(2020) Standard Specification for Seamless Copper Tube
ASTM B88	(2022) Standard Specification for Seamless Copper Water Tube
ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM B813	(2024) Standard Specification for Liquid and Paste Fluxes for Soldering of Copper and Copper Alloy Tube
ASTM D520	(2025) Standard Specification for Zinc Dust Pigment
ASTM D596	(2001; R 2018) Standard Guide for Reporting Results of Analysis of Water
ASTM D3308	(2012; R 2022) Standard Specification for PTFE Resin Skived Tape
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials
ASTM F1007	(2018) Standard Specification for Pipeline Expansion Joints of the Packed Slip Type for Marine Application
ASTM F1120	(1987; R 2019) Standard Specification for Circular Metallic Bellows Type Expansion Joints for Piping Applications

ASTM F1199	(2021) Standard Specification for Cast (All Temperatures and Pressures) and Welded Pipe Line Strainers (150 psig and 150 degrees F Maximum)
ASTM D2308	(2007; R 2013) Standard Specification for Thermoplastic Polyethylene Jacket for Electrical Wire and Cable

EXPANSION JOINT MANUFACTURERS ASSOCIATION (EJMA)

EJMA Stds	(2015) (10th Ed) EJMA Standards

HYDRAULIC INSTITUTE (HI)

HI 1.1-1.2	(2014) Rotodynamic (Centrifugal) Pump for Nomenclature and Definitions

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 515	(2017) Standard for the Testing, Design, Installation, and Maintenance of Electrical Resistance Heat Tracing for Industrial Applications

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-25	(2018) Standard Marking System for Valves, Fittings, Flanges and Unions
MSS SP-58	(2025) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation
MSS SP-67	(2022) Butterfly Valves
MSS SP-69	(2003; Notice 2012) Pipe Hangers and Supports - Selection and Application (ANSI Approved American National Standard)
MSS SP-70	(2011) Gray Iron Gate Valves, Flanged and Threaded Ends
MSS SP-71	(2018) Gray Iron Swing Check Valves, Flanged and Threaded Ends
MSS SP-72	(2010a) Ball Valves with Flanged or Butt-Welding Ends for General Service
MSS SP-78	(2011) Cast Iron Plug Valves, Flanged and Threaded Ends
MSS SP-80	(2019) Bronze Gate, Globe, Angle, and Check Valves
MSS SP-85	(2011) Gray Iron Globe & Angle Valves Flanged and Threaded Ends

MSS SP-110	(2010) Ball Valves Threaded, Socket-Welding, Solder Joint, Grooved and Flared Ends

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2020) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA MG 1	(2021) Motors and Generators
NEMA MG 11	(1977; R 2012) Energy Management Guide for Selection and Use of Single Phase Motors

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 90A	(2024) Standard for the Installation of Air Conditioning and Ventilating Systems

1.2 SYSTEM DESCRIPTION

Provide the water systems having the minimum service (design) temperature-pressure rating indicated. Provision of the piping systems, including materials, installation, workmanship, fabrication, assembly, erection, examination, inspection, and testing shall be in accordance with the required and advisory provisions of ASME B31.9 except as modified or supplemented by this specification section or design drawings. This specification section covers the water systems piping which is located within, on, and adjacent to building(s) within the building(s) 5 foot line.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Calibrated Balancing Valves; G

Water Temperature Regulating Valves; G

Water Pressure Reducing Valve

Pressure Relief Valve

Combination Pressure and Temperature Relief Valves

Expansion Joints; G

Pumps; G

Combination Strainer and Pump Suction Diffuser

Expansion Tanks

Air Separator Tanks

Water Treatment Systems; G

Proposed water treatment plan including a layout, control scheme, a list of existing make-up water conditions including the items listed in paragraph WATER ANALYSIS", a list of chemicals, the proportion of chemicals to be added, the final treated water conditions, and a description of environmental concerns for handling the chemicals.

SD-06 Test Reports

Piping Welds NDE Report

Pressure Tests Reports; G

Report shall be provided in bound 8-1/2 by 11 inch booklets. In the reports, document all phases of the tests performed. Include initial test summaries, all repairs/adjustments made, and the final test results.

SD-07 Certificates

Employer's Record Documents (For Welding)

Welding Procedures and Qualifications

Certificates shall be submitted showing conformance with the referenced standards contained in this section.

SD-08 Manufacturer's Instructions

Lesson plan for the Instruction Course;

SD-10 Operation and Maintenance Data

Requirements for data packages are specified Section 01 78 23 OPERATION AND MAINTENANCE DATA, except as supplemented and modified by this specification section.

Submit spare parts data for each different item of equipment specified, with operation and maintenance data packages. Include a complete list of parts and supplies, with current unit prices and source of supply, a recommended spare parts list for 1 year of operation, and a list of the parts recommended by the manufacturer to be replaced on a routine basis.

Submit a list of qualified permanent service organizations with operation and maintenance data packages. Include service organization addresses and service area or expertise. The service organizations shall be reasonably convenient to the equipment installation and be able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

Water Treatment Systems;

An operation manual in bound 8-1/2 by 11 inch booklets listing

step-by-step procedures required for system startup, operation, abnormal shutdown, emergency shutdown, and normal shutdown. Include testing procedures used in determining water quality.

A maintenance manual in bound 8-1/2 by 11 inch booklets listing routine maintenance procedures, possible breakdowns and repairs, and a trouble shooting guide.

Calibrated Balancing Valves, Data Package 3;

Water Temperature Regulating Valves, Data Package 3;

Water Pressure Reducing Valve, Data Package 3;

Pressure Relief Valve, Data Package 2;

Combination Pressure and Temperature Relief Valves, Data Package 2;

Expansion Joints, Data Package 2;

Pumps, Data Package 3;

Combination Strainer and Pump Suction Diffuser, Data Package 2;

Expansion Tanks, Data Package 2;

Air Separator Tanks, Data Package 2;

1.4 MODIFICATIONS TO REFERENCES

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction", or words of similar meaning, to mean the Contracting Officer.

1.4.1 Definitions

For the International Code Council (ICC) Codes referenced in the contract documents, advisory provisions shall be considered mandatory, the word "should" shall be interpreted as "shall." Reference to the "code official" shall be interpreted to mean the "Contracting Officer." For Navy owned property, references to the "owner" shall be interpreted to mean the "Contracting Officer." For leased facilities, references to the "owner" shall be interpreted to mean the "lessor." References to the "permit holder" shall be interpreted to mean the "Contractor."

1.4.2 Administrative Interpretations

For ICC Codes referenced in the contract documents, the provisions of Chapter 1, "Administrator," do not apply. These administrative requirements are covered by the applicable Federal Acquisition Regulations (FAR) included in this contract and by the authority granted to the Officer in Charge of Construction to administer the construction of this project. References in the ICC Codes to sections of Chapter 1, shall be applied appropriately by the Contracting Officer as authorized by his administrative cognizance and the FAR.

1.5 SAFETY REQUIREMENTS

Exposed moving parts, parts that produce high operating temperature, parts which may be electrically energized, and parts that may be a hazard to operating personnel shall be insulated, fully enclosed, guarded, or fitted with other types of safety devices. Safety devices shall be installed so that proper operation of equipment is not impaired.

1.6 DELIVERY, STORAGE, AND HANDLING

Protect stored items from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Proper protection and care of all material both before and during installation shall be the Contractor's responsibility. Any materials found to be damaged shall be replaced at the Contractor's expense. During installation, cap piping and similar openings to keep out dirt and other foreign matter. Any porous materials found to be contaminated with mold or mildew will be replaced at the Contractor's expense. Non-porous materials found to be contaminated with mold or mildew will be disinfected and cleaned prior to installation.

1.7 PROJECT/SITE CONDITIONS

1.7.1 Verification of Dimensions

The Contractor shall become familiar with all details of the work, verify all dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

1.7.2 Drawings

Because of the small scale of the drawings, it is not possible to indicate all offsets, fittings, and accessories that may be required. The Contractor shall carefully investigate the plumbing, fire protection, electrical, structural and finish conditions that would affect the work to be performed and shall arrange such work accordingly, furnishing required offsets, fittings, and accessories to meet such conditions.

1.7.3 Accessibility

Install all work so that parts requiring periodic inspection, operation, maintenance, and repair are readily accessible. Install concealed valves, expansion joints, controls, dampers, and equipment requiring access, in locations freely accessible through access doors.

PART 2 PRODUCTS

2.1 STANDARD COMMERCIAL PRODUCTS

Materials and equipment shall be standard products of a manufacturer regularly engaged in the manufacturing of such products, which are of a similar material, design and workmanship. The standard products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening.

The two year use shall include applications of equipment and materials under similar circumstances and of similar size. The 2 years experience shall be satisfactorily completed by a product which has been sold or is offered for sale on the commercial market through advertisements, manufacturer's catalogs, or brochures.

Products having less than a 2 year field service record shall be acceptable if a certified record of satisfactory field operation, for not less than 6000 hours exclusive of the manufacturer's factory tests, can be shown. System components shall be environmentally suitable for the indicated locations.

The equipment items shall be supported by service organizations. These service organizations shall be reasonably convenient to the equipment installation and able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

2.2 ELECTRICAL HEAT TRACING

Provide heat trace systems for all exterior pipes, valves, and fittings that are in accordance with IEEE 515 and be UL listed. System include all necessary components, including heaters and controls to prevent freezing. Prior to heat trace installation, Schedule 40 carbon steel piping shall be cleaned, primed and painted.

Provide self-regulating heaters consisting of two 16 AWG tinned-copper bus wires embedded in parallel in a self-regulating polymer core that varies its power output to respond to temperature along its length. Ensure heater is able to be crossed over itself without overheating. Obtain approval before used directly on plastic pipe. Cover heater with a radiation cross-linked modified polyolefin dielectric jacket in accordance with ASTM D2308.

Provide heater with self-regulating factor of at least 90 percent, in order to provide energy conservation and to prevent overheating.

Operate heater on line voltages as shown on plans.

Size Heater according to the following table:

Pipe Size

(Inch, Diameter)	Minus 10 degrees F	Minus 20 degrees F
3 inches or less	5 watts per foot (wpf)	5 wpf
4 inch	5 wpf	8 wpf
6 inch	8 wpf	8 wpf
8 inch	2 strips/5 wpf	2 strips/8 wpf
12 inch	2 strips/8 wpf	2 strips/8 wpf

Control systems by an ambient sensing thermostat set at 40 degrees F either directly or through an appropriate contactor.

2.3 STEEL PIPING

Water piping larger than 100 mm 4 inches shall be steel pipe or copper tubing. Provide steel piping with a ANSI/ASME Class 125 service rating,

which for 150 degrees F, the pressure rating is 175 psig.

2.3.1 Pipe

Steel pipe, conform to ASTM A53/A53M, Schedule 40, Type E or S, Grades A or B. Do not use Type F pipe.

2.3.2 Fittings and End Connections (Joints)

Piping and fittings 3 inches and larger shall have flanged connections. The manufacturer of each fitting shall be permanently identified on the body of the fitting in accordance with MSS SP-25.

2.3.2.1 Flanged Connections

Flanges shall conform to ASME B16.1, Class 125. Gaskets shall be nonasbestos compressed material in accordance with ASME B16.21, 1/16 inch thickness, full face or self-centering flat ring type. These gaskets shall contain aramid fibers bonded with styrene butadeine rubber (SBR) or nitrile butadeine rubber (NBR). Bolts, nuts, and bolt patterns shall conform to ASME B16.1.

2.3.2.2 Dielectric Waterways and Flanges

Provide dielectric waterways with a water impervious insulation barrier capable of limiting galvanic current to 1 percent of short circuit current in a corresponding bimetallic joint. When dry, insulation barrier shall be able to withstand a 600-volt breakdown test. Provide dielectric waterways constructed of galvanized steel and have threaded end connections to match connecting piping. Dielectric waterways shall be suitable for the required operating pressures and temperatures. Provide dielectric flanges with the same pressure ratings as standard flanges and provide complete electrical isolation between connecting pipe and/or equipment as described herein for dielectric waterways.

2.4 COPPER TUBING

Provide copper tubing and fittings for all pipe 100 mm 4 inches and smaller with a ANSI/ASME Class 125 service rating, which for 150 degrees F., the pressure rating is 175 psig.

2.4.1 Tube

Use copper tube conforming to ASTM B88, Type L for aboveground tubing, and Type K for buried tubing.

2.4.2 Fittings and End Connections (Solder and Flared Joints)

Wrought copper and bronze solder joint pressure fittings, including unions ands flanges, shall conform to ASME B16.22 and ASTM B75/B75M. Provide adapters as required. Cast copper alloy solder-joint pressure fittings , including unions and flanges, shall conform to ASME B16.18. Cast copper alloy fittings for flared copper tube shall conform to ASME B16.26 and ASTM B62. ASTM B42 copper pipe nipples with threaded end connections shall conform to ASTM B42.

Copper tubing of sizes larger than 4 inches shall have brazed joints. Brass or bronze adapters for brazed tubing may be used for connecting tubing to flanges and to threaded ends of valves and equipment.

Extracted brazed tee joints may be used if produced with an acceptable tool and installed in accordance with tool manufacturer's written procedures.

2.4.3 Solder

Provide solder in conformance with ASTM B32, grade Sb5, tin-antimony alloy. Solder flux shall be liquid or paste form, non-corrosive and conform to ASTM B813.

2.4.4 Brazing Filler Metal

Filler metal shall conform to AWS A5.8/A5.8M, Type BAg-5 with AWS Type 3 flux, except Type BCuP-5 or BCuP-6 may be used for brazing copper-to-copper joints.

2.5 VALVES

Provide valves with a ANSI/ASME Class 125 service rating, which for 150 degrees F, the pressure rating is 175 psig.

Valves in sizes larger than 1 inch and used on steel pipe systems, may be provided with rigid grooved mechanical joint ends. Such grooved end valves shall be subject to the same requirements as rigid grooved mechanical joints and fittings and, shall be furnished by the same manufacturer as the grooved pipe joint and fitting system.

2.5.1 Gate Valve

Gate valves 2-1/2 inches and smaller shall conform to MSS SP-80 Class 125 and shall be bronze with wedge disc, rising stem and threaded, soldered, or flanged ends. Gate valves 3 inches and larger shall conform to MSS SP-70, Class 125, cast iron with bronze trim, outside screw and yoke, and flanged or threaded ends.

2.5.2 Globe and Angle Valve

Globe and angle valves 2-1/2 inches and smaller shall conform to MSS SP-80, Class 125. Globe and angle valves 3 inches and larger shall conform to MSS SP-85, Class 125.

2.5.3 Check Valve

Check valves 2-1/2 inches and smaller shall conform to MSS SP-80. Check valves 3 inches and larger shall conform to MSS SP-71, Class 125.

2.5.4 Butterfly Valve

Butterfly valves shall conform to MSS SP-67, Type 1 and shall be lug type. Wafer type is prohibited. Valves smaller than 8 inches shall have throttling handles with a minimum of seven locking positions. Valves 8 inches and larger shall have totally enclosed manual gear operators with adjustable balance return stops and position indicators.

2.5.5 Plug Valve

Plug valves 2 inches and larger shall conform to MSS SP-78, have flanged or threaded ends, and have cast iron bodies with bronze trim. Valves 2

inches and smaller shall be bronze with NPT connections for black steel pipe and brazed connections for copper tubing. Valve shall be lubricated, non-lubricated, or tetrafluoroethylene resin-coated type. Valve shall be resilient, double seated, trunnion mounted with tapered lift plug capable of 2-way shutoff. Valve shall operate from fully open to fully closed by rotation of the handwheel to lift and turn the plug. Valves 8 inches or larger shall be provided with manual gear operators with position indicators.

2.5.6 Ball Valve

Full port design. Ball valves 1/2 inch and larger shall conform to MSS SP-72 or MSS SP-110 and shall be cast iron or bronze with threaded, soldered, or flanged ends. Valves 8 inches or larger shall be provided with manual gear operators with position indicators. Ball valves may be provided in lieu of gate valves.

2.5.7 Square Head Cocks

Provide copper alloy or cast-iron body with copper alloy plugs, suitable for 125 psig water working pressure.

2.5.8 Calibrated Balancing Valves

Copper alloy or cast iron body, copper alloy or stainless internal working parts. Provide valve calibrated so that flow can be determined when the temperature and pressure differential across valve is known. Valve shall have an integral pointer which registers the degree of valve opening. Valve shall function as a service valve when in fully closed position. Valve shall be constructed with internal seals to prevent leakage and shall be supplied with preformed insulation.

Provide valve bodies with tapped openings and pipe extensions with positive shutoff valves outside of pipe insulation. The pipe extensions shall be provided with quick connecting hose fittings for a portable differential pressure meter connections to verify the pressure differential. Provide metal tag on each valve showing the gallons per minute flow for each differential pressure reading.

2.5.9 Water Temperature Regulating Valves

Provide copper alloy body, direct acting, pilot operated, for the intended service.

2.5.10 Water Pressure Reducing Valve

Valve, ASSE 1003 for water service, copper alloy body.

2.5.11 Pressure Relief Valve

Valve shall prevent excessive pressure in the piping system when the piping system reaches its maximum heat buildup. Valve, ANSI Z21.22/CSA 4.4 and shall have cast iron bodies with corrosion resistant internal working parts. The discharge pipe from the relief valve shall be the size of the valve outlet unless otherwise indicated.

2.5.12 Combination Pressure and Temperature Relief Valves

ANSI Z21.22/CSA 4.4, copper alloy body, automatic re-seating, test lever,

and discharge capacity based on AGA temperature steam rating.

2.5.13 Float Valve

Angle pattern andor Globe pattern. Valve bodies 3 inches nominal pipe size and smaller shall be bronze. Valve bodies larger than 3 inches shall be cast iron or bronze. Steel parts shall be corrosion resistant. Where float rods are extended for tank applications, extension shall be properly supported and guided to avoid bending of float rod or stressing of valve pilot linkage.

2.5.14 Drain Valves

Valves, MSS SP-80 gate valves. Valve shall be manually-operated, 3/4 inch pipe size and above with a threaded end connection. Provide valve with a water hose nipple adapter and caps or plugs. Freeze-proof type valves shall be provided in installations exposed to freezing temperatures.

2.5.15 Air Venting Valves

Manually-operated general service type air venting valves, brass or bronze valves that are furnished with threaded plugs or caps. Automatic type air venting shall be the ball-float type with brass/bronze or brass bodies, 300 series corrosion-resistant steel float, linkage and removable seat. Air venting valves on water coils shall have not less than 1/8 inch threaded end connections. Air venting valves on water mains shall have not less than 3/4 inch threaded end connections. Air venting valves on all other applications shall have not less than 1/2 inch threaded end connections.

2.5.16 Vacuum Relief Valves

ANSI Z21.22/CSA 4.4

2.6 PIPING ACCESSORIES

All piping accessories used for testing, adjusting and balancing must be extended beyond the pipe insulation to allow for full access.

2.6.1 Strainer

Strainer, ASTM F1199, except as modified and supplemented in this specification. Strainer shall be the cleanable, basket or "Y" type, the same size as the pipeline. Strainer bodies shall be fabricated of cast iron with bottoms drilled, and tapped. Provide blowoff outlet with pipe nipple, gate valve, and discharge pipe nipple. The bodies shall have arrows clearly cast on the sides indicating the direction of flow.

Provide strainer with removable cover and sediment screen. The screen shall be made of minimum 22 gauge monel, with small perforations numbering not less than 400 per square inch to provide a net free area through the basket of at least 3.30 times that of the entering pipe. The flow shall be into the screen and out through the perforations.

2.6.2 Cyclonic Separator

Metal- bodied, with removal capability of removing solids 45 microns/325 mesh in size and heavier than 1.20 specific gravity, maximum pressure drop of 5 psid, with cleanout connection.

2.6.3 Combination Strainer and Pump Suction Diffuser

Angle type body with removable strainer basket and internal straightening vanes, a suction pipe support, and a blowdown outlet and plug. Strainer shall be in accordance with ASTM F1199, except as modified and supplemented by this specification. Unit body shall have arrows clearly cast on the sides indicating the direction of flow.

Strainer screen shall be made of minimum 22 gauge monel, with small perforations numbering not less than 400 per square inch to provide a net free area through the basket of at least 3.30 times that of the entering pipe. Flow shall be into the screen and out through the perforations. Provide an auxiliary disposable fine mesh strainer which shall be removed 30 days after start-up. Provide warning tag for operator indicating scheduled date for removal.

Casing shall have connection sizes to match pump suction and pipe sizes, and be provided with adjustable support foot or support foot boss to relieve piping strains at pump suction. Provide unit casing with blowdown port and plug. Provide a magnetic insert to remove debris from system.

2.6.4 Flexible Pipe Connectors

Provide flexible pipe connectors on piping connected to equipment. Flexible section shall consist of rubber, tetrafluoroethylene resin, corrosion-resistant steel, bronze, monel, or galvanized steel. Material provided and configuration shall be suitable for pressure, temperature, and circulating medium. Flexible section shall have flanged ends and shall be suitable for service intended. Flexible section may be reinforced with metal retaining rings, with built-in braided wire reinforcement and restriction bolts or with wire braid cover suitable for service intended.Unless otherwise indicated, the length of the flexible connectors shall be as recommended by the manufacturer for the service intended. Internal sleeves or liners, compatible with circulating medium, shall be provided when recommended by the manufacturer. Provide covers to protect the bellows where indicated.

2.6.5 Pressure and Vacuum Gauges

Gauges, ASME B40.100 with throttling type needle valve or a pulsation dampener and shut-off valve. Provide gauges with 4.5 inch dial, brass or aluminum case, bronze tube, and siphon. Gauge shall have a range from 0 psig to approximately 1.5 times the maximum system working pressure. Each gauge range shall be selected so that at normal operating pressure, the needle is within the middle-third of the range.

2.6.6 Temperature Gauges

Temperature gauges, shall be the industrial duty type and be provided for the required temperature range. Provide gauges with fixed thread connection, dial face gasketed within the case; and an accuracy within 2 percent of scale range. Gauges shall have Fahrenheit scale in 2 degree graduations scale (black numbers) on a white face. The pointer shall be adjustable. Rigid stem type temperature gauges shall be provided in thermal wells located within 5 feet of the finished floor. Universal adjustable angle type or remote element type temperature gauges shall be provided in thermal wells located 5 to 7 feet above the finished floor or in locations indicated. Remote element type temperature gauges shall be

provided in thermal wells located 7 feet above the finished floor or in locations indicated.

2.6.6.1 Stem Cased-Glass

Stem cased-glass case shall be polished stainless steel or cast aluminum, 9 inches long, with clear acrylic lens, and non-mercury filled glass tube with indicating-fluid column.

2.6.6.2 Bimetallic Dial

Bimetallic dial type case shall be not less than 3-1/2 inches, stainless steel, and shall be hermetically sealed with clear acrylic lens. Bimetallic element shall be silicone dampened and unit fitted with external calibrator adjustment.

2.6.6.3 Liquid-, Solid-, and Vapor-Filled Dial

Liquid-, solid-, and vapor-filled dial type cases shall be not less than 3-1/2 inches, stainless steel or cast aluminum with clear acrylic lens. Fill shall be nonmercury, suitable for encountered cross-ambients, and connecting capillary tubing shall be double-braided bronze.

2.6.6.4 Thermal Well

Thermal well shall be identical size, 1/2 or 3/4 inch NPT connection, brass or stainless steel. Where test wells are indicated, provide captive plug-fitted type 1/2 inch NPT connection suitable for use with either engraved stem or standard separable socket thermometer or thermostat. Mercury shall not be used in thermometers. Extended neck thermal wells shall be of sufficient length to clear insulation thickness by 1 inch.

2.6.7 Pipe Hangers, Inserts, and Supports

Pipe hangers, inserts, guides, and supports: to MSS SP-58 and MSS SP-69. If ferrous materials are utilized provide hot-dipped galvanized hangers, inserts and supports.

2.6.8 Escutcheons

Provide one piece or split hinge metal plates for piping entering floors, walls, and ceilings in exposed spaces. Secure plates in place by internal spring tension or set screws. Provide polished stainless steel plates or chromium-plated finish on copper alloy plates in finished spaces. Provide paint finish on metal plates in unfinished spaces.

2.6.9 Expansion Joints

2.6.9.1 Slip-Tube Type

Slip-tube expansion joints, ASTM F1007, Class I or II. Joints shall be provided with internally-externally alignment guides, injected semi-plastic packing, and service outlets. End connections shall be flanged or beveled for welding as indicated. Initial settings shall be made in accordance with the manufacturer's recommendations to compensate for ambient temperature at time of installation. Pipe alignment guides shall be installed as recommended by the joint manufacturer.

2.6.9.2 Flexible Ball Type

Flexible ball expansion joints shall be capable of 360 degrees rotation plus 15 degrees angular flex movement. Joints shall be constructed of carbon steel with the exterior spherical surface of carbon steel balls plated with a minimum 5 mils of hard chrome in accordance with EJMA Stds. Joint end connections shall be threaded for piping 2 inches or smaller. Joint end connections larger than 2 inches shall be grooved, flanged, or beveled for welding. Provide joint with pressure-molded composition gaskets suitable for continuous operation at twice design temperature.

2.6.9.3 Bellows Type

Bellows expansion type joints, ASTM F1120 with Type 304 stainless steel corrugated bellows, reinforced with equalizing rings, internal sleeves, and external protective covers. Joint end connections shall be grooved, flanged, or beveled for welding. Guiding of piping on both sides of expansion joint shall be in accordance with the published recommendations of the manufacturer of the expansion joint.

2.7 PUMPS

Pumps shall be the electrically driven, non-overloading, centrifugal type which conform to HI 1.1-1.2. Pumps shall be selected at or within 5 percent of peak efficiency. Pump curve shall rise continuously from maximum capacity to shutoff. Pump motor shall conform to NEMA MG 1, be open , and have sufficient horsepower for the service required. Pump motor shall have the required capacity to prevent overloading with pump operating at any point on its characteristic curve. Pump speed shall not exceed 3,600 rpm, except where the pump head is less than 60 feet of water, the pump speed shall not exceed 1,750 rpm. Pump motor shall be equipped with an across-the-line magnetic controller in a NEMA 250, Type 1 enclosure with "START-STOP" switch in the cover.

2.7.1 Construction

Each pump casing shall be designed to withstand the discharge head specified plus the static head on system plus 50 percent of the total, but not less than 125 psig. Pump casing and bearing housing shall be close grained cast iron. High points in the casing shall be provided with manual air vents; low points shall be provided with drain plugs. Provide threaded suction and discharge pressure gage tapping with square-head plugs.

Impeller shall be statically and dynamically balanced. Impeller, impeller wearing rings, glands, casing wear rings, and shaft sleeve shall be bronze. Shaft shall be carbon or alloy steel, turned and ground. Bearings shall be ball-bearings, roller-bearings, or oil-lubricated bronze-sleeve type bearings, and be efficiently sealed or isolated to prevent loss of oil or entrance of dirt or water.

Pump and motor shall be mounted on a common cast iron base having lipped edges and tapped drainage openings or structural steel base with lipped edges or drain pan and tapped drainage openings. Pump shall be provided with steel shaft coupling guard. Base-mounted pump, coupling guard, and motor shall each be bolted to a fabricated steel base which shall have bolt holes for securing base to supporting surface. Close-coupled pump shall be provided with integrally cast or fabricated steel feet with bolt holes for securing feet to supporting surface. Close- coupled pumps shall

be provided with drip pockets and tapped openings. Pump shall be accessible for servicing without disturbing piping connections. Shaft seals shall be mechanical-seals or stuffing-box type.

2.7.2 Mechanical Shaft Seals

Seals shall be single, inside mounted, end-face-elastomer bellows type with stainless steel spring, brass or stainless steel seal head, carbon rotating face, and tungsten carbide or ceramic sealing face. Glands shall be bronze and of the water-flush design to provide lubrication flush across the face of the seal. Bypass line from pump discharge to flush connection in gland shall be provided, with filter or cyclone particle separator in line.

2.7.3 Stuffing-Box Type Seals

Stuffing box shall include minimum 4 rows of square, impregnated TFE (Teflon) or graphite cord packing and a bronze split-lantern ring. Packing gland shall be bronze interlocking split type.

2.8 EXPANSION TANKS

Tank shall be welded steel, constructed for, and tested to pressure-temperature rating of 125 psi at 150 degrees F. Provide tanks precharged to the minimum operating pressure. Tank shall have a replaceable polypropylene or butyl lined diaphragm which keeps the air charge separated from the water; shall be the captive air type.

Tanks shall accommodate expanded water of the system generated within the normal operating temperature range, limiting this pressure increase at all components in the system to the maximum allowable pressure at those components. Each tank air chamber shall be fitted with a drain, fill, an air charging valve, and system connections. Tank shall be supported by steel legs or bases for vertical installation or steel saddles for horizontal installations. The only air in the system shall be the permanent sealed-in air cushion contained within the expansion tank.

2.9 AIR SEPARATOR TANKS

External air separation tank shall have an internal design constructed of stainless steel and suitable for creating the required vortex and subsequent air separation. Tank shall be steel, constructed for, and tested to pressure-temperature rating of 125 psi at 150 degrees F. Tank shall have tangential inlets and outlets connections, threaded for 2 inches and smaller and flanged for sizes 2-1/2 inches and larger. Air released from a tank shall be vented as indicated. Tank shall be provided with a blow-down connection.

2.10 WATER TREATMENT SYSTEMS

When water treatment is specified, the use of chemical-treatment products containing equivalent chromium (CPR) is prohibited.

2.10.1 Water Analysis

Conditions of make-up water to be supplied to the condenser and chilled water systems were reported in accordance with ASTM D596 and are as follows:

Date of Sample	_____
Temperature	_____ degrees F
Silica (Sino 2)	_____ pp (mg/1)
Insoluble	_____ pp (mg/1)
Iron and Aluminum Oxides	_____ pp (mg/1)
Calcium (Ca)	_____ pp (mg/1)
Magnesium (Mg)	_____ pp (mg/1)
Sodium and Potassium (Nan and AK)	_____ pp (mg/1)
Carbonate (HO 3)	_____ pp (mg/1)
Sulfate (SO 4)	_____ pp (mg/1)
Chloride (JCL)	_____ pp (mg/1)
Nitrate (NO 3	_____ pp (mg/1)
Turbidity	_____ unit
pH	_____
Residual Chlorine	_____ pp (mg/1)
Total Alkalinity	_____ PM (me/1
Non-Carbonate Hardness	_____ PM (me/1
Total Hardness	_____ PM (me/1
Dissolved Solids	_____ pp (mg/1)
Fluorine	_____ pp (mg/1)
Conductivity	_____ micromhos/cm

2.10.2 Chilled Water

Water to be used in the chilled and condenser water systems shall be treated to maintain the conditions recommended by this specification as well as the recommendations from the manufacturers of the condenser and evaporator coils. Chemicals shall meet all required federal, state, and local environmental regulations for the treatment of evaporator coils and direct discharge to the sanitary sewer.

2.10.3 Water Treatment Services

The services of a company regularly engaged in the treatment of condenser and chilled water systems shall be used to determine the correct chemicals

required, the concentrations required, and the water treatment equipment sizes and flow rates required. The company shall maintain the chemical treatment and provide all chemicals required for the condenser and chilled water systems for a period of 1 year from the date of occupancy. The chemical treatment and services provided over the 1 year period shall meet the requirements of this specification as well as the recommendations from the manufacturers of the condenser and evaporator coils. Acid treatment and proprietary chemicals shall not be used.

2.10.4 Chilled Water System

A shot feeder shall be provided on the chilled water piping as indicated. Size and capacity of feeder shall be based on local requirements and water analysis. The feeder shall be furnished with an air vent, gauge glass, funnel, valves, fittings, and piping.

2.11 ELECTRICAL WORK

Provide motors, controllers, integral disconnects, contactors, and controls with their respective pieces of equipment, except controllers indicated as part of motor control centers. Provide electrical equipment, including motors and wiring, as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Manual or automatic control and protective or signal devices required for the operation specified and control wiring required for controls and devices specified, but not shown, shall be provided. For packaged equipment, the manufacturer shall provide controllers including the required monitors and timed restart.

Provide high efficiency type, single-phase, fractional-horsepower alternating-current motors, including motors that are part of a system, in accordance with NEMA MG 11.

Provide polyphase, squirrel-cage medium induction motors, including motors that are part of a system, that meet the efficiency ratings for premium efficiency motors in accordance with NEMA MG 1. Provide motors in accordance with NEMA MG 1 and of sufficient size to drive the load at the specified capacity without exceeding the nameplate rating of the motor.

Motors shall be rated for continuous duty with the enclosure specified. Motor duty requirements shall allow for maximum frequency start-stop operation and minimum encountered interval between start and stop. Motor torque shall be capable of accelerating the connected load within 20 seconds with 80 percent of the rated voltage maintained at motor terminals during one starting period. Provide motor starters complete with thermal overload protection and other necessary appurtenances. Motor bearings shall be fitted with grease supply fittings and grease relief to outside of the enclosure.

Where two-speed or variable-speed motors are indicated, solid-state variable-speed controllers may be provided to accomplish the same function. Use solid-state variable-speed controllers for motors rated 10 hp or less and adjustable frequency drives for larger motors. Provide variable frequency drives for motors as specified.

2.12 PAINTING OF NEW EQUIPMENT

New equipment painting shall be factory applied or shop applied, and shall be as specified herein, and provided under each individual section.

2.12.1 Factory Painting Systems

Manufacturer's standard factory painting systems may be provided. The factory painting system applied will withstand 125 hours in a salt-spray fog test, except that equipment located outdoors shall withstand 500 hours in a salt-spray fog test.

Salt-spray fog test shall be in accordance with ASTM B117, and for that test, the acceptance criteria shall be as follows: immediately after completion of the test, the paint shall show no signs of blistering, wrinkling, or cracking, and no loss of 0.125 inch on either side of the scratch mark. The film thickness of the factory painting system applied on the equipment shall not be less than the film thickness used on the test specimen.

If manufacturer's standard factory painting system is being proposed for use on surfaces subject to temperatures above 120 degrees F, the factory painting system shall be designed for the temperature service.

2.12.2 Shop Painting Systems for Metal Surfaces

Clean, retreat, prime and paint metal surfaces; except aluminum surfaces need not be painted. Apply coatings to clean dry surfaces. Clean the surfaces to remove dust, dirt, rust, oil and grease by wire brushing and solvent degreasing prior to application of paint, except metal surfaces subject to temperatures in excess of 120 degrees F shall be cleaned to bare metal.

Where hot-dip galvanized steel has been cut, resulting surfaces with no galvanizing shall be coated with a zinc-rich coating conforming to ASTM D520, Type I.

Where more than one coat of paint is specified, apply the second coat after the preceding coat is thoroughly dry. Lightly sand damaged painting and retouch before applying the succeeding coat. Color of finish coat shall be aluminum or light gray.

a. Temperatures Less Than 120 Degrees F: Immediately after cleaning, the metal surfaces subject to temperatures less than 120 degrees F shall receive one coat of pretreatment primer applied to a minimum dry film thickness of 0.3 mil, one coat of primer applied to a minimum dry film thickness of one mil; and two coats of enamel applied to a minimum dry film thickness of one mil per coat.

b. Temperatures Between 120 and 400 degrees F: Metal surfaces subject to temperatures between 120 and 400 degrees F shall receive two coats of 400 degrees F heat-resisting enamel applied to a total minimum thickness of 2 mils.

c. Temperatures Greater Than 400 degrees F: Metal surfaces subject to temperatures greater than 400 degrees F shall receive two coats of 600 degrees F heat-resisting paint applied to a total minimum dry film thickness of 2 mils.

2.13 FACTORY APPLIED INSULATION

Factory insulated items installed outdoors are not required to be fire-rated. As a minimum, factory insulated items installed indoors shall have a flame spread index no higher than 25 and a smoke developed index no

higher than 150. Factory insulated items (no jacket) installed indoors and which are located in air plenums, in ceiling spaces, and in attic spaces shall have a flame spread index no higher than 25 and a smoke developed index no higher than 50. Flame spread and smoke developed indexes shall be determined by ASTM E84.

Insulation shall be tested in the same density and installed thickness as the material to be used in the actual construction. Material supplied by a manufacturer with a jacket shall be tested as a composite material. Jackets, facings, and adhesives shall have a flame spread index no higher than 25 and a smoke developed index no higher than 50 when tested in accordance with ASTM E84.

2.14 NAMEPLATES

Major equipment including pumps, pump motors, expansion tanks, and air separator tanks shall have the manufacturer's name, type or style, model or serial number on a plate secured to the item of equipment. The nameplate of the distributing agent will not be acceptable. Plates shall be durable and legible throughout equipment life and made of anodized aluminum. Plates shall be fixed in prominent locations with nonferrous screws or bolts.

2.15 RELATED COMPONENTS/SERVICES

2.15.1 Drain and Make-Up Water Piping

Requirements for drain and make-up water piping and backflow preventer is specified in Section 22 00 00 PLUMBING, GENERAL PURPOSE.

2.15.2 Field Applied Insulation

Requirements for field installed insulation is specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS, except as supplemented and modified by this specification section.

2.15.3 Field Painting

Requirements for painting of surfaces not otherwise specified, and finish painting of items only primed at the factory, are specified in Section 09 90 00PAINTS AND COATINGS.

2.15.3.1 Color Coding

Requirements for color coding for piping identification are specified in Section 09 90 00 PAINTS AND COATINGS.

PART 3 EXECUTION

3.1 INSTALLATION

Cut pipe accurately to measurements established at the jobsite, and work into place without springing or forcing, completely clearing all windows, doors, and other openings. Cutting or other weakening of the building structure to facilitate piping installation is not permitted without written approval. Cut pipe or tubing square, remove burrs by reaming, and fashion to permit free expansion and contraction without causing damage to the building structure, pipe, joints, or hangers.

Notify the Contracting Officer in writing at least 15 calendar days prior to the date the connections are required. Obtain approval before interrupting service. Furnish materials required to make connections into existing systems and perform excavating, backfilling, compacting, and other incidental labor as required. Furnish labor and tools for making actual connections to existing systems.

3.1.1 Welding

Provide welding work specified this section for piping systems in conformance with ASME B31.9, as modified and supplemented by this specification section and the accompanying drawings. The welding work includes: qualification of welding procedures, welders, welding operators, brazers, brazing operators, and nondestructive examination personnel; maintenance of welding records, and examination methods for welds.

3.1.1.1 Employer's Record Documents (For Welding)

Submit for review and approval the following documentation. This documentation and the subject qualifications shall be in compliance with ASME B31.9.

a. List of qualified welding procedures that is proposed to be used to provide the work specified in this specification section.

b. List of qualified welders, brazers, welding operators, and brazing operators that are proposed to be used to provide the work specified in this specification section.

c. List of qualified weld examination personnel that are proposed to be used to provide the work specified in this specification section.

3.1.1.2 Welding Procedures and Qualifications

a. Specifications and Test Results: Submit copies of the welding procedures specifications and procedure qualification test results for each type of welding required. Approval of any procedure does not relieve the Contractor of the responsibility for producing acceptable welds. Submit this information on the forms printed in ASME BPVC SEC IX or their equivalent.

b. Certification: Before assigning welders or welding operators to the work, submit a list of qualified welders, together with data and certification that each individual is performance qualified as specified. Do not start welding work prior to submitting welder, and welding operator qualifications. The certification shall state the type of welding and positions for which each is qualified, the code and procedure under which each is qualified, date qualified, and the firm and individual certifying the qualification tests.

3.1.1.3 Examination of Piping Welds

Conduct non-destructive examinations (NDE) on piping welds and brazing and verify the work meets the acceptance criteria specified in ASME B31.9. NDE on piping welds covered by ASME B31.9 is visual inspection only. Submit a piping welds NDE report meeting the requirements specified in ASME B31.9.

3.1.1.4 Welding Safety

Welding and cutting safety requirements shall be in accordance with AWS Z49.1.

3.1.2 Directional Changes

Make changes in direction with fittings, except that bending of pipe 4 inches and smaller is permitted, provided a pipe bender is used and wide weep bends are formed. Mitering or notching pipe or other similar construction to form elbows or tees is not permitted. The centerline radius of bends shall not be less than 6 diameters of the pipe. Bent pipe showing kinks, wrinkles, flattening, or other malformations is not acceptable.

3.1.3 Functional Requirements

Pitch horizontal supply mains down in the direction of flow as indicated. The grade shall not be less than 1 inch in 40 feet. Reducing fittings shall be used for changes in pipe sizes. Cap or plug open ends of pipelines and equipment during installation to keep dirt or other foreign materials out of the system.

Pipe not otherwise specified shall be uncoated. Connections to appliances shall be made with malleable iron unions for steel pipe 2-1/2 inches or less in diameter, and with flanges for pipe 3 inches and above in diameter. Connections between ferrous and copper piping shall be electrically isolated from each other with dielectric waterways or flanges.

Piping located in air plenums shall conform to NFPA 90A requirements. Pipe and fittings installed in inaccessible conduits or trenches under concrete floor slabs shall be welded. Equipment and piping arrangements shall fit into space allotted and allow adequate acceptable clearances for installation, replacement, entry, servicing, and maintenance. Electric isolation fittings shall be provided between dissimilar metals.

3.1.4 Fittings and End Connections

3.1.4.1 Threaded Connections

Threaded connections shall be made with tapered threads and made tight with PTFE tape complying with ASTM D3308 or equivalent thread-joint compound applied to the male threads only. Not more than three threads shall show after the joint is made.

3.1.4.2 Brazed Connections

Brazing, AWS BRH, except as modified herein. During brazing, the pipe and fittings shall be filled with a pressure regulated inert gas, such as nitrogen, to prevent the formation of scale. Before brazing copper joints, both the outside of the tube and the inside of the fitting shall be cleaned with a wire fitting brush until the entire joint surface is bright and clean. Do not use brazing flux. Surplus brazing material shall be removed at all joints. Steel tubing joints shall be made in accordance with the manufacturer's recommendations. Piping shall be supported prior to brazing and not be sprung or forced.

3.1.4.3 Welded Connections

Branch connections shall be made with welding tees or forged welding branch outlets. Pipe shall be thoroughly cleaned of all scale and foreign matter before the piping is assembled. During welding, the pipe and fittings shall be filled with an inert gas, such as nitrogen, to prevent the formation of scale. Beveling, alignment, heat treatment, and inspection of weld shall conform to ASME B31.9. Weld defects shall be removed and rewelded at no additional cost to the Government. Electrodes shall be stored and dried in accordance with AWS D1.1/D1.1M or as recommended by the manufacturer. Electrodes that have been wetted or that have lost any of their coating shall not be used.

3.1.4.4 Flared Connections

When flared connections are used, a suitable lubricant shall be used between the back of the flare and the nut in order to avoid tearing the flare while tightening the nut.

3.1.4.5 Flanges and Unions

Except where copper tubing is used, union or flanged joints shall be provided in each line immediately preceding the connection to each piece of equipment or material requiring maintenance such as coils, pumps, control valves, and other similar items. Flanged joints shall be assembled square end tight with matched flanges, gaskets, and bolts. Gaskets shall be suitable for the intended application.

3.1.5 Valves

Isolation gate or ball valves shall be installed on each side of each piece of equipment, at the midpoint of all looped mains, and at any other points indicated or required for draining, isolating, or sectionalizing purpose. Isolation valves may be omitted where balancing cocks are installed to provide both balancing and isolation functions. Each valve except check valves shall be identified. Valves in horizontal lines shall be installed with stems horizontal or above.

3.1.6 Air Vents

Air vents shall be provided at all high points, on all water coils, and where indicated to ensure adequate venting of the piping system.

3.1.7 Drains

Drains shall be provided at all low points and where indicated to ensure complete drainage of the piping. Drains shall be accessible, and shall consist of nipples and caps or plugged tees unless otherwise indicated.

3.1.8 Flexible Pipe Connectors

Connectors shall be attached to components in strict accordance with the latest printed instructions of the manufacturer to ensure a vapor tight joint. Hangers, when required to suspend the connectors, shall be of the type recommended by the flexible pipe connector manufacturer and shall be provided at the intervals recommended.

3.1.9 Temperature Gauges

Temperature gauges shall be located on coolant supply and return piping at each heat exchanger, on condenser water piping entering and leaving a condenser, at each automatic temperature control device without an integral thermometer, and where indicated or required for proper operation of equipment. Thermal wells for insertion thermometers and thermostats shall extend beyond thermal insulation surface not less than 1 inch.

3.1.10 Pipe Hangers, Inserts, and Supports

Pipe hangers, inserts, and supports shall conform to MSS SP-58 and MSS SP-69, except as supplemented and modified in this specification section. Pipe hanger types 5, 12, and 26 shall not be used. Hangers used to support piping 2 inches and larger shall be fabricated to permit adequate adjustment after erection while still supporting the load. Piping subjected to vertical movement, when operating temperatures exceed ambient temperatures, shall be supported by variable spring hangers and supports or by constant support hangers.

3.1.10.1 Hangers

Type 3 shall not be used on insulated piping. Type 24 may be used only on trapeze hanger systems or on fabricated frames.

3.1.10.2 Inserts

Type 18 inserts shall be secured to concrete forms before concrete is placed. Continuous inserts which allow more adjustments may be used if they otherwise meet the requirements for Type 18 inserts.

3.1.10.3 C-Clamps

Type 19 and 23 C-clamps shall be torqued per MSS SP-69 and have both locknuts and retaining devices, furnished by the manufacturer. Field-fabricated C-clamp bodies or retaining devices are not acceptable.

3.1.10.4 Angle Attachments

Type 20 attachments used on angles and channels shall be furnished with an added malleable-iron heel plate or adapter.

3.1.10.5 Saddles and Shields

Where Type 39 saddle or Type 40 shield are permitted for a particular pipe attachment application, the Type 39 saddle, connected to the pipe, shall be used on all pipe 4 inches and larger when the temperature of the medium is 60 degrees F or higher. Type 40 shields shall be used on all piping less than 4 inches and all piping 4 inches and larger carrying medium less than 60 degrees F. A high density insulation insert of cellular glass shall be used under the Type 40 shield for piping 2 inches and larger.

3.1.10.6 Horizontal Pipe Supports

Horizontal pipe supports shall be spaced as specified in MSS SP-69 and a support shall be installed not over 1 foot from the pipe fitting joint at each change in direction of the piping. Pipe supports shall be spaced not over 5 feet apart at valves. Pipe hanger loads suspended from steel joist with hanger loads between panel points in excess of 50 pounds shall have

the excess hanger loads suspended from panel points.

3.1.10.7 Vertical Pipe Supports

Vertical pipe shall be supported at each floor, except at slab-on-grade, and at intervals of not more than 15 feet, not more than 8 feet from end of risers, and at vent terminations.

3.1.10.8 Pipe Guides

Type 35 guides using, steel, reinforced polytetrafluoroethylene (PTFE) or graphite slides shall be provided where required to allow longitudinal pipe movement. Lateral restraints shall be provided as required. Slide materials shall be suitable for the system operating temperatures, atmospheric conditions, and bearing loads encountered.

3.1.10.9 Steel Slides

Where steel slides do not require provisions for restraint of lateral movement, an alternate guide method may be used. On piping 4 inches and larger, a Type 39 saddle shall be used. On piping under 4 inches, a Type 40 protection shield may be attached to the pipe or insulation and freely rest on a steel slide plate.

3.1.10.10 Multiple Pipe Runs

In the support of multiple pipe runs on a common base member, a clip or clamp shall be used where each pipe crosses the base support member. Spacing of the base support members shall not exceed the hanger and support spacing required for an individual pipe in the multiple pipe run.

3.1.10.11 Structural Attachments

Attachment to building structure concrete and masonry shall be by cast-in concrete inserts, built-in anchors, or masonry anchor devices. Inserts and anchors shall be applied with a safety factor not less than 5. Supports shall not be attached to metal decking. Supports shall not be attached to the underside of concrete filled floors or concrete roof decks unless approved by the Contracting Officer. Masonry anchors for overhead applications shall be constructed of ferrous materials only. Structural steel brackets required to support piping, headers, and equipment, but not shown, shall be provided under this section.

3.1.11 Pipe Alignment Guides

Pipe alignment guides shall be provided where indicated for expansion loops, offsets, and bends and as recommended by the manufacturer for expansion joints, not to exceed 5 feet on each side of each expansion joint, and in lines 4 inches or smaller not more than 2 feet on each side of the joint.

3.1.12 Pipe Anchors

Anchors shall be provided where indicated. Unless indicated otherwise, anchors shall comply with the requirements specified. Anchors shall consist of heavy steel collars with lugs and bolts for clamping and attaching anchor braces, unless otherwise indicated. Anchor braces shall be installed in the most effective manner to secure the desired results using turnbuckles where required.

Supports, anchors, or stays shall not be attached where they will injure the structure or adjacent construction during installation or by the weight of expansion of the pipeline. Where pipe and conduit penetrations of vapor barrier sealed surfaces occur, these items shall be anchored immediately adjacent to each penetrated surface, to provide essentially zero movement within penetration seal.

3.1.13 Building Surface Penetrations

Sleeves shall not be installed in structural members except where indicated or approved. Except as indicated otherwise piping sleeves shall comply with requirements specified. Sleeves in nonload bearing surfaces shall be galvanized sheet metal, conforming to ASTM A653/A653M, Coating Class G-90, 20 gauge. Sleeves in load bearing surfaces shall be uncoated carbon steel pipe, conforming to ASTM A53/A53M, Schedule 20. Sealants shall be applied to moisture and oil-free surfaces and elastomers to not less than 1/2 inch depth. Sleeves shall not be installed in structural members.

3.1.13.1 General Service Areas

Each sleeve shall extend through its respective wall, floor, or roof, and shall be cut flush with each surface. Pipes passing through concrete or masonry wall or concrete floors or roofs shall be provided with pipe sleeves fitted into place at the time of construction. Sleeves shall be of such size as to provide a minimum of 1/4 inch all-around clearance between bare pipe and sleeves or between jacketed-insulation and sleeves. Except in pipe chases or interior walls, the annular space between pipe and sleeve or between jacket over-insulation and sleeve shall be sealed in accordance with Section 07 92 00 JOINT SEALANTS.

3.1.13.2 Waterproof Penetrations

Pipes passing through roof or floor waterproofing membrane shall be installed through a .17 ounce copper sleeve, or a 0.032 inch thick aluminum sleeve, each within an integral skirt or flange.

Flashing sleeve shall be suitably formed, and skirt or flange shall extend not less than 8 inches from the pipe and be set over the roof or floor membrane in a troweled coating of bituminous cement. The flashing sleeve shall extend up the pipe a minimum of 2 inches above the roof or floor penetration. The annular space between the flashing sleeve and the bare pipe or between the flashing sleeve and the metal-jacket-covered insulation shall be sealed as indicated. Penetrations shall be sealed by either one of the following methods.

a. Waterproofing Clamping Flange: Pipes up to and including 10 inches in diameter passing through roof or floor waterproofing membrane may be installed through a cast iron sleeve with caulking recess, anchor lugs, flashing clamp device, and pressure ring with brass bolts. Waterproofing membrane shall be clamped into place and sealant shall be placed in the caulking recess.

b. Modular Mechanical Type Sealing Assembly: In lieu of a waterproofing clamping flange, a modular mechanical type sealing assembly may be installed. Seals shall consist of interlocking synthetic rubber links shaped to continuously fill the annular space between the pipe/conduit and sleeve with corrosion protected carbon steel bolts, nuts, and

pressure plates. Links shall be loosely assembled with bolts to form a continuous rubber belt around the pipe with a pressure plate under each bolt head and each nut.

After the seal assembly is properly positioned in the sleeve, tightening of the bolt shall cause the rubber sealing elements to expand and provide a watertight seal rubber sealing elements to expand and provide a watertight seal between the pipe/conduit seal between the pipe/conduit and the sleeve. Each seal assembly shall be sized as recommended by the manufacturer to fit the pipe/conduit and sleeve involved. The Contractor electing to use the modular mechanical type seals shall provide sleeves of the proper diameters.

3.1.13.3 Fire-Rated Penetrations

Penetration of fire-rated walls, partitions, and floors shall be sealed as specified in Section 07 84 00 FIRESTOPPING.

3.1.13.4 Escutcheons

Finished surfaces where exposed piping, bare or insulated, pass through floors, walls, or ceilings, except in boiler, utility, or equipment rooms, shall be provided with escutcheons. Where sleeves project slightly from floors, special deep-type escutcheons shall be used. Escutcheon shall be secured to pipe or pipe covering.

3.1.14 Access Panels

Access panels shall be provided where indicated for all concealed valves, vents, controls, and additionally for items requiring inspection or maintenance. Access panels shall be of sufficient size and located so that the concealed items may be serviced and maintained or completely removed and replaced. Access panels shall be as specified in Section 08 31 00 ACCESS DOORS AND PANELS.

3.1.15 Heat Trace Cable

Field apply heater tape and cut to fit as necessary, linearly along the length of pipe after piping has been pressure tested and approved by the Contracting Officer. Secure the heater to piping with cable ties . Label thermal insulation on the outside, "Electrical Heat Trace."

Install power connection, end seals, splice kits and tee kit components in accordance with IEEE 515 to provide a complete workable system. Terminate connection to the thermostat and ends of the heat tape in a junction box. Ensure cable and conduit connections are raintight.

3.2 ELECTRICAL INSTALLATION

Install electrical equipment in accordance with NFPA 70 and manufacturers instructions.

3.3 CLEANING AND ADJUSTING

Pipes shall be cleaned free of scale and thoroughly flushed of all foreign matter. A temporary bypass shall be provided for all water coils to prevent flushing water from passing through coils. Strainers and valves shall be thoroughly cleaned. Prior to testing and balancing, air shall be removed from all water systems by operating the air vents. Temporary

measures, such as piping the overflow from vents to a collecting vessel shall be taken to avoid water damage during the venting process. Air vents shall be plugged or capped after the system has been vented. Control valves and other miscellaneous equipment requiring adjustment shall be adjusted to setting indicated or directed.

3.4 FIELD TESTS

Field tests shall be conducted in the presence of the QC Manager or his designated representative to verify systems compliance with specifications. Any material, equipment, instruments, and personnel required for the test shall be provided by the Contractor.

3.4.1 Equipment and Component Isolation

Prior to testing, equipment and components that cannot withstand the tests shall be properly isolated.

3.4.2 Pressure Tests

Each piping system , except for polypropylene piping, shall be hydrostatically tested at a pressure not less than 188 psig for period of time sufficient to inspect every joint in the system and in no case less than 2 hours. Test pressure shall be monitored by a currently calibrated test pressure gauge. Leaks shall be repaired and piping retested until test requirements are met. No leakage or reduction in gage pressure shall be allowed.

Leaks shall be repaired by rewelding or replacing pipe or fittings. Caulking of joints will not be permitted. Concealed and insulated piping shall be tested in place before concealing.

Submit for approval pressure tests reports covering the above specified piping pressure tests; describe the systems tested, test results, defects found and repaired, and signature of the pressure tests' director. Obtain approval from the QC Manager before concealing piping or applying insulation to tested and accepted piping.

3.4.3 Heat Trace Cable

Test heat trace cable system in accordance with IEEE 515 after installation and before and after installation of the thermal insulation. Test heater cable using a 1000 vdc megger. Minimum insulation resistance is 20 to 1000 megohms regardless of cable length.

3.4.4 Related Field Inspections and Testing

3.4.4.1 Piping Welds

Examination of Piping Welds is specified in the paragraph EXAMINATION OF PIPING WELDS (above).

3.4.4.2 HVAC TAB

Requirements for testing, adjusting, and balancing (TAB) of HVAC water piping, and associated equipment is specified in Section 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC. Coordinate with the TAB team, and provide support personnel and equipment as specified in Section 23 05 93 TESTING, ADJUSTING AND BALANCING FOR HVAC to assist TAB team to meet the

TAB work requirements.

3.5 INSTRUCTION TO GOVERNMENT PERSONNEL

Furnish the services of competent instructors to give full instruction to the designated Government personnel in the adjustment, operation, and maintenance, including pertinent safety requirements, of the chilled water, . Instructors shall be thoroughly familiar with all parts of the installation and shall be instructed in operating theory as well as practical operation and maintenance work. Submit a lesson plan for the instruction course for approval. The lesson plan and instruction course shall be based on the approved operation and maintenance data and maintenance manuals.

Conduct a training course for the operating staff and maintenance staff selected by the Contracting Officer. Give the instruction during the first regular work week after the equipment or system has been accepted and turned over to the Government for regular operation. The number of man-days (8 hours per day) of instruction furnished shall be one man-day.. Use approximately half of the time for classroom instruction and the other time for instruction at the location of equipment or system.

When significant changes or modifications in the equipment or system are made under the terms of the contract, provide additional instruction to acquaint the operating personnel with the changes or modifications.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 81 00

DECENTRALIZED UNITARY HVAC EQUIPMENT
05/24

PART 1 GENERAL

1.1 RELATED REQUIREMENTS

Section 23 03 00.00 20 BASIC MECHANICAL MATERIALS AND METHODS BASIC MECHANICAL MATERIALS AND METHODS, applies to this section with the additions and modifications specified herein.

1.2 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AIR-CONDITIONING, HEATING AND REFRIGERATION INSTITUTE (AHRI)

AHRI 700	(2016) Specifications for Fluorocarbon Refrigerants
ANSI/AHRI 210/240	(2008; Add 1 2011; Add 2 2012) Performance Rating of Unitary Air-Conditioning & Air-Source Heat Pump Equipment
ANSI/AHRI 460	(2005) Performance Rating of Remote Mechanical-Draft Air-Cooled Refrigerant Condensers

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ANSI/ASHRAE 15 & 34	(2022) ASHRAE Standard 15-Safety Standard for Refrigeration Systems and ANSI/ASHRAE Standard 34-Designation and Safety Classification of Refrigerants
ASHRAE 15 & 34	(2022) ASHRAE Standard 34-2016 Safety Standard for Refrigeration Systems/ASHRAE Standard 34-2016 Designation and Safety Classification of Refrigerants-ASHRAE Standard 34-2016
ASHRAE 52.2	(2025) Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size
ASHRAE 55	(2017) Thermal Environmental Conditions for Human Occupancy
ASHRAE 62.1	(2016) Ventilation for Acceptable Indoor Air Quality

ASHRAE 90.1 - IP	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME BPVC SEC IX	(2017; Errata 2018) BPVC Section IX-Welding, Brazing and Fusing Qualifications
ASME BPVC SEC VIII D1	(2023) BPVC Section VIII-Rules for Construction of Pressure Vessels Division 1

AMERICAN WELDING SOCIETY (AWS)

AWS Z49.1	(2021) Safety in Welding, Cutting and Allied Processes

ASTM INTERNATIONAL (ASTM)

ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM D520	(2025) Standard Specification for Zinc Dust Pigment
ASTM E84	(2025) Standard Test Method for Surface Burning Characteristics of Building Materials

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 00001	(2024) Motors and Generators
NEMA MG 2	(2014) Safety Standard for Construction and Guide for Selection, Installation and Use of Electric Motors and Generators

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-DTL-5541	(2006; Rev F; Notice 2 2024) Chemical Conversion Coatings on Aluminum and Aluminum Alloys

UL SOLUTIONS (UL)

UL 1995	(2015; Reprint Aug 2022) UL Standard for Safety Heating and Cooling Equipment

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Spare Parts

Posted Instructions

Coil Corrosion Protection

System Performance Tests

Training; G

Inventory

Supplied Products

Manufacturer's Standard Catalog Data

Dehumidifiers

SD-06 Test Reports

Refrigerant Tests, Charging, and Start-Up; G

System Performance Tests; G

SD-07 Certificates

Service Organizations

SD-10 Operation and Maintenance Data

Operation and Maintenance Manuals; G

SD-11 Closeout Submittals

Ozone Depleting Substances; S

1.4 QUALITY ASSURANCE

Carefully investigate the plumbing, fire protection, electrical, structural and finish conditions that would affect the work to be performed and arrange such work accordingly, furnishing required offsets, fittings, and accessories to meet such conditions. Submit drawings consisting of:

a. Equipment layouts which identify assembly and installation details.

b. Plans and elevations which identify clearances required for maintenance and operation.

c. Wiring diagrams which identify each component individually and interconnected or interlocked relationships between components.

d. Foundation drawings, bolt-setting information, and foundation bolts prior to concrete foundation construction for equipment indicated or required to have concrete foundations.

e. Details, if piping and equipment are to be supported other than as indicated, which include loadings and type of frames, brackets, stanchions, or other supports.

f. Automatic temperature control diagrams and control sequences.

g. Installation details which includes the amount of factory set superheat and corresponding refrigerant pressure/temperature.

h. Equipment schedules

1.5 DELIVERY, STORAGE, AND HANDLING

Protect stored items from the weather, humidity and temperature variations, dirt and dust, or other contaminants. Properly protect and care for all material both before and during installation. Submit an inventory of all the stored items. Replace any materials found to be damaged, at no additional cost to the Government. During installation, cap piping and similar openings capped to keep out dirt and other foreign matter.

1.6 ENVIRONMENTAL REQUIREMENTS

For proper Indoor Environmental Quality, maintain pressure within the building as indicated. Ventilation must meet or exceed ASHRAE 62.1 and all published addenda. Meet or exceed filter media efficiency as tested in accordance with ASHRAE 52.2. Thermal comfort must meet or exceed ASHRAE 55.

1.7 WARRANTY

Provide equipment with the Manufacturer's Standard Warranty.

PART 2 PRODUCTS

2.1 ENERGY EFFICIENCY REQUIREMENTS

42 USC 8259b requires the procurement of energy efficient products in product categories covered by the Energy Star program or the Federal Energy Management Program for designated products. A list of covered product categories is available from the Federal Energy Management Web site at: https://www.energy.gov/femp/search-energy-efficient-products.

Submit Material, Equipment, and Fixtures List of all supplied products within a covered product category, including manufacturer's catalog numbers, specification and drawing reference number, warranty information, fabrication site, and energy performance data. For product categories covered by the Federal Energy Management Program, submit documentation that the product meets or exceeds FEMP-designated efficiency requirements.

2.2 MATERIALS

Provide Manufacturer's standard catalog data, at least 5 weeks prior to the purchase or installation of a particular component, highlighted to show material, size, options, performance charts and curves, etc. in adequate detail to demonstrate compliance with contract requirements. Data includes manufacturer's recommended installation instructions and procedures. If vibration isolation is specified for a unit, include vibration isolator literature containing catalog cuts and certification that the isolation characteristics of the isolators provided meet the manufacturer's recommendations. Submit data for each specified component. Minimum efficiency requirements must be in accordance with ASHRAE 90.1 - IP.

2.2.1 Standard Products

Provide materials and equipment that are standard products of a manufacturer regularly engaged in the manufacturing of such products, which are of a similar material, design and workmanship. The standard products must have been in satisfactory commercial or industrial use for 2 years prior to bid opening . The 2 year use includes applications of equipment and materials under similar circumstances and of similar size. The 2 years' experience must be satisfactorily completed by a product which has been sold or is offered for sale on the commercial market through advertisements, manufacturer's catalogs, or brochures. Products having less than a 2 year field service record will be acceptable if a certified record of satisfactory field operation, for not less than 6000 hours exclusive of the manufacturer's factory tests, can be shown. Products must be supported by a service organization. Ensure system components are environmentally suitable for the indicated geographic locations.

2.2.2 Product Sustainability Criteria

2.2.2.1 Energy Efficient Equipment

Provide equipment meeting the efficiency requirements as stated within this section and provide documentation in conformance with Section 01 33 29 SUSTAINABILITY REQUIREMENTS AND REPORTING paragraph ENERGY EFFICIENT EQUIPMENT.

2.2.2.2 Electrical Equipment / Motors

Provide electrical equipment, motors, motor efficiencies, and wiring which are in accordance with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Electrical motor driven equipment specified must be provided complete with motors, motor starters, and controls. Electrical characteristics must be as shown, and unless otherwise indicated, all motors of 1 horsepower and above with open, dripproof, totally enclosed, or explosion proof fan cooled enclosures, must be the premium efficiency type in accordance with NEMA MG 00001. Field wiring must be in accordance with manufacturer's instructions. Each motor must conform to NEMA MG 00001 and NEMA MG 2 and be of sufficient size to drive the equipment at the specified capacity without exceeding the nameplate rating of the motor. Motors must be continuous duty with the enclosure specified. Motor starters must be provided complete with thermal overload protection and other appurtenances necessary for the motor control indicated. Motors must be furnished with a magnetic across-the-line or reduced voltage type starter as required by the manufacturer. Motor duty requirements must allow for maximum frequency start-stop operation and minimum encountered interval between start and stop. Motors must be sized for the applicable loads. Motor torque must be capable of accelerating the connected load within 20 seconds with 80 percent of the rated voltage maintained at motor terminals during one starting period. Motor bearings must be fitted with grease supply fittings and grease relief to outside of enclosure. Manual or automatic control and protective or signal devices required for the operation specified and any control wiring required for controls and devices specified, but not shown, must be provided.

2.2.2.3 Ozone Depleting Substances

Unitary air conditioning equipment must not use CFC-based refrigerants.

Refrigerant may be an approved alternative refrigerant in accordance with EPA's Significant New Alternative Policy (SNAP) listing. Provide documentation in conformance with Section 01 33 29 SUSTAINABILITY REQUIREMENTS AND REPORTING paragraph OZONE DEPLETING SUBSTANCES.

2.2.3 Nameplates

Major equipment including compressors, condensers, receivers, heat exchanges, fans, and motors must have the manufacturer's name, address, type or style, model or serial number, and catalog number on a plate secured to the item of equipment. Plates must be durable and legible throughout equipment life and made of anodized aluminum . Fix plates in prominent locations with nonferrous screws or bolts.

2.2.4 Safety Devices

Exposed moving parts, parts that produce high operating temperature, parts which may be electrically energized, and parts that may be a hazard to operating personnel must be insulated, fully enclosed, guarded, or fitted with other types of safety devices. Safety devices must be installed so that proper operation of equipment is not impaired. Welding and cutting safety requirements must be in accordance with AWS Z49.1.

2.3 EQUIPMENT

2.3.1 Mini-Split-System Air Conditioners & Heat Pumps

2.3.1.1 Small-Capacity Split-System Air-Conditioners (Not Exceeding 65,000 Btu/hr)

Provide an air-cooled, split system which employs a remote condensing unit, a separate wall mounted or ceiling mounted indoor unit, and interconnecting refrigerant piping. Provide the air conditioning or heat pump type unit conforming to applicable Underwriters Laboratories (UL) standards including UL 1995. Unit must be rated in accordance with ANSI/AHRI 210/240. Provide indoor unit with necessary fans, air filters, and galvanized steel cabinet construction. The remote unit must be as specified in paragraph CONDENSING UNIT. Provide double-width, double inlet, forward curved backward inclined, or airfoil blade, centrifugal scroll type evaporator or supply fans. Provide the manufacturer's standard condenser or outdoor fans for the unit specified and may be either propeller or centrifugal scroll type. Fan and condenser motors must have opendrip proof enclosures. Design unit to operate at outdoor ambient temperatures up to 115 degrees F.

2.3.1.1.1 Air-to-Refrigerant Coil

Provide condensing coils with copper tubes of 3/8 inch minimum diameter with aluminum fins that are mechanically bonded or soldered to the tubes. Casing must be galvanized steel or aluminum. Avoid contact of dissimilar metals. Test coils in accordance with ASHRAE 15 & 34 at the factory and ensure suitability for the working pressure of the installed system. Dehydrate and seal each coil testing and prior to evaluation and charging.

Coat condenser and evaporator coil with a uniformly applied epoxy electrodeposition, phenolic, or vinyl type coating to all coil surface areas without material bridging between fins. Apply coating at either the coil or coating manufacturer's factory. Coating process must ensure complete coil encapsulation and be capable of withstanding a minimum 1,000

hours exposure to the salt spray test specified in ASTM B117 using a 5 percent sodium chloride solution.

2.3.1.1.2 Refrigeration Circuit

Refrigerant-containing components must comply with ASHRAE 15 & 34 and be factory tested, cleaned, dehydrated, charged, and sealed. Provide each unit with a factory operating charge of refrigerant and oil or a holding charge. Field charge unit shipped with a holding charge. Provide refrigerant charging valves. Provide filter-drier in liquid line.to prevent freeze-up in event of loss of water flow during heating cycle.

2.3.1.1.3 Unit Controls

Provide unit internally prewired with a 24 volt control circuit powered by an internal transformer. Provide terminal blocks for power wiring and external control wiring. Internally protect unit by fuses or a circuit breaker in accordance with UL 1995. Equip units with three-phase power with phase monitoring protection to protect against problems caused by phase loss, phase imbalance and phase reversal. Provide unit with microprocessor controls to provide all 24V control functions.

Controls must include a control system interface to a BACnet Control system. The control system interface, as well as any network between physically separate units, must meet the requirements of Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS.

Communication networks between physically separate units in a split system must be in accordance with either Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS. and must match the protocol used by the control system interface.

2.3.1.1.4 Condensing Coil

Provide coils with copper tubes of 3/8 inch minimum diameter with aluminum fins that are mechanically bonded or soldered to the tubes. Protect coil in accordance with paragraph CORROSION PROTECTION. Provide galvanized steel or aluminum casing. Avoid contact of dissimilar metals. Test coils in accordance with ANSI/ASHRAE 15 & 34 at the factory and ensure suitability for the working pressure of the installed system. Dehydrate and seal each coil after testing and prior to evaluation and charging. Provide separate expansion devices for each compressor circuit.

2.3.1.1.5 Remote Condenser or Condensing Unit

Fit each remote condenser coil fitted with a manual isolation valve and an access valve on the coil side. Saturated refrigerant condensing temperature must not exceed 120 degrees F at 104 degrees F ambient. Provide unit with low ambient condenser controls to ensure proper operation in an ambient temperature of 20degrees F. Provide fan and cabinet construction as specified in paragraph UNITARY EQUIPMENT ACCESSORIES. Fan and condenser motors must have opendrip proof enclosures.

2.3.1.1.5.1 Air-Cooled Condenser

Provide Unit in accordance with ANSI/AHRI 460 and conform to the requirements of UL 1995. Provide factory fabricated, tested, packaged, and self-contained unit; complete with casing, propeller or centrifugal

type fans, heat rejection coils, connecting piping and wiring, and all necessary accessories.

2.3.1.1.6 Primary/Supplemental Heat

Provide heating unit with internal thermal insulation having a fire hazard rating not to exceed 25 for flame spread and 50 for smoke developed as determined by ASTM E84.

2.3.1.1.7 Air Filters

Provide filters of the sectional or cleanable type that are capable of filtering the entire air supply. Mount filter(s) integral within the unit and make accessible by hinged access panel(s). 1 inch MERV 7, provide throwaway filter on all units below 6 Tons.

Provide filter rack that can be converted to 2.0 inch capability. Filters must have an average dust spot efficiency of 25-35 percent and an average arrestance of 90 percent when tested in accordance with ASHRAE 52.2. Provide UL Class 1 filters.

2.3.1.1.8 Fans

Provide direct driven, statically and dynamically balanced, centrifugal type fans. Design the outdoor fan so that condensate will evaporate without drip, splash, or spray on building exterior. Provide indoor fan with a minimum two-speed motor with built-in overload protection. Fan motors must be the inherently protected, permanent split-capacitor type.

2.3.2 Dehumidifiers

2.3.2.1 General

Unit must be a factory assembled, self-contained dehumidifier unit as indicated. Unit must be provided with a full factory operating charge of refrigerant. Unit must be suitable for indoor installation, continuous-duty operation. Provide all mounting accessories required for hard-mounting unit.

2.3.2.2 Air-to-Refrigerant Coils

Air-to-refrigerant coils must have seamless copper tubes of 5/16 inch minimum diameter with aluminum fins that are mechanically bonded or soldered to the tubes. Casing must be galvanized steel or aluminum. Contact of dissimilar metals must be avoided. Coils must be tested in accordance with ANSI/ASHRAE 15 & 34 at the factory and be suitable for the working pressure of the installed system. Each coil must be factory pressure and leak tested.

2.3.2.3 Fan Section

Fan must be the centrifugal type in accordance with paragraph FANS. Motors must have totally enclosed enclosure and be suitable for the indicated service. The unit design must prevent water from entering into the fan section.

2.3.2.4 Compressor

Provide direct drive, scroll type Compressor. Compressor must have

internal over current and over temperature protection.

2.3.2.5 Refrigeration Circuit

Refrigerant containing components must comply with ANSI/ASHRAE 15 & 34 and be factory tested, cleaned, dehydrated, charged, and sealed. Refrigerant lines must have service pressure tap ports and refrigerant line filter.

2.3.2.6 Unit Controls

Provide units internally prewired by manufacturer with a 24 volt control circuit powered by an internal transformer. Terminal blocks must be provided for power wiring and external control wiring. Unit must be internally protected by fuses in accordance with UL 1995.

2.3.2.7 Single Source Power Entry

Provide single source power entry to allow hard-wired single source power connection to unit with fuse protection as required for the unit.

2.3.2.8 Filters

Provide unit with a washable or throwaway type pre-filter.

2.3.2.9 Condensate Drain Piping

Provide hard piped condensate drain in accordance with Section 23 30 00 HVAC AIR DISTRIBUTION.

2.4 COMPONENTS

2.4.1 Refrigerant and Oil

Refrigerant must be one of the fluorocarbon gases. Refrigerants must have number designations and safety classifications in accordance with ASHRAE 15 & 34. Refrigerants must meet the requirements of AHRI 700 as a minimum. Provide a complete charge of refrigerant for the installed system as recommended by the manufacturer. Lubricating oil must be of a type and grade recommended by the manufacturer for each compressor. Where color leak indicator dye is incorporated, charge must be in accordance with manufacturer's recommendation.

2.4.2 Refrigerant Piping

Provide refrigerant piping in accordance with Section 23 23 00 REFRIGERANT PIPING.

2.4.3 Temperature Controls

Provide temperature controls in accordance with Section 23 09 23.02 BACnet DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDNG CONTROL SYSTEMS.

2.5 FINISHES

2.5.1 Coil Corrosion Protection

Provide coil with a uniformly applied epoxy electrodeposition, phenolic, or vinyl type coating to all coil surface areas without material bridging between fins. Submit product data on the type coating selected, the

coating thickness, the application process used, the estimated heat transfer loss of the coil, and verification of conformance with the salt spray test requirement. Coating must be applied at either the coil or coating manufacturer's factory. Coating process must ensure complete coil encapsulation. Coating must be capable of withstanding a minimum 1,000 hours exposure to the salt spray test specified in ASTM B117 using a 5 percent sodium chloride solution.

2.5.2 Equipment and Components Factory Coating

Unless otherwise specified, equipment and component items, when fabricated from ferrous metal, must be factory finished with the manufacturer's standard finish, except that items located outside of buildings must have weather resistant finishes that will withstand 500 hours exposure to the salt spray test specified in ASTM B117 using a 5 percent sodium chloride solution. Immediately after completion of the test, the specimen must show no signs of blistering, wrinkling, cracking, or loss of adhesion and no sign of rust creepage beyond 1/8 inch on either side of the scratch mark. Cut edges of galvanized surfaces where hot-dip galvanized sheet steel is used must be coated with a zinc-rich coating conforming to ASTM D520, Type I.

Where stipulated in equipment specifications of this section, coat finned tube coils of the affected equipment as specified below. Apply coating at the premises of a company specializing in such work. Degrease and prepare for coating in accordance with the coating applicator's procedures for the type of metals involved. Completed coating must show no evidence of softening, blistering, cracking, crazing, flaking, loss of adhesion, or "bridging" between the fins.

2.5.2.1 Phenolic Coating

Provide a resin base thermosetting phenolic coating. Apply coating by immersion dipping of the entire coil. Provide a minimum of two coats. Bake or heat dry coils following immersions. After final immersion and prior to final baking, spray entire coil with particular emphasis given to building up coating on sheared edges. Total dry film thickness must be 2.5 to 3.0 mils.

2.5.2.2 Chemical Conversion Coating with Polyelastomer Finish Coat

Dip coils in a chemical conversion solution to molecularly deposit a corrosion resistant coating by electrolysis action. Chemical conversion coatings must conform to MIL-DTL-5541, Class 1A. Cure conversion coating at a temperature of 110 to 140 degrees F for a minimum of 3 hours. Coat coil surfaces with a complex polymer primer with a dry film thickness of 1 mil. Cure primer coat for a minimum of 1 hour. Using dip tank method, provide three coats of a complex polyelastomer finish coat. After each of the first two finish coats, cure the coils for 1 hour. Following the third coat, spray a fog coat of an inert sealer on the coil surfaces. Total dry film thickness must be 2.5 to 3.0 mils. Cure finish coat for a minimum of 3 hours. Coating materials must have 300 percent flexibility, operate in temperatures of minus 50 to plus 220 degrees F, and protect against atmospheres of a pH range of 1 to 14.

2.5.2.3 Vinyl Coating

Apply coating using an airless fog nozzle. For each coat, make at least two passes with the nozzle. Materials to be applied are as follows:

a. Total dry film thickness, 6.5 mils maximum

b. Vinyl Primer, 24 percent solids by volume: One coat 2 mils thick

c. Vinyl Copolymer, 30 percent solids by volume: One coat 4.5 mils thick

2.5.3 Factory Applied Insulation

Refrigeration equipment must be provided with factory installed insulation on surfaces subject to sweating including the suction line piping. Where motors are the gas-cooled type, factory installed insulation must be provided on the cold-gas inlet connection to the motor in accordance with manufacturer's standard practice. Factory insulated items installed outdoors are not required to be fire-rated. As a minimum, factory insulated items installed indoors must have a flame spread index no higher than 75 and a smoke developed index no higher than 150. Factory insulated items (no jacket) installed indoors and which are located in air plenums, in ceiling spaces, and in attic spaces must have a flame spread index no higher than 25 and a smoke developed index no higher than 50. Flame spread and smoke developed indexes must be determined by ASTM E84. Insulation must be tested in the same density and installed thickness as the material to be used in the actual construction. Material supplied by a manufacturer with a jacket must be tested as a composite material. Jackets, facings, and adhesives must have a flame spread index no higher than 25 and a smoke developed index no higher than 50 when tested in accordance with ASTM E84.

2.6 TESTS, INSPECTIONS, AND VERIFICATIONS

All manufactured units must be inspected and tested, and documentation provided to demonstrate that each unit is in compliance with ANSI/AHRI and UL requirements and that the minimum efficiency requirements of ASHRAE 90.1 - IP have been met.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the work, perform Verification of Dimensions in the field, and advise the Contracting Officer of any discrepancy before performing any work.

3.2 INSTALLATION

Perform work in accordance with the manufacturer's published diagrams, recommendations, and equipment warranty requirements. Where equipment is specified to conform to the requirements of ASME BPVC SEC VIII D1and ASME BPVC SEC IX, the design, fabrication, and installation of the system must conform to ASME BPVC SEC VIII D1 and ASME BPVC SEC IX.

3.2.1 Equipment

Provide refrigeration equipment conforming to ASHRAE 15 & 34. Provide necessary supports for all equipment, appurtenances, and pipe as required, including frames or supports for compressors, pumps, cooling towers, condensers, and similar items. Isolate compressors from the building structure. If mechanical vibration isolators are not provided, provide vibration absorbing foundations. Each foundation must include isolation

units consisting of machine and floor or foundation fastenings, together with intermediate isolation material. Other floor-mounted equipment must be set on not less than a 6 inch concrete pad doweled in place. Concrete foundations for floor mounted pumps must have a mass equivalent to three times the weight of the components, pump, base plate, and motor to be supported. In lieu of concrete pad foundation, concrete pedestal block with isolators placed between the pedestal block and the floor may be provided. Concrete pedestal block must be of mass not less than three times the combined pump, motor, and base weights. Isolators must be selected and sized based on load-bearing requirements and the lowest frequency of vibration to be isolated. Isolators must limit vibration to 20-40 percent at lowest equipment rpm. Provide lines connected to pumps mounted on pedestal blocks with flexible connectors. Provide foundation drawings, bolt-setting information, and foundation bolts prior to concrete foundation construction for all equipment indicated or required to have concrete foundations. Concrete for foundations must be as specified in Section 03 30 00 CAST-IN-PLACE CONCRETE. Equipment must be properly leveled, aligned, and secured in place in accordance with manufacturer's instructions.

3.2.2 Mechanical Room Ventilation

Provide mechanical ventilation systems in accordance with Section 23 30 00 HVAC AIR DISTRIBUTION.

3.2.3 Field Applied Insulation

Apply field applied insulation as specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS, except as defined differently herein.

3.2.4 Field Painting

Painting required for surfaces not otherwise specified, and finish painting of items only primed at the factory are specified in Section 09 90 00 PAINTS AND COATINGS.

3.3 CLEANING AND ADJUSTING

Equipment must be wiped clean, with all traces of oil, dust, dirt, or paint spots removed. Temporary filters must be provided for all fans that are operated during construction, and new filters must be installed after all construction dirt has been removed from the building. System must be maintained in this clean condition until final acceptance. Bearings must be properly lubricated with oil or grease as recommended by the manufacturer. Belts must be tightened to proper tension. Control valves and other miscellaneous equipment requiring adjustment must be adjusted to setting indicated or directed. Fans must be adjusted to the speed indicated by the manufacturer to meet specified conditions. Testing, adjusting, and balancing must be as specified in Section 23 05 93 TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS.

3.4 TRAINING

Conduct a training course for the operating staff as designated by the Contracting Officer. The training period must consist of a total 8 hours of normal working time and start after the system is functionally completed but prior to final acceptance tests.

a. Submit a schedule, at least 2 weeks prior to the date of the proposed

training course, which identifies the date, time, and location for the training.

b. Submit the field posted instructions, at least 2 weeks prior to construction completion, including equipment layout, wiring and control diagrams, piping, valves and control sequences, and typed condensed operation instructions. The condensed operation instructions must include preventative maintenance procedures, methods of checking the system for normal and safe operation, and procedures for safely starting and stopping the system. The posted instructions must be framed under glass or laminated plastic and be posted where indicated by the Contracting Officer.

c. The posted instructions must cover all of the items contained in the approved operation and maintenance manuals as well as demonstrations of routine maintenance operations. Submit 6 complete copies of an operation manual in bound 8-1/2 by 11 inch booklets listing step-by-step procedures required for system startup, operation, abnormal shutdown, emergency shutdown, and normal shutdown at least 4 weeks prior to the first training course. The booklets must include the manufacturer's name, model number, and parts list. The manuals must include the manufacturer's name, model number, service manual, and a brief description of all equipment and their basic operating features.

d. Submit 6 complete copies of maintenance manual in bound 8-1/2 by 11 inch booklets listing routine maintenance procedures, possible breakdowns and repairs, and a trouble shooting guide. The manuals must include piping and equipment layouts and simplified wiring and control diagrams of the system as installed.

3.5 REFRIGERANT TESTS, CHARGING, AND START-UP

Split-system refrigerant piping systems must be tested and charged as specified in Section 23 23 00 REFRIGERANT PIPING. Packaged refrigerant systems which are factory charged must be checked for refrigerant and oil capacity to verify proper refrigerant levels in accordance with manufacturer's recommendations. Following charging, packaged systems must be tested for leaks with a halide torch or an electronic leak detector.

a. The date the tests were performed.
b. A list of equipment used, with calibration certifications.
c. Initial test summaries.
d. Repairs/adjustments performed.
e. Final test results.

3.5.1 Refrigerant Leakage

If a refrigerant leak is discovered after the system has been charged, the leaking portion of the system must immediately be isolated from the remainder of the system and the refrigerant pumped into the system receiver or other suitable container. Under no circumstances must the refrigerant be discharged into the atmosphere.

3.5.2 Contractor's Responsibility

Take steps, at all times during the installation and testing of the refrigeration system, to prevent the release of refrigerants into the atmosphere. The steps must include, but not be limited to, procedures

which will minimize the release of refrigerants to the atmosphere and the use of refrigerant recovery devices to remove refrigerant from the system and store the refrigerant for reuse or reclaim. At no time must more than 3 ounces of refrigerant be released to the atmosphere in any one occurrence. Any system leaks within the first year must be repaired in accordance with the requirements herein at no cost to the Government including material, labor, and refrigerant if the leak is the result of defective equipment, material, or installation.

3.6 SYSTEM PERFORMANCE TESTS

Before each refrigeration system is accepted, conduct tests to demonstrate the general operating characteristics of all equipment by a registered professional engineer or an approved manufacturer's start-up representative experienced in system start-up and testing, at such times as directed. Six copies of the report provided in bound 8-1/2 by 11 inch booklets. The report must document compliance with the specified performance criteria upon completion and testing of the system. The report must indicate the number of days covered by the tests and any conclusions as to the adequacy of the system.

For equipment providing heating and cooling the system performance tests must be performed during the heating and cooling seasons.

a. Submit a schedule, at least 2 weeks prior to the start of related testing, for the system performance tests. The schedules must identify the proposed date, time, and location for each test. Tests must cover a period of not less than 48 hours for each system and must demonstrate that the entire system is functioning in accordance with the drawings and specifications.

b. Make corrections and adjustments, as necessary, tests must be re-conducted to demonstrate that the entire system is functioning as specified. Prior to acceptance, install and tighten service valve seal caps and blanks over gauge points. Replace any refrigerant lost during the system startup.

c. If tests do not demonstrate satisfactory system performance, correct deficiencies and retest the system. Conduct tests in the presence of the Contracting Officer. Water and electricity required for the tests will be furnished by the Government. Provide all material, equipment, instruments, and personnel required for the test.

d. Coordinate field tests with Section 23 05 93 TESTING, ADJUSTING, AND BALANCING OF HVAC SYSTEMS. Submit 6 copies of the report provided in bound 8-1/2 by 11 inch booklets. The report must document compliance with the specified performance criteria upon completion and testing of the system. The report must indicate the number of days covered by the tests and any conclusions as to the adequacy of the system. Submit the report including the following information (where values are taken at least three different times at outside dry-bulb temperatures that are at least 5 degrees F apart):

    (1) Date and outside weather conditions.

    (2) The load on the system based on the following:

        (a) The refrigerant used in the system.
        (b) Condensing temperature and pressure.

(c) Suction temperature and pressure.
(d) Ambient, condensing and coolant temperatures.
(e) Running current, voltage and proper phase sequence for each phase of all motors.

(3) The actual on-site setting of operating and safety controls.

(4) Thermostatic expansion valve superheat - value as determined by field test.

(5) Subcooling.

(6) High and low refrigerant temperature switch set-points

(7) Low oil pressure switch set-point.

(8) Defrost system timer and thermostat set-points.

(9) Moisture content.

(10) Capacity control set-points.

(11) Field data and adjustments which affect unit performance and energy consumption.

(12) Field adjustments and settings which were not permanently marked as an integral part of a device.

3.7 MAINTENANCE

3.7.1 EXTRA MATERIALS

Submit spare parts data for each different item of equipment specified, after approval of detail drawings and not later than 2 months prior to the date of beneficial occupancy. Include in the data a complete list of parts and supplies, with current unit prices and source of supply, a recommended spare parts list for 1 year of operation, and a list of the parts recommended by the manufacturer to be replaced on a routine basis.

3.7.2 Maintenance Service

Submit a certified list of qualified permanent service organizations, which includes their addresses and qualifications, for support of the equipment. The service organizations must be reasonably convenient to the equipment installation and be able to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 23 82 00.00 20

TERMINAL HEATING UNITS
02/16, CHG 1: 08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 33	(2016) Method of Testing Forced Circulation Air Cooling and Air Heating Coils

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM D1654	(2008; R 2016; E 2017) Standard Test Method for Evaluation of Painted or Coated Specimens Subjected to Corrosive Environments

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA ICS 2	(2000; R 2020) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA MG 1	(2021) Motors and Generators

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 54	(2024) National Fuel Gas Code
NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 90A	(2024) Standard for the Installation of Air Conditioning and Ventilating Systems
NFPA 90B	(2024) Standard for the Installation of

	Warm Air Heating and Air Conditioning Systems
NFPA 91	(2020) Standard for Exhaust Systems for Air Conveying of Vapors, Gases, Mists and Noncombustible Particulate Solids
NFPA 211	(2019) Standard for Chimneys, Fireplaces, Vents, and Solid Fuel-Burning Appliances

1.2 RELATED REQUIREMENTS

Section 23 03 00.00 20 BASIC MECHANICAL MATERIALS AND METHODS, applies to this section with additions and modifications specified herein.

1.3 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Unit Heaters

SD-10 Operation and Maintenance Data

Unit Heaters, Data Package 2

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

PART 2 PRODUCTS

2.1 UNIT HEATERS

Self-contained and factory assembled, propeller or centrifugal fan with capacities expressed as Btu per hour output and cubic foot-per-minute air delivery, operating conditions, and mounting arrangements as indicated. Average fan bearing life must be minimum 200,000 hours at operating conditions. Provide fan motor with direct or belt drive. Construct fan-guard motor mount of steel wire. Equip each heater with individually adjustable package discharge louver. Louvers may be substituted by discharge cones or diffusers. Provide thermostats as indicated. Furnish circuit breaker disconnect switch.

2.1.1 Hot-Water Unit Heater

ASHRAE 33 tested for heating coils; UL listed for motor and controls.

2.1.1.1 Casing

Minimum 20 gage steel or aluminum with removable access panels or means to remove, service, and maintain major components.

2.1.1.2 Coil

Fin-and-tube coil constructed of copper, tubes and copper fins. Use maximum design pressure of hot water at 100 psig and 180 degrees F.

2.1.1.3 Controls

As indicated.

2.1.2 Electric Unit Heater

UL listed; wattage, voltage, phase, and number of steps as indicated. Provide control-circuit terminals and single source of power supply. Heater 5 Kw and larger must be three-phase, with load balanced on each of the three phases. Limit leaving air temperature below 140 degrees F at 60 degrees F entering air.

2.1.2.1 Casing

Minimum 21 gage steel.

2.1.2.2 Heating Element

Nickel-chromium heating wire element, free from expansion noise and 60 Hz hum. Embed element in magnesium-oxide insulating refractory. Seal element in high-mass steel or corrosion-resisting metallic sheath with fins. Enclose element ends in terminal box. Space fins at maximum six fins per inch. Limit fin surface temperature 550 degrees Fat any point during normal operation.

2.1.2.3 Controls

Include limit controls for thermal overheat protection of heaters. For remote thermostatic operation, provide contactor rated for 100,000 duty cycles. Provide room thermostat for pilot duty.

2.1.2.4 Wiring

Completely factory-prewired to terminal strips, ready to receive branch circuit and control connections for 140 degrees F copper or aluminum wiring.

2.2 FAN

Provide steel or aluminum fans with ball or roller bearings for motors over 1/8 horsepower (hp) and sleeve bearings for motors 1/8 hp and under. Provide sleeve bearings with oil reservoir, if not permanently lubricated.

2.3 MOTOR AND STARTER

NEMA MG 1, and NEMA ICS 2, and NEMA ICS 6, respectively. Provide explosion-proof motors and motor starters where indicated. Provide continuous-duty motor with built-in automatic reset thermal overload protection. For motor 1/2 hp and larger, use three-phase. Provide single-phase motor of permanent split capacitor or capacitor start. Limit motor speed at 1800 r/min. Wire motor to heater power supply source.

2.4 HOT WATER PIPING SYSTEM

Section 23 21 13.00 20 LOW TEMPERATURE WATER LTW HEATING SYSTEMS.

2.5 SOURCE QUALITY CONTROL

Special protection is not required for equipment that has a zinc coating conforming to ASTM A123/A123M . Otherwise, protect affected equipment items by manufacturers' corrosion-inhibiting coating or paint system that has proved capable of withstanding salt-spray test in accordance with ASTM B117. Test indoor and outdoor equipment for 125 hours; test outdoor equipment used in a marine atmosphere for 500 hours. For each specimen, perform a scratch test as defined in ASTM D1654.

PART 3 EXECUTION

3.1 INSTALLATION

Install equipment where indicated and as recommended by manufacturer's recommendations, NFPA 54, NFPA 90A, NFPA 90B, NFPA 91 and NFPA 211.

3.1.1 Suspensions of Equipment

Provide equipment supports including beam clamps, turnbuckles and twist links or weld-wire chains, wire ropes with rope clips and rope thimbles, threaded-eye rod hangers with lock nuts and heat-duct hangers, threaded-eye bolts with expansion screws, brackets, platform and mounting frame, and vibration isolators. Locate equipment in such a manner that working space is available for servicing, such as vacuum pump and burner removal, access to automatic controls, and lubrication. Provide electrical isolation of dissimilar metals. Clean interior of casings or cabinets before and after completion of installation.

3.1.2 Vents

NFPA 54 and NFPA 211. Provide vents with weatherproofing flashings in accordance with Section 07 60 00 FLASHING AND SHEET METAL.

3.1.3 Electrical Work

NFPA 70 and Division 26, "ELECTRICAL." When replacing original control wires, provide No. 16 AWG with minimum 105 degrees C insulation.

3.2 FIELD QUALITY CONTROL

Administer, schedule, and conduct specified tests. Furnish personnel, instruments and equipment for such tests. Correct defects and repeat the respective inspections and tests. Conduct inspections and testing in the presence of the Contracting Officer.

3.2.1 Test Instruments and Apparatus

Provide instruments and apparatus currently certified as being accurate to within one percent of their full scale. Use gages with a maximum scale between 1 1/2 and 2 times test pressure.

3.2.2 Field Inspection

Prior to initial operation, inspect equipment installation to ensure that

indicated and specified requirements have been met.

3.2.3 Field Tests

3.2.3.1 Insulation-Resistance Tests for Electrical Equipment

At the completion of wiring, test 600 volt wiring to verify that no short circuits exist before or after the attachment of electrical heating equipment to the power source. Make tests with an instrument which applies a voltage of approximately 500 volts for a direct reading of insulation resistance.

3.2.3.2 Operational Tests

After completing fire tests and insulation-resistance tests, operate equipment continuously under varying load conditions to verify functioning of combustion controls, electrical controls, flame safeguard controls, safety interlocks, and specified operating sequence. Run each test for a minimum period of one hour.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 25 05 11.00

CYBERSECURITY FOR FACILITY-RELATED CONTROL SYSTEMS - ISOLATED SYSTEMS
11/17

PART 1 GENERAL

This section includes requirements in support of the DOD Risk Management Framework (RMF) for implementing cybersecurity. Refer to UFC 4-010-06, Cybersecurity for Facility-Related Control Systems, for requirements on incorporating into control system design and for general information on the RMF process as it applies to control systems.

Many subparts in this Section contain text in curly braces ("{" and "}") indicating which cybersecurity control and control correlation identifier (CCI) the requirements of the subpart relate to. The text inside these curly braces is for Government reference only, and enables coordination of the requirements of this Section with the RMF process throughout the design and construction process. Text in curly braces are not contractor requirements.

This Section refers to Security Requirements Guide (SRGs) and Security Technical Implementation Guide (STIGs). STIGs and SRGs are available online at the Information Assurance Support Environment (IASE) website at http://iase.disa.mil/stigs/Pages/index.aspx. Not all control system components have applicable STIGs or SRGs.

Should any conflict exist between this section and related equipment specifications, the more secure option shall be required and coordinated with Camp Lejeune FRCS Office.

1.1 CONTROL SYSTEM APPLICABILITY

There are multiple versions of this Section associated with this project. Different versions have requirements applicable to different control systems. This specific Section applies only to the following control systems:

a. Elevators and Lift Stations (BCS-C/VTS)

b. Electrical Systems (BCS-ES)

c. Other Isolated Control Systems

1.1.1 CONTROL SYSTEM CLASSIFICATION

The C-I-A impact levels for the control system have been determined to be LOW-LOW-LOW (L-L-L).

1.1.2 INTERCONNECTION

The C/VTS and ES control systems addressed by this specification will have no connection to other systems and function as isolated control systems.

1.2 RELATED REQUIREMENTS

All Sections containing facility-related control systems or control system components are related to the requirements of this Section. Review all specification sections to determine related requirements. Incorporate each of the requirements contained in this specification for systems specified in the following sections:

a.

1.3 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

DODI 8551.01	(2014) Ports, Protocols, and Services Management (PPSM)
UFC 4-010-06	(2016; with Change 1, 2017) Cybersecurity of Facility-Related Control Systems

The specifications 23 09 00 INSTRUMENTATION AND CONTROL FOR HVAC, 23 09 13 INSTRUMENTATION AND CONTROL DEVICES FOR HVAC, and 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS should also be used as an external reference.

1.4 DEFINITIONS

1.4.1 Computer

As used in this Section, a computer is one of the following:

a. a device running a non-embedded desktop or server version of Microsoft Windows

b. a device running a non-embedded version of MacOS

c. a device running a non-embedded version of Linux

d. a device running a version or derivative of the Android OS, where Android is considered separate from Linux

e. a device running a version of Apple iOS

1.4.2 Network Connected

A component is network connected (or "connected to a network") only when the device has a network transceiver which is directly connected to the network and implements the network protocol. A device lacking a network transceiver (and accompanying protocol implementation) can never be considered network connected. Note that a device connected to a non-IP network is still considered network connected (an IP connection or IP address is not required for a device to be network connected).

Any device that supports wireless communication is network connected, regardless of whether the device is communicating using wireless.

1.4.3 User Account Support Levels

The support for user accounts is categorized in this Section as one of three levels:

1.4.3.1 FULLY Supported

Device supports configurable individual accounts. Accounts can be created, deleted, modified, etc. Privileges can be assigned to accounts.

1.4.3.2 MINIMALLY Supported

Device supports a small, fixed number of accounts (perhaps only one). Accounts cannot be modified. A device with only a "User" and an "Administrator" account would fit this category. Similarly, a device with two PINs for logon - one for restricted and one for unrestricted rights would fit here (in other words, the accounts do not have to be the traditional "user name and password" structure).

1.4.3.3 NOT Supported

Device does not support any Access Enforcement therefore the whole concept of "account" is meaningless.

1.4.4 User Interface

Generally, a user interface is hardware on a device allowing user interaction with that device via input (buttons, switches, sliders, keyboard, touch screen, etc.) and a screen. There are three types of user interfaces defined in this Section: Limited Local User Interface, Full Local User Interface and Remote User Interface. In this Section, when the term "User Interface" is used without specifying which type, it refers only to Full Local User Interface and Remote User Interface (NOT to Limited Local User Interface).

1.4.4.1 Limited Local User Interface

A Limited Local User Interface is a user interface where the interaction is limited, fixed at the factory, and cannot be modified in the field. The user must be physically at the device to interact with it.

Examples of Limited Local User Interface include thermostats.

1.4.4.2 Full Local User Interface

A Full Local User Interface is a user interface where the interaction and displays are field-configurable.

Examples of a Full Local User Interface include local applications on a computer.

1.4.4.3 Remote User Interface

A Remote User Interface is a user interface on a Client device allowing user interaction with a different Server device. The user need not be physically at the Server device to interact with it.

Examples of Remote User Interfaces include web browsers.

1.4.5 C-I-A Impact Level

A reference to the security objectives of Confidentiality (C), Integrity (I), and Availability (A) associated with a control system. These values are determined by the System Owner (SO) in conjunction with the Authorizing Official (AO). The potential impact levels for each security objective are LOW (L), MODERATE (M), and HIGH (H).

The determination of control system impact levels is a requirement of UFC 4-010-06.

1.4.6 Isolated Field Control Systems

A control system that does not share its signals, data, or telemetry with any system via communications; the system is completely self-contained. The control system may employ IP and non-IP media and protocols for its own functionality.

1.5 ADMINISTRATIVE REQUIREMENTS

1.5.1 Coordination

Coordinate the execution of this Section with the execution of all other Sections related to control systems as indicated in the paragraph RELATED REQUIREMENTS. Items that must be considered when coordinating project efforts include but are not limited to:

a. If requesting permission for alternate account lock permissions, the Device Account Lock Exception Request must be approved prior to control system device selection and integration by the Camp Lejeune FRCS Office.

b. Wireless testing may be required as part of the control system testing. See requirements for the Wireless Communication Test Report submittal.c. If the Device Audit Record Upload Software is to be installed on a computer not being provided as part of the control system, coordination is required to identify the computer on which to install the software with the Camp Lejeune FRCS Office.

d. Cybersecurity testing support must be coordinated across control systems and with the project cybersecurity testing schedule.

e. Passwords must be coordinated with the Camp Lejeune FRCS Office.

f. If applicable, HTTP web server certificates must be obtained from the indicated contact for the project site.

g. Contractor Computer Cybersecurity Compliance Statements for each contractor using contractor owned computers.

1.6 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Architect/Engineer approval is required for submittals marked with an "AE" designation. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualifications; G

Device Account Lock Exception Request; G

Contractor Computer Cybersecurity Compliance Statements; G

Contractor Temporary Network Cybersecurity Compliance Statements; G

SD-02 Shop Drawings

Cybersecurity Riser Diagram; G

Control System Inventory Report; G

SD-03 Product Data

Control System Cybersecurity Documentation; G

SD-06 Test Reports

Wireless Communication Test Report; G

SD-07 Certificates

Software Licenses; GSD-11 Closeout Submittals

Password Summary Report; G

Software Recovery And Reconstitution Images; G

Device Audit Record Upload Software; G

1.7 QUALITY CONTROL

1.7.1 Qualifications

1.7.1.1 Control System Cybersecurity Subject Matter Expert

The individual will oversee all work within this specification. This position requires that the individual currently meets Information Assurance Manager Level II Certification in accordance with DoDI 8570 Information Workforce Improvement Program.

Individuals for this position should have experience securing Marine Corps systems and with Risk Management Framework. Control System Experience is highly desirable.

Resumes should be submitted to the Government within 14 days after notice to proceed. All certifications to include computing environment must be in effect prior to beginning work.

Control System Cybersecurity Subject Matter Expert can serve across the contract.

1.8 CYBERSECURITY DOCUMENTATION

1.8.1 Cybersecurity Interconnection Schedule

{For Reference Only: This subpart (and its subparts) relates to CA-3(b)}

The control system(s) addressed by this specification will be isolated unto themselves and do not connect or interface to any other system. Therefore the contractor will not be required to provide a cybersecurity interconnection schedule.

1.8.2 Control System Inventory Report

{For Reference Only: This subpart (and its subparts) relates to CM-8(a), IA-3}

Provide a Control System Inventory report using the Inventory Spreadsheet listed under this Section at http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphic documenting all devices, including networked devices, network infrastructure devices, non-networked devices, input devices (e.g. sensors) and output devices (e.g. actuators). For each device provide all applicable information for which there is a field on the spreadsheet in accordance with the instructions on the spreadsheet.

In addition to the requirements of Section 01 33 00 SUBMITTAL PROCEDURES, provide the Control System Inventory Report as an editable Microsoft Excel file.

1.8.3 Software Recovery and Reconstitution Images

For each control system device on which software is configured or installed under this project, provide a recovery image of the final as-built device. This image must allow for bare-metal restore such that restoration of the image is sufficient to restore system operation to the imaged state without the need for re-installation of software.

If additional user permissions are required to meet this requirement, coordinate the creation of the image with Camp Lejeune FRCS Office.

1.8.4 Cybersecurity Riser Diagram

{For Reference Only: This subpart (and its subparts) relates to PL-2(a)}

Provide a cybersecurity riser diagram of the complete control system including all network and controller hardware. If the control system specifications require a riser diagram submittal, provide a copy of that submittal as the cybersecurity riser diagram. Otherwise, provide a riser diagram in one-line format overlayed on a facility schematic.

1.8.5 Control System Cybersecurity Documentation

Provide a Control System Cybersecurity Documentation submittal containing the indicated information for each device and software application.

1.8.5.1 Default Requirements for Control System Devices

For control system devices where Control System Cybersecurity

Documentation requirements are not otherwise indicated in this Section, provide security baseline documentation (CA-5) using CCIs listed below:

a. Documentation that describes secure configuration of the device {for reference only: relates to CCI-003124}

b. Documentation that describes secure installation of the device {for reference only: relates to CCI-003125}

c. Documentation that describes secure operation of the device {for reference only: relates to CCI-003124}

d. Documentation that describes effective use and maintenance of security functions or mechanisms for the device {for reference only: relates to CCI-003127}

e. Documentation that describes known vulnerabilities regarding configuration and use of administrative (i.e. privileged) functions for the device {for reference only: relates to CCI-003128}

f. Documentation that describes user-accessible security functions or mechanisms in the device and how to effectively use those security functions or mechanisms {for reference only: relates to CCI-003129}

g. Documentation that describes methods for user interaction which enables individuals to use the device in a more secure manner {for reference only: relates to CCI-003130}

h. Documentation that describes user responsibilities in maintaining the security of the device {for reference only: relates to CCI-003131}

1.8.6 PLAN OF ACTION AND MILESTONES

{For Reference Only: This subpart (and its subparts) relates to CA-5(a), (b)}

Develop a plan of action and milestones for the system to document the planned remediation actions of the organization to correct weaknesses or deficiencies noted during the assessment of the controls and to reduce or eliminate known vulnerabilities in the system.

Update existing plan of action and milestones based on the findings from control assessments, independent audits or reviews, and continuous monitoring activities should be completed by the Government as part of continuous monitoring.

1.8.7 Personnel and Access Agreement

{For Reference Only: This subpart (and its subparts) relates to PS-3, PS-4, PS-5, PS-6}

Screen individuals prior to authorizing access to the system; and
b. Rescreen individuals in accordance with organization-defined conditions requiring rescreening and, where rescreening is so indicated, the frequency of rescreening.

Upon termination of individual employment:

Disable system access within organization-defined time period

Terminate or revoke any authenticators and credentials associated with the individual

Conduct exit interviews that include a discussion of information security topics

Retrieve all security-related organizational system-related property

Retain access to organizational information and systems formerly controlled by terminated individual

Review and confirm ongoing operational need for current logical and physical access authorizations to systems and facilities when individuals are reassigned or transferred to other positions within the organization. Initiate transfer or reassignment actions within organization-defined time period following the formal transfer action. Modify access authorization as needed to correspond with any changes in operational need due to reassignment or transfer. Notify personnel or roles within organization-defined time period.

Develop and document access agreements for organizational systems. Review and update the access agreements. Verify that individuals requiring access to organizational information and systems:

a. Sign appropriate access agreements prior to being granted access

b. Re-sign access agreements to maintain access to organizational systems when access agreements have been updated

1.8.8 Software, Firmware, and Information Integrity

{For Reference Only: This subpart (and its subparts) relates to SI-7}

Employ integrity verification tools to detect unauthorized changes to control system software, firmware, and information. Take appropriate actions determined by the system owner when unauthorized changes to the software, firmware, and information are detected.

1.9 SOFTWARE UPDATE LICENSING

In addition to all other licensing requirements, all software licensing must include licensing of the following software updates for a period of no less than 5 years:

a. Security and bug-fix patches issued by the software manufacturer.

b. Security patches to address any vulnerability identified in the National Vulnerability Database at http://nvd.nist.gov with a Common Vulnerability Scoring System (CVSS) severity rating of MEDIUM or higher.

Provide a single Software Licenses submittal with documentation of the software licenses for all software provided

1.10 CYBERSECURITY DURING CONSTRUCTION

{For Reference Only: This subpart (and its subparts) relates to SA-3}

In addition to the control system cybersecurity requirements indicated in

this section, meet following requirement throughout the construction process.

1.10.1 Contractor Computer Equipment

Contractor owned computers may be used for construction. When used, contractor computers must meet the following requirements:

1.10.1.1 Operating System

The operating system must be an operating system currently supported by the manufacturer of the operating system. The operating system must be current on security patches and operating system manufacturer required updates.

1.10.1.2 Anti-Malware Software

The computer must run anti-malware software from a reputable software manufacturer. Anti-malware software must be a version currently supported by the software manufacturer, must be current on all patches and updates, and must use the latest definitions file. All computers used on this project must be scanned using the installed software at least once per day.

1.10.1.3 Passwords and Passphrases

The passwords and passphrases for all computers must be changed from their default values. Passwords must be a minimum of eight characters with a minimum of one uppercase letter, one lowercase letter, one number and one special character.

1.10.1.4 Contractor Computer Cybersecurity Compliance Statements

Provide a single submittal containing completed Contractor Computer Cybersecurity Compliance Statements for each company using contractor owned computers. Contractor Computer Cybersecurity Compliance Statements must use the template published at http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphic Each Statement must be signed by a cybersecurity representative for the relevant company.

1.10.2 Temporary IP Networks

Temporary contractor-installed IP networks may be used during construction. When used, temporary contractor-installed IP networks must meet the following requirements:

1.10.2.1 Network Boundaries and Connections

The network must not extend outside the project site and must not connect to any IP network other than IP networks provided under this project or Government furnished IP networks provided for this purpose. Any and all network access from outside the project site is prohibited. Unused network access ports are to be disabled via the management console or command line when not in use.

1.10.3 Government Access to Network

Government personnel must be allowed to have complete and immediate access

to the network at any time in order to verify compliance with this specification

1.10.4 Temporary Wireless IP Networks

Temporary Wireless connections are not allowed by default. The ISSM may approve wireless connections on a case-by-case basis. In addition to the other requirements on temporary IP networks, temporary wireless IP (WiFi) networks must not interfere with existing wireless network and must use WPA2 security. Network names (SSID) for wireless networks must be changed from their default values.

According to DoD, USN, USMC policy there is no separation between temp or perm wireless connections.

1.10.5 Passwords and Passphrases

The passwords and passphrases for all network devices and network access must be changed from their default values. Passwords must be a minimum 8 characters with a minimum of one uppercase letter, one lowercase letter, one number and one special character.

1.10.6 Contractor Temporary Network Cybersecurity Compliance Statements

Provide a single submittal containing completed Contractor Temporary Network Cybersecurity Compliance Statements for each company implementing a temporary IP network. Contractor Temporary Network Cybersecurity Compliance Statements must use the template published at http://www.wbdg.org/ffc/dod/unified-facilities-guide-specifications-ufgs/forms-graphic Each Statement must be signed by a cybersecurity representative for the relevant company. If no temporary IP networks will be used, provide a single copy of the Statement indicating this.

1.10.7 Security Impact Analysis
{For Reference Only: This subpart (and its subparts) relates to CM-4}

If a change is being made while the system is being developed this change should first be analyzed to determine potential security and privacy impacts by the contractor prior to change implementation and the findings should be submitted to the Government.

1.10.8 Contingency Plan
{For Reference Only: This subpart (and its subparts) relates to CP-2}

Develop a contingency plan for the system that:

a. Identifies essential mission and business functions and associated contingency requirements

b. Provides recovery objectives, restoration priorities, and metrics

c. Addresses contingency roles, responsibilities, assigned individuals with contact information

d. Addresses maintaining essential mission and business functions despite a system disruption, compromise, or failure

e. Addresses eventual, full system restoration without deterioration of

the controls originally planned and implemented

f. Addresses the sharing of contingency information

g. Is reviewed and approved by ISSM

Distribute copies of the contingency plan to ISSM. Coordinate contingency planning activities with incident handling activities. Review the contingency plan for the system. Update the contingency plan to address changes to the organization, system, or environment of operation and problems encountered during contingency plan implementation, execution, or testing. Communicate contingency plan changes to ISSM. Incorporate lessons learned from contingency plan testing, training, or actual contingency activities into contingency testing and training. Protect the contingency plan from unauthorized disclosure and modification.

1.11 CYBERSECURITY DURING WARRANTY PERIOD

All work performed on the control system after acceptance must be performed using Government Furnished Equipment . Access to systems and changes must be coordinated through Camp Lejeune FRCS Office and follow established change management procedures.

PART 2 PRODUCTS

(NOT USED)

PART 3 EXECUTION

3.1 ACCESS CONTROL REQUIREMENTS

3.1.1 User Accounts

{For Reference Only: This subpart (and its subparts) relate to AC-2(a)and AC-3}

Any device supporting user accounts (either FULLY or MINIMALLY) must limit access to the device according to specified limitations for each account. Install and configure any device having a STIG or SRG in accordance with that STIG or SRG.

3.1.1.1 C/VTS and ES Control System Devices

a. Devices with full local user interfaces allowing modification of data must at least MINIMALLY support user accounts.

b. Devices with read-only full local user interfaces must at least MINIMALLY support user accounts.

3.1.1.2 Default Requirements for Control System Devices

For control system devices where User Account requirements are not otherwise indicated in this Section:

a. Devices with web interfaces must either FULLY support user accounts or have their web interface disabled.

b. Field devices with full local user interfaces allowing modification of data must at least MINIMALLY support user accounts.

c. Field devices with read-only full local user interfaces must at least MINIMALLY support user accounts.

3.1.2 Unsuccessful Logon Attempts

{For Reference Only: This subpart (and its subparts) relate AC-7 (a), AC-7 (b); CCI-000043, CCI-000044, CCI-001423, CCI-002236, CCI-002237, CCI-002238}

Except for high availability user interfaces indicated as exempt, devices must meet the indicated requirements for handling unsuccessful logon attempts.

3.1.2.1 Devices MINIMALLY Supporting Accounts

Devices which MINIMALLY support accounts are not required to lock based on unsuccessful logon attempts.

3.1.2.2 Devices FULLY Supporting Accounts

Devices which FULLY support accounts must meet the following requirements. If a device cannot meet these requirements, document device capabilities to protect from subsequent unsuccessful logon attempts and propose alternate protections in a Device Account Lock Exception Request submittal. Do not implement alternate protection measures without explicit permission from the Camp Lejeune FRCS Office.

a. It must lock the user account when three unsuccessful logon attempts occur within a 15 minute interval.

3.1.3 Wireless Access

Wireless networking is not authorized for this project as a default. Do not use any wireless communication unless approved by the ISSM which is done on a case-by-case basis. Any device with wireless communication capability is considered to be using wireless communication, regardless of whether or not the device is actively communicating wirelessly, except when wireless communication has been physically permanently disabled (such as through the removal of the wireless transceiver).

Wireless connections must follow all DoD, USN, and USMC requirements and be approved by the PWD ISSM.

3.1.3.1 Wireless IP Communications

Do not install wireless IP networks, including: do not install a wireless access point; do not install or configure an ad-hoc wireless network; do not install or configure a WiFi Direct communication.

3.1.3.2 Non-IP Wireless Communication

Non-IP Wireless networking is not authorized for this project.

3.1.3.3 Wireless Communication Testing

As part of Performance Verification Testing (PVT), conduct testing of wireless communication for all devices indicated on the approved Wireless

Communication Request as requiring testing.

To test wireless communication, test for wireless network reception at multiple points along the wireless test boundary in the vicinity of the wireless device, and record whether a network connection can be established at each point. The wireless test boundary is the building exterior walls. If wireless testing is required, provide a Wireless Communication Test Report documenting the testing points and results at each point for each wireless device.3.1.4 Physical Access Authorizations and Control

{For Reference Only: This subpart (and its subparts) relates to PE-2, PE-3}

Develop, approve, and maintain a list of individuals with authorized access to the facility where the system resides. Issue authorization credentials for facility access. Review the access list detailing authorized facility access by individuals at organization-defined frequency. Remove individuals from the facility access list when access is no longer required.

Enforce physical access authorizations at entry and exit points to the facility where the system resides by:

a. Verifying individual access authorizations before granting access to the facility

b. Controlling ingress and egress to the facility using physical access control systems or devices

Maintain physical access audit logs for entry or exit points. Control access to areas within the facility designated as publicly accessible by implementing the appropriate controls. Escort visitors and control visitor activity for organization-defined circumstnaces. Secure keys, combinations, and other physical access devices. Inventory physical access devices at organization-defined frequency. Change combinations and keys at organization-defined frequency and/or when keys are lost, combinations are compromised, or when individuals possessing the keys or combinations are transferred or terminated.

3.2 CYBERSECURITY AUDITING

3.2.1 Audit Events, Content of Audit Records, and Audit Generation

{For Reference Only: This subpart (and its subparts) relates to AU-2(a),(c),(d), AU-3}

For devices that have STIG/SRGs related to audit events, content of audit records or audit generation, comply with the requirements of those STIG/SRGs.

3.2.1.1 Default Requirements for Control System Devices

For control system devices where Audit Events, Content of Audit Records, and Audit Generation are not otherwise indicated in this Section:

3.2.1.1.1 Devices Which FULLY Support Accounts

For each device which FULLY supports accounts, provide the capability to select audited events and the content of audit logs. Configure devices to

audit the indicated events, and to record the indicated information for each auditable event

3.2.1.1.1.1 Audited Events

Configure each device to audit the following events:

a. Successful and unsuccessful attempts to access, modify, or delete privileges, security objects, security levels, or categories of information (e.g. classification levels)

a. Successful and unsuccessful logon attempts

b. Privileged activities or other system level access

c. Starting and ending time for user access to the system

d. Concurrent logons from different workstations

e. All account creations, modifications, disabling, and terminations

f. All kernel module load, unload, and restart

3.2.1.1.1.2 Audit Event Information To Record

Configure each device to record, for each auditable event, the following information (where applicable to the event):

a. what type of event occurred

b. when the event occurred

c. where the event occurred

d. the source of the event

e. the outcome of the event

f. the identity of any individuals or subjects associated with the event

3.2.1.1.2 Devices Which Do Not FULLY Support Accounts

For each Device which does not FULLY support accounts configure the device to audit all device shutdown and startup events and to record for each event the type of event and when the event occurred.

3.2.2 Audit Storage Capacity and Audit Upload

{For Reference Only: This subpart (and its subparts) relates to AU-4; CCI-001848, CCI-001849}

a. For devices that have STIG/SRGs related to audit storage capacity (CCI-001848 or CCI-001849) comply with the requirements of those STIG/SRGs.

b. For non-computer control system devices capable of generating audit records, provide 60 days worth of secure local storage, assuming 10 auditable events per day.

3.2.2.1 Device Audit Record Upload Software

For each non-computer device required to audit events, provide, and license to the Camp Lejeune FRCS Office, software implementing a secure mechanism of uploading audit records from the device to a computer and of exporting the uploaded audit records as a Microsoft Excel file or comma separated value text file. Where different devices use different software, provide software of each type required to upload audit logs from all devices.

Submit copies of device audit record upload software. If there are no non-computer devices requiring auditing, provide a document stating this in lieu of this submittal.

3.2.3 Time Stamps

3.2.3.1 C/VTS and ES Control System Devices

Devices generating audit records must have internal clocks capable of providing time with a resolution of 1 second. Clocks cannot drift more than 10 seconds per day. Configure the system so that each device generating audit records maintains accurate time to within 1 second.

3.2.3.2 Default Requirements for Control System Devices

For control system devices where Time Stamps requirements are not otherwise indicated in this Section: Devices generating audit records must have internal clocks capable of providing time with a resolution of 1 second. Clocks must not drift more than 10 seconds per day. Configure the system so that each device generating audit records maintains accurate time to within 1 second.

3.3 REQUIREMENTS FOR LEAST FUNCTIONALITY

{For Reference Only: This subpart (and its subparts), along with the network communication report submittal specified elsewhere in this section, relates to CM-7, CM-7 (1)(b)}

For devices that have a STIG or SRG related to Requirements for Least Functionality (such as configuration settings and port and device I/O access for least functionality), install and configure the device in accordance with that STIG or SRGs.

Do not provide devices with user interfaces where one was not required. Do not use a networked sensor or actuator where a non-networked sensor or actuator would suffice.

3.3.1 Non-IP Control Networks

When control system specifications require particular communication protocols, use only those communication protocols and only as specified. Do not implement any other communication protocol, or use any protocol on ports other than those specified.

When control system specifications do not indicate requirements for communication protocols, use only those protocols required for operation of the system as specified.

3.3.1.1 Allowable Non-IP Control Protocols

3.3.1.1.1 Serial RS-232 and USB

For device configuration and troubleshooting only. That are allowable in a point-to-point configuration only.

3.3.2 IP Control Networks

Do not use nonsecure functions, ports, protocols and services as defined in DODI 8551.01 unless those ports, protocols and services are specifically required by the control system specifications or otherwise specifically authorized by the Camp Lejeune FRCS Office. Do not use ports, protocols and services that are not specified in the control system specifications or required for operation of the control system.

3.3.3 Unspecified Protocol Approval

When unspecified communicaitions protocols are required for proper system operation submit to the Camp Lejeune FRCS Office for approval the protocol, port number if IP based, functional requirement, and cybersecurity conformance.

3.4 IDENTIFICATION AND AUTHENTICATION

3.4.1 User Identification and Authentication

{For Reference Only: This subpart (and its subparts) relates to IA-2,(1),(12), IA-4}

a. Devices that FULLY support accounts must uniquely identify and authenticate organizational users.

b. Devices which allow network access to privileged accounts must implement multifactor authentication for network access to privileged accounts.

3.4.1.1 C/VTS and ES Control System Devices

Isolated systems are not required to authenticate using Personal Identity Verification (PIV) credentials.

3.4.1.2 Default Requirements for Control System Devices

For control system devices where User Identification and Authentication requirements are not otherwise indicated in this Section, User Identification and Authentication for network access to privileged accounts must be implemented by accepting and electronically verify Personal Identity Verification (PIV) credentialsorinheriting identification and authentication from the operating system.

3.4.2 Authenticator Management

{For Reference Only: This subpart (and its subparts) relates to IA-5 (b),(c),(e),(g),(1),(11)}

3.4.2.1 Authentication Type

3.4.2.1.1 C/VTS and ES Control System Devices

Unless otherwise indicated:

a. Devices MINIMALLY supporting accounts must use password-based authentication.

3.4.2.1.2 Default Requirements for Control System Devices

For control system devices where Authentication Type requirements are not otherwise indicated in this Section:

a. Software which FULLY supports accounts and which runs on a computer must use password-based authentication or hardware token-based authentication.

b. Other devices which FULLY support accounts must use either password-based authentication or hardware token-based authentication.

c. Devices MINIMALLY supporting accounts must use either password-based authentication or hardware token-based authentication.

3.4.2.2 Password-Based Authentication Requirements

3.4.2.2.1 Passwords for Non-Computer Devices FULLY Supporting Accounts

All non-computer devices FULLY supporting accounts and supporting password-based authentication must enforce the following requirements:

a. Minimum password length of fifteen (15)) characters

b. Password must contain at least one (1) uppercase character.

c. Password must contain at least one (1) lowercase character.

d. Password must contain at least one (1) numeric character.

e. Password must contain at least one (1) special character.

f. Password must have a maximum lifetime of sixty (60) days. When passwords expire, prompt users to change passwords. Do no lock accounts due to expired passwords.

g. Passwords must be cryptographically protected during storage and transmission.

3.4.2.2.2 Passwords for Devices Minimally Supporting Accounts

Devices minimally supporting accounts must support passwords with a minimum length of four (4) characters.

3.4.2.2.3 Password Configuration and Reporting

For all devices with a password, change the password from the default password. Coordinate selection of passwords with the Camp Lejeune FRCS Office. Do not use the same password for more than one device unless specifically instructed to do so. Provide a Password Summary Report

documenting the password for each device and describing the procedure to change the password for each device.

Do not provide the Password Summary Report in electronic format. Provide two hardcopies of the Password Summary Report, each copy in its own sealed envelope.

3.4.2.3 Hardware Token-Based Authentication Requirements

Devices supporting hardware token-based authentication must use Personal Identity Verification (PIV) credentials for the hardware token.

3.4.3 Device Identification and Authentication

{For Reference Only: This subpart (and its subparts) relates to IA-3}

3.4.3.1 Default Requirements for Control System Devices

For control system devices where Device Identification and Authentication requirements are not otherwise indicated in this Section: Devices using HTTP as a control protocol must use HTTPS using a web server certificate obtained from the Government Trusted Agent instead.

3.4.4 Cryptographic Module Authentication

{For Reference Only: This subpart (and its subparts) relates to IA-7}

For devices that have STIG/SRGs related to cryptographic module authentication, comply with the requirements of those STIG/SRGs.At a minimum the contractor must use FIPS 140-2 VALIDATED cryptographic modules and be approved by the ISSM.

3.5 DURABILITY TO VULNERABILITY SCANNING

{For Reference Only: This subpart (and its subparts) relates to RA-5 (a),(b),(c),(d)}

All IP devices must be scannable, such that the device can be scanned by industry standard IP network scanning utilities without harm to the device, application, or functionality.

For control system devices other than computers:

3.5.1 C/VTS and ES Control System Devices Other Than Computers

Elevator and electrical control system devices other than computers are not required to respond to scans.

3.5.2 Default Requirements for Control System Devices

Non-computer control system devices where Durability to Vulnerability Scanning requirements are not otherwise indicated in this Section are not required to respond to scans.

3.6 SYSTEM AND COMMUNICATION PROTECTION

3.6.1 Denial of Service Protection, Process Isolation and Boundary Protection

{For Reference Only: This subpart (and its subparts) relates to SC-5}

To the greatest extent practical, implement control logic in non-computer hardware and without reliance on the network.

3.7 FIELD QUALITY CONTROL

3.7.1 Tests

In addition to testing and testing support required by other Sections, provide a minimum of eight (8) hours of technical support for cybersecurity testing of control systems.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 08 00

APPARATUS INSPECTION AND TESTING
11/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2021) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

1.2 RELATED REQUIREMENTS

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM applies to this section with additions and modifications specified herein.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-06 Test Reports

Acceptance Tests and Inspections; G

SD-07 Certificates

Qualifications of Organization, and Lead Engineering Technician; G

Acceptance Test and Inspections Procedure; G

1.4 QUALITY ASSURANCE

1.4.1 Qualifications

Contractor shall engage the services of a qualified testing organization to provide inspection, testing, calibration, and adjustment of the electrical distribution system and generation equipment listed in paragraph entitled "Acceptance Tests and Inspections" herein. Organization shall be independent of the supplier, manufacturer, and installer of the equipment. The organization shall be a first tier subcontractor. No work required by this section of the specification shall be performed by a second tier subcontractor.

a. Submit name and qualifications of organization. Organization shall have been regularly engaged in the testing of electrical materials, devices, installations, and systems for a minimum of 5 years. The organization shall have a calibration program, and test instruments

used shall be calibrated in accordance with NETA ATS.

b. Submit name and qualifications of the lead engineering technician performing the required testing services. Include a list of three comparable jobs performed by the technician with specific names and telephone numbers for reference. Testing, inspection, calibration, and adjustments shall be performed by an engineering technician, certified by NETA (Level III) or the National Institute for Certification in Engineering Technologies (NICET) with a minimum of 5 years' experience inspecting, testing, and calibrating electrical distribution and generation equipment, systems, and devices.

1.4.2 Acceptance Tests and Inspections Reports

Submit certified copies of inspection reports and test reports. Reports shall include certification of compliance with specified requirements, identify deficiencies, and recommend corrective action when appropriate. Type and neatly bind test reports to form a part of the final record. Submit test reports documenting the results of each test not more than 10 days after test is completed.

1.4.3 Acceptance Test and Inspections Procedure

Submit test procedure reports for each item of equipment to be field tested at least 45 days prior to planned testing date. Do not perform testing until after test procedure has been approved.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 ACCEPTANCE TESTS AND INSPECTIONS

Testing organization shall perform acceptance tests and inspections. Test methods, procedures, and test values shall be performed and evaluated in accordance with NETA ATS, the manufacturer's recommendations, and paragraph entitled "Field Quality Control" of each applicable specification section. Tests identified as optional in NETA ATS are not required unless otherwise specified. Equipment shall be placed in service only after completion of required tests and evaluation of the test results have been completed. Contractor shall supply to the testing organization complete sets of shop drawings, settings of adjustable devices, and other information necessary for an accurate test and inspection of the system prior to the performance of any final testing. Contracting Officer shall be notified at least 14 days in advance of when tests will be conducted by the testing organization. Perform acceptance tests and inspections on applicable equipment and systems specified in the following sections:

a. Section 26 32 15.00 ENGINE-GENERATOR SET STATIONARY 15-2500 KW, WITH AUXILIARIES. Functional engine shutdown tests, vibration base-line test, and load bank test shall not be performed by the testing organization. These tests shall be performed by the start-up engineer.

b. Section 26 12 19.10 THREE-PHASE, LIQUID-FILLED PAD-MOUNTED TRANSFORMERS

e. Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION. Medium voltage cables and grounding systems only.

i. Section 26 36 23 AUTOMATIC TRANSFER SWITCHES AND BY-PASS/ISOLATION SWITCH

k. Section 26 24 13 SWITCHBOARDS

3.2 SYSTEM ACCEPTANCE

Final acceptance of the system is contingent upon satisfactory completion of acceptance tests and inspections.

3.3 PLACING EQUIPMENT IN SERVICE

A representative of the approved testing organization shall be present when equipment tested by the organization is initially energized and placed in service.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 12 19.10

THREE-PHASE, LIQUID-FILLED PAD-MOUNTED TRANSFORMERS
05/19, CHG 1: 11/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C12.1	(2014; Errata 2016) Electric Meters - Code for Electricity Metering

ASTM INTERNATIONAL (ASTM)

ASTM A240/A240M	(2025a) Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications
ASTM C260/C260M	(2010a; R 2016) Standard Specification for Air-Entraining Admixtures for Concrete
ASTM D92	(2012a) Standard Test Method for Flash and Fire Points by Cleveland Open Cup Tester
ASTM D97	(2017b) Standard Test Method for Pour Point of Petroleum Products
ASTM D117	(2018) Standard Guide for Sampling, Test Methods, and Specifications for Electrical Insulating Liquids
ASTM D877/D877M	(2019) Standard Test Method for Dielectric Breakdown Voltage of Insulating Liquids Using Disk Electrodes
ASTM D1535	(2014; R 2018) Standard Practice for Specifying Color by the Munsell System
ASTM D3487	(2016; E2017) Standard Specification for Mineral Insulating Oil Used in Electrical Apparatus

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 386	(2016) Separable Insulated Connector Systems for Power Distribution Systems

Rated 2.5 kV through 35 kV

IEEE C2 (2023) National Electrical Safety Code

IEEE C37.47 (2011) Standard for High Voltage Distribution Class Current-Limiting Type Fuses and Fuse Disconnecting Switches

IEEE C57.12.00 (2021) General Requirements for Liquid-Immersed Distribution, Power, and Regulating Transformers

IEEE C57.12.28 (2014) Standard for Pad-Mounted Equipment - Enclosure Integrity

IEEE C57.12.34 (2015) Standard Requirements for Pad-Mounted, Compartmental-Type, Self-Cooled, Three-Phase Distribution Transformers, 10 MVA and Smaller; High Voltage, 34.5 kV Nominal System Voltage and Below; Low Voltage, 15 kV Nominal System Voltage and Below

IEEE C57.12.80 (2010) Standard Terminology for Power and Distribution Transformers

IEEE C57.12.90 (2021) Test Code for Liquid-Immersed Distribution, Power, and Regulating Transformers

IEEE C57.98 (2011) Guide for Transformer Impulse Tests

IEEE C62.11 (2020) Standard for Metal-Oxide Surge Arresters for Alternating Current Power Circuits (>1kV)

IEEE Stds Dictionary (2009) IEEE Standards Dictionary: Glossary of Terms & Definitions

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS (2021) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 260 (1996; R 2004) Safety Labels for Pad-Mounted Switchgear and Transformers Sited in Public Areas

NEMA Z535.4 (2011; R 2017) Product Safety Signs and Labels

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National

Electrical Code

ORGANISATION FOR ECONOMIC CO-OPERATION AND DEVELOPMENT (OECD)

OECD Test 203	(1992) Fish Acute Toxicity Test

U.S. ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 712-C-98-075	(1998) Fate, Transport and Transformation Test Guidelines - OPPTS 835.3100- "Aerobic Aquatic Biodegradation"
EPA 821-R-02-012	(2002) Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

10 CFR 431	Energy Efficiency Program for Certain Commercial and Industrial Equipment

UL SOLUTIONS (UL)

UL 467	(2022) UL Standard for Safety Grounding and Bonding Equipment

1.2 RELATED REQUIREMENTS

Section 26 08 00 APPARATUS INSPECTION AND TESTING applies to this section, with the additions and modifications specified herein.

1.3 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, are as defined in IEEE Stds Dictionary.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Pad-mounted Transformer Drawings; G

SD-03 Product Data

Pad-mounted Transformers; G

SD-06 Test Reports

Acceptance Checks and Tests; G

SD-07 Certificates

Transformer Efficiencies; G

SD-09 Manufacturer's Field Reports

Transformer Test Schedule; G

Pad-mounted Transformer Design Tests; G

Pad-mounted Transformer Routine and Other Tests; G

SD-10 Operation and Maintenance Data

Transformer(s), Data Package 5; G

1.4.1 Reduced Submittal Requirements

Transformers designed and manufactured by ABB in Jefferson City, MO; by Eaton's Cooper Power Series Transformers in Waukesha, WI; by ERMCO in Dyersburg, TN; or by Howard Industries in Laurel, MS need not submit the entire submittal package requirements of this contract. Instead, submit the following items:

a. A certification, signed by the manufacturer, stating that the manufacturer will meet the technical requirements of this specification.

b. An outline drawing of the transformer with devices identified (paragraph PAD-MOUNTED TRANSFORMER DRAWINGS, item a).

c. ANSI nameplate data of the transformer (paragraph PAD-MOUNTED TRANSFORMER DRAWINGS, item b).

e. Provide transformer test schedule and routine and other tests required by submittal item "SD-09 Manufacturer's Field Reports".

f. Provide acceptance test reports required by submittal item "SD-06 Test Reports".

g. Provide operation and maintenance manuals required by submittal item "SD-10 Operation and Maintenance Data".

1.5 QUALITY ASSURANCE

1.5.1 Pad-Mounted Transformer Drawings

Include the following as a minimum:

a. An outline drawing, including front, top, and side views.

b. IEEE nameplate data.

c. Elementary diagrams and wiring diagrams with terminals identified of watthour meter and current transformers.

d. One-line diagram, including switch(es), current transformers, meters, and fuses.

1.5.2 Regulatory Requirements

In each of the publications referred to herein, consider the advisory

provisions to be mandatory, except of NFPA 70 when more stringent requirements are specified or indicated, as though the word "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Provide equipment, materials, installation, and workmanship in accordance with NFPA 70 unless more stringent requirements are specified or indicated.

1.5.3 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship, and:

a. Have been in satisfactory commercial or industrial use for 2 years prior to bid opening including applications of equipment and materials under similar circumstances and of similar size.

b. Have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period.

c. Where two or more items of the same class of equipment are required, provide products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.3.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.3.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site are not acceptable.

1.6 MAINTENANCE

1.6.1 Additions to Operation and Maintenance Data

Submit operation and maintenance data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA and as specified herein. In addition to requirements of Data Package 5, include the following on the actual transformer(s) provided:

a. An instruction manual with pertinent items and information highlighted

b. An outline drawing, front, top, and side views

c. Prices for spare parts and supply list

d. Routine and field acceptance test reports

e. Fuse curves for primary fuses

f. Information on watthour demand meter, CT's, and fuse block

g. Actual nameplate diagram

h. Date of purchase

PART 2 PRODUCTS

2.1 PRODUCT COORDINATION

Products and materials not considered to be pad-mounted transformers and related accessories are specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM, and Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.

2.2 THREE-PHASE PAD-MOUNTED TRANSFORMERS

IEEE C57.12.34, IEEE C57.12.28 and as specified herein. Submit manufacturer's information for each component, device, insulating fluid, and accessory provided with the transformer.

2.2.1 Compartments

Provide high- and low-voltage compartments separated by steel isolating barriers extending the full height and depth of the compartments. Compartment doors: hinged lift-off type with stop in open position and three-point latching.

2.2.1.1 High Voltage, Dead-Front

High-voltage compartment contains: the incoming line, insulated high-voltage load-break connectors, feed-thru inserts, six high-voltage bushing wells configured for loop feed application, load-break switch handle(s), access to oil-immersed bayonet fuses, dead-front surge arresters, tap changer handle, connector parking stands with insulated standoff bushings, protective caps, and ground pad.

Minimum high-voltage compartment dimensions: IEEE C57.12.34, Figures 16 and 17.

a. Insulated high-voltage load-break connectors: IEEE 386, rated 15 kV, 95 kV BIL. Current rating: 200 amperes rms continuous. Short time rating: 10,000 amperes rms symmetrical for a time duration of 0.17 seconds. Connector must have a steel reinforced hook-stick eye, grounding eye, test point, and arc-quenching contact material.

c. Bushing well inserts and feed-thru inserts: IEEE 386, 200 amperes, 15 kV Class. Provide a bushing well insert for each bushing well unless indicated otherwise. Provide feed-thru inserts as indicated.

e. Load-break switch

Loop feed sectionalizer switches: Provide three, two-position, oil-immersed type switches to permit closed transition loop feed and sectionalizing. Each switch must be rated at 15 kV, 95 kV BIL, with a continuous current rating and load-break rating of 200 amperes, and a make-and-latch rating of 12,000 rms amperes symmetrical. Locate the switch handles in the high-voltage compartment. Operation of switches must be as follows:

ARRANGEMENT NO.	DESCRIPTION OF SWITCH ARRANGEMENT	SWITCH POSITION					
		LINE A SW.		LINE B SW		XFMR. SW	
		OPEN	CLOSE	OPEN	CLOSE	OPEN	CLOSE
1	Line A connected to Line B and both lines connected to transformer		X		X		X
2	Transformer connected to Line A only		X	X			X
3	Transformer connected to Line Bonly	X			X		X
4	Transformer open and loop closed		X		X	X	
5	Transformer open and loop open	X		X		X	

f. Provide bayonet oil-immersed, expulsion fuses in series with oil-immersed, partial-range, current-limiting fuses. The bayonet fuse links sense both high currents and high oil temperature in order to provide thermal protection to the transformer. Coordinate transformer protection with expulsion fuse clearing low-current faults and current-limiting fuse clearing high-current faults beyond the interrupting rating of the expulsion fuse. Include an oil retention valve inside the bayonet assembly housing, which closes when the fuse holder is removed, and an external drip shield to minimize oil spills. Display a warning label adjacent to the bayonet fuse(s) cautioning against removing or inserting fuses unless the transformer has been de-energized and the tank pressure has been released.

Bayonet fuse assembly: 150 kV BIL.

Oil-immersed current-limiting fuses: IEEE C37.47; 50,000 rms amperes symmetrical interrupting rating at the system voltage specified.

g. Surge arresters: IEEE C62.11, rated 10 kV, fully shielded, dead-front, metal-oxide-varistor, elbow type with resistance-graded gap. Provide six arresters for loop feed circuits.

h. Parking stands: Provide a parking stand near each bushing. Provide insulated standoff bushings for parking of energized high-voltage connectors on parking stands.

i. Protective caps: IEEE 386, 200 amperes, 15 kV Class. Provide insulated protective caps (not shipping caps) for insulating and sealing out moisture from unused bushings.

2.2.1.2 Low Voltage

Low-voltage compartment contains: low-voltage bushings with NEMA spade

terminals, accessories, metering, stainless steel or laser-etched anodized aluminum diagrammatic transformer nameplate, and ground pad.

a. Include the following accessories: drain valve with sampler device, fill plug, pressure relief device, liquid level gage, pressure-vacuum gage, and dial type thermometer with maximum temperature indicator.

b. Metering: Provide as specified in Section 26 27 14.00 20 ELECTRICITY METERING.

2.2.2 Transformer

a. Less-flammable bio-based liquid-insulated, two winding, 60 hertz, 65 degrees C rise above a 30 degrees C average ambient, self-cooled type.

b. Transformer rated as indicated kVA.

c. Transformer voltage ratings: as indicated

d. Tap changer: externally operated, manual type for changing tap setting when the transformer is de-energized. Provide four 2.5 percent full capacity taps, two above and two below rated primary voltage. Indicate which tap setting is in use, clearly visible when the compartment is opened.

e. Minimum tested percent impedance at 85 degrees C:

2.50 for units rated 75kVA and below
2.87 for units rated 112.5kVA to 300kVA
4.03 for 500kVA rated units
5.32 for units rated 750kVA and above

f. Comply with the following audible sound level limits:

kVA	DECIBELS (MAX
75	51
112.5	55
150	55
225	55
300	55
500	56
750	57
1000	58
1500	60

2000	61
2500	62

g. Include:

(1) Lifting lugs and provisions for jacking under base, with base construction suitable for using rollers or skidding in any direction.

(3) Provide transformer top with an access handhole.

(4) kVA rating conspicuously displayed using 3 inch high yellow letters on its enclosure.

2.2.2.1 Specified Transformer Efficiencies

Provide transformer efficiency calculations utilizing the actual no-load and load loss values obtained during the routine tests performed on the actual transformer(s) prepared for this project. Reference no-load losses (NLL) at 20 degrees C. Reference load losses (LL) at 55 degrees C and at 50 percent of the nameplate load. The transformer is not acceptable if the calculated transformer efficiency is less than the efficiency indicated in the "KVA / Efficiency" table below. The table is based on requirements contained within 10 CFR 431, Subpart K. Submit certification, including supporting calculations, from the manufacturer indicating conformance.

kVA	EFFICIENCY (percent)
15	98.65
30	98.83
45	98.92
75	99.03
112.5	99.11
150	99.16
225	99.23
300	99.27
500	99.35
750	99.40
1000	99.43
1500	99.48

2000	99.51
2500	99.53
above 2500	99.54

2.2.3 Insulating Liquid

a. Less-flammable transformer liquids: NFPA 70 and FM APP GUIDE for less-flammable liquids having a fire point not less than 300 degrees C tested per ASTM D92 and a dielectric strength not less than 33 kV tested per ASTM D877/D877M. Provide identification of transformer as "non-PCB" and "manufacturer's name and type of fluid" on the nameplate.

Provide a fluid that is a biodegradable, electrical insulating, and cooling liquid classified by UL and approved by FM as "less flammable" with the following properties:

(1) Pour point: ASTM D97, less than -15 degree C

(2) Aquatic biodegradation: EPA 712-C-98-075, ultimately biodegradable as designated by EPA.

(3) Trout toxicity: OECD Test 203, zero mortality of EPA 821-R-02-012, pass

b. Mineral oil: ASTM D3487, Type II, tested in accordance with ASTM D117. Provide identification of transformer as "non-PCB" and "Type II mineral oil" on the nameplate.

2.2.3.1 Liquid-Filled Transformer Nameplates

Provide nameplate information in accordance with IEEE C57.12.00 and as modified or supplemented by this section.

2.2.4 Corrosion Protection

Provide corrosion resistant bases and cabinets of transformers, fabricated of stainless steel conforming to ASTM A240/A240M, Type 304 or 304L. Base includes any part of pad-mounted transformer that is within 3 inches of concrete pad.

Paint entire transformer assembly Munsell 7GY3.29/1.5 green, with paint coating system complying with IEEE C57.12.28 regardless of base, cabinet, and tank material. The Munsell color notation is specified in ASTM D1535.

2.3 WARNING SIGNS AND LABELS

Provide warning signs for the enclosures of pad-mounted transformers having a nominal rating exceeding 600 volts in accordance with NEMA Z535.4 and NEMA 260.

a. When the enclosure integrity of such equipment is specified to be in accordance with IEEE C57.12.28, such as for pad-mounted transformers, provide self-adhesive warning labels on the outside of the high voltage compartment door(s)with nominal dimensions of 7 by 10 inches with the legend "WARNING HIGH VOLTAGE" printed in two lines of nominal 2 inch high letters. Include the work "WARNING" in white letters on

an orange background and the words "HIGH VOLTAGE" in black letters on a white background.

b. When such equipment is guarded by a fence, mount signs on the fence. Provide metal signs having nominal dimensions of 14 by 10 inches with the legend "WARNING HIGH VOLTAGE KEEP OUT" printed in three lines of nominal 3 inch high white letters on an orange and black field.

2.4 ARC FLASH WARNING LABEL

Provide arc flash warning label for the enclosure of pad-mounted transformers. Locate this self-adhesive warning label on the outside of the high voltage compartment door warning of potential electrical arc flash hazards and appropriate PPE required. Provide label format as indicated.

2.5 GROUNDING AND BONDING

UL 467. Provide grounding and bonding as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.

2.6 PADLOCKS

Provide padlocks for pad-mounted equipment and for each fence gate, keyed as directed by the Contracting Officer. Comply with Section 08 71 00 DOOR HARDWARE.

2.7 CAST-IN-PLACE CONCRETE

Provide concrete associated with electrical work as follows:

a. Composed of fine aggregate, coarse aggregate, portland cement, and water so proportioned and mixed as to produce a plastic, workable mixture.

b. Fine aggregate: hard, dense, durable, clean, and uncoated sand.

c. Coarse aggregate: reasonably well graded from 3/16 inch to 1 inch.

d. Fine and coarse aggregates: free from injurious amounts of dirt, vegetable matter, soft fragments or other deleterious substances.

e. Water: fresh, clean, and free from salts, alkali, organic matter, and other impurities.

f. Concrete associated with electrical work for other than encasement of underground ducts: 4000 psi minimum 28-day compressive strength unless specified otherwise.

g. Slump: Less than 4 inches. Retempering of concrete will not be permitted.

h. Exposed, unformed concrete surfaces: smooth, wood float finish.

i. Concrete must be cured for a period of not less than 7 days, and concrete made with high early strength portland cement must be repaired by patching honeycombed or otherwise defective areas with cement mortar as directed by the Contracting Officer.

j. Air entrain concrete exposed to weather using an air-entraining admixture conforming to ASTM C260/C260M.

k. Air content: between 4 and 6 percent.

2.8 SOURCE QUALITY CONTROL

2.8.1 Transformer Test Schedule

The Government reserves the right to witness tests. Provide transformer test schedule for tests to be performed at the manufacturer's test facility. Submit required test schedule and location, and notify the Contracting Officer 30 calendar days before scheduled test date. Notify Contracting Officer 15 calendar days in advance of changes to scheduled date.

a. Test Instrument Calibration

(1) Provide a calibration program which assures that all applicable test instruments are maintained within rated accuracy.

(2) Accuracy: Traceable to the National Institute of Standards and Technology.

(3) Instrument calibration frequency schedule: less than or equal to 12 months for both test floor instruments and leased specialty equipment.

(4) Dated calibration labels: visible on all test equipment.

(5) Calibrating standard: higher accuracy than that of the instrument tested.

(6) Keep up-to-date records that indicate dates and test results of instruments calibrated or tested. For instruments calibrated by the manufacturer on a routine basis, in lieu of third party calibration, include the following:

(a) Maintain up-to-date instrument calibration instructions and procedures for each test instrument.

(b) Identify the third party/laboratory calibrated instrument to verify that calibrating standard is met.

2.8.2 Design Tests

IEEE C57.12.00, and IEEE C57.12.90. Section 5.1.2 in IEEE C57.12.80 states that "design tests are made only on representative apparatus of basically the same design." Submit design test reports (complete with test data, explanations, formulas, and results), in the same submittal package as the catalog data and drawings for each of the specified transformer(s), with design tests performed prior to the award of this contract.

a. Tests: certified and signed by a registered professional engineer.

b. Temperature rise: "Basically the same design" for the temperature rise test means a pad-mounted transformer with the same coil

construction (such as wire wound primary and sheet wound secondary), the same kVA, the same cooling type (KNAN), the same temperature rise rating, and the same insulating liquid as the transformer specified.

c. Lightning impulse: "Basically the same design" for the lightning impulse dielectric test means a pad-mounted transformer with the same BIL, the same coil construction (such as wire wound primary and sheet wound secondary), and a tap changer, if specified. Design lightning impulse tests includes the primary windings only of that transformer.

(1) IEEE C57.12.90, paragraph 10.3 entitled "Lightning Impulse Test Procedures," and IEEE C57.98.

(2) State test voltage levels.

(3) Provide photographs of oscilloscope display waveforms or plots of digitized waveforms with test report.

d. Lifting and moving devices: "Basically the same design" requirement for the lifting and moving devices test means a test report confirming that the lifting device being used is capable of handling the weight of the specified transformer in accordance with IEEE C57.12.34.

e. Pressure: "Basically the same design" for the pressure test means a pad-mounted transformer with a tank volume within 30 percent of the tank volume of the transformer specified.

f. Short circuit: "Basically the same design" for the short circuit test means a pad-mounted transformer with the same kVA as the transformer specified.

2.8.3 Routine and Other Tests

IEEE C57.12.00. Routine and other tests: performed in accordance with IEEE C57.12.90 by the manufacturer on each of the actual transformer(s) prepared for this project to ensure that the design performance is maintained in production. Submit test reports, by serial number and receive approval before delivery of equipment to the project site. Required tests and testing sequence as follows:

a. Phase relation

b. Ratio

c. No-load losses (NLL) and excitation current

d. Load losses (LL) and impedance voltage

e. Dielectric

(1) Impulse

(2) Applied voltage

(3) Induced voltage

f. Leak

PART 3 EXECUTION

3.1 INSTALLATION

Conform to IEEE C2, NFPA 70, and to the requirements specified herein. Provide new equipment and materials unless indicated or specified otherwise.

3.2 GROUNDING

NFPA 70 and IEEE C2, except provide grounding systems with a resistance to solid earth ground not exceeding 25 ohms.

3.2.1 Grounding Electrodes

Provide driven ground rods as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION. Connect ground conductors to the upper end of ground rods by exothermic weld or compression connector. Provide compression connectors at equipment end of ground conductors.

3.2.2 Pad-Mounted Transformer Grounding

Provide a ground ring around the transformer with 4/0 AWG bare copper. Provide four ground rods in the ground ring, one per corner. Install the ground rods at least 10 feet apart from each other. Provide separate copper grounding conductors and connect them to the ground loop as indicated. When work in addition to that indicated or specified is required to obtain the specified ground resistance, the provision of the contract covering "Changes" applies.

3.2.3 Connections

Make joints in grounding conductors and loops by exothermic weld or compression connector. Install exothermic welds and compression connectors as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.

3.2.4 Grounding and Bonding Equipment

UL 467, except as indicated or specified otherwise.

3.3 INSTALLATION OF EQUIPMENT AND ASSEMBLIES

Install and connect pad-mounted transformers furnished under this section as indicated on project drawings, the approved shop drawings, and as specified herein.

3.3.1 Meters and Current Transformers

ANSI C12.1.

3.4 FIELD APPLIED PAINTING

Where field painting of enclosures is required to correct damage to the manufacturer's factory applied coatings, provide manufacturer's recommended coatings and apply in accordance with manufacturer's instructions.

3.5 FOUNDATION FOR EQUIPMENT AND ASSEMBLIES

Mount transformer on concrete slab as follows:

a. Unless otherwise indicated, provide the slab with dimensions at least 8 inches thick, reinforced with a 6 by 6 inches - W2.9 by W2.9 mesh placed uniformly 4 inches from the top of the slab.

b. Place slab on a 6 inch thick, well-compacted gravel base.

c. Install slab such that top of concrete slab is approximately 4 inches above the finished grade with gradual slope for drainage.

d. Provide edges above grade with 1/2 inch chamfer.

e. Provide slab of adequate size to project at least 8 inches beyond the equipment.

Stub up conduits, with bushings, 2 inches into cable wells in the concrete pad. Coordinate dimensions of cable wells with transformer cable training areas.

3.5.1 Cast-In-Place Concrete

Provide cast-in-place concrete work in accordance with the requirements of Section 03 30 00 CAST-IN-PLACE CONCRETE.

3.5.2 Sealing

When the installation is complete, seal all entries into the equipment enclosure with an approved sealing method. Provide seals of sufficient strength and durability to protect all energized live parts of the equipment from rodents, insects, or other foreign matter.

3.6 FIELD QUALITY CONTROL

3.6.1 Performance of Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations and include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS. Submit reports, including acceptance criteria and limits for each test in accordance with NETA ATS "Test Values".

3.6.1.1 Pad-Mounted Transformers

a. Visual and mechanical inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition. Check for damaged or cracked insulators and leaks.

(3) Inspect anchorage, alignment, and grounding.

(4) Verify the presence of PCB content labeling.

(5) Verify the bushings and transformer interiors are clean.

(6) Inspect all bolted electrical connections for high resistance using low-resistance ohmmeter, verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey.

(7) Verify correct liquid level in tanks and bushings.

(8) Verify that positive pressure is maintained on gas-blanketed transformers.

(9) Perform specific inspections and mechanical tests as recommended by manufacturer.

(10) Verify de-energized tap changer position is left as specified.

(11) Verify the presence of transformer surge arresters.

b. Electrical tests

(1) Perform resistance measurements through all bolted connections with low-resistance ohmmeter.

(2) Verify proper secondary voltage phase-to-phase and phase-to-neutral after energization and prior to loading.

(3) Perform insulation-resistance tests, winding-to-winding and each winding-to-ground. Calculate polarization index. Verify that the tap changer is set at the specified ratio.

(4) Perform turns-ratio tests at all tap positions.

(5) Perform insulation power-factor or dissipation-factor tests on all windings in accordance with test equipment manufacturer’s published data.

(6) Perform power-factor or dissipation-factor tests on each bushing equipped with a power-factor/capacitance tap. In the absence of a power-factor/capacitance tap, perform hot-collar tests.

(7) Measure the resistance of each high-voltage winding in each de-energized tap-changer position. Measure the resistance of each low-voltage winding in each de-energized tap-changer position, if applicable.

(8) Remove and test a sample of insulating liquid for the following: Dielectric breakdown voltage, Acid neutralization number, Specific gravity, Interfacial tension, Color, Visual Condition, Water in insulating liquids (Required on 25 kV or higher voltages and on all silicone-filled units.), and Power factor or dissipation factor.

(9) Perform dissolved-gas analysis (DGA) on a sample of insulating liquid.

3.6.1.2 Current Transformers

a. Visual and mechanical inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Verify correct connection.

(4) Verify that adequate clearances exist between primary and secondary circuit wiring.

(5) Verify the unit is clean.

(6) Inspect all bolted electrical connections for high resistance using low-resistance ohmmeter, verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey.

(7) Verify that all required grounding and shorting connections provide good contact.

(8) Verify correct operation of transformer withdrawal mechanism and grounding operation.

(9) Verify appropriate lubrication on moving current-carrying parts and on moving and sliding surfaces.

b. Electrical tests

(1) Perform resistance measurements through all bolted connections with low-resistance ohmmeter, if applicable.

(2) Perform insulation-resistance test.

(3) Perform a polarity test.

(4) Perform a ratio-verification test.

3.6.1.3 Watthour Meter

a. Visual and mechanical inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Verify tightness of electrical connections.

b. Electrical tests

(1) Calibrate watthour meters according to manufacturer's published data.

(2) Verify that correct multiplier has been placed on face of meter, where applicable.

(3) Verify that current transformer secondary circuits are intact.

3.6.1.4 Grounding System

a. Visual and mechanical inspection

(1) Inspect ground system for compliance with contract plans and specifications.

b. Electrical tests

(1) Perform ground-impedance measurements utilizing the fall-of-potential method. On systems consisting of interconnected ground rods, perform tests after interconnections are complete. On systems consisting of a single ground rod perform tests before any wire is connected. Take measurements in normally dry weather, not less than 48 hours after rainfall. Use a portable ground resistance tester in accordance with manufacturer's instructions to test each ground or group of grounds. Use an instrument equipped with a meter reading directly in ohms or fractions thereof to indicate the ground value of the ground rod or grounding systems under test.

(2) Submit the measured ground resistance of each ground rod and grounding system, indicating the location of the rod and grounding system. Include the test method and test setup (i.e., pin location) used to determine ground resistance and soil conditions at the time the measurements were made.

3.6.1.5 Surge Arresters, Medium- and High-Voltage

a. Visual and mechanical inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Inspect anchorage, alignment, grounding, and clearances.

(4) Verify the arresters are clean.

(5) Inspect all bolted electrical connections for high resistance using low-resistance ohmmeter, verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey.

(6) Verify that the ground lead on each device is individually attached to a ground bus or ground electrode.

b. Electrical tests

(1) Perform resistance measurements through all bolted connections with low-resistance ohmmeter, if applicable.

(2) Perform an insulation-resistance test on each arrester, phase terminal-to-ground.

(3) Test grounding connection.

3.6.2 Follow-Up Verification

Upon completion of acceptance checks and tests, show by demonstration in service that circuits and devices are in good operating condition and properly performing the intended function. As an exception to requirements stated elsewhere in the contract, notify the Contracting Officer 5 working days in advance of the dates and times of checking and testing.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 13 00

SF6/HIGH-FIREPOINT FLUIDS INSULATED PAD-MOUNTED SWITCHGEAR
05/21, CHG 1: 05/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D1535	(2014; R 2018) Standard Practice for Specifying Color by the Munsell System
ASTM D2472	(2000; R 2014) Standard Specification for Sulphur Hexafluoride
ASTM D6871	(2017) Standard Specification for Natural (Vegetable Oil) Ester Fluids Used in Electrical Apparatus

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 386	(2016) Separable Insulated Connector Systems for Power Distribution Systems Rated 2.5 kV through 35 kV
IEEE C2	(2023) National Electrical Safety Code
IEEE C37.60	(2019) High-Voltage Switchgear and Controlgear - Part 111: Automatic Circuit Reclosers for Alternating Current Systems Up to 38 kV
IEEE C37.74	(2014) Standard Requirements for Subsurface, Vault, and Pad-Mounted Load-Interrupter Switchgear and Fused Load-Interrupter Switchgear for Alternating Current Systems Up to 38 kV
IEEE C57.12.28	(2014) Standard for Pad-Mounted Equipment - Enclosure Integrity
IEEE C62.11	(2020) Standard for Metal-Oxide Surge Arresters for Alternating Current Power Circuits (>1kV)

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2021) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

INTERNATIONAL ELECTROTECHNICAL COMMISSION (IEC)

IEC 61099	(2010; ED 2.0) Insulating Liquids - Specifications for Unused Synthetic Organic Esters for Electrical Purposes
IEC 62271-103	(2021) High-Voltage Switchgear and Controlgear – Part 103: Switches for Rated Voltages Above 1 Kv up to and Including 52 Kv
IEC 62271-111	(2019) High Voltage Switchgear And Controlgear - Part 111: Automatic Circuit Reclosers for Alternating Current Systems up to and including 38 kV

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 70B	(2023) Recommended Practice for Electrical Equipment Maintenance

U.S. DEPARTMENT OF DEFENSE (DOD)

DOD 8500.01	(2014; Change 1-2019) Cybersecurity
DOD 8510.01	(2022) Risk Management Framework (RMF) for DoD Systems

UL SOLUTIONS (UL)

UL 467	(2022) UL Standard for Safety Grounding and Bonding Equipment

1.2 RELATED REQUIREMENTS

Section 26 08 00 APPARATUS INSPECTION AND TESTING, applies to this section, with the additions and modifications specified herein. Cybersecurity requirements are specified in Section 25 05 11.00 CYBERSECURITY FOR FACILITY-RELATED CONTROL SYSTEMS - ISOLATED SYSTEMS.

1.3 DEFINITIONS

1.3.1 Switched Way

A switched way is considered a three-phase circuit entrance to the bus through a switch. For single-phase switches, it is a single-phase entrance to the bus through a switch.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Switchgear Drawings; G

SD-03 Product Data

Electronic Overcurrent Control Curves; G

SF6/High-Firepoint Fluid Insulated Pad-mounted Switchgear; G

Include data on switches and associated accessories with each submittal. Include manufacturer's information for each component, device and accessory provided with the equipment with each submittal.

Insulated High-Voltage Connectors; G

Surge Arresters; G

SD-06 Test Reports

Acceptance Checks and Tests; G

SD-07 Certificates

Paint Coating System; G

Cybersecurity; G

SD-09 Manufacturer's Field Reports

Switchgear Design and Production Tests; G

SD-10 Operation and Maintenance Data

SF6/High-Firepoint Fluid Insulated Pad-mounted Switchgear, Data Package 5; G

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.5 QUALITY ASSURANCE

1.5.1 Switchgear Drawings

Furnish drawings that include, but are not limited to, the following:

a. Overall dimensions, weights, plan view, and front view

b. Ratings

c. Single-line diagram.

1.5.2 Paint Coating System

Submit IEEE C57.12.28 paint coating system performance requirement tests.

1.5.3 Electronic Overcurrent Control Curves

Provide time-current characteristic curves in PDF format and in electronic format suitable for import or updating into the SKM PowerTools for Windows computer program.

1.6 MAINTENANCE

1.6.1 SF6/High-Firepoint Fluid Insulated Pad-mounted Switchgear Operation and Maintenance

Submit Operation and Maintenance Manuals in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.7 CYBERSECURITY

All control systems (including systems separate from an energy management control system) must be planned, designed, acquired, executed and maintained in accordance with DOD 8500.01 and DOD 8510.01, and as required by individual Service Implementation Policy.

Submit certification that equipment complies with the above DoD instructions and .

PART 2 PRODUCTS

2.1 SF6/HIGH-FIREPOINT FLUID INSULATED PAD-MOUNTED SWITCHGEAR

IEEE C37.74

2.1.1 Ratings and Test Requirements

The voltage rating of the switchgear must be 15.5 kV. Provide the corresponding ratings associated with the required switchgear voltage rating as follows:

Rated Maximum Voltage, kV	15.5
Rated Withstand Impulse Voltage, kV BIL	95
Continuous and Load Interrupting Current, A	600
Short-Time Current, kA rms Sym	12.5
Short-Circuit interrupting Current,kA rms Sym	12.5

2.1.2 Switchgear Construction

Provide switchgear with switch contacts and cable entrance terminations contained in a sealed, dielectric-filled stainless steel tank. Ship switchgear from factory, filled with appropriate levels of SF6 gas conforming to ASTM D2472 or less-flammable, high-firepoint biodegradable fluid conforming to ASTM D6871 or IEC 61099. Configure switchgear with

load interrupting and fault interrupting switched ways as indicated. Provide switchgear with front accessible terminations suitable for cables entering from below with manual operating provisions either mounted on the rear or capable of hookstick operation per IEEE C37.74. Provide internal gas pressure gage or fluid level gage in viewable location from switch operating handle. Provide each switched way with three position switch; Open, Closed, Ground.

2.1.2.1 Pad-mounting Provisions

Provide enclosed switchgear suitable for installation on a concrete pad. Fabricate switchgear enclosure base with type 304 or 304L stainless steel. Enclosure base must include any part of the switchgear enclosure that is within 3 inches of concrete pad. Paint enclosure including base ASTM D1535 Munsell 7GY3.29/1.5 green. Comply with IEEE C57.12.28 for the paint coating system regardless of equipment material.

2.1.3 Load Interrupting Switched Ways

2.1.3.1 Three-Pole Group Operated Switched Ways

Provide three-pole group operated load interrupting switched ways as indicated.

2.1.3.2 Fault Interrupting Switched Ways

IEEE C37.60, IEC 62271-111. Provide non-fused, non-reclosing, manual reset, vacuum interrupters consisting of vacuum interrupter and a spring assisted operating mechanism. Each fault interrupting switched way must utilize internally mounted current transformers and an electronic overcurrent control to provide three-pole ganged tripping as indicated for single-phase and three-phase faults. Provide electronic overcurrent control with provisions for a minimum of ten field changeable overcurrent trip settings.

2.1.4 Automatic Switch Controls

Provide an automatic switch control system to execute Manual, SCADA , Automatic Source-Transfer, and Fault Detection Isolation and Restoration operations. Power the switch control system and associated communication port provisions from an integral battery-charger DC supply system. Use motor operators and associated motor operator controllers for switch way operation. Use 120 Vac control power from switchgear itself for automatic switch control.

2.1.4.1 Manual Operation

Provide the motor operator controllers with "Close" and "Open" pushbuttons for manual operation.

2.1.4.2 SCADA Operation

The automatic switch control system must execute remote commands received from a SCADA master station and transmit switchgear operation information to a SCADA master station via a DNP 3.0 100Base-FX Ethernet communication port. Include transfer of switch ways to "Close" and "Open" positions and enabling of the Source-Transfer operation for execution of remote commands. Include switch way position status, voltage and current readings, and DC supply system status with communication of switchgear

information.

2.1.4.3 Source-Transfer Operation

Provide an automatic switch control system that opens an incoming switch way when voltage is lost and closes the alternate incoming switch way if voltage is present. Include with the Source-Transfer controls an overcurrent-lockout feature that prevents automatic closing of a switch way into a system fault. Include provisions for returning the system to the normal configuration via manual, SCADA, or automatic operations when voltage is restored.

2.1.4.4 Fault Detection Isolation and Restoration Operation

The automatic switch control system must execute circuit fault detection isolation operation for closed and open loop distribution systems. Provide communication via a peer-to-peer fiber optic network for the pad mount switchgear unit automatic switch control systems. Provide an optical fiber cable approved by the automatic switch control system manufacturer.

2.1.5 Low Voltage Test Points

Provide load interrupting switch ways with internal load side voltage sensors that allow for low voltage checks with relay interface at test point of elbow connectors to confirm energized and in-phase conditions using a standard high-impedance voltmeter.

2.1.6 Key Interlock

Provide key interlock system as indicated on the drawings.

2.1.7 Dead-Front High-Voltage Bushings

IEEE 386. 15 kV, 95 kV BIL. Provide 600 ampere one-piece deadbreak apparatus bushings for each switched way.

a. Parking stands: Provide a parking stand near each dead-front bushing. Provide insulated standoff bushings for parking of energized load-break connectors on each parking stands.

2.2 INSULATED HIGH-VOLTAGE CONNECTORS

IEEE 386. Provide corresponding connector for each switched way. Provide a grounding eye and test point on each connector.

a. 600 Ampere deadbreak connector ratings: Voltage: 15 kV, 95 kV BIL. Short time rating: 25,000 rms symmetrical amperes. Provide connectors with 200 ampere bushing interface.

b. Provide one set of three grounding elbows. Deliver grounding elbows to the Contracting Officer.

2.3 SURGE ARRESTERS

IEEE C62.11, rated 10 kV , fully shielded, dead-front, metal-oxide-varistor, elbow type with resistance-graded gap, suitable for plugging into inserts. Provide arresters on switched ways as indicated.

2.4 SF6 REFILL CYLINDERS

Provide two SF6 refill cylinders, minimum size of 6 pounds of SF6; include regulator, valves, and hose for connection to the fill valve of the switch.

2.5 SOURCE QUALITY CONTROL

2.5.1 Switchgear Design and Production Tests

Furnish reports which include results of design and production tests performed according to IEEE C37.74, IEC 62271-103. Perform manufacturer production tests on each switchgear assembly to ensure that design performance is maintained in production.

PART 3 EXECUTION

3.1 INSTALLATION

Conform to IEEE C2, NFPA 70, and to the requirements specified herein.

3.2 GROUNDING

NFPA 70 and IEEE C2, except provide grounds and grounding systems with a resistance to solid earth ground not exceeding 25 ohms. When work, in addition to that indicated or specified, is directed to obtain the specified ground resistance, the provision of the contract covering "Changes" applies.

3.2.1 Grounding Electrodes

Provide driven ground rods as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION at each corner of switchgear pad as indicated.

3.2.2 Switchgear Grounding

Connect #4/0 bare copper conductor ground ring, not less than 24 inches below grade, to the upper end of the ground rods by exothermic welds or compression connectors. Provide #4/0 bare copper conductors connecting the switchgear grounding provisions to two different ground rods.

3.2.3 Connections

Make joints in grounding conductors and ground ring by exothermic weld or compression connector. Install exothermic welds and compression connectors as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.

3.2.4 Grounding and Bonding Equipment

UL 467, except as indicated or specified otherwise.

3.3 FOUNDATION FOR EQUIPMENT AND ASSEMBLIES

Mount switch on concrete slab. Provide slab with dimensions at least 12 inches thick, reinforced with a 6 by 6 - W2.9 by W2.9 mesh, placed uniformly 4 inches from the top of the slab. Place slab on a 6 inch thick, well-compacted gravel base. Install top of concrete slab approximately 4 inches above finished grade. Provide edges above grade with 1/2 inch chamfer. Provide slab of adequate size to project at least

8 inches beyond equipment.

Stub up conduits, with bushings, 2 inches into cable wells in the concrete pad. Coordinate dimensions of cable wells with switch cable training areas. Provide concrete work as specified in Section 03 30 00 CAST-IN-PLACE CONCRETE.

3.4 FIELD QUALITY CONTROL

3.4.1 Performance of Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations, NFPA 70B, NETA ATS and referenced ANSI standards.

Include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

3.4.1.1 Switchgear

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate information with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Check for proper anchorage, alignment, required area clearances, and grounding.

(4) Perform mechanical operator tests in accordance with manufacturer's instructions.

(5) Verify that insulating SF6 gas pressure or dielectric fluid level is correct.

(6) Inspect all indicating devices for proper operation.

(7) Test interlock systems for proper operation and sequencing.

b. Electrical Tests

(1) Perform contact-resistance tests.

(2) Trip fault interrupters by operation of overcurrent control and remote trip.

(3) Perform insulation-resistance tests.

(4) Perform an over-potential test on each switched way pole with the switched way in the open position in accordance with the manufacturer's instructions.

(5) Set fault interrupter overcurrent control in accordance with government provided settings. Request settings from government, in writing, a minimum of 30 days prior to scheduling electrical tests.

3.4.1.2 Grounding System

a. Visual and Mechanical Inspection

Inspect ground system for compliance with contract plans and specifications.

b. Electrical Tests

(1) Perform ground-impedance measurements utilizing the fall-of-potential method. On systems consisting of interconnected ground rods, perform tests after interconnections are complete. On systems consisting of a single ground rod perform tests before any wire is connected. Take measurements in normally dry weather, not less than 48 hours after rainfall. Use a portable ground resistance tester in accordance with manufacturer's instructions to test each ground or group of grounds. Use an instrument equipped with a meter reading directly in ohms or fractions thereof to indicate the ground value of the ground rod or grounding systems under test.

(2) Submit the measured ground resistance of each ground rod and grounding system, indicating the location of the rod and grounding system. Include the test method and test setup (i.e., pin location) used to determine ground resistance and soil conditions at the time the measurements were made.

3.4.2 Follow-Up Verification

Upon completion of acceptance checks and tests, show by demonstration in service that devices are in good operating condition and properly performing the intended function. Perform each test function not less than three times. As an exception to requirements stated elsewhere in the contract, notify the Contracting Officer five working days in advance of the dates and times for checks and tests.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 20 00

INTERIOR DISTRIBUTION SYSTEM
08/19, CHG 3: 11/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B1	(2013) Standard Specification for Hard-Drawn Copper Wire
ASTM B8	(2011; R 2017) Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM D709	(2017) Standard Specification for Laminated Thermosetting Materials

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 81	(2012) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System
IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2021) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA)

NECA NEIS 1	(2015) Standard for Good Workmanship in Electrical Construction

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI C80.1	(2020) American National Standard for Electrical Rigid Steel Conduit (ERSC)
ANSI C80.3	(2020) American National Standard for Electrical Metallic Tubing (EMT)
ANSI C80.5	(2020) American National Standard for Electrical Rigid Aluminum Conduit
NEMA 250	(2020) Enclosures for Electrical Equipment (1000 Volts Maximum)

NEMA FU 1	(2012) Low Voltage Cartridge Fuses
NEMA ICS 1	(2022) Standard for Industrial Control and Systems: General Requirements
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA KS 1	(2013) Enclosed and Miscellaneous Distribution Equipment Switches (600 V Maximum)
NEMA RN 1	(2005; R 2013) Polyvinyl-Chloride (PVC) Externally Coated Galvanized Rigid Steel Conduit and Intermediate Metal Conduit
NEMA ST 20	(2014) Dry-Type Transformers for General Applications
NEMA TC 2	(2020) Standard for Electrical Polyvinyl Chloride (PVC) Conduit
NEMA TC 3	(2021) Polyvinyl Chloride (PVC) Fittings for Use With Rigid PVC Conduit and Tubing
NEMA VE 1	(2017) Metal Cable Tray Systems
NEMA WD 1	(1999; R 2020) Standard for General Color Requirements for Wiring Devices
NEMA WD 6	(2016) Wiring Devices Dimensions Specifications
NEMA Z535.4	(2011; R 2017) Product Safety Signs and Labels

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 70E	(2024) Standard for Electrical Safety in the Workplace
NFPA 780	(2026) Standard for the Installation of Lightning Protection Systems

TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA)

TIA-568.1	(2020e) Commercial Building Telecommunications Infrastructure Standard
TIA-569	(2019e) Telecommunications Pathways and Spaces
TIA-607	(2019d) Generic Telecommunications Bonding

and Grounding (Earthing) for Customer Premises

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

10 CFR 431	Energy Efficiency Program for Certain Commercial and Industrial Equipment
29 CFR 1910.147	The Control of Hazardous Energy (Lock Out/Tag Out)
29 CFR 1910.303	Electrical, General

UL SOLUTIONS (UL)

UL 1	(2005; Reprint Jan 2022) UL Standard for Safety Flexible Metal Conduit
UL 6	(2022) UL Standard for Safety Electrical Rigid Metal Conduit-Steel
UL 6A	(2008; Reprint Mar 2021) UL Standard for Safety Electrical Rigid Metal Conduit - Aluminum, Red Brass, and Stainless Steel
UL 20	(2025) UL Standard for Safety General-Use Snap Switches
UL 50	(2024) UL Standard for Safety Enclosures for Electrical Equipment, Non-Environmental Considerations
UL 67	(2018; Reprint Jul 2020) UL Standard for Safety Panelboards
UL 83	(2017; Reprint Mar 2020) UL Standard for Safety Thermoplastic-Insulated Wires and Cables
UL 248-4	(2010; Reprint Apr 2019) Low-Voltage Fuses - Part 4: Class CC Fuses
UL 248-8	(2011; Reprint Aug 2020) Low-Voltage Fuses - Part 8: Class J Fuses
UL 248-10	(2011; Reprint Aug 2020) Low-Voltage Fuses - Part 10: Class L Fuses
UL 248-12	(2011; Reprint Aug 2020) Low Voltage Fuses - Part 12: Class R Fuses
UL 248-15	(2018) Low-Voltage Fuses - Part 15: Class T Fuses
UL 360	(2013; Reprint Aug 2021) UL Standard for Safety Liquid-Tight Flexible Metal Conduit
UL 467	(2022) UL Standard for Safety Grounding and Bonding Equipment

UL 486A-486B	(2018; Reprint May 2021) UL Standard for Safety Wire Connectors
UL 486C	(2018; Reprint May 2021) UL Standard for Safety Splicing Wire Connectors
UL 489	(2025) UL Standard for Safety Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures
UL 498	(2017; Reprint Sep 2021) UL Standard for Safety Attachment Plugs and Receptacles
UL 510	(2020; Dec 2022) UL Standard for Safety Polyvinyl Chloride, Polyethylene and Rubber Insulating Tape
UL 514A	(2013; Reprint Aug 2017) UL Standard for Safety Metallic Outlet Boxes
UL 514B	(2012; Reprint May 2020) Conduit, Tubing and Cable Fittings
UL 514C	(2014; Reprint Feb 2020) UL Standard for Safety Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers
UL 651	(2011; Reprint Mar 2020) UL Standard for Safety Schedule 40, 80, Type EB and A Rigid PVC Conduit and Fittings
UL 797	(2007; Reprint Mar 2021) UL Standard for Safety Electrical Metallic Tubing -- Steel
UL 817	(2015; Reprint Sep 2021) UL Standard for Safety Cord Sets and Power-Supply Cords
UL 854	(2020) Standard for Service-Entrance Cables
UL 869A	(2006; Reprint Jun 2020) Reference Standard for Service Equipment
UL 943	(2016; Reprint Feb 2018) UL Standard for Safety Ground-Fault Circuit-Interrupters
UL 1242	(2006; Reprint Aug 2020) Standard for Electrical Intermediate Metal Conduit -- Steel
UL 1283	(2017) UL Standard for Safety Electromagnetic Interference Filters
UL 1449	(2021; Reprint Oct 2025) UL Standard for Safety Surge Protective Devices
UL 1561	(2011; Reprint Jun 2015) Dry-Type General Purpose and Power Transformers

UL 1569	(2018) UL Standard for Safety Metal-Clad Cables
UL 1660	(2019) Liquid-Tight Flexible Nonmetallic Conduit
UL 4248-1	(2017) UL Standard for Safety Fuseholders - Part 1: General Requirements
UL 4248-12	(2018) UL Standard for Safety Fuseholders - Part 12: Class R

1.2 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, are as defined in IEEE 100.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Panelboards; G

Transformers; G

Cable Trays; G

SD-03 Product Data

Receptacles; G

Circuit Breakers; G

Switches; G

Transformers; G

Enclosed Circuit Breakers; G
Manual Motor Starters; G

Secondary Bonding Busbar; G

Surge Protective Devices; G

Cable Trays; G

SD-06 Test Reports

600-volt Wiring Test; G

Grounding System Test; G

Transformer Tests; G

Ground-fault Receptacle Test; G

SD-07 Certificates

Fuses; G

SD-09 Manufacturer's Field Reports

Transformer Factory Tests

SD-10 Operation and Maintenance Data

Electrical Systems, Data Package 5; G

1.4 QUALITY ASSURANCE

1.4.1 Fuses

Submit coordination data as specified in paragraph, FUSES of this section.

1.4.2 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Provide equipment, materials, installation, and workmanship in accordance with NFPA 70 unless more stringent requirements are specified or indicated. NECA NEIS 1 shall be considered the minimum standard for workmanship.

1.4.3 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship and:

a. Have been in satisfactory commercial or industrial use for 2 years prior to bid opening including applications of equipment and materials under similar circumstances and of similar size.

b. Have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period.

c. Where two or more items of the same class of equipment are required, provide products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.4.3.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.4.3.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site are not acceptable.

1.5 MAINTENANCE

1.5.1 Electrical Systems

Submit operation and maintenance data in accordance with Section 01 78 23, OPERATION AND MAINTENANCE DATA and as specified herein. Submit operation and maintenance manuals for electrical systems that provide basic data relating to the design, operation, and maintenance of the electrical distribution system for the building. Include the following:

a. Single line diagram of the "as-built" building electrical system.

b. Schematic diagram of electrical control system (other than HVAC, covered elsewhere).

c. Manufacturers' operating and maintenance manuals on active electrical equipment.

1.6 WARRANTY

Provide equipment items supported by service organizations that are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

As a minimum, meet requirements of UL, where UL standards are established for those items, and requirements of NFPA 70 for all materials, equipment, and devices.

2.2 CONDUIT AND FITTINGS

Conform to the following:

2.2.1 Rigid Metallic Conduit

2.2.1.1 Rigid, Threaded Zinc-Coated Steel Conduit

ANSI C80.1, UL 6.

2.2.1.2 Rigid Aluminum Conduit

ANSI C80.5, UL 6A.

2.2.2 Rigid Nonmetallic Conduit

PVC Type EPC-40, and EPC-80 in accordance with NEMA TC 2,UL 651.

2.2.3 Intermediate Metal Conduit (IMC)

UL 1242, zinc-coated steel only.

2.2.4 Electrical, Zinc-Coated Steel Metallic Tubing (EMT)

UL 797, ANSI C80.3.

2.2.5 Plastic-Coated Rigid Steel and IMC Conduit

NEMA RN 1, Type 40(40 mils thick).

2.2.6 Flexible Metal Conduit

UL 1, limited to 6 feet.

2.2.6.1 Liquid-Tight Flexible Metal Conduit, Steel

UL 360, limited to 6 feet.

2.2.7 Fittings for Metal Conduit, EMT, and Flexible Metal Conduit

UL 514B. Ferrous fittings: cadmium- or zinc-coated in accordance with UL 514B.

2.2.7.1 Fittings for Rigid Metal Conduit and IMC

Threaded-type. Split couplings unacceptable.

2.2.7.2 Fittings for EMT

Die Cast compression type.

2.2.8 Fittings for Rigid Nonmetallic Conduit

NEMA TC 3 for PVC, and UL 514B.

2.2.9 Liquid-Tight Flexible Nonmetallic Conduit

UL 1660.

2.3 CABLE TRAYS

NEMA VE 1. Provide the following:

a. Cable trays: form a wireway system, with a nominal depth as indicated.

b. Cable trays: constructed of aluminum.

c. Cable trays: include splice and end plates, dropouts, and miscellaneous hardware.

d. Edges, fittings, and hardware: finished free from burrs and sharp edges.

e. Fittings: ensure not less than load-carrying ability of straight tray sections and have manufacturer's minimum standard radius.

f. Radius of bends: as indicated.

2.3.1 Basket-Type Cable Trays

Provide size as indicated with maximum wire mesh spacing of 2 by 4 inch.

2.3.2 Ladder-Type Cable Trays

Provide size as indicated with maximum rung spacing of 6 inches. Cable tray must be suitable for use as an equipment grounding conductor.

2.4 OUTLET BOXES AND COVERS

UL 514A, cadmium- or zinc-coated, if ferrous metal. UL 514C, if nonmetallic.

2.4.1 Floor Outlet Boxes

Provide the following:

a. Boxes: adjustable and concrete tight.

b. Each outlet: consisting of nonmetallic or cast-metal body with threaded openings, or sheet-steel body with knockouts for conduits, adjustable ring, and cover plate with 2 1/8 inch threaded plug.

d. Receptacle outlets: consisting of flush aluminum or stainless steel housing with duplex-type receptacle as specified herein.

e. Provide gaskets where necessary to ensure watertight installation.

2.5 CABINETS, JUNCTION BOXES, AND PULL BOXES

UL 50; volume greater than 100 cubic inches, NEMA Type 1 enclosure; sheet steel, hot-dip, zinc-coated. Where exposed to wet, damp, or corrosive environments, NEMA Type as indicated.

2.6 WIRES AND CABLES

Provide wires and cables in accordance applicable requirements of NFPA 70 and UL for type of insulation, jacket, and conductor specified or indicated. Do not use wires and cables manufactured more than 12 months prior to date of delivery to site.

2.6.1 Conductors

Provide the following:

a. Conductor sizes and capacities shown are based on copper, unless indicated otherwise.

b. Conductors No. 8 AWG and larger diameter: stranded.

c. Conductors No. 10 AWG and smaller diameter: solid.

d. Conductors for remote control, alarm, and signal circuits, classes 1, 2, and 3: stranded unless specifically indicated otherwise.

e. All conductors: copper.

2.6.1.1 Equipment Manufacturer Requirements

When manufacturer's equipment requires copper conductors at the terminations or requires copper conductors to be provided between components of equipment, provide copper conductors or splices, splice boxes, and other work required to satisfy manufacturer's requirements.

2.6.1.2 Minimum Conductor Sizes

Provide minimum conductor size in accordance with the following:

a. Branch circuits: No. 12 AWG.

b. Class 1 remote-control and signal circuits: No. 14 AWG.

c. Class 2 low-energy, remote-control and signal circuits: No. 16 AWG.

d. Class 3 low-energy, remote-control, alarm and signal circuits: No. 22 AWG.

e. Digital low voltage lighting control (DLVLC) system at 24 Volts or less: Category 5 UTP cables in EMT conduit.

2.6.2 Color Coding

Provide color coding for service, feeder, branch, control, and signaling circuit conductors.

2.6.2.1 Ground and Neutral Conductors

Provide color coding of ground and neutral conductors as follows:

a. Grounding conductors: Green.

b. Neutral conductors: White.

c. Exception, where neutrals of more than one system are installed in same raceway or box, other neutrals color coding: white with a different colored (not green) stripe for each.

2.6.2.2 Ungrounded Conductors

Provide color coding of ungrounded conductors in different voltage systems as follows:

a. 208/120 volt, three-phase

(1) Phase A - black

(2) Phase B - red

(3) Phase C - blue

b. 480/277 volt, three-phase

(1) Phase A - brown

(2) Phase B - orange

(3) Phase C - yellow

c. 120/240 volt, single phase: Black and red

2.6.3 Insulation

Unless specified or indicated otherwise or required by NFPA 70, provide power and lighting wires rated for 600-volts, Type THWN/THHN conforming to UL 83, except that grounding wire may be type TW conforming to UL 83; remote-control and signal circuits: Type TW or TF, conforming to UL 83. Where equipment or devices require 90-degree Centigrade (C) conductors, provide only conductors with 90-degree C insulation or better.

2.6.4 Bonding Conductors

ASTM B1, solid bare copper wire for sizes No. 8 AWG and smaller diameter; ASTM B8, Class B, stranded bare copper wire for sizes No. 6 AWG and larger diameter.

2.6.4.1 Telecommunications Bonding Backbone (TBB)

Provide a copper conductor TBB in accordance with TIA-607 with No. 6 AWG minimum size, and sized at 2 kcmil per linear foot of conductor length up to a maximum size of 750 kcmil. Provide insulated TBB with insulation as specified in the paragraph INSULATION and meeting the fire ratings of its pathway.

2.6.4.2 Bonding Conductor for Telecommunications

Provide a copper conductor Bonding Conductor for Telecommunications between the telecommunications main grounding busbar (PBB) and the electrical service ground in accordance with TIA-607. Size the bonding conductor for telecommunications the same as the TBB.

2.6.5 Service Entrance Cables

Service Entrance (SE) and Underground Service Entrance (USE) Cables, UL 854.

2.6.6 Metal-Clad Cable

UL 1569; NFPA 70, Type MC cable.

2.6.7 Cord Sets and Power-Supply Cords

UL 817.

2.7 SPLICES AND TERMINATION COMPONENTS

UL 486A-486B for wire connectors and UL 510 for insulating tapes. Connectors for No. 10 AWG and smaller diameter wires: insulated, pressure-type in accordance with UL 486A-486B or UL 486C (twist-on splicing connector). Provide solderless terminal lugs on stranded conductors.

2.8 DEVICE PLATES

Provide the following:

a. UL listed, one-piece device plates for outlets to suit the devices

installed.

b. For metal outlet boxes, plates on unfinished walls: zinc-coated sheet steel or cast metal having round or beveled edges.

c. For nonmetallic boxes and fittings, other suitable plates may be provided.

d. Plates on finished walls: nylon or lexan, minimum 0.03 inch wall thickness and same color as receptacle or toggle switch with which they are mounted.

f. Screws: machine-type with countersunk heads in color to match finish of plate.

g. Sectional type device plates are not be permitted.

h. Plates installed in wet locations: gasketed and UL listed for "wet locations."

2.9 SWITCHES

2.9.1 Toggle Switches

NEMA WD 1, UL 20, single pole, three-way, and four-way, totally enclosed with bodies of thermoplastic or thermoset plastic and mounting strap with grounding screw. Include the following:

a. Handles: white thermoplastic.

b. Wiring terminals: screw-type, side-wired.

c. Contacts: silver-cadmium and contact arm - one-piece copper alloy.

d. Switches: rated quiet-type ac only, 120/277 volts, with current rating and number of poles indicated.

2.9.2 Disconnect Switches

NEMA KS 1. Provide heavy duty-type switches where indicated, where switches are rated higher than 240 volts, and for double-throw switches. Utilize Class R fuseholders and fuses for fused switches, unless indicated otherwise. Provide horsepower rated for switches serving as the motor-disconnect means. Provide switches in NEMA 1 3R , enclosure as indicated per NEMA ICS 6.

2.10 FUSES

NEMA FU 1. Provide complete set of fuses for each fusible switch. Coordinate time-current characteristics curves of fuses serving motors or connected in series with circuit breakers or other circuit protective devices for proper operation. Submit coordination data for approval. Provide fuses with a voltage rating not less than circuit voltage.

2.10.1 Fuseholders

Provide in accordance with UL 4248-1.

2.10.2 Cartridge Fuses, Current Limiting Type (Class R)

UL 248-12, Class RK-1 RK-5 time-delay type. Provide only Class R associated fuseholders in accordance with UL 4248-12.

2.10.3 Cartridge Fuses, High-Interrupting Capacity, Current Limiting Type (Classes J, L, and CC)

UL 248-8, UL 248-10, UL 248-4, Class J for zero to 600 amperes, Class L for 601 to 6,000 amperes, and Class CC for zero to 30 amperes.

2.10.4 Cartridge Fuses, Current Limiting Type (Class T)

UL 248-15, Class T for zero to 1,200 amperes, 300 volts; and zero to 800 amperes, 600 volts.

2.11 RECEPTACLES

Provide the following:

a. UL 498, general purpose specification grade, grounding-type. Residential grade receptacles are not acceptable.

b. Ratings and configurations: as indicated.

c. Bodies: white as per NEMA WD 1.

d. Face and body: thermoplastic supported on a metal mounting strap.

e. Dimensional requirements: per NEMA WD 6.

f. Screw-type, side-wired wiring terminals or of the solderless pressure type having suitable conductor-release arrangement.

g. Grounding pole connected to mounting strap.

h. The receptacle: containing triple-wipe power contacts and double or triple-wipe ground contacts.

2.11.1 Split Duplex Receptacles

Provide separate terminals for each ungrounded pole. One receptacle must be controlled separately.

2.11.2 Weatherproof Receptacles

Provide receptacles, UL listed for use in "wet locations" with integral GFCI protection. Include cast metal box with gasketed, hinged, lockable and weatherproof while-in-use, polycarbonate, UV resistant/stabilized cover plate.

2.11.3 Ground-Fault Circuit Interrupter Receptacles

UL 943, duplex type for mounting in standard outlet box. Provide device capable of detecting current leak when the current to ground is 6 milliamperes or higher, and tripping per requirements of UL 943 for Class A ground-fault circuit interrupter devices. Provide screw-type, side-wired wiring terminals or pre-wired (pigtail) leads.

2.11.4 Plugs

Provide heavy-duty, rubber-covered three-, four-, or five-wire cord of required size, install plugs thereon, and attach to equipment. Provide UL listed plugs with receptacles, complete with grounding blades. Where equipment is not available, turn over plugs and cord assemblies to the Government.

2.11.5 Dryer Receptacles

NEMA 14-30 configuration, rated 30 amperes, 125/250 volts. Furnish one matching plug with each receptacle.

2.12 PANELBOARDS

Provide panelboards in accordance with the following:

a. UL 67 and UL 50 having a short-circuit current rating as indicated .

b. Panelboards for use as service disconnecting means: additionally conform to UL 869A.

c. Panelboards: circuit breaker-equipped.

d. Designed such that individual breakers can be removed without disturbing adjacent units or without loosening or removing supplemental insulation supplied as means of obtaining clearances as required by UL.

e. "Specific breaker placement" is required in panelboards to match the breaker placement indicated in the panelboard schedule on the design drawings. If it is not possible to match "specific breaker placement" during construction, obtain Government approval prior to device installation.

f. Use of "Subfeed Breakers" is not acceptable.

g. Main breaker: "separately" mounted "above" or "below" branch breakers.

h. Where "space only" is indicated, make provisions for future installation of breakers.

i. Directories: indicate load served by each circuit in panelboard.

j. Directories: indicate source of service to panelboard (e.g., Panel PA served from Panel MDP).

l.Type directories and mount in holder behind transparent protective covering.

m. Panelboards: listed and labeled for their intended use.

n. Panelboard nameplates: provided in accordance with paragraph FIELD FABRICATED NAMEPLATES.

a. UL 67 and UL 50.

b. Panelboards for use as service disconnecting: additionally conform to UL 869A.

c. Panelboards: circuit breaker-equipped.

d. Designed such that individual breakers can be removed without disturbing adjacent units or without loosening or removing supplemental insulation supplied as means of obtaining clearances as required by UL.

e. Where "space only" is indicated, make provisions for future installation of breaker sized as indicated.

f. Directories: indicate load served by each circuit of panelboard.

g. Directories: indicate source of service (e.g. upstream panel, switchboard, motor control center) to panelboard.

h. Type directories and mount in holder behind transparent protective covering.

i. Panelboard nameplates: provided in accordance with paragraph FIELD FABRICATED NAMEPLATES.

2.12.1 Enclosure

Provide panelboard enclosure in accordance with the following:

a. UL 50.

b. Cabinets mounted outdoors or flush-mounted: hot-dipped galvanized after fabrication .

c. Cabinets: painted in accordance with paragraph PAINTING.

d. Outdoor cabinets: NEMA 3R raintight with conduit hubs welded to the cabinet.

e. Front edges of cabinets: form-flanged or fitted with structural shapes welded or riveted to the sheet steel, for supporting the panelboard front.

f. All cabinets: fabricated such that no part of any surface on the finished cabinet deviates from a true plane by more than 1/8 inch.

g. Holes: provided in the back of indoor surface-mounted cabinets, with outside spacers and inside stiffeners, for mounting the cabinets with a 1/2 inch clear space between the back of the cabinet and the wall surface.

h. Flush doors: mounted on hinges that expose only the hinge roll to view when the door is closed.

i. Each door: fitted with a combined catch and lock latch.

j. Keys: two provided with each lock, with all locks keyed alike.

k. Finished-head cap screws: provided for mounting the panelboard fronts on the cabinets.

2.12.2 Panelboard Buses

Support bus bars on bases independent of circuit breakers. Design main buses and back pans so that breakers may be changed without machining, drilling, or tapping. Provide isolated neutral bus in each panel for connection of circuit neutral conductors. Provide separate ground bus identified as equipment grounding bus per UL 67 for connecting grounding conductors; bond to steel cabinet.

2.12.2.1 Panelboard Neutrals for Non-Linear Loads

Provide in accordance with the following:.

a. UL listed, with panelboard type specifically UL heat rise tested for use on non-linear loads.

b. Panelboard: heat rise tested in accordance with UL 67, except with the neutral assembly installed and carrying 200 percent of the phase bus current during testing.

c. Verification of the testing procedure: provided upon request.

d. Two neutral assemblies paralleled together with cable is not acceptable.

e. Nameplates for panelboard rated for use on non-linear loads: marked "SUITABLE FOR NON-LINEAR LOADS" and in accordance with paragraph FIELD FABRICATED NAMEPLATES.

f. Provide a neutral label with instructions for wiring the neutral of panelboards rated for use on non-linear loads.

2.12.3 Circuit Breakers

UL 489, thermal magnetic-type having a minimum short-circuit current rating equal to the short-circuit current rating of the panelboard in which the circuit breaker will be mounted. Breaker terminals: UL listed as suitable for type of conductor provided. Where indicated on the drawings, provide circuit breakers with shunt trip devices. Series rated circuit breakers and plug-in circuit breakers are unacceptable.

2.12.3.1 Multipole Breakers

Provide common trip-type with single operating handle. Design breaker such that overload in one pole automatically causes all poles to open. Maintain phase sequence throughout each panel so that any three adjacent breaker poles are connected to Phases A, B, and C, respectively.

2.12.3.2 Circuit Breaker With Ground-Fault Circuit Interrupter

UL 943 and NFPA 70. Provide with auto-monitoring (self-test) and lockout features, "push-to-test" button, visible indication of tripped condition, and ability to detect and trip when current imbalance is 6 milliamperes or higher per requirements of UL 943 for Class A ground-fault circuit interrupter devices.

2.13 ENCLOSED CIRCUIT BREAKERS

UL 489. Individual molded case circuit breakers with voltage and

continuous current ratings, number of poles, overload trip setting, and short circuit current interrupting rating as indicated. Enclosure type as indicated. Provide solid neutral.

2.14 TRANSFORMERS

Provide transformers in accordance with the following:

a. NEMA ST 20, general purpose, dry-type, self-cooled, ventilated.

b. Provide transformers in NEMA 1 enclosure.

c. Taps for transformers 15 kVA and larger: Two 2.5 percent taps Full Capacity Above Nominal (FCAN) and four 2.5 percent taps Full Capacity Below Nominal (FCBN) .

d. Transformer insulation system:

(1) 220 degrees C insulation system for transformers 15 kVA and greater, with temperature rise not exceeding 115 degrees C under full-rated load in maximum ambient of 40 degrees C.

(2) 180 degrees C insulation for transformers rated 10 kVA and less, with temperature rise not exceeding 80 degrees C under full-rated load in maximum ambient of 40 degrees C.

f. Transformer of 115 degrees C temperature rise: capable of carrying continuously 115 percent of nameplate kVA without exceeding insulation rating.

2.14.1 Specified Transformer Efficiency

Transformers, indicated and specified with: 480V primary, 80 degrees C or 115 degrees C temperature rise, kVA ratings of 37.5 to 100 for single phase or 30 to 500 for three phase, energy efficient type. The transformer is not acceptable if the calculated transformer efficiency is less than the efficiency indicated in 10 CFR 431, Subpart K.

2.14.2 Transformers With Non-Linear Loads

Provide transformers for non-linear loads in accordance with the following:

a. Transformer insulation: UL recognized 220 degrees C system. Neither the primary nor the secondary temperature is allowed to exceed 220 degrees C at any point in the coils while carrying their full rating of non-sinusoidal load.

b. Transformers are to be UL listed and labeled for K-4 in accordance with UL 1561.

c. Transformers evaluated by the UL K-Factor evaluation: listed for 115 degrees C average temperature rise only.

d. Transformers with K-Factor ratings with temperature rise of 150 degrees C rise are not acceptable.

e. K-Factor rated transformers impedance: allowed range of 3 percent to 5 percent, with a minimum reactance of 2 percent to prevent excessive

neutral current when supplying loads with large amounts of third harmonic.

2.15 MANUAL MOTOR STARTERS (MOTOR RATED SWITCHES)

Single pole designed for surface mounting with overload protection.

2.16 LOCKOUT REQUIREMENTS

Provide circuit breakers, disconnecting means, and other devices that are electrical energy-isolating capable of being locked out for machines and other equipment to prevent unexpected startup or release of stored energy in accordance with 29 CFR 1910.147, NFPA 70E and 29 CFR 1910.303. Comply with requirements of Division 23, "Mechanical" for mechanical isolation of machines and other equipment.

2.17 TELECOMMUNICATIONS SYSTEM

Provide system of telecommunications wire-supporting structures (pathway), including: outlet boxes, conduits with pull wires cable trays, and other accessories for telecommunications outlets and pathway in accordance with TIA-569 and as specified herein. Additional telecommunications requirements are specified in Section 27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEM.

2.18 GROUNDING AND BONDING EQUIPMENT

2.18.1 Ground Rods

UL 467. Ground rods: cone pointed copper-clad steel, with minimum diameter of 3/4 inch and minimum length 10 feet. Sectional type rods may be used for rods 20 feet or longer.

2.18.2 Secondary Bonding Busbar

Provide corrosion-resistant grounding busbar suitable for indoor installation in accordance with TIA-607. Busbars: plated for reduced contact resistance. If not plated, clean the busbar prior to fastening the conductors to the busbar and apply an anti-oxidant to the contact area to control corrosion and reduce contact resistance. Provide a Primary bonding busbar (PBB) in the telecommunications entrance facility and a Secondary bonding busbar (SBB) in all other telecommunications rooms and equipment rooms. The Primary bonding busbar (PBB) and the Secondary bonding busbar (SBB): sized in accordance with the immediate application requirements and with consideration of future growth. Provide Secondary bonding busbars with the following:

a. Predrilled copper busbar provided with holes for use with standard sized lugs,

b. Minimum dimensions of 0.25 in thick by 4 in wide for the PBB and 2 in wide for SBBs with length as indicated;

c. Listed by a nationally recognized testing laboratory.

2.19 MANUFACTURER'S NAMEPLATE

Provide on each item of equipment a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a

conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.20 FIELD FABRICATED NAMEPLATES

Provide field fabricated nameplates in accordance with the following:

a. ASTM D709.

b. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified or as indicated on the drawings.

c. Each nameplate inscription: identify the function and, when applicable, the position.

d. Nameplates: melamine plastic, 0.125 inch thick, white with black center core.

f. Surface: matte finish. Corners: square. Accurately align lettering and engrave into the core.

g. Minimum size of nameplates: one by 2.5 inches.

h. Lettering size and style: a minimum of 0.25 inch high normal block style.

2.21 WARNING SIGNS

Provide warning signs for flash protection in accordance with NFPA 70E and NEMA Z535.4 for switchboards, panelboards, industrial control panels, and motor control centers that are in other than dwelling occupancies and are likely to require examination, adjustment, servicing, or maintenance while energized. Provide field installed signs to warn qualified persons of potential electric arc flash hazards when warning signs are not provided by the manufacturer. Provide marking that is clearly visible to qualified persons before examination, adjustment, servicing, or maintenance of the equipment.

2.22 FIRESTOPPING MATERIALS

Provide firestopping around electrical penetrations in accordance with Section 07 84 00 FIRESTOPPING.

2.23 SURGE PROTECTIVE DEVICES

Provide parallel type surge protective devices (SPD) which comply with UL 1449 at the service entrance , panelboards . Provide surge protectors in a NEMA 1 enclosure per NEMA ICS 6. SPD must have the same short-circuit current rating as the protected equipment and must not be installed at a point of system where the available fault current is in excess of that rating. Use Type 1 or Type 2 SPD and connect on the load side of a dedicated circuit breaker. Submit performance and characteristic curves.

Provide the following modes of protection:

FOR SINGLE PHASE AND THREE PHASE WYE CONNECTED SYSTEMS-
Phase to phase (L-L)

Each phase to neutral (L-N)
Neutral to ground (N-G)
Phase to ground (L-G)

SPDs at the service entrance: provide with a minimum surge current rating of 80,000 amperes for L-L mode minimum and 40,000 amperes for other modes (L-N, L-G, and N-G) and downstream SPDs rated 40,000 amperes for L-L mode minimum and 20,000 amperes for other modes (L-N, L-G, and N-G).

Provide SPDs per NFPA 780 for the lightning protection system.

Maximum L-N, and N-G Voltage Protection Rating:

600V for 208Y/120V, three phase system
1,200V for 480Y/277V, three phase system

Maximum L-G Protection Rating:

700V for 208Y/120V, three phase system
1,200V for 480Y/277V, three phase system

Maximum L-L Voltage Protection Rating:

1,200V for 208Y/120V, three phase system
1,800V for 480Y/277V, three phase system

Provide SPDs. Maximum L-N, L-G, and N-G Voltage Protection Rating:

700V for 208Y/120V, three phase system
1,200V for 480Y/277V, three phase system

Maximum L-L Voltage Protection Rating:

1,200V for 208Y/120V, three phase system
2,000V for 480Y/277V, three phase system

The minimum MCOV (Maximum Continuous Operating Voltage) rating for L-N and L-G modes of operation: 120 percent of nominal voltage for 240 volts and below; 115 percent of nominal voltage above 240 volts to 480 volts.

Provide EMI/RFI filtering per UL 1283 for each mode with the capability to attenuate high frequency noise. Minimum attenuation: 20db.

2.24 FACTORY APPLIED FINISH

Provide factory-applied finish on electrical equipment in accordance with the following:

a. NEMA 250 corrosion-resistance test and the additional requirements as specified herein.

b. Interior and exterior steel surfaces of equipment enclosures: thoroughly cleaned followed by a rust-inhibitive phosphatizing or equivalent treatment prior to painting.

c. Exterior surfaces: free from holes, seams, dents, weld marks, loose

scale or other imperfections.

d. Interior surfaces: receive not less than one coat of corrosion-resisting paint in accordance with the manufacturer's standard practice.

e. Exterior surfaces: primed, filled where necessary, and given not less than two coats baked enamel with semigloss finish.

f. Equipment located indoors: ANSI Light Gray, and equipment located outdoors: ANSI Light Gray.

g. Provide manufacturer's coatings for touch-up work and as specified in paragraph FIELD APPLIED PAINTING.

2.25 SOURCE QUALITY CONTROL

2.25.1 Transformer Factory Tests

Submittal: include routine NEMA ST 20 transformer test results on each transformer and also provide the results of NEMA "design" and "prototype" tests that were made on transformers electrically and mechanically equal to those specified.

2.26 COORDINATED POWER SYSTEM PROTECTION

Prepare analyses as specified in Section 26 28 01.00 10 COORDINATED POWER SYSTEM PROTECTION.

PART 3 EXECUTION

3.1 INSTALLATION

Electrical installations, including weatherproof and hazardous locations and ducts, plenums and other air-handling spaces: conform to requirements of NFPA 70 and to requirements specified herein.

3.1.1 Underground Service

Underground service conductors and associated conduit: continuous from service entrance equipment to outdoor power system connection.

3.1.2 Service Entrance Identification

Service entrance disconnect devices, switches, and enclosures: labeled and identified as such.

3.1.2.1 Labels

Wherever work results in service entrance disconnect devices in more than one enclosure, as permitted by NFPA 70, label each enclosure, new and existing, as one of several enclosures containing service entrance disconnect devices. Label, at minimum: indicate number of service disconnect devices housed by enclosure and indicate total number of enclosures that contain service disconnect devices. Provide laminated plastic labels conforming to paragraph FIELD FABRICATED NAMEPLATES. Use lettering of at least 0.25 inch in height, and engrave on black-on-white matte finish. Service entrance disconnect devices in more than one enclosure: provided only as permitted by NFPA 70.

3.1.3 Wiring Methods

Provide insulated conductors installed in rigid steel conduit, IMC, rigid nonmetallic conduit, or EMT, except where specifically indicated or specified otherwise or required by NFPA 70 to be installed otherwise. Grounding conductor: separate from electrical system neutral conductor. Provide insulated green equipment grounding conductor for circuit(s) installed in conduit and raceways. Minimum conduit size: 1/2 inch in diameter for low voltage lighting and power circuits. Vertical distribution in multiple story buildings: made with metal conduit in fire-rated shafts, with metal conduit extending through shafts for minimum distance of 6 inches. Firestop conduit which penetrates fire-rated walls, fire-rated partitions, or fire-rated floors in accordance with Section 07 84 00 FIRESTOPPING.

3.1.3.1 Pull Wire

Install pull wires in empty conduits. Pull wire: plastic having minimum 200-pound force tensile strength. Leave minimum 36 inches of slack at each end of pull wire.

3.1.3.2 Metal-Clad Cable

Install in accordance with NFPA 70, Type MC cable.

3.1.4 Conduit Installation

Unless indicated otherwise, conceal conduit under floor slabs and within finished walls, ceilings, and floors. Keep conduit minimum 6 inches away from parallel runs of flues and steam or hot water pipes. Install conduit parallel with or at right angles to ceilings, walls, and structural members where located above accessible ceilings and where conduit will be visible after completion of project. Run conduits under floor slab as if exposed.

3.1.4.1 Restrictions Applicable to EMT

a. Do not install underground.

b. Do not encase in concrete, mortar, grout, or other cementitious materials.

c. Do not use in areas subject to physical damage including but not limited to equipment rooms where moving or replacing equipment could physically damage the EMT.

d. Do not use in hazardous areas.

e. Do not use outdoors.

f. Do not use in fire pump rooms.

g. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

3.1.4.2 Restrictions Applicable to Nonmetallic Conduit

a. PVC Schedule 40.

(1) Do not use where subject to physical damage, including but not limited to, mechanical equipment rooms, electrical equipment rooms, fire pump rooms, and where restrictions are applying to both PVC Schedule 40 and PVC Schedule 80.

(2) Do not use above grade, except where allowed in this section for rising through floor slab or indicated otherwise.

b. PVC Schedule 40 and Schedule 80.

(1) Do not use where subject to physical damage, including but not limited to, hospitals, power plant, missile magazines, and other such areas.

(2) Do not use in hazardous (classified) areas.

(3) Do not use in penetrating fire-rated walls or partitions, or fire-rated floors.

-

3.1.4.3 Restrictions Applicable to Flexible Conduit

Use only as specified in paragraph FLEXIBLE CONNECTIONS. Do not use when the enclosed conductors must be shielded from the effects of High-altitude Electromagnetic Pulse (HEMP).

3.1.4.4 Underground Conduit

Plastic-coated rigid steel; plastic-coated steel IMC; PVC, Type EPC-40 Plastic coating: extend minimum 6 inches above floor.

3.1.4.5 Conduit Installed Under Floor Slabs

Conduit run under floor slab: located a minimum of 12 inches below the vapor barrier. Seal around conduits at penetrations thru vapor barrier. Use NECA NEIS 1 Table 2a (Minimum Raceway Spacing) to determine under floor slab conduit spacing unless greater spacing is required elsewhere in this section.

3.1.4.6 Conduit Through Floor Slabs

Where conduits rise through floor slabs, do not allow curved portion of bends to be visible above finished slab. Where conduit rises through slab-on grade, seal all electrical penetrations to address radon mitigation and prevent infiltration of air, insects, and vermin.

3.1.4.7 Conduit Installed in Concrete Floor Slabs

Rigid steel; steel IMC; fiberglass, or PVC, Type EPC-40.Locate so as not to adversely affect structural strength of slabs. Install conduit within middle one-third of concrete slab. Do not stack conduits. Space conduits horizontally not closer than three diameters, except at cabinet locations. Curved portions of bends must not be visible above finish slab. Increase slab thickness as necessary to provide minimum one inch cover over conduit. Where embedded conduits cross building expansion joints, provide suitable watertight expansion/deflection fittings and bonding jumpers. Expansion/deflection fittings must allow horizontal and vertical movement of raceway. Conduit larger than one inch trade size: installed parallel with or at right angles to main reinforcement; when at

right angles to reinforcement, install conduit close to one of supports of slab. Where nonmetallic conduit is used, convert raceway to plastic coated rigid steel or plastic coated steel IMC before rising above floor, unless specifically indicated.

3.1.4.8 Stub-Ups

Provide conduits stubbed up through concrete floor for connection to free-standing equipment with adjustable top or coupling threaded inside for plugs, set flush with finished floor. Extend conductors to equipment in rigid steel conduit, except that flexible metal conduit may be used 6 inches above floor. Where no equipment connections are made, install screwdriver-operated threaded flush plugs in conduit end.

3.1.4.9 Conduit Support

Support conduit by pipe straps, wall brackets, threaded rod conduit hangers, or ceiling trapeze. Plastic cable ties are not acceptable. Fasten by wood screws to wood; by toggle bolts on hollow masonry units; by concrete inserts or expansion bolts on concrete or brick; and by machine screws, welded threaded studs, or spring-tension clamps on steel work. Threaded C-clamps may be used on rigid steel conduit only. Do not weld conduits or pipe straps to steel structures. Do not exceed one-fourth proof test load for load applied to fasteners. Provide vibration resistant and shock-resistant fasteners attached to concrete ceiling. Do not cut main reinforcing bars for any holes cut to depth of more than 1 1/2 inches in reinforced concrete beams or to depth of more than 3/4 inch in concrete joints. Fill unused holes. In partitions of light steel construction, use sheet metal screws. In suspended-ceiling construction, run conduit above ceiling. Do not support conduit by ceiling support system. Conduit and box systems: supported independently of both (a) tie wires supporting ceiling grid system, and (b) ceiling grid system into which ceiling panels are placed. Do not share supporting means between electrical raceways and mechanical piping or ducts. Coordinate installation with above-ceiling mechanical systems to assure maximum accessibility to all systems. Spring-steel fasteners may be used for lighting branch circuit conduit supports in suspended ceilings in dry locations. Where conduit crosses building expansion joints, provide suitable watertight expansion fitting that maintains conduit electrical continuity by bonding jumpers or other means. For conduits greater than 2 1/2 inches inside diameter, provide supports to resist forces of 0.5 times the equipment weight in any direction and 1.5 times the equipment weight in the downward direction.

3.1.4.10 Directional Changes in Conduit Runs

Make changes in direction of runs with symmetrical bends or cast-metal fittings. Make field-made bends and offsets with hickey or conduit-bending machine. Do not install crushed or deformed conduits. Avoid trapped conduits. Prevent plaster, dirt, or trash from lodging in conduits, boxes, fittings, and equipment during construction. Free clogged conduits of obstructions.

3.1.4.11 Locknuts and Bushings

Fasten conduits to sheet metal boxes and cabinets with two locknuts where required by NFPA 70, where insulated bushings are used, and where bushings cannot be brought into firm contact with the box; otherwise, use at least minimum single locknut and bushing. Provide locknuts with sharp edges for

digging into wall of metal enclosures. Install bushings on ends of conduits, and provide insulating type where required by NFPA 70.

3.1.4.12 Flexible Connections

Provide flexible steel conduit between 3 and 6 feet in length for recessed and semirecessed lighting fixtures; for equipment subject to vibration, noise transmission, or movement; and for motors. Install flexible conduit to allow 20 percent slack. Minimum flexible steel conduit size: 1/2 inch diameter. Provide liquid tight flexible nonmetallic conduit in wet and damp locations and in fire pump rooms for equipment subject to vibration, noise transmission, movement or motors. Provide separate ground conductor across flexible connections. Plastic cable ties are not acceptable as a support method.

3.1.4.13 Telecommunications and Signal System Pathway

Install telecommunications pathway in accordance with TIA-569.

a. Horizontal Pathway: Telecommunications pathways from the work area to the telecommunications room: installed and cabling length requirements in accordance with TIA-568.1. Size conduits, and cable trays in accordance with TIA-569 and as indicated.

b. Backbone Pathway: Telecommunication pathways from the telecommunications entrance facility to telecommunications rooms, and, telecommunications equipment rooms (backbone cabling): installed in accordance with TIA-569. Size conduits, and cable trays for telecommunications risers in accordance with TIA-569 and as indicated.

3.1.5 Cable Tray Installation

Install and ground in accordance with NFPA 70. In addition, install and ground telecommunications cable tray in accordance with TIA-569, and TIA-607. Install cable trays parallel with or at right angles to ceilings, walls, and structural members. Cable tray and tray supports must not partially nor completely obstruct access to the room. Support in accordance with manufacturer recommendations but at not more than 6 foot intervals as indicated. Coat contact surfaces of aluminum connections with an antioxidant compound prior to assembly. Adjacent cable tray sections: bonded together by connector plates of an identical type as the cable tray sections. For grounding of cable tray system provide No. 2 AWG bare copper wire throughout cable tray system, and bond to each section, except use No. 1/0 aluminum wire if cable tray is aluminum. Terminate cable trays 10 inches from both sides of smoke and fire partitions. Install conductors run through smoke and fire partitions in 4 inch rigid steel conduits with grounding bushings, extending 12 inches beyond each side of partitions. Seal conduit on both ends to maintain smoke and fire ratings of partitions. Firestop penetrations in accordance with Section 07 84 00, FIRESTOPPING. Provide supports to resist forces of 0.5 times the equipment weight in any direction and 1.5 times the equipment weight in the downward direction.

Install cable trays parallel with or at right angles to ceilings, walls, and structural members. Cable tray and tray supports must not partially nor completely obstruct access to the room. Support at maximum 6 foot intervals. In addition, install and ground telecommunications cable tray in accordance with TIA-569, and TIA-607 Coat contact surfaces of aluminum connections with an antioxidant compound prior to assembly. Ensure edges,

fittings, and hardware are finished free from burrs and sharp edges. Provide No. 2 AWG bare copper wire throughout cable tray system, and bond to each section. Use No. 1/0 aluminum wire if cable tray is aluminum. Install conductors that run though smoke and fire partitions in 4 inch rigid steel conduits with grounding bushing, extending 12 inches beyond each side of partitions. Seal conduit on both ends to maintain smoke and fire ratings of partitions. Provide supports to resist forces of 0.5 times the equipment weight in any direction and 1.5 times the equipment weight in the downward direction.

3.1.6 Boxes, Outlets, and Supports

Provide boxes in wiring and raceway systems wherever required for pulling of wires, making connections, and mounting of devices or fixtures. Boxes for metallic raceways: cast-metal, hub-type when located in wet locations, when surface mounted on outside of exterior surfaces, when surface mounted on interior walls exposed up to 7 feet above floors and walkways, and when specifically indicated. Boxes in other locations: sheet steel, except that aluminum boxes may be used with aluminum conduit, and nonmetallic boxes may be used with nonmetallic conduit system. Provide each box with volume required by NFPA 70 for number of conductors enclosed in box. Boxes for mounting lighting fixtures: minimum 4 inches square, or octagonal, except that smaller boxes may be installed as required by fixture configurations, as approved. Boxes for use in masonry-block or tile walls: square-cornered, tile-type, or standard boxes having square-cornered, tile-type covers. Provide gaskets for cast-metal boxes installed in wet locations and boxes installed flush with outside of exterior surfaces. Provide separate boxes for flush or recessed fixtures when required by fixture terminal operating temperature; provide readily removable fixtures for access to boxes unless ceiling access panels are provided. Support boxes and pendants for surface-mounted fixtures on suspended ceilings independently of ceiling supports. Fasten boxes and supports with wood screws on wood, with bolts and expansion shields on concrete or brick, with toggle bolts on hollow masonry units, and with machine screws or welded studs on steel. In open overhead spaces, cast boxes threaded to raceways need not be separately supported except where used for fixture support; support sheet metal boxes directly from building structure or by bar hangers. Where bar hangers are used, attach bar to raceways on opposite sides of box, and support raceway with approved-type fastener maximum 24 inches from box. When penetrating reinforced concrete members, avoid cutting reinforcing steel.

3.1.6.1 Boxes

Boxes for use with raceway systems: minimum 1 1/2 inches deep, except where shallower boxes required by structural conditions are approved. Boxes for other than lighting fixture outlets: minimum 4 inches square, except that 4 by 2 inch boxes may be used where only one raceway enters outlet. Mount outlet boxes flush in finished walls.

3.1.6.2 Pull Boxes

Construct of at least minimum size required by NFPA 70 of code-gauge aluminum or galvanized sheet steel, except where cast-metal boxes are required in locations specified herein. Provide boxes with screw-fastened covers. Where several feeders pass through common pull box, tag feeders to indicate clearly electrical characteristics, circuit number, and panel designation.

3.1.7 Mounting Heights

Mount panelboards, enclosed circuit breakers, and disconnecting switches so height of center of grip of the operating handle of the switch or circuit breaker at its highest position is maximum 79 inches above floor or working platform or as allowed in Section 404.8 per NFPA 70. Mount lighting switches 48 inches above finished floor. Mount receptacles and telecommunications outlets 18 inches above finished floor, unless otherwise indicated. Wall-mounted telecommunications outlets: mounted at height 60 inches above finished floor. Mount other devices as indicated.

Measure mounting heights of receptacle outlet boxes to the bottom of the outlet box.

3.1.8 Conductor Identification

Provide conductor identification within each enclosure where tap, splice, or termination is made. For conductors No. 6 AWG and smaller diameter, provide color coding by factory-applied, color-impregnated insulation. For conductors No. 4 AWG and larger diameter, provide color coding by plastic-coated, self-sticking markers; colored nylon cable ties and plates; or heat shrink-type sleeves. Identify control circuit terminations in accordance with manufacturer's recommendations. Provide telecommunications system conductor identification as specified in Section 27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEMS.

3.1.8.1 Marking Strips

Provide marking strips for identification of power distribution, control, data, and communications cables in accordance with the following:

a. Provide white or other light-colored plastic marking strips, fastened by screws to each terminal block, for wire designations.

b. Use permanent ink for the wire numbers

c. Provide reversible marking strips to permit marking both sides, or provide two marking strips with each block.

d. Size marking strips to accommodate the two sets of wire numbers.

e. Assign a device designation in accordance with NEMA ICS 1 to each device to which a connection is made. Mark each device terminal to which a connection is made with a distinct terminal marking corresponding to the wire designation used on the Contractor's schematic and connection diagrams.

f. The wire (terminal point) designations used on the Contractor's wiring diagrams and printed on terminal block marking strips may be according to the Contractor's standard practice; however, provide additional wire and cable designations for identification of remote (external) circuits for the Government's wire designations.

3.1.9 Splices

Make splices in accessible locations. Make splices in conductors No. 10 AWG and smaller diameter with insulated, pressure-type connector. Make splices in conductors No. 8 AWG and larger diameter with solderless connector, and cover with insulation material equivalent to conductor

insulation.

3.1.10 Covers and Device Plates

Install with edges in continuous contact with finished wall surfaces without use of mats or similar devices. Plaster fillings are not permitted. Install plates with alignment tolerance of 1/16 inch. Use of sectional-type device plates are not permitted. Provide gasket for plates installed in wet locations.

3.1.11 Electrical Penetrations

Seal openings around electrical penetrations through fire resistance-rated walls, partitions, floors, or ceilings in accordance with Section 07 84 00 FIRESTOPPING.

3.1.12 Grounding and Bonding

Provide in accordance with NFPA 70 and NFPA 780. Ground exposed, non-current-carrying metallic parts of electrical equipment, access flooring support system, metallic raceway systems, grounding conductor in metallic and nonmetallic raceways, telecommunications system grounds, and neutral conductor of wiring systems. Interconnect all grounding media in or on the structure to provide a common ground potential. This includes lightning protection, electrical service, telecommunications system grounds, as well as underground metallic piping systems. Make interconnection to the gas line on the customer's side of the meter. Use main size lightning conductors for interconnecting these grounding systems to the lightning protection system. In addition to the requirements specified herein, provide telecommunications grounding in accordance with TIA-607. Where ground fault protection is employed, ensure that connection of ground and neutral does not interfere with correct operation of fault protection.

3.1.12.1 Ground Rods

Provide ground rods and measure the resistance to ground using the fall-of-potential method described in IEEE 81. Do not exceed 25 ohms under normally dry conditions for the maximum resistance of a driven ground. If this resistance cannot be obtained with a single rod, additional rods, spaced on center. Spacing for additional rods must be a minimum of 10 feet. If the resultant resistance exceeds 25 ohms measured not less than 48 hours after rainfall, notify the Contracting Officer who will decide on the number of ground rods to add.

3.1.12.2 Grounding Connections

Make grounding connections which are buried or otherwise normally inaccessible, excepting specifically those connections for which access for periodic testing is required, by exothermic weld or high compression connector.

a. Make exothermic welds strictly in accordance with the weld manufacturer's written recommendations. Welds which are "puffed up" or which show convex surfaces indicating improper cleaning are not acceptable. Mechanical connectors are not required at exothermic welds.

b. Make high compression connections using a hydraulic or electric

compression tool to provide the correct circumferential pressure. Provide tools and dies as recommended by the manufacturer. Use an embossing die code or other standard method to provide visible indication that a connector has been adequately compressed on the ground wire.

3.1.12.3 Ground Bus

Provide a copper ground bus in the electrical equipment rooms as indicated. Noncurrent-carrying metal parts of transformer neutrals and other electrical equipment: effectively grounded by bonding to the ground bus. Bond the ground bus to both the entrance ground, and to a ground rod or rods as specified above having the upper ends terminating approximately 4 inches above the floor. Make connections and splices of the brazed, welded, bolted, or pressure-connector type, except use pressure connectors or bolted connections for connections to removable equipment. For raised floor equipment rooms in computer and data processing centers, provide a minimum of four, one at each corner, ground buses connected to the building grounding system. Use bolted connections in lieu of thermoweld, so they can be changed as required by additions and alterations.

3.1.12.4 Resistance

Maximum resistance-to-ground of grounding system: do not exceed 5 ohms under dry conditions. Where resistance obtained exceeds 5 ohms, contact Contracting Officer for further instructions.

3.1.12.5 Telecommunications System

Provide telecommunications grounding in accordance with the following:

a. Telecommunications Grounding Busbars: Provide a Primary bonding busbar (PBB) in the telecommunications entrance facility. Install the PBB as close to the electrical service entrance grounding connection as practicable. Provide a Secondary bonding busbar (SBB) in all other telecommunications rooms and telecommunications equipment rooms. Install the SBB as close to the telecommunications room panelboard as practicable, when equipped. Where a panelboard for telecommunications equipment is not installed in the telecommunications room, locate the SBB near the backbone cabling and associated terminations. In addition, locate the SBB to provide for the shortest and straightest routing of the grounding conductors. Where a panelboard for telecommunications equipment is located within the same room or space as a SBB, bond that panelboard's alternating current equipment ground (ACEG) bus (when equipped) or the panelboard enclosure to the SBB. Install Secondary bonding busbars to maintain clearances as required by NFPA 70 and insulated from its support. A minimum of 2 inches separation from the wall is recommended to allow access to the rear of the busbar and adjust the mounting height to accommodate overhead or underfloor cable routing.

b. Telecommunications Bonding Conductors: Provide main telecommunications service equipment ground consisting of separate bonding conductor for telecommunications, between the PBB and readily accessible grounding connection of the electrical service. Grounding and bonding conductors should not be placed in ferrous metallic conduit. If it is necessary to place grounding and bonding conductors in ferrous metallic conduit that exceeds 3 feet in length, bond the conductors to each end of the conduit using a grounding bushing or a

No. 6 AWG conductor, minimum. Provide a telecommunications bonding backbone (TBB) that originates at the PBB extends throughout the building using the telecommunications backbone pathways, and connects to the SBBs in all telecommunications rooms and equipment rooms. Install the TBB conductors such that they are protected from physical and mechanical damage. The TBB conductors should be installed without splices and routed in the shortest possible straight-line path. Make the bonding conductor between a TBB and a SBB continuous. Where splices are necessary, the number of splices should be a minimum. Make the splices accessible and located in telecommunications spaces. Connect joined segments of a TBB using exothermic welding, irreversible compression-type connectors, or equivalent. Install all joints to be adequately supported and protected from damage. Whenever two or more TBBs are used within a multistory building, bond the TBBs together with a grounding equalizer (GE) at the top floor and at a minimum of every third floor in between. Do not connect the TBB and GE to the pathway ground, except at the PBB or the SBB.

c. Telecommunications Grounding Connections: Telecommunications grounding connections to the PBB or SBB: utilize listed compression two-hole lugs, exothermic welding, suitable and equivalent one hole non-twisting lugs, or other irreversible compression type connections. Bond all metallic pathways, cabinets, and racks for telecommunications cabling and interconnecting hardware located within the same room or space as the PBB or SBB to the PBB or SBB respectively. In a metal frame (structural steel) building, where the steel framework is readily accessible within the room; bond each PBB and SBB to the vertical steel metal frame using a minimum No. 6 AWG conductor. Where the metal frame is external to the room and readily accessible, bond the metal frame to the SBB or PBB with a minimum No. 6 AWG conductor. When practicable because of shorter distances and, where horizontal steel members are permanently electrically bonded to vertical column members, the SBB may be bonded to these horizontal members in lieu of the vertical column members. All connectors used for bonding to the metal frame of a building must be listed for the intended purpose.

3.1.13 Equipment Connections

Provide power wiring for the connection of motors and control equipment under this section of the specification. Except as otherwise specifically noted or specified, automatic control wiring, control devices, and protective devices within the control circuitry are not included in this section of the specifications and are provided under the section specifying the associated equipment.

3.1.14 Elevator

Provide circuit to line terminals of elevator controller, and disconnect switch on line side of controller, outlet for control power, outlet receptacle and work light at midheight of elevator shaft, and work light and outlet receptacle in elevator pit.

3.1.15 Government-Furnished Equipment

Contractor rough-in for Government-furnished equipment to make equipment operate as intended, including providing miscellaneous items such as plugs, receptacles, wire, cable, conduit, flexible conduit, and outlet boxes or fittings.

3.1.16 Surge Protective Devices

Connect the surge protective devices in parallel to the power source, keeping the conductors as short and straight as practically possible. Maximum allowed lead length is 3 feet avoiding 90 degree bends. Do not locate surge protective devices inside a panelboard or switchboard enclosure.

3.2 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.3 WARNING SIGN MOUNTING

Provide the number of signs required to be readable from each accessible side. Space the signs in accordance with NFPA 70E.

3.4 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria.

3.5 FIELD QUALITY CONTROL

Furnish test equipment and personnel and submit written copies of test results. Give Contracting Officer 5 working days notice prior to each test. Where applicable, test electrical equipment in accordance with NETA ATS.

3.5.1 Devices Subject to Manual Operation

Operate each device subject to manual operation at least five times, demonstrating satisfactory operation each time.

3.5.2 600-Volt Wiring Test

Test wiring rated 600 volt and less to verify that no short circuits or accidental grounds exist. Perform insulation resistance tests on wiring No. 6 AWG and larger diameter using instrument which applies voltage of 1,000 volts DC for 600 volt rated wiring and 500 volts DC for 300 volt rated wiring per NETA ATS to provide direct reading of resistance. All existing wiring to be reused must also be tested.

3.5.3 Transformer Tests

Perform the standard, not optional, tests in accordance with the Inspection and Test Procedures for transformers, dry type, air-cooled, 600 volt and below; as specified in NETA ATS. Measure primary and secondary voltages for proper tap settings. Tests need not be performed by a recognized independent testing firm or independent electrical consulting firm.

3.5.4 Ground-Fault Receptacle Test

Test ground-fault receptacles with a "load" (such as a plug in light) to verify that the "line" and "load" leads are not reversed. Press the TEST button and then the RESET button to verify by LED status that the device

is a self-test model as specified in UL 943.

3.5.5 Grounding System Test

Test grounding system to ensure continuity, and that resistance to ground is not excessive. Test each ground rod for resistance to ground before making connections to rod; tie grounding system together and test for resistance to ground. Make resistance measurements in dry weather, not earlier than 48 hours after rainfall. Submit written results of each test to Contracting Officer, and indicate location of rods as well as resistance and soil conditions at time measurements were made.

3.5.6 Phase Rotation Test

Perform phase rotation test to ensure proper rotation of service power prior to operation of new or reinstalled equipment using a phase rotation meter. Follow the meter manual directions performing the test.

-- End of Section --

SECTION 26 24 13

SWITCHBOARDS
08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM D709	(2017) Standard Specification for Laminated Thermosetting Materials
ASTM D1535	(2014; R 2018) Standard Practice for Specifying Color by the Munsell System

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 81	(2012) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System
IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms
IEEE C2	(2023) National Electrical Safety Code
IEEE C57.12.28	(2014) Standard for Pad-Mounted Equipment - Enclosure Integrity

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2021) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI/NEMA PB 2.1	(2013) General Instructions for Proper Handling, Installation, Operation and

	Maintenance of Deadfront Distribution Switchboards Rated 600 V or Less
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA PB 2	(2011) Deadfront Distribution Switchboards

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

UL SOLUTIONS (UL)

UL 467	(2022) UL Standard for Safety Grounding and Bonding Equipment
UL 489	(2025) UL Standard for Safety Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures
UL 891	(2019) UL Standard for Safety Switchboards

1.2 RELATED REQUIREMENTS

Section 26 08 00 APPARATUS INSPECTION AND TESTING applies to this section, with the additions and modifications specified herein.

1.3 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, are as defined in IEEE 100.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Switchboard Drawings; G

SD-03 Product Data

Switchboard; G

SD-06 Test Reports

Switchboard Design Tests; G

Switchboard Production Tests; G

Acceptance Checks and Tests; G

SD-10 Operation and Maintenance Data

Switchboard Operation and Maintenance, Data Package 5; G

SD-11 Closeout Submittals

Assembled Operation and Maintenance Manuals; G

Equipment Test Schedule; G

Required Settings; G

Service Entrance Available Fault Current Label; G

1.5 QUALITY ASSURANCE

1.5.1 Product Data

Include manufacturer's information on each submittal for each component, device and accessory provided with the switchboard including:

a. Circuit breaker type, interrupting rating, and trip devices, including available settings.

b. Manufacturer's instruction manuals and published time-current curves (in electronic format) of the main secondary breaker and largest secondary feeder device.

1.5.2 Switchboard Drawings

Include wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure a coordinated installation. Identify circuit terminals on wiring diagrams and indicate the internal wiring for each item of equipment and the interconnection between each item of equipment. Indicate on the drawings adequate clearance for operation, maintenance, and replacement of operating equipment devices. Include the nameplate data, size, and capacity on submittal. Also include applicable federal, military, industry, and technical society publication references on submittals. Include the following:

a. One-line diagram including breakers.

b. Outline drawings including front elevation, section views, footprint, and overall dimensions.

c. Bus configuration including dimensions and ampere ratings of bus bars.

d. Markings and NEMA nameplate data.

e. Circuit breaker type, interrupting rating, and trip devices, including available settings.

f. Wiring diagrams and elementary diagrams with terminals identified, and indicating prewired interconnections between items of equipment and the interconnection between the items.

g. Manufacturer's instruction manuals and published time-current curves (in electronic format) of the main secondary breaker and largest secondary feeder device. Use this information (designer of record) to provide breaker settings that ensures protection and coordination are achieved. For Navy installations, provide electronic format curves using SKM's Power Tools for Windows device library electronic format or EasyPower device library format depending on installation modeling software requirements.

1.5.3 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" or "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Provide equipment, materials, installation, and workmanship in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.5.4 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship, and:

a. Have been in satisfactory commercial or industrial use for 2 years prior to bid opening including applications of equipment and materials under similar circumstances and of similar size.

b. Have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period.

c. Where two or more items of the same class of equipment are required, provide products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.4.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.4.2 Material and Equipment Manufacturing Date

Products manufactured more than one year prior to date of delivery to site are not acceptable.

1.6 MAINTENANCE

1.6.1 Switchboard Operation and Maintenance Data

Submit Operation and Maintenance Manuals in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA.

1.6.2 Assembled Operation and Maintenance Manuals

Assemble and securely bind manuals in durable, hard covered, water resistant binders. Assemble and index the manuals in the following order with a table of contents:

a. Manufacturer's O&M information required by the paragraph SD-10, OPERATION AND MAINTENANCE DATA.

b. Catalog data required by the paragraph SD-03, PRODUCT DATA.

c. Drawings required by the paragraph SD-02, SHOP DRAWINGS.

d. Prices for spare parts and supply list.

f. Design test reports.

g. Production test reports.

1.7 WARRANTY

Provide equipment items that are supported by service organizations reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

PART 2 PRODUCTS

2.1 PRODUCT COORDINATION

Products and materials not considered to be switchboards and related accessories are specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION, and Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

2.2 SWITCHBOARD

NEMA PB 2 and UL 891.

2.2.1 Ratings

Provide equipment with the following ratings:

a. Voltage rating: 208Y/120 volts AC, three-phase, 4-wireas indicated.

b. Continuous current rating of the main bus: as indicated.

c. Short-circuit current rating: as indicated.

d. UL listed and labeled as service entrance equipment.

2.2.2 Construction

Provide the following:

a. Switchboard: consisting of one or more vertical sections bolted together to form a rigid assembly and rearfront and rear aligned.

b. All circuit breakers: front accessible.

c. Rear aligned switchboards: front accessible load connections.

d. Front and rear aligned switchboards: rear accessible load connections.

e. Where indicated, "space for future" or "space" means to include a vertical bus provided behind a blank front cover. Where indicated, "provision for future" means full hardware provided to mount a breaker suitable for the location.

f. Completely factory engineered and assembled, including protective devices and equipment indicated with necessary interconnections, instrumentation, and control wiring.

2.2.2.1 Enclosure

Provide the following:

a. Enclosure: NEMA ICS 6 Type 1.

b. Enclosure: bolted together with removable bolt-on side and rear covers.

c. Front doors: provided with padlockable vault handles with a three point catch.

d. Bases, frames and channels of enclosure: corrosion resistant and fabricated of galvanized steel. Separate sections using vertical steel barriers.

e. Base: includes any part of enclosure that is within 3 inches of concrete pad.

f. Galvanized steel: ASTM A123/A123M, ASTM A653/A653M G90 coating, and ASTM A153/A153M, as applicable. Galvanize after fabrication where practicable.

g. Paint color: ASTM D1535 light gray No. 61 or No. 49 over rust inhibitor.

h. Paint coating system: comply with IEEE C57.12.28 for galvanized steel.

2.2.2.2 Bus Bars

Provide the following:

a. Bus bars: copper with silver-plated contact surfaces.

(1) Phase bus bars: uninsulated.

(2) Neutral bus: rated 100 percent of the main bus continuous current rating as indicated.

b. Make bus connections and joints with hardened steel bolts.

c. Main-bus (through bus): rated at the full ampacity of the main throughout the switchboard.

d. Minimum one-quarter by 2 inch copper ground bus secured to each vertical section along the entire length of the switchboard.

2.2.2.3 Main Section

Provide the main section consisting ofa combination section with molded-case circuit breakers for the main and branch devices as indicated.

2.2.2.4 Distribution Sections

Provide the distribution sections consisting of molded-case circuit breakers as indicated.

2.2.3 Protective Device

Provide main and branch protective devices as indicated.

2.2.3.1 Insulated-Case Breaker

Provide the following:

a. UL 489. UL listed and labeled, 100 percent rated main breaker standard rated branch breakers, manually operated, low voltage, insulated-case circuit breaker, with a short-circuit current rating as indicated

b. Breaker frame size: as indicated.

c. Series rated circuit breakers are unacceptable.

2.2.3.2 Molded-Case Circuit Breaker

Provide the following:

a. UL 489. UL listed and labeled, 100 percent rated main breaker standard rated branch breakers, manually operated, low voltage molded-case circuit breaker, with a short-circuit current rating of as indicated

b. Breaker frame size: as indicated.

c. Series rated circuit breakers are unacceptable.

2.2.4 Terminal Boards

Provide with engraved plastic terminal strips and screw type terminals for external wiring between components and for internal wiring between removable assemblies. Provide short-circuiting type terminal boards associated with current transformer. Terminate conductors for current transformers with ring-tongue lugs. Provide terminal board identification that is identical in similar units. Provide color coded external wiring that is color coded consistently for similar terminal boards.

2.2.5 Wire Marking

Mark control and metering conductors at each end. Provide factory installed, white, plastic tubing, heat stamped with black block type letters on factory-installed wiring. On field-installed wiring, provide white, preprinted, polyvinyl chloride (PVC) sleeves, heat stamped with black block type letters. Provide a single letter or number on each sleeve, elliptically shaped to securely grip the wire, and keyed in such a manner to ensure alignment with adjacent sleeves. Provide specific wire

markings using the appropriate combination of individual sleeves. Indicate on each wire marker the device or equipment, including specific terminal number to which the remote end of the wire is attached.

2.3 MANUFACTURER'S NAMEPLATE

Provide a nameplate on each item of equipment bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent is not acceptable. This nameplate and method of attachment may be the manufacturer's standard if it contains the required information.

2.4 FIELD FABRICATED NAMEPLATES

ASTM D709. Provide laminated plastic nameplates for each switchboard, equipment enclosure, relay, switch, and device; as specified in this section or as indicated on the drawings. Identify on each nameplate inscription the function and, when applicable, the position. Provide nameplates of melamine plastic, 0.125 inch thick, white with black center core. Provide matte finish surface. Provide square corners. Accurately align lettering and engrave into the core. Provide nameplates with minimum size of one by 2.5 inches. Provide lettering that is a minimum of 0.25 inch high normal block style.

2.5 SOURCE QUALITY CONTROL

2.5.1 Equipment Test Schedule

The Government reserves the right to witness tests. Provide equipment test schedules for tests to be performed at the manufacturer's test facility. Submit required test schedule and location, and notify the Contracting Officer 30 calendar days before scheduled test date. Notify Contracting Officer 15 calendar days in advance of changes to scheduled date.

Provide the following as part of test equipment calibration:

a. Provide a calibration program which assures that all applicable test instruments are maintained within rated accuracy.

b. Accuracy: Traceable to the National Institute of Standards and Technology.

c. Instrument calibration frequency schedule: less than or equal to 12 months for both test floor instruments and leased specialty equipment.

d. Dated calibration labels: visible on all test equipment.

e. Calibrating standard: higher accuracy than that of the instrument tested.

f. Keep up-to-date records that indicate dates and test results of instruments calibrated or tested. For instruments calibrated by the manufacturer on a routine basis, in lieu of third party calibration, include the following:

(1) Maintain up-to-date instrument calibration instructions and procedures for each test instrument.

(2) Identify the third party/laboratory calibrated instrument to verify that calibrating standard is met.

2.5.2 Switchboard Design Tests

NEMA PB 2 and UL 891.

2.5.2.1 Design Tests

Furnish documentation showing the results of design tests on a product of the same series and rating as that provided by this specification.

a. Short-circuit current test.

b. Enclosure tests.

c. Dielectric test.

2.5.3 Switchboard Production Tests

NEMA PB 2 and UL 891. Furnish reports which include results of production tests performed on the actual equipment for this project. These tests include:

a. 60-hertz dielectric tests.

b. Mechanical operation tests.

c. Electrical operation and control wiring tests.

d. Ground fault sensing equipment test.

2.6 COORDINATED POWER SYSTEM PROTECTION

Provide a power system study as specified in Section 26 28 01.00 10 COORDINATED POWER SYSTEM PROTECTION.

2.7 ARC FLASH WARNING LABEL

Provide warning label for switchboards. Locate this self-adhesive warning label on the outside of the enclosure warning of potential electrical arc flash hazards and appropriate PPE required. Provide label format as indicated.

2.8 SERVICE ENTRANCE AVAILABLE FAULT CURRENT LABEL

Provide label on exterior of switchboards used as service equipment listing the maximum available fault current at that location. Include on the label the date that the fault calculation was performed and the contact information for the organization that completed the calculation. Locate this self-adhesive warning label on the outside of the switchboard. Provide label format as indicated.

PART 3 EXECUTION

3.1 INSTALLATION

Conform to IEEE C2, NFPA 70, and to the requirements specified herein. Provide new equipment and materials unless indicated or specified

otherwise.

3.2 GROUNDING

NFPA 70 and IEEE C2, except that grounds and grounding systems with a resistance to solid earth ground not exceeding 25 ohms.

3.2.1 Grounding Electrodes

Provide driven ground rods as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION. Connect ground conductors to the upper end of the ground rods by exothermic weld or compression connector. Provide compression connectors at equipment end of ground conductors.

3.2.2 Equipment Grounding

Provide bare copper cable not smaller than No. 4/0 AWG not less than 24 inches below grade connecting to the indicated ground rods. When work in addition to that indicated or specified is directed to obtain the specified ground resistance, the provision of the contract covering "Changes" applies.

3.2.3 Connections

Make joints in grounding conductors and loops by exothermic weld or compression connector. Install exothermic welds and compression connectors as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.

3.2.4 Grounding and Bonding Equipment

UL 467, except as indicated or specified otherwise.

3.3 INSTALLATION OF EQUIPMENT AND ASSEMBLIES

Install and connect equipment furnished under this section as indicated on project drawings, the approved shop drawings, and as specified herein.

3.3.1 Switchboard

ANSI/NEMA PB 2.1.

3.3.2 Field Fabricated Nameplate Mounting

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.4 FOUNDATION FOR EQUIPMENT AND ASSEMBLIES

3.4.1 Interior Location

Mount switchboard on concrete slab as follows:

a. Unless otherwise indicated, provide the slab with dimensions at least 4 inches thick.

b. Install slab such that the top of the concrete slab is approximately 4 inches above the finished grade.

c. Provide edges above grade 1/2 inch chamfer.

d. Provide slab of adequate size to project at least 8 inches beyond the equipment.

e. Provide conduit turnups and cable entrance space required by the equipment to be mounted.

f. Seal voids around conduit openings in slab with water- and oil-resistant caulking or sealant.

g. Cut off and bush conduits 3 inches above slab surface.

h. Provide concrete work as specified in Section 03 30 00 CAST-IN-PLACE CONCRETE.

3.5 FIELD QUALITY CONTROL

Submit Required Settings of breakers to the Contracting Officer after approval of switchboard and at least 30 days in advance of their requirement.

3.5.1 Performance of Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations and include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

3.5.1.1 Switchboard Assemblies

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical, electrical, and mechanical condition.

(3) Verify appropriate anchorage, required area clearances, and correct alignment.

(4) Clean switchboard and verify shipping bracing, loose parts, and documentation shipped inside cubicles have been removed.

(5) Inspect all doors, panels, and sections for paint, dents, scratches, fit, and missing hardware.

(6) Verify that circuit breaker sizes and types correspond to approved shop drawings as well as to the circuit breaker’s address for microprocessor-communication packages.

(8) Inspect all bolted electrical connections for high resistance using low-resistance ohmmeter, verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey.

(9) Confirm correct operation and sequencing of electrical and mechanical interlock systems.

(10) Confirm correct application of manufacturer's recommended lubricants.

(11) Inspect insulators for evidence of physical damage or contaminated surfaces.

(12) Verify correct barrier installation.

(13) Exercise all active components.

(14) Inspect all mechanical indicating devices for correct operation.

(15) Verify that filters are in place and vents are clear.

(16) Test operation, alignment, and penetration of instrument transformer withdrawal disconnects.

(17) Inspect control power transformers.

b. Electrical Tests

(1) Perform insulation-resistance tests on each bus section.

(2) Perform dielectric withstand voltage tests.

(3) Perform insulation-resistance test on control wiring; Do not perform this test on wiring connected to solid-state components.

(4) Perform control wiring performance test.

(5) Perform primary current injection tests on the entire current circuit in each section of assembly.

3.5.1.2 Circuit Breakers - Low Voltage - Power

a. Visual and Mechanical Inspection

(1) Compare nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Inspect anchorage, alignment, and grounding.

(4) Verify that all maintenance devices are available for servicing and operating the breaker.

(5) Inspect arc chutes.

(6) Inspect moving and stationary contacts for condition, wear, and alignment.

(7) Verify that primary and secondary contact wipe and other dimensions vital to satisfactory operation of the breaker are correct.

(8) Perform all mechanical operator and contact alignment tests on both the breaker and its operating mechanism.

(9) Inspect all bolted electrical connections for high resistance using low-resistance ohmmeter, verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey.

(10) Verify cell fit and element alignment.

(11) Verify racking mechanism.

(12) Confirm correct application of manufacturer's recommended lubricants.

b. Electrical Tests

(1) Perform contact-resistance tests on each breaker.

(2) Perform insulation-resistance tests.

(3) Adjust Breaker(s) for final settings in accordance with Government provided settings.

(4) Determine long-time minimum pickup current by primary current injection.

(5) Determine long-time delay by primary current injection.

(10) Verify correct operation of any auxiliary features such as trip and pickup indicators, zone interlocking, electrical close and trip operation, trip-free, and antipump function.

(11) Verify operation of charging mechanism.

3.5.1.3 Circuit Breakers

Low Voltage - Insulated-Case and Low Voltage Molded Case with Solid State Trips

a. Visual and Mechanical Inspection

(1) Compare nameplate data with specifications and approved shop drawings.

(2) Inspect circuit breaker for correct mounting.

(3) Operate circuit breaker to ensure smooth operation.

(4) Inspect case for cracks or other defects.

(5) Inspect all bolted electrical connections for high resistance using low resistance ohmmeter, verifying tightness of accessible bolted connections and/or cable connections by calibrated torque-wrench method, or performing thermographic survey.

(6) Inspect mechanism contacts and arc chutes in unsealed units.

b. Electrical Tests

(1) Perform contact-resistance tests.

(2) Perform insulation-resistance tests.

(3) Perform Breaker adjustments for final settings in accordance with Government provided settings.

(4) Perform long-time delay time-current characteristic tests

3.5.1.4 Current Transformers

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Verify correct connection.

(4) Verify that adequate clearances exist between primary and secondary circuit.

(5) Inspect all bolted electrical connections for high resistance using low-resistance ohmmeter, verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method, or performing thermographic survey.

(6) Verify that all required grounding and shorting connections provide good contact.

b. Electrical Tests

(1) Perform resistance measurements through all bolted connections with low-resistance ohmmeter, if applicable.

(2) Perform insulation-resistance tests.

(3) Perform polarity tests.

(4) Perform ratio-verification tests.

3.5.1.5 Metering and Instrumentation

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Verify tightness of electrical connections.

b. Electrical Tests

(1) Determine accuracy of meters at 25, 50, 75, and 100 percent of full scale.

(2) Calibrate watthour meters according to manufacturer's published data.

(3) Verify all instrument multipliers.

(4) Electrically confirm that current transformer and voltage transformer secondary circuits are intact.

3.5.1.6 Grounding System

a. Visual and Mechanical Inspection

(1) Inspect ground system for compliance with contract plans and specifications.

b. Electrical Tests

(1) IEEE 81. Perform ground-impedance measurements utilizing the fall-of-potential method. On systems consisting of interconnected ground rods, perform tests after interconnections are complete. On systems consisting of a single ground rod perform tests before any wire is connected. Take measurements in normally dry weather, not less than 48 hours after rainfall. Use a portable ground resistance tester in accordance with manufacturer's instructions to test each ground or group of grounds. Use an instrument equipped with a meter reading directly in ohms or fractions thereof to indicate the ground value of the ground rod or grounding systems under test.

(2) Submit the measured ground resistance of each ground rod and grounding system, indicating the location of the rod and grounding system. Include the test method and test setup (i.e., pin location) used to determine ground resistance and soil conditions at the time the measurements were made.

3.5.2 Follow-Up Verification

Upon completion of acceptance checks, settings, and tests, show by demonstration in service that circuits and devices are in good operating condition and properly performing the intended function. Trip circuit breakers by operation of each protective device. Test each item to perform its function not less than three times. As an exception to requirements stated elsewhere in the contract, provide the Contracting Officer five working days advance notice of the dates and times for checks, settings, and tests.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 27 14.00 20

ELECTRICITY METERING
02/21, CHG 1: 05/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI C12.1	(2014; Errata 2016) Electric Meters - Code for Electricity Metering

AMERICAN SOCIETY OF HEATING, REFRIGERATING AND AIR-CONDITIONING ENGINEERS (ASHRAE)

ASHRAE 90.1 - IP	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings
ASHRAE 90.1 - SI	(2019) Energy Standard for Buildings Except Low-Rise Residential Buildings

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C37.90.1	(2013) Standard for Surge Withstand Capability (SWC) Tests for Relays and Relay Systems Associated with Electric Power Apparatus
IEEE C57.13	(2016) Standard Requirements for Instrument Transformers

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2021) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI C12.7	(2014) Requirements for Watthour Meter Sockets
ANSI C12.18	(2006; R 2016) Protocol Specification for ANSI Type 2 Optical Port
ANSI C12.20	(2015; E 2018) Electricity Meters - 0.1, 0.2, and 0.5 Accuracy Classes
NEMA C12.19	(2021) Utility Industry End Device Data Tables

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Installation Drawings; G

SD-03 Product Data

Electricity Meters; G

Current Transformer; G

Potential Transformer; G

External Communications Devices; G

SD-06 Test Reports

Acceptance Checks and Tests; G

System Functional Verification; G

Building Meter Installation Sheet, per Building; G

Meter Configuration Template; G

Contractor must fill in the meter configuration template and submit to the Activity for concurrence.

Meter Configuration Report; G

The meter configuration report must be submitted as a Technical Data Package.

SD-10 Operation and Maintenance Data

Electricity Meters and Accessories, Data Package 5; G

Submit operation and maintenance data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA and as specified herein.

SD-11 Closeout Submittals

System Functional Verification; G

1.3 QUALITY ASSURANCE

1.3.1 Installation Drawings

Drawings must be provided in hard-copy and electronic format, and must include but not be limited to the following:

a. Wiring diagrams with terminals identified of advanced meter, current transformers, potential transformers, protocol modules, communications interfaces, Ethernet connections, telephone lines. For each typical meter installation, provide a diagram.

b. One-line diagram, including meters, switch(es), current transformers, potential transformers, protocol modules, communications interfaces, Ethernet connections, telephone outlets, and fuses. For each typical meter installation, provide a diagram. Provide one-line diagram to the local Public Works department.

1.3.2 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products must have been in satisfactory commercial or industrial use for one year prior to bid opening. The one-year period must include applications of equipment and materials under similar circumstances and of similar size. The product, or an earlier release of the product, must have been on sale on the commercial market through advertisements, manufacturers catalogs, or brochures during the prior one-year period. Where two or more items of the same class of equipment are required, these items must be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.3.3 Material and Equipment Manufacturing Data

Products manufactured more than 1 year prior to date of delivery to site must not be used, unless specified otherwise.

1.4 MAINTENANCE

1.4.1 Additions to Operation and Maintenance Data

In addition to requirements of Data Package 5, include the following on the actual electricity meters and accessories provided:

a. A condensed description of how the system operates

b. Block diagram indicating major assemblies

c. Troubleshooting information

d. Preventive maintenance

e. Prices for spare parts and supply list

1.5 WARRANTY

The equipment items and software must be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment and software on a regular and emergency basis during the warranty period of the contract.

1.6 SYSTEM DESCRIPTION

1.6.1 System Requirements

Electricity metering, consisting of meters and associated equipment, will be used to record the electricity consumption and other values as described in the requirements that follow and as shown on the drawings. Communication system requirements are contained in a separate specification section as identified in paragraph COMMUNICATIONS INTERFACES.

1.6.2 Selection Criteria

Metering components and software are part of a system that includes the physical meter, data recorder function and communications method. Every building site identified must include sufficient metering components to measure the electrical parameters identified and to store and communicate the values as required.

Contractor must verify that the electricity meter installed on any building site is compatible with the base-wide metering system with respect to the types of meters selected and the method used to program the meters for initial use. Software and meter programming tools are necessary to set up the meters described by this specification. New software tools different from the meter programming methods currently used by base personnel will require an Authority to Operate (ATO) by Command Information Office at the Enterprise level..

PART 2 PRODUCTS

2.1 ELECTRICITY METERS AND ACCESSORIES

Provide meter(s) and connect the meter(s) to the existing AMI DAS. The contractor must use the existing government laptop computers to configure the meter using existing software loaded on the computer. The contractor will not be allowed to modify any software or add any additional software to the computer. Alternatively, the government will configure the meter(s), which must be compatible with the existing system, using existing software. Contractor must insure that the meter(s) will transmit the specified data to the DAS. The current meters being used by base are: Coordiante with contracting officer..

2.1.1 Physical and Common Requirements

a. Provide metering system components in accordance with the Metering System Schedule shown in this specification. Provide Meter configuration template.

b.

c. Meter must have NEMA 3R stainless steel enclosure for surface mounting with bottom or rear penetrations.

d. Surge withstand capability must conform to IEEE C37.90.1.

e. Use #12 SIS (XHHW, or equivalent) wiring with ring lugs for all meter connections. Color code and mark the conductors as follows:

(1) Red - Phase A CT - C1
(2) Orange - Phase B CT - C2
(3) Brown - Phase C CT - C3
(4) Gray with white stripe - neutral current return - C0
(5) Black - Phase A voltage - V1
(6) Yellow - Phase B voltage - V2
(7) Blue - Phase C voltage - V3
(8) White - Neutral voltage

2.1.2 Potential Transformer Requirements

a. Meter must be capable of connection to the service voltage phases and magnitude being monitored. If the meter is not rated for the service voltage, provide suitable potential transformers to send an acceptable voltage to the meter.

b. Voltage input must be optically isolated to 2500 volts DC from signal and communications outputs. Components must meet or exceed IEEE C37.90.1.

c. Provide a pull-out type fuse block containing one fuse per phase, Class RK type, to protect the voltage input to the meter. Size fuses as recommended by the meter manufacturer. Fusing must either be inside the secondary compartment of the transformer or inside the same enclosure as the CT shorting device.

d. Potential transformers will be used to convert 480 volt inputs to 120 volts for the locations shown on the metering schedule. Potential transformers must be rated indoor or outdoor, as required for the specific application. Voltage rating must provide 120 volts, wye-connected, 3 phase, 4 wire, 60 Hz, insulation class, 600 volts. Potential transformers BIL must be 10 kV and must have an accuracy class of 0.3 at burdens w, x, and y. Thermal rating must be 500 VA.

e. The Contractor must be responsible for determining the actual voltage ratio of each potential transformer for medium voltage applications. Transformer must conform to IEEE C57.13 and the following requirements.

(1) Type: Dry type, of two-winding construction.

(2) Weather: Outdoor or indoor rated for the application.

(3) Frequency: Nominal 60 Hz.

(4) Accuracy: Plus or minus 0.3 percent at 60 Hz.

f. Potential transformers installed inside switchgear and panels must be rated for interior use. Voltage rating must provide 120 volts, wye-connected, 3 phase, 4 wire, 60 Hz, insulation class, 600 volts. Potential transformers BIL must be a minimum of 10 kV, and have an insulation class and BIL rating that equals or exceeds the ratings of the associated switchgear. Potential transformers must have an accuracy class of 0.15 at burdens w, x, and y. Thermal rating must be

500 VA. Potential transformers must be accessed from the front and mounted in a metering section.

2.1.3 Current Transformer Requirements

a. Current transformer must be installed with a rating as shown in the schedule.

b. Current transformers must have an Accuracy Class of 0.15 (with a maximum error of plus/minus 0.3 percent at 5.0 amperes) when operating within the specified rating factor.

c. Current transformers must be solid-core, bracket-mounted for new installations using ring-tongue lugs for electrical connections. Current transformers must be accessible and the associated wiring must be installed in an organized and neat workmanship arrangement. Current transformers that are retrofitted onto existing switchgear busbar can be a busbar split-core design.

d. Current transformers must have:

(1) Insulation Class: All 600 volt and below current transformers must be rated 10 KV BIL.

(2) Frequency: Nominal 60 Hz.

(3) Burden: Burden class must be selected for the load.

(4) Phase Angle Range: 0 to 60 degrees.

e. Meter must accept current input from standard instrument transformers (5A secondary current transformers).

f. Current inputs must have a continuous rating in accordance with IEEE C57.13.

g. Provide one single-ratio current transformer for each phase per power transformer with characteristics listed in the following table.

Single-Ratio Current Transformer Characteristics

kVA	Sec. Volt	CT Ratio	RF	Meter Acc. Class
500	208Y:120	1200:5	1.33	0.3 thru B0.05
750	480Y:277	800/5	1.33	0.3 thru B0.05

2.1.4 Meter Requirements

Electricity meters must include the following features:

a. Meter must comply with ANSI C12.1, NEMA C12.19, and ANSI C12.20 and must match existing AMI meter system at the installation and be the newest version with ATO.

b. Meter sockets must comply with ANSI C12.7.

e. Provide socket-mounted or panel mounted meters as indicated on the meter schedule.

f. Meter must be a Class 20, transformer rated design.

g. Use Class 200 meters for direct current reading without current transformers for applications with an expected load less than 200 amperes, where indicated.

h. Meter must be rated for use at temperature from minus 40 degrees Centigrade to plus 70 degrees Centigrade.

i. The meters must have an electronic demand recording register and must be secondary reading as indicated. The register must be used to indicate maximum kilowatt demand as well as cumulative or continuously cumulative demand. Demand must be measured on a block-interval basis and must be capable of a 5 to 60 minute interval and initially set to a 15-minute interval. It must have provisions to be programmed to calculate demand on a rolling interval basis. Meter readings must be true RMS.

j. The meter electronic register must be of modular design with non-volatile data storage. Downloading meter stored data must be capable via an optical port. Recording capability of data storage with a minimum capability of 89 days of 15 minute, 2 channel interval data. The meter must be capable of providing at least 2 KYZ pulse outputs (dry contacts). Default initial configuration (unless identified otherwise by base personnel) must meet NAVFAC CIRCUITS Call for Consistency document located on the NAVFAC CIRCUITS Portal and must be:

(1) First channel - kWh
(2) Second channel - kVARh
(3) KYZ output #1 - kWh
(4) KYZ output #2 - kVARh

k. All meters must have identical features available in accordance with this specification. The meter schedule identifies which features must be activated at each meter location.

l. Enable switches for Time of Use (TOU), pulse and load profile measurement module at the factory.

m. Meter must have an optical port on front of meter. Optical device must be compatible with ANSI C12.18.

n. Meters must be 120-480 volts auto ranging.

o. Provide blank tag fixed to the meter faceplate for the addition of the meter multiplier, which will be the product of the current transformer and potential transformer ratio and will be filled in by base personnel on the job site. The meter's nameplate must include:

(1) Meter ID number.
(2) Rated voltage.
(3) Current class.
(4) Metering form.
(5) Test amperes.

(6) Frequency.
(7) Catalog number.
(8) Manufacturing date.

p. On switchboard style installations, provide switchboard case with disconnect means for meter removal incorporating short-circuiting of current transformer circuits.

q. Meter covers must be polycarbonate resins with an optical port and reset. Backup battery must be easily accessible for change-out after removing the meter cover.

r. The normal billing data scroll must be fully programmable. The normal billing data scroll requirements provided in the CIRCUITS Call for Consistency Document located on the NAVFAC CIRCUITS Portal. Data scroll display must include the following.

(1) Number of demand resets.
(2) End-of-interval indication.
(3) Maximum demand.
(4) New maximum demand indication.
(5) Cumulative or continuously cumulative.
(6) Time remaining in interval.
(7) Kilowatt hours.

s. The register must incorporate a built-in test mode that allows it to be tested without the loss of any data or parameters. The following quantities must be available for display in the test mode:

(1) Present interval's accumulating demand.
(2) Maximum demand.
(3) Number of impulses being received by the register.

t. Pulse module simple I/O board with programmable ratio selection.

u. Meters must be programmed after installation via an optical port. Optical display must show TOU data, peak kWh, semi-peak kWh, off peak kWh, and phase angles.

v. Self-monitoring to provide for:

(1) Unprogrammed register.
(2) RAM checksum error.
(3) ROM checksum error.
(4) Hardware failure.
(5) Memory failure.
(6) EPROM error.
(7) Battery status (fault, condition, or time in service).

w. Liquid crystal alphanumeric displays, 9 digits, blinking squares confirm register operation. Six Large digits for data and smaller digits for display identifier.

x. Display operations, programmable sequence with display identifiers. Display identifiers must be selectable for each item. Continually sequence with time selectable for each item.

y. The meters must support three modes of registers: Normal Mode, Alternate Mode, and Test Mode. The meter also must support a

"Toolbox" or "Service Information" (accessible in the field) through an optocom port to a separate computer using the supplied software to allow access to instantaneous service information such as voltage, current, power factor, load demand, and the phase angle for individual phases.

z. Meter must have a standard 4 -year warranty.

2.1.5 Disconnect Method

a. Provide a 10-pole safety disconnect complete with isolation devices for the voltage and current transformer inputs, including a shorting means for the current transformers.

b. Disconnecting wiring blocks must be provided between the current transformer and the meter. A shorting mechanism must be built into the wiring block to allow the current transformer wiring to be changed without removing power to the transformer. The wiring blocks must be located where they are accessible without the necessity of disconnecting power to the transformer.

c. Voltage monitoring circuits must be equipped with disconnect switches to isolate the meter base or socket from the voltage source.

2.1.6 Installation Methods

a. Transformer Mounted ("XFMR" in Metering Systems Schedule). Meter base must be located outside on the secondary side of the pad-mounted transformer.

b. Stand Mounted Adjacent to Transformer ("STAND" in Metering Systems Schedule). Meter base must be mounted on a structural steel pole approximately 4 feet from the transformer pad. This can be used for multiple meters associated with a single transformers.

c. Building Mounted ("BLDG" in Metering Systems Schedule). Meter base must be mounted on the side of the existing building near the service entrance.

d. Panel Mounted. ("PNL" in Metering Systems Schedule). Meter must be mounted where directed.

e. Commercial meter pedestal ("PED" in Metering Systems Schedule).

2.2 COMMUNICATIONS INTERFACES

Meter must have two-way communication with the existing data acquisition system (DAS). Provide a communications interface utilizing base standards.

Provide interfacing software if a meter is used that is different than the existing meters at the Activity to ensure compatibility within the metering system.

Connect to the AMI network utilizing base standards.

PART 3 EXECUTION

3.1 INSTALLATION

Electrical installations must conform to ASHRAE 90.1 - IP, ASHRAE 90.1 - SI IEEE C2, NFPA 70 (National Electrical Code), and to the requirements specified herein. Provide new equipment and materials unless indicated or specified otherwise.

3.1.1 Scheduling of Work and Outages

The Contract Clauses must govern regarding permission for power outages, scheduling of work, coordination with Government personnel, and special working conditions.

3.2 FIELD QUALITY CONTROL

Perform the following acceptance checks and tests on all installed meters.

3.2.1 Performance of Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations and include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

a. Meter Assembly

(1) Visual and mechanical inspection.

(a) Compare equipment nameplate data with specifications and approved shop drawings.

(b) Inspect physical and mechanical condition. Confirm the meter is firmly seated in the socket, the socket is not abnormally heated, the display is visible, and the ring and seal on the cover are intact.

(c) Inspect all electrical connections to ensure they are tight. For Class 200 services, verify tightness of the service conductor terminations for high resistance using low-resistance ohmmeter, or by verifying tightness of accessible bolted electrical connections by calibrated torque-wrench method.

(d) Record model number, serial number, firmware revision, software revision, and rated control voltage.

(e) Verify operation of display and indicating devices.

(f) Record password and user log-in for each meter.

(g) Verify grounding of metering enclosure.

(h) Set all required parameters including instrument transformer ratios, system type, frequency, power demand methods/intervals, and communications requirements. Verify that the CT ratio and the PT ratio are properly included in the meter multiplier or the programming of the meter. Confirm that the multiplier is provided on the meter face or on the meter.

(i) Provide building meter installation sheet, per building for each facility. See example Graphic E-S1.

(2) Electrical tests.

(a) Apply voltage or current as appropriate to each analog input and verify correct measurement and indication.

(b) Confirm correct operation and setting of each auxiliary input/output feature including mechanical relay, digital, and analog.

(c) After initial system energization, confirm measurements and indications are consistent with loads present.

(d) Make note of, and report, any "Error-Code" or "Caution-Code" on the meter's display.

(3) Provide meter configuration report.

b. Current Transformers

(1) Visual and mechanical inspection.

(a) Compare equipment nameplate data with specification and approved shop drawings.

(b) Inspect physical and mechanical condition.

(c) Verify correct connection, including polarity.

(d) Inspect all electrical connections to ensure they are tight.

(e) Verify that required grounding and shorting connections provide good contact.

(2) Electrical Tests.

Verify proper operation by reviewing the meter configuration report.

c. Potential Transformers

(1) Visual and mechanical inspection.

(a) Verify potential transformers are rigidly mounted.

(b) Verify potential transformers are the correct voltage.

(c) Verify that adequate clearances exist between the primary and secondary circuit.

(2) Electrical Tests.

(a) Verify by the meter configuration report that the polarity and phasing are correct.

3.2.2 System Functional Verification

Verify that the installed meters are working correctly in accordance with the meter configuration report:

a. The correct meter form is installed.

b. All voltage phases are present.

c. Phase rotation is correct.

d. Phase angles are correct.

e. The new meter accurately measures power magnitude and direction, and can communicate as required by paragraph COMMUNICATIONS INTERFACES.

-- End of Section --

SECTION 26 28 01.00 10

COORDINATED POWER SYSTEM PROTECTION
08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 242	(2001; Errata 2003) Recommended Practice for Protection and Coordination of Industrial and Commercial Power Systems - Buff Book
IEEE 399	(1997) Brown Book IEEE Recommended Practice for Power Systems Analysis

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Fault Current Analysis

Protective Device Coordination Study

System Coordinator

1.3 QUALITY ASSURANCE

1.3.1 System Coordinator

System coordination, recommended ratings and settings of protective devices, and design analysis must be accomplished by a registered professional electrical power engineer with a minimum of 3 years of current experience in the coordination of electrical power systems. Submit verification of experience and license number, of a registered Professional Engineer as specified above. Provide experience data consisting of at least five references for work of a magnitude comparable to this contract, including points of contact, addresses and telephone numbers.

PART 2 PRODUCTS

2.1 COORDINATED POWER SYSTEM PROTECTION

Prepare analyses to demonstrate that the equipment selected and system constructed meet the contract requirements for ratings, coordination, and

protection. Include a load flow analysis, a fault current analysis, and a protective device coordination study. Submit the study along with protective device equipment submittals. No time extensions or similar contact modifications will be granted for work arising out of the requirements for this study. Approval of protective devices proposed will be based on recommendations of this study. The Government is not responsible for any changes to equipment, device ratings, settings, or additional labor for installation of equipment or devices ordered and/or procured prior to approval of the study. The studies must be performed by a registered professional engineer with demonstrated experience in power system coordination in the last 3 years. Provide a list of references complete with points of contact, addresses and telephone numbers. The selection of the engineer is subject to the approval of the Contracting Officer.

2.1.1 Scope of Analyses

The fault current analysis and protective device coordination study must begin at: the source bus and extend down to system buses where fault availability is 10,000 amperes (symmetrical) for building/facility 600 volt level distribution buses.

2.1.2 Determination of Facts

Determine and document the time-current characteristics, features, and nameplate data for each existing protective device. Coordinate with the installation for fault current availability at the site.

2.1.3 Single Line Diagram

Prepare a single line diagram to show the electrical system buses, devices, transformation points, and all sources of fault current (including generator and motor contributions). A fault-impedance diagram or a computer analysis diagram may be provided. Each bus, device or transformation point must have a unique identifier. If a fault-impedance diagram is provided, show impedance data. Show location of switches, breakers, and circuit interrupting devices on the diagram together with available fault data, and the device interrupting rating.

2.1.4 Fault Current Analysis

2.1.4.1 Method

Perform the fault current analysis in accordance with methods described in IEEE 242, and IEEE 399.

2.1.4.2 Data

Utilize actual data in fault calculations. Bus characteristics and transformer impedance must be those proposed. Document data in the report.

2.1.4.3 Fault Current Availability

Provide balanced three-phase fault, bolted line-to-line fault, and line-to-ground fault current values at each voltage transformation point and at each power distribution bus. Show the maximum and minimum values of fault available at each location in tabular form on the diagram or in the report.

2.1.5 Coordination Study

Demonstrate that the maximum possible degree of selectivity has been obtained between devices specified, consistent with protection of equipment and conductors from damage from overloads and fault conditions. Include a description of the coordination of the protective devices in this project. Provide a written narrative describing: which devices may operate in the event of a fault at each bus; the logic used to arrive at device ratings and settings; situations where system coordination is not achievable due to device limitations (an analysis of any device curves which overlap); coordination between upstream and downstream devices; and relay settings. Provide recommendations to improve or enhance system reliability, and detail where such changes would involve additions or modifications to the contract and cost damages (addition or reduction). Provide composite coordination plots on log-log graph paper.

2.1.6 Study report

a. Include a narrative describing: the analyses performed; the bases and methods used; and the desired method of coordinated protection of the power system.

b. Include descriptive and technical data for existing devices and new protective devices proposed. Include manufacturers published data, nameplate data, and definition of the fixed or adjustable features of the existing or new protective devices.

c. Document utility company data including system voltages, fault MVA, system X/R ratio, time-current characteristic curves, current transformer ratios, and relay device numbers and settings; .

d. The report must contain fully coordinated composite time-current characteristics curves for each bus in the system, as required to ensure coordinated power system protection between protective devices or equipment. Include recommended ratings and settings of all protective devices in tabulated form.

e. Provide the calculation performed for the analyses, including computer analysis programs utilized. Provide the name of the software package, developer, and version number.

PART 3 EXECUTION

Not Used

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 29 23

ADJUSTABLE SPEED DRIVE (ASD) SYSTEMS UNDER 600 VOLTS
02/20, CHG 1: 05/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

EUROPEAN COMMITTEE FOR STANDARDIZATION (CEN/CENELEC)

EN 61800-3	(2017) Requirements for the Control of Electromagnetic Interference Characteristics of Subsystems and Equipment

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 519	(2022) Standard for Harmonic Control in Electrical Power Systems
IEEE C62.41.1	(2002; R 2008) Guide on the Surges Environment in Low-Voltage (1000 V and Less) AC Power Circuits
IEEE C62.41.2	(2002) Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and Less) AC Power Circuits

INTERNATIONAL ELECTROTECHNICAL COMMISSION (IEC)

IEC 61000-3-12	(2012) Electromagnetic Compatibility (EMC) - Part 3-12: Limits - Limits for harmonic currents produced by equipment connected to public low-voltage systems with input current >16 A and </=75 A per phase

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2020) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA ICS 1	(2022) Standard for Industrial Control and Systems: General Requirements
NEMA ICS 3.1	(2019) Guide for the Application, Handling, Storage, Installation and Maintenance of Medium-Voltage AC Contactors, Controllers and Control Centers
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA ICS 7	(2020) Adjustable-Speed Drives

NEMA ICS 7.2	(2015) Application Guide for AC Adjustable Speed Drive Systems
NEMA ICS 61800-2	(2005) Adjustable Speed Electrical Power Drive Systems Part 2: General Requirements - Rating Specifications for Low Voltage Adjustable Frequency A.C. Power Drive Systems
NEMA MG 1	(2021) Motors and Generators

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

47 CFR 15	Radio Frequency Devices

UL SOLUTIONS (UL)

UL 489	(2025) UL Standard for Safety Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures
UL 61800-5-1	(2016) Adjustable Speed Electrical Power Drive Systems - Part 5-1: Safety Requirements - Electrical, Thermal and Energy

1.2 RELATED REQUIREMENTS

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM applies to this section with additions and modifications specified herein.

1.3 SYSTEM DESCRIPTION

1.3.1 Performance Requirements

1.3.1.1 Electromagnetic Interference Suppression

Computing devices, as defined by 47 CFR 15 and EN 61800-3 rules and regulations, must be certified to comply with the requirements for class A computing devices and labeled.

1.3.1.2 Electromechanical and Electrical Components

Ensure electrical and electromechanical components of the Adjustable Speed Drive (ASD) do not cause electromagnetic interference to adjacent electrical or electromechanical equipment while in operation.

1.3.2 Electrical Requirements

1.3.2.1 Power Line Surge Protection

IEEE C62.41.1 and IEEE C62.41.2, IEEE 519, IEC 61000-3-12 Control panel

must have surge protection, included within the panel to protect the unit from damaging transient voltage surges. Surge protective device must be mounted near the incoming power source and properly wired to all three phases and ground. Fuses must not be used for surge protection.

1.3.2.2 Sensor and Control Wiring Surge Protection

I/O functions as specified must be protected against surges induced on control and sensor wiring installed outdoors and as shown. Test the inputs and outputs in both normal mode and common mode using the following two waveforms:

a. A 10 microsecond by 1000 microsecond waveform with a peak voltage of 1500 volts and a peak current of 60 amperes.

b. An 8 microsecond by 20 microsecond waveform with a peak voltage of 1000 volts and a peak current of 500 amperes.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Schematic Diagrams; G

Interconnecting Diagrams; G

Installation Drawings; G

As-Built Drawings; G

SD-03 Product Data

Adjustable Speed Drives; G

Wires and Cables

Equipment Schedule

SD-06 Test Reports

ASD Test

Performance Verification Tests

Endurance Test

SD-08 Manufacturer's Instructions

Installation instructions

SD-09 Manufacturer's Field Reports

ASD Test Plan; G

Standard Products

SD-10 Operation and Maintenance Data

Adjustable Speed Drives, Data Package 4

1.5 QUALITY ASSURANCE

1.5.1 Schematic Diagrams

Submit diagrams showing circuits and device elements for each replaceable module. Schematic diagrams of printed circuit boards are permitted to group functional assemblies as devices, provided that sufficient information is provided for government maintenance personnel to verify proper operation of the functional assemblies.

1.5.2 Interconnecting Diagrams

Show interconnections between equipment assemblies, and external interfaces, including power and signal conductors. Include for enclosures and external devices.

1.5.3 Installation Drawings

Show floor plan of each site, with ASD's and motors indicated. Indicate ventilation requirements, adequate clearances, and cable routes. Submit drawings for government approval prior to equipment construction or integration. Immediately record modifications to original drawings made during installation for inclusion into the as-built drawings.

1.5.4 Equipment Schedule

Provide schedule of equipment supplied. Schedule must provide a cross reference between manufacturer data and identifiers indicated in shop drawings. Schedule must include the total quantity of each item of equipment supplied and data indicating compatibility with motors being driven. For complete assemblies, such as ASD's, provide the serial numbers of each assembly, and a sub-schedule of components within the assembly. Provide recommended spare parts listing for each assembly or component.

1.5.5 Installation Instructions

Provide installation instructions issued by the manufacturer of the equipment, including notes and recommendations, prior to shipment to the site. Provide operation instructions prior to acceptance testing.

1.5.6 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship and:

a. Have been in satisfactory commercial or industrial use for 2 years prior to bid opening including applications of equipment and materials under similar circumstances and of similar size.

b. Have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period.

c. Where two or more items of the same class of equipment are required, provide products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.6 DELIVERY AND STORAGE

Store delivered equipment to protect from the weather, humidity and temperature variations, dirt and dust, or other contaminants.

1.7 WARRANTY

The complete system must be warranted by the manufacturer for a period of 5 years. Repair or replace any component failing to perform its function as specified and documented at no additional cost to the Government. Items repaired or replaced must be warranted for an additional period of at least one year from the date that it becomes functional again, as specified in FAR 52.246-21 Warranty of Construction.

1.8 MAINTENANCE

1.8.1 Spare Parts

Manufacturers provide spare parts in accordance with recommended spare parts list.

1.8.2 Operation and Maintenance Data

Provide in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA. Provide service and maintenance information including preventive maintenance, assembly, and disassembly procedures. Include electrical drawings from electrical general sections. Provide additional information necessary to provide complete operation, repair, and maintenance information, detailed to the smallest replaceable unit. Include copies of as-built submittals. Provide routine preventative maintenance instructions, and equipment required. Provide instructions on how to modify program settings, and modify the control program. Provide instructions on drive adjustment, trouble-shooting, and configuration. Provide instructions on process tuning and system calibration.

1.8.3 Maintenance Support

During the warranty period, provide on-site, on-call maintenance services by drive manufacturer's personnel on the following basis: The service must be on a per-call basis with 36 hour response. Contractor is responsible for the maintenance of all hardware and software of the system during the warranty period. Various personnel of different expertise must be sent on-site depending on the nature of the maintenance service required. Costs must include travel, local transportation, living expenses, and labor rates of the service personnel while responding to the service request. The provisions of this Section are not in lieu of, nor relieve the Contractor of, warranty responsibilities covered in this specification. Should the result of the service request be the uncovering of a system defect covered under the warranty provisions, all costs for the call, including the labor necessary to identify the defect, must be borne by the Contractor.

1.8.4 Technical Support

Provide the ASDs with manufacturer's technical telephone support in English, readily available during normal working hours.

PART 2 PRODUCTS

2.1 ADJUSTABLE SPEED DRIVES (ASD)

Provide adjustable speed drive to control the speed of induction motor(s). The ASD must include the following minimum functions, features and ratings.

a. Input circuit breaker per UL 489 with a minimum of 10,000 amps symmetrical interrupting capacity and door interlocked external operator.

b. A converter stage per UL 61800-5-1 must change fixed voltage, fixed frequency, ac line power to a fixed dc voltage. The converter must utilize a full wave bridge design incorporating diode rectifiers. Silicon Controlled Rectifiers (SCR) are not acceptable. The converter must be insensitive to three phase rotation of the ac line and must not cause displacement power factor of less than .95 lagging under any speed and load condition.

c. An inverter stage must change fixed dc voltage to variable frequency, variable ac voltage for application to a standard NEMA MG 1 Part 30 motor designed for use with adjustable frequency power supplies. Switch the inverter to produce a sine coded pulse width modulated (PWM) output waveform.

d. The ASD shall be capable of supplying 110 percent of rated full load current for one minute at maximum ambient temperature.

e. The ASD must be designed to operate from a 480 volt, plus or minus 10 percent, three phase, 60 Hz supply, and control motors with a corresponding voltage rating.

f. Acceleration and deceleration time must be independently adjustable from one second to 60 seconds.

Adjust decelerating time by providing an external dynamic braking resistor designed to meet NEMA ICS 61800-2 to be capable of decelerating six times the motor inertia with no more than 150 percent of rated current with the motor at its base speed. Required deceleration time may be achieved using not only dynamic braking resistor but with other methods described in NEMA ICS 7.2-2015 paragraph 5.2.5.

g. Adjustable full-time current limiting must limit the current to a preset value which must not exceed 110 percent of the controller rated current. The current limiting action must maintain the V/Hz ratio constant so that variable torque can be maintained. Short time starting override must allow starting current to reach 175 percent of controller rated current to maximum starting torque.

h. The controllers must be capable of producing an output frequency over the range of 3 Hz to 60 Hz (20 to one speed range), without low speed cogging. Over frequency protection must be included such that a failure in the controller electronic circuitry must not cause

frequency to exceed 110 percent of the maximum controller output frequency selected.

i. Minimum and maximum output frequency must be adjustable over the following ranges: 1) Minimum frequency 3 Hz to 50 percent of maximum selected frequency; 2) Maximum frequency 40 Hz to 60 Hz.

j. The controller efficiency at any speed must not be less than 96 percent.

k. The controllers must be capable of being restarted into a motor coasting in the forward direction without tripping.

l. Protection of power semiconductor components must be accomplished without the use of fast acting semiconductor output fuses. Subjecting the controllers to any of the following conditions must not result in component failure or the need for fuse replacement:

(1) Short circuit at controller output

(2) Ground fault at controller output

(3) Open circuit at controller output

(4) Input undervoltage

(5) Input overvoltage

(6) Loss of input phase

(7) AC line switching transients

(8) Instantaneous overload

(9) Sustained overload exceeding 115 percent of controller rated current

(10) Over temperature

(11) Phase reversal

m. Solid state motor overload protection must be included such that current exceeding an adjustable threshold must activate a 60 second timing circuit. Should current remain above the threshold continuously for the timing period, the controller will automatically shut down.

n. Include slip compensation circuit that will sense changing motor load conditions and adjust output frequency to provide speed regulation of NEMA MG 1 Part 30 designed for use with adjustable frequency power supplies motors to within plus or minus 0.5 percent of maximum speed without the necessity of a tachometer generator.

o. The ASD must be factory set for manual restart after the first protective circuit trip for malfunction (overcurrent, undervoltage, overvoltage or overtemperature) or an interruption of power. The ASD must be capable of being set for automatic restart after a selected time delay. If the drive faults again within a specified time period (adjustable 0-60 seconds), a manual restart will be required. Provide

Bidirectional Autospeed Search capable of starting the ASD into rotating loads spinning in either direction and returning motor to set speed in proper direction, without causing damage to drive, motor, or load.

p. The ASD must include external fault reset capability. All the necessary logic to accept an external fault reset contact must be included.

q. Provide critical speed lockout circuitry to prevent operating at frequencies with critical harmonics that cause resonant vibrations. The ASD must have a minimum of three user selectable bandwidths.

r. Provide preperly sized NEMA rated by-pass and isolation contactors to enable operation of motor in the event of ASD failure and for safety transfers motor between power converter output and bypass circuit using a field-selectable automatic and manual bypass mode. Install mechanical and electrical interlocks between the by-pass and isolation contactors. Provide a selector switch and transfer delay timer. Motor overload and short circuit protective features must remain in use during the bypass mode.

s. Each individual ASD must meet the following Total Harmonic Distortion (THD) requirements at the input terminals to the factory assembly of the ASD or at the load disconnecting means serving the ASD and filter assembly. These measurements should be taken with the drive set at 90 percent frequency (rpms) and the motor under a minimum of 50 percent demand.

(1) The Voltage THD should not exceed 2.0 percent THD.

(2) The Current THD should not exceed 15.0 percent THD.

(3) If the standard factory ASD does not meet or exceed these requirements the factory must install appropriate equipment (Harmonic Traps, Filters, different Drive technology, etc.) to mitigate the distortion to assure performance of the VFD is within the limits.

(4) These tests should be performed at the Manufacturers Laboratory facilities and submitted as part of the Product Data Submittals, in order to prevent the necessity of adding mitigation equipment in the field. If the requirements listed above are met, IEEE 519 will also be met.

t. Minimum Operating Conditions. Designed and constructed ASD's to operate within the following service conditions:

(1) Ambient Temperature Rating: 0 to 120 degrees F.

(2) Non-condensing relative humidity rating: less than 95 percent.

(3) Ambient rating: Not exceed 3,300 feet.

2.1.1 ASD for HVAC Application

ASDs must have the following features:

a. A local operator control providing the following functions:

(1) Remote/Local operator selection with password access.

(2) Run/Stop and manual speed commands.

(3) All programming functions.

(4) Scrolling through all display functions.

b. A local operator control panel with the following data displayed:

(1) ASD status.

(2) Frequency.

(3) Motor RPM.

(4) Phase current.

(5) Scrolling through all display functions.

(6) Fault diagnostics in descriptive text.

(7) All programmed parameters.

c. Standard PI loop controller with input terminal for controlled variable and parameter settings.

d. User interface terminals for remote control of ASD speed, speed feedback, and an isolated form C SPDT relay, which energizes on a drive fault condition.

e. An isolated form C SPDT auxiliary relay which energizes on a run command.

f. An adjustable carrier frequency with 16 KHz minimum upper limit.

g. A built-in or external line reactor with 3 percent minimum impedance to protect the DC bus capacitors and rectifier section diodes, reduce power line transient voltage, line notching, DC bus over-voltage tripping and improve the inverter over-current and over-voltage conditions.

h. Historical logging information and displays:

(1) Real-time clock with current time and date.

(2) Running log of total power versus time.

(3) Total run time.

(4) Fault log, maintaining last four faults with time and data stamp for each.

i. The ASD must be capable of automatic control by a remote 4-20 mA signal, by BACnet network command, or manually by the ASD control panel.

j. ASDs must include the following operator programmable parameters:

(1) Upper and lower limit frequency.

(2) Acceleration and deceleration rate.

(3) Variable torque volts per Hertz curve.

(4) Starting voltage level.

(5) Starting frequency level.

(6) Display speed scaling.

(7) Enable/disable soft stall feature.

(8) Motor overload level.

(9) Motor stall level.

(10) Jump frequency and hysteresis band.

(11) PWM carrier frequency.

k. ASD must have the following protective features:

(1) An electronic adjustable inverse time current limit with consideration for additional heating of the motor at frequencies below 45Hz, for the protection of the motor.

(2) An electronic adjustable soft stall feature, allowing the ASD to lower the frequency to a point where the motor will not exceed the full-load amperage when an overload ASD will automatically return to the requested frequency when load conditions permit.

(3) A separate electronic stall at 110 percent ASD rated current, and a separate hardware trip at 190 percent current.

(4) The ability to shut down if inadvertently started into a rotating load without damaging the ASD or the motor.

(5) The ability to keep a log of a minimum of four previous fault conditions, indicating the fault type and time of occurrence in descriptive text.

(6) The ability to sustain 110 percent rated current for 60 seconds.

(7) The ability to shutdown safely or protect against and record the following fault conditions:

(a) Over current (and an indication if the over current was during acceleration, deceleration, or running).

(b) Over current internal to the drive.

(c) Motor overload at start-up.

(d) Over voltage from utility power.

(e) Motor running overload.

(f) Over voltage during deceleration.

(g) ASD over heat.

(h) Load and ground fault.

(h) Abnormal parameters or data in ASD EEPROM.

2.2 ENCLOSURES

Provide equipment enclosures conforming to NEMA 250, NEMA ICS 7, and NEMA ICS 6, with a heater if located outdoors. An HMCP device shall provide the disconnecting means. The operating handle shall protrude through the door, but the disconnect shall not be mounted on the door. The handle shall indicate ON, OFF, and tripped conditions. The handle shall have provisions to accommodate a minimum of three padlocks in the OFF position. Interlocks shall prevent unauthorized opening or closing of the ASD door with the disconnect handle in the ON position. The door handle interlock should have provisions to be defeated by qualified maintenance personnel.

2.3 WIRES AND CABLES

All wires and cables must conform to NEMA 250, NEMA ICS 7, NFPA 70.

2.4 NAMEPLATES

Nameplates external to NEMA enclosures must conform with the requirements of Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide manufacturer's standard, permanent nameplates for internal areas of enclosures.

2.5 SOURCE QUALITY CONTROL

2.5.1 ASD Test Plan

To ensure quality, each ASD must be subject to a series of in-plant quality control inspections before approval for shipment from the manufacturer's facilities. Provide test plans.

2.5.2 ASD Test Report

To ensure quality, each ASD must be subject to a series of in-plant quality control inspections before approval for shipment from the manufacturer's facilities. Provide test reports.

PART 3 EXECUTION

3.1 INSTALLATION

Per NEMA ICS 3.1, install equipment in accordance with the approved manufacturer's printed installation drawings, instructions, wiring diagrams, and as indicated on project drawings and the approved shop drawings. A field representative of the drive manufacturer must supervise the installation of all equipment, and wiring.

3.2 GROUNDING

Per NEMA ICS 7.2, ASD must be solidly grounded to the main distribution.

3.3 FIELD QUALITY CONTROL

Specified products must be tested as a system for conformance to specification requirements prior to scheduling the acceptance tests. Conduct performance verification tests in the presence of Government representative, observing and documenting complete compliance of the system to the specifications. Submit a signed copy of the test results, certifying proper system operation before scheduling tests.

3.3.1 ASD Test

A proposed test plan must be submitted to the contracting officer at least 28 calendar days prior to proposed testing for approval. The tests must conform to NEMA ICS 1, NEMA ICS 7, and all manufacturer's safety regulations. The Government reserves the right to witness all tests and review any documentation. Inform the Government at least 14 working days prior to the dates of testing. Perform the ASD test with the assistance of a factory-authorized service representative.

3.3.2 Performance Verification Tests

"Performance Verification Test" plan must provide the step by step procedure required to establish formal verification of the performance of the ASD. Compliance with the specification requirements must be verified by inspections, review of critical data, demonstrations, and tests. The Government reserves the right to witness all tests, review data, and request other such additional inspections and repeat tests as necessary to ensure that the system and provided services conform to the stated requirements. Inform the Government 14 calendar days prior to the date the test is to be conducted.

3.3.3 Endurance Test

Immediately upon completion of the performance verification test, the endurance test must commence. The system must be operated at varying rates for not less than 192 consecutive hours, at an average effectiveness level of 0.9998, to demonstrate proper functioning of the complete PCS. Continue the test on a day-to-day basis until performance standard is met. The contractor is not allowed in the building during the endurance test. The system must respond as designed.

3.4 DEMONSTRATION

3.4.1 Training

Coordinate training requirements with the Contracting Officer. Provide video tapes, if available, of all training provided to the Government for subsequent use in training new personnel. Provide all training aids, texts, and expendable support material for a self-sufficient presentation shall be provided, the amount of which to be determined by the contracting officer.

3.4.1.1 Instructions to Government Personnel

Provide the services of competent instructors with minimum two-year field

experience with the operation and maintenance of similar ASDs who will give full instruction to designated personnel in operation, maintenance, calibration, configuration, and programming of the complete control system. Orient the training specifically to the system installed. Instructors must be thoroughly familiar with the subject matter they are to teach. The number of training days of instruction furnished must be as specified. A training day is defined as eight hours of instruction, including two 15-minute breaks and excluding lunch time; Monday through Friday. Provide a training manual for each student at each training phase which describes in detail the material included in each training program. Provide one additional copy for archiving. Provide equipment and materials required for classroom training. Provide a list of additional related courses, and offers, noting any courses recommended. List each training course individually by name, including duration, approximate cost per person, and location of course. Unused copies of training manuals must be turned over to the Government at the end of last training session.

3.4.1.2 Operating Personnel Training Program

Provide one 2-hour training session at the site at a time and place mutually agreeable between the Contractor and the Government. Provide session to train 4 operation personnel in the functional operations of the system and the procedures that personnel will follow in system operation. This training shall include:

a. System overview

b. General theory of operation

c. System operation

d. Alarm formats

e. Failure recovery procedures

f. Troubleshooting

3.4.1.3 Engineering/Maintenance Personnel Training

Accomplish the training program as specified. Training must be conducted on site at a location designated by the Government. Provide a one-day training session to train four engineering personnel in the functional operations of the system. This training must include:

a. System overview

b. General theory of operation

c. System operation

d. System configuration

e. Alarm formats

f. Failure recovery procedures

g. Troubleshooting and repair

h. Maintenance and calibration

i. System programming and configuration

-- End of Section --

SECTION 26 32 15.00

ENGINE-GENERATOR SET STATIONARY 15-2500 KW, WITH AUXILIARIES
05/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.3	(2021) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.5	(2020) Pipe Flanges and Flanged Fittings NPS 1/2 Through NPS 24 Metric/Inch Standard
ASME B16.11	(2021) Forged Fittings, Socket-Welding and Threaded
ASME B16.21	(2021) Nonmetallic Flat Gaskets for Pipe Flanges
ASME B31.3	(2016) Process Piping

ASTM INTERNATIONAL (ASTM)

ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A106/A106M	(2019a) Standard Specification for Seamless Carbon Steel Pipe for High-Temperature Service
ASTM A181/A181M	(2014; R 2020) Standard Specification for Carbon Steel Forgings, for General-Purpose Piping
ASTM A193/A193M	(2025) Standard Specification for Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service and Other Special Purpose Applications
ASTM A194/A194M	(2024) Standard Specification for Carbon Steel, Alloy Steel, and Stainless Steel Nuts for Bolts for High-Pressure or High-Temperature Service, or Both
ASTM A234/A234M	(2019) Standard Specification for Piping Fittings of Wrought Carbon Steel and Alloy Steel for Moderate and High Temperature Service

ASTM D975 (2020) Standard Specification for Diesel Fuel Oils

ELECTRICAL GENERATING SYSTEMS ASSOCIATION (EGSA)

EGSA 101P (1995) Performance Standard for Engine Driven Generator Sets

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 1 (2000; R 2011) General Principles for Temperature Limits in the Rating of Electric Equipment and for the Evaluation of Electrical Insulation

IEEE 43 (2013) Recommended Practice for Testing Insulation Resistance of Rotating Machinery

IEEE 81 (2012) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System

IEEE 100 (2000; Archived) The Authoritative Dictionary of IEEE Standards Terms

IEEE 115 (2019) Guide for Test Procedures for Synchronous Machines: Part I Acceptance and Performance Testing; Part II Test Procedures and Parameter Determination for Dynamic Analysis

IEEE 120 (1989; R 2007) Master Test Guide for Electrical Measurements in Power Circuits

IEEE 519 (2022) Standard for Harmonic Control in Electrical Power Systems

IEEE C2 (2023) National Electrical Safety Code

IEEE C50.12 (2005; R 2010) Standard for Salient Pole 50 HZ and 60 Hz Synchronous Generators and Generation/Motors for Hydraulic Turbine Applications Rated 5 MVA and above

IEEE C57.13 (2016) Standard Requirements for Instrument Transformers

IEEE C57.13.1 (2006; R 2012) Guide for Field Testing of Relaying Current Transformers

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC (2024) International Building Code

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS (2021) Standard for Acceptance Testing Specifications for Electrical Power

Equipment and Systems

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

ISO 3046	(2002, 2006, 2009, 2001) Reciprocating Internal Combustion Engines - Performance--Part 1, 3, 4, 5, 6
ISO 8528	(1993; R 2018) Reciprocating Internal Combustion Engine Driven Alternating Current Generator Sets--Part 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 12, 13

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-58	(2025) Pipe Hangers and Supports - Materials, Design and Manufacture, Selection, Application, and Installation
MSS SP-80	(2019) Bronze Gate, Globe, Angle, and Check Valves

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA ICS 2	(2000; R 2020) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA MG 1	(2021) Motors and Generators
NEMA PB 1	(2011) Panelboards
NEMA PB 2	(2011) Deadfront Distribution Switchboards
NEMA/ANSI C12.11	(2006; R 2019) Instrument Transformers for Revenue Metering, 10 kV BIL through 350 kV BIL (0.6 kV NSV through 69 kV NSV)

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 30	(2021; TIA 20-1; TIA 20-2) Flammable and Combustible Liquids Code
NFPA 37	(2021) Standard for the Installation and Use of Stationary Combustion Engines and Gas Turbines
NFPA 54	(2024) National Fuel Gas Code
NFPA 58	(2024; TIA 24-2) Liquefied Petroleum Gas Code
NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National

	Electrical Code
NFPA 99	(2021; TIA 20-1) Health Care Facilities Code
NFPA 110	(2025) Standard for Emergency and Standby Power Systems

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE ARP892	(1965; R 1994) DC Starter-Generator, Engine
SAE J537	(2016) Storage Batteries

U.S. DEPARTMENT OF DEFENSE (DOD)

MIL-DTL-16884	(2017; Rev P) Fuel, Naval Distillate
MIL-STD-461	(2015; Rev G) Requirements for the Control of Electromagnetic Interference Characteristics of Subsystems and Equipment

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 60	Standards of Performance for New Stationary Sources

UL SOLUTIONS (UL)

UL 142	(2019; Reprint Jan 2021) UL Standard for Safety Steel Aboveground Tanks for Flammable and Combustible Liquids
UL 467	(2022) UL Standard for Safety Grounding and Bonding Equipment
UL 489	(2025) UL Standard for Safety Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures
UL 1236	(2015; Reprint Feb 2021) UL Standard for Safety Battery Chargers for Charging Engine-Starter Batteries
UL 1437	(2006) Electrical Analog Instruments - Panel Board Types

1.2 RELATED MATERIALS

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM, and Section 26 08 00 APPARATUS INSPECTION AND TESTING apply to this section, except as modified herein.

1.3 SUBMITTALS

Government approval is required for submittals. with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Engine-Generator Set and Auxiliary Equipment; G
Auxiliary Systems; G

Detailed Drawings; G

Acceptance; G

SD-03 Product Data

Harmonic Requirements; G

Engine-Generator Set Efficiencies; G

Emissions; G

filters; G

special tools; G

Remote Alarm Annunciator; G

Engine-Generator Parameter Schedule

Generator

Manufacturer's Catalog

Spare Parts

Onsite Training

Vibration-Isolation

Posted Data and Instructions; G

Instructions; G

Experience

Field Engineer

General Installation

Exciter

SD-05 Design Data

Performance Criteria

Sound Limitations; G

Integral Main Fuel Storage Tank

Power Factor

Time-Delay on Alarms

Vibration Isolation

Battery Charger

Capacity Calculations for Engine-Generator Set; G

Brake Mean Effective Pressure (BMEP) Calculations; G

Torsional Vibration Stress Analysis Computations; G

Capacity Calculations for Batteries; G

Turbocharger Load Calculations; G

SD-06 Test Reports

Performance Tests

Factory Inspection and Tests

Factory Tests

Onsite Inspection and Tests; G

Acceptance Checks and Tests; G

Functional Acceptance Tests; G

Maintenance Procedures; G

Operation and Maintenance Manuals; G

Inspections; G

Functional Acceptance Test Procedure; G

SD-07 Certificates

Vibration Isolation

Prototype Test

Reliability and Durability

Fuel System Certification; G

Start-Up Engineer; G

Instructor's Qualification Resume; G

Engine Emission Limits; G

Sound Limitations

Site Visit

Current Balance

Materials and Equipment

Factory Inspection and Tests

SD-09 Manufacturer's Field Reports

Engine Tests; G

Generator Tests; G

Assembled Engine-Generator Set Tests; G

SD-10 Operation and Maintenance Data

Preliminary Assembled Operation and Maintenance Manuals; G

Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA and the paragraph ASSEMBLED OPERATION AND MAINTENANCE MANUALS.

SD-11 Closeout Submittals

Posted Data and Instructions; G

Training Plan; G

1.4 QUALITY ASSURANCE

1.4.1 Conformance to Codes and Standards

Where equipment is specified to conform to requirements of any code or standard such as UL, NEMA, etc., the design, fabrication and installation must also conform to the code.

1.4.2 Vibration Limitation

Limit the maximum engine-generator set vibration in the horizontal, vertical, and axial directions to 6 mils (peak-peak RMS), with an overall velocity limit of 0.95 inches/second RMS, at rated speed for all loads through 110 percent of rated speed. The engine-generator set must be provided with vibration isolation in accordance with the manufacturer's standard recommendation. Where the vibration isolation system does not secure the base to the structure floor or unit foundation, provide seismic restraints in accordance with the seismic parameters specified.

1.4.3 Torsional Analysis

Submit torsional analysis including prototype testing or calculations which certify and demonstrate that no damaging or dangerous torsional

vibrations will occur when the prime mover is connected to the generator, at synchronous speeds, plus/minus 10 percent.

1.4.4 Performance Data

Submit vibration isolation system performance data for the range of frequencies generated by the engine-generator set during operation from no load to full load and the maximum vibration transmitted to the floor. Also submit a description of seismic qualification of the engine-generator mounting, base, and vibration isolation.

1.4.5 Experience

Each component manufacturer must have a minimum of 3 years' experience in the manufacture, assembly and sale of components used with stationary engine-generator sets for commercial and industrial use. The engine-generator set manufacturer/assembler must have a minimum of 3 years' experience in the manufacture, assembly and sale of stationary engine-generator sets for commercial and industrial use. Submit a statement showing and verifying these requirements.

1.4.6 Field Engineer

The engine-generator set manufacturer or assembler must furnish a qualified field engineer to supervise the complete installation of the engine-generator set, assist in the performance of the onsite tests, and instruct personnel as to the operational and maintenance features of the equipment. The field engineer must have attended the engine generator manufacturer's training courses on installation and operation and maintenance of engine generator sets. Submit a letter listing the qualifications, schools, formal training, and experience of the field engineer.

1.4.7 Detailed Drawings

Submit detailed drawings showing the following:

a. Base-mounted equipment, complete with base and attachments, including anchor bolt template and recommended clearances for maintenance and operation.

b. Starting system.

c. Fuel system.

d. Cooling system.

e. Exhaust system.

f. Electric wiring of relays, breakers, programmable controllers, and switches including single line and wiring diagrams.

g. Lubrication system, including piping, pumps, strainers, filters, heat exchangers for lube oil and turbocharger cooling, electric heater, controls and wiring.

h. Location, type, and description of vibration isolation devices for all applications.

i. The safety system, including wiring schematics.

j. One-line schematic and wiring diagrams of the generator, exciter, regulator, governor, and instrumentation.

k. Panel layouts.

l. Mounting and support for each panel and major piece of electrical equipment.

m. Engine-generator set rigging points and lifting instructions.

1.4.8 Auxiliary Systems Engine-Generator Set and Auxiliary Equipment Drawing Requirements

Submit drawings pertaining to the engine-generator set and auxiliary equipment, including but not limited to the following:

a. Certified outline, general arrangement (setting plan), and anchor bolt details. Show total weight and center of gravity of assembled equipment on the steel sub-base.

b. Detailed elementary, schematic wiring, and interconnection diagrams of the engine starting system, jacket coolant heating system, engine protective devices, engine alarm devices, engine speed governor system, generator and excitation system, and other integral devices.

c. Detailed elementary, schematic wiring; and interconnection diagrams of the fuel system, starting battery system, engine-generator control panel, generator circuit breaker, and remote alarm annunciator.

d. Dimensional drawings or catalog cuts of exhaust silencers, radiator, fuel day tanks, fuel oil cooler, valves and pumps, intake filters, vibration isolators, and other auxiliary equipment not integral with the engine-generator set.

1.4.9 Auxiliary Systems Drawing Requirements

Submit drawings showing floor plan arrangement of exhaust, air intake, fuel oil cooler, and jacket coolant water systems including arrangement of piping and pipe sizes.

1.4.10 Vibration Isolation System Certification

Submit certification from the manufacturer that the vibration isolation system will reduce the vibration to the limits specified in the paragraph VIBRATION ISOLATION.

1.4.11 Fuel System Certification

When the fuel system requires a fuel oil cooler as described in the paragraph FUEL OIL COOLER, submit certification from the engine manufacturer that the fuel system design is satisfactory.

1.5 DELIVERY, STORAGE, AND HANDLING

Properly protect materials and equipment, in accordance with the manufacturers recommended storage procedures,before, during, and after installation. Protect stored items from the weather and contamination.

During installation, cap piping and similar openings to keep out dirt and other foreign matter.

Deliver equipment on pallets or blocking wrapped in heavy-duty plastic, sealed to protect parts and assemblies from moisture and dirt. Protect and prepare batteries for shipment as recommended by the battery manufacturer. Store auxiliary equipment at the site in covered enclosures, protected from atmospheric moisture, dirt, and ground water.

1.6 EXTRA MATERIALS

Provide two sets of special tools and two sets of filters required for maintenance. Special tools are those that only the manufacturer provides, for special purposes, or to reach otherwise inaccessible parts. One handset must be provided for each electronic governor when required to indicate and/or change governor response settings. Furnish 4 liters one gallon of identical paint used on engine-generator set in manufacturer's sealed container with each engine-generator set.

Wrenches and tools specifically designed and required to work on the new equipment, which are not commercially available as standard mechanic's tools, must be furnished to the Contracting Officer.

Provide proposed operating instructions for the engine-generator set and auxiliary equipment laminated between matte-surface thermoplastic sheets and suitable for placement adjacent to corresponding equipment. After approval, install operating instructions where directed.

1.7 MAINTENANCE SERVICES

Submit the operation and maintenance manuals and have them approved prior to commencing onsite tests.

1.7.1 Operation Manual

Provide three copies of the manufacturers standard operation manual . Sections must be separated by heavy plastic dividers with tabs which identify the material in the section. Fold drawings with the title block visible, and placed in 8-1/2 by 11 inch plastic pockets with reinforced holes. The manual must include:

a. Step-by-step procedures for system startup, operation, and shutdown;

b. Drawings, diagrams, and single-line schematics to illustrate and define the electrical, mechanical, and hydraulic systems with their controls, alarms, and safety systems;

c. Procedures for interface and interaction with related systems to include automatic transfer switches .

1.7.2 Maintenance Manual

Provide three copies of the manufacturers standard maintenance manual . Separate each section by a heavy plastic divider with tabs. Fold drawings with the title block visible, and placed in plastic pockets with reinforced holes. The manual must include:

a. Procedures for each routine maintenance item.Procedures for troubleshooting.Factory-service, take-down overhaul, and repair

service manuals, with parts lists.

b. The manufacturer's recommended maintenance schedule.

c. A component list which includes the manufacturer's name, address, type or style, model or serial number, rating, and catalog number for the major components.

d. A list of spare parts for each piece of equipment and a complete list of materials and supplies needed for operation.

1.7.3 Assembled Operation and Maintenance Manuals

The contents of the assembled operation and maintenance manuals must include the manufacturer's O&M information required by the paragraph SD-10, OPERATION AND MAINTENANCE DATA and the manufacturer's O&M information specified in Section 26 36 23 AUTOMATIC TRANSFER SWITCHES AND BY-PASS/ISOLATION SWITCH.

a. Manuals must be in separate books or volumes, assembled and bound securely in durable, hard covered, water resistant binder, and indexed by major assembly and components in sequential order.

b. A table of contents (index) must be made part of the assembled O&M. The manual must be assembled in the order noted in table of contents.

c. The cover sheet or binder on each volume of the manuals must be identified and marked with the words, "Operation and Maintenance Manual."

1.8 SITE CONDITIONS

Protect the components of the engine-generator set, including cooling system components, pumps, fans, and similar auxiliaries when not operating and provide components capable of the specified outputs in the following environment:

a. Site Location: Cherry Point MCAS (Havelock, NC)

b. Site Elevation: feet above mean sea level.

c. Ambient Temperatures:

(1) Maximum degrees F dry bulb, degrees F wet bulb.

(2) Minimum degrees F dry bulb.

d. Design Wind Velocity: mph.

e. Prevailing Wind Direction:

f. Seismic Zone: Zone as defined by ICC IBC.

PART 2 PRODUCTS

2.1 SYSTEM REQUIREMENTS

a. Provide and install each engine-generator set complete and totally functional, with all necessary ancillary equipment to include: air

filtration; starting system; generator controls, protection, and isolation; instrumentation; lubrication; fuel system; cooling system; and engine exhaust system. Each engine-generator set must satisfy the requirements specified in the Engine-Generator Parameter Schedule. Submit certification that the engine-generator set and cooling system function properly in the ambient temperatures specified.

b. Provide each engine-generator set consisting of one engine, one generator, and one exciter mounted, assembled, and aligned on one base; and all other necessary ancillary equipment which may be mounted separately. Assemble sets having a capacity of 750 kW or smaller and attach to the base prior to shipping. Sets over 750 kW capacity may be shipped in sections. Provide set components that are environmentally suitable for the locations shown and that are the manufacturer's standard product offered in catalogs for commercial or industrial use. Provide a generator strip heater for moisture control when the generator is not operating. Identify any nonstandard products or components and the reason for their use.

2.1.1 Engine-Generator Parameter Schedule

Engine-Generator Set and Auxiliary Equipment Capacity Calculations for Engine-Generator Set

ENGINE-GENERATOR PARAMETER SCHEDULE	
Identification	Make/Model
Electrical Characteristics	
Power Rating	Prime Gross bhp rating / Net brake power rating kW at 0.8 power factor
Governor Type	Type Make / Model Isochronous
Overload Capacity (Prime applications only)	110 percent of Service Load for 1 hour in 12 consecutive hours
Service Load	kVA (maximum) kVA (continuous)
Motor Starting kVA (Max.)	kVA
Power Factor	0.8 lagging
Engine-Generator Applications	stand-alone
Voltage Regulation (No Load to Full Load)(Stand-alone applications)	plus or minus 2 percent (maximum)
Voltage Bandwidth (steady state)	plus or minus 0.5 percent

ENGINE-GENERATOR PARAMETER SCHEDULE	
Frequency	60 Hz
Voltage	208 volts
Phases	3 Phase, Wye
Minimum Generator Sub-transient Reactance	percent Sub-transient
Nonlinear Loads	kVA
Max Step Load Increase	25 percent of Service Load at 0.8 PF
Transient Recovery Time with Step Load Increase (Voltage)	seconds
Transient Recovery	seconds
Time with Step Load Increase (Frequency)	
Maximum Voltage Deviation with Step Load Increase	5 percent of rated voltage
Maximum Frequency Deviation with Step Load Increase	2.5 percent of rated frequency
Max Step Load Decrease (without shutdown)	100 percent of Service Load at 0.8 PF
Frequency Bandwidth (steady state)	plus or minus 0.25 percent
Frequency Regulation (droop) (No Load to Full Load)	3 percent (maximum)
Frequency Bandwidth (steady state)	plus or minus 0.25 percent
Reactances	Synchronous reactance, Xd Transient reactance, X'd Sub-transient reactance, X"d Negative sequence reactance, X2 Zero sequence reactance, Xo
Capacity Calculations	
Calculations must verify that the engine-generator set power rating is adequate for the following load conditions:	

ENGINE-GENERATOR PARAMETER SCHEDULE					
Lighting	kW				
Computer	kW				
Uninterruptible Power Supplies (UPS)	0 kVA, pulse				
Variable Frequency Drives (VFD)	kVA, pulse				
Motor Starting Sequence	Starting Order	Size (hp)	Locked Rotor NEMA Code	Starting Method	Maximum Voltage Dip
			F	Full Voltage	25 Percent
			F	Full Voltage	25 Percent
			F	Full Voltage	25 Percent
Other Load	kW at 0.8 power factor				
Capacity Calculations for Batteries					
Calculation must verify that the engine starting battery capacity exceeds dc power requirements.					
Mechanical Characteristics					
Engine Description	Strokes/cycle Number of cylinders Bore and Stroke, inches				
Engine Speed	1800 rpm				
Piston Speed	fpm				
Heat Exchanger Type	fin-tube (radiator)shell-tube				
Engine Cooling Type	water/ethylene glycol				
Intercooler Type	Air-to-Air / Jacket Water				
Induction Method	Naturally Aspirated / Turbocharged				
Turbocharger	Make / Model				
Max Time to Start and be Ready to Assume Load	10 seconds				

ENGINE-GENERATOR PARAMETER SCHEDULE	
Max Summer Indoor Temp (Prior to Engine-generator Operation)	degrees F
Min Winter Indoor Temp (Prior to Engine-generator Operation)	degrees F
Max Allowable Heat Transferred To Engine Generator Space at Rated Output Capacity	MBTU/hr
Max Summer Outdoor Temp (Ambient)	degrees F
Min Winter Outdoor Temp (Ambient)	degrees F
Installation Elevation	above sea level
Engine-Generator Set Efficiencies	
Fuel Consumption	At 0.8 power factor, Gallons / hour for: 1 / 2 load 3 / 4 load Full Load
Generator Efficiency	At 0.8 power factor,(per cent) for: 1 / 2 load 3 / 4 load Full Load
Radiator Capacity	Coolant Type gpm coolant cfm air through radiator Btu per hr of heat exchange based on optimum coolant temperature to and from engine
Engine-Generator Set Emissions Data	
Exhaust Temperature	Degrees F at full load
Weight of Exhaust Gas	lb per hr at full load
Weight of Intake Air	lb per hr at full load
Total Heat Rejected	Btu per hr, at full load to: Jacket Coolant System Fuel Oil Cooling System

ENGINE-GENERATOR PARAMETER SCHEDULE	
Emissions	lb per hr, at full load Total Suspended Particulate Particulate Matter with an average aerodynamic diameter of 10 microns Sulfur Dioxides Nitrogen Oxides (as NO2) Carbon Monoxide Volatile Organic Compounds
Visible Emissions	Percent opacity at full load

Brake Mean Effective Pressure (BMEP) Calculations

Calculation must verify that the engine meets the specified maximum BMEP, as follows:

$$\text{BMEP psi} = \frac{(120{,}000 \times \text{bkW}) \times (792{,}000 \times \text{bhp})}{(\text{rpm} \times \text{cu. in.})}$$

Where:

bkW bhp = bkW' + bkW" bhp' + bhp"
bkW" bhp" is the Brake kW horsepower required by engine driven fan for cooling radiator or motor driven fan for cooling radiator.
bkW' bhp' = kW/GEN.EFF. kW/(GEN.EFF. times 0.746)
GEN.EFF. = Generator efficiency
cu. in. = Total engine piston displacement in cubic inches
rpm = Engine revolutions per minute
kW = Minimum power rating

Torsional Vibration Stress Analysis Computations

ENGINE-GENERATOR PARAMETER SCHEDULE
Torsional vibrational stresses in the crankshaft and generator shaft of assembled engine and driven generator must not exceed 5000 psi when engine is driving generator at rated speed while assembled unit is loaded to rated engine-generator set power. Computations must be based on a mathematical model of the assembled generator set provided or based on calculations using measured values from tests on a unit identical to the one provided. Calculations based on models of, or measured data from, the unassembled engine and generator will not be acceptable. Calculations must include: a. A description of the system relating information pertinent to analysis such as operating speed range and identification plate data. b. A mass elastic assembly drawing, showing the arrangement of the units in the generator set and dimensions of shafting, including minimum diameters (or section moduli) of shafting in the system. c. A labeled line diagram of the mass elastic system indicating values of masses, stiffness, equivalent lengths, and equivalent diameters including basic assumptions and definition of terms. d. Sample computations showing procedures used to obtain resulting stress values. e. Computations indicating assembled engine-generator speed of 1800 rpm with assembly loaded to rated generator power and the resulting computed critical torsional stress values in the assembled engine crankshaft and generator shaft.
Turbocharger Load Calculations
NOTE: When the engine-generator set installation includes field installed exhaust system (i.e., the engine-generator set is installed internal to a building in lieu of in a self-contained outdoor enclosure), include the following paragraph. When the proposed exhaust system layout is different from that shown on the contract drawings, submit calculations showing that the external loads from the exhaust system such as weight and thermal expansion do not exceed the engine manufacturer's maximum allowed forces and moments on the turbocharger.

2.1.2 Rated Output Capacity

Provide each engine-generator-set with power equal to the sum of service load plus the machine's efficiency loss and associated ancillary equipment loads. Rated output capacity must also consider engine and/or generator oversizing required to meet requirements in paragraph Engine-Generator Parameter Schedule.

The engine must meet the specified maximum BMEP requirements at rated

speed as calculated in accordance with the calculations in the engine-generator parameter schedule. The engine capacity must be based on the following:

a. Engine burning diesel fuel conforming to MIL-DTL-16884 at an ambient temperature of 85 degrees F. For stationary engines operated in the United States, diesel fuel requirements are found in 40 CFR 60 Subpart IIII.

b. Engine cooled by a radiator fan mechanically driven by the engine or remote with a motor driven fan.

c. Engine cooled by coolant mixture of water and ethylene glycol, 50 percent by volume of each.

Maximum BMEP, psi			
	Naturally Aspirated	Turbocharged	Turbocharged and Intercooled
Four-cycle engines			
Engine speed, rpm:	1800		

2.1.2.1 Engine Emission Limits

Engine must be certified by the manufacturer to meet applicable EPA emission standards found in 40 CFR 60 Subpart IIII. In addition, engine must meet any applicable state or local emission requirements (ex: California SCAQMD).

2.1.2.2 Performance Class

The voltage and frequency behavior of the generator set must be in accordance with ISO 8528 operating limit values for performance Class G1.

2.1.3 Power Ratings

Power ratings must be in accordance with EGSA 101P.

2.1.4 Transient Response

The engine-generator set governor and voltage regulator must cause the engine-generator set to respond to the maximum step load changes such that output voltage and frequency recover to and stabilize within the operational bandwidth within the transient recovery time. The engine-generator set must respond to maximum step load changes such that the maximum voltage and frequency deviations from bandwidth are not exceeded.

2.1.5 Reliability and Durability

Provide prime engine-generator sets that have both an engine and a generator capable of delivering the specified power on a prime basis with an anticipated mean time between overhauls of not less than 10,000 hours operating with a 70 percent load factor. Cite two like engines and two like generators that have performed satisfactorily in a stationary power plant, independent from the physical location of the manufacturer's and assembler's facilities. The engine and generators should have been in

operation for a minimum of 8000 actual hours at a minimum load of 70 percent of the rated output capacity. During two consecutive years of service, the units should not have experienced any failure resulting in a downtime in excess of 72 hours. Provide engines that are the same model, speed, bore, stroke, number and configuration of cylinders and rated output capacity. Provide generators that are the same model, speed, pitch, cooling, exciter, voltage regulator and rated output capacity.

Submit a reliability and durability certification letter from the manufacturer and assembler to prove that existing facilities are and have been successfully utilizing the same components proposed to meet this specification, in similar service. Certification may be based on components, i.e. engines used with different models of generators and generators used with different engines, and does not exclude annual technological improvements made by a manufacturer in the basic standard-model component on which experience was obtained, provided parts interchangeability has not been substantially affected and the current standard model meets the performance requirements specified. Provide a list with the name of the installations, completion dates, and name and telephone number of a point of contact.

2.1.6 Engine-Generator Set Enclosure

Provide engine-generator set enclosures that are corrosion resistant and fully weather resistant. The enclosure must contain all set components and provide ventilation to permit operation at Service Load under secured conditions. Provide access doors to controls and equipment requiring periodic maintenance or adjustment. Provide removable panels for access to components requiring periodic replacement. The enclosure must be capable of being removed without disassembly of the engine-generator set or removal of components other than the exhaust system. The enclosure must reduce the noise of the generator set to within the limits specified in the paragraph SOUND LIMITATIONS.

2.1.7 Vibration Isolation

Provide an engine-generator set with a vibration isolation system in accordance with the manufacturer's standard recommendation. Submit vibration isolation system performance data for the range of frequencies generated by the engine-generator set during operation from no load to full load and the maximum vibration transmitted to the floor plus description of seismic qualification of the engine-generator mounting, base, and vibration isolation. Submit torsional analysis including prototype testing or and calculations which certify and demonstrate that no damaging or dangerous torsional vibrations will occur when the prime mover is connected to the generator, at synchronous speeds, plus 10 percent. Design and qualify vibration isolation systems as an integral part of the base and mounting system in accordance with the seismic parameters specified. Where the vibration isolation system does not secure the base to the structure floor or unit foundation, provide seismic restraints in accordance with the seismic parameters specified.

2.1.8 Harmonic Requirements

Non-linear loads to be served by each engine-generator set are as indicated. The maximum linear load demand (kVA at PF) when non-linear loads will also be in use is as indicated.

2.1.9 Starting Time Requirements

Upon receipt of a signal to start, each engine generator set will start, reach rated frequency and voltage and be ready to assume load within the time specified. For standby sets used in emergency power applications, each engine generator set will start, reach rated frequency and voltage, and power will be supplied to the load terminals of the automatic transfer switch within the starting time specified.

2.2 NAMEPLATES

Provide the manufacturer's name, type or style, model or serial number and rating on a plate secured to the equipment for each major component of this specification. Provide plates and tags sized so that inscription is readily legible to operating or maintenance personnel and securely mounted to or attached in proximity of their identified controls or equipment. Lettering must be normal block lettering, a minimum of 0.25 inch high. As a minimum, provide nameplates for:

Engines	Relays
Generators	Transformers (CT & PT)
Regulators	Day tanks
Pumps and pump motors	Governors
Generator Breaker	Air Starting System
Economizers	Heat exchangers (other than base mounted)

Where the following equipment is not provided as a standard component by the engine generator set manufacturer, the nameplate information may be provided in the maintenance manual in lieu of nameplates.

Battery charger	Heaters
Switchboards	Exhaust mufflers
Switchgear	Silencers
Battery	Exciters

2.2.1 Materials

Construct ID plates and tags of 16 gage minimum thickness bronze or stainless steel sheet metal engraved or stamped with inscription. Construct plates and tags not exposed to the weather or high operational temperature of the engine of laminated plastic, 0.125 inch thick, matte white finish with black center core, with lettering accurately aligned and engraved into the core.

2.2.2 Control Devices and Operation Indicators

Provide ID plates or tags for control devices and operation indicators, including valves, off-on switches, visual alarm annunciators, gages and

thermometers, that are required for operation and maintenance of provided mechanical systems. Plates or tags must be minimum of 0.5 inch high and 2 inches long and must indicate component system and component function.

2.2.3 Equipment

Provide ID plates of a minimum size of high and 5 inches long on provided equipment indicating the following information:

a. Manufacturer's name, address, type and model number, serial number, and certificate of compliance with applicable EPA mission standards;

b. Contract number and accepted date;

c. Capacity or size;

d. System in which installed; and

e. System which it controls.

2.3 SAFETY DEVICES

Exposed moving parts, parts that produce high operating temperatures, parts which may be electrically energized, and parts that may be a hazard to operating personnel must be insulated, fully enclosed, guarded, or fitted with other types of safety devices. Install safety devices such that proper operation of the equipment is not impaired.

2.4 MATERIALS AND EQUIPMENT

Submit certification stating that where materials or equipment are specified to comply with requirements of UL, written proof of such compliance has been obtained. The label or listing of the specified agency, or a written certificate from an approved, nationally recognized testing organization equipped to perform such services, stating that the items have been tested and conform to the requirements and testing methods of the specified agency are acceptable as proof.

2.4.1 Circuit Breakers, Low Voltage

UL 489.

2.4.2 Filter Elements

Provide the manufacturer's standard fuel-oil, lubricating-oil, and combustion-air filter elements.

2.4.3 Instrument Transformers

NEMA/ANSI C12.11.

2.4.4 Revenue Metering

IEEE C57.13.

2.4.5 Pipe (Fuel/Lube-Oil, Compressed Air, Coolant, and Exhaust)

ASTM A53/A53M, or ASTM A106/A106M steel pipe. Pipe smaller than 2 inches must be Schedule 80. Pipe 2 inches and larger must be Schedule 40.

2.4.5.1 Flanges and Flanged Fittings

ASTM A181/A181M, Class 60, or ASME B16.5, Grade 1, Class 150.

2.4.5.2 Pipe Welding Fittings

ASTM A234/A234M, Grade WPB or WPC, Class 150 or ASME B16.11, 3000 lb.

2.4.5.3 Threaded Fittings

ASME B16.3, Class 150.

2.4.5.4 Valves

MSS SP-80, Class 150.

2.4.5.5 Gaskets

Manufacturer's standard.

2.4.6 Pipe Hangers

MSS SP-58.

2.4.7 Electrical Enclosures

NEMA ICS 6.

2.4.7.1 Switchboards

NEMA PB 2.

2.4.7.2 Panelboards

NEMA PB 1.

2.4.8 Electric Motors

Provide electric motors that conform to the requirements of NEMA MG 1. Motors must have sealed ball bearings and a maximum speed of 1800 rpm. Motors used indoors must have drip-proof frames; enclose those that are used outside. Alternating current motors larger than 1/2 Hp must be of the squirrel-cage induction type for operation on 208 volts or higher, 60 Hz, and three-phase power. Alternating current motors 1/2 Hp or smaller, must be suitable for operation on 120 volts, 60 Hz, and single-phase power. Direct current motors must be suitable for operation on 125 volts.

2.4.9 Motor Controllers

Provide motor controllers and starters that conform to the requirements of NFPA 70 and NEMA ICS 2.

2.5 ENGINE

Each engine must operate on No. 2-D diesel fuel conforming to ASTM D975, must be designed for stationary applications and must be complete with ancillaries. The engine must be a standard production model shown in the manufacturer's catalog describing and depicting each engine-generator set

and all ancillary equipment in sufficient detail to demonstrate complete specification compliance. The engine must be naturally aspirated, supercharged, or turbocharged. The engine must be 2- or 4-stroke-cycle and compression-ignition type. The engine must be vertical in-line, V- or opposed-piston type, with a solid cast block or individually cast cylinders. The engine must have a minimum of two cylinders. Opposed-piston type engines must have more than four cylinders. Each block must have a coolant drain port. Equip each engine with an over-speed sensor.

ISO 3046. Diesel engines must be four-cycle naturally aspirated, or turbocharged, or turbocharged and intercooled; vertical in-line or vertical Vee type; designed for stationary service. Engines must be capable of immediate acceleration from rest to normal speed without intermediate idle/warm up period or pre-lubrication to provide essential electrical power. Two-cycle engines are not acceptable.

2.5.1 Sub-base Mounting

Mount each engine-generator set on a structural steel sub-base sized to support the engine, generator, and necessary accessories, auxiliaries and control equipment to produce a complete self-contained unit as standard with the manufacturer. Design the structural sub-base to properly support the equipment and maintain proper alignment of the engine-generator set in the specified seismic zone. In addition, provide sub-base with both lifting rings and jacking pads properly located to facilitate shipping and installation of the unit. Factory align engine and generator on the sub-base and securely bolt into place in accordance with the manufacturer's standard practice. Crankshaft must have rigid coupling for connection to the generator.

2.5.2 Assembly

Completely shop assemble each engine-generator set on its structural steel sub-base. Paint entire unit with manufacturer's standard paints and colors. After factory tests and before shipping, thoroughly clean and retouch painting as necessary to provide complete protection.

2.5.3 Turbocharger

If required by the manufacturer to meet the engine-generator set rating, provide turbine type driven by exhaust gas from engine cylinders, and direct connected to the blower supplying air to the engine intake manifold.

2.5.4 Crankcase Protection

2.5.5 Miscellaneous Engine Accessories

Provide the following engine accessories where the manufacturer's standard design permits:

a. Piping on engine to inlet and outlet connections, including nonstandard companion flanges.

b. Structural steel sub-base and vibration isolators, foundation bolts, nuts, and pipe sleeves.

c. Level jack screws or shims, as required.

d. Rails, chocks, and shims for installation of sub-base on the foundation.

e. Removable guard, around fan. Support guard, on engine sub-base, to suit manufacturer's standard.

2.6 FUEL SYSTEM

Provide fuel system conforming to the requirements of NFPA 30 and NFPA 37 and containing the following elements.

2.6.1 Pumps

Fuel transfer pumps may be mounted on the day tank. Pumps must be duplex, horizontal, positive displacement. Direct-connect pump to motor through a flexible coupling. Equip each pump with a bypass relief valve, if not provided with an internal relief valve. Provide motor and controller in accordance with the paragraphs ELECTRIC MOTORS and MOTOR CONTROLLERS, respectively.

2.6.1.1 Main Pump

Provide engines with an engine driven pump. The pump must supply fuel at a minimum rate sufficient to provide the amount of fuel required to meet the performance indicated within the parameter schedule. Base the fuel flow rate on meeting the load requirements and all necessary recirculation.

2.6.1.2 Auxiliary Fuel Pump

Provide auxiliary fuel pumps to maintain the required engine fuel pressure, if either required by the installation or indicated on the drawings. The auxiliary pump must be driven by a dc electric motor powered by the starting/station batteries. Automatically actuate the auxiliary pump by a pressure-detecting device.

2.6.2 Fuel Filter

Provide a minimum of one full-flow fuel filter for each engine. The filter must be readily accessible and capable of being changed without disconnecting the piping or disturbing other components. Mark the inlet and outlet connections of the filter.

Provide intake filter assemblies for each engine of the oil bath or dry type, as standard with the manufacturer. Filters must be capable of removing a minimum of 92 percent of dirt and abrasive 3 microns and larger from intake air. Size filters to suit engine requirements at 100 percent of rated full load. Design unit for field access for maintenance purposes.

2.6.3 Relief/Bypass Valve

Provide a relief/bypass valve to regulate pressure in the fuel supply line, return excess fuel to a return line and prevent the build-up of excessive pressure in the fuel system.

2.6.4 Integral Main Fuel Storage Tank

Provide each engine with an integral main fuel tank. Each tank must be factory installed and provided as an integral part of the generator manufacturer's product. Provide each tank with connections for fuel

supply line, fuel return line, local fuel fill port, gauge, vent line, and float switch assembly. Provide a fuel return line cooler as recommended by the manufacturer and assembler. The temperature of the fuel returning to the tank must be below the flash point of the fuel. Mount the tank within the enclosure for each engine-generator set provided with weatherproof enclosures. The fuel fill line must be accessible without opening the enclosure.

a. All Tanks: UL 142. Provide integral in skid double wall (110 percent containment) fuel tanks with a capacity as indicated. Epoxy coat day tanks inside and prime and paint outside. Construct tanks of not less than 3/16 inch steel plate with welded joints and necessary stiffeners on exterior of tank. Provide a braced structural steel framework support. Weld tank top tight. Provide 4 1/2 inch square inspection port with a 2 inch NPT fill connection and spill box. Provide proper normal and emergency venting for the primary tank and emergency venting only for the secondary tank / containment basin in accordance with UL 142 requirements.

b. Float Switches for Day Tanks: Provide tank-top mounted or external float cage, single-pole, single-throw type designed for use on fuel oil tanks. Arrange high level float switches to close on rise of liquid level, and low level float switches to close on fall of liquid level. Mount float cage units with isolating and drain valves. Contacts must be suitable for the station battery voltage.

(1) Critical low level float switch which must activate at 5 percent of normal liquid level must shut engine off.

(2) Low-low level float switch which must activate alarm at 30 percent of normal liquid level.

(3) Low level float switch which must open the fuel oil solenoid valve and start the fuel transfer pump at 75 percent of normal liquid level.

(4) High level float switch which must close the fuel oil solenoid valve and stop the fuel transfer pump at 90 percent of normal liquid level.

(5) Critical high level float switch which must activate alarm at 95 percent of normal liquid level.

c. Leak Detector Switch for All Tanks: Actuates when fuel is detected in containment basin, stops fuel transfer pump, and closes the fuel oil solenoid valve.

d. Control Panel for All Tanks: Provide NEMA ICS 6, Type 1 , enclosed control panel for each day tank. Control panel must include the following accessories.

(1) Power available LED (green).

(2) Critical low fuel alarm contacts for shut down of engine.

(3) Low-low level fuel alarm LED.

(4) Low-low level fuel alarm contracts for remote annunciator.

(5) Critical high level fuel alarm LED.

(6) Leak detecting alarm LED.

(7) Alarm horn.

e. Tank Gages for All Tanks: Provide buoyant force type gages for fuel tanks with dial indicator not less than 4 inches in size and arranged for top mounting. Calibrate each reading dial or scale for its specific tank to read from empty to full, with intermediate points of 1/4, 1/2, and 3/4.

f. Integral Base Tanks Used as Primary Tank: Provide a 2 inch opening at the tank fill port, fitted an overfill prevention valve (OPV). Additionally, the fill opening must be perpendicular to the tank in order to allow operation of the OPV. Integral base tank must be sized and configured such that the filling and venting nozzles are outside the generator cabinet for ease of accessibility, inspection, and maintenance. Level gage must be in the line of sight from the fill port.

g. Integral Base Tanks Located Inside Buildings. The tank vents must discharge outside the building in accordance with NFPA 30 and NFPA 37. The fill pipe must terminate outside the building. The fill pipe connection point must be housed in a sealed spill box. High level alarms or level gauges used as overfill protection mechanisms must annunciate at the fill connection point. Provide an overfill prevention valve (OPV) at the tank with a check valve mounted on the fill line in the spill box. The fill connection point must be labeled with tank contents and capacity.

2.6.4.1 Fuel Transfer Pumps

Fuel transfer pumps may be mounted on the day tank. Pumps must be duplex, horizontal, positive displacement. Direct-connect pump to motor through a flexible coupling. Equip each pump with a bypass relief valve, if not provided with an internal relief valve. Provide motor and controller in accordance with the paragraphs ELECTRIC MOTORS and MOTOR CONTROLLERS, respectively.

2.6.4.2 Capacity

Each tank must have capacity as shown at 100 percent rated load without being refilled.

2.6.4.3 Local Fuel Fill

Each local fuel fill port on the day tank must have a screw-on cap.

2.6.4.4 Fuel Level Controls

Provide tanks with a float-switch assembly to perform the following functions:

a. Activate the "Low Fuel Level" alarm at 70 percent of the rated tank capacity.

b. Activate the "Overfill Fuel Level" alarm at 95 percent of the rated

tank capacity.

2.6.4.5 Arrangement

Integral tanks may allow gravity flow into the engine. Gravity flow tanks and any tank that allows a fuel level above the fuel injectors must have an internal or external factory installed valve located as near as possible to the shell of the tank. The valve must close when the engine is not operating. Provide integral day tanks with any necessary pumps to supply fuel to the engine as recommended by the generator set manufacturer. The fuel supply line from the tank to the manufacturer's standard engine connection must be welded pipe.

2.7 LUBRICATION

Provide engine with a separate lube-oil system conforming to NFPA 30 and NFPA 37. Pressurize each system by engine-driven pumps. Regulate system pressure as recommended by the engine manufacturer. Provide a pressure relief valve on the crankcase for closed systems. Vent the crankcase in accordance with the manufacturer's recommendation. Do not vent the crankcase to the engine exhaust system. Crankcase breathers, if provided on engines installed in buildings or enclosures, must be piped to vent to the outside. The system must be readily accessible for service such as draining, refilling, etc. Each system must permit addition of oil and have oil-level indication with the set operating. The system must utilize an oil cooler as recommended by the engine manufacturer.

2.7.1 Lube-Oil Filter

Provide one full-flow filter for each pump. The filter must be readily accessible and capable of being changed without disconnecting the piping or disturbing other components. Mark inlet and outlet connections.

2.7.2 Lube-Oil Sensors

Equip each engine with lube-oil pressure sensors located downstream of the filters and provide signals for required indication and alarms. Submit two complete sets of filters, required for maintenance, supplied in a suitable storage box. Provide these filters in addition to filters replaced after testing.

2.7.3 Precirculation Pump

Provide a motor-driven precirculation pump powered by the station battery, complete with motor starter, if recommended by the engine manufacturer.

2.8 SOUND LIMITATIONS

Submit sound power level data for the packaged unit operating at 100 percent load in a free field environment. The data should demonstrate compliance with the sound limitation requirements of this specification. Submit certification from the manufacturer stating that the sound emissions meet the specification. Do not exceed the following sound pressure levels in any of the indicated frequencies when measured in a free field at a radial distance of 22.9 feet 7 meters at 45 degrees apart in all directions when operating at 100 percent load.

Frequency Band (Hz)	Maximum Acceptable Sound Level (Decibels)
31	
63	
125	
250	
500	
1,000	
2,000	
4,000	
8,000	

2.9 AIR INTAKE EQUIPMENT

Locate filters and silencers in locations that are convenient for servicing. Provide high-frequency filter type silencers and locate in the air intake system as recommended by the engine manufacturer. Provide silencer to reduce the noise level at the air intake so that the indicated pressure levels specified in paragraph SOUND LIMITATIONS will not be exceeded. A combined filter-silencer unit meeting requirements for the separate filter and silencer items may be provided. Provide copper expansion elements in air-intake lines.

Provide intake filter assemblies for each engine of the oil bath or dry type, as standard with the manufacturer. Filters must be capable of removing a minimum of 92 percent of dirt and abrasive 3 microns and larger from intake air. Size filters to suit engine requirements at 100 percent of rated full load. Design unit for field access for maintenance purposes.

2.10 EXHAUST SYSTEM

Provide a separate and complete system for each engine. Support piping to minimize vibration. Where a V-type engine is provided, use a V-type connector, with necessary flexible sections and hardware, to connect the engine exhaust outlets.

2.10.1 Flexible Sections and Expansion Joints

Provide a flexible section at each engine and an expansion joint at each muffler. Provide flexible sections and expansion joints that have flanged connections. Provide flexible sections made of convoluted seamless tube without joints or packing. Provide bellows type expansion joints. Provide stainless steel expansion and flexible elements suitable for engine exhaust gas at the maximum exhaust temperature that is specified by the engine manufacturer. Provide expansion and flexible elements that are capable of absorbing vibration from the engine and compensation for thermal expansion and contraction.

2.10.2 Exhaust Muffler

Provide a chamber type exhaust muffler. Provide welded steel muffler designed for outside mounting. Provide eyebolts, lugs, flanges, or other items as necessary for support in the location and position indicated. Do not exceed the engine manufacturer's recommended pressure drop. Outside mufflers must be zinc coated or painted with high temperature 400 degrees F resisting paint. The muffler and exhaust piping together must reduce the noise level to less than the maximum acceptable level listed for sound limitations in paragraph SOUND LIMITATIONS. Provide muffler with a drain valve, nipple, and cap at the low-point of the muffler.

A residential class silencer must be provided for each engine which will reduce the exhaust sound spectrum by the following listed values at a 75 foot radius from the outlet, with generator set loaded to rated capacity and clear weather. Inlet and outlet connections must be flanged.

Octave Band Center Frequency (Hertz)								
Minimum Silencer Attenuation Decibels	63	125	250	500	1000	2000	4000	8000
Critical Class	15	32	37	36	30	36	37	37

2.10.3 Exhaust Piping

Slope horizontal sections of exhaust piping downward away from the engine to a drip leg for collection of condensate with drain valve and cap. Changes in direction must be long radius. Insulate exhaust piping, mufflers and silencers installed inside any building in accordance with paragraph THERMAL INSULATION and covered to protect personnel. Provide vertical exhaust piping with a hinged, gravity-operated, self-closing, rain cover.

Field installed exhaust piping must conform to the following:

a. Exhaust Piping: Provide flanges for connections to engines, exhaust mufflers, and flexible connections. Provide steel pipe conforming to ASTM A53/A53M for each engine complete with necessary fittings, flanges, gaskets, bolts, and nuts. Exhaust piping must be Schedule 40 pipe for 12 inches and smaller, standard weight for sizes 14 inches through 24 inches, and 0.25 inch wall thickness for sizes larger than 24 inches. Flanges must be Class 150 slip-on forged steel welding flanges in accordance with ASME B16.5, with material in accordance with ASTM A181/A181M, Grade I. Fittings must be butt welding conforming to ASTM A234/A234M, with wall thickness same as adjoining piping. Fittings must be of same material and wall thickness as pipe. Built-up miter welded fittings may be used. Miter angles of each individual section must not exceed 22.5 degrees total and not more than 11.25 degrees relative to the axis of the pipe at any one cut. Gaskets for exhaust piping must be of high temperature asbestos-free material suitable for the service and must be ASME B16.21, composition ring, 0.0625 inch thick. Bolting material for exhaust flanges must be alloy-steel bolt-studs conforming to ASTM A193/A193M, Grade B7 bolts and alloy-steel nuts conforming to ASTM A194/A194M, Grade 7. Bolts must be of sufficient length to obtain full bearing on

the nuts and must project not more than two full threads beyond the nut. Provide stainless steel counterbalance type rain caps at termination of each exhaust pipe.

b. Expansion (Flexible) Joints: Provide sections of multiple corrugated stainless steel expansion joints in the engine exhaust piping for each engine to absorb expansion strains and vibration transmitted to the piping. Flexible joints must be suitable for operation at 200 degrees F above normal exhaust gas temperature at 100 percent load, 10,000 cycles, minimum. Joints must be flanged and located between engine exhaust manifold and exhaust piping, must be the same size as exhaust piping size, and must be designed and constructed for engine exhaust service.

c. Hangers and Supports: MSS SP-58.

d. Piping Sleeves: Provide where piping passes through masonry or concrete walls, floors, roofs, and partitions. Sleeves must be placed during construction. Unless indicated otherwise, pipe sleeves must comply with following requirements: sleeves in outside walls below and above grade, in floor, or in roof slabs, must be standard weight zinc coated steel pipe. Sleeves in partitions must be zinc coated sheet steel having a nominal weight of not less than 0.90 pound per square foot. Space between piping insulation and the sleeve must not be less than 0.25 inch. Sleeves must be held securely in proper position and location during construction. Sleeves must be sufficient length to pass through entire thickness of walls, partitions, or slabs. Sleeves in floor slabs must extend 2 inches above the finished floor. Space between the pipe and the sleeve must be firmly packed with insulation and caulked at both ends of the sleeve with plastic waterproof cement.

e. Piping Insulation: Provide exhaust piping insulation in accordance with Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.11 PYROMETER

Provide a pyrometer, with calibrated leads to show the temperature . For a supercharged engine, provide additional points, thermocouples and leads to show the temperature in the turbocharger exhaust gas outlet and combustion air discharge passages. Graduated scale length less than 6 inches is not acceptable. Provide double pole selector switch with an "off" position, one set of points for each thermocouple, and suitable indicating dial. Calibrate the pyrometer, thermocouples, leads and compensating devices to show true exhaust temperature within plus or minus 1 percent above the highest temperature encountered at 110 percent load conditions.

2.12 EMISSIONS

The finished installation must comply with Federal, state, and local regulations and restrictions regarding the limits of emissions, as listed here: . Submit certification from the engine manufacturer stating that the engine exhaust emissions meet the federal, state, and local regulations and restrictions specified. At a minimum this certification must include emission factors for criteria pollutants including nitrogen oxides, carbon monoxide, particulate matter, sulfur dioxide, non-methane hydrocarbon, and for hazardous air pollutants (HAPs).

2.13 STARTING SYSTEM

Provide starting system for engine generator sets used in non-emergency applications as follows.

2.13.1 Controls

Provide an engine control switch with functions including: run/start (manual), off/reset, and, automatic mode. Provide start-stop logic for adjustable cycle cranking and cool-down operation. Arrange the logic for fully automatic starting in accordance with paragraph AUTOMATIC ENGINE-GENERATOR-SET SYSTEM OPERATION. Provide electrical starting systems with an adjustable cranking limit device to limit cranking periods from 1 second up to the maximum duration.

2.13.2 Capacity

Provide starting system with sufficient capacity, at the maximum outdoor summer temperature specified to crank the engine without damage or overheating. The system must provide a minimum of three cranking periods with 15 second intervals between cranks. Each cranking period must have a maximum duration of 15 seconds. Starting must be accomplished using an adequately sized dc starter system with a positive shift solenoid to engage the starter motor and to crank the engine continuously for 60 seconds without overheating.

2.13.3 Electrical Starting

Manufacturers recommended dc system, utilizing a negative circuit ground. Starting motors must be in accordance with SAE ARP892.

2.13.3.1 Battery

Provide a starting battery system including the battery, battery rack, intercell connectors, spacers, automatic battery charger with overcurrent protection, metering and relaying. Provide battery in accordance with SAE J537. Size critical system components (rack, protection, etc.) to withstand the seismic acceleration forces specified. Provide nickel-cadmium battery with sufficient capacity, at the minimum outdoor and maximum outdoor temperature specified, to provide the specified cranking periods. Valve-regulated lead-acid batteries are not acceptable.

Provide maintenance free, sealed, lead-acid, SAE Type D engine starting batteries. Batteries must have sufficient capacity to provide 60 seconds of continuous cranking of the engine in an ambient temperature of degrees F.

2.13.3.2 Battery Charger

Provide a current-limiting battery charger, conforming to UL 1236, that automatically recharges the batteries. Submit battery charger sizing calculations. The charger must be capable of an equalize charging rate for recharging fully depleted batteries within 24 hours and a floating charge rate for maintaining the batteries at fully charged condition. Provide an ammeter to indicate charging rate. Provide a voltmeter to indicate charging voltage. Provide a timer for the equalize charging-rate setting. A battery is considered to be fully depleted when the output voltage falls to a value which will not operate the engine generator set and its components.

Provide 120 volt ac, enclosed, automatic equalizing, dual-rate, solid-state, constant voltage type battery charger with automatic ac line compensation. DC output must be voltage regulated and current limited. Charger must have two ranges, float and equalize, and must provide continuous taper charging. The charger must have a continuous output rating of not less than 10 amperes and must be sized to recharge the engine starting batteries in a minimum of 8 hours while providing the control power needs of the engine-generator set. Enclosure must be NEMA ICS 6, Type 3R. The following accessories must be included:

a. DC ammeter

b. DC voltmeter

c. Equalize light

d. AC on light

e. Low voltage light

f. High voltage light

g. Equalize test button/switch

h. AC circuit breaker

i. Low dc voltage alarm relay

j. High dc voltage alarm relay

k. Current failure relay

l. AC power failure relay

2.13.4 Storage Batteries

Provide storage batteries of suitable rating and capacity to supply and maintain power for the remote alarm annunciator for a period of 90 minutes minimum without the voltage applied falling below 87.5 percent of normal. Provide a 120 volt ac automatic battery charger.

2.13.5 Starting Aids

Provide one or more of other following methods to assist engine starting.

2.13.5.1 Glow Plugs

Design glow plugs to provide sufficient heat for combustion of fuel within the cylinders to guarantee starting at an ambient temperature of -25 degrees F.

2.13.5.2 Jacket-Coolant Heaters

Mount a thermostatically controlled electric heater in the engine coolant jacketing to automatically maintain the coolant within plus or minus 3 degrees F of the control temperature. The heater must operate independently of engine operation so that starting times are minimized. Power for the heaters must be 120/208 volts ac. Include necessary

equipment, piping, controls, wiring, and accessories.

2.13.5.2.1 Prime Rated Sets

The control temperature must be the higher of the manufacturer's recommended temperature or the minimum coolant inlet temperature of the engine recommended in paragraph SUBMITTALS.

2.13.5.2.2 Standby Rated Sets

The control temperature must be the temperature recommended by the engine manufacturer to meet the starting time specified at the minimum winter outdoor temperature.

2.13.5.3 Lubricating-Oil Heaters

Mount a thermostatically controlled electric heater in the engine lubricating-oil system to automatically maintain the oil temperature within plus or minus 3 degrees F of the control temperature. The heater must operate independently of engine operation so that starting times are minimized. Power for the heaters must be 120/208 volts ac.

2.13.6 Exerciser

Provide exerciser in accordance with Section 26 36 23 AUTOMATIC TRANSFER SWITCH AND BY-PASS/ISOLATION SWITCH.

2.14 GOVERNOR

Provide a forward acting type engine speed governor system. Steady-state frequency band and frequency regulation (droop) must be in accordance with the operating limit values of the performance class specified in the paragraph PERFORMANCE CLASS.

Provide engine with a governor which maintains the frequency within a bandwidth of the rated frequency, over a steady-state load range of zero to 100 percent of rated output capacity. Configure the governor for safe manual adjustment of the speed/frequency during operation of the engine-generator set, without special tools, from 90 to 110 percent of the rated speed/frequency, over a steady state load range of 0 to 100 percent or rated capacity. Submit two complete sets of special tools required for maintenance (except for electronic governor handset). Special tools are those that only the manufacturer provides, for special purposes, or to reach otherwise inaccessible parts. Provide a suitable tool box for tools. Provide one handset for each electronic governor when required to indicate and/or change governor response settings.

2.15 GENERATOR

Provide synchronous type, one or two bearing, generator conforming to the performance criteria in NEMA MG 1, equipped with winding terminal housings in accordance with NEMA MG 1, equipped with an amortisseur winding, and directly connected to the engine. Submit calculations of the engine and generator output power capability, including efficiency and parasitic load data. Provide Class H Class F insulation.

a. Select NEMA MG 1, Part 16, standby duty, and temperature rise of 130 degrees C for engine-generator sets which are expected to operate for less than 300 hours per year. Select NEMA MG 1, Part 22, continuous

duty, and temperature rise of 105 degrees C for engine-generator sets expected to operate 300 hours or greater per year or rated 300 kW and above.

b. Select 2/3 pitch design option for engine-generator sets rated 300 kW and above.

c. Select 10-12 lead re-connectable for engine-generator sets rated 300 kW to 800 kW.

d. For applications requiring high SCR loading or in harsh environments laden with salts and chemicals, select vacuum pressure impregnation (VPI) insulated coils. When engine-generator sets are rated 800 kW and larger, also select form wound coils.

e. Provide salient-pole type, ac, brushless-excited, revolving field, air-cooled, self-ventilated, coupled type, synchronous generator conforming to NEMA MG 1, Part 16 , and IEEE C50.12. Generator must be rated for standby duty at 100 percent of the power rating of the engine-generator set as specified in paragraph ENGINE-GENERATOR SET RATINGS AND PERFORMANCE. Temperature rise of each of the various parts of the generator must not exceed 130 degrees C as measured by resistance, based on a maximum ambient temperature of 40 degrees C. Winding insulation must be Class H.

f. Stator: Stator windings must be 2/3 pitch design .

g. Rotor: The rotor must have connected amortisseur windings.

h. Generator Space Heater: Provide 120 volt ac heaters. Heater capacity must be as recommended by the generator manufacturer to aid in keeping the generator insulation dry.

i. Grounding: Provide non-corrosive steel grounding pads located at two opposite mounting legs.

j. Filters: Provide manufacturer's standard generator cooling air filter assembly.

k. Design generator to protect against mechanical, electrical and thermal damage due to vibration, 25 percent overspeeds, or voltages and temperatures at a rated output capacity of 110 percent for prime applications and 100 percent for standby applications.

l. Provide generator ancillary equipment meeting the short circuit requirements of NEMA MG 1. Select drip-proof guarded option for generators without weatherproof enclosures.

m. Submit manufacturer's standard data for each generator (prototype data at the specified rating or above is acceptable), listing the following information:

(1) Direct-Axis sub-transient reactance (per unit).

(2) The generator kW rating and short circuit current capacity (both symmetric and asymmetric).

2.15.1 Current Balance

At 100 percent rated output capacity, and load impedance equal for each of the 3 phases, the permissible current difference between any 2 phases must not exceed 2 percent of the largest current on either of the 2 phases. Submit certification stating that the flywheel has been statically and dynamically balanced and is capable of being rotated at 125 percent of rated speed without vibration or damage.

2.15.2 Voltage Balance

At any balanced load between 75 and 100 percent of rated output capacity, the difference in line-to-neutral voltage among the 3 phases must not exceed 1 percent of the average line-to-neutral voltage. For a single phase load condition, consisting of 25 percent load at unity power factor placed between any phase and neutral with no load on the other 2 phases, the maximum simultaneous difference in line-to-neutral voltage between the phases must not exceed 3 percent of rated line to neutral voltage. The single-phase load requirement must be valid utilizing normal exciter and regulator control. The interpretation of the 25 percent load for single phase load conditions means 25 percent of rated current at rated phase voltage and unity power factor.

2.15.3 Waveform

The deviation factor of the line-to-line voltage at zero load and at balanced rated output capacity must not exceed 10 percent. The RMS of all harmonics must be less than 5.0 percent and that of any one harmonic less than 3.0 percent of the fundamental at rated output capacity. Design and configure engine-generator to meet the total harmonic distortion limits of IEEE 519.

2.16 EXCITER

Provide brushless generator exciter. Provide semiconductor rectifiers that have a minimum safety factor of 300 percent for peak inverse voltage and forward current ratings for all operating conditions, including 110 percent generator output at 104 degrees F ambient. The exciter and regulator in combination must maintain generator-output voltage within the limits specified.

Provide a brushless excitation system consisting of an exciter and rotating rectifier assembly , and permanent magnet generator integral with the generator and a voltage regulator. Insulation class for parts integral with the generator must be as specified in paragraph GENERATOR. System must provide a minimum short circuit of 300 percent rated engine-generator set current for at least 10 seconds. Steady state voltage regulation must be in accordance with the operating limit values of the performance class specified in the paragraph PERFORMANCE CLASS.

a. Exciter and Rotating Rectifier Assembly: Rectifiers must be provided with surge voltage protection.

b. Permanent Magnet Generator: Provide a voltage spike suppression device for permanent magnet generator (PMG) excitation systems.

c. Voltage Regulator: Voltage regulator must be solid state or digital, automatic, three-phase sensing, volts per hertz type regulator. Regulator must receive its input power from a PMG. Voltage variation

for any 40 degree C change over the operating temperature range must be less than plus or minus 1.0 percent. Operating temperature must be minus 40 degree C to plus 70 degree C. Voltage adjust range must be plus to minus 5.0 percent of nominal. Inherent regulator features must include over excitation shutdown.

2.16.1 Electromagnetic Interference (EMI) Suppression

Provide as an integral part of the generator and excitation system, EMI suppression complying with MIL-STD-461.

2.17 VOLTAGE REGULATOR

Provide a solid-state voltage regulator, separate from the exciter, for each generator. Maintain the voltage within a bandwidth of the rated voltage, over a steady-state load range of zero to 100 percent of rated output capacity. Configure regulator for safe manual adjustment of the engine-generator voltage output without special tools, during operation, from 90 to 110 percent of the rated voltage over the steady state load range of 0 to 100 percent of rated output capacity. Regulation drift exceeding plus or minus 0.5 percent for an ambient temperature change of 68 degrees F is not acceptable. Reactive droop compensation or reactive differential compensation must load share the reactive load proportionally between sets during parallel operation. Provide voltage regulator with a maximum droop of 2 percent of rated voltage over a load range from 0 to 100 percent of rated output capacity and automatically maintain the generator output voltage within the specified operational bandwidth.

2.18 GENERATOR ISOLATION AND PROTECTION

Provide necessary devices for electrical protection and isolation of each engine-generator set and its ancillary equipment. The generator circuit breaker (IEEE Device 52) ratings must be consistent with the generator rated voltage and frequency, with continuous, short circuit withstand, and interrupting current ratings to match the generator capacity. Provide manually operated generator circuit breaker. Mount a set of surge capacitors at the generator terminals. Provide monitoring and control devices as specified in paragraph GENERATOR PANEL.

The generator circuit breaker must comply with UL 489 requirements for molded case, adjustable thermal magnetic trip type circuit breaker. The circuit breaker continuous current rating must be adequate for the power rating of the engine-generator set and the circuit breaker must be rated to withstand the short circuit current provided by the generator set. Provide circuit breaker in a NEMA ICS 6, Type 3R enclosure mounted on the engine-generator set.

2.18.1 Devices

Provide switches, circuit breakers, switchgear, fuses, relays, and other protective devices as specified in Section 26 28 01.00 10 COORDINATED POWER SYSTEM PROTECTION.

Furnish with respective pieces of equipment. Motors, controllers, contactors, and disconnects must conform to Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide electrical connections under Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide controllers and contactors with maximum of 120-volt control circuits, and auxiliary contacts for use with controls furnished. When motors and equipment furnished are larger than

size indicated, the cost of providing additional electrical service and related work must be included under this section.

2.19 SAFETY SYSTEM

Provide and install devices, wiring, remote panels, and local panels, etc., as a complete system to automatically activate the appropriate signals and initiate the appropriate actions. Provide a safety system with a self-test method to verify its operability. Provide alarm signals that have manual acknowledgment and reset devices. The alarm signal systems must reactivate for new signals after acknowledgment is given to any signal. Configure the systems so that loss of any monitoring device will be dealt with as an alarm on that system element.

2.19.1 Audible Signal

Provide audible alarm signal sound at a frequency of 70 Hz at a volume of 75 dB at 10 feet. The sound must be continuously activated upon alarm and silenced upon acknowledgment. Locate signal devices as shown.

2.19.2 Visual Signal

The visual alarm signal must be a panel light. The light must be normally off, activated to be blinking upon alarm. The light must change to continuously lit upon acknowledgement. If automatic shutdown occurs, the display must maintain activated status to indicate the cause of failure and must not be reset until cause of alarm has been cleared and/or restored to normal condition. Shutdown alarms must be red; all other alarms must be amber.

2.19.3 Alarms and Action Logic

2.19.3.1 Shutdown

Accomplish simultaneous activation of the audible signal, activation of the visual signal, stopping the engine, and opening the generator main circuit breakers.

2.19.3.2 Problem

Accomplish activation of the visual signal.

2.19.4 Safety Indications and Shutdowns

Provide a local alarm panel with the following shutdown and alarm functions in accordance with NFPA 99 NFPA 110 level 1 mounted either on or adjacent to the engine generator set.

A remote alarm panel is required for audible alarms, e.g., in the control room.

Indicator Function (at battery voltage)	NFPA 99 Level 1 CV S RA	NFPA 110 Level 1 CV S RA	NFPA 110 Level 2 CV S RA
Overcrank	X X X	X X X	X X O

Indicator Function (at battery voltage)	NFPA 99 Level 1 CV S RA	NFPA 110 Level 1 CV S RA	NFPA 110 Level 2 CV S RA
Low water temperature	X NA X	X NA X	X NA O
High engine temperature pre-alarm	X NA X	X NA X	O NA NA
High engine temperature	X X X	X X X	X X O
Low lube oil pressure pre-alarm	X NA X	NA NA NA	NA NA NA
Low lube oil pressure	X X X	X X X	X X O
Overspeed	X X X	X X X	X X O
Low fuel main tank	X NA X	X NA X	O NA O
Low coolant level	X O X	X O X	X O X
EPS supplying load	X NA NA	X NA NA	O NA NA
Control switch not in automatic position	X NA X	X NA X	X NA X
High battery voltage	X NA NA	X NA NA	O NA NA
Low cranking voltage	X NA X	X NA X	O NA NA
Low voltage in battery	X NA NA	X NA NA	O NA NA
Battery charger ac failure	X NA NA	X NA NA	O NA NA
Lamp test	X NA NA	X NA NA	X NA NA
Contacts for local and remote common alarm	X NA X	X NA X	X NA X
Audible alarm silencing switch	NA NA X	NA NA X	NA NA O
Low starting air pressure	X NA NA	X NA NA	O NA NA
Low starting hydraulic pressure	X NA NA	X NA NA	O NA NA
Air shutdown damper when used	X X X	X X X	X X O
Remote emergency stop	NA X NA	NA X NA	NA X NA

Indicator Function (at battery voltage)	NFPA 99 Level 1 CV S RA	NFPA 110 Level 1 CV S RA	NFPA 110 Level 2 CV S RA
Symbology: CV: Control panel-mounted visual. S: Shutdown of EPS indication. RA: Remote audible. Symbology: CV: Control panel-mounted visual. S: Shutdown of EPS indication. RA: Remote audible. X: Required. O: Optional. NA: Not applicable.			

2.19.5 Time-Delay on Alarms

For startup of the engine-generator set, install time-delay devices bypassing the low lubricating oil pressure alarm during cranking, and the coolant-fluid outlet temperature alarm. Submit the magnitude of monitored values which define alarm or action set points, and the tolerance (plus and/or minus) at which the devices activate the alarm or action for items contained within the alarm panels. The lube-oil time-delay device must return its alarm to normal status after the engine starts. The coolant time-delay device must return its alarm to normal status 5 minutes after the engine starts.

2.20 SYNCHRONIZING PANEL

Provide panel as specified in paragraph PANELS and provide controls, gauges, meters, and displays to include:

a. Frequency meters, dial type, with a range of 90 to 110 percent of rated frequency. Do not use vibrating-reed type meters . One must monitor generator output frequency ("Generator Frequency Meter") and the other must monitor the frequency of the parallel source ("Bus Frequency Meter").

b. Voltmeters, ac, dial type, 3-phase, with 4-position selector switch for the generator output ("Generator Volt Meter") and for the parallel power source ("Bus volt meter").

c. Automatic synchronizer.

d. Manual synchronizing controls.

e. Indicating lights for supplementary indication of synchronization.

f. Synchroscope.

g. Wattmeter, indicating.

2.21 PANELS

Each panel must be of the type and kind necessary to provide specified functions. Mount panels on the engine-generator set base by vibration/shock absorbing type mountings . Mount instruments flush or semiflush. Provide convenient access to the back of panels to facilitate maintenance. Calibrate instruments using recognized industry calibration standards. Provide a panel identification plate identifying the panel function. Provide a plate identifying the device and its function for each instrument and device on the panel. Provide switch plates identifying the switch-position function.

2.21.1 Enclosures

Design enclosures for the application and environment, conforming to NEMA ICS 6. Locking mechanisms must be keyed alike.

Provide for each engine-generator set and fabricate from zinc coated or phosphatized and shop primed 16 gage minimum sheet steel in accordance with the manufacturer's standard design. Provide a complete, weatherproof enclosure for the engine, generator, and auxiliary systems and equipment. Support exhaust piping and silencer so that the turbocharger is not subjected to exhaust system weight or lateral forces generated in connecting piping that exceed the engine manufacturer's maximum allowed forces and moments. The housing must have sufficient louvered openings to allow entrance of outside air for engine and generator cooling at full load. Design louvered openings to exclude driving rain and snow. Provide properly arranged and sized, hinged panels in the enclosure to allow convenient access to the engine, generator, and control equipment for maintenance and operational procedures. Provide hinged panels with spring type latches which must hold the panels closed securely and will not allow them to vibrate. Brace the housing internally to prevent excessive vibration when the set is in operation

2.21.2 Analog

Provide analog electrical indicating instruments in accordance with UL 1437 with semi-flush mounting. Switchboard, switchgear, and control-room panel-mounted instruments must have 250 degree scales with an accuracy of not less than 99 percent. Unit-mounted instruments must be the manufacturer's standard with an accuracy of not less than 98 percent. The instrument's operating temperature range must be minus 4 to plus 158 degrees F. Distorted generator output voltage waveform of a crest factor less than 5 must not affect metering accuracy for phase voltages, hertz and amps.

2.21.3 Electronic

Electronic indicating instruments must be true RMS indicating instruments, 100 percent solid state, state-of-the-art, microprocessor controlled to provide specified functions. Provide control, logic, and function devices that are compatible as a system, sealed, dust and water tight, and that utilize modular components with metal housings and digital instrumentation. Provide an interface module to decode serial link data from the electronic panel and translate alarm, fault and status conditions to set of relay contacts. Instrument accuracy less than 98 percent for unit mounted devices and 99 percent for control room, panel mounted devices, throughout a temperature range of minus 4 to 158 degrees F is not acceptable. Provide LED or back lit LCD data display. Additionally, the

display must provide indication of cycle programming and diagnostic codes for troubleshooting. Numeral height must be 0.5 inch .

2.21.4 Parameter Display

Provide indication or readouts of the tachometer, lubricating-oil pressure, ac voltmeter, ac ammeter, frequency meter, and safety system parameters. Specify a momentary switch for other panels.

2.22 SURGE PROTECTION

Electrical and electronic components must be protected from, or designed to withstand the effects of surges from switching and lightning.

2.23 AUTOMATIC ENGINE-GENERATOR-SET SYSTEM OPERATION

Provide fully automatic operation for the following operations: engine-generator set starting and load transfer upon loss of normal source; retransfer upon restoration of the normal source; sequential starting; paralleling, and load-sharing for multiple engine-generator sets; and stopping of each engine-generator set after cool-down. Devices must automatically reset after termination of their function.

2.23.1 Automatic Transfer Switch

Provide automatic transfer switches in accordance with Section 26 36 23 AUTOMATIC TRANSFER SWITCH AND BY-PASS/ISOLATION SWITCH.

2.23.2 Monitoring and Transfer

Provide devices to monitor voltage and frequency for the normal power source and each engine-generator set, and control transfer from the normal source and retransfer upon restoration of the normal source. Describe functions, actuation, and time delays as described in Section 26 36 23 AUTOMATIC TRANSFER SWITCH AND BY-PASS/ISOLATION SWITCH.

2.24 BASE

Provide a steel base. Design the base to rigidly support the engine-generator set, ensure permanent alignment of rotating parts, be arranged to provide easy access to allow changing of lube-oil, and ensure that alignment is maintained during shipping and normal operation. The base must permit skidding in any direction during installation and must withstand and mitigate the affects of synchronous vibration of the engine and generator. Provide base with suitable holes for anchor bolts and jacking screws for leveling.

2.25 THERMAL INSULATION

Provide thermal insulation as specified in Section 23 07 00 THERMAL INSULATION FOR MECHANICAL SYSTEMS.

2.26 PAINTING AND FINISHING

Clean, prime and paintthe engine-generator set in accordance with the manufacturer's standard color and practice.

2.27 FACTORY INSPECTION AND TESTS

Submit six complete reproducible copies of the factory inspection result on the checklist format specified below. Perform the factory tests on each engine-generator set. The component manufacturer's production line test is acceptable as noted. Run each engine-generator set for at least 1 hour at rated output capacity prior to inspections. Complete inspections and make all necessary repairs prior to testing. Use engine generator controls and protective devices that are provided by the generator set manufacturer as part of the standard package for factory tests. When controls and switchgear are not provided as part of the generator set manufacturer's standard package, the actual controls and protective devices provided for the project are not required to be used during the factory test. The Contracting Officer may provide one or more representatives to witness inspections and tests.

2.27.1 Factory Inspection

Perform inspections prior to beginning and after completion of testing of the assembled engine-generator set. Look for leaks, looseness, defects in components, proper assembly, etc. and note any item found to be in need of correction as a necessary repair. Use the following checklist for the inspection:

INSPECTION ITEM	GOOD	BAD	NOTES
Drive belts			
Governor and adjustments			
Engine timing mark			
Starting motor			
Starting aids			
Coolant type and concentration			
Radiator drains			
Block coolant drains			
Coolant fill level			
All coolant line connections			
All coolant hoses			
Combustion air filter			
Combustion air silencer			
Lube oil type			

INSPECTION ITEM	GOOD	BAD	NOTES
Lube oil sump drain			
Lube-oil filter			
Lube-oil-level indicator			
Lube-oil-fill level			
All lube-oil line connections			
All lube-oil lines			
Fuel type and amount			
All fuel-line connections			
All fuel lines			
Fuel filter			
Coupling and shaft alignment			
Voltage regulators			
Battery-charger connections			
All wiring connections			
Instrumentation			
Hazards to personnel			
Base			
Nameplates			
Paint			
Exhaust-heat recovery unit			
Switchboard			
Switchgear			

2.27.2 Factory Tests

Submit a letter giving notice of the proposed dates of factory inspections and tests at least 14 days prior to beginning tests, including:

a. A detailed description of the manufacturer's procedures for factory tests at least 14 days prior to beginning tests.

b. Six copies of the Factory Test data described below in 8-1/2 by 11 inch

binders having a minimum of 3 rings from which material may readily be removed and replaced, including a separate section for each test. Separate sections by heavy plastic dividers with tabs. Provide full size (8-1/2 by 11 inch minimum) data plots showing grid lines, with full resolution.

(1) A detailed description of the procedures for factory tests.

(2) A list of equipment used, with calibration certifications.

(3) A copy of measurements taken, with required plots and graphs.

(4) The date of testing.

(5) A list of the parameters verified.

(6) The condition specified for the parameter.

(7) The test results, signed and dated.

(8) A description of adjustments made.

On engine-generator set tests where the engine and generator are required to be connected and operated together, the load power factor must be 0.8 power factor. For engine-generator set with dual-fuel operating capability, perform the following tests using the primary fuel type . Perform electrical measurements in accordance with IEEE 120. Temperature limits in the rating of electrical equipment and for the evaluation of electrical insulation must be in accordance with IEEE 1. In the following tests where measurements are to be recorded after stabilization of an engine-generator set parameter (voltage, frequency, current, temperature, etc.), stabilization is considered to have occurred when measurements are maintained within the specified bandwidths or tolerances, for a minimum of four consecutive readings. Tests specifically for the generator may be performed utilizing any prime mover.

a. Insulation Resistance for Stator and Exciter Test, IEEE 115 and IEEE 43, to the performance criteria in NEMA MG 1, Part 22. Generator manufacturer's production line test is acceptable.

b. High Potential Test, in accordance with IEEE 115 and NEMA MG 1, test voltage in accordance with NEMA MG 1. Generator manufacturer's production line test is acceptable.

c. Winding Resistance Test, Stator and Exciter, in accordance with IEEE 115. Generator manufacturer's production line test is acceptable.

d. Phase Balance Voltage Test, to the performance criteria specified in paragraph GENERATOR. This test can be performed with any prime mover. Generator manufacturer's production line test results are acceptable.

(1) Start and operate the generator at no load.

(2) Adjust a regulated phase voltage (line-to-neutral) to rated voltage.

(3) Read and record the generator frequency, line-to-neutral voltages, and the line-to-line voltages.

(4) Apply 75 percent rated load and record the generator frequency, line-to-neutral voltages, and the line-to-line voltages.

(5) Apply rated load and record the generator frequency, line-to-neutral voltages, and the line-to-line voltages.

(6) Calculate average line-neutral voltage and percent deviation of individual line-neutral voltages from average for each load condition.

e. Current Balance on Stator Winding Test, by measuring the current on each phase of the winding with the generator operating at 100 percent of Rated Output Capacity, with the load impedance equal for each of the three phases: to the performance criteria specified in paragraph GENERATOR.

f. Voltage Waveform Deviation and Distortion Test in accordance with IEEE 115 to the performance criteria specified in paragraph GENERATOR. Use high-speed recording instruments capable of recording voltage waveform deviation and all distortion, including harmonic distortion. Include appropriate scales to provide a means to measure and interpret results.

g. Voltage and Frequency Droop Test. Verify that the output voltage and frequency are within the specified parameters as follows:

(1) With the generator operating at no load, adjust voltage and frequency to rated voltage and frequency. Record the generator output frequency and line-line and line-neutral voltages.

(2) Increase load to Rated Output Capacity. Record the generator output frequency and line-line and line-neutral voltages.

(3) Calculate the percent droop for voltage and frequency with the following equations:

$$\text{Voltage droop percent} = \frac{\text{(No-Load Volts)} - \text{(Rated Capacity Volts)}}{\text{(Service-Load Volts)}} \times 100$$

$$\text{Frequency droop percent} = \frac{\text{(No-Load Hertz)} - \text{(Rated Capacity Hertz)}}{\text{(Service-Load Hertz)}} \times 100$$

(4) Repeat steps 1 through 3 two additional times without making any adjustments.

h. Frequency and Voltage Stability and Transient Response. Verify that the engine-generator set responds to addition and dropping of blocks of load in accordance with the transient response requirements. Document maximum voltage and frequency variation from bandwidth and verify that voltage and frequency return to and stabilize within the specified bandwidth, within the specified response time period. Document results in tabular form and with high resolution, high speed strip chart recorders or comparable digital recorders, as approved by the Contracting Officer. Include the following tabular data:

(1) Ambient temperature (at 15 minute intervals).

(2) Generator output current (before and after load changes).

(3) Generator output voltage (before and after load changes).

(4) Frequency (before and after load changes).

(5) Generator output power (before and after load changes).

(6) Graphic representations must include the actual instrument trace of voltage and frequency showing: charts marked at start of test; observed steady-state band; mean of observed band; momentary overshoot and undershoot (generator terminal voltage and frequency) and recovery time for each load change together with the voltage and frequency maximum and minimum trace excursions for each steady state load condition prior to and immediately following each load change. Generator terminal voltage and frequency transient recovery time for each step load increase and decrease.

(a) Perform and record engine manufacturer's recommended pre-starting checks and inspections.

(b) Start the engine, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period and no load. Verify stabilization of voltage and frequency within specified bandwidths.

(c) With the unit at no load, apply the Maximum Step Load Increase.

(d) Apply load in steps equal to the Maximum Step Load Increase until the addition of one more step increase will exceed the Service Load.

(e) Decrease load to the unit such that addition of the Maximum Step Load Increase will load the unit to 100 percent of Service Load.

(f) Apply the Maximum Step Load Increase.

(g) Decrease load to zero percent in steps equal to the Maximum Step Load Decrease.

(h) Repeat steps (c) through (g).

j. Test Voltage Unbalance with Unbalanced Load (Line-to-Neutral) to the performance criteria specified in paragraph GENERATOR. Prototype test data is acceptable in lieu of the actual test. Submit manufacturer's standard certification that prototype tests were performed for the generator model proposed. This test may be performed using any prime mover.

(1) Start and operate the generator set at rate voltage, no load, rated frequency, and under control of the voltage regulator. Read and record the generator frequency, line-to-neutral voltages, and the line-to-line voltages.

(2) Apply the specified load between terminals L_1-L_2, L_2-L_0, and L_3-L_0 in turn. Record all instrument readings at each line-neutral condition.

(3) Express the greatest difference between any two of the line-to-line voltages and any two of the line-to-neutral voltages as a percent of rated voltage.

(4) Compare the largest differences expressed in percent with the maximum allowable difference specified.

PART 3 EXECUTION

3.1 EXAMINATION

After becoming familiar with all details of the job, perform a Site Visit to verify the information shown on the drawings, before performing any work. Submit a letter stating the date the site was visited and listing discrepancies found. Notify the Contracting Officer in writing of any discrepancies.

3.2 GENERAL INSTALLATION

Provide clear space for operation and maintenance in accordance with NFPA 70 and IEEE C2. Submit a copy of the manufacturer's installation procedures and a detailed description of the manufacturer's recommended break-in procedure. Install pipe, duct, conduit, and ancillary equipment to facilitate easy removal and replacement of major components and parts of the engine-generator set.

3.3 PIPING INSTALLATION

Weld piping. Provide flanged valve connections. Provide flanged connections at equipment. Provide threaded connections to the engine if the manufacturers standard connection is threaded. Except where otherwise specified, use welded flanged fittings to allow for complete dismantling and removal of each piping system from the facility without disconnecting or removing any portion of any other system's equipment or piping. Make connections to equipment with vibration isolation-type flexible connectors. Support and align piping and tubing to prevent stressing of flexible hoses and connectors. Flash pipes extending through the roof. Install piping clear of windows, doors and openings, to permit thermal expansion and contraction without damage to joints or hangers, and install a 1/2 inch drain valve with cap at each low point.

The installation of gas engines must conform to the requirements of NFPA 37 and its references therein, including NFPA 54, NFPA 58, and ASME B31.3.

3.3.1 Support

Provide hangers, inserts, and supports to accommodate any insulation and conforming to MSS SP-58. Space supports no more than 7 feet on center for pipes 2 inches in diameter or less, no more than 12 feet on center for pipes larger than 2 inches but smaller than 4 inches in diameter, and not more than 17 feet on center for pipes larger than 4 inches in diameter. Provide supports at pipe bends or change of direction.

3.3.1.1 Ceiling and Roof

Support exhaust piping with appropriately sized Type 41 single pipe roll and threaded rods; support all other piping with appropriately sized Type 1 clevis and threaded rods.

3.3.1.2 Wall

Make wall supports for pipe by suspending the pipe from appropriately sized Type 33 brackets with the appropriate ceiling and roof pipe supports.

3.3.2 Flanged Joints

Provide flanges that are Class 125 type, drilled, and of the proper size and configuration to match the equipment and engine connections. Provide gasketed flanged joints that are square and tight.

3.3.3 Cleaning

After fabrication and before assembly, piping interiors must be manually wiped clean of debris.

3.3.4 Pipe Sleeves

Fit pipes passing through construction such as ceilings, floors, or walls with sleeves. Extend each sleeve through and fasten in its respective structure and cut flush with each surface. Build the structure tightly to the sleeve. The inside diameter of each sleeve must be minimum 1/2 inch, and where pipes pass through combustible materials 1 inch larger than the outside diameter of the passing pipe or pipe insulation/covering.

3.4 ELECTRICAL INSTALLATION

Perform electrical installation in compliance with NFPA 70, IEEE C2, and Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. For vibration isolation, provide flexible fittings for conduit, cable trays, and raceways attached to engine-generator sets; provide flexible stranded conductor for metallic conductor cables installed on the engine generator set and from the engine generator set to equipment not mounted on the engine generator set; and provide crimp-type terminals or lugs for terminations of conductors on the engine generator set.

3.5 FIELD PAINTING

Perform field painting as specified in Section 09 90 00 PAINTS AND COATINGS.

3.6 ONSITE INSPECTION AND TESTS

Perform and report on factory tests and inspections prior to shipment. Provide certified copies of manufacturer's test data and results. Test procedures must conform to ASME, IEEE, IEC, and ANSI standards, and to ISO requirements on testing, as appropriate and applicable. The manufacturer performing the tests must provide equipment, labor, and consumables necessary for tests and measuring and indicating devices must be certified to be within calibration. Tests must indicate satisfactory operation and attainment of specified performance. If satisfactory, equipment tested will be given a tentative approval. Equipment must not be shipped before approval of the factory test reports for the following tests.

Submit a letter giving notice of the proposed dates of onsite inspections and tests at least 14 days prior to beginning tests.

a. Submit a detailed description of the Contractor's procedures for onsite tests including the test plan and a listing of equipment necessary to perform the tests at least 14 days prior to beginning tests.

b. Submit six copies of the onsite test data described below in 8-1/2 by 11 inch binders having a minimum of 3 rings from which material may readily be removed and replaced, including a separate section for each test. Separate sections by heavy plastic dividers with tabs. Provide full size (8-1/2 by 11 inch minimum) data plots showing grid lines, with full resolution.

(1) A detailed description of the procedures for onsite tests.

(2) A list of equipment used, with calibration certifications.

(3) A copy of measurements taken, with required plots and graphs.

(4) The date of testing.

(5) A list of the parameters verified.

(6) The condition specified for the parameter.

(7) The test results, signed and dated.

(8) A description of adjustments made.

3.6.1 Test Conditions

3.6.1.1 Data

Make and record measurements of all parameters necessary to verify that each set meets specified parameters. If the results of any test step are not satisfactory, make adjustments, replacements, or repairs and repeat the step until satisfactory results are obtained. Unless otherwise indicated, record data in 15 minute intervals during engine-generator set operation and include: readings of all engine-generator set meters and gauges for electrical and power parameters; oil pressure; ambient temperature; and engine temperatures available from meters and gauges supplied as permanent equipment on the engine-generator set. Perform electrical measurements in accordance with IEEE 120. Definitions of terms are in accordance with IEEE 100. Provide temperature limits in the rating of electrical equipment and for the evaluation of electrical insulations in accordance with IEEE 1.

3.6.1.2 Power Factor

Submit the generator capability curve showing generator kVA output capability (kW vs. kvar) for both leading and lagging power factors ranging from 0 to 1.0. For all engine-generator set operating tests the load power factor must be 0.8 power factor.

3.6.1.3 Contractor Supplied Items

Provide equipment and supplies required for inspections and tests including fuel, test instruments, and loadbanks at the specified power factors.

3.6.1.4 Instruments

Verify readings of panel gauges, meters, displays, and instruments provided as permanent equipment during test runs, using test instruments of greater precision and accuracy. Test instrument accuracy must be within the following: current plus or minus 1.5 percent, voltage plus or minus 1.5 percent, real power plus or minus 1.5 percent, reactive power plus or minus 1.5 percent, power factor plus or minus 3 percent, frequency plus or minus 0.5 percent. Calibrate test instruments by a recognized standards laboratory within 30 days prior to testing.

3.6.1.5 Sequence

Provide the sequence of testing as specified in the approved testing plan unless variance is authorized by the Contracting Officer. Perform field testing in the presence of the Contracting Officer. Schedule and sequence tests in order to optimize run-time periods; however, follow the general order of testing: Construction Tests; Inspections; Pre-operational Tests; Safety Run Tests; Performance Tests; and Final Inspection.

3.6.2 Construction Tests

Perform individual component and equipment functional tests for fuel piping, coolant piping, and lubricating-oil piping, electrical circuit continuity, insulation resistance, circuit protective devices, and equipment not provided by the engine-generator set manufacturer prior to connection to the engine-generator set.

3.6.2.1 Piping Test

a. Flush lube-oil and fuel-oil piping with the same type of fluid intended to flow through the piping, until the outflowing fluid has no obvious sediment or emulsion.

b. Test fuel piping which is external to the engine-generator set in accordance with NFPA 30. Pressure all remaining piping which is external to the engine-generator set with air pressure at 150 percent of the maximum anticipated working pressure, but not less than 150 psi, for a period of 2 hours to prove the piping has no leaks. If piping is to be insulated, perform the test before the insulation is applied.

3.6.2.2 Electrical Equipment Tests

a. Perform low-voltage cable insulation integrity tests for cables connecting the generator breaker to the automatic transfer switch . Test low-voltage cable, complete with splices, for insulation resistance after the cables are installed, in their final configuration, ready for connection to the equipment, and prior to energization. Apply a test voltage of 500 volts dc for one minute between each conductor and ground and between all possible combinations conductors in the same trench, duct, or cable, with all other conductors in the same trench, duct, or conduit. Provide the minimum value of insulation as follows:

(1) R in meg-ohms = (rated voltage in kV plus 1) x 304.8/(length of cable in meters)

(2) R in meg-ohms = (rated voltage in kV plus 1) x 1000/(length of cable in feet)

(3) Each cable failing this test must be repaired or replaced. The repair cable must be retested until failures have been eliminated.

c. Ground-Resistance Tests. Measure the resistance of each grounding electrode system using the fall-of-potential method defined in IEEE 81. On systems consisting of interconnected ground rods, perform tests after interconnections are complete. Take measurements in normally dry weather, not less than 48 hours after rainfall. Provide site diagram indicating location of test probes with associated distances, and provide a plot of resistance vs. distance. The combined resistance of separate systems may be used to meet the requirements resistance, but the specified number of electrodes must still be provided as follows:

(1) Single rod electrode - 25 ohms.

(2) Multiple rod electrodes - ohms.

(3) Ground mat - ohms.

d. Examine and test circuit breakers and switchgear in accordance with the manufacturer's published instructions for functional testing.

3.6.3 Inspections

Perform the following inspections jointly by the Contracting Officer and the Contractor, after complete installation of each engine-generator set and its associated equipment, and prior to startup of the engine-generator set. Submit a letter certifying that all facilities are complete and functional; that each system is fully functional; and that each item of equipment is complete, free from damage, adjusted, and ready for beneficial use. Perform checks applicable to the installation. Document and submit the results of those which are physical inspections (I) in accordance with paragraph SUBMITTALS. Present manufacturer's data for the inspections designated (D) at the time of inspection. Verify that equipment type, features, accessibility, installation and condition are in accordance with the contract specification. Provide manufacturer's statements to certify provision of features which cannot be verified visually.

Drive belts	I
Governor type and features	I
Engine timing mark	I
Starting motor	I

Starting aids	I
Coolant type and concentration	D
Radiator drains	I
Block coolant drains	I
Coolant fill level	I
Coolant line connections	I
Coolant hoses	I
Combustion air filter	I
Intake air silencer	I
Lube oil type	D
Lube oil sump drain	I
Lube-oil filter	I
Lube-oil level indicator	I
Lube-oil fill level	I
Lube-oil line connections	I
Lube-oil lines	I
Fuel type	D
Fuel level	I
Fuel-line connections	I
Fuel lines	I
Fuel filter	I
Access for maintenance	I
Voltage regulator	I
Battery-charger connections	I
Wiring and terminations	I
Instrumentation	I
Hazards to personnel	I

Base	I
Nameplates	I
Paint	I
Exhaust-heat system	I
Exhaust muffler	I
Switchboard	I
Switchgear	I
Access provided to controls	I
Enclosure is weather resistant	I
Engine and generator mounting bolts (application)	I

3.6.4 Engine Tests

Perform customary commercial factory tests in accordance with ISO 3046 on each engine and associated engine protective device, including, but not limited to the following:

a. Perform dynamometer test at rated power. Record horsepower at rated speed and nominal characteristics such as lubricating oil pressure, jacket water temperature, and ambient temperature.

b. Test and record the values that the low oil pressure alarm and protective shutdown devices actuate prior to assembly on the engine.

c. Test and record values that the high jacket water temperature alarm and protective shutdown devices actuate prior to assembly on the engine.

3.6.5 Generator Tests

Tests must be performed on the complete factory assembled generator prior to shipment. Conduct tests in accordance with IEEE 115, and NEMA MG 1.

3.6.5.1 Routine Tests

Perform the following routine tests on the generators and their exciters:

a. Resistance of armature and field windings.

b. Mechanical balance.

c. Phases sequence.

d. Open circuit saturation curve and phase (voltage) balance test.

e. Insulation resistance of armature and field windings.

f. High potential tes.t

3.6.5.2 Design Tests

Submit the following design tests made on prototype machines that are physically and electrically identical to the generators specified.

a. Temperature rise test

b. Short circuit saturation curve and current balance test

3.6.6 Assembled Engine-Generator Set Tests

Submit the following tests made on prototype machines that are physically and electrically identical to the engine-generator set specified.

3.6.6.1 Initial Stabilization Readings

Operate the engine-generator set and allow the set to stabilize at rated kW at rated power factor, rated voltage, and rated frequency. During this period record instrument readings for output power (kW), terminal voltage, line current, power factor, frequency (rpm) generator (exciter) field voltage and current, lubricating oil pressure, jacket water temperature, and ambient temperature at minimum intervals of 15 minutes. Adjust the load, voltage, and frequency to maintain rated load at rated voltage and frequency. Adjustments to load, voltage, or frequency controls must be recorded on the data sheet at the time of adjustment. Stabilization must be considered to have occurred when four consecutive voltage and current recorded readings of the generator (or exciter) field either remain unchanged or have only minor variations about an equilibrium condition with no evident continued increase or decrease in value after the last adjustment to the load, voltage, or frequency has been made.

3.6.6.2 Regulator Range Test

Remove load and record instrument readings (after transients have subsided). Adjust voltage to the maximum attainable value or to a value just prior to actuation of the overvoltage protection device. Apply rated load and adjust voltage to the minimum attainable value or a value just prior to activation of the under-voltage protection device. The data sheets must indicate the voltage regulation as a percent of rated voltage and the maximum and minimum voltages attainable. Voltage regulation must be defined as follows:

$$\text{Percent Regulation} = \frac{(\text{No-Load Voltage}) - (\text{Rated-Load Voltage})}{(\text{Rated-Load Voltage})} \times 100$$

3.6.6.3 Frequency Range Test

Adjust the engine-generator set frequency for the maximum attainable frequency at rated load. Record instrument readings. Adjust the engine-generator set frequency for the specified minimum attainable frequency at rated load. Record instrument readings. Reduce the load to zero and adjust the engine-generator set frequency for the maximum attainable frequency. Record instrument readings. Adjust the engine-generator set frequency for the minimum attainable frequency. Record instrument readings. The data sheet must show the maximum and minimum frequencies attained at rated load, and at no load.

3.6.6.4 Transient Response Test

Drop the load to no load and re-apply rated load three times to ensure that the no load and rated load voltage and frequency values are repeatable and that the frequency and voltage regulation is within the limits specified. Record generator terminal voltage and frequency using a high speed strip chart recorder. The data sheet must show the following results:

a. Frequency

(1) Stability bandwidth or deviation in percent of rated frequency.

(2) Recovery time.

(3) Overshoot and undershoot.

b. Voltage

(1) Stability bandwidth or deviation in percent of rated voltage.

(2) Recovery time.

(3) Overshoot and undershoot.

3.6.7 Pre-operational Tests

3.6.7.1 Protective Relays

Visually and mechanically inspect, adjust, test, and calibrate protective relays in accordance with the manufacturer's published instructions. Include pick-up, timing, contact action, restraint, and other aspects necessary to ensure proper calibration and operation. Implement relay settings in accordance with the installation coordination study. Manually or electrically operate relay contacts to verify that the proper breakers and alarms initiate. Field test relaying current transformers in accordance with IEEE C57.13.1.

3.6.7.2 Insulation Test

Test generator and exciter circuits insulation resistance in accordance with IEEE 43. Take stator readings including generator leads to switchboard at the circuit breaker. Record results of insulation resistance tests. Readings must be within limits specified by the manufacturer. Verify mechanical operation, insulation resistance, protective relay calibration and operation, and wiring continuity of switchboard assembly. Do not damage generator components during test.

3.6.7.3 Engine-Generator Connection Coupling Test

When the generator provided is a two-bearing machine, inspect and check the engine-generator connection coupling by dial indicator to prove that no misalignment has occurred. Use the dial indicator to measure variation in radial positioning and axial clearance between the coupling halves. Take readings at four points, spaced 90 degrees apart. Align solid couplings and pin-type flexible couplings within a total indicator reading of 0.0005 to 0.001 inch for both parallel and angular misalignment. For gear-type or grid-type couplings, 0.002 inch will be acceptable.

3.6.8 Safety Run Test

For the following tests, repeat the associated safety tests if any parts are changed, or adjustments made to the generator set, its controls, or auxiliaries.

a. Perform and record engine manufacturer's recommended prestarting checks and inspections.

b. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period.

c. Activate the manual emergency stop switch and verify that the engine stops.

d. Remove the high and pre-high lubricating oil temperature sensing elements from the engine and temporarily install a temperature gauge in their normal locations on the engine (required for safety, not for recorded data). Where necessary provide temporary wiring harness to connect the sensing elements to their permanent electrical leads.

e. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period. Operate the engine-generator set at no load until the output voltage and frequency stabilize. Monitor the temporarily installed temperature gauges. If either temperature reading exceeds the value required for an alarm condition, activate the manual emergency stop switch.

f. Immerse the elements in a vessel containing controlled-temperature hot oil and record the temperature at which the pre-high alarm activates and the temperature at which the engine shuts down. Remove the temporary temperature gauges and reinstall the temperature sensors on the engine.

g. Remove the high and pre-high coolant temperature sensing elements from the engine and temporarily install a temperature gauge in their normal locations on the engine (required for safety, not for recorded data). Where necessary provide temporary wiring harness to connect the sensing elements to their permanent electrical leads.

h. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period. Operate the engine generator-set at no load until the output voltage and frequency stabilize.

i. Immerse the elements in a vessel containing controlled-temperature hot oil and record the temperature at which the pre-high alarm activates and the temperature at which the engine shuts down. Remove the temporary temperature gauges and reinstall the temperature sensors on the engine.

j. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period.

k. Operate the engine generator-set for at least 2 hours at 75 percent of Service Load.

l. Verify proper operation and set-points of gauges and instruments.

m. Verify proper operation of ancillary equipment.

n. Manually adjust the governor to increase engine speed past the over-speed limit. Record the RPM at which the engine shuts down.

o. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections and operate the engine generator-set for at least 15 minutes at 75 percent of Service Load.

p. Manually adjust the governor to increase engine speed to within 2 percent of the over-speed trip speed previously determined and operate at that point for 5 minutes. Manually adjust the governor to the rated frequency.

q. Manually fill the day tank to a level above the overfill limit. Record the level at which the overfill alarm sounds. Verify shutdown of the fuel transfer pump. Drain the day tank down below the overfill limit.

r. Shut down the engine. Remove the time-delay low lube oil pressure alarm bypass and try to start the engine.

s. Attach a manifold to the engine oil system (at the oil pressure sensor port) that contains a shutoff valve in series with a connection for the engine's oil pressure sensor followed by an oil pressure gauge ending with a bleed valve. Move the engine's oil pressure sensor from the engine to the manifold. Open the manifold shutoff valve and close the bleed valve.

t. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections and operate the engine generator-set for at least 15 minutes at 75 percent of Service Load.

u. Close the manifold shutoff valve. Slowly allow the pressure in the manifold to bleed off through the bleed valve while watching the pressure gauge. Record the pressure at which the engine shuts down. Catch oil spillage from the bleed valve in a container. Add the oil from the container back to the engine, remove the manifold, and reinstall the engine's oil pressure sensor on the engine.

v. Start the engine, record the starting time, make and record engine manufacturer's after-starting checks and inspections and operate the engine generator-set for at least 15 minutes at 100 percent of Service Load. Record the maximum sound level in each frequency band at a distance of 75 feet from the end of the exhaust and air intake piping directly along the path of intake and discharge for horizontal piping; or at a radius of 75 feet from the engine at 45 degrees apart in all directions for vertical piping. If a sound limiting enclosure is provided, modify or replace the enclosure, the muffler, and intake silencer must be modified or replaced as required to meet the sound requirements contained within this specification If a sound limiting enclosure is not provided, the muffler and air intake silencer as required to meet the sound limitations of this specification. If the sound limitations can not be obtained by modifying or replacing the muffler and air intake silencer, notify the Contracting Officers

Representative and provide a recommendation for meeting the sound limitations.

w. Manually drain off fuel slowly from the day tank to empty it to below the low fuel level limit and record the level at which the audible alarm sounds. Add fuel back to the day tank to fill it above low level alarm limits.

3.6.9 Performance Tests

In the following tests, where measurements are to be recorded after stabilization of an engine-generator set parameter (voltage, frequency, current, temperature, etc.), stabilization is considered to have occurred when measurements are maintained within the specified bandwidths or tolerances, for a minimum of four consecutive readings. For the following tests, repeat the associated tests if any parts are changed, or adjustments made to the generator set, its controls, or auxiliaries.

3.6.9.1 Continuous Engine Load Run Test

Test the engine-generator set and ancillary systems at service load to demonstrate durability; verify that heat of extended operation does not adversely affect or cause failure in any part of the system; and check all parts of the system. If the engine load run test is interrupted for any reason, repeat the entire test. Accomplish the engine load run test during daylight hours, with an average ambient temperature of degrees F, during the month of . After each change in load in the following test, measure the vibration at the end bearings (front and back of engine, outboard end of generator) in the horizontal, vertical, and axial directions. Verify that the vibration is within the allowable range. Take data taken at 15 minute intervals and include the following:

Electrical: Output amperes, voltage, real and reactive power, power factor, frequency.

Pressure: Lube-oil.

Temperature: Coolant, Lube-oil, Exhaust, Ambient.

a. Perform and record engine manufacturer's recommended prestarting checks and inspections. Include as a minimum checking of coolant fluid, fuel, and lube-oil levels.

b. Start the engine, make and record engine manufacturer's after-starting checks and inspections during a reasonable warmup period.

c. Operate the engine generator-set for 2 hours at 75 percent of Service Load.

d. Increase load to 100 percent of Service Load and operate the engine generator-set for 4 hours.

e. For prime rated units, increase load to 110 percent of Service Load and operate the engine generator-set for 2 hours.

f. Decrease load to 100 percent of Service Load and operate the engine generator-set for 2 hours or until all temperatures have stabilized.

g. Remove load from the engine-generator set.

3.6.9.2 Voltage and Frequency Droop Test

For the following steps, verify that the output voltage and frequency return to and stabilize within the specified bandwidth values following each load change. Record the generator output frequency and line-line and line-neutral voltages following each load change.

a. With the generator operating at no load, adjust voltage and frequency to rated voltage and frequency.

b. Increase load to 100 percent of Rated Output Capacity. Record the generator output frequency and line-line and line-neutral voltages.

c. Calculate the percent droop for voltage and frequency with the following equations.

$$\text{Voltage droop percent} = \frac{\text{No-load volts - rated output capacity volts}}{\text{Rated output capacity volts}} \times 100$$

$$\text{Frequency droop percent} = \frac{\text{No load hertz - rated output capacity hertz}}{\text{Rated output capacity volts}} \times 100$$

d. Repeat steps a. through c. two additional times without making any adjustments.

3.6.9.3 Voltage Regulator Range Test

a. While operating at no load, verify that the voltage regulator adjusts from 90 to 110 percent of rated voltage.

b. Increase load to 100 percent of Rated Output Capacity. Verify that the voltage regulator adjusts from 90 to 110 percent of rated voltage.

3.6.9.4 Governor Adjustment Range Test

a. While operating at no load, verify that the governor adjusts from 90 to 110 percent of rated frequency.

b. Increase load to 100 percent of Rated Output Capacity. Verify that the governor adjusts from 90 to 110 percent of rated frequency.

3.6.9.5 Frequency and Voltage Stability and Transient Response

Verify that the engine-generator set responds to addition and dropping of blocks of load in accordance with the transient response requirements. Document maximum voltage and frequency variation from bandwidth and verify that voltage and frequency return to and stabilize within the specified bandwidth, within the specified response time period. Document results in tabular form and with high resolution, high speed strip chart recorders or comparable digital recorders, as approved by the Contracting Officer. Include the following tabular data:

(1) Ambient temperature (at 15 minute intervals).

(2) Generator output current (before and after load changes).

(3) Generator output voltage (before and after load changes).

(4) Frequency (before and after load changes).

(5) Generator output power (before and after load changes.

(6) Include the actual instrument trace of voltage and frequency in graphic representations showing:

Charts marked at start of test; observed steady-state band; mean of observed band; momentary overshoot and undershoot (generator terminal voltage and frequency) and recovery time for each load change together with the voltage and frequency maximum and minimum trace excursions for each steady state load condition prior to and immediately following each load change. Generator terminal voltage and frequency transient recovery time for each step load increase and decrease.

a. Perform and record engine manufacturer's recommended prestarting checks and inspections.

b. Start the engine, make and record engine manufacturer's after-starting checks and inspections during a reasonable warm-up period and no load. Verify stabilization of voltage and frequency within specified bandwidths.

c. With the unit at no load, apply the Maximum Step Load Increase.

d. Apply load in steps equal to the Maximum Step Load Increase until the addition of one more step increase will exceed the Service Load.

e. Decrease load to the unit such that addition of the Maximum Step Load Increase will load the unit to 100 percent of Service Load.

f. Apply the Maximum Step Load Increase.

g. Decrease load to zero percent in steps equal to the Maximum Step Load Decrease.

h. Repeat steps c. through g.

3.6.10 Parallel Operation Test

Test the capability of each engine-generator set to parallel and share load with other generator sets, individually and in all combinations. This test must be performed with the voltage regulator and governor adjustment settings used for the Frequency and Voltage Stability and Transient Response test. If settings are changed during the performance of this test, a voltage and frequency stability and transient response test must be performed for each engine generator set using the setting utilized in this test. During operations record load-sharing characteristics of each set in parallel operation. Include the following data:

(1) Ambient temperature (at 15 minute intervals).

(2) Generator output current (before and after load changes).

(3) Generator output voltage (before and after load changes).

(4) Power division and exchange between generator sets.

(5) Real power (watts) and reactive power (vars) on each set.

3.6.10.1 Combinations

Connect each set, while operating at no load, parallel with one other set in the system, operating at service load, until all possible combinations have been achieved. Verify stabilization of voltage and frequency within specified bandwidths and proportional sharing of real and reactive loads. Document stabilization of voltage and frequency within specified bandwidth, the active power division, active power exchange, reactive power division, and voltage and frequency stability and transient response in the following steps for each combination.

a. Divide the load proportionally between the sets and operate in parallel for 15 minutes.

b. Increase the load, in steps equal to the Maximum Step Increase, until each set is loaded to its service load.

c. Decrease the load, in steps equal to the Maximum Step Decrease, until each set is loaded to approximately 25 percent of its service load.

d. Increase the load, in steps equal to the Maximum Step Increase, until each set is loaded to approximately 50 percent of its service load Verify stabilization of voltage and frequency within specified bandwidths and proportional sharing of real and reactive load.

e. Reduce the sum of the loads on both sets to the output rating of the smaller set.

f. Transfer a load equal to the output rating of the smaller of the 2 sets to and from each set. Verify stabilization of voltage and frequency within specified bandwidths and proportional sharing of real and reactive load.

g. Document the active power division, active power exchange, reactive power division, and voltage and frequency stability and transient response.

3.6.10.2 Multiple Combinations

Connect each set, while operating at no load, parallel with all multiple combinations of all other set in the system, while operating at service load, until all multiple combinations of parallel operations have been achieved.

3.6.11 Parallel Operation Test (Commercial Source)

Connect each set parallel with the commercial power source. Operate in parallel for 15 minutes. Verify stabilization of voltage and frequency within specified bandwidths. Record the output voltage, frequency, and loading to demonstrate ability to synchronize with the commercial power source.

3.6.12 Automatic Operation Tests

Test the automatic operating system to demonstrate automatic starting, loading and unloading, the response to loss of operating engine-generator sets, and paralleling of each engine-generator set. Utilize load banks at the indicated power factor for this test, and the loading sequence is the indicated sequence. Record load-sharing characteristics during all operations. Perform this test for a minimum of two successive, successful tests. Include the following data:

(1) Ambient temperature (at 15 minute intervals).

(2) Generator output current (before and after load changes).

(3) Generator output voltage (before and after load changes).

(4) Generator output frequency (before and after load changes).

(5) Power division and exchange between generator sets.

(6) Real and reactive power on each set.

a. Initiate loss of the preferred power source and verify the specified sequence of operation.

b. Verify resetting of automatic starting and transfer logic.

3.6.13 Automatic Operation Tests for Stand-Alone Operation

Test the automatic loading system to demonstrate automatic starting, and loading and unloading of each engine-generator set. Utilize the actual loads to be served for this test, and the loading sequence is the indicated sequence. Perform this test for a minimum of two successive, successful tests. Include the following data:

(1) Ambient temperature (at 15 minute intervals).

(2) Generator output current (before and after load changes).

(3) Generator output voltage (before and after load changes).

(4) Generator output frequency (before and after load changes).

a. Initiate loss of the primary power source and verify automatic sequence of operation.

b. Restore the primary power source and verify sequence of operation.

c. Verify resetting of controls to normal.

3.7 GROUNDING

NFPA 70 and IEEE C2, except that grounding systems must have a resistance to solid earth ground not exceeding 5 ohms.

3.7.1 Grounding Electrodes

Provide driven ground rods as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION . Connect ground conductors to the upper end of

ground rods by exothermic weld or compression connector. Provide compression connectors at equipment end of ground conductors.

3.7.2 Engine-Generator Set Grounding

Provide separate copper grounding conductors and connect them to the ground system as indicated. When work in addition to that indicated or specified is required to obtain the specified ground resistance, the provision of the contract covering "Changes" must apply.

3.7.3 Connections

Make joints in grounding conductors by exothermic weld or compression connector. Exothermic welds and compression connectors must be installed as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION paragraph regarding GROUNDING.

3.7.4 Grounding and Bonding Equipment

UL 467, except as indicated or specified otherwise.

3.8 START-UP ENGINEER

Provide the services of a qualified factory trained start-up engineer, regularly employed by the engine-generator set manufacturer. The start-up services must include conducting preliminary operations and functional acceptance tests. The start-up engineer must be present at the engine generator set installation-site, full-time, while preliminary operations and functional acceptance tests are being conducted.

3.9 PREREQUISITES FOR FUNCTIONAL ACCEPTANCE TESTING

Completion of the following requirements is mandatory prior to scheduling functional acceptance tests for the engine-generator set and auxiliary equipment.

3.9.1 Performance of Acceptance Checks and Tests

The acceptance checks and tests must be accomplished by the testing organization as described in Section 26 08 00 APPARATUS INSPECTION AND TESTING.

3.9.2 Generator Sets

Complete as specified in the paragraph ACCEPTANCE CHECKS AND TESTS.

3.9.2.1 Automatic Transfer Switches

Complete acceptance checks and tests as specified in Section 26 36 23 AUTOMATIC TRANSFER SWITCHES AND BY-PASS/ISOLATION SWITCH.

3.9.3 Preliminary Operations

The start-up engineer must conduct manufacturer recommended start-up procedures and tests to verify that the engine-generator set and auxiliary equipment are ready for functional acceptance tests. Give the Contracting Officer 15 days' advance notice that preliminary operations will be conducted. After preliminary operation has been successfully conducted, the start-up engineer will notify the Contracting Officer in writing

stating the engine-generator set and auxiliary equipment are ready for functional acceptance tests.

3.9.4 Preliminary Assembled Operation and Maintenance Manuals

Preliminary assembled operation and maintenance manuals must have been submitted to and approved by the Contracting Officer. Manuals must be prepared as specified in the paragraph ASSEMBLED OPERATION AND MAINTENANCE MANUALS.

3.9.5 Functional Acceptance Test Procedure

Test procedure must be prepared by the start-up engineer specifically for the engine-generator set and auxiliary equipment. The test agenda must cover the requirements specified in the paragraph FUNCTIONAL ACCEPTANCE TESTS. The test procedure must indicate in detail how tests are to be conducted. A statement of the tests that are to be performed without indicating how the tests are to be performed is not acceptable. Indicate what work is planned on each workday and identify the calendar dates of the planned workdays. Specify what additional technical support personnel is needed such as factory representatives for major equipment. Specify on which testing workday each technical support personnel is needed. Data recording forms to be used to document test results are to be submitted with the proposed test procedure. A list of test equipment and instruments must also be included in the test procedure.

3.9.6 Test Equipment

Test equipment and instruments must be on hand prior to scheduling field tests or, subject to Contracting Officer approval, evidence must be provided to show that arrangements have been made to have the necessary equipment and instruments on-site prior to field testing.

3.10 FIELD QUALITY CONTROL

Give Contracting Officer NAVFAC , Code 30 days' notice of dates and times scheduled for tests which require the presence of the Contracting Officer. The Contracting Officer will coordinate with the using activity and schedule a time that will eliminate or minimize interruptions and interference with the activity operations. The Contractor must be responsible for costs associated with conducting tests outside of normal working hours and with incorporating special arrangements and procedures, including temporary power conditions. The Contractor must provide labor, equipment, fuel, test load, and consumables required for the specified tests. The test load must be a cataloged product. Calibration of measuring devices and indicating devices must be certified. Refer to Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM, for requirements for a cataloged product. Perform the following field tests.

3.10.1 Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations, and include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

3.10.1.1 Circuit Breakers - Low Voltage Insulated Case/Molded Case

a. Visual and Mechanical Inspection

(1) Compare nameplate data with specifications and approved shop drawings.

(2) Inspect circuit breaker for correct mounting.

(3) Operate circuit breaker to ensure smooth operation.

(4) Inspect case for cracks or other defects.

(5) Verify tightness of accessible bolted connections and cable connections by calibrated torque-wrench method. Thermo-graphic survey is not required.

(6) Inspect mechanism contacts and arc chutes in unsealed units.

b. Electrical Tests

(1) Perform contact-resistance tests.

(2) Perform insulation-resistance tests.

(3) Adjust breaker(s) for final settings in accordance with engine-generator set manufacturer's requirements.

3.10.1.2 Current Transformers

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Verify correct connection.

(4) Verify that adequate clearances exist between primary and secondary circuit.

(5) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method. Thermo-graphic survey is not required.

(6) Verify that all required grounding and shorting connections provide good contact.

b. Electrical Tests

(1) Perform insulation-resistance tests.

(2) Perform polarity tests.

(3) Perform ratio-verification tests.

3.10.1.3 Metering and Instrumentation

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Verify tightness of electrical connections.

b. Electrical Tests

(1) Determine accuracy of meters at 25, 50, 75, and 100 percent of full scale.

(2) Calibrate watt-hour meters according to manufacturer's published data.

(3) Verify all instrument multipliers.

(4) Electrically confirm that current transformer secondary circuits are intact.

3.10.1.4 Battery Systems

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method. Thermo-graphic survey is not required.

(4) Measure electrolyte specific gravity and temperature and visually check fill level.

(5) Verify adequacy of battery support racks, mounting, anchorage, and clearances.

b. Electrical Tests

(1) Set charger float and equalizing voltage levels.

(2) Verify all charger functions and alarms.

(3) Measure each cell voltage and total battery voltage with charger energized and in float mode of operation.

(4) Perform a capacity load test.

3.10.1.5 Engine-Generator Set

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Inspect for correct anchorage and grounding.

b. Electrical and Mechanical Tests

(1) Perform an insulation-resistance test on generator winding with respect to ground. Calculate polarization index.

(2) Perform phase rotation test to determine compatibility with load requirements.

3.10.1.6 Grounding System

a. Visual and Mechanical Inspection

(1) Inspect ground system for compliance with contract plans and specifications.

b. Electrical Tests

(1) Perform ground-impedance measurements utilizing the fall-of-potential method defined in IEEE 81. On systems consisting of interconnected ground rods, perform tests after interconnections are complete. Take measurements in normally dry weather, not less than 48 hours after rainfall. Provide site diagram indicating location of test probes with associated distances, and provide a plot of resistance vs. distance.

3.10.2 Functional Acceptance Tests

The tests must be performed by the start-up engineer. Upon successful test completion, the start-up engineer must provide the Contracting Officer with a written test report within 15 calendar days showing the tests performed and the results of each test. The report must include the completed approved test data forms and certification from the start-up engineer that the test results fall within the manufacturer's recommended limits and meet the specified requirements performance. The report must be dated and signed by the start-up engineer, and submitted for approval by the Contracting Officer. The Contracting Officer and NAVFAC , Code will witness final acceptance tests. Testing must include, but not be limited to, the following:

a. Verify proper functioning of each engine protective shutdown device and pre-shutdown alarm device. Testing of the devices must be accomplished by simulating device actuation and observing proper alarm and engine shutdown operation.

b. Verify proper functioning of the engine over-speed trip device. Testing of the over-speed trip device must be accomplished by raising the speed of the engine-generator set until an over-speed trip is experienced.

c. Verify proper functioning of the crank cycle/terminate relay. Testing of the relay must be accomplished by engaging the starter motor with the engine being prevented from running. Observe the complete crank/rest cycle as described in the paragraph STARTING SYSTEM.

d. Verify proper functioning of the following automatic and manual operations. Testing must include, but not be limited to, the following:

(1) Loss of Utility: Initiate a normal power failure with connected

test load of rated kW at 1.0 power factor. Record time delay on start, cranking time until engine starts and runs, time to come up to operating speed, voltage and frequency overshoot, and time to achieve steady state conditions with all switches transferred to emergency position.

(2) Return of Utility: Return normal power and record time delay on retransfer for each automatic transfer switch, and time delay on engine cool-down and shutdown.

(3) Manual starting.

(4) Emergency stop.

e. Operate the engine-generator set at rated current (amperes) until the jacket water temperature stabilizes. Stabilization will be considered to have occurred when three consecutive temperature readings remain unchanged. Continue to operate the generator set for an additional 2 hours. Record instrument readings for terminal voltage, line current, frequency (Hz), engine speed rpm, lubricating oil pressure, jacket water temperature, and ambient temperature at 5 minute intervals for first 15 minutes and at 15 minute intervals thereafter.

3.11 DEMONSTRATION

Upon completion of the work and at a time approved by the Contracting Officer, the Contractor must provide instructions by a qualified instructor to the Government personnel in the proper operation and maintenance of the equipment. Government personnel must receive training comparable to the equipment manufacturer's factory training. The duration of instruction must be for not less than one 8 hour working day for instruction of operating personnel and not less than one 8 hour working day for instruction of maintenance personnel.

3.11.1 Instructor's Qualification Resume

Instructors must be regular employees of the engine-generator set manufacturer. The instruction personnel provided to satisfy the requirements above must be factory certified by the related equipment manufacturer to provide instruction services. Submit the name and qualification resume of instructor to the Contracting Officer for approval.

3.11.2 Training Plan

Submit training plan 30 calendar days prior to training sessions. Training plan must include scheduling, content, outline, and training material (handouts). Content must include, but not be limited to, the following:

3.11.2.1 Operating Personnel Training

This instruction includes operating the engine-generator set, auxiliary equipment including automatic transfer switches in all modes, and the use of all functions and features specified.

3.11.2.2 Maintenance Personnel Training

Training must include mechanical, hydraulic, electrical, and electronic

instructions for the engine-generator set and auxiliary equipment including automatic transfer switches.

a. Mechanical Training: Must include at least the following:

(1) A review of mechanical diagrams and drawings.

(2) Component location and functions.

(3) Troubleshooting procedures and techniques.

(4) Repair procedures.

(5) Assembly/disassembly procedures.

(6) Adjustments (how, when, and where).

(7) Preventive maintenance procedures.

(8) Review of flow diagram.

(9) Valve locations and function.

(10) Valve and hydraulic equipment adjustment and maintenance procedures.

(11) Hydraulic system maintenance and servicing.

(12) Lubrication points, type, and recommended procedures and frequency.

b. Electrical and Electronic Maintenance Training: Must include at least the following:

(1) A review of electrical and electronic systems including wiring diagrams and drawings.

(2) Troubleshooting procedures for the machine and control systems.

(3) Electrical and electronic equipment servicing and care.

(4) Use of diagnostics to locate the causes of malfunction.

(5) Procedures for adjustments (locating components, adjustments to be made, values to be measured, and equipment required for making adjustments).

(6) Maintenance and troubleshooting procedures for microprocessor or minicomputer where applicable.

(7) Circuit board repair procedures where applicable (with schematics provided).

(8) Use of diagnostic tapes.

(9) Recommended maintenance servicing and repair for motors, switches, relays, solenoids, and other auxiliary equipment and devices.

3.12 ONSITE TRAINING

Conduct a training course for the operating staff as designated by the Contracting Officer. The training period must consist of a total hours of normal working time and must start after the system is functionally completed but prior to final acceptance.

a. Submit a letter giving the date proposed for conducting the onsite training course, the agenda of instruction, a description of the digital video recording to be provided. The course instructions must cover pertinent points involved in operating, starting, stopping, servicing the equipment, as well as major elements of the operation and maintenance manuals. Additionally, the course instructions must demonstrate routine maintenance procedures as described in the operation and maintenance manuals.

b. Submit a digital video recording of the manufacturers operating and maintenance training course.

c. One full size reproducible Mylar ach drawing must accompany the booklets. Mylars must be rolled and placed in a heavy cardboard tube with threaded caps on each end. The manual must include step-by-step procedures for system startup, operation, and shutdown; drawings, diagrams, and single-line schematics to illustrate and define the electrical, mechanical, and hydraulic systems together with their controls, alarms, and safety systems; the manufacturer's name, model number, and a description of equipment in the system. The instructions must include procedures for interface and interaction with related systems to include automatic transfer switches . Each booklet must include a CD containing an ASCII file of the procedures.

d. Provide approved operation and maintenance manuals for the training course. Post approved instructions prior to the beginning date of the training course. Coordinate the training course schedule with the using service's work schedule, and submit for approval 14 days prior to beginning date of proposed beginning date of training.

3.13 INSTALLATION

Installation must conform to the applicable requirements of IEEE C2, NFPA 30, NFPA 37, and NFPA 70.

3.14 FINAL TESTING AND INSPECTION

a. Start the engine, record the starting time, make and record all engine manufacturer's after-starting checks and inspections during a reasonable warm-up period.

b. Increase the load in steps no greater than the Maximum Step Load Increase to 100 percent of Service Load, and operate the engine-generator set for at least 30 minutes. Measure the vibration at the end bearings (front and back of engine, outboard end of generator) in the horizontal, vertical, and axial directions. Verify that the vibration is within the same range as previous measurements and is within the required range.

c. Remove load and shut down the engine-generator set after the recommended cool down period.

d. Remove the lube oil filter and have the oil and filter examined by the engine manufacturer for excessive metal, abrasive foreign particles, etc. Verify any corrective action for effectiveness by running the engine for 8 hours at Service Load, then re-examine the oil and filter.

e. Remove the fuel filter and examine the filter for trash, abrasive foreign particles, etc.

f. Visually inspect and check engine and generator mounting bolts for tightness and visible damage.

g. Replace air, oil, and fuel filters with new filters.

3.15 MANUFACTURER'S FIELD SERVICE

The engine generator-set manufacturer must furnish a qualified representative to supervise the installation of the engine generator-set, assist in the performance of the onsite tests, and instruct personnel as to the operational and maintenance features of the equipment.

3.16 POSTED DATA AND INSTRUCTIONS

Post Data and Instructions prior to field acceptance testing of the engine generator set. Provide two sets of instructions/data, typed and framed under weatherproof laminated plastic, and post side-by-side where directed. Include a one-line diagram, wiring and control diagrams and a complete layout of the system in the first set. Include the condensed operating instructions describing manufacturer's pre-start checklist and precautions; startup procedures for test-mode, manual-start mode, and automatic-start mode (as applicable); running checks, procedures, and precautions; and shutdown procedures, checks, and precautions in the second set. Submit posted data including wiring and control diagrams showing the key mechanical and electrical control elements, and a complete layout of the entire system.

a. Include procedures for interrelated equipment (such as heat recovery systems, co-generation, load-shedding, and automatic transfer switches).

c. Submit instructions including: the manufacturers pre-start checklist and precautions; startup procedures for test-mode, manual-start mode, and automatic-start mode (as applicable); running checks, procedures, and precautions; and shutdown procedures, checks, and precautions. Include procedures for interrelated equipment (such as heat recovery systems, co-generation, load-shedding, and automatic transfer switches). Provide weatherproof instructions, laminated in plastic, and post where directed.

3.17 ACCEPTANCE

Submit drawings which accurately depict the as-built configuration of the installation, upon acceptance of the engine-generator set installation. Revise layout drawings to reflect the as-built conditions and submit them with the as-built drawings. Final acceptance of the engine-generator set will not be given until the Contractor has successfully completed all tests and all defects in installation material or operation have been corrected.

-- End of Section --

SECTION 26 36 23

AUTOMATIC TRANSFER SWITCHES AND BY-PASS/ISOLATION SWITCH
05/20, CHG 1: 08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus
ASTM D709	(2017) Standard Specification for Laminated Thermosetting Materials

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2021) Standard for Acceptance Testing Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 250	(2020) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA ICS 2	(2000; R 2020) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V
NEMA ICS 4	(2015) Application Guideline for Terminal Blocks
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 110	(2025) Standard for Emergency and Standby Power Systems

UL SOLUTIONS (UL)

UL 508	(2018; Reprint Jul 2021) UL Standard for Safety Industrial Control Equipment
UL 1008	(2022) UL Standard for Safety Transfer

Switch Equipment

UL 1066 (2022) UL Standard for Safety Low-Voltage AC and DC Power Circuit Breakers Used in Enclosures

1.2 RELATED REQUIREMENTS

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM, and Section 26 08 00 APPARATUS INSPECTION AND TESTING, applies to this section, with the additions and modifications specified herein.

1.3 SUBMITTALS

Government approval is required for submittals. with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Automatic Transfer Switch Drawings; G

SD-03 Product Data

Automatic Transfer Switches; G

Remote Annunciator and Control System Panel; G

SD-06 Test Reports

Acceptance Checks and Tests; G

Functional Acceptance Tests; G

Factory Testing; G

Factory Test Reports; G

SD-07 Certificates

Proof of Listing; G

SD-10 Operation and Maintenance Data

Operation and Maintenance Manual, Submit in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA, Data Package 5; G

1.4 OPERATION AND MAINTENANCE MANUAL

Assemble and bind manuals in durable, hard-covered, water resistant binders. Assemble and index the manuals per the following table of contents:

a. Manufacturer's O&M per "SD-10 Operation and Maintenance Data".

b. Catalog data required by "SD-03 Product Data"

c. Drawings required by "SD-02 Shop Drawings".

1.4.1 Additions to Operation and Maintenance Manuals

In addition to requirements of SD-10 Data Package 5, include the followings on the actual equipment provided:

a. An outline drawing, front, top, and side views.

b. Prices for spare parts and supply list.

c. Date of Purchase.

d. Corrective maintenance procedures.

e. Operating manual outlining step-by-step procedures for system startup, operation, and shutdown.

f. Include simplified wiring and control diagrams in the manual for system as installed.

g. Provide typical contact voltage drop readings under specified conditions for use during periodic maintenance. Provide instructions for determination of contact integrity.

1.4.2 Spare Parts

Furnish the following the following minimum spare parts and any other spare parts required in one-year operation, of the same material and workmanship, meeting the same requirements, and interchangeable with the corresponding original parts.

a. Fuses: Two of each type and rating.

1.5 QUALITY ASSURANCE

1.5.1 Proof of Listing

Submit proof of listing by UL 1008.

1.5.2 Automatic Transfer Switch Drawings

Include the following as a minimum:

a. An outline drawing, including front, top, and side views.

b. Provide a nameplate of corrosion-resistant material with not less than 1/8 inch tall characters showing manufacturer's name and equipment ratings. Mount nameplate to front of enclosure and meet the nameplate requirements of NEMA ICS 2.

c. Provide detail drawings that include manufacturer's name and catalog number, electrical ratings, total system transfer statement, reduced normal supply voltage at which transfer to the alternate supply is initiated, transfer delay times, short-circuit current rating, wiring diagram, description of interconnections, testing instructions, acceptable conductor type for terminals, tightening torque for each wire connector, and other required UL 1008 markings.

d. Submit interface equipment connection diagram showing conduit and

wiring between ATS and related equipment. Provide diagrams showing interlocking provisions and cautionary notes, if any.

e. Drawings are to indicate adequate clearance for operation, maintenance, and replacement of operating equipment devices.

1.5.3 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship must be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated

1.5.4 Standard Product

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship, and:

a. Have been in satisfactory commercial or industrial use for 2 years prior to bid opening including applications of equipment and materials under similar circumstances and of similar size.

b. Have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period.

c. Where two or more items of the same class of equipment are required, provide products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.4.1 Alternative Qualifications

Products having less than a 2-year field service record are acceptable if the manufacturer has been regularly engaged in the design and production of automatic transfer switches and if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.4.2 Material and Equipment Manufacturing Date

Products manufactured more than 1 years prior to date of delivery to site are not acceptable.

1.6 DELIVERY AND STORAGE

Protect equipment placed in storage from humidity and temperature variations, moisture, water intrusion, dirt, dust, or other contaminants. In harsh environments where temperatures exceed non-operational parameters established within this specification, provide an environmentally controlled equipment storage facility to ensure temperature parameters are within equipment specification. Provide documentation of same to the Government when storage is implemented.

1.7 ENVIRONMENTAL CONDITIONS

Provide an ATS that is suitable for prolonged performance under following service conditions:

a. Operating altitude: Sea level to 3,300 ft. (Systems applied at higher altitudes are to be derated in accordance with the manufacturer's instructions).

b. Operating ambient temperature range: 40 to 104 degrees F.

c. Operating relative humidity: 0 to 90 percent, without condensation.

PART 2 PRODUCTS

2.1 AUTOMATIC TRANSFER SWITCHES

Each automatic transfer switch must be rated and marked for total system transfer and have the current and voltage ratings as indicated. Provide a switch operating mechanism that is electrically operated, have quick-make, quick-break, load break contacts, and be mechanically held in both positions. Provide an ATS that is UL listed. ATS must be manufactured and tested in accordance with applicable requirements of NEMA ICS 2, UL 1008 and UL 1066. ATS must conform to NFPA 110. Provide the ATS with the following characteristics:

a. Voltage: as indicated volts ac.

b. Amperage: as indicated amps ac. Provide an ATS with a continuous load current rating of the switch rating.

c. Number of Phases: Three.

d. Number of Wires: Four.

e. Frequency: 60 Hz.

f. Poles: Three switched.

g. ATS Withstand Current Rating: ATS must be rated to close on and withstand the available RMS symmetrical short circuit current at the ATS terminals. The ATS must be listed in accordance with UL 1008 for 3 18 cycle close and withstand ratings. Minimum UL listed close and withstand ratings at 208 VAC must be indicated kA.

h. Nonwelding Contacts: Provide contacts that are nonwelding at the available fault current rating. Contacts must be suitable for repetitive power transfer switching. Switches rated 800 amps and above must have segmented, blow-on construction for high withstand and close-on capability and be protected by separate arcing contacts.

i. Phase Contacts: Provide contacts with silver alloy composition.

j. Configuration. Provide an ATS for use in optional standby systems described in NFPA 70.

k. ATS Configuration. Provide an open transition ATS.

2.1.1 Undervoltage Sensing - Normal/Preferred Source

Undervoltage Sensing - Normal Source. Provide undervoltage sensing for each phase in the normal/preferred source. Sense low phase-to-ground voltage on each phase. Provide sensing circuit with adjustable dropout, 75-98 percent of nominal value and adjustable pickup, 85-100 percent of nominal value. Factory set dropout value to 85percent. Factory set pickup value to 90percent.

2.1.2 Adjustable Time Delay - Override Transfer

Adjustable Time Delay - Override Transfer. For override of normal-source voltage sensing to delay transfer and engine starting signals. Engine starting control contacts with adjustable commit-to-start delay circuit, 0.0-6.0 seconds. Factory set at 1second.

2.1.3 Voltage/Frequency Lockout Relay - Alternate/Emergency Source

Voltage/Frequency Lockout Relay. Three-phase sensing must be provided on the normal and emergency source. Prevent premature transfer to alternate/emergency source. Provide pickup voltage that is adjustable from 85-100 percent of nominal. Factory set for pickup at 90 percent. Provide pickup frequency that is adjustable from 90-97 percent of nominal. Factor set frequency pickup for 95 percent.

2.1.4 Adjustable Time Delay - Transfer to Alternate/Emergency Power Source

Adjustable Time Delay - Transfer to Alternate Power Source. Transfer to alternate power source time delay for transfer switches as indicated, adjustable 0-5 minutes. Factory set to 0 seconds. ATS is to monitor the frequency and voltage of alternate power source and transfer when frequency and voltage are stabilized.

2.1.5 Adjustable Time Delay- Re-transfer to Normal/Preferred Source

Adjustable Time Delay- Transfer to Source. Re-transfer to normal source time delay, adjustable 0-30 minutes. Factory set at 10 minutes. Time delay is automatically defeated upon loss or sustained undervoltage of alternate power source, provided that normal source has been restored.

2.1.6 Engine-Generator Exerciser

Exerciser. Solid-state, programmable-time switch exerciser to allow automatic starting of the generator set, subsequent load transfer, retransfer of load and shuts down engine after a preset cool-down period. Initiates exercise cycle at preset intervals adjustable from on a daily, weekly, bi-weekly or monthly basis.. Running periods are adjustable from 10-30 minutes. Factory settings are for 7-day exercise cycle, 20 minute running period and 5-minute cool-down period. Exerciser features include the following:

a. Exerciser Transfer Selector Switch: Permits selection of exercise with and without load transfer or dual independent exercisers that allow for unloaded and loaded schedule testing.

b. Push-button programming control with digital display of settings.

c. Integral battery operation of time switch when normal control power is

not available.

2.1.7 Engine Shutdown Time Delay

Engine Shutdown. Provide time delay that is adjustable from 0 to 5 minutes and is factory set at 5 minutes.

2.1.8 Engine Starting Contacts

Provide 2 isolated normally closed and 2 isolated normally open contact that is rated 5 A at 250 VAC/30 VDC minimum.

2.1.9 Delayed Transition With Time Delay Neutral

Provide an adjustable time delay transition for indicated transfer switches to allow safe transfer of highly inductive loads between two non-synchronized sources. This transfer between loads has a programmed neutral position arranged to provide a midpoint between the two working positions, with an intentional time-controlled pause at midpoint during transfer. Pause is adjustable from 1 to 300 seconds. Factory set time delay at 0.5 seconds. Time delay occurs for both transfer directions. Manufacturer is to provide recommendations for establishing the length of the time delay.

2.1.10 Unassigned Auxiliary Contacts

Provide two normally open and two normally closed, single-pole, double-throw auxiliary contacts for each switch position rated at 10 amperes at 120 volts.

2.1.11 Front Panel Devices

Provide devices mounted on cabinet front consisting of:

a. Mode selector switch with the following positions and associated functions. Selector switch can be part of the microprocessor controller consisting of an LCD screen with a graphical interface or as a stand-alone test switch.

   (1) TEST - Simulates loss of normal/preferred source system operation.

   (2) NORMAL - Transfers system to normal/preferred source bypassing re-transfer time delay.

b. Switch position indicating lights or graphical LCD display. Indicate source to which load is connected.

c. Source-Available Monitor. Provide source-available indicating lights or graphical LCD display monitor that is labeled to show when one or both sources of power are available. If indicating lights are used, then the preference is to have Green be normal/preferred power and Red be for alternate/emergency power; however, other color schemes are allowed if clearly marked.

d. Provide a transfer override switch. Provide automatic transfer switch microprocessor based controller, which offers field selectable/adjustable inputs and outputs for transfer switch operation. Override switch must bypass automatic transfer controls so ATS will transfer and remain connected to generator power source,

regardless of condition of normal/preferred source. Provide an indicating light to show override status. If alternate source fails and normal source is available, ATS is to automatically retransfer to normal source.

e. Lamp test button.

2.1.12 Voltage Unbalance

Provide automatic transfer switch controller or control logic to include positive and negative sequence voltage detection to identify a phase loss condition that can adversely effect motor loads.

2.2 ENCLOSURE

Provide an enclosure that meets the following:

a. Provide ATS and accessories in a wall-mounted, ventilated NEMA 250, Type 1, smooth sheet metal enclosure constructed in accordance with applicable requirements of NEMA ICS 6, UL 508, UL 1066, and UL 1008. Provide door with suitable hinges, locking handle latch, and gasketed jamb. Provide at least No. 14 metal gauge.

b. Factory wiring within enclosure and field wiring terminating within enclosure must comply with NFPA 70. Provide wire that is permanently tagged or marked near terminal at each end with wire number shown on approved detail drawing, when wiring is not color coded. Conform terminal block to NEMA ICS 4. Arrange terminals for entrance of external conductors from top and bottom of enclosure as shown. Main switch terminals, including neutral terminal if used, must be pressure type suitable for termination of external copper conductors shown.

2.2.1 Construction

Construct enclosure for ease of removal and replacement of ATS components and control devices from front without disconnection of external power conductors or removal or disassembly of major components.

2.2.2 Cleaning and Painting

Protect both the inside and outside surfaces of an enclosure, including means for fastening against corrosion by enameling, galvanizing, plating, powder coating, or other equivalent means. Protection is not required for metal parts that are inherently resistant to corrosion, bearings, sliding surfaces of hinges, or other parts where such protection is impractical. Provide manufacturer's standard finish material, process, and color that is free from runs, sags, peeling, or other defects. An enclosure marked Type 1, 3R, 4 or 12 is acceptable if there is no visible rust at the conclusion of a salt spray (fog) test using the test method in ASTM B117, employing a 5 percent by weight, salt solution for 24 hours. Type 4X enclosures are acceptable following performance of the above test with an exposure time of 200 hours.

2.2.3 Field Fabricated Nameplates

Nameplate is to comply with ASTM D709. Provide laminated plastic nameplates for each equipment enclosure as specified or as indicated on the drawings. Provide an inscription on each nameplate that identifies the name of the equipment, sources of power, calculated short circuit with

date and the location e.g. 'SWB-1 Electrical Room 103'. Provide nameplates that are made of melamine plastic, 0.125 inch thick, white with black center core. Provide the nameplate with a surface that is matte finished and that has square corners.. Accurately align lettering and engrave into the core. Provide nameplates that are at least 1.0 by 2.5 inches with a minimum lettering size of 0.25 inch high normal block style.

2.3 REMOTE ANNUNCIATOR AND CONTROL SYSTEM PANEL

Provide a remote annunciator and control system that utilizes a touchscreen human machine interface (HMI) with the ability to remotely monitor and control multiple transfer switches from a single panel. Minimum screen size is 7 inches. Provide password protection and date/time stamped alarm history. The controller is to have internal battery backup. In the event of a communication link failure, the system is to automatically revert to stand-alone, self-contained operation. Automatic transfer switch sensing, controlling or operating function is not to depend on remote panel for proper operation. Provide a surface mounted cabinet. Communication is to be by a RS-485 connection. The annunciator controller is to be configured to monitor and control 1 transfer switches.

2.3.1 Monitor

Monitor the following:

a. Sources available

b. Switch position.

c. Switch in test mode.

d. Overvoltage

e. Failure of communication link.

f. Engine test or exercise.

2.3.2 Alarm Screen

Alarm for the following conditions:

a. Alternate source closed

b. Undervoltage

c. Lockout.

2.3.3 Control Functions

Provide a means to perform the following functions from the controller: an alarm silence button in addition to monitoring the following items:

a. Control of switch-test initiation.

b. Control of switch operation in either direction.

c. Control of time-delay bypass for transfer to normal source.

d. Control to perform an engine test.

e. Provide a means to remotely configure transfer switch controller setpoints. The means to perform these changes must be password protected.

2.4 FACTORY TESTING

Submit a description of proposed field test procedures, including proposed date and steps describing each test, its duration and expected results, not less than weeks prior to test date. Submit certified factory and field test reports, within 14 days following completion of tests. Provide reports that are certified and dated and that demonstrate that tests were successfully completed prior to shipment of equipment.

2.4.1 Prototype Factory Testing

A prototype of specified ATS is to be factory tested in accordance with UL 1008. In addition, perform factory tests on each ATS as follows:

a. Insulation resistance test to ensure integrity and continuity of entire system

b. Main switch contact resistance test.

c. Visual inspection to verify that each ATS is as specified.

d. Mechanical test to verify that ATS sections are free of mechanical hindrances.

e. Electrical tests to verify complete system electrical operation and to set up time delays and voltage sensing settings.

2.4.2 Factory Test Reports

Provide three certified copies of factory test reports from the manufacturer.

PART 3 EXECUTION

3.1 INSTALLATION

Installation must conform to the requirements of NFPA 70 and manufacturer's recommendation.

3.2 PREREQUISITES FOR FUNCTIONAL ACCEPTANCE TESTING

Completion of the following requirements is mandatory prior to scheduling functional acceptance tests for the automatic transfer switch.

3.2.1 Performance of Acceptance Checks and tests

Complete as specified in paragraph entitled "Acceptance Checks and Tests". The Acceptance Checks and Tests are to be accomplished by the Testing organization as described in Section 26 08 00 APPARATUS INSPECTION AND TESTING.

3.2.2 Manufacturers O&M Information

The manufacturers O&M information required by the paragraph entitled

"SD-10 Operation and Maintenance Data", is to be submitted to and approved by the Contracting Officer.

3.2.3 Test Equipment

Ensure all test equipment and instruments is on hand prior to scheduling field tests, or subject to Contracting Officer's approval, evidence must be provided to show that arrangements have been made to have the necessary equipment and instruments on site prior to field testing.

3.3 FIELD QUALITY CONTROL

Give Contracting Officer 15 days notice of dates and times scheduled for tests which require the presence of the Contracting Officer. The Contracting Officer will coordinate with the using activity and schedule a time that will eliminate or minimize interruptions and interference with the activity operations. The contractor is responsible for costs associated with conducting tests outside of normal working hours and with incorporating special arrangements and procedures, including temporary power conditions. The contractor provides labor, equipment, apparatus, including test load, and consumables required for the specified tests. Calibration of all measuring devices and indicating devices must be certified. Provide the services of a qualified factory-trained manufacturer's representative to assist the contractor in installation and start-up of the equipment specified under this section. The manufacturer's representative is to provide technical direction and assistance to the contractor in general assembly of the equipment, connections and adjustments, and testing of the assembly components contained herein. Perform the following field tests in accordance with the manufacturer's recommendations and include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

3.3.1 Automatic Transfer Switch Acceptance Checks and Tests

a. Visual and Mechanical Inspection

(1) Compare equipment nameplate data with specifications and approved shop drawings.

(2) Inspect physical and mechanical condition.

(3) Confirm correct application of manufacturer's recommended lubricants.

(4) Verify that manual transfer warnings are attached and visible.

(5) Verify tightness of all control connections.

(6) Verify tightness of accessible bolted connections by calibrated torque-wrench method. Thermographic survey is not required.

(7) Perform manual transfer operation.

(8) Verify positive mechanical interlocking between normal and alternate sources.

b. Electrical Tests

(1) Measure contact-resistance. Correct values that exceed 500 microhms and values for 1 pole deviating by more than 50 percent from other poles.

(2) Perform insulation-resistance on each pole, phase-to-phase and phase-to-ground with switch closed, and across each open pole for one minute. Perform tests in both source positions.

(3) Verify settings and operations of control devices.

(4) Calibrate and set all relays and timers.

3.3.2 Functional Acceptance Tests

Functional Acceptance Tests must be coordinated with Section 26 32 15.00 ENGINE-GENERATOR SET STATIONARY 15-2500 KW, WITH AUXILIARIES. Include simulating power failure and demonstrating the following operations for each automatic transfer switch. Demonstrate in service that the automatic transfer switches are in good operating condition, and function not less than five times.

a. Perform automatic transfer tests:

(1) Simulate loss of normal/preferred power.

(2) Return to normal/preferred power.

(3) Simulate loss of emergency/alternate power.

(4) Simulate all forms of single-phase conditions.

b. Verify correct operation and timing of the following functions:

(1) Normal source voltage-sensing relays.

(2) Engine start sequence.

(3) Time delay upon transfer.

(4) Alternate source voltage-sensing relays.

(5) Automatic transfer operation.

(6) Interlocks and limit switch function.

(7) Time delay and retransfer upon normal power restoration.

3.3.3 Infrared Scanning

After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each switch. Remove all access panels so joints and connections are accessible to portable scanner.

a. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each switch 11 months after acceptance.

b. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.

c. Record of Infrared Scanning: Prepare a certified report that identifies switches checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.4 TRAINING

Provide 4 hours of training to maintenance personnel on the proper operation, maintenance and adjustment of the automatic transfer switch. Coordinate this training with that of the generator equipment.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 41 00

LIGHTNING PROTECTION SYSTEM
11/13

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 81	(2012) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 780	(2026) Standard for the Installation of Lightning Protection Systems

UL SOLUTIONS (UL)

UL 96	(2025) UL Standard for Safety Lightning Protection Components
UL 467	(2022) UL Standard for Safety Grounding and Bonding Equipment
UL Electrical Construction	(2012) Electrical Construction Equipment Directory

1.2 RELATED REQUIREMENTS

1.2.1 Verification of Dimensions

Confirm all details of work, verify all dimensions in field, and advise Contracting Officer of any discrepancy before performing work. Obtain prior approval of Contracting Officer before making any departures from the design.

1.2.2 System Requirements

Provide a system furnished under this specification consisting of the latest UL Listed products of a manufacturer regularly engaged in production of lightning protection system components. Comply with NFPA 70, NFPA 780, and UL 96.

1.2.3 Lightning Protection System Installers Documentation

Provide documentation showing that the installer is certified with a commercial third-party inspection company whose sole work is lightning protection, or is a UL Listed Lightning Protection Installer. In either case, the documentation must show that they have completed and passed the requirements for certification or listing, and have a minimum of 2 years documented experience installing lightning protection systems for DoD projects of similar scope and complexity.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Overall lightning protection system; G

Each major component; G

SD-06 Test Reports

Lightning Protection and Grounding System Test Plan; G

Lightning Protection and Grounding System Test; G

SD-07 Certificates

Lightning Protection System Installers Documentation; G

Component UL Listed and Labeled; G

Lightning protection system inspection certificate; G

Roof manufacturer's warranty; G

1.4 QUALITY ASSURANCE

In each standard referred to herein, consider the advisory provisions to be mandatory, as though the word "shall" or "must" has been substituted for "should" wherever it appears. Interpret references in these standards to "authority having jurisdiction," or words of similar meaning, to mean Contracting Officer.

1.4.1 Installation Drawings

1.4.1.1 Overall System Drawing

Submit installation shop drawing for the overall lightning protection system. Include on the drawings the physical layout of the equipment (plan view and elevations), mounting details, relationship to other parts of the work, and wiring diagrams.

1.4.1.2 Major Components

Submit detail drawings for each major component including manufacturer's

descriptive and technical literature, catalog cuts, and installation instructions.

1.4.2 Component UL Listed and Labeled

Submit proof of compliance that components are UL Listed and Labeled. Listing alone in UL Electrical Construction, which is the UL Electrical Construction Directory, is not acceptable evidence. In lieu of Listed and Labeled, submit written certificate from an approved, nationally recognized testing organization equipped to perform such services, stating that items have been tested and conform to requirements and testing methods of Underwriters Laboratories.

1.4.3 Lightning Protection and Grounding System Test Plan

Provide a lightning protection and grounding system test plan. Detail both the visual inspection and electrical testing of the system and components in the test plan. Identify (number) the system test points/locations along with a listing or description of the item to be tested and the type of test to be conducted. As a minimum, include a sketch of the facility and surrounding lightning protection system as part of the specific test plan for each structure. Include the requirements specified in paragraph, "Testing of Integral Lightning Protection System" in the test plan.

1.4.4 Lightning Protection System Inspection Certificate

Provide certification from a commercial third-party inspection company whose sole work is lightning protection, stating that the lightning protection system complies with NFPA 780. Third party inspection company cannot be the system installer or the system designer. Alternatively, provide a UL Lightning Protection Inspection Master Label Certificate for each facility indicating compliance to NFPA 780.

Inspection must cover every connection, air terminal, conductor, fastener, accessible grounding point and other components of the lightning protection system to ensure 100% system compliance. This includes witnessing the tests for the resistance measurements for ground rods with test wells, and for continuity measurements for bonds. It also includes verification of proper surge protective devices for power, data and telecommunication systems. Random sampling or partial inspection of a facility is not acceptable.

1.5 SITE CONDITIONS

Confirm all details of work, verify all dimensions in field, and advise Contracting Officer of any discrepancy before performing work. Obtain prior approval of Contracting Officer before changing the design.

PART 2 PRODUCTS

2.1 MATERIALS

Do not use a combination of materials that forms an electrolytic couple of such nature that corrosion is accelerated in the presence of moisture unless moisture is permanently excluded from the junction of such metals. Where unusual conditions exist which would cause corrosion of conductors, provide conductors with protective coatings, such as tin or lead, or oversize conductors. Where a mechanical hazard is involved, increase

conductor size to compensate for the hazard or protect conductors. When metallic conduit or tubing is provided, electrically bond conductor to conduit or tubing at the upper and lower ends by clamp type connectors or welds (including exothermic). All lightning protection components, such as bonding plates, air terminals, air terminal supports and braces, chimney bands, clips, connector fittings, and fasteners are to comply with the requirements of UL 96 classes as applicable.

2.1.1 Main and Bonding Conductors

NFPA 780 and UL 96 Class I, Class II, or Class II modified materials as applicable.

2.2 COMPONENTS

2.2.1 Air Terminals

Provide solid air terminals with a blunt tip. Tubular air terminals are not permitted. Support air terminals more than 24 inches in length by suitable brace, supported at not less than one-half the height of the terminal.

2.2.2 Ground Rods

Provide ground rods made of copper-clad steel conforming to conform to UL 467. Provide ground rods that are not less than 3/4 inch in diameter and 10 feet in length. Do not mix ground rods of copper-clad steel or solid copper on the job.

2.2.3 Grounding Plates

Provide grounding plates made of copper-clad steel conforming to UL 96.

2.2.4 Connections and Terminations

Provide connectors for splicing conductors that conform to UL 96, class as applicable. Conductor connections can be made by clamps or welds (including exothermic). Provide style and size connectors required for the installation.

2.2.5 Connector Fittings

Provide connector fittings for "end-to-end", "Tee", or "Y" splices that conform to NFPA 780 and UL 96.

PART 3 EXECUTION

3.1 INTEGRAL SYSTEM

Provide a lightning protection system that meets the requirements of NFPA 780. Lightning protection system consists of air terminals, roof conductors, down conductors, ground connections, and grounding electrodes and ground ring electrode conductor. Bond secondary conductors with grounded metallic parts within the building. Make interconnections within side-flash distances at or below the level of the grounded metallic parts.

3.1.1 Roof-Mounted Components

Coordinate with the roofing manufacturer and provide certification that

the roof manufacturer's warranty is not violated by the installation methods for air terminals and roof conductors.

3.1.1.1 Air Terminals

Use a standing seam base for installation of air terminals on a standing seam metal roof that does not produce any roof penetrations.

3.1.1.2 Roof Conductors

Use a standing seam base for installation of roof conductors on a standing seam metal roof that does not produce any roof penetrations. Roof conductors are to be concealed within the ceiling cavities as much as practicable.

3.1.2 Down Conductors

Protect exposed down conductors from physical damage as required by NFPA 780. Use Schedule 80 PVC to protect down conductors. Paint the Schedule 80 PVC to match the surrounding surface with paint that is approved for use on PVC. Down conductors are to be concealed within the wall cavities.

3.1.3 Ground Connections

Attach each down conductor and ground ring electrode to ground rods by welding (including exothermic), brazing, or compression. All connections to ground rods below ground level must be by exothermic weld connection or with a high compression connection using a hydraulic or electric compression tool to provide the correct circumferential pressure. Accessible connections above ground level and in test wells can be accomplished by mechanical clamping.

3.1.4 Grounding Electrodes

Extend driven ground rods vertically into the existing undisturbed earth for a distance of not less 10 feet. Set ground rods not less than 3 feet nor more than 8 feet, from the structure foundation, and at least beyond the drip line for the facility. After the completed installation, measure the total resistance to ground using the fall-of-potential method described in IEEE 81. Maximum allowed resistance of a driven ground rod is 25 ohms, under normally dry conditions when a ground ring electrode is not used. Contact the Contracting Officer for direction on how to proceed when two of any three ground rods, driven not less than 10 feet into the ground, a minimum of 10 feet apart, and equally spaced around the perimeter, give a combined value exceeding 50 ohms immediately after having driven. For ground ring electrode, provide continuous No. 1/0 bare stranded copper cable. Lay ground ring electrode around the perimeter of the structure in a trench not less than 3 feet nor more than 8 feet from the nearest point of the structure foundation, and at least beyond the drip line for the facility. Install ground ring electrode to a minimum depth of 30 inches. Install a ground ring electrode in earth undisturbed by excavation, not earth fill, and do not locate beneath roof overhang, or wholly under paved areas or roadways where rainfall cannot penetrate to keep soil moist in the vicinity of the cable.

3.1.5 Grounding Plates

Provide a grounding plate for each down conductor. Set grounding plates

not less than 3 feet nor more than 8 feet, from the structure foundation, and at least beyond the drip line for the facility. Grounding plate is to be buried as deeply in the existing dirt as local conditions allow, without exceeding 10 feet in depth.

3.2 APPLICATIONS

3.2.1 Nonmetallic Exterior Walls with Metallic Roof

Bond metal roof sections together which are insulated from each other so that they are electrically continuous, having a surface contact of at least 3 square inches.

3.3 INTERFACE WITH OTHER STRUCTURES

3.3.1 Fences

Bond metal fence and gate systems to the lightning protection system whenever the fence or gate is within 6 feet of any part of the lightning protection system in accordance with ANSI C2.

3.4 RESTORATION

Where sod has been removed, place sod as soon as possible after completing the backfilling. Restore, to original condition, the areas disturbed by trenching, storing of dirt, cable laying, and other work. Overfill to accommodate for settling. Include necessary topsoil, fertilizing, liming, seeding, sodding, sprigging or mulching in any restoration. Maintain disturbed surfaces and replacements until final acceptance.

3.5 FIELD QUALITY CONTROL

3.5.1 Lightning Protection and Grounding System Test

Test the lightning protection and grounding system to ensure continuity is not in excess of 1 ohm and that resistance to ground is not in excess of 25 ohms. Provide documentation for the measured values at each test point. Test the ground rod for resistance to ground before making connections to the rod. Tie the grounding system together and test for resistance to ground. Make resistance measurements in dry weather, not earlier than 48 hours after rainfall. Include in the written report: locations of test points, measured values for continuity and ground resistances, and soil conditions at the time that measurements were made. Submit results of each test to the Contracting Officer.

-- End of Section --

SECTION 26 51 00

INTERIOR LIGHTING
05/20, CHG 2: 11/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A580/A580M	(2023) Standard Specification for Stainless Steel Wire
ASTM A641/A641M	(2019) Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire
ASTM A653/A653M	(2025a) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM A1008/A1008M	(2021a) Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Solution Hardened, and Bake Hardenable
ASTM B164	(2003; R 2014) Standard Specification for Nickel-Copper Alloy Rod, Bar, and Wire
ASTM B633	(2019) Standard Specification for Electrodeposited Coatings of Zinc on Iron and Steel
ASTM D4674 REV A	(2002; R 2010) Standard Practice for Accelerated Testing for Color Stability of Plastics Exposed to Indoor Office Environments

EUROPEAN UNION (EU)

Directive 2011/65/EU	(2011) Restriction of the Use of Certain Hazardous Substances in Electrical and Electronic Equipment

ILLUMINATING ENGINEERING SOCIETY (IES)

ANSI/IES LM-79	(2019) Approved Method: Electrical and Photometric Measurements of Solid State Lighting Products
ANSI/IES LM-80	(2020) Approved Method: Measuring Luminous Flux and Color Maintenance of LED

	Packages, Arrays and Modules
ANSI/IES LS-1	(2020) Lighting Science: Nomenclature and Definitions for Illuminating Engineering
ANSI/IES TM-15	(2020) Technical Memorandum: Luminaire Classification System for Outdoor Luminaires
ANSI/IES TM-21	(2021) Technical Memorandum: Projecting Long-TermLuminous, Photon, and Radiant Flux Maintenance of LED Light Sources
ANSI/IES TM-30	(2020) Technical Memorandum: IES Method for Evaluating Light Source Color Rendition
IES Lighting Library	IES Lighting Library

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms
IEEE C2	(2023) National Electrical Safety Code
IEEE C62.41	(1991; R 1995) Recommended Practice on Surge Voltages in Low-Voltage AC Power Circuits

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA 77	(2017) Temporal Light Artifacts: Test Methods and Guidance for Acceptance Criteria
NEMA 250	(2020) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA ANSLG C78.377	(2017) Electric Lamps– Specifications for the Chromaticity of Solid State Lighting Products
NEMA C82.77-10	(2020) Harmonic Emission Limits - Related Power Quality Requirements
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA SSL 1	(2016) Electronic Drivers for LED Devices, Arrays, or Systems
NEMA SSL 3	(2011) High-Power White LED Binning for General Illumination
NEMA SSL 7A	(2015) Phase-Cut Dimming for Solid State Lighting: Basic Compatibility
NEMA WD 1	(1999; R 2020) Standard for General Color Requirements for Wiring Devices

NEMA WD 7	(2011; R 2016; R 2021) Occupancy Motion Sensors Standard

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 101	(2024) Life Safety Code

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

47 CFR 15	Radio Frequency Devices

UL SOLUTIONS (UL)

UL 20	(2025) UL Standard for Safety General-Use Snap Switches
UL 94	(2023; Reprint Jan 2024) UL Standard for Safety Tests for Flammability of Plastic Materials for Parts in Devices and Appliances
UL 508	(2018; Reprint Jul 2021) UL Standard for Safety Industrial Control Equipment
UL 916	(2015; Reprint Oct 2021) UL Standard for Safety Energy Management Equipment
UL 917	(2006; Reprint Aug 2013) UL Standard for Safety Clock-Operated Switches
UL 924	(2016; Reprint May 2020) UL Standard for Safety Emergency Lighting and Power Equipment
UL 1472	(2015) UL Standard for Safety Solid-State Dimming Controls
UL 1598	(2021; Reprint Jun 2021) Luminaires
UL 2043	(2013) Fire Test for Heat and Visible Smoke Release for Discrete Products and Their Accessories Installed in Air-Handling Spaces
UL 8750	(2015; Reprint Sep 2021) UL Standard for Safety Light Emitting Diode (LED) Equipment for Use in Lighting Products

1.2 RELATED REQUIREMENTS

Materials not considered to be luminaires, luminaire accessories, or lighting equipment are specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Luminaires and accessories that are mounted in exterior

environments and not attached to the exterior of the building are specified in Section 26 56 00 EXTERIOR LIGHTING.

1.3 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications and on the drawings, must be as defined in IEEE 100 and ANSI/IES LS-1.

b. For LED luminaire light sources, "Useful Life" is the operating hours before reaching 70 percent of the initial rated lumen output (L70) with no catastrophic failures under normal operating conditions. This is also known as 70 percent "Rated Lumen Maintenance Life" as defined in ANSI/IES LM-80.

c. For LED luminaires, "Luminaire Efficacy" (LE) is the appropriate measure of energy efficiency, measured in lumens/watt. This is gathered from LM-79 data for the luminaire, in which absolute photometry is used to measure the lumen output of the luminaire as one entity, not the source separately and then the source and housing together.

d. Total harmonic distortion (THD) is the root mean square (RMS) of all the harmonic components divided by the total fundamental current.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Luminaire Drawings; G

Occupancy/Vacancy Sensor Coverage Layout; G; S

Sequence of Operation for Lighting Control System; G

SD-03 Product Data

Luminaires; G

Light Sources; G

LED Drivers; G

Luminaire Warranty; G

Lighting Controls Warranty; G

Local Area Controller; G

Switches; G

Wall Box Dimmers; G

Scene Wallstations; G

Occupancy/Vacancy Sensors; G

Time Clocks; G

Power Packs; G

Exit Signs; G

Emergency Drivers; G

SD-05 Design Data

Luminaire Design Data; G

SD-06 Test Reports

ANSI/IES LM-79 Test Report; G

ANSI/IES LM-80 Test Report; G

ANSI/IES TM-21 Test Report; G

ANSI/IES TM-30 Test Report; G

Occupancy/Vacancy Sensor Verification Test; G

SD-07 Certificates

LED Driver and Dimming Switch Compatibility Certificate; G

SD-10 Operation and Maintenance Data

Lighting System, Data Package 5; G

Lighting Control System, Data Package 5; G

Maintenance Staff Training Plan; GEnd-User Training Plan; G

1.5 QUALITY ASSURANCE

Data, drawings, and reports must employ the terminology, classifications and methods prescribed by the IES Lighting Library as applicable, for the lighting system specified.

1.5.1 Luminaire Drawings

Include dimensions, accessories installation details, and construction details. Photometric data, including CRI, CCT, LED driver type, zonal lumen data, and candlepower distribution data must accompany shop drawings.

1.5.2 Luminaire Design Data

a. Provide safety certification and file number for the luminaire family that must be listed, labeled, or identified in accordance with the NFPA 70. Applicable testing bodies are determined by the US Occupational Safety Health Administration (OSHA) as Nationally Recognized Testing Laboratories (NRTL) and include: CSA (Canadian Standards Association), ETL (Edison Testing Laboratory), and UL

(Underwriters Laboratories).

b. Provide long term lumen maintenance projections for each LED luminaire in accordance with ANSI/IES TM-21. Data used for projections must be obtained from testing in accordance with ANSI/IES LM-80.

1.5.3 ANSI/IES LM-79 Test Report

Submit test report on manufacturer's standard production model of specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data in IES format as outlined under "14.0 Test Report" in ANSI/IES LM-79.

1.5.4 ANSI/IES LM-80 Test Report

Submit report on manufacturer's standard production LED light source (package, array, or module) of specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data as outlined under "8.0 Test Report" in ANSI/IES LM-80.

1.5.5 ANSI/IES TM-21 Test Report

Submit test report on manufacturer's standard production LED light source (package, array, or module) of specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data, as well as required interpolation information as outlined under "7.0 Report" in ANSI/IES TM-21.

1.5.6 ANSI/IES TM-30 Test Report

Submit color vector graphic in accordance with ANSI/IES TM-30 on manufacturer's standard production LED light source (package, array, or module) of specified luminaire. Include spectral distribution of test LED light source.

1.5.7 LED Driver and Dimming Switch Compatibility Certificate

Submit certification from the luminaire, driver, or dimmer switch manufacturer that ensures compatibility and operability between devices without flickering and to specified dimming levels.

1.5.8 Occupancy/Vacancy Sensor Coverage Layout

Provide floor plans showing coverage layouts of all devices using manufacturer's product information.

1.5.9 Test Laboratories

Test laboratories for the ANSI/IES LM-79 and ANSI/IES LM-80 test reports must be one of the following:

a. National Voluntary Laboratory Accreditation Program (NVLAP) accredited for solid-state lighting testing as part of the Energy-Efficient Lighting Products laboratory accreditation program for both LM-79 and LM-80 testing.

b. One of the qualified labs listed on the Department of Energy - LED Lighting Facts Approved Testing Laboratories List for LM-79 testing.

c. One of the EPA-Recognized Laboratories listed for LM-80 testing.

1.5.10 Regulatory Requirements

Equipment, materials, installation, and workmanship must be in accordance with the mandatory and advisory provisions of NFPA 70, unless more stringent requirements are specified or indicated. Provide luminaires and assembled components that are approved by and bear the label of UL for the applicable location and conditions unless otherwise specified.

1.5.11 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design, and workmanship. Products must have been in satisfactory commercial or industrial use for six months prior to bid opening. The six-month period must include applications of equipment and materials under similar circumstances and of similar size. The product must have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the six-month period. Where two or more items of the same class of equipment are required, these items must be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.11.1 Alternative Qualifications

Products having less than a six-month field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.11.2 Material and Equipment Manufacturing Date

Do not use products manufactured more than six months prior to date of delivery to site, unless specified otherwise.

1.6 WARRANTY

Support all equipment items by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.6.1 Luminaire Warranty

Provide and transfer to the government the original LED luminaire manufacturers standard commercial warranty for each different luminaire manufacturer used in the project.

a. Provide a written five year minimum replacement warranty for material, luminaire finish, and workmanship. Provide written warranty document that contains all warranty processing information needed, including customer service point of contact, whether or not a return authorization number is required, return shipping information, and closest return location to the luminaire location.

(1) Finish warranty must include failure and substantial deterioration

such as blistering, cracking, peeling, chalking, or fading.

(2) Material warranty must include:

(a) All LED drivers and integral control equipment.

(b) Replacement when more than 15 percent of LED sources in any lightbar or subassembly(s) are defective, non-starting, or operating below 70 percent of specified lumen output.

b. Warranty period must begin in accordance with the manufacturer's standard warranty starting date.

c. Provide replacements that are promptly shipped, without charge, to the using Government facility point of contact and that are identical to or an improvement upon the original equipment. All replacements must include testing of new components and assembly.

1.6.2 Lighting Controls Warranty

Provide and transfer to the government the original lighting controls manufacturers standard commercial warranty for each different lighting controls manufacturer used in the project. Warranty coverage must begin from date of final system commissioning or three months from date of delivery, whichever is the earliest. Warranty service must be performed by a factory-trained engineer or technician.

a. Unless otherwise noted, provide a written five year minimum warranty on the complete system for all systems with factory commissioning. Provide warranty that covers 100 percent of the cost of any replacement parts and services required over the five years which are directly attributable to the product failure. Failures include, but are not limited to, the following:

(1) Software: Failure of input/output to execute switching or dimming commands.

(2) Damage of electronic components due to transient voltage surges.

(3) Failure of control devices, including but not limited to occupancy sensors, photosensors, and manual wall station control devices.

b. Provide a written five year minimum warranty on all input devices against defect in workmanship or materials provided by device manufacturer.

c. Provide a written five year minimum warranty on all control components attached to luminaires against defect in workmanship or materials.

1.7 OPERATION AND MAINTENANCE MANUALS

1.7.1 Lighting System

Provide operation and maintenance manuals for the lighting system in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA that provide basic data relating to the design, operation, and maintenance of the lighting system for the building. Include the following:

a. Manufacturers' operating and maintenance manuals.

b. Luminaire shop drawings for modified and custom luminaires.

c. Luminaire Manufacturers' standard commercial warranty information as specified in paragraph LUMINAIRE WARRANTY.

PART 2 PRODUCTS

2.1 PRODUCT COORDINATION

2.2 LUMINAIRES

UL 1598, NEMA C82.77-10. Provide luminaires as indicated in the luminaire schedule and NL plates or details on project plans, complete with light source, wattage, and lumen output indicated. All luminaires of the same type must be provided by the same manufacturer. Luminaires must be specifically designed for use with the driver and light source provided.

2.2.1 Luminaires

UL 8750, ANSI/IES LM-79, ANSI/IES LM-80. For all luminaires, provide:

a. Complete system with LED drivers and light sources.

b. Housings constructed of non-corrosive materials. All new aluminum housings must be anodized or powder-coated. All new steel housings must be treated to be corrosion resistant.

c. ANSI/IES TM-21, ANSI/IES LM-80. Minimum L70 lumen maintenance value of 50,000 hours unless otherwise indicated in the luminaire schedule. Luminaire drive current value must be identical to that provided by test data for luminaire in question.

d. Minimum efficacy as specified in the luminaire schedule. Theoretical models of initial lamp lumens per watt are not acceptable. If efficacy values are not listed in the luminaire schedule, provide luminaires that meet the following minimum values:

Luminaire Style	Minimum Luminaire Efficacy
Recessed 1 by 4, 2 by 4, and 2 by 2	100 LPW
Recessed Downlight (fixed, adjustable, wallwash)	80 LPW
Linear, Accent (undercabinet, cove)	45 LPW
Linear, Ambient (indirect wall mount, linear pendent)	100 LPW
High Bay, Low Bay, and Industrial Locations	100 LPW
Food Service and Hazardous Locations	60 LPW
Other (track, residential diffusers)	50 LPW
Exterior Wall Sconce	50 LPW

Luminaire Style	Minimum Luminaire Efficacy
Steplight	30 LPW
Parking Garage Luminaire	100 LPW

e. UL listed for dry or damp location typical of interior installations. Any luminaire mounted on the exterior of the building must be UL listed for wet location typical of exterior installations.

f. LED driver and light source package, array, or module are accessible for service or replacement without removal or destruction of luminaire.

g. Lenses constructed of heat tempered borosilicate glass, UV-resistant acrylic, or silicone. Provide polycarbonate vandal-resistant lenses as indicated. Sandblasting, etching and polishing must be performed as indicated in the luminaire description.

h. ANSI/IES TM-15. Provide exterior building-mounted luminaires that do not exceed the BUG ratings as listed in the luminaire schedule. If BUG ratings are not listed in the luminaire schedule, provide luminaires that meet the following minimum values for each application and mounting conditions:

Lighting Application	Mounting Conditions	BUG Rating
Exterior Wall Sconce	Above 4 feet AFF	B1-U0-G2
Exterior Wall Sconce	Below or at 4 feet AFF	B4-U0-G4
Steplight	Above 4 feet AFF	B1-U1-G2
Steplight	Below or at 4 feet AFF	B4-U1-G4
Parking Garage Luminaire	Ceiling mounted	B4-U4-G3

2.3 LIGHT SOURCES

NEMA ANSLG C78.377, NEMA SSL 3. Provide type, delivered lumen output, and wattage as indicated in the luminaire schedule on project plans.

2.3.1 LED Light Sources

Provide LED light sources that meet the following requirements:

a. NEMA ANSLG C78.377. Emit white light and have a nominal CCT of 3500 Kelvin.

b. Minimum Color Rendering Index (CRI) of 90.

c. Directive 2011/65/EU. Restriction of Hazardous Substances (RoHS) compliant.

d. Light source color consistency by utilizing a binning tolerance within

a 3-step McAdam ellipse.

2.4 LED DRIVERS

NEMA SSL 1, UL 8750. Provide LED drivers that are electronic, UL Class 1 or Class 2, constant-current type and that comply with the following requirements:

a. The combined driver and LED light source system does not exceed the minimum luminaire efficacy values as listed in the luminaire schedule provided.

b. Operates at a voltage of 120-277 volts at 50/60 hertz, with input voltage fluctuations of plus/minus 10 percent.

c. Power Factor (PF) greater than or equal to 0.90 at full input power and across specified dimming range.

d. Maximum Total Harmonic Distortion (THD) less than 20 percent at full input power and across specified dimming range.

e. Operates for at least 50,000 hours at maximum case temperature and 90 percent non-condensing relative humidity.

f. Withstands Category A surges of 2 kV without impairment of performance. Provide surge protection that is integral to the driver.

g. Integral thermal protection that reduces the output power to protect the driver and light source from damage if the case temperature approaches or exceeds the driver's maximum operating temperature.

h. 47 CFR 15. Complies with the requirements of the Federal Communications Commission (FCC) rules and regulations, Non-Consumer (Class A) for EMI/RFI (conducted and radiated).

i. Class A sound rating.

j. Directive 2011/65/EU. Restriction of Hazardous Substances (RoHS) compliant.

k. Provide dimming capability as indicated in the luminaire schedule on project plans. Dimmable drivers must dim down to 10 percent. Dimmable drivers must be controlled by a Class 2 low voltage 0-10VDC controller dimming signal protocol unless otherwise specified. LED drivers of the same family/series must track evenly across multiple luminaires at all light levels.

2.4.1 Remote LED Drivers

Provide remote LED Drivers that are UL listed for dry locations typical of interior installations. Provide LED driver in junction box or housing with mounting plate. Housing must allow for field connections to occur inside the housing or must contain mechanical connections.

2.5 LIGHTING CONTROLS

Provide lighting control systems that do not switch off battery-operated or emergency backup luminaires or exit signs in path of egress. Provide system with override of lighting control devices controlling luminaires in

path of egress with activation of fire alarm system.

2.5.1 System

Provide Lighting Control System that operates the lighting system as described in the lighting control strategies in the project plans. Submit Sequence of Operation for Lighting Control System describing the operation of the proposed lighting control system and devices. Sequence of Operation must provide the strategies identified in the lighting control strategies.

2.5.1.1 Localized Control Systems

Provide room or area-wide lighting control system capable of manual control, time-based control, and receiving input from photosensors and occupancy/vacancy sensors.

2.5.1.1.1 Local Area Controller

Provide controller designed for single area or room with the following requirements:

a. Operates at a voltage of 120-277 volts at 50/60 hertz.

b. 2 zone, with 2 relays rated 20 amps each with one manual dimmer per zone.

c. Provide inputs for occupancy/vacancy sensors, photosensors, and low-voltage wall switches.

f. Provide full 'OFF' function with input from external time clock input.

g. Capable of 0-10V dimming.

h. AV interface via RS-232RS-485ethernet and CAT5.

i. Provide override 'ON' function with input from Fire Alarm Control Panel for all emergency lighting. Controller must not turn off power to emergency batteries or exit signs.

2.5.2 Devices

2.5.2.1 Switches

Provide line-voltage toggle switches as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. When used for non-digital loads, devices must be rated at 20 Amps inductive load, and be compatible with the lighting control systems.

2.5.2.2 Wall Box Dimmers

UL 1472, UL 20, IEEE C62.41, NEMA 77, NEMA SSL 7A. Dimmers must provide flicker-free, continuously variable light output throughout the dimming range of 10 percent to 100 percent. Devices must be capable of operating at their full rated capacity regardless of being single or ganged-mounted, and be compatible with three-way and four-way switching scenarios.

Provide wall-box dimmers that meet the following requirements:

a. Device operates as an independent control device.

b. Device operates with the use of a vertical slider, paddle, rotary, button, or toggle with adjacent vertical slider.

c. Finish of device matches switches and outlets in the same area.

d. Back box in wall has sufficient depth to accommodate body of switch and wiring.

e. Dimmer is capable of controlling 0-10 volt LED drivers. Dimmers and the drivers they control must be provided from the same manufacturer or tested and certified as compatible for use together.

f. Radio frequency interference suppression is integral to device.

2.5.2.3 Scene Wallstations

Provide scene wallstations that are compatible with the other components of the lighting control system and capable of Class 1 or 2 wiring methods in accordance with the NEC and local codes. Provide devices that contain on/off group, preset scene functions, or dim up/dim down interface through front panel. Programming of new scenes or zone assignments must be accomplished by authorized personnel from the space being controlled. Provide labeling for each button, including laminated sheet with scene descriptions to be posted near each scene controller.

2.5.2.4 Occupancy/Vacancy Sensors

IEEE C62.41, NEMA WD 1, UL 94, UL 916, UL 508, ASTM D4674 REV A, NEMA WD 7. Provide occupancy/vacancy sensors with coverage patterns as indicated on project plans. Provide no less quantity of sensors as shown on plans, but add additional sensors when required to fulfill coverage requirement for the specific model of sensor provided. Provide occupancy sensor operation that requires movement to activate luminaires controlled and turns luminaires off after a set time of inactivity. Provide ceiling or wall-mounted occupancy/vacancy sensors that meet the following requirements:

a. Operating voltage of 12-24120-277 volts.

b. Time delay of 30 seconds to 30 minutes with at least four intermediate time delay settings.

c. Sensors are ceiling mountedwall-box mounted.

d. No minimum load requirement and be capable of switching from zero to 800 W at 120 VAC, 50/60 Hz and from zero to 1200 W at 277 VAC, 50/60 Hz.

e. Shielded or controlled by internal logic to adjust sensitivity to avoid false triggering due to ambient temperature, air temperature variations or HVAC air movement.

f. Sensor is equipped to automatically energize the connected load upon loss of normal power when located in a means of egress.

g. Occupancy and vacancy operation is field-adjustable and programmable with push-button or dip switch on the sensor device.

h. No leakage current to load when in the off mode.

i. Utilize zero-crossing circuitry to prevent damage from high inrush current and to promote long life operation.

2.5.2.4.1 Dual Technology Sensors

Provide dual technology sensors that meet the requirements for PIR sensors and ultrasonic sensors indicated above. If either the PIR or ultrasonic sensing registers occupancy, the luminaires must remain on.

2.5.2.4.2 Power Packs

UL 2043. Provide power packs to provide power to lighting control sensors as required in accordance with the manufacturer's specifications. Provide power packs that meet the following requirements:

a. Operate at an input voltage of 120-277 VAC, with an output voltage 12-24 VDC at 225 mA.

b. Constructed of plenum-rated, high-impact thermoplastic enclosure.

c. Utilizes zero-crossing circuitry to prevent damage from inrush current.

d. Maximum load rating of 16 amps for electronic LED lighting loads.

e. Directive 2011/65/EU. Restriction of Hazardous Substances (RoHS) compliant.

2.5.2.5 Time Clocks

UL 917, NEMA ICS 6. House time clock in a surface-mounted, lockable, NEMA 1 enclosure constructed of painted steel or plastic polymer. Provide electronic type time clock that meets the following criteria:

a. Astronomic programming function, providing a total of 96 on/off set points.

b. 24 hour type digital clock display format.

c. Power outage back-up for time clock utilizing lithium battery which provides coverage for a minimum of seven days.

d. Capable of controlling a minimum of 4 channels or loads.

e. Contacts are rated for 30 amps at 120-277 VAC resistive load in a SPST normally open (NO) configuration.

f. Contains function that allows automatic control to be skipped on certain selected days of the weekmanual bypass or remote override controldaylight savings time automatic adjustmentEEPROM memory module momentary function for output contactsability for photosensor input.

2.6 EXIT AND EMERGENCY LIGHTING EQUIPMENT

2.6.1 Exit Signs

UL 924, NFPA 101. Provide wattage as indicated in the luminaire schedule on project plans. Provide LED Exit Signs that meet the following criteria:

a. Housing constructed of UV-stable, thermo-plastic.

b. UL listed for damp location.

c. Configured for universal mounting.

d. 6 inch high, 3/4 inch stroke red lettering on face of sign with chevrons on either side of lettering to indicate direction.

e. Single or double face as indicated in project plans and luminaire schedule.

2.6.1.1 Exit Signs with Battery Backup

Equip with automatic power failure device, test switch, and pilot light, and fully automatic high/low trickle charger in a self-contained power pack. Battery must be sealed, maintenance free nickel-cadmium type, and must operate unattended for a period of not less than five years. Emergency run time must be a minimum of 1-1/2 hours. LEDs must have a minimum rated life of 10 years. Provide self-diagnostic circuitry integral to emergency LED driver. In lieu of battery, can use a nonradioactive photoluminescent plate.

2.6.1.2 Remote-Powered Exit Signs

Provide exit sign that contains provision for 120-277 VAC input from remote source.

2.6.2 Emergency Lighting Unit (ELU)

UL 924, NFPA 101. Provide emergency lighting units (ELUs) completely assembled with wiring and mounting devices, ready for installation at the locations indicated. Provide in UV-stable, thermo-plastic housing with UL damp label as indicated. Emergency lighting units must be rated for 12 volts, except units having no remote-mounted light sources and having no more than two unit-mounted light sources may be rated six volts. Equip units with brown-out sensitive circuit to activate battery when input voltage falls to 75 percent of normal. Equip with two LED light sources, automatic power failure device, test switch, and pilot light, and fully automatic high/low trickle charger in a self-contained power pack. Battery must be sealed, maintenance free nickel-cadmium type, and must operate unattended for a period of not less than five years. Emergency run time must be a minimum of 90 minutes. LEDs must have a minimum rated life of 10 years. Provide self-diagnostic circuitry integral to emergency LED driver.

2.6.3 LED Emergency Drivers

UL 924, NFPA 101. Provide LED emergency driver with automatic power failure detection, test switch and LED indicator (or combination switch/indicator) located on luminaire exterior, and fully-automatic solid-state charger, battery and inverter integral to a self-contained housing. Provide self-diagnostic function integral to emergency driver. Integral nickel-cadmium battery is required to supply a minimum of 90 minutes of emergency power at 7 watts, 10-50 VDC, constant output. Driver must be RoHS compliant, rated for installation in plenum-rated spaces and damp locations, and be warranted for a minimum of five years.

2.6.4 Self-Diagnostic Circuitry for LED Drivers

UL 924, NFPA 101. Provide emergency lighting unit with fully-automatic, integral self-testing/diagnostic electronic circuitry. Circuitry must provide for a one minute diagnostic test every 28 days, and a 30 minute diagnostic test every six months, minimum. Any malfunction of the unit must be indicated by LED(s) visible from the exterior of the luminaire. A manual test switch must also be provided to perform a diagnostic test at any given time.

2.7 LUMINAIRE MOUNTING ACCESSORIES

2.7.1 Suspended Luminaires

a. Provide hangers capable of supporting twice the combined weight of luminaires supported by hangers.

b. Hangers must allow luminaires to swing within an angle of 45 degrees. Brace pendents 4 feet or longer to limit swinging.

c. Single-unit suspended luminaires must have cabletwin-stem hangers. Multiple-unit or continuous row luminaires with a separate power supply cord must have a tubing or stem for wiring at one point and a tubing or rod suspension provided for each unit length of chassis, including one at each end.

d. Provide all linear pendent and surface mounted luminaires with two supports per four-foot section or three per eight-foot section unless otherwise recommended by manufacturer.

e. Provide rods in minimum 0.18 inch diameter.

2.7.2 Recess and Surface Mounted Luminaires

Provide access to light source and LED driver from bottom of luminaire. Provide trim and lenses for the exposed surface of flush-mounted luminaires as indicated on project drawings and specifications. Luminaires recessed in ceilings which have a fire resistive rating of one hour or more must be enclosed in a box which has a fire resistive rating equal to that of the ceiling. For surface mounted luminaires with brackets, provide flanged metal stem attached to outlet box, with threaded end suitable for supporting the luminaire rigidly in design position. Flanged part of luminaire stud must be of broad base type, secured to outlet box at not fewer than three points.

2.7.3 Luminaire Support Hardware

2.7.3.1 Wire

ASTM A641/A641M. Galvanized, soft tempered steel, minimum 0.11 inches in diameter, or galvanized, braided steel, minimum 0.08 inches in diameter.

2.7.3.2 Wire for Humid Spaces

ASTM A580/A580M. Composition 302 or 304, annealed stainless steel, minimum 0.11 inches in diameter.

ASTM B164. UNS NO4400, annealed nickel-copper alloy, minimum 0.11 inches in diameter.

2.7.3.3 Threaded Rods

Threaded steel rods, 3/16 inch diameter, zinc or cadmium coated.

2.7.3.4 Straps

Galvanized steel, one by 3/16 inch, conforming to ASTM A653/A653M, with a light commercial zinc coating or ASTM A1008/A1008M with an electrodeposited zinc coating conforming to ASTM B633, Type RS.

2.8 EQUIPMENT IDENTIFICATION

2.8.1 Manufacturer's Nameplate

Each item of equipment must have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.8.2 Labels

UL 1598. All luminaires must be clearly marked for operation of specific light sources and LED drivers. The labels must be easy to read when standing next to the equipment, and durable to match the life of the equipment to which they are attached. Note the following light source characteristics in the format "Use Only _____":

a. Correlated Color Temperature (CCT) and Color Rendering Index (CRI) for all luminaires.

b. Driver and dimming protocol.

All markings related to light source type must be clear and located to be readily visible to service personnel, but unseen from normal viewing angles when light sources are in place. LED drivers must have clear markings indicating dimming type and indicate proper terminals for the various outputs.

2.9 FACTORY APPLIED FINISH

NEMA 250. Provide all luminaires and lighting equipment with factory-applied painting system that as a minimum, meets requirements of corrosion-resistance testing.

PART 3 EXECUTION

3.1 INSTALLATION

IEEE C2, NFPA 70.

3.1.1 Light Sources

When light sources are not provided as an integral part of the luminaire, deliver light sources of the type, wattage, lumen output, color temperature (CCT), color rendering index (CRI), and voltage rating indicated to the project site and install just prior to project completion, if not already installed in the luminaires from the factory.

3.1.2 Luminaires

Set luminaires plumb, square, and level with ceiling and walls, in alignment with adjacent luminaires and secure in accordance with manufacturers' directions and approved drawings. Provide accessories as required for ceiling construction type indicated on Finish Schedule. Luminaire catalog numbers do not necessarily denote specific mounting accessories for type of ceiling in which a luminaire may be installed. Provide wires, straps, or rods for luminaire support in this section. Install luminaires with vent holes free of air blocking obstacles.

3.1.2.1 Suspended Luminaires

Measure mounting heights from the bottom of the luminaire for ceiling-mounted luminaires and to center of luminaire for wall-mounted luminaires. Obtain architect approval of the exact mounting height on the job before commencing installation and, where applicable, after coordinating with the type, style, and pattern of the ceiling being installed. Support suspended luminaires from structural framework of ceiling or from inserts cast into slab.

a. Provide suspended luminaires with 45 degree swivel hangers so that they hang plumb and level.

b. Locate so that there are no obstructions within the 45 degree range in all directions.

c. The stem, canopy and luminaire must be capable of 45 degree swing.

d. Rigid pendent stem, aircraft cable, rods, or chains 4 feet or longer excluding luminaire must be braced to prevent swaying using three cables at 120 degree separation.

e. Suspended luminaires in continuous rows must have internal wireway systems for end to end wiring and must be properly aligned to provide a straight and continuous row without bends, gaps, light leaks or filler pieces.

f. Utilize aligning splines on extruded aluminum luminaires to assure minimal hairline joints.

g. Support steel luminaires to prevent "oil-canning" effects.

h. Match supporting pendents with supported luminaire. Aircraft cable must be stainless steel.

i. Match finish of canopies to match the ceiling, and provide low profile canopies unless otherwise shown.

j. Maximum distance between suspension points must be 10 feet or as recommended by the manufacturer, whichever is less.

3.1.2.2 Recessed and Semi-Recessed Luminaires

a. Support recessed and semi-recessed luminaires independently from the building structure by a minimum of two wires, straps or rods per luminaire and located near opposite corners of the luminaire. Secure horizontal movement with clips provided by manufacturer. Ceiling grid clips are not allowed as an alternative to independently supported

luminaires.

b. Support round luminaires or luminaires smaller in size than the ceiling grid independently from the building structure by a minimum of four wires, straps or rods per luminaire, spaced approximately equidistant around.

c. Do not support luminaires by acoustical tile ceiling panels.

d. Where luminaires of sizes less than the ceiling grid are indicated to be centered in the acoustical panel, support each independently and provide at least two 3/4 inch metal channels spanning, and secured to, the ceiling tees for centering and aligning the luminaire.

e. Luminaires installed in suspended ceilings must also comply with the requirements of Section 09 51 00 ACOUSTICAL CEILINGS.

f. Adjust aperture rings on all applicable ceiling recessed luminaires to accommodate various ceiling material thickness. Coordinate cut-out size in ceiling to ensure aperture covers cut-out entirely. Install aperture rings such that the bottom of the ring is flush with finished ceiling or not more than 1/16 inch above. Do not install luminaires such that the aperture ring extends below the finished ceiling surface.

g. For luminaire recessed in plaster ceilings, provide plaster frames for setting. Install setting such that the bottom of the frame is flush with finished ceiling. Support luminaires with plaster frames utilizing yokes or leveling lugs. Do not mount luminaires or support elements to ducts or pipes. Yokes must support a luminaire by no fewer than two bolts each.

3.1.3 LED Drivers

Provide LED drivers integral to luminaire as constructed by the manufacturer.

3.1.3.1 Remote LED Drivers

Locate Remote LED Drivers within the maximum distance allowed to minimize voltage drop. Do not locate remote LED drivers further from the light source than specified by the manufacturer. Locate remote LED drivers in dry, well-ventilated, and accessible location, above accessible ceilings or behind a removable wall or ceiling panel. Mount housing or junction box so that it is rigidly and securely fastened in place. Install LED drivers such that components are not in contact with combustible materials unless listed for such condition. Remote LED drivers must be grounded in accordance with NFPA 70.

Provide separate compartments for Class 2 wiring connections and for Class 1 wiring connections. Separation must be barrier-type within the same box or separate boxes with close connector conduit fittings. Field connections must be inside housing or junction box or secured by a quick disconnect wire connector.

3.1.4 Exit Signs

NFPA 101. Wire exit signs and emergency lighting units ahead of the local switch, to the normal lighting circuit located in the same room or area.

Connect exit signs on separate circuits and serve from a separate circuit breaker. Provide only one source of control, which would be the separate circuit breaker. Paint source of control red and provide lockout capability.

3.1.5 Lighting Controls

Refer below for additional lighting control installation requirements.

3.1.5.1 Scene Wallstations

Submit labeling templates for all scene wallstations, ganged faceplates and other manual control cover plates. Label each scene control button with approved scene description.

3.1.5.2 Occupancy/Vacancy Sensors

a. Provide quantity of sensor units indicated as a minimum. Provide additional units to give full coverage over controlled area. Full coverage must provide hand and arm motion detection for office and administration type areas and walking motion for industrial areas, warehouses, storage rooms and hallways.

b. Locate ceiling-mounted sensors no closer than 6 feet from the nearest HVAC supply or return diffuser.

c. Locate the sensor(s) as indicated and in accordance with the manufacturer's recommendations.

3.2 FIELD QUALITY CONTROL

3.2.1 Tests

3.2.1.1 Lighting Control Verification Tests

Verify lighting control system and devices operate according to approved sequence of operations. Verification tests are to be completed after commissioning.

a. Verify occupancy/vacancy sensors operate as described in sequence of operations. Provide testing of sensor coverage, sensitivity, and time-out settings in all spaces where sensors are placed. This is to be completed only after all furnishings have been installed. Submit occupancy/vacancy sensor verification test.

b. Verify photosensors operate as described in sequence of operations. Provide testing of sensor coverage, aiming, and calibration in all spaces where sensors are placed. This is to be completed only after all furnishings have been installed.

c. Verify wall box dimmers and scene wallstations operate as described in sequence of operations.

3.2.1.2 Emergency Lighting Test

Interrupt power supply to demonstrate proper operation of emergency lighting. If adjustments are made to the lighting system, re-test system to show compliance with standards.

3.3 CLOSEOUT ACTIVITIES

3.3.1 Commissioning

NFPA 101. Commission all components of the lighting system and lighting control system in accordance with Section 01 91 00.15 20 TOTAL BUILDING COMMISSIONING. Factory Trained Field Service Technician is responsible for calibration and programming sequences for input devices and systems in accordance with the requirements described in the sequence of operation.

3.3.2 Training

3.3.2.1 Maintenance Staff Training

Submit a Maintenance Staff Training Plan at least 30 calendar days prior to training session that describes training procedures for Owner's personnel in the operation and maintenance of lighting and lighting control system. Provide on-site training which demonstrates full system functionality, assigning schedules, calibration adjustments for light levels and sensor sensitivity, integration procedures for connecting to third-party devices, and manual override including information on appropriate use. Provide protocols for troubleshooting, maintenance, repair, and replacement, and literature on available system updates and process for implementing updates.

3.3.2.2 End-User Training

Submit an End-User Training Plan at least 30 calendar days prior to training session that describes training procedures for end-users on the lighting control system. Provide users with a list of control devices located within user-occupied spaces, such as photosensors and occupancy and vacancy sensors, including information on the proper operation and schedule for each device. Provide demonstration for each type of interface. Provide users with the building schedule as currently commissioned, including conditional programming based on astronomic time clock functionality. Provide users with the correct contact information for maintenance personnel who will be available to address any lighting control issues.

Provide laminated instructions to the user at each scene wallstation. Provide only instructions relevant to the functionality of the specific scene wallstation. Provide a description of each labeled scene control button. If the room utilizes occupancy/vacancy sensors or photosensors, include a description of this functionality on the instruction sheet.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 26 56 00

EXTERIOR LIGHTING
08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO LTS	(2013; Errata 2013) Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals

ASTM INTERNATIONAL (ASTM)

ASTM A153/A153M	(2016a) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM B108/B108M	(2019) Standard Specification for Aluminum-Alloy Permanent Mold Castings
ASTM B117	(2019) Standard Practice for Operating Salt Spray (Fog) Apparatus

EUROPEAN UNION (EU)

Directive 2011/65/EU	(2011) Restriction of the Use of Certain Hazardous Substances in Electrical and Electronic Equipment

ILLUMINATING ENGINEERING SOCIETY (IES)

ANSI/IES LM-79	(2019) Approved Method: Electrical and Photometric Measurements of Solid State Lighting Products
ANSI/IES LM-80	(2020) Approved Method: Measuring Luminous Flux and Color Maintenance of LED Packages, Arrays and Modules
ANSI/IES LS-1	(2020) Lighting Science: Nomenclature and Definitions for Illuminating Engineering
ANSI/IES RP-8	(2018; Addenda 1 2020; Errata 1-2 2021) Recommended Practice for Design and Maintenance of Roadway and Parking Facility Lighting
ANSI/IES TM-15	(2020) Technical Memorandum: Luminaire

	Classification System for Outdoor Luminaires
ANSI/IES TM-21	(2021) Technical Memorandum: Projecting Long-TermLuminous, Photon, and Radiant Flux Maintenance of LED Light Sources
IES Lighting Library	IES Lighting Library

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms
IEEE C62.41.2	(2002) Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and Less) AC Power Circuits

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI C136.3	(2020) Roadway and Area Lighting Equipment - Luminaire Attachments
ANSI C136.13	(2020) Roadway and Area Lighting Equipment - Metal Brackets for Wood Poles
ANSI C136.21	(2014) American National Standard for Roadway and Area Lighting Equipment - Vertical Tenons Used with Post-Top-Mounted Luminaires
NEMA 250	(2020) Enclosures for Electrical Equipment (1000 Volts Maximum)
NEMA ANSLG C78.377	(2017) Electric Lamps– Specifications for the Chromaticity of Solid State Lighting Products
NEMA C82.77-10	(2020) Harmonic Emission Limits - Related Power Quality Requirements
NEMA C136.10	(2017) American National Standard for Roadway and Area Lighting Equipment-Locking-Type Photocontrol Devices and Mating Receptacles--Physical and Electrical Interchangeability and Testing
NEMA C136.31	(2018) Roadway and Area Lighting Equipment - Luminaire Vibration
NEMA ICS 2	(2000; R 2020) Industrial Control and Systems Controllers, Contactors, and Overload Relays Rated 600 V
NEMA ICS 6	(1993; R 2016) Industrial Control and Systems: Enclosures
NEMA SSL 1	(2016) Electronic Drivers for LED Devices,

	Arrays, or Systems
NEMA SSL 3	(2011) High-Power White LED Binning for General Illumination

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

UL SOLUTIONS (UL)

UL 773	(2016; Reprint Jul 2020) UL Standard for Safety Plug-In, Locking Type Photocontrols for Use with Area Lighting
UL 773A	(2016; Reprint Jun 2020) UL Standard for Safety Nonindustrial Photoelectric Switches for Lighting Control
UL 1310	(2018; Reprint Jun 2022) UL Standard for Safety Class 2 Power Units
UL 1598	(2021; Reprint Jun 2021) Luminaires
UL 8750	(2015; Reprint Sep 2021) UL Standard for Safety Light Emitting Diode (LED) Equipment for Use in Lighting Products

1.2 RELATED REQUIREMENTS

Materials not considered to be luminaires, luminaire accessories, or lighting equipment are specified in Section(s) 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION . Luminaires and accessories installed in interior of buildings or attached to the exterior of a building are specified in Section 26 51 00 INTERIOR LIGHTING.

1.3 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications and on the drawings must be as defined in IEEE 100 and ANSI/IES LS-1.

b. For LED luminaire light sources, "Useful Life" is the operating hours before reaching 70 percent of the initial rated lumen output (L70) with no catastrophic failures under normal operating conditions. This is also known as 70 percent "Rated Lumen Maintenance Life" as defined in ANSI/IES LM-80.

c. For LED luminaires, "Luminaire Efficacy" (LE) is the appropriate measure of energy efficiency, measured in lumens/watt. This is gathered from LM-79 data for the luminaire, in which absolute photometry is used to measure the lumen output of the luminaire as one entity, not the source separately and then the source and housing together.

d. Total Harmonic Distortion (THD) is the Root Mean Square (RMS) of all

the harmonic components divided by the total fundamental current.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Luminaire Drawings; G

Pole Drawings; G

Control System One-Line Diagram; G

SD-03 Product Data

Luminaires; G

Light Sources; G

LED Drivers; G

Luminaire Warranty; G

Lighting Controls Warranty; G

Pole Warranty; G

Photosensors; G

Time Clock; G

Lighting Contactor; G

Poles; G

Brackets

SD-05 Design Data

Luminaire Design Data; G

SD-06 Test Reports

ANSI/IES LM-79 Test Report; G

ANSI/IES LM-80 Test Report; G

ANSI/IES TM-21 Test Report; G

SD-08 Manufacturer's Instructions

Poles

SD-10 Operation and Maintenance Data

Lighting System, Data Package 5; G

Exterior Lighting Control System, Data Package 5; G

Maintenance Staff Training Plan; G

End-User Training Plan; G

1.5 QUALITY ASSURANCE

Data, drawings, and reports must employ the terminology, classifications and methods prescribed by the IES Lighting Library as applicable, for the lighting system specified.

1.5.1 Drawing Requirements

1.5.1.1 Luminaire Drawings

Include dimensions, effective projected area (EPA), weight, accessories, and installation and construction details. Photometric data, including CRI, CCT, TM-15-11 BUG rating, LED driver type, zonal lumen data, and candlepower distribution data per LM-79 must accompany shop drawings.

1.5.1.2 Pole Drawings

Include dimensions, wind load determined in accordance with AASHTO LTS, pole deflection, pole class, and other applicable information.

1.5.2 Luminaire Design Data

a. Provide distribution data according to IES classification type as defined in IES Lighting Library and ANSI/IES RP-8.

b. B.U.G. rating for the installed position as defined by ANSI/IES TM-15 and shielding as defined by ANSI/IES RP-8.

c. Provide safety certification and file number for the luminaire family. Include listing, labeling and identification in accordance with NFPA 70 (NEC). Applicable testing bodies are determined by the US Occupational Safety Health Administration (OSHA) as Nationally Recognized Testing Laboratories (NRTL) and include: CSA (Canadian Standards Association), ETL (Edison Testing Laboratory), and UL (Underwriters Laboratories).

d. Provide long term lumen maintenance projections for each LED luminaire in accordance with ANSI/IES TM-21. Data used for projections must be obtained from testing in accordance with ANSI/IES LM-80.

e. Provide wind loading calculations for luminaires mounted on poles. Weight and effective projected area (EPA) of luminaires and mounting brackets must not exceed maximum rating of pole as installed in particular wind zone area.

1.5.3 ANSI/IES LM-79 Test Report

Submit test report on manufacturer's standard production model of

specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data as outlined under "14.0 Test Report" in ANSI/IES LM-79.

1.5.4 ANSI/IES LM-80 Test Report

Submit report on manufacturer's standard production LED light source (package, array, or module) of specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data as outlined under "8.0 Test Report" in ANSI/IES LM-80.

1.5.5 ANSI/IES TM-21 Test Report

Submit test report on manufacturer's standard production LED light source (package, array or module) of specified luminaire. Testing must be performed at the same operating drive current as specified luminaire. Include all applicable and required data, as well as required interpolation information as outlined under "7.0 Report" in ANSI/IES TM-21.

1.5.6 Test Laboratories

Test laboratories for the ANSI/IES LM-79 and ANSI/IES LM-80 test reports must be one of the following:

a. National Voluntary Laboratory Accreditation Program (NVLAP) accredited for solid-state lighting testing as part of the Energy-Efficient Lighting Products laboratory accreditation program.

b. One of the qualified labs listed on the Department of Energy - Energy Efficiency & Renewable Energy, Solid-State Lighting web site.

c. One of the EPA-Recognized Laboratories listed at for LM-80 testing.

1.5.7 Regulatory Requirements

Equipment, materials, installation, and workmanship must be in accordance with the mandatory provisions of NFPA 70 unless more stringent requirements are specified or indicated. Provide luminaires and assembled components that are approved by and bear the label of UL for the applicable location and conditions unless otherwise specified.

1.5.8 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products must have been in satisfactory commercial or industrial use for six months prior to bid opening. The six-month period must include applications of equipment and materials under similar circumstances and of similar size. The product must have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the six-month period. Where two or more items of the same class of equipment are required, these items must be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.8.1 Alternative Qualifications

Products having less than a six-month field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.8.2 Material and Equipment Manufacturing Date

Do not use products manufactured more than six months prior to date of delivery to site, unless specified otherwise.

1.6 DELIVERY, STORAGE, AND HANDLING OF POLES

1.6.1 Aluminum Poles

Do not store poles on ground. Support poles so they are at least one foot above ground level and growing vegetation. Do not remove factory-applied pole wrappings until just before installing pole.

1.7 WARRANTY

Support all equipment items by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.7.1 Luminaire Warranty

Provide and transfer to the government the original LED luminaire manufacturers standard commercial warranty for each different luminaire manufacturer used in the project.

a. Provide a written five year minimum replacement warranty for material, luminaire finish, and workmanship. Provide written warranty document that contains all warranty processing information needed, including customer service point of contact, whether or not a return authorization number is required, return shipping information, and closest return location to the luminaire location.

   (1) Finish warranty must include failure and substantial deterioration such as blistering, cracking, peeling, chalking, or fading.

   (2) Material warranty must include:

      (a) All LED drivers and integral control equipment.

      (b) Replacement when more than 15 percent of LED sources in any lightbar or subassembly(s) are defective, non-starting, or operating below 70 percent of specified lumen output.

b. Warranty period must begin in accordance with the manufacturer's standard warranty starting date.

c. Provide replacements that are promptly shipped, without charge, to the using Government facility point of contact and that are identical to or an improvement upon the original equipment. All replacements must include testing of new components and installation.

1.7.2 Lighting Controls Warranty

Provide and transfer to the government the original lighting controls manufacturers standard commercial warranty for each different lighting controls manufacturer used in the project. Warranty coverage must begin from date of final system commissioning or three months from date of delivery, whichever is the earliest. Warranty service must be performed by a factory-trained engineer or technician.

a. Unless otherwise noted, provide a written five year minimum warranty on the complete system for all systems with factory commissioning. Provide warranty that covers 100 percent of the cost of any replacement parts and services required over the five years which are directly attributable to the product failure. Failures include, but are not limited to, the following:

   (1) Software: Failure of input/output to execute switching or dimming commands.

   (2) Damage of electronic components due to transient voltage surges.

   (3) Failure of control devices, including but not limited to photosensors and motion sensors.

b. Provide a written five year minimum warranty on all input devices against defect in workmanship or materials provided by device manufacturer.

c. Provide a written five year minimum warranty on all control components attached to luminaires against defect in workmanship or materials.

1.7.3 Pole Warranty

Provide and transfer to the government the original pole manufacturers standard commercial warranty for each different pole manufacturer used in the project. Warranty coverage must begin from date of final system commissioning or three months from date of delivery, whichever is the earliest. Provide a written three year minimum replacement warranty for material, luminaire finish, and workmanship. Warranty service must be performed by a factory-trained engineer or technician.

1.8 OPERATION AND MAINTENANCE MANUALS

1.8.1 Lighting System

Provide operation and maintenance manuals for the lighting system in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA that provide basic data relating to the design, operation, and maintenance of the lighting system. Include the following:

a. Manufacturers' operating and maintenance manuals.

b. Luminaire shop drawings for modified and custom luminaires.

c. Luminaire Manufacturers' standard commercial warranty information as specified in paragraph LUMINAIRE WARRANTY.

1.8.2 Exterior Lighting Control System

Provide operation and maintenance manuals for the exterior lighting control system in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA that provide basic data relating to the design, operation, and maintenance of the exterior lighting control system. Include the following:

a. Control System One-Line Diagram

b. Product data for all devices, including installation and programming instructions.

c. Training materials, such as videos or in-depth manuals, that cover basic operation of the lighting control system and instructions on modifying the control system. Training materials must include calibration, adjustment, troubleshooting, maintenance, repair, and replacement.

d. Motion sensor coverage layout.

PART 2 PRODUCTS

2.1 PRODUCT COORDINATION

2.2 LUMINAIRES

UL 1598, NEMA C82.77-10. Provide luminaires as indicated in the luminaire schedule and XL plates or details on project plans, complete with light source, wattage, and lumen output indicated. All luminaires of the same type must be provided by the same manufacturer. Luminaires must be specifically designed for use with the LED driver and light source provided.

2.2.1 Luminaires

UL 8750, ANSI/IES LM-79, ANSI/IES LM-80. For all luminaires, provide:

a. Complete system with LED drivers and light sources.

b. Housing constructed of non-corrosive materials. All new aluminum housings must be anodized or powder-coated. All new steel housings must be treated to be corrosion resistant.

c. ANSI/IES TM-21, ANSI/IES LM-80. Minimum L70 lumen maintenance value of 50,000 hours unless otherwise indicated in the luminaire schedule. Luminaire drive current value must be identical to that provided by test data for luminaire in question.

d. Minimum efficacy as specified in the luminaire schedule. Theoretical models of initial lamp lumens per watt are not acceptable. If efficacy values are not listed in the luminaire schedule, provide luminaires that meet the following minimum values:

Luminaire Style	Minimum Luminaire Efficacy
Area and Roadway (pole mounted, arm mounted)	119 LPW
Pedestrian Post-Top (pole mounted, arm mounted)	97 LPW
Bollard	45 LPW
Accent (adjustable landscape, sign lighting)	35 LPW
Linear Accent (facade, wallwash)	80 LPW
Exterior Wall Sconce	50 LPW
Steplight	30 LPW
Parking Garage Luminaire	113 LPW

e. Product rated for operation within an ambient temperature range of minus 22 degrees F to 122 degrees F.

f. UL listed for wet locations.

g. IES Lighting Library. Light distribution and NEMA field angle classifications as indicated in luminaire schedule on project plans.

h. Housing finish that is baked-on enamel, anodized, or baked-on powder coat paint. Finish must be capable of surviving ASTM B117 salt fog environment testing for 2500 hours minimum without blistering or peeling.

i. LED driver and light source package, array, or module are accessible for service or replacement without removal or destruction of luminaire.

j. ANSI/IES TM-15. Does not exceed the BUG ratings as listed in the luminaire schedule.. If BUG ratings are not listed in the luminaire schedule, provide luminaires that meet the following minimum values for each application and mounting conditions:

Lighting Application	Mounting Conditions	BUG Rating
Area and Roadway	All	B3-U0-G3
Pedestrian Post-Top	All	B2-U1-G1
Exterior Wall Sconce	Above 4 feet AFF	B1-U0-G2
Exterior Wall Sconce	Below or at 4 feet AFF	B4-U0-G4
Steplight	Above 4 feet AFF	B1-U1-G2
Steplight	Below or at 4 feet AFF	B4-U1-G4

Lighting Application	Mounting Conditions	BUG Rating
Parking Garage Luminaire	Ceiling mounted	B4-U4-G3

k. Fully assembled and electrically tested prior to shipment from factory.

l. Finish color is as indicated in the luminaire schedule or detail on the project plans.

m. Lenses constructed of clearfrosted tempered glass or UV-resistant acrylic. Provide polycarbonate vandal-resistant lenses.

n. All factory electrical connections are made using crimp, locking, or latching style connectors. Twist-style wire nuts are not acceptable.

o. NEMA C136.31. Comply with 3G vibration testing.

p. Luminaire arm bolts constructed from 304 stainless steel or zinc-plated steel.

q. Wiring compartment on pole-mounted, street and area luminaires is accessible without the use of hand tools to manipulate small screws, bolts, or hardware.

r. Incorporate modular electrical connections, and construct luminaires to allow replacement of all or any part of the optics, heat sinks, LED drivers, surge suppressors and other electrical components using only a simple tool, such as a manual or cordless electric screwdriver.

s. ANSI C136.3. For all roadway and area luminaires, provide products with an integral tilt adjustment of plus or minus 5 degrees to allow the unit to be leveled.

2.3 LIGHT SOURCES

NEMA ANSLG C78.377, NEMA SSL 3. Provide type, lumen rating, and wattage as indicated in luminaire schedule on project plans.

2.3.1 LED Light Sources

Provide LED light sources that meet the following requirements:

a. NEMA ANSLG C78.377. Emit white light and have a nominal Correlated Color Temperature (CCT) of 4000 Kelvin.

b. Minimum Color Rendering Index (CRI) of 80.

c. Directive 2011/65/EU. Restriction of Hazardous Substances (RoHS) compliant.

d. Light source color consistency by utilizing a binning tolerance within a 4-step McAdam ellipse.

2.4 LED DRIVERS

NEMA SSL 1, UL 1310. Provide LED Drivers that are electronic, UL Class 1 or Class 2, constant-current type and meet the following requirements:

a. The combined LED driver and LED light source system is greater than or equal to the minimum luminaire efficacy values as listed in the luminaire schedule provided.

b. Operate at a voltage of 120-277 volts at 50/60 hertz, with input voltage fluctuations of plus or minus 10 percent.

c. Power Factor (PF) greater than or equal to 0.90 at full input power and across specified dimming range.

d. Maximum Total Harmonic Distortion (THD) less than or equal to 20 percent at full input power and across specified dimming range.

e. Operates for at least 50,000 hours at maximum case temperature and 90 percent non-condensing relative humidity.

f. Meets the "Elevated" (10kV/10kA) requirements per IEEE C62.41.2 -2002. Manufacturer must indicate whether failure of the electrical immunity system can possibly result in disconnect of power to luminaire. Provide surge protection that is integral to the LED driver.

g. Contains integral thermal protection that reduces the output power to protect the driver and light source from damage if the case temperature approaches or exceeds the driver's maximum operating temperature.

h. Complies with the requirements of the Federal Communications Commission (FCC) rules and regulations, Title 47 CFR part 15, Non-Consumer (Class A) for EMI/RFI (conducted and radiated).

i. Class A sound rating for all drivers mounted under a covered structure, such as a canopy, or where otherwise appropriate.

j. Directive 2011/65/EU. Restriction of Hazardous Substances (RoHS) compliant.

k. UL listed for wet locations typical of exterior installations.

l. Non-dimmable.

m. Rated to operate between ambient temperatures of minus 22 degrees F and 104 degrees F 122 degrees F.

2.4.1 Remote LED Drivers

Provide remote LED Drivers that are UL listed for wet locations typical of exterior installations.

2.5 LIGHTING CONTROLS

Provide a control system interface within each luminaire that is compatible with the energy management or control system used by the utility department in charge of the project area for control of site lighting.

2.5.1 Devices

2.5.1.1 Time Clock

NEMA ICS 6. House time clock in a surface-mounted, lockable NEMA 1 enclosure constructed of painted steel or plastic polymer. Provide electronic type time clock that meets the following criteria:

a. astronomic programming function, providing a total of 56 on/off set points.

b. 24 hour type digital clock display format.

c. Power outage back-up for switch utilizing lithium battery which provides coverage for a minimum of seven days.

d. Capable of controlling a minimum of 4 channels or loads.

e. Contacts are rated for 30 amps at 120-277 VAC resistive load in a SPST normally open (NO) configuration.

f. Contains function that allows automatic control to be skipped on certain selected days of the weekmanual bypass or remote override controldaylight savings time automatic adjustmentEEPROM memory module momentary function for output contactsability for photosensor input.

2.5.1.2 Photosensors

UL 773, UL 773A. Provide Photosensors that meet the following requirements:

a. Hermetically sealed, silicon diode light sensor type, rated at watts, volts, 50/60 Hz with single-pole, single-throw contacts.

b. Turns ON at 1 to 3 footcandles and turns OFF at 3 to 15 footcandles.

c. Designed to fail to the ON position.

d. Housing is constructed of UV stabilized polypropylene, rated to operate within a temperature range of minus 40 to 158 degrees F.

e. Time delay that prevents accidental switching from transient light sources.

f. Directional lens in front of the cell to prevent fixed light sources from creating a turnoff condition.

g. Designed for 20-year service to match life expectancy of long-life LED fixtures and exceed 15,000 operations at full load. Provide photosensors with zero-cross technology to withstand severe in-rush current and extend relay life.

h. Swivel base type housing with 1/2 in threaded base for mounting to a junction box or conduit.

i. NEMA C136.10. Twist-lock receptacle type. Provide with solid brass prongs and voltage markings and color coding on exterior of housing.

j. Provide photosensors with metal oxide varistor (MOV) type surge

protection.

2.5.1.3 Lighting Contactor

NEMA ICS 2. Provide a mechanically-held lighting contactor housed in a NEMA 1 enclosure conforming to NEMA ICS 6. Contactor must have 6 poles, configured as normally open (NO). Contacts must be rated 600 volts, 30 amperes for a resistive load. Coil operating voltage must be 120 volts. Contactor must have silver cadmium oxide double-break contacts and coil clearing contacts for mechanically held contactors and must require no arcing contacts. Provide contactor with hand-off-automatic on-off selector switch. Provide contactor as specified above along with circuit breaker in integral NEMA 1 enclosure with flange-mounted handle to satisfy requirement for a "combination lighting contactor" when specified.

2.6 POLES

AASHTO LTS. Provide straight poles designed for wind loading of 150 miles per hour while supporting luminaires and all other appurtenances indicated. The effective projected areas (EPA) of luminaires and appurtenances used in calculations must be specific for the actual products provided on each pole. Provide poles that are anchor-base type designed for use with underground supply conductors. Provide metal poles with an internal grounding connection accessible from the hand hole near the bottom of each pole. Install a means of wire disconnection accessible from the hand hole. Do not install square poles. Provide poles from a Manufacturer with a standard provision for protecting the finish during shipment and installation. Do not install scratched, stained, chipped, or dented poles.

2.6.1 Aluminum Poles

Provide aluminum poles with uniform satin finish unless otherwise noted in luminaire schedule on project plans. Do not paint aluminum poles. Provide poles that meet the following requirements:

a. AASHTO LTS. Manufactured of corrosion resistant aluminum alloys for Alloy 6063-T6 or Alloy 6005-T5 for wrought alloys and Alloy 356-T4 (3,5) for cast alloys.

b. Seamless extruded or spun seamless-type with minimum 0.188 inch wall thickness.

c. Top of shaft is fitted with a round or tapered cover.

d. ASTM B108/B108M. Pole base is mounted by anchor bolts, made of cast 356-T6 aluminum alloy. Base must be machined to receive the lower end of shaft.

e. Joint between shaft and base is welded.

f. ASTM B108/B108M. Base cover is cast 356-T6 aluminum alloy.

g. All hardware other than anchor bolts are either 2024-T4 anodized aluminum alloy or stainless steel.

h. Grounding connection is designed to prevent electrolysis when used with copper ground wire.

2.6.2 Brackets and Supports

ANSI C136.3, ANSI C136.13, and ANSI C136.21. Provide pole brackets that are not less than 1 1/4 inch aluminum secured to pole. Slip-fitter or pipe-threaded brackets may be used, but brackets must be coordinated to luminaires provided, and brackets for use with one type of luminaire must be identical. Brackets for pole-mounted street lights must correctly position luminaire no lower than mounting height indicated. Mount brackets not less than 24 feet above street. Provide special mountings or brackets as indicated and of metal which will not promote galvanic reaction with luminaire head.

2.6.3 Pole Foundations

Provide anchor bolts consisting of a steel rod with a minimum yield strength of 50,000 psi; the top 12 inches of the rod must be galvanized in accordance with ASTM A153/A153M. Concrete must be as specified in Section 03 30 00 CAST-IN-PLACE CONCRETE and Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.

2.7 EQUIPMENT IDENTIFICATION

2.7.1 Manufacturer's Nameplate

Each item of equipment must have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.7.2 Labels

UL 1598. Luminaires must be clearly marked for operation of specific light sources and drivers according to proper light source type. Note the following luminaire characteristics in the format "Use Only _____":

a. Correlated color temperature (CCT) and color rendering index (CRI) for all luminaires.

b. Driver and dimming protocol.

Markings related to light source type must be clear and located to be readily visible to service personnel, but unseen from normal viewing angles when light sources are in place. LED drivers must have clear markings indicating dimming type and indicate proper terminals for the various outputs.

2.8 FACTORY APPLIED FINISH

NEMA 250. Provide all luminaires and lighting equipment with factory-applied painting system that as a minimum meets requirements of corrosion-resistance testing.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Luminaires

Install all luminaires in accordance with the luminaire manufacturer's

written instructions. Install all luminaires at locations and heights as indicated on the project plans. Level all luminaires in accordance to manufacturer's written instructions.

3.1.2 LED Drivers

Provide LED drivers integral to luminaire as constructed by the manufacturer.

3.1.2.1 Remote LED Drivers

Locate Remote LED Drivers within the maximum distance allowed to reduce voltage drop. Do not locate remote LED drivers further from the light source than specified by the manufacturer. Locate remote LED drivers in dry, well-ventilated, and accessible location, or in accessible IP68-rated enclosure. Provide separate compartments for Class 2 wiring connections and for Class 1 wiring connections. Separation must be barrier-type within the same box or separate boxes with close connector conduit fittings. Field connections must be inside housing or junction box or secured by a quick disconnect wire connector suitable for wet-location. Remote LED drivers must be electronically grounded in accordance with NFPA 70.

3.1.3 Lighting Controls

Refer below for additional lighting control installation requirements.

3.1.3.1 Photosensors

Aim photosensor according to manufacturer's recommendations. Mount sensor on or beside each luminaire when switch is provided in cast weatherproof aluminum housing with swivel arm.

3.1.4 Grounding

Ground noncurrent-carrying parts of equipment including metal poles, luminaires, mounting arms, brackets, and metallic enclosures as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION. Where copper grounding conductor is connected to a metal other than copper, provide specially treated or lined connectors suitable for this purpose.

3.2 FIELD QUALITY CONTROL

3.2.1 Tests

Upon completion of installation, verify that equipment is properly installed, connected, and adjusted. Perform initial operational test, consisting of the entire system energized for 72 consecutive hours without any failures of any kind occurring in the system. All circuits must test clear of faults, grounds, and open circuits.

3.2.1.1 Lighting Control Verification Test

Verify lighting control system and devices operate according to approved sequence of operations. Verification tests are to be completed after commissioning.

3.3 CLOSEOUT ACTIVITIES

3.3.1 Training

Provide on-site training to the Owner's personnel in the operation and maintenance of lighting and lighting control system. Provide training that includes calibration, adjustment, troubleshooting, maintenance, repair, and replacement.

3.3.1.1 Maintenance Staff Training

Submit a Maintenance Staff Training Plan at least 30 calendar days prior to training session that describes training procedures for Owner's personnel in the operation and maintenance of lighting and lighting control system. Provide on-site training which demonstrate full system functionality, assigning schedules, calibration adjustments for light levels and sensor sensitivity, integration procedures for connecting to third-party devices, and manual override including information on appropriate use. Provide protocols for troubleshooting, maintenance, repair, and replacement, and literature on available system updates and process for implementing updates.

3.3.1.2 End-User Training

Submit a End-User Training Plan at least 30 calendar days prior to training session that describes training procedures for end-users on the lighting control system. Provide demonstration for each type of user interface. Provide users with the curfew schedule as currently commissioned, including conditional programming based on astronomic time clock functionality. Provide users with the correct contact information for maintenance personnel who will be available to address any lighting control issues.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 27 10 00

BUILDING TELECOMMUNICATIONS CABLING SYSTEM (MCBCL)
01/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D709	(2017) Standard Specification for Laminated Thermosetting Materials

ELECTRONIC COMPONENTS INDUSTRY ASSOCIATION (ECIA)

ECIA EIA/ECA 310-E	(2005) Cabinets, Racks, Panels, and Associated Equipment

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms

INSULATED CABLE ENGINEERS ASSOCIATION (ICEA)

ICEA S-83-596	(2016) Indoor Optical Fiber Cables
ICEA S-90-661	(2021) Category 3 and 5E Individually Unshielded Twisted Pairs, Indoor Cables (With or Without an Overall Shield) for Use in General Purpose and LAN Communications Wiring Systems

NATIONAL ELECTRICAL CONTRACTORS ASSOCIATION (NECA)

NECA/BICSI 568	(2006) Standard for Installing Building Telecommunications Cabling

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI/NEMA WC 66	(2019) Performance Standard for Category 6 and Category 7 100 Ohm Shielded and Unshielded Twisted Pairs

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA)

TIA-455-21	(1988a; R 2012) FOTP-21 - Mating Durability of Fiber Optic Interconnecting Devices
TIA-526-7	(2015a) OFSTP-7 Measurement of Optical Power Loss of Installed Single-Mode Fiber Cable Plant
TIA-568.0	(2020e) Generic Telecommunications Cabling for Customer Premises
TIA-568.1	(2020e) Commercial Building Telecommunications Infrastructure Standard
TIA-568.2	(2018d) Balanced Twisted-Pair Telecommunications Cabling and Components Standards
TIA-568.3	(2016d; Add 1 2019) Optical Fiber Cabling Components Standard
TIA-569	(2019e) Telecommunications Pathways and Spaces
TIA-606	(2021d) Administration Standard for Telecommunications Infrastructure
TIA-607	(2019d) Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises
TIA-1152	(2016; R 2021) Requirements for Field Test Instruments and Measurements for Balanced Twisted-Pair Cabling
TIA/EIA-598	(2014D; Add 2 2018) Optical Fiber Cable Color Coding
TIA/EIA-604-3	(2004b; R 2014) Fiber Optic Connector Intermateability Standard (FOCIS), Type SC and SC-APC, FOCIS-3

U.S. FEDERAL COMMUNICATIONS COMMISSION (FCC)

FCC Part 68	Connection of Terminal Equipment to the Telephone Network (47 CFR 68)

UL SOLUTIONS (UL)

UL 50	(2024) UL Standard for Safety Enclosures for Electrical Equipment, Non-Environmental Considerations
UL 444	(2017; Reprint Jun 2021) UL Standard for Safety Communications Cables
UL 467	(2022) UL Standard for Safety Grounding

and Bonding Equipment

UL 514C	(2014; Reprint Feb 2020) UL Standard for Safety Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers
UL 969	(2017; Reprint Mar 2018) UL Standard for Safety Marking and Labeling Systems
UL 1286	(2008; Reprint Apr 2021) UL Standard for Safety Office Furnishings
UL 1666	(2007; Reprint Sep 2021) UL Standard for Safety Test for Flame Propagation Height of Electrical and Optical-Fiber Cables Installed Vertically in Shafts
UL 1863	(2004; Reprint Oct 2019) UL Standard for Safety Communication Circuit Accessories

1.2 RELATED REQUIREMENTS

Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM and Section 33 82 00 TELECOMMUNICATIONS, OUTSIDE PLANT (OSP), apply to this section with additions and modifications specified herein.

Contact Camp Lejeune Base Telephone (aka Telecommunications Support Division or TSD)for special requirements on classified service cabling and color, unofficial service, under slab cabling, using water block, and any item not covered in this document.

Buildings with Special Network Requirements such as Secured Internet Protocol, Classified networks, Commercial network, Charter cable, MCCS.org, Boingo, and Naval Blue Network may require additional guidance outside this specification. Secured areas or secured networks in non-secured areas may require Protected Distribution System (PDS) which is also outside this specification. Classified networks may require shielded twisted pair, distinct color, and has separation requirements outside this specification, and shall be in accordance with current CNSSAM TEMPEST RED/BLACK Installation documentation. In these cases contact Telecommunications Support Division G-6 MCIEAST-MCB CAMLEJ for additional guidance at (910) 451-9439 or (910) 451-4760.

Contact AHJ for special requirements on classified service, unofficial service, under slab cabling, using water block, and any item not covered in this document.

1.3 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms used in this specification shall be as defined in TIA-568.1, TIA-568.2, TIA-568.3, TIA-569, TIA-606 and IEEE 100 and herein.

1.3.1 Campus Distributor (CD)

A distributor from which the campus backbone cabling emanates. (International expression for main cross-connect (MC) also known as central office or Area Distribution Node.)

1.3.2 Building Distributor (BD)

A distributor in which the building backbone (customer owned outside plant) cables terminate and at which connections to the campus backbone cables may be made. Typically a central location for terminating permanent backbone cables to interconnect with service provider (SP) equipment at the activity minimum point of presence. Generally includes specific components to support voice and data circuits, building surge protector assemblies, main cross connect blocks, equipment support frames, and fire rated plywood backboard. (International expression for intermediate cross-connect (IC).)

1.3.3 Floor Distributor (FD)

A distributor used to connect horizontal cable and cabling subsystems or equipment. Usually within telecommunications rooms. Shall be connected to BD with both fiber and copper. A secure Internet Protocol (SIPR) vault or cabinet is considered an FD. (International expression for horizontal cross-connect (HC).)

1.3.4 Telecommunications Room (TR)

An enclosed space for housing telecommunications equipment, cable, terminations, and cross-connects. The room is the recognized cross-connect between the backbone cable and the horizontal cabling.

1.3.5 Entrance Facility (EF) (Telecommunications) (can be within Main TR)

An entrance to the building for both private and public network service cables (including wireless) including the entrance point at the building wall and continuing to the equipment room.

1.3.6 Equipment Room (ER) (Telecommunications)(can be within a TR/ CR)

An environmentally controlled centralized space for telecommunications equipment that serves the occupants of a building. Equipment housed therein is considered distinct from a telecommunications room because of the nature of its complexity.

1.3.7 Open Cable

Cabling that is not run in an enclosed raceway as defined by NFPA 70. This refers to cabling that is "open" to the space in which the cable has been installed and is therefore exposed to the environmental conditions associated with that space, such as wire basket tray, cable tray, J-hooks, D-rings, or bridal rings. D rings should only be used in the TR/CR for cable management and J-hooks/bridal rings shall not be used except in minor renovations where they exist already.

1.3.8 Open Office

A floor space division provided by furniture, moveable partitions, or other means instead of by building walls, normally over 100 square feet.

1.3.9 Pathway

A physical infrastructure utilized for the placement and routing of telecommunications cable.

1.4 SYSTEM DESCRIPTION

The building telecommunications cabling and pathway system shall include permanently installed backbone and horizontal cabling, horizontal and backbone pathways, service entrance facilities, work area pathways, telecommunications outlet assemblies, conduit, raceway, and hardware for splicing, terminating, and interconnecting cabling necessary to transport telephone and data, and other communications systems (including LAN. A/V, intercom, PA, CATV, CCTB, and WiFi) between equipment items in a building. The horizontal system shall be wired in a star topology from the telecommunications work area to the floor distributor /BD /TR /ER or campus distributor at the center or hub of the star. The backbone cabling and pathway system includes intrabuilding and interbuilding interconnecting cabling, pathway, and terminal hardware. The intrabuilding backbone provides connectivity from the floor distributors to the building distributors or to the campus distributor and from the building distributors to the campus distributor as required. The backbone system shall be wired in a star topology with the campus distributor (Area Distribution Node) at the center or hub of the star.

The interbuilding backbone system provides connectivity between the campus distributors and is specified in Section 33 82 00 TELECOMMUNICATIONS OUTSIDE PLANT (OSP). Provide telecommunications pathway systems referenced herein as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM, current TIA-569, and MCB CL Base Telephone (TSD) guidance. The telecommunications contractor must coordinate with the MCB CL Base Telephone via Contracting or Construction Manager / Project Manager concerning access to and configuration of telecommunications spaces. The telecommunications contractor may be required to coordinate work effort within the telecommunications spaces with the electrical sub and general contractor, Resident Officer in Charge of Construction (ROICC) and MCB CL Base Telephone (TSD).

1.5 SUBMITTALS

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Telecommunications Drawings; G

Telecommunications Space Drawings; G

In addition to Section 01 33 00 SUBMITTAL PROCEDURES, provide shop drawings in accordance with paragraph SHOP DRAWINGS.

SD-03 Product Data

Telecommunications Cabling (backbone and horizontal); G

Patch Panels; G

Telecommunications Outlet/Connector Assemblies; G

Equipment Support Frame; G

Connector Blocks; G

Submittals shall include the manufacturer's name, trade name, place of manufacture, and catalog model or number. Include performance and characteristic curves. Submittals shall also include applicable federal, military, industry, and technical society publication references. Should manufacturer's data require supplemental information for clarification, the supplemental information shall be submitted as specified in paragraph REGULATORY REQUIREMENTS and as required in Section 01 33 00 SUBMITTAL PROCEDURES.

SD-06 Test Reports

Telecommunications Cabling Testing; G

SD-07 Certificates

Telecommunications Contractor Qualifications; G

Key Personnel Qualifications; G

Manufacturer Qualifications; G

Test Plan; G

SD-09 Manufacturer's Field Reports

Factory Reel Tests; G

SD-10 Operation and Maintenance Data

Telecommunications Cabling and Pathway System Data Package 5; G

SD-11 Closeout Submittals

Record Documentation; G

1.5.1 ADDITIONAL SUBMITTAL REQUIREMENTS

All submittals of material, equipment and design must be approved by the Telecommunications Support Division (TSD) prior to installing any telecommunications wiring, equipment, or power to support communications.

1.6 QUALITY ASSURANCE

1.6.1 Shop Drawings

In exception to Section 01 33 00 SUBMITTAL PROCEDURES, submitted plan drawings shall be a minimum of 11 by 17 inches in size using a minimum scale of 1/8 inch per foot, except as specified otherwise. Include wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure a coordinated installation. Wiring diagrams shall identify circuit terminals and indicate the internal wiring for each item of equipment and the interconnection between each item of equipment. Drawings shall indicate adequate clearance for operation, maintenance, and replacement of operating equipment devices. Submittals shall include the nameplate data, size, and capacity. Submittals shall also include applicable federal,

military, industry, and technical society publication references.

1.6.1.1 Telecommunications Drawings

Provide registered communications distribution designer (RCDD) approved, drawings in accordance with TIA-606. The identifier for each termination and cable shall appear on the drawings. Drawings shall depict final telecommunications installed wiring system infrastructure in accordance with TIA-606. The drawings should provide details required to prove that the distribution system shall properly support connectivity from the EF /BD telecommunications and ER /TR telecommunications, CD's, and FD's to the telecommunications work area outlets. Provide a plastic laminated schematic of the as-installed telecommunications cable system showing cabling, CD's, BD's, FD's, and the EF and ER for telecommunications keyed to floor plans by room number. Mount the laminated schematic in the EF telecommunications space as directed by the Contracting Officer. The following drawings shall be provided as a minimum:

a. T1 - Layout of complete building per floor - Building Area/Serving Zone Boundaries, Backbone Systems, and Horizontal Pathways. Layout of complete building per floor. The drawing indicates location of building areas, serving zones, vertical backbone diagrams, telecommunications rooms, access points, pathways, grounding system, and other systems that need to be viewed from the complete building perspective.

b. T2 - Serving Zones/Building Area Drawings - Drop Locations and Cable Identification (ID'S). Shows a building area or serving zone. These drawings show drop locations, telecommunications rooms, dedicated electrical for communications equipment, access points and detail call outs for common equipment rooms and other congested areas.

c. T4 - Typical Detail Drawings - Faceplate Labeling, Firestopping, Americans with Disabilities Act (ADA), Safety, Department of Transportation (DOT). Detailed drawings of symbols and typicals such as faceplate labeling, faceplate types, faceplate population installation procedures, detail racking, and raceways.

1.6.1.2 Telecommunications Space Drawings

Provide T3 drawings in accordance with TIA-606 that include telecommunications rooms plan views, pathway layout (cable tray, racks, ladder-racks, etc.), mechanical/electrical layout, and cabinet, rack, backboard and wall elevations. Drawings shall show layout of applicable equipment including incoming cable stub or connector blocks, building protector assembly, outgoing cable connector blocks, dedicated mechnical/electrical, patch panels and equipment spaces and cabinet/racks. Drawings shall include a complete list of equipment and material, equipment rack details, proposed layout and anchorage of equipment and appurtenances, and equipment relationship to other parts of the work including clearance for maintenance and operation. Drawings may also be an enlargement of a congested area of T1 or T2 drawings.

1.6.2 Telecommunications Qualifications

Work under this section shall be performed by and the equipment shall be provided by the approved telecommunications contractor and key personnel. Qualifications shall be provided for: the telecommunications system contractor, the telecommunications system installer, and the supervisor

(if different from the installer). A minimum of 30 days prior to installation, submit documentation of the experience of the telecommunications contractor and of the key personnel.

1.6.2.1 Telecommunications Contractor

The telecommunications contractor shall be a firm which is regularly and professionally engaged in the business of the applications, installation, and testing of the specified telecommunications systems and equipment. The telecommunications contractor shall demonstrate experience in providing successful telecommunications systems within the past 3 years of similar scope and size. Submit documentation for a minimum of three and a maximum of five successful telecommunication system installations for the telecommunications contractor. IAW Section on QC Specialists; a Telecommunications Systems QC Specialist is required on site, full time with 10 years minimum experience in telecom installation and experience. Specialist shall be very familiar with UFGS Divisions 27, 28, 33 concerning communications systems work and installation.

1.6.2.2 Key Personnel

Provide key personnel who are regularly and professionally engaged in the business of the application, installation and testing of the specified telecommunications systems and equipment. There may be one key person or more key persons proposed for this solicitation depending upon how many of the key roles each has successfully provided. Each of the key personnel shall demonstrate experience in providing successful telecommunications systems within the past 3 years.

Supervisors and installers assigned to the installation of this system or any of its components shall be Building Industry Consulting Services International (BICSI) Registered Cabling Installers, Technician Level. Submit documentation of current BICSI certification for each of the key personnel.

In lieu of BICSI certification, supervisors and installers assigned to the installation of this system or any of its components shall have a minimum of 3 years experience in the installation of the specified copper and fiber optic cable and components. They shall have factory or factory approved certification from each equipment manufacturer indicating that they are qualified to install and test the provided products. Submit documentation for a minimum of three and a maximum of five successful telecommunication system installations for each of the key personnel. Documentation for each key person shall include at least two successful system installations provided that are equivalent in system size and in construction complexity to the telecommunications system proposed for this solicitation. Include specific experience in installing and testing telecommunications systems and provide the names and locations of at least two project installations successfully completed using optical fiber and copper telecommunications cabling systems. All of the existing telecommunications system installations offered by the key persons as successful experience shall have been in successful full-time service for at least 18 months prior to the issuance date for this solicitation. Provide the name and role of the key person, the title, location, and completed installation date of the referenced project, the referenced project owner point of contact information including name, organization, title, and telephone number, and generally, the referenced project description including system size and construction complexity.

Indicate that all key persons are currently employed by the telecommunications contractor, or have a commitment to the telecommunications contractor to work on this project. All key persons shall be employed by the telecommunications contractor at the date of issuance of this solicitation, or if not, have a commitment to the telecommunications contractor to work on this project by the date that the bid was due to the Contracting Officer.

Note that only the key personnel approved by the Contracting Officer in the successful proposal shall do work on this solicitation's telecommunications system. Key personnel shall function in the same roles in this contract, as they functioned in the offered successful experience. Any substitutions for the telecommunications contractor's key personnel requires approval from The Contracting Officer.

1.6.2.3 Minimum Manufacturer Qualifications

Cabling, equipment and hardware manufacturers shall have a minimum of 3 years experience in the manufacturing, assembly, and factory testing of components which comply with TIA-568.1, TIA-568.2 and TIA-568.3.

1.6.3 Test Plan

Provide a complete and detailed test plan for the telecommunications cabling system including a complete list of test equipment for the components and accessories for each cable type specified, 60 days prior to the proposed test date. Include procedures for certification, validation, sample report, and testing.

1.6.4 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "shall" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70 manufacturer recommendations, installation manual, best known industry practices, and industry standards, unless more stringent requirements are specified or indicated.

1.6.5 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products shall have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period shall include applications of equipment and materials under similar circumstances and of similar size. The product shall have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items shall be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.6.5.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.6.5.2 Material and Equipment Manufacturing Date

Products manufactured more than 1 year prior to date of delivery to site shall not be used, unless specified otherwise.

1.7 DELIVERY AND STORAGE

Provide protection from weather, moisture, extreme heat and cold, dirt, dust, and other contaminants for telecommunications cabling and equipment placed in storage.

1.8 ENVIRONMENTAL REQUIREMENTS

Connecting hardware shall be rated for operation under ambient conditions of 32 to 140 degrees F and in the range of 0 to 95 percent relative humidity, noncondensing. All telecommunications spaces shall follow TIA-569 design.

1.9 WARRANTY

The equipment items shall be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

1.10 MAINTENANCE

1.10.1 Operation and Maintenance Manuals

Commercial off the shelf manuals shall be furnished for operation, installation, configuration, and maintenance of products provided as a part of the telecommunications cabling and pathway system, Data Package 5. Submit operations and maintenance data in accordance with Section 01 78 23 OPERATION AND MAINTENANCE DATA and as specified herein not later than 2 months prior to the date of beneficial occupancy. In addition to requirements of Data Package 5, include the requirements of paragraphs TELECOMMUNICATIONS DRAWINGS, TELECOMMUNICATIONS SPACE DRAWINGS, and RECORD DOCUMENTATION. Ensure that these drawings and documents depict the as-built configuration. Also provide copies of all Telecommunications manuals to TSD.

1.10.2 Record Documentation

Provide T5 drawings including documentation on cables and termination hardware in accordance with TIA-606. T5 drawings shall include schedules to show information for cut-overs and cable plant management, patch panel layouts and cover plate assignments, cross-connect information and connecting terminal layout as a minimum. T5 drawings shall be provided on electronic media using Windows based computer cable management software. Provide the following T5 drawing documentation as a minimum:

a. Cables - A record of installed cable shall be provided in accordance with TIA-606. The cable records shall include the required data fields for each cable and complete end-to-end circuit report for each complete circuit from the assigned outlet to the entry facility in accordance with TIA-606. Include manufacture date of cable with submittal.

b. Termination Hardware - A record of installed patch panels, cross-connect points, distribution frames, terminating block arrangements and type, and outlets shall be provided in accordance with TIA-606. Documentation shall include the required data fields as a minimum in accordance with TIA-606.

PART 2 PRODUCTS

2.1 COMPONENTS

Components shall be UL or third party certified. Where equipment or materials are specified to conform to industry and technical society reference standards of the organizations, submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. The certificate shall state that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard. Provide a complete system of telecommunications cabling and pathway components using star topology. Provide support structures and pathways, complete with outlets, cables, connecting hardware and telecommunications cabinets/racks. Cabling and interconnecting hardware and components for telecommunications systems shall be UL listed or third party independent testing laboratory certified, and shall comply with NFPA 70 and conform to the requirements specified herein.

2.2 TELECOMMUNICATIONS PATHWAY

Provide telecommunications pathways in accordance with TIA-569 and as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide system furniture pathways in accordance with UL 1286.

2.2.1 PATHWAYS ABOARD CAMP LEJEUNE GREATER AREA, INCLUDING MCAS NEW RIVER

Pathway shall be conduit, cable tray, or modular access flooring that provides protection for cabling. Under floor duct, free laying, case work boxes, and wireway shall not be used. Cantilever-type center hung tray or Poke-Thru devices shall not be used. J-hooks/D-rings/bridal rings and other open face type cable pathways are not authorized except in minor renovations or to continue like existing system. Provide grounding and bonding as required by TIA-607. Cable tray wiring shall comply with NFPA 70. All conduits entering the communications room should be grouped and consolidated.

Individual conduits can be "Home Run" or stubbed to cable tray using approved pull boxes after every 180 degrees of bends, all shall have bonding bushing/plastic insert, and shall extend down from the ceiling to 3 to 4 inches onto the backboard, and will be bonded to the TMGB or TGB by a minimum number 6 green sheathed stranded conductors. All penetrations will be sealed in accordance with code (fire-stopping). A minimum of two

3 inch conduits will be installed overhead between the main communications room and other communication rooms, if installed below slab they are considered OSP and fall under Section 33 82 00 TELECOMMUNICATIONS, OUTSIDE PLANT (OSP). Distribution Enclosures shall not be used as a pull box and will only be approved for their intended use.

2.2.2 WORK AREA PATHWAYS

Comply with TIA-569, except minimum 1 1/4 inch diameter conduit will be used. Each work area outlet must have its own conduit to the comm room or nearest cable tray, multiple outlets cannot be ganged together except in a floor box, MUTOA, or system furniture. System furniture pathways shall comply with UL 1286. In system furniture that blocks access to or is distant from the communications wall outlets: each system furniture desk/cubical shall be equipped with system furniture communications outlets that are plugged into the communications wall outlets. All ports should be extended into the furniture.

2.2.3 TELEPHONE OUTLET BOXES

Communications outlet boxes shall be placed in all work areas and any areas that can be converted to work areas; so any furniture package configuration will have a connection with a 6' base cord. Recommended practice is 6" to the left or right of (the outside edge of) electrical outlet box in workable office areas or any area that could be converted into workable office area such as a large storage closet; also any conference room should have one floor box and one box just above the ceiling. Boxes shall be standard type 5 inches square by 2 7/8 inches deep for CAT6 with 1 1/4 inch diameter knock-outs, with a single gang plaster ring. Mount flush in finished walls or 3 to 12 inches above ceiling tile. Outlet boxes for wall-mounted telephones shall be 2 by 4 by 2-1/8 inches deep with 1 CAT6 cable terminated in a standard CAT6 studded wall phone plate; mounted at ADA required height. Outlet boxes for work counter area or case work shall be mounted through or above casework/ counter, typically at a height 48 inches above finished floor. Outlet boxes installed for CCTV, Wireless access points, and CATV shall contain two CAT 6 cables. Outlet boxes should have their own individual conduit to the comm room or nearest cable tray. Outlets installed in floor shall be communications floor boxes large enough to support a surge of users with proper cable/ port protection and ports that are in multiples of 4. For raised access flooring, boxes shall be below the floor with an access cover flush with the floor. Tombstones above the floor or boxes below floor that require removal of the floor panels to access are not allowed. Floor boxes and under slab cabling should not be used in wet areas. Conduit or furniture managed pathways fed from above the wet area should be used. Multi-user Telecommunications Outlet Assembly i.e. Multimedia Outlet Assemblies (MUTOA) should be placed where best suited for the furniture used in open office spaces and maintain a clearance more than 6" from electrical or 2nd MUTOA for proper operation.

2.3 TELECOMMUNICATIONS CABLING

Cabling shall be UL listed for the application and shall comply with TIA-568.0, TIA-568.1, TIA-568.2, TIA-568.3 and NFPA 70. Provide a

labeling system in accordance with the manufacturer and local AHJ guidance for cabling as required by TIA-606 and UL 969. Confirm labeling is compatible with Base service provider requirements. Ship cable on reels or in boxes bearing manufacture date for for unshielded twisted pair (UTP) in accordance with ICEA S-90-661 and optical fiber cables in accordance with ICEA S-83-596 for all cable used on this project. Cabling manufactured more than 12 months prior to date of installation shall not be used.

2.3.1 Backbone Cabling

2.3.1.1 Backbone Copper

Copper backbone cable and riser shall be solid conductor, 24 AWG, 100 ohm, 100 -pair, Category 3, UTP, in accordance with ICEA S-90-661, TIA-568.1, TIA-568.2 and UL 444, formed into 25 pair binder groups covered with a gray thermoplastic jacket and overall metallic shield if required for additional protection. Cable shall be imprinted with manufacturers name or identifier, flammability rating, gauge of conductor, transmission performance rating (category designation) at regular length marking intervals in accordance with ICEA S-90-661. Sufficient pair count of CAT 3 or 5, as required shall be installed between the MDF and each of the IDF's. Provide plenum (CMP), riser (CMR), or general purpose (CM or CMG)communications rated cabling in accordance with NFPA 70. Substitution of a higher rated cable shall be permitted in accordance with NFPA 70. Any backbone copper run in under slab conduit shall be rated for outdoor use in accordance with AHJ and have lightning protection at both ends.

2.3.1.2 Backbone Optical Fiber

Provide in accordance with ICEA S-83-596, TIA-568.3, UL 1666 and NFPA 70. Cable shall be imprinted with fiber count, fiber type and aggregate length at regular intervals not to exceed 40 inches.

Provide the number of strands indicated, (but not less than 12 strands between the main telecommunication rooms or secure racks/cabinets), of single-mode, tight buffered fiber optic cable.

Provide tight buffered fiber optic multimode, 62.5/125-um diameter(OM1) cable as indicated.

Provide plenum (OFNP), riser (OFNR), or general purpose (OFN or OFNG) rated non-conductive, fiber optic cable in accordance with NFPA 70. Substitution of a higher rated cable shall be permitted in accordance with NFPA 70. The cable cordage jacket, fiber, unit, and group color shall be in accordance with TIA/EIA-598.

Provide plenum (OFNP) riser (OFNR), or general purpose (OFN or OFNG) rated non-conductive, fiber optic cable in accordance with NFPA 70. Substitution of a higher rated cable shall be permitted in accordance with NFPA 70. The cable cordage jacket, fiber, unit, and group color shall be in accordance with TIA/EIA-598.

2.3.2 Horizontal Cabling

Provide horizontal cable in compliance with NFPA 70 and performance characteristics in accordance with TIA-568.1.

2.3.2.1 Horizontal Copper

Provide a minimum of four horizontal copper cables to each work area outlet (faceplate), UTP, 100 ohm in accordance with TIA-568.2, UL 444, ANSI/NEMA WC 66, ICEA S-90-661 . Provide four each individually twisted pair, minimum size 24 AWG conductors, Category 6 or higher, with a green thermoplastic jacket for all unclassified ports (color and cable type for classified services shall be in accordance with current CNSSAM TEMPEST RED/BLACK Installation documentation including Table 1 (below). Cable shall be imprinted with manufacturers name or identifier, flammability rating, gauge of conductor, transmission performance rating (category designation) and length marking at regular intervals in accordance with ICEA S-90-661. Provide plenum (CMP), riser (CMR), or general purpose (CM or CMG) communications rated cabling in accordance with NFPA 70. Substitution of a higher rated cable shall be permitted in accordance with NFPA 70. Cables installed in conduit within and under slabs are not recommended but can be used if approved by local AHJ and shall be UL listed and labeled for wet locations in accordance with NFPA 70. Contact AHJ for special requirements on classified service, under slab cabling, using water block, and any item not covered in this document.

Table 1 - (U/FOUO) Cable Color Scheme

Classification Level	Cable Color
Unclassified	Green
Collateral Confidential	Blue
Collateral Secret	Red
Collateral Top Secret	Orange
Special Category	Yellow

2.3.2.2 Horizontal Optical Fiber

Provide optical fiber horizontal cable in accordance with ICEA S-83-596and TIA-568.3. Cable shall be tight buffered, single-mode, 8/125-um diameter, OS1. Cable shall be imprinted with manufacturer, flammability rating and fiber count at regular intervals not to exceed 40 inches.

Provide plenum (OFNP), riser (OFNR), or general purpose (OFN or OFNG) rated non-conductive, fiber optic cable in accordance with NFPA 70. Substitution of a higher rated cable shall be permitted in accordance with NFPA 70. Cables installed in conduit within and under slabs be UL listed and labeled for wet locations in accordance with NFPA 70. The cable jacket shall be of single jacket construction with color coding of cordage jacket, fiber, unit, and group in accordance with TIA/EIA-598.

2.3.3 Work Area Cabling

2.3.3.1 Work Area Copper

Provide work area copper cable in accordance with TIA-568-C.2, with a green on odd numbered and green on even numbered thermoplastic jacket for

unclassified services (classified color code shall be in accordance with current CNNSSAM TEMPEST RED/BLACK Installation documentation).

Communications CAT6 twisted pair shall have a minimum of 12 inch slack cable loosely coiled into the communications outlet boxes. Minimum manufacturer's bend radius for each type of cable shall not be exceeded. All communications work area outlet boxes should have 4 cables to a double gang box (no rough in or empty conduit for future use allowed).

2.3.3.2 Work Area Optical Fiber

Fiber to the work area is not recommended unless all end devices (computers, printers, phones) have a fiber network interface. Provide optical work area cable in accordance with TSD (Telecommunications Support Division), AHJ, Horizontal Optical Fiber section, and TIA-568-C.3.

2.4 TELECOMMUNICATIONS SPACES

Provide connecting hardware and termination equipment in the telecommunications entrance facility and telecommunication equipment rooms to facilitate installation as shown on design drawings for terminating and cross-connecting permanent cabling. Provide telecommunications interconnecting hardware color coding in accordance with TIA-606.

Space shall be designed per TIA-569 section 6.4.4 Design, unless a local waiver is provided by the AHJ which is TSD aboard Camp Lejeune. Communications distribution room min 10'x10' but could be much larger depending on building size, usable square footage served, multiple networks, classified networks, and customer requirements. Communications rooms shall be centrally located unless there are multiple Communication rooms, and then each room should be centrally located within the area served. Communications Rooms shall not share or be on a wet wall. Generally, the space should be sized to approximately 1.1 percent of the area it serves. For example, a 10,000 sq feet (929 sq m) area should be served by a minimum of one 10 ft x 11 ft (3 m x 3.4 m) Communications room. Access to Rooms shall be from a common area such as a hallway and door shall swing out.

Additional/Multiple communications rooms are required if the usable floor space to be served exceeds 10,000 square feet, or the cable length between the horizontal cross-connect and the communications outlet, including slack and vertical distance, exceeds 295 feet. Multiple communications rooms and IDFs shall be stacked and connected by a minimum of two 3 inch conduits overhead. If under slab it is considered Outside Plant and 3 way 4" shall be used per Section 33 82 00 TELECOMMUNICATIONS, OUTSIDE PLANT (OSP) with proper surge protection at both ends.

The minimum clear height in the room shall be 2.4 m (8 ft) without obstructions. The height between the finished floor and the lowest point of the ceiling should be a minimum of 3 m (10 ft) to accommodate overhead pathways. The flooring shall be sealed concrete or Electro Static Dissipating flooring to reduce dust and static electricity; no carpet or VCT tile.

Two separate dedicated 20 amp electrical circuits in one quadruplex outlet and one 30 amp will be installed above / behind but not attached to each communications equipment rack. Vertical Power Distribution Units should be plugged into the dedicated power and mounted to the back side of the telecomm racks/ cabinets.

OSP conduits and other telecomm equipment shall on the longest furthest wall from the door and to the far left of the communications backboard while facing it (behind the racks). There should not be an electrical panel within the communications room unless it serves only the room, and it should be located as close to the door as possible.
The room requires a lockable door keyed or key padded to restrict access to MCIEAST-MCB G-6 personnel only. Room shall not have any windows or skylights. At least one wall, where the point of presence is located, and two adjacent walls should be covered with fire rated plywood backboard for mounting equipment; additional boards may be needed for mounting additional equipment.

Light, as measured within the communications room, should be a minimum of 500 lux (50 foot-candles). Lighting design should seek to minimize shadows within the telecommunications room (minimum two light fixtures).
Equipment not related to the support of the communications room (e.g., piping, ductwork, pneumatic tubing) shall not be installed in, pass through, or enter the telecommunications room.

Equipment related to the support of the communications room (e.g., piping, ductwork, HVAC drains, and dedicated power) shall be installed in support of the communications equipment and not pose a drip/moisture/trip hazard and be usable as intended.

2.4.1 Backboards

Provide void-free, interior grade A-C plywood 3/4 inch thick 4 by 8 feet as indicated. Fire stamp shall be clearly visible. Backboards shall be provided on the longest furthest wall from the door and a minimum of two adjacent walls, and anywhere mounting is needed in the telecommunication spaces.

2.4.2 Equipment Support Frame

Provide in accordance with ECIA EIA/ECA 310-E and UL 50. Steel construction shall be treated to resist corrosion.

a. Bracket, wall mounted, 8 gauge aluminum (for buildings with very low jack/pair count and no secured electronic equipment requirement). Provide hinged bracket compatible with 482.6 mm 19 inches panel mounting (must be in a secured room).

b. Used within a comm/distribution room, racks, wall or floor mounted modular type, 16 gauge steel or 11 gauge aluminum construction, minimum, treated to resist corrosion (4 post floor mount not allowed). Provide rack with vertical and horizontal cable management channels, top and bottom cable troughs, grounding lug, with surge protected power strips for dedicated power 20/30 amp receptacles. Racks shall be large enough to support all telephone/data equipment required plus 25 percent spare and shall have a maximum of 7' height. Rack shall be compatible with 482.6 mm 19 inches panel mounting and must be in a secured communications room.

c. Used when there is no comm/distribution room due to low user count, cabinets, freestanding modular type, 16 gauge steel or 11 gauge aluminum construction, minimum, treated to resist corrosion. Cabinet shall have removable and lockable side panels, front and rear doors, and have adjustable feet for leveling. All cabinets shall be

keyed to current TSD key and large enough to support all telephone/data equipment required in the building plus 25% for future expansion. A backboard for mounting equipment is still needed when a cabinet is installed. Cabinet shall be mounted to the far right of the board to allow space for OSP cable, lightning protection, and bus bar to be installed on the board's far left. Dedicated power shall be within the cabinet and on the backboard. Cabinet shall be vented in the roof and rear door. Cabinet shall have cable access in the roof and base and be compatible with 482.6 mm 19 inches panel mounting. Provide cabinet with grounding bar, rack mounted 15 cu. m 550 CFM fan with filter and a surge protected power strips with 20/30 amp receptacles.

d. Used when there is no comm/distribution room due to low user count, cabinets, wall-mounted modular type, 16 gauge steel or 11 gauge aluminum construction, minimum, treated to resist corrosion. Cabinet shall have a lockable front door, louvered side panels, 7 cu. m 250 CFM rack mounted fan, ground lug, and top and bottom cable access. Cabinets shall be no smaller than 24"W X 48"H X 30"D, shall be keyed to current TSD key, and large enough to support all telephone/data equipment required in the building plus 25% for future expansion. Dedicated electrical outlets should be installed within the cabinet. A backboard for mounting equipment is still needed when a cabinet is installed. Cabinet shall be mounted to the far right of the board to allow space for OSP cable, lightning protection, and bus bar to be installed on the board's far left. Cabinet shall be compatible with 482.6 mm 19 inches panel mounting. All cabinets shall be keyed alike. A surge protected power strip with 6 duplex 20 amp receptacles shall be provided within the cabinet.

2.4.3 Connector Blocks

Provide insulation displacement connector (IDC) Type 110, 50 pair, rack mounted blocks, compatible with industry standard 110 blade punch down tool, designed for Category 3 and higher systems. Provide blocks for the number of horizontal and backbone cables terminated on the block plus 25 percent spare. Also provide sufficient blocks for cross connects to all IDFs.

2.4.4 Cable Guides

Provide cable guides specifically manufactured for the purpose of routing cables, wires and patch cords horizontally and vertically on 19 inches equipment racks and telecommunications backboards. Cable guides of ring or bracket type devices mounted on rack panels for horizontal cable management and individually mounted for vertical cable management. Mount cable guides with screws, or nuts and lockwashers. Cable guides are not to be used outside of the communications room.

2.4.5 Patch Panels

Provide ports for the number of horizontal and backbone cables terminated on the panel plus 25 percent spare. Provide pre-connectorized optical fiber and copper patch cords for patch panels. Provide patch cords of various appropriate lengths and as complete assemblies, with matching connectors as specified. Provide fiber optic patch cables with crossover

orientation in accordance with TIA-568.3. Patch cords shall meet minimum performance requirements specified in TIA-568.1, TIA-568.2 and TIA-568.3 for cables, cable length and hardware specified. Classified service may require shielded jack sets and panels as approved by AHJ.

2.4.5.1 Modular to 110 Block Patch Panel

Provide in accordance with TIA-568.1 and TIA-568.2. Panels shall be third party verified and shall comply with EIA/TIA Category 6 requirements. Panel shall be constructed of 0.09 inches minimum aluminum and shall be rack mounted and compatible with an ECIA EIA/ECA 310-E 19 inches equipment rack. Panel shall provide 48 non-keyed, 8-pin modular ports, wired to T568A. Patch panels shall terminate the building cabling on Type 110 IDCs and shall utilize a printed circuit board interface. The rear of each panel shall have incoming cable strain-relief and routing guides. Panels shall have each port factory numbered and be equipped with laminated plastic nameplates above each port.

2.4.5.2 Fiber Optic Patch Panel

Provide panel for maintenance and cross-connecting of optical fiber cables. Panel shall be constructed of 16 gauge steel or 11 gauge aluminum minimum and shall be rack mounted and compatible with a ECIA EIA/ECA 310-E 19 inches equipment rack. Each panel shall provide 12 single-mode adapters as duplex SC in accordance with TIA/EIA-604-3 with zirconia ceramic alignment sleeves. Provide dust cover for unused adapters. The rear of each panel shall have a cable management tray a minimum of 8 inches deep with removable cover, incoming cable strain-relief and routing guides. Panels shall have each adapter factory numbered and be equipped with laminated plastic nameplates above each adapter. When populating the panel working left to right start with OSP feed, SM ISO to IDF, MM ISO to IDF, lastly row to row within same comm room.

2.4.6 Optical Fiber Distribution Panel

Rack mounted optical fiber distribution panel (OFDP) shall be constructed in accordance with ECIA EIA/ECA 310-E utilizing 16 gauge steel or 11 gauge aluminum minimum. Panel shall be divided into two sections, distribution and user. Distribution section shall have strain relief, routing guides, splice tray and shall be lockable, user section shall have a cover for patch cord protection. Each panel shall provide 12 single-mode pigtails and adapters. Provide adapters as duplex SC with zirconia ceramic alignment sleeves. Provide dust covers for adapters. Provide patch cords as specified in the paragraph PATCH PANELS.

2.5 TELECOMMUNICATIONS OUTLET/CONNECTOR ASSEMBLIES

2.5.1 Outlet/Connector Copper

Outlet/connectors shall comply with FCC Part 68, TIA-568.1, and TIA-568.2. UTP outlet/connectors shall be UL 1863 listed, non-keyed, 8-pin modular, constructed of high impact rated thermoplastic housing and shall be third party verified and shall comply with TIA-568.2 Category 6 requirements. Outlet/connectors provided for UTP cabling shall meet or exceed the requirements for the cable provided and have the capability to be installed from the front or rear of the faceplate/patch panel.

Outlet/connectors shall be terminated using a standard IDC connector, color-coded for both TIA-568A and TIA-568B wiring. Each outlet/connector

shall be wired T568A. UTP/STP outlet/connectors shall comply with TIA-568.2 for 750 mating cycles. UTP outlet/connectors installed in outdoor or marine environments shall be jell-filled type containing an anti-corrosive, memory retaining compound.

2.5.2 Optical Fiber Adapters(Couplers)

Provide optical fiber adapters suitable for duplex SC in Accordance with TIA/EIA-604-3 with zirconia ceramic alignment sleeves, as indicated. Provide dust cover for adapters. Optical fiber adapters shall comply with TIA-455-21 for 500 mating cycles.

2.5.3 Optical Fiber Connectors

Provide in accordance with TIA-455-21. Optical fiber connectors shall be duplex SC in accordance with TIA/EIA-604-3 with zirconia ceramic ferrule, epoxyless crimp style compatible with 8/125 single-mode fiber. The connectors shall provide a maximum attenuation of 0.3 dB at 1550 nm with less than a 0.2 dB change after 500 mating cycles.

2.5.4 Cover Plates

Telecommunications cover plates shall comply with UL 514C, and TIA-568.1, TIA-568.2, ; flush design constructed of high impact thermoplastic material to match color of receptacle/switch cover plates specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Additionally, it shall be labeled as to its function and color coded (color code shall be in accordance with current CNNSSAM TEMPEST RED/BLACK Installation documentation). Provide labeling in accordance with the paragraph LABELING in this section.

2.6 MULTI-USER TELECOMMUNICATIONS OUTLET ASSEMBLY (MUTOA)

Provide MUTOA(s) in accordance with TIA-568.1 and local guidance. Ensure proper separation from other MUTOAs, networks, and power.

For Modular Furniture, provide horizontal cabling from the MUTOA to an adaptor plate in the Modular Furniture. The MUTOA should be limited to serving a maximum of six work areas with 2 cables each for a total of 12 cables.

2.7 TERMINAL CABINETS

Construct of zinc-coated sheet steel, 36 by 24 by 6 inches deep. Trim shall be fitted with hinged door and locking latch. Doors shall be maximum size openings to box interiors. Boxes shall be provided with 5/8 inch backboard with two-coat varnish finish. Match trim, hardware, doors, and finishes with panelboards. Provide label and identification systems for telecommunications wiring and components consistent with TIA-606.

2.8 GROUNDING AND BONDING PRODUCTS

Provide in accordance with UL 467, TIA-607, and NFPA 70. Components shall be identified as required by TIA-606. Provide ground rods, bonding conductors, and grounding busbars as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. The preferred ground for the Telephone Main Grounding Bus (TMGB) bar will be to the Main electrical Distribution Panel (MDP) bus bar and building steel. In most cases, but not all; a #6 AWG bonding conductor is recommended for telecommunications. All grounding

and bonding conductors within the Telecommunications room will be green sheathed copper conductor, stranded, and labeled as suitable for use as such and tagged "DO NOT REMOVE". All grounding and bonding conductors running out of the Telecommunications room should be protected in conduit or attached to the outside of the cable tray and sized according to references.

The minimum size of the TMGB shall be no smaller than 4" by 10" (could be much longer as needed) by 1/4 inch thick; bus bar should be factory made and factory drilled, not fabricated or drilled onsite. All bonding and grounding terminations shall be irreversible and secured with a double hole crimp termination. Do not exceed minimum bend radius on bonding and grounding conductors. Do not put bonding conductors in conduit and on backboard (should be on backboard OR in conduit, not both). Mount Bus Bar to far left of telecomm backboard at approximately 60-70" AFF.

2.9 FIRESTOPPING MATERIAL

Provide as specified in Section 07 84 00 FIRESTOPPING.

2.10 MANUFACTURER'S NAMEPLATE

Each item of equipment shall have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.11 FIELD FABRICATED NAMEPLATES

ASTM D709. Provide laminated plastic nameplates for each equipment enclosure, relay, switch, and device; as specified or as indicated on the drawings. Each nameplate inscription shall identify the function and, when applicable, the position. Nameplates shall be melamine plastic, 0.125 inches thick, white with black center core. Surface shall be matte finish. Corners shall be square. Accurately align lettering and engrave into the core. Minimum size of nameplates shall be one by 2.5 inches. Lettering shall be a minimum of 0.25 inches high normal block style.

2.12 TESTS, INSPECTIONS, AND VERIFICATIONS

2.12.1 Factory Reel Tests

Provide documentation of the testing and verification actions taken by manufacturer to confirm compliance with TIA-568.1, TIA-568.2, TIA-568.3, TIA-526-7 for single mode optical fiber cables.

PART 3 EXECUTION

3.1 INSTALLATION

Install telecommunications cabling and pathway systems, including the horizontal and backbone cable, pathway systems, telecommunications outlet/connector assemblies, and associated hardware in accordance with NECA/BICSI 568, TIA-568.1, TIA-568.2, TIA-568.3, TIA-569, NFPA 70, manufacturer instructions, current industry best practices, local guidance, and UL standards as applicable (except 1-1/4" conduit should be used for individual WAO).

Provide cabling in a star topology network. Pathways and outlet boxes

shall be installed as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM and local guidance. Standard type 5" x 5" x 2 7/8" square box with a single gang plaster ring shall be used except in concrete or concrete masonry units (CMU) or in slab where a standard 4 11/16" square or a floor box will be used. Mount flush in finished walls at height indicated by drawings and with proper clearances from other networks and power systems. Depth of boxes shall be large enough to allow manufacturer's recommended conductor bend radii, normally 2 7/8" depth.

Install telecommunications cabling with copper media in accordance with the following criteria to avoid potential electromagnetic interference between power and telecommunications equipment.

The interference ceiling shall not exceed 3.0 volts per meter measured over the usable bandwidth of the telecommunications cabling. (normal minimum clearance distances of 4 feet from motors, generators, frequency converters, transformers, x-ray equipment or uninterrupted power system, 300 mm (12 in) from power conduits and cable systems, 125 mm (5 inches) from fluorescent or high frequency lighting system fixtures). Cabling shall be run with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.

3.1.1 Cabling

Install UTP, and optical fiber telecommunications cabling system as detailed in TIA-568.1, TIA-568.2, TIA-568.3. Screw terminals shall not be used except where specifically indicated on plans. Use an approved insulation displacement connection (IDC) tool kit for copper cable terminations. Do not untwist Category 6 cables more than ½" (12 mm) from the point of termination to maintain cable geometry. Provide service loop on each end of the cable, minimum 10' (3 meters) in the telecommunications room, 6" (150mm) in or close to the work area outlet.

Do not exceed manufacturers' cable pull tensions for copper and optical fiber cables. Provide a device to monitor cable pull tensions. Do not exceed 110 N (25 pounds) pull tension for four pair copper cables. Do not chafe or damage outer jacket materials. Use only lubricants approved by cable manufacturer. Do not over cinch cables, or crush cables with staples. Only hook and loop fasteners are allowed on Category 6/6A cable and optical fiber cable. DO NOT USE ZIP TIES.

For UTP cable, bend radii shall not be less than four times the cable diameter. Cables shall be terminated; no cable shall contain unterminated elements (see NFPA 70 abandoned cabling). Category 6/6A Cables shall not be spliced. Label cabling in accordance with paragraph LABELING in this section.

3.1.1.1 Open Cable

Use only where specifically indicated on plans (typically to continue existing systems in a renovation or in interim facilities) or use cable trays, or below raised floors in an approved pathway (free aired or free laid cabling is not authorized). Install in accordance with TIA-568.1, TIA-568.2 and TIA-568.3. Do not exceed cable pull tensions recommended by the manufacturer. Copper cable not in a wireway or pathway shall be suspended a minimum of 8 inches above ceilings by cable supports no greater than 60 inches apart.

Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items. Placement of cable parallel to power conductors shall be avoided, if possible; a minimum separation of 12 inches shall be maintained when such placement cannot be avoided.

Plenum cable shall be used where open cables are routed through plenum areas. Cable routed exposed under raised floors shall be plenum rated. Plenum cables shall comply with flammability plenum requirements of NFPA 70. Install cabling after the flooring system has been installed in raised floor areas. Cable 6 feet long shall be neatly coiled not less than 12 inches in diameter below each feed point in raised floor areas.

3.1.1.2 Backbone Cable

a. Copper Backbone Cable. Install intrabuilding backbone copper cable, in minimum 2-way 3 inch conduit or larger indicated pathways, between the campus distributor, located in the telecommunications entrance facility or room, the building distributors and the floor distributors located in telecommunications rooms and telecommunications equipment rooms as indicated on drawings.

b. Optical fiber Backbone Cable. Install intrabuilding backbone optical fiber in one of multiple interducts installed in conduit so as to maximize pathways, in indicated pathways, between various communications rooms and between racks of different classifications within the same room. Do not exceed manufacturer's recommended bending radii and pull tension. Prepare cable for pulling by cutting outer jacket 10 inches leaving strength members exposed for approximately 10 inches. Twist strength members together and attach to pulling eye. Vertical cable support intervals shall be in accordance with manufacturer's recommendations.

3.1.1.3 Horizontal Cabling

Install horizontal cabling as indicated on drawings Do not untwist Category 6 UTP cables more than one half inch from the point of termination to maintain cable geometry. Provide slack cable in the form of a figure eight (not a service loop) on each end of the cable, 10 feet in the telecommunications room, and 12 inches in the work area outlet.

3.1.2 Pathway Installations

Provide in accordance with TIA-569 and NFPA 70. Provide building pathway as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM, except that 1-1/4 inch diameter conduit from cable tray or telecommunication room backboard to each work area outlet is required.

Conceal conduit within finished walls, ceilings, and floors (not in wet areas). Keep conduit minimum 12 inches away from parallel runs of electrical power equipment, flues, steam, light ballast, and hot water pipes. Install conduit parallel with or at right angles to ceilings, walls, and structural members where located above accessible ceilings and where conduit is visible after completion of project. Run conduits in crawl spaces as if exposed.

Install no more than two 90 degree bends for a single horizontal cable run. All bends/turns in conduits will be in straight runs of conduit; a pull box shall be installed after every 180 degrees of bends or 100'; in

no case will a turn be made within a pull box. The minimum size for a pull box for a single 1¼" conduit will be 5" long by 5" wide by 2 7/8" deep, and for a 3" conduit 30"W x 54"L x9"D. All conduits should contain a bushing at the end to protect the cable from damage and required bonding. Pull points, LC, LB, condulets, and consolidation points are not authorized without a waiver from TSD.

Under floor cabling, under floor duct, and conduit under floor slabs should be avoided in the Camp Lejeune Greater area due to wet area close to coastal waters.

3.1.3 Service Entrance Conduit, Overhead

Provide service entrance overhead as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEMS. Ensure entrance fitting or weather head is sized to ensure min bend radius for largest cable is maintained.

3.1.4 Service Entrance Conduit, Underground

Provide service entrance underground as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Underground portion shall be encased in minimum of 3 inches of concrete extending from the building entrance to OSP demarcation point and shall be a minimum of 18 inches below slab or grade. Location of entrance conduit in communications room shall be to the left, while facing the longest furthest wall from the door.

3.1.5 Cable Tray Installation

Install cable tray as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Only CMP and OFNP type cable shall be installed in a plenum.

A continuous stranded bonding conductor (typically copper #2awg) shall be run on the outside along the tray tapped to each section properly to ensure bonding. Remove all sharps from cable tray and pathways. Ensure bonding is on the pathway so as not to obstruct horizontal cabling. Maintain proper clearance and work space per TIA-569 and TEMPEST.

3.1.6 Work Area Outlets

3.1.6.1 Terminations

Terminate UTP cable in accordance with TIA-568.1, TIA-568.2 and wiring configuration as specified. Terminate fiber optic cables in accordance with TIA-568.3.

All private office (less than 80 sq ft) work areas will contain a minimum of two communications face plates. Any work area larger than 80 sq feet will require additional face plates to service any work location in the room within 6 feet of a faceplate. This also applies to any area that could be converted to work space in the future. Recommend a communications outlet box be placed 6" to the left or right of electrical outlet box in workable office areas or any area that could be converted into workable office area such as a storage closet; All work area face plates will contain four jacks/ four cables terminated with T568A configuration unless otherwise approved by AHJ. MUTOAs contain 12 cables and may require additional clearance and power.

3.1.6.2 Cover Plates

As a minimum, each outlet/connector shall be labeled as to its function and a unique number to identify cable link in accordance with the paragraph LABELING in this section. For secured networks contact AHJ as shielded twisted pair and color coded face plates may be necessary.

3.1.6.3 Cables

Unshielded / Shielded twisted pair and fiber optic cables shall have a minimum of 12 inches of slack cable loosely coiled into the telecommunications outlet boxes or in cable tray as close as possible to outlet box. Minimum manufacturer's bend radius for each type of cable shall not be exceeded.

3.1.6.4 Pull Cords

Pull cords shall be installed in conduit serving telecommunications outlets that do not have cable installed.

3.1.6.5 Multi-User Telecommunications Outlet Assembly (MUTOA)

Run horizontal cable per specifications and terminate cables in MUTOA for each system furniture zone. MUTOAs shall not be located in ceiling spaces, under floors or in any obstructed or normally inaccessible area. MUTOAs shall not be installed in furniture unless that unit of furniture is permanently secured to the building structure. MUTOAs shall be located in an open work area so that each furniture cluster is served by at least one MUTOA. The MUTOA shall be limited to serving a maximum of six work areas with 2 cables each for a total of 12 cables/12 ports.

Maximum work area cable length requirements shall also be taken into account. MUTOAs must be labeled to include the maximum length of work area cables. MUTOA labeling is in addition to the labeling described in TIA-606, or other applicable cabling administration standards. Work area cables extending from the MUTOA to the work area device must also be uniquely identified and labeled.

3.1.7 Telecommunications Space Termination

Install termination hardware required for Category 6 and optical fiber system. A single punch manufacture approved insulation displacement tool shall be used for terminating copper cable to insulation displacement connectors.

3.1.7.1 Connector Blocks

Connector blocks shall be rack mounted in orderly rows and columns. Adequate vertical and horizontal wire routing areas shall be provided between groups of blocks. Install in accordance with industry standard wire routing guides in accordance with TIA-569.

3.1.7.2 Patch Panels

Patch panels shall be mounted racks with sufficient ports to accommodate the installed cable plant plus 25 percent spares.

a. Copper Patch Panel. Copper cable entering a patch panel shall be secured to the panel with cable tiesas recommended by the manufacturer

to prevent movement of the cable.

b. Fiber Optic Patch Panel. Fiber optic cable loop shall be 3 feet in lengthprovided as recommended by the manufacturer. The outer jacket of each cable entering a patch panel shall be secured to the panel per manufacture instructions to prevent movement of the fibers within the panel, using clamps or brackets specifically manufactured for that purpose.

3.1.7.3 Equipment Support Frames

Install in accordance with TIA-569:

a. Bracket, wall mounted. Mount bracket to plywood backboard in accordance with manufacturer's recommendations. Mount rack so height of highest panel does not exceed 78 inches above floor. Mount so there is sufficient space remaining on backboard to mount lightning protection, bonding, and cable managers or install additional backboards.

b. Racks, floor mounted modular type. Permanently anchor rack to the floor in accordance with manufacturer's recommendations. Install sections of ladder rack anchored to telephone rack/cabinet and at least two walls.

c. Cabinets, freestanding modular type. Permanently anchor to the floor in accordance with manufacturer's recommendations. When cabinets are connected together, remove adjoining side panels for cable routing between cabinets. Mount rack mounted fan in base of cabinet and 19" power/surge strip in cabinet. Install sections of ladder rack anchored to telephone rack/cabinet and at least two walls.

d. Cabinets, wall-mounted modular type. Mount cabinet to right on plywood backboard in accordance with manufacturer's recommendations. Mount cabinet so height of highest panel does not exceed 78 inches above floor. Mount so there is sufficient space remaining on backboard to mount lightning protection, bonding, and cable managers or install additional backboards.

3.1.8 Electrical Penetrations

Seal openings around electrical penetrations through fire resistance-rated wall, partitions, floors, or ceilings as specified in Section 07 84 00 FIRESTOPPING.

3.1.9 Grounding and Bonding

Provide in accordance with TIA-607, NFPA 70 and as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM except only two hole irreversible compression lugs will be accepted.

3.2 LABELING

3.2.1 Labels

Provide labeling in accordance with TIA-606, except jacks will be numbered in a logical, sequential, clockwise numbering system from 1 to X with a closet designator. Example would be 145 C 146, would be the 145th & 146th jacks from the C telecom room. All labels shall be numbered with

manufacturer's labeling system (not fabricated) and be equipped with laminated plastic cover.

All terminations that are not to work area outlets should be in the last patch panel locations and labeled accordingly i.e. DDC, FACP, Elevator, Wall phones, or Wireless access points. Handwritten labeling is unacceptable. Stenciled lettering for voice and data circuits shall be provided using laser printer .

3.2.2 Cable

Cables shall be labeled using color labels on both ends with identifiers in accordance with TIA-606.

3.2.3 Termination Hardware

Workstation outlets and patch panel connections shall be labeled using color coded labels with identifiers in accordance with this section and TIA-606. Coordinate with TSD (Base Telephone).

3.3 FIELD APPLIED PAINTING

Paint electrical equipment as required to match finish of adjacent surfaces or to meet the indicated or specified safety criteria. Painting shall be as specified in Section 09 90 00 PAINTS AND COATINGS.

3.3.1 Painting Backboards

Camp Lejeune no longer paints backboards as fire rated plywood is available. Manufactured fire retardant backboard shall be used, so as not to increase flame spread and smoke density and must be appropriately labeled.

3.4 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.5 TESTING

3.5.1 Telecommunications Cabling Testing

Perform telecommunications cabling inspection, verification, and performance tests on both Backbone and Horizontal cabling in accordance with TIA-568.1, TIA-568.2, TIA-568.3 and AHJ local guidance. Test equipment shall conform to TIA-1152. Perform optical fiber field inspection tests via attenuation measurements on factory reels and provide results along with manufacturer certification for factory reel tests. Remove failed cable reels from project site upon attenuation test failure.

3.5.1.1 Inspection

Visually inspect all telecommunications cabling jacket materials for UL or third party certification markings. Inspect cabling terminations in telecommunications rooms and at workstations to confirm color code for T568A or T568B pin assignments, and inspect cabling connections to confirm compliance with TIA-568.1, TIA-568.2, TIA-568.3, . Visually confirm

Category 6, marking of outlets, cover plates, outlet/connectors, cable physical damage, and patch panels.

3.5.1.2 Verification Tests

Backbone copper cabling shall be tested for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors, and between conductors and shield, if cable has overall shield. Test operation of shorting bars in connection blocks. Test cables after termination but prior to being cross-connected.

For single-mode optical fiber, perform optical fiber end-to-end attenuation tests in accordance with TIA-568.3 and TIA-526-7 using Method B, OTDR for single-mode optical fiber. Perform verification acceptance tests.

3.5.1.3 Performance Tests

Provide summary in .pdf detailed tester results in test format .flw , and fiber power meter/OTDR reports summary and detailed. All Test reports should have a building or project number on each page. The final QC and certification of installation will be performed by TSD after the contractor has provided passing and acceptable results on all test and as-built drawings showing all telecommunications outlets and their numbers to include any empty conduit or ports coiled in overhead for future use and all building automated system ports such as DDC, Elevator, FACP, or WAPs.

Test results that are marginal may not be accepted. Also fiber tests that pass the link budget but exceed tolerance on any connector or splice are considered a failure. All discrepancies must be repaired and retested.

Perform testing for each outlet and MUTOA as follows:

a. Perform Category 6 link tests in accordance with TIA-568.1 and TIA-568.2. Tests shall include wire map, length, insertion loss, NEXT, PSNEXT, ELFEXT, PSELFEXT, return loss, propagation delay, and delay skew.

b. Optical fiber Links. Perform optical fiber end-to-end link tests in accordance with TIA-568.3.

3.5.1.4 Final Verification Tests

Perform verification tests for all copper and optical fiber systems after the complete telecommunications cabling and workstation outlet/connectors are installed.

a. Voice Tests. These tests assume that dial tone service has been installed (normally done for FACP, Elevator, or emergency phones). Connect to the network interface device at the demarcation point. Go off-hook and listen and receive a dial tone. If a test number is available, make and receive a local, long distance, and DSN telephone call.

b. Data Tests. These tests assume the Information Technology Staff has a network installed and are available to assist with testing (normally done for VTC, CCTV). Connect to the network interface device at the demarcation point. Log onto the network to ensure proper connection to the network.

-- End of Section --

SECTION 28 31 76

INTERIOR FIRE ALARM AND MASS NOTIFICATION SYSTEM, ADDRESSABLE
08/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ACOUSTICAL SOCIETY OF AMERICA (ASA)

ASA S3.2	(2020) American National Standard Method for Measuring the Intelligibility of Speech Over Communication Systems (ASA 85)

FM GLOBAL (FM)

FM APP GUIDE	(updated on-line) Approval Guide https://www.approvalguide.com/

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE C62.41.1	(2002; R 2008) Guide on the Surges Environment in Low-Voltage (1000 V and Less) AC Power Circuits
IEEE C62.41.2	(2002) Recommended Practice on Characterization of Surges in Low-Voltage (1000 V and Less) AC Power Circuits

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 4	(2018) Standard for Integrated Fire Protection and Life Safety System Testing
NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 72	(2025; TIA 25-1; TIA 25-2; TIA 25-3; TIA 25-4; ERTA 25-1; ERTA 25-2) National Fire Alarm and Signaling Code
NFPA 90A	(2024) Standard for the Installation of Air Conditioning and Ventilating Systems
NFPA 170	(2021) Standard for Fire Safety and Emergency Symbols

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-601-02	(2021) Fire Protection Systems Inspection, Testing, and Maintenance

UFC 4-010-06	(2016; with Change 1, 2017) Cybersecurity of Facility-Related Control Systems

UL SOLUTIONS (UL)

UL 268	(2016; Reprint Nov 2021) UL Standard for Safety Smoke Detectors for Fire Alarm Systems
UL 268A	(2008; Reprint Oct 2014) Smoke Detectors for Duct Application
UL 464	(2016; Reprint Sep 2017) UL Standard for Safety Audible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories
UL 497A	(2001; Bul. 2019) UL Standard for Safety Secondary Protectors for Communications Circuits
UL 497B	(2004; Reprint Feb 2022) UL Standard for Safety Protectors for Data Communications and Fire Alarm Circuits
UL 864	(2014; Reprint May 2020) UL Standard for Safety Control Units and Accessories for Fire Alarm Systems
UL 1283	(2017) UL Standard for Safety Electromagnetic Interference Filters
UL 1449	(2021; Reprint Oct 2025) UL Standard for Safety Surge Protective Devices
UL 1480	(2016; Reprint Sep 2017) UL Standard for Safety Speakers for Fire Alarm and Signaling Systems, Including Accessories
UL 1638	(2016; Reprint Sep 2017) UL Standard for Safety Visible Signaling Devices for Fire Alarm and Signaling Systems, Including Accessories
UL 1971	(2002; Reprint Oct 2008) Signaling Devices for the Hearing Impaired
UL 2017	(2008; Reprint Dec 2018) UL Standard for Safety General-Purpose Signaling Devices and Systems
UL 2034	(2017; Reprint Oct 2022) UL Standard for Safety Single and Multiple Station Carbon Monoxide Alarms
UL 2075	(2013; Bul. 2019) UL Standard for Safety Gas and Vapor Detectors and Sensors

UL 2572	(2016; Bul. 2018) UL Standard for Safety Mass Notification Systems
UL Fire Prot Dir	(2012) Fire Protection Equipment Directory

1.2 RELATED SECTIONS

Section 25 05 11.00 CYBERSECURITY FOR FACILITY-RELATED CONTROL SYSTEMS - ISOLATED SYSTEMS, applies to this section, with the additions and modifications specified herein. In addition, refer to the following sections for related work and coordination:

Section 21 13 13 WET PIPE SPRINKLER SYSTEM, FIRE PROTECTION
Section 21 30 00 FIRE PUMPS
Section 21 13 16 DRY PIPE FIRE SPRINKLER SYSTEMS
Section 08 71 00 DOOR HARDWARE for door unlocking and additional work related to finish hardware.
Section 07 84 00 FIRESTOPPING for additional work related to firestopping.

1.3 SUMMARY

1.3.1 Scope

a. This work includes designing and providing a new, complete, fire alarm and mass notification (MNS) system as described herein and on the contract drawings. Include system wiring, raceways, pull boxes, terminal cabinets, outlet and mounting boxes, control equipment, initiating devices, notification appliances, supervising station fire alarm transmitters/mass notification transceiver, and other accessories and miscellaneous items required for a complete operational system even though each item is not specifically mentioned or described. Provide system(s) complete and ready for operation. Design and installation must comply with UFGS 25 05 11.00, UFC 4-010-06 and AFGM 2019-320-02.

b. Provide equipment, materials, installation, workmanship, inspection, and testing in strict accordance with NFPA 72, except as modified herein. The system layout on the drawings show the intent of coverage and suggested locations. Final quantity, system layout, and coordination are the responsibility of the Contractor.

c. Each remote fire alarm control unit must be powered from a wiring riser specifically for that use or from a local emergency power panel located on the same floor as the remote fire alarm control unit. Where remote fire control units are provided, equipment for notification appliances may be located in the remote fire alarm control units.

d. Where a fire pump is provided, the fire alarm and mass notification system must monitor and transmit the fire pump controller signals in accordance with the provisions of NFPA 72.

e. The fire alarm and mass notification system must be independent of the building security, building management, and energy/utility monitoring systems other than for control functions.

1.3.2 Qualified Fire Protection Engineer (QFPE)

The QFPE in this section is the same as FPQC in Section 01 45 00. Wherever "Qualified Fire Protection Engineer (QFPE)" or "QFPE" appears in this sectionm substitute with "Fire Protection Quality Control Specialist (FPQC)". Services of the QFPE must include:

a. Reviewing SD-02, SD-03, and SD-05 submittal packages for completeness and compliance with the provisions of this specification. Construction (shop) drawings and calculations must be prepared by, or prepared under the immediate supervision of, the QFPE. The QFPE must affix their professional engineering stamp with signature to the shop drawings, calculations, and material data sheets, indicating approval prior to submitting the shop drawings to the DFPE.

b. Providing a letter documenting that the SD-02, SD-03, and SD-05 submittal package has been reviewed and noting any outstanding comments.

c. Performing in-progress construction surveillance prior to installation of ceilings (rough-in inspection).

d. Witnessing pre-Government and final Government functional performance testing and performing a final installation review.

e. Signing applicable certificates under SD-07.

1.4 DEFINITIONS

Wherever mentioned in this specification or on the drawings, the equipment, devices, and functions must be defined as follows:

1.4.1 Interface Device

An addressable device that interconnects hard wired systems or devices to an analog/addressable system.

1.4.2 Fire Alarm and Mass Notification Control Unit (FMCU)

A master control unit having the features of a fire alarm control unit (FACU) and an autonomous control unit (ACU) where these units are interconnected to function as a combined fire alarm/mass notification system. The FACU and ACU functions may be contained in a single cabinet or in independent, interconnected, and co-located cabinets.

1.4.3 Remote Fire Alarm and Mass Notification Control Unit

A control unit, physically remote from the fire alarm and mass notification control unit, that receives inputs from automatic and manual fire alarm devices; may supply power to detection devices and interface devices; may provide transfer of power to the notification appliances; may provide transfer of condition to relays or devices connected to the control unit; and reports to and receives signals from the fire alarm and mass notification control unit.

1.4.4 Local Operating Console (LOC)

A unit designed to allow emergency responders and/or building occupants to operate the MNS including delivery of recorded messages and/or live voice

announcements, initiate visual, textual visual, and audible appliance operation and other relayed functions.

1.4.5 Terminal Cabinet

A steel cabinet with locking, hinge-mounted door where terminal strips are securely mounted inside the cabinet.

1.4.6 Control Module and Relay Module

Terms utilized to describe emergency control function interface devices as defined by NFPA 72.

1.4.7 Designated Fire Protection Engineer (DFPE)

The DoD fire protection engineer that oversees that Area of Responsibility for that project. This is sometimes referred to as the "cognizant" fire protection engineer. Interpret reference to "authority having jurisdiction" and/or AHJ in referenced standards to mean the Designated Fire Protection Engineer (DFPE). The DFPE may be responsible for review of the contractor submittals having a "G" designation, and for witnessing final inspection and testing.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" classification. Submittals not having a "G" classification are for Contractor Quality Control approval.

Shop drawings (SD-02), product data (SD-03) and calculations (SD-05) must be prepared by the fire alarm designer and combined and submitted as one complete package. The QFPE must review the SD-02/SD-03/SD-05 submittal package for completeness and compliance with the Contract provisions prior to submission to the Government. The QFPE must provide a Letter of Confirmation that they have reviewed the submittal package for compliance with the contract provisions. This letter must include their registered professional engineer stamp and signature. Partial submittals and submittals not reviewed by the QFPE will be returned by the Government disapproved without review.

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Qualified Fire Protection Engineer (QFPE); G

Fire alarm system designer; G

Supervisor; G

Technician; G

Installer; G

Test Technician; G

Fire Alarm System Site-Specific Software Acknowledgement; G

SD-02 Shop Drawings

Nameplates; G

Instructions; G

Wiring Diagrams; G

System Layout; G

Notification Appliances; G

Initiating devices; G

Amplifiers; G

Battery Power; G

Voltage Drop Calculations; G

SD-03 Product Data

Fire Alarm and Mass Notification Control Unit (FMCU); G

Local Operating Console (LOC); G

Amplifiers; G

Tone Generators; G

Digitalized voice generators; G

LCD Annunciator; G

Manual Stations; G

Smoke Detectors; G

Duct Smoke Detectors; G

Carbon monoxide detector; G

Addressable Interface Devices; G

Addressable Control Modules; G

Notification Appliances; G

Batteries; G

Battery Chargers; G

Supplemental Notification Appliance Circuit Panels; G

Auxiliary Power Supply Panels; G

Surge Protective Devices; G

Alarm Wiring; G

Back Boxes and Conduit; G

Ceiling Bridges for Ceiling-Mounted Appliances; G

Terminal Cabinets; G

Digital Alarm Communicator Transmitter (DACT); G

Environmental Enclosures or Guards; G

Document Storage Cabinet; G

SD-06 Test Reports

Test Procedures; G

SD-07 Certificates

Verification of Compliant Installation; G

Request for Government Final Test; G

SD-10 Operation and Maintenance Data

Operation and Maintenance (O&M) Instructions; G

Instruction of Government Employees; G

SD-11 Closeout Submittals

As-Built Drawings

Spare Parts

1.6 SYSTEM OPERATION

Fire alarm system/mass notification system, components requiring power, except for the FMCU(s) power supply, must operate on 24 volts DC unless noted otherwise in this section.

The interior fire alarm and mass notification system must be a complete, supervised, noncoded, analog/addressable fire alarm and mass notification system conforming to NFPA 72, UL 864, and UL 2572. Systems meeting UL 2017 only are not acceptable. The system must be activated into the alarm mode by actuation of an alarm initiating device. The system must remain in the alarm mode until the initiating device is reset and the control unit is reset and restored to normal. The system may be placed in the alarm mode by local microphones, LOC, FMCU, or remotely from authorized locations/users.

1.6.1 Alarm Initiating Devices and Notification Appliances (Visual, Voice, Textual)

a. Connect alarm initiating devices to initiating device circuits (IDC) Class "B", or to signaling line circuits (SLC) Class "B" and installed in accordance with NFPA 72.

b. Connect notification appliances to notification appliance circuits

(NAC) Class "B".

1.6.2 Functions and Operating Features

The system must provide the following functions and operating features:

a. Power, annunciation, supervision, and control for the system. Addressable systems must be microcomputer (microprocessor or microcontroller) based with a minimum word size of eight bits with sufficient memory to perform as specified.

b. Visual alarm notification appliances must be synchronized as required by NFPA 72.

c. Electrical supervision of the primary power (AC) supply, presence of the battery, battery voltage, and placement of system modules within the control unit.

d. An audible and visual trouble signal to activate upon a single break or open condition, or ground fault. The trouble signal must also operate upon loss of primary power (AC) supply, absence of a battery supply, low battery voltage, or removal of alarm or supervisory control unit modules. After the system returns to normal operating conditions, the trouble signal must again sound until the trouble is acknowledged. A smoke detector in the process of being verified for the actual presence of smoke must not initiate a trouble condition.

e. A trouble signal silence feature that must silence the audible trouble signal, without affecting the visual indicator.

f. Program capability via switches in a locked portion of the FMCU to bypass the automatic notification appliance circuits, fire reporting system, air handler shutdown, and door unlocking features. Operation of this programmed action must indicate on the FMCU display as a supervisory or trouble condition.

g. Alarm functions must override trouble or supervisory functions. Supervisory functions must override trouble functions.

h. The system must be capable of being programmed from the control unit keyboard. Programmed information must be stored in non-volatile memory.

i. The system must be capable of operating, supervising, and/or monitoring non-addressable alarm and supervisory devices.

j. There must be no limit, other than maximum system capacity, as to the number of addressable devices that may be in alarm simultaneously.

k. Where the fire alarm/mass notification system is responsible for initiating an action in another emergency control device or system, such as HVAC,the addressable fire alarm relay must be located in the vicinity of the emergency control device.

l. An alarm signal must automatically initiate the following functions:

(1) Transmission of an alarm signal to the fire department using Contact ID Protocol.

(2) Visual indication of the device operated on the FMCU, and on the remote annunciator.

(3) Actuation of alarm notification appliances.

(4) Recording of the event electronically in the history log of the FMCU.

(5) Release of power to electric locks (delayed egress locks) on doors that are part of the means of egress.

m. A supervisory signal must automatically initiate the following functions:

(1) Visual indication of the device operated on the FMCU, and on the remote annunciator.

(2) Transmission of a supervisory signal to the fire department using Contact ID Protocol.

(3) Operation of a duct smoke detector must shut down the appropriate air handler in accordance with NFPA 90A in addition to other requirements of this paragraph and as allowed by NFPA 72.

(4) Recording of the event electronically in the history log of the FMCU.

n. A trouble condition must automatically initiate the following functions:

(1) Visual indication of the device operated on the FMCU, and on the remote annunciator.

(2) Transmission of a trouble signal to the fire department using Contact ID Protocol.

(3) Recording of the event electronically in the history log of the FMCU.

o. Activation of a carbon monoxide alarm initiating device must automatically initiate the following functions:

(1) Visual indication of the device operated on the FMCU, and on the remote annunciator.

(2) Transmission of a carbon monoxide alarm signal to the fire department using Contact ID Protocol.

(3) Activation of all strobes and the audible carbon monoxide message throughout the building.

(4) Recording of the event electronically in the history log of the FMCU.

p. System control equipment must be programmed to provide a 60-minute to 180-minute delay in transmission of trouble signals resulting from primary power failure.

q. Activation of a LOC pushbutton must activate the audible and visual

alarms in the facility. The audible message must be the one associated with the pushbutton activated.

1.7 TECHNICAL DATA AND SITE-SPECIFIC SOFTWARE

Technical data and site-specific software (meaning technical data that relates to computer software) that are specifically identified in this project, and may be required in other specifications, must be delivered, strictly in accordance with the CONTRACT CLAUSES. The fire alarm system manufacturer must submit written confirmation of this contract provision as "Fire Alarm System Site-Specific Software Acknowledgement". Identify data delivered by reference to the specification paragraph against which it is furnished. Data to be submitted must include complete system, equipment, and software descriptions. Descriptions must show how the equipment will operate as a system to meet the performance requirements of this contract. The site-specific software data package must also include the following:

a. Items identified in NFPA 72, titled "Site-Specific Software".

b. Identification of programmable portions of the system equipment and capabilities.

c. Description of system revision and expansion capabilities and methods of implementation detailing both equipment and software requirements.

d. Provision of operational software data on all modes of programmable portions for fire alarm and mass notification.

e. Description of Fire Alarm and Mass Notification Control Unit equipment operation.

f. Description of auxiliary and remote equipment operations.

g. Library of application software.

h. Operation and maintenance manuals.

1.8 EXISTING EQUIPMENT

a. Equipment and devices must be compatible and operable with the existing supervising station and must not impair reliability or operational functions of existing supervising station fire alarm system. The supervising equipment is existing and consists of the following brand and model: Sur-Gard System III Multi-Platform Digital Telephone Receiver.

1.9 QUALITY ASSURANCE

1.9.1 Submittal Documents

1.9.1.1 Preconstruction Submittals

Within 36 days of contract award but not less than 14 days prior to commencing any work on site, the Contractor must submit the following for review and approval. SD-02, SD-03 and SD-05 submittals received prior to the review and approval of the qualifications of the fire alarm subcontractor and QFPE must be returned disapproved without review. All resultant delays must be the sole responsibility of the Contractor.

1.9.1.2 Shop Drawings

Shop drawings must not be smaller than the Contract Drawings. Drawings must comply with the requirements of NFPA 72 and NFPA 170. Minimum scale for floor plans must be 1/8"=1'.

1.9.1.3 Nameplates

Nameplate illustrations and data to obtain approval by the Contracting Officer before installation.

1.9.1.4 Wiring Diagrams

One copy of point-to-point wiring diagrams showing the points of connection and terminals used for electrical field connections in the system, including interconnections between the equipment or systems that are supervised or controlled by the system. Diagrams must show connections from field devices to the FMCU and remote FMCU, initiating circuits, switches, relays and terminals, including pathway diagrams between the control unit and shared communications equipment within the protected premises. Point-to-point wiring diagrams must be job specific and must not indicate connections or circuits not being utilized. Provide complete riser diagrams indicating the wiring sequence of all devices and their connections to the control equipment. Include a color-code schedule for the wiring.

1.9.1.5 System Layout

One copy of plan view drawing showing device locations, terminal cabinet locations, junction boxes, other related equipment, conduit routing, conduit sizes, wire counts, conduit fill calculations, wire color-coding, circuit identification in each conduit, and circuit layouts for all floors. Indicate candela rating of each visual notification appliance. Indicate the wattage of each speaker. Clearly identify the locations of isolation modules. Indicate the addresses of all devices, modules, relays, and similar. Show/identify all acoustically similar spaces. Indicate if the environment for the FMCU is within its environmental listing (e.g. temperature/humidity).

Provide a complete description of the system operation in matrix format similar to the "Typical Input/Output Matrix" included in the Annex of NFPA 72.

1.9.1.6 Notification Appliances

Calculations and supporting data on each circuit to indicate that there is at least 25 percent spare capacity for notification appliances. Annotate data for each circuit on the drawings.

1.9.1.7 Initiating Devices

Calculations and supporting data on each circuit to indicate that there is at least 25 percent spare capacity for initiating devices. Annotate data for each circuit on the drawings.

1.9.1.8 Amplifiers

Calculations and supporting data to indicate that amplifiers have

sufficient capacity to simultaneously drive all notification speakers at tapped settings plus 25 percent spare capacity. Annotate data for each circuit on the drawings.

1.9.1.9 Battery Power

Calculations and supporting data as required in paragraph Battery Power Calculations for alarm, alert, and supervisory power requirements. Calculations including ampere-hour requirements for each system component and each control unit component, and the battery recharging period, must be included on the drawings.

1.9.1.10 Voltage Drop Calculations

Voltage drop calculations for each notification circuit indicating that sufficient voltage is available for proper operation of the system and all components, at a minimum rated voltage of the system operating on batteries. Include the calculations on the system layout drawings.

1.9.1.11 Product Data

One copy of annotated descriptive data to show the specific model, type, and size of each item. Catalog cuts must also indicate the NRTL listing. The data must be highlighted to show model, size, and options that are intended for consideration. Data must be adequate to demonstrate compliance with all contract requirements. Product data for all equipment must be combined into a single submittal.

Provide an equipment list identifying the type, quantity, make, and model number of each piece of equipment to be provided under this submittal. The equipment list must include the type, quantity, make and model of spare equipment. Types and quantities of equipment submitted must coincide with the types and quantities of equipment used in the battery calculations and those shown on the shop drawings.

1.9.1.12 Operation and Maintenance (O&M) Instructions

Six copies of the Operation and Maintenance Instructions. The O&M Instructions must be prepared in a single volume or in multiple volumes, with each volume indexed, and may be submitted as a Technical Data Package. Manuals must be approved prior to training. The Interior Fire Alarm And Mass Notification System Operation and Maintenance Instructions must include the following:

a. "Manufacturer Data Package five" as specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA.

b. Operating manual outlining step-by-step procedures required for system startup, operation, and shutdown. The manual must include the manufacturer's name, model number, service manual, parts list, and preliminary equipment list complete with description of equipment and their basic operating features.

c. Maintenance manual listing routine maintenance procedures, possible breakdowns and repairs, and troubleshooting guide. The manuals must include conduit layout, equipment layout and simplified wiring, and control diagrams of the system as installed.

d. Complete procedures for system revision and expansion, detailing both

equipment and software requirements.

e. Software submitted for this project on CD/DVD media utilized.

f. Printouts of configuration settings for all devices.

g. Routine maintenance checklist. The routine maintenance checklist must be arranged in a columnar format. The first column must list all installed devices, the second column must state the maintenance activity or state no maintenance required, the third column must state the frequency of the maintenance activity, and the fourth column provided for additional comments or reference. All data (devices, testing frequencies, and similar) must comply with UFC 3-601-02.

h. A final Equipment List must be submitted with the Operating and Maintenance (O&M) manual.

1.9.1.13 As-Built Drawings

The drawings must show the system as installed, including deviations from both the project drawings and the approved shop drawings. A bill of material and Contact ID Point Description Table must be included on the as-built drawings. These drawings must be submitted within two weeks after the final Government test of the system. At least one set of the as-built (marked-up) drawings must be provided at the time of, or prior to the final Government test.

1.9.2 Qualifications

1.9.2.1 Fire Alarm System Designer

The fire alarm system designer must be certified as a Level IV (minimum) Technician by National Institute for Certification in Engineering Technologies (NICET) in the Fire Alarm Systems subfield of Fire Protection Engineering Technology or meet the qualifications for a QFPE.

1.9.2.2 Supervisor

A NICET Level IV fire alarm technician must supervise the installation of the fire alarm/mass notification system. The fire alarm technicians supervising the installation of equipment must be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.9.2.3 Technician

Fire alarm technicians with a minimum of four years of experience must be utilized to install and terminate fire alarm/mass notification devices, cabinets and control units. The fire alarm technicians installing the equipment must be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.9.2.4 Installer

Fire alarm installer with a minimum of two years of experience utilized to assist in the installation of fire alarm/mass notification devices, cabinets and control units. A licensed electrician must be allowed to install wire, cable, conduit and backboxes for the fire alarm system/mass

notification system. The fire alarm installer must be factory trained in the installation, adjustment, testing, and operation of the equipment specified herein and on the drawings.

1.9.2.5 Test Technician

Fire alarm technicians with a minimum of eight years of experience and NICET Level IV utilized in testing and certification of the installation of the fire alarm/mass notification devices, cabinets and control units. The fire alarm technicians testing the equipment must be factory trained in the installation, adjustment, testing, and operation of the equipment installed as part of this project.

1.9.2.6 Manufacturer

Components must be of current design and must be in regular and recurrent production at the time of installation. Provide design, materials, and devices for a protected premises fire alarm system, complete, conforming to NFPA 72, except as specified herein.

1.9.3 Regulatory Requirements

Equipment and material must be listed or approved. Listed or approved, as used in this section, means listed, labeled or approved by a Nationally Recognized Testing Laboratory (NRTL) such as UL Fire Prot Dir or FM APP GUIDE. The omission of these terms under the description of any item of equipment described must not be construed as waiving this requirement. All listings or approvals by testing laboratories must be from an existing ANSI or UL published standard. The recommended practices stated in the manufacturer's literature or documentation must be considered as mandatory requirements.

1.10 DELIVERY, STORAGE, AND HANDLING

Protect equipment delivered and placed in storage from the weather, humidity, and temperature variation, dirt and dust, and other contaminants.

1.11 MAINTENANCE

1.11.1 Spare Parts

Furnish the following spare parts in the manufacturers original unopened containers:

a. Five complete sets of system keys.

b. One manual stations.

c. Two of each type of detector base and head installed.

d. Two of each type of audible and visual alarm device installed.

e. Two of each type of addressable monitor module installed.

f. Two of each type of addressable control module installed.

g. Two low voltage, one telephone, and one 120 VAC surge protective device.

1.11.2 Special Tools

Software, connecting cables and proprietary equipment, necessary for the maintenance, testing, and reprogramming of the equipment must be furnished to the Contracting Officer, prior to the instruction of Government employees.

PART 2 PRODUCTS

2.1 GENERAL PRODUCT REQUIREMENT

All fire alarm and mass notification equipment must be listed for use under the applicable reference standards. Interfacing of UL 864 or similar approved industry listing with Mass Notification equipment listed to UL 2572 must be done in a laboratory listed configuration, if the software programming features cannot provide a listed interface control.

2.2 MATERIALS AND EQUIPMENT

2.2.1 Standard Products

Provide materials, equipment, and devices that have been tested by a nationally recognized testing laboratory and listed for fire protection service when so required by NFPA 72 or this specification. Select material from one manufacturer, where possible, and not a combination of manufacturers, for any particular classification of materials. Material and equipment must be the standard products of a manufacturer regularly engaged in the manufacture of the products for at least 2 years prior to bid opening.

2.2.2 Nameplates

Major components of equipment must have the manufacturer's name, address, type or style, model or serial number, catalog number, date of installation, installing Contractor's name and address, and the contract number provided on a new name plate permanently affixed to the item or equipment. Major components include, but are not limited to, the following:

a. FMCU

Nameplates must be etched metal or plastic, permanently attached by screws to control units or adjacent walls.

2.2.3 Keys

Keys and locks for equipment, control units and devices must be identical. Master all keys and locks to a single key as required by the Installation Fire Department.

2.2.4 Instructions

Provide a typeset printed or typewritten instruction card mounted behind a Lexan plastic or glass cover in a stainless steel or aluminum frame. Install the frame in a conspicuous location observable from the FMCU. The card must show those steps to be taken by an operator when a signal is received as well as the functional operation of the system under all conditions, normal, alarm, supervisory, and trouble. The instructions must also include procedures for operating live voice microphones. The

instructions and their mounting location must be approved by the Contracting Officer before being posted.

2.3 FIRE ALARM AND MASS NOTIFICATION CONTROL UNIT

Provide a complete fire alarm and mass notification control unit (FMCU) fully enclosed in a lockable steel cabinet as specified herein. Operations required for testing or for normal care, maintenance, and use of the system must be performed from the front of the enclosure. If more than a single unit is required at a location to form a complete control unit, the unit cabinets must match exactly. The system must be capable of defining any module as an alarm module and report alarm trouble, loss of polling, or as a supervisory module, and reporting supervisory short, supervisory open or loss of polling such as waterflow switches, valve supervisory switches, fire pump monitoring, relays for output function actuation.

a. Each control unit must provide power, supervision, control, and logic for the entire system, utilizing solid state, modular components, internally mounted and arranged for easy access. Each control unit must be suitable for operation on a 120 volt, 60 hertz, normal building power supply. Provide each control unit with supervisory functions for power failure, internal component placement, and operation.

b. Visual indication of alarm, supervisory, or trouble initiation on the FMCU must be by liquid crystal display or similar means with a minimum of 80 characters. The mass notification control unit must have the capability of temporarily deactivate the fire alarm audible notification appliances while delivering voice messages.

c. Provide secure operator console for initiating recorded messages, strobes and displays; and for delivering live voice messages. Provide capacity for at least eight prerecorded messages. Provide the ability to automatically repeat prerecorded messages. Provide a secure microphone for delivering live messages. Provide adequate discrete outputs to temporarily deactivate fire alarm audible notification, initiate/synchronize strobes and initiate textual visual notification appliances. Provide a complete set of self-diagnostics for controller and appliance network. Provide local diagnostic information display and local diagnostic information and system event log file.

2.3.1 Cabinet

Install control unit components in cabinets large enough to accommodate all components and also to allow ample gutter space for interconnection of control units as well as field wiring. The cabinet must be a sturdy steel housing, complete with back box, hinged steel door with cylinder lock, and surface mounting provisions. The enclosure must be identified by an engraved phenolic resin nameplate. Lettering on the nameplate must say "Fire Alarm and Mass Notification control unit" and must not be less than 1-inch high. Provide prominent rigid plastic or metal identification plates for lamps, circuits, meters, fuses, and switches.

2.3.2 Silencing Switches

2.3.2.1 Alarm Silencing Switch

Provide an alarm silencing switch at the FMCU that must silence the

audible and visual notification appliances. Subsequent activation of initiating devices must cause the notification appliances to re-activate.

2.3.2.2 Supervisory/Trouble Silencing Switch

Provide supervisory and trouble silencing switch(es) that must silence the audible trouble and supervisory signal(s), but not extinguish the visual indicator. This switch must be overridden upon activation of a subsequent supervisory or trouble condition. Audible trouble indication must resound automatically every 24 hours after the silencing feature has been operated if the supervisory or trouble condition still exists.

2.3.3 Non-Interfering

Power and supervise each circuit such that a signal from one device does not prevent the receipt of signals from any other device. Initiating devices must be manually reset by switch from the FMCU after the initiating device or devices have been restored to normal.

2.3.4 Audible Notification System

The Audible Notification System must comply with the requirements of NFPA 72 for Emergency Voice/Alarm Communications System requirements, except as specified herein. The system must be a one-way, multi-channel voice notification system incorporating user selectability of a minimum eight distinct sounds for tone signaling, and the incorporation of a voice module for delivery of recorded messages. Audible appliances must produce a three-pulse temporal pattern for three cycles followed by a voice message that is repeated until the control unit is reset or silenced. For carbon monoxide detector activation, audible appliances must produce a four-pulse temporal pattern for three cycles followed by a voice message that is repeated until the control unit is reset or silenced. Automatic messages must be broadcast through speakers throughout the building/facility but not in stairs or elevator cabs. A live voice message must override the automatic audible output through use of a microphone input at the control unit or the LOC.

a. When using the microphone, live messages must be broadcast throughout the building. The system must be capable of operating all speakers at the same time. The microphone must be hand-held style. Hand-held microphones must be housed in a separate protective cabinet. The cabinet must be accessible without the use of a key. The location of the microphone(s) must be approved by the Designated Fire Protection Engineer (DFPE).

b. The microprocessor must actively interrogate circuitry, field wiring, and digital coding necessary for the immediate and accurate rebroadcasting of the stored voice data into the appropriate amplifier input. Loss of operating power, supervisory power, or any other malfunction that could render the digitalized voice module inoperative must automatically cause the three-pulse temporal pattern to take over all functions assigned to the failed unit in the event an alarm is activated.

2.3.4.1 Outputs and Operational Modules

All outputs and operational modules must be fully supervised with on-board diagnostics and trouble reporting circuits. Provide form "C" contacts for system alarm and trouble conditions. Provide circuits for operation of

auxiliary appliance during trouble conditions. During a Mass Notification event, the control unit must not generate nor cause any trouble alarms to be generated with the Fire Alarm system.

2.3.4.2 Mass Notification

a. The system must have the capability of utilizing an LOC with redundant controls of the FMCU. Notification Appliance Circuits (NAC) must be provided for the activation of strobe appliances. Audio output must be selectable for line level. A hand-held microphone must be provided and, upon activation, must take priority over any tone signal, recorded message or PA microphone operation in progress, while maintaining the strobe NAC circuit activation.

b. The Mass Notification functions must override the manual or automatic fire alarm notification. Other fire alarm functions including transmission of a signal(s) to the fire department must remain operational. When a mass notification announcement is disengaged and a fire alarm condition still exists, the audible and visual notification appliances must resume activation for alarm conditions. The fire alarm message must be of lower priority that all other messages (except any "test" messages) and must not override any other messages.

c. Messages must be recorded professionally utilizing standard industry methods, in a professional female voice. Message and tone volumes must both be at the same decibel level. Messages recorded from the system microphone must not be accepted. A 1000 Hz tone (as required by NFPA 72) must precede messages and be similar to the following unless Installation or Facility specific messages are required:

(1) Carbon Monoxide: "May I have your attention please. May I have your attention please. High levels of carbon monoxide have been detected in the building. Please leave the building by the nearest exit." (Provide a 2 second pause.) "May I have your attention please, (repeat the tones and message on a continuous loop)."

(2) Fire: "May I have your attention please. May I have your attention please. A fire has been reported in the building. Please leave the building by the nearest exit." (Provide a 2 second pause.) "May I have your attention please, (repeat the tones and message on a continuous loop)."

d. Auxiliary Input Module must be designed to be an outboard expansion module to either expand the number of optional LOC's, or allow a telephone interface.

2.3.4.3 Installation-Wide Control

If an installation-wide control system for mass notification exists on the Base, the autonomous control unit must communicate with the central control unit of the Installation-wide system. The autonomous control unit must receive commands/messages from the central control unit and provide status information.

2.3.5 Memory

Provide each control unit with non-volatile memory and logic for all

functions. The use of long life batteries, capacitors, or other age-dependent devices must not be considered as equal to non-volatile processors, PROMS, or EPROMS.

2.3.6 Field Programmability

Provide control units and control units that are fully field programmable for both input and output of control, initiation, notification, supervisory, and trouble functions. The system program configuration must be menu driven. System changes must be password protected. Any proprietary equipment and proprietary software needed by qualified technicians to implement future changes to the fire alarm system must be provided as part of this contract.

A lockout code must not be installed in the hardware, firmware, or software of any fire protection system. The installer and operator codes must remain as the factory default setting.

2.3.7 Input/Output Modifications

The FMCU must contain features that allow the bypassing of input devices from the system or the modification of system outputs. These control features must consist of a control unit mounted keypad. Any bypass or modification to the system must indicate a trouble condition on the FMCU.

2.3.8 Resetting

Provide the necessary controls to prevent the resetting of any alarm, supervisory, or trouble signal while the alarm, supervisory or trouble condition on the system still exists.

2.3.9 Walk Test

The FMCU must have a walk test feature. When using this feature, operation of initiating devices must result in limited system outputs, so that the notification appliances operate for only a few seconds and the event is indicated in the history log, but no other outputs occur.

2.3.10 History Logging

The control unit must have the ability to store a minimum of 400 events in a log. These events must be stored in a battery-protected memory and must remain in the memory until the memory is downloaded or cleared manually. Resetting of the control unit must not clear the memory.

2.3.11 Manual Access

An operator at the control unit, having a proper access level, must have the capability to manually access the following information for each initiating device.

a. Primary status.

b. Device type.

c. Present average value.

d. Present sensitivity selected.

e. Detector range (normal, dirty).

2.3.12 Floor Plans

A laminated building floor plan (22" x 34") must be provided and mounted at the FMCU location. The floor plan must indicate the FMCU, LOC, remote power supply panel(s) and all initiating devices. The floor plan must indicate all rooms by number.

A laminated as-installed fire alarm wiring diagram (22" x 34") must be provided and mounted at the FMCU location. The wiring diagram must indicate fire alarm wiring, FMCU, LOC, annunciators, remote power supply panel(s), and all initiating device and notification appliances keyed to floor plans by room number. Provide a different color for each signaling line circuit, notification appliance circuit, speaker circuit, and data circuits.

2.4 LOCAL OPERATING CONSOLES (LOC)

2.4.1 General

The LOC must consist of a remote microphone station incorporating a push-to-talk (PTT) hand-held microphone and system status indicators. The LOC must have the capability of being utilized to activate prerecorded messages. The unit must incorporate microphone override of any tone generation or recorded messages. The unit must be fully supervised from the FMCU. The housing for the LOC must not be lockable.

2.5 AMPLIFIERS, PREAMPLIFIERS, TONE GENERATORS

Any amplifiers, preamplifiers, tone generators, digitalized voice generators, and other hardware necessary for a complete, operational, textual audible circuit conforming to NFPA 72 must be housed in a remote FMCU, terminal cabinet, or in the FMCU. Individual amplifiers must be 100 watts maximum.

2.5.1 Operation

The system must automatically operate and control all building speakers.

2.5.2 Construction

Amplifiers must utilize computer grade solid state components and must be provided with output protection devices sufficient to protect the amplifier against any transient up to 10 times the highest rated voltage in the system.

2.5.3 Inputs

Equip each system with separate inputs for the tone generator, digitalized voice driver and control unit mounted microphone. Microphone inputs must be of the low impedance, balanced line type. Both microphone and tone generator input must be operational on any amplifier.

2.5.4 Tone Generator

The tone generator must produce a three-pulse or four-pulse temporal pattern and must be constantly repeated until interrupted by either the digitalized voice message, the microphone input, or the alarm silence mode

as specified. The tone generator must be single channel with an automatic backup generator per channel such that failure of the primary tone generator causes the backup generator to automatically take over the functions of the failed unit and also causes transfer of the common trouble relay. The tone generator must be provided with securely attached labels to identify the component as a tone generator and to identify the specific tone it produces.

2.5.5 Protection Circuits

Each amplifier must be constantly supervised for any condition that could render the amplifier inoperable at its maximum output. Failure of any component must cause illumination of a visual "amplifier trouble" indicator on the control unit, appropriate logging of the condition in the history log, and other actions for trouble conditions as specified.

2.6 REMOTE ANNUNCIATOR

2.6.1 LCD Annunciator

Provide a semi-recessed mounted annunciator that includes an LCD display. The display must indicate the device in trouble/alarm or any supervisory device. Display the device name, address, and actual building location. The remote annunciator must duplicate functions of the FMCU for message display, fire alarm, supervisory alarm, and trouble conditions, visual and audible notification, and system reset functions. Remote annunciator must require the use of a key for accessing the reset, control and other functions.

A building floor plan must be provided and mounted (behind Plexiglass or similar protective material) at the annunciator location. The floor plan must indicate all rooms by name and number including the locations of stairs and elevators. The floor plan must show all devices and their programmed address to facilitate identification of their physical location from the LCD display information.

2.7 MANUAL STATIONS

Provide metal or plastic, semi-flush or surface mounted, double-action, addressable manual stations, that are not subject to operation by jarring or vibration. Stations must be addressable via a dual in-line package (DIP) switch or sundial that is manufactured within the device. Stations must be equipped with screw terminals for each conductor. Stations that require the replacement of any portion of the device after activation are not permitted. Stations must be finished in red with molded raised lettering operating instructions of contrasting color. The use of a key must be required to reset the station.

2.8 SMOKE DETECTORS

2.8.1 Spot Type Detectors

Provide addressable photoelectric smoke detectors as follows:

a. Provide analog/addressable photoelectric smoke detectors utilizing the photoelectric light scattering principle for operation in accordance with UL 268. Smoke detectors must be listed for use with the FMCU.

b. Provide self-restoring type detectors that do not require any

readjustment after actuation at the FMCU to restore them to normal operation. The detector must have a visual indicator to show actuation.

c. Vibration must have no effect on the detector's operation. Protect the detection chamber with a fine mesh metallic screen that prevents the entrance of insects or airborne materials. The screen must not inhibit the movement of smoke particles into the chamber.

d. Provide twist lock bases with screw terminals for each conductor. Provide twist lock base with sounder that produces a minimum of 90 dBA at 10 feet in duty room. The detectors must maintain contact with their bases without the use of springs.

e. The detector address must identify the particular unit, its location within the system, and its sensitivity setting. Detectors must be of the low voltage type rated for use on a 24 VDC system.

2.8.2 Duct Smoke Detectors

Duct-mounted addressable photoelectric smoke detectors must consist of a smoke detector, as specified in paragraph Spot Type Detectors, mounted in a special housing fitted with duct sampling tubes. Detector circuitry must be mounted in a metallic or plastic enclosure exterior to the duct. It is not permitted to cut the duct insulation to install the duct detector directly on the duct. Detectors must be listed for operation over the complete range of air velocities, temperature and humidity expected at the detector when the air-handling system is operating. Detectors must be powered from the FMCU.

a. Sampling tubes must run the full width of the duct. The duct detector package must conform to the requirements of NFPA 90A, UL 268A, and must be listed for use in air-handling systems. The control functions, operation, reset, and bypass must be controlled from the FMCU.

b. Lights to indicate the operation and alarm condition must be visible and accessible with the unit installed and the cover in place. Remote indicators must be provided where required by NFPA 72. Remote indicators as well as the affected fan units must be properly identified in etched plastic placards.

c. Detectors must provide for control of auxiliary contacts that provide control, interlock, and shutdown functions specified in Section 23 09 23.02 BACNET DIRECT DIGITAL CONTROL FOR HVAC AND OTHER BUILDING CONTROL SYSTEMS. Auxiliary contacts provide for this function must be located within 3 feet of the controlled circuit or appliance. The auxiliary contacts must be supplied by the fire alarm system manufacturer to ensure complete system compatibility.

2.9 CARBON MONOXIDE DETECTOR

Analog/addressable carbon monoxide (CO) detectors must be listed to UL 2075 and set to respond to the sensitivity limits of UL 2034. Carbon monoxide detectors must be listed for use with fire alarm control units. Detectors must be surface mounted in the vertical or horizontal orientation and supported independently of wiring connections. Detectors must be self-restoring. For FMCU with no listed compatible addressable CO detectors, provide listed 4-wire detectors. Do not provide CO detectors

with local alarms. Detector must be provided with an LED status indicator.

a. Where 4-wire CO detectors are necessary, each 4-wire CO detector must be individually monitored via addressable interface modules for alarm and off normal/trouble conditions (including loss of power to the individual detector). Power circuits for 4-wire CO detectors must be dedicated to powering the CO detectors only. Battery powered and 120 VAC powered detectors are prohibited.

b. Wiring connections must be made by means of screw terminals and detectors must be equipped with trouble relays. Detectors must be able to mount a single-gang electrical box.

c. A trouble condition at an individual CO detector must not affect any other CO detectors. CO detectors must be powered by the FMCU.

d. Detectors must be provided with a means to test CO gas entry into the CO sensing cell.

2.10 ADDRESSABLE INTERFACE DEVICES

The initiating device being monitored must be configured as a Class "B" initiating device circuits. The module must be listed as compatible with the control unit. The module must provide address setting means compatible with the control unit's SLC supervision and store an internal identifying code. Monitor module must contain an integral LED that flashes each time the monitor module is polled and is visible through the device cover plate. Pull stations with a monitor module in a common backbox are not required to have an LED. Modules must be listed for the environmental conditions in which they will be installed.

2.11 ADDRESSABLE CONTROL MODULES

The control module must be capable of operating as a relay (dry contact form C) for interfacing the control unit with other systems, and to control door holders or initiate elevator fire service. The module must be listed as compatible with the control unit. The indicating device or the external load being controlled must be configured as Class "B" notification appliance circuits. The system must be capable of supervising, audible, visual and dry contact circuits. The control module must have both an input and output address. The supervision must detect a short on the supervised circuit and must prevent power from being applied to the circuit. The control module must provide address setting means compatible with the control unit's SLC supervision and store an internal identifying code. The control module must contain an integral LED that flashes each time the control module is polled and is visible through the device cover plate. Control Modules must be listed for the environmental conditions in which they will be installed.

2.12 NOTIFICATION APPLIANCES

2.12.1 Audible Notification Appliances

Audible appliances must conform to the applicable requirements of UL 464. Appliances must be connected into notification appliance circuits. Surface mounted audible appliances must be painted white. Recessed audible appliances must be installed with a grill that is painted white.

2.12.1.1 Speakers

a. Speakers must conform to the applicable requirements of UL 1480. Speakers must have six different sound output levels and operate with audio line input levels of 70.7 VRMs and 25 VRMs, by means of selectable tap settings. Interior speaker tap settings must include taps of 1/4, 1/2, 1, and 2 watt, at a minimum. Exterior speakers must also be multi-tapped with no more than 15 watt maximum setting. Speakers must incorporate a high efficiency speaker for maximum output at minimum power across a frequency range of 400 Hz to 4,000 Hz, and must have a sealed back construction. Speakers must be capable of installation on standard 4-inch square electrical boxes. Where speakers and strobes are provided in the same location, they may be combined into a single unit. All inputs must be polarized for compatibility with standard reverse polarity supervision of circuit wiring via the FMCU.

b. Provide speaker mounting plates constructed of cold rolled steel having a minimum thickness of 16 gage or molded high impact plastic and equipped with mounting holes and other openings as needed for a complete installation. Fabrication marks and holes must be ground and finished to provide a smooth and neat appearance for each plate. Each plate must be primed and painted.

c. Speakers must utilize screw terminals for termination of all field wiring.

2.12.2 Visual Notification Appliances

Visual notification appliances must conform to the applicable requirements of UL 1638, UL 1971 and conform to the Architectural Barriers Act (ABA). Visual Notification Appliances must have clear high intensity optic lens, xenon flash tubes, or light emitting diode (LED) and be marked "Alert" in letters of contrasting color. The light pattern must be dispersed so that it is visible above and below the strobe and from a 90 degree angle on both sides of the strobe. Strobe flash rate must be 1 flash per second and a minimum of 15 candela based on the UL 1971 test. Strobe must be semi-flush mounted.

2.13 ELECTRIC POWER

2.13.1 Primary Power

Power must be 120 VAC 60 Hz service for the FMCU from the AC service to the building in accordance with NFPA 72.

2.14 SECONDARY POWER SUPPLY

Provide for system operation in the event of primary power source failure. Transfer from normal to auxiliary (secondary) power or restoration from auxiliary to normal power must be automatic and must not cause transmission of a false alarm.

2.14.1 Batteries

Provide sealed, maintenance-free, sealed lead acid batteries as the source for emergency power to the FMCU. Batteries must contain suspended electrolyte. The battery system must be maintained in a fully charged condition by means of a solid state battery charger. Provide an automatic

transfer switch to transfer the load to the batteries in the event of the failure of primary power.

2.14.1.1 Capacity

Battery size must be the greater of the following two capacities. This capacity applies to every control unit associated with this system, including supplemental notification appliance circuit panels, auxiliary power supply panels, fire alarm transmitters, and Base-wide mass notification transceivers. When determining the required capacity under alarm condition, visual notification appliances must include both textual and non-textual type appliances.

a. Sufficient capacity to operate the fire alarm system under supervisory and trouble conditions, including audible trouble signal devices for 48 hours and audible and visual signal devices under alarm conditions for an additional 15 minutes.

b. Sufficient capacity to operate the mass notification for 60 minutes after loss of AC power.

2.14.1.2 Battery Power Calculations

a. Verify that battery capacity exceeds supervisory and alarm power requirements for the criteria noted in the paragraph "Capacity" above.

(1) Substantiate the battery calculations for alarm and supervisory power requirements. Include ampere-hour requirements for each system component and each control unit component, and compliance with UL 864.

(2) Provide complete battery calculations for both the alarm and supervisory power requirements. Submit ampere-hour requirements for each system component with the calculations.

(3) Provide voltage drop calculations to indicate that sufficient voltage is available for proper operation of the system and all components. Calculations must be performed using the minimum rated voltage of each component.

b. For battery calculations assume a starting voltage of 24 VDC for starting the calculations to size the batteries. Calculate the required Amp-Hours for the specified standby time, and then calculate the required Amp-Hours for the specified alarm time. Using 20.4 VDC as starting voltage, perform a voltage drop calculation for circuits containing device and/or appliances remote from the power sources.

2.14.2 Battery Chargers

Provide a solid state, fully automatic, variable charging rate battery charger. The charger must be capable of providing 120 percent of the connected system load and must maintain the batteries at full charge. In the event the batteries are fully discharged (20.4 Volts dc), the charger must recharge the batteries back to 95 percent of full charge within 48 hours after a single discharge cycle as described in paragraph CAPACITY above. Provide pilot light to indicate when batteries are manually placed on a high rate of charge as part of the unit assembly if a high rate switch is provided.

2.15 SURGE PROTECTIVE DEVICES

Surge protective devices must be provided to suppress all voltage transients which might damage fire alarm control unit components. Systems having circuits located outdoors, communications equipment must be protected against surges induced on any signaling line circuit. Cables and conductors, that serve as communications links, must have surge protection circuits installed at each end. The surge protective device must wire in series to the power supply of the protected equipment with screw terminations. Line voltage surge arrestor must be installed directly adjacent to the power panel where the FMCU breaker is located.

a. Surge protective devices for nominal 120 VAC must be UL 1449 listed with a maximum 500 volt suppression level and have a maximum response time of 5 nanoseconds. The surge protective device must also meet IEEE C62.41.1 and IEEE C62.41.2 category B tests for surge capacity. The surge protective device must feature multi-stage construction and be provided with a long-life indicator lamp (either light emitting diode or neon) which extinguishes upon failure of protected components. Any unit fusing must be externally accessible.

b. Surge protective devices for nominal 24 VAC, fire alarm telephone dialer, or ethernet connection must be UL 497B listed, meet IEEE C62.41.1 and have a maximum response time of 1-nanosecond. The surge protective device must feature multi-stage construction and be self-resetting. The surge protective device must be a base and plug style. The base assembly must have screw terminals for fire alarm wiring. The base assembly must accept "plug-in" surge protective module.

c. All surge protective devices (SPD) must be the standard product of a single manufacturer and be equal or better than the following:

(1) For 120 VAC nominal line voltage: UL 1449 and UL 1283 listed, series connected 120 VAC, 20A rated, surge protective device in a NEMA 4x enclosure. Minimum 50,000 amp surge current rating with EMI/RFI filtering and a dry contact circuit for remote monitoring of surge protection status.

(2) For 24-volt nominal line voltage: UL 497B listed, series connected low voltage, 24-volt, 5A rated, loop circuit protector, base and replaceable module.

(3) For alarm telephone dialers: UL 497A listed, series connected, 130-volt, 150 mA rated with self-resetting fuse, dialer circuit protector with modular plug and play.

(4) For IP-DACTS: UL 497B listed, series connected, 6.4-volt, 1.5A rated with 20 kA/pair surge current, data network protector with modular plug and play.

2.16 WIRING

Provide wiring materials under this section as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM with the additions and modifications specified herein.

2.16.1 Alarm Wiring

IDC and SLC wiring must be fiber optic or solid or stranded copper cable in accordance with the manufacturers requirements. Copper signaling line circuits and initiating device circuit field wiring must be No. 14 AWG size conductors at a minimum. Visual notification appliance circuit conductors, that contain audible alarm appliances, must be copper No. 14 AWG size conductors at a minimum. Speaker circuits must be copper No. 16 AWG size twisted and shielded conductors at a minimum. Wire size must be sufficient to prevent voltage drop problems. Circuits operating at 24 VDC must not operate at less than the listed voltages for the detectors and/or appliances. Power wiring, operating at 120 VAC minimum, must be a minimum No. 12 AWG solid copper having similar insulation. Acceptable power-limited cables are FPL, FPLR or FPLP as appropriate with red colored covering. Nonpower-limited cables must comply with NFPA 70.

2.17 AUTOMATIC FIRE ALARM TRANSMITTERS

2.17.1 Digital Alarm Communicator Transmitter (DACT)

Provide DACT that is compatible with the existing supervising station fire alarm system. Transmitter must have a means to transmit alarm, supervisory, and trouble conditions via a single transmitter. Transmitter must have a source of power for operation that conforms to NFPA 72. Transmitter must be capable of initiating a test signal daily at any selected time. Transmitter must be arranged to seize telephone circuits in accordance with NFPA 72. Transmitter must be compatible with the Sur-Gard System III Multi-Platform Digital Telephone Receiver.

2.17.2 Signals to Be Transmitted to the Base Receiving Station

Points must be sent to the base receiving station utilizing Contact ID Protocol.

2.18 SYSTEM MONITORING

2.18.1 Valves

Each valve affecting the proper operation of a fire protection system, including automatic sprinkler control valves, sprinkler service entrance valve, valves at fire pumps, isolating valves for pressure type waterflow or supervision switches, and valves at backflow preventers, whether supplied under this contract or existing, must be electrically monitored to ensure its proper position. Provide each tamper switch with a separate address.

2.18.2 High/Low Nitrogen Supervisory Switches

Provide monitoring of high and low supervisory nitrogen for dry pipe systems. Each air supervisory switch must have a separate address. Switches must be listed extinguishing system attachments. The device must contain double pole, double throw contacts. Operation of the switch must cause a supervisory signal to be transmitted to the FMCU when nitrogen pressure in the system monitored sprinkler system increases more than 5 psi above the normal system pressure or drops halfway from the normal pressure to the tripping point.

2.18.3 Room Low Temperature Supervisory Switch

Provide listed supervisory air temperature switch for the ire pump room. Switch must cause a supervisory signal to be transmitted to the FMCU whenever the temperature in the room drops to below 40 degrees F. Device must reset when temperature rises above 40 degrees F.

2.19 ENVIRONMENTAL ENCLOSURES OR GUARDS

Environmental enclosures must be provided to permit fire alarm/mass notification components to be used in areas that exceed the environmental limits of the listing. The enclosure must be listed for the device or appliance as either a manufactured part number or as a listed compatible accessory for the component is currently listed. Guards required to deter mechanical damage must be either a listed manufactured part or a listed accessory for the category of the initiating device or notification appliance.

PART 3 EXECUTION

3.1 VERIFYING ACTUAL FIELD CONDITIONS

Before commencing work, examine all adjoining work on which the contractor's work is in any way dependent for perfect workmanship according to the intent of this specification section, and report to the Contracting Officer's Representative any condition which prevents performance of first class work. No "waiver of responsibility" for incomplete, inadequate or defective adjoining work will be considered unless notice has been filed before submittal of a proposal.

3.2 INSTALLATION

3.2.1 Fire Alarm and Mass Notification Control Unit (FMCU)

Locate the FMCU where indicated on the drawings. Surface mount the enclosure with the top of the cabinet 6 feet above the finished floor or center the cabinet at 5 feet, whichever is lower. Conductor terminations must be labeled and a drawing containing conductors, their labels, their circuits, and their interconnection must be permanently mounted in the FMCU. Locate the document storage cabinet adjacent to the FMCU unless the Contracting Officer directs otherwise.

3.2.2 Battery Cabinets

When batteries will not fit in the FMCU, locate battery cabinets below or adjacent to the FMCU. Battery cabinets must be installed at an accessible location when standing at floor level. Battery cabinets must not be installed lower than 12 inches above finished floor, measured to the bottom of the cabinet, nor higher than 36 inches above the floor, measured to the top of the cabinet. Installing batteries above drop ceilings or in inaccessible locations is prohibited. Battery cabinets must be large enough to accommodate batteries and also to allow ample gutter space for interconnection of control units as well as field wiring. The cabinet must be provided in a sturdy steel housing, complete with back box, hinged steel door with cylinder lock, and surface mounting provisions.The cabinet must be identified by an engraved phenolic resin nameplate. Lettering on the nameplate must indicate the control unit(s) the batteries power and must not be less than 1-inch high.

3.2.3 Manual Stations

Locate manual stations as required by NFPA 72 and as indicated on the drawings. Mount stations so they are located no farther than 5 feet from the exit door they serve, measured horizontally. Manual stations must be mounted at 48 inches measured to the operating handle.

3.2.4 Notification Appliances

a. Locate notification appliance devices as required by NFPA 72, where indicated, and to meet the intelligibility requirements. Where two or more visual notification appliances are located in the same room or corridor or field of view, provide synchronized operation. Devices must use screw terminals for all field wiring. Audible and visual notification appliances mounted in acoustical ceiling tiles must be centered in the tiles plus or minus 2 inches.

b. Audible and visual notification appliances mounted on the exterior of the building, within unconditioned spaces, or in the vicinity of showers must be listed weatherproof appliances installed on weatherproof backboxes.

c. Speakers must not be located in close proximity to the FMCU or LOC so as to cause feedback when the microphone is in use.

3.2.5 Smoke Detectors

Locate detectors as required by NFPA 72 and their listing and as indicated on the drawings on a 4-inch mounting box. Smoke detectors are permitted to be on the wall no lower than 12 inches from the ceiling with no minimum distance from the ceiling. Install smoke detectors no closer than 3 feet from air handling supply diffusers. Detectors installed in acoustical ceiling tiles must be centered in the tiles plus or minus 2 inches.

3.2.6 Carbon Monoxide Detectors

Locate detectors as required by NFPA 72 and their listings and as indicated on the drawings on a 4-inch mounting box. Carbon monoxide detectors must be installed separate from smoke detectors.

3.2.7 LCD REMOTE Annunciator

Locate the LCD annunciator as shown on the drawings. Mount the annunciator, with the top 6 feet above the finished floor or center the annunciator at 5 feet, whichever is lower.

3.2.8 Local Operating Console (LOC)

Locate the LOC(s) as required by NFPA 72 and as indicated. Mount the console so that the top message button and microphone is no higher than 4 feet above the floor and the bottom (lowest) message button and microphone is at least 3 feet above the finished floor.

3.2.9 Ceiling Bridges

Provide ceiling bridges for ceiling-mounted appliances. Ceiling bridges must be as recommended/required by the manufacturer of the ceiling-mounted notification appliance.

3.3 SYSTEM FIELD WIRING

3.3.1 Wiring within Cabinets, Enclosures, and Boxes

Provide wiring installed in a neat and workmanlike manner and installed parallel with or at right angles to the sides and back of any box, enclosure, or cabinet. Conductors that are terminated, spliced, or otherwise interrupted in any enclosure, cabinet, mounting, or junction box must be connected to screw-type terminal blocks. Mark each terminal in accordance with the wiring diagrams of the system. The use of wire nuts, crimped connectors, or similar devices is prohibited. The twisting of conductors is prohibited. Wiring to conform with NFPA 70.

Indicate the following in the wiring diagrams:

a. Point-to-point wiring diagrams showing the points of connection and terminals used for electrical field connections in the system, including interconnections between the equipment or systems that are supervised or controlled by the system. Diagrams must show connections from field devices to the FMCU and remote fire alarm/mass notification control units, initiating circuits, switches, relays and terminals.

b. Complete riser diagrams indicating the wiring sequence of devices and their connections to the control equipment. Include a color code schedule for the wiring. Include floor plans showing the locations of devices and equipment.

3.3.2 Terminal Cabinets

Provide a terminal cabinet at the base of any circuit riser, on each floor at each riser, and where indicated on the drawings. Terminal size must be appropriate for the size of the wiring to be connected. Conductor terminations must be labeled and a drawing containing conductors, their labels, their circuits, and their interconnection must be permanently mounted in the terminal cabinet. Minimum size is 8 inches by 8 inches. Only screw-type terminals are permitted. Provide an identification label, that displays "FIRE ALARM TERMINAL CABINET" with 2-inch lettering, on the front of the terminal cabinet.

3.3.3 Alarm Wiring

a. Voltages must not be mixed in any conduit or junction box, housing or device, except those containing power supplies and control relays.

b. Utilize shielded wiring where recommended by the manufacturer. For shielded wiring, ground the shield at only one point, in or adjacent to the FMCU.

c. Pigtail or T-tap connections to signal line circuits, initiating device circuits, supervisory alarm circuits, and notification appliance circuits are prohibited.

d. Color coding is required for circuits and must be maintained throughout the circuit. Conductors used for the same functions must be similarly color coded. Conform wiring to NFPA 70.

e. Pull all conductors splice free. The use of wire nuts, crimped connectors, or twisting of conductors is prohibited. Where splices

are unavoidable, the location of the junction box or pull box where they occur must be identified on the as-built drawings. The number and location of splices must be subject to approval by the Designated Fire Protection Engineer (DFPE).

3.3.4 Back Boxes and Conduit

In addition to the requirements of Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM, provide all wiring in rigid metal conduit or intermediate metal conduit unless specifically indicated otherwise. Minimum conduit size must be 3/4-inch in diameter. Do not use electrical non-metallic tubing (ENT) or flexible non-metallic tubing and associated fittings.

a. Galvanized rigid steel (GRS) conduit must be utilized where exposed to weather, where subject to physical damage, and where exposed on exterior of buildings. Intermediate metal conduit (IMC) may be used in lieu of GRS as allowed by NFPA 70.

b. Electrical metallic tubing (EMT) is permitted above suspended ceilings or exposed where not subject to physical damage. Do not use EMT underground, encased in concrete, mortar, or grout, in hazardous locations, where exposed to physical damage, outdoors or in fire pump rooms. Use die-cast compression connectors.

c. For rigid metallic conduit (RMC), only threaded type fitting are permitted for wet or damp locations.

d. Flexible metal conduit is permitted for initiating device circuits 6 feet in length or less. Flexible metal conduit is prohibited for notification appliance circuits and signaling line circuits. Use liquid tight flexible metal conduit in damp and wet locations.

e. Schedule 40 (minimum) polyvinyl chloride (PVC) is permitted where conduit is routed underground or underground below floor slabs. Convert non-metallic conduit, other than PVC Schedule 40 or 80, to plastic-coated rigid, or IMC, steel conduit before turning up through floor slab.

f. Exterior wall penetrations must be weathertight. Conduit must be sealed to prevent the infiltration of moisture.

3.3.5 Conductor Terminations

Labeling of conductors at terminal blocks in terminal cabinets, FMCU, and remote FMCU, and the LOC must be provided at each conductor connection. Each conductor or cable must have a shrink-wrap label to provide a unique and specific designation. Each terminal cabinet, FMCU, and remote FMCU must contain a laminated drawing that indicates each conductor, its label, circuit, and terminal. The laminated drawing must be neat, using 12 point lettering minimum size, and mounted within each cabinet, control unit, or unit so that it does not interfere with the wiring or terminals. Maintain existing color code scheme where connecting to existing equipment.

3.4 CONNECTION OF NEW SYSTEM

The following new system connections must be made during the last phase of construction, at the beginning of the pre-Government tests. New system connections must include:

a. Connection of new system transmitter to existing installation fire reporting system.

Once these connections are made, system must be left energized. Report immediately to the Contracting Officer, coordination and field problems resulting from the connection of the above components.

3.5 FIRESTOPPING

Provide firestopping for holes at conduit penetrations through floor slabs, fire-rated walls, partitions with fire-rated doors, corridor walls, and vertical service shafts in accordance with Section 07 84 00 FIRESTOPPING.

3.6 PAINTING

a. In unfinished areas (including areas above drop ceilings), paint all exposed electrical conduit (serving fire alarm equipment), fire alarm conduit, surface metal raceway, junction boxes and covers red. In lieu of painting conduit, the contractor may utilize red conduit with a factory applied finish.

b. In finished areas, paint exposed electrical conduit (serving fire alarm equipment), fire alarm conduit, surface metal raceways, junction boxes, and electrical boxes to match adjacent finishes. The inside cover of the junction box must be identified as "Fire Alarm" and the conduit must have painted red bands 3/4-inch wide at 10-foot centers and at each side of a floor, wall, or ceiling penetration.

c. Painting must comply with Section 09 90 00 PAINTS AND COATINGS.

3.7 FIELD QUALITY CONTROL

3.7.1 Test Procedures

Submit detailed test procedures, prepared and signed by the NICET Level IV Fire Alarm Technician, and the representative of the installing company, and reviewed by the QFPE 60 days prior to performing system tests. Detailed test procedures must list all components of the installed system such as initiating devices and circuits, notification appliances and circuits, signaling line devices and circuits, control devices/equipment, batteries, transmitting and receiving equipment, power sources/supply, annunciators, special hazard equipment, emergency communication equipment, interface equipment, and surge protective devices. Test procedures must include sequence of testing, time estimate for each test, and sample test data forms. The test data forms must be in a check-off format (pass/fail with space to add applicable test data; similar to the forms in NFPA 72 and NFPA 4.) The test procedures and accompanying test data forms must be used for the pre-Government testing and the Government testing. The test data forms must record the test results and must:

a. Identify the NFPA Class of all Initiating Device Circuits (IDC), and Notification Appliance Circuits (NAC), Voice Notification System Circuits (NAC Audio), and Signaling Line Circuits (SLC).

b. Identify each test required by NFPA 72 Test Methods and required test herein to be performed on each component, and describe how these tests must be performed.

c. Identify each component and circuit as to type, location within the facility, and unique identity within the installed system. Provide necessary floor plan sheets showing each component location, test location, and alphanumeric identity.

d. Identify all test equipment and personnel required to perform each test (including equipment necessary for smoke detector testing. The use of magnets is not permitted.

e. Provide space to identify the date and time of each test. Provide space to identify the names and signatures of the individuals conducting and witnessing each test.

3.7.2 Pre-Government Testing

3.7.2.1 Verification of Compliant Installation

Conduct inspections and tests to ensure that devices and circuits are functioning properly. Tests must meet the requirements of paragraph entitled "Minimum System Tests" as required by NFPA 72. The contractor and an authorized representative from each supplier of equipment must be in attendance at the pre-Government testing to make necessary adjustments. After inspection and testing is complete, provide a signed Verification of Compliant Installation letter by the QFPE that the installation is complete, compliant with the specification and fully operable. The letter must include the names and titles of the witnesses to the pre-Government tests. Provide all completion documentation as required by NFPA 72 including all referenced annex sections and the test reports noted below.

a. NFPA 72 Record of Completion.

b. NFPA 72 Record of Inspection and Testing.

c. Fire Alarm and Emergency Communication System Inspection and Testing Form.

d. Audibility test results with marked-up test floor plans.

e. Intelligibility test results with marked-up floor plans.

f. Documentation that all tests identified in the paragraph "Minimum System Tests" are complete.

3.7.2.2 Request for Government Final Test

When the verification of compliant installation has been completed, submit a formal request for Government final test to the Designated Fire Protection Engineer (DFPE). Government final testing will not be scheduled until the DFPE has received copies of the request for Government final testing and Verification of Compliant Installation letter with all required reports. Government final testing will not be performed until after the connections to the installation-wide fire reporting system been completed and tested to confirm communications are fully functional. Submit request for test at least 15 calendar days prior to the requested test date.

3.7.3 Correction of Deficiencies

If equipment was found to be defective or non-compliant with contract requirements, perform corrective actions and repeat the tests. Tests must be conducted and repeated if necessary until the system has been demonstrated to comply with all contract requirements.

3.7.4 Government Final Tests

The tests must be performed in accordance with the approved test procedures in the presence of the DFPE. Furnish instruments and personnel required for the tests. The following must be provided at the job site for Government Final Testing:

a. The manufacturer's technical representative.

b. The contractor's Qualified Fire Protection Engineer (QFPE).

c. Marked-up red line drawings of the system as actually installed.

d. Loop resistance test results.

e. Complete program printout including input/output addresses.

f. Copy of pre-Government Test Certificate, test procedures and completed test data forms.

g. Audibility test results with marked-up floor plans.

h. Intelligibility test results with marked-up floor plans.

Government Final Tests will be witnessed by the Designated Fire Protection Engineer and Qualified Fire Protection Engineer (QFPE). At this time, any and all required tests noted in the paragraph "Minimum System Tests" must be repeated at their discretion.

3.8 MINIMUM SYSTEM TESTS

3.8.1 System Tests

Test the system in accordance with the procedures outlined in NFPA 72. The required tests are as follows:

a. Loop Resistance Tests: Measure and record the resistance of each circuit with each pair of conductors in the circuit short-circuited at the farthest point from the circuit origin. The tests must be witnessed by the Contracting Officer and test results recorded for use at the final Government test.

b. Verify the absence of unwanted voltages between circuit conductors and ground. Wiring must be free of opens, shorts, and grounds. The tests must be accomplished at the pre-Government test with results available at the final system test.

c. Verify that the control unit is in the normal condition as detailed in the manufacturer's O&M manual.

d. Test each initiating device and notification appliance and circuit for proper operation and response at the control unit. Smoke detectors

must be tested in accordance with manufacturer's recommended calibrated test method. Use of magnets is prohibited. Testing of duct smoke detectors must comply with the requirements of NFPA 72 except disconnect at least 20 percent of devices. If there is a failure at these devices, then supervision must be tested at each device.

e. Carbon Monoxide Detector Tests: Carbon monoxide detectors must be tested in accordance with NFPA 72 and the manufacturer's recommended calibrated test method.

f. Test the system for specified functions in accordance with the contract drawings and specifications and the manufacturer's O&M manual.

g. Test both primary power and secondary power. Verify, by test, the secondary power system is capable of operating the system for the time period and in the manner specified.

h. Determine that the system is operable under trouble conditions as specified.

i. Visually inspect wiring.

j. Test the battery charger and batteries.

k. Verify that software control and data files have been entered or programmed into the FMCU. Hard copy records of the software must be provided to the Contracting Officer.

l. Verify that red-line drawings are accurate.

m. Measure the current in circuits to ensure there is the calculated spare capacity for the circuits.

n. Measure voltage readings for circuits to ensure that voltage drop is not excessive.

o. Disconnect the verification feature for smoke detectors during tests to minimize the amount of smoke needed to activate the sensor. Testing of smoke detectors must be conducted using real smoke or the use of canned smoke which is permitted.

p. Measure the voltage drop at the most remote appliance (based on wire length) on each notification appliance circuit.

q. Verify the documentation cabinet is installed and contains all as-built shop drawings, product data sheets, design calculations, site-specific software data package, and all documentation required by paragraph titled "Test Reports".

3.8.2 Audibility Tests

Sound pressure levels from audible notification appliances must be a minimum of 15 dBa over ambient with a maximum of 110 dBa in any occupiable area. The provisions for audible notification (audibility and intelligibility) must be met with doors, fire shutters, movable partitions, and similar devices closed.

3.8.3 Intelligibility Tests

Intelligibility testing of the System must be accomplished in accordance with NFPA 72 for Voice Evacuation Systems, and ASA S3.2. Following are the specific requirements for intelligibility tests:

a. Intelligibility Requirements: Verify intelligibility by measurement after installation.

b. Ensure that a CIS value greater than the required minimum value is provided in each area where building occupants typically could be found. The minimum required value for CIS is 0.7. Rounding of values is permitted.

c. Areas of the building provided with hard wall and ceiling surfaces (such as metal or concrete) that are found to cause excessive sound reflections may be permitted to have a CIS score less than the minimum required value if approved by the DFPE, and if building occupants in these areas can determine that a voice signal is being broadcast and they must walk no more than 33 feet to find a location with at least the minimum required CIS value within the same area.

d. Areas of the building where occupants are not expected to be normally present are permitted to have a CIS score less than the minimum required value if personnel can determine that a voice signal is being broadcast and they must walk no more than 50 feet to a location with at least the minimum required CIS value within the same area.

e. Take measurements near the head level applicable for most personnel in the space under normal conditions (e.g., standing, sitting, sleeping, as appropriate).

f. The distance the occupant must walk to the location meeting the minimum required CIS value must be measured on the floor or other walking surface as follows:

(1) Along the centerline of the natural path of travel, starting from any point subject to occupancy with less than the minimum required CIS value.

(2) Curving around any corners or obstructions, with a 12 inches clearance there from.

(3) Terminating directly below the location where the minimum required CIS value has been obtained.

g. Intelligibility test is required after the system installation as part of the preliminary tests and final inspection and acceptance tests. This project has a separate FF&E contractor who installs the furniture systems after the construction contractor. FF&E affects tremendously to the fire alarm and mass notification system intelligibility level. To ensure the facility is code compliant prior to building occupancy, the construction contractor is required to conduct another intelligibility test after the completion of FF&E installation, and witnessed by the Government. If the fire alarm and mass notification system fails the intelligibility test, the construction contractor must be responsible to modify the system to meet intelligibility requirement in accordance with the contract without incurring additional cost to the Government.

Use commercially available test instrumentation to measure intelligibility as specified by NFPA 72 as applicable. Use the mean value of at least three readings to compute the intelligibility score at each test location.

3.9 SYSTEM ACCEPTANCE

Following acceptance of the system, as-built drawings and O&M manuals must be delivered to the Contracting Officer for review and acceptance. The drawings must show the system as installed, including deviations from both the project drawings and the approved shop drawings. These drawings must be submitted within two weeks after the final Government test of the system. At least one set of as-built (marked-up) drawings must be provided at the time of, or prior to the Final Government Test.

a. The drawings must be prepared electronically and sized no less than the contract drawings. Furnish one set of CDs or DVDs containing software back-up and CAD based drawings in latest version of AutoCAD, DXF and portable document formats of as-built drawings and schematics.

b. Include complete wiring diagrams showing connections between devices and equipment, both factory and field wired.

c. Include a riser diagram and drawings showing the as-built location of devices and equipment.

d. Provide Operation and Maintenance (O&M) Instructions.

3.10 INSTRUCTION OF GOVERNMENT EMPLOYEES

3.10.1 Instructor

Provide the services of an instructor, who has received specific training from the manufacturer for the training of other persons regarding the operation, inspection, testing, and maintenance of the system provided. The instructor must train the Government employees designated by the Contracting Officer, in the care, adjustment, maintenance, and operation of the fire alarm system. The instructor must be thoroughly familiar with all parts of this installation. The instructor must be trained in operating theory as well as in practical O&M work. Submit the instructors information and qualifications including the training history.

3.10.2 Required Instruction Time

Provide 8 hours of instruction after final acceptance of the system. The instruction must be given during regular working hours on such dates and times selected by the Contracting Officer. The instruction may be divided into two or more periods at the discretion of the Contracting Officer. The training must allow for rescheduling for unforeseen maintenance and/or fire department responses.

3.10.2.1 Technical Training

Equipment manufacturer or a factory representative must provide 1 day of on site and 5 days of technical training to the Government at the manufacturing facility. Training must allow for classroom instruction as well as individual hands on programming, troubleshooting and diagnostics exercises. Factory training must occur within 6 months of system acceptance.

3.10.3 Technical Training Manual

Provide, in manual format, lesson plans, operating instructions, maintenance procedures, and training data for the training courses. The operations training must familiarize designated government personnel with proper operation of the installed system. The maintenance training course must provide the designated government personnel adequate knowledge required to diagnose, repair, maintain, and expand functions inherent to the system.

3.11 EXTRA MATERIALS

3.11.1 Repair Service/Replacement Parts

Repair services and replacement parts for the system must be available for a period of 10 years after the date of final acceptance of this work by the Contracting Officer. During the warranty period, the service technician must be on-site within 24 hours after notification. All repairs must be completed within 24 hours of arrival on-site.

During the warranty period, the installing fire alarm contractor is responsible for conducting all required testing and maintenance in accordance with the requirements and recommended practices of NFPA 72 and the system manufacturer(s). Installing fire alarm contractor is NOT responsible for any damage resulting from abuse, misuse, or neglect of equipment by the end user.

3.11.2 Spare Parts

Provide a spare parts box adjacent to the FMCU. Spare parts box must be a steel cabinet with locking, hinge-mounted door. Spare parts box must be mounted no more than 3-ft above the finished floor.

Spare parts furnished must be directly interchangeable with the corresponding components of the installed system(s). Spare parts must be suitably packaged and identified by nameplate, tagging, or stamping. Spare parts must be placed in the spare parts box and must be accompanied by an inventory list.

3.11.3 Document Storage Cabinet

Upon completion of the project, but prior to project close-out, place in the document storage cabinet copies of the following record documentation:

a. As-built shop drawings

b. Product data sheets

c. Design calculations

d. Site-specific software data package

e. All documentation required by SD-06.

-- End of Section --

SECTION 31 00 00

EARTHWORK
08/23

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(2017) Standard Method of Test for Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and a 457-mm (18-in.) Drop

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C600	(2017) Installation of Ductile-Iron Mains and Their Appurtenances

ASTM INTERNATIONAL (ASTM)

ASTM C33/C33M	(2024a) Standard Specification for Concrete Aggregates
ASTM C117	(2017) Standard Test Method for Materials Finer than 75-um (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C136/C136M	(2019) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM C150/C150M	(2024) Standard Specification for Portland Cement
ASTM C260/C260M	(2010a; R 2016) Standard Specification for Air-Entraining Admixtures for Concrete
ASTM C618	(2025a) Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C989/C989M	(2022) Standard Specification for Slag Cement for Use in Concrete and Mortars
ASTM D698	(2012; E 2014; E 2015) Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/cu. ft. (600 kN-m/cu. m.))
ASTM D1140	(2017) Standard Test Methods for Determining the Amount of Material Finer

	than 75-µm (No. 200) Sieve in Soils by Washing
ASTM D1556/D1556M	(2015; E 2016) Standard Test Method for Density and Unit Weight of Soil in Place by Sand-Cone Method
ASTM D1557	(2012; E 2015) Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft3) (2700 kN-m/m3)
ASTM D2216	(2019) Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass
ASTM D2487	(2017; E 2020) Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D2974	(2020; E 2020) Moisture, Ash, and Organic Matter of Peat and Other Organic Soils
ASTM D4253	(2016; E 2019) Standard Test Methods for Maximum Index Density and Unit Weight of Soils Using a Vibratory Table
ASTM D4254	(2016) Standard Test Methods for Minimum Index Density and Unit Weight of Soils and Calculation of Relative Density
ASTM D4318	(2017; E 2018) Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D4829	(2021) Standard Test Method for Expansion Index of Soils
ASTM D4832	(2016; E 2018) Standard Test Method for Preparation and Testing of Controlled Low Strength Material (CLSM) Test Cylinders
ASTM D5268	(2019) Topsoil Used for Landscaping Purposes
ASTM D6023	(2016) Standard Test Method for Density (Unit Weight), Yield, Cement Content, and Air Content (Gravimetric) of Controlled Low-Strength Material (CLSM)
ASTM D6103/D6103M	(2017; E 2021) Standard Test Method for Flow Consistency of Controlled Low Strength Material (CLSM)
ASTM D6938	(2017a) Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)

ASTM D8167/D8167M	(2023) Standard Test Method for In-Place Bulk Density of Soil and Soil-Aggregate by a Low-Activity Nuclear Method (Shallow Depth)

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2024) Safety -- Safety and Occupational Health (SOH) Requirements

1.2 DEFINITIONS

1.2.1 Structural Fill

Soil material placed to support buildings, walls, pads, and other similar facilities.

1.2.2 Embankment Fill (also referred to as General Site Fill)

Soil material placed to construct embankment(s) or placed at locations outside of structure building lines and pavement areas..

1.2.3 Porous Fill

Free-draining material placed for subsurface drainage, as a capillary break, or another specific purpose.

1.2.4 Topsoil

Surface layer of primarily organic soil capable of supporting vegetation growth.

1.2.5 Utility Bedding Material

Fill placed to directly support pipes, conduits, cables, and appurtenant structures. Bedding may also be used to provide a cushion between utilities and bedrock, obstacles, obstructions and other unyielding materials.

1.2.6 Flowable Fill

Fill placed in a plastic or liquid form that flows to near its final placement location with limited assistance and subsequently cures or solidifies to provide a stable or impermeable barrier.

1.2.7 Satisfactory Materials

Satisfactory materials for fill, backfill, and/or any in-situ soils to remain in place comprise any materials classified by ASTM D2487 as GW, GP, GM, GP-GM, GW-GM, GC, GP-GC, GM-GC, SW, SP, SM, SW-SM, SP-SM. Maximum particle size to be no greater than one-half of the allowable lift thickness in any dimension.

1.2.8 Unsatisfactory Materials

Materials which do not comply with the requirements for satisfactory materials are unsatisfactory. Unsatisfactory materials also include man-made fills; trash; refuse; backfills from previous construction; roots

and other organic matter or frozen material. Notify the Contracting Officer when encountering any contaminated materials.

1.2.9 Cohesionless Materials

Cohesionless materials include materials classified in ASTM D2487 as GW, GP, SW, and SP. Materials classified as GM and SM will be identified as cohesionless only when the fines are nonplastic. Perform testing, required for classifying materials, in accordance with ASTM D4318, ASTM C117, ASTM C136/C136M and ASTM D1140.

1.2.10 Cohesive Materials

Cohesive materials include materials classified as GC, SC, ML, CL, MH, and CH. Materials classified as GM and SM will be identified as cohesive only when the fines are plastic. Perform testing, required for classifying materials, in accordance with ASTM D4318, ASTM C117, ASTM C136/C136M and ASTM D1140.

1.2.11 Hard/Unyielding Materials

Hard/Unyielding materials comprise weathered rock, dense consolidated deposits, or conglomerate materials which are not included in the definition of "rock" with stones greater than 3 inch in any dimension or as defined by the pipe manufacturer, whichever is smaller. These materials usually require the use of heavy excavation equipment, ripper teeth, or jack hammers for removal.

1.2.12 Unstable Material

Unstable materials are too weak to adequately support the utility pipe, conduit, equipment, or appurtenant structure. Satisfactory material may become unstable due to ineffective drainage, dewatering, becoming frozen, excessive loading.

1.2.13 Expansive Soils

Expansive soils are defined as soils that have an expansion index greater than 20 when tested in accordance with ASTM D4829.

1.2.14 Rock

Solid homogeneous interlocking crystalline material with firmly cemented, laminated, or foliated masses or conglomerate deposits, neither of which can be removed without systematic drilling and blasting, drilling and the use of expansion jacks or feather wedges, or the use of backhoe-mounted pneumatic hole punchers or rock breakers; also large boulders, buried masonry, or concrete other than pavement exceeding 1/2 cubic yard in volume. Removal of hard material will not be considered rock excavation because of intermittent drilling and blasting that is performed merely to increase production.

1.2.15 Capillary Water Barrier

A layer of clean, poorly graded crushed rock, stone, or natural sand or gravel having a high porosity which is placed beneath a building slab with or without a vapor barrier to cut off the capillary flow of pore water to the area immediately below a slab.

1.2.16 Degree of Compaction (Proctor)

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum density obtained by the test procedure presented in ASTM D1557 abbreviated as a percent of laboratory maximum density. Since ASTM D1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 3/4 inch sieve, express the degree of compaction for material having more than 30 percent by weight of their particles retained on the 3/4 inch sieve as a percentage of the maximum density in accordance with AASHTO T 180-21 paragraph 1.5, Note 1.

1.2.17 Degree of Compaction (Relative Density)

Degree of compaction required for soils with less than 5 percent passing the No. 200 sieve, is expressed as a relative percentage of the maximum index density/dry unit weight and minimum index density/dry unit weight, obtained by the test procedures in accordance with ASTM D4253 and ASTM D4254, respectively, abbreviated as a percent of laboratory relative density.

1.2.18 Borrow

Soil brought to the project site from an external location for the purposes of project construction.

1.2.19 Subgrade

Earth materials directly below foundations and directly below granular base materials in building slab and pavement areas including shoulders.

1.3 SUBSURFACE DATA

Subsurface soil boring logs are shown in project plans. These data represent available subsurface information; however, variations may exist between boring locations.

1.4 CRITERIA FOR BIDDING

Base bids on the following criteria:

a. Surface elevations are as indicated.

b. Pipes or other artificial obstructions, except those indicated, will not be encountered.

c. Ground water elevations indicated by the boring log were those existing at the time subsurface investigations were made and do not necessarily represent ground water elevation at the time of construction.

d. Ground water elevation is indicated by the boring logs.

e. Material character is indicated by the boring logs.

f. Hard materials and rock will not be encountered.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Excavation and Trenching Plan; G

Dewatering Work Plan; G

Jacking, Boring, and Tunneling Plan; G

Preconstruction Meeting; G

SD-03 Product Data

Flowable Fill Mix Design; G

Geotextiles

SD-06 Test Reports

Material Test Report; G

Pipe Inspection Report; G

Geotechnical Evaluation Report; G

1.6 QUALITY CONTROL

1.6.1 Geotechnical Engineer

Provide a Professional Geotechnical Engineer to provide inspection of excavations and soil/groundwater conditions throughout construction. The Geotechnical Engineer is responsible for performing pre-construction and periodic site visits throughout construction to assess site conditions. The Geotechnical Engineer is responsible for preparing and updating the Excavation and Trenching Plan and Dewatering Work Plan as construction progresses to reflect changing conditions and submit an updated plan if necessary. Submit a monthly Geotechnical Evaluation report, informing the Contractor and Contracting Officer of the status of the plan and an accounting of the Contractor's adherence to the plan addressing any present or potential problems. The Contractor is responsible for arranging meetings with the Geotechnical Engineer and Contracting Officer throughout the contract duration.

1.6.2 Qualified Technician

Provide a Qualified Technician to inspect, monitor, sample, and performing field testing. The technician qualifications need to be one of the following: a current National Institute for Certification in Engineering Technologies (NICET) Level II minimum certification in Construction Materials Testing Soils; a Geologist-in-Training with minimum one-year experience; an Engineer-in-Training with minimum one-year experience; a Registered Geologist; or a Professional Engineer.

1.6.3 Lab Validation

Perform testing by a Corps validated commercial testing laboratory or Contractor established testing laboratory meeting the requirements and approved by the Contracting Officer. Submit testing laboratory validation for the testing to be performed. Do not permit work requiring testing until testing facilities have been inspected, Corps validated and approved by the Contracting Officer.

1.6.4 Preconstruction Meeting

Conduct a preconstruction meeting at the jobsite at least five business days prior to the start of earthwork operations on the project. The preconstruction meeting is to be arranged by the Contractor and is to follow the written agenda submitted prior to the meeting. The purpose of this meeting is to review the requirements of this specification and the associated plans. The following individuals must be in attendance at this meeting: Contractor's Project Manager and Project Superintendent, earthwork subcontractor's Project Manager and Site Foreman, Contractor's Geotechnical Engineer and Testing Agency, Government Geotechnical Engineer and Civil Engineer, and Government Construction Manager and Engineering Technician.

The minutes of this meeting are to be recorded by the Contractor and published via email within 48 hours to all attendees. The minutes must be re-published within 48 hours via email pending any subsequent comments from the attendees.

1.6.5 Excavation and Trenching Plan

Submit an Excavation and Trenching Plan a minimum of 15 days prior to planned start of excavation. The plan must outline the projected depth of the excavation based on soil characteristics and the planned method of sloping, benching, sheeting/shoring, and stabilizing soil to permit construction to progress. Submit drawings and sketches; showing limits methods, and sequencing of excavation, proposed onsite and offsite soil disposal areas; and the numbers, types, and sizes of equipment proposed to perform excavations. The work plan must address any anticipated difficulties and proposed resolutions

1.6.6 Utilities

Movement of construction machinery and equipment over pipes and utilities during construction must be at the Contractors's risk. Excavation made with power-driven equipment is not permitted within two feet of know Government-owned utility or subsurface construction. For work immediately adjacent to or for excavations exposing a utility or other buried obstruction, excavate by hand. Start had excavation on each side of the indicated obstruction and continue until the obstruction is uncovered or until clearance for the new grade is assured. Support uncovered lines or other existing work affected by the contract excavation until approval for backfill is granted by the Contracting Officer. Report damage to utility lines or subsurface construction immediately to the Contracting Officer.

PART 2 PRODUCTS

2.1 SOIL MATERIALS

2.1.1 Structural Fill

Materials classified as GW, GP,GM, GC, SW, SP, SM, or in accordance with ASTM D2487. Select material type appropriate for the intended purpose.

2.1.2 Embankment Fill

Materials classified as GW, GP, GM, GC, GW-GM, GW-GC, GP-GM, GP-GC, GC-GM, SW, SP, SM, SW-SM, SP-SM, or in accordance with ASTM D2487. Select material type appropriate for the intended purpose.

2.1.3 Porous Fill

Materials containing less than 5 percent passing the No. 200 sieve. Provide the gradation as appropriate for the intended purpose.

2.1.4 Topsoil

Material suitable for topsoil obtained from offsite areas is defined as: Natural, friable soil representative of productive, well-drained soils in the area, free of subsoil, stumps, rocks larger than one inch diameter, brush, weeds, toxic substances, and other material detrimental to plant growth. Topsoil material will be in accordance with ASTM D5268.

2.1.5 Capillary Water Barrier

Conform to ASTM C33/C33M for fine aggregate grading with a maximum of 3 percent by weight passing ASTM D1140, No. 200 sieve.

2.1.6 Utility Bedding Material

Except as specified otherwise in the individual piping section, provide bedding for buried piping in accordance with AWWA C600. Install bedding for plastic piping to spring line of pipe. Utility bedding material may include the following:

2.1.6.1 Gravel and Crushed Stone

Clean, coarsely graded natural gravel, crushed stone or a combination thereof identified as #67 stone, or having a classification of GW GP in accordance with ASTM D2487 for bedding. Do not exceed maximum particle size of 3 inches.

2.2 FLOWABLE FILL

Design and submit flowable fill mix design to consist of Portland cement, fly ash, and/or slag cement and fine aggregate. Include the dry weights of cementitious material(s); quality and gradation of aggregates in the saturated surface-dry weights along with gradation tests; quantities, types, and names of admixtures; and quantity of water per cubic yard. The minimum unconfined compressive strength to be 3500 psi at 28 days in accordance with ASTM D4832. The aggregates in accordance with ASTM C33/C33M Fine Aggregates. Air-entrain fill in accordance with ASTM C260/C260M. The air content to be between 8 and 15 percent in accordance with ASTM D6023. The flow to be between 8 and 12 inches in

accordance with ASTM D6103/D6103M. Portland cement to be Type I or II in accordance with ASTM C150/C150M. Fly ash to be Class C in accordance with ASTM C618. Provide slag cement in Grade 100 or 120 in accordance with ASTM C989/C989M.

2.3 BURIED WARNING AND IDENTIFICATION MARKERS

Provide polyethylene plastic and metallic core or metallic-faced, acid- and alkali-resistant, polyethylene plastic warning tape manufactured specifically for warning and identification of buried utility lines. Provide tape on rolls, 3 inches minimum width, color coded as specified below for the intended utility with warning and identification imprinted in bold black letters continuously over the entire tape length. Warning and identification to read, "CAUTION, BURIED (intended service) LINE BELOW" or similar wording. Provide permanent color and printing, unaffected by moisture or soil.

Warning Tape Color Codes	
Red	Electric
Yellow	Gas, Oil; Dangerous Materials
Orange	Telephone and Other Communications
Blue	Water Systems
Green	Sewer Systems
White	Steam Systems
Gray	Compressed Air

2.3.1 Warning Tape for Metallic Piping

Provide acid and alkali-resistant polyethylene plastic tape conforming to the width, color, and printing requirements specified above, with a minimum thickness of 0.003 inch and a minimum strength of 1500 psi lengthwise, and 1250 psi crosswise, with a maximum 350 percent elongation.

2.3.2 Detectable Warning Tape for Non-Metallic Piping

Provide polyethylene plastic tape conforming to the width, color, and printing requirements specified above, with a minimum thickness of 0.004 inch, and a minimum strength of 1500 psi lengthwise and 1250 psi crosswise. Manufacture tape with integral wires, foil backing, or other means of enabling detection by a metal detector when tape is buried up to 3 feet deep. Encase metallic element of the tape in a protective jacket or provide with other means of corrosion protection.

2.3.3 Detection Wire for Non-Metallic Piping

Insulate a single strand, solid copper detection wire with a minimum of 12 AWG.

2.4 MATERIAL FOR RIP-RAP

Provide bedding material or filter fabric and rock conforming to NCDOT SS, Section 1042, Class B for construction indicated.

2.4.1 Bedding Material

Provide bedding material consisting of sand, gravel, or crushed rock, well graded, with a maximum particle size of 2 inches. Compose material of tough, durable particles. Allow fines passing the No. 200 standard sieve with a plasticity index less than 6.

2.4.2 Rock

Provide rock fragments which ensure permanence in the structure and the environment in which it is to be used. Use rock fragments free from cracks, seams, and other defects that would increase the risk of deterioration from natural causes. Provide fragments sized such that no individual fragment exceeds a weight of 150 pounds and that no more than 10 percent of the mixture, by weight, consists of fragments weighing 2 pounds or less each. Provide rock with a minimum specific gravity of 2.50. Do not permit the inclusion of more than trace 1 percent quantities of dirt, sand, clay and rock fines.

2.5 BORROW

Provide borrow materials from sources located outside of Government property meeting the requirements of paragraph STRUCTURAL FILL.

2.6 GEOTEXTILE

Provide a pervious sheet of polyester, nylon, glass or polypropylene ultraviolet resistant filaments woven, spun bonded, fused, or otherwise manufactured into a non-raveling fabric with uniform thickness and strength. Fabric must have manufacturer certified minimum average roll properties that conform with ASTM D4759. Submit a sample and material product data for all Geotextiles utilized.

PART 3 EXECUTION

3.1 PROTECTION

Perform all work specified in accordance with applicable requirements of the Corps of Engineers publication EM 385-1-1 Safety and Health Requirements Manual. Provide a Geotechnical Engineer to monitor construction activities and to prepare necessary work plans and reports; see paragraph QUALITY CONTROL.

Use equipment of type and size appropriate for the site conditions (soil character and moisture content). Maintenance of exposed subgrades and fills is the responsibility of the Contractor. The Contractor is required to prevent damage by ineffective drainage, dewatering, and heavy loads and equipment by implementing precautionary measures. Repair or replace any defects or damage at Contractor's expense..

3.1.1 Underground Utilities

Location of the existing utilities indicated is approximate. Physically verify the location and elevation of the existing utilities indicated

prior to starting construction. The Contractor is responsible for protecting utilities from damage during construction.

3.1.2 Drainage and Dewatering

Provide for the collection and disposal of surface and subsurface water encountered during construction.

3.1.2.1 Drainage

Provide for the collection and disposal of surface and subsurface water encountered during construction. Construct storm drainage features (ponds/basins) at the earliest stages of site development, and throughout construction grade the construction area to provide positive surface water runoff away from the construction activity and provide temporary ditches, swales, and other drainage features and equipment as required to keep soils from becoming unstable, prevent erosion, or undermining of foundations. Remove unstable material from working platforms for equipment operation and soil support for subsequent construction features and provide new material as specified herein. It is the responsibility of the Contractor to assess the site conditions to employ necessary measures to permit construction to proceed.

3.1.2.2 Dewatering

Control groundwater flowing toward or into excavations to prevent sloughing of excavation slopes and walls, boils, uplift and heave in the excavation and to eliminate interference with orderly progress of construction. French drains, sumps, ditches or trenches are not allowed within 3 feet of the foundation of any structure, except with specific written approval, and after specific contractual provisions for restoration of the foundation area have been made. Perform control measures by the time the excavation reaches the water level in order to maintain the integrity of the in-situ material. While the excavation is open, maintain the water level continuously, at least 1 feet below the working level. Submit a Dewatering Work Plan outlining procedures for accomplishing dewatering work.

3.1.3 Shoring and Sheeting

Submit an Excavation and Trenching Plan to stabilize features, prevent undermining or unintended horizontal and vertical movement of adjacent structures, and prevent slippage or movement in banks or slopes adjacent to the excavation. Submit drawings and calculations, certified by a registered professional engineer, describing the methods for shoring and sheeting of excavations. Drawings to include material sizes and types, arrangement of members, and the sequence and method of installation and removal. Calculations are to include data and references used.

3.1.4 Protection of Graded Surfaces

Protect newly backfilled, graded, and topsoiled areas from traffic, erosion, and settlements that may occur. Repair or reestablish damaged grades, elevations, or slopes.

3.1.5 Machinery and Equipment

Movement to construction machinery and equipment over pipes during construction must be at the Contractor's risk. Repair, or remove and

provide new pipe for existing or newly installed pipe that has been damaged or displaced

3.2 BORROW

Select borrow material to meet the requirements and conditions of the fill or embankment for which it is to be used. Obtain borrow material from from approved private sources. Unless otherwise provided in the contract, the Contractor is responsible for obtaining the right to procure material, pay royalties and other charges involved, and bear the expense of developing the sources, including rights-of-way for hauling from the owners. Unless specifically provided, do not obtain borrow within the limits of the project site without prior written approval.

3.2.1 Contractor Furnished Borrow Area(s)

Obtain approved borrow materials from approved offsite sources. If a borrow source is selected that is not a commercial entity from which soil material is directly purchased, submit a Borrow Plan that includes the borrow source location, geotechnical test results showing the fill material meets the Contract requirements, environmental test results in accordance with paragraph ENVIRONMENTAL REQUIREMENTS FOR OFF-SITE SOIL, and any Federal, State, and local permits required for excavation and reclamation of the borrow area.

3.2.2 Environmental Requirements for Off-Site Soil

Environmental requirements are defined within 01 57 19 Temporary Environmental Controls Section 1.5.1.1.1.4 Imported Fill. No material may enter the facility without the written approval from the contracting Officer.

3.3 SURFACE PREPARATION

3.3.1 Clearing and Grubbing

Clear and grub as specified in Section 31 11 00 CLEARING AND GRUBBING.

3.3.2 Stripping

Strip site where indicated on the plans. Strip existing surface materials to a depth of 4 inches below the existing ground surface in areas designated as Clear and Grub on the plans. Strip existing surficial soils to a depth of 4 inches in all other areas. Strip in all areas within the planned limits of disturbance. All stripped materials not suitable for reuse as topsoil will be wasted in specified disposal area. Screen all stripped soils to remove roots and organic materials prior to use as fill material.

Strip suitable soil from the site where excavation or grading is indicated and stockpile separately from other excavated material. Protect topsoil and keep in segregated piles until needed.

3.3.3 Proof Rolling

Perform proof rolling on exposed subgrade that is unfrozen and free of surface water (wet conditions resulting from rainfall). Notify the Contracting Officer a minimum of three days prior to proof rolling.

After stripping and removing topsoil and before fill placement, the exposed subgrade soils in the building and pavement footprints should be densified in place using a
medium weight vibratory roller. The roller should make at least six passes across the site, with the second set of three passes perpendicular to the first set of three passes with intermittent vibration activated at speeds between 2.5 to 3.5 miles per hour. If water is brought to the surface by the vibratory rolling, the operation should be discontinued until the water subsides. Vibratory rolling should be completed during dry weather. Static rolling and additional repairs should be anticipated for areas too wet for vibratory rolling.

After the vibratory rolling, pore pressures should be allowed to dissipate for a minimum of 16 hours. After the waiting period, proofrolling should be performed on the exposed subgrade soils in areas to receive fill or at the subgrade elevation with a loaded, tandem-axle dump truck (15 to 20 ton total vehicle weight) or similar rubber-tired construction equipment. Proofrolling is recommended as a means of detecting areas of soft or unstable subgrade soils. The proofrolling should be performed during a period of dry weather to avoid degrading an otherwise suitable subgrade. The proofrolling operations should be observed by a representative of the geotechnical engineer. Subgrade soils that exhibit excessive rutting or deflection during proofrolling should be repaired as directed by the field representative. Typical repairs include overexcavation followed by replacement with either properly compacted fill or by a subgrade stabilization fabric in conjunction with a sand fill or crushed stone.

3.3.4 Stockpiling Operations

Place and grade stockpiles of materials remaining on site as specified. Keep stockpiles in a neat and well drained condition, giving due consideration to drainage at all times. Clear, grub, and seal by rubber-tired equipment, the ground surface at stockpile locations; separately stockpile excavated satisfactory and unsatisfactory materials. Protect stockpiles of satisfactory materials from contamination which may destroy the quality and fitness of the stockpiled material. Do not create stockpiles that could obstruct the flow of any stream, endanger a partly finished structure, impair the efficiency or appearance of any structure, or be detrimental to the completed work in any way. If the Contractor fails to protect the stockpiles, and any material becomes unsatisfactory, remove and replace such material with satisfactory material from approved sources.

3.4 EXCAVATION

Excavate to contours, elevation, and dimensions indicated. Excavate soil disturbed or weakened by Contractor's operations, and soils softened or made unstable for subsequent construction due to exposure to weather. Use material removed from excavations meeting the specified requirements in the construction of fills, embankments, subgrades, shoulders, bedding (as backfill), and for similar purposes to minimize surplus material and to minimize additional material to brought on site. Do not excavate below indicated depths except to remove unstable material as determined by the Geotechnical Engineer and confirmed by the Contracting Officer. Remove and replace excavations below the grades shown with appropriate materials as directed by the Contracting Officer.

If at any time during excavation, including excavation from borrow areas,

the Contractor encounters material that may be classified as rock or as hard/unyielding material, uncover such material, and notify the Contracting Officer. Do not proceed with the excavation of this material until the Contracting Officer has classified the materials as common excavation or rock excavation. Failure on the part of the Contractor to uncover such material, notify the Contracting Officer, and allow sufficient time for classification and delineation of the undisturbed surface of such material will cause the forfeiture of the Contractor's right of claim to any classification or volume of material to be paid for other than that allowed by the Contracting Officer for the areas of work in which such deposits occur.

3.4.1 Ditches, Gutters, and Channel Changes

Finish excavation of ditches, gutters, and channel changes by cutting accurately to the cross sections, grades, and elevations shown. Do not excavate below grades shown. Backfill excessive excavation as directed by the Contracting Officer, with satisfactory, compacted, material or with suitable stone or cobble to grades shown. Dispose excavated material as shown or as directed. Do not allow material to be deposited within 4 feet from edge of a ditch. Maintain excavations free from detrimental quantities of leaves, brush, sticks, trash, and other debris until final acceptance of the work.

3.4.2 Trench Excavation Requirements

Excavate the trench as recommended by the manufacturer of the pipe to be installed. Slope trench walls below the top of the pipe, or make vertical, and of such width as recommended by the manufacturer. Provide vertical trench walls where no manufacturer installation instructions are available. Do not exceed the trench width of 24 inches below the top pipe plus pipe outside diameter (O.D.) for pipes of less than 24 inches inside diameter, and do not exceed 36 inches plus pipe outside diameter for pipe sizes larger than 24 inches inside diameter. Where recommended trench widths are exceeded, provide redesign, stronger pipe, or special installation procedures. The Contractor is responsible for the cost of redesign, stronger pipe, or special installation procedures without any additional cost to the Government.

3.4.2.1 Bottom Preparation

Grade the bottoms of trenches accurately to provide uniform bearing and support for the bottom quadrant of each section of the pipe. Excavate bell holes to the necessary size at each joint or coupling to eliminate point bearing. Remove stones of 3 inch or greater in any dimension, or as recommended by the pipe manufacturer, whichever is smaller, to avoid point bearing.

3.4.2.2 Removal of Unyielding Material

Where unyielding material is encountered in the bottom of the trench, notify the Contracting Officer. Following approval, remove such material 4 inch below the required grade and replaced with suitable materials as provided in paragraph FILLING AND COMPACTION.

3.4.2.3 Removal of Unstable Material

Where unstable material is encountered in the bottom of the trench, remove such material to the depth directed and replace it to the proper grade

with suitable material as provided in paragraph FILLING AND COMPACTION. When removal of unstable material is required due to the Contractor's fault or neglect in performing the work, the Contractor is responsible for excavating the resulting material and replacing it without additional cost to the Government.

3.4.2.4 Excavation for Appurtenances

Provide excavation for manholes, catch-basins, inlets, or similar structures sufficient to leave at least 12 inches clear between the outer structure surfaces and the face of the excavation or support members.

3.4.2.5 Gas Distribution

Excavate trenches to a depth that will provide a minimum 18 inches of cover in rock excavation and a minimum 24 inches of cover in other excavation.

3.4.2.6 Water Lines

Excavate trenches to a depth that provides a minimum cover of 2.5 feet from the existing ground surface, or from the indicated finished grade, whichever is lower, to the top of the pipe.

3.4.3 Jacking, Boring, and Tunneling

Unless otherwise indicated, provide excavation by open cut except those sections requested and if, in the opinion of the Contracting Officer, can be safely and properly installed and backfill. Provide a Jacking, Boring, and Tunneling Plan, signed and sealed by a licensed Professional Engineer that includes a work site layout, methods and procedures, equipment, alignment control, monitoring, and contingency for responding to unplanned movements.See Section 33 05 07.13 UTILITY DIRECTIONAL DRILLING.

3.4.4 Underground Utilities

Perform work adjacent to utilities as indicated. Report damage to utility lines or subsurface construction immediately to the Contracting Officer.

3.4.5 Structural Excavation

Following general excavation and rough grading activities, scarify the exposed surface to a depth of 10 inches, moisture-condition, and compact to at least 98 percent of laboratory maximum density. For new pavement areas including exterior concrete pads, over-excavate to a minimum of 12 inches below bottom of new pavement/pad base course, scarify, moisture-condition, and compact to at least 95 percent.

Make excavations to the lines, grades, and elevations shown, or as directed. Provide trenches and foundation pits of sufficient size to permit the placement and removal of forms for the full length and width of structure footings and foundations as shown. Clean rock or other hard foundation material of loose debris and cut to a firm, level, stepped, or serrated surface. Remove loose disintegrated rock and thin strata.

Concrete placement is not allowed until footing subgrades have been inspected and approved by the Contracting Officer.

3.4.6 Rock Excavation and Blasting

Excavate rock encountered in the cut section to a depth of 6 inches below finished grade and replace with satisfactory material. Blasting will not be permitted.

3.5 SUBGRADE PREPARATION

3.5.1 General Requirements

Shape subgrade to line, grade, and cross section as indicated. Remove unsatisfactory and unstable material in surfaces to receive fill or in excavated areas, as determined by proof rolling, and replaced with satisfactory materials. Do not place material on surfaces that are muddy, frozen, contain frost, or otherwise containing unstable material. Scarify the surface to a depth of 4 inches prior to placing fill. Step or bench sloped surfaces steeper than 1 vertical to 4 horizontal prior to scarifying. Place 4 inches of loose fill and blend with scarified material. When subgrade is part fill and part excavation or natural ground, scarify to a depth of 8 inches.

3.5.2 Subgrade for Structures, Spread Footings, and Concrete Slabs

Do not excavate below depth shown for structures, spread footings, and concrete slabs. If over excavation occurs, notify the Contracting Officer and remove, replace, and compact as directed. After final rolling, the surface of the subgrade for buildings and pavements must not show deviations greater than 0.05 foot when tested with a 12-foot straightedge applied both parallel and at right angles to the centerline of the area.

3.5.3 Subgrade for Pavements

Compact top 12 inches of subgrade for pavements to at least 95 percent of ASTM D698. After final rolling, the surface of the subgrade for buildings and pavements must not show deviations greater than 0.05 foot when tested with a 12-foot straightedge applied both parallel and at right angles to the centerline of the area.

3.5.4 Subgrade for Shoulders

Compact the upper 12 inches of subgrade for shoulders to at least 95 percent of ASTM D698.

3.5.5 Subgrade Filter Fabric

Place filter fabric as indicated directly on prepared subgrade free of vegetation, stumps, rocks larger than 2 inch diameter and other debris which may puncture or otherwise damage the fabric. Repair damaged fabric by placing an additional layer of fabric to cover the damaged area a minimum of 3 feet overlap in all directions. Overlap fabric at joints a minimum of 3 feet. Obtain approval of filter fabric installation before placing fill or backfill. Place fill or backfill on fabric in the direction of overlaps and compact as specified herein. Follow manufacturer's recommended installation procedures.

3.6 FILLING AND COMPACTION

Prepare ground surface on which backfill is to be placed and provide compaction requirements for backfill materials in conformance with the

applicable portions of paragraphs for SUBGRADE PREPARATION. Do not place material on surfaces that are muddy, frozen, or contain frost. Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, or other approved equipment well suited to the soil being compacted. Moisten material as necessary to provide the moisture content that will readily facilitate obtaining the specified compaction with the equipment used. Fill and backfill to contours, elevations, and dimensions indicated. Compact and test each lift before placing overlaying lift.

3.6.1 Trench Backfill

Backfill the trench to 2 feet above the top of pipe prior to performing the required pressure tests. Leave the joints and couplings uncovered during the pressure test.

3.6.1.1 Replacement of Unyielding Material

Replace unyielding material removed from the bottom of the trench with satisfactory material or initial backfill material.

3.6.1.2 Replacement of Unstable Material

Replace unstable material removed from the bottom of the trench or excavation with satisfactory material placed in layers not exceeding 6 inches loose thickness.

3.6.1.3 Bedding and Initial Backfill

Provide bedding of the type and thickness shown. Place initial backfill material and compact it with approved tampers to a height of at least one foot above the utility pipe or conduit. Bring up the backfill evenly on both sides of the pipe for the full length of the pipe. Take care to ensure thorough compaction of the fill under the haunches of the pipe. Except where shown or when specified otherwise in the individual piping section, provide bedding for buried piping in accordance with PART 2 paragraph UTILITY BEDDING MATERIAL. Compact backfill to top of pipe to 95 percent of ASTM D698 maximum density. Provide plastic piping with bedding to spring line of pipe.

3.6.1.4 Final Backfill

Do not begin backfill until construction below finish grade has been approved, underground utilities systems have been inspected, tested and approved, forms removed, and the excavation cleaned of trash and debris. Bring backfill to indicated finish grade. Where pipe is coated or wrapped for protection against corrosion, the backfill material up to an elevation 2 feet above sewer lines and one foot above other utility lines need to be free from stones larger than one inch in any dimension. Heavy equipment for spreading and compacting backfill are not to be operated closer to foundation or retaining walls than a distance equal to the height of backfill above the top of footing; compact remaining area in layers not more than 4 inches in compacted thickness with power-driven hand tampers suitable for the material being compacted. Place backfill carefully around pipes or tanks to avoid damage to coatings, wrappings, or tanks. Do not place backfill against foundation walls prior to 7 days after completion of the walls. As far as practicable, bring backfill up evenly on each side of the wall and sloped to drain away from the wall.

Fill the remainder of the trench, except for special materials for

buildings and pavements with satisfactory material. Place backfill material and compact as follows:

3.6.1.4.1 Buildings and Pavements

Place backfill up to the required elevation as specified. Do not permit water flooding or jetting methods of compaction. Compact as specified for Structural Fill.

3.6.1.4.2 Turfed or Seeded Areas and Miscellaneous Areas

Deposit backfill in layers of a maximum of 12 inches loose thickness, and compact it to 85 percent maximum density for cohesive soils and 90 percent maximum density for cohesionless soils. Do not permit compaction by water flooding or jetting. Apply this requirement to all other areas not specifically designated above.

3.6.1.5 Electrical Distribution System

Provide a minimum cover of 24 inches from the finished grade to direct burial cable and conduit or duct line, unless otherwise indicated.

3.6.1.6 Displacement of Features

After other required tests have been performed and the trench backfill compacted to the finished grade surface, inspect the pipe to determine whether unexpected or damaging displacement has occurred. Conduct walk-through inspection of pipe sizes larger than 48 inches. Inspect pipes smaller than 48 inches using remote methods using closed circuit television, sonar, or hybrid that can provide a 360-degree inspection of the pipe. Prepare and submit a pipe inspection report consisting of digital video or photos. If, in the judgment of the Contracting Officer, the interior of the pipe shows poor alignment or any other defects that would cause improper functioning of the system, replace or repair the defects as directed at no additional cost to the Government.

3.6.1.7 Buried Tape And Detection Wire

3.6.1.7.1 Buried Warning and Identification Tape

Provide buried utility lines with utility identification tape. Bury tape 12 inches below finished grade; under pavements and slabs, bury tape 6 inches below top of subgrade.

3.6.1.7.2 Buried Detection Wire

Bury detection wire directly above non-metallic piping at a distance not to exceed 12 inches above the top of pipe. Extend the wire continuously and unbroken, from manhole to manhole. Terminate the ends of the wire inside the manholes at each end of the pipe, with a minimum of 3 feet of wire, coiled, remaining accessible in each manhole. Furnish insulated wire over its entire length. Install wires at manholes between the top of the corbel and the frame, and extend up through the chimney seal between the frame and the chimney seal. For force mains, terminate the wire in the valve pit at the pump station end of the pipe.

3.6.2 Structural Fill Placement

Structural fill placed beneath the building footprint should extend

horizontally a minimum distance of 5 feet beyond the outside edge of footings, and two feet beyond the back of curb.

Place fill and backfill beneath and adjacent to structures in successive horizontal layers of loose material not more than 8 inches in depth, or in loose layers not more than 4 inches in depth when using hand-operated compaction equipment. Do not place over wet or frozen materials. Compact to at least 98% of maximum dry density as determined by the Standard Proctor (ASTM D698). Perform compaction in such a manner as to prevent wedging action or eccentric loading upon or other damage to the structure. Moisture condition fill and backfill material to within range of plus 2 or minus 2 percent of optimum moisture content at the time of compaction.

3.6.3 Backfill for Appurtenances

After the manhole, catchbasin, inlet, or similar structure has been constructed, place backfill in such a manner that the structure is not be damaged by the shock of falling earth. Deposit the backfill material, compact it as specified for final backfill, and bring up the backfill evenly on all sides of the structure to prevent eccentric loading and excessive stress.

3.6.4 Porous Fill Placement

Provide under floor and area-way slabs on a compacted subgrade. Place in a single lift and compact with a minimum of two passes of a hand-operated plate-type vibratory compactor.

3.6.5 Flowable Fill

Place fill in a manner to completely fill voids in the location indicated. Do not place when atmospheric temperatures are expected to be below 33 degrees F at any time during the 3 day period following placement.

3.6.6 Compaction

3.6.6.1 General Site

Compact underneath areas designated for vegetation and areas outside the 5 foot line of the paved area or structure to 90 percent of ASTM D698.

3.6.6.2 Adjacent Areas

Compact areas within 5 feet of structures to 98 percent of ASTM D698.

3.7 EMBANKMENTS

3.7.1 Earth Embankments

Construct earth embankments from satisfactory materials free of organic or frozen material and rocks with any dimension greater than 3 inches. Place the material in successive horizontal layers of loose material not more than 8 inches in depth. Spread each layer uniformly on a soil surface that has been moistened or aerated as necessary and scarified or otherwise broken up so that the fill will bond with the surface on which it is placed. After spreading, plow, disk, or otherwise break up each layer; moisten or aerate as necessary; thoroughly mix; and compact to at least 90 percent laboratory maximum density for cohesive materials or 95 percent

laboratory maximum density for cohesionless materials. Backfill and fill material are to be to a moisture content that will readily facilitate obtaining the specified compaction.

Compaction requirements for the upper portion of earth embankments forming subgrade for pavements are identical with those requirements specified in paragraph SUBGRADE PREPARATION. Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment.

3.8 RIP-RAP CONSTRUCTION

Construct rip-rap on bedding material or on filter fabric in the areas indicated. Trim and dress indicated areas to conform to cross sections, lines and grades shown within a tolerance of 0.1 foot.

3.8.1 Bedding Placement

Spread filter fabric and bedding material uniformly to a thickness of at least 3 inches on prepared subgrade as indicated. Compaction of bedding is not required. Finish bedding to present even surface free from mounds and windrows.

3.8.2 Stone Placement

Place rock for rip-rap on prepared bedding material to produce a well graded mass with the minimum practicable percentage of voids in conformance with lines and grades indicated. Distribute larger rock fragments, with dimensions extending the full depth of the rip-rap throughout the entire mass and eliminate "pockets" of small rock fragments. Rearrange individual pieces by mechanical equipment or by hand as necessary to obtain the distribution of fragment sizes specified above.

3.9 FINISHING/FINISH OPERATIONS

During construction, keep embankments and excavations shaped and drained. Maintain ditches and drains along subgrade to drain effectively at all times. Do not disturb the finished subgrade by traffic or other operation. Protect and maintain the finished subgrade in a satisfactory condition until ballast, subbase, base, or pavement is placed. Do not permit the storage or stockpiling of materials on finished subgrade. Do not lay subbase, base course, ballast, or pavement until the subgrade has been checked and approved, and in no case place subbase, base, surfacing, pavement, or ballast on a muddy, spongy, frozen or otherwise unstable subgrade.

Finish the surface of excavations, embankments, and subgrades to a smooth and compact surface in accordance with the lines, grades, and cross sections or elevations shown. Provide the degree of finish for graded areas within 0.1 foot of the grades and elevations indicated except as indicated for subgrades specified in paragraph SUBGRADE PREPARATION. Finish gutters and ditches in a manner that will result in effective drainage. Finish the surface of areas to be turfed to a smoothness suitable for the application of turfing materials. Repair graded, topsoiled, or backfilled areas prior to acceptance of the work, and re-established grades to the required elevations and slopes.

3.9.1 Capillary Water Barrier

Place a capillary water barrier under concrete floor and area-way slabs grade directly on the subgrade and compact with a minimum of two passes of a hand-operated plate-type vibratory compactor.

3.9.2 Grading Around Structures

Construct areas within 5 feet outside of each building and structure line true-to-grade, shape to drain, and maintain free of trash and debris until final inspection has been completed and the work has been accepted.

3.9.3 Shoulder Construction

Construct shoulders of satisfactory material . Submit advanced notice on shoulder construction for rigid pavements. Construct shoulders immediately after adjacent paving is complete. In the case of rigid pavements, do not construct shoulders until permission of the Contracting Officer has been obtained. Compact the entire shoulder area to at least the percentage of maximum density as specified in paragraph SUBGRADE PREPARATION above, for specific ranges of depth below the surface of the shoulder. Finish compaction by sheepsfoot rollers, pneumatic-tired rollers, steel-wheeled rollers, vibratory compactors, or other approved equipment. Finish shoulder construction in proper sequence in such a manner that adjacent ditches will be drained effectively and that no damage of any kind is done to the adjacent completed pavement. Align the completed shoulders true to grade and shaped to drain in conformity with the cross section shown.

3.9.4 Grading

Finish grades as indicated within one-tenth of one foot. Grade areas to drain water away from structures. Maintain areas free of trash and debris. For existing grades that will remain but which were disturbed by Contractor's operations, grade as directed.

3.9.5 Topsoil and Sod

Provide as specified in Section 32 92 23 SODDING. On areas to receive topsoil, prepare the compacted subgrade soil to a 2 inches depth for bonding of topsoil with subsoil. Spread topsoil evenly to a thickness of 2 inch and grade to the elevations and slopes shown. Do not spread topsoil when frozen or excessively wet or dry. Keep topsoil separate from other excavated materials, brush, litter, objectionable weeds, roots, stones larger than 2 inches in diameter, and other materials that would interfere with planting and maintenance operations. Remove from the site any surplus of topsoil from excavations and gradings. Obtain material required for topsoil in excess of that produced by excavation within the grading limits from offsite areas.

3.10 DISPOSITION OF SURPLUS MATERIAL

Remove from Government property all surplus or other soil material not required or not suitable for filling or backfilling, along with brush, refuse, stumps, roots, and timber. Properly disposed of in accordance with all applicable laws and regulations.

3.11 TESTING

Perform testing as indicated in Table 1. Submit Material Test Reports within 3 days of tests being completed.

Material Type list materials to be tested as identified in paragraph DEFINITIONS	Location of Material	Test Method	Test Frequency
		Density - ASTM D1556/D1556M. When ASTM D6938 or ASTM D8167/D8167M is used, check the calibration curves and adjust using only the sand cone method as described in ASTM D1556/D1556M.	One test per 2000 square feet, or fraction thereof, of each lift of fill or backfill areas compacted by other than hand-operated machines. Double testing frequency for areas compacted by hand-operated machines. If ASTM D6938 or ASTM D8167/D8167M is used, check in-place densities by ASTM D1556/D1556M as follows: One check test per lift for every 6 tests. Where ASTM D8167/D8167M is used, provide water content verification in accordance with ASTM D2216 for each test.

Material Type list materials to be tested as identified in paragraph DEFINITIONS	Location of Material	Test Method	Test Frequency
		Moisture Content - ASTM D2216	Two tests per day for each type of fill and backfill. Sample taken immediately prior to compaction after moisture conditioning.
		Moisture Density Relationship - ASTM D698	One representative test per 500 cubic yards of fill and backfill, or when any change in material occurs which may affect the optimum moisture content or laboratory maximum density. Sample to be taken from stockpile or location of placement.
		Relative Density - ASTM D4253 and ASTM D4254	One test per 2000 square feet, or fraction thereof, of each lift of fill or backfill areas compacted by other than hand-operated machines. Double testing frequency for areas compacted by hand-operated machines.

Material Type list materials to be tested as identified in paragraph DEFINITIONS	Location of Material	Test Method	Test Frequency
		Gradation - ASTM C136/C136M	One representative test per 500 cubic yards of fill and backfill, or when any change in material occurs which may affect the optimum moisture content or laboratory maximum density. Sample to be taken from stockpile or location of placement.
		Atterberg Limits - ASTM D4318	One representative test per 500 cubic yards of fill and backfill, or when any change in material occurs which may affect the optimum moisture content or laboratory maximum density. Sample to be taken from stockpile or location of placement.
		Organic Content Test - ASTM D2974, Method C	One representative test per 200 lineal feet of embankment.

-- End of Section --

SECTION 31 11 00

CLEARING AND GRUBBING
11/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

DODI 4150.07 (2019) DOD Pest Management Program

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government.

SD-01 Preconstruction Submittals

Herbicide Application Plan

SD-03 Product Data

Tree Wound Paint

Herbicides; G

SD-07 Certificates

Qualifications; G

SD-11 Closeout Submittals

Pest Management Report

1.3 QUALITY CONTROL

1.3.1 Regulatory Requirements

Comply with DODI 4150.07 for requirements on Contractor's licensing, certification, and record keeping. Maintain daily records using the Pest Management Maintenance Record, DD Form 1532-1, or a computer generated equivalent. These forms may be obtained from the main web site: https://www.acq.osd.mil/eie/afpmb/docs/standardlists/dd1532-1.xlsm.

1.3.2 Qualifications

For the application of herbicides, use the services of an applicator who is commercially certified in the state where the work is to be performed as required by DODI 4150.07. Submit a copy of the pesticide applicator

certificates.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver materials to the site, and handle in a manner which will maintain the materials in their original manufactured or fabricated condition until ready for use.

1.4.1 Storage

Storage of herbicides on the installation will not be permitted unless it is written into the contract.

1.4.2 Handling

Handle herbicides in accordance with the manufacturer's label and Safety Data Sheet (SDS), preventing contamination by dirt, water, and organic material. Protect herbicides from weather elements as recommended by the manufacturer's label and SDS. Spill kits must be maintained on herbicide control vehicles. Mixing of herbicides on the installation will not be permited unless it is written into the contract.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Tree Wound Paint

Use bituminous based paint from standard manufacture specially formulated for tree wounds.

2.1.2 Herbicide

Provide herbicides currently registered by the EPA or approved for such use by the appropriate agency of the host county and approved by the Contracting Officer. Select a herbicide that is suitable for the climatic conditions at the project site. Submit manufacturer's label and SDS for herbicides proposed for use.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Herbicide Application Plan

Prior to commencing application of herbicide, submit a herbicide application plan with proposed sequence of treatment work including dates and times of application. Include the herbicide trade name, EPA registration number, chemical composition, formulation, application rate of active ingredients, method of application, area or volume treated, and amount applied. Include a copy of the pesticide applicator certificates.

3.1.2 Protection

3.1.2.1 Roads and Walks

Keep roads and walks free of dirt and debris at all times.

3.1.2.2 Trees, Shrubs, and Existing Facilities

Provide protection in accordance with Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS.

3.1.2.3 Utility Lines

Protect existing utility lines that are indicated to remain from damage. Notify the Contracting Officer immediately of damage to or an encounter with an unknown existing utility line. The Contractor is responsible for the repair of damage to existing utility lines that are indicated or made known to the Contractor prior to start of clearing and grubbing operations. When utility lines which are to be removed are encountered within the area of operations, notify the Contracting Officer in ample time to minimize interruption of the service. Refer to Section 01 57 19 TEMPORARY ENVIRONMENTAL CONTROLS for additional utility protection.

3.2 APPLICATION

3.2.1 Herbicide Application

Adhere to safety precautions as recommended by the manufacturer concerning handling and application of the herbicide.

3.2.1.1 Clean Up, Disposal, And Protection

Once application has been completed, proceed with clean up and protection of the site without delay. Clean the site of all material associated with the treatment measures, according to label instructions, and as indicated. Remove and dispose of excess and waste material off Government property.

3.2.1.1.1 Disposal of Herbicide

Dispose of residual herbicides and containers off Government property, and in accordance with the approved disposal plan, label instructions and EPA requirements.

3.3 CLEARING

Clearing consists of the felling, trimming, and cutting of trees into sections and the satisfactory disposal of the trees and other vegetation designated for removal, including downed timber, snags, brush, and rubbish occurring within the areas to be cleared. Clearing also includes the removal and disposal of structures that obtrude, encroach upon, or otherwise obstruct the work. Cut off flush with or below the original ground surface trees, stumps, roots, brush, and other vegetation in areas to be cleared, except such trees and vegetation as may be indicated or directed to be left standing. Trim dead branches 1-1/2 inches or more in diameter on trees designated to be left standing within the cleared areas and trim all branches to the heights indicated or directed. Neatly cut close to the bole of the tree or main branches, limbs and branches to be trimmed. Paint, with an approved tree-wound paint, cuts more than 1-1/2 inches in diameter. Apply herbicide in accordance with the manufacturer's label to the top surface of stumps designated not to be removed.

3.3.1 Tree Removal

Where indicated or directed, remove trees and stumps that are designated

as trees from areas outside those areas designated for clearing and grubbing. This work includes the felling of such trees and the removal of their stumps and roots as specified in paragraph GRUBBING. Dispose of trees as specified in paragraph DISPOSAL OF MATERIALS.

3.3.2 Pruning

Trim trees designated to be left standing within the cleared areas of dead branches 1-1/2 inches or more in diameter; and trim branches to heights and in a manner as indicated. Neatly cut limbs and branches to be trimmed close to the bole of the tree or main branches. Paint cuts more than 1-1/4 inches in diameter with an approved tree wound paint.

3.3.3 Grubbing

Grubbing consists of the removal and disposal of stumps, roots larger than 3 inches in diameter, and matted roots from the designated grubbing areas. Remove stumps entirely. Remove material to be grubbed, together with logs and other organic debris not suitable for foundation purposes, to a depth of not less than 18 inches below the original surface level of the ground in areas indicated to be grubbed and in areas indicated as construction areas under this contract, such as areas for buildings, and areas to be paved. Fill depressions made by grubbing with backfill and fill material and compact to specified density to make the surface conform with the original adjacent surface of the ground.

3.4 DISPOSAL OF MATERIALS

Dispose of excess materials in accordance with the approved solid waste management permit and include those materials in the solid waste management report.

All wood or wood like materials, except for salable timber, remaining from clearing, prunning or grubbing such as limbs, tree tops, roots, stumps, logs, rotten wood, and other similiar materials is the property of the Contractor and dispose of as specified. All non-saleable timber and wood or wood like materials remaining from timber harvesting such as limbs, tree tops, roots, stumps, logs, rotten wood, and other similiar materials is the property of the Contractor and dispose of as specified.

3.5 CLOSEOUT ACTIVITIES

3.5.1 Herbicides

Upon completion of this work, submit the Pest Management Report DD Form 1532, or an equivalent computer product, to the Integrated Pest Management Coordinator. This form identifies the type of operation, brand name and manufacturer of herbicide, formulation, concentration or rate of application used.

-- End of Section --

SECTION 31 31 16.13

CHEMICAL TERMITE CONTROL
08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

DODI 4150.07 (2019) DOD Pest Management Program

1.2 ADMINISTRATIVE REQUIREMENTS

Coordinate work related to final grades, landscape plantings, foundations, or any other alterations to the finished construction which might alter the condition of treated soils.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Termiticide Application Plan; G

SD-03 Product Data

Termiticides

SD-05 Design Data

Mixing Formulation

SD-06 Test Reports

Soil Moisture

Calibration Test

SD-07 Certificates

Qualifications; G

Foundation Exterior

Utilities and Vents

Crawl and Plenum Air Spaces

List of Equipment

SD-08 Manufacturer's Instructions

Termiticides

SD-11 Closeout Submittals

Verification of Measurement

Warranty

Pest Management Report

1.4 QUALITY CONTROL

1.4.1 Regulatory Requirements

Comply with DODI 4150.07 for requirements on Contractor's licensing, certification, and record keeping. Maintain daily records using the Pest Management Maintenance Record, DD Form 1532-1, or a computer generated equivalent, and submit copies of records when requested by the Contracting Officer. These forms may be obtained from the main web site: https://www.esd.whs.mil/Directives/forms/fmo_poc/

1.4.2 Qualifications

For the application of pesticides, use the services of an applicator whose principal business is pest control. The applicator must be commercially certified in the state where the work is to be performed as required by DODI 4150.07. No contractor personnel may work under the supervision of a certified person even where this is permitted practice in those States or host nations in which the DOD property is located. Termiticide applicators must also be certified in the U.S. Environmental Protection Agency (EPA) pesticide applicator category which includes structural pest control. Submit a copy of the pest control business license and pesticide applicator certificates to the Contracting Officer prior to any applications.

1.4.3 Safety Requirements

Formulate, apply, and dispose of termiticides and their containers in accordance with label directions. Draw water for formulating only from sites designated by the Contracting Officer, and fit the filling hose with a backflow preventer meeting local plumbing codes or standards. Maintain an air gap between the filling hose and tank. Perform filling operations under the direct and continuous observation of a contractor's representative to prevent overflow. Secure pesticides and related materials under lock and key when unattended. Ensure that proper protective clothing and equipment are worn and used during all phases of termiticide application. Dispose of used pesticide containers off Government property.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

Deliver termiticide material to the site in the original unopened containers bearing legible labels indicating the EPA registration number,

manufacturer's registered uses and in new or otherwise good condition as supplied by the manufacturer or formulator.

1.5.2 Inspection

Inspect termiticides upon arrival at the job site for conformity to type and quality in accordance with paragraph TERMITICIDES. Each label must bear evidence of registration under the Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA), as amended or under appropriate regulations of the host county. Inspect other materials for conformance with specified requirements. Remove unacceptable materials from the job site.

1.5.3 Storage

Storage of pesticides on the installation will not be permitted unless it is written into the contract.

1.5.4 Handling

Handle and mix termiticides in accordance with the manufacturer's label and SDS, preventing contamination by dirt, water, and organic material. Protect termiticides from weather elements as recommended by the manufacturer's label and SDS. Spill kits must be maintained on pest control vehicles and must be available at the mixing site. Conduct termiticide mixing in an area that has been approved by the Integrated Pest Management Coordinator (IPMC) or Contracting Officer, and with adequate spill containment that can contain at least 110 percent of the volume of the tank.

1.6 SITE CONDITIONS

The following site conditions determine the acceptable time of application.

1.6.1 Soil Moisture

Test soils to be treated immediately before application. Test soil moisture content to a minimum depth of 3 inches. The soil moisture must be as recommended by the termiticide manufacturer. Application of the termiticide is not permitted when soil moisture content exceeds manufacturer's recommendations.

1.6.2 Runoff and Wind Drift

Application of termiticide will not be permitted during or immediately following heavy rains, when conditions may allow runoff, when it may create an environmental hazard or when average wind speed exceeds 10 miles per hour. Termiticide is not permitted to enter water systems, aquifers, or endanger humans or animals.

1.7 WARRANTY

Provide a 5 year written warranty against infestations or reinfestations by subterranean termites of the buildings or building additions constructed under this contract. Include in the warranty annual inspections of the buildings or building additions during the warranty period. If live subterranean termite infestation or subterranean termite damage is discovered during the warranty period, and the soil and building conditions have not been altered in the interim:

a. Re-treat the site and perform other treatment as may be necessary for elimination of subterranean termite infestation;

b. Repair damage caused by termite infestation; and

c. Reinspect the building approximately 180 days after the re-treatment.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Chemical termite control uses liquid termiticide treatments applied to the soil to form a continuous chemical barrier in the soil around both sides of the foundation. The application can be surface applied or rodded and trenched. This barrier prevents foraging termites from reaching the foundation and piers. Only the soil adjacent to these foundation elements is treated. For slab construction (including foundations, patios and garages), the entire soil (or gravel) surface is treated before the vapor barrier is installed and the slab poured over it. Soil treatment is coordinated with all building activities from foundation construction through final grading of the soil around the building's exterior. In order for the treatment to be effective, the final phase of the application must be done after final grading and sometimes after landscaping is completed so that the treated soil is not disturbed.

2.2 MATERIALS

2.2.1 Termiticides

Provide termiticides currently registered by the EPA or approved for such use by the appropriate agency of the host county and as approved by the Contracting Officer. Select non-repellent termiticides (active ingredient: chlorantraniliprole, chlorfenapyr, fipronil, or imidacloprid) for maximum effectiveness and duration after application. Select a termiticide that is suitable for the soil and climatic conditions at the project site and apply at the highest labeled rate. Submit manufacturer's label and Safety Data Sheet (SDS) for termiticides proposed for use.

PART 3 EXECUTION

3.1 PREPARATION

Before termiticide application begins, remove all cellulose containing materials from the site such as wood debris from clearing and grubbing and post construction wood scraps, such as ground stakes, form boards, cardboard paper, and scrap lumber from the site.

3.1.1 Verification

Before work starts, verify that final grades are as indicated and smooth grading has been completed in accordance with Section 31 00 00 EARTHWORK. Finely grade soil and remove particles larger than 1 inch. Compact soil particles to eliminate soil movement.

3.1.2 Foundation Exterior

If the exterior perimeter treatment is applied before major construction is completed it will be damaged or removed. The exterior foundation perimeter treatment will have to occur in phases during completion of any

pads, porches, aprons, sidewalks, final grading, or landscape plantings adjacent to the building foundation. These treatment areas should be coordinated after all major construction but before any pads, porches, or other items requiring special consideration are poured adjacent to the foundation walls. Submit written verification that final grading, landscape planting, and other items adjacent to the foundation will not disturb treatment of the soil on the exterior sides of foundation walls, grade beams, and similar structures.

3.1.3 Utilities and Vents

Turn off and block HVAC ducts and vents located in the treatment area prior to application to protect people and animals from termiticide. Submit written verification that the HVAC ducts and vents, water and sewer lines, and plumbing have been turned off or blocked prior to applying termiticide.

3.1.4 Crawl and Plenum Air Spaces

Submit written verification that crawl and plenum air spaces have been located and identified prior to applying termiticide.

3.1.5 Application Plan

Prior to commencing application of termiticide, submit a Termiticide Application Plan addressing the following items:

a. proposed sequence of treatment work including dates and times of application

b. termiticide trade name

c. EPA registration number

d. chemical composition

e. concentration of original and diluted material

f. formulation

g. manufacturer's recommended application rates

h. regional requirements

i. application rate of active ingredients

j. method of application

k. area or volume to be treated

l. amount to be applied

m. copy of the pest control business license

n. copy of the pesticide applicator certificates

3.2 APPLICATION

For areas to be treated, establish complete and unbroken vertical and

horizontal soil chemical barriers between the soil and all portions of the intended structure which may allow termite access to wood and wood related products. Make applications to crawl spaces in accordance with label directions. Applications to crawl space areas that are used as plenum air spaces will not be permitted.

3.2.1 Equipment Calibration and Tank Measurement

Submit a list of equipment to be used. Conduct calibration test on the application equipment to be used immediately prior to commencement of termiticide application. Measure the volume and contents of the application tank. Testing must confirm that the application equipment is operating within the manufacturer's specifications and meets the specified requirements. Submit written certification of the equipment calibration test results within one week of testing. Where results from the equipment calibration and tank measurements tests are unsatisfactory, re-treatment will be required.

3.2.2 Mixing and Application

Perform all work related to formulating, mixing, and application in the presence of the Contracting Officer's representative, a DOD certified pesticide applicator, Pest Management Quality Assurance Evaluator (QAE)/Performance Assessment Representative (PAR), or IPMC. Applications must be made at the highest rate or concentration allowed by the label. Submit mixing formulation:

a. Quantity of pesticide used.

b. Rate of dispersion.

c. Percent of use.

d. Total amount used.

A closed system is recommended as it prevents the termiticide from coming into contact with the applicator or other persons. Only use water from designated locations. Fit filling hoses with a backflow preventer meeting local plumbing codes or standards. Maintain an air gap between filling hoses and tanks. Prevent overflow during the filling operation. Spill kits must be maintained on pest control vehicles and must be available at the mixing site. Termiticide mixing must be conducted in an area that has been designated by the IPMC or Contracting Officer and that has adequate spill containment. Inspect the application equipment prior to each day of use for leaks, clogging, wear, or damage. Immediately perform repairs on the application equipment to prevent or eliminate leaks and clogging.

3.2.2.1 Application Method

3.2.2.1.1 Surface Application

Use surface applications for establishing horizontal barriers. Apply termiticide as a coarse spray and provide uniform distribution over the soil surface. Termiticide must penetrate a minimum of 1 inch into the soil, or as recommended by the manufacturer. If soils are treated to a depth less than specified or approved, repeat work performed to the depth specified at no additional cost to the Government.

3.2.2.1.2 Rodding and Trenching

Use rodding and trenching for establishing vertical soil barriers. Trenching must be to the depth of the foundation footing. Width of trench must be as recommended by the manufacturer, or as indicated. Rodding or other approved method may be implemented for saturating the base of the trench with termiticide. Backfill the trench immediately after termiticide has reached maximum penetration as recommended by the manufacturer. If maximum penetration is not achieved, as recommended by the manufacturer, repeat work performed to maximum penetration as recommended by the manufacturer at no additional cost to the Government. Backfill in 6 inch rises or layers. Treat each rise or layer with termiticide.

3.2.3 Sampling

The Contracting Officer may draw samples for analysis, at any time and without prior notice, from stocks at the job site to determine if the amount of active ingredient specified on the label is being applied. When analysis, performed by the Government, indicates samples contain less than the amount of active ingredient specified on the label, repeat work performed with pesticides conforming to this specification at no additional cost to the Government.

3.2.4 Vapor Barriers and Waterproof Membranes

Apply termiticide prior to placement of a vapor barrier or waterproof membrane.

3.2.5 Placement of Concrete

Place concrete covering treated soils after the termiticide has reached maximum penetration into the soil as recommended by the manufacturer. Cover treated areas with plastic if slab is not to be poured immediately following termiticide application.

3.2.6 Clean Up, Disposal, and Protection

Once application has been completed, proceed with clean up and protection of the site without delay.

3.2.6.1 Clean Up

Clean the site of all material associated with the treatment according to label instructions, and as indicated. Remove and dispose of excess and waste material off Government property.

3.2.6.2 Disposal of Termiticide

Dispose of residual termiticides and containers off Government property, and in accordance with label instructions and EPA criteria.

3.3 FIELD QUALITY CONTROL

3.3.1 Verification of Measurement

Once termiticide application has been completed, measure tank contents to determine the remaining volume. The total volume measurement of used contents for the application must equal the application rate established

in the application plan. Submit written verification that the volume of termiticide used meets the application rate established in the application plan.

3.3.2 Inspection

3.3.2.1 Technical Representative

Provide a technical representative who is a DOD certified pesticide applicator, Pest Management QAE/PAR, or IPMC. The technical representative must be present at all meetings concerning treatment measures for subterranean termites and during treatment application. Contact the Integrated Pest Management Coordinator prior to starting work.

3.4 CLOSEOUT ACTIVITIES

Upon completion of this work, submit the Pest Management Report DD Form 1532, or an equivalent computer product, to the Integrated Pest Management Coordinator. This form identifies the target pest, type of operation, brand name and manufacturer of pesticide, formulation, concentration or rate of application used.

3.5 PROTECTION

3.5.1 Protection of Treated Area

Immediately after the application, protect the area from other use by erecting barricades as required or directed. Place signage inside the entrances to crawl spaces and identify the space as treated with termiticide and not safe for children or animals.

3.5.2 Disturbance of Treated Soils

Re-treat soil and fill material disturbed after treatment before placement of slabs or other covering structures.

-- End of Section --

SECTION 32 01 16.71

COLD MILLING ASPHALT PAVING
11/22

PART 1 GENERAL

1.1 DEFINITIONS

1.1.1 Scabbing/Delamination

Scabbing or delamination is defined as the debonding or raveling of material which may be caused by either the condition of the existing underlying layers of asphalt mixture or the milling operation.

1.1.2 Milling Machine

Milling machines may also be known as pavement cold planers. Throughout this specification, any references to milling machines will also apply to pavement cold planers.

1.1.3 Milling Drum

Milling drums are upward-rotating drums or rotors which are outfitted with toolholders and teeth (picks). Milling drums perform different tasks dependent on the structure and design. The main tasks are cutting particles from the composite pavement, conveying removed material to the ejector, and ejecting removed material. Any reference to milling drum also applies to milling rotors.

1.2 TRAFFIC CONTROL

Provide all necessary traffic control during milling operations.

1.3 SCHEDULING

After completion of the preconstruction submittals, provide notice to the Contracting Officer a minimum of seven days prior to starting milling operations.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government.

SD-01 Preconstruction Submittals

Equipment; G

Proposed Techniques; G

Quality Control Plan; G

1.5 PROJECT/SITE CONDITIONS

1.5.1 Environmental Requirements

Do not perform milling when there is accumulation of snow or ice on the pavement surface.

PART 2 PRODUCTS

2.1 EQUIPMENT

Maintain in a satisfactory working condition equipment, tools, and machines used in the performance of this work.

2.1.1 Cold Milling Machine

Use a self-propelled unit capable of removing the existing asphalt pavement to the depths and widths shown in the Contract. Milling machines will have a minimum cutting width of 4. Use milling machines designed and built exclusively for pavement milling operations and with sufficient power, traction and stability to accurately maintain depth of cut and slope. The equipment will be capable of operating the machine speed independently from the cutting equipment speed. Use milling machines capable of being equipped with dual longitudinal controls (operated from both sides of the machine). Use electronic control systems that will automatically control the longitudinal profile and cross slope of the milled surface. Accomplish this through the use of a mobile grade reference, an erected string line, joint matching shoe, slope control systems, or a combination of approved methods. When using a mobile grade reference, use systems capable of averaging the existing grade or pavement profile over at least 30 foot. Use a machine capable of leaving a uniform surface suitable for handling traffic without damage to the underlying pavement structure. Provide additional equipment necessary to satisfactorily remove the pavement in the area of manholes, water valves, curb, gutter and other obstructions. Provide milling machines with a means of effectively limiting the amount of dust escaping from the removal operations. If milling operations result in excessive fugitive dust, a silica dust suppressant is required at no additional cost to the Government. Milling equipment is not allowed to damage any part of the pavement structure that is not to be removed. Equip the milling machine with a lighting system for night work as required by the Contract. Smaller width milling machines may be necessary for use around structures or other penetrations. Produce the same surface texture with small milling machines as with the large milling machines.

2.1.2 Milling Drums

2.1.2.1 Standard Milling Drum

Provide a standard milling drum having a tool spacing between 1/2 - 3/4 inch.

2.1.3 Sensors and Scanning Components

Provide sensors and scanners as necessary to produce the grade and smoothness as specified. Submit all sensors and scanning components for Government approval.

2.1.4 Cleaning Equipment

Provide cleaning equipment suitable for removing and cleaning loose material from the pavement surface. If using street sweeper type equipment, equip the street sweeper with a water tank, dust control spray assembly, both a pick-up and gutter broom, and a debris hopper.

2.1.5 Straightedge

Furnish and maintain at the site, in good condition, at least one 12 foot straightedge for each milling machine, for testing the finished surface. Make the straightedge available for Government use. Use straightedges constructed of aluminum or other lightweight metal, with blades of box or box-girder cross section with flat bottom reinforced to insure rigidity and accuracy. Use straightedges with handles to facilitate movement on the milled surface.

PART 3 EXECUTION

3.1 CONTRACTOR QUALITY CONTROL

3.1.1 General Quality Control Requirements

Submit the Quality Control Plan a minimum of 30 days in advance of starting milling operations. The Quality Control Plan is specific to this specification and supplements the overall Quality Control Plan required by the project. Do not start milling operations until the Quality Control Plan has been approved. In the Quality Control Plan, address all elements which affect the quality of the milling operation including, but not limited to:

a. Type of cutting teeth and schedule for replacement.

b. The daily preventative maintenance schedule and checklist.

c. The proposed use of grade and slope controls (longitudinal and transverse).

d. The frequency of smoothness testing.

e. The process for milling distressed areas (scabbing/delamination).

f. Corrective procedures if the milling operation does not meet the specified texture or grade requirements.

g. Corrective procedures if the milled surface does not meet the specified minimum transverse or longitudinal smoothness when measured with a 12 foot straightedge.

h. The frequency of macrotexture testing.

3.2 PROPOSED TECHNIQUES

Submit the proposed techniques a minimum of 30 days in advance of starting milling operations. The proposed techniques will be project specific and address the following items:

a. The number, type(s) and size(s) of milling machines to be used.

b. The width and location of each cutting pass.

c. The number and types of brooms to be used with their location with respect to milling machines.

d. The proposed method for milling around existing structures such as manholes, valve boxes, and inlets.

e. The longitudinal and transverse typical sections for tie-ins at the end of the work day.

3.3 MILLING OPERATION

Make sufficient passes so that the designated area is milled to the profile, cross-slope, grade and elevations as indicated. Mill the pavement in depth increments that will not damage the pavement below the designated finished grade. If scabbing or delamination occurs, the milled surface is unlikely to meet smoothness requirements. Notify the Contracting Officer for further direction when delamination or scabbing occurs. Repair or replace items damaged during milling operations such as manholes, valve boxes, utility lines, pavement that is torn, cracked, gouged, broken, or undercut, at no additional cost to the Government. Remove the milled material from the pavement and load into trucks.

3.3.1 Milling Machine and Drum Speed

Operate the milling machine and drum speed at appropriate speeds required to produce a uniform and acceptable surface texture per paragraph ACCEPTABLE SURFACE TEXTURE.

3.4 ACCEPTABLE SURFACE TEXTURE

Produce a milled surface texture with continuous, longitudinal milling striations with no gaps in the longitudinal striations. Gaps in the milling striations and cases where gaps create a diagonal pattern or chevron appearance are required to be milled again such that continuous, longitudinal striations are achieved.

3.5 TRAFFIC ON MILLED SURFACE

Mill the entire pavement width to a flush surface at the end of each work day when the pavement is open to traffic. If uncompleted operations result in a vertical or near vertical longitudinal face, re-slope the longitudinal face to provide a taper, construct a temporary bituminous taper or provide protective measures, as approved by the Contracting Officer. Taper transverse cutting faces at the end of each work day where pavement is open to traffic. Taper transverse edges to a minimum 10:1 taper. Provide taper over a distance of 15feet. Construct temporary bituminous tapers (paper joint) at intersecting streets, around utility appurtenances, and drainage structures during the milling operation. Maintain adequate drainage on the milled surface.

3.5.1 Taper Material

Use the same quality of asphalt mixture used elsewhere on the project or

as detailed in the Contract.

3.6 CLEAN-UP OPERATIONS

After milling to the depth shown in the Contract, sweep or vacuum clean the milled area with the approved equipment.

3.7 REMOVAL OF MILLED MATERIAL

Material that is removed will become the property of the Contractor and removed from the site.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 32 01 19.61

SEALING OF JOINTS IN RIGID PAVEMENT
11/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C603	(2014; R 2019) Standard Test Method for Extrusion Rate and Application Life of Elastomeric Sealants
ASTM C639	(2015; R 2020)Standard Test Method for Rheological (Flow) Properties of Elastomeric Sealants
ASTM C661	(2015; R 2022) Standard Test Method for Indentation Hardness of Elastomeric-Type Sealants by Means of a Durometer
ASTM C679	(2015; R 2022) Standard Test Method for Tack-Free Time of Elastomeric Sealants
ASTM C719	(2014; R 2019) Standard Test Method for Adhesion and Cohesion of Elastomeric Joint Sealants Under Cyclic Movement (Hockman Cycle)
ASTM C792	(2015; R 2020) Effects of Heat Aging on Weight Loss, Cracking, and Chalking of Elastomeric Sealants
ASTM C793	(2005; R 2017) Standard Test Method for Effects of Laboratory Accelerated Weathering on Elastomeric Joint Sealants
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants
ASTM C1016	(2014; R 2022) Standard Test Method for Determination of Water Absorption of Sealant Backing (Joint Filler) Material
ASTM C1193	(2013) Standard Guide for Use of Joint Sealants
ASTM D412	(2016; R 2021) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D789	(2015) Determination of Relative Viscosity

and Moisture Content of Polyamide (PA)

ASTM D903 — (1998; R 2017) Standard Test Method for Peel or Stripping Strength of Adhesive Bonds

ASTM D5249 — (2010; R 2016) Standard Specification for Backer Material for Use with Cold-and Hot-Applied Joint Sealants in Portland-Cement Concrete and Asphalt Joints

ASTM D5329 — (2016) Standard Test Methods for Sealants and Fillers, Hot-Applied, for Joints and Cracks in Asphalt Pavements and Portland Cement Concrete Pavements

ASTM D5893/D5893M — (2016) Standard Specification for Cold Applied, Single Component, Chemically Curing Silicone Joint Sealant for Portland Cement Concrete Pavements

ASTM D6690 — (2015) Standard Specification for Joint and Crack Sealants, Hot Applied, for Concrete and Asphalt Pavements

U.S. ARMY CORPS OF ENGINEERS (USACE)

COE CRD-C 525 — (1989) Corps of Engineers Test Method for Evaluation of Hot-Applied Joint Sealants for Bubbling Due to Heating

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-03 Product Data

Sealants

Submit catalog cuts, specifications, Safety Data Sheets and other information documenting conformance to Contract requirements.

Manufacturer's Recommendations

SD-04 Samples

Sealants

Provide for testing a 5-gal sample of each sealant with associated primer to the Contracting Officer a minimum of 60 days prior to its use on the job. Provide factory-sealed containers with a factory applied label showing the following information:

Name of sealant

Identification of component, or primer

Specification number and type

Manufacturer's name

Manufacturer's lot and batch number

Date of Manufacture (month and year)

Shelf life retest date (month and year)

List of hazardous components

Quantity of material in container (volume)

Storage instructions

Instructions for use

Blocking Media/Backup Materials

Backer Rod

Bond Breaking Tapes

SD-06 Test Reports

SD-07 Certificates

Equipment List

SD-08 Manufacturer's Instructions

Sealants

Provide instructions that include, but not limited to: storage requirements, ambient temperature and humidity ranges, and moisture condition of joints for successful installation; requirements for preparation of joints; safe heating temperature; mixing instructions; installation equipment and procedures; application and disposal requirements; compatibility of sealant with filler material; curing requirements; and restrictions to be adhered to in order to reduce hazards to personnel or to the environment. Submit instructions at least 30 days prior to use.

1.3 QUALITY ASSURANCE

1.3.1 Test Requirements

Test the sealant and backup or separating material for conformance with the referenced material specification. Perform testing of the materials in an approved independent laboratory and submit certified copies of the test reports for approval 30 days prior to the use of the materials at the job site. Submit samples to be retained by the Government for possible future testing if the materials appear defective during or after application. Conformance with the requirements of the laboratory tests specified does not constitute final acceptance of the materials. Base final acceptance on the performance of the in-place materials. Submit samples of the materials (sealant, primer if required, and backup material), in sufficient quantity for testing and approval 30 days prior to the

beginning of work. Do not use material until it has been approved.

1.4 DELIVERY, STORAGE, AND HANDLING

Inspect materials delivered to the site for visible damage, and unload and store with a minimum of handling. Deliver joint materials in original sealed containers and protect from freezing or overheating. Provide jobsite storage facilities capable of maintaining temperature ranges within manufacturers recommendations.

1.5 ENVIRONMENTAL REQUIREMENTS

Do not proceed with work when weather conditions detrimentally affect the quality of cleaning joints or applying sealants. Proceed with joint preparation and sealing only when weather conditions are in accordance with manufacturer's instructions. Install joint sealant to dry surfaces and protect sealant and bond breakers from moisture.

1.6 TRAFFIC CONTROL

Do not permit vehicular or heavy equipment traffic on the pavement in the area of the joints being sealed during the protection and curing period of the sealant. Permit traffic on the pavement at the end of the curing period.

PART 2 PRODUCTS

2.1 SEALANTS

Use materials for sealing cracks in accordance with ASTM D6690 and ASTM D5893/D5893M based on the type of area as follows:

Area	Sealing Material
	ASTM D6690, Type II and ASTM D5329/ COE CRD-C 525

Use self leveling, non-acid curing silicone sealant meeting the following requirements in accordance with ASTM C920 or ASTM C1193:

TEST	TEST METHOD	REQUIREMENTS
Weight Loss	ASTM C792 Modified (see Note 1 below)	10 percent max.
Flow	ASTM C639 (Type I)	Smooth and level
Extrusion Rate	ASTM C603	30 sec. max.
Tack Free Time	ASTM C679	5 hours max.

TEST	TEST METHOD	REQUIREMENTS
Hardness (Shore 00) (see Note 2 below)	ASTM C661	30 - 80
Tensile Stress at 150 Percent Elongation (see Note 2 below)	ASTM D412 (Die C)	30 psi max.
Percent Elongation (see Note 2 below)	ASTM D412 (Die C)	700 min.
Accelerated Weathering	ASTM C793	Pass 5000 hours
Bond and Movement Capability	ASTM C719	Pass 10 cycles at plus 50 percent movement (no adhesion or cohesion failure)
Peel	ASTM D903	Minimum 20 psi of width with at least 75 percent cohesive failure

NOTES:
1. Percent weight loss of wet (uncured) sample after placing in forced-draft oven maintained at 158 degrees plus 1 degree F for two hours.

2. Specimen cured 21 days at 73 degrees plus 1 degree F and 50 percent plus 5 percent humidity.

ACCELERATED WEATHERING FACTORY TEST REPORT. For the Accelerated Weathering test, in lieu of testing of actual sealant to be used on the project, it is permitted to submit a report of a factory test, performed within two years of Contract award.

2.2 PRIMERS

Use primers in accordance with the recommendation of the manufacturer.

2.3 BOND BREAKERS

2.3.1 Blocking Media/Backup Materials

Provide backup (joint filler) material that is a compressible, nonshrinking, nonstaining, nonabsorbing, nonreactive material with the sealant. Use backup material compliant with ASTM D5249. Use material with a melting point at least 5 degrees F greater than the pouring temperature of the sealant being used when tested in accordance with ASTM D789. Use material with a water absorption of not more than 5 percent of the sample weight when tested in accordance with ASTM C1016. Use backup (joint filler) material that is 25 plus or minus 5 percent larger in diameter than the nominal width of the crack. Use blocking media consistent with the sealant manufacturer's installation instructions.

2.3.2 Bond Breaking Tapes

Provide a bond breaking tape or separating material that is a flexible, nonshrinkable, nonabsorbing, nonstaining, and nonreacting adhesive-backed tape. Use material with a melting point at least 5 degrees F greater than the pouring temperature of the sealant being used when tested in

accordance with ASTM D789. Use bond breaker tape approximately 1/8 in wider than the nominal width of the joint and that does not bond to the sealant. Use bond breaking tape consistent with the sealant manufacturer's installation instructions.

PART 3 EXECUTION

3.1 EXECUTING EQUIPMENT

Submit equipment list and description of the equipment to be used and a statement from the supplier of the sealant that the proposed equipment is acceptable for installing the specified sealant. Use equipment for heating, mixing, and installing seals in accordance with the instructions provided by the sealant manufacturer. Provide equipment, tools, and accessories necessary to clean existing joints and install liquid joint sealants. Maintain machines, tools, and other equipment in proper working condition. Submit a list of proposed equipment to be used in performance of construction work including descriptive data, 30 days prior to use on the project.

3.1.1 Joint Cleaning Equipment

3.1.1.1 Tractor-Mounted Routing and Plowing Tool

Use routing tools for removing old sealant from the joints, of such shape and dimensions and so mounted on the tractor that do not damage the sides of the joints. Use tools designed to be adjusted to remove the old material to varying depths and widths as required. Use equipment capable of maintaining accurate cutting depth and width control. Use a joint plow equipped with a spring or hydraulic mechanism to release pressure on the tool prior to spalling the concrete. Do not permit the use of V-shaped tools or rotary impact routing devices. Permit the use of hand-operated spindle routing devices to clean and enlarge random cracks.

3.1.1.2 Concrete Saw

Provide a self-propelled power saw, with water-cooled diamond or abrasive saw blades, for cutting joints to the depths and widths specified, for refacing joints, cleaning sawed joints where sandblasting does not provide a clean joint, widening, or deepening existing joints as specified without damaging the sides, bottom, or top edge of joints. Permit single or gang type blades with one or more blades mounted in tandem for fast cutting. Select saw adequately powered and sized to cut specified opening with not more than two passes of the saw through the joint.

3.1.1.3 Sandblasting Equipment

Include with the sandblasting equipment an air compressor, hose, and long-wearing venturi-type nozzle of proper size, shape and opening. Do not permit the maximum nozzle opening to exceed 1/4 in. Use a portable air compressor capable of providing not less than 150 cfm and maintaining a line pressure of not less than 90 psi at the nozzle while in use. Demonstrate compressor capability, under job conditions, before approval. Use a compressor equipped with traps that maintain the compressed air free of oil and water. Use a nozzle with an adjustable guide that holds the nozzle aligned with the joint approximately 1 in above the pavement surface. Adjust the height, angle of inclination and the size of the nozzle to secure satisfactory results.

3.1.1.4 Waterblasting Equipment

Include with the waterblasting equipment a trailer-mounted water tank, pumps, high-pressure hose, wand with safety release cutoff control, nozzle, and auxiliary water resupply equipment. Provide water tank and auxiliary resupply equipment of sufficient capacity to permit continuous operations. Use a nozzle with an adjustable guide that holds the nozzle aligned with the joint approximately 1 in above the pavement surface. Adjust the height, angle of inclination and the size of the nozzle to obtain satisfactory results. Use a pressure gauge mounted at the pump that shows the pressure in psi at which the equipment is operating.

3.1.1.5 Air Compressor

Use a portable air compressor capable of operating the sandblasting equipment and capable of blowing out sand, water, dust adhering to sidewalls of concrete, and other objectionable materials from the joints. Use a compressor that provides air at a pressure not less than 90 psi and a minimum rate of 150 cubic ft of air per minute at the nozzles and free of oil.

3.1.1.6 Vacuum Sweeper

Use a self-propelled, vacuum pickup sweeper capable of completely removing loose sand, water, joint material, and debris from pavement surface.

3.1.1.7 Hand Tools

Permit the use of hand tools, such as brooms and chisels, when approved, for removing defective sealant from a crack and repairing or cleaning the crack faces.

3.1.2 Sealing Equipment

Use joint sealing equipment of a type required by the sealant manufacturer's installation instructions. Use equipment capable of installing sealant to the depths, widths and tolerances indicated. Do not proceed with joint sealing when malfunctions are noted until the malfunctions are corrected.

3.1.2.1 Hot-Poured Sealing Equipment

Use mobile unit applicators equipped with a double-boiler, agitator-type kettle with an oil medium in the outer space for heat transfer for heating and installing ASTM D6690 joint sealant materials; a direct-connected pressure-type extruding device with a nozzle shaped for inserting in the joint to be filled; positive temperature devices for controlling the temperature of the transfer oil and sealant; and a recording thermometer for indicating the temperature of the sealant. Use an applicator unit designed so that the sealant circulates through the delivery hose and returns to the inner kettle when not in use.

3.1.2.2 Cold-Applied, Single-Component Sealing Equipment

Use equipment for installing ASTM D5893/D5893M single component joint sealants that consists of an extrusion pump, air compressor, following plate, hoses, and nozzle for transferring the sealant from the storage container into the joint opening. Use a nozzle with dimensions that allows the tip of the nozzle to extend into the joint to allow sealing

from the bottom of the joint to the top. Maintain the initially approved equipment in good working condition, serviced in accordance with the supplier's instructions, and unaltered in any way without obtaining prior approval. Use lined hoses and seals to prevent moisture penetration and withstand pumping pressures. Use equipment free of contamination from previously used or other type sealant. Permit use of small hand-held air-powered equipment (i.e., caulking guns) for small applications.

3.2 SAFETY

Do not place sealant within 25 ft of LOX equipment, LOX storage, or LOX piping. Clean joints in this area and leave them unsealed.

In accordance with the provisions of the Contract respecting "Accident Prevention," take appropriate measures to control worker exposure to toxic substances during the work. Provide personnel protective equipment as required. Make Material Safety Data Sheets (Department of Labor Form OSHA-20 or comparable form) available on the site.

3.3 PREPARATION OF JOINTS

Unless otherwise indicated, remove existing material, saw, clean and reseal joints. Do not proceed with final cleaning operations by more than one working day in advance of sealant. Clean joints by removing existing joint sealing compound, bond-breakers, dirt, laitance, curing compound, filler, and protrusions of hardened concrete from the sides and upper edges of the joint space to be sealed and other foreign material with the equipment. Do not permit cleaning procedures that damage joints or previously repaired patches by chipping or spalling. Remove existing sealant to the required depth. Precise shape and size of existing joints vary, and conditions of joint walls and edges vary and include but are not limited to rounding, square edges, sloping, chips, voids, depressions, and projections.

3.3.1 Sawing

3.3.1.1 Facing of Joints

Accomplish facing of joints using a concrete saw as specified in paragraph EQUIPMENT to saw through sawed and filler-type joints to loosen and remove material until the joint is clean and open to the full specified width and depth. Provide exposure of newly clean concrete through removal. Remove burrs and irregularities from sides of joint faces. Stiffen the blade with a sufficient number of dummy (used) blades or washers. Clean, immediately following the sawing operation, the joint opening using a water jet to remove saw cuttings and debris and adjacent concrete surface. Protect adjacent previously cleaned joint spaces from receiving water and debris during the cleaning operation.

a. Joint Widening (Except Expansion Joints): Saw joints having grooves less than 3/8 in wide and less than 1 in deep to a minimum width of 1/4 in and to the minimum depth, as indicated.

3.3.1.2 Refacing of Random Cracks

Accomplish sawing of the cracks using a power-driven concrete saw as specified in paragraph EQUIPMENT. Use a saw blade 6 in or less in diameter to enable the saw to follow the trace of the crack. Stiffen the blade with dummy (or used) blades or washers. Immediately following the

sawing operation, clean the crack opening using a water jet to remove saw cuttings and debris.

3.3.2 Final Cleaning of Joints

3.3.2.1 Sandblasting

Following removal of existing sealant, and sawing, and immediately before resealing, clean newly exposed concrete joint faces and pavement surface extending to a mimimum of 1/2 in up to 2 in from each joint edge by sandblasting until concrete surfaces in the joint space are free of sealants, dust, dirt, water and other foreign materials that prevent bonding of new sealants to the concrete. Use sand particles of the proper size and quality for the work. Perform sandblasting with specified nozzles, air compressor, and other appurtenant equipment. Position nozzles to clean the joint faces. Make at least two passes; one for each joint face. Make as many passes as required for proper cleaning. Immediately prior to sealing the joint, blow out the joint spaces with compressed air until completely free of sand, water, and dust. Install joint sealants to dry joints. Replace expansion joint filler material damaged in performing the work with new materials of the same type and dimensions as the existing material, or with appropriate blocking media.

3.3.3 Bond Breaker

At the time the joints receive the final cleaning and are dry, install bond breaker material as indicated with a steel wheel or other approved device.

3.3.3.1 Blocking Media (Backer Rod) (Except for Expansion Joints)

When the joint opening is of a greater depth than indicated for the sealant depth, plug or seal off the lower portion of the joint opening using a blocking media/back-up material to prevent the entrance of the sealant below the specified depth. Take care to ensure that the blocking media/backup material is placed at the specified depth and is not stretched or twisted during installation.

3.3.3.2 Bond Breaking Tape

Where inserts or filler materials contain bitumen, or the depth of the joint opening does not allow for the use of a backup material, insert a bond breaker separating tape to prevent incompatibility with the filler materials and three-sided adhesion of the sealant. Bond the tape to the bottom of the joint opening to prevent it from floating up into the new sealant.

3.3.4 Rate of Progress of Joint Preparation

Limit the stages of joint preparation, including sandblasting, air pressure cleaning and placing of the back-up material to only that lineal footage that can be sealed during the same day.

3.3.5 Disposal of Debris

Sweep pavement surface to remove excess joint material, dirt, water, sand, and other debris by vacuum sweepers or hand brooms. Remove the debris immediately in accordance with Section 02 41 00 DEMOLITION.

3.4 PREPARATION OF SEALANT

3.4.1 Hot-Poured Sealants

Heat hot-poured sealing materials in accordance with ASTM D6690 and with safe heating temperature ranges recommended by the manufacturer. Withdraw and waste sealant that has been overheated or subjected to heating for over 3 hours or that remain in the applicator at the end of the day's operation. Heat sealant in specified equipment.

3.4.2 Single-Component, Cold-Applied Sealants

Inspect the ASTM D5893/D5893M sealant and containers prior to use. Reject materials that contain water, hard caking of any separated constituents, nonreversible jell, or materials that are otherwise unsatisfactory. Do not reject sealants that exhibit settlement of constituents in a soft mass that can be readily and uniformly remixed in the field with simple tools.

3.5 INSTALLATION OF SEALANT

3.5.1 Time of Application

After approval of the test section, seal joints immediately following final cleaning and placing of bond breakers. Commence sealing joints when walls are dust free and dry, and when weather conditions meet sealant manufacturer's instructions. If the above conditions cannot be met, or when rain interrupts sealing operations, reclean and permit the joints to dry prior to installing the sealant.

3.5.2 Sealing Joints

Do not install joint sealant until joints to be sealed have been inspected and approved. Install bond breaker just prior to pouring sealant. Fill the joints with sealant from bottom up until joints are uniformly filled solid from bottom to top using the specified equipment for the type of sealant required. Fill joints to 1/4 in plus or minus 1/16 in below top of pavement, and without formation of voids or entrapped air. Do not permit gravity methods or pouring pots to be used to install the sealant material. Except as otherwise permitted, tool the sealant immediately after application to provide firm contact with the joint walls and to form the indicated sealant profile below the pavement surface. Remove excess sealant that has been inadvertently spilled on the pavement surface. Do not permit traffic over newly sealed pavement until authorized. When a primer is recommended by the manufacturer, apply it evenly to the joint faces in accordance with the manufacturer's recommendations. Check sealed joints frequently to ensure that newly installed sealant is cured to a tack-free condition within the specified time. Protect new sealant from rain during curing period.

3.6 INSPECTION/FIELD QUALITY CONTROL

3.6.1 Joint Cleaning

Inspect joints during the cleaning process to correct improper equipment and cleaning techniques that damage the concrete pavement in any manner. Approve cleaned joints prior to installation of the separating or back-up material and joint sealant.

3.6.2 Sampling Sealant

Obtain a one gal sample of each type of sealant on the project from material used for each 10,000 linear ft or less of joints sealed. Store samples according to sealant manufacturer's instructions. Retain samples until final acceptance of the work.

3.6.3 Sealant Application Equipment

Inspect the application equipment to ensure conformance to temperature requirements, proper proportioning and mixing (if two-component sealant) and proper installation. Suspend operations if there is evidences of bubbling, improper installation, or failure to cure or set until causes of the deficiencies are determined and corrected.

3.6.4 Joint Sealant

Inspect the joint sealant for proper rate of cure and set, bonding to the joint walls, cohesive separation within the sealant, reversion to liquid, entrapped air and voids. Remove sealants exhibiting these deficiencies prior to the final acceptance of the project from the joint, wasted, and replace at no additional cost to the Government. Obtain approval for each joint seal installation.

3.7 ACCEPTANCE

Reject sealer that fails to cure properly, or fails to bond to joint walls, or reverts to the uncured state, or fails in cohesion, or shows excessive air voids, blisters, surface defects, swelling, or other deficiencies, or is not properly recessed within indicated tolerances. Remove rejected sealer and reclean and reseal joints. Perform removal and reseal work promptly by and at the expense of the Contractor.

3.8 CLEAN-UP

Upon completion of the project, remove unused materials from the site and leave the pavement in a clean condition.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 32 11 23

AGGREGATE BASE COURSE
05/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C88	(2018) Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C117	(2017) Standard Test Method for Materials Finer than 75-um (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C127	(2015) Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Coarse Aggregate
ASTM C128	(2022) Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Fine Aggregate
ASTM C131/C131M	(2020) Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C136/C136M	(2019) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates
ASTM D75/D75M	(2019) Standard Practice for Sampling Aggregates
ASTM D1556/D1556M	(2015; E 2016) Standard Test Method for Density and Unit Weight of Soil in Place by Sand-Cone Method
ASTM D1557	(2012; E 2015) Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft3) (2700 kN-m/m3)
ASTM D2487	(2017; E 2020) Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System)
ASTM D3665	(2012; R 2017) Standard Practice for Random Sampling of Construction Materials

ASTM D4318	(2017; E 2018) Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils
ASTM D4718/D4718M	(2015) Standard Practice for Correction of Unit Weight and Water Content for Soils Containing Oversize Particles
ASTM D4791	(2019) Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate
ASTM D5821	(2013; R 2017) Standard Test Method for Determining the Percentage of Fractured Particles in Coarse Aggregate
ASTM D6938	(2017a) Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth)
ASTM D7928	(2017) Standard Test Method for Particle-Size Distribution (Gradation) of Fine-Grained Soils Using the Sedimentation (Hydrometer) Analysis
ASTM E11	(2022) Standard Specification for Woven Wire Test Sieve Cloth and Test Sieves

NORTH CAROLINA DEPARTMENT OF TRANSPORATION (NCDOT)

NCDOT	(2018) North Carolina Department of Transporation Standard Specifications

1.2 DEFINITIONS

For the purposes of this specification, the following definitions apply.

1.2.1 Aggregate Base Course

Aggregate base course (ABC) is well graded, durable aggregate uniformly moistened and mechanically stabilized by compaction and to be crushed stone meeting North Carolina Department of Transporation (NCDOT) Standard Specifications.

1.2.2 Degree of Compaction

Degree of compaction required, except as noted in the second sentence, is expressed as a percentage of the maximum laboratory dry density obtained by the test procedure presented in ASTM D1557 abbreviated as a percent of laboratory maximum dry density. Since ASTM D1557 applies only to soils that have 30 percent or less by weight of their particles retained on the 3/4 inch sieve, express the degree of compaction for material having more than 30 percent by weight of their particles retained on the 3/4 inch sieve as a percentage of the laboratory maximum dry density in accordance with ASTM D1557 Method C and corrected with ASTM D4718/D4718M.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Plant, Equipment, and Tools; G

SD-06 Test Reports

Initial Tests; G

In-Place Tests; G

1.4 QUALITY ASSURANCE

Perform sampling and testing using a laboratory approved in accordance with Section 01 45 00 QUALITY CONTROL. Do not start work requiring testing until the testing laboratory has been inspected and approved. Test the materials to establish compliance with the specified requirements and perform testing at the specified frequency. Furnish copies of test results within 24 hours of completion of the tests.

1.4.1 Sampling

Take samples for laboratory testing in conformance with ASTM D75/D75M.

1.4.2 Tests

1.4.2.1 Gradation Analysis

Perform gradation analysis in conformance with ASTM C117 and ASTM C136/C136M using sieves conforming to ASTM E11..

1.4.2.2 Liquid Limit and Plasticity Index

Determine liquid limit and plasticity index in accordance with ASTM D4318.

1.4.2.3 Moisture-Density Determinations

Determine the laboratory maximum dry density and optimum moisture content in accordance with paragraph DEGREE OF COMPACTION.

1.4.2.4 Field Density Tests

Measure field density in accordance with ASTM D1556/D1556M, or ASTM D6938. For the method presented in ASTM D1556/D1556M use the base plate as shown in the drawing. For the method presented in ASTM D6938 check the calibration curves and adjust them, if necessary, using only the sand cone method as described in Annex A2 of ASTM D6938. Use ASTM D6938 to determine the moisture content of the soil. Check the calibration curves furnished with the moisture gauges along with density calibration checks as described in ASTM D6938. Make the calibration checks of both the density and moisture gauges using the prepared containers of material method, as described in Annex A2 of ASTM D6938, on each different type of material being tested at the beginning of a job and at intervals as directed.

Submit calibration curves and related test results prior to using the device or equipment being calibrated.

1.4.2.5 Wear Test

Perform wear tests on ABC course material in conformance with ASTM C131/C131M.

1.4.2.6 Flat and Elongated Pieces

Determine flat and elongated pieces on ABC course material in conformance with ASTM D4791, Method A.

1.4.2.7 Soundness

Perform soundness tests on GCA in accordance with ASTM C88.

1.4.2.8 Fractured Faces

Perform fractured faces test on ABC coarse aggregate in comformance with ASTM D5821.

1.5 ENVIRONMENTAL REQUIREMENTS

Perform construction when the atmospheric temperature is above 35 degrees F. When the temperature falls below 35 degrees F, protect all completed areas by approved methods against detrimental effects of freezing. Correct completed areas damaged by freezing, rainfall, or other weather conditions to meet specified requirements.

1.6 ACCEPTANCE

1.6.1 Tolerances

Acceptance of ABC is based on compliance with the tolerances presented in Table 1. Remove any materials found to be non-compliant and replace with compliant material or rework, as directed, to meet the requirements of this specification

TABLE 1

Measurement	Tolerance
Grade	Plus 1/4 inch, Minus 1/2 inch
Smoothness	Plus/Minus 3/8 inch
Individual Test Total Thickness	Plus/Minus
Average Job Thickness	Plus/Minus
Compaction	Minimum 100 percent

1.6.2 Test Section

A test section is not required.

PART 2 PRODUCTS

2.1 AGGREGATES

Provide ABC consisting of clean, sound, durable particles of crushed stone, crushed gravel, angular sand, or other approved material. Provide ABC that is free of lumps of clay, organic matter, and other objectionable materials or coatings. The portion retained on the No. 4 sieve is known as coarse aggregate; that portion passing the No. 4 sieve is known as fine aggregate. When the coarse and fine aggregate is supplied from more than one source, provide aggregate from each source that meets the specified requirements.

2.1.1 Coarse Aggregate

Provide coarse aggregates with angular particles of uniform density. Separately stockpile coarse aggregate supplied from more than one source.

a. Crushed Gravel: Provide crushed gravel that has been manufactured by crushing gravels and that meets all the requirements specified below.

b. Crushed Stone: Provide crushed stone consisting of freshly mined quarry rock, meeting all the requirements specified below.

2.1.1.1 Aggregate Base Course

Limit the percentage of loss of ABC coarse aggregate to a maximum of 50 percent when tested in accordance with ASTM C131/C131M. Provide aggregate that contains a maximum of 30 percent flat and elongated particles when tested in accordance with ASTM D4791, Method A. A flat particle is one having a ratio of width to thickness greater than 3; an elongated particle is one having a ratio of length to width greater than 3. In the portion retained on each sieve specified, provide crushed aggregates containing a minimum of 50 percent by weight of crushed pieces having two or more freshly fractured faces determined in accordance with ASTM D5821. When two fractures are contiguous, the angle between planes of the fractures is required to be a minimum of 30 degrees in order to count as two fractured faces. Manufacture crushed gravel from gravel particles 50 percent of which, by weight, are retained on the maximum size sieve listed in TABLE 2.

2.1.2 Fine Aggregate

Provide fine aggregates consisting of angular particles of uniform density.

2.1.2.1 Aggregate Base Course

Provide ABC fine aggregate that consists of screenings, angular sand, crushed recycled concrete fines, or other finely divided mineral matter processed or naturally combined with the coarse aggregate.

2.1.3 Gradation Requirements

Apply the specified gradation requirements to the completed base course. Provide aggregates that are continuously well graded within the limits specified in TABLE 2. Use sieves that conform to ASTM E11.

TABLE 2. GRADATION OF AGGREGATES			
Percentage By Weight Passsing Square-Mesh Sieve			
Sieve Designation	No. 1	No. 2	No.3
2 inch	100	---	---
1-1/2 inch	70-100	100	---
1 inch	45-80	60-100	100
1/2 inch	30-60	30-65	40-70
No. 4	20-50	20-50	20-50
No. 10	15-40	15-40	15-40
No. 40	5-25	5-25	5-25
No. 200	0-8	0-8	0-8

NOTE 1: Limit particles having diameters less than 0.02 mm to a maximum of 3 percent by weight of the total sample tested as determined in accordance with ASTM D7928.

NOTE 2: The values are based on aggregates of uniform specific gravity. If materials from different sources are used for the coarse and fine aggregates, test the materials in accordance with ASTM C127 and ASTM C128 to determine their specific gravities. Correct the percentages passing the various sieves as directed if the specific gravities vary by more than 10 percent.

NOTE 3: Gradations containing more than 30 percent retained on the ¾ inch sieve can produce inconsistent compacted density values when tested in accordance with paragraph DEGREE OF COMPACTION.

2.2 LIQUID LIMIT AND PLASTICITY INDEX

Apply liquid limit and plasticity index requirements to the completed course and to any component that is blended to meet the required gradation. Limit the portion of any component or of the completed course passing the No. 40 sieve to be either nonplastic or have a maximum liquid limit of 25 and a maximum plasticity index of 5.

2.3 TESTS, INSPECTIONS, AND VERIFICATIONS

2.3.1 Initial Tests

Perform one of each of the following initial tests on the proposed material prior to commencing construction to demonstrate that the proposed material meets all specified requirements when furnished. Complete this testing for each source if materials from more than one source are proposed. Submit certified copies of test results for approval a mimimum

of 30 days before material is required for the work.

a. Gradation Analysis.

b. Liquid limit and plasticity index.

c. Moisture-density relationship.

d. Wear.

e. Flat and Elongated Pieces.

f. Fractured Faces.

2.3.2 Approval of Material

Tentative approval of material will be based on initial test results.

2.4 EQUIPMENT, TOOLS, AND MACHINES

All plant, equipment, and tools used in the performance of the work are subject to approval by the Government before the work is started. Maintain all plant, equipment, and tools in satisfactory working condition at all times. Submit a list of proposed equipment, including descriptive data. Use equipment capable of minimizing segregation, producing the required compaction, meeting grade controls, thickness control, and smoothness requirements as set forth herein.

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

When the ABC is constructed in more than one lift, clean the previously constructed lift of loose and foreign matter by sweeping with power sweepers or power brooms. Use hand brooms in areas where power cleaning is not practicable. Provide adequate drainage during the entire period of construction to prevent water from collecting or standing on the working area.

3.2 OPERATION OF AGGREGATE SOURCES

Condition aggregate sources on private lands in accordance with local laws or authorities.

3.3 STOCKPILING MATERIAL

Clear and level storage sites prior to stockpiling of material. Stockpile all materials, including approved material available from excavation and grading, in the manner and at the locations designated. Stockpile aggregates on the cleared and leveled areas designated to prevent segregation. Stockpile materials obtained from different sources separately.

3.4 PREPARATION OF UNDERLYING COURSE OR SUBGRADE

Clean the underlying course or subgrade of all foreign substances prior to constructing the base course(s). Do not construct base course(s) on underlying course or subgrade that is frozen. Construct the surface of the underlying course or subgrade to meet specified compaction and surface

tolerances. Correct ruts or soft yielding spots in the underlying courses, areas having inadequate compaction, and deviations of the surface from the specified requirements set forth herein by loosening and removing soft or unsatisfactory material and adding approved material, reshaping to line and grade, and recompacting to specified density requirements. For cohesionless underlying courses or subgrades containing sands or gravels, as defined in ASTM D2487, stabilize the surface prior to placement of the base course(s). Stabilize by mixing ABC into the underlying course and compacting by approved methods. Proof roll in accordance with paragraph PROOF ROLLING. Consider the stabilized material as part of the underlying course and meet all requirements of the underlying course. Do not allow traffic or other operations to disturb the finished underlying course and maintain in a compliant condition until the base course is placed.

3.5 GRADE CONTROL

Provide a finished and completed base course conforming to the lines, grades, and cross sections shown. Place line and grade stakes as necessary for control.

3.6 MIXING AND PLACING MATERIALS

3.6.1 Mixing

Mix the coarse and fine aggregates in a stationary plant. Make adjustments in mixing procedures or in equipment to obtain true grades, to minimize segregation or degradation, to obtain the required water content, and to produce a satisfactory base course meeting all requirements of this specification.

3.6.2 Placing

Place the mixed material on the prepared subgrade or subbase in lifts of uniform thickness with an approved spreader. Place the lifts so that when compacted they are true to the grades or levels required with the least possible surface disturbance. Where the base course is placed in more than one lift, clean the previously constructed lift of loose and foreign matter by sweeping with power sweepers, power brooms, or hand brooms. Make adjustments in placing procedures or equipment to obtain true grades, to minimize segregation and degradation, to adjust the water content, and to produce an acceptable base course.

3.7 LAYER THICKNESS

Compact the completed base course to the thickness indicated. Limit individual compacted lifts to a maximum thickness of 6 inches and a minimum thickness of 3 inches. Compact the base course(s) to a total thickness that is within the tolerances of paragraph ACCEPTANCE of the thickness indicated. Where the measured thickness is more than 1/2 inch deficient, correct such areas by scarifying, adding new material of proper gradation, reblading, and recompacting as directed. Where the measured thickness is more than 1/2 inch thicker than indicated, the course will be considered as conforming to the specified thickness requirements. However, the requirements for wearing course thickness and plan grade are still applicable. The average job thickness will be the average of all thickness measurements taken for the job and within the tolerances of paragraph ACCEPTANCE of the thickness indicated.

3.8 COMPACTION

Compact each lift of the base course, as specified, with approved compaction equipment. For cohesive soils, maintain water content during the compaction procedure to within plus or minus 2 percent of the optimum water content determined from laboratory tests as specified and for cohesionless soils, maintain the water content to facilitate compaction without bulking. Begin rolling at the outside edge of the surface and proceed to the center, overlapping on successive trips at least one-half the width of the roller. Slightly vary the length of alternate trips of the roller. Adjust speed of the roller as needed so that displacement of the aggregate does not occur. Compact mixture with hand-operated power tampers in all places not accessible to the rollers. Continue compaction until each lift is compacted through the full depth to meet the compaction requirements of Table 1. Make such adjustments in compacting or finishing procedures to obtain true grades, to minimize segregation and degradation, to reduce or increase water content, and to produce a compliant base course. Remove any materials found to be non-compliant and replace with compliant material or rework, as directed, to meet the requirements of this specification.

3.9 EDGES OF BASE COURSE

Place the base course(s) so that the completed section is a minimum of 2 feet wider, on all sides, than the next lift that will be placed above it. Place approved material along the outer edges of the base course in sufficient quantity to compact to the thickness of the course being constructed. When the course is being constructed in two or more lifts, simultaneously roll and compact at least a 2 foot width of this shoulder material with the rolling and compacting of each lift of the base course.

3.10 FINISHING

Finish the surface of the top lift of base course after final compaction by cutting any overbuild to grade and rolling with a steel-wheeled roller. Do not add thin lifts of material to the top lift of base course to meet grade. If the elevation of the top lift of base course exceeds the tolerances of paragraph ACCEPTANCE, scarify the top lift to a depth of at least 3 inches and blend new material in and compact to bring to grade. Make adjustments to rolling and finishing procedures to minimize segregation and degradation, obtain grades, maintain moisture content, and produce an acceptable base course. If the surface become rough, corrugated, uneven in texture, or traffic marked prior to completion, scarify the non-compliant portion and rework and recompact it or replace as directed.

3.11 SMOOTHNESS TEST

Construct the top lift so that the surface shows no deviations exceeding the tolerances of paragraph ACCEPTANCE when tested with a 12 foot straightedge. Test the entire area in both a longitudinal and a transverse direction on parallel lines. Perform the transverse lines at a maximum spacing of 15 feet or less apart, as directed. Perform the longitudinal lines at the centerline of each placement lane, regardless of whether multiple lanes are allowed to be paved at the same time, and at the 1/8th point in from each side of the lane. Hold the straightedge in contact with the surface and moved ahead one-half the length of the straightedge for each successive measurement. Determine the amount of surface irregularity by placing the freestanding (unleveled) straightedge

on the pavement surface and measuring the maximum gap between the straightedge and the pavement surface. Determine measurements along the entire length of the straight edge. Correct deviations exceeding this amount by removing material and replacing with new material, or by reworking existing material and compacting it to meet these specifications.

3.12 FIELD QUALITY CONTROL

3.12.1 In-Place Tests

Perform each of the following in-place tests on samples taken from the placed and compacted ABC. Determine sample locations using random sampling in accordance with ASTM D3665. Take samples and test at the rates indicated.

a. Perform density tests on every lift of material placed and at a frequency of one set of tests for every 250 square yards, or portion thereof, of completed area. Gradations containing more than 30 percent retained on the ¾ inch sieve can produce inconsistent compacted density values when tested in accordance with paragraph DEGREE OF COMPACTION.

b. Perform gradation analysis on every lift of material placed and at a frequency of one sieve analysis for every 500 square yards, or portion thereof, of material placed.

c. Perform liquid limit and plasticity index tests at the same frequency as the sieve analysis.

d. Measure the thickness of the base course at intervals providing at least one measurement for each 500 square yards of base course or part thereof. Measure the thickness using test holes, at least 3 inch in diameter through the base course.

3.12.2 Approval of Material

Final approval of the materials will be based on tests for gradation, liquid limit, and plasticity index performed on samples taken from the completed and fully compacted course(s).

3.13 TRAFFIC

Completed portions of the base course can be opened to limited traffic, provided there is no marring or distorting of the surface by the traffic. Do not allow heavy equipment on the completed base course except when necessary for construction. When it is necessary for heavy equipment to travel on the completed base course, protect the area against marring or damage to the completed work. Repair damage to meet these specifications.

3.14 MAINTENANCE

Maintain the base course in a satisfactory condition until the full pavement section is completed and accepted. Immediately repair any defects and repeat repairs as often as necessary to keep the area intact. Retest any base course that was not paved over prior to the onset of winter to verify that it still complies with the requirements of this specification. Rework or replace any area of base course that is damaged as necessary to comply with this specification.

3.15 DISPOSAL OF UNSATISFACTORY MATERIALS

Dispose of any unsuitable materials that have been removed outside the limits of Government-controlled land. No additional payments will be made for materials that have to be replaced.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 32 12 16.16

ROAD-MIX ASPHALT PAVING
11/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 156	(2013; R 2017) Standard Specification for Requirements for Mixing Plants for Hot-Mixed, Hot-Laid Bituminous Paving Mixtures
AASHTO T 304	(2011; R 2015) Standard Method of Test for Uncompacted Void Content of Fine Aggregate
AASHTO T 329	(2015) Standard Test Method for Moisture Content of Hot Mix Asphalt (HMA) by Oven Method

ASPHALT INSTITUTE (AI)

AI MS-2	(2015) Asphalt Mix Design Methods

ASTM INTERNATIONAL (ASTM)

ASTM C29/C29M	(2017a) Standard Test Method for Bulk Density ("Unit Weight") and Voids in Aggregate
ASTM C117	(2017) Standard Test Method for Materials Finer than 75-um (No. 200) Sieve in Mineral Aggregates by Washing
ASTM C127	(2015) Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Coarse Aggregate
ASTM C128	(2022) Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Fine Aggregate
ASTM C131/C131M	(2020) Standard Test Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
ASTM C136/C136M	(2019) Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates

ASTM C142/C142M	(2017) Standard Test Method for Clay Lumps and Friable Particles in Aggregates
ASTM C566	(2013) Standard Test Method for Total Evaporable Moisture Content of Aggregate by Drying
ASTM D75/D75M	(2019) Standard Practice for Sampling Aggregates
ASTM D242/D242M	(2009; R 2014) Mineral Filler for Bituminous Paving Mixtures
ASTM D979/D979M	(2015) Sampling Bituminous Paving Mixtures
ASTM D2041/D2041M	(2011) Theoretical Maximum Specific Gravity and Density of Bituminous Paving Mixtures
ASTM D2172/D2172M	(2017; E 2018) Standard Test Methods for Quantitative Extraction of Asphalt Binder from Asphalt Mixtures
ASTM D2419	(2014) Sand Equivalent Value of Soils and Fine Aggregate
ASTM D2726/D2726M	(2019) Standard Test Method for Bulk Specific Gravity and Density of Non-Absorptive Compacted Bituminous Mixtures
ASTM D3203/D3203M	(2017) Standard Test Method for Percent Air Voids in Compacted Asphalt Mixtures
ASTM D3665	(2012; R 2017) Standard Practice for Random Sampling of Construction Materials
ASTM D3666	(2016) Standard Specification for Minimum Requirements for Agencies Testing and Inspecting Road and Paving Materials
ASTM D4791	(2019) Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate
ASTM D4867/D4867M	(2009; R 2014) Effect of Moisture on Asphalt Concrete Paving Mixtures
ASTM D5361/D5361M	(2016) Standard Practice for Sampling Compacted Asphalt Mixtures for Laboratory Testing
ASTM D5444	(2015) Mechanical Size Analysis of Extracted Aggregate
ASTM D5821	(2013; R 2017) Standard Test Method for Determining the Percentage of Fractured Particles in Coarse Aggregate

ASTM D6307	(2019) Standard Test Method for Asphalt Content of Asphalt Mixture by Ignition Method
ASTM D6925	(2014) Standard Test Method for Preparation and Determination of the Relative Density of Hot Mix Asphalt (HMA) Specimens by Means of the Superpave Gyratory Compactor
ASTM D6926	(2020) Standard Practice for Preparation of Asphalt Mixture Specimens Using Marshall Apparatus
ASTM E1274	(2018) Standard Test Method for Measuring Pavement Roughness Using a Profilograph

NORTH CAROLINA DEPARTMENT OF TRANSPORATION (NCDOT)

NCDOT	(2018) North Carolina Department of Transporation Standard Specifications

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-02 Shop Drawings

Placement Plan; G

SD-03 Product Data

Diamond Grinding Plan; G

Mix Design; G

Contractor Quality Control; G

SD-04 Samples

Aggregates

Asphalt Cement Binder

Warm-mix Additive

SD-06 Test Reports

Aggregates; G

QC Monitoring

SD-07 Certificates

Asphalt Cement Binder; G

Laboratory Accreditation and Validation

Warm-mix Additive

1.3 ACCEPTANCE

1.3.1 Acceptability of Work

Acquire the services of an independent commercial laboratory to perform acceptance testing. Acceptance of the plant produced mix and in-place requirements will be on a lot to lot basis. The materials and the pavement itself will be accepted on the basis of production testing. The Government may make check tests from split samples to validate the results of the production testing. Testing performed by the Government does not reduce the required testing of the independent commercial laboratory. Split samples will be taken for Government testing to reduce the variability between the independent commercial laboratory and the Government's test results. When the difference between the independent commercial laboratory and the Government's test results for split samples exceed the acceptable range of two results for multilaboratory precision for the appropriate test method (i.e. ASTM) then at least one of the laboratories is determined to be in error. An evaluation of procedures and equipment in both laboratories will be made to determine the cause(s) for the differences. Develop steps to correct procedures and equipment to bring multilaboratory precision to within acceptable limits.

1.3.2 Acceptance Requirements

Provide all sampling and testing required for acceptance and payment adjustment. Where appropriate, adjustments in percent payment acceptance for individual lots of asphalt pavement will be made based on laboratory air voids, in-place density, smoothness, and grade in accordance with the following paragraphs. Surface smoothness and grade determinations will be made on the lot as a whole. Exceptions or adjustments to this will be made in situations where the mix within one lot is placed as part of both the intermediate and surface courses, thus smoothness and grade measurements for the entire lot cannot be made.

1.3.3 Pavement Lots

A standard lot for all requirements is equal to one day's production or 2,000 tons, whichever is smaller. Divide each lot into four equal sublots in order to evaluate laboratory air voids and in-place density. When operational conditions cause a lot to be terminated before the specified four sublots have been completed, use the following procedure to adjust the lot size and number of tests for the lot. Where three sublots have been completed, they constitute a lot. Where one or two sublots have been completed, incorporate them into the next lot and the total number of sublots (i.e. 5 or 6 sublots) is used for acceptance criteria. Include partial lots at the end of asphalt production into the previous lot. Complete and report all theoretical maximum density, laboratory air voids, and in-place density testing within 24 hours after construction of each lot.

1.3.4 Sublot Sampling

Take one mixture sample for each sublot in accordance with ASTM D979/D979M from a random truck or another location for determining theoretical maximum density, laboratory air voids, any additional testing the Government desires, and Contractor Quality Control. All samples will be

selected randomly, using commonly recognized methods of assuring randomness conforming to ASTM D3665 and employing tables of random numbers or computer programs.

1.3.5 Additional Sampling and Testing

The Government reserves the right to direct additional samples and tests for any area which appears to deviate from the specification requirements. The cost of any additional testing will be paid for by the Government. Testing in these areas will be treated as a separate lot. Payment Acceptance will be made for the quantity of asphalt pavement represented by these tests in accordance with the provisions of this section.

1.3.6 Theoretical Maximum Density (TMD)

Measure theoretical maximum density one time for each sublot in accordance with ASTM D2041/D2041M for purposes of calculating laboratory air voids and determining in-place density. The average TMD for each lot will be determined as the average TMD of the random sublot samples. When the TMD on both sides of a longitudinal joint is different, the average of these two TMD values will be used as the TMD needed to calculate the percent joint density.

1.3.7 Laboratory Air Voids

Prepare one set of laboratory compacted specimens for each sublot in accordance with ASTM D6926 using the hand-held hammer for the Marshall Method. Provide three test specimens prepared from the same sample for each set of laboratory compacted specimens. Compact the specimens within 2 hours of the time the mixture was loaded into trucks at the asphalt plant. Do not reheat samples prior to compaction. Provide insulated containers as necessary to maintain the sample temperature. Measure the bulk density of laboratory compacted specimens in accordance with ASTM D2726/D2726M. Determine laboratory air voids from one set (three laboratory compacted specimens) for each sublot sample in accordance with ASTM D3203/D3203M.

1.3.7.1 Tolerance

Provide laboratory air voids with a mean absolute deviation of 1.00 percent or less from the JMF for each lot. Remove and replace lots that do not meet the laboratory air voids requirement at least 4 inches into the cold (existing) lane adjacent to the longitudinal joint, at no additional cost to the Government. The mean absolute deviation of the laboratory air void contents from the JMF air void content will be evaluated as shown in the example below.

1.3.7.2 Calculating Laboratory Air Voids

Laboratory air void calculations for each lot will use the average theoretical maximum density values obtained for the lot. Determine the average TMD in accordance with paragraph THEORETICAL MAXIMUM DENSITY (TMD). The mean absolute deviation of the laboratory air void contents (one from each sublot) from the JMF air void content will be evaluated as in the following example:

Assume that the laboratory air voids are determined from 4 sublots where one set of laboratory compacted specimens is from a single sublot. The

laboratory air voids for the 4 sublots are determined to be 3.5, 3.0, 4.0, and 3.7. Assume that the target air voids from the JMF is 4.0. The mean absolute deviation is then:

Mean Absolute Deviation = (|3.5 - 4.0| + |3.0 - 4.0| + |4.0 - 4.0| + |3.7 - 4.0|)/4

Mean Absolute Deviation = (0.5 + 1.0 + 0.0 + 0.3)/4 = (1.8)/4 = 0.45

The mean absolute deviation for laboratory air voids is determined to be 0.45. It can be seen that 0.45 is less than 1.00 percent. The lot is acceptable for laboratory air voids.

1.3.8 In-place Density

Obtain one random 4 inch or 6 inch diameter core from the mat and joint of each sublot in accordance with ASTM D5361/D5361M for determining in-place density. Cut samples neatly with a diamond core drill bit. Obtain random cores that are the full thickness of the layer being placed. Select core locations randomly using the procedures contained in ASTM D3665. Locate cores for mat density no closer than 12 inches from a transverse or longitudinal joint including the pavement edge. Center all cores for joint density on the joint. Discard samples that are clearly defective as a result of sampling and take an additional random core. When the random core is less than 1 inch thick, it will not be included in the analysis. In this case, obtain another random core sample. Clean and tack coat dry core holes before filling with asphalt mixture. Fill all core holes with asphalt mixture and compact using a standard Marshall hammer to the density specified. Provide all tools, labor, and materials for cutting samples, cleaning, and filling the cored pavement. Measure in-place density in accordance with ASTM D2726/D2726M using each core obtained from the mat and joint.

1.3.8.1 Tolerance

Provide a minimum in-place mat density of 93.0 percent and a minimum in-place joint density of 90.0 percent for each lot. The average in-place mat and joint densities are expressed as a percentage of the average theoretical maximum density (TMD) for the lot. Determine the average TMD in accordance with paragraph THEORETICAL MAXIMUM DENSITY (TMD). Remove and replace lots that do not meet the in-place mat density requirement at least 4 inches into the cold (existing) lane adjacent to the longitudinal joint, at no additional cost to the Government. Remove and replace the longitudinal joint when the lot does not meet the in-place joint density, at no additional cost to the Government. Use a 10 feet wide paving lane that is centered over the joint.

1.3.9 Surface Smoothness

Use a straightedge and profilograph for measuring surface smoothness. Use the profilograph method for all longitudinal testing, except for paving lanes less than 0.25 miles in length. Use the straightedge method for transverse testing, for longitudinal testing where the length of each pavement lane is less than 0.25 miles, and at the ends of the paving limits for the project. Smoothness requirements do not apply over crowns or grade breaks. Maintain detailed notes of the testing results and provide a copy to the Government immediately after each day's testing.

1.3.9.1 Smoothness Requirements

1.3.9.1.1 Straightedge Testing

Provide finished surfaces of the pavements with no abrupt change of 1/4 inch or more when checked with an approved 12 foot straightedge. Remove and replace surface lift lots when the surface smoothness exceeds 3/8 inch, at no additional cost to the Government. High spots can be diamond ground as an alternative to remove and replace in order to meet surface smoothness requirements at individual locations.

1.3.9.1.2 Profilograph Testing

Provide finished surfaces with a Profile Index not greater than 9 inches per mile when tested with an approved California-type profilograph. Remove and replace the lot when the Profile Index exceeds the tolerance by 4.0 inches per mile or more, at no additional cost to the Government. Correct any small individual area with surface deviation which exceeds the tolerance given above by more than 5.0 inches per mile or more by diamond grinding to meet the specification requirements above or remove and replace at no additional cost to the Government.

1.3.9.2 Testing Method

After the final rolling, but not later than 24 hours after placement, test the surface of the pavement in each entire lot in a manner to reveal surface irregularities exceeding the tolerances specified above. If any pavement areas are diamond ground, retest these areas immediately after diamond grinding. The maximum area allowed to be corrected by diamond grinding is 10 percent of the total area of the lot. Test the entire area of the pavement with a profilograph. Check a number of random locations along with any observed suspicious locations primarily at transverse and longitudinal joints with the straightedge.

1.3.9.2.1 Straightedge Testing

Use the straightedge to measure abrupt changes in surface smoothness. Hold the straightedge in contact with the pavement surface and measure the maximum distance between the straightedge and the pavement surface. Determine the amount of surface irregularity by placing the freestanding (unleveled) straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length, and measuring the maximum gap between the straightedge and the pavement surface in the area between these two high points.

1.3.9.2.2 Profilograph Testing

Perform profilograph testing using an approved California profilograph and procedures described in ASTM E1274. Provide equipment that utilizes electronic recording and automatic computerized reduction of data to indicate "must-grind" bumps and the Profile Index for the pavement. Use a "blanking band" that is 0.2 inch wide and the "bump template" spanning 1 inch with an offset of 0.4 inch. Provide profilograph operated by an approved, factory-trained operator on the alignments specified above. Provide a copy of the reduced tapes to the Government at the end of each day's testing.

1.3.9.2.3 Bumps ("Must Grind" Areas)

Reduce any bumps ("must grind" areas) shown on the profilograph trace which exceed 0.4 inch in height by diamond grinding until they do not exceed 0.3 inch when retested. Taper diamond grinding in all directions to provide smooth transitions to areas not requiring diamond grinding. The following will not be permitted: (1) skin patching for correcting low areas, (2) planing or milling for correcting high areas. At the Contractor's option, pavement areas including diamond ground areas can be rechecked with the profilograph in order to record a lower Profile Index.

1.3.10 Plan Grade

Provide a final wearing surface of pavement conforming to the elevations and cross sections shown and not vary more than 0.05 foot from the plan grade established and approved at site of work. Within 5 working days after completion of a particular lot incorporating the final wearing course, test the final wearing surface of the pavement for conformance with specified plan grade requirements. Match finished surfaces at juncture with other pavements with finished surfaces of abutting pavements. Deviation from the plan elevation will not be permitted in areas of pavements where closer conformance with planned elevation is required for the proper functioning of drainage and other appurtenant structures involved. For roads, the grade will be determined by running lines of levels along the centerline at intervals of 25 feet or less longitudinally to determine the elevation of the completed pavement surface. Measure transverse grades at appropriate intervals. For parking lots, the grade will be determined by running lines of levels at intervals of 25 feet or less longitudinally and transversely to determine the elevation of the completed pavement surface. Diamond grinding can be used to remove high spots to meet grade requirements. Skin patching for correcting low areas or planing or milling for correcting high areas will not be permitted. Maintain detailed notes of the results of the testing and provide a copy to the Government immediately after each day's testing. Remove and replace surface lift lots when individual locations exceed 0.05 foot tolerance, at no additional cost to the Government. High spots can be diamond ground as an alternative to remove and replace in order to meet plan grade requirements at individual locations.

1.3.11 Laboratory Accreditation and Validation

Provide laboratories used to develop the Job Mix Formula (JMF), perform acceptance testing, and Contractor Quality Control testing that meet the requirements of ASTM D3666. Provide laboratories with a masonry saw having a diamond blade for trimming pavement cores and samples. Perform all required test methods by an accredited laboratory. Schedule and provide payment for laboratory inspections. Additional payment or a time extension due to failure to acquire the required laboratory accreditation is not allowed. The Government will inspect the laboratory equipment and test procedures prior to the start of hot-mix warm-mix operations for conformance with ASTM D3666. In addition, all testing laboratories performing acceptance testing require USACE validation by the Material Testing Center (MTC) for both parent laboratory and plant testing laboratory. Validation on all laboratories is required to remain current throughout the duration of the paving project. Contact the MTC manager listed at https://mtc.erdc.dren.mil for costs and scheduling. Submit a certificate of compliance signed by the manager of the laboratory stating that it meets these requirements to the Government prior to the start of construction. At a minimum, include the following certifications:

a. Qualifications of personnel; laboratory manager, supervising technician, and testing technicians.

b. A listing of equipment to be used in developing the job mix.

c. A copy of the laboratory's quality control system.

1.4 ENVIRONMENTAL REQUIREMENTS

Do not place the asphalt mixture upon a wet surface or when the surface temperature of the underlying course is less than specified in Table 3 Table 1. The temperature requirements may be waived by the Government, if requested; however, meet all other requirements including compaction.

Table 3. Table 1. Surface Temperature Limitations of Underlying Course

Mat Thickness, inches	Degrees F
3 or greater	40
Less than 3	45

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Perform the work consisting of pavement courses composed of mineral aggregate and asphalt material heated and mixed in a central mixing plant and placed on a prepared course. Provide asphalt pavement designed and constructed in accordance with this section conforming to the lines, grades, thicknesses, and typical cross sections shown on the drawings. Construct each course to the depth, section, or elevation required by the drawings and rolled, finished, and approved before the placement of the next course. Submit proposed Placement Plan indicating lane widths and longitudinal joints for each course or lift.

2.1.1 Asphalt Mixing Plant

Provide plants used for the preparation of asphalt mixture conforming to the requirements of AASHTO M 156 with the following changes:

2.1.1.1 Truck Scales

Weigh the asphalt mixture on approved scales, or on certified public scales at no additional expense to the Government. Inspect and seal scales at least annually by an approved calibration laboratory.

2.1.1.2 Inspection of Plant

Provide access to the Government at all times, to all areas of the plant for checking adequacy of equipment; inspecting operation of the plant; verifying weights, proportions, and material properties; checking the temperatures maintained in the preparation of the mixtures and for taking samples. Provide assistance as requested, for the Government to procure any desired samples.

2.1.1.3 Storage bins

The asphalt mixture can be stored in non-insulated storage bins for a period of time not exceeding 3 hours. The asphalt mixture can be stored in insulated storage bins for a period of time not exceeding 8 hours. Provide the mix drawn from bins that meets the same requirements as mix loaded directly into trucks.

2.1.2 Hauling Equipment

Provide trucks used for hauling asphalt mixture that have tight, clean, and smooth metal beds. To prevent the mixture from adhering to them, lightly coat the truck beds with a minimum amount of paraffin oil, lime solution, or other approved material. Do not use petroleum based products as a release agent. Provide each truck with a suitable cover to protect the mixture from adverse weather, contamination, and loss of material during hauling. When necessary due to long haul distance and cold weather, provide insulated truck beds with covers (tarps) that are securely fastened.

2.1.3 Asphalt Pavers

Provide mechanical spreading and finishing equipment consisting of a self-powered paver, capable of spreading and finishing the mixture to the specified line, grade, and cross section. Provide paver screed capable of laying a uniform mixture to meet the specified thickness, smoothness, and grade without physical or temperature segregation, the full width of the material being placed. Provide a paver with a vibrating screed to be used during all placement.

2.1.3.1 Receiving Hopper

Provide paver with a receiving hopper of sufficient capacity to permit a uniform spreading operation and a distribution system to place the mixture uniformly in front of the screed without segregation. Provide a screed that effectively produces a finished surface of the required evenness and texture without tearing, shoving, or gouging the mixture.

2.1.3.2 Automatic Grade Controls

Provide a paver equipped with a control system capable of maintaining the specified screed elevation. One of three methods can be used to control grade: stringline, laser, or computerized elevations along with GPS. For multiple layers it is acceptable to control the grade in the underlying layer and control the grade of the surface layer by applying a constant thickness over the underlying layer which has been placed to the desired grade. Slope control can also be used to control the grade of the surface for roads, but is not acceptable for wide pavements such as parking lots. Provide transverse slope controller capable of maintaining the screed at the desired slope within plus or minus 0.1 percent. A ski-type device of not less than 30 ft can be used to provide improved smoothness. Use a shoe on one side of the paver to match an existing paved surface to provide a smooth joint.

2.1.4 Rollers

Provide rollers in good condition and operate at slow speeds to avoid displacement of the asphalt mixture. Provide sufficient number, type, and weight of rollers to compact the mixture to the required density while it

is still in a workable condition. Do not use equipment which causes excessive crushing of the aggregate.

2.1.5 Diamond Grinding

Those performing diamond grinding are required to have a minimum of three years experience in diamond grinding. In areas not meeting the specified limits for surface smoothness and plan grade, reduce high areas to attain the required smoothness and grade, except as depth is limited below. Reduce high areas by diamond grinding the asphalt pavement with approved equipment. Perform diamond grinding by sawing with saw blades impregnated with an industrial diamond abrasive. Assemble the saw blades in a cutting head mounted on a machine designed specifically for diamond grinding that produces the required texture and smoothness level without damage to the asphalt pavement or joint faces. Provide diamond grinding equipment with saw blades that are 1/8-inch wide, a minimum of 60 blades per 12 inches of cutting head width, and capable of cutting a path a minimum of 3 feet wide. Diamond grinding equipment that causes raveling, fracturing of aggregate, or disturbance to the underlying material will not be allowed. The maximum area corrected by diamond grinding the surface of the asphalt pavement is 10 percent of the total area of any lot. The maximum depth of diamond grinding is 1/2 inch. Provide diamond grinding machine equipped to flush and vacuum the pavement surface. Dispose of all debris from diamond grinding operations off Government property. Prior to diamond grinding, submit a Diamond Grinding Plan for review and approval. At a minimum, include the daily reports for the deficient areas, the location and extent of deficiencies, corrective actions, and equipment. Remove and replace all pavement areas requiring plan grade or surface smoothness corrections in excess of the limits specified.

Prior to production diamond grinding operations, perform a test section at the approved location, consisting of a minimum of two adjacent passes with a minimum length of 40 feet to allow evaluation of the finish and transition between adjacent passes. Production diamond grinding operations cannot be performed prior to approval.

2.2 AGGREGATES

Notify the Government at least 7 days before sampling aggregates. Obtain samples in accordance with ASTM D75/D75M that are representative of the materials to be used for the project. Provide aggregates consisting of crushed stone, crushed gravel, crushed slag, screenings, natural sand, and mineral filler as required. The portion of material retained on the No. 4 sieve is coarse aggregate. The portion of material passing the No. 4 sieve and retained on the No. 200 sieve is fine aggregate. The portion passing the No. 200 sieve is defined as mineral filler. Submit sufficient materials to produce 200 pounds of blended mixture for mix design verification. Submit all aggregate test results and samples to the Government at least 14 days prior to start of construction. Perform job aggregate testing no earlier than 6 months before contract award.

2.2.1 Coarse Aggregate

Provide coarse aggregate consisting of sound, tough, durable particles, free from films of material that would prevent thorough coating and bonding with the asphalt material and free from organic matter and other deleterious substances. Provide coarse aggregate particles meeting the following requirements:

a. The percentage of loss not greater than 40 percent after 500 revolutions when tested in accordance with ASTM C131/C131M.

c. At least 75 percent by weight of coarse aggregate containing two or more fractured faces when tested in accordance with ASTM D5821 with fractured faces produced by crushing.

d. The particle shape essentially cubical and the aggregate containing not more than 10 percent, by weight, of flat and elongated particles (5:1 ratio of length to thickness) when tested in accordance with ASTM D4791, Method B.

e. Slag consisting of air-cooled, blast furnace slag with a compacted weight of not less than 75 lb/cu ft when tested in accordance with ASTM C29/C29M.

f. Clay lumps and friable particles not exceeding 0.3 percent, by weight, when tested in accordance with ASTM C142/C142M.

2.2.2 Fine Aggregate

Provide fine aggregate consisting of clean, sound, tough, durable particles. Provide aggregate particles that are free from coatings of clay, silt, or any objectionable material, contain no clay balls, and meet the following requirements:

a. Quantity of natural sand (noncrushed material) added to the aggregate blend not exceeding 15 percent by weight of total aggregate.

b. Individual fine aggregate sources with a sand equivalent value greater than 45 when tested in accordance with ASTM D2419.

c. Fine aggregate portion of the blended aggregate with an uncompacted void content greater than 45.0 percent when tested in accordance with AASHTO T 304 Method A.

d. Clay lumps and friable particles not exceeding 0.3 percent, by weight, when tested in accordance with ASTM C142/C142M.

2.2.3 Mineral Filler

Provide mineral filler consisting of a nonplastic material meeting the requirements of ASTM D242/D242M.

2.2.4 Aggregate Gradation

Provide a combined aggregate gradation that conforms to gradations specified in Table 4 Table 2, when tested in accordance with ASTM C136/C136M and ASTM C117, and does not vary from the low limit on one sieve to the high limit on the adjacent sieve or vice versa, but grades uniformly from coarse to fine. Provide a JMF within the specification limits; however, the gradation can exceed the limits when the allowable deviation from the JMF shown in Tables 6 and 7 Tables 4 and 5 are applied.

Table 4. Table 2. Aggregate Gradations

Sieve Size, inch	Gradation 1 Percent Passing by Mass	Gradation 2 Percent Passing by Mass	Gradation 3 Percent Passing by Mass
1	100	---	---
3/4	90-100	100	---
1/2	68-88	90-100	100
3/8	60-82	69-89	90-100
No. 4	45-67	53-73	58-78
No. 8	32-54	38-60	40-60
No. 16	22-44	26-48	28-48
No. 30	15-35	18-38	18-38
No. 50	9-25	11-27	11-27
No. 100	6-18	6-18	6-18
No. 200	3-6	3-6	3-6

2.3 ASPHALT CEMENT BINDER

Provide asphalt cement binder that conforms to AASHTO M 320 TABLE 1 Performance Grade (PG) 64-22.. Provide test data indicating grade certification by the supplier at the time of delivery of each load to the mix plant. When warm-mix asphalt technology involves additives, grade the asphalt binder with the asphalt binder additive included. Submit copies of these certifications to the Government. The supplier is defined as the last source of any modification to the binder. The Government may sample and test the binder at the mix plant at any time before or during mix production.

2.4 WARM-MIX ASPHALT TECHNOLOGIES/PRODUCTS

Provide warm-mix asphalt technologies/products that have a record of good performance and are included on the local state DOT's qualified products list, if the DOT maintains a qualified products list. These qualified products lists can be found at each state DOT's website.

2.5 MIX DESIGN

Develop the mix design. Perform Job Mix formula (JMF) and aggregates testing no earlier than 6 months before contract award. Provide asphalt mixture composed of well-graded aggregate, mineral filler if required, and asphalt material. Provide aggregate fractions sized, handled in separate size groups, and combined in such proportions that the resulting mixture meets the grading requirements of Table 4 Table 2. Do not produce asphalt pavement for payment acceptance until a JMF has been approved. Design the asphalt mixture using the Superpave gyratory compactor set at 75 gyrations. Prepare samples at various asphalt contents and compacted in accordance with ASTM D6925. Asphalt mix design that meet NCDOT gradation and material properties. Use laboratory compaction temperatures for Polymer Modified Asphalts as recommended by the asphalt binder

manufacturer. Determine the Tensile Strength Ratio (TSR) of the composite mixture in accordance with ASTM D4867/D4867M. Compact the TSR specimens to an air void content of 7 percent plus or minus 1 percent. If the Tensile Strength Ratio (TSR) of the composite mixture is less than 75, reject the aggregates or treat the asphalt mixture with an anti-stripping agent. Add a sufficient amount of anti-stripping agent to produce a TSR of not less than 75. If an antistrip agent is required, provide it at no additional cost to the Government. Provide sufficient materials to produce 200 pound of blended mixture to the Government for verification of mix design at least 14 days prior to construction of test section.

2.5.1 JMF Requirements

Submit the proposed JMF in writing, for approval, at least 14 days prior to the start of the test section including, as a minimum:

a. Percent passing each sieve size.

b. Percent of asphalt cement.

c. Percent of each aggregate and mineral filler to be used.

d. Asphalt performance grade or penetration grade.

e. Number of Superpave gyratory compactor gyrations.

f. Laboratory mixing temperature.

g. Laboratory compaction temperature.

h. Temperature-viscosity relationship of the asphalt cement

i. Plot of the combined gradation on the 0.45 power gradation chart, stating the nominal maximum size.

j. Graphical plots and summary tabulation of air voids, voids in the mineral aggregate, and unit weight versus asphalt content as shown in AI MS-2. Include summary tabulation that includes individual specimen data for each specimen tested.

k. Specific gravity and absorption of each aggregate.

l. Percent natural sand.

m. Percent particles with two or more fractured faces (in coarse aggregate).

n. Fine aggregate angularity.

o. Percent flat or elongated particles in coarse aggregate.

p. Tensile Strength Ratio and wet/dry specimen test results.

q. Antistrip agent (if required).

r. List of all modifiers.

s. Percentage and properties (asphalt content, aggregate gradation, and aggregate properties) of RAP in accordance with paragraph RECYCLED

ASPHALT PAVEMENT, if RAP is used.

t. Warm-mix additive or process.

Table 5. Table 3. Mix Design Criteria

Test Property	Marshall (50 Blows)	Marshall (75 Blows)	Superpave (75 gyrations)
Stability, pounds, minimum (NA for Superpave)	1000(1)	1800(1)	NA
Flow, 0.01 inch, (NA for Superpave)	8-18	8-16	NA
Air voids, percent	3-5	3-5	3-5
Minimum Percent Voids in Mineral Aggregate (VMA)(2)			
Gradation 1	13.0	13.0	13.0
Gradation 2	14.0	14.0	14.0
Gradation 3	15.0	15.0	15.0
TSR, minimum percent	75	75	75
(1) This is a minimum requirement. Provide significantly higher average during construction to ensure compliance with the specifications.			
(2) Calculate VMA in accordance with AI MS-2, based on ASTM C127 and ASTM C128 bulk specific gravity for the aggregate.			

2.5.2 Adjustments to JMF

The JMF for each mixture is in effect until a new formula is approved in writing by the Government. Should a change in sources of any materials be made, perform a new mix design and a new JMF approved before the new material is used. Make minor adjustments within the specification limits to the JMF to optimize mix volumetric properties. Adjustments to the original JMF are limited to plus or minus 4 percent on the No. 4 and coarser sieves; plus or minus 3 percent on the No. 8 to No. 50 sieves; and plus or minus 1 percent on the No. 100 sieve and No. 200 sieve. Asphalt content adjustments are limited to plus or minus 0.40 from the original JMF. If adjustments are needed that exceed these limits, develop a new mix design.

2.6 RECYCLED HOT MIX ASPHALT

Recycled asphalt mixture is not allowed for the project.

PART 3 EXECUTION

3.1 CONTRACTOR QUALITY CONTROL

3.1.1 General Quality Control Requirements

Submit the Quality Control Plan. Do not produce hot-mix warm-mix asphalt for payment acceptance until the quality control plan has been approved. In the quality control plan, address all elements which affect the quality of the pavement including, but not limited to:

a. Mix Design and unique JMF identification code

b. Aggregate Grading

c. Quality of Materials

d. Stockpile Management and procedures to prevent contamination

e. Proportioning including percent of warm-mix additive

f. Mixing and Transportation

g. Mixture Volumetrics

h. Moisture Content of Mixtures

i. Placing and Compaction

j. Joints

k. Surface Smoothness

l. Truck bed release agent

3.1.2 Testing Laboratory

Provide a fully equipped asphalt laboratory located at the plant or job site that is equipped with heating and air conditioning units to maintain a temperature of 75 plus or minus 5 degrees F. Provide laboratory facilities that are kept clean and all equipment maintained in proper working condition. Provide the Government with unrestricted access to inspect the laboratory facility, to witness quality control activities, and to perform any check testing desired. The Government will advise in writing of any noted deficiencies concerning the laboratory facility, equipment, supplies, or testing personnel and procedures. When the deficiencies are serious enough to adversely affect test results, immediately suspend the incorporation of the materials into the work. Incorporation of the materials into the work will not be permitted to resume until the deficiencies are corrected.

3.1.3 Quality Control Testing

Perform all quality control tests applicable to these specifications and as set forth in the Quality Control Program. Use the independent commercial laboratory for acceptance testing in paragraph ACCEPTANCE. Use in-house capabilities or the independent commercial laboratory for quality control testing. Required elements of the testing program include, but are not limited to tests for the control of asphalt content, aggregate

gradation, aggregate moisture, moisture in the asphalt mixture, temperatures, VMA, and in-place density. Develop a Quality Control Testing Plan as part of the Quality Control Program.

3.1.3.1 Asphalt Content

Determine asphalt content a minimum of twice per lot (a lot is defined in paragraph PAVEMENT LOTS) using the ignition method in accordance with ASTM D6307. Use the extraction method in accordance with ASTM D2172/D2172M if the correction factor for the ignition method in ASTM D6307 is greater than 1.0. The asphalt content for the lot will be determined by averaging the test results.

3.1.3.2 Aggregate Properties

Determine aggregate gradations a minimum of twice per lot from mechanical analysis of extracted aggregate in accordance with ASTM D5444, ASTM C136/C136M, and ASTM C117. Determine the specific gravity of each aggregate size grouping for each 20,000 tons in accordance with ASTM C127 or ASTM C128. Determine fractured faces for gravel sources for each 20,000 tons in accordance with ASTM D5821. Determine the uncompacted void content of natural sand, manufactured sand, and blended aggregate for each 20,000 tons in accordance with AASHTO T 304 Method A.

3.1.3.3 Moisture Content of Aggregate

Determine the moisture content of aggregate used for production a minimum of once per lot in accordance with ASTM C566.

3.1.3.4 Moisture Content of Asphalt Mixture

Determine the moisture content of the asphalt mixture at least once per lot in accordance with AASHTO T 329.

3.1.3.5 Temperatures

Check temperatures at least four times per lot, at necessary locations to determine the temperature at the dryer, the asphalt cement binder in the storage tank, the asphalt mixture at the plant, and the asphalt mixture at the job site.

3.1.3.6 VMA

Obtain mixture samples at least four times per lot. Calculate the VMA of each specimen in accordance with AI MS-2 based on ASTM C127 and ASTM C128 bulk specific gravity for the aggregate. Provide VMA within the limits of Table 5 Table 3.

3.1.3.7 In-Place Density

Conduct any necessary testing to ensure the specified density is achieved. A nuclear gauge or other non-destructive testing device can be used to monitor pavement density.

3.1.3.8 Additional Testing

Perform any additional testing deemed necessary to control the process.

3.1.3.9 QC Monitoring

Submit all QC test results to the Government on a daily basis as the tests are performed. The Government reserves the right to monitor any of the Contractor's quality control testing and to perform duplicate testing as a check to the Contractor's quality control testing.

3.1.4 Sampling

When directed by the Government, sample and test any material which appears to not meet specification requirements unless such material is voluntarily removed and replaced or deficiencies corrected. Perform all sampling in accordance with standard procedures specified.

3.1.5 Control Charts

For process control, establish and maintain linear control charts on both individual samples and the running average of last four samples for the parameters listed in Table 6 Table 4, as a minimum. Post the control charts as directed by the Government and maintain current at all times. Identify the following on the control charts: the project number, the test parameter being plotted, the individual sample numbers, the Action and Suspension Limits listed in Table 6 Table 4 applicable to the test parameter being plotted, and the test results. Also show target values (JMF) on the control charts as indicators of central tendency for the cumulative percent passing, asphalt content, and laboratory air voids parameters. When the test results exceed either applicable Action Limit, take immediate steps to bring the process back in control. When the test results exceed either applicable Suspension Limit, halt production until the problem is solved. When the Suspension Limit is exceeded for individual values or running average values, the Government has the option to require removal and replacement of the material represented by the samples or to leave in place and base acceptance on mixture volumetric properties and in place density. Use the control charts as part of the process control system for identifying trends so that potential problems can be corrected before they occur. Make decisions concerning mix modifications based on analysis of the results provided in the control charts. In the Quality Control Plan, indicate the appropriate action to be taken to bring the process into control when certain parameters exceed their Action Limits.

Table 6. Table 4. Action and Suspension Limits for the Parameters to be Plotted on Individual and Running Average Control Charts

	Individual Samples		Running Average of	
Parameter to be Plotted	Action Limit	Suspension Limit	Action Limit	Suspension Limit
No. 4 sieve, Cumulative percent passing, deviation for JMF target; plus or minus values	6	8	4	5
No. 30 sieve, Cumulative percent passing, deviation for JMF target; plus or minus values	4	6	3	4
No. 200 sieve, Cumulative percent passing, deviation for JMF target; plus or minus values	1.4	2.0	1.1	1.5

Table 6. Table 4. Action and Suspension Limits for the Parameters to be Plotted on Individual and Running Average Control Charts

	Individual Samples		Running Average of	
Parameter to be Plotted	Action Limit	Suspension Limit	Action Limit	Suspension Limit
Asphalt content, percent deviation from JMF target; plus or minus value	0.4	0.5	0.2	0.3
Stability, pounds (minimum) (NA for Superpave)				
75 Blow JMF	1800	1700	1900	1800
50 Blow JMF	1000	900	1100	1000
Flow, 0.01 inch (NA for Superpave)				
75 Blow JMF	8 min.	7 min.	9 min.	8 min.
	16 max.	17 max.	15 max.	16 max.
50 Blow JMF	8 min.	7 min.	9 min.	8 min.
	18 max.	19 max.	17 max.	18 max.
Laboratory Air Voids, percent deviation from JMF target value	No specific action and suspension limits set since this parameter is used for acceptance			
In-place Mat Density, percent of TMD	No specific action and suspension limits set since this parameter is used for acceptance			
In-place Joint Density, percent of TMD	No specific action and suspension limits set since this parameter is used for acceptance			
VMA				
Gradation 1	13.5	13.0	13.3	13.0
Gradation 2	14.5	14.0	14.3	14.0
Gradation 3	15.5	15.0	15.3	15.0

3.2 PREPARATION OF ASPHALT BINDER MATERIAL

Heat the asphalt cement material while avoiding local overheating. Provide a continuous supply of the asphalt material to the mixer at a uniform temperature. Maintain the temperature of the asphalt delivered to the mixer to provide a suitable viscosity for adequate coating of the aggregate particles. For hot-mix, do not heat unmodified asphalt to a temperature exceeding 325 degrees F when added to the aggregate. Do not heat modified asphalt to a temperature exceeding 350 degrees F when added to the aggregate. For warm-mix, do not heat asphalt binder to a temperature exceeding 270 degrees F when added to the aggregate.

3.3 PREPARATION OF MINERAL AGGREGATE

Heat and dry the aggregate prior to mixing. Provide a rate of heating and a maximum temperature that does not damage the aggregates. Do not heat the aggregate to a temperature exceeding 350 degrees F when the asphalt binder is added. Maintain the temperature no lower than is required to obtain complete coating and uniform distribution on the aggregate particles and to provide a mixture of satisfactory workability.

3.4 PREPARATION OF ASPHALT MIXTURE

Weigh or meter the aggregates and the asphalt cement and introduce into

the mixer the amount specified by the JMF. Mix the combined materials until the aggregate obtains a uniform coating of asphalt binder and is thoroughly distributed throughout the mixture. The moisture content of all asphalt mixture upon discharge from the plant is not to exceed 0.5 percent by total weight of mixture as measured by AASHTO T 329.

3.5 PREPARATION OF THE UNDERLYING SURFACE

Immediately before placing the asphalt mixture, clean the underlying course of dust and debris.

3.6 TEST SECTION

Prior to full production, place a test section for each JMF used. Construct a test section 250 to 500 feet long and two paver passes wide with a longitudinal cold joint. Do not place the second lane of test section until the temperature of pavement edge is less than 175 degrees F. Construct the test section with the same depth as the course which it represents. Ensure the underlying grade or pavement structure upon which the test section is to be constructed is the same or very similar to underlying layer for the project. Use the same equipment and procedures in construction of the test section as on the remainder of the course represented by the test section. Construct the test section as part of the project pavement, as approved by the Government.

3.6.1 Sampling and Testing for Test Section

Obtain one sample at the plant from a random truck. Compact three specimens and test for laboratory air voids. Test a portion of the same sample for theoretical maximum density (TMD), aggregate gradation, asphalt content, and TSR. Adjust the compactive effort as required to provide TSR specimens with an air void content of 7 plus or minus 1 percent. Obtain four randomly selected cores from each finished pavement mat (eight total), four from the longitudinal joint, and test for density. Perform random sampling in accordance with procedures contained in ASTM D3665. Construction may continue provided the test results are within the tolerances or exceed the minimum values shown in Table 7 Table 5. If all test results meet the specified requirements, the test section may remain as part of the project pavement. If test results exceed the tolerances shown, remove and replace the test section and construct another test section at no additional cost to the Government.

Table 7. Table 5. Test Section Requirements for Material and Mixture Properties

Property	Specification Limit
Aggregate Gradation-Percent Passing (Individual Test Result)	
No. 4 and larger	JMF plus or minus 8
No. 8, No. 16, No. 30, and No. 50	JMF plus or minus 6
No. 100 and No. 200	JMF plus or minus 2.0

Table 7. Table 5. Test Section Requirements for Material and Mixture Properties	
Property	Specification Limit
Asphalt Content, Percent (Individual Test Result)	JMF plus or minus 0.5
Laboratory Air Voids, Percent (Average of 3 specimens)	JMF plus or minus 1.0
VMA, Percent (Average of 3 specimens)	See Table 5 Table 3
Tensile Strength Ratio (TSR) (At 7 percent plus/minus 1 percent air void content)	75 percent minimum
Conditioned Strength	60 psi minimum
Mat Density, Percent of TMD (Average of 4 Random Cores)	92.0 - 96.0 93.0 minimum
Joint Density, Percent of TMD (Average of 4 Random Cores)	89.5 minimum 90.0 minimum

3.6.2 Additional Test Sections

If the initial test section should prove to be unacceptable, make the necessary adjustments to the JMF, plant operation, placing procedures, and rolling procedures before beginning construction of a second test section. Construct and evaluate additional test sections, as required, for conformance to the specifications. Full production paving is not allowed until an acceptable section has been constructed and accepted.

3.7 TRANSPORTING AND PLACING

3.7.1 Transporting

Transport asphalt mixture from the mixing plant to the site in clean, tight vehicles. Schedule deliveries so that placing and compacting of mixture is uniform with minimum stopping and starting of the paver. Provide adequate artificial lighting for night placements. Hauling over freshly placed material will not be permitted until the material has been compacted as specified, and allowed to cool to 140 degrees F.

3.7.2 Placing

Place the mix in lifts of adequate thickness and compact at a temperature suitable for obtaining density, surface smoothness, and other specified

requirements. Upon arrival, place the mixture to the full width by an asphalt paver; strike off in a uniform layer of such depth that, when the work is completed, the required thickness is obtained and the surface conforms to the grade and contour indicated. Do not broadcast waste mixture onto the mat or recycle into the paver hopper. Collect waste mixture and dispose off site. Regulate the speed of the paver to eliminate pulling and tearing of the asphalt mat. Begin placement of the mixture along the centerline of a crowned section or on the high side of areas with a one-way slope. Place the mixture in consecutive adjacent strips having a minimum width of 10 feet. Offset the longitudinal joint in one course from the longitudinal joint in the course immediately below by at least 1 foot; however, locate the joint in the surface course at the centerline of the pavement. Offset transverse joints in one course by at least 10 feet from transverse joints in the previous course. Offset transverse joints in adjacent lanes a minimum of 10 feet. On isolated areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impractical, the mixture can be spread and luted by hand tools.

3.8 COMPACTION OF MIXTURE

3.8.1 General

a. After placing, thoroughly and uniformly compact the mixture by rolling. Compact the surface as soon as possible without causing displacement, cracking, or shoving. Determine the sequence of rolling operations and the type of rollers used with the exception that application of more than three passes with a vibratory roller in the vibrating mode is prohibited. Maintain the speed of the roller, at all times, sufficiently slow to avoid displacement of the asphalt mixture and to be effective in compaction. Correct at once any displacement occurring as a result of reversing the direction of the roller, or from any other cause.

b. Furnish sufficient rollers to handle the output of the plant. Continue rolling until the surface is of uniform texture, true to grade and cross section, and the required field density is obtained. To prevent adhesion of the mixture to the roller, keep the wheels properly moistened, but excessive water is not permitted. In areas not accessible to the roller, thoroughly compact the mixture with hand tampers or small compactors. Remove the full depth of any mixture that becomes loose and broken, mixed with dirt, contains check-cracking, or is in any way defective. Replace with fresh asphalt mixture and immediately compact to conform to the surrounding area. Perform this work at no expense to the Government. Skin patching is not allowed.

3.8.2 Segregation

The Government can sample and test any material that looks deficient. When the in-place material appears to be segregated, the Government has the option to sample the material and have it tested and compared to the aggregate gradation, asphalt content, and in-place density requirements in Table 7 Table 5. If the material fails to meet these specification requirements, remove and replace the extent of the segregated material the full depth of the layer of asphalt mixture at no additional cost to the Government. When segregation occurs in the mat, take appropriate action to correct the process so that additional segregation does not occur.

3.9 JOINTS

Construct joints to ensure a continuous bond between the courses and to obtain the required density. Provide all joints with the same texture as other sections of the course and meet the requirements for smoothness and grade.

3.9.1 Transverse Joints

Do not pass the roller over the unprotected end of the freshly laid mixture, except when necessary to form a transverse joint. When necessary to form a transverse joint, construct by means of placing a bulkhead or by tapering the course. Utilize a dry saw cut on the transverse joint full depth and width on a straight line to expose a vertical face prior to placing the adjacent lane. Remove the cutback material from the project. In both methods, provide a light tack coat of asphalt material to all contact surfaces before placing any fresh mixture against the joint.

3.9.2 Longitudinal Joints

Provide a joint that meets density and smoothness requirements for joints and has uniform texture. Cut back longitudinal joints which are irregular, damaged, uncompacted, cold (less than 175 degrees F at the time of placing adjacent lanes), or otherwise defective, a maximum of 3 inches from the top of the course with a cutting wheel to expose a clean, sound, near vertical surface for the full depth of the course. Remove all cutback material from the project. Provide a light tack coat of asphalt material to all contact surfaces prior to placing any fresh mixture against the joint.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 32 13 13.06

PORTLAND CEMENT CONCRETE PAVEMENT FOR ROADS AND SITE FACILITIES
05/20

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 211.1	(1991; R 2009) Standard Practice for Selecting Proportions for Normal, Heavyweight and Mass Concrete
ACI 305R	(2020) Guide to Hot Weather Concreting
ACI 306R	(2016) Guide to Cold Weather Concreting

ASTM INTERNATIONAL (ASTM)

ASTM A184/A184M	(2019) Standard Specification for Welded Deformed Steel Bar Mats for Concrete Reinforcement
ASTM A615/A615M	(2022) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A966/A966M	(2015; R 2020) Standard Test Method for Magnetic Particle Examination of Steel Forgings Using Alternating Current
ASTM C31/C31M	(2022) Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C33/C33M	(2024a) Standard Specification for Concrete Aggregates
ASTM C42/C42M	(2020) Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete
ASTM C78/C78M	(2022) Standard Test Method for Flexural Strength of Concrete (Using Simple Beam with Third-Point Loading)
ASTM C88	(2018) Standard Test Method for Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
ASTM C94/C94M	(2022a) Standard Specification for Ready-Mixed Concrete

ASTM C143/C143M	(2020) Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C150/C150M	(2024) Standard Specification for Portland Cement
ASTM C171	(2020) Standard Specification for Sheet Materials for Curing Concrete
ASTM C172/C172M	(2017) Standard Practice for Sampling Freshly Mixed Concrete
ASTM C231/C231M	(2022) Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C260/C260M	(2010a; R 2016) Standard Specification for Air-Entraining Admixtures for Concrete
ASTM C309	(2019) Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C494/C494M	(2019; E 2022) Standard Specification for Chemical Admixtures for Concrete
ASTM C595/C595M	(2025) Standard Specification for Blended Hydraulic Cements
ASTM C618	(2025a) Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C881/C881M	(2020a) Standard Specification for Epoxy-Resin-Base Bonding Systems for Concrete
ASTM C989/C989M	(2022) Standard Specification for Slag Cement for Use in Concrete and Mortars
ASTM C1017/C1017M	(2013; E 2015) Standard Specification for Chemical Admixtures for Use in Producing Flowing Concrete
ASTM C1077	(2026) Standard Practice for Agencies Testing Concrete and Concrete Aggregates for Use in Construction and Criteria for Testing Agency Evaluation
ASTM C1240	(2020) Standard Specification for Silica Fume Used in Cementitious Mixtures
ASTM C1260	(2021) Standard Test Method for Potential Alkali Reactivity of Aggregates (Mortar-Bar Method)
ASTM C1542/C1542M	(2019) Standard Test Method for Measuring Length of Concrete Cores

ASTM C1567	(2025) Standard Test Method for Determining the Potential Alkali-Silica Reactivity of Combinations of Cementitious Materials and Aggregate (Accelerated Mortar-Bar Method)
ASTM C1602/C1602M	(2022) Standard Specification for Mixing Water Used in Production of Hydraulic Cement Concrete
ASTM D1751	(2018) Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D2995	(1999; R 2009) Determining Application Rate of Bituminous Distributors
ASTM E1274	(2018) Standard Test Method for Measuring Pavement Roughness Using a Profilograph

NATIONAL READY MIXED CONCRETE ASSOCIATION (NRMCA)

NRMCA QC 3	(2015) Quality Control Manual: Section 3, Plant Certifications Checklist: Certification of Ready Mixed Concrete Production Facilities

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-03 Product Data

Curing Materials

Reinforcement

Epoxy Resin

Dowel Bars

Expansion Joint Filler

SD-04 Samples

Test Section; G

SD-05 Design Data

Mix Design Report; G

SD-06 Test Reports

Concrete Slump Tests

Concrete Uniformity

Flexural Strength

Air Content

SD-07 Certificates

Batch Tickets

NRMCA Certificate Of Conformance

SD-08 Manufacturer's Instructions

Diamond Grinding Plan

1.3 QUALITY CONTROL

1.3.1 NRMCA Certificate of Conformance

Provide a batching and mixing plant consisting of a stationary-type central mix plant, including permanent installations and portable or relocatable plants installed on stable foundations. Provide a plant designed and operated to produce concrete within the specified tolerances, with a minimum capacity of 250 cubic yards per hour. Submit NRMCA Certificate of Conformance that conforms to the requirements of NRMCA QC 3 including provisions addressing:

1. Material Storage and Handling

2. Batching Equipment

3. Central Mixer

4. Ticketing System

5. Delivery System

1.3.2 Qualifications

1.3.2.1 Laboratory Accreditation

Perform sampling and testing using an approved commercial testing laboratory or on-site facilities that are accredited in accordance with ASTM C1077. Do not start work requiring testing until the facilities have been inspected and approved. The Government will inspect all laboratories requiring validation for equipment and test procedures prior to the start of any concreting operations for conformance to ASTM C1077. Schedule and provide payment for laboratory inspections. Additional payment or a time extension due to failure to acquire the required laboratory validation is not allowed. Maintain this certification for the duration of the project.

1.3.2.2 Field Technicians

Provide field technicians meeting one of the following criteria:

a. Have at least one National Ready Mixed Concrete Association (NRMCA) certified concrete craftsman and at least one American Concrete

Institute (ACI) Flatwork Finisher Certified craftsman on site, overseeing each placement crew during all concrete placement.

b. Have no less than three NRMCA certified concrete installers and at least two American Concrete Institute (ACI) Flatwork Finisher Certified installers on site working as members of each placement crew during all concrete placement.

1.3.3 Batch Tickets

Submit batch tickets for each load of ready-mixed concrete in accordance with ASTM C94/C94M.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver concrete paving in accordance with ASTM C94/C94M.

1.5 ACCEPTANCE

1.5.1 Tolerances

Acceptance of Portland cement concrete pavement is based on compliance with the tolerances presented in Table 1. Remove and replace concrete pavement represented by the failing tests or submit repair plan for approval.

Edge Slump	85 percent less than 1/4 inch and 100 percent less than 3/8 inch.

1.5.2 Test Section

Construct a minimum 400 square feet test section to demonstrate typical joints, surface finish, texture, color, thickness, and standard of workmanship using the mixture proportions, materials, and equipment as proposed for the project. Test in accordance with requirements in FIELD QUALITY CONTROL.

When a test section does not meet one or more of the tolerances in Table 1, remove and reconstruct the test section. If the test section is acceptable, it may be incorporated into the project.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Cementitious Materials

2.1.1.1 Portland Cement

Conforming to ASTM C150/C150M, Type I or II.

2.1.1.2 Blended Cement

Provide blended cement conforming to ASTM C595/C595M, Type IP or IS, including the optional requirement for mortar expansion. Provide pozzolan added to the Type IP blend consisting of ASTM C618 Class F or Class N and that is interground with the cement clinker. Include in written statement from the manufacturer that the amount of pozzolan in the finished cement

does not vary more than plus or minus 5 mass percent of the finished cement from lot to lot or within a lot. The percentage and type of mineral admixture used in the blend are not allowed to change from that submitted for the aggregate evaluation and mixture proportioning. The requirements of paragraph Supplementary Cementitious Materials (SCM) Content do not apply to the SCM content of blended cement.

2.1.1.3 Fly Ash and Pozzolan

Conforming to ASTM C618, Type F, or N, with a loss on ignition not exceeding 3 percent. Include test results in accordance with ASTM C618.

2.1.1.4 Ultra Fine Fly Ash and Ultra Fine Pozzolan

Ultra Fine Fly Ash (UFFA) and Ultra Fine Pozzolan (UFP) conforming to ASTM C618, Class F or N, and the following additional requirements:

a. The strength activity index at 28 days of age at least 95 percent of the control specimens.

b. The average particle size not exceeding 6 microns.

c. Loss on ignition not exceeding 3 percent.

2.1.1.5 Silica Fume

Provide silica fume that conforms to ASTM C1240, including the optional limits on reactivity with cement alkalis. Provide silica fume as a dry, densified material or as a slurry. Provide the services of a manufacturer's technical representative, experienced in mixing, proportioning, placement procedures, and curing of concrete containing silica fume, at no expense to the Government. This representative is required to be present on the project prior to and during at least the first 4 days of concrete production and placement using silica fume.

2.1.1.6 Slag

Conforming to ASTM C989/C989M, Slag Cement (formerly Ground Granulated Blast Furnace Slag) Grade 100 or 120. Include test results in accordance with ASTM C989/C989M.

2.1.1.7 Supplementary Cementitious Materials (SCM) Content

Use of one of the SCMs listed below is optional, unless the SCM is required to mitigate ASR.

TABLE 2
SUPPLEMENTARY CEMENTITIOUS MATERIALS CONTENT

Supplementary Cementitious Material	Minimum Content (percent)	Maximum Content (percent)
Class N Pozzolan and Class F Fly Ash		
SiO2 + Al2O3 + Fe2O3 greater than 70 percent	25	35

TABLE 2
SUPPLEMENTARY CEMENTITIOUS MATERIALS CONTENT

Supplementary Cementitious Material	Minimum Content (percent)	Maximum Content (percent)
SiO2 + A12O3 + Fe2O3 greater than 80 percent	20	35
SiO2 + A12O3 + Fe2O3 greater than 90 percent	15	35
UFFA and UFP	7	16
GGBF Slag	40	50

2.1.2 Water

Water conforming to ASTM C1602/C1602M.

2.1.3 Aggregate

2.1.3.1 Durability

Evaluate and test all fine and coarse aggregates to be used in all concrete for durability in accordance with ASTM C88. Provide fine and coarse aggregates with a maximum of 18 percent loss when subjected to 5 cycles using Magnesium Sulfate or a maximum of 12 percent loss when subjected to 5 cycles of Sodium Sulfate.

2.1.3.2 Alkali Reactivity Test

Evaluate and test fine and coarse aggregates to be used in all concrete for alkali-aggregate reactivity. Test all size groups and sources proposed for use.

a. Evaluate the fine and coarse aggregates separately, using ASTM C1260. Reject individual aggregates with test results that indicate an expansion of greater than 0.08 percent after 28 days of immersion in 1N NaOH solution, or perform additional testing as follows: utilize the proposed low alkali portland cement, blended cement, or SCM in combination with each individual aggregate. Test in accordance with ASTM C1567. Determine the quantity that meets all the requirements of these specifications and that lowers the expansion equal to or less than 0.08 percent after 28 days of immersion in a 1N NaOH solution. Base the mixture proportioning on the highest percentage of SCM required to mitigate ASR-reactivity.

b. If any of the above options does not lower the expansion to less than 0.08 percent after 28 days of immersion in a 1N NaOH solution, reject the aggregate(s) and submit new aggregate sources for retesting. Submit the results of testing for evaluation and acceptance.

2.1.3.3 Fine Aggregates

Conforming to the quality and gradation of ASTM C33/C33M.

2.1.3.4 Coarse Aggregates

Coarse aggregate consisting of crushed or uncrushed gravel, crushed stone, or a combination thereof. Provide aggregates, as delivered to the mixers, consisting of clean, hard, uncoated particles. Wash coarse aggregate sufficient to remove dust and other coatings. Provide fine aggregate consisting of natural sand, manufactured sand, or a combination of the two, and composed of clean, hard, durable particles. Provide both coarse and fine aggregates meeting the requirements of ASTM C33/C33M.

a. Gradation: Provide coarse aggregate with a nominal maximum size of 1.5 inches. Grade and provide the individual aggregates in two or more size groups meeting the individual grading requirements of ASTM C33/C33M, Size No. 4 (1.5 to 0.75 inch) and Size No. 67 (0.75 inch to No. 4).

b. Quality: Conforming to ASTM C33/C33M, Class 4M.

2.1.4 Chemical Admixtures

2.1.4.1 Water Reducing Admixtures

Provide admixture conforming to ASTM C494/C494M: Type A, water reducing; Type B, retarding; Type C, accelerating; Type D, water-reducing and retarding; and Type E, water-reducing and accelerating admixture. Do not use calcium chloride admixtures. ASTM C494/C494M Type S specific performance admixtures and ASTM C1017/C1017M flowable admixtures are not allowed.

2.1.4.2 Air Entraining Admixture

Conforming to ASTM C260/C260M: Air-entraining.

2.1.4.3 High Range Water Reducing Admixture

ASTM C494/C494M Type F and G high range water reducing admixtures are not allowed.

2.1.5 Reinforcement

2.1.5.1 Dowel Bars

Dowel bars conforming to ASTM A615/A615M, Grade 40 for plain billet-steel bars of the size and length indicated. Remove all burrs and projections from the bars.

2.1.5.2 Tie Bars

Billet or axle steel deformed bars conforming to ASTM A615/A615M or ASTM A966/A966M Grade 40 .

2.1.5.3 Reinforcement

Deformed steel bar mats conforming to ASTM A184/A184M. Bar reinforcement conforming to ASTM A615/A615M , Grade 40 .

2.1.6 Curing Materials

Provide curing materials consisting of:

2.1.6.1 White-Burlap-Polyethylene Sheet

Conforming to ASTM C171, 0.004 inch thick white opaque polyethylene bonded to 10 oz/linear yard (40 inch) wide burlap.

2.1.6.2 Liquid Membrane-Forming Compound

Conforming to ASTM C309, white pigmented, Type 2, Class B, free of paraffin or petroleum.

2.1.6.3 Liquid Chemical Sealer-Hardener Compound

Compound consisting of magnesium fluosilicate which when mixed with water seals and hardens the surface of the concrete. Do not use on exterior slabs exposed to freezing conditions.

2.1.7 Joint Fillers and Sealants

Provide as specified in Section 32 01 19.61 SEALING OF JOINTS IN RIGID PAVEMENT.

2.1.8 Biodegradable Form Release Agent

Provide form release agent that is colorless and biodegradable. Provide product that does not bond with, stain, or adversely affect concrete surfaces and does not impair subsequent treatments of concrete surfaces. Provide form release agent with a minimum of 87 percent biobased material and does not contain diesel fuel, petroleum-based lubricating oils, waxes, or kerosene.

2.1.9 Epoxy Resin

Provide epoxy-resin materials that consist of two-component materials conforming to the requirements of ASTM C881/C881M, Class as appropriate for each application temperature to be encountered, except that in addition, the materials meet the following requirements:

a. Type IV, Grade 3, for use for embedding dowels and anchor bolts.

b. Type III, Grade as approved, for use as patching materials for complete filling of spalls and other voids and for use in preparing epoxy resin mortar.

c. Type IV, Grade 1, for use for injecting cracks.

d. Type V, Grade as approved, for bonding freshly mixed portland cement concrete or mortar or freshly mixed epoxy resin concrete or mortar to hardened concrete.

2.1.10 Joint Materials

2.1.10.1 Expansion Joint Materials

Provide preformed expansion joint filler material conforming to ASTM D1751. Provide expansion joint filler that is 3/4 inch thick, unless otherwise indicated, and provided in a single full depth piece.

2.1.10.2 Slip Joint Material

Provide slip joint material that is 1/4 inch thick expansion joint filler, unless otherwise indicated, conforming to paragraph EXPANSION JOINT MATERIAL.

2.2 MIX DESIGN

Proportion concrete mix in accordance with ACI 211.1 except as modified herein.

2.2.1 Specified Concrete Properties

2.2.1.1 Flexural Strength

Provide concrete with a minimum flexural strength of 650 psi at 28 days of age.

2.2.1.2 Air Entrainment

Provide an entrained air content of 6.0 percent.

2.2.1.3 Slump

For fixed form and hand placement, provide a maximum slump of 3 inches.

2.2.1.4 Water/Cementitious Materials Ratio

Maximum allowable water-cementitious material ratio is 0.40. The water-cementitious material ratio is based on absolute volume equivalency, where the ratio is determined using the weight of cement for a cement only mix, or using the total volume of cement plus pozzolan converted to an equivalent weight of cement by the absolute volume equivalency method described in ACI 211.1.

2.2.2 Mix Design Report

Perform trial design batches, mixture proportioning studies, testing, and include test results demonstrating that the proposed mixture proportions produce concrete of the qualities indicated. An existing mix design may be submitted if developed within the previous 12 months. Submit test results in a mix design report to include:

a. Coarse and fine aggregate gradations and plots.

b. Coarse and fine aggregate quality test results, include deleterious materials and ASR testing.

c. Mill certificates for cement and supplemental cementitious materials.

d. Certified test results for all proposed admixtures.

e. Specified flexural strength, slump, and air content.

f. Recommended proportions and volumes for proposed mixture and each of three trial water-cementitious materials ratios.

g. Individual beam breaks.

h. Flexural strength summaries and plots.

i. Historical record of test results, documenting production standard deviation (if available).

j. Narrative discussing methodology on how the mix design was developed.

2.2.3 Mix Verification

Mix verification tests may be performed by the Government. Provide quantities of cementitious materials, aggregates and admixtures as requested.

2.3 EQUIPMENT

2.3.1 Batching and Mixing

Provide truck mixers. Provide a batch plant conforming to ASTM C94/C94M and as specified. Do not weigh water or measure cumulatively with another ingredient. Batch all concrete materials in accordance with ASTM C94/C94M requirements. Verify batching, mixers, mixing time, permitted reduction of mixing time, and concrete uniformity in accordance with the requirements of ASTM C94/C94M, and document in the initial weekly QC Report.

2.3.2 Transporting Equipment

Provide transporting equipment in conformance with ASTM C94/C94M and as specified herein. Transport concrete to the paving site in rear-dump trucks, in truck mixers designed with extra large blading and rear opening specifically for low slump concrete, or in agitators. Do not permit bottom-dump trucks for delivery of concrete.

2.3.3 Delivery Equipment

When concrete transport equipment cannot operate on the paving lane, provide side-delivery transport equipment consisting of self-propelled moving conveyors to deliver concrete from the transport equipment and discharge it in front of the paver. Do not permit front-end loaders, dozers, or similar equipment to distribute the concrete.

2.3.4 Paver-Finisher

Provide a heavy-duty, self-propelled paver-finisher machine designed specifically for paving and finishing high quality pavement and capable of spreading, consolidating, and shaping the plastic concrete to the desired cross section in one pass. Equip the paver-finisher with a full width "knock-down" auger, capable of operating in both directions, which will evenly spread the fresh concrete in front of the screed or extrusion plate. Gang-mount immersion vibrators at the front of the paver on a frame equipped with suitable controls so that all vibrators can be operated at any desired depth within the slab or completely withdrawn from the concrete. Automatically control the vibrators so they will be immediately stopped as forward motion of the paver ceases. Space the immersion vibrators across the paving lane as necessary to properly consolidate the concrete, but limit the clear distance between vibrators not to exceed 30 inches, and the outside vibrators not to exceed 12 inches from the edge of the lane. Vibrators may be pneumatic, gas driven, or electric, and operated at frequencies within the concrete between 6,000

and 7,000 vibrations per minute, with an amplitude of vibration such that noticeable vibrations occur at 1.5 foot radius when the vibrator is inserted in the concrete to the depth specified. Equip the paver-finisher with a transversely oscillating screed or an extrusion plate to shape, compact, and smooth the surface.

2.3.4.1 Paver-Finisher with Fixed Forms

Equip the paver-finisher with wheels designed to ride the forms, keep it aligned with the forms, and to prevent deformation of the forms.

2.3.4.2 Slipform Paver-Finisher

Provide a track-mounted slipform paver-finisher with automatic controls and padded tracks. Electronically reference horizontal alignment to a taut wire guideline. Electronically reference vertical alignment on both sides of the paver to a taut wire guideline, to an approved laser control system, or to a ski operating on a completed lane. Do not control from a slope-adjustment control or from the underlying material.

2.3.4.3 Other Types of Finishing Equipment

Heavy duty vibratory truss screeds may be approved for use if successfully demonstrated on the test section to consolidate the slab full depth and without segregation. Clary screeds, rotating tube floats, or laser screeds will not be allowed on the project. Provide hand floats that are not less than 12 feet long and 6 inches wide and stiffened to prevent flexing and warping.

2.3.4.4 Work Bridge

Provide a self-propelled work bridge capable of spanning the paving lane and supporting the workmen without excessive deflection.

2.3.5 Texturing Equipment

Provide texturing equipment as specified below.

2.3.5.1 Fabric Drag

Clean, reasonably new burlap measuring from 3 to 10 feet long, 2 feet wider than the width of the pavement, and securely attached to a separate wheel mounted frame spanning the paving lane or to one of the other similar pieces of equipment. Select dimension of burlap drag so that at least 3 feet of the material is in contact with the pavement.

2.3.5.2 Deep Texturing Equipment

Provide texturing equipment consisting of a stiff bristled broom which will produce true, even grooves. Mount this drag in a wheeled frame spanning the paving lane and constructed to mechanically pull the drag in a straight line across the paving lane perpendicular to the centerline.

2.3.6 Curing Equipment

Provide equipment for applying membrane-forming curing compound mounted on a self-propelled frame that spans the paving lane. Constantly agitate the curing compound reservoir mechanically (not air) during operation and provide a means for completely draining the reservoir. Provide a spraying

system that consists of a mechanically powered pump which maintains constant pressure during operation, an operable pressure gauge, and either a series of spray nozzles evenly spaced across the lane to provide uniformly overlapping coverage or a single spray nozzle which is mounted on a carriage which automatically traverses the lane width at a speed correlated with the forward movement of the overall frame. Protect all spray nozzles with wind screens. Calibrate the spraying system in accordance with ASTM D2995, Method A, for the rate of application required in subpart CURING AND PROTECTION. Provide hand-operated sprayers powered by compressed air supplied by a mechanical air compressor. Immediately replace curing equipment if it fails to apply an even coating of compound at the specified rate.

2.3.7 Sawing Equipment

Provide equipment for sawing joints and for other similar sawing of concrete consisting of standard diamond-type concrete saws mounted on a wheeled chassis which can be easily guided to follow the required alignment. Provide diamond tipped blades. If demonstrated to operate properly, abrasive blades may be used. Provide spares as required to maintain the required sawing rate. Early-entry saws may be used, subject to demonstration and approval. No change to the initial sawcut depth is permitted.

2.3.8 Straightedge

Furnish one 12 foot straightedge constructed of aluminum or magnesium alloy, having blades of box or box-girder cross section with flat bottom, adequately reinforced to insure rigidity and accuracy. Provide handles for operation on the pavement.

PART 3 EXECUTION

3.1 PREPARATION FOR PAVING

3.1.1 Weather Limitations

When windy conditions during paving appear probable, have equipment and material at the paving site to provide windbreaks, shading, fogging, or other action to prevent plastic shrinkage cracking or other damaging drying of the concrete.

3.1.1.1 Inclement Weather

Do not commence placing operations when heavy rain or other damaging weather conditions appear imminent. At all times when placing concrete, maintain on-site sufficient waterproof cover and means to rapidly place it over all unhardened concrete or concrete that might be damaged by rain. Suspend placement of concrete whenever rain, high winds, or other damaging weather commences to damage the surface or texture of the placed unhardened concrete, washes cement out of the concrete, or changes the water content of the surface concrete. Immediately cover and protect all unhardened concrete from the rain or other damaging weather. Completely remove and replace any slab damaged by rain or other weather full depth, by full slab width, to the nearest original joint.

3.1.1.2 Hot Weather

Maintain required concrete temperature in accordance with ACI 305R to

prevent evaporation rate from exceeding 0.2 pound of water per square foot of exposed concrete per hour. Cool ingredients before mixing, place concrete during cooler night time hours, or use other suitable means to control concrete temperature and prevent rapid drying of newly placed concrete. Water is not allowed to be added after the initial introduction of mixing water except, when on arrival at the job site, the slump is less than specified and the water-cement ratio is less than that given as a maximum in the approved mixture. Additional water may be added to bring the slump within the specified range provided the approved water-cement ratio is not exceeded. Inject water into the head of the mixer (end opposite the discharge opening) drum under pressure, and turn the drum or blades a minimum of 30 additional revolutions at mixing speed. The addition of water to the batch at any later time is not allowed. After placement, use fog spray, apply monomolecular film, or use other suitable means to reduce the evaporation rate. Start curing when surface of fresh concrete is sufficiently hard to permit curing without damage. Cool underlying material by sprinkling lightly with water before placing concrete. Follow practices found in ACI 305R.

3.1.1.3 Prevention of Plastic Shrinkage Cracking

During weather with low humidity, and particularly with high temperature and appreciable wind, develop and institute measures to prevent plastic shrinkage cracks from developing. If plastic shrinkage cracking occurs, halt further placement of concrete until protective measures are in place to prevent further cracking. Periods of high potential for plastic shrinkage cracking can be anticipated by use of ACI 305R. In addition to the protective measures specified in the previous paragraph, the concrete placement may be further protected by erecting shades and windbreaks and by applying fog sprays of water, the addition of monomolecular films, or wet covering. Apply monomolecular films after finishing is complete, do not use in the finishing process. Immediately commence curing procedures when such water treatment is stopped.

3.1.1.4 Cold Weather

Do not place concrete when ambient temperature is below 40 degrees F or when concrete is likely to be subjected to freezing temperatures within 24 hours. When authorized, when concrete is likely to be subjected to freezing within 24 hours after placing, heat concrete materials so that temperature of concrete when deposited is between 65 and 80 degrees F. Methods of heating materials are subject to approval. Do not heat mixing water above 165 degrees F. Remove lumps of frozen material and ice from aggregates before placing aggregates in mixer. Follow practices found in ACI 306R.

3.1.2 Conditioning of Underlying Material

Verify the underlying material, upon which concrete is to be placed is clean, damp, and free from debris, waste concrete or cement, frost, ice, and standing or running water. Prior to setting forms or placement of concrete, verify the underlying material is well drained and has been satisfactorily graded by string-line controlled, automated, trimming machine and uniformly compacted in accordance with the applicable Section of these specifications. Test the surface of the underlying material to crown, elevation, and density in advance of setting forms or of concrete placement using slip-form techniques. Trim high areas to proper elevation. Fill and compact low areas to a condition similar to that of surrounding grade, or fill with concrete monolithically with the

pavement. Low areas filled with concrete are not to be cored for thickness to avoid biasing the average thickness used for evaluation and payment adjustment. Rework and compact any underlying material disturbed by construction operations to specified density immediately in front of the paver. If a slipform paver is used, continue the same underlying material under the paving lane beyond the edge of the lane a sufficient distance that is thoroughly compacted and true to grade to provide a suitable trackline for the slipform paver and firm support for the edge of the paving lane.

3.1.3 Forms

Use steel forms, except that wood forms may be used for curves having a radius of 150 feet or less, and for fillets. Forms may be built up with metal or wood, added only to the base, to provide an increase in depth of not more than 25 percent. Provide forms with the base width not less than eight-tenths of the vertical height of the form, except that for forms 8 inches or less in vertical height, provide forms with a base width not less than the vertical height of the form. Provide wood forms adequate in strength and rigidly braced for curves and fillets. Set forms on firm material cut true to grade so that each form section when placed will be firmly in contact with the underlying layer for its entire base. Do not set forms on blocks or on built-up spots of underlying material. Before placing the concrete, coat the contact surfaces of forms except existing pavement sections where bonding is required, with a non-staining mineral oil, non-staining form coating compound, biodegradable form release agent, or two coats of nitro-cellulose lacquer. When using existing pavement as a form, clean existing concrete and then coat with asphalt emulsion bondbreaker before concrete is placed. Check and correct grade elevations and alignment of the forms immediately before placing concrete.

3.1.4 Reinforcement

3.1.4.1 Dowel Bars

Install dowels with horizontal and vertical alignment plus or minus 1 inch. Except as otherwise specified, maintain location of dowels within a skew alignment of 1/4 inch over 1 foot length. Reject coatings which are perforated, cracked or otherwise damaged. While handling avoid scuffing or gouging of the coatings. Omit Dowels when the center of the dowel is located within a horizontal distance from an intersecting joint equal to or less than one-fourth of the slab thickness. Maintain dowels in position during concrete placement and curing. Before concrete placement, thoroughly grease the entire length of each dowel secured in a dowel basket or fixed form.

3.1.4.2 Tie Bars

Install bars, accurately aligned horizontally and vertically, and to the tolerances shown on the drawings, at indicated locations.

3.1.4.3 Setting Slab Reinforcement

Position reinforcement on suitable chairs prior to concrete placement. At expansion, contraction and construction joints, place the reinforcement as indicated. Clean reinforcement free of mud, oil, scale or other foreign materials. Place reinforcement accurately and wire securely. Lap splices 12 inches minimum. Maintain the bar spacing from ends and sides of slabs and joints as indicated.

3.2 MEASURING, MIXING, CONVEYING, AND PLACING CONCRETE

3.2.1 Measuring

Conform to ASTM C94/C94M.

3.2.2 Mixing

Conform to ASTM C94/C94M, except as modified herein. Begin mixing within 30 minutes after cement has been added to aggregates. When the air temperature is greater than 85 degrees F, place concrete within 60 minutes. With approval, a hydration stabilizer admixture meeting the requirements of ASTM C494/C494M Type D, may be used to extend the placement time to 90 minutes. Additional water may be added to bring slump within required limits as specified in ASTM C94/C94M, provided that the specified water-cement ratio is not exceeded.

3.2.3 Conveying

Conform to ASTM C94/C94M.

3.2.4 Placing

Do not exceed a free vertical drop of 5 feet from the point of discharge. Deposit concrete either directly from the transporting equipment or by conveyor on to the pre-wetted subgrade or subbase, unless otherwise specified. Deposit the concrete between the forms to an approximately uniform height. Place concrete continuously at a uniform rate, without damage to the grade and without unscheduled stops except for equipment failure or other emergencies. If an unscheduled stop occurs within 10 feet of a previously placed expansion joint, remove concrete back to joint, repair any damage to grade, install a construction joint and continue placing concrete only after cause of the stop has been corrected.

3.3 PAVING

Construct pavement with paving and finishing equipment utilizing fixed forms .

3.3.1 Paving Plan

Submit for approval a paving plan identifying the following items:

a. A description of the placing and protection methods proposed when concrete is to be placed in or exposed to hot, cold, or rainy weather conditions.

b. A detailed paving sequence plan and proposed paving pattern showing all planned construction joints.

c. Plan and equipment proposed to control alignment of formed or sawn joints within the specified tolerances.

3.3.2 Required Results

Operate the paver-finisher to produce a thoroughly consolidated slab throughout, true to line and grade within specified tolerances. Adjust the paver-finishing operation to produce a surface finish free of

irregularities, tears, voids of any kind, and other discontinuities, with only a minimum of paste at the surface. Do not permit multiple passes of the paver-finisher. Produce a finished surface requiring no hand finishing, other than the use of cutting straightedges, except in very infrequent instances. Do not apply water, other than true fog sprays (mist), to the concrete surface during paving and finishing.

3.3.3 Operation

When the paver is operated between or adjacent to previously constructed pavement (fill-in lanes), make provisions to prevent damage to the previously constructed pavement, including keeping the existing pavement surface free of debris, and placing rubber mats beneath the paver tracks. Operate transversely oscillating screeds and extrusion plates to overlap the existing pavement the minimum possible, but in no case more than 8 inches.

3.3.4 Consolidation

Immediately after spreading concrete, consolidate full depth with internal type vibrating equipment along the boundaries of all slabs regardless of slab thickness, and interior of all concrete slabs. For pavements less than 10 inches thick, operate vibrators at mid-depth parallel with or at a slight angle to the base course. For thicker pavements, angle vibrators toward the vertical, with vibrator tip preferably about 2 inches above the base course, and top of vibrator a few inches below pavement surface. Automatically control the vibrators or tamping units in front of the paver so that they stop immediately as forward motion ceases. Limit duration of vibration to that necessary to produce consolidation of concrete. Do not permit excessive vibration. Vibrate concrete in small, odd-shaped slabs or in locations inaccessible to the paver mounted vibration equipment with a hand-operated immersion vibrator operated from a bridge spanning the area. Do not operate vibrators at one location for more than 15 seconds. Do not use vibrators to transport or spread the concrete.

3.3.5 Fixed Form Paving

Spread and strike off concrete with with the paver. Shape the concrete to the specified and indicated cross section in one pass, and finish the surface and edges so that only a very minimum amount of hand finishing is required. Use single spud hand vibrators to consolidate the concrete adjacent to fixed forms as required to achieve a void-free formed edge. Do not allow vibrators to contact reinforcement, forms, or the grade during vibration.

3.4 JOINTS

3.4.1 Contraction Joints

Hold dowels in longitudinal and transverse contraction joints within the paving lane securely in place by means of rigid metal basket assemblies. Weld the dowels to the assembly or hold firmly by mechanical locking arrangements that will prevent them from becoming distorted during paving operations. Anchor the basket assemblies securely in the proper location.

3.4.2 Construction Joints - Fixed Form Paving

Install dowels by the bonded-in-place method, supported by means of devices fastened to the forms. Do not permit installation by removing and

replacing in preformed holes.

3.4.3 Dowels Installed In Hardened Concrete

Install by bonding the dowels into holes drilled into the hardened concrete. Drill holes into the hardened concrete approximately 1/8 inch greater in diameter than the dowels. Bond the dowels in the drilled holes using epoxy resin injected at the back of the hole before installing the dowel and extruded to the collar during insertion of the dowel so as to completely fill the void around the dowel. Application by buttering the dowel is not permitted. Hold the dowels in alignment at the collar of the hole, after insertion and before the epoxy resin hardens, by means of a suitable metal or plastic collar fitted around the dowel. Check the vertical alignment of the dowels by placing the straightedge on the surface of the pavement over the top of the dowel and measuring the vertical distance between the straightedge and the beginning and ending point of the exposed part of the dowel. Where tie bars are required in longitudinal construction joints of slipform pavement, install bent tie bars at the paver, in front of the transverse screed or extrusion plate. If tie bars are required, construct a standard keyway and install the bent tie bars into the plastic concrete through a 26 gauge thick metal keyway liner. Do not install tie bars in preformed holes. Protect the keyway liner and maintain in place and become part of the joint. Before placement of the adjoining paving lane, straighten the tie bars, without spalling the concrete around the bar.

3.5 FINISHING CONCRETE

Start finishing operations immediately after placement of concrete. Use finishing machine, except hand finishing may be used in emergencies and for concrete slabs in inaccessible locations or of such shapes or sizes that machine finishing is impracticable. Immediately halt any operations which produce more than 1/8 inch of mortar-rich surface (defined as deficient in plus U.S. No. 4 sieve size aggregate) and modify the equipment, mixture, or procedures. Finish pavement surface on both sides of a joint to the same grade. Finish formed joints from a securely supported transverse bridge. Provide hand finishing equipment for use at all times.

3.5.1 Machine Finishing

Strike off and screed concrete to the required slope and cross-section by a power-driven transverse finishing machine. A transverse rotating tube or pipe is not permitted. Maintain elevation of concrete such that, when consolidated and finished, pavement surface will be adequately consolidated and at the required grade. Equip finishing machine with a screed which is readily and accurately adjustable for changes in pavement slope and compensation for wear and other causes. Do not permit excessive operation over an area, which will result in an excess of mortar and water being brought to the surface.

3.5.1.1 Equipment Operation

Maintain the travel of machine on the forms without lifting, wobbling, or other variation of the machine which tend to affect the precision of concrete finish. Keep the tops of the forms clean by a device attached to the machine. Maintain a uniform ridge of concrete ahead of the front screed for its entire length.

3.5.1.2 Joint Finish

Before concrete is hardened, correct edge slump of pavement, exclusive of edge rounding, in excess of 0.25 inches. Finish concrete surface on each side of construction joints to the same plane, and correct deviations before newly placed concrete has hardened.

3.5.1.3 Hand Finishing

Strike-off and screed surface of concrete to elevations slightly above finish grade so that when concrete is consolidated and finished, the pavement surface is at the indicated elevation. Vibrate entire surface until required compaction and reduction of surface voids is secured with a strike-off template. After initial finishing, further smooth and consolidate concrete by means of hand-operated longitudinal floats.

3.5.2 Texturing

Before the surface sheen has disappeared and before the concrete hardens, provide a texture to the surface of the pavement as described herein. After curing is complete, thoroughly broom all textured surfaces to remove all debris. Finish the concrete in areas of recesses for tie-down anchors, lighting fixtures, and other outlets in the pavement to provide a surface of the same texture as the surrounding area.

3.5.2.1 Burlap Drag Finish

3.5.2.2 Brooming

3.5.3 Edging

At the time the concrete has attained a degree of hardness suitable for edging, carefully finish slab edges, including edges at formed joints, with an edge having a maximum radius of 1/8 inch. Clean by removing loose fragments and soupy mortar from corners or edges of slabs which have crumbled and areas which lack sufficient mortar for proper finishing. Refill voids solidly with a mixture of suitable proportions and consistency and refinish. Remove unnecessary tool marks and edges. Smooth remaining edges true to line.

3.6 CURING AND PROTECTION

Protect concrete adequately from injurious action by sun, rain, flowing water, mechanical injury, tire marks and oil stains, and do not allow it to dry out from the time it is placed until the expiration of the minimum curing periods specified herein. Do not use membrane-forming compound on surfaces where its appearance would be objectionable, on surfaces to be painted, where coverings are to be bonded to concrete, or on concrete to which other concrete is to be bonded.

3.6.1 Moist Curing

Maintain concrete to be moist-cured continuously wet for the entire curing period, or until curing compound is applied, commencing immediately after finishing. If forms are removed before the end of the curing period, provide curing on unformed surfaces, using suitable materials. Cure surfaces by ponding, by continuous sprinkling, by continuously saturated burlap or cotton mats, or by continuously saturated plastic coated burlap. Provide burlap and mats that are clean and free from any

contamination and completely saturated before being placed on the concrete. Lap sheets to provide full coverage. Provide an approved work system to ensure that moist curing is continuous 24 hours per day and that the entire surface is wet.

3.6.2 White-Burlap-Polyethylene Sheet

Wet entire exposed surface thoroughly with a fine spray of water, saturate burlap but do not have excessive water dripping off the burlap and then cover concrete with White-Burlap-Polyethylene Sheet, burlap side down. Lay sheets directly on concrete surface and overlap 12 inches. Make sheeting not less than 18 inches wider than concrete surface to be cured, and weight down on the edges and over the transverse laps to form closed joints. Repair or replace sheets when damaged during curing. Check daily to assure burlap has not lost all moisture. If moisture evaporates, resaturate burlap and re-place on pavement (limit re-saturation and re-placing to less than 10 minutes per sheet). Leave sheeting on concrete surface to be cured for at least 7 days.

3.6.3 Liquid Membrane-Forming Compound Curing

Apply compound immediately after surface loses its water sheen and has a dull appearance and before joints are sawed. Agitate curing compound thoroughly by mechanical means during use and apply uniformly in a two-coat continuous operation by suitable power-spraying equipment. Apply a total coverage for the two coats at least one gallon of undiluted compound per 200 square feet to produce a uniform, continuous, coherent film that will not check, crack, or peel and free from pinholes or other imperfections. The application of curing compound by hand-operated, mechanical powered pressure sprayers is permitted only on odd widths or shapes of slabs and on concrete surfaces exposed by the removal of forms. When the application is made by hand-operated sprayers, apply a second coat in a direction approximately at right angles to the direction of the first coat. Apply an additional coat of compound immediately to areas where film is defective. Respray concrete surfaces that are subject to heavy rainfall within 3 hours after curing compound has been applied in the same manner.

3.6.4 Protection of Treated Surfaces

After the initial saw cut is complete and the slurry has been removed, respray the area with curing compound or restore the white burlap polyethylene sheet to maintain a continuous curing environment in the area of the sawn joints. Keep concrete surfaces to which liquid membrane-forming compounds have been applied free from vehicular traffic and other sources of abrasion for not less than 72 hours. Foot traffic is allowed after 24 hours for inspection purposes. Maintain continuity of coating for entire curing period and repair damage to coating immediately.

3.7 FIELD QUALITY CONTROL

3.7.1 Sampling

Collect samples of fresh concrete in accordance with ASTM C172/C172M during each working day as required to perform tests specified herein. Make test specimens in accordance with ASTM C31/C31M.

3.7.2 Consistency Tests

Perform concrete slump tests in accordance with ASTM C143/C143M. Take samples for slump determination from concrete during placement. Perform tests at the beginning of a concrete placement operation and for each batch (minimum) or every 20 cubic yards (maximum) of concrete to ensure that specification requirements are met. In addition, perform tests each time test beams are made.

3.7.3 Flexural Strength Tests

Test for flexural strength in accordance with ASTM C78/C78M. Fabricate and cure four test specimens in accordance with ASTM C31/C31M for each set of tests. Test two specimens at 7 days, and the other two at 28 days. Concrete strength will be considered satisfactory when the minimum of the 28-day test results equals or exceeds the specified 28-day flexural strength, and no individual strength test is less than the tolerance indicated on Table 1. If the ratio of the 7-day strength test to the specified 28-day strength is less than 65 percent, make necessary adjustments for conformance. Fabricate, cure and test a minimum of one set of four beams for each shift of concrete placement. Remove concrete which is determined to be defective, based on the strength acceptance criteria therein, and replace with acceptable concrete.

3.7.4 Air Content Tests

Test air-entrained concrete for air content at the same frequency as specified for slump tests. Determine percentage of air in accordance with ASTM C231/C231M on samples taken during placement of concrete in forms.

3.7.5 Surface Testing

Use the profilograph method for all longitudinal testing, except for paving lanes less than 200 feet in length. Use the straightedge method for transverse testing, for longitudinal testing where the length of each pavement lane is less than 200 feet, and at the ends of the paving limits for the project. Smoothness requirements do not apply over crowns, drainage structures, or similar penetrations. Maintain detailed notes of the testing results and submit a copy to the Government after each day's testing.

3.7.5.1 Straightedge Testing Method

Test the surface of the pavement with the straightedge to identify all surface irregularities exceeding the tolerances specified in Table 1. Test the entire area of the pavement in both a longitudinal and a transverse direction on parallel lines approximately 15 feet apart. Hold the straightedge in contact with the surface and move ahead one-half the length of the straightedge for each successive measurement. Determine the amount of surface irregularity by placing the straightedge on the pavement surface and allowing it to rest upon the two highest spots covered by its length and measuring the maximum gap between the straightedge and the pavement surface, in the area between these two high points.

3.7.5.2 Profilograph Testing Method

Perform profilograph testing using approved California profilograph and procedures described in ASTM E1274. Utilize electronic recording and automatic computerized reduction of data equipment to indicate

"must-grind" bumps and the Profile Index for each 0.1 mile segment of the day's paving. Accommodate grade breaks on parking lots by breaking the profile segment into short sections and repositioning the blanking band on each section. Provide the "blanking band" of 0.2 inch wide and the "bump template" span 1 inch with an offset of 0.4 inch. Count the profilograph testing of the last 30 feet of a paving lane in the longitudinal direction from each day's paving operation on the following day's continuation lane. Compute the profile index for each pass of the profilograph (3 per lane) in each 0.1 mile segment. The profile index for each segment is the average of the profile indices for each pass in each segment. Scale and proportion profilographs of unequal lengths to an equivalent 0.1 mile as outlined in the ASTM E1274. Submit a copy of the reduced tapes to the Government at the end of each day's testing.

3.7.5.3 "Bumps" (Must Grind Areas)

Reduce any bumps ("must grind" areas) shown on the profilograph trace which exceed 0.4 inch in height by diamond grinding in accordance with subparagraph Diamond Grinding until they do not exceed 0.3 inch when retested. Taper such diamond grinding in all directions to provide smooth transitions to areas not requiring diamond grinding.

3.7.5.4 Diamond Grinding

Those performing diamond grinding are required to have a minimum of three years experience in diamond grinding of rigid concrete pavements. In areas not meeting the specified limits for surface smoothness and plan grade, reduce high areas to attain the required smoothness and grade, except as depth is limited below. Reduce high areas by diamond grinding the hardened concrete with an approved equipment after the concrete is at a minimum age of 14 days. Perform diamond grinding by sawing with an industrial diamond abrasive which is impregnated in the saw blades. Assemble the saw blades in a cutting head mounted on a machine designed specifically for diamond grinding that produces the required texture and smoothness level without damage to the concrete pavement or joint faces. Provide diamond grinding equipment with saw blades that are 1/8-inch wide, a minimum of 60 blades per 12 inches of cutting head width, and capable of cutting a path a minimum of 3 ft wide. Diamond grinding equipment that causes ravels, aggregate fractures, spalls or disturbance to the joints is not permitted. The maximum area corrected by diamond grinding the surface of the hardened concrete is 10 percent of the total area of a day's production. The maximum depth of diamond grinding is 1/4 inch. Provide diamond grinding machine equipped to flush and vacuum the pavement surface. Dispose of all debris from diamond grinding operations off Government property. Prior to diamond grinding, submit a Diamond Grinding Plan for review and approval. At a minimum, include the daily reports for the deficient areas, the location and extent of deficiencies, corrective actions, and equipment. Remove and replace all pavement areas requiring plan grade or surface smoothness corrections in excess of the limits specified in Table 1. All areas in which diamond grinding has been performed are subject to the thickness tolerances specified in Table 1.

3.7.6 Plan Grade Testing and Conformance

Within 5 days after each day's paving, test the finished surface of the pavement area by running lines of levels at intervals corresponding with every longitudinal and transverse joint to determine the elevation at each joint intersection. Record the results of this survey and submit a copy to the Government at the completion of the survey.

3.7.7 Edge Slump

Test the pavement surface to determine edge slump immediately after the concrete has hardened sufficiently to permit walking thereon. Perform testing with a minimum 12 foot straightedge to reveal irregularities exceeding the edge slump tolerance specified in Table 1. Determine the vertical edge slump at each free edge of each slipformed paving lane constructed. Place the straightedge transverse to the direction of paving and the end of the straightedge located at the edge of the paving lane. Record measurements at 5 to 10 foot spacings, as directed, commencing at the header where paving was started. Initially record measurements at 5 foot intervals in each lane. When no deficiencies are present after 5 measurements, the interval may be increased. The maximum interval is 10 feet. When any deficiencies exist, return the interval to 5 feet. In addition to the transverse edge slump determination above, at the same time, record the longitudinal surface smoothness of the joint on a continuous line 1 inch back from the joint line using the minimum 12 foot straightedge advanced one-half its length for each reading. Perform other tests of the exposed joint face to ensure that a uniform, true vertical joint face is attained. Properly reference all recorded measurements in accordance with paving lane identification and stationing, and submit a report within 24 hours after measurement is made. Identify areas requiring replacement within the report.

3.7.8 Test for Pavement Thickness

Take full depth cores of 4 inch diameter of concrete pavement every 5000 square feet in accordance with ASTM C42/C42M. Measure thickness in accordance with ASTM C1542/C1542M. Record and submit testing, inspection, and evaluation of each core for surface paste, uniformity of aggregate distribution, segregation, voids, cracks, and depth of reinforcement or dowel (if present). Moisten the core with water to visibly expose the aggregate and take a minimum of three photographs of the sides of the core, rotating the core approximately 120 degrees between photographs. Include a ruler for scale in the photographs. Submit plan view of location for each core.

3.7.9 Reinforcement

Inspect reinforcement prior to installation to verify it is free of loose flaky rust, loose scale, oil, mud, or other objectionable material.

3.7.10 Dowels

Inspect dowel placement prior to placing concrete to verify that dowels are of the size indicated, and are spaced, aligned and painted and oiled as specified. Do not permit dowels to exceed the tolerances shown in paragraph: DOWEL BARS.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 32 16 19

CONCRETE CURBS, GUTTERS AND SIDEWALKS
05/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 182	(2005; R 2017) Standard Specification for Burlap Cloth Made from Jute or Kenaf and Cotton Mats

ASTM INTERNATIONAL (ASTM)

ASTM A615/A615M	(2022) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A1064/A1064M	(2024) Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete
ASTM C31/C31M	(2022) Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C143/C143M	(2020) Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C171	(2020) Standard Specification for Sheet Materials for Curing Concrete
ASTM C172/C172M	(2017) Standard Practice for Sampling Freshly Mixed Concrete
ASTM C173/C173M	(2016) Standard Test Method for Air Content of Freshly Mixed Concrete by the Volumetric Method
ASTM C231/C231M	(2022) Standard Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method
ASTM C309	(2019) Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C920	(2018; R 2024) Standard Specification for Elastomeric Joint Sealants

ASTM D1751	(2018) Standard Specification for Preformed Expansion Joint Filler for Concrete Paving and Structural Construction (Nonextruding and Resilient Bituminous Types)
ASTM D1752	(2018) Standard Specification for Preformed Sponge Rubber, Cork and Recycled PVC Expansion Joint Fillers for Concrete Paving and Structural Construction
ASTM D5893/D5893M	(2016) Standard Specification for Cold Applied, Single Component, Chemically Curing Silicone Joint Sealant for Portland Cement Concrete Pavements

INTERNATIONAL CODE COUNCIL (ICC)

ICC A117.1	(2017) Standard And Commentary Accessible and Usable Buildings and Facilities

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-03 Product Data

Concrete

SD-06 Test Reports

Field Quality Control

1.3 EQUIPMENT, TOOLS, AND MACHINES

1.3.1 General Requirements

Plant, equipment, machines, and tools used in the work will be subject to approval and must be maintained in a satisfactory working condition at all times. Use equipment capable of producing the required product, meeting grade controls, thickness control and smoothness requirements as specified. Discontinue using equipment that produces unsatisfactory results. Allow the Contracting Officer access at all times to the plant and equipment to ensure proper operation and compliance with specifications.

1.3.2 Slip Form Equipment

Slip form paver or curb forming machines, will be approved based on trial use on the job and must be self-propelled, automatically controlled, crawler mounted, and capable of spreading, consolidating, and shaping the plastic concrete to the desired cross section in one pass.

1.4 ENVIRONMENTAL REQUIREMENTS

1.4.1 Placing During Cold Weather

Do not place concrete when the air temperature reaches 40 degrees F and is falling, or is already below that point. Placement may begin when the air temperature reaches 35 degrees F and is rising, or is already above 40 degrees F. Make provisions to protect the concrete from freezing during the specified curing period. If necessary to place concrete when the temperature of the air, aggregates, or water is below 35 degrees F, placement and protection must be approved in writing. Approval will be contingent upon full conformance with the following provisions. Prepare and protect the underlying material so that it is entirely free of frost when the concrete is deposited. Heat mixing water and aggregates as necessary to result in the temperature of the in-place concrete being between 50 and 85 degrees F. Methods and equipment for heating must be approved. Use only aggregates that are free of ice, snow, and frozen lumps before entering the mixer. Provide covering or other means as needed to maintain the concrete at a temperature of at least 50 degrees F for not less than 72 hours after placing, and at a temperature above freezing for the remainder of the curing period.

1.4.2 Placing During Warm Weather

The temperature of the concrete as placed must not exceed 85 degrees F except where an approved retarder is used. Cool the mixing water and aggregates as necessary to maintain a satisfactory placing temperature. The placing temperature must not exceed 95 degrees F at any time.

PART 2 PRODUCTS

2.1 CONCRETE

Concrete must have a minimum compressive strength of 3500 psi at 28 days. Size of aggregate must not exceed 1-1/2 inches. Submit copies of certified delivery tickets for all concrete used in the construction.

2.1.1 Air Content

Use concrete mixtures that have an air content by volume of concrete of 5 to 7 percent, based on measurements made immediately after discharge from the mixer.

2.1.2 Slump

Use concrete with a slump of 3 inches plus or minus 1 inch for hand placed concrete or 1 inch plus or minus 1/2 inch for slipformed concrete as determined in accordance with ASTM C143/C143M.

2.1.3 Reinforcement Steel

Use reinforcement bars conforming to ASTM A615/A615M. Use wire mesh reinforcement conforming to ASTM A1064/A1064M.

2.2 CONCRETE CURING MATERIALS

2.2.1 Impervious Sheet Materials

Use impervious sheet materials conforming to ASTM C171, type optional,

except that polyethylene film, if used, must be white opaque.

2.2.2 Burlap

Use burlap conforming to AASHTO M 182.

2.2.3 White Pigmented Membrane-Forming Curing Compound

Use white pigmented membrane-forming curing compound conforming to ASTM C309, Type 2.

2.3 CONCRETE PROTECTION MATERIALS

Use concrete protection materials consisting of a linseed oil mixture of equal parts, by volume, of linseed oil and either mineral spirits, naphtha, or turpentine. At the option of the Contractor, commercially prepared linseed oil mixtures, formulated specifically for application to concrete to provide protection against the action of deicing chemicals may be used, except that emulsified mixtures are not acceptable.

2.4 JOINT FILLER STRIPS

2.4.1 Contraction Joint Filler for Curb and Gutter

Use hard-pressed fiberboard contraction joint filler for curb and gutter.

2.4.2 Expansion Joint Filler, Premolded

Onless otherwise indicated, use 1/2 inch thick premolded expansion joint filler conforming to ASTM D1751 or ASTM D1752.

2.5 JOINT SEALANTS

Use cold-applied joint sealant conforming to ASTM C920 or ASTM D5893/D5893M.

2.6 FORM WORK

Design and construct form work to ensure that the finished concrete will conform accurately to the indicated dimensions, lines, and elevations, and within the tolerances specified. Use wood or steel forms that are straight and of sufficient strength to resist springing during depositing and consolidating concrete.

2.6.1 Wood Forms

Use forms that are surfaced plank, 2 inches nominal thickness, straight and free from warp, twist, loose knots, splits or other defects. Use forms with a nominal length of 10 feet. Radius bends may be formed with 3/4 inch boards, laminated to the required thickness.

2.6.2 Steel Forms

Use channel-formed sections with a flat top surface and welded braces at each end and at not less than two intermediate points. Use forms with interlocking and self-aligning ends. Provide flexible forms for radius forming, corner forms, form spreaders, and fillers as needed. Use forms with a nominal length of 10 feet and that have a minimum of 3 welded stake pockets per form. Use stake pins consisting of solid steel rods with chamfered heads and pointed tips designed for use with steel forms.

2.6.3 Sidewalk Forms

Use sidewalk forms that are of a height equal to the full depth of the finished sidewalk.

2.6.4 Curb and Gutter Forms

Use curb and gutter outside forms that have a height equal to the full depth of the curb or gutter. Use rigid forms for curb returns, except that benders or thin plank forms may be used for curb or curb returns with a radius of 10 feet or more, where grade changes occur in the return, or where the central angle is such that a rigid form with a central angle of 90 degrees cannot be used. Back forms for curb returns may be made of 1-1/2 inch benders, for the full height of the curb, cleated together. In lieu of inside forms for curbs, a curb "mule" may be used for forming and finishing this surface, provided the results are approved.

2.7 Detectable Warning System

Detectable Warning Systems shown on the Contract plans are to meet requirements of ICC A117.1 - Section 705.

PART 3 EXECUTION

3.1 SUBGRADE PREPARATION

Construct subgrade to the specified grade and cross section prior to concrete placement.

3.1.1 Sidewalk Subgrade

Test the subgrade for grade and cross section with a template extending the full width of the sidewalk and supported between side forms.

3.1.2 Curb and Gutter Subgrade

Place and compact the subgrade in accordance with Section 32 11 23 AGGREGATE BASE COURSE FOR FLEXIBLE PAVING. Test the subgrade for grade and cross section by means of a template extending the full width of the curb and gutter. Use subgrade materials equal in bearing quality to the subgrade under the adjacent pavement.

3.1.3 Maintenance of Subgrade

Maintain subgrade in a smooth, compacted condition in conformity with the required section and established grade until the concrete is placed. The subgrade must be in a moist condition when concrete is placed. Prepare and protect subgrade so that it is free from frost when the concrete is deposited.

3.2 FORM SETTING

Set forms to the indicated alignment, grade and dimensions. Hold forms rigidly in place by a minimum of 3 stakes per form placed at intervals not to exceed 4 feet. Use additional stakes and braces at corners, deep sections, and radius bends, as required. Use clamps, spreaders, and braces where required to ensure rigidity in the forms. Remove forms in a manner that will not injure the concrete. Do not use bars or heavy tools

against the concrete when removing the forms. Promptly and satisfactorily repair concrete found to be defective after form removal. Clean forms and coat with form oil or biodegradable form release agent each time before concrete is placed. Wood forms may, instead, be thoroughly wetted with water before concrete is placed, except that with probable freezing temperatures, oiling is mandatory.

3.2.1 Sidewalks

Set forms for sidewalks with the upper edge true to line and grade with an allowable tolerance of 1/8 inch in any 10 foot long section. After forms are set, grade and alignment must be checked with a 10 foot straightedge. Sidewalks must have a transverse slope as indicated Do not remove side forms less than 12 hours after finishing has been completed.

3.2.2 Curbs and Gutters

Remove forms used along the front of the curb not less than 2 hours nor more than 6 hours after the concrete has been placed. Do not remove forms used along the back of curb until the face and top of the curb have been finished, as specified for concrete finishing. Do not remove gutter forms while the concrete is sufficiently plastic to slump in any direction.

3.3 SIDEWALK CONCRETE PLACEMENT AND FINISHING

3.3.1 Formed Sidewalks

Place concrete in the forms in one layer. When consolidated and finished, the sidewalks must be of the thickness indicated. Use a strike-off guided by side forms after concrete has been placed in the forms to bring the surface to proper section to be compacted. Consolidate concrete by tamping and spading or with an approved vibrator. Finish the surface to grade with a strike off.

3.3.2 Concrete Finishing

After straightedging, when most of the water sheen has disappeared, and just before the concrete hardens, finish the surface with a wood or magnesium float or darby to a smooth and uniformly fine granular or sandy texture free of waves, irregularities, or tool marks. Produce a scored surface by brooming with a fiber-bristle brush in a direction transverse to that of the traffic, followed by edging.

3.3.3 Edge and Joint Finishing

Finish all slab edges, including those at formed joints, with an edger having a radius of 1/8 inch. Edge transverse joints before brooming. Eliminate the flat surface left by the surface face of the edger with brooming. Clean and solidly fill corners and edges which have crumbled and areas which lack sufficient mortar for proper finishing with a properly proportioned mortar mixture and then finish.

3.3.4 Surface and Thickness Tolerances

Finished surfaces must not vary more than 5/16 inch from the testing edge of a 10-foot straightedge. Permissible deficiency in section thickness will be up to 1/4 inch.

3.4 CURB AND GUTTER CONCRETE PLACEMENT AND FINISHING

3.4.1 Formed Curb and Gutter

Place concrete to the required section in a single lift. Consolidate concrete using approved mechanical vibrators. Curve shaped gutters must be finished with a standard curb "mule".

3.4.2 Curb and Gutter Finishing

Approved slipformed curb and gutter machines may be used in lieu of hand placement.

3.4.3 Concrete Finishing

Float and finish exposed surfaces with a smooth wood float until true to grade and section and uniform in texture. Brush floated surfaces with a fine-hair brush using longitudinal strokes. Round the edges of the gutter and top of the curb with an edging tool to a radius of 1/2 inch. Immediately after removing the front curb form, rub the face of the curb with a wood or concrete rubbing block and water until blemishes, form marks, and tool marks have been removed. Brush the front curb surface, while still wet, in the same manner as the gutter and curb top. Finish the top surface of gutter and entrance to grade with a wood float.

3.4.4 Joint Finishing

Finish curb edges at formed joints as indicated.

3.4.5 Surface and Thickness Tolerances

Finished surfaces must not vary more than 1/4 inch from the testing edge of a 10-foot straightedge. Permissible deficiency in section thickness will be up to 1/4 inch.

3.5 SIDEWALK JOINTS

Construct sidewalk joints to divide the surface into rectangular areas. Space transverse contraction joints at a distance equal to the sidewalk width or 5 feet on centers, whichever is less, and continuous across the slab. Construct longitudinal contraction joints along the centerline of all sidewalks 10 feet or more in width. Construct transverse expansion joints at sidewalk returns and opposite expansion joints in adjoining curbs. Where the sidewalk is not in contact with the curb, install transverse expansion joints as indicated. Form expansion joints around structures and features which project through or into the sidewalk pavement, using joint filler of the type, thickness, and width indicated. Expansion joints are not required between sidewalks and curb that abut the sidewalk longitudinally.

3.5.1 Sidewalk Contraction Joints

Form contraction joints in the fresh concrete by cutting a groove in the top portion of the slab to a depth of at least one-fourth of the sidewalk slab thickness. Unless otherwise approved or indicated, either use a jointer to cut the groove or saw a groove in the hardened concrete with a power-driven saw. Construct sawed joints by sawing a groove in the concrete with a 1/8 inch blade. Provide an ample supply of saw blades on the jobsite before concrete placement is started. Provide at least one

standby sawing unit in good working order at the jobsite at all times during the sawing operations.

3.5.2 Sidewalk Expansion Joints

Form expansion joints using 1/2 inch joint filler strips. Joint filler in expansion joints surrounding structures and features within the sidewalk may consist of preformed filler material conforming to ASTM D1752 or building paper. Hold joint filler in place with steel pins or other devices to prevent warping of the filler during floating and finishing. Immediately after finishing operations are completed, round joint edges using an edging tool having a radius of 1/8 inch. Remove any concrete over the joint filler. At the end of the curing period, clean the top of expansion joints and fill with cold-applied joint sealant. Use joint sealant that is gray or stone in color. Thoroughly clean the joint opening before the sealing material is placed. Do not spill sealing material on exposed surfaces of the concrete. Apply joint sealing material only when the concrete at the joint is surface dry and atmospheric and concrete temperatures are above 50 degrees F. Immediately remove any excess material on exposed surfaces of the concrete and clean the concrete surfaces.

3.5.3 Reinforcement Steel Placement

Accurately and securely fasten reinforcement steel in place with suitable supports and ties before the concrete is placed.

3.6 CURB AND GUTTER JOINTS

Construct curb and gutter joints at right angles to the line of curb and gutter.

3.6.1 Contraction Joints

Construct contraction joints directly opposite contraction joints in abutting portland cement concrete pavements and spaced so that monolithic sections between curb returns will not be less than 5 feet nor greater than 15 feet in length.

a. Construct contraction joints (except for slip forming) by means of 1/8 inch thick separators and of a section conforming to the cross section of the curb and gutter. Remove separators as soon as practicable after concrete has set sufficiently to preserve the width and shape of the joint and prior to finishing.

b. When slip forming is used, cut the contraction joints in the top portion of the gutter/curb hardened concrete in a continuous cut across the curb and gutter, using a power-driven saw. Cut the contraction joint to a depth of at least one-fourth of the gutter/curb depth using a 1/8 inch saw blade.

3.6.2 Expansion Joints

Form expansion joints by means of preformed expansion joint filler material cut and shaped to the cross section of curb and gutter. Construct expansion joints in curb and gutter directly opposite expansion joints of abutting portland cement concrete pavement using the same type and thickness of joints as joints in the pavement. Where curb and gutter do not abut portland cement concrete pavement, provide expansion joints at

least 1/2 inch in width at intervals not less than 30 feet nor greater than 120 feet. Seal expansion joints immediately following curing of the concrete or as soon thereafter as weather conditions permit. Seal expansion joints and the top 1 inch depth of curb and gutter contraction-joints with joint sealant. Thoroughly clean the joint opening before the sealing material is placed. Do not spill sealing material on exposed surfaces of the concrete. Concrete at the joint must be surface dry and atmospheric and concrete temperatures must be above 50 degrees F at the time of application of joint sealing material. Immediately remove excess material on exposed surfaces of the concrete and clean concrete surfaces.

3.7 CURING AND PROTECTION

3.7.1 General Requirements

Protect concrete against loss of moisture and rapid temperature changes for at least 7 days from the beginning of the curing operation. Protect unhardened concrete from rain and flowing water. All equipment needed for adequate curing and protection of the concrete must be on hand and ready for use before actual concrete placement begins. Protect concrete as necessary to prevent cracking of the pavement due to temperature changes during the curing period.

3.7.1.1 Mat Method

Cover the entire exposed surface with two or more layers of burlap. Overlap mats at least 6 inches. Thoroughly wet the mat with water prior to placing on concrete surface and keep the mat continuously in a saturated condition and in intimate contact with concrete for not less than 7 days.

3.7.1.2 Impervious Sheeting Method

Wet the entire exposed surface with a fine spray of water and then cover with impervious sheeting material. Lay sheets directly on the concrete surface with the light-colored side up and overlapped 12 inches when a continuous sheet is not used. Use sheeting that is not less than 18-inches wider than the concrete surface to be cured. Secure sheeting using heavy wood planks or a bank of moist earth placed along edges and laps in the sheets. Satisfactorily repair or replace sheets that are torn or otherwise damaged during curing. Sheeting must remain on the concrete surface to be cured for not less than 7 days.

3.7.1.3 Membrane Curing Method

Apply a uniform coating of white-pigmented membrane-curing compound to the entire exposed surface of the concrete as soon after finishing as the free water has disappeared from the finished surface. Coat formed surfaces immediately after the forms are removed and in no case longer than 1 hour after the removal of forms. Do not allow concrete surface to dry before application of the membrane. If drying has occurred, moisten the surface of the concrete with a fine spray of water and apply the curing compound as soon as the free water disappears. Apply curing compound in two coats by hand-operated pressure sprayers at a coverage of approximately 200 square feet/gallon for the total of both coats. Apply the second coat in a direction approximately at right angles to the direction of application of the first coat. The compound must form a uniform, continuous, coherent film that will not check, crack, or peel and must be free from pinholes or

other imperfections. If pinholes, abrasion, or other discontinuities exist, apply an additional coat to the affected areas within 30 minutes. Respray concrete surfaces that are subjected to heavy rainfall within 3 hours after the curing compound has been applied by the method and at the coverage specified above. Respray areas where the curing compound is damaged by subsequent construction operations within the curing period. Take precautions necessary to ensure that the concrete is properly cured at sawed joints, and that no curing compound enters the joints. Tightly seal the top of the joint opening and the joint groove at exposed edges before the concrete in the region of the joint is resprayed with curing compound. Use a method used for sealing the joint groove that prevents loss of moisture from the joint during the entire specified curing period. Provide approved standby facilities for curing concrete pavement at a location accessible to the jobsite for use in the event of mechanical failure of the spraying equipment or other conditions that might prevent correct application of the membrane-curing compound at the proper time. Adequately protect concrete surfaces to which membrane-curing compounds have been applied during the entire curing period from pedestrian and vehicular traffic, except as required for joint-sawing operations and surface tests, and from other possible damage to the continuity of the membrane.

3.7.2 Backfilling

After curing, remove debris and backfill, grade, and compact the area adjoining the concrete to conform to the surrounding area in accordance with lines and grades indicated.

3.7.3 Protection

Protect completed concrete from damage until accepted. Repair damaged concrete and clean concrete discolored during construction. Remove and reconstruct concrete that is damaged for the entire length between regularly scheduled joints. Refinishing the damaged portion will not be acceptable. Dispose of removed material as directed.

3.7.4 Protective Coating

Apply a protective coating of linseed oil mixture to the exposed-to-view concrete surface after the curing period, if concrete will be exposed to de-icing chemicals within 6 weeks after placement. Moist cure concrete to receive a protective coating.

3.7.4.1 Application

Complete curing and backfilling operation prior to applying two coats of protective coating. Concrete must be surface dry and clean before each application. Spray apply at a rate of not more than 50 square yards/gallon for first application and not more than 70 square yards/gallon for second application, except that the number of applications and coverage for each application for commercially prepared mixture must be in accordance with the manufacturer's instructions. Protect coated surfaces from vehicular and pedestrian traffic until dry.

3.7.4.2 Precautions

Do not heat protective coating by direct application of flame or electrical heaters and protect the coating from exposure to open flame, sparks, and fire adjacent to open containers or applicators. Do not apply

material at ambient or material temperatures lower than 50 degrees F.

3.8 FIELD QUALITY CONTROL

Submit copies of all test reports within 24 hours of completion of the test.

3.8.1 General Requirements

Perform the inspection and tests described and meet the specified requirements for inspection details and frequency of testing. Based upon the results of these inspections and tests, take the action and submit reports as required below, and additional tests to ensure that the requirements of these specifications are met.

3.8.2 Concrete Testing

3.8.2.1 Strength Testing

Take concrete samples in accordance with ASTM C172/C172M not less than once a day nor less than once for every 250 cubic yards of concrete placed. Mold cylinders in accordance with ASTM C31/C31M for strength testing by an approved laboratory. Each strength test result must be the average of 2 test cylinders from the same concrete sample tested at 28 days, unless otherwise specified or approved. Concrete specified on the basis of compressive strength will be considered satisfactory if the averages of all sets of three consecutive strength test results equal or exceed the specified strength, and no individual strength test result falls below the specified strength by more than 500 psi.

3.8.2.2 Air Content

Determine air content in accordance with ASTM C173/C173M or ASTM C231/C231M. Use ASTM C231/C231M with concretes and mortars made with relatively dense natural aggregates. Make two tests for air content on randomly selected batches of each class of concrete placed during each shift. Make additional tests when excessive variation in concrete workability is reported by the placing foreman or the Government inspector. Notify the placing foreman if results are out of tolerance. The placing foreman must take appropriate action to have the air content corrected at the plant. Additional tests for air content will be performed on each truckload of material until such time as the air content is within the tolerance specified.

3.8.2.3 Slump Test

Perform two slump tests on randomly selected batches of each class of concrete for every 250 cubic yards, or fraction thereof, of concrete placed during each shift. Perform additional tests when excessive variation in the workability of the concrete is noted or when excessive crumbling or slumping is noted along the edges of slip-formed concrete.

3.8.3 Thickness Evaluation

Determine the anticipated thickness of the concrete prior to placement by passing a template through the formed section or by measuring the depth of opening of the extrusion template of the curb forming machine. If a slip form paver is used for sidewalk placement, construct the subgrade true to grade prior to concrete placement. The thickness will be determined by

measuring each edge of the completed slab.

3.8.4 Surface Evaluation

Provide finished surfaces for each category of the completed work that are uniform in color and free of blemishes and form or tool marks.

3.9 SURFACE DEFICIENCIES AND CORRECTIONS

3.9.1 Thickness Deficiency

When measurements indicate that the completed concrete section is deficient in thickness by more than 1/4 inch the deficient section will be removed, between regularly scheduled joints, and replaced.

3.9.2 High Areas

In areas not meeting surface smoothness and plan grade requirements, reduce high areas either by rubbing the freshly finished concrete with carborundum brick and water when the concrete is less than 36 hours old or by grinding the hardened concrete with an approved surface grinding machine after the concrete is 36 hours old or more. The area corrected by grinding the surface of the hardened concrete must not exceed 5 percent of the area of any integral slab, and the depth of grinding must not exceed 1/4 inch. Remove and replace pavement areas requiring grade or surface smoothness corrections in excess of the limits specified.

3.9.3 Appearance

Exposed surfaces of the finished work will be inspected by the Contracting Officer and deficiencies in appearance will be identified. Remove and replace areas which exhibit excessive cracking, discoloration, form marks, or tool marks or which are otherwise inconsistent with the overall appearances of the work.

3.10 DETECTABLE WARNING SYSTEM

Install Detectable Warning Systems required by Contract plans in accordance with ICC A117.1, Section 705, and by manufacturers' installation instructions.

-- End of Section --

SECTION 32 17 23

PAVEMENT MARKINGS
08/16, CHG 5: 11/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 247	(2013) Standard Specification for Glass Beads Used in Pavement Markings
AASHTO M 249	(2012; R2016) Standard Specification for White and Yellow Reflective Thermoplastic Striping Material (Solid Form)

ASTM INTERNATIONAL (ASTM)

ASTM D6628	(2003; R 2015) Standard Specification for Color of Pavement Marking Materials

INTERNATIONAL CONCRETE REPAIR INSTITUTE (ICRI)

ICRI 03732	(1997) Selecting and Specifying Concrete Surface Preparation for Sealers, Coatings, and Polymer Overlays

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE AMS-STD-595A	(2017) Colors used in Government Procurement

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)

MUTCD	(2023) Manual on Uniform Traffic Control Devices

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. When used, a code following the "G" classification identifies the office that will review the submittal for the Government.

SD-03 Product Data

Surface Preparation Equipment List; G

Application Equipment List; G

Exterior Surface Preparation

Safety Data Sheets; G

Waterborne Paint; G

Thermoplastic compound; G

Waterborne Paint; G

Thermoplastic Compound; G

SD-07 Certificates

Qualifications; G

Waterborne Paint

Volatile Organic Compound, (VOC); G

Thermoplastic Compound

SD-08 Manufacturer's Instructions

Waterborne Paint; G

Thermoplastic Compound; G

1.3 QUALITY ASSURANCE

1.3.1 Regulatory Requirements

Submit certificate stating that the proposed pavement marking paint meets the Volatile Organic Compound, (VOC) regulations of the local Air Pollution Control District having jurisdiction over the geographical area in which the project is located. Submit Safety Data Sheets for each product.

1.3.2 Qualifications

Submit documentation certifying that pertinent personnel are qualified for equipment operation and handling of applicable chemicals. The documentation should include experience on five projects of similar size and scope with references for all personnel.

1.4 DELIVERY AND STORAGE

Deliver paint materials, thermoplastic compound materials, and reflective media in original sealed containers that plainly show the designated name, specification number, batch number, color, date of manufacture, manufacturer's directions, and name of manufacturer.

Provide storage facilities at the job site for maintaining materials at temperatures recommended by the manufacturer.

1.5 PROJECT/SITE CONDITIONS

1.5.1 Environmental Requirements

1.5.1.1 Weather Limitations for Application

Apply pavement markings to clean, dry surfaces, and unless otherwise approved, only when the air and pavement surface temperature is at least 5 degrees F above the dew point and the air and pavement temperatures are within the limits recommended by the pavement marking manufacturer. Allow pavement surfaces to dry after water has been used for cleaning or rainfall has occurred prior to striping or marking. Test the pavement surface for moisture before beginning work each day and after cleaning. Do not commence marking until the pavement is sufficiently dry and the pavement condition has been approved by the Contracting Officer. Employ the "plastic wrap method" to test the pavement for moisture as specified in paragraph TESTING FOR MOISTURE.

1.5.1.2 Weather Limitations for Removal of Pavement Markings on Roads and Automotive Parking Areas

Pavement surface must be free of snow, ice, or slush; with a surface temperature of at least 40 degrees F and rising at the beginning of operations, except those involving shot or sand blasting or grinding. Cease operation during thunderstorms, or during rainfall, except for waterblasting and removal of previously applied chemicals. Cease waterblasting where surface water accumulation alters the effectiveness of material removal.

1.5.2 Traffic Controls

Place warning signs conforming to MUTCD near the beginning of the worksite and well ahead of the worksite for alerting approaching traffic from both directions. Place small markers along newly painted lines or freshly placed raised markers to control traffic and prevent damage to newly painted surfaces or displacement of raised pavement markers. Mark painting equipment with large warning signs indicating slow-moving painting equipment in operation.

When traffic must be rerouted or controlled to accomplish the work, provide necessary warning signs, flag persons, and related equipment for the safe passage of vehicles.

PART 2 PRODUCTS

2.1 EQUIPMENT

2.1.1 Surface Preparation and Paint Removal

2.1.1.1 Surface Preparation and Paint Removal Equipment for Airfield Pavements

Prepare all airfield surfaces and remove paint from airfield surfaces in accordance with UFGS 32 01 11.51 Rubber and Paint Removal From Airfield Pavements. Provide submittals in accordance with UFGS 32 01 11.51 Rubber and Paint Removal From Airfield Pavements.

2.1.1.2 Surface Preparation Equipment for Roads and Automotive Parking Areas

Submit a surface preparation equipment list by serial number, type, model, and manufacturer. Include descriptive data indicating area of coverage per pass, pressure adjustment range, tank and flow capacities, and safety precautions required for the equipment operation. Mobile equipment must allow for removal of markings without damaging the pavement surface or joint sealant. Maintain machines, tools, and equipment used in the performance of the work in satisfactory operating condition.

2.1.1.2.1 Waterblasting Equipment

Use mobile waterblasting equipment capable of producing a pressurized stream of water that effectively removes paint from the pavement surface without significantly damaging the pavement. Provide equipment, tools, and machinery which are safe and in good working order at all times.

2.1.1.2.2 Grinding or Scarifying Equipment

Use equipment capable of removing surface contaminates, paint build-up, or extraneous markings from the pavement surface without leaving any residue. Clean the surface by hydro blast to remove surface contaminates and ash after a weed torch is used to remove paint.

2.1.1.2.3 Chemical Removal Equipment

Use chemical equipment capable of applying and removing chemicals and paint from the pavement surface, leaving only non-toxic biodegradable residue without scarring or other damage to the pavement or joints and joint seals.

2.1.2 Application Equipment

Submit application equipment list appropriate for the material(s) to be used. Include manufacturer's descriptive data and certification for the planned use that indicates area of coverage per pass, pressure adjustment range, tank and flow capacities, and all safety precautions required for operating and maintaining the equipment. Provide and maintain machines, tools, and equipment used in the performance of the work in satisfactory operating condition, or remove them from the work site. Provide mobile and maneuverable application equipment to the extent that straight lines can be followed and normal curves can be made in a true arc.

2.1.2.1 Paint Application Equipment

2.1.2.1.1 Hand-Operated, Push-Type Machines

Provide hand-operated push-type applicator machine of a type commonly used for application of water based paint or two-component, chemically curing paint, thermoplastic, or preformed tape, to pavement surfaces for small marking projects, such as legends and cross-walks, automotive parking areas, or surface painted signs. Provide applicator machine equipped with the necessary tanks and spraying nozzles capable of applying paint uniformly at coverage specified. Hand operated spray guns may be used in areas where push-type machines cannot be used.

2.1.2.1.2 Self-Propelled or Mobile-Drawn Spraying Machines

Provide self-propelled or mobile-drawn spraying machine with suitable arrangements of atomizing nozzles and controls to obtain the specified results. Provide machine having a speed during application capable of applying the stripe widths indicated at the paint coverage rate specified herein and of even uniform thickness with clear-cut edges.

2.1.2.1.2.1 Road Marking

Provide equipment used for marking roads capable of placing the prescribed number of lines at a single pass as solid lines, intermittent lines, or a combination of solid and intermittent lines using a maximum of three different colors of paint as specified.

2.1.2.1.2.2 Airfield Marking

Provide self-propelled or mobile-drawn spraying machine for applying the paint for airfield pavements with an arrangement of atomizing nozzles capable of applying the specified line width in a single pass. Provide paint applicator with paint reservoirs or tanks of sufficient capacity and suitable gages to apply paint in accordance with requirements specified. Equip tanks with suitable mechanical agitators. Equip spray mechanism with quick-action valves conveniently located, and include necessary pressure regulators and gages in full view and reach of the operator. Install paint strainers in paint supply lines to ensure freedom from residue and foreign matter that may cause malfunction of the spray guns. The paint applicator must be readily adaptable for attachment of a dispenser for the reflective media approved for use.

2.1.2.1.2.3 Hand Application

Provide spray guns for hand application of paint in areas where the mobile paint applicator cannot be used.

2.1.2.2 Thermoplastic Application Equipment

2.1.2.2.1 Thermoplastic Material

Apply thermoplastic material with equipment that is capable of providing continuous uniformity in the dimensions and reflectorization of the marking.

2.1.2.2.2 Application Equipment

a. Provide application equipment capable of continuous mixing and agitation of the material, with conveying parts which prevent accumulation and clogging between the main material reservoir and the extrusion shoe or spray gun. All parts of the equipment which come into contact with the material must be easily accessible and exposed for cleaning and maintenance. All mixing and conveying parts up to and including the extrusion shoes and spray guns must maintain the material at the required temperature with heat-transfer oil or electrical-element-controlled heat.

b. Provide application equipment constructed to ensure continuous uniformity in the dimensions of the stripe. Provide an applicator with a means for cleanly cutting off stripe ends squarely and providing a method of applying "skiplines." Provide equipment capable

of applying varying widths of traffic markings.

c. Provide mobile and maneuverable application equipment allowing straight lines to be followed and normal curves to be made in a true arc. Provide equipment used for the placement of thermoplastic pavement markings of two general types: mobile applicator and portable applicator.

d. Equip the applicator with a pressurized or drop-on type bead dispenser capable of uniformly dispensing reflective glass spheres at controlled rates of flow. The bead dispenser must operate automatically to begin flow prior to the flow of binder to assure that the strip is fully reflectorized.

2.1.2.2.3 Mobile Application Equipment

Provide a truck-mounted, self-contained pavement marking machine that is capable of hot applying thermoplastic by either the extrusion or spray method.

a. Equip the unit to apply the thermoplastic marking material at temperatures according to the manufacturer's instructions, at widths varying from 3 to 12 inches, with an automatic pressurized or drop-on bead dispensing system, capable of operating continuously, and of installing a minimum of 20,000 lineal feet of longitudinal markings in an 8-hour day.

b. Equip the mobile unit with a melting kettle which holds a minimum of 6000 pounds of molten thermoplastic material; capable of heating the thermoplastic composition to temperatures as recommended by the manufacturer. Use a thermostatically controlled heat transfer liquid. Heating of the composition by direct flame is not allowed. Oil and material temperature gauges must be visible at both ends of the kettle.

c. Equip mobile units for application of extruded markings with a minimum of two extrusion shoes; located one on each side of the truck, capable of marking simultaneous edge line and centerline stripes; each being a closed, oil-jacketed unit; holding the molten thermoplastic at a temperature as recommended by the manufacturer; and capable of extruding a line of 3 to 8 inches in width; and at a thickness of not less than 0.120 inch nor more than 0.190 inch, of generally uniform cross section.

d. Equip mobile units for application of spray markings with a spray gun system capable of marking simultaneous edgeline and centerline stripes. Surround (jacket) the spray system with heating oil to maintain the molten thermoplastic at a temperature of 375 to 425 degrees F, capable of spraying a stripe of 3 to 12 inches in width, and in thicknesses varying from 0.060 inch to 0.098 inch, of generally uniform cross section.

e. Equip the mobile unit with an electronic programmable line pattern control system, capable of applying skip or solid lines in any sequence, through any and all of the extrusion shoes, or the spray guns, and in programmable cycle lengths. In addition, equip the mobile unit with an automatic counting mechanism capable of recording the number of lineal feet of thermoplastic markings applied to the pavement surface with an accuracy of 0.5 percent.

2.1.2.2.4 Portable Application Equipment

Provide portable hand-operated equipment, specifically designed for placing special markings such as crosswalks, stop bars, legends, arrows, and short lengths of lane, edge and centerlines; and capable of applying thermoplastic pavement markings by the extrusion method. Equip the portable applicator with all the necessary components, including a materials storage reservoir, bead dispenser, extrusion shoe, and heating accessories, capable of holding the molten thermoplastic at the temperature recommended by the manufacturer, and of extruding a line of 3 to 12 inches in width, and in thickness of not less than 0.120 inch nor more than 0.190 inch and of generally uniform cross section.

2.1.2.3 Reflective Media Dispenser

Attach the dispenser for applying the reflective media to the thermoplastic dispenser and designed to operate automatically and simultaneously with the applicator through the same control mechanism. The bead applicator must be capable of adjustment and designed to provide uniform flow of reflective media over the full length and width of the stripe at the rate of coverage specified in paragraph APPLICATION.

2.1.2.4 Preformed Tape Application Equipment

Provide and use mechanical application equipment for the placement of preformed marking tape which is a mobile pavement marking machine specifically designed for use in applying pressure-sensitive pavement marking tape of varying widths. Equip the applicator with rollers, or other suitable compaction device to provide initial adhesion of the material with the pavement surface. Use additional tools and devices as needed to properly seat the applied material as recommended by the manufacturer.

2.2 MATERIALS

Use non-reflectorized waterborne paint for automotive parking areas. The maximum allowable VOC content of pavement markings is 150 grams per liter. Color of markings are indicated on the drawings and must conform to ASTM D6628 for roads and automotive parking areas and SAE AMS-STD-595A for airfields. Provide materials conforming to the requirements specified herein.

2.2.1 Thermoplastic Compound

2.2.1.1 Composition Requirements

Thermoplastic compound must conform to AASHTO M 249. Formulate the binder component as an alkyd resin.

2.2.1.2 Primer

a. Asphalt concrete primer: Provide thermosetting adhesive primer with a solids content of pigment reinforced synthetic rubber and synthetic plastic resin dissolved or dispersed in a volatile organic solvent for asphaltic concrete pavements. The solids content must not be less than 10 percent by weight at 70 degrees F and 60 percent relative humidity. A wet film thickness of 0.005 inch, plus or minus 0.001 inch, must dry to a tack-free condition in less than 5 minutes.

b. Portland cement concrete primer: Provide an epoxy resin primer for Portland cement concrete pavements, of the type recommended by the manufacturer of the thermoplastic composition.

PART 3 EXECUTION

3.1 EXAMINATION

3.1.1 Testing for Moisture

Test the pavement surface for moisture before beginning pavement marking after each period of rainfall, fog, high humidity, or cleaning, or when the ambient temperature has fallen below the dew point. Do not commence marking until the pavement is sufficiently dry and the pavement condition has been approved by the Contracting Officer or authorized representative.

Employ the "plastic wrap method" to test the pavement for moisture as follows: Cover the pavement with a 12 inch by 12 inch section of clear plastic wrap and seal the edges with tape. After 15 minutes, examine the plastic wrap for any visible moisture accumulation inside the plastic. Do not begin marking operations until the test can be performed with no visible moisture accumulation inside the plastic wrap. Re-test surfaces when work has been stopped due to rain.

3.2 EXTERIOR SURFACE PREPARATION

Allow new pavement surfaces to cure for a period of not less than 30 days before application of marking materials. Thoroughly clean surfaces to be marked before application of the paint. Remove dust, dirt, and other granular surface deposits by sweeping, blowing with compressed air, rinsing with water, or a combination of these methods as required. Remove rubber deposits, residual curing compounds, and other coatings adhering to the pavement by water blasting.

a. For Portland Cement Concrete pavement, grinding, light shot blasting, or light scarification, to a resulting profile equal to ICRI 03732 CSP 2, CSP 3, and CSP 4, respectively, can be used in addition to water blasting on most pavements, to either remove existing coatings, or for surface preparation.

b. Do not use shot blasting on airfield pavements due to the potential of Foreign Object Damage (FOD) to aircraft. Scrub affected areas, where oil or grease is present on old pavements to be marked, with several applications of trisodium phosphate solution or other approved detergent or degreaser and rinse thoroughly after each application. After cleaning oil-soaked areas, seal with shellac or primer recommended by the manufacturer to prevent bleeding through the new paint. Do not commence painting in any area until pavement surfaces are dry and clean.

3.2.1 Early Painting of Rigid Pavements

Pretreat rigid pavements that require early painting with an aqueous solution containing 3 percent phosphoric acid and 2 percent zinc chloride. Apply the solution to the areas to be marked.

3.2.2 Early Painting of Asphalt Pavements

For asphalt pavement systems requiring painting application at less than 30 days, apply the paint and beads at half the normal application rate, followed by a second application at the normal rate after 30 days.

3.3 APPLICATION

Apply pavement markings to dry pavements only.

3.3.1 Paint

Apply paint with approved equipment at rate of coverage specified herein. Provide guidelines and templates as necessary to control paint application. Take special precautions in marking numbers, letters, and symbols. Manually paint numbers, letters, and symbols. Sharply outline all edges of markings. The maximum drying time requirements of the paint specifications will be strictly enforced, to prevent undue softening of bitumen, and pickup, displacement, or discoloration by tires of traffic. If there is a deficiency in drying of the markings, painting operations must cease until the cause of the slow drying is determined and corrected.

3.3.1.1 Waterborne Paint

3.3.1.1.1 Roads

Apply paint at a rate of 105 plus or minus 5 square feet per gallon. Apply beads at a rate of 7 plus or minus 0.5 pounds of glass spheres per gallon.

3.3.2 Thermoplastic Compound

Place thermoplastic pavement markings, free from dirt or tint, upon dry pavement. The temperature must be a minimum of 40 degrees F and rising at the time of installation. Apply all centerline, skipline, edgeline, and other longitudinal type markings with a mobile applicator. Place all special markings, crosswalks, stop bars, legends, arrows, and similar patterns with a portable applicator, using the extrusion method.

3.3.2.1 Reflective Media

Immediately after installation of the thermoplastic material, mechanically apply drop-on reflective glass spheres conforming to AASHTO M 247 Type 1 at the rate of one pound per 20 square feet such that the spheres are held by and imbedded in the surface of the molten material. Accomplish drop-on application of the glass spheres to ensure even distribution at the specified rate of coverage. If there is a malfunction of either thermoplastic applicator or reflective media dispenser, discontinue operations until deficiency is corrected.

3.3.3 Raised Pavement Markers

Align prefabricated markers carefully at the spacing indicated on the drawings and permanently fix in place by means of epoxy adhesives. To ensure good bond prior to applying adhesive, thoroughly clean all areas where markers are to be set by water blasting and use of compressed air.

3.3.4 Preformed Tape

The pavement surface and ambient air temperature must be a minimum of 60 degrees F and rising. Place the preformed markings in accordance with the manufacturer's written instructions.

3.3.5 Cleanup and Waste Disposal

Keep the worksite clean and free of debris and waste from the removal and application operations. Dispose of debris at approved sites.

3.4 FIELD QUALITY CONTROL

3.4.1 Sampling and Testing

As soon as the paint and thermoplastic materials and reflective media are available for sampling, obtain by random selection from the sealed containers, two quart samples of each batch in the presence of the Contracting Officer. Accomplish adequate mixing prior to sampling to ensure a uniform, representative sample. A batch is defined as that quantity of material processed by the manufacturer at one time and identified by number on the label. Clearly identify samples by designated name, specification number, batch number, project contract number, intended use, and quantity involved.

3.4.2 Material Inspection

Examine material at the job site to determine that it is the material referenced in the report of test results or certificate of compliance. Provide test results substantiating conformance to the specified requirements with each certificate of compliance.

3.4.3 Dimensional Tolerances

Apply all markings in the standard dimensions provide in the drawings. New markings may deviate a maximum of 10 percent larger than the standard dimension. The maximum deviation allowed when painting over an old marking is up to 20 percent larger than the standard dimensions.

3.4.4 Bond Failure Verification

Inspect newly applied markings for signs of bond failure based on visual inspection and comparison to results from Test Stripe Demonstration paragraph.

3.4.5 Reflective Media and Coating Application Verification

Use a wet film thickness gauge to measure the application of wet paint. Use a microscope or magnifying glass to evaluate the embedment of glass beads in the paint. Verify the glass bead embedment with approximately 50 percent of the individual bead spheres embedded and 50 percent of the individual bead spheres exposed.

-- End of Section --

SECTION 32 17 23.16

ROAD AND PARKING LOT PAVEMENT MARKINGS
11/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO M 247	(2013) Standard Specification for Glass Beads Used in Pavement Markings

ASTM INTERNATIONAL (ASTM)

ASTM D4414	(1995; R 2020) Standard Practice for Measurement of Wet Film Thickness by Notch Gages
ASTM E1710	(2011) Standard Test Method for Measurement of Retroreflective Pavement Marking Materials with CEN-Prescribed Geometry Using a Portable Retroreflectometer

MASTER PAINTERS INSTITUTE (MPI)

MPI 97	(2012) Traffic Marking Paint, Latex

SOCIETY OF AUTOMOTIVE ENGINEERS INTERNATIONAL (SAE)

SAE AMS-STD-595A	(2017) Colors used in Government Procurement

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)

MUTCD	(2023) Manual on Uniform Traffic Control Devices

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-01 Preconstruction Submittals

Quality Control Plan; G

Qualifications; G

Safety Data Sheets For Each Paint Type; G

Safety Data Sheets For Chemicals Used In Surface Preparation; G

Data Sheets For Paint Removal Equipment; G

Surface Preparation Equipment List; G

Marking Applications Equipment List; G

Detour Plans; G

SD-03 Product Data

Manufacturer Data Sheets for all Marking Materials; G

SD-04 Samples

Samples of Marking Materials; G

Samples of each Reflective Media; G

SD-06 Test Reports

Marking Application Wet Film Thickness Test; G

Reflective Media Reflectivity Test; G

SD-07 Certificates

Manufacturer Certificate of Compliance for Marking Materials; G

Manufacturer Certificate of Compliance for Reflective Materials; G

Manufacturer Certificate of Conformance for Volatile Organic Compliance; G

SD-08 Manufacturer's Instructions

Marking Materials Storage and Application; G

Reflective Media Storage and Application; G

Chemicals Used in Surface Preparation; G

1.3 QUALITY CONTROL

1.3.1 Quality Control Plan

Within 10 calendar days of project award, submit a quality control plan. The plan must state the means, methods, equipment, and materials to be employed for the performance of the surface preparation, existing markings removal, application of reflective and non-reflective marking, and marking layout. At a minimum, provide descriptive criteria for each of the following activities for review and approval by the Contracting Officer:

a. Describe the means and methods used to layout marking geometry and the location of marking elements.

b. Describe the protocol for determination of the operating pressure and speed of the equipment for surface preparation.

c. Describe the protocol for surface preparation when not using water.

d. Describe the protocol for existing markings removal.

e. Define the protocol for the performance of test stripes for each line width, color, and paint type.

f. Provide equipment details to include speed, pressures and application rate for the minimum wet film thickness and the application rate of reflective media to provide the specified glass bead anchoring and reflectivity.

g. Provide and discuss safety directives for maintaining traffic on roads and parking lots.

h. Define communications procedures when operating on roads and parking lots.

1.3.2 Qualifications

Submit documentation certifying that pertinent personnel are qualified for equipment operation and handling of applicable chemicals. The documentation should include experience on five projects of similar size and scope with references for all personnel.

1.4 DELIVERY, STORAGE, AND HANDLING

A conditioned storage and staging area on the installation will be provided for all materials intended to be used on the project. Ensure all materials delivered to the storage location are in the original container and clearly marked with the product name, compliance information, batch number, color, manufactured date, instructions for storage, instructions for application, and the name of the manufacturer. All materials are to be stored in conformance with the manufacturer instructions. Provide manufacturer instructions for; marking materials storage and application, reflective media storage and application, and the chemicals used in surface preparation.

1.5 PROJECT/SITE SPECIAL CONDITIONS

1.5.1 Environmental Requirements

Pavement surface must be free of snow, ice, or slush; with a surface temperature of at least 40 degrees F and rising at the beginning of operations, except those involving shot blasting or grinding. Cease operation during thunderstorms, or during rainfall, except for water blasting and removal of previously applied chemicals. Cease water blasting where surface water accumulation alters the effectiveness of material removal.

1.5.1.1 Weather Limitations for Marking Application

Apply pavement markings to clean, dry surfaces and only when the ambient temperature is at least 5 degrees F above the dew point and the pavement surface temperatures are within the limits recommended by the manufacturer of the material being used unless otherwise noted. Allow the pavement surface to dry after the water has been used for surface preparation or after a precipitation event. Do not perform marking applications when the

wind carries overspray onto locations adjacent to the marking. Provide wind screens to shroud application equipment.

1.5.1.2 Testing Dry Surfaces

Do not commence marking until the pavement surface is dry. Use the plastic wrap method as described in paragraph PRE-APPLICATION TESTING to test the pavement surface for moisture. Do not proceed with marking until the Contracting Officer has observed the moisture test and has accepted the area prepared for marking.

1.5.1.3 Volatile Organic Compounds Compliance

Submit a manufacturer certificate stating that the proposed pavement marking paint meets the Volatile Organic Compound (VOC) regulations of the local Air Pollution Control District having jurisdiction over the geographical area in which the project is located. Submit manufacturer certificate of conformance for volatile organic compliance.

1.5.2 Traffic Control for Roads and Parking Lots

Place approved signs conforming to MUTCD near the beginning of the worksite and well ahead of the worksite to alert approaching traffic from both directions. Place markers along newly painted lines to control traffic and prevent damage to newly painted surfaces or displacement of raised pavement markers. Mark painting equipment with warning signs that can be read from a distance of 100 feet, indicating slow-moving painting equipment in operation. Provide all lighting and equipment necessary to light the work area during night operations effectively.

When traffic is rerouted or controlled to accomplish the work, provide necessary warning signs, flag persons, and related equipment for the safe passage of vehicles. Submit detour plans to the Contracting Officer for approval before doing the work.

1.6 APPLICATION EQUIPMENT CALIBRATION

Before performing any marking application, calibrate the paint and glass bead application equipment at the necessary speed to execute the application. Calibration and application will be performed using paint that is not diluted or thinned. Paint will be used as formulated by the manufacturer. Calibrate paint and bead guns for each line width and color intended to be applied. Use metal coupons placed in the path of the equipment to capture a test line without glass beads. Use a wet film gauge in accordance with ASTM D4414, to determine if the wet film thickness is the same at each edge and at the center of the marking. Adjust each paint gun to provide a line of uniform thickness.

Collect a sample of glass beads directly from the glass bead dispenser along a measured distance. Weigh the glass beads captured and determine the coverage by dividing the weight by the area of the line placed during the calibration. Adjust the glass bead dispenser to provide an application rate necessary to meet or exceed the reflectivity specified. After determining the application rate, apply a reflective marking using the wet film thickness to be used for the color and marking element. Using a magnifying glass, examine the distribution and embedment of the glass beads. Beads are to be distributed uniformly for the width of the marking. Adjust the wet film thickness if the beads are submerged or predominantly on the surface of the marking.

PART 2 PRODUCTS

2.1 EQUIPMENT

Submit a surface preparation equipment list by serial number, type, model, and manufacturer. Include descriptive data indicating area of coverage per pass, pressure adjustment range, tank and flow capacities, and safety precautions required for the equipment operation. Mobile equipment must allow for removal of markings without damaging the pavement surface or joint sealant. Maintain machines, tools, and equipment used in the performance of the work in satisfactory operating condition.

2.1.1 Surface Preparation and Paint Removal for Roads and Parking Lots

Submit data sheets for paint removal equipment intended for use in preparation of the pavement surface for marking. In the submittal, include descriptive information on the means for adjusting coverage per each pass, water pressure adjustment range, and tank and flow capacities. The equipment must have a range of adjustments that will provide a clean surface free of dirt, dust, oil, grease, algae, mildew, mold, and loose paint. Submit safety data sheets for chemicals used in surface preparation. Chemicals must be bio-degradable.

2.1.1.1 Water Blasting Equipment

Use mobile water blasting equipment capable of producing a pressurized stream of water that effectively removes paint from the pavement surface without significantly damaging the pavement. Provide equipment, tools, and machinery which are safe and in good working order.

2.1.1.2 Shot Blasting Equipment

Use mobile self-propelled shot blasting equipment capable of producing an adjustable depth of paint removal and propelling abrasive particles at high velocities on the paint for effective removal. Ensure each unit is self-cleaning and self-contained. Use equipment able to confine the abrasive, any dust that is produced, and removed paint and is capable of recycling the abrasive for reuse.

2.1.1.3 Grinding or Scarifying Equipment

Use equipment capable of removing surface contaminates, paint build-up, or extraneous markings from the pavement surface without leaving any residue. Clean the surface by a hydro blast to remove surface contaminants, and ash after a weed torch is used to remove paint.

2.1.1.4 Chemical Removal Equipment

Use chemical equipment capable of applying and removing chemicals and paint from the pavement surface, leaving only non-toxic biodegradable residue without scarring or other damage to the pavement or joints and joint seals.

2.1.2 Markings Application Equipment

Submit a marking applications equipment list of equipment appropriate for the material(s) to be used. Include the manufacturer's descriptive data and certification for the planned use that indicates the area of coverage

per pass, pressure adjustment range, tank and flow capacities, and all safety precautions required for operating and maintaining the equipment. Provide and maintain machines, tools, and equipment used in the performance of the work in satisfactory operating condition, or remove equipment that is not providing satisfactory performance from the work site. Provide mobile and maneuverable application equipment to the extent that straight lines can be followed and normal curves can be made in a true arc.

2.1.2.1 Airless or Atomizing Equipment

Provide mobile airless or pneumatic air-atomized application equipment that is maneuverable to the extent that straight lines can be followed and normal curves can be made in a true arc. Mount equipment on trucks, skids or tractors. Use equipment suitable for application of the marking material specified. Airless systems are used to apply waterborne and epoxy coatings. Pneumatic systems are used only to apply waterborne and solvent based coatings.

Provide equipment capable of applying a marking from 4 inches to 12 inches wide in a single pass and also capable of applying two single solid or intermittent lines using a minimum of two colors. Provide equipment with tanks or reservoirs equipped with mechanical agitators, pressure regulators, and gages in full view of the equipment operator. Use paint strainers suitable to screen paint flowing in all supply lines.

2.1.2.2 Hand-Operated Machines

Provide a hand-operated push-type applicator machine commonly used for the application of water-based paint or two-component, chemically curing paint, thermoplastic, or preformed tape to pavement surfaces for small marking projects, such as legends and cross-walks, parking lots, or surface painted signs. Provide an applicator machine with the necessary tanks and spraying nozzles capable of applying paint uniformly at specified wet film thickness. Provide spray guns for hand application of paint in areas where push-type machines cannot be used.

2.1.2.3 Reflective Media Dispenser

Mount glass bead dispensers that are automatically triggered when paint guns are activated. The dispensers may be pressurized or gravity-drop systems. Pressurized systems require moisture control.

2.1.3 Reflective Thermoplastic Striping Material (Hot Applied) Application Equipment

Apply thermoplastic material with equipment capable of providing continuous uniformity for the dimensional and reflectivity requirements of the marking.

2.1.3.1 Application Equipment

a. Provide application equipment capable of continuous mixing and agitation of the material, with conveying parts that prevent accumulation and clogging between the main material reservoir and the extrusion shoe or spray gun. Ensure all parts of the equipment which come into contact with the material are easily accessible and exposed for cleaning and maintenance. All mixing and conveying parts including the extrusion shoes and spray guns are to maintain the

material at the required temperature with heat-transfer oil or electrical-element-controlled heat.

b. Provide application equipment constructed to ensure continuous uniformity in the stripe dimensions. Provide an applicator with a means for cleanly cutting off stripe ends squarely and providing a method of applying skip lines. Provide equipment capable of applying varying widths of traffic markings.

c. Provide mobile application equipment allowing straight lines to be followed and normal curves to be made in a true arc. Provide equipment for the placement of thermoplastic pavement markings of two general types: mobile applicator and hand-operated applicator.

d. Equip the applicator with a pressurized or drop-on type bead dispenser capable of uniformly dispensing reflective glass spheres at controlled flow rates. The bead dispenser must operate automatically to begin flow before the flow of the binder to assure that the strip is fully reflectorized.

2.1.3.2 Mobile Application Equipment

Provide a truck-mounted, self-contained pavement marking machine capable of hot applying thermoplastic by either the extrusion or spray method.

a. Equip the mobile unit with a melting kettle that holds a minimum of 6000 pounds of molten thermoplastic material, capable of heating the thermoplastic composition to temperatures as recommended by the manufacturer. Use a thermostatically controlled heat transfer liquid. Heating the composition by direct flame is not allowed. Oil and material temperature gauges must be visible at both ends of the kettle.

b. Equip mobile units for application of extruded markings with a minimum of two extrusion shoes; located one on each side of the truck, capable of marking simultaneous edge line and centerline stripes, each being a closed, oil-jacketed unit.

c. Equip the mobile unit with an electronic programmable line pattern control system capable of applying skip or solid lines in any sequence, through any and all extrusion shoes, or spray guns, and in programmable cycle lengths. In addition, equip the mobile unit with an automatic counting mechanism capable of recording the number of lineal feet of thermoplastic markings applied to the pavement surface with an accuracy of 0.5 percent.

2.1.3.3 Hand-Operated Machines

Provide portable hand-operated equipment, specifically designed for placing special markings such as crosswalks, stop bars, legends, arrows, and short lengths of the lane, edge, and centerlines; and apply thermoplastic pavement markings by the extrusion method. Equip the hand-operated applicator with all the necessary components, including a materials storage reservoir, bead dispenser, extrusion shoe, and heating accessories.

2.1.3.4 Reflective Media Dispenser

Attach the dispenser for applying the reflective media to the

thermoplastic dispenser that is designed to operate automatically and simultaneously with the applicator through the same control mechanism. Provide a bead applicator capable of adjustment and designed to provide a uniform flow of reflective media over the full length and width of the marking.

2.1.4 Preformed Retroreflective Pavement Marking Tape Application Equipment

Provide mechanical application equipment specifically designed for the placement of preformed marking tape. The equipment is specifically designed to apply pressure-sensitive pavement marking tape of varying widths. Equip the applicator with rollers, or other suitable compaction devices to provide initial adhesion of the material with the pavement surface. Use additional tools and devices for properly seating the applied material, as the manufacturer recommends.

2.2 ROAD AND PARKING LOT MATERIALS

Submit safety data sheets for each paint type and preformed tape as well as manufacturer data sheets for all marking materials; include with the submittal a manufacturer certificate of compliance for marking materials and a manufacturer certificate of compliance for reflective materials.

2.2.1 Marking Colors

Provide markings for pavements that conform to SAE AMS-STD-595A color numbers as listed in Table I.

Table I - SAE AMS-STD-595A Color Numbers

Paint Color	SAE AMS-STD-595A Color Number
White	37925
Yellow	33538
Black	37038
Green	34108
Red	33411

2.2.2 Waterborne Paint

Use MPI 97 paint.

PART 3 EXECUTION

3.1 TEST SECTIONS

Before the performance of any marking application, demonstrate to the Government, using the equipment, materials, and personnel identified in the approved quality control plan, that the requirements for acceptance of the final product(s) are attainable. The minimum length of the test section is 50 feet of marking for each line width, color, and wet film thickness. Perform demonstrations in a location designated by the Contracting Officer within the project scope of work. Do not perform the test section(s) until the Contracting Officer is present to observe the

test. Table III identifies minimum and maximum wet film thickness based on glass bead type. Each test section's result is the standard of performance for the color, width, wet film thickness, and glass bead application rate for each marking element. Submit the color, line width, wet film thickness, and measured reflectivity.

3.2 SURFACE PREPARATION

Clean surfaces before the application of marking materials. Remove all dust, dirt, scaling or loose paint, algae, oils, and grease and mineral deposits such as iron stains by use of water blasting or chemical removal. Follow the cleaning with sweeping, blowing or using water rinse. Do not begin painting in any location prepared for marking until surfaces are dry and clean.

Scrub areas with oil or grease present with applications of trisodium phosphate solution or other approved detergent or degreaser. Rinse thoroughly after each application to prevent staining of the new marking. After cleaning oil-soaked areas, seal with shellac or primer as the manufacturer recommends to prevent bleeding through the new paint.

3.3 PRE-APPLICATION TESTING

Test the pavement surface for moisture before beginning pavement marking after each period of rainfall, fog, high humidity, or cleaning or when the ambient temperature has fallen below the dew point. Do not commence marking until the pavement is sufficiently dry and the Contracting Officer has approved the pavement condition.

Employ the plastic wrap method, described as follows, to test the pavement for moisture:

a. Cover the pavement with a 12 inch by 12 inch section of clear plastic wrap and seal the edges with tape.

b. After 15 minutes, examine the plastic wrap for any visible moisture accumulation. Do not begin marking operations until the test can be performed with no visible moisture accumulation inside the plastic wrap.

c. Re-test surfaces when work has been stopped due to a precipitation event.

3.4 MARKINGS APPLICATION

3.4.1 Marking Materials for Roads and Parking Lots Pavement

3.4.1.1 Waterborne Paint

The dilution or thinning of paint prior to application is not allowed.

Provide MPI 97 paint and apply AASHTO M 247 glass beads. Apply reflective and non-reflective markings in accordance with Table III. Use the paint type and bead type as shown on the drawings.

The paint wet film thickness and glass bead application rate is provided in Table III. Perform the marking and bead application test section beginning at the minimum value and adjust the application rate up or down until the requirements of WET FILM THICKNESS TEST SECTION and REFLECTIVE

TEST SECTION are satisfied. The values of wet film thickness and bead application rate established by the test section will be the standard of performance for the respective marking type and color.

Table III. Paint Wet Film Thickness and Bead Application Rate

Paint Type	Non-Reflectorized Marking Wet Film Thickness (mil)	Reflectorized Marking			
		Wet Film Thickness (mil) based on Glass Bead Type		Minimum Bead Application Rate	
		Type I Gradation A	Type IV Gradation B	Type I Gradation A	Type IV Gradation B
Type I	14-16	14-16	--	7 lb/gal	--
Type II	14-16	14-16	--	7 lb/gal	--
Type III	16-20	--	25-30	--	8 lb/gal

3.4.1.2 Preformed Reflective Pavement Marking Tape

The pavement surface and ambient air temperature must be at a minimum of 60 degrees F and rising. Place the preformed tape markings according to the written instructions provided by the manufacturer.

3.4.1.3 Raised Pavement Markers

Align prefabricated markers carefully at the spacing indicated on the drawings and permanently fix them by using epoxy adhesives. Clean all areas where markers are to be set by water blasting. Markers are not to be set until the pavement surface is dry and contaminant-free.

3.5 FIELD QUALITY CONTROL AND ACCEPTANCE

3.5.1 Material Inspection

The Contractor is responsible for examining all materials accepted for delivery for compliance with the certificate of compliance.

3.5.2 Sampling and Testing

As soon as the marking materials are available for sampling, obtain materials by random selection directly from equipment already calibrated. Four quarts of paint are to be collected; two quarts for the Contractor and two quarts for the Government. Samples of marking materials and samples of each reflective media are to be collected by the Contractor in the presence of the Contracting Officer. Identify samples by project name and number, manufacture date, batch number, and the square yards of markings represented by the sample.

The Government will retain samples for the warranty period under storage conditions recommended by the manufacturer. If there is an issue with a material defect during the period of the warranty the Contractor will incur the cost for an accredited independent laboratory to test the material(s) for conformance with the certifications and the contract specifications. The Government reserves the right to test the samples for verification of materials.

3.5.3 Dimensional Tolerance

The Contractor applies layout markings. All layout markings are placed before the marking material application. The edges of a line must not vary from a straight line drawn between the beginning and end of the line more than 1/2-inch to 50 feet. Marking dimensions and spacing must be within the tolerances provided in Table IV.

TABLE IV - Dimensional Tolerance for Marking Elements

Dimension and Spacing	Tolerance
12 inch or less	+/- 1/2 inch
Greater than 36 inch to 6 feet	+/- 1 inch
Greater than 6 feet to 60 feet	+/- 2 inch
Greater than 60 feet	+/- 3 inch

3.5.4 Coating and Reflective Media Application Reporting

3.5.4.1 Reporting Wet Film Thickness and Reflectivity

Submit documentation on the wet film thickness and reflectivity for each marking element. Provide a reading at the rate of one reading per 1000 linear feet of line marking. A reading is the average of 10 measurements at random locations within the marking element area. Submit the results of the marking application wet film thickness test and Reflective Media Reflectivity Test to the Contracting Officer before proceeding with work on the project.

3.5.4.2 Wet Film Thickness

Conduct a marking application wet film thickness test. Provide a wet film thickness gauge to measure the wet film thickness using ASTM D4414 at the edge(s) and one interior location of the marking. When more than 3 in 10 consecutive measurements of wet film thickness are outside of the tolerances in Table III, remove and replace areas not meeting the wet film thickness requirement.

3.5.4.3 Reflectivity

Provide documentation that records the readings for white, yellow and red reflective markings. Conduct a Reflective Media Reflectivity Test. Measure the reflectivity using a Retro-Reflectometer using ASTM E1710. The minimum reading for white, yellow, and red markings is provided in Table V in millicandelas per square meter per lux (mcd/m2/lx) at the time of

marking. When more than 3 in 10 consecutive measurements of reflectivity are outside of the minimum in Table V, remove and replace the areas not meeting the minimum reflectivity requirements.

TABLE VI - Minimum Reflectivity (millicandelas per square meter per lux)		
Bead Type	Minimum Reflectivity at Time of Marking	
Type I	White - 300	Yellow - 175
Type IV	White - 300	Yellow - 200

Preformed Tape pavement markings will yield a minimum of 225 mcd/m2/lux on white markings at installation and a minimum of 100 mcd/m2/lux on yellow markings at installation.

3.6 CLEANUP AND WASTE DISPOSAL

The worksite and the material staging area must be free of debris, dirt, and items that will blow away during periods of elevated wind speeds. Dispose of all materials at a site approved by the Contracting Officer. Dispose of waste from cleaning the marking equipment at a facility that is permitted to accept the material.

3.6.1 Cleanup Requirements

Provide a vacuum sweeper after each work area when markings are cured. Vacuum sweep the entire pavement surface to provide a clean pavement without fugitive glass beads and debris.

-- End of Section --

SECTION 32 31 13

CHAIN LINK FENCES AND GATES
11/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A392	(2011; R 2022a) Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric
ASTM A780/A780M	(2020) Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings
ASTM A824	(2001; R 2022) Standard Specification for Metallic-Coated Steel Marcelled Tension Wire for Use With Chain Link Fence
ASTM C94/C94M	(2022a) Standard Specification for Ready-Mixed Concrete
ASTM F567	(2014a; R 2019) Standard Practice for Installation of Chain Link Fence
ASTM F626	(2014; R 2019) Standard Specification for Fence Fittings
ASTM F883	(2013; R 2022) Standard Performance Specification for Padlocks

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FS RR-F-191/1	(Rev F) Fencing, Wire and Post, Metal (Chain-Link Fence Fabric)
FS RR-F-191/2	(Rev E) Fencing, Wire and Post, Metal (Chain-Link Fence Gates)
FS RR-F-191/3	(Rev E; Am 1) Fencing, Wire and Post, Metal (Chain-Link Fence Posts, Top Rails and Braces)
FS RR-F-191/4	(Rev F) Fencing, Wire and Post, Metal (Chain-Link Fence Accessories)

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-02 Shop Drawings

Fence Assembly; G

Location of Gate, Corner, End, and Pull Posts; G

Gate Assembly; G

Gate Hardware and Accessories; G

Erection/Installation Drawings; G

SD-03 Product Data

Fence Assembly; G

Gate Assembly; G

Gate Hardware and Accessories; G

Zinc Coating; G

PVC Coating; G

Aluminum Alloy Coating; G

Fabric; G

Stretcher Bars; G

Concrete; G

SD-04 Samples

Fabric; G

Posts; G

Braces; G

Line Posts; G

Sleeves; G

Top Rail; G

Tension Wire; G

Stretcher Bars; G

Gate Posts; G

Gate Hardware and Accessories; G

Wire Ties; G

SD-07 Certificates

Certificates of Compliance

SD-08 Manufacturer's Instructions

Fence Assembly

Gate Assembly

Hardware Assembly

Accessories

SD-11 Closeout Submittals

Recycled Material Content

1.3 QUALITY CONTROL

1.3.1 Certificates of Compliance

Submit certificates of compliance in accordance with the applicable reference standards and descriptions of this section for the following:

a. Zinc coating

b. PVC coating

c. Aluminum alloy coating

d. Fabric

e. Stretcher bars

f. Gate hardware and accessories

g. Concrete

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver materials to site in an undamaged condition. Store materials off the ground to provide protection against oxidation caused by ground contact.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Submit reports of listing chain-link fencing and accessories regarding weight in ounces for zinc coating.

Submit manufacturer's catalog data for complete fence assembly, gate assembly, hardware assembly and accessories.

2.2 FENCES

2.2.1 Fabric

FS RR-F-191/1; Type I, zinc-coated steel, 9 gauge conforming to ASTM A392,

with 2.0 ounces per square foot of coated surface. Provide selvage twisted and barbed at both selvages. Height of fabric, as indicated.

Provide fabric consisting of wires woven into a 2 inch diamond mesh. Provide one-piece fabric widths for fence heights up to 12 feet.

2.2.2 Posts

2.2.2.1 Metal

2.2.2.1.1 Line Posts

Provide line posts complying with FS RR-F-191/3. Provide Class 1, steel pipe, Grade A Regular Strength or in.

2.2.2.1.2 End, Corner and Pull Posts

Provide end, corner, and pull posts in minimum sizes listed in FS RR-F-191/3 for each class and grade. Provide Class 1, steel pipe, Grade A High Strength.

2.2.2.2 Post Tops

Provide steel, wrought iron, or malleable iron tops and designed as a weathertight closure cap. Post top to have finish and coating matching rails and posts. Steel type to be pressed steel galvanized after fabrication having a minimum zinc coating of 1.20 ounces per square foot. Provide one cap for each post, unless equal protection is provided by a combination post-cap and wire supporting arm. Provide caps with an opening to permit through passage of the top rail.

2.2.3 Braces and Rails

Class 1, steel pipe, Grade A High Strength or, in minimum sizes listed in FS RR-F-191/3 for each class and grade.

2.2.3.1 Top Rail

Provide top rail conforming to minimum sizes specified in FS RR-F-191/3 for each class and grade unless members are to be oversized. Provide expansion couplings 6 inches long at each joint in top rails.

2.2.3.2 Post-Brace Assembly

Provide bracing conforming to minimum sizes specified in FS RR-F-191/3 for each class and grade, and 3/8 inch adjustable truss rods and turnbuckles.

2.2.4 Wire Ties

Provide 9-gauge wire for tying fabric to line posts,spaced 12 inches on center. For tying fabric to rails and braces, space wire ties 24 inches on center. For tying fabric to tension wire, space 0.105-inch hog rings 24 inches on center. Manufacturer's standard procedure will be accepted if of equal strength and durability.

FS RR-F-191/4. Provide wire ties constructed of the same material and coating as the fencing fabric.

2.2.5 Sleeves

Provide sleeves for setting into concrete construction of the same material as post sections, sized 1 inch greater than the diameter or dimension of the post. Weld flat plates to each sleeve base to provide anchorage and prevent intrusion of concrete.

2.2.6 Stretcher Bars

Provide bars that have one-piece lengths equal to the full height of the fabric with a minimum cross section of 3/16 by 3/4 inch, in accordance with ASTM F626.

2.2.7 Stretcher Bar Bands

Provide bar bands for securing stretcher bars to posts that are steel, wrought iron, or malleable iron spaced not over 15 inches on center. Bands may also be used in conjunction with special fittings for securing rails to posts. Provide bands with projecting edges chamfered or eased.

2.2.8 Tension Wire

Provide metallic coated steel marcelled tension wire,(No. 7-gauge) complying with ASTM A824. Provide zinc-coated steel wire with zinc coating that weighs not less than 1.2 ounces per square foot.

2.2.9 Miscellaneous Hardware

Provide miscellaneous hot-dip galvanized hardware as required.

2.3 GATES

FS RR-F-191/2; Type II, double swing. Shape and size of gate frame, as indicated. Framing and bracing members, round of steel alloy. Steel member finish, zinc-coated. Provide gate frames and braces of minimum sizes listed in FS RR-F-191/3 for each Class and Grade, except that steel pipe frames are a minimum of 1.90 inches o.d., 0.120 inches minimum wall thickness and aluminum pipe frames and intermediate braces are 1.869 inches o.d. minimum, 0.940 lb/ft of length. Provide intermediate members as necessary for gate leaves more than 8 feet wide, to provide rigid construction, free from sag or twist.

2.3.1 Gate Posts

Provide gate posts for supporting each gate leaf in size 6 inches. Gate post material class, grade and finish to match other fence posts.

2.3.2 Gate Fabric

Gate fabric, is as specified for fencing fabric. Attach gate fabric to gate frame in accordance with manufacturer's standards, except that welding is not permitted.

2.3.3 Gate Frame

Provide gate frame assembly that is welded or assembled with special malleable or pressed-steel fittings and rivets to provide rigid connections. Install fabric with stretcher bars at vertical edges; stretcher bars may also be used at top and bottom edges. Attach stretcher

bars and fabric to gate frames on all sides at intervals not exceeding 15 inches. Attach hardware with rivets or by other means which provides equal security against breakage or removal.

2.3.4 Gate Bracing

Provide diagonal cross-bracing, consisting of 3/8 inch diameter adjustable-length truss rods on welded gate frames, where necessary to obtain frame rigidity without sag or twist. Provide nonwelded gate frames with diagonal bracing.

2.3.5 Padlocks

Provide padlocks conforming to ASTM F883, with chain.

2.3.6 Gate Hardware and Accessories

Provide gate hardware and accessories that conforms to ASTM A392 and ASTM F626, and as specified. Coating for steel latches, stops, hinges, keepers, and accessories, is galvanized

a. Provide malleable iron hinges to suit gate size, non-lift-off type, offset to permit 180-degree opening. Provide hinge with stainless steel pin.

b. Provide latch that permits accessibility and operation from either side of the gate regardless of the latching arrangement, and with a padlock eye provided as an integral part of the latch. Provide fork type gate latches.

c. Provide stops and holders of malleable iron for vehicular gates. Provide stops that automatically engage the gate and hold it in the open position until manually released.

d. Provide double gates with a cane bolt and ground-set keeper, with latch or locking device and padlock eye designed as an integral part.

2.4 MATERIALS

2.4.1 Zinc Coating

Provide zinc-coated ferrous metal components and accessories that are factory coated after fabrication, except as otherwise specified.

For galvanizing field repairs, provide material that is cold-applied zinc-rich coating conforming to ASTM A780/A780M.

2.4.2 Concrete

Provide concrete conforming to ASTM C94/C94M, and obtaining a minimum 28-day compressive strength of 3,000 psi.

2.4.3 Grout

Provide grout of proportions one part portland cement to three parts clean, well-graded sand and a minimum amount of water to produce a workable mix.

PART 3 EXECUTION

Submit manufacturer's erection/installation drawings and instructions that detail proper assembly and materials in the design for fence, gate, hardware and accessories.

Provide complete installation conforming to ASTM F567.

3.1 PREPARATION

Ensure final grading and established elevations are complete prior to commencing fence installation.

3.1.1 Clearing and Grading

Clear fence line of trees, brush, and other obstacles to install fencing for a distance of 20 feet inside; and 10 feet outside the fence. Establish a graded, compacted fence line prior to fencing installation.

3.2 INSTALLATION

3.2.1 Security

Install new chain link fencing, remove existing fencing, and perform related work to provide continuous security for facility. Schedule and fully coordinate work with Contracting Officer and cognizant Security Officer.

3.2.2 Fence Installation

Install fence on prepared surfaces to line and grade indicated. Install fence in accordance with fence manufacturer's written installation instructions except as modified herein.

3.2.2.1 Post Spacing

Provide line posts spaced equidistantly apart, not exceeding 10 feet on center. Provide gate posts spaced as necessary for size of gate openings. Do not exceed 500 feet on straight runs between braced posts. Provide corner or pull posts, with bracing in both directions, for changes in direction of 15 degrees or more, or for abrupt changes in grade. Submit drawings showing location of gate, corner, end, and pull posts.

3.2.2.2 Top and Bottom Tension Wire

Install top and bottom tension wires before installing chain-link fabric, and pull wires taut. Place top and bottom tension wires within 8 inches of respective fabric line.

3.2.3 Excavation

Provide excavations for post footings which are in virgin or compacted soil, of minimum sizes as indicated. Space footings for line posts 10 feet on center maximum and at closer intervals when indicated, with bottoms of the holes approximately 3 inches below the bottoms of the posts. Set bottom of each post not less than 36 inches below finished grade when in firm, undisturbed soil. Set posts deeper, as required, in soft and problem soils and for heavy, lateral loads. Uniformly spread soil from excavations adjacent to the fence line or on areas of Government property,

as directed.

When solid rock is encountered near the surface, drill into the rock at least 12 inches for line posts and at least 18 inches for end, pull, corner, and gate posts. Drill holes at least 1 inch greater in diameter than the largest dimension of the placed post. If solid rock is below the soil overburden, drill to the full depth required except that penetration into rock need not exceed the minimum depths specified above.

3.2.4 Setting Posts

Remove loose and foreign materials from holes and moisten the soil prior to placing concrete. Provide tops of footings that are trowel finished and sloped or domed to shed water away from posts. Set hold-open devices, sleeves, and other accessories in concrete.

Keep exposed concrete moist for at least 7 calendar days after placement or cured with a membrane curing material, as approved. Maintain vertical alignment of posts in concrete construction until concrete has set.

3.2.4.1 Earth and Bedrock

Provide concrete bases of dimensions indicated on the manufactures installation drawings. Compact concrete to eliminate voids, and finish to a dome shape.

3.2.4.2 Bracing

Brace gate, corner, end, and pull posts to nearest post with a horizontal brace used as a compression member, placed at least 12 inches below top of fence, and a diagonal tension rod.

3.2.4.3 Tolerances

Provide posts that are straight and plumb within a vertical tolerance of 1/4 inch after the fabric has been stretched. Provide fencing and gates that are true to line with no more than 1/2 inch deviation from the established centerline between line posts. Repair defects as directed.

3.2.5 Concrete Strength

Provide concrete that has attained at least 75 percent of its minimum 28-day compressive strength, but in no case sooner than 7 calendar days after placement, before rails, tension wire, or fabric are installed. Do not stretch fabric and wires or hang gates until the concrete has attained its full design strength.

3.2.6 Top Rails

Provide top rails that run continuously through post caps or extension arms, bending to radius for curved runs. Provide expansion couplings as recommended by the fencing manufacturer.

3.2.7 Brace Assembly

Provide bracing assemblies at end and gate posts and at both sides of corner and pull posts, with the horizontal brace located at midheight of the fabric.

Install brace assemblies so posts are plumb when the diagonal rod is under proper tension. Provide two complete brace assemblies at corner and pull posts where required for stiffness and as indicated.

3.2.8 Tension Wire Installation

Install tension wire by weaving them through the fabric and tying them to each post with not less than 7-gauge galvanized wire or by securing the wire to the fabric with 10-gauge ties or clips spaced 24 inches on center.

3.2.9 Fabric Installation

Provide fabric in single lengths between stretch bars with bottom barbs placed approximately 1-1/2 inches above the ground line. Pull fabric taut and tied to posts, rails, and tension wire with wire ties and bands.

Install fabric on the security side of fence, unless otherwise directed. Ensure fabric remains under tension after the pulling force is released.

3.2.10 Stretcher Bar Installation

Thread stretcher bars through or clamped to fabric 4 inches on center and secured to posts with metal bands spaced 15 inches on center.

3.2.11 Gate Installation

Install gates plumb, level, and secure, with full opening without interference. Install ground set items in concrete for anchorage as recommended by the fence manufacturer. Adjust hardware for smooth operation and lubricated where necessary.

3.2.12 Tie Wires

Provide tie wires that are U-shaped to the pipe diameters to which attached. Twist ends of tie wires not less than two full turns and bent so as not to present a hazard.

3.2.13 Fasteners

Install nuts for tension bands and hardware on the side of the fence opposite the fabric side. Peen ends of bolts to prevent removal of nuts.

3.2.14 Zinc-Coating Repair

Clean and repair galvanized surfaces damaged by welding or abrasion, and cut ends of fabric, or other cut sections with specified galvanizing repair material applied in strict conformance with the manufacturer's printed instructions.

3.2.15 Accessories Installation

3.2.15.1 Post Caps

Install post caps as recommended by the manufacturer.

3.2.15.2 Padlocks

Provide padlocks for gate openings and provide chains that are securely attached to gate or gate posts. Provide padlocks keyed alike, and provide

two keys for each padlock.

3.2.16 Grounding

Ground fencing as indicated on drawings.

3.3 CLOSEOUT ACTIVITIES

Remove waste fencing materials and other debris from the work site.

Submit manufacturer's data indicating percentage of recycled material content in protective fence materials, including chain link fence, fabric, and gates to verify affirmative procurement compliance.

-- End of Section --

SECTION 32 92 23

SODDING
04/06, CHG 1: 08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM D4972	(2018) Standard Test Methods for pH of Soils

TURFGRASS PRODUCERS INTERNATIONAL (TPI)

TPI GSS	(1995) Guideline Specifications to Turfgrass Sodding

U.S. DEPARTMENT OF AGRICULTURE (USDA)

DOA SSIR 42	(1996) Soil Survey Investigation Report No. 42, Soil Survey Laboratory Methods Manual, Version 3.0

1.2 DEFINITIONS

1.2.1 Stand of Turf

100 percent ground cover of the established species.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-03 Product Data

Fertilizer

Include physical characteristics, and recommendations.

SD-06 Test Reports

Topsoil composition tests (reports and recommendations).

SD-07 Certificates

Sod farm certification for sods. Indicate type of sod in accordance with TPI GSS.

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 Delivery

1.4.1.1 Sod Protection

Protect from drying out and from contamination during delivery, on-site storage, and handling.

1.4.1.2 Fertilizer Delivery

Deliver to the site in original, unopened containers bearing manufacturer's chemical analysis, name, trade name, trademark, and indication of conformance to state and federal laws. Instead of containers, fertilizer may be furnished in bulk with certificate indicating the above information.

1.4.2 Storage

1.4.2.1 Sod Storage

Lightly sprinkle with water, cover with moist burlap, straw, or other approved covering; and protect from exposure to wind and direct sunlight until planted. Provide covering that will allow air to circulate so that internal heat will not develop. Do not store sod longer than 24 hours. Do not store directly on concrete or bituminous surfaces.

1.4.2.2 Topsoil

Prior to stockpiling topsoil, treat growing vegetation with application of appropriate specified non-selective herbicide. Clear and grub existing vegetation three to four weeks prior to stockpiling topsoil.

1.4.2.3 Handling

Do not drop or dump materials from vehicles.

1.5 TIME RESTRICTIONS AND PLANTING CONDITIONS

1.5.1 Restrictions

Do not plant when the ground is frozen, snow covered, muddy, or when air temperature exceeds 90 degrees Fahrenheit.

1.6 TIME LIMITATIONS

1.6.1 Sod

Place sod a maximum of thirty six hours after initial harvesting, in accordance with TPI GSS as modified herein.

PART 2 PRODUCTS

2.1 SODS

2.1.1 Classification

Nursery grown, certified as classified in the TPI GSS. Machine cut sod at a uniform thickness of 3/4 inch within a tolerance of 1/4 inch, excluding

top growth and thatch. Each individual sod piece shall be strong enough to support its own weight when lifted by the ends. Broken pads, irregularly shaped pieces, and torn or uneven ends will be rejected.Wood pegs and wire staples for anchorage shall be as recommended by sod supplier.

2.1.2 Purity

Sod species shall be genetically pure, free of weeds, pests, and disease.

2.1.3 Planting Dates

Lay sod from April to September for warm season spring planting and from October to March for cool season fall planting.

2.1.4 Composition

2.1.4.1 Sod Farm Overseeding

At the sod farm provide sod with overseeding of type recommended by seed producer.

2.2 TOPSOIL

2.2.1 On-Site Topsoil

Surface soil stripped and stockpiled on site and modified as necessary to meet the requirements specified for topsoil in paragraph entitled "Composition." When available topsoil shall be existing surface soil stripped and stockpiled on-site in accordance with Section 31 00 00 EARTHWORK.

2.2.2 Off-Site Topsoil

Conform to requirements specified in paragraph entitled "Composition." Additional topsoil shall be furnished by the Contractor.

2.2.3 Composition

Containing from 5 to 10 percent organic matter as determined by the topsoil composition tests of the Organic Carbon, 6A, Chemical Analysis Method described in DOA SSIR 42. Maximum particle size, 3/4 inch, with maximum 3 percent retained on 1/4 inch screen. The pH shall be tested in accordance with ASTM D4972. Topsoil shall be free of sticks, stones, roots, and other debris and objectionable materials. Other components shall conform to the following limits:

Silt	25-50 percent
Clay	10-30 percent
Sand	20-35 percent
pH	5.5 to 7.0

Soluble Salts	600 ppm maximum

2.3 FERTILIZER

2.3.1 Granular Fertilizer

Organic, granular controlled release fertilizer containing the following minimum percentages, by weight, of plant food nutrients:

10 percent available nitrogen
10 percent available phosphorus
10 percent available potassium
10 percent sulfur

2.4 WATER

Source of water shall be approved by Contracting Officer and of suitable quality for irrigation containing no element toxic to plant life.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Extent Of Work

Provide soil preparation (including soil conditioners), fertilizing, and sodding of all newly graded finished earth surfaces, unless indicated otherwise, and at all areas inside or outside the limits of construction that are disturbed by the Contractor's operations.

3.1.2 Soil Preparation

Provide 4 inches of off-site topsoil to meet indicated finish grade. After areas have been brought to indicated finish grade, incorporate fertilizer into soil a minimum depth of 4 inches by disking, harrowing, tilling or other method approved by the Contracting Officer. Remove debris and stones larger than 3/4 inch in any dimension remaining on the surface after finish grading. Correct irregularities in finish surfaces to eliminate depressions. Protect finished topsoil areas from damage by vehicular or pedestrian traffic.

3.2 SODDING

3.2.1 Finished Grade and Topsoil

Prior to the commencement of the sodding operation, the Contractor shall verify that finished grades are as indicated on drawings; the placing of topsoil, smooth grading, and compaction requirements have been completed in accordance with Section 31 00 00 EARTHWORK.

The prepared surface shall be a maximum 1 inch below the adjoining grade of any surfaced area. New surfaces shall be blended to existing areas. The prepared surface shall be completed with a light raking to remove from the surface debris and stones over a minimum 5/8 inch in any dimension.

3.2.2 Placing

Place sod a maximum of 36 hours after initial harvesting, in accordance

with TPI GSS as modified herein.

3.2.3 Sodding Slopes and Ditches

For slopes 2:1 and greater, lay sod with long edge perpendicular to the contour. For V-ditches and flat bottomed ditches, lay sod with long edge perpendicular to flow of water. Anchor each piece of sod with wood pegs or wire staples maximum 2 feet on center. On slope areas, start sodding at bottom of the slope.

3.2.4 Finishing

After completing sodding, blend edges of sodded area smoothly into surrounding area. Air pockets shall be eliminated and a true and even surface shall be provided. Frayed edges shall be trimmed and holes and missing corners shall be patched with sod.

3.2.5 Rolling

Immediately after sodding, firm entire area except for slopes in excess of 3 to 1 with a roller not exceeding 90 pounds for each foot of roller width.

3.2.6 Watering

Start watering areas sodded as required by daily temperature and wind conditions. Apply water at a rate sufficient to ensure thorough wetting of soil to minimum depth of 6 inches. Run-off, puddling, and wilting shall be prevented. Unless otherwise directed, watering trucks shall not be driven over turf areas. Watering of other adjacent areas or plant material shall be prevented.

3.3 PROTECTION OF TURF AREAS

Immediately after turfing, protect area against traffic and other use.

3.4 RESTORATION

Restore to original condition existing turf areas which have been damaged during turf installation operations. Keep clean at all times at least one paved pedestrian access route and one paved vehicular access route to each building. Clean other paving when work in adjacent areas is complete.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 32 93 00

EXTERIOR PLANTS
08/17, CHG 1: 08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)

AWPA P5	(2015) Standard for Waterborne Preservatives
AWPA T1	(2022) Use Category System: Processing and Treatment Standard
AWPA U1	(2022) Use Category System: User Specification for Treated Wood

AMERICANHORT (AH)

ANSI/ANLA Z60.1	(2004) American Standard for Nursery Stock

ASTM INTERNATIONAL (ASTM)

ASTM A580/A580M	(2023) Standard Specification for Stainless Steel Wire
ASTM C602	(2020) Agricultural Liming Materials
ASTM D4427	(2018) Standard Classification of Peat Samples by Laboratory Testing
ASTM D4972	(2018) Standard Test Methods for pH of Soils
ASTM D5268	(2019) Topsoil Used for Landscaping Purposes
ASTM D5852	(2000; R 2007; E 2014) Standard Test Method for Erodibility Determination of Soil in the Field or in the Laboratory by the Jet Index Method
ASTM D6155	(2019) Nontraditional Coarse Aggregate for Bituminous Paving Mixtures
ASTM D6629	(2001; R 2012; E 2012) Selection of Methods for Estimating Soil Loss by Erosion

L.H. BAILEY HORTORIUM (LHBH)

LHBH	(1976) Hortus Third

TREE CARE INDUSTRY ASSOCIATION (TCIA)

TCIA A300P1	(2017) ANSI A300 Part1: Tree Care Operations - Trees, Shrubs and Other Woody Plant Maintenance Standard Practices - Pruning
TCIA Z133	(2017) American National Standard for Arboricultural Operations - Pruning, Repairing, Maintaining, and Removing Trees, and Cutting Brush - Safety Requirements

U.S. DEPARTMENT OF AGRICULTURE (USDA)

DOA SSIR 42	(1996) Soil Survey Investigation Report No. 42, Soil Survey Laboratory Methods Manual, Version 3.0

1.2 RELATED REQUIREMENTS

Section 31 23 00.00 80 EXCAVATION AND FILL, Section 32 92 23 SODDING applies to this section for pesticide use and plant establishment requirements, with additions and modifications herein.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-01 Preconstruction Submittals

State Landscape Contractor's License

Time Restrictions and Planting Conditions

Indicate anticipated dates and locations for each type of planting.

SD-03 Product Data

Peat

Composted Derivatives

Rotted Manure

Organic Mulch Materials

Gypsum

Mulch

Ground Stakes

Recycled Plastic Edging

Fertilizer

Weed Control Fabric;

Root Control Barrier;

Staking Material

Wood Edging

Metal Anchors

Antidesiccants

SD-06 Test Reports

Topsoil Composition Tests; Soil Test of proposed area

Percolation Test; Percolation Test of proposed area

SD-07 Certificates

Nursery Certifications

SD-10 Operation and Maintenance Data

Plastic Identification

When not labeled, identify types in Operation and Maintenance Manual.

1.4 QUALITY ASSURANCE

1.4.1 Topsoil Composition Tests

Commercial test from an independent testing laboratory including basic soil groups (moisture and saturation percentages, Nitrogen-Phosphorus-Potassium (N-P-K) ratio, pH (ASTM D4972), soil salinity), secondary nutrient groups (calcium, magnesium, sodium, Sodium Absorption Ratio (SAR)), micronutrients (zinc, manganese, iron, copper), toxic soil elements (boron, chloride, sulfate), cation exchange and base saturation percentages, and soil amendment and fertilizer recommendations with quantities for plant material being transplanted. Soil required for each test must include a maximum depth of 18 inches of approximately one quart volume for each test. Areas sampled should not be larger than one acre and should contain at least 6-8 cores for each sample area and be thoroughly mixed. Problem areas should be sampled separately and compared with samples taken from adjacent non-problem areas. The location of the sample areas should be noted and marked on a parcel or planting map for future reference.

1.4.2 Nursery Certifications

a. Indicate on nursery letterhead the name of plants in accordance with the LHBH, including botanical common names, quality, and size.

b. Inspection certificate.

c. Mycorrhizal fungi inoculum for plant material treated

1.4.3 State Landscape Contractor's License

Construction company must hold a landscape contractors license in the state where the work is performed and have a minimum of five years landscape construction experience. Submit copy of license and three references for similar work completed in the last five years.

1.4.4 Percolation Test

Immediately following rough grading operation, identify a typical location for one of the largest trees and or shrubs and excavate a pit per the project details. Fill the pit with water to a depth of 12 inches. The length of time required for the water to percolate into the soil, leaving the pit empty, must be measured by the project Landscape Architect and verified by the Contracting Officer. Within six hours of the time the water has drained from the pit, the Contractor, with the Contracting Officer and project Landscape Architect present, must again fill the pit with water to a depth of 12 inches. If the water does not completely percolate into the soil within 9 hours, a determination must be made whether a drainage system or a soil penetrant will be required for each tree and or shrub being transplanted.

1.4.5 Erosion Assessment

Assess potential effects of soil management practices on soil loss in accordance with ASTM D6629. Assess erodibility of soil with dominant soil structure less than 2.8 to 3.1 inches in accordance with ASTM D5852.

1.4.6 Pre-Installation Meeting

Convene a pre-installation meeting a minimum of one week prior to commencing work of this section. Require attendance of parties directly affecting work of this section. Review conditions of operations, procedures and coordination with related work. Agenda must include the following:

a. Tour, inspect, and discuss conditions of planting materials.

b. Review planting schedule and maintenance.

c. Review required inspections.

d. Review environmental procedures.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery

1.5.1.1 Branched Plant Delivery

Deliver with branches tied and exposed branches covered with material which allows air circulation. Prevent damage to branches, trunks, root systems, and root balls and desiccation of leaves.

1.5.1.2 Soil Amendment Delivery

Deliver to the site in original, unopened containers bearing manufacturer's chemical analysis, name, trade name, or trademark, and

indication of conformance to state and federal laws. Instead of containers, fertilizer, gypsum, sulfur, iron, and lime may be furnished in bulk with a certificate indicating the above information. Store in dry locations away from contaminates.

1.5.1.3 Plant Labels

Deliver plants with durable waterproof labels in weather-resistant ink. Provide labels stating the correct botanical and common plant name and variety as applicable and size as specified in the list of required plants. Attach to plants, bundles, and containers of plants. Groups of plants may be labeled by tagging one plant. Labels must be legible for a minimum of 60 days after delivery to the planting site.

1.5.2 Storage

1.5.2.1 Plant Storage and Protection

Store and protect plants not planted on the day of arrival at the site as follows:

a. Shade and protect plants in outside storage areas from the wind and direct sunlight until planted.

b. Heel-in bare root plants.

c. Protect balled and burlapped plants from freezing or drying out by covering the balls or roots with moist burlap, sawdust, wood chips, shredded bark, peat moss, or other approved material. Provide covering which allows air circulation.

d. Keep plants in a moist condition until planted by watering with a fine mist spray.

e. Do not store plant material directly on concrete or bituminous surfaces.

1.5.2.2 Fertilizer, Gypsum, pH Adjusters and Storage

Store in dry locations away from contaminants.

1.5.2.3 Topsoil

Prior to stockpiling topsoil, eradicate on site undesirable growing vegetation. Clear and grub existing vegetation three to four weeks prior to stockpiling existing topsoil.

1.5.3 Handling

Do not drop or dump plants from vehicles. Avoid damaging plants being moved from nursery or storage area to planting site. Handle boxedballed and burlapped bare root balled and pottedprocessed balledin-ground fabric bag grown container plants carefully to avoid damaging or breaking the earth ball or root structure. Do not handle plants by the trunk or stem. Remove damaged plants from the site.

1.5.4 TIME LIMITATION

Except for container-grown plant material, the time limitation from

digging to installing plant material must be a maximum of 30 days. The time limitation between installing the plant material and placing the mulch must be a maximum of 24 hours.

1.6 TIME RESTRICTIONS AND PLANTING CONDITIONS

Coordinate installation of planting materials during optimal planting seasons for each type of plant material required.

1.6.1 Planting Dates

Plant all plants from March to May (Spring) and October to December (Fall or specifically from grower's recommendations.

1.6.2 Restrictions

Do not plant when ground is frozen, snow covered, muddy, or when air temperature exceeds 90 degrees Fahrenheit

1.7 GUARANTEE

All plants must be guaranteed for one year beginning on the date of inspection by the Contracting Officer to commence the plant establishment period, against defects including death and unsatisfactory growth, except for defects resulting from lack of adequate maintenance, neglect, or abuse by the Government or by weather conditions unusual for the warranty period.

Remove and replace dead planting materials immediately unless required to plant in the succeeding planting season. At end of warranty period, replace planting materials that die or have 25 percent or more of their branches that die during the construction operations or the guarantee period.

1.8 PLASTIC IDENTIFICATION

Provide product data indicating polymeric information in Operation and Maintenance Manual.

Type 1: Polyethylene Terephthalate (PET, PETE).

Type 2: High Density Polyethylene (HDPE).

Type 3: Vinyl (Polyvinyl Chloride or PVC).

Type 4: Low Density Polyethylene (LDPE).

Type 5: Polypropylene (PP).

Type 6: Polystyrene (PS).

Type 7: Other. Use of this code indicates that the package in question is made with a resin other than the six listed above, or is made of more than one resin listed above, and used in a multi-layer combination.

PART 2 PRODUCTS

2.1 PLANTS

2.1.1 Regulations and Varieties

Existing trees and shrubs to remain must be protected and a planting plan be arranged around them. Furnish nursery stock in accordance with ANSI/ANLA Z60.1, except as otherwise specified or indicated. Each plant or group of planting must have a "key" number indicated on the nursery certifications of the plant schedule. Furnish plants, including turf grass, grown under climatic conditions similar to those in the locality of the project. Plants specified must be low maintenance varieties, tolerant of site's existing soils and climate without supplemental irrigation or fertilization once established. Plants of the same specified size must be of uniform size and character of growth. Plants must be chosen with their mature size and growth habit in mind to avoid over-planting and conflict with other plants, structures or underground utility lines. All plants must comply with all Federal and State Laws requiring inspection for plant diseases and infestation.

2.1.2 Shape and Condition

Well-branched, well-formed, sound, vigorous, healthy planting stock free from disease, sunscald, windburn, abrasion, and harmful insects or insect eggs and having a healthy, normal, and undamaged root system.

2.1.2.1 Deciduous Trees and Shrubs

Symmetrically developed and of uniform habit of growth, with straight boles or stems, and free from objectionable disfigurements.

2.1.2.2 Evergreen Trees and Shrubs

Well developed symmetrical tops with typical spread of branches for each particular species or variety.

2.1.2.3 Ground Covers and Vines

Number and length of runners and clump sizes indicated, and of the proper age for the grade of plants indicated, furnished in removable containers, integral containers, or formed homogeneous soil section.

2.1.3 Plant Size

Minimum sizes measured after pruning and with branches in normal position, must conform to measurements indicated, based on the average width or height of the plant for the species as specified in ANSI/ANLA Z60.1. Plants larger in size than specified may be provided with approval of the Contracting Officer. When larger plants are provided, increase the ball of earth or spread of roots in accordance with ANSI/ANLA Z60.1.

2.1.4 Root Ball Size

All box-grown, field potted, field boxed, collected, plantation grown, bare root, balled and burlapped, container grown, processed-balled, and in-ground fabric bag-grown root balls must conform to ANSI/ANLA Z60.1. All wrappings and ties must be biodegradable. Root growth in container grown plants must be sufficient to hold earth intact when removed from

containers. Root bound plants will not be accepted.

2.1.4.1 Mycorrhizal fungi inoculum

Before shipment, root systems must contain mycorrhizal fungi inoculum.

2.1.5 Growth of Trunk and Crown

2.1.5.1 Deciduous Trees

A height to caliper relationship must be provided in accordance with ANSI/ANLA Z60.1. Height of branching must bear a relationship to the size and species of tree specified and with the crown in good balance with the trunk. The trees must not be "poled" or the leader removed.

a. Single stem: The trunk must be reasonably straight and symmetrical with crown and have a persistent main leader.

b. Multi-stem: All countable stems, in aggregate, must average the size specified. To be considered a stem, there must be no division of the trunk which branches more than 6 inches from ground level.

2.1.5.2 Deciduous Shrubs

Deciduous shrubs must have the height and number of primary stems recommended by ANSI/ANLA Z60.1. Acceptable plant material must be well shaped, with sufficient well-spaced side branches, and recognized by the trade as typical for the species grown in the region of the project.

2.1.5.3 Coniferous Evergreen Plant Material

Coniferous Evergreen plant material must have the height-to-spread ratio recommended by ANSI/ANLA Z60.1. The coniferous evergreen trees must not be "poled" or the leader removed. Acceptable plant material must be exceptionally heavy, well shaped and trimmed to form a symmetrical and tightly knit plant. The form of growth desired must be as indicated.

2.1.5.4 Broadleaf Evergreen Plant Material

Broadleaf evergreen plant material must have the height-to-spread ratio recommended by ANSI/ANLA Z60.1. Acceptable plant material must be well shaped and recognized by the trade as typical for the variety grown in the region of the project.

2.1.5.5 Ground Cover and Vine Plant Material

Ground cover and vine plant material must have the minimum number of runners and length of runner recommended by ANSI/ANLA Z60.1. Plant material must have heavy, well developed and balanced crown with vigorous, well developed root system and must be furnished in containers.

2.2 TOPSOIL

2.2.1 Existing Soil

Modify to conform to requirements specified in paragraph COMPOSITION.

2.2.2 On-Site Topsoil

Surface soil stripped and stockpiled on site and modified as necessary to meet the requirements specified for topsoil in paragraph COMPOSITION. When available topsoil must be existing surface soil stripped and stockpiled on-site in accordance with Section 31 00 00 EARTHWORK.

2.2.3 Off-Site Topsoil

Conform to requirements specified in paragraph COMPOSITION. Additional topsoil must be furnished by the Contractor.

2.2.4 Composition

Evaluate soil for use as topsoil in accordance with ASTM D5268. From 5 to 10 percent organic matter as determined by the topsoil composition tests of the Organic Carbon, 6A, Chemical Analysis Method described in DOA SSIR 42. Maximum particle size, 3/4 inch, with maximum 3 percent retained on 1/4 inch screen. The pH must be tested in accordance with ASTM D4972. Topsoil must be free of sticks, stones, roots, plants, and other debris and objectionable materials. Other components must conform to the following limits:

Silt	7 to 17 percent
Clay	4 to 12 percent
Sand	70 to 82 percent
pH	5.5 to 7.0
Soluble Salts	600 ppm maximum

2.3 SOIL CONDITIONERS

Provide singly or in combination as required to meet specified requirements for topsoil. Soil conditioners must be nontoxic to plants.

2.3.1 Lime

Commercial grade hydrated or burnt limestone containing a calcium carbonate equivalent (C.C.E.) as specified in ASTM C602 of not less than 80 percent.

2.3.2 Aluminum Sulfate

Commercial grade.

2.3.3 Sulfur

100 percent elemental

2.3.4 Iron

100 percent elemental

2.3.5 Peat

Natural product of peat moss derived from a freshwater site and conforming to ASTM D4427 as modified herein. Shred and granulate peat to pass a 1/2 inch mesh screen and condition in storage pile for minimum 6 months after excavation. Peat must not contain invasive species, including seeds.

2.3.6 Sand

Clean and free of materials harmful to plants.

2.3.7 Perlite

Horticultural grade.

2.3.8 Composted Derivatives

Ground bark, nitrolized sawdust, humus or other green wood waste material free of stones, sticks, invasive species, including seeds, and soil stabilized with nitrogen and having the following properties:

2.3.8.1 Particle Size

Minimum percent by weight passing:

No. 4 mesh screen	95
No. 8 mesh screen	80

2.3.8.2 Nitrogen Content

Minimum percent based on dry weight:

Fir Sawdust	0.7
Fir or Pine Bark	1.0

2.3.9 Gypsum

Coarsely ground gypsum comprised of calcium sulfate dihydrate 80 percent, calcium 18 percent, sulfur 14 percent; minimum 96 percent passing through 20 mesh screen, 100 percent passing thru 16 mesh screen.

2.3.10 Vermiculite

Horticultural grade for planters.

2.3.11 Rotted Manure

Well rotted horse or cattle manure containing maximum 25 percent by volume of straw, sawdust, or other bedding materials; free of seeds, stones, sticks, soil, and other invasive species.

2.4 PLANTING SOIL MIXTURES

Sandy topsoil: one part topsoil to one part peat; clay topsoil: two parts topsoil to one part peat. Thoroughly mix all parts of planting soil mixture to a uniform blend throughout.

2.5 FERTILIZER

Fertilizer for groundcover, wildflowers and grasses is not permitted. Fertilizer for trees, plants, and shrubs must be as recommended by plant supplier, except synthetic chemical fertilizers are not permitted. Fertilizers containing petrochemical additives or that have been treated with pesticides or herbicides are not permitted.

2.5.1 Granular Fertilizer

Organic, granular controlled release fertilizer containing the following minimum percentages, by weight, of plant food nutrients:

10 percent available nitrogen
10 percent available phosphorus
10 percent available potassium
10 percent sulfur

2.5.2 Fertilizer Tablets

Organic, plant tablets composed of tightly compressed fertilizer chips forming a tablet that is insoluble in water, is designed to provide a continuous release of nutrients for at least 24 months and contains the following minimum percentages, by weight, of plant food nutrients:

20 percent available nitrogen
20 percent available phosphorus
5 percent available potassium

2.6 WEED CONTROL FABRIC

2.6.1 Roll Type Polypropylene or Polyester Mats

Fabric must be woven, needle punched or non-woven and treated for protection against deterioration due to ultraviolet radiation. Fabric must be minimum 99 percent opaque to prevent photosynthesis and seed germination from occurring, yet allowing air, water and nutrients to pass thru to the roots. Minimum weight must be 5 ounces per square yard with a minimum thickness of 20 mils with a 20 year (minimum) guarantee.

2.7 MULCH

Free from noxious weeds, mold, pesticides, or other deleterious materials.

2.7.1 Inert Mulch Materials

Provide recycled stone, riverbank stone, crushed pit-run rock, granite chips, complying with ASTM D6155.

2.7.2 Organic Mulch Materials

Provide wood cellulose fiber, wood chips, shredded hardwood, shredded redwood bark, pine straw mulch, pine needles, or from site when available. Wood cellulose fiber must be processed to contain no growth or germination-inhibiting factors, dyed with non-toxic, biodegradable dye to an appropriate color to facilitate visual metering of materials application. Paper-based hydraulic mulch must contain 100 percent post-consumer recycled content. Wood-based hydraulic mulch must contain 100 percent total recovered materials content.

2.7.3 Recycled Organic Mulch

Recycled mulch may include compost, tree trimmings, or pine needles with a gradation that passes through a 2-1/2 by 2-1/2 inch screen. It must be cleaned of all sticks a minimum one inch in diameter and plastic materials a minimum 3 inches length. The material must be treated to retard the growth of mold and fungi.

2.8 STAKING AND GUYING MATERIAL

2.8.1 Staking Material

2.8.1.1 Tree Support Stakes

Rough sawn hard wood free of knots, rot, cross grain, bark, long slivers, or other defects that impair strength. Stakes must be minimum 2 inches square or 2-1/2 inch diameter by 8 feet long, pointed at one end. Paint or stain wood stakes dark brown..

2.8.1.2 Ground Stakes

Rough sawn hard wood or plastic, 2 inches square are by 3 feet long, pointed at one end.

2.8.2 Guying Material

2.8.2.1 Guying Wire

12 gauge annealed galvanized steel, ASTM A580/A580M.

2.8.2.2 Guying Cable

Minimum five-strand, 3/16 inch diameter galvanized steel cable.

2.8.3 Hose Chafing Guards

New or used 2 ply 3/4 inch diameter reinforced rubber or plastic hose, black or dark green, all of same color.

2.8.4 Flags

White surveyor's plastic tape, 1/2 inch diameter PVC pipe, 6 inches long, fastened to guying wires or cables.

2.8.5 Turnbuckles

Galvanized or cadmium-plated steel with minimum 3 inch long openings fitted with screw eyes. Eye bolts must be galvanized or cadmium-plated steel with one inch diameter eyes and screw length 1-1/2 inches, minimum.

2.8.6 Deadmen

4 by 8 inch rectangular or 8 inch diameter by 36 inch long, pine wood material.

2.8.7 Metal Anchors

2.8.7.1 Driven Anchors

Malleable iron, arrow shaped, galvanized, sized as follows:

Tree Caliper	Anchor Size
2 inches and under	3 inches
3 to 6 inches	4 inches
6 to 8 inches	6 inches
8 to 10 inches	8 inches
10 to 12 inches	10 inches

2.8.7.2 Screw Anchors

Steel, screw type with welded-on 3 inch round helical steel plate, minimum 3/8 inch diameter, 15 inches long.

2.9 EDGING MATERIAL

2.9.1 Wood Edging

Redwood Cypress Western Red Cedar _____ wood edging must be free of solvent at time of delivery. Minimum 8 by 1/2 inch treated in accordance with AWPA U1 and AWPA T1 with preservatives conforming to AWPA P5 before installation. Anchoring stakes must be the same material as wood edging, 1/2 by 2 inches, 12 inches long.

2.9.2 Recycled Plastic Edging

100 percent recycled polyethylene edging, resistant to insects, termites, boring worms, splintering and rotting, and must not absorb moisture or promote bacterial growth. Minimum 1 by 6 inch, capable of bending a minimum 24 radius, integrally colored brown with slip joint connections. Anchors and stakes must be of the same manufacturer and color as the edging.

2.10 ANTIDESICCANTS

Sprayable, water insoluble vinyl-vinledine complex which produce a moisture retarding barrier not removable by rain or snow. Film must form at temperatures commonly encountered out of doors during planting season and have a moisture vapor transmission rate (MVT) of the resultant film of maximum 10 grams per 24 hours at 70 percent humidity.

2.11 WATER

Source of water to be approved by Contracting Officer and suitable quality for irrigation and must not contain elements toxic to plant life, including acids, alkalis, salts, chemical pollutants, and organic matter. Use collected storm water or graywater when available.

2.12 MYCORRHIZAL FUNGI INOCULUM

Mycorrhizal fungi inoculum must be composed of multiple-fungus inoculum as recommended by the manufacturer for the plant material specified.

2.13 SOURCE QUALITY CONTROL

The Contracting Officer will inspect plant materials at the project site and approve them. Tag plant materials for size and quality.

PART 3 EXECUTION

3.1 EXTENT OF WORK

Provide soil preparation, including soil conditioners and soil amendments prior to planting. Provide tree, shrub, vine, groundcover, seed, and sod planting, post-planting fertilizer, edging, staking, guying, weed control fabric, erosion control material, root control barrier installation, and mulch topdressing of all newly graded finished earth surfaces, unless indicated otherwise, and at all areas inside or outside the limits of construction that are disturbed by the Contractor's operations.

3.2 PREPARATION

3.2.1 Layout

Stake out approved plant material locations and planter bed outlines on the project site before digging plant pits or beds. The Contracting Officer reserves the right to adjust plant material locations to meet field conditions. Do not plant closer than 36 inches to a building wall. Provide on-site locations for excavated rock, soil, and vegetation.

3.2.2 Erosion Control

Provide erosion control and seeding with native plant species to protect slopes.

3.2.3 Soil Preparation

3.2.3.1 pH Adjuster Application Rates

Apply pH adjuster at rates as determined by laboratory soil analysis of the soils at the job site. For bidding purposes only apply at rates for the following:

Lime 40 pounds per 1000 square feet

Sulfur 5 pounds per 1000 square feet

Iron 40 pounds per 1000 square feet

Aluminum Sulfate 4 pounds per 1000 square feet

3.2.3.2 Fertilizer Application Rates

Apply fertilizer at rates as determined by laboratory soil analysis of the soils at the job site. For bidding purposes only apply at rates for the following:

Organic granular fertilizer 4 pounds per 1000 square feet.

3.2.4 Root Control Barrier

Install geotextile fabric in the soil in a vertical application. Use appropriate holding device to assure fabric position. For vertical or horizontal application, a minimum 1 inch soil cover is required over the top surface. A minimum 18 inch extension of fabric beyond the structure area to be protected is required to prevent root growth from growing around fabric edges.

3.3 PLANT BED PREPARATION

Verify location of underground utilities prior to excavation. Protect existing adjacent turf before excavations are made. Do not disturb topsoil and vegetation in areas outside those indicated on Drawings. Where planting beds occur in existing turf areas, remove turf to a depth that will ensure removal of entire root system. Measure depth of plant pits from finished grade. Depth of plant pit excavation must be as indicated and provide proper relation between top of root ball and finished grade. Install plant material as specified in paragraph PLANT INSTALLATION. Do not install trees within 10 feet of any utility lines or building walls.

3.4 PLANT INSTALLATION

3.4.1 Individual Plant Pit Excavation

Excavate pits at least twice as large in diameter as the size of ball or container to depth shown.

3.4.2 Plant Beds with Multiple Plants

Excavate plant beds continuously throughout entire bed as outlined to depth shown.

3.4.3 Handling and Setting

Move plant materials only by supporting the root ball. Set plants on hand compacted layer of prepared backfill soil mixture 6 inches thick and hold plumb in the center of the pit until soil has been tamped firmly around root ball. Set plant materials, in relation to surrounding finish grade, one to 2 to inches above depth at which they were grown in the nursery, collecting field or container. Replace plant material whose root balls are cracked or damaged either before or during the planting process.

Plant material must be set in plant beds according to the drawings. Backfill soil mixture must be placed on previously scarified subsoil to completely surround the root balls, and must be brought to a smooth and even surface, blending to existing areas.

3.4.3.1 Balled and Burlapped Stock

Backfill with prepared soil mixture to approximately half the depth of ball and then tamp and water. Carefully remove or fold back excess burlap and tying materials from the top a minimum 1/3 depth from the top of the rootball. Tamp and complete backfill, place mulch topdressing, and water. Remove wires and non-biodegradable materials from plant pit prior

to backfill operations.

3.4.3.2 Bare-Root Stock

Plant so roots are arranged in a natural position. Place roots in water a minimum of 30 minutes prior to planting. Carefully work prepared soil mixture among roots. Tamp remainder of backfill, place mulch topdressing and water.

3.4.3.3 Container Grown Stock

Remove from container and prevent damage to plant or root system.

3.4.3.4 Ground Covers and Vines

Plant after placing mulch topdressing. Do not remove plant materials from flats or containers until immediately before planting. Space at intervals indicated. Plant at a depth to sufficiently cover all roots. Start watering areas planted as required by temperature and wind conditions. Apply water at a rate sufficient to ensure thorough wetting of soil to a depth of 6 inches without run off or puddling. Smooth planting areas after planting to provide even, smooth finish.

3.4.4 Earth Mounded Watering Basin for Individual Plant Pits

Form with topsoil around each plant by replacing a mound of topsoil around the edge of each plant pit. Watering basins must be 6 inches deep for trees and 4 inches deep for shrubs. Eliminate basins around plants in plant beds containing multiple plants.

3.4.5 Weed Control Fabric Installation

Remove grass and weed vegetation, including roots, from within the area enclosed by edging. Completely cover areas enclosed by edging with specified weed control fabric prior to placing mulch layer. Overlap cut edges 6 inches.

3.4.6 Placement of Mulch Topdressing

Place specified mulch topdressing on top of weed control fabric covering total area enclosed by edging. Place mulch topdressing to a depth of 3 inches.

3.4.7 Mulch Topdressing

Provide mulch topdressing over entire planter bed surfaces and individual plant surfaces including earth mound watering basin around plants to a depth of 3 inches after completion of plant installation and before watering. Keep mulch out of the crowns of shrubs. Place mulch a minimum 2 to 3 inches away from trunk of shrub or tree. Place on top of any weed control fabric.

3.4.8 Installation of Edging

Uniformly edge beds of plants to provide a clear cut division line between planted area and adjacent lawn. Construct bed shapes as indicated. Install wood or plastic edging material as indicated. Install edging material in a perfect 4 foot diameter circle inside the 4-1/2 foot watering basin, around individual specimen trees and shrubs not planted in

a close group. Install edging with minimum one inch left above ground level.

3.4.9 Fertilization

3.4.9.1 Fertilizer Tablets

Place fertilizer planting tablets evenly spaced around the plant pits to the manufacturer's recommended depth.

3.4.9.2 Granular Fertilizer

Apply granular fertilizer as a top coat prior to placing mulch layer and water thoroughly.

3.4.10 Watering

Start watering areas planted as required by temperature and wind conditions. Apply water at a rate sufficient to ensure thorough wetting of soil to a depth of 12 inches without run off or puddling.

3.4.11 Staking and Guying

3.4.11.1 Staking

Stake plants with the number of stakes indicated complete with double strand of 12 gage guy wire as detailed. Attach guy wire half the tree height but not more than 5 feet high. Drive stakes to a depth of 2-1/2 to 3 feet into the ground outside the plant pit. Do not injure the root ball. Use hose chafer guards where guy wire comes in contact with tree trunk.

3.4.11.2 Guying

Guy plants as indicated. Attach three strands of guying wire around the tree trunk at an angle of 45 degrees at approximately 1/2 of the trunk height. Protect tree trunks with chafing guards where guying wire contacts the tree trunk. Anchor guys to deadmen wood blocks wood ground stakes malleable iron anchors steel screw anchors. Fasten flags to each guying wire approximately 2/3 of the distance up from ground level. Provide turnbuckles as indicated.

3.4.11.3 Chafing Guards

Use hose chafing guards, as specified where guy wire will contact the plant.

3.4.11.4 Deadmen

Place deadmen minimum 18 inches below ground surface. Place equal distance from tree trunk and around the plant pit.

3.4.11.5 Wood Ground Stakes

Drive wood ground stakes into firm ground outside of plant pit with top of stake flush with ground. Place equal distance from tree trunk and around the plant pit.

3.4.11.6 Iron Anchors

Drive malleable iron anchors into firm ground outside of plant pit a minimum 30 inches below finish grade. Place equal distance from tree trunk and around the plant pit.

3.4.11.7 Steel Screw Anchors

Insert steel screw anchors as recommended in manufacturer's data. Place equal distance from tree trunk and around the plant pit.

3.4.11.8 Flags

Securely fasten flags on each guy wire andcable approximately two-thirds of the distance up from ground level.

3.4.12 Pruning

Prune in accordance with safety requirement of TCIA Z133.

3.4.12.1 Trees and Shrubs

Remove dead and broken branches. Prune to correct structural defects only. Retain typical growth shape of individual plants with as much height and spread as practical. Do not cut central leader on trees. Make cuts with sharp instruments. Do not flush cut with trunk or adjacent branches. Collars must remain in place. Pruning must be accomplished by trained and experienced personnel and must be accordance with TCIA A300P1.

3.4.12.2 Wound Dressing

Do not apply tree wound dressing to cuts.

3.5 RESTORATION AND CLEAN UP

3.5.1 Restoration

Turf areas, pavements and facilities that have been damaged from the planting operation must be restored to original condition at the Contractor's expense.

3.5.2 Clean Up

Excess and waste material must be removed from the installed area and must be disposed offsite at an approved landfill, recycling center, or composting center. Separate and recycle or reuse the following landscape waste materials: nylon straps, wire, ball wrap, burlap, wood stakes, _____. Adjacent paved areas must be cleared.

-- End of Section --

SECTION 33 01 30.16

TV INSPECTION OF SEWER LINES
11/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. DEPARTMENT OF DEFENSE (DOD)

DODI 4150.07 (2019) DOD Pest Management Program

1.2 DEFINITIONS

1.2.1 CCTV Video

CD or DVD storage media containing the recorded video.

1.2.2 Cleaning

To remove soil or solid deposited materials from a pipe segment when the pipe is less than half full of deposited materials.

1.2.3 Defects

Defects in the pipe, manholes, structures, and services include cracks, separation of joints, collapsed pipe, grade irregularities, leaks, roots, grease buildup, offset joints, reverse grades, obstructions, delamination, missing pipe, restrictions, fractures and similar structural irregularities.

1.2.4 Entry Point

The leading edge of the access point or the manhole or structure wall where the pipe segment begins. Only the pipe is video inspected from manhole or structure wall to manhole or structure wall and does not include any portion of the manhole or structure.

1.2.5 Exit Point

The point where the downstream access manhole or structure wall is encountered. Only the pipe is video inspected from manhole or structure wall to manhole or structure wall and does not include any portion of the manhole or structure.

1.2.6 Heavy Cleaning

To remove soil or solid deposited materials from a pipe segment when the materials in the pipe are between half full to full.

1.2.7 Hydraulically Propelled Cleaning Tools

Tools that depend upon water pressure to provide their cleaning force.

1.2.8 National Association of Sewer Service Companies (NASSCO)

National Association of Sewer Service Companies (NASSCO) identifies the generally accepted industry standards for CCTV inspection, observation coding, and certification.

1.2.9 Pipe Segment

The length of pipe from entry point to exit point along the main or service.

1.2.10 Pipeline Assessment and Certification Program (PACP)

A CCTV Inspection standardization certification and observation coding system sponsored by NASSCO.

1.2.11 Point Repair

The location of a failure where a repair is has occurred.

1.2.12 Post-Installation CCTV (Post-TV)

Post-TV inspection is used to determine the slip lining of sanitary or storm sewers has been completed in accordance with the contract documents.

1.2.13 Pre-Installation CCTV (Pre-TV)

Pre-TV inspection is a video inspection of existing sewer lines to confirm cleaning activities, locations of service connections, and identify defects in the existing sewer system infrastructure prior to any work being performed.

1.2.14 Re-TV Inspection

Upon the completion of repairs made after performing a Post-TV Inspection or Warranty TV inspection, the mains or services are re-inspected by performing a Re-TV inspection. Also, refers to rework for a TV-Inspection that has video interruptions, gaps, or is not continuous.

1.2.15 TV Inspection Log

Information collected and recorded by the CCTV operator for each CCTV inspection effort and includes pertinent information for the respective inspection section; such as, date of inspection, location of site, CCTV technician, direction of CCTV inspection with manhole or structure identifiers, weather conditions, pipe size(s), pipe materials, conditions found, locations where the conditions were found.

1.2.16 Warranty CCTV (Warranty-TV)

Warranty-TV inspection is used to determine the slip lining of sanitary or storm sewers does not have any defects present, remains in compliance with project specifications and Post-TV inspection.

1.3 ADMINISTRATIVE REQUIREMENTS

1.3.1 Disposal Plan

Submit a disposal plan prior to performing any work that might generate waste materials. Include a complete description of the materials that are expected to be encountered and their proposed disposal sites. No changes to the disposal plan will be made without prior written acceptance by the Contracting Officer.

1.3.2 Sewage Handling Permit

Prior to commencing application of herbicide, obtain and maintain a valid State sewage handling permit and permits required by local jurisdictions. Submit a copy of this permit to the Contracting Officer prior to beginning any cleaning or pump and haul operations.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-01 Preconstruction Submittals

Traffic Control Plan; G

Disposal Plan; G

Sewage Handling Permit; G

SD-03 Product Data

Cleaning Products; G

SD-07 Certificates

CCTV Technician's Qualifications; G

Pre-TV Inspection; G

Post-TV Inspection; G

Warranty-TV Inspection; G

RE-TV Inspection; G

SD-11 Closeout Submittals

Records of Disposals

1.5 QUALITY CONTROL

1.5.1 Regulatory Requirements

Comply with DODI 4150.07 for requirements on Contractor's licensing, certification, and record keeping. Maintain daily records using the Pest Management Maintenance Record, DD Form 1532-1, or a computer generated equivalent, and submit copies of records when requested by the Contracting

Officer. These forms may be obtained from the Armed Forces Pest Management Board web site: https://www.acq.osd.mil/eie/afpmb/docs/standardlists/dd1532-1.xlsm

1.5.2 CCTV Technician's Qualifications

Provide a CCTV technician with three years of total experience with the CCTV technology. Submit a current PACP Operator certification for personnel performing closed circuit television inspection and pipeline assessments.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

TV inspection of sewer pipelines encompasses cleaning, heavy cleaning, CCTV inspection and video recording of the existing sanitary or storm sewer mains included in the contract documents. This work includes by-pass pumping or diversion of sanitary sewer, sound reduction enclosure of by-pass pump, inspection logs, video requirements, permits, traffic control and the legal disposal of materials removed from the mains. It is typically used in coordination with slip lining existing piping.

It includes the mechanical equipment used to clean and dispose of the materials found in sewer pipes and structures, CCTV cameras and recording devices used to record the internal conditions of non-pressurized sewer piping.

2.2 EQUIPMENT

2.2.1 Cleaning Equipment

Utilize mechanically powered equipment necessary for the proper rodding, bucketing, brushing, root cutting, and flushing of the sewers, including a heavy duty power rodding machine that is compatible with the cleaning to be performed.

2.2.1.1 Rodding

Provide rodding equipment capable of rodding distances of up to 1000 feet in one set-up and having the following capabilities:

a. The ability to spin the rod either clockwise or counter-clockwise, and be able to be pushed straight out or pulled back without rotating the machine.

b. The capability of pulling pipe-size swabs or brushes back through the pipeline for cleaning and flushing purposes.

2.2.1.2 Bucket Machine

Provide heavy-duty bucket machines for use on dragline work to clean the pipeline with buckets, brushes, scrapers, swabs or other similar devices in order to effectively remove debris and provide a clean sewer for the CCTV inspection, repair, or lining activities.

2.2.1.3 Hydraulic Flusher

Provide hydraulic high-pressure sewer cleaners used for sewer cleaning,

specifically designed and constructed for such cleaning, that have a minimum usable water capacity of 600 gallons and a pump capable of delivering at least 30 gallons per minute (gpm) at 100 psi and having the following capabilities:

a. Pressure regulator nozzle capable of adjustment from 1 psi to 1500 psi.

b. Constructed for ease of use and safety of operation with two or more high-velocity nozzles capable of producing a scouring action from 15 to 45 degrees in lines designated to be cleaned.

c. A high-velocity gun for washing and scouring the manhole or structure walls and floor capable of producing flows from a fine spray to a solid stream.

d. Carry its own water tank, auxiliary engines, pumps, and hydraulically driven hose reel.

2.2.1.4 Sanitary Sewer Cleaning Equipment

Provide movable dam type hydraulically propelled equipment constructed in such a way that a portion of the dam may be collapsed at any time during the cleaning operation to protect against flooding of the sanitary sewer and having the following capabilities:

a. A movable dam equal in diameter to the pipe being cleaned.

b. A flexible scraper around the periphery to ensure the removal of grease.

Sewer cleaning balls or other equipment, which cannot be collapsed, are not allowed when cleaning sanitary sewer.

2.2.2 CCTV Equipment

Provide a video system capable of producing a sharply focused, well-lit and color balanced picture in accordance with the following requirements:

2.2.2.1 Pipe Inspection Camera and Associated Equipment

a. Provide a pipe inspection camera system that produces a video using a pan and tilt, radial viewing, that pans a minimum of 275 degrees and rotates 360 degrees. Illumination sensitivity of 3 Lux or less and a minimum of 460 lines of resolution is required.

b. Utilize video cameras specifically designed and constructed for CCTV inspection.

c. Provide a camera that is operative in 100 percent humidity conditions.

d. Provide a camera with an accurate footage counter that displays on the monitor the exact distance of the camera to the nearest 1/10 of a foot.

e. Provide a camera with a height adjustment so that the camera lens is typically centered in the pipe, or higher depending on water levels in the pipe.

f. Provide equipment that will produce digital color images and allows the CCTV technician to remotely balance the iris and color to produce

a clear and true video of the pipeline.

g. Provide lighting for the camera that is suitable to provide a clear color picture of the entire periphery of the pipe.

h. Provide a reflector in front of the camera as necessary to enhance the lighting on dark or large diameter pipes.

i. Provide an accompanying computer and recording device capable of projecting and recording the facility location, project name, Contractor's name, date, line size, material type, line identification, manhole or structure ID numbers and ongoing footage counter onto the video screen.

2.3 MATERIALS

2.3.1 Cleaning Products

Select cleaning products that do not present a health and safety concern, are allowed for use in the sewer system according to Federal and State regulations, will not adversely affect the water quality of the water being conveyed in the sewer system, are suitable for the wastewater treatment plant and the climatic conditions at the project site. Submit manufacturer's label and SDS for the cleaning products proposed for use.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Traffic Control

a. Submit a detailed Traffic Control Plan to the Contracting Officer at least 10 days in advance when the manholes used to perform the TV inspection are located in or adjacent to the road. Comply with all applicable State Highway, Local and Installation requirements when preparing the traffic control plan.

b. Provide labor, signs, barricades, cones, arrow boards, flaggers, and any additional equipment necessary to complete the work.

3.1.2 Sewer Line Cleaning

Immediately prior to conducting CCTV activities, thoroughly clean the segment of sewer pipe to be video inspected. Clean the segments using hydraulically propelled, high-velocity jet, or mechanically powered equipment.

a. During cleaning and preparation operations, undertake precautions to protect the sewer system and property from damage. Restore property damaged as a result of such cleaning and preparation operations to pre-existing conditions.

b. During the course of normal cleaning operations immediately report pre-existing damage such as broken or missing pipe to the Contracting Officer.

c. When hydraulically propelled cleaning tools or tools which retard the flow in the sewer line are utilized, take precautions to ensure that the water pressure created does not damage or cause flooding on the

adjacent site.

d. Maintain access to fire hydrants for the purpose of fire protection at all times.

e. If cleaning of an entire sewer section cannot be successfully performed from one manhole or structure, set up the equipment on the other entry or exit point and attempt cleaning again.

f. If successful cleaning cannot be performed from the opposite end or the equipment fails to traverse the entire pipeline section, cease cleaning those specific sewer sections, notify the Contracting Officer and CCTV inspect both sides of the pipeline section to determine the cause of the blockage.

3.1.2.1 Sanitary Sewer Cleaning

Minimize the interruptions to the existing flows to perform the cleaning of the sewers. Prevent sewage backups and immediately clear back-ups resulting from the cleaning operations. When possible, utilize the flow in the sewer system to provide the necessary pressure for the hydraulic cleaning devices. Return sewage diverted during cleaning operations to the sanitary system and do not discharge onto any surface, or into any water body or storm drain system.

3.1.3 Manhole or Structure Cleaning

Clean concrete and masonry surfaces prior to CCTV inspection. Completely remove grease, laitance, loose bricks, mortar, unsound concrete, loose or damaged wall mounted steps (cut flush with wall), and other materials.

Utilize water blasting (minimum 1200 psi) with compatible nozzles as the primary method of cleaning. It is acceptable to use other methods of cleaning such as concrete cleaners, degreasers or mechanical means to clean the surfaces. Thoroughly rinse, scrub, and neutralize the surfaces in order to remove cleaning agents and their reactant products. Do not allow material to pass to pipeline sections, which could adversely affect water quality, cause stoppages, accumulations of sand in wet wells, or damage to pumping equipment.

3.1.4 Flow Control

Reduce the flow depth to allow a minimum of 80 percent of the pipe wall to be displayed at all times during inspection so that defects, features, and other notable information can be collected.

3.1.4.1 Flow Reduction

Flow depth reduction can be accomplished by:

a. Providing bypass pumping.

b. High-pressure jet nozzle.

c. Plugging or by pulling the camera with a swab.

d. Performing the CCTV inspection during periods of minimal flow.

3.1.4.2 Floating the Camera

Video inspection performed while floating the camera is not acceptable. Lower water levels as indicated in paragraph FLOW CONTROL.

3.1.5 Root Removal

Remove roots in the designated sewer sections and manholes or structures. Ensure complete removal of roots to the joints. Use mechanical equipment that can be operated remotely, such as rodding machines, bucket machines, winches using root cutters and porcupines, and equipment such as high-velocity jet cleaners. Capture and remove roots from the sewerline at the downstream manhole or structure.

3.1.6 Material Removal and Disposal

Remove sludge, dirt, roots, grease, and other solid or semi-solid material resulting from cleaning operations at the downstream manhole or structure of the section being cleaned.

3.1.6.1 Dams or Weirs

When hydraulic cleaning equipment is used, place dam or weir in the downstream manhole or structure to trap such materials. Do not allow material to pass from pipeline section to pipeline section, which could cause stoppages, accumulations of sand in wet wells, or damage to pumping equipment.

3.1.6.2 Sludge and Debris Storage

Under no circumstances is sludge or other debris removed during these operations to be stored, dumped or spilled into streets, ditches, storm drains, or other sanitary sewer systems.

a. Dispose of solids and semi-solids resulting from the cleaning operations no less often than the end of each work day in accordance with the approved Disposal Plan.

b. Under no circumstances will debris be allowed to accumulate on the work site beyond the end of each work day, except in totally enclosed containers and as acceptable by the Contracting Officer.

c. Continuously maintain the haul route and work areas neat, clean, and reasonably free of odor. Cleanup any spill which occurs during the transport of cleaning or surface preparation by-products. Perform the cleanup of any such material pursuant to this Contract and in accordance with applicable law and environmental regulations.

d. Immediately notify the Contracting Officer of any spill and begin clean up any such spill or waste.

e. The Government will charge to the Contractor for any costs incurred or penalties imposed upon the Government as a result of the spill, dump or discard.

f. Under no circumstances is this material to be discharged into the waterways or any place other than where authorized to do so in accordance with the approved Disposal Plan.

3.1.6.3 Hauling of Waste Material

Provide vehicles hauling such waste material that meet the following requirements:

a. Provide transport vehicles of the type(s) approved for this application by the jurisdictions where those vehicles will be operated in the performance of activities associated with this Contract.

b. Provide transport vehicles with watertight bodies equipped and fitted with seals and covers to prohibit material spillage or drainage.

c. Clean vehicles to prevent deposits of material on roadways.

d. Load vehicles within legal weight limits and operate safely within traffic speed regulations.

e. The routes used for the conveyance of this material on a regular basis is subject to approval by the local governing bodies having jurisdiction over such routes.

3.2 APPLICATION

3.2.1 Inspection of Sewer Lines

Inspection of sewer lines applies to Pre-TV inspection, Post-TV inspection, RE-TV inspection and Warranty-TV inspection. Perform inspections of sewer lines in the presence of the Contracting Officer.

3.2.1.1 Communication

Set up hand operated radios, telephones, or other means of communication between the entry and exit points being inspected to ensure uninterrupted communication between members of the CCTV crew when manually operated winches are used to pull the television camera through the line.

3.2.1.2 Flush Main

Introduce a minimum of 1000 gallons of clear, potable water into the upstream manhole or structure or access structure of the mains to be CCTV inspected just prior to inserting the camera. The Contractor is responsible for collecting and disposing of the water in accordance with the approved disposal plan.

3.2.1.3 Camera Operation

Set counter to 0.00 feet at the entry point, which is the beginning manhole or structure wall. Move the camera through the line in either direction at a moderate speed, stopping to permit proper documentation of the sewer's condition or service connection locations. In no case will the camera be operated at a speed greater than 30 feet per minute. Slowly pan and tilt the camera at the beginning and ending manhole, structure connections, service connections, joints, visible defects, and pipe arterial transitions. Provide a full 360 degree view of the pipe, joints, and service connections.

Utilize manual winches, power winches, cable, powered rewinds or other devices that do not obstruct the camera view or interfere with camera operation or CCTV inspection of the pipe conditions as the camera is moved

through the sewer line.

3.2.1.3.1 Recording Defects

During CCTV inspection, temporarily stop the camera at each defect or feature along the line.

3.2.1.4 Documentation of CCTV Inspection

Documentation of CCTV inspection applies to Pre-TV inspection, Post-TV inspection, RE-TV inspection and Warranty-TV inspection.

Utilize a data logger and reporting system that is PACP compliant to make a video and audio recording of the CCTV inspections. Submit video recordings, inspection logs, and digital photographs as indicated in the following sub-paragraphs.

3.2.1.4.1 Video Recordings

Provide a color video showing the completed work and document the inspection on a digital recorder. Capture inspection video in either MPEG-4 or Windows Media Video (WMV) format with a minimum resolution of 352 x 240 pixels and an interlaced frame rate at a minimum of 24 frames per second. Save video on CD or DVD. However, the CCTV inspection video of a segment must be wholly contained on a single CD or DVD. The video recording must meet the following requirements:

a. Provide a continuous and uninterrupted recorded video for the pipe segment being examined. Include the official project title, Contracting party, Contractor's name, street name, manhole or structure ID numbers, direction of video and flow, date and time video was recorded, continuous counter text, pipe size and material, material changes in the pipe segment, audio and text call outs of laterals, fixtures and problem areas in the recorded video.

b. Include an audio track recorded by the CCTV technician during the actual inspection work with a description of the parameters of the line being inspected on the video recordings. The audio may be from the voice of the CCTV technician or it may be computer generated.

c. Include the location, pipe diameter, pipe material, defects, service lateral locations and any unusual conditions found in PACP format.

d. Submit labeled CDs or DVDs of the video inspections.

e. Without exception, CCTV inspections must be continuous without video interruption or gaps for pipe segments.

f. Clean, flush, and RE-TV pipe segments with video interruptions or gaps.

3.2.1.4.2 TV Inspection Logs

Submit computer generated records that clearly show the location and orientation in relation to an adjacent manhole or structure of each infiltration point observed during the inspection.

Record other points of significance such as locations and orientations of service connections, missing or broken pipe, roots, the presence of grease, scale or corrosion, bellies, fractures, cracks, and other

discernible features using PACP designations.

3.2.1.4.3 Digital Photographs

Submit JPEG images at a minimum resolution of 640 x 480 pixels. Save digital photographs in JPEG file format on CD or DVD. Document noted defects and lateral connections as color digital files and hard copy print-outs. Photo logs are to accompany each photo submitted.

3.2.2 Pre-TV Inspection

Immediately after cleaning has been performed, complete a Pre-TV inspection, in accordance with paragraph INSPECTION OF SEWER LINES. Submit Pre-TV inspection documentation in accordance with paragraph DOCUMENTATION OF CCTV INSPECTION.

3.2.3 Post-TV Inspection

Immediately after visual, deflection, pressure and leak testing and service reconnections are complete on a pipe segment, complete Post-TV inspection accordance with paragraph INSPECTION OF SEWER LINES. Submit Post-TV inspection documentation in accordance with paragraph DOCUMENTATION OF CCTV INSPECTION. Provide post installation inspection documentation within 10 working days of the liner installation. The Contracting Officer may, at his or her discretion, suspend any further installation of lining materials if post-installation documentation is not submitted within 10 working days. As a result of this suspension, no additional working days will be added to the Contract, nor will any adjustment be made for increase in cost.

3.2.3.1 Post-TV Defects

If defects are found in the mains or services during the Post-TV inspection make repairs according to the specifications. RE-TV all repairs accordance with paragraph INSPECTION OF SEWER LINES. Provide additional RE-TV inspections of complete pipe segments as follows:

a. Perform a RE-TV inspection of the complete pipe segment. If no additional defects are found in the Re-TV inspections, then the Post-TV inspection is complete.

b. If defects are found in these additional inspections make repairs according to the specifications and provide Re-TV inspection for the complete pipe segment.

c. If defects are found in these additional inspections make repairs according to the specifications and Re-TV the repaired pipe segments until no Post-TV defects are found.

3.2.4 Warranty-TV Inspection

Submit Warranty-TV Inspection no later than 30 days prior to the expiration of the warranty. Comply with paragraphs INSPECTION OF SEWER LINES and DOCUMENTATION OF CCTV INSPECTION. Complete Warranty-TV inspections in the presence of the Contracting Officer. The Contracting Officer has the option to select the pipe segments for the Warranty-TV inspection. Comply with the following requirements:

a. Provide a complete pipe segment Warranty-TV inspection of pipe

segments where a liner repair was performed during Post-TV Inspection.

b. Provide a complete pipe segment Warranty-TV inspection of pipe segments where a point repair was performed.

c. Provide a Warranty-TV inspection of at least one full pipe segment of each size and type of slip lining installed.

d. Provide a Warranty-TV inspection of at least 10 percent of the total length of all pipe segments.

All of Warranty-TV inspections above may be included to satisfy the percentage of total length requirement. If no defects are found in the mains and services in the above minimum pipe segments inspected, then the Warranty-TV inspection is complete.

3.2.4.1 Warranty-TV Defects

If defects are found in the mains or services during the Post-TV inspection make repairs according to the specifications. RE-TV all repairs. Provide additional Warranty-TV inspections of complete pipe segments as follows:

a. Warranty-TV inspect an additional 15 percent of the footage based on the length of the total project. If no additional defects are found in the additional Warranty-TV inspections, then the Warranty-TV inspection is complete.

b. If defects are found in these additional inspections make repairs according to the specifications, RE-TV all repairs and provide Warranty-TV inspections for the remaining pipe segments in the project.

c. If defects are found in these additional inspections make repairs according to the specifications and Re-TV the repaired pipe segments.

3.2.5 RE-TV Inspection

After repairs are made to a main or service, complete RE-TV inspection accordance with paragraph INSPECTION OF SEWER LINES and DOCUMENTATION OF CCTV INSPECTION.

3.3 FIELD QUALITY CONTROL

3.3.1 Inspection

3.3.1.1 Technical Representative

Provide a technical representative who is a DOD certified pesticide applicator or Pest Management Quality Assurance Evaluator (QAE)/Performance Assessment Representative (PAR). The technical representative must be present at all meetings concerning root removal and during treatment application. Contact the Integrated Pest Management Coordinator prior to starting work.

3.4 CLOSEOUT ACTIVITIES

3.4.1 Sewer Cleaning

Submit copies of Records of Disposals indicating the disposal site, date,

amount, and a brief description of the materials disposed.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 05 07.13

UTILITY DIRECTIONAL DRILLING
02/24

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO T 180	(2017) Standard Method of Test for Moisture-Density Relations of Soils Using a 4.54-kg (10-lb) Rammer and a 457-mm (18-in.) Drop

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C900	(2016) Polyvinyl Chloride (PVC) Pressure Pipe, and Fabricated Fittings, 4 In. Through 60 In. (100 mm Through 1,500 mm)

ASTM INTERNATIONAL (ASTM)

ASTM D1784	(2020) Standard Specification for Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D1785	(2015; E 2018) Standard Specification for Poly(Vinyl Chloride) (PVC), Plastic Pipe, Schedules 40, 80, and 120

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI Z535.1	(2017) Safety Colors

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Statement of Qualifications and Records; G

SD-03 Product Data

Pipe; G

Drilling Fluids; G

Additives; G

Tracer Wire; G

SD-05 Design Data

Secondary Containment Plan; G

SD-06 Test Reports

Soil Test Data

SD-07 Certificates

Drill Rod

SD-11 Closeout Submittals

Record Drawings

Complete Work Logs of Guided Directional Drill Operations

1.3 QUALITY CONTROL

1.3.1 Qualifications

Ensure that the field supervisor and workers assigned to this project are experienced in work of this nature and have successfully completed similar projects of similar length, pipe type, pipe size, and soil type using directional drilling in the last three (3) years. As part of the bid submission, submit project descriptions which include, at a minimum, a listing of the location(s), date of project(s), owner, pipe type and material, size installed, length of installation, manufacturer of equipment used, and other information relevant to the successful completion of the project.

1.3.2 Safety

Include in directional drilling equipment machine safety requirements a common grounding system to prevent electrical shock in the event of underground electrical cable strike. Ensure the grounding system connects all pieces of interconnecting machinery; the drill, mud mixing system, drill power unit, drill rod trailer, operator's booth, worker grounding mats, and any other interconnected equipment to a common ground. Equip the drill with an "electrical strike" audible and visual warning system that notifies the system operators of an electrical strike.

1.4 DELIVERY, STORAGE, AND HANDLING

Inspect materials delivered to the site for damage. All materials found during inspection or during the progress of work to have cracks, flaws, surface abrasions, or other defects will be rejected. Remove defective materials from the job site.

Protect stored piping from moisture and dirt and place on level surface. Store plastic piping protected from direct sunlight.

PART 2 PRODUCTS

2.1 EQUIPMENT

2.1.1 Drill Rod

Select the appropriate drill rod to be used. Submit certified statement that the drill rod has been inspected and is in satisfactory condition for its intended use.

2.2 MATERIALS

2.2.1 Pipe

2.2.1.1 Fusible PVC

Install 5 inch (nominal) diameter fusible polyvinyl chloride pipe , Schedule 40 conforming to ASTM D1785. Provide pipe made from PVC compound meeting or exceeding cell classification 12454 per ASTM D1784. Provide fusible polyvinyl chloride pipe with plain ends. Pipe is orange in color.

Use butt fusion jointing method for plain end PVC pipe. Comply with AWWA C900 for butt fusion joints.

2.2.2 Drilling Fluids

Use a high quality bentonite drilling fluid to ensure hole stability, cuttings transport, bit and electronics cooling, and hole lubrication to reduce drag on the drill pipe and the product pipe. Use only fluid with a composition which complies with all Federal, State, and local environmental regulations.

2.2.3 Additives

Use admixtures as required to address soil conditions and water conditions such as water hardness, acidity, and alkalinity.

2.2.4 Tracer Wire

Use a continuous sheathed solid conductor copper wire line, minimum #12 AWG. Sheathing must be color coded to match the utility.

PART 3 EXECUTION

3.1 EXAMINATION

a. Soil Test Data

Provide written documentation of conformance with AASHTO T 180.

3.2 INSTALLATION

Ensure all utilities are located and clearly marked prior to start of excavation or drilling.

3.2.1 Drill Set-Up

Design and construct the drill entrance and exit pits.

3.2.1.1 Drilling Fluids

Mix the bentonite drilling fluid with potable water (of proper pH) to ensure no contamination is introduced into the soil during the drilling, reaming, or pipe installation process. Make any required additive adjustments.

3.2.2 Drill Entrance and Exit Pits

Drill entrance and exit pits are required. Maintain at minimum size to allow only the minimum amount of drilling fluid storage prior to transfer to mud recycling or processing system or removal from the site.

Do not allow drilling mud to flow freely on the site or around the entrance or exit pits. Remove spilled mud and restore ground to original condition..

Drilling near wetlands or water courses requires secondary containment to prevent drilling fluids from entering the wetlands. Secure written approval of a secondary containment plan from the Contracting Officer.

3.2.3 Drill Entrance and Exit Angle

Ensure entrance and exit angles and elevation profile maintains adequate cover to reduce risk of drilling fluid breakouts and ground exit occurs as specified herein. Ensure that entrance and exit angles generate pullback forces that do not exceed 7.5 percent strain on the fusible polyvinyl chloride pipe.

3.2.4 Pilot Hole

The type and size of the pilot string cutting head and the diameter of the drill pipe are at the Contractor's discretion.

Drill the pilot hole along the path shown on the plan and profile drawings. Pilot hole tolerances are as follows:

a. Vertical Tolerance: Provide minimum cover below channel bottom as specified on the plans. Pilot hole may go deeper if necessary to prevent breakout.

b. Horizontal Tolerance: Plus or minus - 60 inches from the centerline of the product pipe.

c. Curve Radius: No curve is acceptable with a radius less than 1,000 feet.

d. Entry Point Location: Make pilot hole entry point within plus or minus - 60 inches of the location shown on the drawings or as directed by the Contracting Officer in the field.

e. Exit Point Location: Make the exit point location within plus/minus - 60 inches of the location shown on the drawings or as directed by the Contracting Officer in the field.

f. Mandatory pipeline cover requirements are as shown on the drawings or as specified.

3.2.5 Guidance Systems

Allow walkover guidance systems where suitable for this project; use a magnetic survey tool locator installed behind the pilot string cutting head and an electric grid (tru-tracker) system for this project; shorter bores not under water ways. Ensure proper calibration of all equipment before commencing directional drilling operation.

3.2.6 Reaming

Conduct reaming operations at the Contractor's discretion. Determine the type of back reamer to be utilized by the type of subsurface soil conditions that are encountered during the pilot hole drilling operation. The reamer type is at the Contractor's discretion.

3.2.7 Pull Back

Fully assemble the entire pipeline to be installed via direction drill prior to commencement of pull back operations. Install a continuous length of tracer wire for the full length of each run of nonmetallic pipe in accordance with ANSI Z535.1. Attach wire to top of pipe in such a manner that it will not be displaced during construction operations.

Support the pipeline during pullback operations in a manner to enable it to move freely and prevent damage. Install the pipeline in one continuous pull.

Minimize torsion stress by using a swivel to connect the pull section to the reaming assembly.

Maximum allowable tensile force imposed on the pull section is not to exceed 90 percent of the pipe manufacturer's safe pull (or tensile) strength. If the pull section is made up of multiple pipe size or materials, the lowest safe pull strength value governs and the maximum allowable tensile force is not to exceed 90 percent of this value.

Minimize external pressure during installation of the pullback section in the reamed hole. Replace damaged pipe resulting from external pressure at no cost to the Government. Buoyancy modification is at the discretion of the Contractor.

3.2.8 Drilling Fluids Disposal

Collect drilling fluid returns in the entrance pit, exit pit, or spoils recovery pit. Immediately clean up any drilling fluid spills or overflows from these pits.

Dispose of fluids in a manner that is in compliance with all permits and applicable Federal, State, and local regulations. Disposal of the drilling fluids may occur on approved land owned by the Government subject to written approval from the Contracting Officer. Spread the drilling slurry over the Government-approved disposal area and plow into the soil.

Conduct disposal in compliance with all relative environmental regulations, right-of-way and work space agreements, and permit requirements.

3.2.9 Connection of Product Pipe to Pipeline

After the product pipe has been successfully installed, allow the product pipe to recover for 24 hours prior to connection of the pipeline. Ensure that a sufficient length of the product pipe has been pulled through the hole so that the pull-nose is not pulled back into bore hole due to stretch recovery of the product pipe.

3.3 FIELD QUALITY CONTROL

3.3.1 Field Tests

Perform field tests and provide labor, equipment, and incidentals required for testing. Submit test results, identifying any results that do not meet requirements, to the Contracting Officer within four days of test completion. Provide corrective action and retest pipe not meeting requirements. Provide corrective action as recommended by the pipe manufacturer and subject to approval by the Contracting Officer.

3.4 CLOSEOUT ACTIVITIES

Immediately upon completion of work, remove all rubbish and debris from the job site. Remove all construction equipment and implements of service leaving the entire area involved in a neat condition acceptable to the Contracting Officer.

Immediately clean "blow holes" or "breakouts" of drilling fluid to the surface and return the surface area to its original condition. Dispose of all drilling fluids, soils, and separated materials in compliance with Federal, State, and local environmental regulations.

Provide a post-construction fusion report including the following data for each fusible connection:

a. Pipe Size and Thickness

b. Machine Size

c. Fusion Technician Identification

d. Job Identification

e. Fusion Joint Number

f. Fusion, Heating, and Drag Pressure Settings

g. Heat Plate Temperature

h. Time Stamp

i. Heating and Cool Down Time of Fusion

j. Ambient Temperature

Submit an electronic copy and three hard copies of the record drawings to the Contracting Officer within five days after completing the pull back. Include in the record drawings a plan, profile, and all information recorded during the progress of the work. Clearly tie the record drawings

to the project's survey control. Maintain, and submit upon completion, signed complete work logs of guided directional drill operations.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 11 00

WATER UTILITY DISTRIBUTION PIPING
02/18, CHG 1: 02/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B1.20.1	(2013; R 2018) Pipe Threads, General Purpose (Inch)
ASME B1.20.3	(1976; R 2013) Dryseal Pipe Threads (Inch)
ASME B16.18	(2021) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.26	(2024) Cast Copper Alloy Fittings for Flared Copper Tubes

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA B300	(2024) Hypochlorites
AWWA B301	(2024) Liquid Chlorine
AWWA C104/A21.4	(2022) Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water
AWWA C110/A21.10	(2021) Ductile-Iron and Gray-Iron Fittings
AWWA C111/A21.11	(2017) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C151/A21.51	(2017) Ductile-Iron Pipe, Centrifugally Cast
AWWA C153/A21.53	(2019) Ductile-Iron Compact Fittings for Water Service
AWWA C500	(2019) Metal-Seated Gate Valves for Water Supply Service
AWWA C502	(2018) Dry-Barrel Fire Hydrants
AWWA C503	(2021) Wet-Barrel Fire Hydrants
AWWA C504	(2015) Standard for Rubber-Seated Butterfly Valves
AWWA C508	(2017) Swing-Check Valves for Waterworks Service, 2 In. Through 48-In. (50-mm

Through 1,200-mm) NPS

AWWA C509 (2015) Resilient-Seated Gate Valves for Water Supply Service

AWWA C512 (2015) Air-Release, Air/Vacuum, and Combination Air Valves for Water and Wastewater Service

AWWA C515 (2020) Reduced-Wall, Resilient-Seated Gate Valves for Water Supply Service

AWWA C600 (2017) Installation of Ductile-Iron Mains and Their Appurtenances

AWWA C605 (2021) Underground Installation of Polyvinyl Chloride (PVC) and Molecularly Oriented Polyvinyl Chloride (PVCO) Pressure Pipe and Fittings

AWWA C651 (2023) Standard for Disinfecting Water Mains

AWWA C655 (2009) Field Dechlorination

AWWA C700 (2020) Cold-Water Meters - Displacement Type, Metal Alloy Main Case

AWWA C800 (2021) Underground Service Line Valves and Fittings

AWWA M6 (2012) Water Meters - Selection, Installation, Testing, and Maintenance

AWWA M9 (2008; Errata 2013) Manual: Concrete Pressure Pipe

AWWA M23 (2020) Manual: PVC Pipe - Design and Installation - Third Edition

AWWA M41 (2009; 3rd Ed) Ductile-Iron Pipe and Fittings

ASTM INTERNATIONAL (ASTM)

ASTM A48/A48M (2003; R 2021) Standard Specification for Gray Iron Castings

ASTM B32 (2020) Standard Specification for Solder Metal

ASTM B61 (2015; R 2021) Standard Specification for Steam or Valve Bronze Castings

ASTM B62 (2017; R 2025) Standard Specification for Composition Bronze or Ounce Metal Castings

ASTM B88 (2022) Standard Specification for Seamless Copper Water Tube

ASTM B584	(2022) Standard Specification for Copper Alloy Sand Castings for General Applications
ASTM C94/C94M	(2022a) Standard Specification for Ready-Mixed Concrete
ASTM F1674	(2011) Standard Test Method for Joint Restraint Products for Use with PVC Pipe
ASTM F3190	(2021) Standard Practice for Heat Fusion Equipment (HFE) Operator Qualification on Polyethylene (PE) and Polymide (PA) Pipe and Fittings

MANUFACTURERS STANDARDIZATION SOCIETY OF THE VALVE AND FITTINGS INDUSTRY (MSS)

MSS SP-80	(2019) Bronze Gate, Globe, Angle, and Check Valves

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 24	(2022) Standard for the Installation of Private Fire Service Mains and Their Appurtenances

NSF INTERNATIONAL (NSF)

NSF/ANSI 14	(2024) Plastics Piping System Components and Related Materials
NSF/ANSI 61	(2022) Drinking Water System Components - Health Effects

U.S. DEPARTMENT OF DEFENSE (DOD)

UFC 3-600-01	(2016; with Change 6, 2021) Fire Protection Engineering for Facilities

UNDERWRITERS LABORATORIES (UL)

UL 246	(2011; Reprint Jul 2020) UL Standard for Safety Hydrants for Fire-Protection Service
UL 262	(2004; Reprint Oct 2011) Gate Valves for Fire-Protection Service
UL 312	(2022) UL Standard for Safety Check Valves for Fire-Protection Service

1.2 DEFINITIONS

1.2.1 Water Transmission Mains

Water transmission mains include water piping having diameters greater than 14 inch, specific materials, methods of joining and any appurtenances deemed necessary for a satisfactory system.

1.2.2 Water Mains

Water mains include water piping having diameters 4 through 14 inch, specific materials, methods of joining and any appurtenances deemed necessary for a satisfactory system.

1.2.3 Water Service Lines

Water service lines include water piping from a water main to a building service at a point approximately 5 feet from building or the point indicated on the drawings, specific materials, methods of joining and any appurtenances deemed necessary for a satisfactory system.

1.2.4 Additional Definitions

For additional definitions refer to the definitions in the applicable referenced standard.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-01 Preconstruction Submittals

Connections; G

SD-03 Product Data

Pipe, Fittings, Joints and Couplings; G

Valves; G

Valve Boxes; G

Fire Hydrants; G

Pipe Restraint; G

Corporation Stops; G

Disinfection Procedures; G

SD-06 Test Reports

Bacteriological Samples; G

Hydrostatic Sewer Test

Leakage Test

Hydrostatic Test

SD-07 Certificates

Pipe, Fittings, Joints and Couplings

Lining

Valves

Fire Hydrants

Fusion Technician Qualifications; G

Displacement Type Meters

SD-08 Manufacturer's Instructions

Ductile-Iron Piping

Copper Pipe For Service Lines

1.4 QUALITY CONTROL

1.4.1 Regulatory Requirements

Use NSF/ANSI 61 or NSF/ANSI 14 materials for potable water systems to comply with lead free content requirements as defined by the U.S. Safe Drinking Water Act effective January 2014.

1.4.2 Qualifications

1.4.2.1 Fusion Technician Qualifications

Submit a certificate from the manufacturer of the fusible pipe that shows the fusion technician is fully qualified to install fusible pipe of the types and sizes being used. Qualification must be current as of the actual date of fusion performance on the project.

1.4.2.1.1 Fusion Technician Qualification on Polyethylene (PE) Pipe and Fittings

Provide certification for PE Pipe heat fusion in accordance with ASTM F3190.

1.5 DELIVERY, STORAGE, AND HANDLING

1.5.1 Delivery and Storage

Inspect materials delivered to site for required pipe markings and damage. Unload and store with minimum handling and in accordance with manufacturer's instructions to prevent cuts, scratches and other damage. Store materials on site in enclosures or under protective covering. Store plastic piping, jointing materials and rubber gaskets under cover out of direct sunlight. Do not store materials directly on the ground. Keep inside of pipes, fittings, valves, fire hydrants, and other accessories free of dirt and debris or other contaminates.

1.5.2 Handling

Handle pipe, fittings, valves, fire hydrants, and other accessories in

accordance with applicable AWWA standard, manufacturer's instructions and in a manner to ensure delivery to the trench in sound undamaged condition. Avoid injury to coatings and linings on pipe and fittings; make repairs if coatings or linings are damaged. Do not place other material, hooks, or pipe inside a pipe or fitting after the coating has been applied. Inspect the pipe for defects before installation. Carry, do not drag pipe to the trench. Use of pinch bars and tongs for aligning or turning pipe will be permitted only on the bare ends of the pipe. Clean the interior of pipe and accessories of foreign matter before being lowered into the trench and keep them clean during laying operations by plugging. Replace defective material without additional expense to the Government. Store rubber gaskets, not immediately installed, under cover or out of direct sunlight.

Handle ductile iron pipe, fittings, and accessories in accordance with AWWA C600 and AWWA M41. Handle PVC pipe, fittings, and accessories in accordance with AWWA C605.

PART 2 PRODUCTS

2.1 MATERIALS

All materials are intended for potable water use unless otherwise indicated. Comply with NSF/ANSI 61 or NSF/ANSI 14 for all potable water pipe, fittings and other applicable materials. Provide pipe, fittings and other applicable materials bearing NSF/ANSI 61 or NSF/ANSI 14 markings for potable water service.

Provide all materials in accordance with AWWA C800 and as indicated herein. Provide valves and fittings with pressure ratings equivalent to the pressure ratings of the pipe.

2.1.1 Pipe, Fittings, Joints And Couplings

Submit manufacturer's standard drawings or catalog cuts, except submit both drawings and cuts for push-on and rubber-gasketed bell-and-spigot joints. Include information concerning gaskets with submittal for joints and couplings.

2.1.1.1 Ductile-Iron Piping

2.1.1.1.1 Pipe and Fittings

Pipe, AWWA C151/A21.51. Fittings, AWWA C110/A21.10 or AWWA C153/A21.53. Provide fittings with pressure ratings equivalent to that of the pipe. Provide compatible pipe ends and fittings for the specified joints. Provide cement-mortar lining, AWWA C104/A21.4, standard thickness on pipe and fittings.

2.1.1.1.2 Joints and Jointing Material

Provide push-on joints or mechanical joints for pipe and fittings.

a. Push-On Joints: Shape of pipe ends and fitting ends, gaskets, and lubricant for joint assembly as recommended in AWWA C111/A21.11.

b. Mechanical Joints: Dimensional and material requirements for pipe ends, glands, bolts and nuts, and gaskets as recommended in AWWA C111/A21.11.

2.1.1.2 Copper Pipe For Service Lines

2.1.1.2.1 Copper Tubing and Associated Fittings

Provide ASTM B88, Type K copper tubing. Provide AWWA C800 fittings. AWWA C800 includes ASME B1.20.3, ASME B1.20.1, ASME B16.18 solder-type joint fittings.

2.1.2 Valves

2.1.2.1 Gate Valves 3 Inch Size and Larger on Buried Piping

AWWA C500, AWWA C509, AWWA C515, or UL 262 and:

a. AWWA C500: nonrising stem type with double-disc gate and mechanical-joint ends or push-on joint ends compatible for the adjoining pipe

b. AWWA C509 or AWWA C515: nonrising stem type with mechanical-joint ends

c. UL 262: inside-screw type with operating nut, double-disc or split-wedge type gate, designed for a hydraulic working pressure of 175 psi, and have mechanical-joint ends or push-on joint ends as appropriate for the pipe to which it is joined.

Match materials for UL 262 gate valves to the reference standards specified in AWWA C500. Gate valves open by counterclockwise rotation of the valve stem. Stuffing boxes have 0-ring stem seals. Stuffing boxes are bolted and constructed so as to permit easy removal of parts for repair. Provide valve ends and gaskets for connection to sleeve-type mechanical couplings that conform to the requirements specified for the coupling. Provide all valves from one manufacturer.

2.1.2.2 Check Valves

Swing-check type, AWWA C508 or UL 312 and:

a. AWWA C508: Iron or steel body and cover and flanged ends

b. UL 312: Cast iron or steel body and cover, flanged ends, and designed for a minimum working pressure of 150 psi.

Materials for UL 312 check valves are to match the reference standards specified in AWWA C508. Provide check valves with a clear port opening. Provide all check valves from one manufacturer.

2.1.2.3 Rubber-Seated Butterfly Valves

Provide rubber-seated butterfly valves and wafer type valves that match the performance requirements of AWWA C504. Wafer type valves not meeting laying length requirements are acceptable if supplied and installed with a spacer, providing the specified laying length. Meet all tests required by AWWA C504. Flanged-end valves are required in a pit. Provide a union or sleeve-type coupling in the pit to permit removal. Direct-bury mechanical-end valves 3 through 10 inches in diameter. Provide a valve box, means for manual operation, and an adjacent pipe joint to facilitate valve removal. Provide valve operators that restrict closing to a rate requiring approximately 60 seconds, from fully open to fully closed.

2.1.2.4 Air Release, Air/Vacuum, and Combination Air Valves

Provide AWWA C512 air release and combination air valves that release air and prevent the formation of a vacuum. Provide valves with an iron body, lead-free bronze trim and stainless steel float that automatically releases air when the lines are being filled with water and admits air into the line when water is being withdrawn in excess of the inflow.

2.1.2.5 Water Service Valves

2.1.2.5.1 Gate Valves Smaller than 3 Inch in Size on Buried Piping

Gate valves smaller than 3 inch size on Buried Piping MSS SP-80, Class 150, solid wedge, nonrising stem, with flanged or threaded end connections, a union on one side of the valve, and a handwheel operator.

2.1.2.5.2 Gate Valves Smaller Than 3 Inch Size in Valve Pits

MSS SP-80, Class 150, solid wedge, inside screw, rising stem. Provide valves with flanged or threaded end connections, a union on one side of the valve, and a handwheel operator.

2.1.2.5.3 Check Valves Smaller than 2 Inch in Size

Provide check valves with a minimum working pressure of 150 psi or as indicated with a clear waterway equal to the full nominal diameter of the valve. Valves open to permit flow when inlet pressure is greater than the discharge pressure, and close tightly to prevent return flow when discharge pressure exceeds inlet pressure. Cast the size of the valve, working pressure, manufacturer's name, initials, or trademark on the body of each valve.

Provide valves for screwed fittings, made of lead-free bronze and in conformance with MSS SP-80, Class 150, Types 3 and 4 compatible for the application.

2.1.2.6 Valve Boxes

Provide a valve box for each gate valve on buried piping. Construct adjustable valve boxes manufactured from cast iron of a size compatible for the valve on which it is used. Cast the word "WATER" on the lid. The minimum diameter of the shaft of the box is as indicated. Provide precast concrete valve box.

2.1.2.7 Valve Pits

Construct the valve pits at locations indicated or as required above and in accordance with the details shown.

2.1.3 Blowoff Valve Assemblies

Provide blowoff valve assemblies complete with all pipe, fittings, valve, valve box, riser box and lid, riser extension, discharge fitting and other materials required to connect to the water main. Provide blow off valve assemblies 4 inches or larger with AWWA C110/A21.10 or AWWA C153/A21.53 fittings.

2.1.4 Fire Hydrants

2.1.4.1 Fire Hydrants

Provide fire hydrants where indicated. Paint fire hydrants with at least one coat of primer and two coats of enamel paint. Paint barrel and bonnet colors in accordance with UFC 3-600-01. Stencil fire hydrant number and main size on the fire hydrant barrel using black stencil paint.

2.1.4.1.1 Wet-Barrel Type Fire Hydrants

Provide Provide Wet-barrel type fire hydrants, AWWA C503 or UL 246, "Wet Barrel" with 6 inch inlet, one 4 1/2 inch pumper connection, and two 2 1/2 inch hose connections. Individually valve pumper connection and hose connections with independent nozzle gate valves.

Provide mechanical-joint end only inlet ; with end matching requirements as specified in AWWA C502 or UL 246 for size and shape of operating nut, cap nuts, and threads on hose and pumper connections. Provide fire hydrants with breakable features as mentioned in AWWA C503. Provide fire hydrant with special couplings joining upper and lower sections of fire hydrant barrel that break from a force imposed by a moving vehicle.

2.1.4.1.2 Flush-Type Fire Hydrants

Provide flush-type fire hydrants that conform to the applicable requirements of AWWA C502, except that they are designed to permit placement of fire hydrant below surface of pavement. Provide 6 inch inlet, 4 1/4 inch minimum valve opening, one 4 1/2 inch pumper connection, and one 2 1/2 inch hose connection that have readily accessible hose and pumper connections and operating nuts enclosed in a cast iron box with a cast-iron cover set flush with the pavement. Provide flush lifting cover handle. Inlet has either mechanical-joint or push-on joint end. Size and shape of operating nut and cap nuts and threads on hose and pumper connections as indicated.

2.1.5 Meters

Submit certificates certifying all required and recommended tests set forth in the referenced standard and AWWA M6 have been performed and comply with all applicable requirements of the referenced standard and AWWA M6 within the past three years. Include certification that each meter has been tested for accuracy of registration and that each meter complies with the accuracy and capacity requirements of the referenced standard when tested in accordance with AWWA M6.

Include a register with all meters whether they are or are not connected to a remote reading system.

2.1.5.1 Displacement Type Meters

Provide AWWA C700 meter with oscillating piston. Pressure casings constructed of copper alloy containing not less than 75 percent copper. Provide registers with breakable covers and straight-reading permanently sealed registers. copper alloy conforming to ASTM B584. For meter sizes 1/2 inch through 1 inch provide split-case.

2.1.5.2 Meter Connections

Provide connections compatible with the type of pipe and conditions encountered.

2.1.5.3 Meter Boxes

Provide meter boxes of sufficient size to completely enclose the meter and shutoff valve or service stop and in accordance with the details shown on the drawings. Provide a meter boxes or vaults with a height equal to the distance from invert of the service line to finished grade at the meter location.

2.1.5.3.1 Cast Iron

Provide ASTM A48/A48M, Class 25 cast iron meter box and lid. Provide a lid having the word "WATER" cast on the top surface.

2.1.5.3.2 Plastic Meter Boxes

Provide manufactured plastic boxes and lids meeting the following requirements:

a. One-piece molded construction

b. Vertical load rating for medium duty use of 15,000 lbs

c. Ultraviolet (UV) exterior surface protection

d. White interior surface

2.1.6 Disinfection

Chlorinating materials are to conform to: Chlorine, Liquid: AWWA B301; Hypochlorite, Calcium and Sodium: AWWA B300.

2.2 ACCESSORIES

2.2.1 Pipe Restraint

2.2.1.1 Thrust Blocks

Use ASTM C94/C94M concrete having a minimum compressive strength of 3,000 psi at 28 days.

2.2.1.2 Joint Restraint

Provide restrained joints in accordance with NFPA 24, Chapter 10 and in accordance with ASTM F1674.

Provide mechanical joint restraint .

2.2.2 Tapping Sleeves

Provide cast gray, ductile, malleable iron or stainless steel, split-sleeve type tapping sleeves of the sizes indicated for connection to existing main with flanged or grooved outlet, and with bolts, follower rings and gaskets on each end of the sleeve. Utilize similar metals for bolts, nuts, and washers to minimize the possibility of galvanic

corrosion. Provide dielectric gaskets where dissimilar metals adjoin. Provide a tapping sleeve assembly with a maximum working pressure of 150 psi. Provide bolts with square heads and hexagonal nuts. Longitudinal gaskets and mechanical joints with gaskets as recommended by the manufacturer of the sleeve. When using grooved mechanical tee, utilize an upper housing with full locating collar for rigid positioning which engages a machine-cut hole in pipe, encasing an elastomeric gasket which conforms to the pipe outside diameter around the hole and a lower housing with positioning lugs, secured together during assembly by nuts and bolts as specified, pre-torqued to 50 foot-pound.

2.2.3 Insulating Joints

Provide a rubber-gasketed insulating joint or dielectric coupling between pipe of dissimilar metals which will effectively prevent metal-to-metal contact between adjacent sections of piping.

2.2.4 Water Service Line Appurtenances

2.2.4.1 Corporation Stops

Ground key type; lead-free bronze, ASTM B61 or ASTM B62; compatible with the working pressure of the system and solder-joint, or flared tube compression type joint. Threaded ends for inlet and outlet of corporation stops, AWWA C800; coupling nut for connection to flared copper tubing, ASME B16.26.

2.2.4.2 Curb or Service Stops

Ground key, round way, inverted key type; made of lead-free bronze, ASTM B61or ASTM B62; and compatible with the working pressure of the system. Provide compatible ends for connection to the service piping. Cast an arrow into body of the curb or service stop indicating direction of flow.

2.2.4.3 Curb Boxes

Provide a curb box for each curb or service stop manufactured from cast iron, size capable of containing the stop where it is used. Provide a round head. Cast the word "WATER" on the lid. Factory coat the box with a heavy coat of bituminous paint.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Connections to Existing System

Perform all connections to the existing water system in the presence of the Contracting Officer.

3.1.2 Operation of Existing Valves

Do not operate valves within or directly connected to the existing water system unless expressly directed to do so by the Contracting Officer.

3.1.3 Earthwork

Perform earthwork operations in accordance with Section 31 00 00 EARTHWORK .

3.2 INSTALLATION

Install all materials in accordance with the applicable reference standard, manufacturers instructions and as indicated herein.

3.2.1 Piping

3.2.1.1 General Requirements

Install pipe, fittings, joints and couplings in accordance with the applicable referenced standard, the manufacturer's instructions and as specified herein.

3.2.1.1.1 Termination of Water Lines

Terminate the work covered by this section at a point approximately 5 feet from the building, unless otherwise indicated.

Do not lay water lines in the same trench with gas lines, fuel lines, electric wiring, or any other utility. Do not install copper tubing in the same trench with ferrous piping materials. Where nonferrous metallic pipe (i.e., copper tubing) crosses any ferrous piping, provide a minimum vertical separation of 12 inches between pipes.

3.2.1.1.2 Pipe Laying and Jointing

Remove fins and burrs from pipe and fittings. Before placing in position, clean pipe, fittings, valves, and accessories, and maintain in a clean condition. Provide proper facilities for lowering sections of pipe into trenches. Under no circumstances is it permissible to drop or dump pipe, fittings, valves, or other water line material into trenches. Cut pipe cleanly, squarely, and accurately to the length established at the site and work into place without springing or forcing. Replace a pipe or fitting that does not allow sufficient space for installation of jointing material. Blocking or wedging between bells and spigots is not permitted. Lay bell-and-spigot pipe with the bell end pointing in the direction of laying. Grade the pipeline in straight lines; avoid the formation of dips and low points. Support pipe at the design elevation and grade. Secure firm, uniform support. Wood support blocking is not permitted. Lay pipe so that the full length of each section of pipe and each fitting rests solidly on the pipe bedding; excavate recesses to accommodate bells, joints, and couplings. Provide anchors and supports for fastening work into place. Make provision for expansion and contraction of pipelines. Keep trenches free of water until joints have been assembled. At the end of each work day, close open ends of pipe temporarily with wood blocks or bulkheads. Do not lay pipe when conditions of trench or weather prevent installation. Provide a minimum of 2 1/2 feet depth of cover over top of pipe.

3.2.1.1.3 Tracer Wire

Install a continuous length of tracer wire for the full length of each run of nonmetallic pipe. Attach wire to top of pipe in such manner that it will not be displaced during construction operations.

3.2.1.1.4 Connections to Existing Water Lines

Make connections to existing water lines after coordination with the

facility and with a minimum interruption of service on the existing line. Make connections to existing lines under pressure in accordance with the recommended procedures of the manufacturer of the pipe being tapped and as indicated, except as otherwise specified, tap concrete pipe in accordance with AWWA M9 for tapping concrete pressure pipe.

3.2.1.1.5 Sewer Manholes

No water piping is to pass through or come in contact with any part of a sewer manhole.

3.2.1.1.6 Water Piping Parallel With Sewer Piping

a. Normal Conditions: Lay water piping at least 10 feet horizontally from sewer or sewer manhole whenever possible. Measure the distance from outside edge to outside edge of pipe or outside edge of manhole. When local conditions prevent horizontal separation install water piping in a separate trench with the bottom of the water piping at least 18 inches above the top of the sewer piping.

b. Unusual Conditions: When local conditions prevent vertical separation, construct sewer piping of AWWA compliant ductile iron water piping and perform hydrostatic sewer test, without leakage, prior to backfilling. When local conditions prevent vertical separation, test the sewer manhole in place to ensure watertight construction.

3.2.1.1.7 Water Piping Crossing Sewer Piping

a. Normal Conditions: Provide a separation of at least 18 inches between the bottom of the water piping and the top of the sewer piping in cases where water piping crosses above sewer piping.

b. Unusual Conditions: When local conditions prevent a vertical separation described above, construct sewer piping passing over or under water piping of AWWA compliant ductile iron water piping and perform hydrostatic sewer test, without leakage, prior to backfilling. Construct sewer crossing with a minimum 20 feet length of the AWWA compliant ductile iron water piping, centered at the point of the crossing so that joints are equidistant and as far as possible from the water piping. Protect water piping passing under sewer piping by providing a vertical separation of at least 18 inches between the bottom of the sewer piping and the top of the water piping; adequate structural support for the sewer piping to prevent excessive deflection of the joints and the settling on or damage to the water piping.

3.2.1.1.8 Penetrations

Provide ductile-iron or Schedule 40 steel wall sleeves for pipe passing through walls of valve pits and structures. Fill annular space between walls and sleeves with rich cement mortar. Fill annular space between pipe and sleeves with mastic.

3.2.1.1.9 Flanged Pipe

Only install flanged pipe aboveground or with the flanges in valve pits.

3.2.1.2 Ductile-Iron Piping

Unless otherwise specified, install pipe and fittings in accordance with the paragraph GENERAL REQUIREMENTS and with the requirements of AWWA C600 for pipe installation, joint assembly, valve-and-fitting installation, and thrust restraint.

a. Jointing: Make push-on joints with the gaskets and lubricant specified for this type joint; assemble in accordance with the applicable requirements of AWWA C600 and AWWA M41 for joint assembly. Make mechanical joints with the gaskets, glands, bolts, and nuts specified for this type joint; assemble in accordance with the applicable requirements of AWWA C600 and AWWA M41 for joint assembly and the recommendations of Appendix A to AWWA C111/A21.11.

b. Allowable Deflection: Follow AWWA C600 and AWWA M41 for the maximum allowable deflection. If the alignment requires deflection in excess of the above limitations, provide special bends or a sufficient number of shorter lengths of pipe to achieve angular deflections within the limit set forth.

3.2.1.3 Metallic Piping for Service Lines

Install pipe and fittings in accordance with the paragraph GENERAL REQUIREMENTS and with the applicable requirements of AWWA C600 for pipe installation, unless otherwise specified.

3.2.1.3.1 Screwed Joints

Make screwed joints up tight with a stiff mixture of graphite and oil, inert filler and oil, or graphite compound; apply to male threads only or with PTFE Tape, for use with threaded pipe. Threads are to be full cut; do not leave more than three threads on the pipe exposed after assembling the joint.

3.2.1.3.2 Joints for Copper Tubing

Cut copper tubing with square ends; remove fins and burrs. Replace dented, gouged, or otherwise damaged tubing with undamaged tubing. Make solder joints using ASTM B32, 95-5 tin-antimony or Grade Sn96 solder. Use solder and flux containing less than 0.2 percent lead. Before making joint, clean ends of tubing and inside of fitting or coupling with wire brush or abrasive. Apply a rosin flux to the tubing end and on recess inside of fitting or coupling. Insert tubing end into fitting or coupling for the full depth of the recess and solder. For compression joints on flared tubing, insert tubing through the coupling nut and flare tubing.

3.2.1.3.3 Flanged Joints

Make flanged joints up tight, avoid undue strain on flanges, valves, fittings, and accessories.

3.2.1.4 Fire Protection Service Lines for Sprinkler Supplies

Connect water service lines used to supply building sprinkler systems for fire protection to the water main in accordance with NFPA 24.

3.2.1.5 Water Service Piping

3.2.1.5.1 Location

Connect water service piping to the building service where the building service has been installed. Where building service has not been installed, terminate water service lines approximately 5 feet from the building line at the points indicated; close such water service lines with plugs or caps.

3.2.1.5.2 Water Service Line Connections to Water Mains

Connect 3/4 inch and 1.5 inch water service lines to the main by a corporation stop and gooseneck and install a service stop below the frostline as indicated. Connect 3 inch water service lines to the main with a rigid connection and install a gate valve on service line below the frostline as indicated. Connect water service lines to ductile-iron water mains in accordance with AWWA C600 for service taps.

3.2.2 Meters

Install meters and meter boxes at the locations shown on the drawings. Center meters in the boxes to allow for reading and ease of removal or maintenance. Set top of box or vault at finished grade.

3.2.3 Backflow Preventers

Install backflow preventers of type, size, and capacity indicated a minimum of 12 inch and a maximum of 36 inch above concrete base. Include valves and test cocks. Install according to the manufacturers requirements and the requirements of plumbing and health department and authorities having jurisdiction. Support NPS 2 1/2 inch and larger backflow preventers, valves, and piping near floor with 12 inch minimum air gap, and on concrete piers or steel pipe supports. Do not install backflow preventers that have a relief drain in vault or in other spaces subject to flooding. Do not install by-pass piping around backflow preventers.

3.2.4 Disinfection

Prior to disinfection, provide disinfection procedures, proposed neutralization and disposal methods of waste water from disinfection as part of the disinfection submittal. Disinfect new water piping and existing water piping affected by Contractor's operations in accordance with AWWA C651. Disinfect new water piping using the AWWA C651 continuous-feed method of chlorination. Ensure a free chlorine residual of not less than 10 parts per million after 24 hour holding period and prior to performing bacteriological tests.

3.2.5 Flushing

Perform bacteriological tests prior to flushing. Flush solution from the systems with domestic water until maximum residual chlorine content is within the range of 0.2 to 0.5 parts per million, the residual chlorine content of the distribution system, or acceptable for domestic use. Use AWWA C655 neutralizing chemicals.

3.2.6 Pipe Restraint

3.2.6.1 Concrete Thrust Blocks

Install concrete thrust blocks where indicated.

3.2.6.2 Restrained Joints

Install restrained joints in accordance with the manufacturer's instructions where indicated. For metal harness use tie rods and clamps as shown in NFPA 24.

3.2.7 Valves

3.2.7.1 Gate Valves

Install gate valves, AWWA C500 and UL 262, in accordance with the requirements of AWWA C600 for valve-and-fitting installation and with the recommendations of the Appendix ("Installation, Operation, and Maintenance of Gate Valves") to AWWA C500. Install gate valves, AWWA C509 or AWWA C515, in accordance with the requirements of AWWA C600 for valve-and-fitting installation and with the recommendations of the Appendix ("Installation, Operation, and Maintenance of Gate Valves") to AWWA C509 or AWWA C515. Install gate valves on PVC water mains in accordance with the recommendations for appurtenance installation in AWWA M23, Chapter 7, "Installation." Make and assemble joints to gate valves as specified for making and assembling the same type joints between pipe and fittings.

3.2.7.2 Check Valves

Install check valves in accordance with the applicable requirements of AWWA C600 for valve-and-fitting installation. Make and assemble joints to check valves as specified for making and assembling the same type joints between pipe and fittings.

3.2.7.3 Air Release, Air/Vacuum, and Combination Air Valves

Install pressure vacuum assemblies of type, size, and capacity indicated. Include valves and test cocks. Install according to the requirements of plumbing and health department and authorities having jurisdiction. Do not install pressure vacuum breaker assemblies in vault or other space subject to flooding.

3.2.8 Blowoff Valve Assemblies

Install blowoff valve assemblies as indicated on the drawings or in accordance with the manufactures recommendations. Install discharge fitting on the end of riser pipe to direct the flow of water so as to minimize damage to surrounding areas.

3.2.9 Fire Hydrants

Install fire hydrants in accordance with AWWA C600 for fire hydrant installation and as indicated. Make and assemble joints as specified for making and assembling the same type joints between pipe and fittings. Install fire hydrants with the 4 1/2 inch connections facing the adjacent paved surface. If there are two paved adjacent surfaces, install fire hydrants with the 4 1/2 inch connection facing the paved surface where the connecting main is located.

3.3 FIELD QUALITY CONTROL

3.3.1 Tests

Notify the Contracting Officer a minimum of five days in advance of hydrostatic testing. Coordinate the proposed method for disposal of waste water from hydrostatic testing. Perform field tests, and provide labor, equipment, and incidentals required for testing. Provide documentation that all items of work have been constructed in accordance with the Contract documents.

3.3.1.1 Hydrostatic Test

Test the water system in accordance with the applicable AWWA standard specified below. Where water mains provide fire service, test in accordance with the special testing requirements given in the paragraph SPECIAL TESTING REQUIREMENTS FOR FIRE SERVICE. Test ductile-iron water mains in accordance with the requirements of AWWA C600 for hydrostatic testing. The amount of leakage on ductile-iron pipelines with mechanical-joints is not to exceed the amounts given in AWWA C600; no leakage will be allowed at joints made by any other methods. Test concrete water mains in accordance with the recommendations in AWWA M9, "Hydrostatic Testing and Disinfection of Mains." The amount of leakage on concrete pipelines is not to exceed 20 gallons per 24 hours per inch of pipe diameter per mile of pipeline. Test water service lines in accordance with requirements of AWWA C600 for hydrostatic testing. No leakage will be allowed at copper pipe joints, copper tubing joints (soldered, compression type, brazed), flanged joints. Do not backfill utility trench or begin testing on any section of a pipeline where concrete thrust blocks have been provided until at least 7 days after placing of the concrete.

3.3.1.2 Hydrostatic Sewer Test

The hydrostatic pressure sewer test will be performed in accordance with the applicable AWWA standard for the piping material or AWWA C600 with a minimum test pressure of 30.

3.3.1.3 Leakage Test

For leakage test, use a hydrostatic pressure not less than the maximum working pressure of the system. Leakage test may be performed at the same time and at the same test pressure as the pressure test.

3.3.1.4 Bacteriological Testing

Perform bacteriological tests in accordance with AWWA C651 Option A. For new water mains use Option A and obtain two sets of samples for coliform analysis, each sample being collected at least 16 hours apart. Take samples every 1,200 ft plus one set from the end of the line and at least one from each branch greater than one pipe length. Analyze samples by a certified laboratory, and submit the results of the bacteriological samples.

3.3.1.5 Special Testing Requirements for Fire Service

Test water mains and water service lines providing fire service or water and fire service in accordance with NFPA 24. The additional water added to the system must not exceed the limits given in NFPA 24

3.3.1.6 Tracer Wire Continuity Test

Test tracer wire for continuity after service connections have been completed and prior to final pavement or restoration. Verify that tracer wire is locatable with electronic utility locating equipment. Repair breaks or separations and re-test for continuity.

3.4 SYSTEM STARTUP

Water mains and appurtenances must be completely installed, disinfected, flushed, and satisfactory bacteriological sample results received prior to permanent connections being made to the active distribution system. Obtain approval by the Contracting Officer prior to the new water piping being placed into service.

3.5 CLEANUP

Upon completion of the installation of water lines and appurtenances, remove all debris and surplus materials resulting from the work.

-- End of Section --

SECTION 33 30 00

SANITARY SEWERAGE
05/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B1.20.1	(2013; R 2018) Pipe Threads, General Purpose (Inch)

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C104/A21.4	(2022) Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water
AWWA C110/A21.10	(2021) Ductile-Iron and Gray-Iron Fittings
AWWA C111/A21.11	(2017) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C153/A21.53	(2019) Ductile-Iron Compact Fittings for Water Service
AWWA C600	(2017) Installation of Ductile-Iron Mains and Their Appurtenances
AWWA C605	(2021) Underground Installation of Polyvinyl Chloride (PVC) and Molecularly Oriented Polyvinyl Chloride (PVCO) Pressure Pipe and Fittings
AWWA C900	(2016) Polyvinyl Chloride (PVC) Pressure Pipe, and Fabricated Fittings, 4 In. Through 60 In. (100 mm Through 1,500 mm)

ASTM INTERNATIONAL (ASTM)

ASTM A48/A48M	(2003; R 2021) Standard Specification for Gray Iron Castings
ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A536	(1984; R 2019; E 2019) Standard Specification for Ductile Iron Castings
ASTM C33/C33M	(2024a) Standard Specification for Concrete Aggregates

ASTM C94/C94M	(2022a) Standard Specification for Ready-Mixed Concrete
ASTM C150/C150M	(2024) Standard Specification for Portland Cement
ASTM C270	(2025b) Standard Specification for Mortar for Unit Masonry
ASTM C443	(2021) Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets
ASTM C478	(2018) Standard Specification for Circular Precast Reinforced Concrete Manhole Sections
ASTM C478M	(2018) Standard Specification for Precast Reinforced Concrete Manhole Sections (Metric)
ASTM C972	(2000; R 2011) Compression-Recovery of Tape Sealant
ASTM C1244	(2020) Standard Test Method for Concrete Sewer Manholes by the Negative Air Pressure (Vacuum) Test Prior to Backfill
ASTM C1644	(2006; R 2017) Standard Specification for Resilient Connectors Between Reinforced Concrete On-Site Wastewater Tanks and Pipes
ASTM D412	(2016; R 2021) Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension
ASTM D624	(2000; R 2020) Standard Test Method for Tear Strength of Conventional Vulcanized Rubber and Thermoplastic Elastomers
ASTM D1784	(2020) Standard Specification for Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D1785	(2015; E 2018) Standard Specification for Poly(Vinyl Chloride) (PVC), Plastic Pipe, Schedules 40, 80, and 120
ASTM D2241	(2015) Standard Specification for Poly(Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series)
ASTM D2321	(2020) Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications
ASTM D2464	(2015) Standard Specification for Threaded Poly(Vinyl Chloride) (PVC) Plastic Pipe

Fittings, Schedule 80

ASTM D2466 (2017) Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 40

ASTM D2467 (2015) Standard Specification for Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80

ASTM D3034 (2016) Standard Specification for Type PSM Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings

ASTM D3139 (2019) Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals

ASTM D3212 (2020) Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals

ASTM D4101 (2017) Standard Classification System and Basis for Specification for Polypropylene Injection and Extrusion Materials

ASTM F477 (2014; R 2021) Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe

ASTM F949 (2020) Standard Specification for Poly(Vinyl Chloride) (PVC) Corrugated Sewer Pipe with a Smooth Interior and Fittings

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.27 (Nov 2016) Scaffolds and Roope Descent Systems

UNI-BELL PVC PIPE ASSOCIATION (UBPPA)

UBPPA UNI-B-6 (1998) Recommended Practice for Low-Pressure Air Testing of Installed Sewer Pipe

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-01 Preconstruction Submittals

Contractor's License; G

SD-02 Shop Drawings

Installation Drawings; G

SD-03 Product Data

Precast Concrete Manholes

Frames, Covers, and Gratings

Gravity Pipe

Pressure Pipe

SD-06 Test Reports

Precast Concrete Sewer Manhole Test; G

Hydrostatic Sewer Test; G

Negative Air Pressure Test; G

Low-Pressure Air Tests; G

Tests For Pressure Lines; G

SD-07 Certificates

Portland Cement

Gaskets

Post-Installation Inspection; G

1.3 QUALITY CONTROL

1.3.1 Installer Qualifications

Install specified materials by a licensed underground utility Contractor licensed for such work in the state where the work is to be performed. Verify installing Contractor's License is current and state certified or state registered.

1.4 DELIVERY, STORAGE, AND HANDLING

1.4.1 Delivery and Storage

Check upon arrival; identify and segregate as to types, functions, and sizes. Store off the ground in a manner affording easy accessibility and not causing excessive rusting or coating with grease or other objectionable materials.

1.4.1.1 Piping

Inspect materials delivered to site for damage; store with minimum of handling. Store materials on site in enclosures or under protective coverings. Store plastic piping and jointing materials and rubber gaskets under cover out of direct sunlight. Do not store materials directly on the ground. Keep inside of pipes and fittings free of dirt and debris.

1.4.2 Handling

Handle pipe, fittings, and other accessories in such manner as to ensure

delivery to the trench in sound undamaged condition. Take special care not to damage linings of pipe and fittings; if lining is damaged, make satisfactory repairs. Carry, do not drag, pipe to trench. Store solvents, solvent compounds, lubricants, elastomeric gaskets, and any similar materials required to install the plastic pipe in accordance with the manufacturer's recommendation and discard those materials if the storage period exceeds the recommended shelf life. Discard solvents in use when the recommended pot life is exceeded.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

2.1.1 Sanitary Sewer Gravity Pipeline

Provide mains and laterals of ductile-iron pipe or polyvinyl chloride (PVC) plastic pipe. Provide building connections of polyvinyl chloride (PVC) plastic pipe.

2.1.2 Sanitary Sewer Pressure Lines

Provide pressure lines of polyvinyl chloride (PVC) plastic pressure pipe.

2.2 MATERIALS

Provide materials conforming to the respective specifications and other requirements specified below. Submit manufacturer's product specification,standard drawings or catalog cuts.

2.2.1 Gravity Pipe

2.2.1.1 PVC Gravity Sewer Piping

2.2.1.1.1 PVC Gravity Pipe and Fittings

ASTM D3034, SDR 35, or ASTM F949 with ends suitable for elastomeric gasket joints.

2.2.1.1.2 PVC Gravity Joints and Jointing Material

Provide joints conforming to ASTM D3212. Gaskets are to conform to ASTM F477.

2.2.2 Pressure Pipe

2.2.2.1 PVC Pressure Pipe and Associated Fittings

Pipe, couplings and fittings are to be manufactured of materials conforming to ASTM D1784, Class 12454B.

2.2.2.1.1 Pipe and Fittings Less Than 4 inch Diameter

####### 2.2.2.1.1.1 Screw-Joint

Provide pipe conforming to dimensional requirements of ASTM D1785, Schedule 80, with joints meeting requirements of 150 psi working pressure, 200 psi hydrostatic test pressure, unless otherwise shown or specified. Provide fittings for threaded pipe conforming to requirements of ASTM D2464, threaded to conform to the requirements of ASME B1.20.1 for use with

Schedule 80 pipe and fittings. Pipe couplings when used, are to be tested as required by ASTM D2464.

2.2.2.1.1.2 Push-On Joint

ASTM D3139, with ASTM F477 gaskets. Fittings for push-on joints are to be iron conforming to AWWA C110/A21.10 or AWWA C153/A21.53 and AWWA C111/A21.11 with a cement-mortar lining conforming to AWWA C104/A21.4, standard thickness.

2.2.2.1.1.3 Solvent Cement Joint

Provide pipe conforming to dimensional requirements of ASTM D1785 or ASTM D2241 with joints meeting the requirements of 150 psi working pressure and 200 psi hydrostatic test pressure. Fittings for solvent cement jointing are to conform to ASTM D2466 or ASTM D2467.

2.2.2.1.2 Pipe and Fittings 4 inch Diameter And Larger

Provide pipe conforming to AWWA C900 and be plain end or gasket bell end, Pressure Class 150 (DR 18) , with cast-iron-pipe-equivalent OD. Fittings are to be gray-iron or ductile-iron conforming to AWWA C110/A21.10 or AWWA C153/A21.53 and AWWA C111/A21.11 with a cement-mortar lining conforming to AWWA C104/A21.4, standard thickness. Fittings for pipe to pipe push-on joint ends are to conform with AWWA C900.

2.2.3 Cement Mortar

Provide cement mortar conforming to ASTM C270, Type M with Type II cement.

2.2.4 Portland Cement

Submit certificates of compliance stating the type of cement used in manufacture of concrete pipe, fittings, septic tanks, and precast manholes. Provide portland cement conforming to ASTM C150/C150M, Type II for concrete used in concrete pipe, concrete pipe fittings, septic tanks, and manholes and type optional for cement used in concrete cradle, concrete encasement, and thrust blocking. ,Use a cement containing less than 0.60 percent alkalies where aggregates are alkali reactive, as determined by Appendix XI of ASTM C33/C33M.

2.2.5 Portland Cement Concrete

Provide portland cement concrete conforming to ASTM C94/C94M, compressive strength of 4000 psi at 28 days, except for concrete cradle and encasement or concrete blocks for manholes. Concrete used for cradle and encasement is to have a compressive strength of 2500 psi minimum at 28 days. Protect concrete in place from freezing and moisture loss for 7 days.

2.2.6 Precast Concrete Manholes

Provide precast concrete manholes, risers, base sections, and tops conforming to ASTM C478.

2.2.7 Gaskets and Connectors

Provide gaskets for joints between manhole sections conforming to ASTM C443. Resilient connectors for making joints between manhole and pipes entering manhole are to conform toASTM C1644.

2.2.8 External Preformed Rubber Joint Seals

An external preformed rubber joint seal is an accepted method of sealing cast iron covers to precast concrete sections to prevent ground water infiltration into sewer systems. All finished and sealed manholes constructed in accordance with paragraph entitled "Manhole Construction" are to be tested for leakage in the same manner as pipelines as described in paragraph entitled "Leakage Tests." The seal is to be multi-section with a neoprene rubber top section and all lower sections made of Ethylene Propylene Diene Monomer (EPDM) rubber with a minimum thickness of 60 mils. Each unit is to consist of a top and bottom section and have mastic on the bottom of the bottom section and mastic on the top and bottom of the top section. The mastic is to be a non-hardening butyl rubber sealant and seal to the cone/top slab of the manhole/catch basin and over the lip of the casting. Extension sections are to cover up to two more adjusting rings. Properties and values are listed in the following table:

Properties, Test Methods and Minimum Values for Rubber used in Preformed Joint Seals				
Physical Properties	Test Methods	EPDM	Neoprene	Butyl Mastic
Tensile, psi	ASTM D412	1840	2195	--
Elongation, percent	ASTM D412	553	295	350
Tear Resistance, ppi	ASTM D624 (Die B)	280	160	--
Rebound, percent, 5 minutes	ASTM C972 (mod.)	--	--	11
Rebound, percent, 2 hours	ASTM C972	--	--	12

2.2.9 Frames, Covers, and Gratings for Manholes

Submit certification on the ability of frame and cover to carry the imposed live load. Frame and cover are to be cast gray iron, ASTM A48/A48M, Class 35B, cast ductile iron, ASTM A536, Grade 65-45-12, or reinforced concrete, ASTM C478 ASTM C478M. Frames and covers are to be circular with vent holes. Size are to be for 24 inch opening. Stamp or cast the words "Sanitary Sewer" into covers so that it is plainly visible.

2.2.10 Manhole Steps

Zinc-coated steel conforming to 29 CFR 1910.27 with a plastic or rubber coating pressure-molded to the steel is to be used. Provide plastic coating conforming to ASTM D4101, copolymer polypropylene. Rubber is to conform to ASTM C443, except shore A durometer hardness is to be 70 plus or minus 5. Aluminum steps or rungs will not be permitted. Steps are not required in manholes less than 4 feet deep.

2.2.11 Manhole Ladders

Provide a steel ladder where the depth of a manhole exceeds 12 feet. The ladder is not to be less than 16 inches in width, with 3/4 inch diameter rungs spaced 12 inches apart. The two stringers are to be a minimum 3/8 inch thick and 2 inches wide. Galvanize ladders and inserts after fabrication in conformance with ASTM A123/A123M.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Installation Drawings

Submit Installation Drawings showing complete detail, both plan and side view details with proper layout and elevations.

3.2 INSTALLATION

Backfill after inspection by the Contracting Officer. Before, during, and after installation, protect plastic pipe and fittings from any environment that would result in damage or deterioration to the material. Keep a copy of the manufacturer's instructions available at the construction site at all times and follow these instructions unless directed otherwise by the Contracting Officer.

3.2.1 Connections to Existing Lines

Obtain approval from the Contracting Officer before making connection to existing line. Conduct work so that there is minimum interruption of service on existing line.

3.2.2 General Requirements for Installation of Pipelines

These general requirements apply except where specific exception is made in the following paragraphs entitled "Special Requirements."

3.2.2.1 Location

Terminate the work covered by this section at a point approximately 5 feet from the building.

3.2.2.1.1 Sanitary Piping Installation Parallel with Water Line

3.2.2.1.1.1 Normal Conditions

Install sanitary piping or manholes at least 10 feet horizontally from a water line whenever possible. Measure the distance from edge-to-edge.

3.2.2.1.1.2 Unusual Conditions

When local conditions prevent a horizontal separation of 10 feet, the sanitary piping or manhole may be laid closer to a water line provided that:

a. The top (crown) of the sanitary piping is to be at least 18 inches below the bottom (invert) of the water main.

b. Where this vertical separation cannot be obtained, construct the

sanitary piping with AWWA-approved ductile iron water pipe pressure and conduct a hydrostatic sewer test without leakage prior to backfilling.

c. The sewer manhole is to be of watertight construction and tested in place.

3.2.2.1.2 Installation of Sanitary Piping Crossing a Water Line

3.2.2.1.2.1 Normal Conditions

Lay sanitary sewer piping by crossing under water lines to provide a separation of at least 18 inches between the top of the sanitary piping and the bottom of the water line whenever possible.

3.2.2.1.2.2 Unusual Conditions

When local conditions prevent a vertical separation described above, use the following construction:

a. Construct sanitary piping passing over or under water lines with AWWA-approved ductile iron water pressure piping and conduct a hydrostatic sewer test without leakage prior to backfilling.

b. Protect sanitary piping passing over water lines by providing:

(1) A vertical separation of at least 18 inches between the bottom of the sanitary piping and the top of the water line.

(2) Adequate structural support for the sanitary piping to prevent excessive deflection of the joints and the settling on and breaking of the water line.

(3) That the length, minimum 20 feet, of the sanitary piping be centered at the point of the crossing so that joints are equidistant and as far as possible from the water line.

3.2.2.1.3 Sanitary Sewer Manholes

No water piping must pass through or come in contact with any part of a sanitary sewer manhole.

3.2.2.2 Earthwork

Perform earthwork operations in accordance with Section 31 00 00 EARTHWORK .

3.2.2.3 Pipe Laying and Jointing

Inspect each pipe and fitting before and after installation; replace those found defective and remove from site. Provide proper facilities for lowering sections of pipe into trenches. Lay nonpressure pipe with the bell ends in the upgrade direction. Adjust spigots in bells to give a uniform space all around. Blocking or wedging between bells and spigots will not be permitted. Replace by one of the proper dimensions, pipe or fittings that do not allow sufficient space for installation of joint material. At the end of each work day, close open ends of pipe temporarily with wood blocks or bulkheads. Provide batterboards not more than 25 feet apart in trenches for checking and ensuring that pipe invert elevations are as indicated. Laser beam method may be used in lieu of

batterboards for the same purpose. Construct branch connections by use of regular fittings or solvent cemented saddles as approved. Provide saddles for PVC pipe conforming to Table 4 of ASTM D3034.

3.2.3 Special Requirements

3.2.3.1 Installation of PVC Piping

Install pipe and fittings in accordance with paragraph entitled "General Requirements for Installation of Pipelines" of this section and with the requirements of ASTM D2321 for laying and joining pipe and fittings. Make joints with the gaskets specified for joints with this piping and assemble in accordance with the requirements of ASTM D2321 for assembly of joints. Make joints to other pipe materials in accordance with the recommendations of the plastic pipe manufacturer.

3.2.3.2 Installation of PVC Pressure Pipe

Unless otherwise specified, install pipe and fittings in accordance with AWWA C605. AWWA C605 includes requirements such as excavation, installation, and placement of apputenances.

3.2.3.2.1 Pipe Less Than 4 Inch Diameter

3.2.3.2.1.1 Threaded Joints

Make by wrapping the male threads with joint tape or by applying an approved thread lubricant, then threading the joining members together. Tighten the joints with strap wrenches which will not damage the pipe and fittings. Tighten the joint no more than 2 threads past hand-tight.

3.2.3.2.1.2 Push-On Joints

Bevel the ends of pipe for push-on joints to facilitate assembly. Mark pipe to indicate when the pipe is fully seated. Lubricate the gasket to prevent displacement. Exercise care to ensure that the gasket remains in proper position in the bell or coupling while making the joint.

3.2.3.2.1.3 Solvent-Weld Joints

Comply with the manufacturer's instructions.

3.2.3.2.2 Pipe 4 inch Diameter And Larger

Make push-on joints with AWWA C900 pipe with intrgral elastomeric gasket. For pipe-to-pipe push-on joint connections, use only pipe with push-on joint ends having factory-made bevel. For push-on joint connections to fittings, use cut spigot end of pipe off square, marked to match the manufacturer's insertion line and beveled to match factory supplied bevel. Use an approved lubricant recommended by the pipe manufacturer for push-on joints. Assemble push-on joints for pipe-to-pipe joint connections in accordance with the requirements of AWWA C605. Assemble push-on joints for connection to fittings in accordance with the requirements of AWWA C605 for joining PVC pipe to fittings and accessories and with the applicable requirements of AWWA C600 for joint assembly. Make mechanical-joints or flanged jointswith the gaskets, glands, bolts, nuts, and internal stiffeners specified for this type joint and assemble in accordance with the requirements of AWWA C605 for joining PVC pipe to fittings and accessories or with the applicable requirements of AWWA C600

for ductile iron joint assembly, and with the recommendations of Appendix A to AWWA C111/A21.11. Cut off spigot end of pipe for mechanical-joint or flanged jointconnections and do not bevel.

3.2.3.2.3 Pipe Anchorage

Provide concrete thrust blocks (reaction backing) for pipe anchorage. Size and position thrust blocks as indicated. Use concrete conforming to ASTM C94/C94M having a minimum compressive strength of 2,000 psi at 28 days; or use concrete of a mix not leaner than one part cement, 2 1/2 parts sand, and 5 parts gravel, having the same minimum compressive strength.

3.2.4 Manhole Construction

Construct base slab of cast-in-place concrete or use precast concrete base sections. Make inverts in cast-in-place concrete and precast concrete bases with a smooth-surfaced semi-circular bottom conforming to the inside contour of the adjacent sewer sections. For changes in direction of the sewer and entering branches into the manhole, make a circular curve in the manhole invert of as large a radius as manhole size will permit. For cast-in-place concrete construction, either pour bottom slabs and walls integrally or key and bond walls to bottom slab. No parging will be permitted on interior manhole walls. For precast concrete construction, make joints between manhole sections with the gaskets specified for this purpose; install in the manner specified for installing joints in concrete piping. Parging will not be required for precast concrete manholes. Perform cast-in-place concrete work in accordance with the requirements specified under paragraph entitled "Concrete Work" of this section. Make joints between concrete manholes and pipes entering manholes with the resilient connectors specified for this purpose; install in accordance with the recommendations of the connector manufacturer. Where a new manhole is constructed on an existing line, remove existing pipe as necessary to construct the manhole. Cut existing pipe so that pipe ends are approximately flush with the interior face of manhole wall, but not protruding into the manhole. Use resilient connectors as previously specified for pipe connectors to concrete manholes.

3.2.5 Miscellaneous Construction and Installation

3.2.5.1 Connecting to Existing Manholes

Connect pipe to existing manholes such that finish work will conform as nearly as practicable to the applicable requirements specified for new manholes, including all necessary concrete work, cutting, and shaping. Center the connection on the manhole. Holes for the new pipe are be of sufficient diameter to allow packing cement mortar around the entire periphery of the pipe but no larger than 1.5 times the diameter of the pipe. Cut the manhole in a manner that will cause the least damage to the walls.

3.2.5.2 Metal Work

3.2.5.2.1 Workmanship and Finish

Perform metal work so that workmanship and finish will be equal to the best practice in modern structural shops and foundries. Form iron to shape and size with sharp lines and angles. Do shearing and punching so that clean true lines and surfaces are produced. Make castings sound and

free from warp, cold shuts, and blow holes that may impair their strength or appearance. Give exposed surfaces a smooth finish with sharp well-defined lines and arises. Provide necessary rabbets, lugs, and brackets wherever necessary for fitting and support.

3.2.5.2.2 Field Painting

After installation, clean cast-iron frames, covers, gratings, and steps not buried in concrete to bare metal, remove mortar, rust, grease, dirt, and other deleterious materials and apply a coat of bituminous paint. Do not paint surfaces subject to abrasion.

3.3 FIELD QUALITY CONTROL

The Contracting Officer will conduct field inspections and witness field tests specified in this section. Be able to produce evidence, when required, that each item of work has been constructed in accordance with the drawings and specifications.

3.3.1 Tests

Perform field tests and provide labor, equipment, and incidentals required for testing.

3.3.1.1 Leakage Tests for Nonpressure Lines

Test lines for leakage by either or by low-pressure air tests. When necessary to prevent pipeline movement during testing, place additional backfill around pipe sufficient to prevent movement, but leaving joints uncovered to permit inspection. When leakage or pressure drop exceeds the allowable amount specified, make satisfactory correction and retest pipeline section in the same manner. Correct visible leaks regardless of leakage test results.

3.3.1.1.1 Negative Air Pressure Test3.3.1.1.1.1 Precast Concrete Manholes

Test precast concrete sewer manhole test in accordance with ASTM C1244. The allowable vacuum drop is located in ASTM C1244 Make calculations in accordance with the Appendix to ASTM C1244.

3.3.1.1.2 Low-Pressure Air Tests

3.3.1.1.2.1 PVC Pipelines

Test PVC pipe in accordance with UBPPA UNI-B-6. The allowable pressure drop is located in UBPPA UNI-B-6. Make calculations in accordance with the Appendix to UBPPA UNI-B-6.

3.3.1.2 Tests for Pressure Lines

Test pressure lines in accordance with the applicable standard specified in this paragraph, except for test pressures. For hydrostatic pressure test, use a hydrostatic pressure 50 psi in excess of the maximum working pressure of the system, but not less than 100 psi, holding the pressure for a period of not less than one hour. For leakage test, use a hydrostatic pressure not less than the maximum working pressure of the system. Leakage test may be performed at the same time and at the same test pressure as the pressure test.

3.3.1.2.1 PVC Pressure Pipe

Test PVC pressure pipe in accordance with the requirements of AWWA C605 for hydrostatic and leakage tests. The quantity of water that must be supplied during testing is not to exceed the quantity of water calculated in accordance with AWWA C605 to maintain the specified test pressure within 5 psi.

3.3.2 Inspection

3.3.2.1 Post-Installation Inspection

Perform a post-installation CCTV inspection after connection has been made and before the connection is buried. Submit post-installation inspection request for field support at least 14 days in advance. The Installation's Utilities Field Support personnel will perform the post-connection inspection.During the post-installation inspection the Contractor will be responsible for performing a CCTV test according to Section 33 01 30.16 CCTV Sewer Inspection.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 31 23.00 10

SANITARY SEWER FORCE MAIN PIPING
08/18

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO HB-17	(2002; Errata 2003; Errata 2005, 17th Edition) Standard Specifications for Highway Bridges

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.1	(2020) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C110/A21.10	(2021) Ductile-Iron and Gray-Iron Fittings
AWWA C111/A21.11	(2017) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C115/A21.15	(2020) Flanged Ductile-Iron Pipe With Ductile-Iron or Gray-Iron Threaded Flanges
AWWA C151/A21.51	(2017) Ductile-Iron Pipe, Centrifugally Cast
AWWA C203	(2025) Coal-Tar Protective Coatings and Linings for Steel Water Pipe and Fittings
AWWA C210	(2015) Standard for Liquid Epoxy Coating Systems for the Interior and Exterior of Steel Water Pipelines
AWWA C500	(2019) Metal-Seated Gate Valves for Water Supply Service
AWWA C600	(2017) Installation of Ductile-Iron Mains and Their Appurtenances
AWWA C900	(2016) Polyvinyl Chloride (PVC) Pressure Pipe, and Fabricated Fittings, 4 In. Through 60 In. (100 mm Through 1,500 mm)
AWWA C909	(2022) Molecularly Oriented Polyvinyl Chloride (PVCO) Pressure Pipe, 4 In. (100 mm) and Larger

ASTM INTERNATIONAL (ASTM)

ASTM D1784	(2020) Standard Specification for Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D2241	(2015) Standard Specification for Poly(Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series)
ASTM D2464	(2015) Standard Specification for Threaded Poly(Vinyl Chloride) (PVC) Plastic Pipe Fittings, Schedule 80
ASTM D2564	(2020) Standard Specification for Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems
ASTM D2774	(2021) Underground Installation of Thermoplastic Pressure Piping
ASTM D3139	(2019) Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals
ASTM D3308	(2012; R 2022) Standard Specification for PTFE Resin Skived Tape
ASTM D4161	(2014) "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe Joints Using Flexible Elastomeric Seals
ASTM F477	(2014; R 2021) Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe
ASTM F1483	(2023) Standard Specification for Oriented Poly(Vinyl Chloride), PVCO, Pressure Pipe

DUCTILE IRON PIPE RESEARCH ASSOCIATION (DIPRA)

DIPRA TRD	(2016) Thrust Restraint Design for Ductile Iron Pipe

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-06 Test Reports

Disposal of Waste Water

Final Test Report

1.3 DELIVERY, STORAGE, AND HANDLING

Do not damage pipe, fittings and accessories, and pipe coatings during delivery, handling, and storage.

PART 2 PRODUCTS

2.1 PIPE AND FITTINGS

Provide piping in locations and sizes as specified in the following table. Also conform to the respective specifications and other requirements specified below

Location	Piping Size Range	Piping Material
Force Mains	4 inches in diameter and larger	Ductile Iron, Steel, Concrete Pressure Pipe, PVC Plastic, Oriented PVC PE Plastic, or Reinforced Thermosetting Resin Pipe (RTRP)
Inside Pump Stations	4 inches in diameter and larger	Ductile Iron Pipe with Bolted Flange Joints

2.1.1 Plastic Pipe

2.1.1.1 PVC Pressure Pipe

b. PVC Pressure Pipe and Fittings 4 inches Diameter and Larger: ASTM D2241, SDR 21, or AWWA C900, Class 100, with push-on joints.

2.1.1.2 Oriented Polyvinyl Chloride (PVCO) Plastic Pipe

Provide pipe, couplings, and fittings manufactured of material conforming to ASTM D1784, Class 12454-B. Provide pipe conforming to AWWA C909, Class 150, and to ASTM F1483 with an outside diameter equal to cast iron outside diameter.

2.1.2 Ductile Iron Pipe

2.1.2.1 Ductile Iron Pipe

AWWA C151/A21.51, working pressure not less than 150 psi, unless otherwise shown or specified.

2.1.2.2 River Crossing Pipe

AWWA C151/A21.51, minimum thickness Class 54 with joints in compliance with applicable requirements of AWWA C110/A21.10.

2.1.2.3 Fittings, Mechanical

AWWA C110/A21.10, rated for 150 psi.

2.1.2.4 Fittings, Push-On

AWWA C110/A21.10 and AWWA C111/A21.11, rated for 150 psi.

2.2 JOINTS

2.2.1 PVC Piping

Provide centering rings or stops to ensure couplings used with plain end pipe are centered on the joint.

2.2.1.1 Screw Joint Fittings

ASTM D2464, Schedule 80

2.2.1.2 Push-On Joint Fittings

ASTM D3139, with ASTM F477gaskets

2.2.1.3 Solvent Cement

ASTM D2564

2.2.2 Ductile Iron Piping

2.2.2.1 Push-on Joints

AWWA C111/A21.11.

2.2.2.2 Mechanical Joints

AWWA C111/A21.11 as modified by AWWA C151/A21.51.

2.2.2.3 Flanged Joints

AWWA C115/A21.15.

2.2.3 RPMP Piping

Provide bell and spigot gasket coupling joints utilizing an elastomeric gasket in accordance with ASTM D4161 and ASTM F477.

2.3 VALVES

2.3.1 Gate Valves

Provide gate valves 3 inches and larger in compliance with AWWA C500. Provide non-rising stem (NRS) valves for buried service, 2 inch square nut operated with joints applicable to the pipe or installation. Furnish buried valves with extension stems comprising socket, extension stem and operating nut, and of an appropriate length to bring operating nut to within 6 inches of grade. Provide one 4 foot "T" handle valve wrench for each quantity of 6 buried valves. Provide outside screw and yoke (OS&Y), handwheel operated with flange ends for gate valves that are exposed or installed inside unless otherwise indicated. Cast an arrow and the word "OPEN" on all gate valve operating nuts and handwheels in raised letters to indicate the direction of opening. Equip gate valves 14 inches and larger with gearing to reduce operating effort. Equip gate valves 14 inches and larger, installed in horizontal lines in horizontal position

with stems horizontal, with bronze track, roller and scrapers to support the weight of the gate for its full length of travel. Fit gate valves 14 inches and larger installed in vertical pipe lines with stems horizontal with slides to assist the travel of the gate assembly.

2.3.2 Check Valves

Provide iron-bodied check valves that permit free flow of sewage forward and provide a positive check against backflow. Design check valves for a minimum working pressure of 150 psi or as indicated. Directly cast the manufacturer's name, initials, or trademark and also the size of the valve, working pressure, and direction of flow on the body.

2.3.2.1 Ball Check Valves

Provide iron-bodied ball check valves, with flanged ends, that are of the non-slam type. Provide 125 pound type flanges complying with ASME B16.1 with stainless steel ball unless otherwise specified.

2.3.3 Air Release Valves

Provide air release valves designed to permit release of air from an empty pipe during filling and capable of discharging accumulated air in the line while the line is in operation and under pressure. Attach valves by means of threaded pipe connections. Vent valves to the atmosphere.

2.3.3.1 Automatic Air Release Valve

Compound lever type capable of withstanding operating pressures of 150 psi, with a 1/2 inch outlet. Provide with iron body and cover of the valve and a stainless steel float. Provide internal parts made entirely of stainless steel or bronze. Provide valve specifically adapted for use with sewage and complete with hose and blow-off valves to permit backflushing without dismantling the valve.

2.4 VALVE VAULTS

Cast iron or concrete, except design concrete vaults installed in locations subject to vehicular traffic to withstand the following AASHTO load designation as outlined in AASHTO HB-17. Provide extension type cast iron vaults with slide type adjustment and flared base. Provide 3/16 inch minimum metal. Ensure that the vault length is adaptable, without full extension, to the depth of cover over the pipe at the valve locations. Cast the word "SEWER" in the cover.

2.5 MISCELLANEOUS MATERIALS

Provide miscellaneous materials in compliance with the following requirements:

2.5.1 Pipe Coatings and Linings

a. Steel, interior: AWWA C203 or AWWA C210.

b. Steel, exterior, buried: AWWA C203.

c. Steel, exterior, exposed: AWWA C210.

2.5.2 Joint Lubricants

Provide joint lubricants as recommended by the pipe manufacturer.

2.5.3 Bolts, Nuts and Glands

AWWA C111/A21.11.

2.5.4 Joint Compound

A stiff mixture of graphite and oil or inert filler and oil.

2.5.5 Joint Tape

ASTM D3308.

2.5.6 Bond Wire

Bond wire type RHW or USE, Size 1/0 AWG, neoprene jacketed copper conductor shaped to stand clear of the joint.

PART 3 EXECUTION

3.1 INSTALLATION

Install pipe, pipe fittings, and appurtenances at the locations indicated. Perform excavation, trenching, and backfilling as specified in Section 31 00 00 EARTHWORK.

3.1.1 Cutting

Cut pipe in a neat manner with mechanical cutters. Use wheel cutters where practicable. Grind sharp and rough edges smooth and remove loose material from the pipe before laying.

3.1.2 Laying

Except where otherwise authorized, lay pipe with bells facing the direction of laying. Before lowering and while suspended, inspect the pipe for defects. Reject defective material. Lay pipe in compliance with the following:

Ductile Iron	AWWA C600
Steel	AWWA C600
Concrete	Manufacturer's instructions
Polyvinyl Chloride	Manufacturer's instructions
Polyethylene	ASTM D2774
Polypropylene	ASTM D2774
Reinforced Thermosetting Resin	Manufacturer's instructions

Reinforced Plastic Mortar	Manufacturer's instructions

3.1.3 Jointing

3.1.3.1 Joints for PVC Pipe

a. Make threaded joints by wrapping the male threads with joint tape or by applying an approved thread lubricant, then threading the joining members together. Tighten the joint with strap wrenches taking care not to damage the pipe and fittings. Tighten the joint no more than 2 threads past hand-tight.

b. Bevel the ends of pipe for push-on joints to facilitate assembly. Mark pipe to indicate when the pipe is fully seated. Lubricate the gasket to prevent displacement. Ensure the gasket remains in proper position in the bell or coupling while the joint is made.

c. Ensure solvent-weld joints comply with the manufacturer's instructions.

3.1.3.2 Joints for Ductile Iron Pipe

Install mechanical and push-on type joints in compliance with AWWA C600 and the manufacturer's instructions. Install flanged joints in compliance with manufacturer's instructions.

3.1.4 Installation of Valves

Prior to installation, clean valves of all foreign matter and inspect for damage and then fully open and close valves to ensure that all parts are properly operating. Install valves with the stem in the vertical position. Install valves in valve vaults as indicated.

3.1.5 Installation of Valve Boxes

Install valve boxes over each outside gate valve, unless otherwise indicated. Center valve boxes over the valve. Carefully tamp fill around each valve box to a distance of 4 feet on all sides or to undisturbed trench face, if less than 4 feet.

3.1.6 Installation of Valve Vaults

Install valve vaults as indicated.

3.1.7 Drain Lines

Install drain lines where indicated. The drain line consists of a tee in the main line with a 4 inch diameter branch, a 4 inch diameter elbow, and a 4 inch gate valve.

3.1.8 Thrust Restraint

Provide thrust restraint as specified in Section 33 11 00 WATER UTILITY DISTRIBUTION PIPING. Securely anchor valves or provide with thrust restraints to prevent movement. Install thrust restraints made from either thrust blocks or, for ductile-iron pipes, restrained joints.

3.1.8.1 Thrust Blocks

Provide concrete thrust blocking of a mix not leaner than: 1 cement, 2-1/2 sand, 5 gravel; and having a compressive strength of not less than 2000 psi after 28 days. Place blocking between solid ground and the fitting to be anchored. Unless otherwise indicated or directed, place the base and thrust bearing sides of thrust blocks directly against undisturbed earth. Place the side of thrust blocks not subject to thrust against forms, if applicable. Provide the area of bearing as shown or as directed. Place blocking so that the fitting joints are accessible for repair. Use steel rods and clamps, protected by galvanizing or by coating with bituminous paint, to anchor vertical down bends into gravity thrust blocks.

3.1.8.2 Restrained Joints

For ductile iron pipe, design restrained joints in accordance with DIPRA TRD.

3.1.9 Grout

Provide grout mix for exterior joint protection on concrete pipes of 1 part portland cement, 2 parts sand, and of sufficient liquid consistency to flow into the joint recess beneath the diaper. Provide grout mix for interior joint protection of 1 part portland cement and 1 part sand. Substitute a polyurethane foam loop, impregnated with portland cement, in lieu of grout for exterior joints, if directed.

3.1.10 Bonded Joints

Where indicated, provide a thermally welded metallic bond at each joint, including joints made with flexible couplings or rubber gaskets, of ferrous-metallic piping to effect continuous conductivity.

3.2 FIELD QUALITY CONTROL

Perform both a pressure test and a leakage test on all pipelines. Obtain the Contracting Officer's approval of the method proposed for disposal of waste water from hydrostatic tests. Notify the Contracting Officer at least 7 days in advance of equipment tests. Submit the final test report to the Contracting Officer within 30 days after the test.

3.2.1 Pressure Test

After installing the pipe, joints, and thrust blocks, wait at least five days before pressure testing. For the pressure test, partially backfill the trench but leave the joints exposed for examination, then fill the pipe with water to expel all air. Subject the pipeline to a test pressure of 100 psi or 150 percent of the working pressure, whichever is greater, for a period of at least one hour. Open and close each valve several times during the test. Examine the exposed pipe, joints, fitting, and valves for leaks. Stop visible leaks or replace defective pipe, fittings, joints, or valves.

3.2.2 Leakage Test

Conduct the leakage test subsequent to or concurrently with the pressure test. Place the amount of water permitted as leakage for the line in a sealed container attached to the supply side of the test pump. Apply no

other source of supply to the pump or line under test. Pump the water into the line by the test pump as required to maintain the specified test pressure as described for a 2 hour period. The test will be considered a failure upon exhaustion of the supply or the inability to maintain the required pressure. PE pipe experiences diametric expansion and pressure elongation during initial testing. Consult the manufacturer prior to testing for special testing considerations. Determine allowable leakage by the following I-P formula:

L = NDP/K Where:

L = Allowable leakage in gallons per hour.

N = Number of joints in length of pipeline tested.

D = Nominal diameter of the pipe in inches.

P = Square root of the test pressure in psig.

K = 7400 for pipe materials.

At the conclusion of the test, measure the amount of water remaining in the container and record the results in the test report.

Test ductile iron pressure lines in accordance with the requirements of AWWA C600.

3.2.3 Retesting

If any deficiencies are revealed during any test, correct such deficiencies and repeat the tests until the results of the tests are within specified allowances, without additional cost to the Government.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 32 16

PACKAGED UTILITY WASTEWATER PUMPING STATIONS
11/19

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.1	(2020) Gray Iron Pipe Flanges and Flanged Fittings Classes 25, 125, and 250
ASME B16.3	(2021) Malleable Iron Threaded Fittings, Classes 150 and 300
ASME B16.11	(2021) Forged Fittings, Socket-Welding and Threaded

AMERICAN WATER WORKS ASSOCIATION (AWWA)

AWWA C110/A21.10	(2021) Ductile-Iron and Gray-Iron Fittings
AWWA C111/A21.11	(2017) Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C115/A21.15	(2020) Flanged Ductile-Iron Pipe With Ductile-Iron or Gray-Iron Threaded Flanges
AWWA C151/A21.51	(2017) Ductile-Iron Pipe, Centrifugally Cast
AWWA C500	(2019) Metal-Seated Gate Valves for Water Supply Service
AWWA C509	(2015) Resilient-Seated Gate Valves for Water Supply Service
AWWA C515	(2020) Reduced-Wall, Resilient-Seated Gate Valves for Water Supply Service
AWWA C600	(2017) Installation of Ductile-Iron Mains and Their Appurtenances
AWWA C605	(2021) Underground Installation of Polyvinyl Chloride (PVC) and Molecularly Oriented Polyvinyl Chloride (PVCO) Pressure Pipe and Fittings

ASTM INTERNATIONAL (ASTM)

ASTM A48/A48M	(2003; R 2021) Standard Specification for Gray Iron Castings

ASTM A53/A53M	(2024) Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless
ASTM A126	(2004; R 2023) Standard Specification for Gray Iron Castings for Valves, Flanges, and Pipe Fittings
ASTM A536	(1984; R 2019; E 2019) Standard Specification for Ductile Iron Castings
ASTM A615/A615M	(2022) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM C443	(2021) Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets
ASTM C478	(2018) Standard Specification for Circular Precast Reinforced Concrete Manhole Sections
ASTM C618	(2025a) Standard Specification for Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use in Concrete
ASTM C989/C989M	(2022) Standard Specification for Slag Cement for Use in Concrete and Mortars

INTERNATIONAL ORGANIZATION FOR STANDARDIZATION (ISO)

ISO 1940-1	(2003; R 2008) Mechanical Vibration - Balance Quality Requirements for Rotors in a Constant (Rigid) State - Part 1: Specification and Verification of Balance Tolerances

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

NEMA MG 1	(2021) Motors and Generators

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code
NFPA 820	(2016) Standard for Fire Protection in Wastewater Treatment and Collection Facilities

UL SOLUTIONS (UL)

UL 67	(2018; Reprint Jul 2020) UL Standard for Safety Panelboards

UL 489 (2025) UL Standard for Safety Molded-Case Circuit Breakers, Molded-Case Switches and Circuit-Breaker Enclosures

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-02 Shop Drawings

Fabrication Drawings

Erection/Installation Drawings

SD-03 Product Data

Submersible Sewage nonclog Pumps; G

Pump Performance Curve; G

Pump Motor; G

Pump Control System; G

Wet Well and Valve Vault; G

Flexible Flanged Coupling; G

Station Piping and fittings; G

Valves; G

Spare Parts Data; G

Access Hatch Covers

SD-05 Design Data

Buoyancy Calculations; G

SD-06 Test Reports

Pump Test; G

SD-07 Certificates

Submersible Sewage nonclog Pumps; G

Recycled Material Content

Manhole Chamber

Access Hatch Covers

Gate Valves

Check Valves

Blowers

Dehumidifier

Pump Motor

SD-08 Manufacturer's Instructions

Manhole Chamber

Access Hatch Covers

Pump Control System

Gate Valves

Check Valves

Blowers

Dehumidifier

Pump Motor

Special Tools

Posted Instructions

SD-10 Operation and Maintenance Data

Operation And Maintenance Manuals

SD-11 Closeout Submittals

Warranty

1.3 QUALITY CONTROL

1.3.1 Installer Qualifications

Provide manufacturer's authorized pump representative who is trained and approved for installation of pumps and packaged pump station required for this project.

1.4 DELIVERY, STORAGE, AND HANDLING OF MATERIALS

1.4.1 Delivery and Storage

Inspect materials delivered to site for damage. Unload and store with minimum handling. Store materials in enclosures or under protective covering. Rubber gaskets which are not to be installed immediately must be stored under cover, out of direct sunlight. Do not store materials directly on the ground. Keep interior of pipes, valves and fittings free of dirt and debris.

1.4.2 Handling

Handle pipe, fittings, valves, and other accessories in such manner as to

ensure delivery to the trench in sound, undamaged condition. Avoid injury to coatings and linings on pipe and fittings; make repairs if coatings or linings are damaged. Carry pipe to the trench; do not drag it. Do not use any device or fitting inserted into (such as loader forks) or attached to (such as chain hooks) the bell or spigot ends of the pipe to transport pipe. Handle ductile iron pipe, fittings, and accessories in accordance with AWWA C600. Handle PVC pipe, fittings, and accessories in accordance with AWWA C605.

1.5 WARRANTY

Provide manufacturer's standard warranty for a minimum of one year for package pump station including pumps, valves, controls, wet well basin and accessories.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

Provide a complete packaged sewage pump station with submersible nonclog pumps including equipment and materials, installed and ready for operation. The pump supplier furnishes the controls, pumps and rail system to ensure unit integrity.

Submit fabrication drawings before installation. Submit drawings covering necessary or recommended changes to accommodate the equipment offered. Show on the drawings the design of the chamber, with dimensions, types, and thicknesses of materials, and elevation levels with reference to those elevations indicated.

Submit erection/installation drawings for the manhole chamber with the required equipment and accessories. Provide precast reinforced concrete manhole sections conforming to ASTM C478. Show the design of the chamber, with dimensions, types, and thicknesses of materials, and elevation levels with reference to those elevations indicated.

2.2 SUBMERSIBLE SEWAGE NONCLOG PUMPS

Provide submersible sewage nonclog pumps as indicated. Provide UL listed pumps for explosion proof Class 1, Division 1, Groups C and D hazardous locations. Provide submersible, centrifugal sewage pumps of the nonclogging type with passageways designed to pass 3 inch diameter spheres without clogging. Provide pump capacity, number of pumps and motor characteristics as indicated on the drawings. Select pumps to continuously operate in a submerged or partially submerged condition.

2.2.1 Pump Construction

2.2.1.1 Casing

Provide hard, close-grained cast iron casing or steel that is free from blow holes, porosity, hard spots, shrinkage defects, cracks, and other injurious defects. Provide casings permitting replacement of wearing parts. Ensure all joints are gasketed to prevent leakage. Ensure passageways permit smooth flow of sewage and are free of sharp turns and projections.

2.2.1.2 Impeller

Provide nonclogging type cast-iron impeller, conforming to ASTM A48/A48M, Class 30, for a submersible nonclog pump. Ensure the impeller has a smooth surface and allows free flowing with the clearance to permit objects in the sewage to pass. Fit and key, spline, or thread impeller on shaft, and lock in such manner that lateral movement is prevented and reverse rotation will not cause loosening.

2.2.1.3 Bearings

Provide heavy duty ball thrust bearing or roller type bearing sized to withstand imposed loads. Oil lubricate bearings.

2.2.1.4 Lubrication

Provide the pump manufacturer's standard type grease fittings.

2.2.1.5 Balance

Balance rotating parts of the equipment mechanically and hydraulically to operate throughout the required range without excessive end thrust, vibration, and noise. Conform allowable vibration limits with ISO 1940-1, Table 1. Existence of defects that cannot be eliminated by adjustment will be sufficient cause for rejection of the equipment.

2.3 PUMP MOTOR

Provide hermetically sealed electric motors with moisture and temperature-sensing probes in the wet well NEMA MG 1, 3450 RPM, 460 volt, 3 phase, and 60 Hz cycle for submersible pumps. Motor horsepower must not be less than pump horsepower at any point on the pump performance curve. Fit motors with lifting "eyes" capable of supporting entire weight of pump and motor. Seal the power cable inside the motor end bell. Provide a waterproof power cable for its full length. Motors will be UL listed for explosion proof Class 1, Division 1, Groups C and D. Air filled motors are not acceptable. Oil used must be able to be disposed as non-hazardous waste.

2.4 PUMP CONTROL SYSTEM

2.4.1 General

Provide an automatic type pump operating control including all necessary components to function reliably. Mount controls in a NEMA 3R rated stainless steel control panel. Ensure equipment subject to contact with sewage or sewage gases is corrosion-resistant metal. Provide an electronic controller that automatically activates and alternates the pump operation. If the liquid level continues to rise to the plans-specified level, the controller engages both pumps to operate simultaneously until both shut off at the specified low level. Provide hand-off-auto switches to choose the mode of operation for each pump. Provide controls with a 12 VDC powered float switch connected to the alarm contact of the battery charger to activate high-level alarms.

Protect pumping stations from lightning and transient voltage surges and equip with phase protection.

Provide the station with a three-wire, 4-pole (grounding) receptacle for a

portable generator in case there is an external power outage.

Design the control system to operate pumps at the power characteristics as shown on the plans. Ensure all controls and wiring meet or exceed the requirements of NFPA 70.

For pumps specified as explosion proof, have pump power and control installation meets NEC requirements for Class 1, Division 1, Group D Hazardous Location, including intrinsically safe controls. Provide components that are UL listed or FM approved.

Require the control function to provide for the operation of the pumps under normal conditions and alternates the pumps on each pump down cycle.

In the event the incoming flow exceeds the pumping capacity of the lead pump, the offline pumps automatically start to handle the increased flow. As the flow decreases, the pumps cut off at the elevations set on the controller.

2.4.2 Enclosure

Provide a NEMA 3R rated enclosure manufactured from stainless steel. Provide a rubber composition door gasket and assures a positive weatherproof seal. Provide a door that opens a minimum of 180 degrees and is equipped with a 3-point latch and padlockable handle.

Provide a dead front mounted in the panel to provide protection of personnel from live internal wiring. Install cutouts for breaker handles to allow operation of breakers without entering the compartment.

Mount all control switches, indicator pilot lights, elapsed time meters, duplex receptacle and other operational devices on the external surface of the dead front.

Ensure the dead front opens a minimum of 150 degrees to allow access to equipment for maintenance.

Manufacture the back plate from 12-gauge (minimum) steel and finished with a primer coat and two (2) coats of baked on white enamel. Mount all hardware to the subpanel with machine thread tapped holes. Sheet metal screws are not acceptable. Permanently identify all devices to match the schematic diagram.

Provide an enclosure ventilator located near the top of the enclosure on the opposite side of the generator receptacle. Provide a rain and vermin proof ventilator and made of fire retardant thermoplastic material.

2.4.3 Level Control System

Provide a sealed, mercury-free float switch control system to sense variations of sewage level in the wet well.

Use a direct acting float switch consisting of a normally-open mercury switch enclosed in a float. Use float molded of rigid high-density polyurethane foam, color-coded and coated with a durable, water and corrosion-resistant jacket of clear urethane.

Provide stainless steel float brackets in accordance with manufacturer's recommendations.

Mount floats at fixed elevations as shown on the drawings.

Use floats designed to tilt and operate their switches causing sequential turn-on turn-off of the pump, when the liquid level being sensed rises or falls past the float.

Float switches must be intrinsically safe relays. Provide an intrinsically safe barrier relay between the wet well and the control panel.

Provide an intrinsically safe barrier relay between the wet well and the control panel.

2.4.4 Alternator

Provide an alternator control switch to operate in connection with each float. Use an alternator control switch to alternate the operation of the pumps and operate both pumps if the water level rises above the second high water level. Incorporate time delay function and devices in the alternator controls such that both sewage pumps cannot be started simultaneously for an adjustable period of 10 to 120 seconds after shutdown. Use the delay function designed to operate in any condition of start-up in either normal or emergency operational mode.

2.4.5 Sewage Pump Alarm and Control Panel

Enclose alarm panel in NEMA 4X enclosure and with a flashing red light that is visible from 50 feet away, with long life bulb in guarded enclosure and 6 inch diameter horn. Use horns capable of emitting 120 DB at 10 feet. Power alarm horn and light from 12V DC power supply with battery backup. Provide a rechargeable battery rated to power both the horn and light for a minimum of two hours upon loss of main power. Provide circuitry to automatically recharge the battery after main power is restored. Use batteries capable of being fully recharged in no more than 20 hours. Use panel with power on light, push to test button for horn and light and push to silence button for horn and light with automatic reset for next alarm.

2.4.5.1 Alarms

Provide a test function ability for the alarm system. Provide alarms to activate under the following conditions:

a. High liquid level as sensed by the level control system.

b. Loss of main power.

c. No flow light as sensed by limit switch on the check valve or as sensed by current sensors.

d. Pump failure via temperature overload or motor heat sensor trip; provide motor high temperature light.

e. Seal failure with indication light.

2.4.5.2 Circuit Breakers

a. Provide an individual circuit breaker for each pump.

b. Include a control circuit breaker and an alarm circuit breaker in the control panel.

c. Allow for two additional spare 115V single phase 20A circuit breakers for local pole lighting and future spare.

d. Provide circuit breakers in accordance with UL 489

e. Conform to UL 67 for circuit breaker mounting.

2.4.5.3 Motor Starter and Overload Protection

Provide an International Electrotechnical Commission (IEC) rated motor starter and thermal overload protection located in the control panel for each pump. Include undervoltage release, manual reset buttons and hand-automatic selector switches.

2.4.5.4 Power Lugs

a. Size the incoming power lugs for the proper voltage, amperage, and horsepower for each pump station.

b. Include grounding lugs for the incoming power. Provide a dedicated grounding lug in the control panel for each pump.

c. Size ground lug and rod according to local and base electrical codes and install by a licensed electrician.

d. Use UL listed power lugs.

e. Conform to UL 67 for required power lug mounting.

2.4.5.5 Anti-Condensation Heater

a. Provide an anti-condensation heater in the control panel that is sized based upon the size of the particular pump station's control panel size.

b. Power the heater from the control voltage transformer for three phase pump motor units and from the incoming power for single phase pump motor units.

c. Control the heater by a thermostat, coming on at 50 degree F and going off at 65 degree F.

d. Clearly label panel directory for breakers.

2.4.5.6 Trouble Light

Provide a fluorescent trouble shooting light in the panel that is hard-wired into an appropriately sized circuit breaker. It is acceptable for the light and one of the convenience outlets to share the same circuit breaker.

2.4.5.7 Convenience Outlets

a. Place two duplex convenience outlets in the control panel; utilize one for the battery charger. The battery receives power from the control

voltage transformer via the alarm fuse.

b. Upsize the alarm fuse to 1 to 1.5 amps for the battery charger.

c. Provide each outlet with its own 20 amp 115/1/60 circuit breaker.

2.4.5.8 Additional Requirements

a. Provide elapsed time meter for each pump that measures run time in hours to 9999.9.

b. Do not place junction boxes between pumps, control systems and control panels; provide conduit seals at all wet well penetrations. If this is unavoidable, use NEMA 7 construction.

2.4.6 Electrical Requirements

Install labels to identify switches and controls. Provide internal wiring for components of packaged equipment as an integral part of the equipment. Provide power wiring and conduit for field installed equipment.

2.5 WET WELL AND VALVE VAULT

2.5.1 Wet Well and Valve Vault

Provide a precast concrete wet well; include a separate precast concrete valve vault. Provide a wet well and valve vault with inside diameters as indicated and to the depths indicated on the drawings.

Precast structures may be provided in lieu of cast-in-place structures.

2.5.1.1 Precast Concrete Structures

Submit manufacturer's data indicating percentage of recycled material content in packaged sewage lift stations to verify affirmative procurement compliance.

Fly ash is required as an admixture and is to conform to ASTM C618, Class F. Fly ash replacement of cement is not to exceed 20 percent (maximum one part fly ash to four parts cement) by weight.

Ground granulated blast furnace slag used as an admixture is to conform to ASTM C989/C989M, Grade 120 with between 25 to 50 percent maximum cement replacement by weight. Submit certificate to verify EPA-CPG compliance.

a. Buoyancy Calculations: Submit buoyancy calculations sealed by a licensed professional engineer assuming seasonal high groundwater elevation at proposed finished grade.

b. Construct precast concrete structures in accordance with ASTM C478, except as specified herein. Provide precast concrete structures with a compressive strength of 4000 psi at 28 days and an air entrainment of 6 percent, plus or minus 2 percent, and a minimum wall thickness of 5 inches. ASTM A615/A615M reinforcing bars. ASTM C443, Type B gaskets for joint connections. Use monolithic base and first riser.

2.5.2 Access Hatch Covers

Provide aluminum access hatch covers as indicated. Include lifting

mechanism, automatic hold open arm, slam lock with handle, and flush lift handle with vinyl grip. Use automatic hold open arm that locks in the 90 degree position. Use cover that is 1/4 inch diamond plate with 1/4 inch channel frame and continuous anchor flange. Use access hatch cover capable of withstanding a live load of 300 lb/sq. ft. Provide stainless steel cylinder lock with two keys per lock. Key all the locks the same.

2.5.3 Wet Well Base Material

Provide crushed stone as indicated and specified in Section 31 00 00 EARTHWORK.

2.5.3.1 Ventilating Blower

Ensure blowers maintain air changes in accordance with NFPA 820. Mount a manual and automatic switch on the side of the entrance tube for operation of the blower. Provide vent to atmosphere with covers and screens to prevent the entrance of rain, insects, and rodents. Automatically actuate blower upon opening the entrance tube cover, unless overridden by the manual control.

2.5.3.2 Dehumidifier

Furnish and install a packaged dehumidifier in accordance with lift station manufacturer's recommendations. Include in controls a humidistat and low-temperature cutout/discharge condensate to the wet well.

2.6 STATION PIPING

Provide pressure piping, emergency pump connection, air release valves, and related accessories for force main piping outside the sewage wet well and valve vault in accordance with Section 33 30 00 SANITARY SEWERAGE.

2.6.1 Ductile-Iron Pressure Pipe and Associated Fittings

Conform to AWWA C151/A21.51, Pressure Class 350.

2.6.1.1 Flanged Pipe

Conform to AWWA C115/A21.15, ductile iron.

2.6.1.2 Fittings

AWWA C110/A21.10, flanged. Provide flanged joint fittings within wet well and valve vault as indicated. Provide mechanical joint fittings outside valve vault enclosure as indicated. Use fittings with pressure rating at least equivalent to that of the pipe.

2.6.1.3 Joints

AWWA C115/A21.15 for flanged joints. Use bolts, nuts, and gaskets for flanged connections recommended in the Appendix to AWWA C115/A21.15. Provide ductile iron flange for setscrewed flanges in accordance with ASTM A536, Grade 70-50-05 or 60-42-10, and meeting the applicable requirements of ASME B16.1, Class 125. Use 190,000 psi tensile strength, heat treated, and zinc-coated steel setscrews for setscrewed flanges. Conform to the applicable requirements for mechanical-joint gaskets specified in AWWA C111/A21.11 for setscrewed flange gaskets. Use setscrewed gasket designed to provide for confinement and compression of

gasket when joint to adjoining flange is made.

2.6.2 Insulating Joints

Provide between pipes of dissimilar metals a rubber gasket or other approved type of insulating joint or dielectric coupling to effectively prevent metal-to-metal contact between adjacent sections of piping.

2.6.3 Accessories

Provide flanges, connecting pieces, transition glands, transition sleeves, and other adapters as required.

2.6.4 Flexible Flanged Coupling

Provide flexible flanged couplings applicable for sewage as indicated. Use flexible flanged coupling designed for a working pressure of 350 psi.

2.7 VALVES AND OTHER PIPING ACCESSORIES

2.7.1 Isolation Gate Valves in Valve Vault

Conform to AWWA C500 for gate valves with outside-screw-and-yoke rising-stem type with double disc gates and flanged ends. Conform to AWWA C509 for valves with outside-screw-and-yoke rising-stem type with flanged ends. Provide valves that open by counterclockwise rotation of the valve stem. Use valves from one manufacturer.

2.7.1.1 Valves Larger Than 2 Inches

Resilient seat gate valves conforming to AWWA C509 with non-rising stems and flanged ends.

2.7.2 Check Valves 4 inch and Larger Diameter

Provide nonclogging swing check valve rated for not less than 175 psig working pressure capable of passing 3-inch diameter solids. Match cast iron to ASTM A126 and flanged ends to AWWA C110/A21.10 Buna-N disc and integral seat.

Provide a positive horizontal, swing check type check valves. Provide valves that permit a free flow of sewage forward and a positive check against backflow. Provide iron body valves with a removable cover for inspection and removal of the gate assembly. Provide bronze gate, gate seats, shaft, studs, and nuts.

2.7.3 Identification Tags and Plates

Provide the manufacturer's name or trademark on a corrosion-resistant identification plate or cast integrally, stamped, or otherwise permanently marked in a conspicuous place on each item of equipment. Include on the pump identification plate the pump capacity in gpm, pump head in feet and speed of rotation. Cast on the body of the pump the direction of rotation.

2.7.4 Pipe Support

Use pipe support schedule 40 galvanized steel piping matching ASTM A53/A53M. Provide either ASME B16.3 or ASME B16.11 galvanized threaded fittings.

2.7.5 Miscellaneous Metals

Use stainless steel bolts, nuts, washers, anchors, and supports for installation of equipment.

2.7.6 Quick Disconnect System with Hydraulic Sealing Flange and Rail System

Use quick disconnect system consisting of a steel base plate for supporting the pumps, a hydraulic sealing flange, pump guide rails and the discharge pipe supports. Provide stainless steel guide rails, brackets and lifting chain for raising and lowering the pump in the basin. Build guides onto pump housing to fit the guide post to assure perfect alignment between pump and guide rails.

2.7.7 Wet Well Vent

Provide a flanged ductile iron pipe and bend, conforming to AWWA C115/A21.15 with insect screening.

2.8 EXCAVATION, TRENCHING, AND BACKFILLING

Provide in accordance with Section 31 00 00 EARTHWORK, except as specified herein.

PART 3 EXECUTION

3.1 INSTALLATION

Provide pump station in accordance with drawings and requirements of the respective equipment manufacturers. Dampen and isolate equipment vibration.

3.1.1 Equipment Installation

Install equipment in accordance with these specifications and the manufacturer's installation instructions. Grout equipment mounted on concrete foundations before installing piping. Install piping to avoid imposing stress on equipment. Match flanges before securing bolts.

3.1.2 Installation of Ductile-Iron Pressure Pipe and Fittings

Unless otherwise specified, install pipe and fittings in accordance with the paragraph GENERAL REQUIREMENTS FOR INSTALLATION OF PIPELINES of Section 33 30 00 SANITARY SEWERAGE, and with the requirements of AWWA C600 for pipe installation, joint assembly, and valve-and-fitting installation.

Make flanged joint with gaskets, bolts, and nuts specified for this type joint. Make flanged joints tight, avoid strain on flanges, fittings, and other accessories. Align bolt holes for each flanged joint. Use bolts sized for the bolt holes; use of undersized bolts is not permitted. Do not allow adjoining flange faces to be out of parallel to such degree that the flanged joint cannot be made watertight without overstraining the flange.

3.1.3 Valves

Make and assemble joints to gate valves and check valves as specified for making and assembling the same type joints between pipe and fittings.

Install valves in accordance with manufacturer's installation instructions. Install gate valves as described in AWWA C500, AWWA C509, and AWWA C515 and with AWWA C600 for valve-and-fitting installation and with the recommendations of the Appendix ("Installation, Operation, and Maintenance of Gate Valves") to AWWA C500.

3.2 FIELD QUALITY CONTROL

Provide appliances, materials, water, and equipment for testing, except that water and electric power needed for field tests will be provided as set forth in Division 01. Conduct testing after equipment, electrical services, and piping are installed, and the pump station is ready for operation. Correct defects discovered to the satisfaction of the Contracting Officer, and tests repeated, at no expense to the Government, until the equipment functions as intended and designed.

3.2.1 Testing Procedure

Perform a pump test, float test. Submit the test results to the Contracting Officer.

Test all panels to the power requirements as shown on the plans to assure proper component operation. Activate each control function to check for proper operation and indication.

3.2.2 Field Representative

A representative of the pump manufacturer is to direct the startup of the station and instruct representatives of the Government in startup and operation procedures.

3.3 CLOSEOUT ACTIVITIES

3.3.1 Operation and Maintenance

Submit operation and maintenance manuals including Equipment Description, Assembly and Installation Procedures, Adjustment and Alignment, Checkout Procedures, Procedures of Operation and Troubleshooting. Include preventative maintenance and inspection procedures for package lift stations. Include in procedures the frequency of preventative maintenance, inspection, adjustment, lubrication, and cleaning necessary to minimize corrective maintenance and repair.

Supply special tools that are required for maintenance and testing of the package lift stations.

Submit spare parts data, including a complete list of parts and supplies with current unit prices and source of supply. List parts and supplies that are either normally furnished at no extra cost with the purchase of equipment, or specified to be furnished as a part of the contract, and list additional items recommended by the manufacturer to ensure an efficient operation for a period of one year.

Install on or near the package lift stations, a complete package of posted instructions, consisting of labels, signs, and templates of operating instructions.

Provide a list or reference all specific operation and maintenance procedures that are required to keep the warranty valid.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 40 00

STORMWATER UTILITIES
11/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO HB-17	(2002; Errata 2003; Errata 2005, 17th Edition) Standard Specifications for Highway Bridges

ASTM INTERNATIONAL (ASTM)

ASTM A48/A48M	(2003; R 2021) Standard Specification for Gray Iron Castings
ASTM A123/A123M	(2024) Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
ASTM A536	(1984; R 2019; E 2019) Standard Specification for Ductile Iron Castings
ASTM A760/A760M	(2015, R 2020) Standard Specification for Corrugated Steel Pipe, Metallic-Coated for Sewers and Drains
ASTM A798/A798M	(2022) Standard Practice for Installing Factory-Made Corrugated Steel Pipe for Sewers and Other Applications
ASTM B26/B26M	(2018; E 2018) Standard Specification for Aluminum-Alloy Sand Castings
ASTM C76	(2022a) Standard Specification for Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe
ASTM C76M	(2022a) Standard Specification for Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe (Metric)
ASTM C270	(2025b) Standard Specification for Mortar for Unit Masonry
ASTM C425	(2021) Standard Specification for Compression Joints for Vitrified Clay Pipe and Fittings

ASTM C443	(2021) Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets
ASTM C443M	(2021) Standard Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets (Metric)
ASTM C478/C478M	(2022) Standard Specification for Circular Precast Reinforced Concrete Manhole Sections
ASTM C923/C923M	(2020) Standard Specification for Resilient Connectors Between Reinforced Concrete Manhole Structures, Pipes and Laterals
ASTM C990	(2009; R 2019) Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants
ASTM C990M	(2009; R 2019) Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants (Metric)
ASTM D1056	(2020) Standard Specification for Flexible Cellular Materials - Sponge or Expanded Rubber
ASTM D1171	(2018) Standard Test Method for Rubber Deterioration - Surface Ozone Cracking Outdoors (Triangular Specimens)
ASTM D2321	(2020) Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications
ASTM D2564	(2020) Standard Specification for Solvent Cements for Poly(Vinyl Chloride) (PVC) Plastic Piping Systems
ASTM D3034	(2016) Standard Specification for Type PSM Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings
ASTM D3212	(2020) Standard Specification for Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals
ASTM F477	(2014; R 2021) Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe
ASTM F679	(2016) Standard Specification for Poly(Vinyl Chloride) (PVC) Large-Diameter Plastic Gravity Sewer Pipe and Fittings

ASTM F794	(2021) Standard Specification for Poly(Vinyl Chloride) (PVC) Profile Gravity Sewer Pipe and Fittings Based on Controlled Inside Diameter
ASTM F949	(2020) Standard Specification for Poly(Vinyl Chloride) (PVC) Corrugated Sewer Pipe with a Smooth Interior and Fittings

1.2 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval.

SD-06 Test Reports

Leakage Test; G

SD-07 Certificates

Hydrostatic Test on Watertight Joints; G

Frame and Cover or Gratings; G

SD-08 Manufacturer's Instructions

Placing Pipe and Box Culvert; G

SD-11 Closeout Submittals

Post-Installation Inspection Report; G

LID Verification Report; G

1.3 DELIVERY, STORAGE, AND HANDLING

1.3.1 Delivery and Storage

Inspect materials delivered to site for damage and unload and store materials with minimumal handling. Do not store materials directly on the ground. Keep the inside of pipes and fittings free of dirt and debris. Before, during, and after installation, protect plastic pipe and fittings from any environment that would result in damage or deterioration to the material. Keep a copy of the manufacturer's instructions available at the construction site at all times and follow these instructions unless directed otherwise by the Contracting Officer. Store solvents, solvent compounds, lubricants, elastomeric gaskets, and any similar materials required to install plastic pipe in accordance with the manufacturer's recommendations and discard if the storage period exceeds the recommended shelf life. Discard solvents in use when the recommended pot life is exceeded.

1.3.2 Handling

Handle materials in a manner that ensures delivery to the trench in sound, undamaged condition. Carry pipe to the trench.

PART 2 PRODUCTS

2.1 PIPE FOR CULVERTS AND STORM DRAINS

Pipe sizes for culverts and storm drains are indicated on the drawings.

2.1.1 Concrete Pipe

2.1.1.1 Reinforced Culvert and Storm Drain Pipe

Manufactured in accordance with and conforming to ASTM C76M ASTM C76, Class IV.

2.1.2 Poly Vinyl Chloride (PVC) Pipe

2.1.2.1 Type PSM PVC Pipe

ASTM D3034, maximum SDR 35.

2.1.2.2 Profile PVC Pipe

ASTM F794, Series 46.

2.1.2.3 Smooth Wall PVC Pipe

ASTM F679.

2.1.2.4 Corrugated PVC Pipe

ASTM F949.

2.2 PIPE JOINTS

2.2.1 Concrete Pipe

2.2.1.1 Rubber Gasket Joints

Provide rubber gasket joints of a design and physical requirements conforming to ASTM C443.

2.2.1.2 Preformed Flexible Sealant Joints

Provide joints made with preformed flexible joint sealant conforming to ASTM C990.

2.2.2 Corrugated Aluminized Steel Type 2 and Aluminum Pipe

Factory reform each end of pipe with helical corrugations to create annular corrugations of the same dimensions as those in the pipe. Provide reformed ends with a width equal to at least half the width of the band being used. Join pipe using annular corrugated coupling bands. Except as otherwise specified or indicated, provide annular corrugated coupling bands including connectors and hardware conforming to ASTM A760/A760M. Provide coupling bands with either rod and lug or angle-bolt type connectors.

2.2.2.1 Annular Corrugated Bands

Provide sleeve type gaskets made of approximately 3/8 inch thick by 7 inch

minimum width closed cell, expanded synthetic rubber, fabricated in the form of a cylinder with a diameter approximately 10 percent less than the nominal pipe size with annular corrugated type bands. Provide sleeve type gaskets that meet the requirements of ASTM D1056 and have a quality retention rating of not less than 70 percent when tested for weather resistance by ozone chamber exposure, Method B of ASTM D1171

2.2.3 PVC Plastic Pipe

Provide solvent cement or elastomeric gasket type joints in accordance with the specification for the pipe and as recommended by the pipe manufacturer. Use solvent cement conforming to ASTM D2564. Provide gaskets for elastomeric joints conforming to ASTM F477.

2.3 MISCELLANEOUS MATERIALS

2.3.1 Mortar

Mortar is not allowed for pipe joints. Provide mortar for pipe connections to drainage structures conforming to ASTM C270, Type M, except that the maximum placement time will be 1 hour. Provide a sufficient quantity of water in the mixture to produce a stiff workable mortar but in no case may the quantity exceed 5 gallons of water per sack of cement. Use water that is clean and free of harmful acids, alkalis, and organic impurities. Use the mortar within 30 minutes after the ingredients are mixed with water.

2.3.2 Precast Reinforced Concrete Manholes

Provide precast reinforced concrete manholes conforming to ASTM C478/C478M. Provide joints between precast concrete risers and tops that are full-bedded in cement mortar and smoothed to a uniform surface on both interior and exterior of the structure.

2.3.3 Frame and Cover or Gratings

Provide frame and cover or gratings made of cast gray iron, ASTM A48/A48M, Class 35B; cast ductile iron, ASTM A536, Grade 65-45-12; or cast aluminum, ASTM B26/B26M, Alloy 356.0-T6. Stamp or cast the word "Storm Sewer" into covers so that it is plainly visible.

2.3.4 Steel Ladder

Provide a steel ladder where the depth of the storm drainage structure exceeds 12 feet. Provide ladders not less than 16 inches in width, with 3/4 inch diameter rungs spaced 12 inches apart. Provide two stringers that are a minimum 3/8 inch thick and 2-1/2 inches wide. Galvanize ladders and inserts after fabrication in conformance with ASTM A123/A123M.

2.3.5 Resilient Connectors

Provide flexible, watertight connectors conforming to ASTM C923/C923M for connecting pipe to manholes and inlets.

2.3.6 Flared End Sections

2.3.6.1 Concrete Flared End Sections

Provide sections of a standard design fabricated with reinforced concrete.

2.4 TESTS, INSPECTIONS, AND VERIFICATIONS

2.4.1 Hydrostatic Test on Watertight Joints

Perform a hydrostatic test on the watertight joint types as proposed. This test will be conducted at the plant or by an independent laboratory. Only one sample joint of each type needs testing; however, if the sample joint fails because of faulty design or workmanship, an additional sample joint may be tested.

2.4.1.1 Concrete, PVC, PE and PP Pipe

Provide joints in reinforced and nonreinforced concrete pipe meeting the performance requirements in ASTM C990M ASTM C990 or ASTM C443M ASTM C443. Provide joints in clay pipe meeting the test requirements in ASTM C425. Provide joints in PVC, PE, SRPE, and PP plastic pipe meeting the test requirements in ASTM D3212.

2.4.1.2 Corrugated Steel and Aluminum Pipe

Perform a hydrostatic pressure test on the proposed joining system in accordance with ASTM A760/A760M. The joining system must not leak when subjected to an internal hydrostatic pressure of 10 psi for a 10 minute period

PART 3 EXECUTION

3.1 EXCAVATION FOR PIPE CULVERTS, BOX CULVERTS, STORM DRAINS, AND DRAINAGE STRUCTURES

Excavate trenches, excavate for appurtenances and backfill for culverts and storm drains, in accordance with the applicable portions of Section 31 00 00 EARTHWORK and the requirements specified below.

3.1.1 Trenching

Excavate trenches to the width indicated on the drawings or as specified herein. Trench width should permit satisfactory jointing and thorough tamping of the bedding material under and around the pipe. Place sheeting and bracing, where required, within the trench width as specified, without any overexcavation.

3.1.2 Removal of Rock

Replace rock in either ledge or boulder formation with suitable materials to provide a compacted earth cushion. Provide a compacted earth cushion between unremoved rock and the pipe with a thickness of at least 8 inches or 1/2 inch for each foot of fill over the top of the pipe, whichever is greater, but not more than three-fourths the nominal diameter of the pipe. Maintain the cushion under the bell as well as under the straight portion of the pipe where bell-and-spigot pipe is used. Provide a compacted earth cushion between unremoved rock and the box culvert of at least 8 inches in thickness for concrete box culverts. Excavate rock as specified and defined in Section 31 00 00 EARTHWORK.

3.1.3 Removal of Unstable Material

Where wet or otherwise unstable soil incapable of properly supporting the

pipe or box culvert, as determined by the Contracting Officer, is unexpectedly encountered in the bottom of a trench, remove such material to the depth required and replace with select granular material to the proper grade. Compact select granular material as specified in paragraph FINAL BACKFILL. When removal of unstable material is due to the fault or neglect of the Contractor while performing shoring and sheeting, water removal, or other specified requirements, perform such removal and replacement at no additional cost to the Government.

3.2 BEDDING AND INITIAL BACKFILL

Provide a firm bedding foundation of uniform density throughout the entire length of the pipe or box culvert.

3.2.1 Concrete Pipe

Use select granular material conforming to Section 31 00 00 EARTHWORK for haunch and bedding material. Compact haunch and outer bedding to at least 90 percent laboratory maximum density and place in layers not exceeding 6 inch loose thickness for compaction by hand-operated compactors and 200 mm 8 inches for other than hand-operated machines. Loosely place middle bedding and do not compact. After the pipe has been properly bedded, place haunch material, at a moisture content that will facilitate compaction, evenly along both sides of the pipe and thoroughly compact each layer with mechanical tampers or rammers to the springline of the pipe. Thoroughly compact the haunch material under the haunches of the pipe. For bell and spigot pipe, form a depression in bedding material for bells so entire barrel of pipe is uniformly supported. Minimize the length, depth, and width of bell depressions to that required for properly making the particular type of joint.

3.2.1.1 Trenches

After the pipe has been properly bedded and haunch material placed to the midpoint (springline) of the pipe, backfill and compact the remainder of the trench by spreading and rolling or compacting by mechanical rammers or tampers in layers not exceeding 6 inches. Test for density as necessary to ensure conformance to the compaction requirements specified below. Leave untreated sheeting in place beneath structures or pavements.

3.2.1.2 Fill Sections

For pipe placed in fill sections, uniformly spread fill material longitudinally on both sides of the pipe in layers not exceeding 6 inches in compacted depth, and compact by rolling parallel with pipe or by mechanical tamping or ramming. Prior to commencing normal filling operations, the crown width of the fill at a height of 12 inches above the top of the pipe must extend a distance of not less than twice the outside pipe diameter on each side of the pipe or 12 feet, whichever is less. After the backfill has reached at least 12 inches above the top of the pipe, place and thoroughly compact the remainder of the fill in layers not exceeding 8 inches.

3.2.2 Plastic Pipe

Provide bedding for PVC, PE, SRPE and PP pipe meeting the requirements of ASTM D2321. Use Class IB or II material for PVC, PE, SRPE pipe bedding, haunching, and initial backfill. Use Class I, II, or III material for PP pipe bedding, haunching and initial backfill.

3.3 PLACING PIPE AND BOX CULVERT

Submit printed copies of the pipe or box culvert manufacturer's recommended pipe or box culvert installation procedures prior to installation. Thoroughly examine each section of pipe or box culvert before being laid; do not use defective or damaged pipe. Protect plastic pipe, excluding SRPE pipe, from exposure to direct sunlight prior to laying, if necessary to maintain adequate pipe stiffness and meet installation deflection requirements. Lay pipelines to the grades and alignment indicated. Provide proper facilities for lowering sections of pipe into trenches. Do not lay pipe in water or when trench conditions or weather are unsuitable for such work. Divert drainage or dewater trenches during construction as necessary. Deflection of installed flexible pipe must not exceed the following limits:

TYPE OF PIPE	MAXIMUM ALLOWABLE DEFLECTION (percent)

3.3.1 Concrete, PVC, Ribbed PVC, Ductile Iron Pipe

Lay pipe proceeding upgrade with spigot ends of bell-and-spigot pipe and tongue ends of tongue-and-groove pipe pointing in the direction of the flow.

3.4 JOINTING

3.4.1 Concrete Pipe

3.4.1.1 Plastic Sealing Compound Joints for Tongue-and-Grooved Pipe and Box Culverts

Follow the recommendation of the particular manufacturer in regard to sealing compound special installation requirements. When lubricants, primers, or adhesives are used, only apply on surfaces that are dry and clean. Affix sealing compounds to the pipe or box culvert not more than 3 hours prior to installation of the pipe or box culvert. Protect sealing compounds from the sun, blowing dust, and other deleterious agents at all times. Inspect sealing compounds before installation of the pipe or box culvert, and remove and replace any loose or improperly affixed sealing compound. Align the pipe or box culvert with the previously installed pipe or box culvert, and pull the joint together.

3.4.1.2 Flexible Watertight Joints

Use lubricants, cements, adhesives, and other special installation requirements for gaskets and jointing materials as recommended by the manufacturer. When lubricants, cements, or adhesives are used, only apply on surfaces that are clean and dry. Affix gaskets and jointing materials to the pipe not more than 24 hours prior to the installation of the pipe,

and protect from the sun, blowing dust, and other deleterious agents at all times. Inspect gaskets and jointing materials before installing the pipe; remove and replace any loose or improperly affixed gaskets and jointing materials. Align the pipe with the previously installed pipe, and push the joint home. If the gasket becomes visibly dislocated when joining sections of pipe, remove the pipe and remake the joint.

3.4.2 Corrugated Aluminized Steel Type 2 and Aluminum Pipe

3.4.2.1 Field Joints

Provide transverse field joints designed so that the successive connection of pipe sections will form a continuous line free of appreciable irregularities in the flow line. Provide joints meeting the general performance requirements described in ASTM A798/A798M. Suitable transverse field joints which satisfy the requirements for one or more of the joint performance categories can be obtained with the following types of connecting bands furnished with suitable band-end fastening devices: corrugated bands, bands with projections, flat bands, and bands of special design that engage factory reformed ends of corrugated pipe. Keep the space between the pipe and connecting bands free from dirt and grit so that corrugations fit snugly. While being tightened, tap the connecting band with a soft-head mallet of wood, rubber or plastic, to take up slack and ensure a tight joint. Provide field joints for each type of corrugated metal pipe that maintain pipe alignment during construction and prevent infiltration of fill material during the life of the installations.

3.4.2.2 Flexible Watertight, Gasketed Joints

Use lubricants or cements and other special installation requirements as recommended by the gasket manufacturer. Where sleeve type gaskets are used, place the gasket over one end of a section of pipe for half the width of the gasket. Then double over the other half over the end of the same pipe. When the adjoining section of pipe is in place, roll the doubled-over half of the gasket over the adjoining section. Correct any unevenness in overlap so that the gasket covers the end of pipe sections equally. Center connecting bands over adjoining sections of pipe, and place rods or bolts in position and tighten nuts. Band Tightening: Tighten the band evenly, keep even tension on the rods or bolts, and the gasket; properly seat the gasket in the corrugations. Keep watertight joints uncovered for a period of time designated by the Contracting Officer. Before covering joints, measure the tightness of the nuts with a torque wrench. If the nut has tended to loosen its grip on the bolts or rods, retighten the nut with a torque wrench and keep uncovered until a tight, permanent joint is assured.

3.5 DRAINAGE STRUCTURES

3.5.1 Manholes and Inlets

Construct manholes of precast reinforced concrete. Construct inlets of precast reinforced concrete. Provide manholes and inlets complete with frames and covers or gratings; and with fixed galvanized steel ladders as indicated. The wall along the line where steel ladders are installed must be vertical for its entire length. Adequately anchor ladders to the wall by means of steel inserts spaced not more than 6 feet vertically, and install to provide at least 6 inches of space between the wall and the rungs. Make pipe connections to concrete manholes and inlets with

flexible, watertight connectors.

3.5.2 Walls and Headwalls

Construct headwalls as indicated.

3.6 INSTALLATION OF TRACER WIRE AND WARNING TAPE

Install warning tape above all storm drain pipe in accordance with Section 31 00 00 EARTHWORK.

3.7 FINAL BACKFILL

Backfill trenches with satisfactory material deposited in layers of a maximum of 8 inches loose thickness and compacted to 90 percent of maximum density for cohesive soils and 95 percent of maximum density for cohesionless soils in accordance with Section 31 00 00 EARTHWORK. Testing is the responsibility of the Contractor and will be performed at no additional cost to the Government. Unless otherwise specified, determine field in-place density of final backfill at a frequency of one test per 50 linear feet, or fraction thereof, of each lift of backfill. Submit test results in accordance with Section 31 00 00 EARTHWORK. Do not displace or damage pipe or box when compacting final backfill by rolling or operating heavy equipment parallel with the pipe or box. Movement of construction machinery over a culvert or storm drain at any stage of construction will be at the Contractor's risk. Repair or replace any damaged pipe. Protect concrete pipes with a minimum of 3 feet of cover prior to permitting heavy construction equipment to pass over them during construction. Provide the minimum cover for construction loads over corrugated steel pipes as specified in Section 26, Division II of AASHTO HB-17. Provide minimum cover for construction loads over plastic pipes as specified in ASTM D2321.

3.8 FIELD QUALITY CONTROL

3.8.1 Tests

Testing is the responsibility of the Contractor. Perform all testing and retesting at no additional cost to the Government.

3.8.1.1 Tracer Wire Continuity

Test tracer wire for continuity after initial and final backfilling of pipes. Verify that tracer wire is locatable with electronic utility location equipement. Repair breaks or separations and re-test for continuity.

3.8.2 Inspection

3.8.2.1 Low Impact Development Inspection

Inspect Low Impact Development (LID) features indicated on the design portion of the LID Verification Report. Certify LID features were constructed according to plans and specifications or by submitting as-built drawings. When as-built drawings show deviations to the LID features, document the deviations on the LID Verification Report.

3.8.3 Repair of Defects

3.8.3.1 Leakage Test

When leakage exceeds the maximum amount specified, correct source of excess leakage by replacing damaged pipe and gaskets and retest.

3.8.3.2 Deflection Testing

When deflection readings are in excess of the allowable deflection of average inside diamater of pipe are obtained, remove pipe which has excessive deflection and replace with new pipe. Retest 30 days after completing backfill, leakage testing and compaction testing.

3.8.3.3 Inspection

Replace pipe or repair defects indicated in the Post-Installation Inspection Report.

3.8.3.3.1 Concrete Pipe

Replace pipes having cracks with a width greater than 0.1 inches.

3.8.3.3.2 Flexible Pipe

Replace pipes having cracks or splits.

3.9 PROTECTION

Protect storm drainage piping and adjacent areas from superimposed and external loads during construction.

3.10 WARRANTY PERIOD

Pipe segments found to have defects during the warranty period must be replaced with new pipe and retested.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 61 14

EXTERIOR BURIED PREINSULATED WATER PIPING
02/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF MECHANICAL ENGINEERS (ASME)

ASME B16.18	(2021) Cast Copper Alloy Solder Joint Pressure Fittings
ASME B16.22	(2021) Wrought Copper and Copper Alloy Solder Joint Pressure Fittings
ASME B16.24	(2022) Cast Copper Alloy Pipe Flanges, Flanged Fittings, and Valves Classes 150, 300, 600, 900, 1500, and 2500
ASME B31.1	(2024) Power Piping

ASTM INTERNATIONAL (ASTM)

ASTM A193/A193M	(2025) Standard Specification for Alloy-Steel and Stainless Steel Bolting Materials for High-Temperature Service and Other Special Purpose Applications
ASTM A194/A194M	(2024) Standard Specification for Carbon Steel, Alloy Steel, and Stainless Steel Nuts for Bolts for High-Pressure or High-Temperature Service, or Both
ASTM B32	(2020) Standard Specification for Solder Metal
ASTM B88	(2022) Standard Specification for Seamless Copper Water Tube
ASTM D229	(2019) Standard Test Methods for Rigid Sheet and Plate Materials Used for Electrical Insulation
ASTM D1330	(2004; R 2010) Rubber Sheet Gaskets
ASTM D1784	(2020) Standard Specification for Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D2996	(2017) Standard Specification for Filament-Wound "Fiberglass"

(Glass-Fiber-Reinforced
Thermosetting-Resin) Pipe

1.2 SYSTEM DESCRIPTION

Provide new exterior buried factory-prefabricated preinsulated water piping system to the first piping connection aboveground or within each building complete and ready for operation. Piping system includes hot domestic water piping, recirculating hot domestic water piping, chilled water piping, and related work . Hot domestic water piping within each building is specified under Section 22 00 00 PLUMBING, GENERAL PURPOSE. Chilled water piping within each building is specified under Section 23 64 26 CHILLED WATER PIPING SYSTEMS.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Factory-prefabricated preinsulated water piping system

Preinsulated plastic pipe field joints

Show layout of piping system. Drawings must have Professional Engineer Seal.

SD-03 Product Data

Pipe, fittings, and end connections

Factory-prefabricated preinsulated water piping system

SD-07 Certificates

Certification of welders' qualifications

SD-08 Manufacturer's Instructions

Installation manual for buried factory-prefabricated preinsulated water piping system

1.4 QUALITY ASSURANCE

1.4.1 Certification of Welders' Qualifications

Submit prior to site welding of steel piping; certifications shall be not more than one year old.

PART 2 PRODUCTS

2.1 BURIED FACTORY-PREFABRICATED PREINSULATED WATER PIPING SYSTEM

Piping (pipe, fittings, and end connections) system shall be suitable for

working pressure of 125 psig at 250 degrees F, except plastic polyvinyl chloride (PVC) chilled water piping shall be suitable for working pressure of 125 psig at 75 degrees F. Piping system shall withstand H-20 highway loading with 2 feet of compacted backfill over top of conduit. Mark each section of conduit with fabricator's name, product identification, and publications to which the items conform. Provide each section of carrier pipe including factory-applied insulation and conduit, with waterproof conduit ends at both ends of each section of carrier pipe, except for piping systems which have the field joints insulated and covered with waterproof shrink sleeves.

2.1.1 Factory-Applied Insulation

Polyurethane or polyisocyanate insulation, minimum density of 1.7 pcf, rated for not less than 250 degrees F, completely filling space between carrier pipe and conduit.

2.1.2 Factory-Applied Conduit

Conduit material, size, and thickness shall be as follows:

Carrier Pipe (Inches)	Minimum Conduit Size (Inches)	Minimum Conduit Thickness (Inches)
2	4	0.060
3	6	0.060
4	8	0.080
6	10	0.100
8	12	0.120
10	14	0.120

a. Plastic PVC pipe conduit: ASTM D1784, Class 12454-B compound extruded seamless PVC plastic pipe.

b. Plastic RTR pipe conduit: ASTM D2996, filament-wound, fiberglass RTR plastic pipe, without liner.

c. Plastic RTR factory lay-up conduit: Conduit shall be machine-applied continuous rovings of fiberglass strands saturated with isophthalic polyester or epoxy resin filament wound in helical pattern directly to the outer surface of the pipe insulation. In lieu of minimum conduit size for each size of carrier pipe, provide minimum of one inch thick insulation for 2 inch carrier pipe and provide minimum of 1.5 inch thick insulation for 3 inch and larger carrier pipe.

2.1.3 Factory-Applied End Seals

Provide watertight end seal, or factory lay-up type end seal between carrier pipe and conduit. Provide sufficient surface bonding area between carrier pipe and conduit to ensure permanent watertight end seal suitable for use with temperature limits of carrier pipe.

2.1.4 Factory-Prefabricated Carrier Piping

Pipe, fittings, flanges, and couplings shall be marked with manufacturer's name, product identification, and publication to which items conform. Carrier piping shall be as specified in this section.

2.2 CARRIER PIPING

2.2.1 Copper Tubing

Provide copper tubing for hot domestic water piping, recirculating hot domestic water piping, chilled water piping, chilled-hot water piping, and hot water piping.

a. Copper tubing: Provide ASTM B88, Type K copper tubing for buried factory-prefabricated preinsulated piping and for aboveground piping. Provide ASME B16.18 or ASME B16.22 solder joint fittings, unions, and flanges; provide adapters as required.

b. Solder for copper tubing: Provide ASTM B32, 95-5 tin-antimony solder or provide Plumbing Code approved lead-free solder.

c. Flanged connections: Provide ASME B16.24, Class 150, solder joint flat face flanged connections.

2.3 FLANGED CONNECTIONS

Provide ASME Class 150 flat face flanged connections.

a. Gaskets: ASTM D1330, except Shore A durometer hardness shall be 55 to 65, 0.125 inch thick ethylene propylene. Provide one piece factory cut full-face gaskets.

b. Bolts: ASTM A193/A193M, Grade B7. Extend minimum of two full threads beyond nut with bolts tightened to required torque.

c. Nuts: ASTM A194/A194M, Grade 7, with Teflon coated threads.

d. Washers: Provide galvanized steel flat circular washers under bolt heads and nuts.

e. Electrically isolating (insulating) gaskets for connections between metal flanges: Provide ASTM D229 electrical insulating material of 1000 ohms minimum resistance. Provide one piece factory cut insulating gaskets between flanges. Provide silicon-coated fiberglass insulating sleeves between bolts and holes in flanges; bolts may have reduced shanks of diameter not less than diameter at root of threads. Provide 0.125 inch thick high-strength insulating washers next to flanges and provide stainless steel flat circular steel washers over insulating washers and under bolt heads and nuts. Provide bolts 0.5 inch longer than standard length to compensate for thicker insulating gaskets and washers under bolt heads and nuts.

2.4 BURIED WARNING AND IDENTIFICATION TAPE

Provide detectable aluminum foil plastic backed tape or detectable magnetic plastic tape manufactured specifically for warning and identification of buried piping. Tape shall be detectable by an electronic detection instrument. Provide tape in rolls, 3 inches minimum

width, color coded for the utility involved with warning and identification imprinted in bold black letters continuously and repeatedly over entire tape length. Warning and identification shall read "CAUTION BURIED PREINSULATED WATER PIPING BELOW" or similar wording. Use permanent code and letter coloring unaffected by moisture and other substances contained in trench backfill material.

2.5 CONCRETE THRUST BLOCKS

Provide concrete thrust blocks as specified in Section 03 30 00 CAST-IN-PLACE CONCRETE. Concrete shall be of 4000 psi minimum 28 day compressive strength, air-entrained admixture (3.6 ounces per cubic yard) with water-reducing admixture (22 ounces per cubic yard).

2.6 PIPE SLEEVES

Provide where piping passes entirely through walls and floors. Provide sleeves of sufficient length to pass through entire thickness of walls and floors. Provide one inch minimum clearance between exterior of piping or pipe insulation, and interior of sleeve or core-drilled hole. Firmly pack space with mineral wool insulation. Seal space at both ends of sleeve or core-drilled hole with plastic waterproof cement which will dry to a firm but pliable mass, or provide mechanically adjustable segmented elastomeric seal. In fire walls and fire floors, seal both ends of sleeves or core-drilled holes with UL listed fill, void, or cavity material.

a. Sleeves in masonry and concrete walls and floors: Provide hot-dip galvanized steel, ductile-iron, or cast-iron sleeves. Core drilling of masonry and concrete may be provided in lieu of sleeves when cavities in the core-drilled hole are grouted smooth.

b. Sleeves in other than masonry and Concrete walls and floors: Provide 26 gage galvanized steel sheet.

2.7 ESCUTCHEON PLATES

Provide split hinge type metal plates for piping entering walls and floors in exposed spaces. Provide polished stainless steel plates or chromium-plated finish on copper alloy plates in finished spaces. Provide paint finish on metal plates in unfinished spaces.

PART 3 EXECUTION

3.1 INSTALLATION

Installation of exterior buried factory-prefabricated preinsulated water piping systems shall be in accordance with manufacturer's installation manual. Welding of steel piping including qualification of welders shall be in accordance with ASME B31.1, metallic arc process. Deviations shall not be permitted unless authorized in writing by Contracting Officer. Install piping straight and true to bear evenly on sand bedding material. Installation and field assembly of plastic RTR piping shall be in accordance with the Federal Agency Approved Brochure.

a. Cleaning of piping: Keep interior and ends of new piping and existing piping affected by the Contractor's operations, cleaned of water and foreign matter during installation by means of plugs or other approved methods. When work is not in progress, securely close open ends of pipe and fittings to prevent entry of water and foreign matter.

Inspect piping before placing into position.

b. Demolition: Remove materials so as not to damage materials which are to remain. Replace existing work damaged by the Contractor's operations with new work of the same construction.

3.2 FIELD JOINTS

a. Carrier piping joints without concrete anchor: Pressure test and approve piping joints. Provide joints with polyurethane or polyisocyanate insulation of same type and thickness as insulation on carrier piping. Provide waterproof shrink sleeves to cover insulation and overlap not less than 6 inches of each end of conduit section.

b. Carrier piping joints with concrete anchor: Pressure test and approve piping joints. Provide each elbow and tee with concrete anchors (thrust blocks). Provide waterproof end seals between carrier piping and conduit adjacent to each carrier pipe fitting. Encase carrier pipe fitting and at least 2 inches of each end of conduit with a minimum of 6 inches of concrete.

3.3 BURIED FACTORY-PREFABRICATED PREINSULATED PIPE INSTALLATION

a. Assembly and alignment: Assemble carrier pipe and fittings according to manufacturer's installation manual. Maintain proper alignment during assembly of joints.

b. Bedding: Accurately grade trench bedding with a minimum of 6 inches of manufactured or natural sand. Backfill sand to a minimum of 6 inches above and below conduit. Lay bedding to firmly support conduit along entire length.

c. Concrete thrust blocks: Encase each elbow and tee of carrier pipe in thrust block with minimum of 3 square feet of thrust-bearing surface cast against undisturbed soil, minimum pipe-to-bearing surface single dimension of 10 inches perpendicular to bearing surface, and minimum volume of 9 cubic feet, except as indicated otherwise. Disturbed soil under and around thrust blocks shall be compacted.

3.4 FIELD QUALITY CONTROL

Before final acceptance of work, test each system to demonstrate compliance with contract requirements. Thoroughly flush and clean piping before placing in operation. Flush piping at minimum velocity of 8 fps. Correct defects in the work and repeat tests until work is in compliance with contract requirements. Furnish potable water, electricity, instruments, connecting devices, and personnel for tests.

a. Field tests of carrier piping: Do not cover carrier piping joints with insulation or concrete anchors (thrust blocks), until carrier piping joints pass field tests.

b. Hydrostatic pressure test: Test piping system at 200 psig for minimum holding period of 2 hours during which time pressure shall not drop more than 4 psi; test plastic RTR piping in accordance with Federal Agency Approved Brochure. Pressure drop greater than 4 psicorrected for temperature variation constitutes failure. Valve off piping system and disconnect method of piping system pressurization before starting the 2 hour pressure holding period. During hydrostatic

pressure test, examine piping system for leaks. Repair leaking joints, replace damaged and porous pipe and fittings with new materials, and repeat tests.

c. Thrust blocks: If O-ring connections are used, provide temporary thrust blocks prior to hydrostatic pressure testing of piping system. Place bedding and backfill around center portion of piping system, leaving thrust blocks and field joints clear for observation. After successful completion of hydrostatic pressure test, cast concrete thrust blocks.

d. Field inspections: Prior to initial operation, inspect piping system for compliance with drawings, specifications, and manufacturer's submittals.

3.5 DISINFECTION

Disinfect new hot domestic water piping under Section 22 00 00 PLUMBING, GENERAL PURPOSE.

-- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 71 02

UNDERGROUND ELECTRICAL DISTRIBUTION
08/21

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO)

AASHTO HB-17	(2002; Errata 2003; Errata 2005, 17th Edition) Standard Specifications for Highway Bridges

AMERICAN CONCRETE INSTITUTE (ACI)

ACI 318M	(2014; ERTA 2015) Building Code Requirements for Structural Concrete & Commentary
ACI SP-66	(2004) ACI Detailing Manual

ASSOCIATION OF EDISON ILLUMINATING COMPANIES (AEIC)

AEIC CS8	(2013) Specification for Extruded Dielectric Shielded Power Cables Rated 5 Through 46 kV

ASTM INTERNATIONAL (ASTM)

ASTM B1	(2013) Standard Specification for Hard-Drawn Copper Wire
ASTM B3	(2013) Standard Specification for Soft or Annealed Copper Wire
ASTM B8	(2011; R 2017) Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM B496	(2016; R 2021) Standard Specification for Compact Round Concentric-Lay-Stranded Copper Conductors
ASTM C309	(2019) Standard Specification for Liquid Membrane-Forming Compounds for Curing Concrete
ASTM C478	(2018) Standard Specification for Circular Precast Reinforced Concrete Manhole Sections

ASTM C857	(2016) Standard Practice for Minimum Structural Design Loading for Underground Precast Concrete Utility Structures
ASTM C990	(2009; R 2019) Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants
ASTM F512	(2019) Standard Specification for Smooth-Wall Poly (Vinyl Chloride) (PVC) Conduit and Fittings for Underground Installation
ASTM F2160	(2016) Standard Specification for Solid Wall High Density Polyethylene (HDPE) Conduit Based on Controlled Outside Diameter (OD)

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 48	(2020) Test Procedures and Requirements for Alternating-Current Cable Terminations Used on Shielded Cables Having Laminated Insulation Rated 2.5 kV through 765 kV or Extruded Insulation Rated 2.5 kV through 500 kV
IEEE 81	(2012) Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System
IEEE 386	(2016) Separable Insulated Connector Systems for Power Distribution Systems Rated 2.5 kV through 35 kV
IEEE 400.2	(2013) Guide for Field Testing of Shielded Power Cable Systems Using Very Low Frequency (VLF)
IEEE 404	(2012) Standard for Extruded and Laminated Dielectric Shielded Cable Joints Rated 2500 V to 500,000 V
IEEE 495	(2007) Guide for Testing Faulted Circuit Indicators
IEEE C2	(2023) National Electrical Safety Code
IEEE C37.20.3	(2013) Standard for Metal-Enclosed Interrupter Switchgear
IEEE Stds Dictionary	(2009) IEEE Standards Dictionary: Glossary of Terms & Definitions

INTERNATIONAL ELECTRICAL TESTING ASSOCIATION (NETA)

NETA ATS	(2021) Standard for Acceptance Testing

Specifications for Electrical Power Equipment and Systems

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI/NEMA WC 71/ICEA S-96-659 (2014) Standard for Nonshielded Cables Rated 2001-5000 Volts for use in the Distribution of Electric Energy

NEMA RN 1 (2005; R 2013) Polyvinyl-Chloride (PVC) Externally Coated Galvanized Rigid Steel Conduit and Intermediate Metal Conduit

NEMA TC 2 (2020) Standard for Electrical Polyvinyl Chloride (PVC) Conduit

NEMA TC 6 & 8 (2020) Standard for Polyvinyl Chloride (PVC) Plastic Utilities Duct for Underground Installations

NEMA TC 7 (2021) Smooth-Wall Coilable and Straight Electrical Polyethylene Conduit

NEMA TC 9 (2020) Standard for Fittings for Polyvinyl Chloride (PVC) Plastic Utilities Duct for Underground Installation

NEMA WC 74/ICEA S-93-639 (2012) 5-46 kV Shielded Power Cable for Use in the Transmission and Distribution of Electric Energy

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70 (2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA)

TIA-758 (2012b) Customer-Owned Outside Plant Telecommunications Infrastructure Standard

U.S. DEPARTMENT OF AGRICULTURE (USDA)

RUS Bull 1751F-644 (2002) Underground Plant Construction

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-60005 (Basic; Notice 2) Frames, Covers, Gratings, Steps, Sump And Catch Basin, Manhole

UL SOLUTIONS (UL)

UL 6 (2022) UL Standard for Safety Electrical Rigid Metal Conduit-Steel

UL 83 (2017; Reprint Mar 2020) UL Standard for

	Safety Thermoplastic-Insulated Wires and Cables
UL 94	(2023; Reprint Jan 2024) UL Standard for Safety Tests for Flammability of Plastic Materials for Parts in Devices and Appliances
UL 467	(2022) UL Standard for Safety Grounding and Bonding Equipment
UL 486A-486B	(2018; Reprint May 2021) UL Standard for Safety Wire Connectors
UL 510	(2020; Dec 2022) UL Standard for Safety Polyvinyl Chloride, Polyethylene and Rubber Insulating Tape
UL 514A	(2013; Reprint Aug 2017) UL Standard for Safety Metallic Outlet Boxes
UL 514B	(2012; Reprint May 2020) Conduit, Tubing and Cable Fittings
UL 651	(2011; Reprint Mar 2020) UL Standard for Safety Schedule 40, 80, Type EB and A Rigid PVC Conduit and Fittings
UL 854	(2020) Standard for Service-Entrance Cables
UL 1072	(2006; Reprint Apr 2020) Medium-Voltage Power Cables
UL 1242	(2006; Reprint Aug 2020) Standard for Electrical Intermediate Metal Conduit -- Steel

1.2 RELATED REQUIREMENTS

Section 26 08 00 APPARATUS INSPECTION AND TESTING applies to this section, with the additions and modifications specified herein.

1.3 DEFINITIONS

a. Unless otherwise specified or indicated, electrical and electronics terms used in these specifications, and on the drawings, are as defined in IEEE Stds Dictionary.

b. In the text of this section, the words conduit and duct are used interchangeably and have the same meaning.

c. In the text of this section, "medium voltage cable splices," and "medium voltage cable joints" are used interchangeably and have the same meaning.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for

Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Precast Underground Structures; G

SD-03 Product Data

Medium Voltage Cable; G

Medium Voltage Cable Joints; G

Medium Voltage Cable Terminations; G

Precast Concrete Structures; G

Sealing Material

Pulling-In Irons

Manhole Frames and Covers; G

Handhole Frames and Covers; GCable Supports (racks, arms and insulators); G

SD-06 Test Reports

Medium Voltage Cable Qualification and Production Tests; G

Field Acceptance Checks and Tests; G

Arc-proofing Test for cable fireproofing tape; G

Cable Installation Plan and Procedure; G

Six copies of the information described below in 8-1/2 by 11 inch binders having a minimum of three rings from which material may readily be removed and replaced, including a separate section for each cable pull. Separate sections by heavy plastic dividers with tabs, with all data sheets signed and dated by the person supervising the pull.

a. Site layout drawing with cable pulls numerically identified.

b. A list of equipment used, with calibration certifications. The manufacturer and quantity of lubricant used on pull.

c. The cable manufacturer and type of cable.

d. The dates of cable pulls, time of day, and ambient temperature.

e. The length of cable pull and calculated cable pulling tensions.

f. The actual cable pulling tensions encountered during pull.

SD-07 Certificates

Cable splicer/terminator; G

Cable Installer Qualifications; G

Directional Boring Certificate of Conformance; G

1.5 QUALITY ASSURANCE

1.5.1 Precast Underground Structures

Submittal required for each type used. Provide calculations and drawings for precast manholes and handholes bearing the seal of a registered professional engineer including:

a. Material description (i.e., f'c and Fy)

b. Manufacturer's printed assembly and installation instructions

c. Design calculations

d. Reinforcing shop drawings in accordance with ACI SP-66

e. Plans and elevations showing opening and pulling-in iron locations and details

1.5.2 Certificate of Competency for Cable Splicer/Terminator

The cable splicer/terminator must have a certification from the National Cable Splicing Certification Board (NCSCB) in the field of splicing and terminating shielded medium voltage (5 kV to 35 kV) power cable using pre-manufactured kits (pre-molded, heat-shrink, cold shrink). Submit "Proof of Certification" for approval, for the individuals that will be performing cable splicer and termination work, 30 days before splices or terminations are to be made.

Submit certification of the qualification of the cable splicer/terminator for approval, 30 days before splices or terminations are to be made in medium voltage (5 kV to 35 kV) cables. Include the training, and experience of the individual on the specific type and classification of cable to be provided under this contract. Indicate that the individual has had three or more years recent experience splicing and terminating medium voltage cables. List a minimum of three splices/terminations that have been in operation for more than one year. In addition, the individual may be required to perform a dummy or practice splice/termination in the presence of the Contracting Officer, before being approved as a qualified cable splicer. If that additional requirement is imposed, the Contractor must provide short sections of the approved types of cables along with the approved type of splice/termination kit, and detailed manufacturer's instructions for the cable to be spliced. The Contracting Officer reserves the right to require additional proof of competency or to reject the individual and call for certification of an alternate cable splicer.

1.5.3 Cable Installer Qualifications

Provide at least one onsite person in a supervisory position with a documentable level of competency and experience to supervise all cable pulling operations. Provide a resume showing the cable installers' experience in the last three years, including a list of references complete with points of contact, addresses and telephone numbers. Cable installer must demonstrate experience with a minimum of three medium

voltage cable installations. The Contracting Officer reserves the right to require additional proof of competency or to reject the individual and call for an alternate qualified cable installer.

1.5.4 Directional Boring Certificate of Conformance

Provide certification of compliance with the registered Professional Engineer's design requirements for each directional bore, including: HDPE conduit size and type, bend radius, elevation changes, vertical and horizontal path deviations, conductor size and type and any conductor derating due to depth of conduit. Record location and depth of all directional-bore installed HDPE conduits using Global Positioning System (GPS) recording means with "resource grade" accuracy.

1.5.5 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean the Contracting Officer. Equipment, materials, installation, and workmanship must be in accordance with the mandatory and advisory provisions of IEEE C2 and NFPA 70 unless more stringent requirements are specified or indicated.

1.5.6 Standard Products

Provide materials and equipment that are products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship. Products must have been in satisfactory commercial or industrial use for 2 years prior to bid opening. The 2-year period must include applications of equipment and materials under similar circumstances and of similar size. The product must have been for sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Where two or more items of the same class of equipment are required, these items must be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section.

1.5.6.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is furnished.

1.5.6.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site are not acceptable, unless specified otherwise.

PART 2 PRODUCTS

2.1 CONDUIT, DUCTS, AND FITTINGS

2.1.1 Rigid Metal Conduit

UL 6.

2.1.1.1 Rigid Metallic Conduit, PVC Coated

NEMA RN 1, Type A40, except that hardness must be nominal 85 Shore A durometer, dielectric strength must be minimum 400 volts per mil at 60 Hz, and tensile strength must be minimum 3500 psi.

2.1.2 Intermediate Metal Conduit

UL 1242.

2.1.2.1 Intermediate Metal Conduit, PVC Coated

NEMA RN 1, Type A40, except that hardness must be nominal 85 Shore A durometer, dielectric strength must be minimum 400 volts per mil at 60 Hz, and tensile strength must be minimum 3500 psi.

2.1.3 Plastic Conduit for Direct Burial and Riser Applications

UL 651 and NEMA TC 2, EPC-40 or EPC-80 as indicated.

2.1.4 Plastic Duct for Concrete Encasement

Provide Type EB-20 per UL 651, ASTM F512, and NEMA TC 6 & 8 or Type EPC-40 per UL 651 and NEMA TC 2, as indicated.

2.1.5 High Density Polyethylene (HDPE) Electrical Conduit for Directional Boring

Smoothwall, approved/listed for directional boring, minimum Schedule 80, ASTM F2160, NEMA TC 7.

2.1.6 Duct Sealant

UL 94, Class HBF. Provide high-expansion urethane foam duct sealant that expands and hardens to form a closed, chemically and water resistant, rigid structure. Sealant must be compatible with common cable and wire jackets and capable of adhering to metals, plastics and concrete. Sealant must be capable of curing in temperature ranges of 35 degrees F to 95 degrees F. Cured sealant must withstand temperature ranges of -20 degrees F to 200 degrees F without loss of function.

2.1.7 Fittings

2.1.7.1 Metal Fittings

UL 514B.

2.1.7.2 PVC Conduit Fittings

UL 514B, UL 651.

2.1.7.3 PVC Duct Fittings

NEMA TC 9.

2.1.7.4 Outlet Boxes for Steel Conduit

Outlet boxes for use with rigid or flexible steel conduit must be cast-metal cadmium or zinc-coated if of ferrous metal with gasketed

closures and must conform to UL 514A.

2.2 LOW VOLTAGE INSULATED CONDUCTORS AND CABLES

Insulated conductors must be rated 600 volts and conform to the requirements of NFPA 70, including listing requirements. Wires and cables manufactured more than 24 months prior to date of delivery to the site are not acceptable. Service entrance conductors must conform to UL 854, type USE.

2.2.1 Conductor Types

Cable and duct sizes indicated are for copper conductors and THHN/THWN unless otherwise noted. Conductors No. 10 AWG and smaller must be solid. Conductors No. 8 AWG and larger must be stranded. All conductors must be copper.

2.2.2 Conductor Material

Unless specified or indicated otherwise or required by NFPA 70, wires in conduit, other than service entrance, must be 600-volt, Type THWN/THHN conforming to UL 83. Copper conductors must be annealed copper complying with ASTM B3 and ASTM B8.

2.2.3 Jackets

Provide multiconductor cables with an overall PVC outer jacket.

2.2.4 Cable Marking

Insulated conductors must have the date of manufacture and other identification imprinted on the outer surface of each cable at regular intervals throughout the cable length.

Identify each cable by means of a fiber, laminated plastic, or non-ferrous metal tags in each manhole, handhole, junction box, and each terminal. Each tag must contain the following information; cable type, conductor size, circuit number, circuit voltage, cable destination and phase identification.

Color code conductors. Provide conductor identification within each enclosure where a tap, splice, or termination is made. Conductor identification must be by color-coded insulated conductors, plastic-coated self-sticking printed markers, colored nylon cable ties and plates, heat shrink type sleeves,or colored electrical tape. Properly identify control circuit terminations. Color must be green for grounding conductors and white for neutrals; except where neutrals of more than one system are installed in same raceway or box, other neutrals may be white with a different colored (not green) stripe for each. Color of ungrounded conductors in different voltage systems are as follows:

a. 208/120 volt, three-phase

(1) Phase A - black

(2) Phase B - red

(3) Phase C - blue

b. 480/277 volt, three-phase

(1) Phase A - brown

(2) Phase B - orange

(3) Phase C - yellow

c. 120/240 volt, single phase: Black and red

2.3 LOW VOLTAGE WIRE CONNECTORS AND TERMINALS

Provide a uniform compression over the entire conductor contact surface. Use solderless terminal lugs on stranded conductors.

a. For use with copper conductors: UL 486A-486B.

2.4 MEDIUM VOLTAGE CABLE

Cable (conductor) sizes are designated by American Wire Gauge (AWG) and Thousand Circular Mils (Kcmil). Conductor and conduit sizes indicated are for copper conductors unless otherwise noted. Insulated conductors must have the date of manufacture and other identification imprinted on the outer surface of each cable at regular intervals throughout cable length. Wires and cables manufactured more than 24 months prior to date of delivery to the site are not acceptable. Provide single conductor type cables unless otherwise indicated.

2.4.1 Cable Configuration

Provide Type MV cable, conforming to NEMA WC 74/ICEA S-93-639 and UL 1072. Provide cables manufactured for use in duct applications as indicated. Cable must be rated 15 kVas indicated with 133 percent insulation level.

2.4.2 Conductor Material

Provide concentric-lay-stranded, Class B compact round conductors. Provide soft drawn copper cables complying with ASTM B3 and ASTM B8 for regular concentric and compressed stranding or ASTM B496 for compact stranding.

2.4.3 Insulation

Provide ethylene-propylene-rubber (EPR) insulation conforming to the requirements of ANSI/NEMA WC 71/ICEA S-96-659 and AEIC CS8.

2.4.4 Shielding

Cables rated for 2 kV and above must have a semiconducting conductor shield, a semiconducting insulation shield, and an overall copper tape or wire shield for each phase.

2.4.5 Neutrals

Neutral conductors must be copper, employing the same insulation and jacket materials as phase conductors, except that a 600-volt insulation rating is acceptable.

2.4.6 Jackets

Provide cables with a PVC jacket. Provide PVC jackets with a separator that prevents contact with underlying semiconducting insulating shield.

2.5 MEDIUM VOLTAGE CABLE TERMINATIONS

IEEE 48 Class 1; of the molded elastomer, prestretched elastomer, or heat-shrinkable elastomer. Acceptable elastomers are track-resistant silicone rubber or track-resistant ethylene propylene compounds, such as ethylene propylene rubber or ethylene propylene diene monomer. Separable insulated connectors may be used for apparatus terminations, when such apparatus is provided with suitable bushings. Provide terminations, where required, with mounting brackets suitable for the intended installation and with grounding provisions for the cable shielding, metallic sheath, or armor. Provide terminations in a kit, including: skirts, stress control terminator, ground clamp, connectors, lugs, and complete instructions for assembly and installation. Terminations must be the product of one manufacturer, suitable for the type, diameter, insulation class and level, and materials of the cable terminated. Do not use separate parts of copper or copper alloy in contact with aluminum alloy parts in the construction or installation of the terminator.

2.5.1 Cold-Shrink Type

Terminator must be a one-piece design, utilizing the manufacturer's latest technology, where high-dielectric constant (capacitive) stress control is integrated within a skirted insulator made of silicone rubber. Termination must not require heat or flame for installation. Termination kit must contain all necessary materials (except for the lugs). Design termination for installation in low or highly contaminated indoor and outdoor locations and must resist ultraviolet rays and oxidative decomposition.

2.5.2 Heat Shrinkable Type

Terminator must consist of a uniform cross section heat shrinkable polymeric construction stress relief tubing and environmentally sealed outer covering that is nontracking, resists heavy atmospheric contaminants, ultra violet rays and oxidative decomposition. Provide heat shrinkable sheds or skirts of the same material. Design termination for installation in low or highly contaminated indoor or outdoor locations.

2.5.3 Separable Insulated Connector Type

IEEE 386. Provide connector with steel reinforced hook-stick eye, grounding eye, test point, and arc-quenching contact material. Provide connectors of the loadbreak or deadbreak type as indicated, of suitable construction for the application and the type of cable connected, and that include cable shield adaptors. Provide external clamping points and test points. Do no use separable connectors in manholes/handholes.

a. 200 Ampere loadbreak connector ratings: Voltage: 15 kV, 95 kV BIL. Short time rating: 10,000 rms symmetrical amperes.

b. 600 Ampere deadbreak connector ratings: Voltage: 15 kV, 95 kV BIL. Short time rating: 25,000 rms symmetrical amperes. Connectors must have 200 ampere bushing interface for surge arresters as indicated.

c. Provide sets of three grounding elbows and sets of three feed-thru inserts. Deliver grounding elbows and feed-thru inserts to the Contracting Officer.

d. Install one set of faulted circuit indicators, complying with IEEE 495, on the test points of each set of separable insulated connectors. Indicators must be self powered; with automatic trip with mechanical flag indication upon overcurrent followed by loss of system voltage, and automatic reset upon restoration of system voltage. Indicators must be compact, sealed corrosion resistant construction with provision for hotstick installation and operation.

2.6 MEDIUM VOLTAGE CABLE JOINTS

Provide joints (splices) in accordance with IEEE 404 suitable for the rated voltage, insulation level, insulation type, and construction of the cable. Joints must be certified by the manufacturer for waterproof, submersible applications. Upon request, supply manufacturer's design qualification test report in accordance with IEEE 404. Connectors for joint must be tin-plated electrolytic copper, having ends tapered and having center stops to equalize cable insertion.

2.6.1 Heat-Shrinkable Joint

Consists of a uniform cross-section heat-shrinkable polymeric construction with a linear stress relief system, a high dielectric strength insulating material, and an integrally bonded outer conductor layer for shielding. Replace original cable jacket with a heavy-wall heat-shrinkable sleeve with hot-melt adhesive coating.

2.6.2 Cold-Shrink Rubber-Type Joint

Joint must be of a cold shrink design that does not require any heat source for its installation. Splice insulation and jacket must be of a one-piece factory formed cold shrink sleeve made of black EPDM rubber. Splice should be packaged three splices per kit, including complete installation instructions.

2.7 TELECOMMUNICATIONS CABLING

Provide telecommunications cabling in accordance with Section 33 82 00 TELECOMMUNICATIONS OUTSIDE PLANT (OSP).

2.8 TAPE

2.8.1 Insulating Tape

UL 510, plastic insulating tape, capable of performing in a continuous temperature environment of 80 degrees C.

2.8.2 Buried Warning and Identification Tape

Provide detectable tape in accordance with Section 31 00 00 EARTHWORK.

2.8.3 Fireproofing Tape

Provide tape composed of a flexible, conformable, unsupported intumescent elastomer. Tape must be not less than .030 inch thick, noncorrosive to cable sheath, self-extinguishing, noncombustible, adhesive-free, and must

not deteriorate when subjected to oil, water, gases, salt water, sewage, and fungus.

2.9 PULL ROPE

Plastic or flat pull line (bull line) having a minimum tensile strength of 200 pounds.

2.10 GROUNDING AND BONDING

2.10.1 Driven Ground Rods

Provide copper-clad steel ground rods conforming to UL 467 not less than 3/4 inch in diameter by 10 feet in length. Sectional type rods may be used for rods 20 feet or longer.

2.10.2 Grounding Conductors

Stranded-bare copper conductors must conform to ASTM B8, Class B, soft-drawn unless otherwise indicated. Solid-bare copper conductors must conform to ASTM B1 for sizes No. 8 and smaller. Insulated conductors must be of the same material as phase conductors and green color-coded, except that conductors must be rated no more than 600 volts. Aluminum is not acceptable.

2.11 CAST-IN-PLACE CONCRETE

Provide concrete in accordance with Section 03 30 00 CAST-IN-PLACE CONCRETE. In addition, provide concrete for encasement of underground ducts with 3000 psi minimum 28-day compressive strength. Concrete associated with electrical work for other than encasement of underground ducts must be 4000 psi minimum 28-day compressive strength unless specified otherwise.

2.12 UNDERGROUND STRUCTURES

Provide precast concrete underground structures or standard type cast-in-place manhole types as indicated, conforming to ASTM C857 and ASTM C478. Top, walls, and bottom must consist of reinforced concrete. Walls and bottom must be of monolithic concrete construction. Locate duct entrances and windows near the corners of structures to facilitate cable racking. Covers must fit the frames without undue play. Form steel and iron to shape and size with sharp lines and angles. Castings must be free from warp and blow holes that may impair strength or appearance. Exposed metal must have a smooth finish and sharp lines and arises. Provide necessary lugs, rabbets, and brackets. Set pulling-in irons and other built-in items in place before depositing concrete. Install a pulling-in iron in the wall opposite each duct line entrance. Cable racks, including rack arms and insulators, must be adequate to accommodate the cable.

2.12.1 Precast Concrete Structures, Risers and Tops

Precast concrete underground structures may be provided in lieu of cast-in-place subject to the requirements specified below. Precast units must be the product of a manufacturer regularly engaged in the manufacture of precast concrete products, including precast manholes.

2.12.1.1 General

Precast concrete structures must have the same accessories and facilities as required for cast-in-place structures. Likewise, precast structures must have plan area and clear heights not less than those of cast-in-place structures. Concrete materials and methods of construction must be the same as for cast-in-place concrete construction, as modified herein. Slope in floor may be omitted provided precast sections are poured in reinforced steel forms. Concrete for precast work must have a 28-day compressive strength of not less than 4000 psi. Structures may be precast to the design and details indicated for cast-in-place construction, precast monolithically and placed as a unit, or structures may be assembled sections, designed and produced by the manufacturer in accordance with the requirements specified. Structures must be identified with the manufacturer's name embedded in or otherwise permanently attached to an interior wall face.

2.12.1.2 Design for Precast Structures

ACI 318M. In the absence of detailed on-site soil information, design for the following soil parameters/site conditions:

a. Angle of Internal Friction (phi) = 30 degrees

b. Unit Weight of Soil (Dry) = 110 pcf, (Saturated) = 130 pcf

c. Coefficient of Lateral Earth Pressure (Ka) = 0.33

d. Ground Water Level = 3 feet below ground elevation

e. Vertical design loads must include full dead, superimposed dead, and live loads including a 30 percent magnification factor for impact. Live loads must consider all types and magnitudes of vehicular (automotive, industrial, or aircraft) traffic to be encountered. The minimum design vertical load must be for H20 highway loading per AASHTO HB-17.

f. Horizontal design loads must include full geostatic and hydrostatic pressures for the soil parameters, water table, and depth of installation to be encountered. Also, horizontal loads imposed by adjacent structure foundations, and horizontal load components of vertical design loads, including impact, must be considered, along with a pulling-in iron design load of 6000 pounds.

g. Each structural component must be designed for the load combination and positioning resulting in the maximum shear and moment for that particular component.

h. Design must also consider the live loads induced in the handling, installation, and backfilling of the manholes. Provide lifting devices to ensure structural integrity during handling and installation.

2.12.1.3 Construction

Provide a uniform thickness for structure top, bottom, and wall not less than 6 inches. Thin-walled knock-out panels for designed or future duct bank entrances are not permitted. Provide quantity, size, and location of

duct bank entrance windows as directed, and cast completely open by the precaster. Size of windows must exceed the nominal duct bank envelope dimensions by at least 12 inches vertically and horizontally to preclude in-field window modifications made necessary by duct bank misalignment. However, the sides of precast windows must be a minimum of 6 inches from the inside surface of adjacent walls, floors, or ceilings. Form the perimeter of precast window openings to have a keyed or inward flared surface to provide a positive interlock with the mating duct bank envelope. Provide welded wire fabric reinforcing through window openings for in-field cutting and flaring into duct bank envelopes. Provide additional reinforcing steel comprised of at least two No. 4 bars around window openings. Provide drain sumps a minimum of 12 inches in diameter and 4 inches deep for precast structures.

2.12.1.4 Joints

Provide tongue-and-groove joints on mating edges of precast components. Shiplap joints are not allowed. Design joints to firmly interlock adjoining components and to provide waterproof junctions and adequate shear transfer. Seal joints watertight using preformed plastic strip conforming to ASTM C990. Install sealing material in strict accordance with the sealant manufacturer's printed instructions. Provide waterproofing at conduit/duct entrances into structures, and where access frame meets the top slab, provide continuous grout seal.

2.12.2 Manhole Frames and Covers

Provide cast iron frames and covers for manholes conforming to CID A-A-60005. Cast the words "ELECTRIC" or "TELECOMMUNICATIONS" in the top face of power and telecommunications manhole covers, respectively.

2.12.3 Handhole Frames and Covers

Frames and covers of steel must be welded by qualified welders in accordance with standard commercial practice. Provide rolled-steel floor plate covers having an approved antislip surface. Hinges must be of stainless steel with bronze hinge pin , 5 by 5 inches by approximately 3/16 inch thick, without screw holes, and must be for full surface application by fillet welding. Hinges must have nonremovable pins and five knuckles. The surfaces of plates under hinges must be true after the removal of raised antislip surface, by grinding or other approved method.

2.13 CABLE SUPPORTS (RACKS, ARMS, AND INSULATORS)

Zinc coat the metal portion of racks and arms after fabrication.

2.13.1 Cable Rack Stanchions

The wall bracket or stanchion must be 4 inches by approximately 1-1/2 inch by 3/16 inch channel steel, or 4 inches by approximately 1 inch glass-reinforced nylon with recessed bolt mounting holes, 48 inches long (minimum) in manholes. Space slots for mounting cable rack arms at 8 inch intervals.

2.13.2 Rack Arms

Cable rack arms must be steel or malleable iron or glass reinforced nylon and must be of the removable type. Rack arm length must be a minimum of 8 inches and a maximum of 12 inches.

2.13.3 Insulators

Insulators for metal rack arms must be dry-process glazed porcelain. Insulators are not required for nylon arms.

2.14 CABLE TAGS IN MANHOLES

Provide polyethylene tags for each power cable located in manholes. Do not provide handwritten letters. The first position on the power cable tag denotes the voltage. The second through sixth positions on the tag identifies the circuit. The next to last position denotes the phase of the circuit and include the Greek "phi" symbol. The last position denotes the cable size. As an example, a tag could have the following designation: "11.5 NAS 1-8(Phase A)500," denoting that the tagged cable is on the 11.5kV system circuit number NAS 1-8, underground, Phase A, sized at 500 kcmil.

2.14.1 Polyethylene Cable Tags

Provide tags of polyethylene having an average tensile strength of 3250 pounds per square inch; and that are 0.08 inch thick (minimum), non-corrosive non-conductive; resistive to acids, alkalis, organic solvents, and salt water; and distortion resistant to 170 degrees F. Provide 0.05 inch (minimum) thick black polyethylene tag holder. Provide a one-piece nylon, self-locking tie at each end of the cable tag, having a minimum loop tensile strength of 175 pounds and black block letters, numbers, and symbols one inch high on a yellow background. Letters, numbers, and symbols must not fall off or change positions regardless of the cable tags' orientation.

2.15 MEDIUM VOLTAGE ABOVE GROUND CABLE TERMINATING CABINETS

Cable terminating cabinets must be hook-stick operable, deadfront construction conforming to the requirements of IEEE C37.20.3, Category A. Provide cabinets with 200 A. loadbreak junctions and elbow-type separable loadbreak connectors, cable parking stands, and grounding lugs600 A. dead-break junctions and elbow-type separable dead-break connectors, cable parking stands, and grounding lugs. Provide cable terminating equipment in conformance with IEEE 386.

Ratings at 60 Hz must be:

Nominal voltage (kV)	
Rated maximum voltage (kV)	15
Rated continuous current (A)	200600
One-second short-time current-carrying capacity (kA)	
BIL (kV)	

2.16 SOURCE QUALITY CONTROL

2.16.1 Arc-Proofing Test for Cable Fireproofing Tape

Manufacturer must test one sample assembly consisting of a straight lead tube 12 inches long with a 2 1/2 inch outside diameter, and a 1/8 inch thick wall, and covered with one-half lap layer of arc and fireproofing tape per manufacturer's instructions. The arc and fireproofing tape must withstand extreme temperature of a high-current fault arc 13,000 degrees K for 70 cycles as determined by using an argon directed plasma jet capable of constantly producing and maintaining an arc temperature of 13,000 degrees K. Temperature (13,000 degrees K) of the ignited arc between the cathode and anode must be obtained from a dc power source of 305 (plus or minus 5) amperes and 20 (plus or minus 1) volts. Direct the arc toward the sample assembly accurately positioned 5 (plus or minus 1) millimeters downstream in the plasma from the anode orifice by fixed flow rate of argon gas (0.18 g per second). Test each sample assembly at three unrelated points. Start time for tests must be taken from recorded peak current when the specimen is exposed to the full test temperature. Surface heat on the specimen prior to that time must be minimal. The end point is established when the plasma or conductive arc penetrates the protective tape and strikes the lead tube. Submittals for arc-proofing tape must indicate that the test has been performed and passed by the manufacturer.

2.16.2 Medium Voltage Cable Qualification and Production Tests

Results of AEIC CS8 qualification and production tests as applicable for each type of medium voltage cable.

PART 3 EXECUTION

3.1 INSTALLATION

Install equipment and devices in accordance with the manufacturer's published instructions and with the requirements and recommendations of NFPA 70 as applicable. In addition to these requirements, install telecommunications in accordance with TIA-758 and RUS Bull 1751F-644.

3.2 CABLE INSPECTION

Inspect each cable reel for correct storage positions, signs of physical damage, and broken end seals prior to installation. If end seal is broken, remove moisture from cable prior to installation in accordance with the cable manufacturer's recommendations.

3.3 CABLE INSTALLATION PLAN AND PROCEDURE

Obtain from the manufacturer an installation manual or set of instructions which addresses such aspects as cable construction, insulation type, cable diameter, bending radius, cable temperature limits for installation, lubricants, coefficient of friction, conduit cleaning, storage procedures, moisture seals, testing for and purging moisture, maximum allowable pulling tension, and maximum allowable sidewall bearing pressure. Prepare a checklist of significant requirements Perform pulling calculations and prepare a pulling plan and submit along with the manufacturer's instructions in accordance with SUBMITTALS. Install cable strictly in accordance with the cable manufacturer's recommendations and the approved installation plan.

Calculations and pulling plan must include:

a. Site layout drawing with cable pulls identified in numeric order of expected pulling sequence and direction of cable pull.

b. List of cable installation equipment.

c. Lubricant manufacturer's application instructions.

d. Procedure for resealing cable ends to prevent moisture from entering cable.

e. Cable pulling tension calculations of all cable pulls.

f. Cable percentage conduit fill.

g. Cable sidewall bearing pressure.

h. Cable minimum bend radius and minimum diameter of pulling wheels used.

i. Cable jam ratio.

j. Maximum allowable pulling tension on each different type and size of conductor.

k. Maximum allowable pulling tension on pulling device.

3.4 UNDERGROUND FEEDERS SUPPLYING BUILDINGS

Terminate underground feeders supplying building at a point 5 feet outside the building and projections thereof, except that conductors must be continuous to the terminating point indicated. Coordinate connections of the feeders to the service entrance equipment with Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM. Provide PVC, Type EPC-40 conduit from the supply equipment to a point 5 feet outside the building and projections thereof. Protect ends of underground conduit with plastic plugs until connections are made.

Encase the underground portion of the conduit in a concrete envelope and bury as specified for underground duct with concrete encasement.

3.5 UNDERGROUND STRUCTURE CONSTRUCTION

Provide standard type cast-in-place construction as specified herein and as indicated, or precast construction as specified herein. Horizontal concrete surfaces of floors must have a smooth trowel finish. Cure concrete by applying two coats of white pigmented membrane forming-curing compound in strict accordance with the manufacturer's printed instructions, except that precast concrete may be steam cured. Curing compound must conform to ASTM C309. Locate duct entrances and windows in the center of end walls (shorter) and near the corners of sidewalls (longer) to facilitate cable racking and splicing. Covers for underground structures must fit the frames without undue play. Form steel and iron to shape and size with sharp lines and angles. Castings must be free from warp and blow holes that may impair strength or appearance. Exposed metal must have a smooth finish and sharp lines and arises. Provide necessary lugs, rabbets, and brackets. Set pulling-in irons and other built-in items in place before depositing concrete. Manhole locations, as

indicated, are approximate. Coordinate exact manhole locations with other utilities and finished grading and paving.

3.5.1 Precast Concrete Construction

Set commercial precast structures on 6 inches of level, 90 percent compacted granular fill, 3/4 inch to 1 inch size, extending 12 inches beyond the structure on each side. Compact granular fill by a minimum of four passes with a plate type vibrator. Installation must additionally conform to the manufacturer's instructions.

3.5.2 Pulling-In Irons

Provide steel bars bent as indicated, and cast in the walls and floors. Alternatively, pipe sleeves may be precast into the walls and floors where required to accept U-bolts or other types of pulling-in devices possessing the strengths and clearances stated herein. The final installation of pulling-in devices must be made permanent. Cover and seal exterior projections of thru-wall type pulling-in devices with an appropriate protective coating. In the floor, locate the irons a minimum of 6 inches from the edge of the sump, and in the walls, locate the irons within 6 inches of the projected center of the duct bank pattern or precast window in the opposite wall. However, the pulling-in iron must not be located within 6 inches of an adjacent interior surface, or duct or precast window located within the same wall as the iron. If a pulling-in iron cannot be located directly opposite the corresponding duct bank or precast window due to this clearance limitation, locate the iron directly above or below the projected center of the duct bank pattern or precast window the minimum distance required to preserve the 6 inch clearance previously stated. In the case of directly opposing precast windows, pulling-in irons consisting of a 3 foot length of No. 5 reinforcing bar, formed into a hairpin, may be cast-in-place within the precast windows simultaneously with the end of the corresponding duct bank envelope. Irons installed in this manner must be positioned directly in line with, or when not possible, directly above or below the projected center of the duct bank pattern entering the opposite wall, while maintaining a minimum clear distance of 3 inches from any edge of the cast-in-place duct bank envelope or any individual duct. Pulling-in irons must have a clear projection into the structure of approximately 4 inches and must be designed to withstand a minimum pulling-in load of 6000 pounds. Hot-dip galvanize irons after fabrication.

3.5.3 Cable Racks, Arms and Insulators

Cable racks, arms and insulators must be sufficient to accommodate the cables. Space racks in power manholes not more than 3 feet apart, and provide each manhole wall with a minimum of two racks. Space racks in signal manholes not more than 16 1/2 inches apart with the end rack being no further than 12 inches from the adjacent wall. Methods of anchoring cable racks are as follows:

a. Provide a 5/8 inch diameter by 5 inch long anchor bolt with 3 inch foot cast in structure wall with 2 inch protrusion of threaded portion of bolt into structure. Provide 5/8 inch steel square head nut on each anchor bolt. Coat threads of anchor bolts with suitable coating immediately prior to installing nuts.

b. Provide concrete channel insert with a minimum load rating of 800 pounds per foot. Insert channel must be steel of the same length as

"vertical rack channel;" and cast flush in structure wall. Provide 5/8 inch steel nuts in channel insert to receive 5/8 inch diameter by 3 inch long steel, square head anchor bolts.

c. Provide concrete "spot insert" at each anchor bolt location, cast flush in structure wall. Each insert must have minimum 800 pound load rating. Provide 5/8 inch diameter by 3 inch long steel, square head anchor bolt at each anchor point. Coat threads of anchor bolts with suitable coating immediately prior to installing bolts.

3.5.4 Field Painting

Clean cast-iron frames and covers not buried in concrete or masonry of mortar, rust, grease, dirt and other deleterious materials, and coat with bituminous paint.

3.6 UNDERGROUND CONDUIT AND DUCT SYSTEMS

3.6.1 Requirements

Run conduit in straight lines except where a change of direction is necessary. Provide numbers and sizes of ducts as indicated. Provide a 4/0 AWG bare copper grounding conductor below medium-voltage distribution duct banks. Bond bare copper grounding conductor to ground rings (loops) in all manholes and to ground rings (loops) at all equipment slabs (pads). Route grounding conductor into manholes with the duct bank (sleeving is not required). Ducts must have a continuous slope downward toward underground structures and away from buildings, laid with a minimum slope of 3 inches per 100 feet. Depending on the contour of the finished grade, the high-point may be at a terminal, a manhole, a handhole, or between manholes or handholes. Terminate all PVC conduit end points in utility holes, switching cabinets, transform handholes and buildings with end bells. The bell end of the conduits that enter manholes and handholes must be flush with the wall.

Perform changes in ductbank direction as follows:

a. Short-radius manufactured 90-degree duct bends may be used only for pole or equipment risers, unless specifically indicated as acceptable.

b. The minimum manufactured bend radius must be 18 inches for ducts of less than 3 inch diameter, and 36 inches for ducts 3 inches or greater in diameter.

c. As an exception to the bend radius required above, provide field manufactured longsweep bends having a minimum radius of 25 feet for a change of direction of more than 5 degrees, either horizontally or vertically, using a combination of curved and straight sections. Maximum manufactured curved sections allowed for use in field manufactured longsweep bend: 30 degrees.

3.6.2 Treatment

Keep ducts clean of concrete, dirt, or foreign substances during construction. Make field cuts requiring tapers with proper tools and match factory tapers. Use a coupling recommended by the duct manufacturer whenever an existing duct is connected to a duct of different material or shape. Store ducts to avoid warping and deterioration with ends sufficiently plugged to prevent entry of any water or solid substances.

Thoroughly clean ducts before being laid. Store plastic ducts on a flat surface and protected from the direct rays of the sun.

3.6.3 Conduit Cleaning

As each conduit run is completed, for conduit sizes 3 inches and larger, draw a flexible testing mandrel approximately 12 inches long with a diameter less than the inside diameter of the conduit through the conduit. After which, draw a stiff bristle brush through until conduit is clear of particles of earth, sand and gravel; then immediately install conduit plugs. For conduit sizes less than 3 inches, draw a stiff bristle brush through until conduit is clear of particles of earth, sand and gravel; then immediately install conduit plugs.

3.6.4 Jacking and Drilling Under Roads and Structures

Conduits to be installed under existing paved areas which are not to be disturbed, and under roads and railroad tracks, must be zinc-coated, rigid steel, jacked into place. Where ducts are jacked under existing pavement, install rigid steel conduit because of its strength. To protect the corrosion-resistant conduit coating, predrilling or installing conduit inside a larger iron pipe sleeve (jack-and-sleeve) is required. For crossings of existing railroads and airfield pavements greater than 50 feet in length, the predrilling method or the jack-and-sleeve method will be used. Separators or spacing blocks must be made of steel, concrete, plastic, or a combination of these materials placed not farther apart than 4 feet on centers.

3.6.5 Galvanized Conduit Concrete Penetrations

Galvanized conduits which penetrate concrete (slabs, pavement, and walls) in wet locations must be PVC coated and extend from at least 2 inches within the concrete to the first coupling or fitting outside the concrete (minimum of 6 inches from penetration).

3.6.6 Multiple Conduits

Separate multiple conduits by a minimum distance of 3 inches, except that light and power conduits must be separated from control, signal, and telephone conduits by a minimum distance of 12 inches. Stagger the joints of the conduits by rows (horizontally) and layers (vertically) to strengthen the conduit assembly. Provide plastic duct spacers that interlock vertically and horizontally. Spacer assembly must consist of base spacers, intermediate spacers, ties, and locking device on top to provide a completely enclosed and locked-in conduit assembly. Install spacers per manufacturer's instructions, but provide a minimum of two spacer assemblies per 10 feet of conduit assembly.

3.6.7 Conduit Plugs and Pull Rope

Provide new conduit indicated as being unused or empty with plugs on each end. Plugs must contain a weephole or screen to allow water drainage. Provide a plastic pull rope having 3 feet of slack at each end of unused or empty conduits.

3.6.8 Conduit and Duct Without Concrete Encasement

Depths to top of the conduit must be not less than 24 inches below finished grade. Provide not less than 3 inches clearance from the conduit

to each side of the trench. Grade bottom of trench smooth; where rock, soft spots, or sharp-edged materials are encountered, excavate the bottom for an additional 3 inches, fill and tamp level with original bottom with sand or earth free from particles, that would be retained on a 1/4 inch sieve. The first 6 inch layer of backfill cover must be sand compacted as previously specified. The rest of the excavation must be backfilled and compacted in 3 to 6 inch layers. Provide color, type and depth of warning tape as specified in Section 31 00 00 EARTHWORK.

3.6.8.1 Encasement Under Roads and Structures

Under roads, paved areas, and railroad tracks, install conduits in concrete encasement of rectangular cross-section providing a minimum of 3 inch concrete cover around ducts. Extend concrete encasement at least 5 feet beyond the edges of paved areas and roads, and 12 feet beyond the rails on each side of railroad tracks. Depths to top of the concrete envelope must be not less than 24 inches below finished grade.

3.6.8.2 Directional Boring

HDPE conduits must be installed below the frostline and as specified herein.

For distribution voltages greater than 1000 volts and less than 34,500 volts, depths to the top of the conduit must not be less than 48 inches in pavement-covered areas and not less than 120 inches in non-pavement-covered areas. For distribution voltages less than 1000 volts, depths to the top of the conduit must not be less than 48 inches in pavement- or non-pavement-covered areas. For branch circuit wiring less than 600 volts, depths to the top of the conduit must not be less than 24 inches in pavement- or non-pavement-covered areas.

3.6.9 Duct Encased in Concrete

Construct underground duct lines of individual conduits encased in concrete. Depths to top of the concrete envelope must be not less than 18 inches below finished grade, except under roads and pavement, concrete envelope must be not less than 24 inches below finished grade. Do not mix different kinds of conduit in any one duct bank. Concrete encasement surrounding the bank must be rectangular in cross-section and provide at least 3 inches of concrete cover for ducts. Separate conduits by a minimum concrete thickness of 3 inches. Before pouring concrete, anchor duct bank assemblies, prevent floating during concrete pouring by driving reinforcing rods adjacent to duct spacer assemblies and attaching the rods to the spacer assembly. Provide steel reinforcing in the concrete envelope as indicated. Provide color, type and depth of warning tape as specified in Section 31 00 00 EARTHWORK.

3.6.9.1 Connections to Manholes

Duct bank envelopes connecting to underground structures must be flared to have enlarged cross-section at the manhole entrance to provide additional shear strength. Dimensions of the flared cross-section must be larger than the corresponding manhole opening dimensions by no less than 12 inches in each direction. Perimeter of the duct bank opening in the underground structure must be flared toward the inside or keyed to provide a positive interlock between the duct bank and the wall of the structure. Use vibrators when this portion of the encasement is poured to assure a seal between the envelope and the wall of the structure.

3.6.9.2 Connections to Existing Underground Structures

For duct bank connections to existing structures, break the structure wall out to the dimensions required and preserve steel in the structure wall. Cut steel and extend into the duct bank envelope. Chip the perimeter surface of the duct bank opening to form a key or flared surface, providing a positive connection with the duct bank envelope.

3.6.9.3 Connections to Existing Concrete Pads

For duct bank connections to concrete pads, break an opening in the pad out to the dimensions required and preserve steel in pad. Cut the steel and extend into the duct bank envelope. Chip out the opening in the pad to form a key for the duct bank envelope.

3.6.9.4 Connections to Existing Ducts

Where connections to existing duct banks are indicated, excavate the banks to the maximum depth necessary. Cut off the banks and remove loose concrete from the conduits before new concrete-encased ducts are installed. Provide a reinforced concrete collar, poured monolithically with the new duct bank, to take the shear at the joint of the duct banks. Remove existing cables which constitute interference with the work. Abandon in place those no longer used ducts and cables which do not interfere with the work.

3.6.9.5 Partially Completed Duct Banks

During construction wherever a construction joint is necessary in a duct bank, prevent debris such as mud, and, and dirt from entering ducts by providing suitable conduit plugs. Fit concrete envelope of a partially completed duct bank with reinforcing steel extending a minimum of 2 feet back into the envelope and a minimum of 2 feet beyond the end of the envelope. Provide one No. 4 bar in each corner, 3 inches from the edge of the envelope. Secure corner bars with two No. 3 ties, spaced approximately one foot apart. Restrain reinforcing assembly from moving during concrete pouring.

3.6.9.6 Removal of Ducts

Where duct lines are removed from existing underground structures, close the openings to waterproof the structure. Chip out the wall opening to provide a key for the new section of wall.

3.6.10 Duct Sealing

Seal all electrical penetrations for radon mitigation, maintaining integrity of the vapor barrier, and to prevent infiltration of air, insects, and vermin.

3.7 CABLE PULLING

Test existing duct lines with a mandrel and thoroughly swab out to remove foreign material before pulling cables. Pull cables down grade with the feed-in point at the manhole or buildings of the highest elevation. Use flexible cable feeds to convey cables through manhole opening and into duct runs. Do not exceed the specified cable bending radii when installing cable under any conditions, including turnups into switches,

transformers, switchgear, switchboards, and other enclosures. Cable with tape or wire shield must have a bending radius not less than 12 times the overall diameter of the completed cable. If basket-grip type cable-pulling devices are used to pull cable in place, cut off the section of cable under the grip before splicing and terminating.

3.7.1 Cable Lubricants

Use lubricants that are specifically recommended by the cable manufacturer for assisting in pulling jacketed cables.

3.8 CABLES IN UNDERGROUND STRUCTURES

Do not install cables utilizing the shortest path between penetrations, but route along those walls providing the longest route and the maximum spare cable lengths. Form cables to closely parallel walls, not to interfere with duct entrances, and support on brackets and cable insulators. Support cable splices in underground structures by racks on each side of the splice. Locate splices to prevent cyclic bending in the spliced sheath. Install cables at middle and bottom of cable racks, leaving top space open for future cables, except as otherwise indicated for existing installations. Provide one spare three-insulator rack arm for each cable rack in each underground structure.

3.8.1 Cable Tag Installation

Install cable tags in each manhole as specified, including each splice. Tag wire and cable provided by this contract. Install cable tags over the fireproofing, if any, and locate the tags so that they are clearly visible without disturbing any cabling or wiring in the manholes.

3.9 CONDUCTORS INSTALLED IN PARALLEL

Group conductors such that each conduit of a parallel run contains one Phase A conductor, one Phase B conductor, one Phase C conductor, and one neutral conductor.

3.10 LOW VOLTAGE CABLE SPLICING AND TERMINATING

Make terminations and splices with materials and methods as indicated or specified herein and as designated by the written instructions of the manufacturer. Do not allow the cables to be moved until after the splicing material has completely set. Make splices in underground distribution systems only in accessible locations such as manholes, handholes, or aboveground termination pedestals.

3.11 MEDIUM VOLTAGE CABLE TERMINATIONS

Make terminations in accordance with the written instruction of the termination kit manufacturer.

3.12 MEDIUM VOLTAGE CABLE JOINTS

Provide power cable joints (splices) suitable for continuous immersion in water. Make joints only in accessible locations in manholes or handholes by using materials and methods in accordance with the written instructions of the joint kit manufacturer.

3.12.1 Joints in Shielded Cables

Cover the joined area with metallic tape, or material like the original cable shield and connect it to the cable shield on each side of the splice. Provide a bare copper ground connection brought out in a watertight manner and grounded to the manhole grounding loop as part of the splice installation. Ground conductors, connections, and rods must be as specified elsewhere in this section. Wire must be trained to the sides of the enclosure to prevent interference with the working area.

3.13 CABLE END CAPS

Cable ends must be sealed at all times with coated heat shrinkable end caps. Cables ends must be sealed when the cable is delivered to the job site, while the cable is stored and during installation of the cable. The caps must remain in place until the cable is spliced or terminated. Sealing compounds and tape are not acceptable substitutes for heat shrinkable end caps. Cable which is not sealed in the specified manner at all times will be rejected.

3.14 FIREPROOFING OF CABLES IN UNDERGROUND STRUCTURES

Fireproof (arc proof) wire and cables which will carry current at 2200 volts or more in underground structures.

3.14.1 Fireproofing Tape

Tightly wrap strips of fireproofing tape around each cable spirally in half-lapped wrapping. Install tape in accordance with manufacturer's instructions.

3.14.2 Tape-Wrap

Tape-wrap metallic-sheathed or metallic armored cables without a nonmetallic protective covering over the sheath or armor prior to application of fireproofing. Wrap must be in the form of two tightly applied half-lapped layers of a pressure-sensitive 10 mil thick plastic tape, and must extend not less than one inch into the duct. Even out irregularities of the cable, such as at splices, with insulation putty before applying tape.

3.15 GROUNDING SYSTEMS

NFPA 70 and IEEE C2, except provide grounding systems with a resistance to solid earth ground not exceeding 25 ohms.

3.15.1 Grounding Electrodes

Provide cone pointed driven ground rods driven full depth plus 6 inches, installed to provide an earth ground of the appropriate value for the particular equipment being grounded.
If the specified ground resistance is not met, provide an additional ground rod in accordance with the requirements of NFPA 70 (placed not less than 6 feet from the first rod). Should the resultant (combined) resistance exceed the specified resistance, measured not less than 48 hours after rainfall, notify the Contracting Officer immediately.

3.15.2 Grounding Connections

Make grounding connections which are buried or otherwise normally inaccessible, by exothermic weld or compression connector.

a. Make exothermic welds strictly in accordance with the weld manufacturer's written recommendations. Welds which are "puffed up" or which show convex surfaces indicating improper cleaning are not acceptable. Mechanical connectors are not required at exothermic welds.

b. Make compression connections using a hydraulic compression tool to provide the correct circumferential pressure. Tools and dies must be as recommended by the manufacturer. An embossing die code or other standard method must provide visible indication that a connector has been adequately compressed on the ground wire.

3.15.3 Grounding Conductors

Provide bare grounding conductors, except where installed in conduit with associated phase conductors. Ground cable sheaths, cable shields, conduit, and equipment with No. 6 AWG. Ground other noncurrent-carrying metal parts and equipment frames of metal-enclosed equipment. Ground metallic frames and covers of handholes and pull boxes with a braided, copper ground strap with equivalent ampacity of No. 6 AWG.

3.15.4 Ground Cable Crossing Expansion Joints

Protect ground cables crossing expansion joints or similar separations in structures and pavements by use of approved devices or methods of installation which provide the necessary slack in the cable across the joint to permit movement. Use stranded or other approved flexible copper cable across such separations.

3.15.5 Manhole Grounding

Loop a 4/0 AWG grounding conductor around the interior perimeter, approximately 12 inches above finished floor. Secure the conductor to the manhole walls at intervals not exceeding 36 inches. Connect the conductor to the manhole grounding electrode with 4/0 AWG conductor. Connect all incoming 4/0 grounding conductors to the ground loop adjacent to the point of entry into the manhole. Bond the ground loop to all cable shields, metal cable racks, and other metal equipment with a minimum 6 AWG conductor.

3.15.6 Fence Grounding

Provide grounding for fences with a ground rod at each fixed gate post and at each corner post. Drive ground rods until the top is 12 inches below grade. Attach a No. 4 AWG copper conductor, by exothermic weld to the ground rods and extend underground to the immediate vicinity of fence post. Lace the conductor vertically into 12 inches of fence mesh and fasten by two approved bronze compression fittings, one to bond wire to post and the other to bond wire to fence. Bond each gate section to its gatepost by a 1/8 by one inch flexible braided copper strap and ground post clamps. Clamps must be of the anti-electrolysis type.

3.16 EXCAVATING, BACKFILLING, AND COMPACTING

Provide in accordance with NFPA 70 and Section 31 00 00 EARTHWORK.

3.16.1 Reconditioning of Surfaces

3.16.1.1 Unpaved Surfaces

Restore to their original elevation and condition unpaved surfaces disturbed during installation of duct . Preserve sod and topsoil removed during excavation and reinstall after backfilling is completed. Replace sod that is damaged by sod of quality equal to that removed. When the surface is disturbed in a newly seeded area, re-seed the restored surface with the same quantity and formula of seed as that used in the original seeding, and provide topsoiling, fertilizing, liming, seeding, sodding, sprigging, or mulching.

3.16.1.2 Paving Repairs

Where trenches, pits, or other excavations are made in existing roadways and other areas of pavement where surface treatment of any kind exists , restore such surface treatment or pavement the same thickness and in the same kind as previously existed, except as otherwise specified, and to match and tie into the adjacent and surrounding existing surfaces.

3.17 FIELD QUALITY CONTROL

3.17.1 Performance of Field Acceptance Checks and Tests

Perform in accordance with the manufacturer's recommendations, and include the following visual and mechanical inspections and electrical tests, performed in accordance with NETA ATS.

3.17.1.1 Medium Voltage Cables

Perform tests after installation of cable, splices, and terminators and before terminating to equipment or splicing to existing circuits.

a. Visual and Mechanical Inspection

(1) Inspect exposed cable sections for physical damage.

(2) Verify that cable is supplied and connected in accordance with contract plans and specifications.

(3) Inspect for proper shield grounding, cable support, and cable termination.

(4) Verify that cable bends are not less than ICEA or manufacturer's minimum allowable bending radius.

(5) Inspect for proper fireproofing.

(6) Visually inspect jacket and insulation condition.

(7) Inspect for proper phase identification and arrangement.

b. Electrical Tests

(1) Perform a shield continuity test on each power cable by ohmmeter method. Record ohmic value, resistance values in excess of 10 ohms per 1000 feet of cable must be investigated and justified.

(2) Perform acceptance test on new cables before the new cables are connected to existing cables and placed into service, including terminations and joints. Perform maintenance test on complete cable system after the new cables are connected to existing cables and placed into service, including existing cable, terminations, and joints. Tests must be very low frequency (VLF) alternating voltage withstand tests in accordance with IEEE 400.2. VLF test frequency must be 0.05 Hz minimum for a duration of 60 minutes using a sinusoidal waveform. Test voltages must be as follows:

CABLE RATING AC TEST VOLTAGE for ACCEPTANCE TESTING	
5 kV	10kV rms(peak)
8 kV	13kV rms(peak)
15 kV	20kV rms(peak)
25 kV	31kV rms(peak)
35 kV	44kV rms(peak)

CABLE RATING AC TEST VOLTAGE for MAINTENANCE TESTING	
5 kV	7kV rms(peak)
8 kV	10kV rms(peak)
15 kV	16kV rms(peak)
25 kV	23kV rms(peak)
35 kV	33kV rms(peak)

3.17.1.2 Low Voltage Cables, 600-Volt

Perform tests after installation of cable, splices and terminations and before terminating to equipment or splicing to existing circuits.

a. Visual and Mechanical Inspection

(1) Inspect exposed cable sections for physical damage.

(2) Verify that cable is supplied and connected in accordance with contract plans and specifications.

(3) Verify tightness of accessible bolted electrical connections.

(4) Inspect compression-applied connectors for correct cable match and

indentation.

(5) Visually inspect jacket and insulation condition.

(6) Inspect for proper phase identification and arrangement.

b. Electrical Tests

(1) Perform insulation resistance tests on wiring No. 6 AWG and larger diameter using instrument which applies voltage of approximately 1000 volts dc for one minute.

(2) Perform continuity tests to insure correct cable connection.

3.17.1.3 Grounding System

a. Visual and mechanical inspection

Inspect ground system for compliance with contract plans and specifications.

b. Electrical tests

Perform ground-impedance measurements utilizing the fall-of-potential method in accordance with IEEE 81. On systems consisting of interconnected ground rods, perform tests after interconnections are complete. On systems consisting of a single ground rod perform tests before any wire is connected. Take measurements in normally dry weather, not less than 48 hours after rainfall. Use a portable ground resistance tester in accordance with manufacturer's instructions to test each ground or group of grounds. The instrument must be equipped with a meter reading directly in ohms or fractions thereof to indicate the ground value of the ground rod or grounding systems under test. Provide site diagram indicating location of test probes with associated distances, and provide a plot of resistance vs. distance.

3.17.2 Follow-Up Verification

Upon completion of acceptance checks and tests, show by demonstration in service that circuits and devices are in good operating condition and properly performing the intended function. As an exception to requirements stated elsewhere in the contract, the Contracting Officer must be given 5 working days advance notice of the dates and times of checking and testing.

.... -- End of Section --

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 82 00

TELECOMMUNICATIONS OUTSIDE PLANT (OSP)
08/22

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM B1	(2013) Standard Specification for Hard-Drawn Copper Wire
ASTM B8	(2011; R 2017) Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft
ASTM D709	(2017) Standard Specification for Laminated Thermosetting Materials
ASTM D1557	(2012; E 2015) Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft3) (2700 kN-m/m3)

INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS (IEEE)

IEEE 100	(2000; Archived) The Authoritative Dictionary of IEEE Standards Terms
IEEE C2	(2023) National Electrical Safety Code

INSULATED CABLE ENGINEERS ASSOCIATION (ICEA)

ICEA S-87-640	(2016) Optical Fiber Outside Plant Communications Cable; 4th Edition
ICEA S-98-688	(2012) Broadband Twisted Pair Telecommunication Cable, Aircore, Polyolefin Insulated, Copper Conductors Technical Requirements
ICEA S-99-689	(2012) Broadband Twisted Pair Telecommunication Cable Filled, Polyolefin Insulated, Copper Conductors Technical Requirements

NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION (NEMA)

ANSI C62.61	(1993) American National Standard for Gas Tube Surge Arresters on Wire Line Telephone Circuits

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 70	(2026; TIA 26-1; ERTA 26-1; TIA 26-2; TIA 26-3; TIA 26-4; TIA 26-5; TIA 26-6; TIA 26-7; ERTA 26-2; ERTA 26-3) National Electrical Code

TELECOMMUNICATIONS INDUSTRY ASSOCIATION (TIA)

TIA-455-78-B	(2020c) FOTP-78 Optical Fibres - Part 1-40: Measurement Methods and Test Procedures - Attenuation
TIA-455-107	(1999a) FOTP-107 Determination of Component Reflectance or Link/System Return Loss using a Loss Test Set
TIA-472D000	(2007b) Fiber Optic Communications Cable for Outside Plant Use
TIA-492E000	(1996; R 2002) Sectional Specification for Class IVd Nonzero-Dispersion Single-Mode Optical Fibers for the 1550 nm Window
TIA-526-7	(2015a) OFSTP-7 Measurement of Optical Power Loss of Installed Single-Mode Fiber Cable Plant
TIA-526-14	(2015c) OFSTP-14A Optical Power Loss Measurements of Installed Multimode Fiber Cable Plant
TIA-568.1	(2020e) Commercial Building Telecommunications Infrastructure Standard
TIA-568.2	(2018d) Balanced Twisted-Pair Telecommunications Cabling and Components Standards
TIA-568.3	(2016d; Add 1 2019) Optical Fiber Cabling Components Standard
TIA-569	(2019e) Telecommunications Pathways and Spaces
TIA-590	(1997a) Standard for Physical Location and Protection of Below Ground Fiber Optic Cable Plant
TIA-606	(2021d) Administration Standard for Telecommunications Infrastructure
TIA-607	(2019d) Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises
TIA-758	(2012b) Customer-Owned Outside Plant Telecommunications Infrastructure Standard

TIA/EIA-455	(1998b) Standard Test Procedure for Fiber Optic Fibers, Cables, Transducers, Sensors, Connecting and Terminating Devices, and Other Fiber Optic Components
TIA/EIA-455-204	(2000) Standard for Measurement of Bandwidth on Multimode Fiber
TIA/EIA-598	(2014D; Add 2 2018) Optical Fiber Cable Color Coding

U.S. DEPARTMENT OF AGRICULTURE (USDA)

RUS 1755	Telecommunications Standards and Specifications for Materials, Equipment and Construction
RUS Bull 345-65	(1985) Shield Bonding Connectors (PE-65)
RUS Bull 345-72	(1985) Filled Splice Closures (PE-74)
RUS Bull 345-83	(1979; Rev Oct 1982) Gas Tube Surge Arrestors (PE-80)
RUS Bull 1751F-630	(1996) Design of Aerial Plant
RUS Bull 1751F-643	(2002) Underground Plant Design
RUS Bull 1751F-815	(1979) Electrical Protection of Outside Plant
RUS Bull 1753F-201	(1997) Acceptance Tests of Telecommunications Plant (PC-4)
RUS Bull 1753F-401	(1995) Splicing Copper and Fiber Optic Cables (PC-2)

UL SOLUTIONS (UL)

UL 83	(2017; Reprint Mar 2020) UL Standard for Safety Thermoplastic-Insulated Wires and Cables
UL 497	(2001; Reprint Jul 2013) Protectors for Paired Conductor Communication Circuits
UL 510	(2020; Dec 2022) UL Standard for Safety Polyvinyl Chloride, Polyethylene and Rubber Insulating Tape

1.2 RELATED REQUIREMENTS

Section 27 10 00, BUILDING TELECOMMUNICATIONS CABLING SYSTEM andSection 33 71 02, UNDERGROUND ELECTRICAL DISTRIBUTION apply to this section with additions and modifications specified herein.

1.3 DEFINITIONS

Unless otherwise specified or indicated, electrical and electronics terms

used in this specification must be as defined in TIA-568.1, TIA-568.2, TIA-568.3, TIA-569, TIA-606, and IEEE 100 and herein.

1.3.1 Campus Distributor (CD)

A distributor from which the campus backbone cabling emanates. (International expression for main cross-connect - (MC).)

1.3.2 Entrance Facility (EF) (Telecommunications)

An entrance to the building for both private and public network service cables (including antennae) including the entrance point at the building wall and continuing to the entrance room or space.

1.3.3 Entrance Room (ER) (Telecommunications)

A centralized space for telecommunications equipment that serves the occupants of a building. Equipment housed therein is considered distinct from a telecommunications room because of the nature of its complexity.

1.3.4 Building Distributor (BD)

A distributor in which the building backbone cables terminate and at which connections to the campus backbone cables may be made. (International expression for intermediate cross-connect - (IC).)

1.3.5 Pathway

A physical infrastructure utilized for the placement and routing of telecommunications cable.

1.4 SYSTEM DESCRIPTION

The telecommunications outside plant consists of cable, conduit, manholes, poles, etc. required to provide signal paths from the closest point of presence to the new facility, including free standing frames or backboards, interconnecting hardware, terminating cables, lightning and surge protection modules at the entrance facility. The work consists of providing, testing and making operational cabling, interconnecting hardware and lightning and surge protection necessary to form a complete outside plant telecommunications system for continuous use. The telecommunications contractor must coordinate with the TSD (Base Telephone) concerning layout and configuration of the EF telecommunications and OSP. The telecommunications contractor may be required to coordinate work effort for access to the EF telecommunications and OSP with TSD (Base Telephone).

1.5 SUBMITTALS

Government approval is required for submittals with a "G" or "S" classification. Submittals not having a "G" or "S" classification are for Contractor Quality Control approval. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Telecommunications Outside Plant; G

Telecommunications Entrance Facility Drawings; G

In addition to Section 01 33 00 SUBMITTAL PROCEDURES, provide shop drawings in accordance with paragraph SHOP DRAWINGS.

SD-03 Product Data

Wire and Cable; G

Cable Splices, and Connectors; G

Closures; G

Building Protector Assemblies; G

Protector Modules; G

Submittals must include the manufacturer's name, trade name, place of manufacture, and catalog model or number. Submittals must also include applicable federal, military, industry, and technical society publication references. Should manufacturer's data require supplemental information for clarification, the supplemental information must be submitted as specified in paragraph REGULATORY REQUIREMENTS and as required for certificates in Section 01 33 00 SUBMITTAL PROCEDURES.

SD-06 Test Reports

Pre-installation Tests; G

Acceptance Tests; G

Outside Plant Test Plan; G

SD-07 Certificates

Telecommunications Contractor Qualifications; G

Key Personnel Qualifications; G

Minimum Manufacturer's Qualifications; G

SD-08 Manufacturer's Instructions

Building Protector Assembly Installation; G

Cable Tensions; G

Fiber Optic Splices; G

Submit instructions prior to installation.

SD-09 Manufacturer's Field Reports

Factory Reel Test Data; G

SD-10 Operation and Maintenance Data

Telecommunications Outside Plant (OSP), Data Package 5; G

Commercial off-the-shelf manuals (TIA-758) must be provided for operation, installation, configuration, and maintenance of products provided as a part of the telecommunications outside plant (OSP). Submit operations and maintenance data in accordance with Section 01 78 23, OPERATION AND MAINTENANCE DATA and as specified herein not later than 2 months prior to the date of beneficial occupancy. In addition to requirements of Data package 5, include the requirements of paragraphs TELECOMMUNICATIONS OUTSIDE PLANT SHOP DRAWINGS and TELECOMMUNICATIONS ENTRANCE FACILITY DRAWINGS.

SD-11 Closeout Submittals

Record Documentation; G

In addition to other requirements, provide in accordance with paragraph RECORD DOCUMENTATION.

1.6 QUALITY ASSURANCE

1.6.1 Shop Drawings

Include wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, control panels, accessories, piping, ductwork, and other items that must be shown to ensure a coordinated installation. Wiring diagrams must identify circuit terminals and indicate the internal wiring for each item of equipment and the interconnection between each item of equipment. Drawings must indicate adequate clearance for operation, maintenance, and replacement of operating equipment devices. Submittals must include the nameplate data, size, and capacity. Submittals must also include applicable federal, military, industry, and technical society publication references.

1.6.1.1 Telecommunications Outside Plant Shop Drawings

Provide Outside Plant Design in accordance with TIA-758, RUS Bull 1751F-630 for aerial system design, and RUS Bull 1751F-643 for underground system design. Provide T0 shop drawings that show the physical and logical connections from the perspective of an entire campus, such as actual building locations, exterior pathways and campus backbone cabling on plan view drawings, major system nodes, and related connections on the logical system drawings in accordance with TIA-606. Drawings must include wiring and schematic diagrams for fiber optic and copper cabling and splices, copper conductor gauge and pair count, fiber pair count and type, pathway duct and innerduct arrangement, associated construction materials, and any details required to demonstrate that cable system has been coordinated and will properly support the switching and transmission system identified in specification and drawings. Provide Registered Communications Distribution Designer (RCDD) approved drawings of the telecommunications outside plant. The telecommunications outside plant (OSP) shop drawings must be included in the operation and maintenance manuals.

1.6.1.2 Telecommunications Entrance Facility Drawings

Provide T3 drawings for EF Telecommunications as specified in the paragraph TELECOMMUNICATIONS SPACE DRAWINGS of Section 27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEMS. The telecommunications entrance

facility shop drawings must be included in the operation and maintenance manuals.

1.6.2 Telecommunications Qualifications

Work under this section must be performed by and the equipment must be provided by the approved telecommunications contractor and key personnel. Qualifications must be provided for: the telecommunications system contractor, the telecommunications system installer, the supervisor (if different from the installer), and the cable splicing and terminating personnel. A minimum of 30 days prior to installation, submit documentation of the experience of the telecommunications contractor and of the key personnel.

1.6.2.1 Telecommunications Contractor Qualifications

The telecommunications contractor must be a firm which is regularly and professionally engaged in the business of the applications, installation, and testing of the specified telecommunications systems and equipment. The telecommunications contractor must demonstrate experience in providing successful telecommunications systems that include outside plant and broadband cabling within the past 3 years. Submit documentation for a minimum of three and a maximum of five successful telecommunication system installations for the telecommunications contractor. Each of the key personnel must demonstrate experience in providing successful telecommunications systems in accordance with TIA-758 within the past 3 years.

1.6.2.2 Key Personnel Qualifications

Provide key personnel who are regularly and professionally engaged in the business of the application, installation and testing of the specified telecommunications systems and equipment. There may be one key person or more key persons proposed for this solicitation depending upon how many of the key roles each has successfully provided. Each of the key personnel must demonstrate experience in providing successful telecommunications systems within the past 3 years.

Cable splicing and terminating personnel assigned to the installation of this system or any of its components must have training in the proper techniques and have a minimum of 3 years experience in splicing and terminating the specified cables. Modular splices must be performed by factory certified personnel or under direct supervision of factory trained personnel for products used.

Supervisors and installers assigned to the installation of this system or any of its components must have factory or factory approved certification from each equipment manufacturer indicating that they are qualified to install and test the provided products.

Submit documentation for a minimum of three and a maximum of five successful telecommunication system installations for each of the key personnel. Documentation for each key person must include at least two successful system installations provided that are equivalent in system size and in construction complexity to the telecommunications system proposed for this solicitation. Include specific experience in installing and testing telecommunications outside plant systems, including broadband cabling, and provide the names and locations of at least two project installations successfully completed using optical fiber and copper

telecommunications cabling systems. All of the existing telecommunications system installations offered by the key persons as successful experience must have been in successful full-time service for at least 18 months prior to the issuance date for this solicitation. Provide the name and role of the key person, the title, location, and completed installation date of the referenced project, the referenced project owner point of contact information including name, organization, title, and telephone number, and generally, the referenced project description including system size and construction complexity.

Indicate that all key persons are currently employed by the telecommunications contractor, or have a commitment to the telecommunications contractor to work on this project. All key persons must be employed by the telecommunications contractor at the date of issuance of this solicitation, or if not, have a commitment to the telecommunications contractor to work on this project by the date that the bid was due to the Contracting Officer.

Note that only the key personnel approved by the Contracting Officer in the successful proposal must do work on this solicitation's telecommunications system. Key personnel must function in the same roles in this contract, as they functioned in the offered successful experience. Any substitutions for the telecommunications contractor's key personnel requires approval from The Contracting Officer.

1.6.2.3 Minimum Manufacturer's Qualifications

Cabling, equipment and hardware manufacturers must have a minimum of 3 years experience in the manufacturing, assembly, and factory testing of components which comply with, TIA-568.1, TIA-568.2 and TIA-568.3. In addition, cabling manufacturers must have a minimum of 3 years experience in the manufacturing and factory testing of cabling which comply with ICEA S-87-640, ICEA S-98-688, and ICEA S-99-689.

1.6.3 Outside Plant Test Plan

Prepare and provide a complete and detailed test plan for field tests of the outside plant including a complete list of test equipment for the copper conductor and optical fiber cables, components, and accessories for approval by the Contracting Officer. Include a cut-over plan with procedures and schedules for relocation of facility station numbers without interrupting service to any active location. Submit the plan at least 30 days prior to tests for Contracting Officer approval. Provide outside plant testing and performance measurement criteria in accordance with TIA-568.1 and RUS Bull 1753F-201. Include procedures for certification, validation, and testing that includes fiber optic link performance criteria.

1.6.4 Standard Products

Provide materials and equipment that are standard products of manufacturers regularly engaged in the production of such products which are of equal material, design and workmanship and must be the manufacturer's latest standard design that has been in satisfactory commercial or industrial use for at least 2 years prior to bid opening. The 2-year period must include applications of equipment and materials under similar circumstances and of similar size. The product must have been on sale on the commercial market through advertisements, manufacturers' catalogs, or brochures during the 2-year period. Products

supplied must be specifically designed and manufactured for use with outside plant telecommunications systems. Where two or more items of the same class of equipment are required, these items must be products of a single manufacturer; however, the component parts of the item need not be the products of the same manufacturer unless stated in this section. All products must be approved by BCO/TSD via CO.

1.6.4.1 Alternative Qualifications

Products having less than a 2-year field service record will be acceptable if a certified record of satisfactory field operation for not less than 6000 hours, exclusive of the manufacturers' factory or laboratory tests, is provided.

1.6.4.2 Material and Equipment Manufacturing Date

Products manufactured more than 3 years prior to date of delivery to site must not be used, unless specified otherwise.

1.6.5 Regulatory Requirements

In each of the publications referred to herein, consider the advisory provisions to be mandatory, as though the word, "must" had been substituted for "should" wherever it appears. Interpret references in these publications to the "authority having jurisdiction," or words of similar meaning, to mean BCO/TSD via the Contracting Officer. Equipment, materials, installation, and workmanship must be in accordance with the mandatory and advisory provisions of NFPA 70 unless more stringent requirements are specified or indicated.

1.6.5.1 Independent Testing Organization Certificate

In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. The certificate must state that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.7 DELIVERY, STORAGE, AND HANDLING

Ship cable on reels in 500 feet length with a minimum overage of 10 percent. Radius of the reel drum must not be smaller than the minimum bend radius of the cable. Wind cable on the reel so that unwinding can be done without kinking the cable. Two meters of cable at both ends of the cable must be accessible for testing. Attach permanent label on each reel showing length, cable identification number, cable size, cable type, and date of manufacture. Provide water resistant label and the indelible writing on the labels. Apply end seals to each end of the cables to prevent moisture from entering the cable. Reels with cable must be suitable for outside storage conditions when temperature ranges from minus 40 degrees C to plus 65 degrees C, with relative humidity from 0 to 100 percent. Equipment, other than cable, delivered and placed in storage must be stored with protection from weather, humidity and temperature variation, dirt and dust, or other contaminants in accordance with manufacturer's requirements.

1.8 MAINTENANCE

1.8.1 Record Documentation

Provide the activity responsible for telecommunications system maintenance and administration a single complete and accurate set of record documentation for the entire telecommunications system with respect to this project.

Provide record documentation as specified in Section 27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEM.

1.9 WARRANTY

The equipment items must be supported by service organizations which are reasonably convenient to the equipment installation in order to render satisfactory service to the equipment on a regular and emergency basis during the warranty period of the contract.

PART 2 PRODUCTS

2.1 MATERIALS AND EQUIPMENT

Products supplied must be specifically designed and manufactured for use with outside plant telecommunications systems and must be approved by BCO/TSD.

2.2 TELECOMMUNICATIONS ENTRANCE FACILITY

2.2.1 Building Protector Assemblies

Provide self-contained 5 pin unit supplied with a field cable stub factory connected to protector socket blocks to terminate and accept protector modules for pairs of outside cable. Building protector assembly must have interconnecting hardware for connection to interior cabling at full capacity. Provide manufacturers instructions for building protector assembly installation. Provide copper cable interconnecting hardware as specified in Section 27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEM. Coordinate multiple protectors with BCO.

2.2.2 Protector Modules

Provide in accordance with UL 497 solid state type 5 pin rated for the application. Provide protection modules in accordance with RUS Bull 345-83 and must be heavy duty, A>10kA, B>400, C>65A where A is the maximum single impulse discharge current, B is the impulse life and C is the AC discharge current in accordance with ANSI C62.61. The modules must shunt high voltage to ground, fail short, and be equipped with an external spark gap and heat coils in accordance with UL 497. Provide the number of surge protection modules equal to the number of pairs of exterior cable of the building protector assembly.

2.2.3 Fiber Optic Terminations

Provide fiber optic cable terminations as specified in 27 10 00 BUILDING TELECOMMUNICATIONS CABLING SYSTEM.

2.3 CLOSURES

2.3.1 Copper Conductor Closures

2.3.1.1 Underground Cable Closures

a. Aboveground: Provide aboveground closures constructed of not less than 14 gauge steel and acceptable for pole mounting in accordance with RUS 1755.910. Closures must be sized and contain a marker as indicated. Covers must be secured to prevent unauthorized entry.

b. Direct burial: Provide buried closure suitable for enclosing a straight, butt, and branch splice in a container into which can be poured an encapsulating compound. Closure must have adequate strength to protect the splice and maintain cable shield electrical continuity in the buried environment. Encapsulating compound must be reenterable and must not alter the chemical stability of the closure. Provide filled splice cases in accordance with RUS Bull 345-72. Note: Camp Lejeune does not use buried closures.

c. In vault or manhole: Provide underground closure suitable to house a foldback splice in a protective housing into which can be poured an encapsulating compound. Closure must be of suitable thermoplastic, thermoset, or stainless steel material supplying structural strength necessary to pass the mechanical and electrical requirements in a vault or manhole environment. Encapsulating compound must be reenterable and must not alter the chemical stability of the closure. Provide filled splice cases in accordance with RUS Bull 345-72. Closure must only be flash tested and encapulate provided.

2.3.2 Fiber Optic Closures

2.3.2.1 Aerial

Provide aerial closure that is free breathing and suitable for housing splice organizer of non -pressurized cables. Closure must be constructed from heavy PVC with ultraviolet resistance. Note: Camp Lejeune does not have Aerial.

2.3.2.2 Direct Burial

Provide buried closure suitable to house splice organizer in protective housing into which can be poured an encapsulating compound. Closure must have adequate strength to protect the splice and maintain cable shield electrical continuity, when metallic, in buried environment. Encapsulating compound must be reenterable and must not alter chemical stability of the closure. Note: Camp Lejeune does not use buried closures.

2.3.2.3 In Vault or Manhole

Provide underground closure suitable to house splice organizer in a protective housing into which can be poured an encapsulating compound. Closure must be of thermoplastic, thermoset, or stainless steel material supplying structural strength necessary to pass the mechanical and electrical requirements in a vault or manhole environment. Encapsulating compound must be reenterable and must not alter the chemical stability of the closure. Closure should only be flash tested and encapsulate provided.

2.4 CABLE SPLICES, AND CONNECTORS

2.4.1 Copper Cable Splices

Provide multipair, foldback splices of a moisture resistant, two-wire insulation displacement connector held rigidly in place to assure maximum continuity in accordance with RUS Bull 1753F-401. Cables greater than 25 pairs must be spliced using multipair splicing connectors, which accommodate 25 pairs of conductors at a time. Provide correct connector size to accommodate the cable gauge of the supplied cable.

2.4.2 Copper Cable Splice Connector

Provide splice connectors with a polycarbonate body and cap and a tin-plated brass contact element. Connector must accommodate 22 to 26 AWG solid wire with a maximum insulation diameter of 0.065 inch. Fill connector with sealant grease to make a moisture resistant connection, in accordance with RUS Bull 1753F-401.

2.4.3 Fiber Optic Cable Splices

Provide fiber optic cable splices and splicing materials for fusion methods at locations shown on the construction drawings. The splice insertion loss must be 0.3 dB maximum when measured in accordance with TIA-455-78-B using an Optical Time Domain Reflectometer (OTDR). Splices must be designed for a return loss of 40.0 db max for single mode fiber when tested in accordance with TIA-455-107. Physically protect each fiber optic splice by a splice kit specially designed for the splice.

2.4.4 Shield Connectors

Provide connectors with a stable, low-impedance electrical connection between the cable shield and the bonding conductor in accordance with RUS Bull 345-65.

2.5 CONDUIT

Provide conduit as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION, BICSI OSP Design, and guidance from BCO/TSD via Contracting Officer.

2.6 PLASTIC INSULATING TAPE

UL 510. Tape must be premium quality, heavy-duty, weather resistant.

2.7 WIRE AND CABLE

2.7.1 Copper Conductor Cable

Solid copper conductors, covered with an extruded solid insulating compound. Insulated conductors must be twisted into pairs which are then stranded or oscillated to form a cylindrical core. For special high frequency applications, the cable core must be separated into compartments. Cable must be completed by the application of a suitable core wrapping material, a corrugated copper or plastic coated aluminum shield, and an overall extruded jacket. Telecommunications contractor must verify distances between splice points prior to ordering cable in specific cut lengths. Gauge of conductor must determine the range of numbers of pairs specified; 19 gauge (6 to 400 pairs), 22 gauge (6 to 1200

pairs), 24 gauge (6 to 2100 pairs), and 26 gauge (6 to 3000 pairs). PE-39 must be used whenever available. PE-89 is only authorized when PE-39 is not available. Copper conductor must conform to the following:

2.7.1.1 Underground

Provide filled cable meeting the requirements of ICEA S-99-689 and RUS 1755.390 (type PE-39/89). Provide enough slack for splicing.

2.7.1.2 Screen

Provide screen-compartmental core cable filled cable meeting the requirements of ICEA S-99-689 and RUS 1755.390.

2.7.2 Fiber Optic Cable

Provide single-mode, 8/125-um, 0.10 aperture 1550 nm fiber optic cable in accordance with TIA-492E000, TIA-472D000, and ICEA S-87-640 including any special requirements made necessary by a specialized design. Provide 12 optical fibers as indicated. Fiber optic cable must be shielded and specifically designed for outside use with loose buffer construction. Provide fiber optic color code in accordance with TIA/EIA-598

2.7.2.1 Strength Members

Provide central, non-metallic strength members with sufficient tensile strength for installation and residual rated loads to meet the applicable performance requirements in accordance with ICEA S-87-640. The strength member is included to serve as a cable core foundation to reduce strain on the fibers, and must not serve as a pulling strength member.

2.7.2.2 Shielding or Other Metallic Covering

Provide copper, copper alloy or copper and steel laminate, single tape covering or shield in accordance with ICEA S-87-640. Over all shield is for locating.

2.7.2.3 Performance Requirements

Provide fiber optic cable with optical and mechanical performance requirements in accordance with ICEA S-87-640.

2.7.3 Grounding and Bonding Conductors

Provide grounding and bonding conductors in accordance with RUS 1755.200, TIA-607, IEEE C2, and NFPA 70. Solid bare copper wire meeting the requirements of ASTM B1 for sizes No. 8 AWG and smaller and stranded bare copper wire meeting the requirements of ASTM B8, for sizes No. 6 AWG and larger. Insulated conductors must have 600-volt, Type TW insulation meeting the requirements of UL 83.

2.8 CABLE TAGS IN MANHOLES, HANDHOLES, AND VAULTS

Provide tags for each telecommunications cable or wire located in manholes, handholes, and vaults. Cable tags must be stainless steel and labeled in accordance with TIA-606. Handwritten labeling is unacceptable. Coordinate cable tag information with TSD.

2.8.1 Stainless Steel

Provide stainless steel, cable tags 1 5/8 inches in diameter 1/16 inch thick minimum, and circular in shape. Tags must be die stamped with numbers, letters, and symbols not less than 0.25 inch high and approximately 0.015 inch deep in normal block style.

2.9 BURIED WARNING AND IDENTIFICATION TAPE

Provide fiber optic media marking and protection in accordance with TIA-590. Provide color, type and depth of tape as specified in paragraph BURIED WARNING AND IDENTIFICATION TAPE in Section 31 00 00, EARTHWORK.

2.10 GROUNDING BRAID

Provide grounding braid that provides low electrical impedance connections for dependable shield bonding in accordance with RUS 1755.200. Braid must be made from flat tin-plated copper.

2.11 MANUFACTURER'S NAMEPLATE

Each item of equipment must have a nameplate bearing the manufacturer's name, address, model number, and serial number securely affixed in a conspicuous place; the nameplate of the distributing agent will not be acceptable.

2.12 FIELD FABRICATED NAMEPLATES

Provide laminated plastic nameplates in accordance with ASTM D709 for each patch panel, protector assembly, rack, cabinet and other equipment or as indicated on the drawings. Each nameplate inscription must identify the function and, when applicable, the position. Nameplates must be melamine plastic, 0.125 inch thick, white with black center core. Surface must be matte finish. Corners must be square. Accurately align lettering and engrave into the core. Minimum size of nameplates must be one by 2.5 inches. Lettering must be a minimum of 0.25 inch high normal block style.

2.13 TESTS, INSPECTIONS, AND VERIFICATIONS

2.13.1 Factory Reel Test Data

Test 100 percent OTDR test of FO media at the factory in accordance with TIA-568.1 and TIA-568.3. Use TIA-526-7 for single mode fiber and TIA-526-14 Method B for multi mode fiber measurements. Calibrate OTDR to show anomalies of 0.2 dB minimum. Enhanced performance filled OSP copper cables, referred to as Broadband Outside Plant (BBOSP), must meet the requirements of ICEA S-99-689. Enhanced performance air core OSP copper cables must meet the requirements of ICEA S-98-688. Submit test reports, including manufacture date for each cable reel and receive approval before delivery of cable to the project site.

PART 3 EXECUTION

3.1 INSTALLATION

Install all system components and appurtenances in accordance with manufacturer's instructions IEEE C2, NFPA 70, and as indicated. Provide all necessary interconnections, services, and adjustments required for a complete and operable telecommunications system.

3.1.1 Contractor Damage

Promptly repair indicated utility lines or systems damaged during site preparation and construction. Damages to lines or systems not indicated, which are caused by Contractor operations, must be treated as "Changes" under the terms of the Contract Clauses. When Contractor is advised in writing of the location of a nonindicated line or system, such notice must provide that portion of the line or system with "indicated" status in determining liability for damages. In every event, immediately notify the BCO/TSD vis Contracting Officer of damage.

3.1.2 Cable Inspection and Repair

Handle cable and wire provided in the construction of this project with care. Inspect cable reels for cuts, nicks or other damage. Damaged cable must be replaced or repaired to the satisfaction of the Contracting Officer / BCO/TSD. Reel wraps must remain intact on the reel until the cable is ready for placement.

3.1.3 Cable Protection

Provide direct burial cable protection in accordance with NFPA 70 and as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION. Galvanized conduits which penetrate concrete (slabs, pavement, and walls) must be PVC coated and must extend from the first coupling or fitting outside either side of the concrete minimum of 6 inches per 12 inches burial depth beyond the edge of the surface where cable protection is required; all conduits must be sealed on each end. Where additional protection is required, cable may be placed in galvanized iron pipe (GIP) sized on a maximum fill of 40 percent of cross-sectional area, or in concrete encased 4 inches PVC pipe. Conduit may be installed by jacking or trenching. Trenches must be backfilled with earth and mechanically tamped at 6 inches lift so that the earth is restored to the same density, grade and vegetation as adjacent undisturbed material.

3.1.3.1 Cable End Caps

Cable ends must be sealed at all times with coated heat shrinkable end caps. Cables ends must be sealed when the cable is delivered to the job site, while the cable is stored and during installation of the cable. The caps must remain in place until the cable is spliced or terminated. Sealing compounds and tape are not acceptable substitutes for heat shrinkable end caps. Cable which is not sealed in the specified manner at all times will be rejected.

3.1.4 Underground Duct

Provide underground duct and connections to existing manholes, handholes, existing ducts as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION with any additional requirements as specified herein. Ducts must be min 103mm 4 inch and 4way.

3.1.5 Reconditioning of Surfaces

Provide reconditioning of surfaces as specified in Section 33 71 02 UNDERGROUND ELECTRICAL DISTRIBUTION.

3.1.6 Penetrations

Caulk and seal cable access penetrations in walls, ceilings and other parts of the building. Seal openings around electrical penetrations through fire resistance-rated wall, partitions, floors, or ceilings in accordance with Section 07 84 00 FIRESTOPPING.

3.1.7 Cable Pulling

Test duct lines with BCO/TSD aluminum test mandrel, after contractor removal of foreign material and before the pulling of cables. Avoid damage to cables in setting up pulling apparatus or in placing tools or hardware. Do not step on cables when entering or leaving the manhole. Do not place cables in ducts other than those shown without prior written approval of the Contracting Officer / BCO/TSD. Roll cable reels in the direction indicated by the arrows painted on the reel flanges. Set up cable reels on the same side of the manhole as the conduit section in which the cable is to be placed. Level the reel and bring into proper alignment with the conduit section so that the cable pays off from the top of the reel in a long smooth bend into the duct without twisting. Under no circumstances must the cable be paid off from the bottom of a reel. Check the equipment set up prior to beginning the cable pulling to avoid an interruption once pulling has started. Use a cable feeder guide of suitable dimensions between cable reel and face of duct to protect cable and guide cable into the duct as it is paid off the reel. As cable is paid off the reel, lubricate and inspect cable for sheath defects. When defects are noticed, stop pulling operations and notify the Contracting Officer to determine required corrective action. Cable pulling must also be stopped when reel binds or does not pay off freely. Rectify cause of binding before resuming pulling operations. Provide cable lubricants recommended by the cable manufacturer. Avoid bends in cables of small radii and twists that might cause damage. Do not bend cable and wire in a radius less than 10 times the outside diameter of the cable or wire. Mandrel should glide through and be hand pulled (BICSI).

3.1.7.1 Cable Tensions

Obtain from the cable manufacturer and provide to the Contracting Officer, the maximum allowable pulling tension. This tension must not be exceeded.

3.1.7.2 Pulling Eyes

Equip cables 1.25 inches in diameter and larger with cable manufacturer's factory installed pulling-in eyes. Provide cables with diameter smaller than 1.25 inches with heat shrinkable type end caps or seals on cable ends when using cable pulling grips. Rings to prevent grip from slipping must not be beaten into the cable sheath. Use a swivel of 3/4 inch links between pulling-in eyes or grips and pulling strand.

3.1.7.3 Installation of Cables in Manholes, Handholes, and Vaults

Do not install cables utilizing the shortest route, but route along those walls providing the longest route and the maximum spare cable lengths. Form cables to closely parallel walls, not to interfere with duct entrances, and support cables on brackets and cable insulators at a maximum of 4 feet. In existing manholes, handholes, and vaults where new ducts are to be terminated, or where new cables are to be installed, modify the existing installation of cables, cable supports, and grounding as required with cables arranged and supported as specified for new

cables. Identify each cable with corrosion-resistant embossed metal tags. Provide adequate slack for splicing operations.

3.1.8 Cable Splicing

3.1.8.1 Copper Conductor Splices

Perform splicing in accordance with requirements of RUS Bull 1753F-401 except that direct buried splices and twisted and soldered splices are not allowed. Exception does not apply for pairs assigned for carrier or CATV application.

3.1.8.2 Fiber Optic Splices

Fiber optic splicing must be in accordance with manufacturer's recommendation and must exhibit an insertion loss not greater than 0.2 dB for fusion splices.

3.1.9 Surge Protection

All cables and conductors, except fiber optic cable, which serve as communication lines through off-premise lines, must have surge protection installed at each end which meet the requirements of RUS Bull 1751F-815.

3.1.10 Grounding

Provide grounding and bonding in accordance with RUS 1755.200, TIA-607, IEEE C2, and NFPA 70. Ground exposed noncurrent carrying metallic parts of telephone equipment, cable sheaths, cable splices, and terminals.

3.1.10.1 Telecommunications Master Ground Bar (TMGB)

The TMGB is the hub of the basic telecommunications grounding system providing a common point of connection for ground from outside cable, CD, and equipment. Establish a TMGB for connection point for cable stub shields to connector blocks and CD protector assemblies as specified in Section 26 20 00 INTERIOR DISTRIBUTION SYSTEM.

3.1.10.2 Incoming Cable Shields

Shields must not be bonded across the splice to the cable stubs. Ground shields of incoming cables in the EF Telecommunications to the TMGB.

3.1.10.3 Campus Distributor Grounding

a. Protection assemblies: Mount CD protector assemblies directly on the telecommunications backboard. Connect assemblies mounted on each vertical frame with No. 6 AWG copper conductor to provide a low resistance path to TMGB.

b. TMGB connection: Connect TMGB to TGB with copper conductor with a total resistance of less than 0.01 ohms.

3.1.11 Cut-Over

All necessary transfers and cut-overs, must be coordinated with BCO/TSD as some may/may not be accomplished by the telecommunications contractor.

3.2 LABELING

3.2.1 Labels

Provide labeling for new cabling and termination hardware located within the facility in accordance with TIA-606. Handwritten labeling is unacceptable. Stenciled lettering for cable and termination hardware must be provided using laser printer.

3.2.2 Cable Tag Installation

Install cable tags for each telecommunications cable or wire located in manholes, handholes, and vaults including each splice. Tag new wire and cable provided under this contract and existing wire and cable which are indicated to have splices and terminations provided by this contract. The labeling of telecommunications cable tag identifiers must be in accordance with TIA-606. Do not provide handwritten letters. Install cable tags so that they are clearly visible without disturbing any cabling or wiring in the manholes, handholes, and vaults.

3.2.3 Termination Hardware

Label patch panels, distribution panels, connector blocks and protection modules using color coded labels with identifiers in accordance with TIA-606.

3.3 FIELD FABRICATED NAMEPLATE MOUNTING

Provide number, location, and letter designation of nameplates as indicated. Fasten nameplates to the device with a minimum of two sheet-metal screws or two rivets.

3.4 FIELD QUALITY CONTROL

Provide the Contracting Officer 10 working days notice prior to each test. Provide labor, equipment, and incidentals required for testing. Correct defective material and workmanship disclosed as the results of the tests. Furnish a signed copy of the test results to the Contracting Officer within 3 working days after the tests for each segment of construction are completed. Perform testing as construction progresses and do not wait until all construction is complete before starting field tests.

3.4.1 Pre-Installation Tests

Perform the following tests on cable at the job site before it is removed from the cable reel. For cables with factory installed pulling eyes, these tests must be performed at the factory and certified test results must accompany the cable.

3.4.1.1 Cable Capacitance

Perform capacitance tests on at least 10 percent of the pairs within a cable to determine if cable capacitance is within the limits specified.

3.4.1.2 Loop Resistance

Perform DC-loop resistance on at least 10 percent of the pairs within a cable to determine if DC-loop resistance is within the manufacturer's

calculated resistance.

3.4.1.3 Pre-Installation Test Results

Provide results of pre-installation tests to the Contracting Officer at least 5 working days before installation is to start. Results must indicate reel number of the cable, manufacturer, size of cable, pairs tested, and recorded readings. When pre-installation tests indicate that cable does not meet specifications, remove cable from the job site.

3.4.2 Acceptance Tests

Perform acceptance testing in accordance with RUS Bull 1753F-201 and as further specified in this section. Provide personnel, equipment, instrumentation, and supplies necessary to perform required testing. Notification of any planned testing must be given to the Contracting Officer at least 14 days prior to any test unless specified otherwise. Testing must not proceed until after the Contractor has received written Contracting Officer's approval of the test plans as specified. Test plans must define the tests required to ensure that the system meets technical, operational, and performance specifications. The test plans must define milestones for the tests, equipment, personnel, facilities, and supplies required. The test plans must identify the capabilities and functions to be tested. Provide test reports in local provider format showing all field tests performed, upon completion and testing of the installed system, to the Contracting Officer /BCO /TSD. Measurements must be tabulated on a pair by pair or strand by strand basis.

3.4.2.1 Copper Conductor Cable

Perform the following acceptance tests in accordance with TIA-758:

a. Wire map (pin to pin continuity)

b. Continuity to remote end

c. Crossed pairs

d. Reversed pairs

e. Split pairs

f. Shorts between two or more conductors

3.4.2.2 Fiber Optic Cable

Test fiber optic cable in accordance with TIA/EIA-455 and as further specified in this section. Two optical tests must be performed on all optical fibers: Optical Time Domain Reflectometry (OTDR) Test, and Attenuation Test. In addition, a Bandwidth Test must be performed on all multimode optical fibers. These tests must be performed on the completed end-to-end spans which include the near-end pre-connectorized single fiber cable assembly, outside plant as specified, and the far-end pre-connectorized single fiber cable assembly.

a. OTDR Test: The OTDR test must be used to determine the adequacy of the cable installations by showing any irregularities, such as discontinuities, micro-bendings or improper splices for the cable span under test. Hard copy fiber signature records must be obtained from

the OTDR for each fiber in each span and must be included in the test results. The OTDR test must be measured in both directions. A reference length of fiber, 66 feet minimum, used as the delay line must be placed before the new end connector and after the far end patch panel connectors for inspection of connector signature. Conduct OTDR test and provide calculation or interpretation of results in accordance with TIA-526-7 for single-mode fiber and TIA-526-14 for multimode fiber. Splice losses must not exceed 0.3 db.

b. Attenuation Test: End-to-end attenuation measurements must be made on all fibers, in both directions, using a 1550 nanometer light source at one end and the optical power meter on the other end to verify that the cable system attenuation requirements are met in accordance with TIA-526-7 for single-mode fiber optic cables. The measurement method must be in accordance with TIA-455-78-B. Attenuation losses must not exceed 0.5 db/km at 1310 nm and 1550 nm for single-mode fiber. Attenuation losses must not exceed 5.0 db/km at 850 nm and 1.5 db/km at 1300 nm for multimode fiber.

c. Bandwidth Test: The end-to-end bandwidth of all multimode fiber span links must be measured by the frequency domain method. The bandwidth must be measured in both directions on all fibers. The bandwidth measurements must be in accordance with TIA/EIA-455-204.

3.4.3 Soil Density Tests

a. Determine soil-density relationships for compaction of backfill material in accordance with ASTM D1557, Method D.

-- End of Section --