Government Response to RFCs

9) Question: Attachment-2 Price Worksheet shows item 3.1.13 Shifting the Vessel but it is not included in the SOW. Can you provide clarification whether this work item is required?
Answer: This effort has been updated in the SOW attached.

---

10) Question: Remove existing and install new quantity (7 EA) item numbers 2, 3, 4, 5 attached to the thru hull fittings. Using drawing 124A-504 as guidance. The referenced drawing shows items 2, 3, 4, 5 with a total count of twenty-two (22). Is it possible that item #2 may have been mistaken as quantity 1 instead of 16?
Answer: Item#2 are ½ ball valves used throughout the boat for fresh water hook-up and flushing points. The DWG QTY:16 is correct for the boat, but not for this context of hull valve replacement.

Below are the hull valves to be removed and replaced:

- Raw water wash down hull valve: Item# 2 QTY:1
- Main Propulsion Diesel Engines: Item# 5 QTY: 2
- Generators: Item# 3 QTY: 2
- Educator/Monkey Heater Booster Pump: Item# 4 QTY: 1

---

11) Question: SOW States: Remove existing and install new hydraulic hose assemblies for the HPU, crane, and steering systems. Certification shall be documented on metal tags attached to each hose. Using drawing 31743-17500 and Table 6 as guidance. We are unable to locate Ref Drawing 31743-17500 in the drawing index. Can this be provided?
Answer: Drawing 31743-17500 is now available. Please see attachments.

---

12) Question: SOW States: Remove existing and install new Generator quantity (2 EA) in accordance with BOATALT 65DS/1C using drawings 5113813A, 5113814, and 5113815 as guidance. GFE indicates that only one generator is being provided. Can you confirm that contractor is to procure the second generator?
Answer: Two generators are listed in the SOW, IGE, and GFP attachment.