PERFORMANCE WORK STATEMENT/STATEMENT OF WORK

NCTS SICILY

EMERGENCY GENERATOR #5 OUTPUT CIRCUIT BREAKER Acquisition

1.0 **INTRODUCTION:** NCTS Sicily executes continuous operations to ensure access and superiority within the electromagnetic (EM) and cyberspace domains for U.S, NATO, and coalition forces operating in the U.S. European Command (EUCOM), U.S. Africa Command (AFRICOM), and U.S. Central Command (CENTCOM) areas of responsibility.

2.0 **BACKGROUND:** Commander, Navy Information Forces (COMNAVIFOR) has ultimate ownership of standalone non-structural mission support equipment, which can include generators; UPS Systems; heating, ventilation and air conditioning (HVAC) and other critical electrical and mechanical systems that support the COMNAVIFOR mission.

The services provided by the contractor are a requirement for continuous operation of the site providing backup power via emergency generator to NCTS Sicily mission.

3.0 SCOPE OF WORK:

3.1 This PWS defines the requirements for a contractor to provide a non-functional 2500-amp Eaton/Cutler Hammer 3-pole circuit breaker (CB) connected to Generator #5 at Naval Computer and Telecommunications Station (NCTS) Sicily, NAS II Sigonella and provide shipping to the location.

3.1.1 Performance Objectives:

3.1.1.1 Provide exact brand, Part and specification part

3.1.1.2 Provide Cost including shipping to the location.

3.1.2 The Contractor shall perform the following tasks:

3.1.2.1 Thoroughly inspect the new 2500-amp Eaton/Cutler Hammer circuit breaker before shipping it to the below mentioned location.

3.1.2.2 Provide the cost for shipping overseas as well as for NCTAMS LANT as well.

3.2 Location of Performance

3.2.1 The site address for shipping to US and Point of contact for the generator breaker listed below for CONUS location:
NCTAMS LANT,
1518 Piersey St,
BLDG MB-100,
Norfolk, VA-23511
Tione Faulcon
tione.a.faulcon.civ@us.navy.mil
757-400-9058

3.2.2 The site address for shipping thru MILAIR to Italy and Point of contact for the generator breaker is listed as followed for OCONUS location:

NCTS SICILY N68893
8849 AIR CARGO ROAD
BLDG LP-205
NORFOLK, VA 23511
Primary POC:
ENS Max Vargo
Email: nctsn43facilities_emergencypower@us.navy.mil
Tel: 011-39-095-86-2413
Cell: +1 (919) 302-9541
Secondary POC for Logistics:
LS1 Rio Wood
rio.a.wood.mil@us.navy.mil
COMM: 011-39-095-86-6237
DSN:314-624-6036

3.3 Proposed Period of Performance

3.3.1 The Period of Performance for this contract is:

3.3.1.1 Immediately after award.

3.4 Location Work Hours

3.4.1 The working hours is 0700 – 1600, Monday through Friday, except for federal holidays.

3.4.2 Additionally, the government may pause services at any site and during any time due to the unique mission requirements that may be presented at any of the sites.

3.5 Details of Required Services

3.5.1 Breaker Information:

Eaton Cutler-Hammer Magnum DS
MDSC253WEA Low Voltage Power CB
CAT# MDSC253WEA25MTCNAA6Y HNNAX

3.6 Government Furnished Material:

3.6.1 None

3.7 Contractor Furnished Material:

3.7.1 All labor, materials, tools, and equipment necessary to perform the required tasks.

3.7.2 All replacement parts required to repair the circuit breaker, anticipating all likely failure scenarios.

4.0 APPLICABLE DOCUMENTS

4.1 Instructions, regulations, and OEM manuals.

4.1.1 COMNAVIFOR 11311.1

5.0 Qualifications/Certifications

N/A

6.0 QUALITY CONTROL SURVEILLANCE PLAN (QASP)

6.1 Contractor Quality Control methods

6.1.1 The contractor will provide a written report with shipped equipment.

6.2 Government Quality Assurance

6.2.1 The performance and quality of work delivered by the contractor, including delivery services rendered and any documentation or written material compiled shall be subject to inspection, review, and acceptance by the Government.

7.0 CANCELLATION/OTHER CONDITIONS

7.1 This contract may be cancelled in whole or in part with a 30-day written notice from the Contracting Officer. If this tasking is cancelled, the U.S. Government shall be liable only for payment of services received before the effective date of the termination.

7.2 The contractor must be aware of contingencies. Due to the emergent nature of exercise and real-world communications requirements and schedules, adjustments in the amount of labor, overtime and other resources needed to complete the task may be required.

8.0 BASE ACCESS/SECURITY

N/A

9.0 POINTS OF CONTACT

9.1 COR

9.1.1 TBD

9.2 KO

9.2.1 Samantha Ballance/ (564) 230-2642/ samantha.a.ballance.civ@us.navy.mil

9.3 NCTS Sicily CO

9.3.1 CDR Patrick Jones / 001-39-095-86-5521 / patrick.w.jones54.mil@us.navy.mil

9.4 NCTAMSLANT N4 Facilities, Chief Engineer

9.4.1 Aaron Edwards / 757-400-9200 / aaron.t.edwards6.civ@us.navy.mil