Beg Sta	End Sta	Description of Work	Drawing #	Spec	SPS	Pay Item	Unit	Quantity
0+00		Begin work on Sweet Trunk Trail #274 at the trailhead parking near Half Moon campground, at the end of Big Timber Canyon.						
0+00		Install post where staked.	952-1	952		952(01)	EA	1
0+00	971+53	Clear trail for duration of contract.	911-1	982		982(01)	MI	18.41
0+00	971+53	Construct 100 Drain Dips where staked and drained to daylight; Leadoff ditches incidental.	912-5	912		912(05)	EA	100
0+00	971+53	Construct 96,153 LF of new stock trail. Includes clearing, grubbing and unclassified excavation. Numerous sections of surface rock may need blasting or hammering, incidental.	911-1 912-1	911 912		911(01) 912(01)	LF LF	95,153 95,153
0+00	971+53	Construct 1000 LF of new stock trail within rock. Blasting or hammering may be required. Includes clearing, grubbing and unclassified excavation.	911-1 912-1 912-2	911 912		911(01) 912(01) 912(02)	LF LF LF	1000 1000 1000
0+50		Fence. Install 72” steel pipe swing gate, and 2 H-braces with 4 posts (6-8” diameter) where staked near trailhead.	952-1	952		952(01)	EA	1
18+00		2 climbing turns.						
24+90		Construct 6’ radius switchback, unclassified excavation, with max. 8% grade throughout, including 50’ long approaches. Rock Walls where staked lumped under 914(06)a . (55% slope.)	914-1	914		914(01) 914(06)	EA	1
28+60		Construct 6’ radius switchback, unclassified excavation, with max. 8% grade throughout, including 50’ long approaches. Rock Walls where staked lumped under 914(06)a . (35% slope.)	914-1	914		914(01) 914(06)	EA	1
32+00		Construct 6’ radius switchback, unclassified excavation, with max. 8% grade throughout, including 50’ long approaches. Rock Walls where staked lumped under 914(06)a (55% slope)	914-1	914		914(01) 914(06)	EA	1
35+20		Construct 6’ radius switchback, unclassified	914-1	914		914(01)	EA	1

Beg Sta	End Sta	Description of Work	Drawing #	Spec	SPS	Pay Item	Unit	Quantity
		excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a (60% slope)				914(06)		
38+10		Private property. Install post where staked.	952-1	952		952(01)	EA	1
38+70		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a (60% slope)	914-1	914		914(01) 914(06)	EA	1
39+30		Private property. Install post where staked.	952-1	952		952(01)	EA	1
41+40		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a (70% slope)	914-1	914		914(01) 914(06)	EA	1
43+20		Private property. Install post where staked.	952-1	952		952(01)	EA	1
49+30		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
55+10		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. (75% slope.) Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
62+80		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. (70% slope.) Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
70+00		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. (75% slope.) Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1

Beg Sta	End Sta	Description of Work	Drawing #	Spec	SPS	Pay Item	Unit	Quantity
73+80		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. (70% slope.) Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
75+00		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. (50% slope.) Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
77+60		Private property. Install post where staked.	952-1	952		952(01)	EA	1
81+30		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. (70% slope.) Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
84+20		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. (70% slope.) Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
107+30		Install trail marker post where staked.	952-1	952		952(01)	EA	1
109+00		Install trail marker post where staked.	952-1	952		952(01)	EA	1
110+40		Install trail marker post where staked.	952-1	952		952(01)	EA	1
117+00		Stream crossing. NO WORK.						
133+50		Install trail marker post where staked.	952-1	952		952(01)	EA	1
134+80		Install trail marker post where staked.	952-1	952		952(01)	EA	1
211+00		Stream Crossing. North Amalong Creek. NO WORK.						
246+20		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout,	914-1	914		914(01) 914(06)	EA	1

Beg Sta	End Sta	Description of Work	Drawing #	Spec	SPS	Pay Item	Unit	Quantity
		including 50' long approaches. Rock Walls where staked lumped under 914(06)a						
317+00		Natural Ford. (side channel to Otter Creek)	912-5	912		912(06)	EA	1
317+40		Stream Crossing. Otter creek. NO WORK	917(10)	917		917(10)	EA	1
341+90		Stream crossing. NO WORK						1
349+10		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
350+70		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
375+50	376+30	Talus rock						
409+00		Dry wash						
410+00		Dry wash						
423+70		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
449+00		Dry Wash						
520+30		Dry wash						
612+50		Install post where staked.	952-1	952		952(01)	EA	1
614+00		Install post where staked.	952-1	952		952(01)	EA	1
615+50		Install post where staked.	952-1	952		952(01)	EA	1

Beg Sta	End Sta	Description of Work	Drawing #	Spec	SPS	Pay Item	Unit	Quantity
628+00		Install post where staked.	952-1	952		952(01)	EA	1
630+00		Follow old road prism. Install post where staked.	952-1	952		952(01)	EA	1
633+70		Leaving road prism. Install post where staked.	952-1	952		952(01)	EA	1
633+70		Ditching. Construct 15 sediment trap ditches where staked, across the steep CAT trail. Distance between traps is approximately 80-100LF. Install trap above each trail crossing. Sediment traps 3'x3'x25', in rocky soil.		912		912(09)	LF	375
646+80		Intersection with CAT trail. Install post where staked.	952-1	952		952(01)	EA	1
647+50		Intersection with CAT trail. Install post where staked.	952-1	952		952(01)	EA	1
652+30		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
658+70		Intersection with CAT trail. Install post where staked.	952-1	952		952(01)	EA	1
666+20		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
671+40		Intersection with CAT trail. Install post where staked.	952-1	952		952(01)	EA	1
675+50		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
680+80		Intersection with CAT trail. Install post where staked.	952-1	952		952(01)	EA	1

Beg Sta	End Sta	Description of Work	Drawing #	Spec	SPS	Pay Item	Unit	Quantity
697+60		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
702+40		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
729+50		Natural Ford	917(10)	917		917(10)	EA	1
734+00		Construct 6' radius switchback, unclassified excavation, with max. 8% grade throughout, including 50' long approaches. Rock Walls where staked lumped under 914(06)a	914-1	914		914(01) 914(06)	EA	1
760+20		Intersection with user made stock trail. Install post where staked.	952-1	952		952(01)	EA	1
760+70		Intersection with user made stock trail. Install post where staked.	952-1	952		952(01)	EA	1
763+00		Intersection with user made stock trail. Install post where staked.	952-1	952		952(01)	EA	1
763+50		Intersection with user made stock trail. Install post where staked.	952-1	952		952(01)	EA	1
780+50		Scenic overlook. Devils Slide						
783+70		Private property boundary. Install post where staked.	952-1	952		952(01)	EA	1
791+20		Natural Ford (Hell Roaring Creek)	917(10)	917		917(10)	EA	1
797+90		Private property boundary. Install post where staked.	952-1	952		952(01)	EA	1
862+00		Private property boundary. Install post where staked.	952-1	952		952(01)	EA	1
875+50		Stream Ford. Bruin Creek.	917(10)	917		917(10)	EA	1

Beg Sta	End Sta	Description of Work	Drawing #	Spec	SPS	Pay Item	Unit	Quantity
882+90		Private property boundary. Install post where staked.	952-1	952		952(01)	EA	1
917+00		Construct 15' Turnpike, Rock Retainer – Type II	913(02)	913		913(02)	LF	15
920+50		Construct 30' Turnpike, Rock Retainer – Type II	913(02)	913		913(02)	LF	30
923+30		Install one 15"x15' PE culvert without headwalls with outlet ditch to daylight (ditching incidental to 921(01)a	921-2	921		921(02)	LF	15
929+00		Stream crossing. NO WORK.						
931+90		Install post where staked.	952-1	952		952(01)	EA	1
933+20		Install post where staked.	952-1	952		952(01)	EA	1
944+60		Install post where staked.	952-1	952		952(01)	EA	1
944+70	945+70	Stream crossing. Sweet Grass creek. (100'x4") NO WORK.						
945+80		Install post where staked.	952-1	952		952(01)	EA	1
948+50		Intersection with Cave Lake trail. Install post where staked.	952-1	952		952(01)	EA	1
948+50	971+53	Install 5 posts where staked.	952-1	952		952(01)	EA	5
970+00		Old collapsed fence.						
971+53		Intersection with existing trail. End of project. Install post where staked.	952-1	952		952(01)	EA	1