PERFORMANCE WORK STATEMENT

RSS Modification and Restoration for Fuselage Trainer Installation

AT

Joint Base Andrews, MD

29 June 2026

PERFORMANCE-BASED WORK STATEMENT

TABLE OF CONTENTS

SECTION PAGE

1. DESCRIPTION OF SERVICES……3

2. SPECIFICATIONS…….....3

3. GENERAL INFORMATION…….4

4. PROJECTED PERIOD OF PERFORMANCE……..5

5. GOVERNMENT FURNISHED PROPERTY (GFP) AND SERVICES……6

1 DESCRIPTION OF SERVICES:

The 89AW executes a no-fail executive airlift mission that depends on a highly trained and continuously qualified aircrew force, requiring robust and realistic training capabilities to sustain readiness for more than 430 aircrew members. To support this mission, the Wing is procuring fuselage trainers that provide hands-on, high-fidelity training essential for safe and effective aircrew operations. These trainers must be installed within an existing Relocatable Simulator Shelter (RSS) on the installation; however, due to the size and configuration of the equipment, temporary structural modification of an RSS is required to allow delivery and placement. Contractor support is therefore necessary to remove a wall section to facilitate installation by the fuselage trainer manufacturer and to restore the RSS to its original, fully functional condition upon completion. The contractor shall provide all required personnel, equipment, tools, materials, vehicles, supervision, and services necessary to perform RSS Modification and Restoration for Fuselage Trainer Installation on Joint Base Andrews (JBA). Performance shall be in accordance with all applicable laws, standards, instructions, executive orders, commercial practices, and requirements contained in this Performance Work Statement (PWS).

2 SPECIFICATIONS

2.1 RSS SPECIFICATIONS

	Length		Height			Width		
	Exterior	Interior	Exterior W/ Roof Lights	Exterior	Interior	Exterior	Interior	Volume
Ft In	34’1”	33-1”	19’7”	18’7-3/4”	16’	61’ 7-7/16”	60’ 7-7/16”	32,088 Cu. Ft
Metric	10,391	10,083	5,968	5,682	4,876	18,781	18,476	908.63 Cu. M

2.2 RSS MODIFICATION SPECFICATIONS

The contractor will provide an RSS installation team, equipment, tools and transportation to remove and replace a portion of the rear wall section of an existing RSS (RSS #2) at Joint Base Andrews. Specifically:

2.2.1. Remove roof caps, corner caps and sealant

2.2.2 Remove electrical from rear door, rear receptacles

2.2.3 Remove (5) structural insulated wall panels

2.2.4 Remove (1) horizontal i-beam

2.2.5 ****Allow Fuselage Trainer Installation Team to Complete their Installation, then:****

2.2.6 Re-install (1) horizontal i-beam

2.2.7 Re-install (5) structural insulated wall panels

2.2.8 Re-install electrical to rear door, rear receptacles

2.2.9 Re-install roof caps, corner caps and sealant

2.2.10 Inspect & Test as needed to ensure RSS is structurally sound and working properly

2.2.12 The contractor will provide all materials, equipment, and manpower necessary to complete the job.

2.2.13 The contractor is not required beyond normal hours of operation.

3 GENERAL INFORMATION:

3.1 HOURS OF OPERATION: The contractor shall perform the services required under this contract during the following hours: 6:00 A.M. - 6:00 P.M., Monday through Friday excluding Federal Holidays notated at https://www.opm.gov/policy-data-oversight/pay-leave/federal-holidays/#url=2026 unless coordinated with the Contracting Officer or an authorized Government representative associated with the contract. Any holiday rescheduling shall be at no additional cost to the government and shall not be the basis for non-performance.

3.2 Security Requirements: All personnel employed by the contractor in the performance of this contract, or any representative of the contractor entering the government installation, shall abide by all security regulations of the installation. The contractor shall be responsible for the action of any of their subcontractors and their employees who are working on JBA. The contractor and subcontractor shall hire U.S. citizen(s) that are in possession of a valid State driver's license, birth certificate and or Real ID. If the employee is not a U.S. citizen, the contractor and/or subcontractor may hire non-U.S. citizens if they are in possession of a Green Card, Social Security Card, Resident Card, Work Visa, and State issued Identification Card. If driving on base a State issued driver's license is required. The Contractor shall ensure the pass and identification items required for contract performance are obtained for employees and non-government owned vehicles.

3.3 Weapons: Weapons of any sort are not authorized on JBA, this includes guns, knives, swords, nunchucks, brass knuckles, or any other weapon that has a sole purpose to injure or maim. Combination tools such as Leatherman and small pocketknives with folding blades less than four inches are authorized if used in the performance of duty. Those found in violation of this directive are subject to apprehension, criminal charges, and debarment from the installation.

3.4 Illegal Controlled Substances: The U.S. Federal government is the most vocal opponent of the drug industry and it has set the de facto international standards regarding the legality and illegality of different drugs. Illegal controlled substance and narcotics are not authorized on JBA whatsoever. Controlled substances shall not be transported on the installation via vehicle or on an individual person. Marijuana/cannabis, cocaine, crack cocaine, LSD, methamphetamine (meth), heroin, anabolic steroids, psilocybin mushrooms, are some of the forbidden substances (this list is not all-inclusive). Prescription medications are authorized for the person the medication is issued; however, the medication must not be expired, and the label must clearly indicate the name of the person the medication is issued to. Otherwise, prescription medication may be deemed illegal by law enforcement officials. Those found in violation of this directive are subject to apprehension, criminal charges, and debarment from the installation.

3.5 Continuation of Essential Department of Defense (DOD) Contractor Services During Crisis: In the event the contractor is unable to perform his daily operations due to peacetime emergency and/or wartime contingency disturbances, etc., neither the Government nor the contractor shall take action for non-compliance with contract requirements. Upon notification by the CO, the contractor shall perform emergency and special event services, contingencies, operational readiness exercises or inspections. Emergency and special event services will be priced separately from routine services.

3.6 Government Remedies: The Contracting Officer shall follow Revolutionary Federal Acquisition Regulation Overhaul 52.212-4, Terms and Conditions – Commercial Products and Commercial Services for contractor's failure to perform satisfactory services or failure to correct non-conforming services.

3.7 Special Qualifications: Any special qualification required for commencement of duties in relation to this contract must be confirmed by the contractor. The government will not provide any training in relation to this contract.

4. Projected Period of Performance:

4.1 Initial Performance: This project will be completed in two phases. The first phase of the contract requires the contractor to complete requirements in Section 2.2.1, 2.2.2, 2.2.3, and 2.2.4 of this PWS no later than 12 October 2026. A secondary contractor will install fuselages in RSS #2 with a completion date of 26 October 2026.

4.2 Secondary Performance: Upon completion of secondary contractor performance, the contractor of this requirement shall follow requirements in Section 2.2.6, 2.2.7, 2.2.8, 2.2.9, 2.2.10, 2.2.11, 2.2.12, and 2.2.13 of this PWS with an estimated start date of 27 October 2026.

4.3 Deviations from Projected Performance: In the event the secondary contractor is delayed from completing the installation of the fuselages, an authorized Government representative will inform the contractor of this requirement for an updated work schedule, and the Contracting Officer will modify the contract to reflect updated changes.

5. Government Furnished Property (GFP) and Services:

The US Government will not provide any equipment, fuel, personnel, utilities or facilities to the contractor for the execution of this contract. Should an emergency arise, only the necessary basic lifesaving and life support measures will be provided during the emergency.