AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE OF PAGES	
J	1	2

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO.(If applicable)
0007	17-Jun-2026	AMS00725177	

6. ISSUED BY	CODE	7. ADMINISTERED BY (If other than item 6)	CODE
NAVFACSYSCOM MID-ATLANTIC PWD OCEANA FACILITIES ENGINEERING & ACQ DIV 953 HORNET DR SUITE 213 VIRGINIA BEACH VA 23460-2190	N40085	**See Item 6**	

8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)			
		X	9A. AMENDMENT OF SOLICITATION NO. N4008526R0169
		X	9B. DATED (SEE ITEM 11) 17-Jun-2026
			10A. MOD. OF CONTRACT/ORDER NO.
			10B. DATED (SEE ITEM 13)
CODE	FACILITY CODE		

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer [X] is extended, [ ] is not extended.

Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA (If required)

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS.
IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

[ ] A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

[ ] B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).

[ ] C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

[ ] D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [ ] is not, [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

SOLICITATION N4008526R0169, CONVERT INTEL SPACES TO CONTROLLED AREA, BLDG 145, NAS OCEANA

The purpose of this amendment is to issue PPI responses and to extend the proposal due date.

Receipt of Proposal due date is 15 July 2026 at 2:00PM EDT.

SEE CONTINUATION PAGE.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print) TEL: EMAIL:	
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED 17-Jun-2026

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

SECTION SF 30 - BLOCK 14 CONTINUATION PAGE

The following have been added by full text:

AMENDMENT 0007

SOLICITATION N4008526R0169, CONVERT INTEL SPACES TO CONTROLLED AREA, BLDG 145, NAS OCEANA

The purpose of this amendment is to issue PPI Responses and to extend the proposal due date.

Please submit your proposal by 15 July 2026 at 2pm EDT through PIEE. Late submission will not be considered.

Attachment:
1. pdf: AMEND 0007 PPI Spreadsheet

(End of Summary of Changes)

Project Title: CONVERT INTEL SPACES TO CONTROLLED AREA, BLDG 145, NAS OCEANA	Solicitation / RFP#: N4008526R0169 - PPI Cut Off Date: 29-MAY-2026

PPI No.	Offeror	Date Submitted	REFERENCE				QUESTION	GOVERNMENT RESPONSE	Amend No.
			Page	Section	Para.	Dwg #			
267		06/15/26		Am. 6, PPI Responses			PPI #206 identifies Thermo-Trol Systems as the existing ALC contractor but states that the SOW does not require Thermo-Trol to perform the DDC work. Please confirm whether DDC controls work must be performed by Thermo-Trol Systems, or whether another qualified ALC controls contractor may perform the work. If Thermo-Trol is not mandatory, please confirm that the Contractor remains responsible to provide a qualified ALC controls technician to support the following: 1. Temporary removal, storage, reinstallation, and rewiring of existing room temperature sensors at new perimeter furring walls. 2. Verification of existing VAV box operation/sequences after sensor reinstallation. 3. Modification of the existing ALC DDC system to monitor space temperature and humidity for the new ductless split system serving TEL/COM Room W205. 4. Installation/commissioning support for the manufacturer-provided wired remote controller/thermostat for the ductless split system. 5. TAB support for existing ALC-controlled VAV boxes as required by D3070. Reason for Request: The SOW requires work on and verification of the existing ALC DDC system. Clarification is needed to determine whether Thermo-Trol must be carried specifically, or whether pricing may include another qualified ALC controls contractor."	ALC contractor is Thermo-Trol Systems. (757)-428-4646. The SOW does not require Thermo-Trol to perform DDC work. Existing Thermo-Trol System to remain. Contractor will perform DDC work for Convert Intel Spaces to Controlled Area. It is up to Contractor to engage Thermo-Trol or another sub-contractor who understand Thermo-Trol System.	0007
268		06/15/26		Att. A			What frequency range is required to achieve 60 dB isolation?	The shielding system must meet minimum performance requirements stated in IEEE 299	0007
269		06/15/26		Att. A			If IEEE 299 field testing is required, please identify the discrete test frequencies, test locations, number of test points, and acceptance criteria.	Contractor to conduct independent IEEE-299 testing to determine shielding effectiveness. Results to be validated by the DONSAPCO Certified Technical TEMPEST Authority.	0007
270		06/15/26		Att. A			Is the required validation full IEEE 299 field testing, modified IEEE 299 testing, or the typical three-part qualification/validation procedure associated with RF/EMI shielding specifications?	Contractor to conduct independent IEEE-299 testing to determine shielding effectiveness. Results to be validated by the DONSAPCO Certified Technical TEMPEST Authority.	0007
271		06/15/26		Att. A			At what stage shall RF testing occur: prior to MEP/FP/telecom/security penetrations, after all penetrations are complete, after finishes, or at final acceptance?	Contractor to conduct independent IEEE-299 testing to determine shielding effectiveness. Results to be validated by the DONSAPCO Certified Technical TEMPEST Authority.	0007
272		06/15/26		Att. A			Amendment 0006 responses indicate that power filters and certain RF filters are not required at RF boundary penetrations. Please confirm whether the Contractor will be held responsible for achieving 60 dB performance if the Government-directed configuration does not include RF filters needed to achieve the specified performance.	No power filters are required	0007
273		06/15/26		Att. A			Please confirm whether the RF shielding subcontractor is expected to provide full design-assist/modeling/shop drawing coordination for 100% of the RF shielding scope, including all six sides and all penetrations, or whether the RF shielding subcontractor is intended to provide consulting/testing support only.	Yes to provide design-assist/modeling/shop drawing coordination for 100% of the RF shielding scope, including all six sides and all penetrations	0007