MTRA DISPOSAL BOX SUPPLEMENTAL REQUIREMENTS

1. Vendor shall provide one additional set of forty-eight (48) studs, forty-eight (48) lock washers, and forty-eight (48) nylon insert lock nuts to be used as spares.

    1.1 The spares shall be provided in one or more good quality sealed bags or containers that will prevent the contents from spilling out during shipping and handling.

    1.2 The spares are items 12, 13, and 14 of drawing 2370.2-7407V (revision D).

2. A certificate of compliance is required.

3. Ensure studs installed on box remain unpainted.

4. The boxes shall be fabricated per the Norfolk Naval Shipyard (NNSY) provided drawing. NNSY will not review a vendor provided drawing.

[redacted]