AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF	PAGES
J	1		10

2. AMENDMENT/MODIFICATION NUMBER	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQUISITION NUMBER	5. PROJECT NUMBER *(If applicable)*
0002	01 JUL 2026		N/A

6. ISSUED BY CODE W15QKN

W6QK ACC-PICA
KO CONTRACTING OFFICE, BUILDING 10 PHIPPS RD
PICATINNY ARSENAL, NJ 07806-5000
UNITED STATES
NELIA SHYSHAK, EMAIL: NELIA.SHYSHAK.CIV@ARMY.MIL TELEPHONE: 609 562 3774

7. ADMINISTERED BY *(If other than Item 6)* CODE

SCD: PAS:

8. NAME AND ADDRESS OF CONTRACTOR *(Number, street, county, State and ZIP Code)*

CODE FACILITY CODE

(X)	
[X]	9A. AMENDMENT OF SOLICITATION NUMBER W15QKN26RA056
	9B. DATED *(SEE ITEM 11)* 17 JUN 2026
[ ]	10A. MODIFICATION OF CONTRACT/ORDER NUMBER
	10B. DATED *(SEE ITEM 13)*

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers [ ] is extended. [X] is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

SEE SECTION G - CONTRACT ADMINISTRATION DATA

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

CHECK ONE	
[ ]	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A.
[ ]	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
[ ]	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
[ ]	D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor [ ] is not [ ] is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

The purpose of this Amendment is to answer vendors' questions.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
		EDWARD SHERWOOD	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		Edward L Sherwood *(Signature of Contracting Officer)*	02 JUL 2026

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

Section A - Solicitation/Contract Form

The following changes have been made:

Miscellaneous text in this section has been modified to:

The purpose of this Amendment 0002 is to answer vendors' questions:

Question 1. Please confirm the window quantities for each type. Our local representative was onsite for the walk through yesterday and only saw 2 type A windows, they also counted 14 type B windows. Please advise.

Answer 1. There are 2 Type A windows on each floor; 3 floors equals 6. There are 6 Type B windows on the First floor and 2 on the second and third floor for a total of 10.

Question 2. Wage Determination Applicability (MA20260001). Wage Determination MA20260001 (Mod. 1, 05/18/2026) attached to the solicitation lists the following Massachusetts counties: Barnstable, Bristol, Dukes, Essex, Middlesex, Nantucket, Norfolk, and Suffolk. The project site (USAG Devens RFTA) is located in Worcester County, Massachusetts, which is not enumerated on the referenced WD. Please confirm whether (a) MA20260001 is the governing wage determination for this project notwithstanding the county roster, or (b) a corrected/alternate Worcester County WD will be issued by amendment. This confirmation is required to lock prevailing-wage pricing and avoid post-award equitable-adjustment requests.

Answer 2. Site Location is Middlesex County. It is not Worcester County.

Question 3. PWS Building Reference Discrepancy. PWS Section 1.1 (Scope) references "Buildings 646 and 653," while the solicitation title, drawings (A100-A104), site signage, and all other PWS sections reference Building 674 exclusively. Please confirm that the scope of work is limited to Building 674 at 49 Queenstown Street and that the "646 and 653" references in Section 1.1 are a typographical carryover from a prior/sister-building solicitation.

Answer 3. Correct. That is a misprint. The only building in this project is 674. This misprint has been addressed in Solicitation narrative paragraph 1(b) "Resolution of PWS Technical Site Inconsistencies".

Question 4. Window Operation Type and Frame Material. PWS Division 08 specifies "vinyl single-hung" windows. Site observation and the elevation drawings (A104) indicate the existing units are painted steel commercial sash with projected (awning/hopper) operable lites and fixed transom lites - not single-hung. Please confirm:

(a) whether single-hung vinyl is the required replacement configuration, or

(b) whether projected operable + fixed transom configurations are acceptable to maintain ventilation parity with the existing assemblies, and

(c) whether thermally-broken aluminum or aluminum-clad frames are acceptable for the larger CC /DD openings where vinyl span limits may be exceeded.

Answer 4. Window spec is aluminum frame 08-51-31. We are good with either type of replacement a., b., or c. if that reduces cost and improves function.

(a) whether single-hung vinyl is the required replacement configuration, or

(b) whether projected operable + fixed transom configurations are acceptable to maintain ventilation parity with the existing assemblies, and

(c) whether thermally-broken aluminum or aluminum-clad frames are acceptable for the larger CC /DD openings where vinyl span limits may be exceeded.

Question 5. Lead-Based Paint (LBP) and Asbestos-Containing Material (ACM) Surveys. Building 674 is of 1940s-era construction. PWS Section 02 41 00 (Demolition) is silent on LBP and ACM. Please confirm whether (a) AHERA/LBP survey reports for Building 674 will be released as Government-Furnished Information (GFI) prior to bid, or (b) offerors should price the work on a presumed-present basis with the Government's acknowledgment of equitable-adjustment rights if abatement scope exceeds presumed conditions.

Answer 5.

The building was constructed in 1969.

Windows have been replaced in the last thirty years; however, I will submit Hazard surveys.

Question 6. Bid Guarantee - Acceptable Instruments and Delivery. Per FAR 52.228-1, the Bid Guarantee is set at 20% of the bid price or $3,000,000, whichever is less. Please confirm:

(a) acceptable instrument forms (SF 24 Bid Bond, certified/cashier's check, Irrevocable Letter of Credit, electronic Bid Bond),

(b) whether PDF submission with the offer is sufficient or whether a hard-copy original is required, and

(c) if hard-copy is required, the deadline and delivery address for the original instrument.

Answer 6.

(a) Per the full text of FAR 52.228-1 "Bid Guarantee," which is included on page 74 of the solicitation, the following instruments are acceptable for the required bid guarantee:

A bid bond (such as an SF 24) from a surety acceptable to the Government.

A postal money order.

A certified check.

A cashier's check.

An irrevocable letter of credit (ILC).

United States bonds or notes (per Treasury Department regulations).

The solicitation does not permit electronic bid bonds for this procurement. Please ensure the bid guarantee is submitted with your proposal by the deadline of 4:00 PM EST on July 8, 2026.

(b) PDF submission with the offer is sufficient.

Question 7. Official Project Address for Permitting and Access. The PWS cover sheet lists the project address as "30 Quebec Street," while the on-site building signage and drawing title blocks (A100-A104) read "49 Queenstown Street." Please confirm the official project address of record for use in permitting, DD-1391 references, certified payroll submissions, and base access pass requests.

Answer 7. The Government confirms that Building 674, 49 Queenstown Street, Devens, MA 01434 is the official physical project address. Please ensure this address (49 Queenstown Street) is utilized on all official permitting, certified payroll submissions, DD-1391 references, and base access pass requests. The address listed on the PWS cover sheet (30 Quebec Street) is the administrative billing/DoDAAC address for the DPW office and is not the physical site of work.

Question 8. Please confirm the total quantity: 86 rough openings or approximately 282 windows?

Answer 8. Total quantity expressed in the PWS stated that contractor should make their own determination. What we counted was displayed in the PWS.

Question 9. Are the large openings to be provided as factory-mulled assemblies or multiple individual replacement windows?

Answer 9. How the window configurations are purchased is up to the contractor.

Question 10. Is lead paint and/or asbestos testing available, and are any abatement requirements anticipated?

Answer 10. The building was constructed in 1969. Windows have been replaced in the last thirty years. Please see Hazard surveys via the following attachments:

Hazard Surveys_674 and 681 acm removal and testing

Hazard Surveys_A000_ACM_CompleteBase_1995 (1)

Hazard Surveys_AB005_ACM_B674_04292015 (1)

Hazard Surveys_AB005_ACM_B674_04292015

Question 11. Are there any restrictions on lift, scaffold, or boom lift access around the building?

Answer 11. No restrictions on lift, scaffold, or boom.

Question 12. Are there any building occupancy restrictions or required work hours?

Answer 12. Working hours are 0700 - 1700, no holidays or weekends unless authorized by COR /Contracting.

Question 13. Please confirm whether any interior finish repairs beyond normal installation are required.

Answer 13. Interior finish should be seamless; in kind to the existing finish.

Question 14. Please confirm whether any exterior siding, masonry, or framing repairs are required if concealed damage is discovered.

Answer 14. Exterior should be finished in the same manner as the interior. If damage is discovered, notification to COR/Contracting must take place to determine if modification is needed.

Question 15. Is temporary weather protection required during window replacement operations?

Answer 15. Yes, weather protection is needed.

Question 16. Who is responsible for removing, relocating, protecting, and reinstalling existing furniture and furnishings affected by the window replacement work?

Answer 16. Contractor is responsible for moving furniture to access windows for replacement.

Question 17. Who is responsible for removing, storing, protecting, and reinstalling existing curtains, blinds, shades, and other window treatments affected by the window replacement work?

Answer 17. Contractor is responsible for removing blinds, shades etc., and replacing them following install of new windows.

Question 18. The drawings and specifications indicate a 3-1/4-inch deep vinyl window with 7/8-inch insulated Low-E glass. Can the Government provide the basis-of-design manufacturer and model, or identify acceptable manufacturers and approved equal products for bidding purposes?

Answer 18. Window spec is aluminum frame 08-51-31. We are good with either type of replacement a., b., or c. if that reduces cost and improves function.

(a) whether single-hung vinyl is the required replacement configuration, or

(b) whether projected operable + fixed transom configurations are acceptable to maintain ventilation parity with the existing assemblies, and

(c) whether thermally-broken aluminum or aluminum-clad frames are acceptable for the larger CC /DD openings where vinyl span limits may be exceeded.

Question 19. The drawings and specifications indicate a 3-1/4-inch deep vinyl window with 7/8-inch insulated Low-E glass. Can the Government provide the basis-of-design manufacturer and model, or identify acceptable manufacturers and approved equal products for bidding purposes?

Answer 19. Contractor is responsible for sourcing replacement windows. Our only spec is listed above.

Question 20. Can manufacturer information, window schedules, and dimensions for each window type be provided to ensure consistent bidding and product selection?

Answer 20. Contractor is responsible for determining window replacement manufacturer. We are not looking for top of the line. Middle of the road will be perfectly fine.

Question 21. After today's walk through the window count is: AA type 1; BB Type 15; CC type 24; DD Type 46 Please confirm.

Answer 21. Window count is listed below as it was in the PWS. It is the Contractor's responsibility to verify prior to bid.

Window AA- 2'0x4'8

1st Floor- 2

2nd Floor-2 Total= 6

3rd Floor- 2

Window BB- 7'8 x 4'8

1st Floor- 6

2nd Floor-2 Total=10

3rd Floor-2

Window CC- 11'4 x 4'8

1st Floor 8

2nd Floor 8 Total= 24

3rd Floor 8

Window DD -15'8 x 4'8

1st Floor 14

2nd Floor 16 Total=46

3rd Floor 16

Question 22. Window treatments shades etc. are not mentioned in the SOW. Are they to

be removed and reinstalled. If so, do you have a count of what is required to be removed?

Answer 22. Contractor is responsible for removing blinds, shades etc., and replacing them following install of new windows. Contractor is responsible for verifying for bid.

Question 23. Fire Rate Vinyl. Whatever the trade standard is for fire rating will suffice.

Answer 23. Drawings submitted in the PWS are what we have available.

All other terms and conditions remain unchanged and in full force and effect.

Section J - List of Attachments

The attachments table has changed from:

Identifier	Document Name	Document Description	Reference Identifier	Date	Line Item	Page Numbers	Document Type	Provided Under Separate Cover

0001	BLDG 674 Window Replacement PWS 30 APRIL 2026	Performance Work Statement		04 Jun 2026			Attachment	No
0002	Davis-Bacon Act WD # MA20260001 d. 5.18.2026	Wage Determination		04 Jun 2026			Attachment	No
0003	Attachment 0003 - Contractor Cost Breakdown Form	Purchase Plan		16 Jun 2026			Attachment	No
0004	Devens_Visitors_Pass_Request	Visitor Pass Request		04 Jun 2026			Attachment	No

To:

Identifier	Document Name	Document Description	Reference Identifier	Date	Line Item	Page Numbers	Document Type	Provided Under Separate Cover
0001	BLDG 674 Window Replacement PWS 30 APRIL 2026	Performance Work Statement		04 Jun 2026			Attachment	No
0002	Davis-Bacon Act WD # MA20260001 d. 5.18.2026	Wage Determination		04 Jun 2026			Attachment	No
0003	Attachment 0003 - Contractor Cost Breakdown Form	Purchase Plan		16 Jun 2026			Attachment	No
0004	Devens_Visitors_Pass_Request	Visitor Pass Request		04 Jun 2026			Attachment	No
0005	Hazard Surveys_674	Supporting Technical Documentation		01 Jul 2026			Attachment	No

	and 681 acm removal and testing							
0006	Hazard Surveys_A000_ACM_CompleteBase_1995 (1)	Supporting Technical Documentation		01 Jul 2026			Attachment	No
0007	Hazard Surveys_AB005_ACM_B674_04292015 (1)	Supporting Technical Documentation		01 Jul 2026			Attachment	No
0008	Hazard Surveys_AB005_ACM_B674_04292015	Supporting Technical Documentation		01 Jul 2026			Attachment	No

The following contract documents were added:

Hazard Surveys_674 and 681 acm removal and testing
Hazard Surveys_A000_ACM_CompleteBase_1995 (1)
Hazard Surveys_AB005_ACM_B674_04292015
Hazard Surveys_AB005_ACM_B674_04292015 (1)

Miscellaneous text in this section has been modified to:

Attachment 0001 - Performance Work Statement (PWS)

Attachment 0002 - Applicable Davis-Bacon Act Wage Determination

Attachment 0003 - Contractor Cost Breakdown Form

Attachment 0004 - Devens Visitors Pass Request

Attachment 0005:

Hazard Surveys_674 and 681 acm removal and testing

Hazard Surveys_A000_ACM_CompleteBase_1995 (1)

Hazard Surveys_AB005_ACM_B674_04292015 (1)

Hazard Surveys_AB005_ACM_B674_04292015