Question: The SOW references replacing the 2×2 supply air diffusers. Could you clarify whether the diffusers should remain in their current ceiling grid locations, or relocate to align with the new LED fixture and grid layout? This will affect our mechanical subcontractor requirements and pricing.

Answer: The diffusers will align with new 2X2 Ceiling Grid and LED light placement with contractors submitted lighting plot.

Question: Is a dedicated Superintendent/SSHO required for this project or is it sufficient for our working team members to hold the necessary OSHA certifications?

Answer: Per the CSS, you must have an OSHA-certified competent person onsite during all working activities. This person can perform trade work, provided they are in the presence of the other workers and are able to see their work activities.