PROJECT TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

01 33 00 SUBMITTAL PROCEDURES
01 33 29 SUSTAINABILITY REPORTING
01 42 00 SOURCES FOR REFERENCE PUBLICATIONS
01 45 00.10 20 QUALITY CONTROL FOR MINOR CONSTRUCTION

DIVISION 02 - EXISTING CONDITIONS

02 41 00 DEMOLITION AND DECONSTRUCTION
02 82 33.13 20 REMOVAL/CONTROL AND DISPOSAL OF PAINT WITH LEAD

DIVISION 03 - CONCRETE

03 33 00 CAST-IN-PLACE ARCHITECTURAL CONCRETE

DIVISION 04 - MASONRY

04 03 00 CONSERVATION TREATMENT FOR PERIOD MASONRY

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

06 10 00 ROUGH CARPENTRY
06 20 00 FINISH CARPENTRY
06 82 14 FIBERGLASS REINFORCED PLASTIC (FRP) PIPE AND TUBE RAILINGS

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

07 60 00 FLASHING AND SHEET METAL
07 92 00 JOINT SEALANTS

DIVISION 08 - OPENINGS

08 71 00 DOOR HARDWARE
08 81 00 GLAZING

DIVISION 09 - FINISHES

09 90 00 PAINTS AND COATINGS

-- End of Project Table of Contents --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 33 00

SUBMITTAL PROCEDURES

08/18

PART 1 GENERAL

1.1 SUMMARY
1.1.1 Submittal Information
1.1.2 Project Type
1.1.3 Submision of Submittals
1.2 DEFINITIONS
1.2.1 Submittal Descriptions (SD)
1.2.2 Approving Authority
1.2.3 Work
1.3 SUBMITTALS
1.4 SUBMITTAL CLASSIFICATION
1.4.1 Government Approved (G)
1.4.2 Design-Build Submittal Classifications
1.4.2.1 Designer of Record Approved (DA)
1.4.2.2 Government Conformance Review of Design (CR)
1.4.2.3 Designer of Record Approved/Government Conformance Review (DA/CR)
1.4.2.3.1 Variations from the Accepted Design
1.4.2.3.2 Substitutions
1.4.2.4 Designer of Record Approved/Government Approved (DA/GA)
1.4.3 For Information Only
1.4.4 Sustainability Reporting Submittals (S)
1.5 PREPARATION
1.5.1 Transmittal Form
1.5.2 Submittal Format
1.5.2.1 Format of SD-01 Preconstruction Submittals
1.5.2.2 Format for SD-02 Shop Drawings
1.5.2.2.1 Drawing Identifaction
1.5.2.3 Format of SD-03 Product Data
1.5.2.3.1 Product Information
1.5.2.3.2 Standards
1.5.2.3.3 Data Submission
1.5.2.4 Format of SD-04 Samples
1.5.2.4.1 Sample Characteristics
1.5.2.4.2 Sample Incorporation
1.5.2.4.3 Comparison Sample
1.5.2.5 Format of SD-05 Design Data
1.5.2.6 Format of SD-06 Test Reports
1.5.2.7 Format of SD-07 Certificates
1.5.2.8 Format of SD-08 Manufacturer's Instructions
1.5.2.8.1 Standards
1.5.2.9 Format of SD-09 Manufacturer's Field Reports
1.5.2.10 Format of SD-10 Operation and Maintenance Data (O&M)
1.5.2.11 Format of SD-11 Closeout Submittals
1.5.3 Source Drawings for Shop Drawings

1.5.3.1 Source Drawings
1.5.3.2 Terms and Conditions
1.5.4 Electronic File Format
1.6 QUANTITY OF SUBMITTALS
1.6.1 Number of SD-01 Preconstruction Submittal Copies
1.6.2 Number of SD-02 Shop Drawing Copies
1.6.3 Number of SD-03 Product Data Copies
1.6.4 Number of SD-04 Samples
1.6.5 Number of SD-05 Design Data Copies
1.6.6 Number of SD-06 Test Report Copies
1.6.7 Number of SD-07 Certificate Copies
1.6.8 Number of SD-08 Manufacturer's Instructions Copies
1.6.9 Number of SD-09 Manufacturer's Field Report Copies
1.6.10 Number of SD-10 Operation and Maintenance Data Copies
1.6.11 Number of SD-11 Closeout Submittals Copies
1.7 INFORMATION ONLY SUBMITTALS
1.8 PROJECT SUBMITTAL REGISTER
1.8.1 Submittal Management
1.8.2 Design-Build Submittal Register
1.8.3 Preconstruction Use of Submittal Register
1.8.4 Contractor Use of Submittal Register
1.8.5 Approving Authority Use of Submittal Register
1.8.6 Action Codes
1.8.7 Delivery of Copies
1.9 VARIATIONS
1.9.1 Considering Variations
1.9.2 Proposing Variations
1.9.3 Warranting that Variations are Compatible
1.9.4 Review Schedule Extension
1.10 SCHEDULING
1.11 GOVERNMENT APPROVING AUTHORITY
1.11.1 Review Notations
1.12 DISAPPROVED SUBMITTALS
1.13 APPROVED SUBMITTALS
1.14 APPROVED SAMPLES
1.15 SUBMITTAL FORMS
1.15.1 Submittal Forms to be Used

PART 2 PRODUCTS

PART 3 EXECUTION

ATTACHMENTS:

ENG Form 4025-R

Appendix A - Submittal Register

-- End of Section Table of Contents --

SECTION 01 33 00

SUBMITTAL PROCEDURES
08/18

PART 1 GENERAL

1.1 SUMMARY

1.1.1 Submittal Information

The Contracting Officer may request submittals in addition to those specified when deemed necessary to adequately describe the work covered in the respective sections. Each submittal is to be complete and in sufficient detail to allow ready determination of compliance with contract requirements.

Units of weights and measures used on all submittals are to be the same as those used in the contract drawings.

1.1.2 Project Type

1.1.3 Submision of Submittals

Schedule and provide submittals requiring Government approval before acquiring the material or equipment covered thereby. Pick up and dispose of samples not incorporated into the work in accordance with manufacturer's Safety Data Sheets (SDS) and in compliance with existing laws and regulations.

1.2 DEFINITIONS

1.2.1 Submittal Descriptions (SD)

Submittal requirements are specified in the technical sections. Examples and descriptions of submittals identified by the Submittal Description (SD) numbers and titles follow:

SD-01 Preconstruction Submittals

Submittals that are required prior to or at the start of construction (work) or the next major phase of the construction on a multiphase contract.

Preconstruction Submittals include schedules and a tabular list of locations, features, and other pertinent information regarding products, materials, equipment, or components to be used in the work.

Certificates Of Insurance

Surety Bonds

List Of Proposed Subcontractors

List Of Proposed Products

Baseline Network Analysis Schedule (NAS)

Submittal Register

Schedule Of Prices Or Earned Value Report

Accident Prevention Plan

Work Plan

Quality Control (QC) plan

Environmental Protection Plan

SD-02 Shop Drawings

Drawings, diagrams and schedules specifically prepared to illustrate some portion of the work.

Diagrams and instructions from a manufacturer or fabricator for use in producing the product and as aids to the Contractor for integrating the product or system into the project.

Drawings prepared by or for the Contractor to show how multiple systems and interdisciplinary work will be coordinated.

SD-03 Product Data

Catalog cuts, illustrations, schedules, diagrams, performance charts, instructions and brochures illustrating size, physical appearance and other characteristics of materials, systems or equipment for some portion of the work.

Samples of warranty language when the contract requires extended product warranties.

SD-04 Samples

Fabricated or unfabricated physical examples of materials, equipment or workmanship that illustrate functional and aesthetic characteristics of a material or product and establish standards by which the work can be judged.

Color samples from the manufacturer's standard line (or custom color samples if specified) to be used in selecting or approving colors for the project.

Field samples and mock-ups constructed on the project site establish standards ensuring work can be judged. Includes assemblies or portions of assemblies that are to be incorporated into the project and those that will be removed at conclusion of the work.

SD-05 Design Data

Design calculations, mix designs, analyses or other data pertaining to a part of work.

Design submittals, design substantiation submittals and extensions of design submittals.

SD-06 Test Reports

Report signed by authorized official of testing laboratory that a material, product or system identical to the material, product or system to be provided has been tested in accord with specified requirements. Unless specified in another section, testing must have been within three years of date of contract award for the project.

Report that includes findings of a test required to be performed on an actual portion of the work or prototype prepared for the project before shipment to job site.

Report that includes finding of a test made at the job site or on sample taken from the job site, on portion of work during or after installation.

Investigation reports

Daily logs and checklists

Final acceptance test and operational test procedure

SD-07 Certificates

Statements printed on the manufacturer's letterhead and signed by responsible officials of manufacturer of product, system or material attesting that the product, system, or material meets specification requirements. Must be dated after award of project contract and clearly name the project.

Document required of Contractor, or of a manufacturer, supplier, installer or Subcontractor through Contractor. The document purpose is to further promote the orderly progression of a portion of the work by documenting procedures, acceptability of methods, or personnel qualifications.

Confined space entry permits

Text of posted operating instructions

SD-08 Manufacturer's Instructions

Preprinted material describing installation of a product, system or material, including special notices and (SDS)concerning impedances, hazards and safety precautions.

SD-09 Manufacturer's Field Reports

Documentation of the testing and verification actions taken by manufacturer's representative at the job site, in the vicinity of the job site, or on a sample taken from the job site, on a portion of the work, during or after installation, to confirm compliance with manufacturer's standards or instructions. The documentation must be signed by an authorized official of a testing laboratory or agency and state the test results; and indicate whether the material, product, or system has passed or failed the test.

Factory test reports.

SD-10 Operation and Maintenance Data

Data provided by the manufacturer, or the system provider, including manufacturer's help and product line documentation, necessary to maintain and install equipment, for operating and maintenance use by facility personnel.

Data required by operating and maintenance personnel for the safe and efficient operation, maintenance and repair of the item.

Data incorporated in an operations and maintenance manual or control system.

SD-11 Closeout Submittals

Documentation to record compliance with technical or administrative requirements or to establish an administrative mechanism.

Submittals required for Guiding Principle Validation (GPV) or Third Party Certification (TPC).

Special requirements necessary to properly close out a construction contract. For example, Record Drawings and as-built drawings. Also, submittal requirements necessary to properly close out a major phase of construction on a multi-phase contract.

1.2.2 Approving Authority

Office or designated person authorized to approve the submittal.

1.2.3 Work

As used in this section, on-site and off-site construction required by contract documents, including labor necessary to produce submittals, construction, materials, products, equipment, and systems incorporated or to be incorporated in such construction. In exception, excludes work to produce SD-01 submittals.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor QC approval. Submittals with an "S" are for inclusion in the Sustainability Notebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with this section.

SD-01 Preconstruction Submittals

Submittal Register; G

1.4 SUBMITTAL CLASSIFICATION

1.4.1 Government Approved (G)

Government approval is required for any variations from the Solicitation or the Accepted Proposal and for other items as designated by the Government.

Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR

CONSTRUCTION, submittals are considered to be "shop drawings."

1.4.2 Design-Build Submittal Classifications

1.4.2.1 Designer of Record Approved (DA)

Designer of Record (DOR) approval is required for extensions of design; critical materials; any variations from the Solicitation, the Accepted Proposal, or the completed design; equipment whose compatibility with the entire system must be checked; and other items as designated by the Contracting Officer. Provide the Government with the number of copies designated hereinafter of all DOR approved submittals. The Government may review any or all Designer of Record approved submittals for conformance with the Solicitation, the Accepted Proposal, and the completed design. The Government will review all submittals designated as varying from the Solicitation or Accepted Proposal, as described below. Provide design submittals in accordance with Section 01 33 16.00 10 DESIGN DATA (DESIGN AFTER AWARD). Generally, list design submittals under SD-05 Design Data.

1.4.2.2 Government Conformance Review of Design (CR)

The Government will review all intermediate and final design submittals for conformance with the technical requirements of the Solicitation. Section 01 33 16.00 10 DESIGN DATA (DESIGN AFTER AWARD) covers the design submittal and review process in detail. Review will be only for conformance with the applicable codes, standards, and contract requirements. Design data includes the design documents described in Section 01 33 16.00 10 DESIGN DATA (DESIGN AFTER AWARD).

1.4.2.3 Designer of Record Approved/Government Conformance Review (DA/CR)

1.4.2.3.1 Variations from the Accepted Design

DOR approval and the Government's concurrence are required for any proposed variation from the accepted design that still complies with the contract before the Contractor is authorized to proceed with material acquisition or installation. If necessary to facilitate the project schedule, before offical submission to the Government, the Contractor and the DOR may discuss with the Contracting Officer's Representative a submittal proposing a variation. However, the Government reserves the right to review the submittal before providing an opinion. In any case, the Government will not formally agree to or provide a preliminary opinion on any variation without the DOR's approval or recommended approval. The Government reserves the right to reject any design, variation that may affect furniture, furnishings, equipment selections, or operational decisions that were made, based on the reviewed and concurred design.

1.4.2.3.2 Substitutions

Unless prohibited or otherwise provided for elsewhere in the contract, where the Accepted Proposal named products, systems, materials or equipment by manufacturer, brand name, model number, or other specific identification, and the Contractor desires to substitute a manufacturer or model after award, submit a requested substitution for Government concurrence. Include substantiation, through identifying information and the DOR's approval, that the substitute meets the contract requirements and that it is equal in function, performance, quality, and salient features to that in the accepted contract proposal. If the contract otherwise prohibits substitutions of equal named products, systems, materials or

equipment by manufacturer, brand name, m,odel number or other specific identification, the request is considered a "variation" to the contract. Variations are discussed below in paragraphs: "DESIGNER OF RECORD APPROVED/GOVERNMENT APPROVED" and VARIATIONS.

1.4.2.4 Designer of Record Approved/Government Approved (DA/GA)

In addition to the above-stated requirements for proposed variations to the accepted design, both DOR and Government Approval and, where applicable, a contract modification are required before the Contractor is authorized to proceed with material acquisition or installation for any proposed variation to the contract (the Solicitation or the Accepted Proposal), that constitutes a change to the contract terms. The Government reserves the right to accept or reject any such proposed variation.

1.4.3 For Information Only

Submittals not requiring Government approval will be for information only. For Design-build construction all submittals not requiring DOR or Government approval will be for information only. Within the terms of the Contract Clause SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION, they are not considered to be "shop drawings."

1.4.4 Sustainability Reporting Submittals (S)

Submittals for Guiding Principle Validation (GPV) or Third Party Certification (TPC) are indicated with an "S" designation. These submittals are for information only and for use as specified in Section 01 33 29 SUSTAINABILITY REPORTING.

Schedule submittals for these items throughout the course of construction as provided; do not wait until closeout.

1.5 PREPARATION

1.5.1 Transmittal Form

Use the ENG Form 4025-R transmittal form for submitting both Government-approved and information-only submittals. Submit in accordance with the instructions on the reverse side of the form. These forms will be furnished to the Contractor. Properly complete this form by filling out all the heading blank spaces and identifying each item submitted. Exercise special care to ensure proper listing of the specification paragraph and sheet number of the contract drawings pertinent to the data submitted for each item.

1.5.2 Submittal Format

1.5.2.1 Format of SD-01 Preconstruction Submittals

When the submittal includes a document that is to be used in the project, or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

Paint and Repair Requirements

1.5.2.2 Format for SD-02 Shop Drawings

Provide shop drawings not less than 8 1/2 by 11 inches nor more than 30 by 42 inches, except for full-size patterns or templates. Prepare drawings to accurate size, with scale indicated, unless another form is required. Ensure drawings are suitable for reproduction and of a quality to produce clear, distinct lines and letters, with dark lines on a white background.

a. Include the nameplate data, size, and capacity on drawings. Also include applicable federal, military, industry, and technical society publication references.

b. Dimension drawings, except diagrams and schematic drawings. Prepare drawings demonstrating interface with other trades to scale. Use the same unit of measure for shop drawings as indicated on the contract drawings. Identify materials and products for work shown.

Present shop drawings sized 8 1/2 by 11 inches as part of the bound volume for submittals. Present larger drawings in sets. Submit an electronic copy of drawings in PDF format.

1.5.2.2.1 Drawing Identifaction

Include on each drawing the drawing title, number, date, and revision numbers and dates, in addition to information required in paragraph IDENTIFYING SUBMITTALS.

Number drawings in a logical sequence. Each drawing is to bear the number of the submittal in a uniform location next to the title block. Place the Government contract number in the margin, immediately below the title block, for each drawing.

Reserve a blank space, no smaller than 4 inches on the right-hand side of each sheet for the Government disposition stamp.

1.5.2.3 Format of SD-03 Product Data

Present product data submittals for each section as a complete, bound volume. Include a table of contents, listing the page and catalog item numbers for product data.

Indicate, by prominent notation, each product that is being submitted; indicate the specification section number and paragraph number to which it pertains.

1.5.2.3.1 Product Information

Supplement product data with material prepared for the project to satisfy the submittal requirements where product data does not exist. Identify this material as developed specifically for the project, with information and format as required for submission of SD-07 Certificates.

Provide product data in units used in the Contract documents. Where product data are included in preprinted catalogs with another unit, submit the dimensions in contract document units, on a separate sheet.

1.5.2.3.2 Standards

Where equipment or materials are specified to conform to industry or

technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.2.3.3 Data Submission

Collect required data submittals for each specific material, product, unit of work, or system into a single submittal that is marked for choices, options, and portions applicable to the submittal. Mark each copy of the product data identically. Partial submittals will not be accepted for expedition of the construction effort.

Submit the manufacturer's instructions before installation.

1.5.2.4 Format of SD-04 Samples

1.5.2.4.1 Sample Characteristics

Furnish samples in the following sizes, unless otherwise specified or unless the manufacturer has prepackaged samples of approximately the same size as specified:

a. Sample of Equipment or Device: Full size.

b. Sample of Materials Less Than 2 by 3 inches: Built up to 8 1/2 by 11 inches.

c. Sample of Materials Exceeding 8 1/2 by 11 inches: Cut down to 8 1/2 by 11 inches and adequate to indicate color, texture, and material variations.

d. Sample of Linear Devices or Materials: 10 inch length or length to be supplied, if less than 10 inches. Examples of linear devices or materials are conduit and handrails.

e. Sample Volume of Nonsolid Materials: Pint. Examples of nonsolid materials are sand and paint.

f. Color Selection Samples: 2 by 4 inches. Where samples are specified for selection of color, finish, pattern, or texture, submit the full set of available choices for the material or product specified. Sizes and quantities of samples are to represent their respective standard unit.

g. Sample Panel: 4 by 4 feet.

h. Sample Installation: 100 square feet.

1.5.2.4.2 Sample Incorporation

Reusable Samples: Incorporate returned samples into work only if so

specified or indicated. Incorporated samples are to be in undamaged condition at the time of use.

Recording of Sample Installation: Note and preserve the notation of any area constituting a sample installation, but remove the notation at the final clean-up of the project.

1.5.2.4.3 Comparison Sample

Samples Showing Range of Variation: Where variations in color, finish, pattern, or texture are unavoidable due to nature of the materials, submit sets of samples of not less than three units showing extremes and middle of range. Mark each unit to describe its relation to the range of the variation.

When color, texture, or pattern is specified by naming a particular manufacturer and style, include one sample of that manufacturer and style, for comparison.

1.5.2.5 Format of SD-05 Design Data

Provide design data and certificates on 8 1/2 by 11 inch paper. Provide a bound volume for submittals containing numerous pages.

1.5.2.6 Format of SD-06 Test Reports

Provide reports on 8 1/2 by 11 inch paper in a complete bound volume.

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.2.7 Format of SD-07 Certificates

Provide design data and certificates on 8 1/2 by 11 inch paper. Provide a bound volume for submittals containing numerous pages.

1.5.2.8 Format of SD-08 Manufacturer's Instructions

Present manufacturer's instructions submittals for each section as a complete, bound volume. Include the manufacturer's name, trade name, place of manufacture, and catalog model or number on product data. Also include applicable federal, military, industry, and technical-society publication references. If supplemental information is needed to clarify the manufacturer's data, submit it as specified for SD-07 Certificates.

Submit the manufacturer's instructions before installation.

1.5.2.8.1 Standards

Where equipment or materials are specified to conform to industry or technical-society reference standards of such organizations as the American National Standards Institute (ANSI), ASTM International (ASTM), National Electrical Manufacturer's Association (NEMA), Underwriters Laboratories (UL), or Association of Edison Illuminating Companies (AEIC), submit proof of such compliance. The label or listing by the specified organization will be acceptable evidence of compliance. In lieu of the label or listing, submit a certificate from an independent testing organization, competent to perform testing, and approved by the Contracting Officer. State on the certificate that the item has been tested in accordance with

the specified organization's test methods and that the item complies with the specified organization's reference standard.

1.5.2.9 Format of SD-09 Manufacturer's Field Reports

Provide reports on 8 1/2 by 11 inch paper in a complete bound volume.

By prominent notation, indicate each report in the submittal. Indicate the specification number and paragraph number to which each report pertains.

1.5.2.10 Format of SD-10 Operation and Maintenance Data (O&M)

Comply with the requirements specified in Section 01 78 23 OPERATION AND MAINTENANCE DATA for O&M Data format.

1.5.2.11 Format of SD-11 Closeout Submittals

When the submittal includes a document that is to be used in the project or is to become part of the project record, other than as a submittal, do not apply the Contractor's approval stamp to the document itself, but to a separate sheet accompanying the document.

Provide data in the unit of measure used in the contract documents.

1.5.3 Source Drawings for Shop Drawings

1.5.3.1 Source Drawings

The entire set of source drawing files (DWG) will not be provided to the Contractor. Request the specific Drawing Number for the preparation of shop drawings. Only those drawings requested to prepare shop drawings will be provided. These drawings are provided only after award.

1.5.3.2 Terms and Conditions

Data contained on these electronic files must not be used for any purpose other than as a convenience in the preparation of construction data for the referenced project. Any other use or reuse is at the sole risk of the Contractor and without liability or legal exposure to the Government. The Contractor must make no claim, and waives to the fullest extent permitted by law any claim or cause of action of any nature against the Government, its agents, or its subconsultants that may arise out of or in connection with the use of these electronic files. The Contractor must, to the fullest extent permitted by law, indemnify and hold the Government harmless against all damages, liabilities, or costs, including reasonable attorney's fees and defense costs, arising out of or resulting from the use of these electronic files.

These electronic source drawing files are not construction documents. Differences may exist between the source drawing files and the corresponding construction documents. The Government makes no representation regarding the accuracy or completeness of the electronic source drawing files, nor does it make representation to the compatibility of these files with the Contractor hardware or software. The Contractor is responsible for determining if any conflict exists. In the event that a conflict arises between the signed and sealed construction documents prepared by the Government and the furnished source drawing files, the signed and sealed construction documents govern. Use of these source drawing files does not relieve the Contractor of the duty to fully comply

with the contract documents, including and without limitation the need to check, confirm and coordinate the work of all contractors for the project. If the Contractor uses, duplicates or modifies these electronic source drawing files for use in producing construction data related to this contract, remove all previous indication of ownership (seals, logos, signatures, initials and dates).

1.5.4 Electronic File Format

Provide submittals in electronic format, with the exception of material samples required for SD-04 Samples items. In addition to the electronic submittal, provide three hard copies of the submittals. Compile the submittal file as a single, complete document, to include the Transmittal Form described within. Name the electronic submittal file specifically according to its contents, and coordinate the file naming convention with the Contracting Officer. Electronic files must be of sufficient quality that all information is legible. Use PDF as the electronic format, unless otherwise specified or directed by the Contracting Officer. Generate PDF files from original documents with bookmarks so that the text included in the PDF file is searchable and can be copied. If documents are scanned, optical character resolution (OCR) routines are required. Index and bookmark files exceeding 30 pages to allow efficient navigation of the file. When required, the electronic file must include a valid electronic signature or a scan of a signature.

E-mail electronic submittal documents smaller than 10MB to an e-mail address as directed by the Contracting Officer. Provide electronic documents over 10 MB on an optical disc or through an electronic file sharing system such as the AMRDEC SAFE Web Application located at the following website: https://safe.amrdec.army.mil/safe/.

1.6 QUANTITY OF SUBMITTALS

1.6.1 Number of SD-01 Preconstruction Submittal Copies

Unless otherwise specified, submit three sets of administrative submittals.

1.6.2 Number of SD-02 Shop Drawing Copies

Submit three copies of submittals of shop drawings requiring review and approval by a QC organization. Submit three copies of shop drawings requiring review and approval by the Contracting Officer.

1.6.3 Number of SD-03 Product Data Copies

Submit in compliance with quantity requirements specified for shop drawings.

1.6.4 Number of SD-04 Samples

a. Submit two samples, or two sets of samples showing the range of variation, of each required item. One approved sample or set of samples will be retained by the approving authority and one will be returned to the Contractor.

b. Submit one sample panel or provide one sample installation where directed. Include components listed in the technical section or as directed.

c. Submit one sample installation, where directed.

d. Submit one sample of nonsolid materials.

1.6.5 Number of SD-05 Design Data Copies

Submit in compliance with quantity requirements specified for shop drawings.

1.6.6 Number of SD-06 Test Report Copies

Submit in compliance with quantity and quality requirements specified for shop drawings, other than field test results that will be submitted with QC reports.

1.6.7 Number of SD-07 Certificate Copies

Submit in compliance with quantity requirements specified for shop drawings.

1.6.8 Number of SD-08 Manufacturer's Instructions Copies

Submit in compliance with quantity requirements specified for shop drawings.

1.6.9 Number of SD-09 Manufacturer's Field Report Copies

Submit in compliance with quantity and quality requirements specified for shop drawings other than field test results that will be submitted with QC reports.

1.6.10 Number of SD-10 Operation and Maintenance Data Copies

Submit three copies of O&M data to the Contracting Officer for review and approval.

1.6.11 Number of SD-11 Closeout Submittals Copies

Unless otherwise specified, submit three sets of administrative submittals.

1.7 INFORMATION ONLY SUBMITTALS

Submittals without a "G" designation must be certified by the QC manager and submitted to the Contracting Officer for information-only. Approval of the Contracting Officer is not required on information only submittals. The Contracting Officer will mark "receipt acknowledged" on submittals for information and will return only the transmittal cover sheet to the Contractor. Normally, submittals for information only will not be returned. However, the Government reserves the right to return unsatisfactory submittals and require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe.

1.8 PROJECT SUBMITTAL REGISTER

A sample Project Submittal Register showing items of equipment and materials for when submittals are required by the specifications is

provided as "Appendix A - Submittal Register."

1.8.1 Submittal Management

Prepare and maintain a submittal register, as the work progresses. Do not change data that is output in columns (c), (d), (e), and (f) as delivered by Government; retain data that is output in columns (a), (g), (h), and (i) as approved. As an attachment, provide a submittal register showing items of equipment and materials for which submittals are required by the specifications. This list may not be all-inclusive and additional submittals may be required. Maintain a submittal register for the project in accordance with Section 01 45 00.15 10 RESIDENT MANAGEMENT SYSTEM CONTRACTOR MODE(RMS CM). The Government will provide the initial submittal register in electronic format with the following fields completed, to the extent that will be required by the Government during subsequent usage.

Column (c): Lists specification section in which submittal is required.

Column (d): Lists each submittal description (SD Number. and type, e.g., SD-02 Shop Drawings) required in each specification section.

Column (e): Lists one principal paragraph in each specification section where a material or product is specified. This listing is only to facilitate locating submitted requirements. Do not consider entries in column (e) as limiting the project requirements.

Thereafter, the Contractor is to track all submittals by maintaining a complete list, including completion of all data columns and all dates on which submittals are received by and returned by the Government.

1.8.2 Design-Build Submittal Register

The Designer of Record develops a complete list of submittals during design and identify required submittals in the specifications, and use the list to prepare the Submittal Register. The list may not be all inclusive and additional submittals may be required by other parts of the contract. Complete the submittal register and submit it to the Contracting Officer for approval within 30 calendar days after Notice to Proceed. The approved submittal register will serve as a scheduling document for submittals and will be used to control submittal actions throughout the contract period. Coordinate the submit dates and need dates with dates in the Contractor prepared progress schedule. Submit monthly or until all submittals have been satisfactorily completed, updates to the submittal register showing the Contractor action codes and actual dates with Government action codes. Revise the submittal register when the progress schedule is revised and submit both for approval.

1.8.3 Preconstruction Use of Submittal Register

Submit the submittal register. Include the QC plan and the project schedule. Verify that all submittals required for the project are listed and add missing submittals. Coordinate and complete the following fields on the register submitted with the QC plan and the project schedule:

Column (a) Activity Number: Activity number from the project

schedule.

Column (g) Contractor Submit Date: Scheduled date for the approving authority to receive submittals.

Column (h) Contractor Approval Date: Date that Contractor needs approval of submittal.

Column (i) Contractor Material: Date that Contractor needs material delivered to Contractor control.

1.8.4 Contractor Use of Submittal Register

Update the following fields in the Government-furnished submittal register program or equivalent fields in the program used by the Contractor with each submittal throughout the contract.

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (j) Action Code (k): Date of action used to record Contractor's review when forwarding submittals to QC.

Column (l) Date submittal transmitted.

Column (q) Date approval was received.

1.8.5 Approving Authority Use of Submittal Register

Update the following fields:

Column (b) Transmittal Number: List of consecutive, Contractor-assigned numbers.

Column (l) Date submittal was recieved.

Column (m) through (p) Dates of review actions.

Column (q) Date of return to Contractor.

1.8.6 Action Codes

1.8.7 Delivery of Copies

Submit an updatd electronic copy of the submittal register to the Contracting Officer with each invoice request. Provide an updated Submittal Register monthly regardless of whether an invoice is submitted.

1.9 VARIATIONS

Variations from contract requirements require Contracting Officer approval pursuant to contract Clause FAR 52.236-21 Specifications and Drawings for Construction, and will be considered where advantageous to the Government.

1.9.1 Considering Variations

Discussion of variations with the Contracting Officer before submission will help ensure that functional and quality requirements are met and minimize rejections and resubmittals. When contemplating a variation that

results in lower cost, consider submission of the variation as a Value Engineering Change Proposal (VECP).

Specifically point out variations from contract requirements in transmittal letters. Failure to point out variations may cause the Government to require rejection and removal of such work at no additional cost to the Government.

1.9.2 Proposing Variations

When proposing variation, deliver a written request to the Contracting Officer, with documentation of the nature and features of the variation and why the variation is desirable and beneficial to Government. Include the DOR's written analysis and approval. If lower cost is a benefit, also include an estimate of the cost savings. In addition to documentation required for variation, include the submittals required for the item. Clearly mark the proposed variation in all documentation.

Check the column "variation" of ENG Form 4025 for submittals that include variations proposed by the Contractor. Set forth in writing the reason for any variations and note such variations on the submittal. The Government reserves the right to rescind inadvertent approval of submittals containing unnoted variations.

1.9.3 Warranting that Variations are Compatible

When delivering a variation for approval, the Contractor warrants that this contract has been reviewed to establish that the variation, if incorporated, will be compatible with other elements of work.

1.9.4 Review Schedule Extension

In addition to the normal submittal review period, a period of 14 calendar days will be allowed for the Government to consider submittals with variations.

1.10 SCHEDULING

Schedule and submit concurrently product data and shop drawings covering component items forming a system or items that are interrelated. Submit pertinent certifications at the same time. No delay damages or time extensions will be allowed for time lost in late submittals. .

a. Coordinate scheduling, sequencing, preparing, and processing of submittals with performance of work so that work will not be delayed by submittal processing. The Contractor is responsible for additional time required for Government reviews resulting from required resubmittals. The review period for each resubmittal is the same as for the initial submittal.

b. Submittals required by the contract documents are listed on the submittal register. If a submittal is listed in the submittal register but does not pertain to the contract work, the Contractor is to include the submittal in the register and annotate it "N/A" with a brief explanation. Approval by the Contracting Officer does not relieve the Contractor of supplying submittals required by the contract documents but that have been omitted from the register or marked "N/A."

c. Resubmit the submittal register and annotate it monthly with actual

submission and approval dates. When all items on the register have been fully approved, no further resubmittal is required.

Contracting Officer review will be completed within 14 calendar days after the date of submission.

1.11 GOVERNMENT APPROVING AUTHORITY

When the approving authority is the Contracting Officer, the Government will:

a. Note the date on which the submittal was received.

b. Review submittals for approval within the scheduling period specified and only for conformance with project design concepts and compliance with contract documents.

c. Identify returned submittals with one of the actions defined in paragraph REVIEW NOTATIONS and with comments and markings appropriate for the action indicated.

Upon completion of review of submittals requiring Government approval, stamp and date submittals. 2 copies of the submittal will be retained by the Contracting Officer and 1 copies of the submittal will be returned to the Contractor. If the Government performs a conformance review of other Designer of Record approved submittals, the submittals will be identified and returned, as described above.

1.11.1 Review Notations

Submittals will be returned to the Contractor with the following notations:

a. Submittals marked "approved" or "accepted" authorize proceeding with the work covered.

b. Submittals marked "approved as noted" or "approved, except as noted, resubmittal not required," authorize proceeding with the work covered provided that the Contractor takes no exception to the corrections.

c. Submittals marked "not approved," "disapproved," or "revise and resubmit" indicate incomplete submittal or noncompliance with the contract requirements or design concept. Resubmit with appropriate changes. Do not proceed with work for this item until the resubmittal is approved.

d. Submittals marked "not reviewed" indicate that the submittal has been previously reviewed and approved, is not required, does not have evidence of being reviewed and approved by Contractor, or is not complete. A submittal marked "not reviewed" will be returned with an explanation of the reason it is not reviewed. Resubmit submittals returned for lack of review by Contractor or for being incomplete, with appropriate action, coordination, or change.

e. Submittals marked "receipt acknowledged" indicate that submittals have been received by the Government. This applies only to "information-only submittals" as previously defined.

1.12 DISAPPROVED SUBMITTALS

Make corrections required by the Contracting Officer. If the Contractor

considers any correction or notation on the returned submittals to constitute a change to the contract drawings or specifications, give notice to the Contracting Offficer as required under the FAR clause titled CHANGES. The Contractor is responsible for the dimensions and design of connection details and the construction of work. Failure to point out variations may cause the Government to require rejection and removal of such work at the Contractor's expense.

If changes are necessary to submittals, make such revisions and resubmit in accordance with the procedures above. No item of work requiring a submittal change is to be accomplished until the changed submittals are approved.

1.13 APPROVED SUBMITTALS

The Contracting Officer's approval of submittals is not to be construed as a complete check, and indicates only that the design, general method of construction, materials, detailing, and other information appear to meet the Solicitation and Accepted Proposal.

Approval or acceptance by the Government for a submittal does not relieve the Contractor of the responsibility for meeting the contract requirements or for any error that may exist, because under the Quality Control (QC) requirements of this contract, the Contractor is responsible for ensuring information contained with in each submittal accurately conforms with the requirements of the contract documents.

After submittals have been approved or accepted by the Contracting Officer, no resubmittal for the purpose of substituting materials or equipment will be considered unless accompanied by an explanation of why a substitution is necessary.

1.14 APPROVED SAMPLES

Approval of a sample is only for the characteristics or use named in such approval and is not be construed to change or modify any contract requirements. Before submitting samples, provide assurance that the materials or equipment will be available in quantities required in the project. No change or substitution will be permitted after a sample has been approved.

Match the approved samples for materials and equipment incorporated in the work. If requested, approved samples, including those that may be damaged in testing, will be returned to the Contractor, at its expense, upon completion of the contract. Unapproved samples will also be returned to the Contractor at its expense, if so requested.

Failure of any materials to pass the specified tests will be sufficient cause for refusal to consider, under this contract, any further samples of the same brand or make as that material. The Government reserves the right to disapprove any material or equipment that has previously proved unsatisfactory in service.

Samples of various materials or equipment delivered on the site or in place may be taken by the Contracting Officer for testing. Samples failing to meet contract requirements will automatically void previous approvals. Replace such materials or equipment to meet contract requirements.

Paint and Repair Requirements

1.15 SUBMITTAL FORMS1.15.1 Submittal Forms to be Used

Use United States Army Corps of Enngineers form 4025-R

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 33 29

SUSTAINABILITY REPORTING

02/17

PART 1 GENERAL

1.1 REFERENCES
1.2 SUMMARY
1.3 SUBMITTALS
1.4 GUIDING PRINCIPLES VALIDATION (GPV)
1.4.1 Sustainability Action Plan
1.4.2 Costs
1.4.3 Calculations
1.5 SUSTAINABILITY SUBMITTALS
1.5.1 High Performance Sustainable Building (HPSB) Checklist
1.5.1.1 HPSB Checklist Submittals
1.5.2 "S" Submittals for Sustainability Documentation
1.5.3 Sustainability eNotebook
1.5.3.1 Sustainability eNotebook Submittal Schedule
1.6 DOCUMENTATION REQUIREMENTS
1.6.1 Reduce Volatile Organic Compounds (VOC) (Low Emitting Materials)
1.6.2 Recycled Content
1.6.3 Bio-Based Products
1.6.4 Waste Material Management (Recycling – Construction)

PART 2 PRODUCTS

3.1 SUSTAINABILITY COORDINATION
3.1.1 Coordinating Sustainability Documentation Progress
3.2 [Enter Appropriate Subpart Title Here]

-- End of Section Table of Contents --

SECTION 01 33 29

SUSTAINABILITY REPORTING
02/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

COUNCIL ON ENVIRONMENTAL QUALITY (CEQ) (WHITE HOUSE)

HPSB Guiding Principles	(2016) Guiding Principles for Sustainable Federal Buildings and Determining Compliance with the Guiding Principles for Sustainable Federal Buildings

U.S. DEPARTMENT OF AGRICULTURE (USDA)

FSRIA 9002	Farm Security and Rural Investment Act Section 9002 (USDA Biopreferred Program)

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 247	Comprehensive Procurement Guideline for Products Containing Recovered Materials

1.2 SUMMARY

This specification includes general requirements and procedures for this project to be constructed and documented per the federally mandated High Performance and Sustainable Building or HPSB Guiding Principles (GP), , UFC 1-200-02 High Performance and Sustainable Building Requirements, and other requirements identified in this specification.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to this section. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Preliminary High Performance and Sustainable Building Checklist; G

Sustainability Action Plan; G

Preliminary Sustainability eNotebook; G

SD-11 Closeout Submittals

Final High Performance and Sustainable Building Checklist; G

Final Sustainability eNotebook; G

Amended Final Sustainability eNotebook; G

Amended Final High Performance and Sustainable Building Checklist; G

1.4 GUIDING PRINCIPLES VALIDATION (GPV)

Provide construction related sustainability documentation to verify achievement of HPSB Guiding Principles Validation (GPV). Provide the following for GPV:

a. Refer to HPSB Checklist at the end of this specification section. These requirements are based on legislative mandates that must be met by all projects. (Multiple checklists indicate multiple buildings that require HPSB tracking.)

b. No variations to the HPSB Checklist are allowed without written consent from the Contracting Officer. Immediately bring to the attention of the Contracting Officer any changes that impact meeting the approved HPSB Guiding Principles Requirements for this project.

c. All work, including "S" submittals, required to incorporate the applicable HPSB Guiding Principles Requirements indicated on the HPSB Checklist and in this contract.

d. Sustainability Action Plan

e. Construction related documentation for the project Sustainability eNotebook, and keep updated with regularly-scheduled construction meetings. Include construction related documentation containing the following components;

(1) HPSB Checklist

(2) Sustainability Action Plan

(3) Documentation illustrating HPSB Guiding Principles Requirements compliance (including "S" submittals)

1.4.1 Sustainability Action Plan

Include the following information in the Sustainability Action Plan:

a. Planned method to achieve each construction related GP requirement.

b. For each designated construction related HPSB Guiding Principles Requirements that is applicable, as defined in UFC 1-200-02, provide justification narrative explaining what precludes achieving specific sustainability requirement or goal. Provide analysis of particular requirement and level to which project is able to comply. Final government-approved narrative(s) must be included with the HPSB Checklist submittal.

c. Name and contact information for: Point of Contact (POC) responsible for ensuring sustainability goals are accomplished and documentation is assembled.

Paint and Repair Requirements

1.4.2 Costs

Bear all costs associated with constructing, demonstrating, and documenting that project complies with approved HPSB Guiding Principles Requirements.

1.4.3 Calculations

Provide calculations, product data, labels and product certifications, required in this section to demonstrate compliance with the HPSB Guiding Principles Requirements.

1.5 SUSTAINABILITY SUBMITTALS

Provide HPSB Checklist and other documentation in the Sustainability eNotebook to indicate compliance with the sustainability requirements of the project.

1.5.1 High Performance Sustainable Building (HPSB) Checklist

Provide construction documentation that provides proof of and supports compliance with the completed HPSB Checklist.

1.5.1.1 HPSB Checklist Submittals

Submit updated HPSB Checklist with each Sustainability eNotebook submittal. Attach final HPSB Checklist(s) to draft final DD1354 Real Property Record Submittal.

1.5.2 "S" Submittals for Sustainability Documentation

Submit the GPV and TPC sustainability documentation required in this specification as "S" submittals in all affected UFGS Sections.

a. Highlight GPV and TPC compliance data in "S" submittal.

b. Add "S" submittals to the Sustainability eNotebook only after submittal approval, and bookmark them as required in paragraph SUSTAINABILITY eNOTEBOOK below.

c. Ensure all approved "S" submittals (the sustainability documentation requirements) are included in each Sustainability eNotebook submittal.

1.5.3 Sustainability eNotebook

The Sustainability eNotebook is an electronic organizational file that serves as a repository for all required sustainability submittals. To support documentation of compliance with an approved HPSB and TPC checklist, provide and maintain a comprehensive and current Sustainability eNotebook Sustainability eNotebook must contain all required data to support full compliance with the HPSB Guiding Principles Requirements, including:

a. HPSB checklist

b. Sustainable Action Plan

c. Calculations

d. Labels

e. "S" submittals (sustainability documentation requirements)

f. Certifications, assessments, or validations

Provide sustainability eNotebook in the form of an Adobe PDF file; bookmark each HPSB Guiding Principles Requirement , TPC requirement,and sub-bookmark at each document. Match format to HPSB Guiding Principles numbering system indicated herein. Maintain up-to-date information, spreadsheets, templates, and other required documentation with each current submittal. For TPC projects, provide a second Table of contents using TPC numbering system, for maintaining documentation unique to TPC.

Contracting Officer may deduct from the monthly progress payment accordingly if Sustainability eNotebook information is not current, until information is updated and on track per project goals.

1.5.3.1 Sustainability eNotebook Submittal Schedule

Provide Sustainability eNotebook Submittals at the following milestones of the project:

a. Preliminary Sustainability eNotebook

Submit preliminary Sustainability eNotebook for approval at the Pre-construction conference. Include Preliminary High Performance and Sustainable Building Checklist and TPC checklist.

b. Construction Progress Meetings. Provide up-to-date GP and TPC documentation in the Sustainability eNotebook and TPC Online tool for each meeting.

c. Final Sustainability eNotebook

Provide up-to-date Sustainability eNotebook at the Beneficial Occupancy Date (BOD). Final progress payment retainage may be held by Contracting Officer until final sustainability documentation is complete. Submit three electronic copies of the Final Sustainability eNotebook on DVDs to the Government. Include Final High Performance and Sustainable Building Checklist.

d. Amended Final Sustainability eNotebook

Amend and resubmit the Final Sustainability eNotebook to include post-occupancy corrections, updates, and requirements. Include Amended Final High Performance and Sustainable Building Checklist. Final progress payment retainage may be held by Contracting Officer until amended final sustainability documentation is complete. Submit one final electronic copies of the Amended Final Sustainability eNotebook Submittal on DVDs to the Government no longer than 30 days after the GP, TPC designated data collection period.

1.6 DOCUMENTATION REQUIREMENTS

a. Incorporate each of the following HPSB Guiding Principles Requirements into project construction; and provide documentation that proves compliance with each listed requirement. Items below are organized according to the HPSB Guiding Principles. For life-cycle cost analysis

requirements, one document with all analyses is acceptable, with Contracting Officer approval.

b. For each of the following paragraphs that require the use of products listed on Government-required websites, provide documentation of the process used to select products, or process used to determine why listed products do not meet project performance requirements.

1.6.1 Reduce Volatile Organic Compounds (VOC) (Low Emitting Materials)

Meet the requirements of Table 3-1 at the end of this specification. Provide the following documentation:

Provide certifications or labels that demonstrate compliance with cited requirements.

1.6.2 Recycled Content

Comply with 40 CFR 247. Refer to https://www.epa.gov/smm/comprehensive-procurement-guideline-cpg-program for assistance identifying products cited in 40 CFR 247. Selected products must comply with non-proprietary requirements of the Federal Acquisition Regulation, and must meet performance requirements. Provide the following documentation:

a. Manufacturers' documents stating the recycled content by material, or written justification for claiming one of the exceptions allowed on the cited website.

b. Substitutions: Submit for Government approval, proposed alternative products or systems that provide equivalent performance and appearance and have greater contribution to project recycled content requirements. For all such proposed substitutions, submit with the Sustainability Action Plan accompanied by product data demonstrating equivalence.

c. In order to complete compliance with FAR 52.223-9 Estimate of Percentage of Recovered Material Content for EPA Designated Items, refer to submittal requirement for recycled/recovered material content in Section 01 78 00.

1.6.3 Bio-Based Products

Provide products and material composed of the highest percentage of biobased materials (including rapidly renewable resources and certified sustainably harvested products), consistent with FSRIA 9002 USDA BioPreferred Program, to the maximum extent possible without jeopardizing the intended end use or detracting from the overall quality delivered to the end user. Use only supplies and materials of a type and quality that conform to applicable specifications and standards.

Comply with FSRIA 9002 USDA BioPreferred Program. Refer to https://www.biopreferred.gov/BioPreferred/ for the product categories and BioPreferred Catalog. Selected products must comply with non-proprietary requirements of the Federal Acquisition Regulation, and must meet performance requirements. Provide the following documentation:

a. USDA BioPreferred label for each product; for bio-based products used

on project but not listed with BioPreferred program, provide bio-based content and percentage.

b. In order to complete compliance with FAR 52.223-2 Affirmative Procurement of Biobased Products Under Service and Construction Contracts, refer to submittal requirement for biobased products in Section 01 78 00.

1.6.4 Waste Material Management (Recycling – Construction)

Divert construction debris from landfill disposal where markets or on-site recycling exists, and provide documentation in accordance with Section 01 74 19 CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT.

PART 2 PRODUCTS

Not used.

PART 3 EXECUTION

3.1 SUSTAINABILITY COORDINATION

3.1.1 Coordinating Sustainability Documentation Progress

Provide sustainability focus and coordination at the following meetings to achieve sustainability goals. The designated TPC accredited sustainability professional responsible for GP and TPC documentation must participate in the following meetings to coordinate documentation completion.

a. Pre-Construction Conference: Discuss the following: HPSB Checklists, Sustainability Action Plan, Construction submittal requirements and schedule, individuals responsible for achieving each Guiding Principle Requirement and TPC prerequisite and credit.

b. Construction Progress Meetings: Review GP and TPC sustainability requirements with project team including contractor and sub-contractor representatives. Demonstrate GP and TPC documentation is being collected and updated to the Sustainability eNotebook and TPC Online tool.

(1) For TPC that include on-site visit by third party representative, execute, coordinate, and facilitate the visit.

(2) Facility Turnover Meetings: Review Sustainability eNotebook, and TPC Online submission for completeness and identify any outstanding issues relating to final documentation requirements.

(3) Final Sustainability eNotebook Review

3.2 [Enter Appropriate Subpart Title Here][Enter Appropriate Subpart Title Here][Enter Appropriate Subpart Title Here]TABLE 3-1 VOLATILE ORGANIC COMPOUNDS (VOC) (LOW EMITTING MATERIALS) REQUIREMENTS

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ASHRAE 189.1 section 8.4.2 (Materials)(Interior Applications Only)

MATERIAL CATEGORY	**EMISSIONS REQUIREMENT**		**MATERIALS WITH ADDED VOC REQUIREMENT**	**MATERIAL CATEGORY**
Paints and Coatings	**CDPH/EHLB/Standard method V1.1 (California Section 01350)** (Use "office" or "classroom" space limits for all applications)	or	Flat and nonflat topcoats, primers, undercoaters, and anti-corrosive coatings	**Green Seal Standard GS-11**

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ASHRAE 189.1 section 8.4.2 (Materials)(Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	MATERIAL CATEGORY
Paints and Coatings	**CDPH/EHLB/Standard method V1.1 (California Section 01350)** (Use "office" or "classroom" space limits for all applications)	or	Concrete/masonry sealers (waterproofing concrete/masonry sealers), concrete curing compounds, dry fog coatings, faux finishing coatings, fire resistive coatings, floor coatings, graphic arts (sign) coatings, industrial maintenance coatings, mastic texture coatings, metallic pigmented coatings, multicolor coatings, pretreatment wash primers, reactive penetrating sealers, recycled coatings, shellacs (clear and opaque), specialty primers, stains, wood coatings (clear wood finishes), wood preservatives, and zinc primers	**California Air Resources Board (CARB) Suggested Control Measure for Architectural Coatings** or **SCAQMD Rule 1113**

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ASHRAE 189.1 section 8.4.2 (Materials)(Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	MATERIAL CATEGORY
Paints and Coatings	**CDPH/EHLB/Standard method V1.1 (California Section 01350)** (Use "office" or "classroom" space limits for all applications)	or	Basement specialty coatings, high-temperature coatings, low solids coatings, stone consolidants, swimming-pool coatings, tub- and tile-refining coatings, and waterproofing membranes	**California Air Resources Board (CARB) Suggested Control Measure for Architectural Coatings**
				none

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements

Source: ASHRAE 189.1 section 8.4.2 (Materials)(Interior Applications Only)

MATERIAL CATEGORY	EMISSIONS REQUIREMENT		MATERIALS WITH ADDED VOC REQUIREMENT	MATERIAL CATEGORY
Composite Wood, Wood Structural Panel, and Agrifiber Products particleboard medium density fiberboard (MDF) wheatboard strawboard panel substrates door cores **no added urea-formaldehyde resins** including laminating adhesives for composite wood and agrifiber assemblies	Third-party certification (approved by CARB) of **California Air Resource Board's (CARB) regulation**, Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products		none	
	CDPH/EHLB/Standard method V1.1 (California Section 01350) (Use "office" or "classroom" space limits for all applications) (except: Structural panel components such as plywood, particle board, wafer board, and oriented strand board identified as "EXPOSURE 1," "EXTERIOR," or "HUD-APPROVED" are considered acceptable for interior use.)			

TABLE 3-1 Volatile Organic Compounds (VOC) (Low Emitting Materials) Requirements Source: ASHRAE 189.1 section 8.4.2 (Materials)(Interior Applications Only)				
MATERIAL CATEGORY	**EMISSIONS REQUIREMENT**		**MATERIALS WITH ADDED VOC REQUIREMENT**	**MATERIAL CATEGORY**

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS

11/14

PART 1 GENERAL

1.1 REFERENCES
1.2 ORDERING INFORMATION

PART 2 PRODUCTS

PART 3 EXECUTION

-- End of Section Table of Contents --

SECTION 01 42 00

SOURCES FOR REFERENCE PUBLICATIONS
11/14

PART 1 GENERAL

1.1 REFERENCES

Various publications are referenced in other sections of the specifications to establish requirements for the work. These references are identified in each section by document number, date and title. The document number used in the citation is the number assigned by the standards producing organization (e.g. ASTM B564 Standard Specification for Nickel Alloy Forgings). However, when the standards producing organization has not assigned a number to a document, an identifying number has been assigned for reference purposes.

1.2 ORDERING INFORMATION

The addresses of the standards publishing organizations whose documents are referenced in other sections of these specifications are listed below, and if the source of the publications is different from the address of the sponsoring organization, that information is also provided.

AMERICAN CONCRETE INSTITUTE INTERNATIONAL (ACI)
38800 Country Club Drive
Farmington Hills, MI 48331-3439
Ph: 248-848-3700
Fax: 248-848-3701
E-mail: bkstore@concrete.org
Internet: http://www.concrete.org

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)
1330 Kemper Meadow Drive
Cincinnati, OH 45240
Ph: 513-742-2020 or 513-742-6163
Fax: 513-742-3355
E-mail: mail@acgih.org
Internet: http://www.acgih.org

AMERICAN FOREST FOUNDATION (AFF)
American Tree Farm System
2000 M Street, NW, Suite 550
Washington, DC 20036
Ph: 202-765-3660
Fax: 202-827-7924
Email: info@treefarmsystem.org
Internet: https://www.treefarmsystem.org/standards-review

AMERICAN HARDBOARD ASSOCIATION (AHA)
1210 West Northwest Highway
Palatine, IL 60067
Ph: 847-934-8800
Fax: 847-934-8803
E-mail: aha@hardboard.org

Internet: http://domensino.com/AHA/

AMERICAN INDUSTRIAL HYGIENE ASSOCIATION (AIHA)
3141 Fairview Park Dr, Suite 777
Falls Church, VA 22042
Tel: 703-849-8888
Fax: 703-207-3561
E-mail: infonet@aiha.org
Internet http://www.aiha.org

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)
7012 South Revere Parkway, Suite 140
Centennial, CO 80112
Ph: 503-639-0651
Fax: 503-684-8928
E-mail: info@aitc-glulam.org
Internet: http://www.aitc-glulam.org

AMERICAN LUMBER STANDARDS COMMITTEE (ALSC)
P.O. Box 210
Germantown, MD 20875-0210
Ph: 301-972-1700
Fax: 301-540-8004
E-mail: alsc@alsc.org
Internet: http://www.alsc.org

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)
1899 L Street, NW,11th Floor
Washington, DC 20036
Ph: 202-293-8020
Fax: 202-293-9287
E-mail: storemanager@ansi.org
Internet: http://www.ansi.org/

AMERICAN RAILWAY ENGINEERING AND MAINTENANCE-OF-WAY ASSOCIATION (AREMA)
4501 Forbes Blvd., Suite 130
Lanham, MD 20706
Ph: 301-459-3200
Fax: 301-459-8077
E-mail: bcaruso@arema.org
Internet: http://www.arema.org

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)
1801 Alexander Bell Drive
Reston, VA 20191
Ph: 703-295-6300; 800-548-2723
E-mail: member@asce.org
Internet: http://www.asce.org

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)
1800 East Oakton Street
Des Plaines, IL 60018
Ph: 847-699-2929
Internet: http://www.asse.org

AMERICAN WOOD COUNCIL (AWC)
222 Catoctin Circle SE, Suite 201
Leesburg, VA 20175

Ph: 800-890-7732
Fax: 412-741-0609
E-mail: publications@awc.org
Internet: http://www.awc.org

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)
P.O. Box 361784
Birmingham, AL 35236-1784
Ph: 205-733-4077
Fax: 205-733-4075
Internet: http://www.awpa.com

APA - THE ENGINEERED WOOD ASSOCIATION (APA)
7011 South 19th St.
Tacoma, WA 98466-5333
Ph: 253-565-6600
Fax: 253-565-7265
Internet: http://www.apawood.org

ASME INTERNATIONAL (ASME)
Two Park Avenue, M/S 10E
New York, NY 10016-5990
Ph: 800-843-2763
Fax: 973-882-1717
E-mail: customercare@asme.org
Internet: http://www.asme.org

ASTM INTERNATIONAL (ASTM)
100 Barr Harbor Drive, P.O. Box C700
West Conshohocken, PA 19428-2959
Ph: 877-909-2786
Internet: http://www.astm.org

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)
355 Lexington Avenue, 15th Floor
New York, NY 10017
Ph: 212-297-2122
Fax: 212-370-9047
Internet: http://www.buildershardware.com

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)
PO Box 997377, MS 0500
Sacramento, CA 95899-7377
Ph: 916-558-1784
Internet: http://www.cdph.ca.gov

COUNCIL ON ENVIRONMENTAL QUALITY (CEQ) (WHITE HOUSE)
722 Jackson Place
Washington DC 20506
Internet: https://www.whitehouse.gov/administration/eop/ceq

CSA GROUP (CSA)
178 Rexdale Blvd.
Toronto, ON, Canada M9W 1R3
Ph: 416-747-4044
Fax: 416-747-2510
E-mail: sales@csagroup.org
Internet: http://www.csagroup.org/us/en/home

FM GLOBAL (FM)
270 Central Avenue
P.O. Box 7500
Johnston, RI 02919-4923
Ph: 877-364-6726
Fax: 401-275-3029
E-mail: servicedesk.myrisk@fmglobal.com
Internet: http://www.fmglobal.com

FOREST STEWARDSHIP COUNCIL (FSC)
212 Third Avenue North
Suite 445
Minneapolis, MN 55401
Ph: 612-353-4511
E-mail: info@us.fcs.org
Internet: https://us.fsc.org/

GLASS ASSOCIATION OF NORTH AMERICA (GANA)
800 SW Jackson St., Suite 1500
Topeka, KS 66612-1200
Ph: 785-271-0208
E-mail: gana@glasswebsite.com
Internet: http://www.glasswebsite.com

HARDWOOD PLYWOOD AND VENEER ASSOCIATION (HPVA)
1825 Michael Faraday Dr.
Reston, VA 20190
Ph: 703-435-2900
Fax: 703-435-2537
E-mail: hpva@hpva.org
Internet: http://www.hpva.org

INSULATING GLASS MANUFACTURERS ALLIANCE (IGMA)
27 N. Wacker Dr. Suite 365
Chicago, IL 60606-2800
Ph: 613-233-1510
Fax: 613-482-9436
E-mail: enquiries@igmaonline.org
Internet: http://www.igmaonline.org

INTERNATIONAL CODE COUNCIL (ICC)
500 New Jersey Avenue, NW
6th Floor, Washington, DC 20001
Ph: 800-786-4452 or 888-422-7233
E-mail: order@iccsafe.org
Internet: www.iccsafe.org

MASTER PAINTERS INSTITUTE (MPI)
2800 Ingleton Avenue
Burnaby, BC CANADA V5C 6G7
Ph: 1-888-674-8937
Fax: 1-888-211-8708
E-mail: info@paintinfo.com or techservices@mpi.net
Internet: http://www.mpi.net/

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)
1 Batterymarch Park
Quincy, MA 02169-7471

Ph: 617-770-3000
Fax: 617-770-0700
Internet: http://www.nfpa.org

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)
6830 Raleigh LaGrange Road
PO Box 34518
Memphis, TN 38184
Ph: 901-377-1818
Store: 901-399-7563
Internet: http://www.nhla.org

NATIONAL PARK SERVICE (NPS)
National Park Service
1849 C Street, NW
Washington, DC 20240
Ph: 202-513-7156
http://www.nps.gov

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)
272 Tuttle Road
Cumberland, ME 04021
Ph: 207-829-6901
Fax: 207-829-4293
E-mail: info@nelma.org
Internet: http://www.nelma.org

PROGRAMME FOR ENDORSEMENT OF FOREST CERTIFICATION (PEFC)
10, Route de l'Aeroport
Case Postale 638
1215 Geneva - Switzerland
Ph: +41 (22) 799-4540
Fax: +41 (22) 799-4550
Internet: http://www.pefc.org

REDWOOD INSPECTION SERVICE (RIS) OF THE CALIFORNIA REDWOOD ASSOCIATION (CRA)
818 Grayson Road, Suite 201
Pleasant Hill, CA 94523
Ph: 925-935-1499
Fax: 925-935-1496
E-Mail: ris@calredwood.org
Internet: http://www.redwoodinspection.com/

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)
4201 Lafayette Center Drive
Chantilly, VA 20151-1219
Ph: 703-803-2980
Fax: 703-803-3732
Internet: http://www.smacna.org

SOCIETY FOR PROTECTIVE COATINGS (SSPC)
40 24th Street, 6th Floor
Pittsburgh, PA 15222
Ph: 412-281-2331
Fax: 412-281-9992
E-mail: info@sspc.org
Internet: http://www.sspc.org

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)
21865 Copley Drive
Diamond Bar, CA 91765
Ph: 909-396-2000
E-mail: webinquiry@aqmd.gov
Internet: http://www.aqmd.gov

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)
665 Rodi Road, Suite 305
Pittsburgh, PA 15235
Ph: 412-244-0440
Fax: 412-244-9090
E-Mail: member-services@cypressinfo.org
Internet: http://www.cypressinfo.org

SOUTHERN PINE INSPECTION BUREAU (SPIB)
P.O. Box 10915
Pensacola, FL 32504-0915
Ph: 850-434-2611
Fax: 850-433-5594
Internet: http://www.spib.org

SUSTAINABLE FOREST INITIATIVE (SFI)
2121 K Street NW
Suite 750
Washington, DC 20037
Ph: 202-596-3450
Fax: 202-596-3451
Internet: http://www.sfiprogram.org

THE MASONRY SOCIETY (TMS)
105 South Sunset Street, Suite Q
Longmont, CO 80501-9215
Ph: 303-939-9700
Fax: 303-541-9215
E-mail: info@masonrysociety.org
http://www.masonrysociety.org

TRUSS PLATE INSTITUTE (TPI)
218 N. Lee Street, Suite 312
Alexandria, VA 22314
Ph: 703-683-1010
Fax: 866-501-4012
E-mail: info@tpinst.org
Internet: http://www.tpinst.org

U.S. ARMY CORPS OF ENGINEERS (USACE)
CRD-C DOCUMENTS available on Internet:
http://www.wbdg.org/ccb/browse_cat.php?c=68
Order Other Documents from:
USACE Publications Depot
Attn: CEHEC-IM-PD
2803 52nd Avenue
Hyattsville, MD 20781-1102
Ph: 301-394-0081
Fax: 301-394-0084
E-mail: pubs-army@usace.army.mil
Internet: http://www.publications.usace.army.mil/

or
http://www.hnc.usace.army.mil/Missions/Engineering/TECHINFO.aspx

U.S. DEPARTMENT OF AGRICULTURE (USDA)
Order AMS Publications from:
AGRICULTURAL MARKETING SERVICE (AMS)
Seed Regulatory and Testing Branch
801 Summit Crossing Place, Suite C
Gastonia, NC 28054-2193
Ph: 704-810-8871
Fax: 704-852-4189
E-mail: seed.ams@usda.gov
Internet: http://www.ams.usda.gov/lsg/seed.htm
Order Other Publications from:
U.S. Department of Agriculture, Rural Utilities Program
USDA Rural Development, Room 4051-S
Mail Stop 1510
1400 Independence Avenue SW
Washington, DC 20250-1510
Phone: (202) 720-9540
TTY: (800) 877-8339 (Federal Relay Service)
Fax: (202) 720-1725
Internet: http://www.rurdev.usda.gov/utilities_lp.html

U.S. DEPARTMENT OF COMMERCE (DOC)
1401 Constitution Avenue, NW
Washington, DC 20230
Ph: 202-482-2000
Internet: http://www.commerce.gov/
Order Publications From:
National Technical Information Service (NTIS)
Alexandria, VA 22312
Ph: 703-605-6050 or 800-533-6847
E-mail: customerservice@ntis.gov
Internet: http://www.ntis.gov

U.S. DEPARTMENT OF ENERGY (DOE)
1000 Independence Avenue Southwest
Washington, D.C. 20585
Internet: www.eere.energy.gov

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (HUD)
HUD User
P.O. Box 23268
Washington, DC 20026-3268
Ph: 800-245-2691 or 202-708-3178
TDD: 800-927-7589
Fax: 202-708-9981
Internet: http://www.huduser.org

U.S. GENERAL SERVICES ADMINISTRATION (GSA)
General Services Administration
1275 First St. NE
Washington, DC 20417
Ph: 202-501-1231
Internet: http://www.gsaelibrary.gsa.gov/ElibMain/home.do
Obtain documents from:
Acquisition Streamlining and Standardization Information System (ASSIST)

Internet: https://assist.dla.mil/online/start/; account registration required

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)
8601 Adelphi Road
College Park, MD 20740-6001
Ph: 866-272-6272
Fax: 301-837-0483
Internet: http://www.archives.gov
Order documents from:
Superintendent of Documents
U.S.Government Printing Office (GPO)
710 North Capitol Street, NW
Washington, DC 20401
Ph: 202-512-1800
Fax: 202-512-2104
E-mail: contactcenter@gpo.gov
Internet: http://www.gpoaccess.gov

UNDERWRITERS LABORATORIES (UL)
2600 N.W. Lake Road
Camas, WA 98607-8542
Ph: 877-854-3577
E-mail: CEC.us@us.ul.com
Internet: http://www.ul.com/
UL Directories available through IHS at http://www.ihs.com

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)
P.O. Box 23145
Portland, OR 97281
Ph: 503-639-0651
Fax: 503-684-8928
E-mail: info@wclib.org
Internet: http://www.wclib.org

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)
1500 SW First Ave., Suite 870
Portland, OR 97201
Ph: 503-224-3930
Fax: 503-224-3934
E-mail: info@wwpa.org
Internet: http://www.wwpa.org

WINDOW AND DOOR MANUFACTURERS ASSOCIATION (WDMA)
330 N Wabash Avenue, Suite 2000
Chicago, IL 60611
Ph: 312-321-6802
E-mail: wdma@wdma.com
Internet: http://www.wdma.com

WOOD MOULDING AND MILLWORK PRODUCERS ASSOCIATION (WMMPA)
507 First Street
Woodland, CA 95695
Ph: 530-661-9591 or 800-550-7889
Fax: 530-661-9586
E-mail: info@wmmpa.com
Internet: http://www.wmmpa.com

PART 2 PRODUCTS

Not used

PART 3 EXECUTION

Not used

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 01 - GENERAL REQUIREMENTS

SECTION 01 45 00.10 20

QUALITY CONTROL FOR MINOR CONSTRUCTION

02/10

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 INFORMATION FOR THE CONTRACTING OFFICER (KO)
1.4 QC PROGRAM REQUIREMENTS
1.4.1 Preliminary Work Authorized Prior to Acceptance
1.4.2 Acceptance
1.4.3 Notification of Changes
1.5 QC ORGANIZATION
1.5.1 QC Manager
1.5.1.1 Duties
1.5.1.2 Qualifications
1.5.1.3 Construction Quality Management Training
1.5.2 Alternate QC Manager Duties and Qualifications
1.6 QC PLAN
1.6.1 Requirements
1.7 COORDINATION AND MUTUAL UNDERSTANDING MEETING
1.8 QC MEETINGS
1.9 THREE PHASES OF CONTROL
1.9.1 Preparatory Phase
1.9.2 Initial Phase
1.9.3 Follow-Up Phase
1.9.4 Additional Preparatory and Initial Phases
1.9.5 Notification of Three Phases of Control for Off-Site Work
1.10 SUBMITTAL REVIEW AND APPROVAL
1.11 TESTING
1.11.1 Accreditation Requirements
1.11.2 Laboratory Accreditation Authorities
1.11.3 Capability Check
1.11.4 Test Results
1.12 QC CERTIFICATIONS
1.12.1 Contractor Quality Control Report Certification
1.12.2 Invoice Certification
1.12.3 Completion Certification
1.13 COMPLETION INSPECTIONS
1.13.1 Punch-Out Inspection
1.13.2 Pre-Final Inspection
1.13.3 Final Acceptance Inspection
1.14 DOCUMENTATION
1.14.1 Quality Control Validation
1.14.2 As-Built Drawings
1.15 NOTIFICATION ON NON-COMPLIANCE

PART 2 PRODUCTS

PART 3 EXECUTION

-- End of Section Table of Contents --

SECTION 01 45 00.10 20

QUALITY CONTROL FOR MINOR CONSTRUCTION
02/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2014) Safety and Health Requirements Manual

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

QC Plan; G

Submit a QC plan within 15 calendar days after receipt of Notice of Award.

1.3 INFORMATION FOR THE CONTRACTING OFFICER (KO)

Prior to commencing work on construction, the Contractor can obtain a single copy set of the current report forms from the KO. The report forms will consist of the Contractor Production Report, Contractor Production Report (Continuation Sheet), Contractor Quality Control (CQC) Report, CQC Report (Continuation Sheet), Preparatory Phase Checklist, Initial Phase Checklist, Rework Items List, and Testing Plan and Log.

Deliver the following to the KO:

a. CQC Report: Original and one copy, by 10:00 AM the next working day after each day that work is performed;

b. Contractor Production Report: Original and one copy by 10:00 AM the next working day after each day that work is performed;

c. Preparatory Phase Checklist: Original attached to the original CQC Report and one copy attached to each copy;

d. Initial Phase Checklist: Original attached to the original CQC Report and one copy attached to each copy;

e. Field Test Reports: One copy, within the week after the test is performed, attached to the CQC Report;

f. QC Meeting Minutes: One copy, within two working days after the meeting; and

g. QC Certifications: As required by the paragraph entitled "QC Certifications."

1.4 QC PROGRAM REQUIREMENTS

Establish and maintain a QC program as described in this section. The QC program consists of a QC Manager, a QC plan, a Coordination and Mutual Understanding Meeting, QC meetings, three phases of control, submittal review and approval, testing, and QC certifications and documentation necessary to provide materials, equipment, workmanship, fabrication, construction and operations which comply with the requirements of this contract. The QC program shall cover on-site and off-site work and shall be keyed to the work sequence. No work or testing may be performed unless the QC Manager is on the work site.

1.4.1 Preliminary Work Authorized Prior to Acceptance

The only work that is authorized to proceed prior to the acceptance of the QC plan is mobilization of storage and office trailers, temporary utilities, and surveying.

1.4.2 Acceptance

Acceptance of the QC plan is required prior to the start of construction. The KO reserves the right to require changes in the QC plan and operations as necessary, including removal of personnel, to ensure the specified quality of work. The KO reserves the right to interview any member of the QC organization at any time in order to verify the submitted qualifications.

1.4.3 Notification of Changes

Notify the KO, in writing, of any proposed change, including changes in the QC organization personnel, a minimum of seven calendar days prior to a proposed change. Proposed changes shall be subject to the acceptance by the KO.

1.5 QC ORGANIZATION

1.5.1 QC Manager

1.5.1.1 Duties

Provide a QC Manager at the work site to implement and manage the QC program. In addition to implementing and managing the QC program, the QC Manager may perform the duties of project superintendent. The QC Manager is required to attend the Coordination and Mutual Understanding Meeting, conduct the QC meetings, perform the three phases of control, perform submittal review and approval, ensure testing is performed and provide QC certifications and documentation required in this contract. The QC Manager is responsible for managing and coordinating the three phases of control and documentation performed by others.

1.5.1.2 Qualifications

An individual with a minimum of 5 years combined experience as a superintendent, inspector, QC Manager, project manager, or construction manager on similar size and type construction contracts which included the major trades that are part of this contract. The individual must be familiar with the requirements of the EM 385-1-1 and have experience in the areas of hazard identification and safety compliance.

1.5.1.3 Construction Quality Management Training

In addition to the above experience and education requirements, the QC Manager shall have completed the course Construction Quality Management for Contractors and will have a current certificate.

1.5.2 Alternate QC Manager Duties and Qualifications

Designate an alternate for the QC Manager to serve in the event of the designated QC Manager's absence. The period of absence may not exceed two weeks at one time, and not more than 30 workdays during a calendar year. The qualification requirements for the Alternate QC Manager shall be the same as for the QC Manager.

1.6 QC PLAN

1.6.1 Requirements

Provide, for acceptance by the KO, a QC plan submitted in a three-ring binder that covers both on-site and off-site work and includes the following with a table of contents listing the major sections identified with tabs.

I. QC ORGANIZATION: A chart showing the QC organizational structure and its relationship to the production side of the organization.

II. NAMES AND QUALIFICATIONS: In resume format, for each person in the QC organization. Include the CQM for Contractors course certification required by the paragraph entitled "Construction Quality Management Training".

III. DUTIES, RESPONSIBILITY AND AUTHORITY OF QC PERSONAL: Of each person in the QC organization.

IV. OUTSIDE ORGANIZATIONS: A listing of outside organizations such as architectural and consulting engineering firms that will be employed by the Contractor and a description of the services these firms will provide.

V. APPOINTMENT LETTERS: Letters signed by an officer of the firm appointing the QC Manager and Alternate QC Manager and stating that they are responsible for managing and implementing the QC program as described in this contract. Include in this letter the QC Manager's authority to direct the removal and replacement of non-conforming work.

VI. SUBMITTAL PROCEDURES AND INITIAL SUBMITTAL REGISTER: Procedures for reviewing, approving and managing submittals. Provide the name(s) of the person(s) in the QC organization authorized to review and certify submittals prior to approval.

VII. TESTING LABORATORY INFORMATION: Testing laboratory information required by the paragraphs "Accredited Laboratories" or "Testing Laboratory Requirements", as applicable.

VIII. TESTING PLAN AND LOG: A Testing Plan and Log that includes the tests required, referenced by the specification paragraph number requiring the test, the frequency, and the person responsible for each test.

IX. PROCEDURES TO COMPLETE REWORK ITEMS: Procedures to identify, record, track and complete rework items.

X. DOCUMENTATION PROCEDURES: Use Government formats.

XI. LIST OF DEFINABLE FEATURES: A Definable Feature of Work (DFOW) is a task, which is separate and distinct from other tasks, has the same control requirements and work crews. The list shall be cross-referenced to the Contractor's Construction Schedule and the specification sections. For projects requiring a Progress Chart, the list of definable features of work shall include but not be limited to all items of work on the schedule. For projects requiring a Network Analysis Schedule, the list of definable features of work shall include but not be limited to all critical path activities.

XII. PROCEDURES FOR PERFORMING THREE PHASES OF CONTROL: For each DFOW provide Preparatory and Initial Phase Checklists. Each list shall include a breakdown of quality checks that will be used when performing the quality control functions, inspections, and tests required by the contract documents. The preparatory and initial phases shall be conducted with a view towards obtaining quality construction by planning ahead and identifying potential problems.

XIII. PERSONNEL MATRIX: Not Applicable.

XIV. PROCEDURES FOR COMPLETION INSPECTION: See the paragraph entitled "COMPLETION INSPECTIONS".

XV. TRAINING PROCEDURES AND TRAINING LOG: Not Applicable.

1.7 COORDINATION AND MUTUAL UNDERSTANDING MEETING

During the Pre-Construction conference and prior to the start of construction, discuss the QC program required by this contract. The purpose of this meeting is to develop a mutual understanding of the QC details, including documentation, administration for on-site and off-site work, and the coordination of the Contractor's management, production and the QC personnel. At the meeting, the Contractor will be required to explain how three phases of control will be implemented for each DFOW. Contractor's personnel required to attend shall include the QC Manager, project manager, and superintendent. Minutes of the meeting will be prepared by the QC Manager and signed by both the Contractor and the KO. The Contractor shall provide a copy of the signed minutes to all attendees. Repeat the coordination and mutual understanding meeting when a new QC Manager is appointed.

1.8 QC MEETINGS

After the start of construction, the QC Manager shall conduct QC meetings once every two weeks at the work site with the superintendent and the foreman responsible for the ongoing and upcoming work. The QC Manager shall prepare the minutes of the meeting and provide a copy to the KO within two working days after the meeting. As a minimum, the following shall be accomplished at each meeting:

a. Review the minutes of the previous meeting;

b. Review the schedule and the status of work and rework;

c. Review the status of submittals;

d. Review the work to be accomplished in the next two weeks and documentation required;

e. Resolve QC and production problems (RFIs, etc.);

f. Address items that may require revising the QC plan; and

g. Review Accident Prevention Plan (APP).

1.9 THREE PHASES OF CONTROL

The three phases of control shall adequately cover both on-site and off-site work and shall include the following for each DFOW.

1.9.1 Preparatory Phase

Notify the KO at least two work days in advance of each preparatory phase. Conduct the preparatory phase with the superintendent and the foreman responsible for the definable feature of work. Document the results of the preparatory phase actions in the daily CQC Report and in the QC checklist. Perform the following prior to beginning work on each definable feature of work:

a. Review each paragraph of the applicable specification sections;

b. Review the contract drawings;

c. Verify that appropriate shop drawings and submittals for materials and equipment have been submitted and approved. Verify receipt of approved factory test results, when required;

d. Review the testing plan and ensure that provisions have been made to provide the required QC testing;

e. Examine the work area to ensure that the required preliminary work has been completed;

f. Examine the required materials, equipment and sample work to ensure that they are on hand and conform to the approved shop drawings and submitted data;

g. Review the APP and appropriate Activity Hazard Analysis (AHA) to ensure that applicable safety requirements are met, and that required Safety Data Sheets (SDS) are submitted; and

h. Discuss specific controls used and the construction methods and the approach that will be used to provide quality construction by planning ahead and identifying potential problems for each DFOW.

1.9.2 Initial Phase

Notify the KO at least two work days in advance of each initial phase. When construction crews are ready to start work on a DFOW, conduct the Initial Phase with the foreman responsible for that DFOW. Observe the initial segment of the work to ensure that it complies with contract requirements. Document the results of the Initial Phase in the daily CQC Report and in the QC checklist. Perform the following for each DFOW:

a. Establish the quality of workmanship required;

b. Resolve conflicts;

c. Ensure that testing is performed by the approved laboratory; and

d. Check work procedures for compliance with the APP and the appropriate AHA to ensure that applicable safety requirements are met.

1.9.3 Follow-Up Phase

Perform the following for on-going work daily, or more frequently as necessary, until the completion of each DFOW and document in the daily CQC Report and in the QC checklist:

a. Ensure the work is in compliance with contract requirements;

b. Maintain the quality of workmanship required;

c. Ensure that testing is performed by the approved laboratory;

d. Ensure that rework items are being corrected; and

e. Assure manufacturers representatives have performed necessary inspections, if required.

1.9.4 Additional Preparatory and Initial Phases

Additional preparatory and initial phases shall be conducted on the same DFOW if the quality of on-going work is unacceptable, if there are changes in the applicable QC organization, if there are changes in the on-site production supervision or work crew, if work on a DFOW is resumed after substantial period of inactivity, or if other problems develop.

1.9.5 Notification of Three Phases of Control for Off-Site Work

Notify the KO at least two weeks prior to the start of the preparatory and initial phases.

1.10 SUBMITTAL REVIEW AND APPROVAL

Procedures for submission, review, and approval of submittals are described in the submittal section of the specification.

1.11 TESTING

Except as stated otherwise in the specification sections, perform sampling and testing required under this contract.

1.11.1 Accreditation Requirements

Construction materials testing laboratories must be accredited by a laboratory accreditation authority and will be required to submit a copy of the Certificate of Accreditation and Scope of Accreditation. The laboratory's scope of accreditation must include the appropriate ASTM standards (i.e.; E 329, C 1077, D 3666, D 3740, A 880, E 543) listed in the technical sections of the specifications. Laboratories engaged in Hazardous Materials Testing shall meet the requirements of OSHA and EPA. The policy applies to the specific laboratory performing the actual testing, not just the "Corporate Office."

1.11.2 Laboratory Accreditation Authorities

Laboratory Accreditation Authorities include the National Voluntary Laboratory Accreditation Program (NVLAP) administered by the National Institute of Standards and Technology, the American Association of State Highway and Transportation Officials (AASHTO), International Accreditation Services, Inc. (IAS), U. S. Army Corps of Engineers Materials Testing Center (MTC), the American Association for Laboratory Accreditation (A2LA), the Washington Association of Building Officials (WABO) (Approval authority for WABO is limited to projects within Washington State), and the Washington Area Council of Engineering Laboratories (WACEL) (Approval authority by WACEL is limited to projects within the NAVFAC WASH and Public Works Center Washington geographical area).

1.11.3 Capability Check

The KO retains the right to check laboratory equipment in the proposed laboratory and the laboratory technician's testing procedures, techniques, and other items pertinent to testing, for compliance with the standards set forth in this contract.

1.11.4 Test Results

Cite applicable Contract requirements, tests or analytical procedures used. Provide actual results and include a statement that the item tested or analyzed conforms or fails to conform to specified requirements. If the item fails to conform, notify the KO immediately. Conspicuously stamp the cover sheet for each report in large red letters "CONFORMS" or "DOES NOT CONFORM" to the specification requirements, whichever is applicable. Test results shall be signed by a testing laboratory representative authorized to sign certified test reports. Furnish the signed reports, certifications, and other documentation to the KO.

1.12 QC CERTIFICATIONS

1.12.1 Contractor Quality Control Report Certification

Each CQC Report shall contain the following statement: "On behalf of the Contractor, I certify that this report is complete and correct and equipment and material used and work performed during this reporting period is in compliance with the contract drawings and specifications to the best of my knowledge except as noted in this report."

1.12.2 Invoice Certification

Furnish a certificate to the KO with each payment request, signed by the QC Manager, attesting that as-built drawings are current and attesting that the work for which payment is requested, including stored material, is in compliance with contract requirements.

1.12.3 Completion Certification

Upon completion of work under this contract, the QC Manager shall furnish a certificate to the KO attesting that "the work has been completed, inspected, tested and is in compliance with the contract."

1.13 COMPLETION INSPECTIONS

1.13.1 Punch-Out Inspection

Near the completion of all work or any increment thereof established by a completion time stated in the Contract clause "Commencement, Prosecution, and Completion of Work," or stated elsewhere in the specifications, the QC Manager shall conduct an inspection of the work and develop a punch list of items which do not conform to the approved drawings and specifications. Include in the punch list any remaining items of the "Rework Items List", which were not corrected prior to the Punch-Out inspection. The punch list shall include the estimated date by which the deficiencies will be corrected. A copy of the punch list shall be provided to the KO. The QC Manager or staff shall make follow-on inspections to ascertain that all deficiencies have been corrected. Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government "Pre-Final Inspection".

1.13.2 Pre-Final Inspection

The Government and QC manager will perform this inspection to verify that the facility is complete and ready to be occupied. A Government pre-final punch list may be developed as a result of this inspection. The QC Manager shall ensure that all items on this list are corrected prior to notifying the Government that a "Final" inspection with the customer can be scheduled. Any items noted on the "Pre-Final" inspection shall be corrected in a timely manner and shall be accomplished before the contract completion date for the work or any particular increment thereof if the project is divided into increments by separate completion dates.

1.13.3 Final Acceptance Inspection

The QC Manager, the superintendent, or other Contractor management personnel and the KO will be in attendance at this inspection. Additional Government personnel may be in attendance. The final acceptance inspection will be formally scheduled by the KO based upon results of the "Pre-Final Inspection". Notice shall be given to the KO at least 14 days prior to the final inspection. The notice shall state that all specific items previously identified to the Contractor as being unacceptable will be complete by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the KO to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause "Inspection of Construction".

1.14 DOCUMENTATION

Maintain current and complete records of on-site and off-site QC program operations and activities. The forms identified under the paragraph "INFORMATION FOR THE CONTRACTING OFFICER (KO)" shall be used. Reports are required for each day work is performed. Account for each calendar day throughout the life of the contract. Every space on the forms must be filled in. Use N/A if nothing can be reported in one of the spaces. The superintendent and the QC Manager must prepare and sign the Contractor Production and CQC Reports, respectively. The reporting of work shall be identified by terminology consistent with the construction schedule. In the "remarks" section in this report which will contain pertinent information including directions received, problems encountered during construction, work progress and delays, conflicts or errors in the drawings or specifications, field changes, safety hazards encountered, instructions given and corrective actions taken, delays encountered and a record of visitors to the work site. For each remark given, identify the Schedule Activity No. that is associated with the remark.

1.14.1 Quality Control Validation

Establish and maintain the following in a series of three ring binders. Binders shall be divided and tabbed as shown below. These binders shall be readily available to the Government's Quality Assurance Team during all business hours.

a. All completed Preparatory and Initial Phase Checklists, arranged by specification section.

b. All milestone inspections, arranged by Activity/Event Number.

c. A current up-to-date copy of the Testing and Plan Log with supporting field test reports, arranged by specification section.

d. Copies of all contract modifications, arranged in numerical order. Also include documentation that modified work was accomplished.

e. A current up-to-date copy of the Rework Items List.

f. Maintain up-to-date copies of all punch lists issued by the QC Staff on the Contractor and Sub-Contractors and all punch lists issued by the Government.

1.14.2 As-Built Drawings

The QC Manager is required to review the as-built drawings, required by Section 01 78 00 CLOSEOUT SUBMITTALS, are kept current on a daily basis and marked to show deviations, which have been made from the Contract drawings. Ensure each deviation has been identified with the appropriate modifying documentation, e.g. PC number, modification number, RFI number, etc. The QC Manager shall initial each deviation or revision. Upon completion of work, the QC Manager shall submit a certificate attesting to the accuracy of the as-built drawings prior to submission to the KO.

1.15 NOTIFICATION ON NON-COMPLIANCE

The KO will notify the Contractor of any detected non-compliance with the foregoing requirements. The Contractor shall take immediate corrective

action. If the contractor fails or refuses to correct the non-compliant work, the KO will issue a non compliance notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the KO may issue an order stopping all or part of the work until satisfactory corrective action has been taken. The Contractor shall make no part of the time lost due to such stop orders the subject of claim for extension of time, for excess costs, or damages.

PART 2 PRODUCTS

Not Used

PART 3 EXECUTION

Not Used

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 02 - EXISTING CONDITIONS

SECTION 02 41 00

DEMOLITION AND DECONSTRUCTION

05/10

PART 1 GENERAL

1.1 REFERENCES
1.2 PROJECT DESCRIPTION
1.2.1 Demolition/Deconstruction Plan
1.2.2 General Requirements
1.3 ITEMS TO REMAIN IN PLACE
1.3.1 Existing Construction Limits and Protection
1.3.2 Weather Protection
1.3.3 Trees
1.3.4 Utility Service
1.3.5 Facilities
1.4 BURNING
1.5 SUBMITTALS
1.6 QUALITY ASSURANCE
1.6.1 Dust and Debris Control
1.7 PROTECTION
1.7.1 Traffic Control Signs
1.7.2 Protection of Personnel
1.8 RELOCATIONS
1.9 EXISTING CONDITIONS

PART 2 PRODUCTS

2.1 FILL MATERIAL

PART 3 EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED
3.1.1 Utilities and Related Equipment
3.1.1.1 General Requirements
3.1.1.2 Disconnecting Existing Utilities
3.1.2 Masonry
3.1.3 Concrete
3.1.4 Carpentry
3.1.5 Patching
3.2 DISPOSITION OF MATERIAL
3.2.1 Title to Materials
3.2.2 Reuse of Materials and Equipment
3.2.3 Salvaged Materials and Equipment
3.2.4 Unsalvageable and Non-Recyclable Material
3.3 CLEANUP
3.4 DISPOSAL OF REMOVED MATERIALS
3.4.1 Regulation of Removed Materials
3.4.2 Removal to Spoil Areas on Government Property
3.4.3 Removal from Government Property

3.5 REUSE OF SALVAGED ITEMS

-- End of Section Table of Contents --

SECTION 02 41 00

DEMOLITION AND DECONSTRUCTION
05/10

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)

ASSE/SAFE A10.6	(2006) Safety Requirements for Demolition Operations

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2014) Safety and Health Requirements Manual

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

40 CFR 61	National Emission Standards for Hazardous Air Pollutants

1.2 PROJECT DESCRIPTION

1.2.1 Demolition/Deconstruction Plan

Prepare a Demolition Plan Deconstruction Plan and submit proposed salvage, demolition, deconstruction, and removal procedures for approval before work is started. Include in the plan procedures for careful removal and disposition of materials specified to be salvaged, coordination with other work in progress, a disconnection schedule of utility services, a detailed description of methods and equipment to be used for each operation and of the sequence of operations. Coordinate with Waste Management Plan. Provide procedures for safe conduct of the work in accordance with EM 385-1-1. Plan shall be approved by Contracting Officer prior to work beginning.

1.2.2 General Requirements

Do not begin demolition or deconstruction until authorization is received from the Contracting Officer. Remove rubbish and debris from the project site; do not allow accumulations inside or outside the buildings. The work includes demolition, deconstruction, salvage of identified items and materials, and removal of resulting rubbish and debris. Remove rubbish and debris from Government property daily, unless otherwise directed. Store materials that cannot be removed daily in areas specified by the Contracting Officer. In the interest of occupational safety and health, perform the work in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections.

Paint and Repair Requirements

1.3 ITEMS TO REMAIN IN PLACE

Take necessary precautions to avoid damage to existing items to remain in place, to be reused, or to remain the property of the Government. Repair or replace damaged items as approved by the Contracting Officer. Coordinate the work of this section with all other work indicated. Construct and maintain shoring, bracing, and supports as required. Ensure that structural elements are not overloaded. Increase structural supports or add new supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract. Do not overload structural elements pavements to remain. Provide new supports and reinforcement for existing construction weakened by demolition, deconstruction, or removal work. Repairs, reinforcement, or structural replacement require approval by the Contracting Officer prior to performing such work.

1.3.1 Existing Construction Limits and Protection

Do not disturb existing construction beyond the extent indicated or necessary for installation of new construction. Provide temporary shoring and bracing for support of building components to prevent settlement or other movement. Provide protective measures to control accumulation and migration of dust and dirt in all work areas. Remove dust, dirt, and debris from work areas daily.

1.3.2 Weather Protection

For portions of the building to remain, protect building interior and materials and equipment from the weather at all times. Where removal of existing roofing is necessary to accomplish work, have materials and workmen ready to provide adequate and temporary covering of exposed areas.

1.3.3 Trees

Protect trees within the project site which might be damaged during demolition or deconstruction, and which are indicated to be left in place, by a 6 foot high fence. Erect and secure fence a minimum of 5 feet from the trunk of individual trees or follow the outer perimeter of branches or clumps of trees. Replace any tree designated to remain that is damaged during the work under this contract with like-kind or as approved by the Contracting Officer.

1.3.4 Utility Service

Maintain existing utilities indicated to stay in service and protect against damage during demolition and deconstruction operations. Prior to start of work, .

1.3.5 Facilities

Protect electrical and mechanical services and utilities. Where removal of existing utilities and pavement is specified or indicated, provide approved barricades, temporary covering of exposed areas, and temporary services or connections for electrical and mechanical utilities. Floors, roofs, walls, columns, pilasters, and other structural components that are designed and constructed to stand without lateral support or shoring, and are determined to be in stable condition, must remain standing without additional bracing, shoring, or lateral support until demolished or deconstructed, unless directed otherwise by the Contracting Officer. Ensure that no elements

determined to be unstable are left unsupported and place and secure bracing, shoring, or lateral supports as may be required as a result of any cutting, removal, deconstruction, or demolition work performed under this contract.

1.4 BURNING

The use of burning at the project site for the disposal of refuse and debris will not be permitted.

1.5 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Demolition Plan; G
Deconstruction Plan; G
Existing Conditions

SD-07 Certificates

Notification; G

SD-11 Closeout Submittals

Receipts

1.6 QUALITY ASSURANCE

Submit timely notification of demolition deconstruction and renovation projects to Federal, State, regional, and local authorities in accordance with 40 CFR 61, Subpart M. Notify the Regional Office of the United States Environmental Protection Agency (USEPA) State's environmental protection agency local air pollution control district/agency and the Contracting Officer in writing 10 working days prior to the commencement of work in accordance with 40 CFR 61, Subpart M. Comply with federal, state, and local hauling and disposal regulations. In addition to the requirements of the "Contract Clauses," conform to the safety requirements contained in ASSE/SAFE A10.6. Comply with the Environmental Protection Agency requirements specified. Use of explosives will not be permitted.

1.6.1 Dust and Debris Control

Prevent the spread of dust and debris to occupied portions of the building and avoid the creation of a nuisance or hazard in the surrounding area. Do not use water if it results in hazardous or objectionable conditions such as, but not limited to, ice, flooding, or pollution.

Paint and Repair Requirements

1.7 PROTECTION

1.7.1 Traffic Control Signs

a. Where pedestrian and driver safety is endangered in the area of removal work, use traffic barricades with flashing lights. Anchor barricades in a manner to prevent displacement by wind. Notify the Contracting Officer prior to beginning such work.

1.7.2 Protection of Personnel

Before, during and after the demolition and deconstruction work continuously evaluate the condition of the structure being demolished and deconstructed and take immediate action to protect all personnel working in and around the project site. No area, section, or component of floors, roofs, walls, columns, pilasters, or other structural element will be allowed to be left standing without sufficient bracing, shoring, or lateral support to prevent collapse or failure while workmen remove debris or perform other work in the immediate area.

1.8 RELOCATIONS

Perform the removal and reinstallation of relocated items as indicated with workmen skilled in the trades involved. Repair or replace items to be relocated which are damaged by the Contractor with new undamaged items as approved by the Contracting Officer.

1.9 EXISTING CONDITIONS

Before beginning any demolition or deconstruction work, survey the site and examine the drawings and specifications to determine the extent of the work. Record existing conditions in the presence of the Contracting Officer showing the condition of structures and other facilities adjacent to areas of alteration or removal. Photographs sized 4 inch will be acceptable as a record of existing conditions. Include in the record the elevation of the top of foundation walls, finish floor elevations, possible conflicting electrical conduits, plumbing lines, alarms systems, the location and extent of existing cracks and other damage and description of surface conditions that exist prior to before starting work. It is the Contractor's responsibility to verify and document all required outages which will be required during the course of work, and to note these outages on the record document. Submit survey results.

PART 2 PRODUCTS

2.1 FILL MATERIAL

a. Comply with excavating, backfilling, and compacting procedures for soils used as backfill material to fill basements, voids, depressions or excavations resulting from demolition or deconstruction of structures.

PART 3 EXECUTION

3.1 EXISTING FACILITIES TO BE REMOVED

Inspect and evaluate existing structures onsite for reuse. Existing construction scheduled to be removed for reuse shall be disassembled. Dismantled and removed materials are to be separated, set aside, and

prepared as specified, and stored or delivered to a collection point for reuse, remanufacture, recycling, or other disposal, as specified. Materials shall be designated for reuse onsite whenever possible.

3.1.1 Utilities and Related Equipment

3.1.1.1 General Requirements

Do not interrupt existing utilities serving occupied or used facilities, except when authorized in writing by the Contracting Officer. Do not interrupt existing utilities serving facilities occupied and used by the Government except when approved in writing and then only after temporary utility services have been approved and provided. Do not begin demolition or deconstruction work until all utility disconnections have been made. Shut off and cap utilities for future use, as indicated.

3.1.1.2 Disconnecting Existing Utilities

Remove existing utilities if needed for safe construction and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the Contracting Officer. When utility lines are encountered but are not indicated on the drawings, notify the Contracting Officer prior to further work in that area. Remove meters and related equipment and deliver to a location on the station in accordance with instructions of the Contracting Officer.

3.1.2 Masonry

Sawcut and remove masonry so as to prevent damage to surfaces to remain and to facilitate the installation of new work. Where new masonry adjoins existing, the new work shall abut or tie into the existing construction as specified for the new work. Provide square, straight edges and corners where existing masonry adjoins new work and other locations..

3.1.3 Concrete

Saw concrete along straight lines to a depth of a minimum 2 inch. Make each cut in walls perpendicular to the face and in alignment with the cut in the opposite face. Break out the remainder of the concrete provided that the broken area is concealed in the finished work, and the remaining concrete is sound. At locations where the broken face cannot be concealed, grind smooth or saw cut entirely through the concrete.

3.1.4 Carpentry

Salvage for recycle lumber, millwork items, and finished boards, and sort by type and size. Chip or shred and recycle salvaged wood unfit for reuse, except stained, painted, or treated wood. Remove windows, doors, frames, and cabinets, and similar items as whole units, complete with trim and accessories. Brace the open end of door frames to prevent damage.

3.1.5 Patching

Where removals leave holes and damaged surfaces exposed in the finished work, patch and repair these holes and damaged surfaces to match adjacent finished surfaces, using on-site materials when available. Where new work is to be applied to existing surfaces, perform removals and patching in a manner to produce surfaces suitable for receiving new work. Finished surfaces of patched area shall be flush with the adjacent existing surface

and shall match the existing adjacent surface as closely as possible as to texture and finish. Patching shall be as specified and indicated, and shall include:

a. Concrete and Masonry: Completely fill holes and depressions, caused by previous physical damage or left as a result of removals in existing masonry walls to remain, with an approved masonry patching material, applied in accordance with the manufacturer's printed instructions.

b. Where existing partitions have been removed leaving damaged or missing resilient tile flooring, patch to match the existing floor tile.

c. Patch acoustic lay-in ceiling where partitions have been removed. The transition between the different ceiling heights shall be effected by continuing the higher ceiling level over to the first runner on the lower ceiling and closing the vertical opening with a painted sheet metal strip.

3.2 DISPOSITION OF MATERIAL

3.2.1 Title to Materials

Except for salvaged items specified in related Sections, and for materials or equipment scheduled for salvage, all materials and equipment removed and not reused or salvaged, shall become the property of the Contractor and shall be removed from Government property. Title to materials resulting from demolition and deconstruction, and materials and equipment to be removed, is vested in the Contractor upon approval by the Contracting Officer of the Contractor's demolition, deconstruction, and removal procedures, and authorization by the Contracting Officer to begin demolition and deconstruction. The Government will not be responsible for the condition or loss of, or damage to, such property after contract award. Showing for sale or selling materials and equipment on site is prohibited.

3.2.2 Reuse of Materials and Equipment

Remove and store materials and equipment indicated by Construction Representative to be reused or relocated to prevent damage, and reinstall as the work progresses.

3.2.3 Salvaged Materials and Equipment

Remove materials and equipment that are specified by the Construction Representative to be removed by the Contractor and that are to remain the property of the Government, and deliver to a storage site , as directed within 2 miles of the work site.

a. Salvage items and material to the maximum extent possible.

b. Store all materials salvaged for the Contractor as approved by the Contracting Officer and remove from Government property before completion of the contract. On site sales of salvaged material is prohibited.

c. Remove salvaged items to remain the property of the Government in a manner to prevent damage, and packed or crated to protect the items from damage while in storage or during shipment. Items damaged during removal or storage must be repaired or replaced to match existing

items. Properly identify the contents of containers. Deliver the following items reserved as property of the Government to the areas designated: .

d. Remove the following items reserved as property of the using service prior to commencement of work under this contract: .

e. Remove historical items in a manner to prevent damage. Deliver the following historical items to the Government for disposition: Corner stones, contents of corner stones, and document boxes wherever located on the site.

3.2.4 Unsalvageable and Non-Recyclable Material

Dispose of unsalvageable and non-recyclable noncombustible material in the disposal area located off post. The fill in the disposal area shall remain below elevation and after disposal is completed, the disposal area shall be uniformly graded to drain. Dispose of unsalvageable and non-recyclable combustible material off the site.

3.3 CLEANUP

Remove debris and rubbish from basement and similar excavations. Remove and transport the debris in a manner that prevents spillage on streets or adjacent areas. Apply local regulations regarding hauling and disposal.

3.4 DISPOSAL OF REMOVED MATERIALS

3.4.1 Regulation of Removed Materials

Dispose of debris, rubbish, scrap, and other nonsalvageable materials resulting from removal operations with all applicable federal, state and local regulations as contractually specified off the post center. Storage of removed materials on the project site is prohibited.

3.4.2 Removal to Spoil Areas on Government Property

Transport noncombustible materials removed from demolition and deconstruction structures to designated spoil areas on Government property.

3.4.3 Removal from Government Property

Transport waste materials removed from demolished and deconstructed structures, except waste soil, from Government property for legal disposal. Dispose of waste soil as directed.

3.5 REUSE OF SALVAGED ITEMS

Recondition salvaged materials and equipment designated for reuse before installation. Replace items damaged during removal and salvage operations or restore them as necessary to usable condition.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 02 - EXISTING CONDITIONS

SECTION 02 82 33.13 20

REMOVAL/CONTROL AND DISPOSAL OF PAINT WITH LEAD

08/11

PART 1 GENERAL

1.1 REFERENCES
1.2 DEFINITIONS
1.2.1 Abatement
1.2.2 Action Level
1.2.3 Area Sampling
1.2.4 Child Occupied Facility
1.2.5 Competent Person (CP)
1.2.6 Contaminated Room
1.2.7 Decontamination Shower Facility
1.2.8 Deleading
1.2.9 Eight-Hour Time Weighted Average (TWA)
1.2.10 High Efficiency Particulate Air (HEPA) Filter Equipment
1.2.11 Lead
1.2.12 Lead-Based Paint (LBP)
1.2.13 Lead-Based Paint Activities
1.2.14 Lead-Based Paint Hazard (LBP Hazard)
1.2.15 Paint with Lead (PWL)
1.2.16 Lead Control Area
1.2.17 Lead Permissible Exposure Limit (PEL)
1.2.18 Personal Sampling
1.2.19 Physical Boundary
1.2.20 Target Housing
1.3 DESCRIPTION
1.3.1 Description of Work
1.3.2 Coordination with Other Work
1.4 SUBMITTALS
1.5 QUALITY ASSURANCE
1.5.1 Qualifications
1.5.1.1 Qualifications of CP
1.5.1.2 Training Certification
1.5.1.3 Testing Laboratory
1.5.2 Requirements
1.5.2.1 Competent Person (CP) Responsibilities
1.5.2.2 Lead-Based Paint/Paint with Lead Removal/Control Plan (LBP/PWL R/CP)
1.5.2.3 Occupational and Environmental Assessment Data Report
1.5.2.4 Medical Examinations
1.5.2.5 Training
1.5.2.6 Respiratory Protection Program
1.5.2.7 Hazard Communication Program
1.5.2.8 Lead Waste Management
1.5.2.9 Environmental, Safety and Health Compliance
1.5.3 Pre-Construction Conference
1.6 EQUIPMENT

1.6.1 Respirators
1.6.2 Special Protective Clothing
1.6.3 Rental Equipment Notification
1.6.4 Vacuum Filters
1.6.5 Equipment for Government Personnel
1.7 PROJECT/SITE CONDITIONS
1.7.1 Protection of Existing Work to Remain

PART 2 PRODUCTS

PART 3 EXECUTION

3.1 PREPARATION
3.1.1 Protection
3.1.1.1 Notification
3.1.1.2 Boundary Requirements
3.1.1.3 Decontamination Shower Facility
3.1.1.4 Eye Wash Station
3.1.1.5 Mechanical Ventilation System
3.1.1.6 Personnel Protection
3.2 ERECTION
3.2.1 Lead Control Area Requirements
3.3 APPLICATION
3.3.1 Work Procedures
3.3.2 Lead-Based Paint Removal/Control/Deleading
3.3.2.1 Outdoor Paint Removal
3.3.3 Personnel Exiting Procedures
3.4 FIELD QUALITY CONTROL
3.4.1 Tests
3.4.1.1 Air and Wipe Sampling
3.4.1.2 Air Sampling During Paint Removal Work
3.4.1.3 Sampling After Paint Removal/Control
3.4.1.4 Testing of Removed Paint and Used Abrasive
3.5 CLEANING AND DISPOSAL
3.5.1 Cleanup
3.5.1.1 Clearance Certification
3.5.2 Disposal
3.5.2.1 Disposal Documentation
3.5.3 Payment for Hazardous Waste

-- End of Section Table of Contents --

SECTION 02 82 33.13 20

REMOVAL/CONTROL AND DISPOSAL OF PAINT WITH LEAD
08/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN INDUSTRIAL HYGIENE ASSOCIATION (AIHA)

AIHA Z88.6	(2006) Respiratory Protection - Respirator Use-Physical Qualifications for Personnel

U.S. DEPARTMENT OF HOUSING AND URBAN DEVELOPMENT (HUD)

HUD 6780	(1995; Errata Aug 1996;Rev Ch. 7 - 1997) Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926.103	Respiratory Protection
29 CFR 1926.21	Safety Training and Education
29 CFR 1926.33	Access to Employee Exposure and Medical Records
29 CFR 1926.55	Gases, Vapors, Fumes, Dusts, and Mists
29 CFR 1926.59	Hazard Communication
29 CFR 1926.62	Lead
29 CFR 1926.65	Hazardous Waste Operations and Emergency Response
40 CFR 260	Hazardous Waste Management System: General
40 CFR 261	Identification and Listing of Hazardous Waste
40 CFR 262	Standards Applicable to Generators of Hazardous Waste
40 CFR 263	Standards Applicable to Transporters of Hazardous Waste
40 CFR 264	Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities

40 CFR 265	Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities
40 CFR 268	Land Disposal Restrictions
40 CFR 745	Lead-Based Paint Poisoning Prevention in Certain Residential Structures
49 CFR 172	Hazardous Materials Table, Special Provisions, Hazardous Materials Communications, Emergency Response Information, and Training Requirements
49 CFR 178	Specifications for Packagings

UNDERWRITERS LABORATORIES (UL)

UL 586	(2009; Reprint Dec 2017) Standard for High-Efficiency Particulate, Air Filter Units

1.2 DEFINITIONS

1.2.1 Abatement

As applied to target housing and child occupied facilities, "abatement" means any set of measures designed to permanently eliminate lead-based paint hazards in accordance with standards established by appropriate Federal agencies. Such term includes:

a. The removal of lead-based paint and lead-contaminated dust, the permanent containment or encapsulation of lead-based paint, the replacement of lead-painted surfaces or fixtures, and the removal or covering of lead contaminated soil; and

b. All preparation, cleanup, disposal, and post-abatement clearance testing activities associated with such measures.

1.2.2 Action Level

Employee exposure, without regard to use of respirators, to an airborne concentration of lead of 30 micrograms per cubic meter of air averaged over an 8 hour period in a work environment.

1.2.3 Area Sampling

Sampling of lead concentrations within the lead control area and inside the physical boundaries, which is representative of the airborne lead concentrations but is not collected in the breathing zone of personnel.

1.2.4 Child Occupied Facility

A building or portion of a building constructed prior to 1978 visited regularly by the same child, 6 years of age or under, on a least two different days within any week, provided each days visit last at least 3 hours and the combined weekly visit last at least 6 hours and the combined annual visit last at least 60 hours. Child occupied facilities may include, but are not limited to day-care centers, preschools and

kindergarten classrooms.

1.2.5 Competent Person (CP)

As used in this section, refers to a person employed by the Contractor who is trained in the recognition and control of lead hazards in accordance with current federal, State, and local regulations. A Certified Industrial Hygienist (CIH) certified for comprehensive practice by the American Board of Industrial Hygiene or a Certified Safety Professional (CSP) certified by the Board of Certified Safety Professionals is the best choice.

1.2.6 Contaminated Room

Refers to a room for removal of contaminated personal protective equipment (PPE).

1.2.7 Decontamination Shower Facility

That facility that encompasses a clean clothing storage room, and a contaminated clothing storage and disposal rooms, with a shower facility in between.

1.2.8 Deleading

Activities conducted by a person who offers to eliminate lead-based paint or lead-based paint hazards or to plan such activities in commercial buildings, bridges or other structures.

1.2.9 Eight-Hour Time Weighted Average (TWA)

Airborne concentration of lead to which an employee is exposed, averaged over an 8 hour workday as indicated in 29 CFR 1926.62.

1.2.10 High Efficiency Particulate Air (HEPA) Filter Equipment

HEPA filtered vacuuming equipment with a UL 586 filter system capable of collecting and retaining lead-contaminated paint dust. A high efficiency particulate filter means 99.97 percent efficient against 0.3 micron or larger size particles.

1.2.11 Lead

Metallic lead, inorganic lead compounds, and organic lead soaps.

1.2.12 Lead-Based Paint (LBP)

Paint or other surface coating that contains lead in excess of 1.0 milligrams per centimeter squared or 0.5 percent by weight.

1.2.13 Lead-Based Paint Activities

In the case of target housing or child occupied facilities, lead-based paint activities include; a lead-based paint inspection, a risk assessment, or abatement of lead-based paint hazards.

1.2.14 Lead-Based Paint Hazard (LBP Hazard)

Any condition that causes exposure to lead from lead-contaminated dust, lead-contaminated soil, lead-based paint that is deteriorated or present in

accessible surfaces, friction surfaces, or impact surfaces that would result in adverse human health effects.

1.2.15 Paint with Lead (PWL)

Any paint that contains lead as determined by the testing laboratory using a valid test method. The requirements of this section does not apply if no detectable levels of lead are found using a quantitative method for analyzing paint using laboratory instruments with specified limits of detection (usually 0.01 percent). An X-Ray Fluorescence (XRF) instrument is not considered a valid test method.

1.2.16 Lead Control Area

A system of control methods to prevent the spread of lead dust, paint chips or debris to adjacent areas that may include temporary containment, floor or ground cover protection, physical boundaries, and warning signs to prevent unauthorized entry of personnel. HEPA filtered local exhaust equipment may be used as engineering controls to further reduce personnel exposures or building/outdoor environmental contamination.

1.2.17 Lead Permissible Exposure Limit (PEL)

Fifty micrograms per cubic meter of air as an 8 hour time weighted average as determined by 29 CFR 1926.62. If an employee is exposed for more than eight hours in a workday, the PEL shall be determined by the following formula:

PEL (micrograms/cubic meter of air) = 400/No. hrs worked per day

1.2.18 Personal Sampling

Sampling of airborne lead concentrations within the breathing zone of an employee to determine the 8 hour time weighted average concentration in accordance with 29 CFR 1926.62. Samples shall be representative of the employees' work tasks. Breathing zone shall be considered an area within a hemisphere, forward of the shoulders, with a radius of 6 to 9 inches and centered at the nose or mouth of an employee.

1.2.19 Physical Boundary

Area physically roped or partitioned off around an enclosed lead control area to limit unauthorized entry of personnel. As used in this section, "inside boundary" shall mean the same as "outside lead control area but inside the physical boundary."

1.2.20 Target Housing

Housing constructed prior to 1978. It does not include housing for the elderly, or persons with disabilities unless any one or more children age 6 years and younger resides or is expected to reside in such housing.

1.3 DESCRIPTION

1.3.1 Description of Work

Remove/control lead-based / paint with lead in good condition, located on

post.

1.3.2 Coordination with Other Work

The contractor shall coordinate with work being performed in adjacent areas. Coordination procedures shall be explained in the Removal/Control Plan and shall describe how the Contractor will prevent lead exposure to other contractors and/or Government personnel performing work unrelated to lead activities.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Vacuum Filters; G

Respirators; G

SD-06 Test Reports

Sampling Results; G

Occupational and Environmental Assessment Data Report; G

SD-07 Certificates

Qualifications of CP; G

Testing Laboratory qualifications; G

Occupant Notification; G

Training Certification of workers and supervisors; G

Notification of the Commencement of LBP Hazard Abatement; G

lead-based paint/paint with lead removal/control plan including CP approval (signature, date, and certification number); G

Rental equipment notification; G

Respiratory Protection Program; G

Hazard Communication Program; G

EPA or State approved hazardous waste treatment, storage, or disposal facility for lead disposal; G

Lead Waste Management Plan; G

Vacuum filters; G

Clearance Certification; G

SD-11 Closeout Submittals

Completed and Signed Hazardous Waste Manifest from Treatment or Disposal Facility; G

Certification of Medical Examinations; G

Employee Training Certification; G

Waste Turn-In Documents or Weight Tickets for Non-Hazardous Wastes that are Disposed of at Sanitary or Construction and Demolition Landfills; G

1.5 QUALITY ASSURANCE

1.5.1 Qualifications

1.5.1.1 Qualifications of CP

Submit name, address, and telephone number of the CP selected to perform responsibilities specified in paragraph entitled "Competent Person (CP) Responsibilities." Provide previous experience of the CP. Submit proper documentation that the CP is trained and licensed and certified in accordance with Federal, State, and local laws.

1.5.1.2 Training Certification

Submit a certificate for each employee and supervisor, signed and dated by the authorized training provider meeting 40 CFR 745 (Subpart L) requirements, stating that the employee or supervisor has received the required lead training and is certified to perform or supervise deleading or lead removal. Submit proof the work will be performed by a certified firm.

1.5.1.3 Testing Laboratory

Submit the name, address, and telephone number of the testing laboratory selected to perform the air and wipe sampling, testing, and reporting of airborne concentrations of lead. Use a laboratory accredited under the EPA National Lead Laboratory Accreditation Program (NLLAP) by either the American Association for Laboratory Accreditation (A2LA) or the American Industrial Hygiene Association (AIHA) and that is successfully participating in the Environmental Lead Proficiency Analytical Testing (ELPAT) program to perform sample analysis. Laboratories selected to perform blood lead analysis shall be OSHA approved.

1.5.2 Requirements

1.5.2.1 Competent Person (CP) Responsibilities

a. Verify training meets all federal, State, and local requirements.

b. Review and approve lead-based paint/paint with lead removal/control plan for conformance to the applicable standards. Ensure work is performed in strict accordance with specifications at all times.

c. Continuously inspect lead-based paint removal/control work for

conformance with the approved plan.

d. Perform air and wipe sampling.

e. Control work to prevent hazardous exposure to human beings and to the environment at all times.

f. Certify the conditions of the work as called for elsewhere in this specification.

1.5.2.2 Lead-Based Paint/Paint with Lead Removal/Control Plan (LBP/PWL R/CP)

Submit a detailed job-specific plan of the work procedures to be used in the removal/control of LBP/PWL. The plan shall include a sketch showing the location, size, and details of lead control areas, location and details of decontamination facilities, viewing ports, and mechanical ventilation system. Include a description of equipment and materials, controls and job responsibilities for each activity from which lead is emitted. Include in the plan, eating, drinking, smoking and sanitary procedures, interface of trades, sequencing of lead related work, collected waste water and paint debris disposal plan, air sampling plan, respirators, personal protective equipment, and a detailed description of the method of containment of the operation to ensure that lead is not released outside the lead control area. Include site preparation, cleanup and clearance procedures. Include occupational and environmental sampling, training, sampling methodology, frequency, duration of sampling, and qualifications of sampling personnel in the air sampling portion of the plan. Include a description of arrangements made among contractors on multi-contractor worksites to inform affected employees and to clarify responsibilities to control exposures.

The Removal/Control Plan shall be developed by a certified planner/project designer.

In occupied buildings, the Removal/Control Plan shall also include an occupant protection program that describes the measures that will be taken during the work to protect the building occupants.

1.5.2.3 Occupational and Environmental Assessment Data Report

If initial monitoring is necessary, submit occupational and environmental sampling results to the Contracting Officer within three working days of collection, signed by the testing laboratory employee performing the analysis, the employee that performed the sampling, and the CP.

In order to reduce the full implementation of 29 CFR 1926.62, the Contractor shall provide documentation. Submit a report that supports the determination to reduce full implementation of the requirements of 29 CFR 1926.62 and supporting the Lead Removal/Control Plan.

a. The initial monitoring shall represent each job classification, or if working conditions are similar to previous jobs by the same employer, provide previously collected exposure data that can be used to estimate worker exposures per 29 CFR 1926.62. The data shall represent the worker's regular daily exposure to lead for stated work.

b. Submit worker exposure data gathered during the task based trigger operations of 29 CFR 1926.62 with a complete process description. This includes manual demolition, manual scraping, manual sanding, heat gun,

power tool cleaning, rivet busting, cleanup of dry expendable abrasives, abrasive blast enclosure removal, abrasive blasting, welding, cutting and torch burning where lead containing coatings are present.

c. The initial assessment shall determine the requirement for further monitoring and the need to fully implement the control and protective requirements including the lead compliance plan per 29 CFR 1926.62.

1.5.2.4 Medical Examinations

Initial medical surveillance as required by 29 CFR 1926.62 shall be made available to all employees exposed to lead at any time (1 day) above the action level. Full medical surveillance shall be made available to all employees on an annual basis who are or may be exposed to lead in excess of the action level for more than 30 days a year or as required by 29 CFR 1926.62. Adequate records shall show that employees meet the medical surveillance requirements of 29 CFR 1926.33, 29 CFR 1926.62, and 29 CFR 1926.103. Maintain complete and accurate medical records of employees for a period of at least 30 years or for the duration of employment plus 30 years, whichever is longer.

1.5.2.5 Training

Train each employee performing paint removal, disposal, and air sampling operations prior to the time of initial job assignment and annually thereafter, in accordance with 29 CFR 1926.21, 29 CFR 1926.62, and State and local regulations where appropriate.

1.5.2.6 Respiratory Protection Program

a. Provide each employee required to wear a respirator a respirator fit test at the time of initial fitting and at least annually thereafter as required by 29 CFR 1926.62.

b. Establish and implement a respiratory protection program as required by AIHA Z88.6, 29 CFR 1926.103, 29 CFR 1926.62, and 29 CFR 1926.55.

1.5.2.7 Hazard Communication Program

Establish and implement a Hazard Communication Program as required by 29 CFR 1926.59.

1.5.2.8 Lead Waste Management

The Lead Waste Management Plan shall comply with applicable requirements of federal, State, and local hazardous waste regulations and address:

a. Identification and classification of hazardous wastes associated with the work.

b. Estimated quantities of wastes to be generated and disposed of.

c. Names and qualifications of each contractor that will be transporting, storing, treating, and disposing of the wastes. Include the facility location and a 24-hour point of contact. Furnish two copies of proof of EPA State and local hazardous waste permit applications permits

manifests and EPA Identification numbersTransporter Number.

d. Names and qualifications (experience and training) of personnel who will be working on-site with hazardous wastes.

e. List of waste handling equipment to be used in performing the work, to include cleaning, volume reduction, and transport equipment.

f. Spill prevention, containment, and cleanup contingency measures including a health and safety plan to be implemented in accordance with 29 CFR 1926.65.

g. Work plan and schedule for waste containment, removal and disposal. Wastes shall be cleaned up and containerized daily. Proper containment of the waste includes using acceptable waste containers (e.g., 55-gallon drums) as well as proper marking/labeling of the containers.

h. Unit cost for waste disposal according to this plan.

1.5.2.9 Environmental, Safety and Health Compliance

In addition to the detailed requirements of this specification, comply with laws, ordinances, rules, and regulations of Federal, State, and local authorities regarding removing, handling, storing, transporting, and disposing of lead waste materials. Comply with the applicable requirements of the current issue of 29 CFR 1926.62. Submit matters regarding interpretation of standards to the Contracting Officer for resolution before starting work. Where specification requirements and the referenced documents vary, the most stringent requirement shall apply.

Licensing and certification in the State of Kansas is required.

1.5.3 Pre-Construction Conference

Along with the CP, meet with the Contracting Officer to discuss in detail the lead waste management plan and the lead-based paint/paint with lead removal/control plan, including work procedures and precautions for the removal plan.

1.6 EQUIPMENT

1.6.1 Respirators

Furnish appropriate respirators approved by the National Institute for Occupational Safety and Health (NIOSH), Department of Health and Human Services, for use in atmospheres containing lead dust. Respirators shall comply with the requirements of 29 CFR 1926.62.

1.6.2 Special Protective Clothing

Furnish personnel who will be exposed to lead-contaminated dust with proper disposable uncontaminated, reusable protective whole body clothing, head covering, gloves, and foot coverings as required by 29 CFR 1926.62. Furnish proper disposable plastic or rubber gloves to protect hands. Reduce the level of protection only after obtaining approval from the CP.

1.6.3 Rental Equipment Notification

If rental equipment is to be used during lead-based paint handling and disposal, notify the rental agency in writing concerning the intended use of the equipment. Furnish a copy of the written notification to the Contracting Officer.

1.6.4 Vacuum Filters

UL 586 labeled HEPA filters.

1.6.5 Equipment for Government Personnel

Furnish the Contracting Officer with two complete sets of personal protective equipment (PPE) daily, as required herein, for entry into and inspection of the paint removal work within the lead controlled area. Personal protective equipment shall include disposable whole body covering, including appropriate foot, head, and hand protection. PPE shall remain the property of the Contractor. The Government will provide respiratory protection for the Contracting Officer.

1.7 PROJECT/SITE CONDITIONS

1.7.1 Protection of Existing Work to Remain

Perform paint removal work without damage or contamination of adjacent areas. Where existing work is damaged or contaminated, restore work to its original condition or better.

PART 2 PRODUCTS

Section 01 35 26 GOVERNMENTAL SAFETY REQUIREMENTS.

PART 3 EXECUTION

3.1 PREPARATION

3.1.1 Protection

3.1.1.1 Notification

a. Notify the Contracting Officer 5 days prior to the start of any paint removal work.

b. Occupant Notification

Submit occupant written acknowledgment of the delivery of lead hazard information pamphlet (EPA 747-K-99-001 "Protect Your Family From Lead in Your Home") prior to commencing the renovation work for each affected unit per 40 CFR 745 Subpart E.

c. Notification of the Commencement of LBP Hazard Abatement

Submit a copy of the notification of the commencement of LBP hazard abatement to Construction Representative according to the procedures established by MICC.

3.1.1.2 Boundary Requirements

a. Provide physical boundaries around the lead control area by roping off the area designated in the work plan or providing curtains, portable partitions or other enclosures to ensure that lead will not escape outside the lead control area.

b. Warning Signs - Provide warning signs at approaches to lead control areas. Locate signs at such a distance that personnel may read the sign and take the necessary precautions before entering the area. Signs shall comply with the requirements of 29 CFR 1926.62.

3.1.1.3 Decontamination Shower Facility

Provide clean and contaminated change rooms and shower facilities in accordance with this specification and 29 CFR 1926.62.

3.1.1.4 Eye Wash Station

Where eyes may be exposed to injurious corrosive materials, suitable facilities for quick drenching or flushing of the eyes shall be provided within the work area.

3.1.1.5 Mechanical Ventilation System

a. Use adequate ventilation to control personnel exposure to lead in accordance with 29 CFR 1926.62.

b. To the extent feasible, use local exhaust ventilation connected to HEPA filters or other collection systems, approved by the CP. Local exhaust ventilation systems shall be evaluated and maintained in accordance with 29 CFR 1926.62.

c. Vent local exhaust outside the building only and away from building ventilation intakes.

d. Use locally exhausted, power actuated, paint removal tools.

3.1.1.6 Personnel Protection

Personnel shall wear and use protective clothing and equipment as specified herein. Eating, smoking, or drinking or application of cosmetics is not permitted in the lead control area. No one will be permitted in the lead control area unless they have been appropriately trained and provided with protective equipment.

3.2 ERECTION

3.2.1 Lead Control Area Requirements

Establish a lead control area by situating critical barriers and physical boundaries around the area or structure where LBP/PWL removal/control operations will be performed.

3.3 APPLICATION

3.3.1 Work Procedures

Perform removal of lead-based paint in accordance with approved lead-based paint/paint with lead removal/control plan. Use procedures and equipment required to limit occupational and environmental exposure to lead when lead-based paint is removed in accordance with 29 CFR 1926.62. Dispose of removed paint chips and associated waste in compliance with Environmental Protection Agency (EPA), State, and local requirements.

3.3.2 Lead-Based Paint Removal/Control/Deleading

Manual or power sanding of interior and exterior surfaces is not permitted unless tools are equipped with HEPA attachments or wet methods. The dry sanding or grinding of surfaces that contain lead is prohibited Provide methodology for LBP removal/control in work plan. Remove paint within the areas designated on the drawings in order to completely expose the substrate. Take whatever precautions necessary to minimize damage to the underlying substrate.

Avoid flash rustingdeterioration of the substrate. Provide surface preparations for painting in accord with Section 09 90 00 PAINTS AND COATINGS.

Provide methodology for LBP/PWL removal abatement/control and processes to minimize contamination of work areas outside the control area with lead-contaminated dust or other lead-contaminated debris/waste and to ensure that unprotected personnel are not exposed to hazardous concentrations of lead. Describe this LBP/PWL removal/control process in the LBP/PWL R/CP.

3.3.2.1 Outdoor Paint Removal

Perform outdoor removal as indicated in federal, State, and local regulations and in the LBP/CPR/CP. The worksite preparation (barriers or containments) shall be job dependent and presented in the LBP/PWL R/CP.

3.3.3 Personnel Exiting Procedures

Whenever personnel exit the lead-controlled area, they shall perform the following procedures and shall not leave the work place wearing any clothing or equipment worn during the work day:

a. Vacuum themselves off.

b. Remove protective clothing in the contaminated change room, and place them in an approved impermeable disposal bag.

c. Shower.

c. Wash hands and face at the site, don appropriate disposable or uncontaminated reusable clothing; move to an appropriate facility; shower.

d. Change to clean clothes prior to leaving the physical boundary designated around the lead control area.

3.4 FIELD QUALITY CONTROL

3.4.1 Tests

3.4.1.1 Air and Wipe Sampling

Air sample for lead in accordance with 29 CFR 1926.62 and as specified herein. Air and wipe sampling shall be directed or performed by the CP.

a. The CP shall be on the job site directing the air and non-clearance wipe sampling and inspecting the lead-based paint removal/control work to ensure that the requirements of the contract have been satisfied during the entire lead-based paint removal operation.

b. Collect personal air samples on employees who are expected to have the greatest risk of exposure as determined by the CP. In addition, collect air samples on at least 25 percent of the work crew or a minimum of two employees, whichever is greater, during each work shift.

c. Submit results of air samples, within 72 hours after the air samples are taken.

e. Collect surface wipe samples at a location no greater than 10 feet outside the lead control area at a frequency of once per day while lead removal work is conducted. Surface wipe results shall meet criteria in paragraph "Clearance Certification."

3.4.1.2 Air Sampling During Paint Removal Work

Conduct area air sampling daily, on each shift in which lead-based paint removal operations are performed, in areas immediately adjacent to the lead control area. Sufficient area monitoring shall be conducted to ensure unprotected personnel are not exposed at or above 30 micrograms per cubic meter of air. If 30 micrograms per cubic meter of air is reached or exceeded, stop work, correct the conditions(s) causing the increased levels. Notify the Contracting Officer immediately. Determine if condition(s) require any further change in work methods. Removal work shall resume only after the CP and the Contracting Officer give approval. For outdoor operations, at least one sample on each shift shall be taken on the downwind side of the lead control area.

3.4.1.3 Sampling After Paint Removal/Control

After the visual inspection, collect wipe samples according to the HUD protocol contained in HUD 6780 to determine the lead content of settled dust and dirt in micrograms per square meter foot of surface area .

3.4.1.4 Testing of Removed Paint and Used Abrasive

Test removed paint and used abrasive in accordance with 40 CFR 261 for hazardous waste.

3.5 CLEANING AND DISPOSAL

3.5.1 Cleanup

Maintain surfaces of the lead control area free of accumulations of paint chips and dust. Restrict the spread of dust and debris; keep waste from

being distributed over the work area. Do not dry sweep or use compressed air to clean up the area. At the end of each shift and when the paint removal operation has been completed, clean the area of visible lead paint contamination by vacuuming with a HEPA filtered vacuum cleaner, wet mopping the area and wet wiping the area as indicated by the CP. Reclean areas showing dust or residual paint chips or debris. After visible dust, chips and debris is removed, wet wipe and HEPA vacuum all surfaces in the work area. If adjacent areas become contaminated at any time during the work, clean, visually inspect, and then wipe sample all contaminated areas. The CP shall then certify in writing that the area has been cleaned of lead contamination before restarting work.

3.5.1.1 Clearance Certification

The CP shall certify in writing that air samples collected outside the lead control area during paint removal operations are less than 30 micrograms per cubic meter of air; the respiratory protection used for the employees was adequate; the work procedures were performed in accordance with 29 CFR 1926.62 and 40 CFR 745; and that there were no visible accumulations of material and dust containing lead left in the work site. Do not remove the lead control area or roped off boundary and warning signs prior to the Contracting Officer's acknowledgement of receipt of the CP certification.

Certify surface wipe samples are not significantly greater than the initial surface loading determined prior to work.

For exterior paint removal/control work, soil samples taken at the exterior of the work site shall be used to determine if soil lead levels had increased at a statistically significant level (significant at the 95 percent confidence limit) from the soil lead levels prior to the work. If soil lead levels do show a statistically significant increase or is above any applicable Federal or State standard for lead in soil, the soil shall be remediated back to the pre-work level.

Clear the lead control area in industrial facilities of all visible dust and debris.

For lead-based paint hazard abatement work, surface wipe and soil sampling shall be conducted and clearance determinations made according to the work practice standards presented in 40 CFR 745.227.

3.5.2 Disposal

a. Collect lead-contaminated waste, scrap, debris, bags, containers, equipment, and lead-contaminated clothing that may produce airborne concentrations of lead particles. Label the containers in accordance with 29 CFR 1926.62 and 40 CFR 262. Dispose of lead-contaminated waste material at an EPA or State approved hazardous waste treatment, storage, or disposal facility off Government property.

b. Place waste materials in U.S. Department of Transportation (49 CFR 178) approved 55 gallon drums. Properly label each drum to identify the type of waste (49 CFR 172) and the date the drum was filled. For hazardous waste, the collection drum requires marking/labeling in accordance with 40 CFR 262 during the accumulation/collection timeframe. The Contracting Officer or an authorized representative will assign an area for interim storage of waste-containing drums. Do not store hazardous waste drums in interim storage longer than 90 calendar days from the

date affixed to each drum.

c. Handle, transport, and dispose lead or lead-contaminated material classified as hazardous waste in accordance with 40 CFR 260, 40 CFR 261, 40 CFR 262, 40 CFR 263, 40 CFR 264, and 40 CFR 265. Comply with land disposal restriction notification requirements as required by 40 CFR 268.

d. All material, whether hazardous or non-hazardous shall be disposed in accordance with laws and provisions and Federal, State, or local regulations. Ensure waste is properly characterized. The result of each waste characterization (TCLP for RCRA materials) will dictate disposal requirements.

3.5.2.1 Disposal Documentation

Submit written evidence to demonstrate the hazardous waste treatment, storage, or disposal facility (TSD) is approved for lead disposal by the EPA, State or local regulatory agencies. Submit one copy of the completed hazardous waste manifest, signed and dated by the initial transporter in accordance with 40 CFR 262. Contractor shall provide a certificate that the waste was accepted by the disposal facility. Provide turn-in documents or weight tickets for non-hazardous waste disposal.

3.5.3 Payment for Hazardous Waste

Payment for disposal of hazardous and non-hazardous waste will not be made until a signed copy of the manifest from the treatment or disposal facility certifying the amount of lead-containing materials or non-hazardous waste delivered is returned and a copy is furnished to the Government.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 03 - CONCRETE

SECTION 03 33 00

CAST-IN-PLACE ARCHITECTURAL CONCRETE

11/09

PART 1 GENERAL

1.1 REFERENCES
1.2 SYSTEM DESCRIPTION
1.2.1 Concrete Mix Design
1.2.2 Formwork Design
1.3 SUBMITTALS
1.4 QUALITY ASSURANCE
1.4.1 Detail Drawings
1.4.2 Panels

PART 2 PRODUCTS

2.1 MATERIALS
2.1.1 Aggregates
2.1.2 Reinforcing Steel
2.1.3 Tie Wire
2.1.4 Plates, Angles, Anchors, and Embedments
2.1.5 Formwork
2.1.6 Form Release Agents
2.1.7 Surface Sealer

PART 3 EXECUTION

3.1 FORMWORK ERECTION
3.2 CONCRETE FINISHES
3.3 JOINT SEALING
3.4 CLEANING
3.5 SURFACE SEALING
3.6 PROTECTION OF WORK
3.7 DEFECTIVE WORK

-- End of Section Table of Contents --

SECTION 03 33 00

CAST-IN-PLACE ARCHITECTURAL CONCRETE
11/09

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONCRETE INSTITUTE INTERNATIONAL (ACI)

ACI 211.1	(1991; R 2009) Standard Practice for Selecting Proportions for Normal, Heavyweight and Mass Concrete
ACI 211.2	(1998; R 2004) Standard Practice for Selecting Proportions for Structural Lightweight Concrete
ACI 301	(2016) Specifications for Structural Concrete
ACI 318	(2014; Errata 1-2 2014; Errata 3-5 2015; Errata 6 2016; Errata 7-9 2017) Building Code Requirements for Structural Concrete (ACI 318-14) and Commentary (ACI 318R-14)
ACI 347R	(2014; Errata 1 2017) Guide to Formwork for Concrete
ACI SP-66	(2004) ACI Detailing Manual

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2014) Standard Specification for Carbon Structural Steel

1.2 SYSTEM DESCRIPTION

All materials, procedures, and requirements specified in Section 03 30 00.00 10 CAST-IN-PLACE CONCRETE shall fully apply to cast-in-place architectural concrete, except as otherwise specified.

1.2.1 Concrete Mix Design

Design the concrete mix in accordance with ACI 211.1 and ACI 211.2 including consideration of the finishes required.

1.2.2 Formwork Design

Design formwork conforming to ACI 301 and ACI 347R.

Paint and Repair Requirements

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-02 Shop Drawings

Detail Drawings.

SD-04 Samples

Materials
Panels

1.4 QUALITY ASSURANCE

1.4.1 Detail Drawings

Submit detail drawings conforming to ACI SP-66 and ACI 318. Detail drawings shall show location of cast-in-place elements in the work, building elevations, formwork fabrication details, reinforcements, embedments, dimensions, concrete strength, interface with adjacent materials, and special placing instructions, in sufficient detail to cover fabrication, placement, stripping, and finishing.

1.4.2 Panels

Provide sample panels 6 feet long and 4 feet high with the thickness to match building conditions for each type of architectural concrete and finish, located where directed. Panel forms shall include a typical joint between form panels, form tie conditions and finishes. Protect panels from weather, and other damage until acceptance of work. Sample panels shall be used as job standards throughout construction. Submit a sample panel for approval.

PART 2 PRODUCTS

2.1 MATERIALS

Submit samples of materials listed below, indicating sizes, shapes, finishes, color, and pertinent accessories: .

2.1.1 Aggregates

Aggregates shall conform to KDOT specifications.

2.1.2 Reinforcing Steel

Reinforcing steel shall be galvanized if clearance to an exterior face is 1 inch or less.

2.1.3 Tie Wire

Tie wire shall be soft monel or 18-8 stainless steel.

Paint and Repair Requirements

2.1.4 Plates, Angles, Anchors, and Embedments

Plates, angles, anchors, and embedments shall conform to ASTM A36/A36M, and shall be prime painted with inorganic zinc primer.

2.1.5 Formwork

Formwork for special effects shall be as approved.

2.1.6 Form Release Agents

Form release agents shall be manufacturer's standard, nonstaining, nonpetroleum based, compatible with surface sealer finish coating.

2.1.7 Surface Sealer

Surface sealer shall be methyl methacrylate polymer acrylic emulsion, clear color.

PART 3 EXECUTION

3.1 FORMWORK ERECTION

Erect formwork in accordance with the detail drawings to ensure that the finished concrete members conform accurately to the indicated dimensions, lines, elevations, and finishes. Deflection shall not exceed 1/360th of each component span or distance between adjacent supports. Deflections and tolerance shall not be cumulative. Install form lines as necessary to provide the required finish. Forms shall be coated with form release agents before reinforcement is placed. Formwork shall conform to ACI 301 and ACI 347R.

3.2 CONCRETE FINISHES

Concrete finishes shall conform to the approved finishes. Finishing shall be accomplished at the time of concrete placement or immediately after formwork removal, as follows:

a. Smooth finish: (1) As cast using flat smooth nonporous forms. (2) As cast using fluted, sculptured, board finish or textured form liners.

b. Textured finish: (1) Textured form liners applied to inside of forms. (2) Distress finish by breaking off portion of face of raised portion of unit.

c. Exposed aggregate finish: (1) Finish obtained by applying even coat of retardant to face of form, removing forms after concrete hardens, and exposing coarse aggregate to a depth of 1/2 inches by washing and brushing or lightly sandblasting away surface mortar. (2) Finish obtained by treating surface of unit with brushes which have been immersed in acid solution.

3.3 JOINT SEALING

Joint sealing shall be as specified in Section 07 92 00 JOINT SEALANTS.

3.4 CLEANING

No sooner than 72 hours after joints are sealed, faces and other exposed

surfaces of cast-in-place concrete shall be washed down, cleaned with soap and water applied with a soft bristle brush, then washed down again with clean water, or by other approved procedures. Discolorations which cannot be removed by these procedures, shall be considered defective work. Cleaning work shall be done when temperature and humidity conditions are such that surfaces dry rapidly. Care shall be taken during cleaning operations to protect adjacent surfaces from damage.

3.5 SURFACE SEALING

After cleaning, exterior exposed architectural concrete surfaces indicated shall be given one coat of surface sealer, spray applied unless otherwise approved. Adjacent surfaces shall be protected to prevent damage from the surface sealer.

3.6 PROTECTION OF WORK

Work shall be protected against damage from subsequent operations.

3.7 DEFECTIVE WORK

Defective work shall be repaired or replaced, as directed, using approved procedures.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 04 - MASONRY

SECTION 04 03 00

CONSERVATION TREATMENT FOR PERIOD MASONRY

11/17

PART 1 GENERAL

1.1 REFERENCES
1.2 DEFINITIONS
1.2.1 Aggregates
1.2.2 Biocides
1.2.3 Binder
1.2.4 Dispersed Lime Crack Injection
1.2.5 Consolidant
1.2.6 Dutchman
1.2.7 Harvested
1.2.8 In situ
1.2.9 Joint Sealant
1.2.10 Lead Flashing
1.2.11 Lime Wash
1.2.12 Mockup
1.2.13 Mortar
1.2.14 New Elements
1.2.15 Patch
1.2.16 Remediate
1.2.17 Remove
1.2.18 Replace
1.2.19 Repoint
1.2.20 Retool
1.2.21 Stucco
1.2.22 Surface Treatment
1.2.23 Test Panel
1.2.24 Tuckpointing
1.2.25 Water Repellent
1.2.26 Wall System
1.2.27 Masonry Treatment Requirement (MTR)
1.2.28 Saturated Surface Dry (SSD)
1.3 ADMINISTRATIVE REQUIREMENTS
1.3.1 Pre-Installation Meeting
1.4 SUBMITTALS
1.5 QUALITY CONTROL
1.5.1 Quality Control Plan
1.5.2 Qualifications
1.5.2.1 Historic Masonry Consultant
1.5.2.2 Masonry Firm
1.5.2.3 Field Supervisor
1.5.2.4 Masonry Applicator
1.5.3 Project Training Definition and Use
1.5.4 Mortar Analyst
1.5.5 Documentation
1.5.6 Cleaning and Restoration Methods

1.5.6.1 General Procedure
1.5.6.2 Cleaning Products and Procedures
1.5.6.2.1 General Cleaning Requirements
1.5.6.2.2 Cleaning Mock-Ups
1.5.7 Masonry Restoration Products and Procedures
1.5.7.1 General Restoration Requirements
1.5.7.2 General Restoration Mock-Up Requirements
1.5.7.2.1 Mock-ups
1.5.7.3 Restoration Mock-Ups
1.5.7.3.1 Repointing
1.5.7.3.2 Retooling Stone Masonry In Situ
1.5.7.3.3 Masonry Removal and Replacement
1.5.7.3.4 Repair Material
1.5.7.3.4.1 Patching
1.5.7.3.4.2 Dutchman
1.5.7.3.5 Crack Repair
1.5.7.3.6 Surface Treatments
1.5.7.3.7 New Masonry Elements
1.6 DELIVERY, STORAGE, AND HANDLING
1.7 PROJECT/SITE CONDITIONS
1.7.1 Environmental Requirements
1.7.2 Masonry Installation Requirements
1.8 WARRANTY
1.8.1 Cleaning Warranty
1.8.2 Repair Warranty

PART 2 PRODUCTS

2.1 CLEANING MATERIALS
2.1.1 General Requirements
2.1.2 Paint Removers
2.1.3 Chemical Cleaners
2.1.4 Biocides
2.1.5 Liquid Strippable Masking Agent
2.1.6 Cleaning Implements
2.1.7 Water
2.2 REPAIR MATERIALS
2.2.1 General
2.2.2 Mortar and Stucco
2.2.2.1 Testing and Matching
2.2.2.2 Replacement Mortar and Stucco
2.2.2.3 Binder Content
2.2.2.4 Repointing Mortar
2.2.2.5 Admixtures
2.2.3 Crack Injection
2.2.4 Replacement Masonry Materials
2.2.4.1 Clay Brick
2.2.4.2 Stone
2.2.5 Surface Treatments
2.2.5.1 General
2.2.5.2 Consolidants
2.2.5.3 Water Repellents
2.2.6 Miscellaneous Materials
2.2.6.1 Cementitious Grout
2.2.6.2 Metal Attachments
2.2.6.3 Lead Flashing
2.3 EQUIPMENT
2.3.1 Cleaning Equipment
2.3.1.1 Sandblasting

2.3.1.2 Water Blasting
2.3.1.3 Alternative Blasting Equipment
2.3.2 Spray Equipment
2.3.3 Drilling Equipment
2.3.4 Compressed Air Supplies
2.3.5 Material Handling and Associated Equipment
2.3.5.1 Mixing, Transporting, and Placing Job Materials
2.3.5.2 Associated Equipment
2.4 Mortar Mix
2.4.1 General
2.4.2 Batching
2.4.3 Cement and Lime Proportions
2.4.4 Sand Proportions

PART 3 EXECUTION

3.1 EXAMINATION
3.1.1 Field (In Situ) Mortar Examination
3.1.2 Taking and Preparation of Samples
3.2 PREPARATION
3.2.1 Protection
3.2.2 Surface Preparation
3.2.3 Equipment and Techniques Demonstration
3.3 MASONRY CLEANING
3.3.1 General
3.3.2 Chemical Cleaners
3.3.3 Paint Removal
3.3.4 Water Cleaning
3.3.4.1 Pressure Spraying
3.3.4.2 Hand Scrubbing
3.3.4.3 Rinsing
3.3.5 Chemical Cleaning
3.3.5.1 General
3.3.5.2 Surface Prewetting
3.3.5.3 Acidic Chemical Cleaning
3.3.5.4 Alkaline Chemical Cleaning
3.3.5.4.1 Prewash Phase
3.3.5.4.2 Afterwash Phase
3.3.5.5 Rinsing and pH Testing
3.4 MASONRY REPAIR
3.4.1 General
3.4.2 Repointing Masonry
3.4.2.1 Wall Preparation
3.4.2.2 Presoaking Masonry / Mortar Consistency / Lifts
3.4.2.3 Compression / Joint Finish / Curing
3.4.2.4 Protection
3.4.3 Retooling Stone Masonry In situ
3.4.4 Masonry Removal and Replacement
3.4.5 Material Repair
3.4.5.1 Selective Demolition
3.4.5.2 Application of Substitute Repair Materials
3.4.5.3 Patch Anchors
3.4.5.4 Cleanup
3.4.6 Dutchman Repairs
3.4.7 Crack Injection with Dispersed Hydrated Lime (DHL)
3.4.7.1 General
3.4.7.2 Application of DHL
3.4.7.3 Tools and Equipment
3.4.8 Surface Treatments

3.4.8.1 Stucco
3.4.8.2 Limewashes
3.4.8.3 Water Repellents Infiltration
3.4.8.4 Stone Consolidants
3.5 INSTALLATION OF NEW ELEMENTS
3.5.1 Structural Upgrades
3.5.2 Joint Sealant and Lead Flashing
3.6 FINAL CLEANING
3.7 PROTECTION OF WORK
3.8 DEFECTIVE WORK
3.9 FINAL INSPECTION

-- End of Section Table of Contents --

SECTION 04 03 00

CONSERVATION TREATMENT FOR PERIOD MASONRY
11/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH 0100	(2015; Suppl 2002-2016) Documentation of the Threshold Limit Values and Biological Exposure Indices

ASTM INTERNATIONAL (ASTM)

ASTM A36/A36M	(2014) Standard Specification for Carbon Structural Steel
ASTM C1196	(2014) Standard Test Method for In Situ Compressive Stress Within Solid Unit Masonry Esitmated Using Flatjack Measurements
ASTM C1197	(2014) Standard Test Method for In Situ Measurement of Masonry Deformability Properties Using the Flatjack Method
ASTM C1324	(2015) Standard Test Method for Examination and Analysis of Hardened Masonry Mortar
ASTM C1489	(2015) Standard Specification for Lime Putty for Structural Purposes
ASTM C1531	(2015) Standard Test Methods for In Situ Measurement of Masonry Mortar Joint Shear Strength Index
ASTM C1601	(2014) Standard Test Method for Field Measurement of Water Penetration of Masonry Wall Surfaces
ASTM C170/C170M	(2017) Standard Test Method for Compressive Strength of Dimension Stone
ASTM C1713	(2012) Standard Specification for Mortars for the Repair of Historic Masonry
ASTM C207	(2006; R 2011) Standard Specification for Hydrated Lime for Masonry Purposes

ASTM C216	(2017) Standard Specification for Facing Brick (Solid Masonry Units Made from Clay or Shale)
ASTM C67/C67M	(2018) Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile
ASTM C926	(2018a) Standard Specification for Application of Portland Cement-Based Plaster
ASTM E2260	(2012) Standard Guide for Repointing (Tuckpointing) Historic Masonry
ASTM E2659	(2018) Standard Practice for Certificate Programs
ASTM E96/E96M	(2016) Standard Test Methods for Water Vapor Transmission of Materials

NATIONAL PARK SERVICE (NPS)

NPS Hist Prop	(2017) National Standards for the Treatment of Historic Properties with Guidelines for Preserving, Rehabilitating, Restoring, and Reconstructing Historic Buildings
NPS TPS Brief 1	(2000) Assessing Cleaning and Water-Repellent Treatments for Historic Masonry Buildings
NPS TPS Brief 2	(1998) Repointing Mortar Joints in Historic Masonry Buildings

THE MASONRY SOCIETY (TMS)

TMS MSJC	(2016) Masonry Standard Joint Committee's (MSJC) Book - Building Code Requirements and Specification for Masonry Structures, Containing TMS 402/ACI 530/ASCE 5, TMS 602/ACI 530.1/ASCE 6, and Companion Commentaries

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

GSA HPTP 07656-01	Installing Lead Stone Flashing to Protect Masonry Joints

1.2 DEFINITIONS

Terms are defined below as applicable to this project.

1.2.1 Aggregates

The sand component of mortar.

1.2.2 Biocides

A chemical treatment that inhibits, deters, or controls organic growth. Such growth is typically removed by cleaning following biocide treatment..

1.2.3 Binder

The component of mortar that binds together the aggregate particles into a cohesive material.

1.2.4 Dispersed Lime Crack Injection

A repair method in which dispersed lime material is injected into small cracks ranging in width from hairline to 1/8 in by use of needle or syringe.

1.2.5 Consolidant

A chemical product meant to strengthen loose or deteriorated stone.

1.2.6 Dutchman

A repair method in which deteriorated stone is removed in part and replaced with salvaged, harvested or new stone to make a seamless patch.

1.2.7 Harvested

Units removed from inconspicuous areas of the building.

1.2.8 In situ

A term referencing a repair procedure in which the masonry units and mortar remain in place and are repaired without removal from the wall system

1.2.9 Joint Sealant

A flexible, chemical product that is used to create a weather-tight seal at the boundary of masonry units with other units or dissimilar materials.

1.2.10 Lead Flashing

An extruded lead material that is inserted into joints to assist in precluding water entry into the masonry.

1.2.11 Lime Wash

A protective surface treatment comprised of calcium hydroxide particles in suspension in water, along with small amounts of calcium carbonate, silica particles and other minerals.

1.2.12 Mockup

Specific area on the building approved by Contracting Officer to demonstrate the ability to apply, match and install specified materials.

1.2.13 Mortar

A mixture of binders, aggregates, and pigments used for reconstruction, repointing or stucco applications.

1.2.14 New Elements

New, non-historic materials added to masonry structures to aid in their ability to resist loads (typically seismic) or to resist water infiltration.

1.2.15 Patch

The use of substitute repair materials to treat damaged or deteriorated masonry units in situ.

1.2.16 Remediate

An intervention of a historic masonry structure and its component materials with the intent to maintain the original fabric to the greatest extent possible.

1.2.17 Remove

Specifically for historic masonry materials, the term means to detach an item from existing construction to the limits indicated.

1.2.18 Replace

To reinstall an item in its original position (or where indicated) after remedial treatment, or to duplicate and reinstall an entire item with new material; with the original item serving as the pattern for creating the duplicate.

1.2.19 Repoint

To remove existing mortar joints to the specified depth and replace with a mortar that matches in color, texture, and performance with water vapor transmission, bond, hardness, and flexibility compatible with original mortar, as assessed in accordance with ASTM C1713.

1.2.20 Retool

A repair method in which a chisel is used to re-create the surrounding stone texture finish by removing loose pieces of stone.

1.2.21 Stucco

A mixture of binders and aggregates, sometimes including animal hair or fibers used for the repair treatment of existing stucco.

1.2.22 Surface Treatment

The application of traditional materials or contemporary chemical products to the surface of masonry to provide protection to the masonry units and mortar and/or reduce water infiltration.

1.2.23 Test Panel

Specific area on the building approved by the Contracting Officer to demonstrate individual applicator competency and workmanship proficiency prior to the start of restoration work.

1.2.24 Tuckpointing

Often called skim-coating, an American practice of surface repairing mortar joints without the required removal of existing deteriorated mortar beneath. This practice is not recommended for mortar joint repair work on historic masonry. There is also an acceptable British form of tuckpointing practice that involves careful thin penciling of smaller joints within larger ones to give the wall the appearance of an ashlar finish.

1.2.25 Water Repellent

A surface-applied chemcial intended to reduce liquid water entry into a masonry wall without significantly affecting the vapro transmission properties of the original material.

1.2.26 Wall System

A term used to address the fact that masonry structures are comprised of different materials but function holistically, requiring that all restoration and cleaning process take into account the implications of the treatment to the adjacent materials and the building as a whole.

1.2.27 Masonry Treatment Requirement (MTR)

Defined treatments that are required by the specification (contract) documents for project specific repairs to masonry.

1.2.28 Saturated Surface Dry (SSD)

Condition of the wall surface after water has been applied sufficient to saturate more than the surface, then allowed to dry until the surface is dry but the body of the masonry still has moisture.

1.3 ADMINISTRATIVE REQUIREMENTS

1.3.1 Pre-Installation Meeting

Prior to beginning the work of this Section, convene a meeting with the Contracting Officer's Representative(s) to review the requirements of the Quality Control Plan, Project Training Program, installation procedures, location of required mockup areas, and all job conditions and processes. All subcontracting firms involved with this work must participate in this meeting.

1.4 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Quality Control Plan; G

Project Training Program; G

Qualifications; G

SD-03 Product Data

Qualifications

Cleaning and Restoration Methods; G

Cleaning Materials; G

Biocides

Replacement Mortar; G

Mortar Mix; G

Water Repellents Infiltration; G

Stone Consolidants; G

SD-04 Samples

Mock-ups; G

SD-05 Design Data

Calculations for Structural Upgrades; G

SD-06 Test Reports

Testing and Matching

Existing Sealants for Asbestos and PCBs

SD-07 Certificates

Repair Materials

1.5 QUALITY CONTROL

1.5.1 Quality Control Plan

Include a separate section in the overall project Quality Control Plan specifically addressing this restoration and cleaning work. Do not proceed without written approval of the Quality Control Plan. At a minimum, include the following items in the Quality Control Plan:

a. Describe methods of dust containment during the work specific to the work of this section.

b. Describe the methods of protecting surrounding masonry, windows, doors, roof, and building trim as well as surrounding landscape. Provide drawings of protection when requested.

c. Describe the work procedures, materials, and proposed tools to use for each Masonry Treatment Requirement (MTR) specified.

d. Describe the sequence of each MTR.

e. Describe how each MTR sequence and the overall construction schedule changes with weather variations and how completed work will be protected.

f. Describe the methods for surveying original layout and collecting datum points and plumb lines for rebuilding masonry.

g. Describe the methods for shoring and providing a safe working environment.

h. Describe the methods for select deconstruction of individual masonry units and tools/methods for cleaning the masonry for reuse.

i. Describe the method and approach to mortar joint removal.

j. Describe the method and approach for assuring repair material compatibility with original materials.

k. Describe the method and approach to cleaning mortar, coating, smears and old patching materials from the masonry surfaces.

l. Describe, in detail, the procedures relating to techniques and tools proposed for masonry matching.

m. Describe the complete masonry removal and matching procedures; include equipment, approach, length of time the masonry will be out of the wall, documentation on mapping the location, and where (on-site or in shop) the masonry units will be repaired.

n. Describe the procedure for matching of different colors at different locations.

o. Describe the procedure for mixing and matching of repair materials.

p. Describe the methods and system by which the use of reclaimed masonry units can be utilized.

q. Describe the methods for setting masonry back into its original position and maintaining the original bond patterns and joint width.

r. Describe the methods of transition points where replacement/preservation work will meet the original historic work.

s. Describe the on-site project training program. Provide the opportunity for workers to be trained in each masonry treatment requirement (MTR) as work proceeds.

1.5.2 Qualifications

1.5.2.1 Historic Masonry Consultant

a. Secure the services of a historic masonry consultant with a minimum of 10 years experience applying NPS Hist Prop as they relate to the work in this section.

b. Submit a resume that describes five relevant projects within that period and include how NPS Hist Prop was applied to the work of similar scope and scale and what jurisdiction or agency was involved in approving the work..

c. The consultant's services include:

(1) Investigating the condition of the masonry materials and mortar.

(2) Arranging for material analysis in the laboratory

(3) Recommending appropriate cleaning methods and materials

(4) Recommending restoration options.

(5) Providing project specific specifications.

(6) Providing an on-site training program.

(7) Providing quality control services during construction.

(8) Recommending appropriate repair and restoration materials.

1.5.2.2 Masonry Firm

a. The firm performing the masonry work must have a minimum of five years experience on relevant projects.

b. The firm must have completed work similar in material, design, and extent to that indicated for this Project and demonstrate a record of successful in-service performance.

c. Proven implementation of NPS Hist Prop and related Preservation Briefs are required.

d. Submit a resume that describes the required experience.

1.5.2.3 Field Supervisor

Retain an experienced full-time supervisor on the project site at all times when masonry restoration is in progress. A single individual must be responsible for supervising the historic masonry restoration work throughout the duration of the project.

Submit a resume that describes the required experience.

1.5.2.4 Masonry Applicator

a. Employ craftspeople who are experienced with and specialize in restoration work of the types they will be performing.

b. All masonry restoration treatments must be performed by a craftsperson that is familiar with historic masonry construction and has worked on historic masonry projects for at least five years.

c. Only skilled technicians who are familiar and experienced with the materials and methods specified may be used.

d. Submit resumes for all historic masonry applicators, demonstrating the required experience.

1.5.3 Project Training Definition and Use

In addition to five years demonstrable experience on masonry restoration projects, offer workers project training certificate(s) within the framework of ASTM E2659. Project training certificates are earned by individual workers and issued with the understanding that they are for limited time use, enforceable only to this specific project and for a specific MTR. It is not necessary, nor a requirement of this specification, that all restoration workers obtain all project training certificates offered. Rather it is desirable that workers be trained for each project specific task they will perform to ensure the highest quality results from the cleaning and restoration program.

1.5.4 Mortar Analyst

Laboratory mortar analysis equipment should be operated by and results analyzed by trained personnel experienced with analysis of historic masonry mortar.

1.5.5 Documentation

Submit digital photographic documentation of the all phases of masonry restoration, including prior to the start of restoration work.

Provide thorough photo documentation of the project and project details and targeted areas.

1.5.6 Cleaning and Restoration Methods

1.5.6.1 General Procedure

a. Submit the cleaning and restoration methods, and materials selected for a specific structure for approval before work starts.

b. Take into account the total construction system of the building to be worked upon, including different masonry and mortar materials, as well as non-masonry elements which may be affected by the work.

c. Utilize mockups to identify the appropriate cleaning and restoration treatment and materials and set the standard for each project task.

d. Demonstrate the correct execution of the approved cleaning and restoration methods and materials during the on-site workmanship training program within the framework of ASTM E2659.

1.5.6.2 Cleaning Products and Procedures

1.5.6.2.1 General Cleaning Requirements

a. Establish cleaning products and procedures during the mockup process.

b. Select the least aggressive method used to achieve the desired level of cleanliness.

c. Where chemical products are selected for cleaning, use them in accordance with the manufacturer's instructions.

1.5.6.2.2 Cleaning Mock-Ups

a. Demonstrate the materials, equipment, and methods to be used in cleaning in a test section approximately 3 feet by 3 feet.

b. Locate test patches in inconspicuous areas of the building. The areas tested are subject to approval by the Contracting Officer. The areas tested must exhibit soiling characteristics representative of those larger areas to be cleaned.

c. Adjust the cleaning process as required and the test section rerun until an acceptable process is obtained.

d. Conduct tests on areas to be stripped of paint.

e. Allow tested areas to dry before a determination is made on the effectiveness of a particular treatment.

1.5.7 Masonry Restoration Products and Procedures

1.5.7.1 General Restoration Requirements

a. Do not use masonry or mortar in the work until the mock-ups and the represented material and workmanship have been submitted and approved.

b. Demonstrate the methods and quality of workmanship to be performed in each masonry treatment requirement (MTR). Provide a mock-up for each MTR indicated.

1.5.7.2 General Restoration Mock-Up Requirements

a. Throughout restoration, retain approved mock-up panels in undisturbed condition, suitably marked, as a standard for judging completed work.

b. Review manufacturer's product data sheets to determine suitability of each product for each surface.

c. Apply products using manufacturer-approved application methods, determining actual requirements for application.

d. Obtain approval as to the preservation treatment approach, design, and workmanship to include, but not limited to the verification of all material applications and finishes as specified to the requirements of color, texture, profiles, and finishes before proceeding with work.

1.5.7.2.1 Mock-ups

May be performed on inconspicuous sections of actual construction under the same weather conditions expected the remainder of the work.

a. Location and number as directed.

b. Size: 3 feet by 3 feet or as appropriate for the repair specified.

c. Repair unacceptable work.

1.5.7.3 Restoration Mock-Ups

1.5.7.3.1 Repointing

Repoint mortar joints, minimum acceptable mock up dimensions: twelve feet in length - 2/3 horizontal joints and 1/3 vertical joints. Demonstrate method for cutting out mortar joints, preparing wall for repointing, mixing mortar, installing mortar and curing the mortar. Prepare and place repointing mortar in accordance with NPS TPS Brief 2 and in compliance with NPS Hist Prop.

1.5.7.3.2 Retooling Stone Masonry In Situ

Demonstrate treatment technique and methods to retool three deteriorated stone faces in situ in all known historic profile textures identified.

1.5.7.3.3 Masonry Removal and Replacement

Fully remove masonry and replace to specified dimensions and texture. Select size of masonry units representing typical conditions. Return one masonry unit to same location, set to surrounding profile joint width and bond pattern. Set masonry unit using specified mortar. Confirm with Contracting Officer's Representative that the replacement masonry units meet specification requirements for matching and that sufficient quantity required for the work have been identified. Leave one stone dry-set into opening set on wood shims for evaluation and approval of preparation conditions.

1.5.7.3.4 Repair Material

1.5.7.3.4.1 Patching

Apply repair material on at least two masonry units for repair. Include one masonry unit on which to demonstrate proficiency in removing previous patching material and repairing with new substitute repair material. Include the removal of metal anchors at two locations and fill in the holes with repair material on the second masonry unit (where applicable).

1.5.7.3.4.2 Dutchman

Undertake dutchman repairs in two locations, including one that is only cut and prepared for application. Demonstrate the quality of the stone insert, as well as the workmanship and techniques to be performed in the dutchman repairs. Do not proceed with other dutchman repairs until the technique has been approved.

1.5.7.3.5 Crack Repair

Repair one crack, 2 feet in length, using mortar. Repair one crack, 2 feet in length, using dispersed hydrated lime injection technique with appropriate repair material.

1.5.7.3.6 Surface Treatments

Install a minimum 1.5 square meter 16 square foot mockup for each surface treatment on each substrate to be treated. For stucco, demonstrate the means for installing each coat; including mechanical support systems such as wood or metal lath. For water repellents and/or consolidants, demonstrate the equipment and installation procedure. Allow 48 hours for

limewash applications to dry to their final color and appearance.

1.5.7.3.7 New Masonry Elements

Install new components in a manner demonstrating their final installation on the structure.

1.6 DELIVERY, STORAGE, AND HANDLING

a. Furnish cement in suitable bags used for packaging cements.

b. Provide packages with labeling that clearly defines contents, manufacturer, and batch identification.

c. Provide detergents, masonry cleaners, paint removers, solvents, epoxies and other chemicals used for masonry cleaning in sealed containers that legibly show the designated name, formula or specification number, quantity, date of manufacture, manufacturer's formulation number, manufacturer's directions including any warnings and special precautions, and name of manufacturer.

d. Store materials in weathertight structures which will protect all materials from moisture and contaminants.

e. Store accessories to avoid contamination and deterioration.

f. Do not use admixtures which have been in storage onsite for six months or longer, or which have been subjected to freezing, unless retested and proven to meet the specified requirements.

1.7 PROJECT/SITE CONDITIONS

1.7.1 Environmental Requirements

a. Do not place materials when weather conditions adversely affect the quality of the finished product.

b. Do not place masonry or mortar when the air or surface temperature is below 40 degrees F in the shade and will remain so for at least 48 hours after completion of the work. Heated enclosures may be used to overcome ambient weather restrictions, where such enclosures are feasible.

c. Do not place masonry or mortar when air or surface temperature is above 90 degrees F with a wind speed above8 miles per hour and will remain so for at least 48 hours after completion of the work.

d. Do not place masonry or mortar when air or surface temperature is above 100 degrees F with or without wind and will remain so for at least 48 ours after completion of the work.

e. Do not product or place materials during periods of rain or other precipitation. Stop material placements, and protect all in-place material from exposure, during periods of rain or other precipitation.

f. Clean masonry surfaces when air temperatures are above 40 degrees F and will remain so until masonry has dried out, but for not less than 7 days after completion of the work.

g. Do not perform work in wind conditions that may blow materials onto surfaces not intended to be treated.

1.7.2 Masonry Installation Requirements

a. Phase work during hot weather by performing work on the shady side(s) of the building during daylight hours and on the daylight side(s) of the building during cooler evening hours to prevent premature evaporation of the water from the mortar.

b. Do not use frozen materials or materials mixed or coated with ice or frost. Do not apply materials to frozen surfaces; allow complete thawing prior to installation.

c. Do not lower the freezing point of mortar by the use of admixtures or anti-freeze agents. Do not add chlorides or admixtures containing greater than 0.2 percent chlorides to the mortar, per TMS MSJC.

d. Prevent mortar from staining the face of the masonry or other exposed surfaces. Immediately remove mortar that comes in contact with such surfaces. Cover partially completed work when work is not in progress. Protect sills, ledges and projections from mortar droppings. Building damage resulting from work of this Section is the Contractor's responsibility. Restore damaged areas to the satisfaction of the Owner at no expense to the Owner. Do not apply products under conditions outside product manufacturer's requirements.

1.8 WARRANTY

1.8.1 Cleaning Warranty

Warrant cleaning procedures for a period of two years against harm to substrate (masonry and mortar) or to adjacent materials including, but not limited to discoloration of substrate from improper procedures or usage, chemical damage from inadequate rinse procedures, and abrasive damage from improper procedures.

1.8.2 Repair Warranty

Warrant repair procedures, including repointing, for a period of two years against: discoloration or mismatch of new mortar to adjacent original historic mortar, discoloration or damage to masonry from improper mortar clean-up, loss of bond between masonry and mortar, fracturing of masonry edges from improper mortar joint preparation procedures or improper mortar formulation, and occurrence of efflorescence from improper repair procedures.

PART 2 PRODUCTS

2.1 CLEANING MATERIALS

2.1.1 General Requirements

Selection of appropriate cleaning products requires a clear understanding of the masonry materials to be cleaned, a rationale for the cleaning, and an understanding of the anticipated level of cleanliness expected from the cleaning program. Overly aggressive cleaning methods and materials can cause subtle, long-term damage to masonry units. Use products that have a minimum 5 year performance record on relevant projects. Select the

products predicated on long-term negative effects to the masonry rather than current level of cleanliness of the comparable structure.

2.1.2 Paint Removers

a. Provide chemical paint removers that are water soluble, low toxicity products, effective for removal of paint on masonry without altering, damaging, or discoloring the masonry surface.

b. Provide commercially available poulticing materials designed to adhere to and peel off paint without damaging the underlying masonry or project specific mixtures that include absorbent materials and cleaning solutions which can be demonstrated to do no harm to the masonry.

2.1.3 Chemical Cleaners

a. Provide commercially available products that have a proven record of cleaning masonry without altering, damaging or discoloring the masonry units, mortar or surrounding materials.

b. Provide the associated pre and post treatment material to neutralize the long term effects of the chemicals.

2.1.4 Biocides

Provide commercially available biocides with accompanying product literature containing information on the product as well as the expected service life of the material and any detrimental effects it may have on the masonry or mortar.

2.1.5 Liquid Strippable Masking Agent

Provide manufacturer's standard liquid, film-forming, strippable masking material for protecting glass, metal, and polished stone surfaces from the damaging effect of acidic and alkaline masonry cleaners.

2.1.6 Cleaning Implements

Furnish brushes that contain natural or nylon fiber bristles only. Do not use metallic wire brushes. Use scrapers and application paddles made of wood with rounded edges. Metallic tools are not permitted.

2.1.7 Water

Obtain potable water from a local source. Filter to remove minerals resulting in a neutral pH, prior to application.

2.2 REPAIR MATERIALS

2.2.1 General

Use repair materials of one type and from one source, when used in repair treatments that will have surfaces exposed in the finished structure.

2.2.2 Mortar and Stucco

2.2.2.1 Testing and Matching

a. Take test specimens of existing mortar and stucco from a sound and intact representative portion of the structure, at locations by the Contracting Officer's Representative and assess in accordance with ASTM C1713 and ASTM C1324.

b. Subject a part of the historic mortar sample to petrographic examination and differential thermal analysis, or X-ray diffraction, or analytical chemistry to determine the binder components.

c. Aggregate Analysis

(1) Separate aggregate of the mortar sample from the binder by taking the crushed mortar sample and either gently blowing away the fine binder material, placing the crushed sample in a centrifuge, or chemically separating the aggregate from the binder.

(2) Rinse the separated aggregate clean with water and dry.

(3) Perform sand analysis using a sieve analysis of the aggregate as part of the ASTM C1324 process.

d. Match the replacement mortar and stucco to the original existing material in color, texture and tooling.

2.2.2.2 Replacement Mortar and Stucco

Provide replacement mortar and stucco that will:

a. Coexist with the old in a sympathetic, supportive and, if necessary, sacrificial capacity.

b. Have greater vapor permeability and be softer (measured in compressive strength) than the masonry units.

(1) Measure water vapor transmission in accordance with ASTM E96/E96M.

(2) Prepare ASTM E96/E96M water vapor transmission specimens with thickness similar to that expected in service, or a maximum of 1/2 inch, whichever is thinner.

c. Be as vapor permeable, and as soft, or softer, (measured in compressive strength) than the existing historic mortar or stucco.

2.2.2.3 Binder Content

Provide binder type or mixture of mortar (and stucco) with a cement, lime, or combination thereof consistent with the original existing mortar (and stucco) content in order to provide uniform durability, weathering characteristics, and the same, or better, life-cycle performance expectations.

2.2.2.4 Repointing Mortar

Repointing mortar may be site mixed, Type S, Type N, Type L, Type O and Type K.Use lime for repointing mortar that conforms to ASTM C207, Type S,

or ASTM C1489 or unless otherwise specified.

2.2.2.5 Admixtures

Do not use admixtures in the mortar or stucco unless specifically approved in writing by the Contracting Officer.

2.2.3 Crack Injection

a. Comply with the dispersed hydrated lime manufacturer's written instructions.

b. Inject cracks that are no greater than 1/8 inch in width and masonry is soundly bonded but cracked.

c. Inject the full length of the cracks unless specifically instructed otherwise.

2.2.4 Replacement Masonry Materials

2.2.4.1 Clay Brick

a. Provide replacement brick matching color, shape, size, texture, appearance, and thermal expansion properties of the existing historic brick.

b. Test brick in comparison to the original existing historic brick using ASTM C67/C67M.

c. Do not use reclaimed brick unless approved by Contracting Officer.

d. Provide brick meeting the requirements of ASTM C216 Grade SW, including a rating of "not effloresced", unless otherwise specified.

2.2.4.2 Stone

a. Provide replacement sotne matching type, color, shape, size, texture, finish-profile, and compressive strength of the existing historic stone units.

b. Test replacement stone in comparison to the existing historic stone using ASTM C170/C170M.

2.2.5 Surface Treatments

2.2.5.1 General

Provide commercially available coatings with water vapor permeabillity of 0.98 or greater, as measured in accordance with ASTM E96/E96M, including silanes and siloxanes.

2.2.5.2 Consolidants

Provide commercially available consolidants designed to strengthen loose or deteriorated stone without damaging intact stone or reducing water vapor permeability below 0.98, as measured in accordance with ASTM E96/E96M.

2.2.5.3 Water Repellents

Provide commercially available water repellents designed to preclude water droplet entry into the masonry walls without reducing water vapor permeability below 0.98. as measured in accordance with ASTM E96/E96M.

2.2.6 Miscellaneous Materials

2.2.6.1 Cementitious Grout

Use cementitious grout, recommended by the manufacturer for the application, to bond steel anchors to masonry.

2.2.6.2 Metal Attachments

a. Provide threaded or deformed stainless steel anchors for spall repairs, size as indicated.

b. Provide other plates, angles, anchors, and embedments conforming to ASTM A36/A36M, prime painted with inorganic zinc primer.

2.2.6.3 Lead Flashing

Provide commercially available lead flashing conforming to GSA HPTP 07656-01.

2.3 EQUIPMENT

2.3.1 Cleaning Equipment

Provide cleaning equipment that does not cause staining, erosion, marring, or other damage or changes in the appearance of the surfaces to be cleaned.

2.3.1.1 Sandblasting

Use of sandblasting equipment is not allowed for cleaning masonry surfaces.

2.3.1.2 Water Blasting

a. Provide water blasting equipment including a trailer-mounted water tank, pumps, high-pressure hose, wand with safety release cutoff control, nozzle, and auxiliary water re-supply equipment.

b. Do not operate the equipment at a pressure which will cause etching or other damage to the masonry surface or mortar joints. Operate the equipment at a discharge capacity of 55 to 400 psi and 2.5 to 3 gpm for general surface cleaning operations.

c. Provide water tank and auxiliary re-supply equipment of sufficient capacity to permit continuous operations.

d. Provide protective covers and barriers as required to prevent over-spray onto adjacent surfaces.

2.3.1.3 Alternative Blasting Equipment

a. Alternative blasting methods require equipment designed to discharge sponges, walnut shells, ice, soda and other friable materials.

b. Operate equipment in accordance with manufacturer's recommendations and

maintain in good working order.

c. Do not operate equipment at a pressure which will cause etching or other damage to the masonry surface or mortar joints.

d. Determine discharge capacity on a case by case basis during the mockup test panel demonstration and approval process.

e. Provide protective covers and barriers as required to prevent over-spray onto adjacent surfaces.

2.3.2 Spray Equipment

a. Provide spray equipment for chemical cleaners with low-pressure tanks or chemical pumps suitable for chemical cleaner indicated, and equipped with stainless steel, cone-shaped spray-tip.

b. Disperse water through a fan-shaped spray tip at an angle of not less than 15 degrees.

c. Deliver water at a pressure not greater than 400 psi and at a volume between 2.5 and 3 gpm.

d. Deliver heated water at flow rates indicated maintaining between 140 and 180 degrees F.

2.3.3 Drilling Equipment

a. Use standard small, powered, handheld masonry drills, commonly used for drilling small holes in concrete and masonry to drill holes in masonry for patch anchors and other applications.

b. Use drills in rotary mode only. Do not use impact type drills.

2.3.4 Compressed Air Supplies

a. Use compressed air equipment that delivers clean, oil and moisture free compressed air at the surface to be cleaned. Use a minimum of two in-line air filters to remove oil and moisture from the air supply.

b. Test the compressed air supply during each shift for the presence of oil and moisture.

2.3.5 Material Handling and Associated Equipment

2.3.5.1 Mixing, Transporting, and Placing Job Materials

a. Provide equipment used for mixing, transporting, placing, and confining masonry and mortar placements capable of satisfactorily mixing material and supporting uninterrupted placement operations.

b. Provide equipment used for mixing, conveying, and placing of materials that is clean, free of old materials and contaminants, and in conformance with material manufacturer's recommendations.

2.3.5.2 Associated Equipment

Provide associated equipment, such as mixer timing equipment, valves, pressure gauges, pressure hoses, other hardware, and tools, as required to

ensure a continuous supply of material and operation control.

2.4 Mortar Mix

2.4.1 General

a. Proportion materials appropriately with regard to the effect of moisture content on the individual components (cement, sand and lime).

b. Batch materials using volumetric measurement devices and consistently consolidate the material in these devices to ensure the uniformity of the mortar. Do not batch by shovel counts.

2.4.2 Batching

a. Utilize a calibrated measuring device for batching Portland cement.

b. Utilize a calibrated measuring device for batching hydrated lime or lime putty.

c. Utilize a calibrated measuring device for batching the sand.

2.4.3 Cement and Lime Proportions

a. Fill the measuring device with portland cement, hydrated lime or lime putty.

b. Briskly strike the bottom of the measuring device against the ground a minimum of ten times and then strike the top flush.

c. For dry hydrate lime, fill the measuring device using a minimum of three lifts, strike the bottom of the measuring device against the ground a minimum of ten times for each lift and then strike the top flush. Mix dry hydrate lime to a wet paste that is 40 to 42 percent solid.

d. For lime putty briskly strike the bottom of the measuring device against the ground a minimum of ten times and then strike the top flush. No additional lime is required when measuring from putty.

2.4.4 Sand Proportions

a. Proportion sand when the sand is in saturated surface dry (SSD), loose damp condition.

b. Proportion the sand by filling a measuring device using a minimum of three lifts, striking the sides a minimum of ten times, and then striking the top flush.

PART 3 EXECUTION

3.1 EXAMINATION

a. Undertake masonry renovation only after complete evaluation and analysis of the areas to be repaired are completed, including sampling and testing of the existing mortar to determine its composition and qualities. Do not start repair work until conditions that have caused masonry deterioration have been identified and corrected.

b. Use the gentlest means to perform the work and take the greatest of care to ensure that the historic materials are not damaged in the process of the work, as established by mock-ups and testing.

c. In addition to requirements in this Section, comply with NPS Hist Prop.

3.1.1 Field (In Situ) Mortar Examination

a. Detect cracks, degradation and de-bonding from the surrounding masonry.

b. Determine previous surface coating treatments that may be contributing to the current conditions.

c. Compare the bedding mortar with the pointing mortar and determine the cross-sectional characteristics of the wall.

d. Determine the level of moisture movement in the in situ mortar, and if the mortar or masonry units are handling the brunt of the water movement through the wall.

e. Evaluate in situ mortar joint shear strength in accordance with ASTM C1531.

3.1.2 Taking and Preparation of Samples

a. Take and analyze samples of unweathered original historic mortar and different types of mortar in the structure in order to match the new mortar to be used for repointing.

b. Remove three or four samples of each type of mortar to be matched with a hand chisel from several locations on the building. Mortar samples to be intact pieces with a minimum size of 1 ounce.

c. Set aside the largest sample for comparison with the repointing mortar.

d. Place the remaining samples in labeled, sealed sample bags for transport to the laboratory for evaluation per Part 2 of this Specification.

3.2 PREPARATION

3.2.1 Protection

a. Protect persons, motor vehicles, adjacent surfaces, surrounding buildings, equipment, and landscape materials from chemicals used and runoff from cleaning and paint removal operations.

b. Erect temporary protection covers, which will remain in operation during the course of the work, over pedestrian walkways and at personnel and vehicular points of entrance and exit.

c. Protect the interior of buildings from the weather, cleaning, and repair operations at all times.

d. Do not expose workers to chemical substances in excess of the limits established by ACGIH 0100. Comply with more stringent regulations where applicable.

3.2.2 Surface Preparation

a. Do not proceed with cleaning until mock-ups have been approved.

b. Do not proceed with repointing or stucco until existing mortar and stucco have been analyzed and suitable repair materials have been determined.

c. Do not proceed with restoration work until the cause of observed distresses have been identified and corrected.

d. Do not proceed with surface treatments until all other restoration work has been completed.

3.2.3 Equipment and Techniques Demonstration

a. Demonstrate equipment and techniques of operation in an approved location.

b. Assemble dependable and sufficient equipment, appropriate and adequate to accomplish the work specified, at the work site with sufficient lead time before the start of the work to permit inspection, calibration of weighing and measuring devices, adjustment of parts, and the making of any repairs that may be required.

c. Maintain the equipment in good working condition throughout the project.

3.3 MASONRY CLEANING

3.3.1 General

a. Exercise caution against over-cleaning of surfaces, which may be detrimental, and which may remove desirable historic surface details or patinas. For example, if cleaning reveals unexpected joint painting or historic signage; suspend the cleaning action, protect the exposed area and notify the Contracting Officer.

b. Do not damage or mar historic materials in the process of cleaning.

c. Perform cleaning per NPS TPS Brief 1.

d. Protect open joints to prevent water and cleaner intrusion into the interior of the structure.

e. Protect non-masonry materials and severely deteriorated masonry by approved methods prior to initiation of cleaning operations.

f. Remove all organic and inorganic contaminants from the surface and pores of the substrate, without causing any short or long-term negative consequences.

g. Clean surfaces evenly with no evidence of streaking or bleaching.

h. Do not affect the density, porosity, or color of the existing masonry or mortar.

i. Maintain a neutral pH on surface of cleaned masonry units.

j. Use the gentlest methods possible for cleaning historic masonry to

achieve the desired results.

k. Proceed with cleaning in an orderly manner, working from top to bottom of each scaffold width and from one end of each elevation to the other.

l. Perform cleaning in a manner which results in uniform coverage of all surfaces, including corners, moldings, interstices and which produces an even effect without streaking or damage to masonry.

m. Use the following sequence of methods to determine the least aggressive, effective cleaning method:

(1) Water with non-metallic brushes (cold water).
(2) Water with mild soap
(3) Water with stronger soap
(4) Water with stronger soap plus ammonia
(5) Water with stronger soap plus vinegar (but not on calcareous masonry)
(6) Stronger chemical cleaners, only when above methods are determined to be ineffective by the Contracting Officer

3.3.2 Chemical Cleaners

a. Do not use chemical cleaners without approval from the Contracting Officer.

b. Do not use acidic chemical cleaners on limestone, marble, concrete and other calcareous (calcium containing) masonry materials. If chemical cleaners are used on such materials, use alkaline based cleaners with neutralizing afterwashes.

3.3.3 Paint Removal

a. Prior to removal, test existing paint for lead in accordance with Section 02 83 19.13 10 LEAD-BASED PAINT ABATEMENT.

b. Clean areas where paint is to be removed with water and detergent solution to remove surface dirt. Rinse and allow to dry.

c. Remove paint and other coatings from masonry surfaces in areas indicated prior to general cleaning.

d. Do not damage or mar masonry in the process of paint removal.

e. Apply chemical paint removers in accordance with manufacturer's instructions.

f. Protect surrounding painted surfaces from exposure to chemical paint removers to avoid damage.

g. Remove paint containing lead in accordance with Section 02 83 19.13 10 LEAD-BASED PAINT ABATEMENT.

3.3.4 Water Cleaning

3.3.4.1 Pressure Spraying

a. Spray apply water to masonry surfaces to comply with requirements indicated by test patches for location, purpose, water temperature,

pressure, volume, and equipment.

b. Unless otherwise indicated, wash the surface with clean, low pressure water (pressure of less than 55 psi and 2.5 to 3 gpm discharge) and hold spray nozzle not less than 12 inches from surface of masonry.

c. Apply water side to side and top to bottom in overlapping bands to produce uniform coverage.

3.3.4.2 Hand Scrubbing

a. Scrub surfaces to be cleaned to remove surface contaminants.

b. Pre-wet surfaces and use hand-held natural bristle or nylon brushes.

c. Do not use wire brushes.

3.3.4.3 Rinsing

a. Rinse scrubbed surfaces clean of all contaminants and cleaning solutions with water in a low-to-moderate pressure spray, working from top to bottom of each treated area.

b. Remove all traces of contaminants and cleaning solutions.

3.3.5 Chemical Cleaning

3.3.5.1 General

a. Chemical cleaning is the use of any product in addition to water, including detergents, ammonia, vinegar, and bleach.

b. Use gentlest means possible to achieve the desired result as determined by test patches.

c. Proceed in an orderly manner, working from top to bottom of each scaffold width and from one end of each elevation to the other.

d. Provide uniform coverage of all surfaces, including corners, moldings, interstices and produce an even effect without streaking or damage to masonry.

e. Do not apply chemical cleaners to the same masonry surfaces more than twice.

3.3.5.2 Surface Prewetting

a. Wet masonry surfaces to be cleaned with chemical cleaners with water using a low pressure spray before application of any cleaner.

b. Prewet walls working from top to bottom, except work bottom to top on one-story walls.

c. Do not prewet masonry surface prior to applying biocides.

3.3.5.3 Acidic Chemical Cleaning

a. Apply acidic chemical cleaners according to manufacturer's instructions.

b. Do not apply acidic chemical cleaners to masonry with high calcium content (e.g. marble, limestone.

c. Apply acidic cleaners to masonry surfaces by low pressure spray 50 psi max., roller, or brush.

d. Leave cleaner on on masonry surface for the time period recommended by the manufacturer.

e. Employ manual scrubbing by brushes as indicated by test patches for the specific location.

f. Rinse cleaned surfaces with a low-to-moderate pressure spray of water to remove all traces of chemical cleaner.

3.3.5.4 Alkaline Chemical Cleaning

3.3.5.4.1 Prewash Phase

a. Apply alkaline chemical cleaners to masonry surfaces according to manufacturer's instructions, by low pressure spray 50 psi max., roller, or brush.

b. Leave cleaner on masonry surface for the time period recommended by the manufacturer.

c. Employ manual scrubbing by brushes as indicated by test patches for the specific location.

d. Rinse cleaned surfaces with a low-to-moderate pressure spray of water.

3.3.5.4.2 Afterwash Phase

a. Immediately after rinsing of alkaline cleaned surfaces, apply a neutralizing afterwash to the cleaned masonry areas.

b. Apply neutralizing afterwash according to manufacturer's instructions, by low pressure spray 50 psi max., roller, or brush.

c. Leave afterwash on masonry surface for the time period recommended by manufacturer.

d. Rinse cleaned surfaces with a low-to-moderate pressure spray of water to remove all traces of chemical cleaners.

3.3.5.5 Rinsing and pH Testing

a. Determine the pH of masonry surfaces that have been chemically cleaned using pH monitoring pencils or papers.

b. Rinse chemically cleaned masonry, using a low pressure spray, until a neutral pH (7) reading is obtained from the masonry unit surface.

3.4 MASONRY REPAIR

3.4.1 General

a. Match repaired surfaces with adjacent existing surfaces in all respects.

b. Demonstrate the materials, methods and equipment proposed for use in the repair work in mock-ups, as specified in PART 2.

c. Use products in accordance with the manufacturer's instructions.

d. Proceed with masonry repair only after the cause of deterioration has been corrected.

e. Assist Historic Masonry Consultant with performing field investigation to determine the causes and extent of degradation. Utilize the following techniques.

(1) Employ a field microscope to closely assess the conditions at the surface of the mortar and masonry units. Detect cracks and assess for degradation and debonding from the surrounding masonry. Detect previous surface coating treatments on the mortar and masonry that may be contributing to the current conditions.

(2) Employ a boroscope to examine mortar deeper in the joint. Compare the bedding mortar with the pointing mortar and ascertain the cross-sectional characteristics of the wall.

(3) Employ moisture meters to determine the level of moisture in the mortar and masonry, and if the mortar or masonry units are handling the brunt of the water movement through the wall. Infrared thermography, employed by a trained investigator, can provide additional information on the moisture conditions.

(4) Employ RILEM tubes using the method of RILEM II.4 or water penetration testing in accordance with ASTM C1601 to determine the rate of water uptake into the masonry.

(5) To access the physical characteristics of hard mortar, use a spring loaded or pendulum impact device to determine surface hardness as an indicator of relative compressive strength. For evaluating softer mortars, mortar integrity deeper in the wall, and the condition of the masonry units, use a drill resistance tool by an experienced consultant.

(6) Utilize technologies such as ground penetrating radar or metal detection equipment to map metal reinforcement and embedments in the wall.

(7) Use flat jack or jacks and rams to gather information on in situ compressive stress (ASTM C1196, masonry compressive response ASTM C1197, and mortar joint shear strength ASTM C1531.

3.4.2 Repointing Masonry

Repoint masonry in accordance with NPS TPS Brief 2, using ASTM E2260 as a reference guide.

3.4.2.1 Wall Preparation

a. Remove old caulking, grout, or non-original mortar from previously repaired joints to a minimum depth of 2.5 times the width of the joint. Cut all joints (unless otherwise noted) back to sound, solid, back up material. Leave a clean, square face at the back of the joint to provide for maximum contact of repointing mortar.

b. Shallow or feather edging is not permitted. Remove loose particles from joints. Clean joints, followed by blowing with filtered, dry, compressed air or vacuum.

c. Cut out existing horizontal mortar joints (bed joints) that are filled with a hard Portland mortar using a diamond blade that is narrower than the joint width. Cut out the middle one-third of the mortar joint using a rotary power saw. Remove the remaining mortar from the masonry joints by hand using masonry chisels or pneumatic carving tools.

d. Do not use rotary power saws to cut out vertical joints (head joints) . Remove all vertical head joints by hand using a pneumatic carving tool, or hammer and chisel.

e. Remove existing historic lime-based mortar using only small-headed chisels that are no wider than half the width of the existing masonry joints. Pneumatic air carving chisels are permitted as are specially designed mortar removal reciprocating tools (i.e. Arbortech Saw).

f. Do not widen the existing masonry joints. Do not chip or spall the surrounding masonry edges in the process of mortar removal. Damage to surrounding masonry units resulting from rotary blade over running is not permitted. Damages to adjacent materials exceeding 1/8 inch in size are the responsibility of the contractor and must be repaired by removal and replacement of damaged materials.

g. Permit applicators to be trained at the project site in this masonry treatment requirement.

3.4.2.2 Presoaking Masonry / Mortar Consistency / Lifts

a. Use the same mortar as the repointing mortar for setting the replacement masonry.

b. Soak exposed surfaces of historic masonry adjacent to joint with water prior to repointing.

c. Allow time for excess water to run off and evaporate prior to repointing. Joint surfaces must be damp but free from standing water.

d. Maintain a water sprayer on site at all times during the repointing process.

e. The mortar material must resemble the consistency of brown sugar during installation. This drier consistency enables the material to be tightly packed into the joint, allows for cleaner work, and prevents shrinkage cracks as the mortar cures.

f. Allow mixed repointing mortar to stand for not less than one-half hour and not more than one and one-half hours for pre-hydration to reduce post-curing shrinkage. After this time, water can be added to small batches by hand to bring the mortar to a stiff yet workable consistency. Use repointing mortar within two and one-half hours after initial mixing and within one hour after adding water to bring the mortar to a working consistency. Retempering of the mortar to replace evaporated water is permitted within these time frames.

g. Point joints in layers or "lifts" where the joints are deeper than

1-1/4 inch. Apply in layers not less than 1/2 the depth but not more than 1-1/4 inch or until a uniform depth is formed.

3.4.2.3 Compression / Joint Finish / Curing

a. Compress each layer thoroughly.

b. When mortar is thumbprint hard at the surface of the wall, finish the joints to match the original historic joint profile.

c. For Type L mortar:

(1) Allow water evaporation from the freshly repointed walls in order to initiate the carbonation process in high lime content mortars. The carbonation of lime mortar initially requires wet-and-dry cycles, which can be created by water misting the joints after the mortar application when dry weather conditions prevail. Finish the joint profile before these cycles are started.

(2) Depending on the environmental conditions (temperature and humidity), carry out water misting until a full nine alternating wet-and-dry cycles are completed.

(3) Adjust curing methods to ensure that the repointing mortar is damp without eroding the surface of the mortar.

3.4.2.4 Protection

a. Keep the mortar from drying out too quickly or from becoming too wet.

b. Protect mortar from direct sun and high winds for the first 72 hours after installation or from driving rain for the first 24 hours, using plastic sheeting if necessary. Do not create a greenhouse effect by sealing off air movement in an attempt to protect the wall with plastic. Allow for air circulation to facilitate the carbonation process.

3.4.3 Retooling Stone Masonry In situ

a. Scale off all loose pieces of original stone from masonry intended to remain in place, including surface material in powder or granular form and detachments of planer elements, spalls and chips.

b. Assess all stone on building by sounding (tapping with a small hammer) or by using impact echo (for massive stones), surface penetrating radar, or infrared thermography in order to distinguish fully intact stone from those in which delamination may be hidden or pieces of unstable material may not be immediately visible.

c. Remove and replace stone units that are designated for retooling in situ, but develop a solid stone substrate that is no longer in plane or plumb with the surrounding stone masonry surfaces after chiseling is complete.

3.4.4 Masonry Removal and Replacement

a. Before removing any deteriorated masonry units, establish bonding patterns, levels and coursings. Remove masonry that has deteriorated or is damaged beyond repair, as determined through investigation and

evaluation. Carefully demolish or remove entire units from joint to joint, without damaging surrounding units in a manner that permits replacement with full-size units. Support and protect remaining masonry work that surrounds removal area. Maintain flashing, reinforcement, lintels, and adjoining construction in an undamaged condition. Notify Contracting Officer of unforeseen detrimental conditions including voids, cracks, bulges, and loose masonry units in existing masonry backup, rotted wood, rusted metal, and other deteriorated items. Remove as many whole masonry units as possible without damage.

b. Remove mortar, loose particles, and soil from masonry by cleaning with hand chisels, non-metallic brushes, and water.

c. Remove sealants by cutting close to masonry units with utility knife and cleaning with solvents. Clean surrounding masonry areas by removing mortar, dust, and loose particles in preparation for replacement.

d. Replace removed masonry with masonry units removed from inconspicuous areas of the building, where possible, or with new masonry units matching the existing units. Butter vertical joints for full width before setting and set units in full bed of mortar, unless otherwise indicated. Remove mortar used for laying/setting masonry units before mortar sets to the repointing depth of the surrounding area. Repoint new mortar joints in repaired area to comply with requirements for repointing at existing masonry units.

e. If a few isolated masonry units are to be replaced, remove each without disturbing the surrounding masonry. Remove deteriorated masonry units and mortar requiring replacement by hand chiseling. Do not damage adjoining masonry units during the removal of deteriorated units and mortar.

f. Test the new element for fitting into its space without mortar. Use wedges made from non-expanding, non-corrosive material such as plastic to support and align the new unit, cover them with at least 1-1/2 inches of mortar when pointing is complete.

g. Cover the four sides of the space with sufficient mortar to ensure that there will be no air spaces when the new unit is set. Fill the back of the space with mortar only if it matches existing construction.

h. Line up and set the new unit by tapping it into place with a wooden or rubber mallet. Align the face of new unit with that of existing masonry.

i. Repoint joints to match the rest of the wall after new units have been properly installed and adjusted.

j. Clean replacement areas with a non-metallic brush and water to remove excess mortar.

3.4.5 Material Repair

Repair or replace original historic masonry materials only if surfaces are extensively deteriorated (surface missing to a depth of 4 inches or more) or are threatening the safety of the structure or individuals. If additional damage is found, notify the Contracting Officer. Repairs and

replacements must match the materials, colors, and finish of the existing historic masonry as closely as possible.

3.4.5.1 Selective Demolition

a. Remove unsound, weak, or damaged masonry and mortar in areas as indicated.

b. Remove loose particles, laitance, spalling, cracked, or debonded masonry and mortar and foreign materials with hand tools unless otherwise noted.

c. Clean surfaces prepared for repair free of dust, dirt, masonry chips, oil or other contaminants, rinsed with water, and dried before repair work is begun.

d. Protect surfaces of the structure, and surfaces adjacent to the work area from damage which may result from removal, cleaning, and repair operations.

3.4.5.2 Application of Substitute Repair Materials

a. Place repair materials to rebuild spalled or damaged areas to match the original surface finish, level, texture, bonding patterns, color and porosity. Match the finished appearance of the substitute repair material patch with the adjacent existing surface. Apply samples to the masonry units in situ.

b. Do not install repair material in thicknesses exceeding 2 inches. Utilize a Dutchman repair approach or replacement unit for masonry repairs in excess of 2 inches.

c. Remove loose mortar and masonry prior to installation of the repair material. "Sound" the masonry with a hammer to verify its integrity. If necessary, cut away an additional 1/2 inch of the masonry substrate to ensure the surface to be repaired is solid and stable.

d. Remove all deteriorated stone, mortar, sealant residue, and previous repair materials back to sound substrate using hammer and chisel or power equipment. Finish edges square to a minimum depth of 1/2 inch. Do not feather edges. Roughen substrate surface to achieve surface roughness required by manufacturer for good bond, but do not overly damage the substrate surface.

e. Remove sealant residue. Cut out used anchors, threaded rod anchors and/or dowels within the damaged masonry area. Any anchors that are free of rust, solidly embedded, and do not project beyond the solid masonry surface may remain.

f. Using clean water and a non-metallic scrub brush, clean dust from surface and pores of the substrate.

g. Pre-wet the substrate with water prior to the application of the repair material to prevent the substrate from drawing out the moisture too quickly. Re-wet the surface with water again immediately before applying the repair material. Use methods approved by the repair material manufacturer to deliver the substitute repair work as demonstrated.

h. Follow manufacturers' instructions pertaining to the placement of materials. If the manufacturer requires that installers of a specified product be trained, provide this documentation to the Contracting Officer. Training certificates previously issued by product companies for the application of specified products cannot be substituted for the Project Training "Substitute Repair Material Certificate" on this project.

i. Masonry and Material Repair Finishes and Color

(1) Match the exposed surfaces of masonry and substitute material repair finish, color, texture, and surface detail with the original surface. Mechanical finishing and texturing may be required to produce the required finish and appearance.

(2) Conceal bond lines between the repaired area and adjacent surfaces.

(3) Replicate all surface details, including tooling and machine marks.

(4) Use low-impact energy type equipment in finishing and texturing, which will not weaken the patch or damage the patch bond and the adjacent masonry.

3.4.5.3 Patch Anchors

a. Provide patch anchors to ensure that the patch is tied to the existing masonry structure at a frequency of at least one patch anchor per 4 square inches of patch plan surface area; specific locations for patch anchors must be as indicated.

b. Use small handheld, low-speed rotary masonry drills to produce holes in the existing masonry, within the limits for the patch anchor installation.

(1) Drill holes into the existing substrate material of the masonry using rotary (non-hammer) drills making holes with a diameter of 1/8 inch larger than the anchor diameter and a depth of 4 inches, except as otherwise indicated or directed.

(2) Drill holes must not penetrate completely through the masonry, and must provide at least 1 inch of cover around the drill hole.

(3) Clean holes by water blasting to remove drill dust and other debris and then blow dry with filtered, dry, compressed air.

(4) Condition drill holes in accordance with the epoxy adhesive manufacturer's recommendations.

c. Clean anchors to remove all contaminants which may hinder epoxy bond.

d. Pressure inject adhesive into the back of the drilled holes.

(1) Fill holes without spilling excess grout when the anchors are inserted.

(2) Insert anchors immediately into the holes.

(3) Set back anchors from the exterior face at least 1 inch.

(4) Install anchors without breaking or chipping the exposed masonry surface.

(5) Use socked or screen tube anchors where voids exist in the masonry units or between the wythes.

3.4.5.4 Cleanup

a. Protect masonry surfaces from excess grount adhesive and spills.

b. Leave the surface of the masonry in a clean and uncontaminated condition.

3.4.6 Dutchman Repairs

a. Select stone for Dutchman repairs from the following three sources listed in order of priority:

(1) Stone harvested from the same elevation and stone type.

(2) Approved salvaged stone.

(3) New stone made from a similar stone type.

b. Fit the new piece into place with tolerances of no more than plus or minus 1/16-inch.

c. Provide supporting rods of stainless steel as necessary for the extent of the repair and the location.

d. Closely blend repairs in with the surrounding original materials.

3.4.7 Crack Injection with Dispersed Hydrated Lime (DHL)

3.4.7.1 General

a. Notify the Contracting Officer as to when and where the installation will occur at least 48 hours prior to start.

b. Provide samples to the Government representative from the dispenser during the course of the injection.

c. Apply in accordance with the manufacturer's instructions.

3.4.7.2 Application of DHL

a. Drill 1/8-inch diameter, downward-sloping injection holes. For transverse cracks less than 1/8 inch wide, drill holes through center of crack at 1 to 1.5 inches on center.

b. Clean out drill holes and cracks with compressed air and potable water. Remove dirt and organic matter, loose material, sealants, and failed crack repair materials.

c. Inject Dispersed Hydrated Lime using hypodermic needles or pressure ports through holes sequentially, beginning at one end of area and working to opposite end. Do not exceed 10 psi injection pressure. Where possible begin at lower end of injection area and work upward. Inject Dispersed Hydrated Lime until it extrudes from adjacent holes.

After Dispersed Hydrated Lime has set, remove excess material and patch injection holes and surface of cracks with appropriate surface treatment.

3.4.7.3 Tools and Equipment

Do not use tools and equipment that have not been cleaned of set dispersed hydrated lime.

3.4.8 Surface Treatments

3.4.8.1 Stucco

a. Apply stucco on a clean surface in accordance with ASTM C926 at a thickness matching surrounding historic surfaces.

b. Soak the substrate with water to saturated surface dry (SSD) condition prior to application of scratch-coat.

c. Apply the scratch-coat and allow to partially-set on the wall surface.

d. Use a scratch rake to create the keys into the scratch coat for acceptance of the finish coat.

e. Apply the finish coat approximately 24 hours after the scratch coat application.

f. Soak the scratch coat with water to SSD condition prior to the application of the finish coat.

g. Apply the textured finish and profile to match the surrounding historic surfaces.

3.4.8.2 Limewashes

a. Apply limewash using fiber brushes in three thin coats on saturated surface dry (SSD) raw masonry surfaces.

b. Do not allow the material to dry out before it has had a chance to absorb into the masonry surfaces.

c. Work from top to bottom of the wall working from the dry-edge.

d. Allow six hours drying time between coats

e. Where colors are desired, use natural earth pigments.

f. Verify all applications, materials and colors through mock ups panels applied to the substrate prior to the start of the work.

3.4.8.3 Water Repellents Infiltration

Application of water proofing is not allowed.

Application of water repellents may be performed upon Contracting Officer approval of the recommendation and justification, by the historic masonry consultant, that no other means will control water infiltration. Apply water repellents per manufacturer's instructions.

3.4.8.4 Stone Consolidants

Use of stone consolidants requires Contracting Officer approval of the historic masonry consultants recommendation, including justifying data. Apply stone consolidants per manufacturer's instructions.

3.5 INSTALLATION OF NEW ELEMENTS

Evaluate new materials and components for both functional and aesthetic impacts on historic structures.

3.5.1 Structural Upgrades

For mechanical anchors used to reinforce masonry structures, provide design by a registered professional structural engineer. Strengthening measures must take into account the current loads and stresses in the structure and the nature in which the building has historically managed thermal and other environmental changes or cycles.

Submit manufacturers literature, design analysis and detail drawings for the proposed additional materials.

3.5.2 Joint Sealant and Lead Flashing

a. Test existing sealants for asbestos and PCBs before performing demolition.

b. Provide joint sealing as specified in Section 07 92 00 JOINT SEALANTS.

   (1) Augmentation with lead flashing is allowed for upward facing joints exposed to weather.

   (2) Install sealants and lead flashing in accordance with manufacturer's recommendations.

3.6 FINAL CLEANING

a. No sooner than 72 hours after completion of the repair work and after joints are sealed, wash down faces and other exposed surfaces of masonry with water applied with a soft bristle brush, then rinse with clean water.

b. Discolorations that cannot be removed by these procedures, are considered defective work.

c. Perform cleaning work when temperature and humidity conditions allow the surfaces to dry rapidly.

d. Protect adjacent surfaces from damage during cleaning operations.

3.7 PROTECTION OF WORK

Protect work against damage from subsequent operations.

3.8 DEFECTIVE WORK

Repair or replace defective work as directed by Contracting Officer, using approved procedures.

3.9 FINAL INSPECTION

Following completion of the work, inspect the structure for damage, staining, and other distresses. Inspect the patches for cracking, crazing, delamination, unsoundness, staining and other defects. Inspect the finish, texture, color and shade, and surface tolerances of the patches to verify that all requirements have been met. Repair surfaces exhibiting defects as directed.

a. Following completion of the work, inspect the structure for damage, staining, and other distresses.

   (1) Inspect patches for cracking, crazing, delamination, unsoundness, staining and other defects.

   (2) Inspect finish, texture, color and shade, and surface tolerances of the patches to verify that all requirements have been met.

b. Repair surfaces exhibiting defects as directed by Contracting Officer.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

SECTION 06 10 00

ROUGH CARPENTRY

08/16

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 DELIVERY AND STORAGE
1.4 GRADING AND MARKING
1.4.1 Lumber
1.4.2 Plywood
1.4.3 Preservative-Treated Lumber and Plywood
1.4.4 Fire-Retardant Treated Lumber
1.5 SIZES AND SURFACING
1.6 MOISTURE CONTENT
1.7 PRESERVATIVE TREATMENT
1.8 FIRE-RETARDANT TREATMENT
1.9 QUALITY ASSURANCE
1.9.1 Data Required
1.9.2 Plastic Lumber Performance
1.10 CERTIFICATIONS
1.10.1 Certified Wood Grades
1.10.2 Certified Sustainably Harvested Wood

PART 2 PRODUCTS

2.1 MATERIALS
2.1.1 Virgin Lumber
2.1.2 Natural Decay- and Insect-Resistant Wood
2.1.3 Plastic Lumber
2.1.3.1 Shear Parallel to Length
2.1.3.2 Density
2.1.3.3 Compressive Strength
2.1.3.4 Flexural Strength
2.1.3.5 Tensile Strength
2.1.3.6 Coefficient of Thermal Expansion
2.1.3.7 Screw Withdrawal
2.1.3.8 Nail Withdrawal
2.2 LUMBER
2.2.1 Structural Lumber
2.2.2 Framing Lumber
2.3 PLYWOOD, STRUCTURAL-USE, AND ORIENTED STRAND BOARD (OSB) PANELS
2.3.1 Other Uses
2.3.1.1 Plywood
2.3.1.2 Structural-Use and OSB Panels
2.4 [Enter Appropriate Subpart Title Here]
2.4.1 Other Materials
2.4.1.1 Wood Members
2.4.2 [Enter Appropriate Subpart Title Here]

2.4.2.1 Nonstress Graded Members
2.4.2.2 Wood Bumpers
2.4.2.3 Sill Plates
2.4.2.4 Blocking
2.4.2.5 Rough Bucks and Frames
2.4.3 Adhesives
2.5 ROUGH HARDWARE
2.5.1 Bolts, Nuts, Studs, and Rivets
2.5.2 Anchor Bolts
2.5.3 Expansion Shields
2.5.4 Lag Screws and Lag Bolts
2.5.5 Wood Screws
2.5.6 Nails
2.5.7 Wire Nails
2.5.8 Timber Connectors
2.5.9 Clip Angles
2.5.10 Joist Hangers
2.5.11 Tie Straps
2.5.12 Joist Anchors
2.5.13 Door Buck Anchors
2.5.14 Metal Bridging
2.5.15 Toothed Rings and Shear Plates
2.5.16 Beam Anchors
2.5.17 Metal Framing Anchors
2.5.18 Panel Edge Clips

PART 3 EXECUTION

3.1 INSTALLATION
3.1.1 Sills
3.1.1.1 Anchors in Masonry
3.1.1.2 Anchors in Concrete
3.1.2 Beams and Girders
3.1.3 Roof Framing or Rafters
3.1.4 Joists
3.1.4.1 Floor (Ceiling) Framing
3.1.4.2 Doubled Joists
3.1.4.3 Tie Straps
3.1.4.4 Joist Anchors
3.1.5 Bridging
3.1.5.1 Wood Cross-Bridging
3.1.5.2 Metal Cross-Bridging
3.1.6 Columns and Posts
3.1.7 Wall Framing
3.1.7.1 Studs
3.1.7.2 Plates
3.1.7.3 Firestops
3.1.7.4 Diagonal Bracing
3.1.8 Ceiling Joists
3.1.9 Metal Framing Anchors
3.1.10 Stair Framing
3.2 MISCELLANEOUS
3.2.1 Wood Roof Nailers, Edge Strips, Crickets, Curbs, and Cants
3.2.1.1 Roof Nailing Strips
3.2.1.2 Roof Edge Strips and Nailers
3.2.1.3 Crickets, Cants, and Curbs
3.2.2 Rough Wood Bucks
3.2.3 Wood Blocking
3.2.4 Wood Furring

3.2.5 Wood Bumpers
3.2.6 Temporary Closures
3.2.7 Wood Sleepers
3.2.8 Bridging
3.2.9 Corner Bracing
3.2.10 Sill Plates
3.3 INSTALLATION OF TIMBER CONNECTORS
3.4 ERECTION TOLERANCES
3.5 WASTE MANAGEMENT OF WOOD PRODUCTS

-- End of Section Table of Contents --

SECTION 06 10 00

ROUGH CARPENTRY
08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN FOREST FOUNDATION (AFF)

ATFS STANDARDS	(2015) American Tree Farm System Standards of Sustainability 2015-2020

AMERICAN INSTITUTE OF TIMBER CONSTRUCTION (AITC)

AITC TCM	(2012) Timber Construction Manual, 5th Edition

AMERICAN LUMBER STANDARDS COMMITTEE (ALSC)

ALSC PS 20	(2015) American Softwood Lumber Standard

AMERICAN RAILWAY ENGINEERING AND MAINTENANCE-OF-WAY ASSOCIATION (AREMA)

AREMA Eng Man	(2017) Manual for Railway Engineering

AMERICAN WOOD COUNCIL (AWC)

AWC NDS	(2015) National Design Specification (NDS) for Wood Construction
AWC WFCM	(2012) Wood Frame Construction Manual for One- and Two-Family Dwellings

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)

AWPA M2	(2016) Standard for the Inspection of Preservative Treated Wood Products for Industrial Use
AWPA M6	(2013) Brands Used on Preservative Treated Materials

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

APA E445	(2002) Performance Standards and Qualification Policy for Structural-Use Panels (APA PRP-108)
APA EWS T300	(2007) Technical Note: Glulam Connection Details

APA F405	(19) Product Guide: Performance Rated Panels
APA L870	(2010) Voluntary Product Standard, PS 1-09, Structural Plywood
APA S350	(2014) PS 2-10, Performance Standard for Wood-Based Structural-Use Panels

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2015) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B18.5.2.1M	(2006; R 2011) Metric Round Head Short Square Neck Bolts
ASME B18.5.2.2M	(1982; R 2010) Metric Round Head Square Neck Bolts
ASME B18.6.1	(2016) Wood Screws (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM A153/A153M	(2016) Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
ASTM A307	(2014; E 2017) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM A653/A653M	(2017) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM D1435	(2013) Standard Practice for Outdoor Weathering of Plastics
ASTM D198	(2015) Standard Test Methods of Static Tests of Lumber in Structural Sizes
ASTM D2344/D2344M	(2016) Standard Test Method for Short-Beam Strength of Polymer Matrix Composite Materials and Their Laminates
ASTM D2898	(2010; R 2017) Standard Practice for Accelerated Weathering of Fire-Retardant-Treated Wood for Fire Testing
ASTM D6108	(2013) Standard Test Method for Compressive Properties of Plastic Lumber

	and Shapes
ASTM D6109	(2013) Standard Test Methods for Flexural Properties of Unreinforced and Reinforced Plastic Lumber and Related Products
ASTM D6111	(2013a) Standard Test Method for Bulk Density and Specific Gravity of Plastic Lumber and Shapes by Displacement
ASTM D6112	(2013) Compressive and Flexural Creep and Creep-Rupture of Plastic Lumber and Shapes
ASTM D6117	(2016) Standard Test Methods for Mechanical Fasteners in Plastic Lumber and Shapes
ASTM D696	(2016) Standard Test Method for Coefficient of Linear Thermal Expansion of Plastics Between -30 degrees C and 30 degrees C With a Vitreous Silica Dilatometer
ASTM F1667	(2017) Standard Specification for Driven Fasteners: Nails, Spikes, and Staples
ASTM F547	(2017) Standard Terminology of Nails for Use with Wood and Wood-Base Materials

CSA GROUP (CSA)

CSA Z809-08	(R2013) Sustainable Forest Management

FM GLOBAL (FM)

FM 4435	(2013) Roof Perimeter Flashing

FOREST STEWARDSHIP COUNCIL (FSC)

FSC STD 01 001	(2015) Principles and Criteria for Forest Stewardship

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2018) International Building Code

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)

NHLA Rules	(2015) Rules for the Measurement & Inspection of Hardwood & Cypress

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)

NELMA Grading Rules	(2013) Standard Grading Rules for Northeastern Lumber

PROGRAMME FOR ENDORSEMENT OF FOREST CERTIFICATION (PEFC)

PEFC ST 2002:2013	(2015) PEFC International Standard Chain

of Custody of Forest Based Products Requirements

REDWOOD INSPECTION SERVICE (RIS) OF THE CALIFORNIA REDWOOD ASSOCIATION (CRA)

RIS Grade Use (1998) Redwood Lumber Grades and Uses

SOUTHERN CYPRESS MANUFACTURERS ASSOCIATION (SCMA)

SCMA Spec (1986; Supple. No. 1, Aug 1993) Standard Specifications for Grades of Southern Cypress

SOUTHERN PINE INSPECTION BUREAU (SPIB)

SPIB 1003 (2014) Standard Grading Rules for Southern Pine Lumber

SUSTAINABLE FOREST INITIATIVE (SFI)

SFI 2015-2019 (2015) Standards, Rules for Label Use, Procedures and Guidance

TRUSS PLATE INSTITUTE (TPI)

TPI 1 (2014) National Design Standard for Metal Plate Connected Wood Truss Construction, Including Commentary and Appendices

TPI HIB (1991) Commentary and Recommendations for Handling, Installing and Bracing Metal Plate Connected Wood Trusses

U.S. DEPARTMENT OF COMMERCE (DOC)

DOC/NIST PS56 (1973) Structural Glued Laminated Timber

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

CID A-A-1923 (Rev A; Notice 3) Shield, Expansion (Lag, Machine and Externally Threaded Wedge Bolt Anchors)

CID A-A-1924 (Rev A; Notice 3) Shield, Expansion (Self Drilling Tubular Expansion Shell Bolt Anchors

CID A-A-1925 (Rev A; Notice 3) Shield Expansion (Nail Anchors)

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)

WCLIB 17 (2015) Standard Grading Rules

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)

WWPA G-5 (2017) Western Lumber Grading Rules

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Plastic Lumber

Fire-retardant Treatment

Adhesives

Recycled Content for Plastic Lumber; S

SD-05 Design Data

Modifications of Structural Members; G

Design analysis and calculations showing design criteria used to accomplish the applicable analysis.

SD-06 Test Reports

Preservative-treated Lumber and Plywood

SD-07 Certificates

Certificates of Grade

Certified Sustainably Harvested Virgin Lumber; S

Certified Sustainably Harvested Natural-decay and Insect-resistant Wood; S

Certified Sustainably Harvested Framing Lumber; S

Certified Sustainably Harvested Structural Glued Laminated Timber; S

Certified Sustainably Harvested Plywood Subflooring; S

Certified Sustainably Harvested Structural-use and OSB Panel Subfloor Sheathing; S

Certified Sustainably Harvested Plywood Combination Subfloor Underlayment; S

Certified Sustainably Harvested Plywood Wall Sheathing; S

Certified Sustainably Harvested Structural-use and OSB Panel Wall Sheathing; S

Certified Sustainably Harvested Structural-use and OSB Panel Diaphragm; S

Paint and Repair Requirements

Certified Sustainably Harvested Plywood Shear Wall; S

Certified Sustainably Harvested Structural-use and OSB Panel Shear Wall; S

Certified Sustainably Harvested Plywood for Other Uses; S

Certified Sustainably Harvested Structural-use and OSB Panels for Other Uses; S

Preservative Treatment

SD-10 Operation and Maintenance Data

Take-back Program

Include contact information, summary of procedures, and the limitations and conditions applicable to the project. Indicate manufacturer's commitment to reclaim materials for recycling or reuse.

1.3 DELIVERY AND STORAGE

Deliver materials to the site in an undamaged condition. Store, protect, handle, and install prefabricated structural elements in accordance with manufacturer's instructions and as specified. Store materials off the ground to provide proper ventilation, with drainage to avoid standing water, and protection against ground moisture and dampness. Store materials with a moisture barrier at both the ground level and as a cover forming a well ventilated enclosure. Store wood I-beams and glue-laminated beams and joists on edge. Adhere to requirements for stacking, lifting, bracing, cutting, notching, and special fastening requirements. Do not use materials that have visible moisture or biological growth. Remove defective and damaged materials and provide new materials. Store separated reusable wood waste convenient to cutting station and area of work.

1.4 GRADING AND MARKING

1.4.1 Lumber

Mark each piece of framing and board lumber or each bundle of small pieces of lumber with the grade mark of a recognized association or independent inspection agency. Such association or agency must be certified by the Board of Review, American Lumber Standards Committee, to grade the species used. Surfaces that are to be exposed to view must not bear grademarks, stamps, or any type of identifying mark. Hammer marking will be permitted on timbers when all surfaces will be exposed to view.

1.4.2 Plywood

Mark each sheet with the mark of a recognized association or independent inspection agency that maintains continuing control over the quality of the plywood. The mark must identify the plywood by species group or span rating, exposure durability classification, grade, and compliance with APA L870. Surfaces that are to be exposed to view must not bear grademarks or other types of identifying marks.

1.4.3 Preservative-Treated Lumber and Plywood

The Contractor is responsible for the quality of treated wood products. Each treated piece must be inspected in accordance with AWPA M2 and permanently marked or branded, by the producer, in accordance with AWPA M6. The Contractor must provide Contracting Officer's Representative (COR) with the inspection report of an approved independent inspection agency that offered products comply with applicable AWPA Standards. The appropriate Quality Mark on each piece will be accepted, in lieu of inspection reports, as evidence of compliance with applicable AWPA treatment standards.

1.4.4 Fire-Retardant Treated Lumber

Mark each piece in accordance with AWPA M6, except pieces that are to be natural or transparent finished. In addition, exterior fire-retardant lumber must be distinguished by a permanent penetrating blue stain. Labels of a nationally recognized independent testing agency will be accepted as evidence of conformance to the fire-retardant requirements of AWPA M6.

1.5 SIZES AND SURFACING

ALSC PS 20 for dressed sizes of yard and structural lumber. Lumber must be surfaced four sides. Size references, unless otherwise specified, are nominal sizes, and actual sizes must be within manufacturing tolerances allowed by the standard under which the product is produced. Other measurements are IP or SI standard.

1.6 MOISTURE CONTENT

Air-dry or kiln-dry lumber. Kiln-dry treated lumber after treatment. Maximum moisture content of wood products must be as follows at the time of delivery to the job site:

a. Framing lumber and board, 19 percent maximum

b. Timbers 5 inches and thicker, 25 percent maximum

c. Roof planking, 15 percent maximum

d. Porch decking, 15 percent maximum

e. Materials other than lumber; moisture content must be in accordance with standard under which the product is produced

1.7 PRESERVATIVE TREATMENT

a. 0.25 pcf intended for above ground use.

b. 0.40 pcf intended for ground contact and fresh water use. 0.60 pcf intended for Ammoniacal Copper Quaternary Compound (ACQ)-treated foundations. 0.80 to 1.00 pcf intended for ACQ-treated pilings. All wood must be air or kiln dried after treatment. Specific treatments must be verified by the report of an approved independent inspection agency, or the AWPA Quality Mark on each piece. Do not incise surfaces of lumber that will be exposed. Brush coat areas that are cut or drilled after treatment with either the same preservative used in the treatment or with a 2 percent copper naphthenate solution. Plastic lumber must not be preservative treated. The following items must be

preservative treated:

(1) Wood framing, woodwork, and plywood up to and including the subflooring at the first-floor level of structures having crawl spaces when the bottoms of such items are 24 inches or less from the earth underneath.

(2) Wood members that are in contact with water.

(3) Exterior wood steps, platforms, and railings; and all wood framing of open, roofed structures.

(4) Wood sills, soles, plates, furring, and sleepers that are less than 24 inches from the ground, furring and nailers that are set into or in contact with concrete or masonry.

(5) Nailers, edge strips, crickets, curbs, and cants for roof decks.

1.8 FIRE-RETARDANT TREATMENT

Fire-retardant treated wood must be pressure treated Treatment and performance inspection must be by an independent and qualified testing agency that establishes performance ratings. Each piece or bundle of treated material must bear identification of the testing agency to indicate performance in accordance with such rating. Treated materials to be exposed to rain wetting must be subjected to an accelerated weathering technique in accordance with ASTM D2898 prior to being tested. Such items which will not be inside a building, and such items which will be exposed to heat or high humidity, must receive exterior fire-retardant treatment. Fire-retardant-treated wood products must be free of halogens, sulfates, ammonium phosphate, and formaldehyde. Items to be treated include the following:

1.9 QUALITY ASSURANCE

1.9.1 Data Required

Submit calculations and drawings for all proposed modifications of structural members. Do not proceed with modifications until the submittal has been approved.

1.9.2 Plastic Lumber Performance

Plastic lumber intended for use in exterior applications must have no fading or discoloration and no change in dimensional stability as tested in accordance with ASTM D1435 for a period of 5 years.

1.10 CERTIFICATIONS

1.10.1 Certified Wood Grades

Provide certificates of grade from the grading agency on graded but unmarked lumber or plywood attesting that materials meet the grade requirements specified herein.

1.10.2 Certified Sustainably Harvested Wood

Provide wood certified as sustainably harvested by FSC STD 01 001, ATFS STANDARDS, CSA Z809-08, SFI 2015-2019, or other third party program

certified by PEFC ST 2002:2013. Provide a letter of Certification of Sustainably Harvested Wood signed by the wood supplier. Identify certifying organization and their third party program name and indicate compliance with chain-of-custody program requirements. Submit sustainable wood certification data; identify each certified product on a line item basis. Submit copies of invoices bearing certification numbers.

PART 2 PRODUCTS

2.1 MATERIALS

2.1.1 Virgin Lumber

Lumber fabricated from old growth timber is not permitted. Avoid companies who buy, sell, or use old growth timber in their operations, when possible. Provide certified sustainably harvested virgin lumber.

2.1.2 Natural Decay- and Insect-Resistant Wood

Naturally durable wood must be certified sustainably harvested natural-decay and insect-resistant wood. An occasional piece with corner sapwood is permitted if 90 percent or more of the width of each side on which the sapwood occurs is heartwood. The primary species to use on this project is , douglas fir.

2.1.3 Plastic Lumber

HDPE lumber must contain a minimum of 90 percent total recycled content. Mixed plastics and cellulose lumber must contain a minimum of 100 percent total recovered materials content, with a minimum of 50 percent post-consumer recycled content. HDPE/fiberglass lumber must contain a minimum of 95 percent total recovered materials content with a minimum of 75 percent post-consumer recycled content. Other mixed resin lumber must contain a minimum of 95 percent total recovered materials content with a minimum of 50 percent post-consumer recycled content. Provide data identifying percentage of recycled content for plastic lumber.

2.1.3.1 Shear Parallel to Length

Maximum 1,000 psi in accordance with ASTM D2344/D2344M.

2.1.3.2 Density

ASTM D6111.

2.1.3.3 Compressive Strength

a. Secant Modulus: Minimum 70,000 psi in accordance with ASTM D6108.

b. Stress at 3 percent strain: Minimum 1,500 psi in accordance with ASTM D6108.

c. Compression Parallel to Grain: Minimum 3,000 psi in accordance with ASTM D6112.

d. Compression Perpendicular to Grain: Minimum 1,000 psi in accordance with ASTM D6112.

2.1.3.4 Flexural Strength

Minimum 2,000 psi in accordance with ASTM D6109.

2.1.3.5 Tensile Strength

Minimum 1,250 psi in accordance with ASTM D198.

2.1.3.6 Coefficient of Thermal Expansion

Maximum 0.000080 in/in/degree F in accordance with ASTM D696.

2.1.3.7 Screw Withdrawal

350 lbs in accordance with ASTM D6117.

2.1.3.8 Nail Withdrawal

150 lbs in accordance with ASTM D6117.

2.2 LUMBER

2.2.1 Structural Lumber

Except where a specific grade is indicated or specified, Any of the species and grades listed in AWC NDS that have allowable unit stresses in pounds per square inch (psi) not less than 1200 Fb, 780 Ft, 1200 Fc, with 1,200,000E E. Use for joists, rafters, headers, trusses, beams (except collar beams), columns, posts, stair stringers, girders, and all other members indicated to be stress rated. Structural lumber exposed to view in porch must be appearance grade of douglas fir species meeting the allowable unit stresses indicated. Design of members and fastenings must conform to AITC TCM. Other stress graded or dimensioned items such as blocking, carriages, and studs must be standard or No. 2 grade except that studs may be Stud grade.

2.2.2 Framing Lumber

Framing lumber such as studs, plates, caps, collar beams, cant strips, bucks, sleepers, nailing strips, and nailers and board lumber such as subflooring and wall and roof sheathing must be one of the species listed in the table below. Minimum grade of species must be as listed. Finger-jointed lumber may be used in the same applications as solid lumber of an equivalent species and grade, provided the finger-jointed lumber meets all the requirements of the certification and the quality control programs of the rules writing agency having jurisdiction and all applicable requirements of DOC/NIST PS56.

Table of Grades for Framing and Board Lumber			
Grading Rules	Species	Framing	Board Lumber
WWPA G-5 standard grading rules	Aspen, Douglas Fir-Larch, Douglas Fir South, Engelmann Spruce-Lodgepole Pine, Engelmann Spruce, Hem-Fir, Idaho White Pine, Lodgepole Pine, Mountain Hemlock, Mountain Hemlock-Hem-Fir, Ponderosa Pine-Sugar Pine, Ponderosa Pine-Lodgepole Pine, Subalpine Fir, White Woods, Western Woods, Western Cedars, Western Hemlock	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	All Species: No. 3 Common
WCLIB 17 standard grading rules	Douglas Fir-Larch, Hem-Fir, Mountain Hemlock, Sitka Spruce, Western Cedars, Western Hemlock	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	All Species: Standard

Table of Grades for Framing and Board Lumber			
Grading Rules	Species	Framing	Board Lumber
SPIB 1003 standard grading rules	Southern Pine	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	No. 2 Boards
SCMA Spec standard specifications	Cypress	No. 2 Common	No. 2 Common
NELMA Grading Rules standard grading rules	Balsam Fir, Eastern Hemlock-Tamarack, Eastern Spruce, Eastern White Pine, Northern Pine, Northern Pine-Cedar	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	All Species: No. 3 Common except Standard for Eastern White and Northern Pine
RIS Grade Use standard specifications	Redwood	All Species: Standard Light Framing or No. 3 Structural Light Framing (Stud Grade for 2x4 nominal size, 10 feet and shorter)	Construction Heart

Paint and Repair Requirements

Table of Grades for Framing and Board Lumber			
Grading Rules	Species	Framing	Board Lumber
NHLA Rules rules for the measurement and inspection of hardwood and cypress lumber	Cypress	No. 2 Dimension	No. 2 Common

2.3 PLYWOOD, STRUCTURAL-USE, AND ORIENTED STRAND BOARD (OSB) PANELS

APA L870, APA S350, APA E445, and APA F405 respectively.

2.3.1 Other Uses

2.3.1.1 Plywood

Plywood for areas needed. C-D Grade, Exposure 1.

2.3.1.2 Structural-Use and OSB Panels

Structural-use and OSB panels for areas as needed. Sheathing grade with durability equivalent to Exposure 1 and a minimum thickness of as required inch.

2.4 [Enter Appropriate Subpart Title Here]

2.4.1 Other Materials

2.4.1.1 Wood Members

2.4.2 [Enter Appropriate Subpart Title Here]2.4.2.1 Nonstress Graded Members

Members must include bridging, corner bracing, furring, grounds, and nailing strips. Members must be in accordance with TABLE I for the species used. Sizes must be as follows unless otherwise shown:

Member	Size inch
Bridging	1 x 3 or 1 x 4 for use between members 2 x 12 and smaller; 2 x 4 for use between members larger than 2 x 12.
Corner bracing	1 x 4.

Paint and Repair Requirements

Member	Size inch
Furring	1 x 2 3

2.4.2.2 Wood Bumpers

AREMA Eng Man, Industrial grade cross ties

2.4.2.3 Sill Plates

Sill plates must be standard or number 2 grade.

2.4.2.4 Blocking

Blocking must be standard or number 2 grade.

2.4.2.5 Rough Bucks and Frames

Rough bucks and frames must be straight standard or number 2 grade.

2.4.3 Adhesives

Comply with applicable regulations regarding toxic and hazardous materials and as specified.

2.5 ROUGH HARDWARE

Unless otherwise indicated or specified, rough hardware must be of the type and size necessary for the project requirements. Sizes, types, and spacing of fastenings of manufactured building materials UST be as recommended by the product manufacturer unless otherwise indicated or specified. Rough hardware exposed to the weather or embedded in or in contact with preservative treated wood, exterior masonry, or concrete walls or slabs must be hot-dip zinc-coated in accordance with ASTM A153/A153M. Nails and fastenings for fire-retardant treated lumber and woodwork exposed to the weather must be copper alloy or hot-dipped galvanized fasteners as recommended by the treated wood manufacturer.

2.5.1 Bolts, Nuts, Studs, and Rivets

ASME B18.2.1, ASME B18.5.2.1M, ASME B18.5.2.2M and ASME B18.2.2.

2.5.2 Anchor Bolts

ASTM A307, size as indicated, complete with nuts and washers.

2.5.3 Expansion Shields

CID A-A-1923, CID A-A-1924, and CID A-A-1925. Except as shown otherwise, maximum size of devices must be 3/8 inch.

2.5.4 Lag Screws and Lag Bolts

ASME B18.2.1.

2.5.5 Wood Screws

ASME B18.6.1.

2.5.6 Nails

ASTM F547, size and type best suited for purpose. For sheathing and subflooring, length of nails must be sufficient to extend 1 inch into supports. In general, 8-penny or larger nails must be used for nailing through 1 inch thick lumber and for toe nailing 2 inch thick lumber; 16-penny or larger nails must be used for nailing through 2 inch thick lumber. Nails used with treated lumber and sheathing must be hot-dipped galvanized in accordance with ASTM A153/A153M. Nailing must be in accordance with the recommended nailing schedule contained in AWC WFCM. Where detailed nailing requirements are not specified, nail size and spacing must be sufficient to develop an adequate strength for the connection. The connection's strength must be verified against the nail capacity tables in AWC NDS. Reasonable judgment backed by experience must ensure that the designed connection will not cause the wood to split. If a load situation exceeds a reasonable limit for nails, a specialized connector must be used.

2.5.7 Wire Nails

ASTM F1667.

2.5.8 Timber Connectors

Unless otherwise specified, timber connectors must be in accordance with TPI 1, APA EWS T300 or AITC TCM.

2.5.9 Clip Angles

Steel, 3/16 inch thick, size best suited for intended use; or zinc-coated steel or iron commercial clips designed for connecting wood members.

2.5.10 Joist Hangers

Steel or iron, zinc coated, sized to fit the supported member, of sufficient strength to develop the full strength of the supported member in accordance with ICC IBC, and furnished complete with any special nails required.

2.5.11 Tie Straps

For joists supported by the lower flange of steel beams, provide 1/8 by 1-1/2 inch steel strap, 2 feet long .

2.5.12 Joist Anchors

For joists supported by masonry walls, provide anchors 3/16 by 1 1/2 inch steel tee or strap, bent and of length to provide 4 inches embedment into wall and 12 inches along joist . For joists parallel to masonry or concrete walls, provide anchors 1/4 by 1-1/4 inch minimum cross-sectional area, steel strap, length as necessary to extend over top of first three

joists and into wall 8 inches, and with wall end of bend or pin type .

2.5.13 Door Buck Anchors

Metal anchors, 1/8 by 1-1/4 inch steel, 12 inches long, with ends bent 2 inches . Anchors must be screwed to the backs of bucks and built into masonry or concrete. Locate 8 inches above sills and below heads and not more than 24 inches intermediately between. Anchorage of bucks to steel framing must be as necessary to suit the conditions.

2.5.14 Metal Bridging

No. 16 U.S. Standard gage, cadmium-plated or zinc-coated.

2.5.15 Toothed Rings and Shear Plates

AWC NDS.

2.5.16 Beam Anchors

Steel U-shaped strap anchors 1/4 inch thick by 1-1/2 inches wide .

2.5.17 Metal Framing Anchors

Construct anchors to the configuration shown using hot dip zinc-coated steel conforming to ASTM A653/A653M, G90. Steel must be not lighter than 18 gage. Special nails supplied by the manufacturer must be used for all nailing.

2.5.18 Panel Edge Clips

Extruded aluminum or galvanized steel, H-shaped clips to prevent differential deflection of roof sheathing.

PART 3 EXECUTION

3.1 INSTALLATION

Do not install building construction materials that show visual evidence of biological growth.

Conform to AWC WFCM unless otherwise indicated or specified. Select lumber sizes to minimize waste. Fit framing lumber and other rough carpentry, set accurately to the required lines and levels, and secure in place in a rigid manner. Do not splice framing members between bearing points. Set joists, rafters, and purlins with their crown edge up. Frame members for the passage of pipes, conduits, and ducts. Do not cut or bore structural members for the passage of ducts or pipes without approval. Reinforce all members damaged by such cutting or boring by means of specially formed and approved sheet metal or bar steel shapes, or remove and provide new, as approved. Provide as necessary for the proper completion of the work all framing members not indicated or specified. Spiking and nailing not indicated or specified otherwise must be in accordance with the Nailing Schedule contained in ICC IBC; perform bolting in an approved manner. Spikes, nails, and bolts must be drawn up tight. Timber connections and fastenings must conform to AWC NDS. Provide 2 inch minimum clearance between chimneys and wood framing; provide 4 inch minimum clearance at fireplaces. Fill the spaces with strips of approved noncombustible material. Use slate or steel shims when leveling joists, beams, and

girders on masonry or concrete. Do not use shimming on wood or metal bearings. When joists, beams, and girders are placed on masonry or concrete, a wood base plate must be positioned and leveled with grout. The joist, beam, or girder must then be placed on the plate. When joists, beams, and girders are set into masonry or concrete, a pocket must be formed into the wall. The joist, beam, or girder must then be placed into the pocket and leveled with a steel shim.

3.1.1 Sills

Set sills level and square and wedge with steel or slate shims; point or grout with non-shrinking cement mortar to provide continuous and solid bearing. Anchor sills to the foundations as indicated. Where sizes and spacing of anchor bolts are not indicated, provide not less than 5/8 inch diameter bolts at all corners and splices and space at a maximum of 6 feet o.c. between corner bolts. Provide at least two bolts for each sill member. Lap and splice sills at corners and bolt through the laps or butt the ends and through-bolt not more than 6 inches from the ends. Provide bolts with plate washers and nuts. Bolts in exterior walls must be zinc-coated.

3.1.1.1 Anchors in Masonry

Embed anchor bolts not less than 15 inches in masonry unit walls and provide each with a nut and a 2 inch diameter washer at bottom end. Fully grout bolts with mortar.

3.1.1.2 Anchors in Concrete

Embed anchor bolts not less than 8 inches in poured concrete walls and provide each with a nut and a 2 inch diameter washer at bottom end. A bent end may be substituted for the nut and washer; bend must be not less than 90 degrees. Powder-actuated fasteners spaced 3 feet o.c. may be provided in lieu of bolts for single thickness plates on concrete.

3.1.2 Beams and Girders

Set beams and girders level and in alignment and anchor to bearing walls, piers, or supports with U-shaped steel strap anchors. Embed anchors in concrete or masonry at each bearing and through-bolt to the beams or girders with not less than two bolts. Provide bolts not less than 1/2 inch in diameter and with plate washers under heads and nuts. Install beams and girders with 8 inch minimum end bearing on walls or supports. Install beams and girders into walls with 1/2 inch clearance at the top, end, and sides or standard steel wall-bearing boxes. Provide joints and splices over bearings only and bolt or spike together.

3.1.3 Roof Framing or Rafters

Tops of supports or rafters must form a true plane. Valley, ridge, and hip members must be of depth equal to cut on rafters where practicable, but in no case less than depth of rafters and nominally 2 inches thick. Rafters must be notched and have full and solid bearing on plates. Valleys, hips, and ridges must be straight and true intersections of roof planes. Necessary crickets and watersheds must be formed. Rafters, except hip and valley rafters, must be spiked to wall plate and to ceiling joists with no less than three 8-penny nails bolted by angles. Rafters must be toe-nailed to ridge, valley, or hip members with at least three 8-penny nails. Rafters must be braced to prevent movement until permanent bracing, decking

or sheathing is installed. Hip and valley rafters must be secured to wall plates by clip angles. Openings in roof must be framed with headers and trimmers. Unless otherwise indicated, headers carrying more than two rafters and trimmers supporting headers carrying more than one rafter must be double. Hip rafters longer than the available lumber must be butt jointed and scabbed. Valley rafters longer than the available lumber must be double, with pieces lapped not less than 4 feet and well spiked together. Install trussed rafters in accordance with TPI HIB. Install engineered wood joists in accordance with distributor's instructions.

3.1.4 Joists

Provide joists of the sizes and spacing indicated, accurately and in alignment, and of uniform width. Joists must have full bearing on sills, plates, beams, girders, and trusses; provide laps over bearing only and spike. Where joists are of insufficient length to produce a 12 inch lap, butt joists over bearing and provide wood scabs 2 nominal inches thick by depth of joists by 24 inches long or metal straps 1/4 by 1 1/2 inch by not less than 18 inches long nailed to each joist with not less than four 10-penny nails, or approved sheet metal connectors installed in accordance with the manufacturer's recommendations. Provide joists built into masonry with a beveled fire cut so that the top of the joist does not enter the wall more than one inch or standard steel wall bearing boxes. Provide metal hangers for joists framing into the side of headers, beams, or girders. When a portion of the joist extends above the top flange of a steel beam or girder, provide a 3/8 inch space between the top flange and the extended portion of the joists to allow for shrinkage of joists. The minimum joist end bearing must be 4 inches, and joists built into concrete or masonry must have a 1/2 inch minimum clearance at the top, end, and sides. For joists approved to be bored for the passage of pipes or conduits, bore through the neutral axis of the joist. Provide steel joist hangers of proper size and type to receive the ends of all framed joists.

3.1.4.1 Floor (Ceiling) Framing

Except where otherwise indicated joists must have bearings not less than 4 inches on concrete or masonry and 1-1/2 inches on wood or metal. Joists, trimmers, headers, and beams framing into carrying members at the same relative levels must be carried on joist hangers. Joists must be lapped and spiked together at bearings or butted end-to-end with scab ties at joint and spiked to plates. Openings in floors must be framed with headers and trimmers. Headers carrying more than two tail joists and trimmers supporting headers carrying more than one tail joist must be doubled, unless otherwise indicated. Joists built into masonry must be provided with a beveled fire cut so that the top of the joist does not enter the wall more than 1 inch or standard steel wall bearing boxes. Install engineered wood joists in accordance with distributor's instructions.

3.1.4.2 Doubled Joists

Provide under bearing walls and partitions running parallel with the floor joists, around stairways, chimneys, fireplaces, and at other openings where joists are cut and framed. Double, space for clearance, block apart 4 feet on center, rigidly frame, and spike together joists under partitions that are to receive ducts, pipes, and conduits.

3.1.4.3 Tie Straps

For joists supported by the lower flange of steel beams, provide straps at

every fourth joist and the corresponding fourth joist on the opposite side. Tie joists across the top of the steel beam with a steel strap. Form straps to lie flat across the top of the beam and twist at the ends to provide flat contact with the side of each joist. Nail each strap at each end with three 10-penny nails spaced 2 inches o.c.

3.1.4.4 Joist Anchors

Provide anchors for each fourth joist supported by a masonry wall. Build wall end of anchors into the wall. Nail anchor to the joist with three 10-penny nails spaced 2 inches o.c. Anchor the first three joists parallel to concrete or masonry walls at bridging points, but not less than 8 feet o.c. from end walls. Let anchors into the tops of each joist and spike to the top of joist with one 10-penny nail. Extend anchors at least 8 inches into the wall.

3.1.5 Bridging

Provide bridging for floor and ceiling joists and for roof rafters having slopes of less than 1/3. Locate bridging as indicated and as specified herein. Provide bridging for spans greater than 6 feet, but do not exceed 8 feet maximum spacing between rows of bridging. Install rows of bridging uniformly. Provide metal or wood cross-bridging, except where solid bridging is indicated. Do not nail the bottom end of cross-bridging until the subfloor has been laid.

3.1.5.1 Wood Cross-Bridging

Provide wood cross-bridging not less than 1 by 3 2 by 3 2 by 4 nominal size. Nail wood cross-bridging at each end with two 8-penny nails for one by thick material and three 8-penny nails for 2 by thick material.

3.1.5.2 Metal Cross-Bridging

Must be the manufacturer's standard product, not less than 16 gage before forming and coating. Metal bridging must be the compression type, lodged into or nailed to the wide faces of opposite joists at points diagonally across from each other near the bottoms and tops of joists.

3.1.6 Columns and Posts

Set columns and posts, plumb, in alignment, and with full and uniform bearing. Do not embed the bottom and bearing surfaces of posts columns in concrete or set in direct contact with concrete slabs on grade. Provide post and beam construction with wood bolsters steel post caps in such a manner that the post above will tier directly over the one below; fabricate the assembly in a rigid and substantial manner using bolts or lag screws.

3.1.7 Wall Framing

3.1.7.1 Studs

Select studs for straightness and set plumb, true, and in alignment. In walls and partitions more than 8 feet tall, provide horizontal bridging at not more than 8 feet o.c. using nominal 2 inch material of the same width as the studs; install the bridging flat. Sizes and spacing of studs must be as needed. Double studs at jambs and heads of openings and triple at corners to form corner posts. Frame corner posts to receive sheathing, lath, and interior finish. Truss over openings exceeding 4 feet in width

or use a header of sufficient depth. Toe-nail studs to sills or sole plates with four 8-penny nails or fasten with metal nailing clips or connectors. Anchor studs abutting concrete or masonry walls thereto near the top and bottom and at midheight of each story using expansion bolts or powder-actuated drive studs.

3.1.7.2 Plates

Use plates for walls and partitions of the same width as the studs to form continuous horizontal ties. Splice single plates; stagger the ends of double plates. Double top plates in walls and bearing partitions, built up of two nominal 2 inch thick members. Top plates for nonbearing partitions must be single or double plates of the same size as the studs. Nail lower members of double top plates and single top plates to each stud and corner post with two 16-penny nails. Nail the upper members of double plates to the lower members with 10-penny nails, two near each end, and stagger 16 inches o.c. intermediately between. Nail sole plates on wood construction through the subfloor to each joist and header; stagger nails. Anchor sole plates on concrete with expansion bolts, one near each end and at not more than 6 feet o.c., or with powder-actuated fasteners, one near each end and at not more than 3 feet o.c. Provide plates cut for the passage of pipes or ducts with a steel angle as a tie for the plate and bearing for joist.

3.1.7.3 Firestops

Provide firestops for wood framed walls and partitions and for furred spaces of concrete or masonry walls at each floor level and at the ceiling line in the top story. Where firestops are not automatically provided by the framing system used, they must be formed of closely fitted wood blocks of nominal 2 inch thick material of the same width as the studs and joists.

3.1.7.4 Diagonal Bracing

Provide diagonal bracing at all external corners and internal angles and at maximum 40 foot centers in stud walls, except that bracing may be omitted where diagonally applied wood sheathing, plywood or structural-use panel sheathing, 4 by 8 foot fiberboard sheathing, or gypsum board sheathing is used. Bracing must be of 1 by 6 material, let into the exterior face of studs. Extend bracing from top plates to sill at an angle of approximately 45 degrees and double nail at each stud. When openings occur near corners, provide diagonal knee braces extending from the corner post above headers to top plates and from below window sills to the main sill. Nail bracing at each bearing with two 8-penny nails.

3.1.8 Ceiling Joists

Size as indicated and set accurately and in alignment. Toe-nail joists to all plates with not less than three 10-penny nails. Frame openings in ceilings with headers and trimmers.

3.1.9 Metal Framing Anchors

Provide framing anchors at every rafter to fasten rafter to plates and studs against uplift movement and forces as indicated. Anchors must be punched and formed for nailing so that nails will be stressed in shear only. Nails must be zinc-coated; drive a nail in each nail hole provided in the anchor.

3.1.10 Stair Framing

Cut carriages to exact shape required to receive treads and risers, with risers of uniform height and treads of uniform width. Provide trimmers, nailers, and blocking as required to support finish materials.

3.2 MISCELLANEOUS

3.2.1 Wood Roof Nailers, Edge Strips, Crickets, Curbs, and Cants

Provide sizes and configurations indicated or specified and anchored securely to continuous construction.

3.2.1.1 Roof Nailing Strips

Provide roof nailing strips for roof decks as specified herein. Apply nailing strips in straight parallel rows in the direction and spacing specified in or needed. Strips must be surface applied.

a. Surface-Applied Nailers: Must be 3 inches wide and of thickness to finish flush with the top of the insulation. Anchor strips securely to the roof deck with powder actuated fastening devices or expansion shields and bolts, spaced not more than 24 inches o.c.

b. Embedded Nailers: Must be nominal 2 by 3 with 2 inch sides beveled. Set and anchor nailers to finish flush with the roof deck surface.

3.2.1.2 Roof Edge Strips and Nailers

Provide at perimeter of roof, around openings through roof, and where roofs abut walls, curbs, and other vertical surfaces. Except where indicated otherwise, nailers must be 6 inches wide and the same thickness as the insulation. Anchor nailers securely to underlying construction. Anchor perimeter nailers in accordance with FM 4435. Strips must be grooved for edge venting; install at walls, curbs, and other vertical surfaces with a 1/4 to 1/2 inch air space.

3.2.1.3 Crickets, Cants, and Curbs

Provide wood saddles or crickets, cant strips, curbs for scuttles and ventilators, and wood nailers bolted to tops of concrete or masonry curbs and at expansion joints, as indicated, specified, or necessary and of lumber.

3.2.2 Rough Wood Bucks

2 inch nominal thickness. Set wood bucks true and plumb. Anchor bucks to concrete or masonry with steel straps extending into the wall 8 inches minimum. Place anchors near the top and bottom of the buck and space uniformly at 2 foot maximum intervals.

3.2.3 Wood Blocking

Provide proper sizes and shapes at proper locations for the installation and attachment of wood and other finish materials, fixtures, equipment, and items indicated or specified.

3.2.4 Wood Furring

Provide where shown and as necessary for facing materials specified. Except

as shown otherwise, furring strips must be nominal one by 3, continuous, and spaced 16 inches o.c. Erect furring vertically or horizontally as necessary. Nail furring strips to masonry. Do not use wood plugs. Provide furring strips around openings, behind bases, and at angles and corners. Furring must be plumb, rigid, and level and must be shimmed as necessary to provide a true, even plane with surfaces suitable to receive the finish required. Form furring for cornices, offsets and breaks in walls or ceilings on 1 by 4 wood strips spaced 16 inches o.c.

3.2.5 Wood Bumpers

Dress to the sizes indicated, and bevel edges. Bore, countersink, and bolt bumpers in place.

3.2.6 Temporary Closures

Provide with hinged doors and padlocks and install during construction at exterior doorways and other ground level openings that are not otherwise closed. Cover windows and other unprotected openings with polyethylene or other approved material, stretched on wood frames. Provide dustproof barrier partitions to isolate areas as directed.

3.2.7 Wood Sleepers

Run wood sleepers in lengths as long as practicable and stagger end joints in adjacent rows.

3.2.8 Bridging

Wood bridging must have ends accurately bevel-cut to afford firm contact and must be nailed at each end with two nails. Indall metal bridging as recommended by the manufacturer. The lower ends of bridging must be driven up tight and secured after subflooring or roof sheathing has been laid and partition framing installed.

3.2.9 Corner Bracing

Indatall corner bracing when required by type of sheathing used or when siding, other than panel siding, is applied directly to studs. Corner bracing must be let into the exterior surfaces of the studs at an angle of approximately 45 degrees, must extend completely over wall plates, and must be secured at each bearing with two nails.

3.2.10 Sill Plates

Sill plates must be set level and square and anchor bolted at not more than 6 feet on centers and not more than 12 inches from end of each piece. A minimum of two anchors must be used for each piece.

3.3 INSTALLATION OF TIMBER CONNECTORS

Install timber connectors in conformance with requirements of AWC NDS.

3.4 ERECTION TOLERANCES

a. Framing members which will be covered by finishes such as wallboard, plaster, or ceramic tile set in a mortar setting bed, must be within the following limits:

(1) Layout of walls and partitions: 1/4 inch from intended position;

(2) Plates and runners: 1/4 inch in 8 feet from a straight line;

(3) Studs: 1/4 inch in 8 feet out of plumb, not cumulative; and

(4) Face of framing members: 1/4 inch in 8 feet from a true plane.

b. Framing members which will be covered by ceramic tile set in dry-set mortar, latex-portland cement mortar, or organic adhesive must be within the following limits:

(1) Layout of walls and partitions: 1/4 inch from intended position;

(2) Plates and runners: 1/8 inch in 8 feet from a straight line;

(3) Studs: 1/8 inch in 8 feet out of plumb, not cumulative; and

(4) Face of framing members: 1/8 in 8 feet from a true plane.

3.5 WASTE MANAGEMENT OF WOOD PRODUCTS

In accordance with the Waste Management Plan and as specified. Clearly separate damaged wood and other scrap lumber for acceptable alternative uses on site, including bracing, blocking, cripples, ties, and shims.

Separate composite wood from other wood types and recycle or reuse. Coordinate with manufacturer for take-back program and submit manufacturer's policy statement on program. Set aside scrap plastic lumber and return to manufacturer for recycling into new product. When such a service is not available, local recyclers must be sought after to reclaim the materials. Fold up metal banding, flatten, and recycle.

Separate treated, stained, painted, and contaminated wood and place in designated area for hazardous materials. Dispose of according to local regulations. Do not leave any wood, shavings, sawdust, or other wood waste buried in fill or on the ground, unless for planned future use. Prevent sawdust and wood shavings from entering the storm drainage system. Compost sawdust. Do not burn scrap lumber that has been pressure treated, or lumber that is less than one year old.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

SECTION 06 20 00

FINISH CARPENTRY

08/16

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 PRODUCT DATA
1.4 DELIVERY, STORAGE, AND HANDLING
1.5 QUALITY ASSURANCE
1.5.1 Certifications
1.5.1.1 Certified Wood Grades
1.5.1.2 Certified Sustainably Harvested Wood
1.5.2 Lumber
1.5.3 Plywood
1.5.4 Hardboard
1.5.5 Pressure Treated Lumber and Plywood
1.5.6 Non-Pressure Treated Woodwork and Millwork
1.5.7 Fire-Retardant Treated Lumber

PART 2 PRODUCTS

2.1 WOOD PRODUCTS
2.1.1 Sizes and Patterns of Wood Products
2.1.2 Species and Grades
2.1.3 Trim, Finish, and Frames
2.1.4 Utility Shelving
2.1.5 Softwood Plywood
2.1.6 Hardwood Plywood
2.1.7 Hardboard
2.1.8 Stairs
2.1.9 Shoe Mould
2.1.10 Wood Seats
2.1.11 Wood Bumpers
2.1.12 Catwalks
2.1.13 Siding
2.1.13.1 Horizontal Hardboard Siding
2.1.13.2 Horizontal Plywood Siding
2.1.13.3 Panel Plywood Siding
2.1.13.4 Horizontal Rated Siding
2.1.13.5 Panel Rated Siding
2.1.13.6 Wood Siding
2.1.13.6.1 PORCH DECKING
2.1.13.7 Engineered Wood Structural Panels
2.2 SOFFITS
2.2.1 Hardboard and Plywood
2.3 FASCIAS AND TRIM
2.3.1 Wood
2.4 MOISTURE CONTENT OF WOOD PRODUCTS

2.5 PRESERVATIVE TREATMENT OF WOOD PRODUCTS
2.5.1 Non-Pressure Treatment
2.5.2 Pressure Treatment
2.6 FIRE-RETARDANT TREATMENT
2.6.1 Wood Products
2.7 HARDWARE AND ACCESSORIES
2.7.1 Wood Screws
2.7.2 Bolts, Nuts, Lag Screws, and Studs
2.7.3 Nails
2.8 FABRICATION
2.8.1 Quality Standards (QS)
2.8.1.1 Grades
2.8.1.2 Adhesives

PART 3 EXECUTION

3.1 FINISH WORK
3.1.1 Exterior Finish Work
3.1.2 Finish Stair Work
3.2 SIDING
3.2.1 Installation of Siding
3.2.2 Horizontal Siding
3.2.3 Vertical Board Siding
3.2.4 Vertical Board and Batten Siding
3.2.5 Panel Siding
3.3 SOFFITS
3.3.1 Wood
3.4 FASCIAE AND EXTERIOR TRIM
3.4.1 TONGUE & GROOVE WOOD PORCH DECKING

-- End of Section Table of Contents --

SECTION 06 20 00

FINISH CARPENTRY
08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN FOREST FOUNDATION (AFF)

ATFS STANDARDS	(2015) American Tree Farm System Standards of Sustainability 2015-2020

AMERICAN HARDBOARD ASSOCIATION (AHA)

AHA A135.4	(1995; R 2004) Basic Hardboard
AHA A135.6	(1998; R 2006) Hardboard Siding

AMERICAN LUMBER STANDARDS COMMITTEE (ALSC)

ALSC PS 20	(2015) American Softwood Lumber Standard

AMERICAN WOOD PROTECTION ASSOCIATION (AWPA)

AWPA M4	(2015) Standard for the Care of Preservative-Treated Wood Products
AWPA U1	(2017) Use Category System: User Specification for Treated Wood

APA - THE ENGINEERED WOOD ASSOCIATION (APA)

APA E445	(2002) Performance Standards and Qualification Policy for Structural-Use Panels (APA PRP-108)
APA L870	(2010) Voluntary Product Standard, PS 1-09, Structural Plywood
APA S350	(2014) PS 2-10, Performance Standard for Wood-Based Structural-Use Panels

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2015) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)

ASME B18.6.1 (2016) Wood Screws (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM D2898 (2010; R 2017) Standard Practice for Accelerated Weathering of Fire-Retardant-Treated Wood for Fire Testing

ASTM F547 (2017) Standard Terminology of Nails for Use with Wood and Wood-Base Materials

CSA GROUP (CSA)

CSA Z809-08 (R2013) Sustainable Forest Management

FOREST STEWARDSHIP COUNCIL (FSC)

FSC STD 01 001 (2015) Principles and Criteria for Forest Stewardship

HARDWOOD PLYWOOD AND VENEER ASSOCIATION (HPVA)

HPVA HP-1 (2016) American National Standard for Hardwood and Decorative Plywood

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC (2018) International Building Code

NATIONAL HARDWOOD LUMBER ASSOCIATION (NHLA)

NHLA Rules (2015) Rules for the Measurement & Inspection of Hardwood & Cypress

NORTHEASTERN LUMBER MANUFACTURERS ASSOCIATION (NELMA)

NELMA Grading Rules (2013) Standard Grading Rules for Northeastern Lumber

PROGRAMME FOR ENDORSEMENT OF FOREST CERTIFICATION (PEFC)

PEFC ST 2002:2013 (2015) PEFC International Standard Chain of Custody of Forest Based Products Requirements

REDWOOD INSPECTION SERVICE (RIS) OF THE CALIFORNIA REDWOOD ASSOCIATION (CRA)

RIS Grade Use (1998) Redwood Lumber Grades and Uses

SOUTHERN PINE INSPECTION BUREAU (SPIB)

SPIB 1003 (2014) Standard Grading Rules for Southern Pine Lumber

SUSTAINABLE FOREST INITIATIVE (SFI)

SFI 2015-2019 (2015) Standards, Rules for Label Use,

Procedures and Guidance

WEST COAST LUMBER INSPECTION BUREAU (WCLIB)

WCLIB 17 (2015) Standard Grading Rules

WESTERN WOOD PRODUCTS ASSOCIATION (WWPA)

WWPA G-5 (2017) Western Lumber Grading Rules

WINDOW AND DOOR MANUFACTURERS ASSOCIATION (WDMA)

WDMA I.S.4 (2015A) Preservative Treatment for Millwork

WOOD MOULDING AND MILLWORK PRODUCERS ASSOCIATION (WMMPA)

WMMPA WM 6 (2007) Quality Industry Standards Booklet

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Wood Products; G

Engineered Wood Products; G

Treated Wood Products; G

Soffits; G

Fascias and Trim; G

SD-04 Samples

Samples; G

SD-07 Certificates

Certificates of Grade; G,

Certified Sustainably Harvested Wood for Trim and Frames; S

Certified Sustainably Harvested Softwood Plywood; S

Certified Sustainably Harvested Hardwood Plywood; S

Certified Sustainably Harvested Hardboard; S

Certified Sustainably Harvested Siding; S

Paint and Repair Requirements

1.3 PRODUCT DATA

Submit Manufacturers printed data including proposed species, grade, density grain, and finish as applicable; sufficient to demonstrate compliance with this specification for each type of wood product specified. For treated wood products also provide documentation of environmentally safe preservatives for each type of wood product specified.

Provide Manufacturers printed data for hardware and all wood accessories including but not limited to edge banding, adhesives, and sealers.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver wood products to the jobsite in an undamaged condition. Stack materials to ensure ventilation and drainage. Protect against dampness before and after delivery. Store materials under cover in a well ventilated enclosure and protect against extreme changes in temperature and humidity. Keep materials wrapped and separated from off-gassing materials (such as drying paints and adhesives). Do not use materials that have visible moisture or biological growth. Do not store products in building until wet trade materials are dry and humidity of the space is within wood manufacturer's tolerance limits for storage.

1.5 QUALITY ASSURANCE

1.5.1 Certifications

1.5.1.1 Certified Wood Grades

Provide certificates of grade from the grading agency on graded but unmarked lumber or plywood attesting that materials meet the grade requirements specified herein.

1.5.1.2 Certified Sustainably Harvested Wood

Provide wood certified as sustainably harvested by FSC STD 01 001, ATFS STANDARDS, CSA Z809-08, SFI 2015-2019, or other third party program certified by PEFC ST 2002:2013. Provide a letter of Certification of Sustainably Harvested Wood signed by the wood supplier. Identify certifying organization and their third party program name and indicate compliance with chain-of-custody program requirements. Submit sustainable wood certification data; identify each certified product on a line item basis. Submit copies of invoices bearing certification numbers.

1.5.2 Lumber

Identify each piece or each bundle of lumber, millwork, and trim by the grade mark of a recognized association or independent inspection agency certified by the Board of Review of the ALSC to grade the species.

1.5.3 Plywood

Provide each sheet of plywood with the mark of a recognized association or independent inspection agency that maintains continuing control over the quality of the plywood. Marks must identify plywood by species group or span rating, exposure durability classification, grade, and compliance with APA L870.

Paint and Repair Requirements

1.5.4 Hardboard

Provide materials marks or written documentation identifying the producer and the applicable standard.

1.5.5 Pressure Treated Lumber and Plywood

Inspect each treated piece in accordance with AWPA U1.

1.5.6 Non-Pressure Treated Woodwork and Millwork

Mark, stamp, or label to indicate compliance with WDMA I.S.4.

1.5.7 Fire-Retardant Treated Lumber

Each piece must bear an Underwriters Laboratories fire resistance label or comparable label of another nationally recognized independent fire retardant materials testing laboratory.

PART 2 PRODUCTS

2.1 WOOD PRODUCTS

2.1.1 Sizes and Patterns of Wood Products

Provide yard and board lumber sizes in accordance with ALSC PS 20. Provide shaped lumber and millwork in the patterns indicated and in standard patterns of the association covering the species. Size references, unless otherwise specified, are nominal sizes. Provide actual sizes within manufacturing tolerances allowed by the applicable standard.

2.1.2 Species and Grades

Provide in accordance with AWPA U1 Use Category System Tables unless otherwise specified herein.

2.1.3 Trim, Finish, and Frames

Provide species and grades listed in the table below for wood materials that must be painted. For materials that must be stained, have a natural, or a transparent finish, provide materials one grade higher than those listed in the table below. Provide trim, except window stools and aprons with hollow backs.

TABLE OF GRADES FOR WOOD TO RECEIVE PAINT FINISH		
Grading Rules	Species	Exterior and Interior Trim, Finish, and Frames
WWPA G-5 standard grading rules	Aspen, Douglas Fir-Larch, Douglas Fir South, Engelmann Spruce-Lodgepole Pine, Engelmann Spruce, Hem-Fir, Idaho White Pine, Lodgepole Pine, Mountain Hemlock, Mountain Hemlock-Hem-Fir, Ponderosa Pine-Sugar Pine, (Ponderosa Pine-Lodgepole Pine,) White Woods, (Western Woods,) Western Cedars, Western Hemlock	All Species: C & BTR. Select (Choice & BTR Idaho White Pine) or Superior Finish. Western Red Cedar may be graded C & BTR. Select or A & BTR in accordance with Special Western Red Cedar Rules.
WCLIB 17 standard grading rules	Douglas Fir-Larch, Hem-Fir, Mountain Hemlock, Sitka Spruce, Western Cedars, Western Hemlock	All Species: C & BTR VG, except A for Western Red Cedar
SPIB 1003 standard grading rules	Southern Pine	C & BTR
NHLA Rules	Cypress	C-Select
NELMA Grading Rules standard grading rules **	Balsam Fir, Eastern Hemlock-Tamarack, Eastern Spruce, Eastern White Pine, Northern Pine, Northern Pine, Northern White Cedar	All Species: C-Select except C & BTR for Eastern White Pine and Norway Pine
RIS Grade Use standard specifications	Redwood	Clear, Clear All Heart
NHLA Rules	Cypress	B Finish
	Red Gum, Soft Elm, Birch	Select or BTR (for interior use only)

Note: ** http://www.nelma.org/library/2013-standard-grading-rules-for-northeastern-lumber/

2.1.4 Utility Shelving

Provide utility shelving in a suitable species equal to or exceeding the requirements of No. 3 common white fir under WWPA G-5, 1 inch thick; or plywood, interior type, Grade A-B, 1/2 inch thick, any species group.

2.1.5 Softwood Plywood

Provide in accordance with APA L870. Provide certified sustainably harvested softwood plywood.

a. Plywood for Soffits: Exterior type, B-B medium density overlay.

2.1.6 Hardwood Plywood

HPVA HP-1, Type Technical (Exterior) I (Exterior), Premium (A) Grade, hardwood veneer core construction, lumber core construction, face veneers of , of thickness indicated. Provide certified sustainably harvested hardwood plywood.

2.1.7 Hardboard

AHA A135.4, standard tempered service type, 1/4 inch thick.

2.1.8 Stairs

Treads 1-1/4 inches thickness, clear red or white oak. Risers 1 inch nominal finish lumber.

2.1.9 Shoe Mould

Clear red or white oak, 1/2 by 5/8 inch unless otherwise indicated.

2.1.10 Wood Seats

Clear maple, oak, or other suitable hardwood, not less than 1-5/8 inches thick, with rounded edges. Provide stainless steel stanchions or brackets.

2.1.11 Wood Bumpers

Clear oak, maple, birch, dressed to size indicated and with outer edges beveled.

2.1.12 Catwalks

Boards, 1 by 6 inches nominal, species and grade equal to or exceeding 3 Common Hem-Fir under WWPA G-5.

2.1.13 Siding

Provide hardboard, plywood, or wood for horizontal siding. Provide hardboard or plywood for panel siding. Provide certified sustainably harvested siding.

2.1.13.1 Horizontal Hardboard Siding

AHA A135.6, factory primed face and longitudinal edges, factory sealed back, lap type, 4, 6, 8, 9, 10, and 12 inches wide, maximum practicable lengths, 3/8 or 7/16 inch thick, smooth embossed textured face.

2.1.13.2 Horizontal Plywood Siding

APA L870, exterior, medium density overlay lap type, 4, 6, 8, and 12 inches wide, maximum practicable lengths, 3/8 7/16 15/32 1/2 inch thick, smooth embossed rough sawn texture embossed face.

2.1.13.3 Panel Plywood Siding

APA L870, exterior, medium density overlay, 4 feet wide, maximum practicable lengths, span rating of 16 24 inches on center, smooth embossed rough sawn texture striated face, and grooved as selected from manufacturer's standard patterns.

2.1.13.4 Horizontal Rated Siding

Qualified under APA E445, exterior type medium density overlay, lap types, 44, 6, 8, 10, and 12 inches wide, maximum practicable lengths, 7/16 15/32 1/2 inch thick, smooth embossed rough sawn texture face.

2.1.13.5 Panel Rated Siding

Qualified under APA E445, exterior type, 4 feet wide, maximum practicable lengths, span rated at 16 inch span rated at 24 inch, smooth embossed striated face , and grooves as selected from manufacturer's standard patterns.

2.1.13.6 Wood Siding

Provide horizontal bevel type, minimum 3/16 inch thin edge by minimum 7/16 inch thick edge, horizontal plain lap type horizontal drop type vertical board, tongue and groove or shiplap on long edges, vertical board and batten type, 1 inch thick, 6 8 10 inches wide, maximum practicable lengths, smooth rough sawn texture.

2.1.13.6.1 PORCH DECKING

Provide tongue and groove, vertical grain Douglas Fir wood Grade A. for porch decking. Sizes vary in thickness 3/4", 5/4", 1" 1-3/8", 1-5/16".

2.1.13.7 Engineered Wood Structural Panels

Comply with ICC IBC, Chapter 23 Wood, and with APA S350, exterior, exposure 1 2, single-faced double-faced, 4 feet wide, maximum practicable lengths, selected from manufacturer's standard patterns to satisfy the wind load for the specified span.

2.2 SOFFITS

2.2.1 Hardboard and Plywood

Provide hardboard and plywood soffits in siding grade hardboard, 3/8 or 7/16 inch thick; plywood, APA L870, exterior type, Grade A-C plywood panel siding,11/32 inch thick for 24 inches on center 15/32 inch thick for 32 inches on center 19/32 inches thick for 48 inches on center maximum span with all edges supported.

2.3 FASCIAS AND TRIM

2.3.1 Wood

Provide species and grades for all fasciae and trim, including exterior door and window casings, in accordance with AWPA U1 Use Category System Tables. Provide sizes indicated. Metal corners may be provided in lieu of wood corner boards for horizontal siding. If metal corners are used, provide galvanized steel or aluminum, completely coated with primer compatible for the specific metal substrate.

2.4 MOISTURE CONTENT OF WOOD PRODUCTS

Air dry or kiln dry lumber. Kiln dry treated lumber after treatment. Maximum moisture content of wood products at time of delivery to the jobsite, and when installed, must be as follows:

c. Exterior Treated and Untreated Finish Lumber and Trim: 4 inches Nominal or Less in Thickness: 19 percent.

d. Exterior Wood Siding: 15 percent.

e. Provide moisture content of other materials in accordance with the applicable standards.

2.5 PRESERVATIVE TREATMENT OF WOOD PRODUCTS

2.5.1 Non-Pressure Treatment

Treat woodwork and millwork, such as exterior trim, door trim, and window trim, in accordance with WDMA I.S.4, with either 2 percent copper napthenate, 3 percent zinc napthenate, or 1.8 percent copper-8-quinolinolate. Provide a liberal brush coat of preservative treatment to field cuts and holes.

2.5.2 Pressure Treatment

Treat lumber and plywood used on the exterior of buildings or in contact with masonry or concrete with a waterborne preservative listed in AWPA U1 (P series is included therein by reference) as applicable, and inspected in accordance with AWPA U1. Identify treatment on each piece of material by the quality mark of an agency accredited by the Board of Review of the American Lumber Standards Committee. Provide treated plywood to a reflection level as follows:

Preservative treat exterior wood moulding and millwork that will be within 18 inches of soil or in contact with water or concrete in accordance with WMMPA WM 6. Provide a field treatment in accordance with AWPA M4 of exposed areas of treated wood that have been cut or drilled. Items of all-heart material of cedar, cypress, or redwood do not require preservative treatment except when in direct contact with soil.

2.6 FIRE-RETARDANT TREATMENT

2.6.1 Wood Products

Pressure treat fire-retardant treated lumber and plywood in accordance with AWPA U1. Comply with material use as defined in AWPA U1 for Interior Type A and B and Exterior Type. Treatment and performance inspection must be

conducted by a qualified independent testing agency that establishes performance ratings. Each piece or bundle of treated material must bear identification of the testing agency to indicate performance with such rating. Subject treated materials that will be exposed to rain wetting to an accelerated weathering technique in accordance with ASTM D2898, Method A, prior to being tested for compliance with AWPA U1.

2.7 HARDWARE AND ACCESSORIES

Provide sizes, types, and spacings of hardware and accessories as recommended in writing by the wood product manufacturer, except as otherwise specified.

2.7.1 Wood Screws

ASME B18.6.1.

2.7.2 Bolts, Nuts, Lag Screws, and Studs

ASME B18.2.1 and ASME B18.2.2.

2.7.3 Nails

Use nails of a size and type best suited for each application and in accordance with ASTM F547. Use hot-dipped galvanized or aluminum nails for exterior applications. For siding, provide nails of sufficient length to extend 1-1/2 inches into supports, including wood sheathing over framing. Where nailing is impractical, provide screws of a size and type best suited for each application.

2.8 FABRICATION

2.8.1 Quality Standards (QS)

2.8.1.1 Grades

The terms "Premium," "Custom," and "Economy" refer to the quality grades defined in AWI AWS. Provide items not otherwise specified in a specific grade as "Custom" grade.

2.8.1.2 Adhesives

Select adhesives for durability and permanent bonding. Address factors such as materials that must be bonded, expansion and contraction, bond strength, fire rating, moisture resistance, and manufacturer's recommendations.

PART 3 EXECUTION

Do not install building construction materials that show visual evidence of biological growth.

3.1 FINISH WORK

Apply primer to finish work before installing. Where practicable, shop assemble and finish millwork items. Construct joints tight and in a manner to conceal shrinkage but to avoid cupping, twisting and warping after installation. Miter trim and mouldings at exterior angles; cope at interior angles and at returns. Provide millwork and trim in maximum

practical lengths. Fasten finish work with finish nails. Provide blind nailing where practicable. Set face nails for putty stopping.

3.1.1 Exterior Finish Work

Machine sand exposed flat members and square edges. Machine finish semi-exposed surfaces. Construct joints to exclude water. In addition to nailing, glue joints with waterproof glue as necessary for weather resistant construction. Evenly distribute end joints in built-up members. Provide shoulder joints in flat work. Reinforce backs of wide-faced miters with metal rings and waterproof glue. Unless otherwise indicated, provide fasciae and other flat members 3/4 inch thick minimum. Provide door and window trim in single lengths. Provide braced, blocked, and rigidly anchored cornices for support and protection of vertical joints. Provide soffits in largest practical size. Align joints of plywood over centerlines of supports. Fasten soffits with aluminum or stainless steel nails. Back prime all concealed surfaces of exterior trim.

3.1.2 Finish Stair Work

Fit, nail, screw, bolt, and glue stair work together to form a strong, rigid structure without squeaks or vibrations. Anchor newels and posts securely to stair framing. Cut newels, posts, and drops accurately around floor construction to make a tight fit. Embed balusters into treads and landings and secure with glue. Provide railings with straight runs that follow the slope of the stairs and have smooth curved turns. Return railing profile at ends and secure joints with bolts and nuts in accordance with structural load requirements for railings. Secure railing to posts and newels with concealed anchors. Support wall rails on metal brackets spaced near ends and at not more than 5 feet on center.

3.2 SIDING

3.2.1 Installation of Siding

Fit and position siding without springing or otherwise forcing panels into place. For siding to have a stain finish, set nails and stop with nonstaining putty to match finished siding. For siding to have a paint finish, drive nails flush.

3.2.2 Horizontal Siding

Locate end joints over framing members and alternate such that there are a minimum of two boards between joints on the same support. Evenly distribute shorter pieces throughout the installation. Provide starter strips to establish proper cant for siding. Predrill ends of siding as necessary to prevent splitting when nailed. Horizontal bevel or plain lap siding: Overlap and nail into each support in accordance with recommendations of siding manufacturer. Horizontal drop siding: Work each course into top edge of previous course. Nail into each support with two nails, one near lower edge to clear top of previous course, and one just above mid-height of course.

3.2.3 Vertical Board Siding

Apply siding with horizontal joints only at locations indicated. Work each board into edge of previous course. Nail into supports at 24 inches on center with two nails, one blind if possible at or near joint with previous board, and one just outside board centerline.

3.2.4 Vertical Board and Batten Siding

Apply with horizontal joints only at locations indicated. Install each board with 1/2 inch of space between boards. Nail at center of board and into supports at 24 inches on center. Center battens over space between boards and nail down center at 16 inches on center.

3.2.5 Panel Siding

Apply panels with edges at joints spaced in accordance with manufacturer's recommendations. Provide shiplapped edges or square edges that will be covered by battens in a primed for paint finish,. Back all edges with framing members. Nail panels at edges 6 inches on center and at intermediate supports 12 inches on center. Locate edge nailing 3/8 inch from edges. For shiplap joints, nail 3/8 inch from visible joint and at a location to penetrate lap with previous panel. When panel siding is part of an engineered shear wall or used as wall bracing, nail shiplap joints to supports with double rows of nails. Space battens at 12 16 inches on center and nail down center at 24 inches on center.

3.3 SOFFITS

3.3.1 Wood

Provide panels with edges at joints spaced in accordance with manufacturer's written instructions and with all edges backed by framing members. Nail panels 3/8 inch from edges at 6 inches on center and at intermediate supports at 12 inches on center. Provide panels in maximum practicable lengths.

3.4 FASCIAE AND EXTERIOR TRIM

Construct, caulk, and machine sand exposed surfaces and edges to exclude water. In addition to nailing, glue joints as necessary for weather resistance. Evenly distribute end joints in built-up members. Shoulder joints in flat work. Reinforce backs of wide-faced miters with metal rings and glue. Provide fasciae and other flat members in maximum practicable lengths. Braced, block, and rigidly anchor cornices for support and protection of vertical joints.

3.4.1 TONGUE & GROOVE WOOD PORCH DECKING

The Contractor shall install all exterior T&G wood floor porch decking with a Pneumatic flooring nailer, to install, at a minimum, a 2" steel "L" head-shape floor nail or cleat. The "L" head cleated nails shall minimize wood splitting and for expansion and contration of the wood materials the pneumatic nailer shall be work contact safety, which is activated when the tool is positioned on the flooring tongue - not by depressing a trigger, which helps to eliminate scratching and damage to the wood surface. This tool shall set the tongue and groove porch decking and drives the cleat nails at a 45 degree angle. Run a full bead of caulk along the the lenght of the tongue before installing another board.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

SECTION 06 82 14

FIBERGLASS REINFORCED PLASTIC (FRP) PIPE AND TUBE RAILINGS

05/18

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 QUALITY CONTROL
1.3.1 Qualifications of Manufacturer
1.3.2 Qualifications of Engineer of Record
1.4 DELIVERY, HANDLING, AND STORAGE

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION
2.1.1 Installation Drawings
2.1.2 Product Data
2.1.3 Design Requirements
2.1.4 Performance Requirements
2.1.4.1 Structural Performance of Pipe and Tube Railings
2.2 FABRICATION
2.3 MATERIALS
2.3.1 Fasteners
2.3.2 Anchors
2.3.3 Grout And Anchoring Cement
2.3.4 Component Connections
2.3.4.1 Lag Screws and Bolts
2.3.4.2 Toggle Bolts
2.3.4.3 Bolts, Nuts, Studs, and Rivets
2.3.4.4 Powder-Driven Fasteners
2.3.4.5 Screws
2.3.4.6 Washers

PART 3 EXECUTION

3.1 INSTALLATION
3.1.1 Anchorage, Fastenings, and Connections
3.1.2 Workmanship
3.2 CLOSEOUT ACTIVITIES
3.2.1 Warranty
3.2.2 Manufacturer's Instructions

-- End of Section Table of Contents --

SECTION 06 82 14

FIBERGLASS REINFORCED PLASTIC (FRP) PIPE AND TUBE RAILINGS
05/18

PART 1 GENERAL

This Section includes new fiberglass reinforced plastic (FRP) pipe and tube railing/guards, mounting systems and accessories.

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE 7	(2017) Minimum Design Loads for Buildings and Other Structures

AMERICAN SOCIETY OF SAFETY ENGINEERS (ASSE/SAFE)

ASSE/SAFE A10.3	(2013) Operations - Safety Requirements for Powder Actuated Fastening Systems

ASME INTERNATIONAL (ASME)

ASME B18.2.1	(2012; Errata 2013) Square and Hex Bolts and Screws (Inch Series)
ASME B18.2.2	(2015) Nuts for General Applications: Machine Screw Nuts, Hex, Square, Hex Flange, and Coupling Nuts (Inch Series)
ASME B18.21.1	(2009; R 2016) Washers: Helical Spring-Lock, Tooth Lock, and Plain Washers (Inch Series)
ASME B18.21.2M	(1999; R 2014) Lock Washers (Metric Series)
ASME B18.6.2	(1998; R 2010) Slotted Head Cap Screws, Square Head Set Screws, and Slotted Headless Set Screws: Inch Series
ASME B18.6.3	(2013; R 2017) Machine Screws, Tapping Screws, and Machine Drive Screws (Inch Series)

ASTM INTERNATIONAL (ASTM)

ASTM A307	(2014; E 2017) Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength
ASTM C1107/C1107M	(2017) Standard Specification for Packaged Dry, Hydraulic-Cement Grout (Nonshrink)

ASTM D1148	(2013) Standard Test Method for Rubber Deterioration—Discoloration from Ultraviolet (UV) and Heat Exposure of Light-Colored Surfaces
ASTM D2344/D2344M	(2016) Standard Test Method for Short-Beam Strength of Polymer Matrix Composite Materials and Their Laminates
ASTM D430	(2006; R 2012) Standard Test Methods for Rubber Deterioration - Dynamic Fatigue
ASTM D638	(2014) Standard Test Method for Tensile Properties of Plastics
ASTM D696	(2016) Standard Test Method for Coefficient of Linear Thermal Expansion of Plastics Between -30 degrees C and 30 degrees C With a Vitreous Silica Dilatometer
ASTM D790	(2017) Standard Test Methods for Flexural Properties of Unreinforced and Reinforced Plastics and Electrical Insulating Materials
ASTM E488/E488M	(2015) Standard Test Methods for Strength of Anchors in Concrete and Masonry Elements
ASTM E84	(2018) Standard Test Method for Surface Burning Characteristics of Building Materials

INTERNATIONAL CODE COUNCIL (ICC)

ICC IBC	(2018) International Building Code

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 101	(2018; TIA 18-1; TIA 18-2; TIA 18-3) Life Safety Code

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.23	(Nov 2016) Ladders
29 CFR 1926	Safety and Health Regulations for Construction

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval.for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL

PROCEDURES:

SD-01 Preconstruction Submittals

Qualifications of Manufacturer; G

Qualifications of Engineer of Record; G

SD-03 Product Data

FRP Pipe and Tube; G

Railings/Guards; G

Anchorage Materials; G

Adhesives; G

Resins; G

Hardeners; G

Manufacturer's Sample Warranty

SD-06 Test Reports

Ultraviolet Test Reports

Thermal Expansion Test Reports

Flame Spread Test Reports

SD-07 Certificates

Manufacturer's Certification by the State of Kansas Product Approval

Proof of Certification from a minimum of two quality assurance programs for its facilities or products (UL, DNV, ABS, USCG, AARR)

SD-08 Manufacturer's Instructions

Manufacturer's Instructions

SD-09 Manufacturer's Field Reports

Manufacturer's Certification of Installation

SD-11 Closeout Submittals

Manufacturer's Warranty

1.3 QUALITY CONTROL

1.3.1 Qualifications of Manufacturer

Submit Qualifications Of Manufacturer documentation certifying that the Fiberglass Reinforced Plastic (FRP) manufacturer has a minimum of 5 years of experience in manufacturing FRP products.

Provide items within this section from manufacturers having a minimum of 5 years of experience in the design and manufacture of similar products and systems.

Submit documentation proving a minimum of five separate, similar installations within the last 5 years.

Submit the Proof of Certification from a minimum of two quality assurance programs for its facilities or products (UL, DNV, ABS, USCG, AARR).

Provide the manufacturer's sample warranty for all FRP products against defects in material and workmanship for a minimum of 5 years. Provide evidence of manufacturer's ISO 9001:2000 standard certification.

1.3.2 Qualifications of Engineer of Record

a. The design in accordance with International Building Code and ASCE 7

b. Installation drawings

1.4 DELIVERY, HANDLING, AND STORAGE

Deliver all manufactured materials in original, unbroken pallets, packages, containers, or bundles bearing the label of the manufacturers, clearly marked and identified relative to the complete system. Provide all adhesives, resins and their catalysts and hardeners in clearly marked or noted crates or boxes. Store all manufactured materials in dry indoor facilities with a constant temperature range between 70 and 85 degrees F until they are required.

Handle all materials to prevent abrasion, cracking, chipping, twisting, or other deformations, and other types of damage.

PART 2 PRODUCTS

2.1 SYSTEM DESCRIPTION

2.1.1 Installation Drawings

Submit templates and erection and installation drawings indicating thickness, type, and dimensions. Show construction details, reinforcement, anchorage, and installation with relation to the building construction.

Include plans, elevations, sections, details, and attachments to other work. Indicate for installed products to comply with design loads. Include structural analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

2.1.2 Product Data

Submit the manufacturer's catalog data including two copies of manufacturer's specifications, load tables, dimension diagrams, and anchor details for the following items:

a. FRP Pipe and Tube

b. Railings/Guards

c. Anchorage Materials

d. Adhesives

e. Resins

f. Hardeners

2.1.3 Design Requirements

Ensure that all posts and rails are FRP structural shapes manufactured by the pultrusion process. Compose structural shapes of fiberglass reinforcement and resin in qualities, quantities, properties, arrangements, and dimensions as necessary to meet the design requirements in accordance with ASCE 7, 29 CFR 1910.23, NFPA 101, and dimensions specified.

Ensure that fiberglass reinforcements are a combination of continuous roving, continuous strand mat, and surfacing veil in sufficient quantities as needed by the application required, the physical properties required, or both.

Provide resins, with appropriate hardeners, of isophthalic polyester, with the chemical formulation necessary for corrosion resistance, strength, and other physical properties.

Ensure that all finished surfaces of FRP items, including FRP pipe and tube, railings/guards, anchorage materials, and fabrications, are smooth, resin-rich, and free of voids, dry spots, cracks, and unreinforced areas. Provide complete coverage of all glass fibers with resin to protect against their exposure to wear or weathering.

Protect all pultruded structural shapes from ultraviolet (UV) attack with:

a. Integral UV inhibitors within the resin

b. Synthetic surfacing veil to help produce a resin-rich surface

c. UV-resistant coating for outdoor exposures

Provide FRP products that have a flame spread rating of 25 or less as specified in ASTM E84, Tunnel Test. Submit 2 copies of Flame Spread Test Reports to the Contracting Officer.

Ensure that rails, posts, and kick plates are integrally pigmented yellow. Submit 2 copies of Ultraviolet Test Reports for FRP material, similar to the requirements of ASTM D1148 for rubber deterioration, and ASTM D430, to the Contracting Officer. Submit testing data relating to Thermal Expansion Test Reports.

Provide structural shapes in the guardrail system to meet minimum longitudinal mechanical properties as follows:

Tensile Strength	ASTM D638	30,000 psi
Tensile Modulus	ASTM D638	2,500,000 psi

Paint and Repair Requirements

Flexural Strength	ASTM D790	30,000 psi
Flexural Modulus	ASTM D790	1,800,000 psi
Flexural Modulus-Full Section		2,800,000 psi
Short Beam Shear	ASTM D2344/D2344M	4,500 psi
Shear Modulus-Transverse		450,000 psi
Coefficient of Thermal Expansion	ASTM D696	.000008 in/in/F
Flame Spread	ASTM E84	25 or less

2.1.4 Performance Requirements

2.1.4.1 Structural Performance of Pipe and Tube Railings

Provide a pipe and tube railing system capable of withstanding the effects of gravity loads in accordance with ASCE 7 and International Building Code, ICC IBC the State of Kansas Building Code, with the following loads and stresses within limits and under the conditions indicated:

a. Handrails:

(1) Uniform load of 50 lbf/foot applied in any direction.

(2) Concentrated load of 200 lbf applied in any direction.

(3) Uniform and concentrated loads need not be assumed to act concurrently.

b. Top Rails of Guards:

(1) Uniform load of 50 lbf/foot applied in any direction.

(2) Concentrated load of 200 lbf applied in any direction.

(3) Uniform and concentrated loads need not be assumed to act concurrently.

c. Infill of Guards:

(1) Concentrated load of 50 lbf applied horizontally on an area of 1 square foot.

(2) Uniform load of 25 lbf/square foot applied horizontally.

(3) Infill load and other loads need not be assumed to act concurrently.

2.2 FABRICATION

Perform fabrication of the handrail post/rail connection such that the rails are unbroken and continuous through the post without the use of packs

or splices. Install the bottom rail through the post at a prepared hole made to fit the outside dimensions of the rail, and the top rail fit into a machined, u-shaped pocket formed into the top of the post such that the rail is located at the center of the post. Radius all exposed corners to eliminate sharp edges. Join the rails to the post through a combination of bonding and riveting. Ensure that no sharp, protruding edges remain after assembly of the handrail. Space the posts no more than 72 inches apart. Attach post bases according to the construction contract drawings. Reinforce post bases to a height of 8 1/2 inches. Coat all field-fabricated and shop-fabricated cuts with a vinyl ester resin to provide maximum corrosion resistance.

2.3 MATERIALS

2.3.1 Fasteners

Provide Type 316 stainless-steel concealed fasteners, unless unavoidable or standard for railings indicated.

2.3.2 Anchors

Provide cast-in-place epoxy mechanical anchors, fabricated from corrosion-resistant materials with capability to sustain, without failure, a load equal to six times the design load imposed when installed in unit masonry and equal to four times the design load imposed when installed in concrete, as determined by testing as specified in ASTM E488/E488M.

2.3.3 Grout And Anchoring Cement

Provide factory-packaged, nonshrink, nonmetallic grout complying with ASTM C1107/C1107M; or water-resistant, nonshrink anchoring cement; recommended by the manufacturer for exterior use. Ensure that all other adhesives conform to the manufacturer's recommendations and instructions.

2.3.4 Component Connections

2.3.4.1 Lag Screws and Bolts

Provide lag screws and bolts conforming to ASME B18.2.1, of the type and grade best suited for the purpose.

2.3.4.2 Toggle Bolts

Provide toggle bolts conforming to ASME B18.2.1.

2.3.4.3 Bolts, Nuts, Studs, and Rivets

Provide bolts, nuts, studs, and rivets conforming to ASME B18.2.2 and ASTM A307.

2.3.4.4 Powder-Driven Fasteners

Follow safety provisions of ASSE/SAFE A10.3.

2.3.4.5 Screws

Provide screws conforming to ASME B18.2.1, ASME B18.6.2, and ASME B18.6.3.

Paint and Repair Requirements

2.3.4.6 Washers

Provide plain washers conforming to ASME B18.21.1. Provide beveled washers for American Standard beams and channels, square or rectangular, tapered in thickness, and smooth. Provide lock washers conforming to ASME B18.21.2M and ASME B18.21.1.

PART 3 EXECUTION

3.1 INSTALLATION

Install items in accordance with 29 CFR 1910.23 and 29 CFR 1926 at locations indicated, according to the manufacturer's instructions. Verify all measurements and take all field measurements necessary before fabrication. Include all materials and parts necessary to complete each item, even though such work is not definitely shown or specified. Perform cutting, drilling, and fitting required for installing railings. Set railings accurately in location, alignment, and elevation. Submit 2 signed copies of Manufacturer's Certification of Installation.

a. Set posts plumb within a tolerance of 1/16 inch in 3 feet.

b. Align rails so variations from level for horizontal members and variations from parallel with rake of steps and ramps for sloping members do not exceed 1/4 inch in 12 feet.

3.1.1 Anchorage, Fastenings, and Connections

Provide anchorage where necessary for fastening miscellaneous FRP items securely in place. Include for anchorage not otherwise specified or indicated slotted inserts, expansion shields, and powder-driven fasteners, when approved for concrete; toggle bolts and through-bolts for masonry; machine and carriage bolts for steel; through-bolts and screws. Conceal fastenings where practicable.

3.1.2 Workmanship

Ensure that FRP work is well formed to shape and size, with sharp lines and angles and true curves. Ensure that drilling and punching produces clean true lines and surfaces. Ensure that exposed surfaces of work-in-place to have smooth finishes. Mill joints where tight fits are required. Ensure that corner joints are coped or mitered, well formed, and in true alignment. Accurately set work to established lines and elevations and securely fasten in place. Ensure that the installation is in accordance with the manufacturer's installation instructions and the approved drawings, cuts, and details.

3.2 CLOSEOUT ACTIVITIES

3.2.1 Warranty

Submit 3 signed copies of the Manufacturer's Warranty 30 calendar days before final inspection.

3.2.2 Manufacturer's Instructions

Paint and Repair Requirements

Submit the manufacturer's instructions for shipping and handling, and procedures for erection, care, and maintenance upon completion of installation.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

SECTION 07 60 00

FLASHING AND SHEET METAL

05/17

PART 1 GENERAL

1.1 REFERENCES
1.2 GENERAL REQUIREMENTS
1.3 SUBMITTALS
1.4 MISCELLANEOUS REQUIREMENTS
1.4.1 Product Data
1.4.2 Finish Samples
1.4.3 Operation and Maintenance Data
1.5 DELIVERY, HANDLING, AND STORAGE

PART 2 PRODUCTS

2.1 MATERIALS
2.1.1 Exposed Sheet Metal Items
2.1.2 Drainage
2.1.3 Copper, Sheet and Strip
2.1.4 Lead-Coated Copper Sheet
2.1.5 Lead Sheet
2.1.6 Steel Sheet, Zinc-Coated (Galvanized)
2.1.7 Zinc Sheet and Strip
2.1.8 Stainless Steel
2.1.9 Terne-Coated Steel
2.1.10 Aluminum Alloy Sheet and Plate
2.1.10.1 Alclad
2.1.11 Finishes
2.1.12 Cool Roof Finishes
2.1.12.1 Energy Star Certification
2.1.13 Aluminum Alloy, Extruded Bars, Rods, Shapes, and Tubes
2.1.14 Solder
2.1.15 Reglets
2.1.15.1 Polyvinyl Chloride Reglets
2.1.15.2 Metal Reglets
2.1.15.2.1 Caulked Reglets
2.1.15.2.2 Friction Reglets
2.1.16 Scuppers
2.1.17 Conductor Heads
2.1.18 Copings
2.1.19 Bituminous Plastic Cement
2.1.20 Roofing Felt
2.1.21 Asphalt Primer
2.1.22 Fasteners

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Gutters
3.1.2 Downspouts
3.2 PAINTING
3.2.1 Aluminum Surfaces
3.3 CLEANING
3.4 REPAIRS TO FINISH
3.5 FIELD QUALITY CONTROL
3.5.1 Procedure

-- End of Section Table of Contents --

SECTION 07 60 00

FLASHING AND SHEET METAL
05/17

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM A308/A308M	(2010) Standard Specification for Steel Sheet, Terne (Lead-Tin Alloy) Coated by the Hot Dip Process
ASTM A480/A480M	(2017) Standard Specification for General Requirements for Flat-Rolled Stainless and Heat-Resisting Steel Plate, Sheet, and Strip
ASTM A653/A653M	(2017) Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process
ASTM B101	(2012) Standard Specification for Lead-Coated Copper Sheet and Strip for Building Construction
ASTM B209	(2014) Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
ASTM B221	(2014) Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes
ASTM B32	(2008; R 2014) Standard Specification for Solder Metal
ASTM B370	(2012) Standard Specification for Copper Sheet and Strip for Building Construction
ASTM B69	(2013) Standard Specification for Rolled Zinc
ASTM D1784	(2011) Standard Specification for Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds
ASTM D226/D226M	(2017) Standard Specification for Asphalt-Saturated Organic Felt Used in Roofing and Waterproofing

ASTM D41/D41M	(2011; R 2016) Standard Specification for Asphalt Primer Used in Roofing, Dampproofing, and Waterproofing
ASTM D4586/D4586M	(2007; E 2012; R 2012) Asphalt Roof Cement, Asbestos-Free
ASTM E408	(2013) Standard Test Methods for Total Normal Emittance of Surfaces Using Inspection-Meter Techniques

SHEET METAL AND AIR CONDITIONING CONTRACTORS' NATIONAL ASSOCIATION (SMACNA)

SMACNA 1793	(2012) Architectural Sheet Metal Manual, 7th Edition

U.S. DEPARTMENT OF ENERGY (DOE)

Energy Star	(1992; R 2006) Energy Star Energy Efficiency Labeling System (FEMP)

1.2 GENERAL REQUIREMENTS

Finished sheet metal assemblies must form a weathertight enclosure without waves, warps, buckles, fastening stresses or distortion, while allowing for expansion and contraction without damage to the system. The sheet metal installer is responsible for cutting, fitting, drilling, and other operations in connection with sheet metal modifications required to accommodate the work of other trades. Coordinate installation of sheet metal items used in conjunction with roofing with roofing work to permit continuous, uninterrupted roofing operations.

1.3 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-04 Samples

Finish Samples; G

SD-08 Manufacturer's Instructions

Instructions for Installation; G

SD-10 Operation and Maintenance Data

Cleaning and Maintenance; G

Paint and Repair Requirements

1.4 MISCELLANEOUS REQUIREMENTS

1.4.1 Product Data

Indicate thicknesses, dimensions, fastenings, anchoring methods, expansion joints, and other provisions necessary for thermal expansion and contraction. Scaled manufacturer's catalog data may be submitted for factory fabricated items.

1.4.2 Finish Samples

Submit two color charts and two finish sample chips from manufacturer's standard color and finish options for each type of finish indicated.

1.4.3 Operation and Maintenance Data

Submit detailed instructions for installation and quality control during installation, cleaning and maintenance, for each type of assembly indicated.

1.5 DELIVERY, HANDLING, AND STORAGE

Package and protect materials during shipment. Uncrate and inspect materials for damage, dampness, and wet-storage stains upon delivery to the job site. Remove from the site and replace damaged materials that cannot be restored to like-new condition. Handle sheet metal items to avoid damage to surfaces, edges, and ends. Store materials in dry, weather-tight, ventilated areas until installation.

PART 2 PRODUCTS

2.1 MATERIALS

Do not use lead, lead-coated metal, or galvanized steel. Use any metal listed by SMACNA 1793 for a particular item, unless otherwise indicated. Provide materials, thicknesses, and configurations in accordance with SMACNA 1793 for each material. Different items need not be of the same metal, except that if copper is selected for any exposed item, all exposed items must be copper, and that contact between dissimilar metals must be avoided.

Furnish sheet metal items in 8 to 10 foot lengths. Single pieces less than 8 feet long may be used to connect to factory-fabricated inside and outside corners, and at ends of runs. Factory fabricate corner pieces with minimum 12 inch legs. Provide accessories and other items essential to complete the sheet metal installation. Provide accessories made of the same or compatible materials as the items to which they are applied. Fabricate sheet metal items of the materials specified below and to the gage, thickness, or weight shown in Table I at the end of this section. Provide sheet metal items with mill finish unless specified otherwise. Where more than one material is listed for a particular item in Table I, each is acceptable and may be used, except as follows:

2.1.1 Exposed Sheet Metal Items

Must be of the same material. Consider the following as exposed sheet metal: gutters, including hangers; downspouts; gravel stops and fasciae; cap, valley, steeped, base, and eave flashings and related accessories.

2.1.2 Drainage

Do not use copper for an exposed item if drainage from that item will pass over exposed masonry, stonework or other metal surfaces. In addition to the metals listed in Table I, lead-coated copper may be used for such items.

2.1.3 Copper, Sheet and Strip

Provide in accordance with ASTM B370, cold-rolled temper, H 00 (standard).

2.1.4 Lead-Coated Copper Sheet

Provide in accordance with ASTM B101.

2.1.5 Lead Sheet

Provide in a minimum weight of 4 pounds per square foot.

2.1.6 Steel Sheet, Zinc-Coated (Galvanized)

Provide in accordance with ASTM A653/A653M.

2.1.7 Zinc Sheet and Strip

Provide in accordance with ASTM B69, Type I, a minimum of 0.024 inch thick.

2.1.8 Stainless Steel

Provide in accordance with ASTM A480/A480M, Type 302 or 304, 2D Finish, fully annealed, dead-soft temper.

2.1.9 Terne-Coated Steel

Provide in accordance with ASTM A308/A308M, a minimum of 14 by 20 inch with minimum of 40 pound coating per double base box. ASTM A308/A308M.

2.1.10 Aluminum Alloy Sheet and Plate

Provide in accordance with ASTM B209 anodized color form alloy, and temper appropriate for use.

2.1.10.1 Alclad

When fabricated of aluminum, fabricate the following items with Alclad 3003, Alclad 3004, or Alclad 3005, clad on both sides unless otherwise indicated.

a. Gutters, downspouts, and hangers

b. Gravel stops and fasciae

c. Flashing

2.1.11 Finishes

Provide exposed exterior sheet metal and aluminum with a baked on, factory applied color coating of polyvinylidene fluoride (PVF2) or approved equal fluorocarbon coating. Dry film thickness of coatings must be 0.8 to 1.3 mils. Color to be selected from manufacturer's standard range of color

choices. Field applications of color coatings are prohibited and will be rejected.

2.1.12 Cool Roof Finishes

Provide cool roof finish coatings and colors in accordance with one of the following methods of analysis:

2.1.12.1 Energy Star Certification

Provide roof finishes having an initial solar reflectance of and an initial emissivity of when tested in accordance with ASTM E408, or as certified by Energy Star for the particular product proposed. Certified Energy Star roof products are listed at https://www.energystar.gov/productfinder/product/certified-roof-products/results

2.1.13 Aluminum Alloy, Extruded Bars, Rods, Shapes, and Tubes

ASTM B221.

2.1.14 Solder

Provide in accordance with ASTM B32, 95-5 tin-antimony.

2.1.15 Reglets

2.1.15.1 Polyvinyl Chloride Reglets

Provide in accordance with ASTM D1784, Type II, Grade 1, Class 14333-D, 0.075 inch minimum thickness.

2.1.15.2 Metal Reglets

Provide factory fabricated caulked type or friction type reglets with a minimum opening of 1/4 inch and a depth of 1-1/4 inch, as approved.

2.1.15.2.1 Caulked Reglets

Provide with rounded edges, temporary reinforcing cores, and accessories as required for securing to adjacent construction. Provide built-up mitered corner pieces for inside and outside corners.

2.1.15.2.2 Friction Reglets

Provide with flashing receiving slots not less than 5/8 inch deep, one inch jointing tongues, and upper and lower anchoring flanges installed at 24 inch maximum snap-lock type receiver.

2.1.16 Scuppers

Line interiors of scupper openings with sheet metal. Provide a drip edge at bottom edges with returns of not less than one inch against the face of the outside wall at the top and sides. Provide the perimeter of the lining approximately 1/2 inch less than the perimeter of the scupper.

2.1.17 Conductor Heads

Provide conductor heads and screens in the same material as downspouts. Provide outlet tubes not less than 4 inches long.

2.1.18 Copings

Unless otherwise indicated, provide copings in copper sheets, 8 or 10 feet long, joined by a 3/4 inch locked and soldered seam.

2.1.19 Bituminous Plastic Cement

Provide in accordance with ASTM D4586/D4586M, Type I.

2.1.20 Roofing Felt

Provide in accordance with ASTM D226/D226M Type I.

2.1.21 Asphalt Primer

Provide in accordance with ASTM D41/D41M.

2.1.22 Fasteners

Use the same metal as, or a metal compatible with the item fastened. Use stainless steel fasteners to fasten. Confirm compatibility of fasteners and items to be fastened to avoid galvanic corrosion due to dissimilar materials.

PART 3 EXECUTION

3.1 INSTALLATION

3.1.1 Gutters

The hung type of shape indicated and supported on underside by brackets that permit free thermal movement of the gutter. Provide gutters in sizes indicated complete with mitered corners, end caps, outlets, brackets, and other accessories necessary for installation. Bead with hemmed edge or reinforce the outer edge of gutter with a stiffening bar not less than 3/4 by 3/16 inch of material compatible with gutter. Fabricate gutters in sections not less than 8 feet. Lap the sections a minimum of one inch in the direction of flow or provide with concealed splice plate 6 inches minimum. Join the gutters, other than aluminum, by riveted and soldered joints. Join aluminum gutters with riveted sealed joints. Provide expansion-type slip joints midway between outlets. Install gutters below slope line of the roof so that snow and ice can slide clear. Support gutters on adjustable hangers spaced not more than 30 inches on center. Adjust gutters to slope uniformly to outlets, with high points occurring midway between outlets. Fabricate hangers and fastenings from compatible metals.

3.1.2 Downspouts

Space supports for downspouts according to the manufacturer's recommendation for the wood masonry or steel substrate. Types, shapes and sizes are indicated. Provide complete including elbows and offsets. Provide downspouts in approximately 10 foot lengths. Provide end joints to telescope not less than 1/2 inch and lock longitudinal joints. Provide gutter outlets with wire ball strainers for each outlet. Provide strainers to fit tightly into outlets and be of the same material used for gutters. Keep downspouts not less than one inch away from walls. Fasten to the walls at top, bottom, and at an intermediate point not to exceed 5 feet on

center with leader straps or concealed rack-and-pin type fasteners. Form straps and fasteners of metal compatible with the downspouts.

3.2 PAINTING

Touch ups in the field may be applied only after metal substrates have been cleaned and pretreated in accordance with manufacturer's written instructions and products.

Field-paint sheet metal for separation of dissimilar materials.

3.2.1 Aluminum Surfaces

Clean with solvent and apply one coat of zinc-molybdate primer and one coat of aluminum paint.

3.3 CLEANING

Clean exposed sheet metal work at completion of installation. Remove grease and oil films, handling marks, contamination from steel wool, fittings and drilling debris, and scrub-clean. Free the exposed metal surfaces of dents, creases, waves, scratch marks, and solder or weld marks.

3.4 REPAIRS TO FINISH

Scratches, abrasions, and minor surface defects of finish may be repaired in accordance with the manufacturer's printed instructions and as approved. Repair damaged surfaces caused by scratches, blemishes, and variations of color and surface texture. Replace items which cannot be repaired.

3.5 FIELD QUALITY CONTROL

Establish and maintain a Quality Control Plan for sheet metal used in conjunction with roofing to assure compliance of the installed sheet metalwork with the contract requirements. Remove work that is not in compliance with the contract and replace or correct. Include quality control, but not be limited to, the following:

a. Observation of environmental conditions; number and skill level of sheet metal workers; condition of substrate.

b. Verification that specified material is provided and installed.

c. Inspection of sheet metalwork, for proper size(s) and thickness(es), fastening and joining, and proper installation.

3.5.1 Procedure

Submit for approval prior to start of roofing work. Include a checklist of points to be observed. Document the actual quality control observations and inspections. Furnish a copy of the documentation to the Contracting Officer at the end of each day.

HL4>TABLE I. SHEET METAL WEIGHT, THICKNESSES, AND GAGES					
Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch	Terne-Coated Stainless Steel, inch	Zinc-Coated Steel, U.S. Std. Gage
	16	.032	.015	.015	24
	16	-	.015	.015	-
	20	.040	.018	.018	-
Downspouts and leaders	16	.032	.015	.015	24
Downspout clips and anchors	-	.040 clip .125 anchor	-	-	-
Downspout straps, 2-inch	48 (a)	.060	.050	-	-
	16	.032	.015	.015	-
	20	.032	.015	.015	-
	No. 9 gage	.144 diameter	.109 diameter	-	
	20	.040	.018	.018	24
	16	.032	.015	.015	26
	16	-	.015	.015	24
	10	-	.010	.010	-
	16	-	.015	.015	-
	16	.032	.015	.015	-
	16	.032	.015	.015	-

HL4>TABLE I. SHEET METAL WEIGHT, THICKNESSES, AND GAGES					
Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch	Terne-Coated Stainless Steel, inch	Zinc-Coated Steel, U.S. Std. Gage
	16 (b)				
	16	-	-	-	-
	-	.075	-	-	-
	16	.032	.015	.015	-
	20	.050	.018	.018	24
	24	.050	.025	-	-
Gutters:					
Gutter section	16	.032	.015	.015	24
Continuous cleat	16	.032	.015	.015	24
Hangers, dimensions	1 inch by 1/8 inch (a)	1 inch by .(inch (c)	1 inch by .0: inch	-	-
Joint Cover plates (See Table II)	16	.032	.015	.015	24
Reglets (c)	10	-	.010	.010	-
	16	.040	.018	.018	-
(a) Brass.					
(b) May be lead weighing 4 pounds per square foot.					
(c) May be polyvinyl chloride.					

HL4>TABLE I. SHEET METAL WEIGHT, THICKNESSES, AND GAGES					
Sheet Metal Items	Copper kilograms per square foot	Aluminum, inch	Stainless Steel, inch	Terne-Coated Stainless Steel, inch	Zinc-Coated Steel, U.S. Std. Gage
(d) 2.5 pound minimum lead sleeve with 4 inch flange. Where lead sleeve is impractical, refer to paragraph SINGLE PIPE VENTS for optional material.					

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

SECTION 07 92 00

JOINT SEALANTS

08/16

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 PRODUCT DATA
1.4 ENVIRONMENTAL CONDITIONS
1.5 DELIVERY AND STORAGE
1.6 QUALITY ASSURANCE
1.6.1 Compatibility with Substrate
1.6.2 Joint Tolerance
1.6.3 Mock-Up
1.6.4 Adhesion

PART 2 PRODUCTS

2.1 SEALANTS
2.1.1 Exterior Sealants
2.1.2 Floor Joint Sealants
2.1.3 Preformed Sealants
2.2 PRIMERS
2.3 [Enter Appropriate Subpart Title Here]
2.3.1 Butyl Rubber Based
2.3.2 Silicone Rubber Base
2.4 CLEANING SOLVENTS

PART 3 EXECUTION

3.1 FIELD QUALITY CONTROL
3.2 SURFACE PREPARATION
3.2.1 Steel Surfaces
3.2.2 Aluminum or Bronze Surfaces
3.2.3 Concrete and Masonry Surfaces
3.2.4 Wood Surfaces
3.3 SEALANT PREPARATION
3.4 APPLICATION
3.4.1 Joint Width-To-Depth Ratios
3.4.2 Unacceptable Sealant Use
3.4.3 Masking Tape
3.4.4 Backstops
3.4.5 Primer
3.4.6 Sealants
3.5 PROTECTION AND CLEANING
3.5.1 Protection
3.5.2 Final Cleaning

-- End of Section Table of Contents --

SECTION 07 92 00

JOINT SEALANTS
08/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM C1193	(2013) Standard Guide for Use of Joint Sealants
ASTM C1311	(2014) Standard Specification for Solvent Release Agents
ASTM C1521	(2013) Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints
ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants

CALIFORNIA DEPARTMENT OF PUBLIC HEALTH (CDPH)

CDPH SECTION 01350	(2010; Version 1.1) Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources using Environmental Chambers

SOUTH COAST AIR QUALITY MANAGEMENT DISTRICT (SCAQMD)

SCAQMD Rule 1168	(2017) Adhesive and Sealant Applications

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Sealants; G

Primers; G

SD-06 Test Reports

Field Adhesion; G

1.3 PRODUCT DATA

Include storage requirements, shelf life, curing time, instructions for mixing and application, and accessories. Provide manufacturer's Safety Data Sheets (SDS) for each solvent, primer and sealant material proposed.

1.4 ENVIRONMENTAL CONDITIONS

Apply sealant when the ambient temperature is between 40 and 90 degrees F.

1.5 DELIVERY AND STORAGE

Deliver materials to the jobsite in unopened manufacturers' sealed shipping containers, with brand name, date of manufacture, color, and material designation clearly marked thereon. Label elastomeric sealant containers to identify type, class, grade, and use. Handle and store materials in accordance with manufacturer's printed instructions. Prevent exposure to foreign materials or subjection to sustained temperatures exceeding 90 degrees F or lower than 0 degrees F. Keep materials and containers closed and separated from absorptive materials such as wood and insulation.

1.6 QUALITY ASSURANCE

1.6.1 Compatibility with Substrate

Verify that each sealant is compatible for use with each joint substrate in accordance with sealant manufacturer's printed recommendations for each application.

1.6.2 Joint Tolerance

Provide joint tolerances in accordance with manufacturer's printed instructions.

1.6.3 Mock-Up

Provide a mock-up of each type of sealant using materials, colors, and techniques approved for use on the project. Approved mock-ups may be incorporated into the Work.

1.6.4 Adhesion

Provide in accordance with ASTM C1193 or ASTM C1521.

PART 2 PRODUCTS

2.1 SEALANTS

Provide sealant products that have been tested, found suitable, and documented as such by the manufacturer for the particular substrates to which they will be applied.

2.1.1 Exterior Sealants

For joints in vertical surfaces, provide ASTM C920, Type S or M, Grade NS, Class 25, Use NT. For joints in horizontal surfaces, provide ASTM C920, Type S or M, Grade P, Class 25, Use T. Provide location(s) and color(s) of sealant as follows. Note, color "as selected" refers to manufacturer's full range of color options:

Paint and Repair Requirements

LOCATION	COLOR
a. Joints and recesses formed where frames and subsills of windows, doors, louvers, and vents adjoin masonry, concrete, or metal frames. Use sealant at both exterior and interior surfaces of exterior wall penetrations.	Match adjacent surface color
b. Joints between new and existing exterior masonry walls.	Match adjacent surface color
c. Masonry joints where shelf angles occur.	Match adjacent surface color
d. Joints in wash surfaces of stonework.	Match adjacent surface color
e. Expansion and control joints.	Match adjacent surface color
f. Interior face of expansion joints in exterior concrete or masonry walls where metal expansion joint covers are not required.	Match adjacent surface color
g. Voids where items pass through exterior walls.	Match adjacent surface color
h. Metal reglets, where flashing is inserted into masonry joints, and where flashing is penetrated by coping dowels.	Match adjacent surface color
i. Metal-to-metal joints where sealant is indicated or specified.	Match adjacent surface color
j. Joints between ends of gravel stops, fasciae, copings, and adjacent walls.	Match adjacent surface color
k.	

2.1.2 Floor Joint Sealants

ASTM C920, Type S or M, Grade P, Class 25, Use T. Provide sealant products used on the interior of the building (defined as inside of the weatherproofing system) meeting either emissions requirements of CDPH SECTION 01350 (limit requirements for either office or classroom spaces regardless of space type) or VOC content requirements of SCAQMD Rule 1168. Provide certification or validation of indoor air quality for interior floor joint sealants. Provide location(s) and color(s) of sealant as follows. Note, color "as selected" refers to manufacturer's full range of color options:

Paint and Repair Requirements

LOCATION	COLOR
a. Seats of metal thresholds for exterior doors.	As selected
b. Control and expansion joints in floors, slabs, ceramic tile, and walkways.	As selected

2.1.3 Preformed Sealants

Provide preformed sealants of polybutylene or isoprene-butylene based pressure sensitive weather resistant tape or bead sealants capable of sealing out moisture, air and dust when installed as recommended by the manufacturer. At temperatures from minus 30 to plus 160 degrees F, sealants must be non-bleeding and have no loss of adhesion.

2.2 PRIMERS

Non-staining, quick drying type and consistency as recommended by the sealant manufacturer for the particular application. Provide primers for interior applications that meet the indoor air quality requirements of the paragraph SEALANTS above.

2.3 [Enter Appropriate Subpart Title Here]BOND BREAKERS

2.3.1 Butyl Rubber Based

Provide in accordance with ASTM C1311, from a single component, with solvent release. color as selected from manufacturer's full range of color choices.

2.3.2 Silicone Rubber Base

Provide in accordance with ASTM C920, from a single component, with solvent release, Non-sag, Type I, Grade A, Class 25. Color as selected from manufacturer's full range of color choices.

2.4 CLEANING SOLVENTS

Provide type(s) recommended by the sealant manufacturer and in accordance with environmental requirements herein. Protect adjacent aluminum and bronze surfaces from solvents. Provide solvents for interior applications that meet the indoor air quality requirements of the paragraph SEALANTS above.

PART 3 EXECUTION

3.1 FIELD QUALITY CONTROL

Perform a field adhesion test in accordance with manufacturer's instructions and ASTM C1193, Method A or ASTM C1521, Method A, Tail Procedure. Remove sealants that fail adhesion testing; clean substrates, reapply sealants, and re-test. Test sealants adjacent to failed sealants. Submit field adhesion test report indicating tests, locations, dates, results, and remedial actions taken.

3.2 SURFACE PREPARATION

Prepare surfaces according to manufacturer's printed installation instructions. Clean surfaces from dirt, frost, moisture, grease, oil, wax, lacquer, paint, or other foreign matter that would destroy or impair adhesion. Remove oil and grease with solvent; thoroughly remove solvents prior to sealant installation. Wipe surfaces dry with clean cloths. When resealing an existing joint, remove existing caulk or sealant prior to applying new sealant. For surface types not listed below, provide in accordance with sealant manufacturer's printed instructions for each specific surface.

3.2.1 Steel Surfaces

Remove loose mill scale by sandblasting or, if sandblasting is impractical or would damage finished work, scraping and wire brushing. Remove protective coatings by sandblasting or using a residue free solvent. Remove resulting debris and solvent residue prior to sealant installation.

3.2.2 Aluminum or Bronze Surfaces

Remove temporary protective coatings from surfaces that will be in contact with sealant. When masking tape is used as a protective coating, remove tape and any residual adhesive prior to sealant application. For removing protective coatings and final cleaning, use non-staining solvents recommended by the manufacturer of the item(s) containing aluminum or bronze surfaces.

3.2.3 Concrete and Masonry Surfaces

Where surfaces have been treated with curing compounds, oil, or other such materials, remove materials by sandblasting or wire brushing. Remove laitance, efflorescence and loose mortar from the joint cavity. Remove resulting debris prior to sealant installation.

3.2.4 Wood Surfaces

Ensure wood surfaces that will be in contact with sealants are free of splinters, sawdust and other loose particles.

3.3 SEALANT PREPARATION

Do not add liquids, solvents, or powders to sealants. Mix multicomponent elastomeric sealants in accordance with manufacturer's printed instructions.

3.4 APPLICATION

3.4.1 Joint Width-To-Depth Ratios

Acceptable Ratios:

JOINT WIDTH	JOINT DEPTH	
	Minimum	Maximum
For metal, glass, or other nonporous surfaces:		

JOINT WIDTH	JOINT DEPTH	
	Minimum	Maximum
1/4 inch (minimum)	1/4 inch	1/4 inch
over 1/4 inch	1/2 of width	Equal to width
For wood, concrete, masonry, stone, or to fill in gap:		
1/4 inch (minimum)	1/4 inch	1/4 inch
over 1/4 inch to 1/2 inch	1/4 inch	Equal to width
over 1/2 inch to 1 inch	1/2 inch	5/8 inch
Over 1 inch	prohibited	

Unacceptable Ratios: Where joints of acceptable width-to-depth ratios have not been provided, clean out joints to acceptable depths and grind or cut to acceptable widths without damage to the adjoining work. Grinding is prohibited at metal surfaces.

3.4.2 Unacceptable Sealant Use

Do not install sealants in lieu of other required building enclosure weatherproofing components such as flashing, drainage components, and joint closure accessories, or to close gaps between walls, floors, roofs, windows, and doors, that exceed acceptable installation tolerances. Remove sealants that have been used in an unacceptable manner and correct building enclosure deficiencies to comply with contract documents requirements.

3.4.3 Masking Tape

Place masking tape on the finished surface on one or both sides of joint cavities to protect adjacent finished surfaces from primer or sealant smears. Remove masking tape within 10 minutes of joint filling and tooling.

3.4.4 Backstops

Provide backstops dry and free of tears or holes. Tightly pack the back or bottom of joint cavities with backstop material to provide joints in specified depths. Provide backstops where indicated and where backstops are not indicated but joint cavities exceed the acceptable maximum depths specified in JOINT WIDTH-TO-DEPTH RATIOS Table.

3.4.5 Primer

Clean out loose particles from joints immediately prior to application of. Apply primer to joints in concrete masonry units, wood, and other porous surfaces in accordance with sealant manufacturer's printed instructions. Do not apply primer to exposed finished surfaces.

3.4.6 Sealants

Provide sealants compatible with the material(s) to which they are applied. Do not use a sealant that has exceeded its shelf life or has jelled and

cannot be discharged in a continuous flow from the sealant gun. Apply sealants in accordance with the manufacturer's printed instructions with a gun having a nozzle that fits the joint width. Work sealant into joints so as to fill the joints solidly without air pockets. Tool sealant after application to ensure adhesion. Apply sealant uniformly smooth and free of wrinkles. Upon completion of sealant application, roughen partially filled or unfilled joints, apply additional sealant, and tool smooth as specified. Apply sealer over sealants in accordance with the sealant manufacturer's printed instructions.

3.5 PROTECTION AND CLEANING

3.5.1 Protection

Protect areas adjacent to joints from sealant smears. Masking tape may be used for this purpose if removed 5 to 10 minutes after the joint is filled and no residual tape marks remain.

3.5.2 Final Cleaning

Upon completion of sealant application, remove remaining smears and stains and leave the work in a clean and neat condition.

a. Masonry and Other Porous Surfaces: Immediately remove fresh sealant that has been smeared on adjacent masonry, rub clean with a solvent, and remove solvent residue, in accordance with sealant manufacturer's printed instructions. Allow excess sealant to cure for 24 hour then remove by wire brushing or sanding. Remove resulting debris.

b. Metal and Other Non-Porous Surfaces: Remove excess sealant with a solvent moistened cloth. Remove solvent residue in accordance with solvent manufacturer's printed instructions.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - OPENINGS

SECTION 08 71 00

DOOR HARDWARE

02/16

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 PRODUCT DATA

PART 2 PRODUCTS

2.1 Weatherstripping Gasketing
2.2 FINISHES

PART 3 EXECUTION

3.1 INSTALLATION
3.1.1 Weatherstripping Installation
3.1.1.1 Stop Applied Weatherstripping
3.1.1.2 Interlocking Type Weatherstripping
3.1.1.3 Spring Tension Type Weatherstripping
3.2 FIELD QUALITY CONTROL

-- End of Section Table of Contents --

SECTION 08 71 00

DOOR HARDWARE
02/16

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by the basic designation only.

ASTM INTERNATIONAL (ASTM)

ASTM E283	(2004; R 2012) Determining the Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen

BUILDERS HARDWARE MANUFACTURERS ASSOCIATION (BHMA)

ANSI/BHMA A156.18	(2016) Materials and Finishes
ANSI/BHMA A156.22	(2017) Door Gasketing and Edge Seal Systems

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

36 CFR 1191	Americans with Disabilities Act (ADA) Accessibility Guidelines for Buildings and Facilities; Architectural Barriers Act (ABA) Accessibility Guidelines

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Hardware Items; G

SD-08 Manufacturer's Instructions

Installation

SD-10 Operation and Maintenance Data

Hardware Schedule Items, Data Package 1; G

Paint and Repair Requirements

1.3 PRODUCT DATA

Indicate fire-ratings at applicable components. Provide documentation of ABA/ADA accessibility compliance of applicable components, as required by 36 CFR 1191 Appendix D - Technical.

PART 2 PRODUCTS

2.1 Weatherstripping Gasketing

Provide in accordance with ANSI/BHMA A156.22. Provide the type and function designation where specified in paragraph HARDWARE SCHEDULE. Provide a set to include head and jamb seals, sweep strips, and, for pairs of doors, astragals. Air leakage of weatherstripped doors not to exceed 0.5 cubic feet per minute of air per square foot of door area when tested in accordance with ASTM E283. Provide weatherstripping with one of the following:

2.2 FINISHES

Provide in accordance with ANSI/BHMA A156.18. Provide hardware in BHMA 630 finish (satin stainless steel), unless specified otherwise. Provide items not manufactured in stainless steel in BHMA 626 finish (satin chromium plated) over brass or bronze, except prime coat finish for surface door closers, and except BHMA 652 finish (satin chromium plated) for steel hinges. Provide hinges for exterior doors in stainless steel with BHMA 630 finish or chromium plated brass or bronze with BHMA 626 finish. Furnish exit devices in BHMA 626 finish in lieu of BHMA 630 finish . Match exposed parts of concealed closers to lock and door trim. Match hardware finish for aluminum doors to the doors.

PART 3 EXECUTION

3.1 INSTALLATION

Provide hardware in accordance with manufacturers' printed installation instructions. Fasten hardware to wood surfaces with full-threaded wood screws or sheet metal screws. Provide machine screws set in expansion shields for fastening hardware to solid concrete and masonry surfaces. Provide toggle bolts where required for fastening to hollow core construction. Provide through bolts where necessary for satisfactory installation.

3.1.1 Weatherstripping Installation

Provide full contact, weathertight seals that allow operation of doors without binding the weatherstripping.

3.1.1.1 Stop Applied Weatherstripping

Fasten in place with color matched sheet metal screws not more than 9 inch on center after doors and frames have been finish painted.

3.1.1.2 Interlocking Type Weatherstripping

Provide interlocking, self adjusting type on heads and jambs and flexible hook type at sills. Nail weatherstripping to door 1 inch on center and to heads and jambs at 4 inch on center.

Paint and Repair Requirements

3.1.1.3 Spring Tension Type Weatherstripping

Provide spring tension type on heads and jambs. Provide bronze nails with bronze. Provide stainless steel nails with stainless steel. Space nails not more than 1-1/2 inch on center.

3.2 FIELD QUALITY CONTROL

After installation, protect hardware from paint, stains, blemishes, and other damage until acceptance of work. Correct, repair, and finish, errors in cutting and fitting and damage to adjoining work.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 08 - OPENINGS

SECTION 08 81 00

GLAZING

08/11

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 SYSTEM DESCRIPTION
1.4 DELIVERY, STORAGE, AND HANDLING
1.5 ENVIRONMENTAL REQUIREMENTS
1.6 WARRANTY
1.6.1 Warranty for Insulating Glass Units
1.6.2 Warranty for Polycarbonate Sheet

PART 2 PRODUCTS

2.1 GLASS
2.1.1 Clear Glass
2.1.2 Annealed Glass
2.1.3 Heat-Absorbing Glass
2.1.4 Wired Glass
2.1.5 Fire/Safety Rated Glass
2.1.6 Tinted (Light-Reducing) Glass
2.2 PLASTIC GLAZING
2.2.1 Acrylic Sheet
2.2.2 Polycarbonate Sheet
2.2.3 Extruded Polycarbonate Profiled Sheet
2.2.4 Bullet-Resistant Plastic Sheet
2.3 SETTING AND SEALING MATERIALS
2.3.1 Putty and Glazing Compound
2.3.2 Glazing Compound
2.3.3 Sealants
2.3.3.1 Elastomeric Sealant
2.3.3.2 Structural Sealant

PART 3 EXECUTION

3.1 PREPARATION
3.2 GLASS SETTING
3.2.1 Sheet Glass
3.2.2 Installation of Wire Glass
3.2.3 Installation of Heat-Absorbing Glass
3.2.4 Plastic Sheet
3.3 CLEANING
3.4 PROTECTION

-- End of Section Table of Contents --

SECTION 08 81 00

GLAZING
08/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z97.1	(2015) Safety Glazing Materials Used in Buildings - Safety Performance Specifications and Methods of Test

ASTM INTERNATIONAL (ASTM)

ASTM C1036	(2016) Standard Specification for Flat Glass
ASTM C1184	(2014) Standard Specification for Structural Silicone Sealants
ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants
ASTM D4802	(2016) Standard Specification for Poly(Methyl Methacrylate) Acrylic Plastic Sheet
ASTM E119	(2018) Standard Test Methods for Fire Tests of Building Construction and Materials
ASTM E1300	(2016) Standard Practice for Determining Load Resistance of Glass in Buildings
ASTM E2226	(2015a) Standard Practice for Application of Hose Stream

GLASS ASSOCIATION OF NORTH AMERICA (GANA)

GANA Glazing Manual	(2008) Glazing Manual
GANA Sealant Manual	(2008) Sealant Manual

INSULATING GLASS MANUFACTURERS ALLIANCE (IGMA)

IGMA TB-3001	(2001) Guidelines for Sloped Glazing
IGMA TM-3000	(1990; R 2016) North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial & Residential Use

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 252	(2017) Standard Methods of Fire Tests of Door Assemblies
NFPA 257	(2012; ERTA 2017) Standard on Fire Test for Window and Glass Block Assemblies
NFPA 80	(2016; TIA 16-1) Standard for Fire Doors and Other Opening Protectives

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

16 CFR 1201	Safety Standard for Architectural Glazing Materials

UNDERWRITERS LABORATORIES (UL)

UL 752	(2005; Reprint Dec 2015) Standard for Bullet-Resisting Equipment
UL MEAPD	(2011) Mechanical Equipment and Associated Products Directory (online version is listed under Certifications at www.ul.com)

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance to Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-03 Product Data

Exterior Glazing - performance documentation for all glass types

Plastic Glazing

Glazing Accessories

Manufacturer's descriptive product data, handling and storage recommendations, installation instructions, and cleaning instructions.

SD-04 Samples

Plastic Sheet

Glazing Compound

Sealant

Two 5 by 7 inch samples of each of the following: tinted glass, Wire reinforced glass.

One samples of each indicated material. Samples of plastic

sheets must be minimum 5 by 7 inches.

SD-08 Manufacturer's Instructions

Setting and Sealing Materials

Glass Setting

Submit glass manufacturer's recommendations for setting and sealing materials and for installation of each type of glazing material specified. Include cleaning instructions for plastic sheets.

1.3 SYSTEM DESCRIPTION

Fabricate and install watertight and airtight glazing systems to withstand thermal movement and wind loading without glass breakage, gasket failure, deterioration of glazing accessories, or defects in the work. Glazed panels must comply with the safety standards, in accordance with ANSI Z97.1, and comply with indicated wind/snow loading in accordance with ASTM E1300.

1.4 DELIVERY, STORAGE, AND HANDLING

Deliver products to the site in unopened containers, labeled plainly with manufacturers' names and brands. Store glass and setting materials in safe, enclosed dry locations and do not unpack until needed for installation. Handle and install materials in a manner that will protect them from damage.

1.5 ENVIRONMENTAL REQUIREMENTS

Do not start glazing work until the outdoor temperature is above40 degrees F and rising, unless procedures recommended by the glass manufacturer and approved by the Contracting Officer are made to warm the glass and rabbet surfaces. Provide ventilation to prevent condensation of moisture on glazing work during installation. Do not perform glazing work during damp or rainy weather.

1.6 WARRANTY

1.6.1 Warranty for Insulating Glass Units

Warranty insulating glass units against development of material obstruction to vision (such as dust, fogging, or film formation on the inner glass surfaces) caused by failure of the hermetic seal, other than through glass breakage, for a 10-year period following acceptance of the work. Provide new units for any units failing to comply with terms of this warranty within 45 working days after receipt of notice from the Government.

1.6.2 Warranty for Polycarbonate Sheet

For a 5-year period following acceptance of the work:

a. Warranty Type I, Class A (UV stabilized) sheets against breakage;

b. Warranty Type III (coated, mar-resistant) sheets against breakage and against coating delamination;

c. Warranty Type IV (coated sheet) against breakage and against yellowing;

d. Warranty extruded polycarbonate profile sheet against breakage.

For a 10-year period following acceptance of the work, warranty Type IV against yellowing and loss of light transmission.

PART 2 PRODUCTS

2.1 GLASS

ASTM C1036, unless specified otherwise. In doors and sidelights, provide safety glazing material conforming to 16 CFR 1201.

2.1.1 Clear Glass

Type I, Class 1 (clear), Quality q4 (A). Provide for glazing openings not indicated or specified otherwise. Use double-strength sheet glass or 1/8 inch float glass for openings up to and including 15 square feet, 3/16 inch for glazing openings over 15 square feet but not over 30 square feet, and 1/4 inch for glazing openings over 30 square feet but not over 45 square feet.

2.1.2 Annealed Glass

Annealed glass must be Type I transparent flat type, Class 1 - clear tinted, Quality q3 - glazing select, 80 percent light transmittance, 60 percent shading coefficient, conforming to ASTM C1036. Color must be gray.

2.1.3 Heat-Absorbing Glass

Type I, Class 2 (heat absorbing and light reducing), Quality q3 (select), 1/4 inch thick, blue in color, 50 percent light transmittance, 50 percent shading coefficient, conforming to ASTM C1036. Color must be gray for 1/4 inch thickness.

2.1.4 Wired Glass

Provide UL listed glass for fire-rated windows rated for 45 minutes when tested in accordance with ASTM E2226. Wired glass must be Type II flat type, Class 1 - translucent, Quality q8 - glazing, Form 1 - wired and polished both sides, 70 percent light transmittance, 30 percent shading coefficient, conforming to ASTM C1036. Wire mesh must be polished stainless steel Mesh 1 - diamond. Wired glass for fire-rated windows must bear an identifying UL label or the label of a nationally recognized testing agency, and be rated for 45 minutes when tested in accordance with NFPA 257. Wired glass for fire-rated doors must be tested as part of a door assembly in accordance with NFPA 252.

2.1.5 Fire/Safety Rated Glass

Fire/safety rated glass must be laminated Type I transparent flat type, Class 1-clear. Glass must have a 45 minute rating when tested in accordance with ASTM E119. Glass must be permanently labeled with appropriate markings.

2.1.6 Tinted (Light-Reducing) Glass

Tinted (light-reducing) glass must be Type I transparent flat type, Class

3-tinted, Quality q3 - glazing select, 30 percent light transmittance, 70 percent shading coefficient, conforming to ASTM C1036. Color must be gray.

2.2 PLASTIC GLAZING

Plastic glazing must have a U-factor maximum of 20 Btu per square foot by hr by degree F.

2.2.1 Acrylic Sheet

ASTM D4802, Type I, regular ultraviolet stabilized, scratch resistant, in. thick.

2.2.2 Polycarbonate Sheet

ANSI Z97.1, Clear and smooth both sides Translucent, textured both sides Gray tint Bronze tint mar-resistant high abrasion resistant, ultraviolet stabilized, 1/4 inch thick and listed in UL MEAPD as burglar resisting.

2.2.3 Extruded Polycarbonate Profiled Sheet

Provide double walled, surface treated for improved UV resistance, offering thermal efficiency and impact strength.

2.2.4 Bullet-Resistant Plastic Sheet

Cast acrylic sheet or mar-resistant polycarbonate sheet laminated with a special interlayer, and listed in UL 752 as bullet resisting, Class I, clear in color.

2.3 SETTING AND SEALING MATERIALS

Provide as specified in the GANA Glazing Manual, IGMA TM-3000, IGMA TB-3001, and manufacturer's recommendations, unless specified otherwise herein. Do not use metal sash putty, nonskinning compounds, nonresilient preformed sealers, or impregnated preformed gaskets. Materials exposed to view and unpainted must be gray or neutral color.

2.3.1 Putty and Glazing Compound

Provide glazing compound as recommended by manufacturer for face-glazing metal sash. Putty must be linseed oil type. Do not use putty and glazing compounds with insulating glass or laminated glass.

2.3.2 Glazing Compound

Use for face glazing metal sash. Do not use with insulating glass units or laminated glass.

2.3.3 Sealants

Provide elastomeric and structural sealants.

2.3.3.1 Elastomeric Sealant

ASTM C920, Type S, Grade NS, Class 12.5, Use G. Use for channel or stop glazing wood and metal sash. Sealant must be chemically compatible with setting blocks, edge blocks, and sealing tapes, with sealants used in manufacture of insulating glass units, and with plastic sheet. Color of

sealant must be white.

2.3.3.2 Structural Sealant

ASTM C1184, Type S.

PART 3 EXECUTION

Any materials that show visual evidence of biological growth due to the presence of moisture must not be installed on the building project.

3.1 PREPARATION

Preparation, unless otherwise specified or approved, must conform to applicable recommendations in the GANA Glazing Manual, GANA Sealant Manual, IGMA TB-3001, IGMA TM-3000, and manufacturer's recommendations. Determine the sizes to provide the required edge clearances by measuring the actual opening to receive the glass. Grind smooth in the shop glass edges that will be exposed in finish work. Leave labels in place until the installation is approved, except remove applied labels on heat-absorbing glass and on insulating glass units as soon as glass is installed. Securely fix movable items or keep in a closed and locked position until glazing compound has thoroughly set.

3.2 GLASS SETTING

Shop glaze or field glaze items to be glazed using glass of the quality and thickness specified or indicated. Glazing, unless otherwise specified or approved, must conform to applicable recommendations in the GANA Glazing Manual, GANA Sealant Manual, IGMA TB-3001, IGMA TM-3000, and manufacturer's recommendations. Aluminum windows, wood doors, and wood windows may be glazed in conformance with one of the glazing methods described in the standards under which they are produced, except that face puttying with no bedding will not be permitted. Handle and install glazing materials in accordance with manufacturer's instructions. Use beads or stops which are furnished with items to be glazed to secure the glass in place. Verify products are properly installed, connected, and adjusted.

3.2.1 Sheet Glass

Cut and set with the visible lines or waves horizontal.

3.2.2 Installation of Wire Glass

Install glass for fire doors in accordance with installation requirements of NFPA 80.

3.2.3 Installation of Heat-Absorbing Glass

Provide glass with clean-cut, factory-fabricated edges. Field cutting will not be permitted.

3.2.4 Plastic Sheet

Conform to manufacturer's recommendations for edge clearance, type of sealant and tape, and method of installation.

3.3 CLEANING

Clean glass surfaces and remove labels, paint spots, putty, and other defacement as required to prevent staining. Glass must be clean at the time the work is accepted. Clean plastic sheet in accordance with manufacturer's instructions.

3.4 PROTECTION

Protect glass work immediately after installation. Identify glazed openings with suitable warning tapes, cloth or paper flags, attached with non-staining adhesives. Protect reflective glass with a protective material to eliminate any contamination of the reflective coating. Place protective material far enough away from the coated glass to allow air to circulate to reduce heat buildup and moisture accumulation on the glass.Remove and replace glass units which are broken, chipped, cracked, abraded, or otherwise damaged during construction activities with new units.

-- End of Section --

SECTION TABLE OF CONTENTS

DIVISION 09 - FINISHES

SECTION 09 90 00

PAINTS AND COATINGS

05/11

PART 1 GENERAL

1.1 REFERENCES
1.2 SUBMITTALS
1.3 APPLICATOR'S QUALIFICATIONS
1.3.1 Contractor Qualification
1.3.2 SSPC QP 1 Certification
1.4 QUALITY ASSURANCE
1.4.1 Field Samples and Tests
1.4.1.1 Sampling Procedure
1.4.1.2 Testing Procedure
1.5 REGULATORY REQUIREMENTS
1.5.1 Environmental Protection
1.5.2 Lead Content
1.5.3 Chromate Content
1.5.4 Asbestos Content
1.5.5 Mercury Content
1.5.6 Silica
1.5.7 Human Carcinogens
1.6 PACKAGING, LABELING, AND STORAGE
1.7 SAFETY AND HEALTH
1.7.1 Safety Methods Used During Coating Application
1.7.2 Toxic Materials
1.8 ENVIRONMENTAL CONDITIONS
1.8.1 Coatings
1.9 COLOR SELECTION
1.10 LOCATION AND SURFACE TYPE TO BE PAINTED
1.10.1 Painting Included
1.10.1.1 Exterior Painting
1.10.2 Painting Excluded
1.10.3 Mechanical and Electrical Painting
1.10.4 Definitions and Abbreviations
1.10.4.1 Qualification Testing
1.10.4.2 Batch Quality Conformance Testing
1.10.4.3 Coating
1.10.4.4 DFT or dft
1.10.4.5 DSD
1.10.4.6 EPP
1.10.4.7 EXT
1.10.4.8 INT
1.10.4.9 micron / microns
1.10.4.10 mil / mils
1.10.4.11 mm
1.10.4.12 MPI Gloss Levels
1.10.4.13 MPI System Number
1.10.4.14 Paint

1.10.4.15 REX
1.10.4.16 RIN

PART 2 PRODUCTS

2.1 MATERIALS

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED
3.2 REPUTTYING AND REGLAZING
3.3 RESEALING OF EXISTING EXTERIOR JOINTS
3.3.1 Surface Condition
3.3.2 Backstops
3.3.3 Primer and Bond Breaker
3.3.4 Ambient Temperature
3.3.5 Exterior Sealant
3.3.6 Cleaning
3.4 SURFACE PREPARATION
3.4.1 Additional Requirements for Preparation of Surfaces With Existing Coatings
3.4.2 Existing Coated Surfaces with Minor Defects
3.4.3 Removal of Existing Coatings
3.4.4 Substrate Repair
3.5 PREPARATION OF METAL SURFACES
3.5.1 Existing and New Ferrous Surfaces
3.5.2 Final Ferrous Surface Condition:
3.5.3 Galvanized Surfaces
3.5.4 Non-Ferrous Metallic Surfaces
3.5.5 Terne-Coated Metal Surfaces
3.5.6 Existing Surfaces with a Bituminous or Mastic-Type Coating
3.6 PREPARATION OF CONCRETE AND CEMENTITIOUS SURFACE
3.6.1 Concrete and Masonry
3.6.2 Gypsum Board, Plaster, and Stucco
3.7 REPARATION OF WOOD AND PLYWOOD SURFACES
3.7.1 New , Existing Uncoated, and Existing Coated Plywood and Wood Surfaces, Except Floors:
3.7.2 Water Blasting of Existing Coated Wood Surfaces:
3.8 APPLICATION
3.8.1 Coating Application
3.8.2 Mixing and Thinning of Paints
3.8.3 Two-Component Systems
3.8.4 Coating Systems
3.9 COATING SYSTEMS FOR METAL
3.10 COATING SYSTEMS FOR CONCRETE AND CEMENTITIOUS SUBSTRATES
3.11 COATING SYSTEMS FOR WOOD AND PLYWOOD
3.12 INSPECTION AND ACCEPTANCE
3.13 WASTE MANAGEMENT
3.14 PAINT TABLES
3.14.1 Exterior Paint Tables

-- End of Section Table of Contents --

SECTION 09 90 00

PAINTS AND COATINGS
05/11

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only.

AMERICAN CONFERENCE OF GOVERNMENTAL INDUSTRIAL HYGIENISTS (ACGIH)

ACGIH 0100	(2015; Suppl 2002-2016) Documentation of the Threshold Limit Values and Biological Exposure Indices

ASTM INTERNATIONAL (ASTM)

ASTM C920	(2018) Standard Specification for Elastomeric Joint Sealants
ASTM D235	(2002; R 2012) Mineral Spirits (Petroleum Spirits) (Hydrocarbon Dry Cleaning Solvent)
ASTM D2824/D2824M	(2018) Standard Specification for Aluminum-Pigmented Asphalt Roof Coatings, Non-Fibered, and Fibered without Asbestos
ASTM D4214	(2007; R 2015) Standard Test Method for Evaluating the Degree of Chalking of Exterior Paint Films
ASTM D4263	(1983; R 2012) Indicating Moisture in Concrete by the Plastic Sheet Method
ASTM D4444	(2013) Use and Calibration of Hand-Held Moisture Meters
ASTM D523	(2014; R 2018) Standard Test Method for Specular Gloss
ASTM D6386	(2016) Standard Practice for Preparation of Zinc (Hot-Dip Galvanized) Coated Iron and Steel Product and Hardware Surfaces for Painting
ASTM F1869	(2016) Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride

MASTER PAINTERS INSTITUTE (MPI)

MPI 1	(2012) Aluminum Paint

MPI 10	(2012) Latex, Exterior Flat (MPI Gloss Level 1)
MPI 101	(2012) Primer, Epoxy, Anti-Corrosive, for Metal
MPI 107	(2012) Primer, Rust-Inhibitive, Water Based
MPI 108	(2012) Epoxy, High Build, Low Gloss
MPI 11	(2012) Latex, Exterior Semi-Gloss, MPI Gloss Level 5
MPI 113	(2012) Elastomeric, Pigmented, Exterior, Water Based, Flat
MPI 119	(2012) Latex, Exterior, Gloss (MPI Gloss Level 6)
MPI 13	(2012) Stain, Exterior Solvent-Based, Semi-Transparent
MPI 134	(2012) Primer, Galvanized, Water Based
MPI 16	(2012) Stain, Exterior, Water Based, Solid Hide
MPI 161	(2012) Light Industrial Coating, Exterior, Water Based (MPI Gloss Level 3)
MPI 163	(2012) Light Industrial Coating, Exterior, Water Based, Semi-Gloss (MPI Gloss Level 5)
MPI 164	(2012) Light Industrial Coating, Exterior, Water Based, Gloss (MPI Gloss Level 6)
MPI 19	(2012) Primer, Zinc Rich, Inorganic
MPI 2	(2012) Aluminum Heat Resistant Enamel (up to 427 C and 800 F
MPI 21	(2012) Heat Resistant Coating, (Up to 205°C/402°F), MPI Gloss Level 6
MPI 22	(2012) Aluminum Paint, High Heat (up to 590° C/1100° F)
MPI 23	(2012) Primer, Metal, Surface Tolerant
MPI 26	(2012) Primer, Galvanized Metal, Cementitious
MPI 27	(2012) Floor Enamel, Alkyd, Gloss (MPI Gloss Level 6)
MPI 4	(2012) Interior/Exterior Latex Block Filler
MPI 42	(2012) Textured Coating, Latex, Flat

MPI 5	(2012) Primer, Exterior Alkyd Wood
MPI 59	(2012) Floor Paint, Alkyd, Low Gloss
MPI 6	(2012) Primer, Exterior Latex Wood
MPI 7	(Oct 2009) Exterior Oil Wood Primer
MPI 72	(2012) Polyurethane, Two-Component, Pigmented, Gloss (MPI Gloss Level 6-7)
MPI 77	(2012) Epoxy, Gloss
MPI 79	(2012) Primer, Alkyd, Anti-Corrosive for Metal
MPI 8	(2012) Alkyd, Exterior Flat (MPI Gloss Level I)
MPI 9	(2012) Alkyd, Exterior Gloss (MPI Gloss Level 6)
MPI 94	(2012) Alkyd, Exterior, Semi-Gloss (MPI Gloss Level 5)
MPI 95	(2012) Primer, Quick Dry, for Aluminum

SOCIETY FOR PROTECTIVE COATINGS (SSPC)

SSPC 7/NACE No.4	(2007; E 2004) Brush-Off Blast Cleaning
SSPC Guide 6	(2015) Guide for Containing Surface Preparation Debris Generated During Paint Removal Operations
SSPC Guide 7	(2004; E 2004) Guide to the Disposal of Lead-Contaminated Surface Preparation Debris
SSPC PA 1	(2016) Shop, Field, and Maintenance Coating of Metals
SSPC PA Guide 3	(1982; E 1995) A Guide to Safety in Paint Application
SSPC Paint 18	(1982; E 2004) Chlorinated Rubber Intermediate Coat Paint
SSPC QP 1	(2012; E 2012) Standard Procedure for Evaluating Painting Contractors (Field Application to Complex Industrial Structures)
SSPC SP 1	(2015) Solvent Cleaning
SSPC SP 10/NACE No. 2	(2007) Near-White Blast Cleaning
SSPC SP 12/NACE No.5	(2002) Surface Preparation and Cleaning of Metals by Waterjetting Prior to Recoating

SSPC SP 2	(1982; E 2000; E 2004) Hand Tool Cleaning
SSPC SP 3	(1982; E 2004) Power Tool Cleaning
SSPC SP 6/NACE No.3	(2007) Commercial Blast Cleaning
SSPC VIS 1	(2002; E 2004) Guide and Reference Photographs for Steel Surfaces Prepared by Dry Abrasive Blast Cleaning
SSPC VIS 3	(2004) Guide and Reference Photographs for Steel Surfaces Prepared by Hand and Power Tool Cleaning
SSPC VIS 4/NACE VIS 7	(1998; E 2000; E 2004) Guide and Reference Photographs for Steel Surfaces Prepared by Waterjetting

U.S. ARMY CORPS OF ENGINEERS (USACE)

EM 385-1-1	(2014) Safety and Health Requirements Manual

U.S. GENERAL SERVICES ADMINISTRATION (GSA)

FED-STD-313	(2014; Rev E) Material Safety Data, Transportation Data and Disposal Data for Hazardous Materials Furnished to Government Activities

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1910.1000	Air Contaminants
29 CFR 1910.1025	Lead
29 CFR 1926.62	Lead

1.2 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for Contractor Quality Control approval. Submittals with an "S" are for inclusion in the Sustainability eNotebook, in conformance with Section 01 33 29 SUSTAINABILITY REPORTING. Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

The current MPI, "Approved Product List" which lists paint by brand, label, product name and product code as of the date of contract award, will be used to determine compliance with the submittal requirements of this specification. The Contractor may choose to use a subsequent MPI "Approved Product List", however, only one list may be used for the entire contract and each coating system is to be from a single manufacturer. Provide all coats on a particular substrate from a single manufacturer. No variation from the MPI Approved Products List is acceptable.

Samples of specified materials may be taken and tested for compliance with specification requirements.

SD-03 Product Data

Coating; G

Sealant

SD-04 Samples

Color; G

SD-07 Certificates

Applicator's Qualifications

Qualification Testing laboratory for coatings; G

SD-08 Manufacturer's Instructions

Application Instructions

Mixing

Manufacturer's Safety Data Sheets

SD-10 Operation and Maintenance Data

Coatings; G

1.3 APPLICATOR'S QUALIFICATIONS

1.3.1 Contractor Qualification

Submit the name, address, telephone number, FAX number, and e-mail address of the contractor that will be performing all surface preparation and coating application. Submit evidence that key personnel have successfully performed surface preparation and application of coatings on multiple surfaces on a minimum of three similar projects within the past three years. List information by individual and include the following:

a. Name of individual and proposed position for this work.

b. Information about each previous assignment including:

Position or responsibility

Employer (if other than the Contractor)

Name of facility owner

Mailing address, telephone number, and telex number (if non-US) of facility owner

Name of individual in facility owner's organization who can be contacted as a reference

Location, size and description of structure

Dates work was carried out

Description of work carried out on structure

1.3.2 SSPC QP 1 Certification

All contractors and subcontractors that perform surface preparation or coating application must be certified by the Society for Protective Coatings (formerly Steel Structures Painting Council) (SSPC) to the requirements of SSPC QP 1 prior to contract award, and must remain certified while accomplishing any surface preparation or coating application. If a contractor's or subcontractor's certification expires, the firm will not be allowed to perform any work until the certification is reissued. Requests for extension of time for any delay to the completion of the project due to an inactive certification will not be considered and liquidated damages will apply. Notify the Contracting Officer of any change in contractor certification status.

1.4 QUALITY ASSURANCE

1.4.1 Field Samples and Tests

The Contracting Officer may choose up to two coatings that have been delivered to the site to be tested at no cost to the Government. Take samples of each chosen product as specified in the paragraph SAMPLING PROCEDURES. Test each chosen product as specified in the paragraph TESTING PROCEDURE. Remove products from the job site which do not conform, and replace with new products that conform to the referenced specification. Test replacement products that failed initial testing at no cost to the Government.

Another required testing is Batch Quality Conformance Testing to prove conformance of the manufacturer's paint to the specified MPI standard. This testing is accomplished before the materials are delivered to the job site. Provide testing for exterior paint products. Test paint products as specified in the paragraph "Testing Procedure".

1.4.1.1 Sampling Procedure

The Contracting Officer will select paint at random from the products that have been delivered to the job site for sample testing. The Contractor will provide one quart samples of the selected paint materials. Take samples in the presence of the Contracting Officer, and label, and identify each sample. Provide labels in accordance with the paragraph PACKAGING, LABELING, AND STORAGE of this specification.

1.4.1.2 Testing Procedure

Provide Batch Quality Conformance Testing for specified products, as defined by and performed by MPI. As an alternative to Batch Quality Conformance Testing, the Contractor may provide Qualification Testing for specified products above to the appropriate MPI product specification, using the third-party laboratory approved under the paragraph "Qualification Testing" laboratory for coatings. Include the backup data and summary of the test results within the qualification testing lab report. Provide a summary listing of all the reference specification

requirements and the result of each test. Clearly indicate in the summary whether the tested paint meets each test requirement. Note that Qualification Testing may take 4 to 6 weeks to perform, due to the extent of testing required.

Submit name, address, telephone number, FAX number, and e-mail address of the independent third party laboratory selected to perform testing of coating samples for compliance with specification requirements. Submit documentation that laboratory is regularly engaged in testing of paint samples for conformance with specifications, and that employees performing testing are qualified. If MPI is chosen to perform the Batch Quality Conformance testing, the above submittal information is not required, only a letter is required from the Contractor stating that MPI will perform the testing.

1.5 REGULATORY REQUIREMENTS

1.5.1 Environmental Protection

In addition to requirements specified elsewhere for environmental protection, provide coating materials that conform to the restrictions of the local Air Pollution Control District and regional jurisdiction. Notify Contracting Officer of any paint specified herein which fails to conform.

1.5.2 Lead Content

Do not use coatings having a lead content over 0.06 percent by weight of nonvolatile content.

1.5.3 Chromate Content

Do not use coatings containing zinc-chromate or strontium-chromate.

1.5.4 Asbestos Content

Provide asbestos-free materials.

1.5.5 Mercury Content

Provide materials free of mercury or mercury compounds.

1.5.6 Silica

Provide abrasive blast media containing no free crystalline silica.

1.5.7 Human Carcinogens

Provide materials that do not contain ACGIH 0100 confirmed human carcinogens (A1) or suspected human carcinogens (A2).

1.6 PACKAGING, LABELING, AND STORAGE

Provide paints in sealed containers that legibly show the contract specification number, designation name, formula or specification number, batch number, color, quantity, date of manufacture, manufacturer's formulation number, manufacturer's directions including any warnings and special precautions, and name and address of manufacturer. Furnish pigmented paints in containers not larger than 5 gallons. Store paints and thinners in accordance with the manufacturer's written directions, and as a

minimum, stored off the ground, under cover, with sufficient ventilation to prevent the buildup of flammable vapors, and at temperatures between 40 to 95 degrees F.

1.7 SAFETY AND HEALTH

Apply coating materials using safety methods and equipment in accordance with the following:

Comply with applicable Federal, State, and local laws and regulations, and with the ACCIDENT PREVENTION PLAN, including the Activity Hazard Analysis as specified in Section 01 35 26 GOVERNMENT SAFETY REQUIREMENTS and in Appendix A of EM 385-1-1. Include in the Activity Hazard Analysis the potential impact of painting operations on painting personnel and on others involved in and adjacent to the work zone.

1.7.1 Safety Methods Used During Coating Application

Comply with the requirements of SSPC PA Guide 3.

1.7.2 Toxic Materials

To protect personnel from overexposure to toxic materials, conform to the most stringent guidance of:

a. The applicable manufacturer's Safety Data Sheets (SDS) or local regulation.

b. 29 CFR 1910.1000.

c. ACGIH 0100, threshold limit values.

d. The appropriate OSHA standard in 29 CFR 1910.1025 and 29 CFR 1926.62 for surface preparation on painted surfaces containing lead. Removal and disposal of coatings which contain lead is specified in Section 02 82 33.13 20 REMOVAL/CONTROL AND DISPOSAL OF PAINT WITH LEAD." Additional guidance is given in SSPC Guide 6 and SSPC Guide 7. Refer to drawings for list of hazardous materials located on this project. Coordinate paint preparation activities with this specification section.

Submit manufacturer's Safety Data Sheets for coatings, solvents, and other potentially hazardous materials, as defined in FED-STD-313.

1.8 ENVIRONMENTAL CONDITIONS

Comply, at minimum, with manufacturer recommendations for space ventilation during and after installation.

1.8.1 Coatings

Do not apply coating when air or substrate conditions are:

a. Less than 5 degrees F above dew point;

b. Below 50 degrees F or over 95 degrees F, unless specifically pre-approved by the Contracting Officer and the product manufacturer. Do not, under any circumstances, violate the manufacturer's application recommendations.

1.9 COLOR SELECTION

Provide colors of finish coats as indicated or specified. Allow Contracting Officer to select colors not indicated or specified. Manufacturers' names and color identification are used for the purpose of color identification only. Named products are acceptable for use only if they conform to specified requirements. Products of other manufacturers are acceptable if the colors approximate colors indicated and the product conforms to specified requirements.

Tint each coat progressively darker to enable confirmation of the number of coats.

Provide color, texture, and pattern of wall coating systems as needed for task order.

Submit manufacturer's samples of paint colors. Cross reference color samples to color scheme as indicated. Submit color stencil codes.

1.10 LOCATION AND SURFACE TYPE TO BE PAINTED

1.10.1 Painting Included

Where a space or surface is indicated to be painted, include the following unless indicated otherwise.

a. Surfaces behind portable objects and surface mounted articles readily detachable by removal of fasteners, such as screws and bolts.

b. New factory finished surfaces that require identification or color coding and factory finished surfaces that are damaged during performance of the work.

c. Existing coated surfaces that are damaged during performance of the work.

1.10.1.1 Exterior Painting

Includes new surfaces, existing coated surfaces, and existing uncoated surfaces, of the buildings and appurtenances. Also included are existing coated surfaces made bare by cleaning operations.

1.10.2 Painting Excluded

Do not paint the following unless indicated otherwise.

c. Steel to be embedded in concrete.

d. Copper, stainless steel, aluminum, brass, and lead except existing coated surfaces.

e. Hardware, fittings, and other factory finished items.

1.10.3 Mechanical and Electrical Painting

Includes field coating of exterior new and existing surfaces.

a. Where a space or surface is indicated to be painted, include the following items unless indicated otherwise.

(1) Exposed piping, conduit, and ductwork;

(2) Supports, hangers, air grilles, and registers;

(3) Miscellaneous metalwork and insulation coverings.

1.10.4 Definitions and Abbreviations

1.10.4.1 Qualification Testing

Qualification testing is the performance of all test requirements listed in the product specification. This testing is accomplished by MPI to qualify each product for the MPI Approved Product List, and may also be accomplished by Contractor's third party testing lab if an alternative to Batch Quality Conformance Testing by MPI is desired.

1.10.4.2 Batch Quality Conformance Testing

Batch quality conformance testing determines that the product provided is the same as the product qualified to the appropriate product specification. This testing must be accomplished by an MPI testing lab.

1.10.4.3 Coating

A film or thin layer applied to a base material called a substrate. A coating may be a metal, alloy, paint, or solid/liquid suspensions on various substrates (such as metals, plastics, wood, paper, leather, cloth). They may be applied by electrolysis, vapor deposition, vacuum, or mechanical means such as brushing, spraying, calendaring, and roller coating. A coating may be applied for aesthetic or protective purposes or both. The term "coating" as used herein includes emulsions, enamels, stains, varnishes, sealers, epoxies, and other coatings, whether used as primer, intermediate, or finish coat. The terms paint and coating are used interchangeably.

1.10.4.4 DFT or dft

Dry film thickness, the film thickness of the fully cured, dry paint or coating.

1.10.4.5 DSD

Degree of Surface Degradation, the MPI system of defining degree of surface degradation. Five (5) levels are generically defined under the Assessment sections in the MPI Maintenance Repainting Manual.

1.10.4.6 EPP

Environmentally Preferred Products, a standard for determining environmental preferability in support of Executive Order 13101.

1.10.4.7 EXT

MPI short term designation for an exterior coating system.

1.10.4.8 INT

MPI short term designation for an interior coating system.

1.10.4.9 micron / microns

The metric measurement for 0.001 mm or one/one-thousandth of a millimeter.

1.10.4.10 mil / mils

The English measurement for 0.001 in or one/one-thousandth of an inch, equal to 25.4 microns or 0.0254 mm.

1.10.4.11 mm

The metric measurement for millimeter, 0.001 meter or one/one-thousandth of a meter.

1.10.4.12 MPI Gloss Levels

MPI system of defining gloss. Seven (7) gloss levels (G1 to G7) are generically defined under the Evaluation sections of the MPI Manuals. Traditionally, Flat refers to G1/G2, Eggshell refers to G3, Semigloss refers to G5, and Gloss refers to G6.

Gloss levels are defined by MPI as follows:

Gloss Level	Description	Units at 60 degrees	Units at 85 degrees
G1	Matte or Flat	0 to 5	10 max
G2	Velvet	0 to 10	10 to 35
G3	Eggshell	10 to 25	10 to 35
G4	Satin	20 to 35	35 min
G5	Semi-Gloss	35 to 70	
G6	Gloss	70 to 85	
G7	High Gloss		

Gloss is tested in accordance with ASTM D523. Historically, the Government has used Flat (G1 / G2), Eggshell (G3), Semi-Gloss (G5), and Gloss (G6).

1.10.4.13 MPI System Number

The MPI coating system number in each Division found in either the MPI Architectural Painting Specification Manual or the Maintenance Repainting Manual and defined as an exterior (EXT/REX) or interior system (INT/RIN). The Division number follows the CSI Master Format.

1.10.4.14 Paint

See Coating definition.

1.10.4.15 REX

MPI short term designation for an exterior coating system used in repainting projects or over existing coating systems.

1.10.4.16 RIN

MPI short term designation for an interior coating system used in repainting projects or over existing coating systems.

PART 2 PRODUCTS

2.1 MATERIALS

Conform to the coating specifications and standards referenced in PART 3. Submit product data sheets for specified coatings and solvents. Provide preprinted cleaning and maintenance instructions for all coating systems.

Submit Manufacturer's Instructions on Mixing: Detailed mixing instructions, minimum and maximum application temperature and humidity, potlife, and curing and drying times between coats.

PART 3 EXECUTION

3.1 PROTECTION OF AREAS AND SPACES NOT TO BE PAINTED

Prior to surface preparation and coating applications, remove, mask, or otherwise protect hardware, hardware accessories, machined surfaces, radiator covers, plates, lighting fixtures, public and private property, and other such items not to be coated that are in contact with surfaces to be coated. Following completion of painting, reinstall removed items by workmen skilled in the trades. Restore surfaces contaminated by coating materials, to original condition and repair damaged items.

3.2 REPUTTYING AND REGLAZING

Remove cracked, loose, and defective putty or glazing compound on glazed sash and provide new putty or glazing compound. Where defective putty or glazing compound constitutes 30 percent or more of the putty at any one light, remove the glass and putty or glazing compound and reset the glass. Remove putty or glazing compound without damaging sash or glass. Clean rabbets to bare wood or metal and prime prior to reglazing. Provide linseed oil putty for wood sash. Patch surfaces to provide smooth transition between existing and new surfaces. Finish putty or glazing compound to a neat and true bead. Allow glazing compound time to cure, in accordance with manufacturer's recommendation, prior to coating application. Allow putty to set one week prior to coating application.

3.3 RESEALING OF EXISTING EXTERIOR JOINTS

3.3.1 Surface Condition

Begin with surfaces that are clean, dry to the touch, and free from frost and moisture; remove grease, oil, wax, lacquer, paint, defective backstop, or other foreign matter that would prevent or impair adhesion. Where adequate grooves have not been provided, clean out to a depth of 1/2 inch and grind to a minimum width of 1/4 inch without damage to adjoining work. Grinding is not required on metal surfaces.

3.3.2 Backstops

In joints more than 1/2 inch deep, install glass fiber roving or neoprene, butyl, polyurethane, or polyethylene foams free of oil or other staining elements as recommended by sealant manufacturer. Provide backstop material compatible with sealant. Do not use oakum and other types of absorptive materials as backstops.

3.3.3 Primer and Bond Breaker

Install the type recommended by the sealant manufacturer.

3.3.4 Ambient Temperature

Between 38 degrees F and 95 degrees F when applying sealant.

3.3.5 Exterior Sealant

For joints in vertical surfaces, provide ASTM C920, Type S or M, Grade NS, Class 25, Use NT. For joints in horizontal surfaces, provide ASTM C920, Type S or M, Grade P, Class 25, Use T. Color(s) will be selected by the Contracting Officer. Apply the sealant in accordance with the manufacturer's printed instructions. Force sealant into joints with sufficient pressure to fill the joints solidly. Apply sealant uniformly smooth and free of wrinkles.

3.3.6 Cleaning

Immediately remove fresh sealant from adjacent areas using a solvent recommended by the sealant manufacturer. Upon completion of sealant application, remove remaining smears and stains and leave the work in a clean condition. Allow sealant time to cure, in accordance with manufacturer's recommendations, prior to coating.

3.4 SURFACE PREPARATION

Remove dirt, splinters, loose particles, grease, oil, disintegrated coatings, and other foreign matter and substances deleterious to coating performance as specified for each substrate before application of paint or surface treatments. Remove oil and grease prior to mechanical cleaning. Schedule cleaning so that dust and other contaminants will not fall on wet, newly painted surfaces. Spot-prime exposed ferrous metals such as nail heads on or in contact with surfaces to be painted with water-thinned paints, with a suitable corrosion-inhibitive primer capable of preventing flash rusting and compatible with the coating specified for the adjacent areas.

3.4.1 Additional Requirements for Preparation of Surfaces With Existing Coatings

Before application of coatings, perform the following on surfaces covered by soundly-adhered coatings, defined as those which cannot be removed with a putty knife:

a. Test existing finishes for lead before sanding, scraping, or removing. If lead is present, refer to paragraph Toxic Materials.

b. Wipe previously painted surfaces to receive solvent-based coatings, except stucco and similarly rough surfaces clean with a clean, dry cloth saturated with mineral spirits, ASTM D235. Allow surface to dry. Wipe immediately preceding the application of the first coat of any coating, unless specified otherwise.

c. Sand existing glossy surfaces to be painted to reduce gloss. Brush, and wipe clean with a damp cloth to remove dust.

d. The requirements specified are minimum. Comply also with the

application instructions of the paint manufacturer.

e. Thoroughly clean previously painted surfaces specified to be repainted of all grease, dirt, dust or other foreign matter.

f. Remove blistering, cracking, flaking and peeling or otherwise deteriorated coatings.

g. Remove chalk so that when tested in accordance with ASTM D4214, the chalk resistance rating is no less than 8.

h. Roughen slick surfaces. Repair damaged areas such as, but not limited to, nail holes, cracks, chips, and spalls with suitable material to match adjacent undamaged areas.

i. Feather and sand smooth edges of chipped paint.

j. Clean rusty metal surfaces as per SSPC requirements. Use solvent, mechanical, or chemical cleaning methods to provide surfaces suitable for painting.

k. Provide new, proposed coatings that are compatible with existing coatings.

3.4.2 Existing Coated Surfaces with Minor Defects

Sand, spackle, and treat minor defects to render them smooth. Minor defects are defined as scratches, nicks, cracks, gouges, spalls, alligatoring, chalking, and irregularities due to partial peeling of previous coatings. Remove chalking by sanding so that when tested in accordance with ASTM D4214, the chalk rating is not less than 8.

3.4.3 Removal of Existing Coatings

Remove existing coatings from the following surfaces:

a. Surfaces containing large areas of minor defects;

b. Surfaces containing more than 20 percent peeling area; and

c. Surfaces designated by the Contracting Officer, such as surfaces where rust shows through existing coatings.

3.4.4 Substrate Repair

a. Repair substrate surface damaged during coating removal;

b. Sand edges of adjacent soundly-adhered existing coatings so they are tapered as smooth as practical to areas involved with coating removal; and

c. Clean and prime the substrate as specified.

3.5 PREPARATION OF METAL SURFACES

3.5.1 Existing and New Ferrous Surfaces

a. Ferrous Surfaces including Shop-coated Surfaces and Small Areas That Contain Rust, Mill Scale and Other Foreign Substances: Solvent clean or

detergent wash in accordance with SSPC SP 1 to remove oil and grease. Where shop coat is missing or damaged, clean according to SSPC SP 2, SSPC SP 3, SSPC SP 6/NACE No.3, or SSPC SP 10/NACE No. 2. Brush-off blast remaining surface in accordance with SSPC 7/NACE No.4; Water jetting to SSPC SP 12/NACE No.5 WJ-4 may be used to remove loose coating and other loose materials. Use inhibitor as recommended by coating manufacturer to prevent premature rusting. Protect shop-coated ferrous surfaces from corrosion by treating and touching up corroded areas immediately upon detection.

b. Surfaces With More Than 20 Percent Rust, Mill Scale, and Other Foreign Substances: Clean entire surface in accordance with SSPC SP 6/NACE No.3 /SSPC SP 12/NACE No.5 WJ-3SSPC SP 10/NACE No. 2/SSPC SP 12/NACE No.5 WJ-2.

c. Metal Floor Surfaces to Receive Nonslip Coating: Clean in accordance with SSPC SP 10/NACE No. 2SSPC SP 12/NACE No.5 WJ-2.

3.5.2 Final Ferrous Surface Condition:

For tool cleaned surfaces, the requirements are stated in SSPC SP 2 and SSPC SP 3. Use as a visual reference, photographs in SSPC VIS 3 for the appearance of cleaned surfaces.

For abrasive blast cleaned surfaces, the requirements are stated in SSPC 7/NACE No.4, SSPC SP 6/NACE No.3, and SSPC SP 10/NACE No. 2. Use as a visual reference, photographs in SSPC VIS 1 for the appearance of cleaned surfaces.

For waterjet cleaned surfaces, the requirements are stated in SSPC SP 12/NACE No.5. Use as a visual reference, photographs in SSPC VIS 4/NACE VIS 7 for the appearance of cleaned surfaces.

3.5.3 Galvanized Surfaces

a. New or Existing Galvanized Surfaces With Only Dirt and Zinc Oxidation Products: Clean with solvent, steam, or non-alkaline detergent solution in accordance with SSPC SP 1. Completely remove coating by brush-off abrasive blast if the galvanized metal has been passivated or stabilized. Do not "passivate" or "stabilize" new galvanized steel to be coated. If the absence of hexavalent stain inhibitors is not documented, test as described in ASTM D6386, Appendix X2, and remove by one of the methods described therein.

b. Galvanized with Slight Coating Deterioration or with Little or No Rusting: Water jetting to SSPC SP 12/NACE No.5 WJ3 to remove loose coating from surfaces with less than 20 percent coating deterioration and no blistering, peeling, or cracking. Use inhibitor as recommended by the coating manufacturer to prevent rusting.

c. Galvanized With Severe Deteriorated Coating or Severe Rusting: Water jet to SSPC SP 12/NACE No.5 WJ3 degree of cleanliness. Spot abrasive blast rusted areas as described for steel in SSPC SP 6/NACE No.3, and waterjet to SSPC SP 12/NACE No.5, WJ3 to remove existing coating.

3.5.4 Non-Ferrous Metallic Surfaces

Aluminum and aluminum-alloy, lead, copper, and other nonferrous metal surfaces.

Surface Cleaning: Solvent clean in accordance with SSPC SP 1 and wash with mild non-alkaline detergent to remove dirt and water soluble contaminants.

3.5.5 Terne-Coated Metal Surfaces

Solvent clean surfaces with mineral spirits, ASTM D235. Wipe dry with clean, dry cloths.

3.5.6 Existing Surfaces with a Bituminous or Mastic-Type Coating

Remove chalk, mildew, and other loose material by washing with a solution of 1/2 cup trisodium phosphate, 1/4 cup household detergent, one quart 5 percent sodium hypochlorite solution and 3 quarts of warm water.

3.6 PREPARATION OF CONCRETE AND CEMENTITIOUS SURFACE

3.6.1 Concrete and Masonry

a. Curing: Allow concrete, stucco and masonry surfaces to cure at least 30 days before painting, and concrete slab on grade to cure at least 90 days before painting.

b. Surface Cleaning: Remove the following deleterious substances.

(1) Dirt, Chalking, Grease, and Oil: Wash new and existing uncoated surfaces with a solution composed of 1/2 cup trisodium phosphate, 1/4 cup household detergent, and 4 quarts of warm water. Then rinse thoroughly with fresh water. Wash existing coated surfaces with a suitable detergent and rinse thoroughly. For large areas, water blasting may be used.

(2) Fungus and Mold: Wash new, existing coated, and existing uncoated surfaces with a solution composed of 1/2 cup trisodium phosphate, 1/4 cup household detergent, 1 quart 5 percent sodium hypochlorite solution and 3 quarts of warm water. Rinse thoroughly with fresh water.

(3) Paint and Loose Particles: Remove by wire brushing.

(4) Efflorescence: Remove by scraping or wire brushing followed by washing with a 5 to 10 percent by weight aqueous solution of hydrochloric (muriatic) acid. Do not allow acid to remain on the surface for more than five minutes before rinsing with fresh water. Do not acid clean more than 4 square feet of surface, per workman, at one time.

c. Cosmetic Repair of Minor Defects: Repair or fill mortar joints and minor defects, including but not limited to spalls, in accordance with manufacturer's recommendations and prior to coating application.

d. Allowable Moisture Content: Latex coatings may be applied to damp surfaces, but not to surfaces with droplets of water. Do not apply epoxies to damp vertical surfaces as determined by ASTM D4263 or horizontal surfaces that exceed 3 lbs of moisture per 1000 square feet in 24 hours as determined by ASTM F1869. In all cases follow manufacturers recommendations. Allow surfaces to cure a minimum of 30 days before painting.

3.6.2 Gypsum Board, Plaster, and Stucco

a. Surface Cleaning: Verify that plaster and stucco surfaces are free from loose matter and that gypsum board is dry. Remove loose dirt and dust by brushing with a soft brush, rubbing with a dry cloth, or vacuum-cleaning prior to application of the first coat material. A damp cloth or sponge may be used if paint will be water-based.

b. Repair of Minor Defects: Prior to painting, repair joints, cracks, holes, surface irregularities, and other minor defects with patching plaster or spackling compound and sand smooth.

c. Allowable Moisture Content: Latex coatings may be applied to damp surfaces, but not surfaces with droplets of water. Do not apply epoxies to damp surfaces as determined by ASTM D4263. Verify that new plaster to be coated has a maximum moisture content of 8 percent, when measured in accordance with ASTM D4444, Method A, unless otherwise authorized. In addition to moisture content requirements, allow new plaster to age a minimum of 30 days before preparation for painting.

3.7 REPARATION OF WOOD AND PLYWOOD SURFACES

3.7.1 New , Existing Uncoated, and Existing Coated Plywood and Wood Surfaces, Except Floors:

a. Clean wood surfaces of foreign matter.

Surface Cleaning: Verify that surfaces are free from dust and other deleterious substances and in a condition approved by the Contracting Officer prior to receiving paint or other finish. Do not use water to clean uncoated wood. Scrape to remove loose coatings. Lightly sand to roughen the entire area of previously enamel-coated wood surfaces.

b. Removal of Fungus and Mold: Wash existing coated surfaces with a solution composed of 3 ounces (2/3 cup) trisodium phosphate, 1 ounce (1/3 cup) household detergent, 1 quart 5 percent sodium hypochlorite solution and 3 quarts of warm water. Rinse thoroughly with fresh water.

c. Do not exceed 12 percent moisture content of the wood as measured by a moisture meter in accordance with ASTM D4444, Method A, unless otherwise authorized.

d. Prime or touch up wood surfaces adjacent to surfaces to receive water-thinned paints before applying water-thinned paints.

e. Cracks and Nailheads: Set and putty stop nailheads and putty cracks after the prime coat has dried.

f. Cosmetic Repair of Minor Defects:

(1) Knots and Resinous Wood and Fire, Smoke, Water, and Color Marker Stained Existing Coated Surface: Prior to application of coating, cover knots and stains with two or more coats of 3-pound-cut shellac varnish, plasticized with 5 ounces of castor oil per gallon. Scrape away existing coatings from knotty areas, and sand before treating. Prime before applying any putty over shellacked area.

(2) Open Joints and Other Openings: Fill with whiting putty, linseed oil putty. Sand smooth after putty has dried.

(3) Checking: Where checking of the wood is present, sand the surface, wipe and apply a coat of pigmented orange shellac. Allow to dry before paint is applied.

g. Prime Coat For New Exterior Surfaces: Prime coat wood doors, windows, frames, and trim before wood becomes dirty, warped, or weathered.

3.7.2 Water Blasting of Existing Coated Wood Surfaces:

Provide water blasting for the following surfaces: surfaces with no lead paint.

a. Sample Panel: Prior to the initial surface cleaning, water blast a representative surface designated by the Contracting Officer. Provide surface cleaning of the remaining work to match the sample panel approved by the Contracting Officer.

b. Initial Surface Cleaning: Water blast surfaces to receive paint with a high pressure spray, to remove loose paint, dirt, and other foreign or deleterious materials. Provide working pressure between 400 and 700 pounds per square inch gage (psig) at a nozzle operating rate of a minimum 20 gallons per minute (g/min.). Do not flood vents or damage windows and floors. If the pressure specified will cause damage to existing wood, advise the Contracting Officer and obtain permission to vary the pressure. Direct the wash nozzle at the surface at an angle of approximately 75 degrees with the surface and at a distance not greater than 5 feet to apply water pressure required to remove loose paint, dirt, chalking, and other foreign matter.

c. Final Surface Cleaning: After allowing the surfaces to dry for a minimum of 24 hours, remove remaining dirt, splinters, loose particles, disintegrated and loose paint, grease, oil, and other foreign matter from the surface.

3.8 APPLICATION

3.8.1 Coating Application

Comply with applicable federal, state and local laws enacted to insure compliance with Federal Clean Air Standards. Apply coating materials in accordance with SSPC PA 1. SSPC PA 1 methods are applicable to all substrates, except as modified herein.

At the time of application, paint must show no signs of deterioration. Maintain uniform suspension of pigments during application.

Unless otherwise specified or recommended by the paint manufacturer, paint may be applied by brush, roller, or spray. Use trigger operated spray nozzles for water hoses. Use rollers for applying paints and enamels of a type designed for the coating to be applied and the surface to be coated. Wear protective clothing and respirators when applying oil-based paints or using spray equipment with any paints.

Only apply paints, except water-thinned types to surfaces that are completely free of moisture as determined by sight or touch.

Thoroughly work coating materials into joints, crevices, and open spaces. Pay special attention to ensure that all edges, corners, crevices, welds,

and rivets receive a film thickness equal to that of adjacent painted surfaces.

Apply each coat of paint so that dry film is of uniform thickness and free from runs, drops, ridges, waves, pinholes or other voids, laps, brush marks, and variations in color, texture, and finish. Completely hide all blemishes.

Touch up damaged coatings before applying subsequent coats. Broom clean and clear dust from interior areas before and during the application of coating material.

a. Drying Time: Allow time between coats, as recommended by the coating manufacturer, to permit thorough drying, but not to present topcoat adhesion problems. Provide each coat in specified condition to receive next coat.

b. Primers, and Intermediate Coats: Do not allow primers or intermediate coats to dry more than 30 days, or longer than recommended by manufacturer, before applying subsequent coats. Follow manufacturer's recommendations for surface preparation if primers or intermediate coats are allowed to dry longer than recommended by manufacturers of subsequent coatings. Cover each preceding coat or surface completely by ensuring visually perceptible difference in shades of successive coats.

c. Finished Surfaces: Provide finished surfaces free from runs, drops, ridges, waves, laps, brush marks, and variations in colors.

d. Thermosetting Paints: Topcoats over thermosetting paints (epoxies and urethanes) should be applied within the overcoating window recommended by the manufacturer.

e. Floors: For nonslip surfacing on level floors, as the intermediate coat is applied, cover wet surface completely with almandite garnet, Grit No. 36, with maximum passing U.S. Standard Sieve No. 40 less than 0.5 percent. When the coating is dry, use a soft bristle broom to sweep up excess grit, which may be reused, and vacuum up remaining residue before application of the topcoat. For nonslip surfacing on ramps, provide MPI 77 with non-skid additive, applied by roller in accordance with manufacturer's instructions.

3.8.2 Mixing and Thinning of Paints

Reduce paints to proper consistency by adding fresh paint, except when thinning is mandatory to suit surface, temperature, weather conditions, application methods, or for the type of paint being used. Obtain written permission from the Contracting Officer to use thinners. Verify that the written permission includes quantities and types of thinners to use.

When thinning is allowed, thin paints immediately prior to application with not more than 1 pint of suitable thinner per gallon. The use of thinner does not relieve the Contractor from obtaining complete hiding, full film thickness, or required gloss. Thinning cannot cause the paint to exceed limits on volatile organic compounds. Do not mix paints of different manufacturers.

3.8.3 Two-Component Systems

Mix two-component systems in accordance with manufacturer's instructions. Follow recommendation by the manufacturer for any thinning of the first coat to ensure proper penetration and sealing for each type of substrate.

3.8.4 Coating Systems

a. Systems by Substrates: Apply coatings that conform to the respective specifications listed in the following Tables:

Table

Division 3. Exterior Concrete Paint Table
Division 4. Exterior Concrete Masonry Units Paint Table
Division 5. Exterior Metal, Ferrous and Non-Ferrous Paint Table
Division 6. Exterior Wood; Dressed Lumber, Paneling, Decking, Shingles Paint Table
Division 9: Exterior Stucco Paint Table
Division 10. Exterior Cloth Coverings and Bituminous Coated Surfaces Paint Table

b. Minimum Dry Film Thickness (DFT): Apply paints, primers, varnishes, enamels, undercoats, and other coatings to a minimum dry film thickness of 1.5 mil each coat unless specified otherwise in the Tables. Coating thickness where specified, refers to the minimum dry film thickness.

c. Coatings for Surfaces Not Specified Otherwise: Coat surfaces which have not been specified, the same as surfaces having similar conditions of exposure.

d. Existing Surfaces Damaged During Performance of the Work, Including New Patches In Existing Surfaces: Coat surfaces with the following:

(1) One coat of primer.

(2) One coat of undercoat or intermediate coat.

(3) One topcoat to match adjacent surfaces.

e. Existing Coated Surfaces To Be Painted: Apply coatings conforming to the respective specifications listed in the Tables herein, except that pretreatments, sealers and fillers need not be provided on surfaces where existing coatings are soundly adhered and in good condition. Do not omit undercoats or primers.

3.9 COATING SYSTEMS FOR METAL

Apply coatings of Tables in Division 5 for Exterior and Interior.

a. Apply specified ferrous metal primer on the same day that surface is cleaned, to surfaces that meet all specified surface preparation requirements at time of application.

b. Inaccessible Surfaces: Prior to erection, use one coat of specified primer on metal surfaces that will be inaccessible after erection.

c. Shop-primed Surfaces: Touch up exposed substrates and damaged coatings to protect from rusting prior to applying field primer.

d. Surface Previously Coated with Epoxy or Urethane: Apply MPI 101, 1.5 mils DFT immediately prior to application of epoxy or urethane coatings.

e. Pipes and Tubing: The semitransparent film applied to some pipes and tubing at the mill is not to be considered a shop coat. Overcoat these items with the specified ferrous-metal primer prior to application of finish coats.

f. Exposed Nails, Screws, Fasteners, and Miscellaneous Ferrous Surfaces. On surfaces to be coated with water thinned coatings, spot prime exposed nails and other ferrous metal with latex primer MPI 107.

3.10 COATING SYSTEMS FOR CONCRETE AND CEMENTITIOUS SUBSTRATES

Apply coatings of Tables in Division 3, 4 and 9 for Exterior.

3.11 COATING SYSTEMS FOR WOOD AND PLYWOOD

a. Apply coatings of Tables in Division 6 for Exterior.

b. Prior to erection, apply two coats of specified primer to treat and prime wood and plywood surfaces which will be inaccessible after erection.

c. Apply stains in accordance with manufacturer's printed instructions.

3.12 INSPECTION AND ACCEPTANCE

In addition to meeting previously specified requirements, demonstrate mobility of moving components, including swinging and sliding doors, cabinets, and windows with operable sash, for inspection by the Contracting Officer. Perform this demonstration after appropriate curing and drying times of coatings have elapsed and prior to invoicing for final payment.

3.13 WASTE MANAGEMENT

As specified in the Waste Management Plan and as follows. Do not use kerosene or any such organic solvents to clean up water based paints. Properly dispose of paints or solvents in designated containers. Close and seal partially used containers of paint to maintain quality as necessary for reuse. Store in protected, well-ventilated, fire-safe area at moderate temperature. Place materials defined as hazardous or toxic waste in designated containers. Coordinate with manufacturer for take-back program. Set aside scrap to be returned to manufacturer for recycling into new product. When such a service is not available, contact local recyclers to reclaim the materials. Set aside extra paint for future color matches or reuse by the Government. Where local options exist for leftover paint recycling, collect all waste paint by type and provide for delivery to recycling or collection facility for reuse by local organizations.

3.14 PAINT TABLES

All DFT's are minimum values. Acceptable products are listed in the MPI Green Approved Products List, available at http://www.specifygreen.com/APL/ProductIdxByMPInum.asp.

3.14.1 Exterior Paint Tables

DIVISION 3: EXTERIOR CONCRETE PAINT TABLE

A. New and uncoated existing and Existing, previously painted concrete; vertical surfaces, including undersides of balconies and soffits but excluding tops of slabs:

1. Latex
New; MPI EXT 3.1A-G2 (Flat) / Existing; MPI REX 3.1A-G2 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 10	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 3.5 mils

New; MPI EXT 3.1A-G5 (Semigloss) / Existing; MPI EXT 3.1A-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 11	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 3.5 mils

New; MPI EXT 3.1A-G6 (Gloss) / Existing; MPI REX 3.1A-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 119	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 3.5 mils

Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces.

B. New and uncoated existing and Existing, previously painted concrete, textured system; vertical surfaces, including undersides of balconies and soffits but excluding tops of slabs:

1. Latex Aggregate
New; MPI EXT 3.1B-G2 (Flat) / Existing; MPI REX 3.1B-G2 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 42	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: Per Manufacturer

New; MPI EXT 3.1B-G5 (Semigloss) / Existing; MPI REX 3.1B-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 42	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: Per Manufacturer

New; MPI EXT 3.1B-G6 (Gloss) / Existing; MPI REX 3.1B-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 42	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: Per Manufacturer

Texture - Fine Medium Coarse . Surface preparation and number of coats in accordance with manufacturer's instructions. Topcoat: Coating to match adjacent surfaces.

C. New and uncoated existing and Existing, previously painted concrete, elastomeric System; vertical surfaces, including undersides of balconies

DIVISION 3: EXTERIOR CONCRETE PAINT TABLE
and soffits but excluding tops of slabs:

1. Elastomeric Coating
New; MPI EXT 3.1F / Existing; MPI REX 3.1F

Primer:	Intermediate:	Topcoat:
Per Manufacturer	MPI 113	MPI 113

System DFT: 16 mils

Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces. Surface preparation and number of coats in accordance with manufacturer's instructions.

NOTE: Apply sufficient coats of MPI 113 to achieve a minimum dry film thickness of 16 mils.

D. New and uncoated existing and Existing, previously painted concrete: walls and bottom of swimming pools.

1. Chlorinated Rubber
New; / Existing;

Primer:	Intermediate:	Topcoat:
SSPC Paint 18	SSPC Paint 18	SSPC Paint 18

System DFT: Per Manufacturer

NOTE: Thin first coat (primer) with 1 part of approved thinner to 4 parts of paint by volume.

E. New and Existing Cementitious composition board:

1. Latex
New; MPI EXT 3.3A-G1 (Flat) /Existing; MPI REX 3.3A-G1 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 10	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 4.5 mils

New; MPI EXT 3.3A-G5 (Semigloss) / Existing; MPI REX 3.3A-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 11	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 4.5 mils

New; MPI EXT 3.3A-G6 (Gloss) / Existing; MPI REX 3.3A-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 119	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 4.5 mils

Topcoat: Coating to match adjacent surfaces.

DIVISION 4: EXTERIOR CONCRETE MASONRY UNITS PAINT TABLE

A. New and Existing concrete masonry on uncoated surface:

1. Latex
New; MPI EXT 4.2A-G1 (Flat) / Existing; MPI REX 4.2A-G1 (Flat)

DIVISION 4: EXTERIOR CONCRETE MASONRY UNITS PAINT TABLE

Block Filler:	Primer:	Intermediate:	Topcoat:
MPI 4	N/A	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 11 mils

New; MPI EXT 4.2A-G5 (Semigloss) / Existing; MPI REX 4.2A-G5 (Semigloss)

Block Filler:	Primer:	Intermediate:	Topcoat:
MPI 4	N/A	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 11 mils

New; MPI EXT 4.2A-G6 (Gloss) / Existing; MPI REX 4.2A-G6 (Gloss)

Block Filler:	Primer:	Intermediate:	Topcoat:
MPI 4	N/A	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 11 mils

Topcoat: Coating to match adjacent surfaces.

B. New and Existing concrete masonry, textured system; on uncoated surface:

1. Latex Aggregate

New; MPI EXT 4.2B-G1 (Flat) / Existing; MPI REX 4.2B-G1 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 42	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: Per Manufacturer

New; MPI EXT 4.2B-G5 (Semigloss) / Existing; MPI REX 4.2B-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 42	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: Per Manufacturer

New; MPI EXT 4.2B-G6 (Gloss) / Existing; MPI REX 4.2B-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 42	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: Per Manufacturer

Texture - Fine Medium Coarse . Surface preparation and number of coats in accordance with manufacturer's instructions. Topcoat: Coating to match adjacent surfaces.

C. New and Existing concrete masonry, elastomeric system; on uncoated surface:

1. Elastomeric Coating

New; MPI EXT 4.2D / Existing; MPI REX 4.2D

Primer:	Intermediate:	Topcoat:
Per Manufacturer	MPI 113	MPI 113

System DFT: 16 mils

Primer as recommended by manufacturer. Topcoat: Coating to match adjacent surfaces. Surface preparation and number of coats in accordance with manufacturer's instructions.

DIVISION 4: EXTERIOR CONCRETE MASONRY UNITS PAINT TABLE
NOTE: Apply sufficient coats of MPI 113 to achieve a minimum dry film thickness of 16 mils.

DIVISION 5: EXTERIOR METAL, FERROUS AND NON-FERROUS PAINT TABLE

STEEL / FERROUS SURFACES

A. New Steel that has been hand or power tool cleaned to SSPC SP 2 or SSPC SP 3

1. Alkyd
New; MPI EXT 5.1Q-G5 (Semigloss) Existing; MPI REX 5.1D-G5

Primer:	Intermediate:	Topcoat:
MPI 23	MPI 94	MPI 94

System DFT: 5.25 mils

New; MPI EXT 5.1Q-G6 (Gloss) / Existing; MPI REX 5.1D-G6

Primer:	Intermediate:	Topcoat:
MPI 23	MPI 9	MPI 9

System DFT: 5.25 mils

B. New Steel that has been blast-cleaned to SSPC SP 6/NACE No.3:

2. Alkyd
New; MPI EXT 5.1D-G5 (Semigloss) / Existing; MPI REX 5.1D-G5

Primer:	Intermediate:	Topcoat:
MPI 79	MPI 94	MPI 94

System DFT: 5.25 mils

New; MPI EXT 5.1D-G6 (Gloss) / Existing; MPI REX 5.1D-G6

Primer:	Intermediate:	Topcoat:
MPI 79	MPI 9	MPI 9

System DFT: 5.25 mils

C. Existing steel that has been spot-blasted to SSPC SP 6/NACE No.3:

1. Surface previously coated with alkyd or latex:

Waterborne Light Industrial Coating
MPI REX 5.1C-G5 (Semigloss)

Spot Primer:	Intermediate:	Topcoat:
MPI 79	MPI 163	MPI 163

System DFT: 5 mils

MPI REX 5.1C-G6 (Gloss)

Spot Primer:	Intermediate:	Topcoat:
MPI 79	MPI 164	MPI 164

System DFT: 5 mils

2. Surface previously coated with epoxy:

Waterborne Light Industrial
a. MPI REX 5.1L-G5 (Semigloss)

Spot Primer:	Intermediate:	Topcoat:
MPI 101	MPI 163	MPI 163

System DFT: 5 mils

STEEL / FERROUS SURFACES

MPI REX 5.1L-G6 (Gloss)
Spot Primer: Intermediate: Topcoat:
MPI 101 MPI 164 MPI 164
System DFT: 5 mils

Pigmented Polyurethane
b. MPI REX 5.1H-G6 (Gloss)
Spot Primer: Intermediate: Topcoat:
MPI 101 MPI 108 MPI 72
System DFT: 8.5 mils

D. New and existing steel blast cleaned to SSPC SP 10/NACE No. 2:

1.

2. Pigmented Polyurethane
MPI EXT 5.1J-G6 (Gloss)
Primer: Intermediate: Topcoat:
MPI 101 MPI 108 MPI 72
System DFT: 8.5 mils

E. Metal floors (non-shop-primed surfaces or non-slip deck surfaces) with non-skid additive (NSA), load at manufacturer's recommendations.:

1. Alkyd Floor Enamel
MPI EXT 5.1S-G6 (Gloss)
Primer: Intermediate: Topcoat:
MPI 79 MPI 27 MPI 27 (plus NSA)
System DFT: 5.25 mils

EXTERIOR GALVANIZED SURFACES

F. New Galvanized surfaces:

1. Cementitious primer / Latex
MPI EXT 5.3A-G1 (Flat)
Primer: Intermediate: Topcoat:
MPI 26 MPI 10 MPI 10
System DFT: 4.5 mils

MPI EXT 5.3A-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 26 MPI 11 MPI 11
System DFT: 4.5 mils

MPI EXT 5.3A-G6 (Gloss)
Primer: Intermediate: Topcoat:
MPI 26 MPI 119 MPI 119
System DFT: 4.5 mils

2. Waterborne Primer / Latex
MPI EXT 5.3H-G1 (Flat)
Primer: Intermediate: Topcoat:
MPI 134 MPI 10 MPI 10

EXTERIOR GALVANIZED SURFACES
System DFT: 4.5 mils

MPI EXT 5.3H-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 134	MPI 11	MPI 11

System DFT: 4.5 mils

MPI EXT 5.3H-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 134	MPI 119	MPI 119

System DFT: 4.5 mils

3. Waterborne Primer / Waterborne Light Industrial Coating
MPI EXT 5.3J-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 134	MPI 163	MPI 163

System DFT: 4.5 mils

MPI EXT 5.3J-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 134	MPI 164	MPI 164

System DFT: 4.5 mils

4. Epoxy Primer / Waterborne Light Industrial Coating
MPI EXT 5.3K-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 101	MPI 163	MPI 163

System DFT: 5 mils

MPI EXT 5.3K-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 101	MPI 164	MPI 164

System DFT: 5 mils

5. Pigmented Polyurethane
MPI EXT 5.3L-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 101	N/A	MPI 72

System DFT: 5 mils

G. Galvanized surfaces with slight coating deterioration; little or no rusting:

1. Waterborne Light Industrial Coating
MPI REX 5.3J-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 134	N/A	MPI 163

System DFT: 4.5 mils

2. Pigmented Polyurethane
MPI REX 5.3D-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 101	N/A	MPI 72

System DFT: 5 mils

H. Galvanized surfaces with severely deteriorated coating or rusting:

1. Waterborne Light Industrial Coating

Paint and Repair Requirements

EXTERIOR GALVANIZED SURFACES

MPI REX 5.3L-G5(Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 101	MPI 108	MPI 163

System DFT: 8.5 mils

MPI REX 5.3L-G6(Gloss)

Primer:	Intermediate:	Topcoat:
MPI 101	MPI 108	MPI 164

System DFT: 8.5 mils

2. Pigmented Polyurethane

MPI REX 5.3K-G6(Gloss)

Primer:	Intermediate:	Topcoat:
MPI 101	MPI 108	MPI 72

System DFT: 5 mils

EXTERIOR SURFACES, OTHER METALS (NON-FERROUS)

I. Aluminum, aluminum alloy and other miscellaneous non-ferrous metal items not otherwise specified except hot metal surfaces, roof surfaces, and new prefinished equipment. Match surrounding finish:

1. Alkyd

MPI EXT 5.4F-G1 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 95	MPI 8	MPI 8

System DFT: 5 mils

MPI EXT 5.4F-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 95	MPI 94	MPI 94

System DFT: 5 mils

MPI EXT 5.4F-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 95	MPI 9	MPI 9

System DFT: 5 mils

2. Waterborne Light Industrial Coating

MPI EXT 5.4G-G3(Eggshell)

Primer:	Intermediate:	Topcoat:
MPI 95	MPI 161	MPI 161

System DFT: 5 mils

MPI EXT 5.4G-G5(Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 95	MPI 163	MPI 163

System DFT: 5 mils

MPI EXT 5.4G-G6(Gloss)

Primer:	Intermediate:	Topcoat:
MPI 95	MPI 164	MPI 164

System DFT: 5 mils

I. Existing roof surfaces previously coated:

1. Aluminum Pigmented Asphalt Roof Coating

ASTM D2824/D2824M: Sufficient coats to provide not less than 8 mils

EXTERIOR SURFACES, OTHER METALS (NON-FERROUS)
of finished coating system (without asbestos fibers).

2. Aluminum Paint
MPI REX 10.2D
Primer: Intermediate: Topcoat:
MPI 107 MPI 1 MPI 1
System DFT: 3.5 mils

J. Surfaces adjacent to painted surfaces; Mechanical, Electrical, Fire extinguishing sprinkler systems including valves, conduit, hangers, supports, and miscellaneous metal items not otherwise specified except floors, hot metal surfaces, and new prefinished equipment. Match surrounding finish:

1. Alkyd
MPI EXT 5.1D-G1 (Flat)
Primer: Intermediate: Topcoat:
MPI 79 MPI 8 MPI 8
System DFT: 5.25 mils

MPI EXT 5.1D-G5 (Semigloss)
Primer: Intermediate: Topcoat:
MPI 79 MPI 94 MPI 94
System DFT: 5.25 mils

MPI EXT 5.1D-G6 (Gloss)
Primer: Intermediate: Topcoat:
MPI 79 MPI 9 MPI 9
System DFT: 5.25 mils

2. Waterborne Light Industrial Coating
MPI EXT 5.1C-G3(Eggshell)
Primer: Intermediate: Topcoat:
MPI 79 MPI 161 MPI 161
System DFT: 5 mils

MPI EXT 5.1C-G5(Semigloss)
Primer: Intermediate: Topcoat:
MPI 79 MPI 163 MPI 163
System DFT: 5 mils

MPI EXT 5.1C-G6(Gloss)
Primer: Intermediate: Topcoat:
MPI 79 MPI 164 MPI 164
System DFT: 5 mils

K. Hot metal surfaces including smokestacks subject to temperatures up to 400 degrees F:

1. Heat Resistant Enamel
MPI EXT 5.2A
Primer: Intermediate: Topcoat:
MPI 21 Surface preparation and number of coats per manufacturer's instructions.
System DFT: Per Manufacturer

L. Ferrous metal subject to high temperature, up to 750 degrees F:

EXTERIOR SURFACES, OTHER METALS (NON-FERROUS)

1. Inorganic Zinc Rich Coating
   MPI EXT 5.2C
   Primer: Intermediate: Topcoat:
   MPI 19 Surface preparation and number of coats per manufacturer's instructions.
   System DFT: Per Manufacturer

2. Heat Resistant Aluminum Enamel
   MPI EXT 5.2B (Aluminum Finish)
   Primer: Intermediate: Topcoat:
   MPI 2 Surface preparation and number of coats per manufacturer's instructions.
   System DFT: Per Manufacturer

M. New surfaces and Existing surfaces made bare cleaning to SSPC SP 10/NACE No. 2 subject to temperatures up to 593 degrees C (1100 degrees F):

1. Heat Resistant Coating
   MPI EXT 5.2D
   Primer: Intermediate: Topcoat:
   MPI 22 Surface preparation and number of coats per manufacturer's instructions.
   System DFT: Per Manufacturer

DIVISION 6: EXTERIOR WOOD; DRESSED LUMBER, PANELING, DECKING, SHINGLES PAINT TABLE

A. New and Existing, uncoated Dressed lumber, Wood and plywood, trim, including top, bottom and edges of doors not otherwise specified:

1. Alkyd
   MPI EXT 6.3B-G5 (Semigloss)
   Primer: Intermediate: Topcoat:
   MPI 7 MPI 94 MPI 94
   System DFT: 5 mils

   MPI EXT 6.3B-G6 (Gloss)
   Primer: Intermediate: Topcoat:
   MPI 7 MPI 9 MPI 9
   System DFT: 5 mils

2. Latex
   MPI EXT 6.3A-G1 (Flat)
   Primer: Intermediate: Topcoat:
   MPI 7 Sherwin Williams Duration or Equal Sherwin Williams Duration or Equal
   System DFT: 5 mils

   MPI EXT 6.3A-G5 (Semigloss)
   Primer: Intermediate: Topcoat:
   MPI 7 Sherwin Williams Duration or Equal Sherwin Williams Duration or Equal
   System DFT: 5 mils

   MPI EXT 6.3A-G6 (Gloss)
   Primer: Intermediate: Topcoat:

DIVISION 6: EXTERIOR WOOD; DRESSED LUMBER, PANELING, DECKING, SHINGLES PAINT TABLE

MPI 7	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 5 mils

3. Waterborne Solid Color Stain
   MPI EXT 6.3K

Primer:	Intermediate:	Topcoat:
MPI 7	MPI 16	MPI 16

System DFT: 4.25 mils

B. Existing, dressed lumber, Wood and plywood, trim, including top, bottom and edges of doors previously coated with an alkyd / oil based finish coat not otherwise specified:

1. Alkyd
   MPI REX 6.3B-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 5	MPI 94	MPI 94

System DFT: 5 mils

MPI REX 6.3B-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 5	MPI 9	MPI 9

System DFT: 5 mils

2. Latex
   MPI REX 6.3A-G1 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 5	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 5 mils

MPI REX 6.3A-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 5	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 5 mils

MPI REX 6.3A-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 5	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 5 mils

C. Existing, dressed lumber, Wood and plywood, trim, including top, bottom and edges of doors previously coated with a latex / waterborne finish coat not otherwise specified:

1. Latex
   MPI REX 6.3L-G1 (Flat)

Spot Primer:	Intermediate:	Topcoat:
MPI 6	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 4.5 mils

MPI REX 6.3L-G5 (Semigloss)

Spot Primer:	Intermediate:	Topcoat:

DIVISION 6: EXTERIOR WOOD; DRESSED LUMBER, PANELING, DECKING, SHINGLES PAINT TABLE

MPI 6	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal
System DFT: 4.5 mils		

MPI REX 6.3L-G6 (Gloss)

Spot Primer:	Intermediate:	Topcoat:
MPI 6	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal
System DFT: 4.5 mils		

2. Waterborne Solid Color Stain

MPI REX 6.3K (Stain)

Spot Primer:	Intermediate:	Topcoat:
MPI 6	MPI 16	MPI 16
System DFT: 4 mils		

D. New, Uncoated wood siding:

1. Semi-Transparent Stain

MPI EXT 6.3D

Spot Primer:	Intermediate:	Topcoat:
N/A	MPI 13	MPI 13
System DFT: N/A		

E. Existing, previously stained wood siding:

1. Latex

MPI REX 6.2K-G1 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 5	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal
System DFT: 4.5 mils		

MPI REX 6.2K-G5 (Semigloss)

Primer:	Intermediate:	Topcoat:
MPI 5	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal
System DFT: 4.5 mils		

F. Existing Uncoated or previously semitransparent stained wood siding:

1. Semi-Transparent Stain

MPI REX 6.3D

Spot Primer:	Intermediate:	Topcoat:
N/A	MPI 13	MPI 13
System DFT: Per Manufacturer		

G. Wood: Steps, platforms, floors of open porches, and with non-skid additive (NSA), load at manufacturer's recommendations. :

1. Latex Floor Paint

MPI EXT 6.5A-G2 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 5	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal
System DFT: 4.5 mils		

DIVISION 6: EXTERIOR WOOD; DRESSED LUMBER, PANELING, DECKING, SHINGLES PAINT TABLE

MPI EXT 6.5A-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 5	Sherwin Williams Duration or Equal	Sherwin Williams Duration or Equal

System DFT: 4.5 mils

2. Alkyd Floor Paint

MPI EXT 6.5B-G2 (Flat)

Primer:	Intermediate:	Topcoat:
MPI 59	MPI 59	MPI 59

System DFT: 5 mils

MPI EXT 6.5B-G6 (Gloss)

Primer:	Intermediate:	Topcoat:
MPI 27	MPI 27	MPI 27

System DFT: 5 mils

-- End of Section --