PIT DEVELOPMENT PLAN NOTES:

1. LIMITS OF EXCAVATION SHALL BE FLAGGED ON-THE-GROUND BY THE CONTRACTING OFFICER (C.O.), IN ADVANCE OF ALL OPERATIONS.
2. STOCKPILE AREA SHALL BE APPROVED IN WRITING BY THE CONTRACTING OFFICER PRIOR TO USE.
3. ALL SLOPES SHALL BE LEFT NO STEEPER THAN 1:1 UPON COMPLETION.
4. CLEARING LIMITS SHOWN ON THE PIT DEVELOPMENT PLAN ARE APPROXIMATE AND WILL BE SPECIFIED ON-THE-GROUND BY THE CONTRACTING OFFICER.
5. THE TOP THREE (3) FEET OF SOILS (OVERBURDEN) WILL BE REMOVED AND STOCKPILED PRIOR TO CRUSHING OPERATIONS. UPON COMPLETION OF CRUSHING OPERATIONS, OVERBURDEN WILL BE PLACED EVENLY ACROSS ALL DISTURBED AREAS. ALL DISTURBED AREAS SHALL BE SEEDED. SEEDING SHALL B E DONE IN ACCORDANCE WITH FSSS SECTION 625 TURF ESTABLISHMENT.
6. PIT SHALL BE SLOPED TO DRAIN BETWEEN TWO (2) AND FOUR (4) PERCENT FROM HIGH POINT TO LOW POINT BASED ON EXISTING ELEVATIONS ON-THE-GROUND AND AWAY FROM STOCKPILE.

ITEM NO.	DESCRIPTION	PAY UNIT	EST. QTY.
15101	MOBILIZATION. INCLUDES OBTAINING INSURANCE AND BONDS	LPSM	1.00
15301 A	CONTRACTOR QUALITY CONTROL. STATE CERTIFIED BELT SCALE CALIBRATION. INITIAL VERIFICATION	LPSM	1.00
15301 B	CONTRACTOR QUALITY CONTROL. STATE CERTIFIED BELT SCALE CALIBRATION. SUBSEQUENT VERIFICATIONS	EACH	12.00
15401	CONTRACTOR SAMPLING AND TESTING. AASHTO T27 AND T11 AND T90 = EVERY 1000 TONS	EACH	29.00
31401 A	STOCKPILED AGGREGATES, GRADING DESIGNATION = A (2.5 INCH MINUS). REFER TO FP-24 TABLE 703-1	TON	5000.00
31401 B	STOCKPILED AGGREGATES, GRADING DESIGNATION = F (1.5 INCH MINUS). REFER TO FOREST SERVICE SUPPLEMENTAL SPECIFICATIONS (FSSS) TABLE 703-1	TON	25000.00
62301	GENERAL LABOR. SPECIALIZED LABOR. SURVEY SERVICES. UAV (DRONE) SURVEYS	EACH	9.00

United States Department of Agriculture
Forest Service

R02
ROCKY MOUNTAIN REGION

PROJECT NAME

ANDERSON GRAVEL PIT ROCK CRUSHING

GRAND MESA, UNCOMPAHGRE, AND GUNNISON NATIONAL FORESTS

GRAND VALLEY RANGER DISTRICT

DRAWING TITLE

PIT DEVELOPMENT PLAN

DATE
05/01/2026

ARCHIVE NO.
R020402

DESIGNER
C. PHELPS

DRAWN
C. PHELPS

CHECKED
D. MARAH

PROJECT NO.

DWG SHEET NO.
C-01

SHEET **02** OF **02**

5/1/26 10:15 CPHELPS C:\USERS\CPHELPS\DOCUMENTS\2026 GRAVEL CRUSHING OPERATIONS\ANDERSON GRAVEL\2026\DRAWINGS\02 ANDERSON GRAVEL PIT ROCK CRUSHING PIT DEVELOPMENT PLAN.DWG;