Revised AHU AC-21 Schedule_ADDENDUM#1.

AHU AC-21 SCHEDULE

Tag	Location .	Fan Cfm	PRESSURE IN. W.G.	PRESSURE IN, WG,	MOTOR		FAN			COOLING COIL								HEATING COIL										PRE-FILTERS	BASED ON	REMARKS
			Ext, S.P.	Total S.P.	BHP/HP	Volts/Ph/Hz	Diam In	RPM	Type	Face Area.	GPM	EAT DB/WB	LAT DB/WB	SC MBH	TC MBH	No. of Rows/fpi	EWT °F	LWT °F	Face Area Sq. Ft.	EWT °F	LWT °F	No. of Rows/fpi	EAT °F	LAT °F	Capacity MBH	GPM	AIR FRICT. INCH WG	WTR FRICT. FT. WG			
AC-21	Roof	28,740	3.5	6.47		208/3ϕ/60			Plug Fan		444	95/75	53.5/53.5	1375	2190	8/11	40	55		180	160	8/11	-10	88.1	3248	325			PF-1 = MERV 7. PF-2 = MERV 13.	CARRIER 39M OUTDOOR AHU TEMTROL PF SERIES AHU YORK CUSTOM-MADE AHU	30% GLYCOL