Questions and Answers:

RFQ: 140A1626QD002

Funding:

Questions 1: FAR 52.232-18 Availability of Funds is sited in the RFP. Are funds available for this project?

Answer: Funds are available for this requirement.

Question 2: Bonds:

- The RFP does not state the requirement for any bid bonds or payment/performance bonds.
- Are any bid, payment or performance bonds required for this Solicitation?

Answer: This will be Firm-Fixed-Price order.

Question 3: What specific problems are you trying to solve?, is this simply a Tech refresh or bringing up to today's CYBER code.

Answer: This is a technical refresh of the system.

Question 4: Why is the current system failing you?

Answer: the current system is **not** experiencing a failure. This initiative represents a routine technical refresh intended to modernize the existing environment. Discussion of vulnerabilities at the AIRR is not advised.

Question 5: Which components must you keep or reuse? If any?

Answer: none

Question 6: How old is your current cabling infrastructure?

Answer: unknown

Question 7: Can we mount our own cable pathways or do the existing need to be utilized?

Answer: Yes, but any wall penetrations must be in compliance with 36 CFR 1234 subpart K.

Question 8: Is the current access control system integrated with the camera system?

Answer: No.

Question 9 Where will you host the video footage? (on-premise servers, cloud, or hybrid)
Answer: On premise

Question 10: How much retention time do you require for video storage? (e.g., 30, 60, 90 days)

Answer: 30 days

Question 11: Does your existing network bandwidth support high-definition video streaming?

Answer: Yes it should.

Question 12: Is there Power over Ethernet (PoE) available at all equipment locations? or does new cable need to be pulled?

Answer: PoE availability at equipment locations is currently unknown. Vendors should assess the existing infrastructure during proposal development and plan accordingly, including any required new cabling

Question 13: Approximately how many doors and cameras are being upgraded? are you adding more cameras to the current layout?

Answer: vendors are expected to determine the appropriate quantities based on their professional assessment, site-visit observations, and their proposed technical solution.

Question 14: Are you looking for a cloud-based (VSaaS) or on-premise solution?

Answer: On prem. Cloud hositing is possible if it is Fedramp certified

Question 15: What credentials are you currently using?

Answer: Homeland Security Presidential Directive-12 (HSPD-12)

Question 16: Are there additional industry regulations or compliance standards must you meet? (e.g., HIPAA, PCI, GDPR)

Answer: No additional compliance frameworks (e.g., HIPAA, PCI, GDPR) are specifically mandated by the Government. Offerors are responsible for ensuring compliance with all applicable industry standards, federal security requirements, and best practices for physical security systems

Question 17: Are there specific local fire codes we must follow for door hardware integration?

Answer: Any for Lenexa Kansas or NFPA regulations

Question 18:What is your target timeline for project completion? Stated in the Sow.

Answer: 180 days from contract award.

Question 19: Have you allocated separate budgets for installation labor and ongoing software licensing?

Answer: No this is all inclusive.