DEPARTMENT OF THE AIR FORCE
HEADQUARTERS 72 AIR BASE WING (AFMC)
TINKER AIR FORCE BASE OKLAHOMA

28 Oct. 25

MEMORANDUM FOR AFSC/PZIOC (ATTN: Stephen Palmer)
THROUGH: 72 ABW/CENM

FROM: 72 ABW/CEED
Tepa Companies

SUBJECT: Pre-Bid RFI Responses
Project: WWYK190068, REPAIR FIRE SUPRESSION SYSTEM, B2280

Reference: Memo, 06 October 2025, Pre-Bid RFIs, WWYK190068, REPAIR FIRE SUPRESSION SYSTEM, B2280

1. This office reviewed the referenced RFIs for the subject project and provided answers below. Please forward to the contractor(s) for their use in preparing proposals.

1. Request for information: The Capsol LEDM C1D1 text sign as a basis for design will not interface with the Monaco MAPP-X control panel. Please see Email below from Monaco
Government Response: Direct interface between the LED Text Sign and the Monaco MAPP-X is not required. Using the Capsol LEDM C1D1 as a basis of design, the LED Text Signs would be controlled by the Capsol Controller. The controller can monitor up to 12 input relays from the Monaco MAPP-X panel that would be used to trigger any of the up to 12 programmed messages. The controller has a trouble monitor point that can be monitored by the Monaco MAPP-X panel. The dedicated monitor module from the Monaco MAPP-X will provide a point-to-point monitoring of the Capsol Controller.

2. Request for information. Based on NFPA 72 18.9.4.7 and accompanying table the CAPCON text signs character height is too small (1.2”)
Government Response: Due to the limited options for providing a LED Text Sign within a Classified Location, the Tinker Air Force Base Fire Protection Standards have been modified to find UFC and NFPA code compliant solutions. This includes the mounting location of the LED Text Sign at each exit. The height of the LED Text Sign can be adjusted to meet NFPA 72 Table 18.9.4.7 for the size of lettering provided by the LED Text Sign.

3. The points of contact for this project are:
    1. Bash Jimoh, Project Manager. PH: 582-4828
    2. Adam Gibson, Construction Inspector. PH: 736-5028
    3. Joshua Wheeler, CSAG Program Manager. PH: 582-4826
    4. Matthew Morris, Contracting Officer Representative (COR). PH: 736-7081

JIMOH.BASHIRU.BABATUNDE.1399499174 Digitally signed by JIMOH.BASHIRU.BABATUNDE.1399499174 Date: 2025.10.28 12:35:18 -05'00'

BASH JIMOH
Project Manager
72d Civil Engineering Directorate (Tepa)

MORRIS.MATTHEW.K.1385757456 Digitally signed by MORRIS.MATTHEW.K.1385757456 Date: 2025.11.04 14:16:51 -06'00'

MATTHEW MORRIS
ELECTRICAL ENGINEER/COR
72d Civil Engineering Directorate

2 Attachment(s):

1. WWYK190068 RFI 25A Contractor Response
2. WWYK190068_RFI_003_20251006_Redacted

cc:
Project folder