Schedule of Items - Echo Amphitheater Pavement Preservation

Item Number	Description	Method of Measurement	Pay Unit	Estimated Quantity	Unit Price	Total
	BASE (Pavement Preservation at Echo Amphitheater Recreation Site Parking Lot and Entrance)					
151-01	Mobilization	CQ	LS	-	$	$
410-05	Paved Surface Cleaning: Road Construction Sweeper/Broom, Broce 350 or equivalent (Approx. 7100 sq. yds, Parking Lot and Entrance)	CQ	LS	1	$	$
414-01	Asphalt Pavement Crack and Joint Sealing and Filling: Joint and Crack Sealant ASTM D6690 Type II (1.5" width or less approx. 6330 LF)	CQ	LS	1	$	$
414-02	Asphalt Pavement Crack and Joint Sealing and Filling: Asphalt Aggregate-Filled Mastic ASTM D8260 Type II (1.5" width of more approx. 2430 LF)	CQ	LS	1	$	$
418-01	Asphalt Concrete Pavement Patching: Pavement Patch, Type II, Replace With a Minimum of 4" Asphalt and 6" Untreated Base Course	CQ	SY	24	$	$
634-01	Permanent Pavement Markings (2 coats): Type A with Glass Beads, White, Directional Traffic Arrows	CQ	EA	4	$	$
634-02	Permanent Pavement Markings (2 coats) Type A with Glass Beads, White, Parking Stall Lines	CQ	LF	705	$	$
634-03	Permanent Pavement Markings (2 coats) Type A with Glass Beads, White, Crosswalk & Hatching	CQ	LS	1	$	$
634-04	Permanent Pavement Markings (2 coats) Type A with Glass Beads, White, Stop Bar Lines	CQ	LF	56	$	$
634-05	Permanent Pavement Markings (2 coats) Type A with Glass Beads, 3 Accessible Parking Spaces Hatching and Emblems	CQ	LS	1	$	$
634-06	Permanent Pavement Markings (2 coats): Type A with Glass Beads, White, Shoulder Stripes	CQ	LF	1240	$	$
634-07	Permanent Pavement Markings (2 coats): Type A with Glass Beads, Yellow, Double Center Line	CQ	LF	660	$	$
609-01	Curb and Gutter: Wheel stop Relocation, Accessible Parking	CQ	EA	1	$	$
633-01	Permanent Traffic Control: Remove and Dispose of 3 Accessible Parking and 1 Stop Sign, Replace 3 New Accessible Signs and Posts	CQ	LS	1	$	$
633-02	Permanent Traffic Control: Furnish and Install New Yield Sign	CQ	EA	1	$	$
	Price Either Slurry Seal (A) or Microsurfacing (B) (Only one Seal Type Shall be Included in Offer). Do Not Price Both Options A & B.					
410-01	Option A: Slurry Seal, Type II (Parking Lot and Entrance approx. 7100 sq. yds)	CQ	SY	7100	$	$
409-01	Option B: Microsurfacing, Type II (Parking Lot and Entrance approx. 7100 sq. yds)	CQ	SY	7100	$	$
					Total Base Contract:	$
					Total Base Contract Tax: NM Gross Receipts Tax 6.625%	$
					Total Base + Tax	$
	ADDITIVE OPTIONS					
609-03	Wheel stops: Along South Parking, Relocate Existing and Install on Angle	CQ	EA	10	$	$
609-04	Wheel Stops: Remove, Dispose, and Replace New Wheel Stops	CQ	EA	10	$	$
					Total Additive Options:	$
					Total Option Contract Tax: NM Gross Receipts Tax 6.625%	$
					Total Additive Options + Tax	$
					Grand Total Base + Additive Option Including Tax	$

CQ= Contract Quantity, EA= Each, LF=Linear Feet, SY=Square Yards