SCHEDULE OF ITEMS

Project:	**NFSR 307/310 ROAD AND PARKING LOT RECONSTRUCTION**					
Forest:	**Kaibab National Forest**	**Date:**				
Base Bid Line Items						
Pay Item #	Pay Item Description	Method of Measure	Estimated Quantity	Pay Unit	Unit Cost	Total
FSR 310 Roadwork - Base Bid						
15101(01)	Mobilization	LSQ	1	LS		
30315(01)	Roadway reconditioning. Cattle guard cleaning per FSSS 303.07. Culvert inlet/outlet maintenance per FP-24 303.03.	DQ	0.88	Mile		
30103(01)	Government source aggregate base, grading G, 4-inch (compacted in place) compaction method A	DQ	0.88	Mile		
63501(01)	Temporary Traffic Control for Base Bid	LSQ	1	LS		
FSR 307 Roadwork - Base Bid						
30315(02)	Roadway reconditioning. Cattle guard cleaning per FSSS 303.07. Culvert inlet/outlet maintenance per FP-24 303.03.	DQ	1.62	Mile		
30103(02)	Government source aggregate base, grading G, 4-inch (compacted in place) compaction method A	DQ	1.62	Mile		
Grandview Parking Lot - Base Bid						
30103(03)	Commercial Sourced Aggregate Gradation T, Grading, 4-inch (compacted in-place), Compaction Method A. Parking Lot Drives, Spaces and Path to Existing Toilet and Kiosk	CQ	**455**	CY		
0001(01)	Boulder Barrier	**LSQ**	**1**	**LS**		
					Base Bid Estimate Total	
Additive Bid Line Items						
FSR 307 Roadwork - Additive Item 1						
15101(02)	Mobilization	LSQ	1	LS		
30315(03)	Roadway reconditioning. Cattle guard cleaning per FSSS 303.07. Culvert inlet/outlet maintenance per FP-24 303.03.	DQ	**3.38**	Mile		
30103(04)	Government source aggregate base, grading G, 4-inch (compacted in place) compaction method A	DQ	**3.38**	Mile		
60702(01)	Clean out existing culvert per FP-14 607.02	DQ	1	Each		
63501(02)	Temporary Traffic Control for Additive Items	LSQ	1	LS		
FSR 310 Roadwork - Additive Item 2						
30315(04)	Roadway reconditioning. Cattle guard cleaning per FSSS 303.07. Culvert inlet/outlet maintenance per FP-24 303.03.	DQ	1.3	Mile		
30103(05)	Government source aggregate base, grading G, 4-inch (compacted in place) compaction method A	DQ	1.3	Mile		
					Additive Items Total	
					Base Bid + Additive Items Estimate Total	