AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE	PAGE	OF PAGES
	1	3

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. *(If applicable)*
00001	07/10/2026	1169291	

6. ISSUED BY CODE 7EAW

USDA FOREST SERVICE
PROCUREMENT OPERATIONS
CONSTRUCTION AND A-E DIVISION, WEST

7. ADMINISTERED BY *(If other than Item 6)* CODE

8. NAME AND ADDRESS OF CONTRACTOR *(No., street, county, State and ZIP Code)*

ALL OFFERORS

CODE FACILITY CODE

(x) 9A. AMENDMENT OF SOLICITATION NO. 127EAW26Q0034

x 9B. DATED *(SEE ITEM 11)* 06/16/2026

10A. MODIFICATION OF CONTRACT/ORDER NO.

10B. DATED *(SEE ITEM 13)*

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended, ☒ is not extended.
Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended , by one of the following methods: (a) By completing Items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted ; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGEMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted , such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE

A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.

B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).

C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:

D. OTHER *(Specify type of modification and authority)*

E. IMPORTANT: Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

Solicitation: 127EAW26Q0034

Project Name: 2026 Septic Replacement Big Pines Barracks

Angeles National Forest, California

The purpose of this amendment is to provide responses to Requests for Information (RFIs).

See page 2 for additional information.

Except as provided herein, all terms and conditions of the document referenced in Item 9 A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)*	
		TANYA I. TORRES	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
(Signature of person authorized to sign)		*(Signature of Contracting Officer)*	

Amendment 00001 is hereby issued to provide responses to Requests for Information. These responses are formally incorporated into the solicitation and shall be binding upon any subsequent contract award. Failure to utilize the revised documents, and to comply with the requirements contained therein, will result in a determination that the quote is non-responsive.

RFI 1: The Statement of Work references a California C-36 Plumbing Contractor license for the preparation and submission of the onsite wastewater permit application.
Our firm holds a California Class A General Engineering Contractor license as well as a C-34 Pipeline Contractor license. Could you please confirm whether a California Class A General Engineering Contractor license is acceptable for this solicitation, or if the prime contractor is specifically required to hold a C-36 Plumbing Contractor license?
Response: A C-36 Plumbing Contractor license is required for the onsite wastewater permitting and installation work. The prime contractor does not need to hold the C-36 license themselves as long as a properly licensed C-36 subcontractor is listed in the bid and performs the requested work. The prime contractor will still be required for the project's primary oversight.

RFI 2: Please clarify that the C-36 license requirement is for the contractor, either PRIME or a SUB who shall pull the Permit from the County of Los Angeles.
Response: A C-36 Plumbing Contractor license is required for the onsite wastewater permitting and installation work. The prime contractor does not need to hold the C-36 license themselves as long as a properly licensed C-36 subcontractor is listed in the bid and performs the requested work. The prime contractor will still be required for the project's primary oversight.

RFI 3: Please clarify that an A class license requirement is acceptable for the PRIME Contractor.
Response: A Class A license is acceptable for the prime contractor, but the subcontractor performing the C-36 classified work and permitting must hold a valid C-36 license and be properly listed in the bid. The prime contractor will still be required for the project's primary oversight.

RFI 4: May I submit an invoice to the Government after mobilizing to the site?
Response: Mobilizing to the site by itself does not qualify for payment. You may only invoice for work or deliverables that have been completed and accepted. The contractor may submit partial invoices (no more than one per month) or submit one final invoice following project completion.

RFI 5: The second cleanout on the outlet serves as an access point for future camera analysis of the leach lines and/or to verify water flow. No snaking is permitted. This cleanout should be a 4-inch PVC pipe with a screw-on cap and a cover installed to grade.
Response: Please maintain to the current scope of work.

RFI 6: It would be safer, more cost-effective, and faster to leave the existing tank in place and install the new one beside it. There is sufficient fall on the main sewer line to allow for this approach. The existing tank can simply be backfilled with native soil, and the inlet and outlet can be rerouted to the new tank. The primary reason for this recommendation is to maintain the stability of the mountain slope between the tank and the street. Excavating the existing tank could undermine the road, which has gained stability over time as the concrete has continued to cure and strengthen. Following this approach would prevent potential slope or road issues and result in significant cost savings both now and in the future.
Response: The primary goal of the US Forest Service is to reduce the disturbance of natural resources and footprint. Please keep to the current scope of wor*k.*

RFI 7: There is a large void approximately 25 feet on the opposite side of the tank where an asbestos-based pipe is exposed. This area should be filled with native soil to avoid removing or disturbing

the pipe. As long as the pipe remains undisturbed, it is not classified as a hazardous material. There is adequate native soil available on site to properly fill the area.
Response: Please maintain to the current scope of work.

RFI 8: Are plastic risers acceptable for use on a new 2,000-gallon septic tank that includes four manholes?
Response: No. Please maintain to the current scope of work.

RFI 9: Is there water available on site?
Response: No, the contractor is responsible for providing their own water.

RFI #10 -Please define the required dimensions and specifications for the septic tank.
Response: The dimensions are provided in the attachment titled "C04 - 2 - Statement of Work.pdf," and the specifications are detailed in the documents labeled "C04 - 8 - Specifications.pdf.

RFI #11 – Please clarify the required depth and materials for the septic tank installation.
Response: The dimensions are provided in the attachment titled "C04 - 2 - Statement of Work.pdf," and the specifications are detailed in the documents labeled "C04 - 8 - Specifications.pdf.

RFI #12 – Please confirm how many linear feet of distribution lines shall be considered, as well as their required specifications.
Response: The statement of work states the following "remove and replace approximately 40 linear feet of inlet and outlet distribution ABS piping". The dimensions are provided in the attachment titled "C04 - 2 - Statement of Work.pdf," the schedule of items are listed under the document "C04 - 3 - Schedule of Items - 127EAW26Q0034.docx", and the specifications are detailed in the documents labeled "C04 - 8 - Specifications.pdf". Please revise the documents mentioned.

RFI #13 – Please provide any available drawings, details, quantities, or required installation methods for this scope of work.
Response: The following documents were provided , 'C04 - 7 - Drawings.PDF', 'C04 - 8 - Specifications.pdf', 'C04 - 2 - Statement of Work.pdf', and C04 - 3 – 'Schedule of Items - 127EAW26Q0034.docx'. Please revise documents listed for the drawings, details, quantities, and specifications. Installation should be performed in accordance with the project documents, and the contractor must also follow the manufacturer's installation guidelines for the septic tank.