FA301626Q0073
Amendment 0002
Honeywell Vindicator IDS - Combo Synopsis/Solicitation

#	Question	Government Response
1	1.To set expectations on schedule, current lead times for Vindicator Site Commander / SAW 2 is 90-120 days. There is no replacement for this hardware in an ICD-705 compliant space. Therefore, the schedule we submit will align with Vindicator lead times.	Delivery/Installation will be 90-120 days after contract award
2	The V5 is no longer a procurable item from Honeywell Vindicator Technologies (HVT). Please confirm that the V3 and 1500 are acceptable if technical capabilities and system intent are achieved.	Yes, V3s and 1500s are acceptable.
3	Under the "SCOPE" section of the SOW, item XIII states, "Ensure each alarm device will have its own alarm point". Please confirm if this was intended to ensure discreet tampers back to HVT headend equipment or if use of multistate resistor packs is acceptable.	Request each device be identified as a point for identification, assessment and penetration patterns, when reporting to head at BDOC. Devices should have tamper alert notification.
4	Please confirm if the conduit shall be EMT or Rigid	They must be installed in a closed and sealed metal conveyance defined as a pipe, tube or the like constructed of ferrous EMT, ferrous pipe conduit or ferrous rigid sheet metal. All joinst permanently sealed completely around surfaces. continuus bond between conveyence. No set screws.
5	During the survey, no specific location was identified for the IDS/ACS and power supply enclosures to be mounted. Please confirm if a specific location is preferred or if this will be field coordinated during the execution phase.	Field coordinated shall happened after award
6	The communication cabinet was mounted near the ceiling and was not accessible during the survey. This was identified as the communications pathway to BDOC. Please confirm if there is a security switch in the cabinet or if raw fibers are available for use. If raw fiber, please provide the type of fiber being used to ensure an accurate proposal.	A site survey shall happened after award
7	Are maglocks the only acceptable electronic lock type to use, or is an electric strike acceptable to be integrated into the doors?	Strike release would be acceptable; however, the current door is not what will be utilized so would need to be re-installed later either way. May be eliminated from requirements. Refer to attachment 5 - CUI ESS Non-Nuclear CMD for AF approved equipment listing for Vindicator.
8	Please identify the ideal location for the VVS.	VVS (CCTV) will be mounted inside the building entry vestibule hallway to monitor doors for visitor/intruder.
9	Please confirm the video retention time required for the single entrance CCTV Camera.	The CCTV Cameras that feed back to BDOC is a 30 day retention time. The customer has requested 90 days, if possible
10	Please confirm that the unit will be providing the desk for the DVR workstation	Yes, unit will provide desk for workstation