AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

BPA NO.	1. CONTRACT ID CODE	PAGE 1 OF PAGES 7

2. AMENDMENT/MODIFICATION NUMBER	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NUMBER	5. PROJECT NUMBER (if applicable)
0001	07-10-2026	508-26-3-535-0463	

6. ISSUED BY CODE 508A

DEPARTMENT OF VETERANS AFFAIRS
VETERANS HEALTH ADMINISTRATION
Network Contracting Office (NCO) 7
2957 CLAIRMONT ROAD NE, Suite 1200
Atlanta GA 30329

7. ADMINISTERED BY (If other than Item 6) CODE 508A

DEPARTMENT OF VETERANS AFFAIRS
VETERANS HEALTH ADMINISTRATION
Network Contracting Office (NCO) 7
2957 CLAIRMONT ROAD NE, Suite 1200
Atlanta GA 30329

8. NAME AND ADDRESS OF CONTRACTOR (Number, street, county, State and ZIP Code)

To all Offerors/Bidders

CODE | FACILITY CODE

(X)	
	9A. AMENDMENT OF SOLICITATION NUMBER: 36C24726Q0615
X	9B. DATED (SEE ITEM 11)
☐	10A. MODIFICATION OF CONTRACT/ORDER NUMBER
	10B. DATED (SEE ITEM 13)

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers [X] is extended, [ ] is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified. ** HOUR & DATE for Receipt of Offers is EXTENDED to: 07-17-2026 1:00PM EDT

12. ACCOUNTING AND APPROPRIATION DATA (If required)

See CONTINUATION Page

13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE	
☐	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
☐	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
☐	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
☐	D. OTHER (Specify type of modification and authority)

E. IMPORTANT: Contractor [ ] is not, [X] is required to sign this document and return 1 copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.)

The purpose of this amendment is to extend the closing date and update the Statement of Work (SOW). The solicitation will now close at 1:00pm on July 17, 2026. The SOW has been revised to clarify that the required services involve fuel tank cleaning only. Fuel removal is no longer included within the scope of this requirement.

Please review the updated SOW carefully and ensure that any further communications, proposals, or cost estimates reflect this revised scope of work.

All other terms and conditions remain the same.

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER (Type or print)		16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
		Don Grier Contracting Officer	NCO715L2-70721
15B. CONTRACTOR/OFFEROR (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA DON GRIER Digitally signed by DON GRIER Date: 2026.07.10 09:53:59 -04'00' (Signature of Contracting Officer)	16C. DATE SIGNED

STATEMENT OF WORK

Fuel Oil Tank Cleaning and Permanent Out-of-Service Safeguarding

Atlanta VA Health Care System

1. Scope

The contractor shall provide all labor, supervision, equipment, materials, transportation, and disposal services necessary to service an out-of-service above-ground storage tank (AST) at the Atlanta VA Medical Center by cleaning and decontaminating the tank interior; render the tank vapor-free at the time of testing and place it in a safe condition for permanent out-of-service status; safeguard the tank against tampering or unauthorized reuse; and provide documentation of final tank condition and waste disposition, if any. Physical removal of the tank is not included.

1.1 Place of Performance

Joseph Maxwell Cleland VA Medical Center, 1670 Clairmont Road, Decatur, GA 30033. The tank and work area are exterior to the main hospital building.

1.2 Period of Performance

The period of performance shall begin upon contract award or written authorization to proceed by the Contracting Officer and shall not exceed 30 calendar days. On-site work is anticipated to be completed in one to two workdays.

1.3 Contract Type

Firm-Fixed-Price.

1.4 Points of Contact

The Contracting Officer’s Representative (COR) and other technical points of contact will be designated in writing at or after award. The Contractor shall not accept technical direction from any individual other than the Contracting Officer or a designated COR acting within the limits of their delegation.

1.5 Tank Information

The tank is a single 4,500-gallon nominal capacity, horizontal, aboveground carbon steel storage tank (AST), approximately 8-10 feet in diameter and 20-25 feet long (dimensions to be field verified). Pumpable fuel has been removed from the tank; however, residual fuel, sludge, sediment, water bottom, oily film, vapors, or other secondary waste may remain. See below pictures.

2. Applicable Standards

The contractor shall perform the work in accordance with the applicable requirements of, including but not limited to:

- NFPA 30, Flammable and Combustible Liquids Code (provisions for above-ground tanks taken out of service);
- NFPA 326, Standard for the Safeguarding of Tanks and Containers for Entry, Cleaning, or Repair;
- OSHA 29 CFR 1910.146 (Permit-Required Confined Spaces) and 29 CFR 1910.120 (HAZWOPER), as applicable;
- EPA RCRA and used oil management standards (40 CFR Part 279), as applicable;
- DOT Hazardous Materials Regulations (49 CFR Parts 100–185), as applicable;
- Georgia EPD requirements; and the Authority Having Jurisdiction (AHJ).

Where requirements appear to conflict, the contractor shall notify the COR and Contracting Officer before proceeding and shall comply with applicable law, permit conditions, and the direction of the AHJ. The contractor shall obtain or complete any permits, notifications, facility approvals, waste profiles, transportation documents, or disposal/recycling approvals required for the contractor's work, including tank cleaning, waste handling, transportation, recycling, treatment, disposal, and permanent out-of-service safeguarding.

3. Specific Tasks

3.1 Pre-Work Coordination

- A pre-work site visit is not required but may be conducted if requested by the contractor or the Contracting Officer. If the contractor elects not to conduct a site visit, the

contractor remains responsible for verifying means, methods, access, equipment needs, and site conditions necessary to complete the work within the awarded firm-fixed price.

- Submit a brief work plan, schedule, and site-specific health and safety plan (including a confined-space entry plan if tank entry is required) to the COR at least five (5) business days before mobilization.
- Provide not less than 72 hours advance notice of mobilization.

3.2 Waste Characterization (if applicable).

- Characterize and profile the #2 fuel oil residue if any, and each secondary waste stream (oily water, sludge, sediment, rinse water, absorbents, used PPE) based on analytical data, generator knowledge, and applicable regulations.
- Submit waste profiles and receiving facility approvals before shipment of each waste stream, unless the receiving facility allows management under an existing approved profile or other lawful acceptance process. Copies shall be provided to the COR.
- The Government makes no representation as to whether any waste stream is hazardous or non-hazardous; the Contractor shall manage all waste in accordance with their actual regulatory status.

3.3 Secondary Waste Management (if applicable)

- Containerize, label, manifest, and transport each waste stream to a permitted facility for disposal or recycling, in accordance with applicable EPA, DOT, state, and local regulations.
- Discharge no fuel, wastewater, rinse water, or other residue to VA storm drains, sanitary sewer, soil, surface water, or any other location on or off VA property.

3.4 Tank Cleaning and Decontamination

- Clean and decontaminate the tank interior to remove residual fuel, sludge, sediment, water bottom, oily film, and other residue remaining after prior fuel removal. Cleaning methods may include vacuum extraction, pressure washing, wiping, mechanical ventilation, or other methods appropriate for the tank condition and consistent with applicable safety requirements.
- Collect, containerize, and manage all wastewater, rinse water, sludge, sediment, absorbents, used PPE, and other secondary waste generated during cleaning.
- No fuel, wastewater, rinse water, sludge, sediment, or other residue shall be discharged to VA storm drains, sanitary sewer, soil, surface water, or any other location on VA property.

3.5 Atmospheric Testing and Vapor-Free Status

- Perform atmospheric testing using properly calibrated instruments to document the tank's condition at the time of completion. Testing shall include, at minimum, combustible vapor/LEL and oxygen concentration, plus any additional constituents required by the Contractor's health and safety plan, the receiving facility, applicable standard, or the AHJ.
- Provide written documentation, signed by a qualified person, of atmospheric test results and the tank's safe condition at the time of testing. Any certification of vapor-free status applies only at the time of testing.

3.6 Permanent Out-of-Service Safeguarding

- Upon completion of cleaning and atmospheric testing, safeguard the tank for permanent out-of-service status in accordance with NFPA 30 and NFPA 326.
- Secure all tank openings, manways, fill ports, gauge openings, and appurtenances disturbed during the work by capping, plugging, blind-flanging, locking, or otherwise mechanically securing access points as appropriate to prevent tampering, unauthorized reuse, or inadvertent filling. The tank vent shall remain configured in a safe manner unless otherwise directed by the AHJ.
- Apply durable, weather-resistant labeling at conspicuous locations on the tank indicating that the tank is out of service, empty, tested at completion, and not to be filled. Labeling shall include the date of the work.
- The contractor shall not cut, weld, hot-work, remove, demolish, or permanently alter the tank shell unless separately authorized in writing by the Contracting Officer.

3.7 Deliverables

- Pre-work plan, schedule, and site-specific health and safety plan (including confined-space entry plan, if applicable) prior to mobilization.
- Approved waste profiles or evidence of acceptance under an existing profile prior to shipment of each waste stream.
- Shipping papers, manifests, bills of lading, disposal tickets, recycling certificates, or other receiving facility documentation, as applicable, at the time of each shipment.
- Certificates of disposal, recycling, treatment or destruction, if applicable, within 30 calendar days of the final shipment.
- Atmospheric test records and signed documentation of the tank's safe condition at the time of completion.
- A final completion report within 15 business days of completing on-site work, including: quantities of secondary waste disposed, if any; receiving facility names, addresses, and EPA ID or permit numbers, if applicable; final disposition path; dates of service; cleaning method; atmospheric test results; safeguarding measures performed; and final tank condition.
- Invoice documentation shall include, at minimum, the contract/order number, date of service, quantities of secondary waste removed (if any), waste streams generated if any, manifests or bills of lading, receiving facility documentation, and certification/disposition documents supporting the completed work.

4. Acceptance

All work is subject to review and acceptance by the COR. The Government will accept the work when the tank interior has been cleaned and decontaminated; atmospheric testing has been completed and documented; the tank has been documented as vapor-free or otherwise in a safe condition at the time of completion; permanent out-of-service safeguarding measures identified in Section 3.6 have been completed; all secondary waste generated by the work has been removed from VA property; and all required closeout documentation has been submitted and accepted.

5. Hours of Work

Monday–Friday, 7:30 AM – 4:30 PM. Weekend or after-hours work is permitted with COR approval.

6. Safety

The contractor shall comply with VA safety requirements; OSHA confined-space and HAZWOPER standards as applicable; NFPA 30 and NFPA 326; lockout/tagout for contractor equipment; and DOT placarding and labeling for transportation. Spill kits and containment shall be staged at the work area for the duration of the work. The contractor is responsible for the immediate containment, cleanup, and lawful disposal of any spill caused by contractor operations, and for any required regulatory notifications. The contractor shall immediately notify the COR and designated VA site contact of any spill, release, leak, fire, injury, property damage, unsafe condition, or unexpected tank condition encountered during the work.

7. Site Conduct

- Contractor personnel shall check in with Engineering Service.
- Escort required as determined by VA staff.
- Contractor vehicles are limited to two (2) and shall be legally parked in designated areas. The pump/vacuum truck shall have access to the tank as needed to perform the work; staging and parking shall be coordinated with the COR.
- Photography on VA property only with prior COR approval.
- The Atlanta VA Health Care System is a tobacco-free campus; tobacco use of any kind is prohibited on VA property.

8. General Provisions

The contractor shall be self-sufficient for all equipment, tools, pumps, hoses, lighting, ventilation, confined-space equipment, PPE, containers, and safety equipment. Use of VA water or electrical services is not guaranteed and must be approved in advance by the COR.

COR approvals under this SOW are for technical coordination and site access only and do not authorize changes in contract scope, price, or period of performance. Changes to scope, price, or period of performance must be authorized by the Contracting Officer.

Records Management and Contract Security:

Procedures and VA Handbook 6500.6 Contract Security. Both can be found at: https://www.va.gov/vapubs/search_action.cfm?dType=2 **Note: This link is the complete list of VA Handbooks and are in sequential order. **Instructions for accessing VA Handbooks at link listed above: Click on link above and once it is opened, please scroll down on the left side until you get to VA Handbook 6300.1. Once there, go to the PDF Format Column and click on PDF. VA Handbook 6300.1 will then ask you to open or save the document.

Please follow the same instructions listed above for accessing VA Handbook 6500.6.

All contractor employees working on this requirement are required to complete mandatory annual training entitled, “VA Privacy and Information Security Awareness” and “HIPPA Training” prior to providing service for each year of the contract with copies sent to the COR for each and available for audit as requested. The course numbers are VA10203 and VA 10176. You must select that you are a contractor. Contractor employees are to self-enroll into TMS via the link:

https://www.tms.va.gov/learning/user/SelfRegistrationUserSelection.do A VA employee will escort the contractor when contractor is required to enter/work in sensitive areas.

Identifications, smoking and VA Regulations:

The Contractor's FSE shall wear visible identification always while on the premises of the Atlanta VA Medical Center. Contractor shall contact the Contracting Officer's Representative (COR) upon contract award, to receive instructions on how to obtain a VA Identification Badge during the performance of this contract. Atlanta VA Medical Center is a smoke-free campus which includes both tobacco and e-cigarettes; tickets can be issued by Police Services. Possession of weapons is prohibited. Enclosed containers, including tool kits, shall be subject to search. Violations of VA regulations may result in citation answerable in the United States (Federal) District Court, not a local district, state, or municipal court. Photography or Video on medical center premises is strictly prohibited. Additionally, pursuant to 38 CFR 1.218(b) (23) Use of recording devices of any kind to record patients or employees is strictly prohibited.

VA Notice of Limitations on Subcontracting - Certificate of Compliance: To be eligible for evaluation and consideration for award, offerors must return the entire Limitations on Subcontracting Certificate of Compliance clause containing a fully completed certification at the time offers are due or the offer will be rejected and not forwarded for evaluation. In addition to completing the offeror 'fill-in' requirements for this clause, offerors must insert the offeror's name in the brackets. Electronic signatures are not acceptable.

Fuel Oil Tank Cleaning