# AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

| 1. CONTRACT ID CODE | PAGE | OF | PAGES |
|---|---|---|---|
| J | 1 | | 1 |

| 2. AMENDMENT/MODIFICATION NUMBER | 3. EFFECTIVE DATE | 4. REQUISITION/PURCHASE REQUISITION NUMBER | 5. PROJECT NUMBER *(If applicable)* |
|---|---|---|---|
| 0005 | 02 Jul 2026 | See Continuation Sheet | J-875 |

6. ISSUED BY CODE N62742

NAVFACSYSCOM PACIFIC
258 MAKALAPA DR STE 100, JBPHH HI 96860-3134
JBPHH, HI 96860-3134
UNITED STATES
Jennifer Hue, Email: jennifer.m.hue.civ@us.navy.mil Telephone: 8086026755

7. ADMINISTERED BY *(If other than Item 6)* CODE

SCD: PAS:

8. NAME AND ADDRESS OF CONTRACTOR *(Number, street, county, State and ZIP Code)*

CODE FACILITY CODE

(X)

☒ 9A. AMENDMENT OF SOLICITATION NUMBER N6274226R1306

9B. DATED *(SEE ITEM 11)* 10 Apr 2026

☐ 10A. MODIFICATION OF CONTRACT/ORDER NUMBER

10B. DATED *(SEE ITEM 13)*

## 11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended. ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing items 8 and 15, and returning 1 copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or electronic communication which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by letter or electronic communication, provided each letter or electronic communication makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

**12.** ACCOUNTING AND APPROPRIATION DATA *(If required)*

See Section 00 70 00 - Conditions of the Contract

## 13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NUMBER AS DESCRIBED IN ITEM 14.

| CHECK ONE | |
|---|---|
| ☐ | A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NUMBER IN ITEM 10A. |
| ☐ | B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation data, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b). |
| ☐ | C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF: |
| ☐ | D. OTHER *(Specify type of modification and authority)* |

**E. IMPORTANT:** Contractor ☐ is not ☐ is required to sign this document and return _____ copies to the issuing office.

**14.** DESCRIPTION OF AMENDMENT/MODIFICATION (*Organized by UCF section headings, including solicitation/contract subject matter where feasible.*)

RFP N62742-26-R-1306, JFY 2022 PROJECT J-875, BATTLE STAFF TRAINING FACILITY, U.S. NAVSUPPACT MCB CAMP BLAZ, GUAM; AMENDMENT 0005 is for the following:

SPECIFICATIONS (Due to system character limitation, see attached SPECIFICATIONS SUMMARY OF CHANGES)

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

| 15A. NAME AND TITLE OF SIGNER *(Type or print)* | | 16A. NAME AND TITLE OF CONTRACTING OFFICER *(Type or print)* | |
|---|---|---|---|
| 15B. CONTRACTOR/OFFEROR<br>*(Signature of person authorized to sign)* | 15C. DATE SIGNED | 16B. UNITED STATES OF AMERICA<br>*(Signature of Contracting Officer)* | 16C. DATE SIGNED |

# SPECIFICATIONS SUMMARY OF CHANGES

**DOCUMENT 00 01 15 – LIST OF DRAWINGS**

- PARA. 1.2 CONTRACT DRAWINGS: The following drawings, bearing revision date of 6/5/2026, supersede previously issued drawings bearing the same number and title. The revised drawings accompany this Amendment, see Attachment (1).

| SHEET NO. | NAVFAC DWG NO. | REVISION NO. | TITLE |
|---|---|---|---|
| G-002 | 17321760 | 2 | LIST OF SHEETS |
| G-003 | 17321761 | 1 | LIST OF SHEETS |
| | | | |
| CS100 | 17321786 | 2 | CIVIL SITE PLAN – BASE AND BID OPTIONS |
| CG501 | 17321798 | 1 | CIVIL GRADING DETAILS – SHEET 1 |
| | | | |
| LP101 | 17321828 | 2 | LANDSCAPE PLAN - BASE AND OPTIONS |
| LP502 | 17321830 | 1 | SITE FURNISHING DETAILS AND OPTIONS |
| LP601 | 17321831 | 1 | PLANT MATERIAL SCHEDULE AND NOTES |
| | | | |
| SS111 | 17321842 | 1 | PAVILION ROOF PLAN |
| SB101 | 17321847 | 1 | COMPREHENSIVE FOUNDATION PLAN |
| SB102 | 17321848 | 1 | FOUNDATION PARTIAL PLAN - AREA ‘A’ |
| SB103 | 17321849 | 1 | FOUNDATION PARTIAL PLAN - AREA ‘B’ |
| SB104 | 17321850 | 1 | COMPREHESIVE SLAB PLAN (EL. 0'-0", UNO) |
| SB105 | 17321851 | 2 | SLAB PLAN - AREA 'A' (EL. 0'-0", UNO) |
| SB106 | 17321852 | 2 | SLAB PLAN - AREA 'B' (EL. 0'-0", UNO) |
| SB401 | 17321853 | 2 | MECHANICAL ENCLOSURE FOUNDATION / SLAB PLAN |
| SB403 | 17321855 | 1 | ELEVATOR PIT ENLARGED PLAN |
| SB501 | 17321856 | 1 | STRUCTURAL FOUNDATION – SLAB DETAILS – SHEET 1 |
| SB502 | 17321857 | 1 | STRUCTURAL FOUNDATION – SLAB DETAILS – SHEET 2 |
| SF101 | 17321859 | 1 | COMPREHENSIVE SECOND FLOOR FRAMING PLAN (EL. 14'-0", UNO) |
| SF102 | 17321860 | 2 | SECOND FLOOR FRAMING PLAN - AREA 'A' (EL. 14'-0", UNO) |
| SF103 | 17321861 | 2 | SECOND FLOOR FRAMING PLAN - AREA 'A' (EL. 16'-0", UNO) |
| SF104 | 17321862 | 2 | SECOND FLOOR FRAMING PLAN -AREA 'B' (EL. 14'-0", UNO) |
| SF105 | 17321863 | 2 | SECOND FLOOR FRAMING PLAN - AREA 'B' (EL. 16'-0", UNO) |

| | | | |
|---|---|---|---|
| SF106 | 17321864 | 1 | COMPREHENSIVE ROOF FRAMING PLAN (ABOVE EL. 32'-0") |
| SF107 | 17321865 | 1 | ROOF FRAMING PLAN - AREA 'A' (ABOVE EL. 32'-0") |
| SF108 | 17321866 | 1 | ROOF FRAMING PLAN - AREA 'B' (ABOVE EL. 32'-0") |
| SF301 | 17321867 | 1 | STRUCTURAL SECTIONS - SHEET 1 |
| SF302 | 17321868 | 1 | STRUCTURAL SECTIONS - SHEET 2 |
| SF401 | 17321869 | 2 | MECHANICAL ENCLOSURE FRAMING PLAN |
| SF402 | 17321870 | 2 | CANOPY ROOF FRAMING PLAN |
| SF501 | 17321871 | 1 | STRUCTURAL FLOOR FRAMING DETAILS – SHEET 1 |
| SF502 | 17321872 | 1 | STRUCTURAL FLOOR FRAMING DETAILS – SHEET 2 |
| SF503 | 17321873 | 1 | STRUCTURAL ROOF FRAMING DETAILS |
| SJ601 | 17321876 | 1 | STRUCTURAL SCHEDULES |
| SK506 | 17321882 | 1 | CONCRETE COLUMN DETAILS |
| | | | |
| A-001 | 17321900 | 1 | ARCHITECTURAL NOTES AND SYMBOLS |
| AS102 | 17321902 | 2 | CHILLER ENCLOSURE PLAN, EXTERIOR ELEVATIONS, AND SECTION |
| AS107 | 17321907 | 1 | GENERATOR & FUEL TANK ENCLOSURE PLAN AND ROOF PLAN, OPTION ITEM #2 |
| AS110 | 17321910 | 1 | PAVILION PLANS, ELEVATIONS & SECTIONS, OPTION ITEM #1 |
| A-101 | 17321912 | 2 | OVERALL FIRST FLOOR PLAN |
| A-102 | 17321913 | 2 | ENLARGED FLOOR PLAN - 1A |
| A-103 | 17321914 | 2 | ENLARGED FLOOR PLAN - 1B & OPTION ITEM #2 |
| A-104 | 17321915 | 2 | OVERALL SECOND FLOOR PLAN |
| A-105 | 17321916 | 2 | ENLARGED FLOOR PLAN - 2A |
| A-106 | 17321917 | 2 | ENLARGED FLOOR PLAN - 2B |
| A-111 | 17321918 | 2 | OVERALL FIRST FLOOR REFLECTED CEILING PLAN |
| A-112 | 17321919 | 1 | ENLARGED REFLECTED CEILING PLAN – 1A |
| A-113 | 17321920 | 2 | ENLARGED REFLECTED CEILING PLAN - 1B & OPTION ITEM #2 |
| A-114 | 17321921 | 2 | OVERALL SECOND FLOOR REFLECTED CEILING PLAN |
| A-115 | 17321922 | 2 | ENLARGED REFLECTED CEILING PLAN - 2A |
| A-116 | 17321923 | 2 | ENLARGED REFLECTED CEILING PLAN - 2B |
| A-201 | 17321925 | 1 | EXTERIOR ELEVATIONS - NORTH AND EAST & OPTION ITEM #2 |
| A-202 | 17321926 | 1 | EXTERIOR ELEVATIONS - SOUTH AND WEST & OPTION ITEM #2 |
| A-301 | 17321928 | 2 | BUILDING SECTIONS |
| A-401 | 17321931 | 2 | INTERIOR ELEVATIONS |
| A-402 | 17321932 | 2 | INTERIOR ELEVATIONS |
| A-403 | 17321933 | 2 | INTERIOR ELEVATIONS |
| A-404 | 17321934 | 2 | INTERIOR ELEVATIONS |

| | | | |
|---|---|---|---|
| A-405 | 17321935 | 2 | INTERIOR ELEVATIONS |
| A-406 | 17321984 | 1 | INTERIOR ELEVATIONS – ADDED SHEET |
| A-407 | 17321985 | 1 | INTERIOR ELEVATIONS – ADDED SHEET |
| A-408 | 17321986 | 1 | INTERIOR ELEVATIONS – ADDED SHEET |
| A-409 | 17321987 | 1 | INTERIOR ELEVATIONS – ADDED SHEET |
| A-410 | 17321988 | 1 | INTERIOR ELEVATIONS – ADDED SHEET |
| A-411 | 17321936 | 2 | DETAILED RESTROOM PLANS AND INTERIOR ELEVATIONS |
| A-412 | 17321937 | 2 | DETAILED RESTROOM PLANS AND INTERIOR ELEVATIONS |
| A-413 | 17321938 | 2 | DETAILED ELEVATOR PLANS AND SECTION |
| A-501 | 17321942 | 2 | TYPICAL MOUNTING HEIGHTS |
| A-502 | 17321943 | 2 | PARTITION TYPES |
| A-601 | 17321946 | 2 | DOOR AND OPERABLE PARTITION SCHEDULES |
| A-602 | 17321947 | 1 | DOOR, WINDOW, LOUVER TYPES AND SCHEDULES & OPTION ITEM #2 |
| A-610 | 17321955 | 2 | INTERIOR COLOR MATERIAL SCHEDULE |
| A-612 | 17321957 | 1 | ROOM FINISH SCHEDULE |
| A-613 | 17321958 | 1 | ROOM FINISH SCHEDULE |
| A-750 | 17321971 | 1 | MISCELLANEOUS EXTERIOR DETAILS |
| A-902 | 17321977 | 2 | AIR BARRIER DIAGRAM |
| AI101 | 17321979 | 2 | ENLARGED FLOOR FINISH PLAN – 1A |
| AI102 | 17321980 | 2 | ENLARGED FLOOR FINISH PLAN – 1B |
| | | | |
| PL114 | 17322060 | 1 | PLUMBING PLAN - FIRST FLOOR - AREA 'D' |
| PL115 | 17322061 | 2 | PLUMBING PLAN - FIRST FLOOR - AREA 'E' |
| PL124 | 17322067 | 1 | PLUMBING PLAN - SECOND FLOOR - AREA 'D' |
| PL400 | 17322071 | 1 | ENLARGED PLUMBING PLANS – SHEET 1 |
| PL401 | 17322072 | 1 | ENLARGED PLUMBING PLANS – SHEET 2 |
| PL502 | 17322082 | 1 | PLUMBING DETAILS – SHEET 3 – ADDED SHEET |
| PL600 | 17322075 | 1 | PLUMBING SCHEDULES – SHEET 1 |
| | | | |
| MH103 | 17322096 | 2 | HVAC DUCT PLAN – FIRST FLOOR – AREA 'C' |
| MH704 | 17322133 | 2 | MECHANICAL SCHEDULES – SHEET 5 |
| MH800 | 17322134 | 1 | MECHANICAL CONTROLS |
| MP105 | 17322142 | 2 | HVAC PIPING PLAN - FIRST FLOOR - AREA 'E' |
| MP107 | 17322144 | 2 | HVAC PIPING PLAN - FIRST FLOOR - MECHANICAL ENCLOSURE |
| MP115 | 17322150 | 2 | HVAC PIPING PLAN - SECOND FLOOR - AREA 'E' |
| MP400 | 17322152 | 1 | ENLARGED FLOOR PLAN – SHEET 1 |
| | | | |
| EP504 | 17322232 | 1 | ELECTRICAL DETAILS – SHEET 4 |

**SPECIFICATIONS PROJECT TABLE OF CONTENTS**

- Delete this Section in its entirety and replace it with PROJECT TABLE OF CONTENTS, dated 06-05-2026. The revised Section accompanies this Amendment, see Attachment (2).

**SECTION 08 71 00 – DOOR HARDWARE**

- PARA 3.6 HARDWARE SETS, Set: 24. 0: Replace Door "117C" with "117B".
- PARA 3.6 HARDWARE SETS, Set: 43.0: Remove Door "215A".

**SECTION 09 65 00 – RESILIENT FLOORING**

- Delete this Section in its entirety and replace it with Section 09 65 00 – RESILIENT FLOORING, dated 06-05-2026. The revised Section accompanies this Amendment, see Attachment (2).

**SECTION 09 67 23.13 – STANDARD RESINOUS FLOORING**

- Delete this Section in its entirety and replace it with Section 09 67 23.13 – STANDARD RESINOUS FLOORING, dated 06-05-2026. The revised Section accompanies this Amendment, see Attachment (2).

**SECTION 10 26 00 – WALL AND DOOR PROTECTION**

- Delete this Section in its entirety and replace it with Section 10 26 00 – WALL AND DOOR PROTECTION, dated 06-05-2026. The revised Section accompanies this Amendment, see Attachment (2).

**SECTION 14 24 23 – HYDRAULIC PASSENGER ELEVATORS**

- Delete this Section in its entirety and replace it with Section 14 24 23 – HYDRAULIC PASSENGER ELEVATORS, dated 06-05-2026. The revised Section accompanies this Amendment, see Attachment (2).

**SECTION 23 64 10 – WATER CHILLERS, VAPOR COMPRESSION TYPE**

- PARA. 2.5.8 Water Cooler (Evaporator), Line 1: Replace the first sentence with "Cooler must be of the shell-and-coil, shell-and-tube, or brazed plate & frame type design."

**SECTION 26 32 15 – ENGINE-GENERATOR SET STATIONARY 15-2500 KW, WITH AUXILIARIES**

- PARA 2.1.1 Engine-Generator Parameter Schedule, Power Rating: Replace "1100 kW" with "1000 kW".
- PARA 2.1.1 Engine-Generator Parameter Schedule, Service Load: Replace "1375 kVA" with "1250 kVA".
- PARA 2.1.1 Engine-Generator Parameter Schedule, Motor Starting kVA: Replace "1375 kVA" with "1250 kVA".

**SECTION 26 32 15.01 – ENGINE-GENERATOR SET STATIONARY 15-2500 KW, WITH AUXILIARIES – EMERGENCY**

- Add Section 26 32 15.01 – ENGINE-GENERATOR SET STATIONARY 15-2500KW, WITH AUXILIARIES – EMERGENCY, dated 06-05-2026. This added Section accompanies this Amendment, see Attachment (2).

**SECTION 31 00 00 – EARTHWORK**

- PARA 3.4 SUBGRADE PREPARATION, 2nd Paragraph, Line 9. Add "The horizontal extent of the soil replacement is 5 ft from the vertical face of the footings."

**SECTION 31 62 00 – CEMENT DEEP SOIL MIXING**

- PARA 3.1 FIELD VALIDATION PROGRAM, e., Line 6: Replace "3-feet" with "1-feet".
- PARA 3.2 INSTALLATION OF CDSM, 9th Paragraph, End of this paragraph: Add "The 60-days calendar restriction may be shortened if the 28-days specified unconfined compression strength of the treated soil of 1,200 kPa (175 psi) is achieved.".