TITLE: DINING AREA LIGHTING REPLACEMENT WC100

ATTACHMENTS:

SCOPE OF WORK: The contractor shall provide all material, labor, equipment, and supervision required to accomplish the following:

General description – Replace the existing lighting and controls in the dining and served line areas of mess hall WC100 aboard Marine Corps Base Camp Lejeune, North Carolina.

ELECTRICAL WORK:

-The existing recessed lighting in the dining and served line areas have been repaired/replaced with varying light source, style, lumen output, and color temperature lamps. This has left lighting in these areas inadequate.

-The intent of this project is to replace all the existing recessed can lights on the patron side of the mess hall.

Construction:

1. Remove the existing lighting in the dining and served line areas. Install new LED lighting and switches/controls in the dining and served line areas.

GENERAL REQUIREMENTS:

1. Equipment, material, installation, and workmanship shall be in accordance with the mandatory and advisory provisions of NFPA 70.
2. All conductors shall be copper, and insulation shall be 600-volt type THHN/THWN unless noted otherwise.

SUBMITTALS:

SPECIAL SCHEDULING AND ACCESS: Mr. Paul Mack shall be the point of contact for scheduling and access at paul.mack@usmc.mil or (910) 451-6270.

SPECIAL CONDITIONS: The mess hall shall remain open during construction and work should be scheduled as to not have more than one dining area closed at a time.

HAZARDOUS MATERIALS: None Identified

ENVIRONMENTAL REQUIREMENTS: None Identified

DISTRIBUTION: DoW COMMUNITY ONLY