BID SCHEDULE
COOTER CREEK, NFSR # 202-3.1 BRIDGE REPLACEMENT

Bridge Replacement - Huger, SC - NFSR #202-3.1					District:		Francis-Marion
ITEM NO.	SPEC NO.	DESCRIPTION	METHOD OF MEASURE	UNIT	QUANTITY	UNIT PRICE	TOTALS
1	151	MOBILIZATION	CQ	LS	1		
2	152	CONSTRUCTION SURVEY AND STAKING	CQ	LS	1		
3	154	CONTRACTOR SAMPLING AND TESTING	CQ	LS	1		
4	155	SCHEDULES FOR CONSTRUCTION CONTRACTS	CQ	LS	1		
5	157	EROSION CONTROL	CQ	LS	1		
6	201	CLEARING AND GRUBBING	CQ	ACRE	0.4		
7	203	REMOVAL OF EXISTING STRUCTURE	CQ	LS	1		
8	204	EXCAVATION AND EMBANKMENT (ROADWAY GRADING)	CQ	LS	1		
9	207	EARTHWORK GEOSYNTHETICS	AQ	SY	690		
10	209	STRUCTURE EXCAVATION AND BACKFILL - COMPACTION METHOD 2	CQ	LS	1		
11	251	RIP RAP (CLASS 5)	AQ	TON	620		
12	301	8" AGGREGATE BASE COURSE (PAVEMENT SCHEDULE J) - COMPACTION METHOD A	AQ	TON	185		
13	403	ASPHALT SURFACE COURSE (PAVEMENT SCHEDULE C)	AQ	TON	50		
14	403	ASPHALT BINDER	AQ	TON	5		
15	551	HP 12X53 STEEL PILES (GALVANIZED)	AQ	LF	725		
16	552	STRUCTURAL CONCRETE (3000 PSI)	AQ	CY	30.6		
17	553	3'-0" X 2'-0" PRESTRESSED CONCRETE CORED SLABS	AQ	LF	420		
18	554	REINFORCING STEEL - UNCOATED (ABUTMENTS)	CQ	LB	3418		
19	556	BRIDGE RAILING (CONCRETE CURB, REINFORCING STEEL, STEEL BEAM GUARDRAIL, POSTS, SPACERS, HARDWARE, ETC.)	AQ	LF	145.0		
20	564	BEARING DEVICES	CQ	LS	1		
21	617	GUARDRAIL (APPROACH ROADWAY)	AQ	LF	50		
22	617	GREU TYPE TL-2 (APPROACH ROADWAY)	AQ	EACH	4		
23	625	TURF ESTABLISHMENT (PERMANENT)	CQ	ACRE	0.5		
24	635	TEMPORARY TRAFFIC CONTROL	CQ	LS	1		
25	551	DYNAMIC LOAD TESTING	CQ	EACH	2		
26	SS 802A	EARTHQUAKE DRAIN SYSTEM DESIGN	CQ	LS	1		
27	SS 802B	EARTHQUAKE DRAINS	AQ	LF	1000		
28	SS 801	BRIDGE APPROACH SLABS	CQ	LS	1		
			TOTAL				