No.	Reference Document (If Applicable)	Paragraph/Section Reference (If Applicable)	QUESTION	GOVERNMENT RESPONSE
1			Please confirm whether quotations are due August 12 or August 14, 2026, at 8:00 AM HST. Both dates appear in the RFQ	Quotes are due August 14, 2026, at 1:00 PM HST
2			Is attendance at the August 5 site visit mandatory?	No, attendance is not required.
3	ATTCH 1 - PWS	Section 2	Will the Government provide a final camera count and location schedule, or must each offeror develop the proposed quantity and placement from the site visit?	No, the contractor will provide a proposal on the number of the cameras and location. Goal is to the have coverage of the areas identified in ATTCH 2 - CCTV Area of Coverage.
4	ATTCH 1 - PWS	Section 2	Does the 40-frames-per-second requirement apply to each camera continuously, and what resolution, codec, bitrate, and recording mode must be used?	The frame-per-second will be vary based on the location of the camera. The range will vary from 15-30 frames-per-second.
5	ATTCH 1 - PWS	Section 2	Must all cameras retain 180 days of continuous footage, or is motion-based recording acceptable?	PWS has been updated to reflect 90 days for minimum retention of combined contineous and motion based footage.
6	ATTCH 1 - PWS	Section 2	Are RAID redundancy, hot-spare drives, UPS protection, or minimum usable-storage requirements applicable?	RAID 1 will be required. The minimum storage capacity must support a 90-day retention period.
7	ATTCH 2 - CCTV Area Of Coverage		Please identify the required location for the NVR/server, monitor, joystick, network switches and associated equipment.	ATTCH 2 - CCTV Area Of Coverage has been updated to reflect the server room location. The exisiting monitors may be utilized if they integate with the new CCTV system.

8	ATTCH 1 - PWS	Section 1, Section 2	May any existing cabling, conduit, power supplies or mounting hardware be reused?	Yes, if current conduit, cabling, mounting hardware is working properly after testing it may be reused.
9	ATTCH 1 - PWS	Section 3.3.3	Will the Government retain the removed CCTV equipment, or must the contractor dispose of it?	Yes, the contractor will be responsible for removing and disposing of the previous CCTV system.
10			Please confirm whether the system must be completely air-gapped and whether all remote or cloud access is prohibited.	Air-gapped is required. No network connectivity is permitted, cloud functionality and remote access is prohibited.
11	ATTCH 5 - SCA - Wage Determinations / ATTCH 1 - PWS	PWS, Section 3.1.6	Clarify whether the attached SCA Wage Determination 2015-5689 or a Davis-Bacon wage determination applies to CCTV cabling and electrical work. PWS paragraph 3.1.6 references HI20250001	Updated the PWS to reflect the updated version of the Wage Determination.
12	ATTCH 1 - PWS	Section 2	Is there any required manufacturer, VMS platform, ONVIF compatibility, cybersecurity certification or minimum commercial warranty requirements?	No required manufacturer, VMS platform, ONIVIF compatibility. Cybersecurity certifications include NDAA compliance (Section 889), TAA Compliance, and FIPS encryption certification.
13			Please confirm whether FAR 52.219-14, Limitations on Subcontracting, applies to this acquisition	RFO 52.219-14 is not applicable to this contract.
14			Please clarify whether DFARS 252.217-7027 is applicable, as the included clause contains blank definitization and not-to-exceed fields.	No, this clause is not applicable due to this contract action not meeting the definition of a underdefinitized contract action outlined in Subpart 217.7401. Clause will be removed from ATTCH 3 - Provisions and Clauses.

15			Please confirm the required WAWF document type for CLIN 0001 materials	CLIN 0001 is to include a breakdown of the cost for cameras, materials, and supporting equipment.
16			Is there a cost estimate , budget or ballpark figure for the project listed?	We are unable to provide any information regarding the budget for this project.
17	ATTCH 1 - PWS	Section 3.2	What is the start date for the project?	Work on the project is estimated to start immediately upon award. Completion within 21 duty days after award and invoice submission within 48 hours of project completion.
18	ATTCH 1 - PWS	Section 2	Is there a set number of cameras required?	No, contractor is to propose the necessary number of cameras to cover the required area.
19	ATTCH 1 - PWS	Section 3.3.5	What are the mounting options for the cameras?	Cameras are to be mounted on internal building/walls. No cameras are to be mounting on the frame of the hangar.
20	ATTCH 1 - PWS	Section 2	Is there a list of specific cameras or hardware?	The type and number of cameras is not specified. The contractor will provide the number of cameras required to provide coverage of specified areas based on industry capabilities. Types of cameras listed in the PWS include fixed, PTZ, and 360 degree.
21	ATTCH 1 - PWS	Section 2	What camera resolution is required for the cameras?	The resolution should range between 1080P/2MP and 4K/8MP depending on the location of the camera(s).