PROJECT DESCRIPTION

The work includes removal and replacement of damaged sidewalk portions located off Powder Lane on Stone Bay, Camp Lejeune NC as well as repair to any damaged grass and/or road that occurred during construction of this project.

This scope of work is to be accomplished at MTI Reflector Towers 01, 05, 19 & 23 on the flightline aboard, New River, North Carolina. The work includes pouring (4) new 4" concrete slabs measuring 20'x22'-6" each over crushed rock at existing MTI reflector locations. (3) of the sites will include minimal site work to ensure level slab, (1) site includes building of retaining wall and dirt infill to create level slab. Each concrete slab will have (2) 2” Sch 40 PVC conduits built into slab and ran below grade 5’ beyond slab edge for future use.

SPECIAL SCHEDULING

The facility/activity will remain in operation during the entire construction period. The Contractor shall conduct his operations so as to cause the least possible interference with normal operations of the facility/activity.

SUPERVISION

One person may fill the roles of Superintendent, Quality Control Manager, and Safety & Health Officer, if duly qualified for all three positions as defined in the project specification.

DISTRIBUTION: DoD COMMUNITY ONLY