Questions and Answers during Advertisement for
CO ERFO FS SNJUAN 2026-1(1) Fall Creek Road

July 14, 2026

	Questions	Answers
1	Is a site visit scheduled or can I arrange a site visit for the project?	There is no site visit scheduled. The site is open and accessible to the public.
2	When is it due?	Please see page A-1, box 13

July 28, 2026

	Questions	Answers
1	What is the overall period of performance for all work to be completed on this project?	Please reference Section 108
2	Specifically, when can we start and what is the final deadline for completion?	Start once Notice-to-Proceed is issued, and reference Section 108 for completion.

August 3, 2026

	Questions	Answers
1	Is the 16x6 able to be changed to a double run of 8x6 per ASTM C1577.	No, while the conveyance area might be equal, a double barrel CBC does not meet the design intent, especially with regards to debris passage.
2	Is the Concrete Box Culvert going to be redesigned for the depth of cover required in the drawings? Existing specifications indicate a maximum cover of 4 feet vs the design of 10 feet.	The contractor is required to submit shop drawings per Section 602 of the Special Contract Requirements. The wall thickness of the submitted box culvert should be sized appropriate to design earth cover as conveyed in the plans and cross sections.
3	The Substituted paragraphs on page E-12, 108.05 Failure to Complete Work on Time are confusing. If a Winter storm event shuts down the job, are we going to be charged $230.00 / Day until we can go back to work?	If the project enters an approved winter shutdown period after the contract completion date, liquidated damages will be assessed at $230.00 per day. Under Section 108.05 of the Special Contract Requirements, liquidated damages assessed during an active winter shutdown period are reduced to 10 percent of the full rate specified in FAR Clause 52.211-12. Once the winter shutdown ends and work resumes, the full liquidated damages rate of $2,300.00 per day will resume until the work is substantially complete.

August 4, 2026

	Questions	Answers
1	We saw that in the fall creek project that there was a line item with spring bypass/ creek bypass. We have heard from a few contractors that they would like numbers to assist in the bypass. I looked through the plans and was able to locate what CFS the bridge will need to be able to withstand but was unable to locate the CFS the creek is expected to be running at when the project is happening. Do you have any additional information to this, or can you point me in the right direction?	Section 628 specifies a stream diversion for a 2-year peak flow, which is 205 cfs in this case, as shown in the Hydraulic Report Table 4. See Section 628.03 for contractor submittal requirements. A different flow and supporting analysis can be submitted with the contractor's diversion plan. Since this stream is not gaged, CFL cannot make this determination or provide a recommendation.

August 6, 2026

	Questions	Answers
1	Is this project tax exempt?	See RFO Clause 52.229-3 Federal, State, and Local Taxes