STATEMENT OF WORK for 550-27-111

1. **Scope of Work:**

VA Illiana Healthcare System, Danville, IL seeks a contractor to perform the work prescribed within this document to re-roof Building 58 and perform associated work:

-Tear off and remove from site all existing roofing material down to the existing decking.

-Install 7/16" OSB on top of existing decking.

-Repair any damaged sheathing, trim, fascia, dormer framing, gutter, vents, soffit, and decking.

-There shall be no gaps in flashing.

-Paint any newly installed exposed wood to match existing

-Repair roof hatch to match rest of roof.

-Install new felt roofing underlayment

-Install new asphalt shingles of the same style currently in place

-Replace flashing and decking as needed.

-Caulk and seal as needed

-Contractor to provide temporary metal fencing around work area to protect pedestrians/vehicles from falling debris

-Contractor to be solely responsible for adherence to OSHA requirements for fall protection, no assumption of approved anchor points should be made. Contractor to verify

-Post-completion, sweep all surrounding areas with magnetic sweep to collect any loose nails

-Patch any holes that would allow for animals to enter the building.

3. **Performance Period**

Contractor shall complete all work associated with this project within sixty (60) calendar days of the receipt of the Notice to Proceed (NTP). Normal working hours are Monday through Friday, 0700-1630, excluding Federal Holidays. Contractor shall provide a schedule to the Contracting Officer's Representative, through the Contracting Officer, prior to any onsite work taking place. If for any reason the contractor can't meet the

required period of performance for this project he/she must submit, in writing, to the Contracting Officer, a revised schedule, justification, and request for additional time.

Contractor shall make all concerted efforts to minimize the duration of downtime to each building. The C&A requirements do not apply and a Security Accreditation Package is not required.

4. Background:

Work will be performed at:

VA Illiana Health Care System

1900 East Main St.

Danville, IL 61832

Shaded areas are in scope