Statement of Work (SOW)
Acquisition of One (1) 40-Yard Radius Container with Rolling Lid
USCG Base Alameda, CA

1. Scope

The Contractor shall provide all labor, materials, and equipment to fabricate, deliver, and install **one (1) 40-yard roll-off container with a rolling lid** at U.S. Coast Guard Base Alameda, CA. The container shall be designed to accommodate operational waste management requirements and must be compatible with Alameda County Industries (ACI) hauling equipment.

2. Background

USCG Base Alameda historically operated two (2) 20-yard covered roll-off containers to manage operational waste. The first of these 20-yard containers became unserviceable and was recycled; it has already been replaced by a 40-yard capacity container.

The second, remaining 20-yard container is non-compliant with environmental regulations and may leave the base with a critical capacity shortage for waste collection. To resolve this deficiency, restore full operational readiness, and ensure environmental compliance, USCG Base Alameda requires a second 40-yard capacity container to replace this unserviceable 20-yard unit.

3. Requirements

3.1. Equipment Specifications

3.1.1. **Container Size:** 40-yard radius body container
3.1.2. **Dimensions:** Approximately 8 ft wide x 21 ft long x 5.5 ft high (per site needs and manufacturer's design)
3.1.3. **Lid:** Rolling lid, overlapping and capable of opening in either direction
3.1.4. **Door Seal:** Must include a liquid-tight door seal
3.1.5. **Paint Color:** To be determined by USCG at time of order
3.1.6. **Compatibility:** Must be compatible with ACI hauling systems
3.1.7. **Construction:** Fabricated from durable steel, suitable for outdoor industrial use

3.2. Installation & Delivery

3.2.1. Contractor shall conduct a **site survey** before installation
3.2.2. Contractor shall provide **delivery, offloading, and placement** of the

container at the designated USCG Base Alameda location

3.2.3. Contractor shall provide **all equipment (e.g., forklift)** necessary for placement

3.2.4. Installation must meet all applicable safety standards

3.3. Government Responsibilities

3.3.1. Provide a **designated clear area** for offloading and forklift operation

3.3.2. Provide **concrete foundation**

3.3.3. Identify paint color prior to fabrication

3.4. Exclusions

The following are not included under this requirement unless specifically contracted:

3.4.1. Permitting, inspections, or special compliance requirements (e.g., OSHPD)

3.4.2. Additional trips outside scheduled installation date

3.4.3. Rush delivery unless specifically authorized

4. Deliverables

4.1. One (1) 40-yard roll-off container with rolling lid and liquid-tight door seal, delivered and installed at USCG Base Alameda

4.2. Manufacturer's standard warranty documentation

4.3. Final inspection and acceptance by USCG

5. Schedule

5.1. Work shall begin upon contract award

5.2. Estimated lead time: as determined by the Contractor's production schedule (subject to workload fluctuations).

5.3. Contractor shall notify the USCG of any delays

6. Required Delivery Date

The Required Delivery Date (RDD) is **no later than 120 days** from contract award.

7. Security & Access

Contractor personnel shall comply with all USCG Base Alameda security procedures. Access badges and vehicle inspections may be required.